


[\[Team LiB \]](#)

NEXT ▶



- [Table of Contents](#)
- [Index](#)
- [Reviews](#)
- [Reader Reviews](#)
- [Errata](#)

C# in a Nutshell, 2nd Edition

By [Ben Albahari](#), [Peter Drayton](#), [Ted Neward](#)

START READING

Publisher: O'Reilly

Pub Date: August 2003

ISBN: 0-596-00526-1

Pages: 926

The heart of *C# in a Nutshell* is a succinct but detailed reference to the C# language and the .NET types most essential to C# programmers. Each chapter in the API reference begins with an overview of a .NET namespace and a diagram of its types, including a quick-reference entry for each type, with name, assembly, category, description, member availability, class hierarchy, and other relevant information, such as whether the type is part of the ECMA CLI specification. Newly updated for .NET Framework version 1.1, the second edition also adds a CD that allows you to integrate the book's API Quick Reference directly into the help files of Visual Studio .NET 2002 & 2003, giving you direct access to this valuable information via your computer.

[\[Team LiB \]](#)

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)



- [Table of Contents](#)
- [Index](#)
- [Reviews](#)
- [Reader Reviews](#)
- [Errata](#)

C# in a Nutshell, 2nd Edition

By [Ben Albahari](#), [Peter Drayton](#), [Ted Neward](#)

[START READING](#)

Publisher: O'Reilly

Pub Date: August 2003

ISBN: 0-596-00526-1

Pages: 926

[Copyright](#)

[Preface](#)

[Audience](#)

[Contents of This Book](#)

[Assumptions This Book Makes](#)

[Conventions Used in This Book](#)

[Related Books](#)

[C# Resources Online](#)

[How to Contact Us](#)

[How the Quick Reference Is Generated](#)

[Acknowledgments](#)

[Part I: Programming with C#](#)

[Chapter 1. Introducing C# and the .NET Framework](#)

[Section 1.1. The C# Language](#)

[Section 1.2. The .NET Framework](#)

[Section 1.3. ECMA Standardization](#)

[Section 1.4. Changes in Visual C# 2003](#)

Chapter 2. C# Language Basics

[Section 2.1. A First C# Program](#)

[Section 2.2. Identifiers and Keywords](#)

[Section 2.3. Type Basics](#)

[Section 2.4. Value Types and Reference Types](#)

[Section 2.5. Predefined Types](#)

[Section 2.6. Arrays](#)

[Section 2.7. Variables and Parameters](#)

[Section 2.8. Expressions and Operators](#)

[Section 2.9. Statements](#)

[Section 2.10. Namespaces](#)

Chapter 3. Creating Types in C#

[Section 3.1. Classes](#)

[Section 3.2. Inheritance](#)

[Section 3.3. Access Modifiers](#)

[Section 3.4. Structs](#)

[Section 3.5. Interfaces](#)

[Section 3.6. Enums](#)

Chapter 4. Advanced C# Features

[Section 4.1. Delegates](#)

[Section 4.2. Delegates Versus Function Pointers](#)

[Section 4.3. Delegates Versus Interfaces](#)

[Section 4.4. Events](#)

[Section 4.5. Operator Overloading](#)

[Section 4.6. Try Statements and Exceptions](#)

[Section 4.7. Attributes](#)

[Section 4.8. Unsafe Code and Pointers](#)

[Section 4.9. Preprocessor Directives](#)

[Section 4.10. XML Documentation](#)

Part II: Programming with the .NET Framework

Chapter 5. Framework Class Library Overview

[Section 5.1. Core Types](#)

[Section 5.2. Text](#)

[Section 5.3. Collections](#)

[Section 5.4. Streams and I/O](#)

[Section 5.5. Networking](#)

[Section 5.6. Threading](#)

[Section 5.7. Security](#)

[Section 5.8. Reflection and Metadata](#)

[Section 5.9. Assemblies](#)

[Section 5.10. Serialization](#)

[Section 5.11. Remoting](#)

[Section 5.12. Web Services](#)

[Section 5.13. Data Access](#)

[Section 5.14. XML](#)

[Section 5.15. Graphics](#)

[Section 5.16. Rich Client Applications](#)

[Section 5.17. Web-Based Applications](#)

[Section 5.18. Globalization](#)

[Section 5.19. Configuration](#)

[Section 5.20. Advanced Component Services](#)

[Section 5.21. Diagnostics and Debugging](#)

[Section 5.22. Interoperating with Unmanaged Code](#)

[Section 5.23. Compiler and Tool Support](#)

[Section 5.24. Runtime Facilities](#)

[Section 5.25. Native OS Facilities](#)

[Section 5.26. Undocumented Types](#)

[Chapter 6. String Handling](#)

[Section 6.1. String Class](#)

[Section 6.2. StringBuilder Class](#)

[Section 6.3. Regular Expression Support](#)

[Section 6.4. Regular Expression Basics](#)

[Section 6.5. Procedural- and Expression-Based Patterns](#)

[Section 6.6. Cookbook Regular Expressions](#)

[Chapter 7. Collections](#)

[Section 7.1. Iterating Over Collections](#)

[Section 7.2. Standard Collection Interfaces](#)

[Section 7.3. Predefined Collection Classes](#)

[Section 7.4. Ordering Instances](#)

[Section 7.5. Generating Hash Code](#)

[Chapter 8. XML I/O](#)

[Section 8.1. Accessing XML Documents](#)

[Section 8.2. Parsing an XML Stream](#)

[Section 8.3. Selecting Nodes Using XPath](#)

[Section 8.4. Transforming a Document Using XSLT](#)

[Chapter 9. Networking](#)

[Section 9.1. Network Programming Models](#)

[Section 9.2. Generic Request/Response Architecture](#)

[Section 9.3. HTTP-Specific Support](#)

[Section 9.4. WebClient](#)

[Section 9.5. Adding New Protocol Handlers](#)

[Section 9.6. Using TCP, UDP, and Sockets](#)

[Section 9.7. Using DNS](#)

[Chapter 10. Streams and I/O](#)

[Section 10.1. Streams and Backing Stores](#)

[Section 10.2. Encapsulating Raw Streams](#)

[Section 10.3. Directories and Files](#)

[Section 10.4. Isolated Storage](#)

[Chapter 11. Serialization](#)

[Section 11.1. What Is Serialization?](#)

[Section 11.2. Serialization Support in the Framework](#)

[Section 11.3. Explicit Serialization](#)

[Section 11.4. Implicit Serialization](#)

[Section 11.5. \[Serializable\]](#)

[Section 11.6. \[NonSerialized\]](#)

[Section 11.7. IDeserializationCallback](#)

[Section 11.8. ISerializable](#)

[Section 11.9. \[Serializable\] and ISerializable](#)

[Chapter 12. Assemblies](#)

[Section 12.1. Elements of an Assembly](#)

[Section 12.2. Assemblies and Modules](#)

[Section 12.3. Scoping Types and Type References](#)

[Section 12.4. Naming and Signing Assemblies](#)

[Section 12.5. Resolving and Loading Assemblies](#)

[Section 12.6. Deployment](#)

[Section 12.7. Security Permissions](#)

[Chapter 13. Reflection](#)

[Section 13.1. Type Hierarchy](#)

[Section 13.2. Types, Members, and Nested Types](#)

[Section 13.3. Retrieving the Type for an Instance](#)

[Section 13.4. Retrieving a Type Directly](#)

[Section 13.5. Reflecting Over a Type Hierarchy](#)

[Section 13.6. Late Binding](#)

[Section 13.7. Advanced Uses of Reflection](#)

[Section 13.8. Creating New Types at Runtime](#)

[Chapter 14. Custom Attributes](#)

[Section 14.1. Language Support](#)

[Section 14.2. Compiler Support](#)

[Section 14.3. Runtime Support](#)

[Section 14.4. Predefined Attributes](#)

[Section 14.5. Defining a New Custom Attribute](#)

[Section 14.6. Retrieving a Custom Attribute at Runtime](#)

[Chapter 15. Memory Management](#)

[Section 15.1. The Garbage Collector](#)

[Section 15.2. Optimization Techniques](#)

[Section 15.3. Finalizers](#)

[Section 15.4. Dispose and Close Methods](#)

[Chapter 16. Threading](#)

[Section 16.1. Thread Synchronization](#)

[Section 16.2. Common Thread Types](#)

[Section 16.3. Asynchronous Delegates](#)

[Chapter 17. Integrating with Native DLLs](#)

[Section 17.1. Calling Into DLLs](#)

[Section 17.2. Marshaling Common Types](#)

[Section 17.3. Marshaling Classes and Structs](#)

[Section 17.4. In and Out Marshaling](#)

[Section 17.5. Callbacks from Unmanaged Code](#)

[Section 17.6. Simulating a C Union](#)

[Section 17.7. Mapping a Struct to a Binary Format](#)

[Section 17.8. Predefined Interop Support Attributes](#)

[Chapter 18. Integrating with COM Components](#)

[Section 18.1. Binding COM and C# Objects](#)

[Section 18.2. Exposing COM Objects to C#](#)

[Section 18.3. Exposing C# Objects to COM](#)

[Section 18.4. COM Mapping in C#](#)

[Section 18.5. Common COM Interop Support Attributes](#)

[Section 18.6. COM+ Support](#)

[Chapter 19. Diagnostics](#)

[Section 19.1. Logging and Assertion Facilities](#)

[Section 19.2. Conditional Compilation](#)

[Section 19.3. Debugger Integration](#)

[Section 19.4. Processes, Threads, and Stacks](#)

[Section 19.5. Event Logs](#)

[Section 19.6. Performance Counters](#)

[Chapter 20. C# Language Reference](#)

[Part III: Language and Tools Reference](#)

[Chapter 21. XML Documentation Tag Reference](#)

[Chapter 22. C# Naming and Coding Conventions](#)

[Section 22.1. Case](#)

[Section 22.2. Mechanics](#)

[Section 22.3. Word Choice](#)

[Section 22.4. Namespaces](#)

[Chapter 23. C# Development Tools](#)

[ADepends.exe](#)

[Al.exe](#)

[Cordbg.exe](#)

[Csc.exe](#)
[DbgCLR.exe](#)
[GacUtil.exe](#)
[ILasm.exe](#)
[ILDasm.exe](#)
[InstallUtil.exe](#)
[Ngen.exe](#)
[Nmake.exe](#)
[PEVerify.exe](#)
[RegAsm.exe](#)
[RegSvcs.exe](#)
[Sn.exe](#)
[SoapSuds.exe](#)
[TlbExp.exe](#)
[TlbImp.exe](#)
[Wsdl.exe](#)
[WinCV.exe](#)
[Xsd.exe](#)

[Part IV: API Quick Reference](#)

[Chapter 24. How to Use This Quick Reference](#)

[Section 24.1. Finding a Quick-Reference Entry](#)

[Section 24.2. Reading a Quick-Reference Entry](#)

[Chapter 25. The Microsoft.Win32 Namespace](#)

[PowerModeChangedEventArgs](#)
[PowerModeChangedEventHandler](#)
[PowerModes](#)
[Registry](#)
[RegistryHive](#)
[RegistryKey](#)
[SessionEndedEventArgs](#)
[SessionEndedEventHandler](#)
[SessionEndingEventArgs](#)
[SessionEndingEventHandler](#)
[SessionEndReasons](#)
[SystemEvents](#)
[TimerElapsedEventArgs](#)
[TimerElapsedEventHandler](#)
[UserPreferenceCategory](#)
[UserPreferenceChangedEventArgs](#)
[UserPreferenceChangedEventHandler](#)
[UserPreferenceChangingEventArgs](#)
[UserPreferenceChangingEventHandler](#)

Chapter 26. System

[Activator](#)
[AppDomain](#)
[AppDomainSetup](#)
[AppDomainUnloadedException](#)
[ApplicationException](#)
[ArgIterator](#)
[ArgumentException](#)
[ArgumentNullException](#)
[ArgumentOutOfRangeException](#)
[ArithmeticException](#)
[Array](#)
[ArrayTypeMismatchException](#)
[AssemblyLoadEventArgs](#)
[AssemblyLoadEventHandler](#)
[AsyncCallback](#)
[Attribute](#)
[AttributeTargets](#)
[AttributeUsageAttribute](#)
[BadImageFormatException](#)
[BitConverter](#)
[Boolean](#)
[Buffer](#)
[Byte](#)
[CannotUnloadAppDomainException](#)
[Char](#)
[CharEnumerator](#)
[CLSCompliantAttribute](#)
[Console](#)
[ContextBoundObject](#)
[ContextMarshalException](#)
[ContextStaticAttribute](#)
[Convert](#)
[CrossAppDomainDelegate](#)
[DateTime](#)
[DayOfWeek](#)
[DBNull](#)
[Decimal](#)
[Delegate](#)
[DivideByZeroException](#)
[DllNotFoundException](#)
[Double](#)
[DuplicateWaitObjectException](#)
[EntryPointNotFoundException](#)
[Enum](#)
[Environment](#)

[Environment.SpecialFolder](#)
[EventArgs](#)
[EventHandler](#)
[Exception](#)
[ExecutionEngineException](#)
[FieldAccessException](#)
[FlagsAttribute](#)
[FormatException](#)
[GC](#)
[Guid](#)
[IAsyncResult](#)
[ICloneable](#)
[IComparable](#)
[IConvertible](#)
[ICustomFormatter](#)
[IDisposable](#)
[IFormatProvider](#)
[IFormattable](#)
[IndexOutOfRangeException](#)
[Int16](#)
[Int32](#)
[Int64](#)
[IntPtr](#)
[InvalidCastException](#)
[InvalidOperationException](#)
[InvalidProgramException](#)
[IServiceProvider](#)
[LoaderOptimization](#)
[LoaderOptimizationAttribute](#)
[LocalDataStoreSlot](#)
[MarshalByRefObject](#)
[Math](#)
[MemberAccessException](#)
[MethodAccessException](#)
[MissingFieldException](#)
[MissingMemberException](#)
[MissingMethodException](#)
[MTAThreadAttribute](#)
[MulticastDelegate](#)
[MulticastNotSupportedException](#)
[NonSerializedAttribute](#)
[NotFiniteNumberException](#)
[NotImplementedException](#)
[NotSupportedException](#)
[NullReferenceException](#)
[Object](#)

[ObjectDisposedException](#)
[ObsoleteAttribute](#)
[OperatingSystem](#)
[OutOfMemoryException](#)
[OverflowException](#)
[ParamArrayAttribute](#)
[PlatformID](#)
[PlatformNotSupportedException](#)
[Random](#)
[RankException](#)
[ResolveEventArgs](#)
[ResolveEventHandler](#)
[RuntimeTypeHandle](#)
[SByte](#)
[SerializableAttribute](#)
[Single](#)
[StackOverflowException](#)
[STAThreadAttribute](#)
[String](#)
[SystemException](#)
[ThreadStaticAttribute](#)
[TimeSpan](#)
[TimeZone](#)
[Type](#)
[TypeCode](#)
[TypeInitializationException](#)
[TypeLoadException](#)
[TypeUnloadedException](#)
[UInt16](#)
[UInt32](#)
[UInt64](#)
[UIntPtr](#)
[UnauthorizedAccessException](#)
[UnhandledExceptionEventArgs](#)
[UnhandledExceptionHandler](#)
[Uri](#)
[UriBuilder](#)
[UriFormatException](#)
[UriHostNameType](#)
[UriPartial](#)
[ValueType](#)
[Version](#)
[Void](#)
[WeakReference](#)

[Chapter 27. System.Collections](#)

[ArrayList](#)
[BitArray](#)
[CaseInsensitiveComparer](#)
[CaseInsensitiveHashCodeProvider](#)
[CollectionBase](#)
[Comparer](#)
[DictionaryBase](#)
[DictionaryEntry](#)
[Hashtable](#)
[ICollection](#)
[IComparer](#)
[IDictionary](#)
[IDictionaryEnumerator](#)
[IEnumerable](#)
[IEnumerator](#)
[IHashCodeProvider](#)
[IList](#)
[Queue](#)
[ReadOnlyCollectionBase](#)
[SortedList](#)
[Stack](#)

[Chapter 28. System.Collections.Specialized](#)

[BitVector32](#)
[BitVector32.Section](#)
[CollectionsUtil](#)
[HybridDictionary](#)
[ListDictionary](#)
[NameObjectCollectionBase](#)
[NameObjectCollectionBase.KeysCollection](#)
[NameValueCollection](#)
[StringCollection](#)
[StringDictionary](#)
[StringEnumerator](#)

[Chapter 29. System.Diagnostics](#)

[BooleanSwitch](#)
[ConditionalAttribute](#)
[CounterCreationData](#)
[CounterCreationDataCollection](#)
[CounterSample](#)
[CounterSampleCalculator](#)
[Debug](#)
[DebuggableAttribute](#)
[Debugger](#)
[DebuggerHiddenAttribute](#)

[DebuggerStepThroughAttribute](#)
[DefaultTraceListener](#)
[EntryWrittenEventArgs](#)
[EntryWrittenEventHandler](#)
[EventLog](#)
[EventLogEntry](#)
[EventLogEntryCollection](#)
[EventLogEntryType](#)
[EventLogInstaller](#)
[EventLogPermission](#)
[EventLogPermissionAccess](#)
[EventLogPermissionAttribute](#)
[EventLogPermissionEntry](#)
[EventLogPermissionEntryCollection](#)
[EventLogTraceListener](#)
[FileVersionInfo](#)
[InstanceData](#)
[InstanceDataCollection](#)
[InstanceDataCollectionCollection](#)
[MonitoringDescriptionAttribute](#)
[PerformanceCounter](#)
[PerformanceCounterCategory](#)
[PerformanceCounterInstaller](#)
[PerformanceCounterPermission](#)
[PerformanceCounterPermissionAccess](#)
[PerformanceCounterPermissionAttribute](#)
[PerformanceCounterPermissionEntry](#)
[PerformanceCounterPermissionEntryCollection](#)
[PerformanceCounterType](#)
[Process](#)
[ProcessModule](#)
[ProcessModuleCollection](#)
[ProcessPriorityClass](#)
[ProcessStartInfo](#)
[ProcessThread](#)
[ProcessThreadCollection](#)
[ProcessWindowStyle](#)
[StackFrame](#)
[StackTrace](#)
[Switch](#)
[TextWriterTraceListener](#)
[ThreadPriorityLevel](#)
[ThreadState](#)
[ThreadWaitReason](#)
[Trace](#)
[TraceLevel](#)

[TraceListener](#)
[TraceListenerCollection](#)
[TraceSwitch](#)

[Chapter 30. System.Globalization](#)

[Calendar](#)
[CalendarWeekRule](#)
[CompareInfo](#)
[CompareOptions](#)
[CultureInfo](#)
[CultureTypes](#)
[DateTimeFormatInfo](#)
[DateTimeStyles](#)
[DaylightTime](#)
[GregorianCalendar](#)
[GregorianCalendarTypes](#)
[HebrewCalendar](#)
[HijriCalendar](#)
[JapaneseCalendar](#)
[JulianCalendar](#)
[KoreanCalendar](#)
[NumberFormatInfo](#)
[NumberStyles](#)
[RegionInfo](#)
[SortKey](#)
[StringInfo](#)
[TaiwanCalendar](#)
[TextElementEnumerator](#)
[TextInfo](#)
[ThaiBuddhistCalendar](#)
[UnicodeCategory](#)

[Chapter 31. System.IO](#)

[BinaryReader](#)
[BinaryWriter](#)
[BufferedStream](#)
[Directory](#)
[DirectoryInfo](#)
[DirectoryNotFoundException](#)
[EndOfStreamException](#)
[ErrorEventArgs](#)
[ErrorEventHandler](#)
[File](#)
[FileAccess](#)
[FileAttributes](#)
[FileInfo](#)

- [FileLoadException](#)
- [FileMode](#)
- [FileNotFoundException](#)
- [FileShare](#)
- [FileStream](#)
- [FileSystemEventArgs](#)
- [FileSystemEventHandler](#)
- [FileSystemInfo](#)
- [FileSystemWatcher](#)
- [InternalBufferOverflowException](#)
- [IODescriptionAttribute](#)
- [IOException](#)
- [MemoryStream](#)
- [NotifyFilters](#)
- [Path](#)
- [PathTooLongException](#)
- [RenamedEventArgs](#)
- [RenamedEventHandler](#)
- [SeekOrigin](#)
- [Stream](#)
- [StreamReader](#)
- [StreamWriter](#)
- [StringReader](#)
- [StringWriter](#)
- [TextReader](#)
- [TextWriter](#)
- [WaitForChangedResult](#)
- [WatcherChangeTypes](#)

[Chapter 32. System.IO.IsolatedStorage](#)

- [INormalizeForIsolatedStorage](#)
- [IsolatedStorage](#)
- [IsolatedStorageException](#)
- [IsolatedStorageFile](#)
- [IsolatedStorageFileStream](#)
- [IsolatedStorageScope](#)

[Chapter 33. System.Net](#)

- [AuthenticationManager](#)
- [Authorization](#)
- [Cookie](#)
- [CookieCollection](#)
- [CookieContainer](#)
- [CookieException](#)
- [CredentialCache](#)
- [Dns](#)

[DnsPermission](#)
[DnsPermissionAttribute](#)
[EndPoint](#)
[EndpointPermission](#)
[FileWebRequest](#)
[FileWebResponse](#)
[GlobalProxySelection](#)
[HttpContinueDelegate](#)
[HttpStatusCode](#)
[HttpVersion](#)
[HttpRequest](#)
[HttpResponse](#)
[IAuthenticationModule](#)
[ICertificatePolicy](#)
[ICredentials](#)
[IPAddress](#)
[IEndPoint](#)
[IHostEntry](#)
[IWebProxy](#)
[IWebRequestCreate](#)
[NetworkAccess](#)
[NetworkCredential](#)
[ProtocolViolationException](#)
[SecurityProtocolType](#)
[ServicePoint](#)
[ServicePointManager](#)
[SocketAddress](#)
[SocketPermission](#)
[SocketPermissionAttribute](#)
[TransportType](#)
[WebClient](#)
[WebException](#)
[WebExceptionStatus](#)
[WebHeaderCollection](#)
[WebPermission](#)
[WebPermissionAttribute](#)
[WebProxy](#)
[WebRequest](#)
[WebResponse](#)

[Chapter 34. System.Net.Sockets](#)

[AddressFamily](#)
[IPv6MulticastOption](#)
[LingerOption](#)
[MulticastOption](#)
[NetworkStream](#)

[ProtocolFamily](#)
[ProtocolType](#)
[SelectMode](#)
[Socket](#)
[SocketException](#)
[SocketFlags](#)
[SocketOptionLevel](#)
[SocketOptionName](#)
[SocketShutdown](#)
[SocketType](#)
[TcpClient](#)
[TcpListener](#)
[UdpClient](#)

[Chapter 35. System.Reflection](#)

[AmbiguousMatchException](#)
[Assembly](#)
[AssemblyAlgorithmIdAttribute](#)
[AssemblyCompanyAttribute](#)
[AssemblyConfigurationAttribute](#)
[AssemblyCopyrightAttribute](#)
[AssemblyCultureAttribute](#)
[AssemblyDefaultAliasAttribute](#)
[AssemblyDelaySignAttribute](#)
[AssemblyDescriptionAttribute](#)
[AssemblyFileVersionAttribute](#)
[AssemblyFlagsAttribute](#)
[AssemblyInformationalVersionAttribute](#)
[AssemblyKeyFileAttribute](#)
[AssemblyKeyNameAttribute](#)
[AssemblyName](#)
[AssemblyNameFlags](#)
[AssemblyNameProxy](#)
[AssemblyProductAttribute](#)
[AssemblyTitleAttribute](#)
[AssemblyTrademarkAttribute](#)
[AssemblyVersionAttribute](#)
[Binder](#)
[BindingFlags](#)
[CallingConventions](#)
[ConstructorInfo](#)
[CustomAttributeFormatException](#)
[DefaultMemberAttribute](#)
[EventAttributes](#)
[EventInfo](#)
[FieldAttributes](#)

[FieldInfo](#)
[ICustomAttributeProvider](#)
[InterfaceMapping](#)
[InvalidFilterCriteriaException](#)
[IReflect](#)
[ManifestResourceInfo](#)
[MemberFilter](#)
[MemberInfo](#)
[MemberTypes](#)
[MethodAttributes](#)
[MethodBase](#)
[MethodImplAttributes](#)
[MethodInfo](#)
[Missing](#)
[Module](#)
[ModuleResolveEventHandler](#)
[ParameterAttributes](#)
[ParameterInfo](#)
[ParameterModifier](#)
[Pointer](#)
[PropertyAttributes](#)
[PropertyInfo](#)
[ReflectionTypeLoadException](#)
[ResourceAttributes](#)
[ResourceLocation](#)
[StrongNameKeyPair](#)
[TargetException](#)
[TargetInvocationException](#)
[TargetParameterCountException](#)
[TypeAttributes](#)
[TypeDelegator](#)
[TypeFilter](#)

[Chapter 36. System.Reflection.Emit](#)

[AssemblyBuilder](#)
[AssemblyBuilderAccess](#)
[ConstructorBuilder](#)
[CustomAttributeBuilder](#)
[EnumBuilder](#)
[EventBuilder](#)
[EventToken](#)
[FieldBuilder](#)
[FieldToken](#)
[FlowControl](#)
[ILGenerator](#)
[Label](#)

[LocalBuilder](#)
[MethodBuilder](#)
[MethodRental](#)
[MethodToken](#)
[ModuleBuilder](#)
[OpCode](#)
[OpCodes](#)
[OpCodeType](#)
[OperandType](#)
[PackingSize](#)
[ParameterBuilder](#)
[ParameterToken](#)
[PEFileKinds](#)
[PropertyBuilder](#)
[PropertyToken](#)
[SignatureHelper](#)
[SignatureToken](#)
[StackBehaviour](#)
[StringToken](#)
[TypeBuilder](#)
[TypeToken](#)
[UnmanagedMarshal](#)

[Chapter 37. System.Runtime.InteropServices](#)

[ArrayWithOffset](#)
[AssemblyRegistrationFlags](#)
[BestFitMappingAttribute](#)
[CallingConvention](#)
[CharSet](#)
[ClassInterfaceAttribute](#)
[ClassInterfaceType](#)
[CoClassAttribute](#)
[ComAliasNameAttribute](#)
[ComCompatibleVersionAttribute](#)
[ComConversionLossAttribute](#)
[COMException](#)
[ComImportAttribute](#)
[ComInterfaceType](#)
[ComMemberType](#)
[ComRegisterFunctionAttribute](#)
[ComSourceInterfacesAttribute](#)
[ComUnregisterFunctionAttribute](#)
[ComVisibleAttribute](#)
[CurrencyWrapper](#)
[DispatchWrapper](#)
[DispIdAttribute](#)

[DllImportAttribute](#)
[ErrorWrapper](#)
[ExtensibleClassFactory](#)
[ExternalException](#)
[FieldOffsetAttribute](#)
[GCHandle](#)
[GCHandleType](#)
[GuidAttribute](#)
[HandleRef](#)
[IDispatchImplAttribute](#)
[IDispatchImplType](#)
[InAttribute](#)
[InterfaceTypeAttribute](#)
[InvalidComObjectException](#)
[InvalidOleVariantTypeException](#)
[IRegistrationServices](#)
[LayoutKind](#)
[LCIDConversionAttribute](#)
[Marshal](#)
[MarshalAsAttribute](#)
[MarshalDirectiveException](#)
[ObjectCreationDelegate](#)
[OptionalAttribute](#)
[OutAttribute](#)
[PreserveSigAttribute](#)
[ProgIdAttribute](#)
[RegistrationServices](#)
[RuntimeEnvironment](#)
[SafeArrayRankMismatchException](#)
[SafeArrayTypeMismatchException](#)
[SEHException](#)
[StructLayoutAttribute](#)
[TypeLibVersionAttribute](#)
[UnknownWrapper](#)
[UnmanagedType](#)
[VarEnum](#)
[IExpando](#)

[Chapter 38. System.Runtime.Serialization](#)

[Formatter](#)
[FormatterConverter](#)
[FormatterServices](#)
[IDeserializationCallback](#)
[IFormatter](#)
[IFormatterConverter](#)
[IObjectReference](#)

- [ISerializable](#)
- [ISerializationSurrogate](#)
- [ISurrogateSelector](#)
- [ObjectIDGenerator](#)
- [ObjectManager](#)
- [SerializationBinder](#)
- [SerializationEntry](#)
- [SerializationException](#)
- [SerializationInfo](#)
- [SerializationInfoEnumerator](#)
- [StreamingContext](#)
- [StreamingContextStates](#)
- [SurrogateSelector](#)

[Chapter 39. System.Runtime.Serialization.Formatters](#)

- [BinaryFormatter](#)
- [FormatterAssemblyStyle](#)
- [FormatterTypeStyle](#)
- [IFieldInfo](#)
- [ISoapMessage](#)
- [ServerFault](#)
- [SoapFault](#)
- [SoapFormatter](#)
- [SoapMessage](#)
- [TypeFilterLevel](#)

[Chapter 40. System.Text](#)

- [ASCIIEncoding](#)
- [Decoder](#)
- [Encoder](#)
- [Encoding](#)
- [StringBuilder](#)
- [UnicodeEncoding](#)
- [UTF7Encoding](#)
- [UTF8Encoding](#)

[Chapter 41. System.Text.RegularExpressions](#)

- [Capture](#)
- [CaptureCollection](#)
- [Group](#)
- [GroupCollection](#)
- [Match](#)
- [MatchCollection](#)
- [MatchEvaluator](#)
- [Regex](#)
- [RegexCompilationInfo](#)

[RegexOptions](#)

[Chapter 42. System.Threading](#)

[ApartmentState](#)

[AutoResetEvent](#)

[Interlocked](#)

[IOCompletionCallback](#)

[LockCookie](#)

[ManualResetEvent](#)

[Monitor](#)

[Mutex](#)

[NativeOverlapped](#)

[Overlapped](#)

[ReaderWriterLock](#)

[RegisteredWaitHandle](#)

[SynchronizationLockException](#)

[Thread](#)

[ThreadAbortException](#)

[ThreadExceptionEventArgs](#)

[ThreadExceptionHandler](#)

[ThreadInterruptedException](#)

[ThreadPool](#)

[ThreadPriority](#)

[ThreadStart](#)

[ThreadState](#)

[ThreadStateException](#)

[Timeout](#)

[Timer](#)

[TimerCallback](#)

[WaitCallback](#)

[WaitHandle](#)

[WaitOrTimerCallback](#)

[Chapter 43. System.Timers](#)

[ElapsedEventArgs](#)

[ElapsedEventHandler](#)

[Timer](#)

[TimersDescriptionAttribute](#)

[Chapter 44. System.Xml](#)

[EntityHandling](#)

[Formatting](#)

[IHasXmlNode](#)

[IXmlLineInfo](#)

[NameTable](#)

[ReadState](#)

[ValidationType](#)
[WhitespaceHandling](#)
[WriteState](#)
[XmlAttribute](#)
[XmlAttributeCollection](#)
[XmlCDataSection](#)
[XmlCharacterData](#)
[XmlComment](#)
[XmlConvert](#)
[XmlDataDocument](#)
[XmlDeclaration](#)
[XmlDocument](#)
[XmlDocumentFragment](#)
[XmlDocumentType](#)
[XmlElement](#)
[XmlEntity](#)
[XmlEntityReference](#)
[XmlException](#)
[XmlImplementation](#)
[XmlLinkedNode](#)
[XmlNamedNodeMap](#)
[XmlNamespaceManager](#)
[XmlNameTable](#)
[XmlNode](#)
[XmlNodeChangedAction](#)
[XmlNodeChangedEventArgs](#)
[XmlNodeChangedEventHandler](#)
[XmlNodeList](#)
[XmlNodeOrder](#)
[XmlNodeReader](#)
[XmlNodeType](#)
[XmlNotation](#)
[XmlParserContext](#)
[XmlProcessingInstruction](#)
[XmlQualifiedName](#)
[XmlReader](#)
[XmlResolver](#)
[XmlSecureResolver](#)
[XmlSignificantWhitespace](#)
[XmlSpace](#)
[XmlText](#)
[XmlTextReader](#)
[XmlTextWriter](#)
[XmlTokenizedType](#)
[XmlUriResolver](#)
[XmlValidatingReader](#)

[XmlWhitespace](#)

[XmlWriter](#)

[Chapter 45. System.Xml.XPath](#)

[XPathNavigable](#)

[XmlCaseOrder](#)

[XmlDataType](#)

[XmlSortOrder](#)

[XPathDocument](#)

[XPathException](#)

[XPathExpression](#)

[XPathNamespaceScope](#)

[XPathNavigator](#)

[XPathNodeIterator](#)

[XPathNodeType](#)

[XPathResultType](#)

[Chapter 46. System.Xml.Xsl](#)

[IXsltContextFunction](#)

[IXsltContextVariable](#)

[XsltArgumentList](#)

[XsltCompileException](#)

[XsltContext](#)

[XsltException](#)

[XsltTransform](#)

[Part V: Appendixes](#)

[Appendix A. Regular Expressions](#)

[Appendix B. Format Specifiers](#)

[Section B.1. Picture Format Specifiers](#)

[Section B.2. DateTime Format Specifiers](#)

[Appendix C. Data Marshaling](#)

[Appendix D. C# Keywords](#)

[Appendix E. Namespaces and Assemblies](#)

[Appendix F. Type, Method, Property, Event, and Field Index](#)

[A-D](#)

[E-I](#)

[J-R](#)

[S-Z](#)

[Colophon](#)

[Index](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Copyright

Copyright © 2003, 2002 O'Reilly & Associates, Inc.

Printed in the United States of America.

Published by O'Reilly & Associates, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly & Associates books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (<http://safari.oreilly.com>). For more information, contact our corporate/institutional sales department: (800) 998-9938 or corporate@oreilly.com.

Nutshell Handbook, the Nutshell Handbook logo, and the O'Reilly logo are registered trademarks of O'Reilly & Associates, Inc. Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly & Associates, Inc. was aware of a trademark claim, the designations have been printed in caps or initial caps. The association between the image of a numidian crane and the topic of C# is a trademark of O'Reilly & Associates, Inc.

Microsoft, .NET logo, Visual Basic .NET, Visual Studio .NET, and Windows are registered trademarks of Microsoft Corporation.

While every precaution has been taken in the preparation of this book, the publisher and authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Preface

This book is a desktop reference for Microsoft's C# programming language, designed to sit comfortably next to you while you program and to accompany you faithfully in your travels. The first version of C# shipped in January 2002 as part of Visual Studio .NET and the .NET Framework, after an extensive public beta release.

C# in a Nutshell is divided into four parts (along with five appendixes and a Type, Method, Property, Event, and Field Index). [Part I](#) introduces the C# language and the .NET Common Language Runtime (CLR). It is a fast-paced, no-fluff introduction to the C# programming language, from its data types through all of the statements and features that make it the modern component-oriented language it was designed to be.

[Part II](#) shows how to use the C# language in conjunction with core classes of the .NET Framework Class Library (FCL) to accomplish a variety of common programming tasks, from manipulating strings to interacting with legacy COM components. [Part III](#) contains a number of useful references, including a summary of C# syntax, presented in the unique notation developed for both this title and *C# Essentials*, as well as a reference to useful command-line tools that ship with Visual Studio .NET and the .NET Framework.

[Part IV](#) is a quick reference to 21 of the most important namespaces of the FCL and their more than 700 types, complete with namespace maps, type descriptions, member signatures, and useful cross references and annotations. Also included is a class and method index that can be used to locate the type in which a given member is found or the namespace that contains a given type.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Audience

If you're a working C# programmer, we think you'll want *C# in a Nutshell* to be part of your reference library regardless of your present level of ability. With its thorough coverage of language elements, its compact language and tools reference, and its unique, jam-packed guide to the core FCL APIs, you should easily be able to find answers to most questions of syntax and functionality that you will encounter on the job.

If you are an experienced Java, C++, or Visual Basic programmer encountering the C# language and the CLR for the first time, this book will enable you to master the essentials of the language. Less experienced programmers may wish to first work through an introductory text, such as *Programming C#*, by Jesse Liberty (O'Reilly & Associates).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Contents of This Book

[Part I](#), [Part II](#), and [Part III](#) of this book document the C# language, the .NET CLR, and relevant tools that ship with the .NET Framework downloadable SDK. [Part I](#), *Programming with C#*, introduces the C# language and the .NET Framework:

[Chapter 1](#)

[Chapter 1](#) provides an overview of the C# language and the .NET Framework, with special attention to their key features and benefits.

[Chapter 2](#)

This chapter introduces the elements of the C# language, including data types and basic constructs such as expressions and statements. Special notation is used throughout the chapter to summarize C# syntax rules for later reference.

[Chapter 3](#)

[Chapter 3](#) explains how to define and instantiate new types in C#. In C#, all classes are components that embody both executable code and metadata used by the CLR at runtime.

[Chapter 4](#)

This chapter explains features of the C# language used to handle events and exceptions, callbacks, custom attributes and more.

[Part II](#) contains:

[Chapter 5](#)

[Chapter 5](#) is an overview of the core .NET Framework APIs covered in this book. The APIs themselves are covered in [Part IV](#). Here you will find a summary of the support you can expect in each functional area of the FCL, along with lists of the namespaces in which the relevant types are found.

[Chapter 6](#),

This chapter describes key FCL types available for string manipulation and shows how to program them using C#. The FCL offers a wide range of advanced string handling features. FCL types for regular expression matching and replacement capabilities based on Perl5 regular expressions are also covered.

[Chapter 7](#)

[Chapter 7](#) presents the most important FCL types for working with common data structures such as arrays, hashtables, dictionaries, stacks, and more. Also covered are key collection interfaces such as `IEnumerable`, `ICollection`, and `Comparable`.

[Chapter 8](#)

This chapter introduces built-in FCL support for XML, explains the relationships between XML and the I/O system in general, demonstrates the consumption and production of XML documents in both node-based and Infoset-based forms, highlights the use of XPath, and

explores XSLT.

[Chapter 9](#)

The FCL includes a number of types that make accessing networked resources easy. [Chapter 9](#) describes the core networking support in the FCL and provides numerous examples leveraging the predefined classes.

[Chapter 10](#)

This chapter introduces built-in FCL support for handling streams and I/O, explains relationships between the abstract and concrete classes in the streams architecture, demonstrates their usage, and explores the filesystem-specific support.

[Chapter 11](#)

[Chapter 11](#) introduces the built-in support for object serialization and deserialization, and demonstrates how clients and objects can participate in the serialization and deserialization process.

[Chapter 12](#)

This chapter explains the configuration and use of assemblies, the fundamental unit of deployment in .NET. The FCL provides attributes and types for managing assemblies, which are also covered.

[Chapter 13](#)

[Chapter 13](#) describes the key FCL types available for examining the metadata of existing types using reflection. Creating new types (and associated metadata) is termed `Reflection.Emit`, and is done via the types in the `System.Reflection.Emit` namespace, which is also explored in this chapter.

[Chapter 14](#)

Types, members, modules, and assemblies all have associated metadata that is used by all the major CLR services, which is considered an indivisible part of an application, and can be accessed via reflection, as explained in [Chapter 13](#). This chapter explains how to add custom metadata to application elements by writing custom attributes.

[Chapter 15](#)

The .NET Framework provides automatic garbage collection of types no longer in use, and allows programmers to provide their own finalizers via C# destructors. This chapter also shows how to provide `Dispose()` or `Close()` methods to clean up after an object whose work is finished.

[Chapter 16](#)

[Chapter 16](#) explains the use of FCL types to manage application threads. C# provides a lock statement to synchronize access to shared resources, and the FCL includes a `Monitor` class to implement `pulse` and `wait`, `atomic`, and other thread operations.

[Chapter 17](#)

This chapter explains the PInvoke services through which C# programs can interact with legacy DLLs.

[Chapter 18](#)

[Chapter 18](#) discusses FCL types and attributes used to expose COM objects to C# programs and to expose C# objects to COM.

[Chapter 19](#)

Because providing integrated error handling and reporting is such a common need among applications, the .NET Framework provides a diverse set of facilities to monitor application behavior, detect runtime errors, inspect the application environment, report application status, and integrate with debugging tools if available. This chapter introduces the debugging and diagnostics support provided by the FCL.

[Chapter 20](#)

[Chapter 20](#) contains a concise alphabetical listing of all C# language constructs and their syntax.

[Part III](#) contains:

[Chapter 21](#)

C# provides XML documentation tags that facilitate the development of application documentation within the source code itself. This chapter presents the tags available to programmers and illustrates their use.

[Chapter 22](#)

[Chapter 22](#) proposes guidelines for naming and casing elements of C# programs. The guidelines are drawn from official Microsoft documents and the experiences of the authors.

[Chapter 23](#)

This chapter is a reference to useful command-line tools that ship with Visual Studio .NET and the .NET Framework, including the compiler and debugger.

The 23 chapters in Parts I-III of *C# in a Nutshell* teach you the C# language and get you up and running with many of the most important APIs of the .NET Framework. The other half of the book is [Part IV](#), which is a succinct but detailed API reference of 21 important namespaces and more than 700 core types and their members. Please be sure to read [Chapter 24](#), *How to Use This Quick Reference*, which appears at the beginning of [Part IV](#) and explains how to get the most from its content.

[Part V](#) includes additional reference tables for regular expression syntax ([Appendix A](#)); format specifiers ([Appendix B](#)); C#-to-COM default data mapping ([Appendix C](#)); a glossary of C# keywords ([Appendix D](#)); an alphabetical list of .NET namespaces and the DLLs that expose them ([Appendix E](#)); and a [Appendix F](#) in which you can look up a method or field and find what type it is defined in.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Assumptions This Book Makes

To program in C#, you must have installed one of the many editions of Visual Studio .NET on your system (Standard, Professional, Enterprise, or Architect), or have downloaded and installed the .NET Framework SDK. Visual Studio provides a complete interactive developer environment that simplifies many of the tasks of C# programming, especially the development of Windows clients, server-side web applications and web services. In addition, Visual Studio provides excellent support for the debugging and project management of applications.

However, with the .NET Framework SDK installed on your system you can write C# programs using an editor such as emacs, SharpDevelop, or Microsoft Notepad, and compile, debug, and execute them using the command-line utilities described in [Chapter 23](#).

To download the .NET Framework SDK (currently a 106 MB file), see <http://msdn.microsoft.com/net/>.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Conventions Used in This Book

The following typographical conventions are used in this book.

Italic is used for:

- Directory pathnames and filenames
- Domain names and example URLs
- New terms where they are first defined

`Constant width` is used for:

- Code examples and output
- Names and keywords in C# programs, including method or field names, variable names, and class names
- XML and HTML element tags
- Registry keys

`Constant width italic` is used for:

- Replaceable parameter names or user-provided elements in syntax

In several parts of this book, we have included simple grammar specifications for many, but not all, of the language constructs introduced in this book, to provide you with a fast way to understand the grammar of a particular construct and its valid combinations. In this grammar syntax, the XML occurrence operators (`?`, `*`, and `+`) are used to specify more precisely the number of times an element may occur in a particular construct:

`x`

Indicates `x` is to be used verbatim (`constant width`)

`x`

Indicates `x` is supplied by the programmer (`constant width italic`)

`x?`

Indicates `x` may occur zero or one times.

`x*`

Indicates `x` may occur zero or more times, separated by commas.

`x+`

Indicates x may occur one or more times, separated by commas.

[...]

Indicates a logical grouping of code elements, when not implicitly grouped using the verbatim terms { }, (), and [].

[x|y]

Indicates only one of a choice of code elements may occur.



This icon designates a note, which is an important aside to the nearby text.

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Related Books

O'Reilly & Associates, Inc., publishes an entire series of books on C# programming and .NET, including several companion books to this one. Some recommended books in the O'Reilly .NET series include:

- *Programming C#*, by Jesse Liberty
- *.NET Framework Essentials*, by Thuan Thai and Hoang Q. Lam
- *VB.NET Language in a Nutshell*, by Steven Roman, Ron Petruscha, and Paul Lomax
- *Programming Visual Basic .NET*, by Dave Grundgeiger
- *Programming ASP.NET*, by Jesse Liberty and Dan Hurwitz
- *C# and VB.NET Conversion Pocket Reference*, by Jose Mojica

You can find a complete list of O'Reilly .NET books and other programming titles at <http://dotnet.oreilly.com>.

We also recommend *C# Primer: A Practical Approach*, by Stanley B. Lippman (Addison-Wesley Professional) and *Effective Java*, by Joshua Bloch (Addison-Wesley Professional) (an excellent programming book for C# programmers as well).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

C# Resources Online

Even this book cannot answer every question you might have about the language. There are many online resources that can help you get the most out of C#. We recommend the following sites:

<http://msdn.microsoft.com/net/>

The Microsoft .NET Developer Center is the official site for all things .NET, including the latest version of the .NET Framework SDK, as well as documentation, technical articles, sample code, pointers to discussion groups, and third-party resources.

<http://www.gotdotnet.com>

Community support site run by the .NET Framework team. Includes articles, specifications, and numerous samples from .NET Framework team members and the community at large.

<http://discuss.develop.com>

The DevelopMentor DOTNET discussion lists are the best site for freewheeling, independent discussion of the .NET Framework; participants often include key Microsoft engineers and program managers.

<http://www.ecma.ch/ecma1/stand/ECMA-334.htm>

<http://www.ecma.ch/ecma1/stand/ECMA-335.htm>

The official ECMA C# (ECMA-334) and CLI (ECMA-335) specifications.

<http://www.ondotnet.com>

The .NET DevCenter on the O'Reilly Network, featuring original articles, news, and weblogs of interest to .NET programmers.

<http://dotnet.oreilly.com>

The O'Reilly .NET Center. Visit this page frequently for information on current and upcoming books from O'Reilly. You'll find sample chapters, articles, and other resources.

<http://msdn.microsoft.com/community/net.asp>

A list of third-party resources for C# and .NET Framework developers.

You can also find Usenet discussions about .NET in the *microsoft.public.dotnet.** family of newsgroups. In addition, the newsgroup *microsoft.public.dotnet.languages.csharp* specifically addresses C#. If your news server does not carry these groups, you can find them at <news://msnews.microsoft.com>.

Lastly, two articles of interest are:

http://windows.oreilly.com/news/hejlsberg_0800.html

An interview with chief C# architect Anders Hejlsberg, by O'Reilly editor John Osborn.

http://www.genamics.com/developer/csharp_comparative.htm

A comparison of C# to C++ and Java by coauthor Ben Albahari.

[\[Team LiB \]](#)

[← PREVIOUS](#) [NEXT →](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

How to Contact Us

We have tested and verified the information in this book to the best of our ability, but you may find that features have changed (or even that we have made mistakes!). Please let us know about any errors you find, as well as your suggestions for future editions, by writing to:

O'Reilly & Associates, Inc.
1005 Gravenstein Highway North
Sebastopol, CA 95472
(800) 998-9938 (in the U.S. or Canada)
(707) 829-0515 (international/local)
(707) 829-0104 (fax)

You can also send us messages electronically. To be put on the mailing list or request a catalog, send email to:

info@oreilly.com

To ask technical questions or comment on the book, send email to:

bookquestions@oreilly.com

We have a web site for the book, where we'll list examples, errata, and any plans for future editions. You can access this page at:

<http://www.oreilly.com/catalog/csharpnut2/>

For more information about this book and others, see the following O'Reilly web sites:

<http://www.oreilly.com>
<http://dotnet.oreilly.com>

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

How the Quick Reference Is Generated

[Part IV](#) was generated using .NET's reflection API (described in [Chapter 13](#)). Using reflection, we drilled down into selected classes, structs, enums, delegates, and interfaces from the Framework Class Library, and extracted detailed information on each type and its members. Next, we structured this information as DocBook XML, which we used to generate the printed pages.

Each detailed type listing is accompanied by one or more paragraphs describing the type and its significant members. These descriptions offer an overview of how you can use the type in your own applications and describe related types, pitfalls, and useful features.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Acknowledgments

This book would not be possible without the contribution and support of many individuals, including family, friends, and the hard-working folks at O'Reilly & Associates, Inc.

Brian Jepson and Lenny Muellner developed the programs responsible for generating [Part IV](#) and the [Appendix F](#). Brian also developed the namespace maps that are found in the overviews that begin each chapter of the Reference with input from Ted and Peter. Peter Drayton developed the program that generated material for [Appendix E](#). Ted Neward, Matthew MacDonald, Martin Smith, Steve Spainhour, and Brian Jepson wrote the more than 700 insightful namespace and type descriptions that make the API reference so valuable.

Brad Merrill of Microsoft wrote the sections on regular expressions and provided content for [Appendix A](#).

Brad Abrams and members of his .NET Framework team contributed to the design of the API reference and provided technical review that immeasurably improved its quality. Additional technical review of the manuscript was provided by Joe Nalewabau and Kerry Loynd of Microsoft.

The C# in a Nutshell for Visual Studio .NETCD that accompanies the print version of this book is the work of many individuals. Mike Sierra of O'Reilly converted the API Quick Reference entries to Microsoft Help 2.0 format and added the XML tags needed to integrate their content with the Visual Studio .NET Dynamic Help system. His work was made easier by former O'Reilly tools group members Lenny Muellner and Erik Ray who wrote the scripts for converting Frame pages to HTML. The O'Reilly Tech Support group tested each pre-release build of the software.

Our thanks also to Kipper York and Shane McRoberts, former members of the Microsoft Help team, who provided invaluable technical assistance at critical moments during our initial encounters with Visual Studio .NET Dynamic Help. Erik Promislow of Active State built the install packages that make our Help files an integral part of the Visual Studio .NET developer environment. Frank Gocinski of the Visual Studio .NET third-party integration program was instrumental in making O'Reilly a full Microsoft VSIP partner. A special tip of the hat as well to Rob Howard of Microsoft who understood our original vision and helped us make the right connections to get this project off the ground

Peter Drayton

Above all, I'd like to thank my wife Julie DuBois, who never fails to make days spent without .NET even more wonderful than days spent *with* .NET. I'd also like to thank Ben Albahari, for charging the C# and .NET hill with me for the second time in less than 18 months; Ted Neward, who played the role of the cavalry, arriving at an opportune time and making the back half of the book all that it could be; and Brian Jepson, Nancy Kotary, and John Osborn for their tireless support and efforts (editorial and otherwise).

Casting a slightly wider net, the stories in this book were immeasurably improved by comments and insights from Simon Fell, Don Box, Brock Allen, and all the other incredibly smart, talented DevelopMentor instructors I am fortunate to count as colleagues.

Lastly, I'd like to dedicate this book to my father, Peter Drayton, Sr., and my late mother, Irene Mary Rochford Drayton, for giving me a strong rudder to navigate life.

Ben Albahari

I'd like to thank Peter, for asking me to participate in this book and who has yet to fail at making me enthusiastic about what I do; the O'Reilly editors (Brian, Nancy, and John) for their commitment and courteous patience required to finish this project; Ted, for joining us to tackle the most formidable part of the book; and my girlfriend, Karen, who motivated me with a mixture of love and logic.

Ted Neward

First and foremost, my thanks to Peter for inviting (dragging?) me into this project. I've had nothing but fun working with him and Ben on what I hope is a useful resource for the thousands of expatriate C++, Java, and VB programmers flocking to this new language. Second, my thanks to the team at O'Reilly, for making my first O'Reilly book a wonderful experience. Third, my thanks to my students, past and present, who challenged, questioned, argued, and laughed (hysterically, maybe) at my C# teaching efforts. Fourth, my thanks to Don Box and Mike Abercrombie, for DevelopMentor and the wonderful culture they created there, and for allowing me to be a part of it. Last, but of course not least, I want to thank my wonderful family: my wife Charlotte, and my sons Michael and Matthew, for putting up with Dad while he once again disappeared into the study for a while.

I would also like to thank you, the reader, for taking the time to include us as part of your C# experience. It is my hope that our efforts will yield fruit in the form of less time to learn C#, leaving you more time to spend with your family and friends. It may seem trite to say it, but in this "new age" in which we find ourselves, such things are as valuable as gold; as for me and my newfound time, I'm going off for pizza with my family.

[\[Team LiB \]](#)

[< PREVIOUS](#) [NEXT >](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Part I: Programming with C#

Part I introduces the C# language and the .NET Framework:

[Chapter 1](#)

[Chapter 2](#)

[Chapter 3](#)

[Chapter 4](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 1. Introducing C# and the .NET Framework

C# is a programming language from Microsoft designed specifically to target the .NET Framework. Microsoft's .NET Framework is a runtime environment and class library that dramatically simplifies the development and deployment of modern, component-based applications.

When the .NET Framework and C# language compiler were shipped in final form in January 2002, both the platform and programming language had already garnered much industry attention and widespread use among Microsoft-centric early adopters. Why this level of success? Certainly, the C# language and the .NET Framework address many of the technical challenges facing modern developers as they strive to develop increasingly complex distributed systems with ever-shrinking schedules and team sizes.

However, in addition to its technical merits, one of the main reasons for the success that the language and platform has enjoyed thus far is the unprecedented degree of openness that Microsoft has shown. From July 2000 to January 2002, the .NET Framework underwent an extensive public beta that allowed tens of thousands of developers to "kick the tires" of the programming environment. This allowed Microsoft to both solicit and react to developer community feedback before finalizing the new platform.

Additionally, the key specifications for both the language and the platform have been published, reviewed, and ratified by an international standards organization called the European Computer Manufacturers Association (ECMA). These standardization efforts have led to multiple third-party initiatives that bring the C# language and the .NET platform to non-Microsoft environments. They have also prompted renewed interest among academics in the use of Microsoft technologies as teaching and research vehicles.

Lastly, although the language and platform are shiny and new, the foundations for the C# language and the .NET Framework have been years in the making, reaching back more than half a decade. Understanding where the language and platform have come from gives us a better understanding of where they are headed.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

1.1 The C# Language

Reports of a new language from Microsoft first started surfacing in 1998. At that time the language was called COOL, and was said to be very similar to Java. Although Microsoft consistently denied the reports of the new language, rumors persisted.

In June 2000, Microsoft ended the speculation by releasing the specifications for a new language called C# (pronounced "see-sharp"). This was rapidly followed by the release of a preview version of the .NET Framework SDK (which included a C# compiler) at the July 2000 Professional Developer's Conference (PDC) in Orlando, Florida.

The new language was designed by Anders Hejlsberg (creator of Turbo Pascal and architect of Delphi), Scott Wiltamuth, and Peter Golde. Described in the C# Language Specification as a "...simple, modern, object-oriented, and type-safe programming language derived from C and C++," C# bears many syntactic similarities to C++ and Java.

However, focusing on the syntactic similarities between C# and Java does the C# language a disservice. Semantically, C# pushes the language-design envelope substantially beyond where the Java language was circa 2001, and could rightfully be viewed as the next step in the evolution of component-oriented programming languages. While it is outside the scope of this book to perform a detailed comparison between C# and Java, we urge interested readers to read the widely cited article "A Comparative Overview of C# and Java," by co-author Ben Albahari, available at http://genamics.com/developer/csharp_comparative.htm.

1.1.1 Enabling Component-Based Development

Over the last 10 years, programming techniques such as object-oriented design, interface-based programming, and component-based software have become ubiquitous. However, programming language support for these constructs has always lagged behind the current state-of-the-art best practices. As a result, developers tend to either depend on programming conventions and custom code rather than direct compiler and runtime support, or to not take advantage of the techniques at all.

As an example, consider that C++ supported object orientation, but had no formal concept of interfaces. C++ developers resorted to abstract base classes and mix-in interfaces to simulate interface-based programming, and relied on external component programming models such as COM or CORBA to provide the benefits of component-based software.

While Java extended C++ to add language-level support for interfaces and packages (among other things), it too had very little language-level support for building long-lived component-based systems (in which one needs to develop, interconnect, deploy, and version components from various sources over an extended period of time). This is not to say that the Java community hasn't built many such systems, but rather that these needs were addressed by programming conventions and custom code: relying on naming conventions to identify common design patterns such as properties and events, requiring external metadata for deployment information, and developing custom class loaders to provide stronger component versioning semantics.

By comparison, the C# language was designed from the ground up around the assumption that modern systems are built using components. Consequently, C# provides direct language support for common component constructs such as properties, methods, and events (used by RAD tools to build applications out of components, setting properties, responding to events, and wiring components together via method calls). C# also allows developers to directly annotate and extend a component's type information to provide deployment, design, or runtime support, integrate component versioning directly into the programming model, and integrate XML-based documentation directly into C# source files. C# also discards the C++ and COM approach of spreading source artifacts across header files, implementation files, and type libraries in favor of a much simpler source organization and component reuse model.

While this is by no means an exhaustive list, the enhancements in C# over Java and C++ qualify it as the next major step in the evolution of component-based development languages.

1.1.2 A Modern Object-Oriented Language

In addition to deeply integrated support for building component-based systems, C# is also a fully capable object-oriented language, supporting all the common concepts and abstractions that exist in languages such as C++ and Java.

As is expected of any modern object-oriented language, C# supports concepts such as inheritance, encapsulation, polymorphism, and interface-based programming. C# supports common C, C++, and Java language constructs such as classes, structs, interfaces, and enums, as well as more novel constructs such as delegates, which provide a type-safe equivalent to C/C++ function pointers, and custom attributes, which allow annotation of code elements with additional information.

In addition, C# incorporates features from C++ such as operator overloading, user-defined conversions, true rectangular arrays, and pass-by-reference semantics that are currently missing from Java.

Unlike most programming languages, C# has no runtime library of its own. Instead, C# relies on the vast class library in the .NET Framework for all its needs, including console I/O, network and file handling, collection data structures, and many other facilities. Implemented primarily in C# and spanning more than a million lines of code, this class library served as an excellent torture-test during the development cycle for both the C# language and the C# compiler.

The C# language strives to balance the need for consistency and efficiency. Some object-oriented languages (such as Smalltalk) take the viewpoint that "everything is an object." This approach has the advantage that instances of primitive types (such as integers) are first-class objects. However, it has the disadvantage of being very inefficient. To avoid this overhead, other languages (such as Java) choose to bifurcate the type system into primitives and everything else, leading to less overhead, but also to a schism between primitive and user-defined types.

C# balances these two conflicting viewpoints by presenting a unified type system in which all types (including primitive types) are derived from a common base type, while simultaneously allowing for performance optimizations that allow primitive types and simple user-defined types to be treated as raw memory, with minimal overhead and increased efficiency.

1.1.3 Building Robust and Durable Software

In a world of always-on connectivity and distributed systems, software robustness takes on new significance. Servers need to stay up and running 24 x 7 to service clients, and clients need to be able to download code off the network and run it locally with some guarantee that it will not misbehave. The C# language (in concert with the .NET Framework) promotes software robustness in a number of different ways.

First and foremost, C# is a type-safe language, meaning that programs are prevented from accessing objects in inappropriate ways. All code and data is associated with a type, all objects have an associated type, and only operations defined by the associated type can be performed on an object. Type-safety eliminates an entire category of errors in C and C++ programs stemming from invalid casts, bad pointer arithmetic, and even malicious code.

C# also provides automatic memory management in the form of a high-performance tracing generational garbage collector. This frees programmers from performing manual memory management or reference counting, and eliminates an entire category of errors, such as dangling pointers, memory leaks, and circular references.

Even good programs can have bad things happen to them, and it is important to have a consistent mechanism for detecting errors. Over the years, Windows developers have had to contend with numerous error reporting mechanisms, such as simple failure return codes, Win32 structured exceptions, C++ exceptions, COM error `HResults`, and OLE automation `IErrorInfo` objects. This proliferation of approaches breeds complexity and makes it difficult for designers to create standardized error-handling strategies. The .NET Framework eliminates this complexity by standardizing on a single exception-handling mechanism that is used throughout the framework, and exposed in all .NET languages including C#.

The C# language design also includes numerous other features that promote robustness, such as language-level support for independently versioning base classes (without changing derived class semantics or mandating recompilation of derived classes), detection of attempts to use uninitialized variables, array bounds checking, and support for checked arithmetic.

1.1.4 A Pragmatic World View

Many of the design decisions in the C# language represent a pragmatic world view on the part of the designers. For example, the syntax was selected to be familiar to C, C++, and Java developers, making it easier to learn C# and aiding source code porting.

While C# provides many useful, high-level object-oriented features, it recognizes that in certain limited cases these features can work against raw performance. Rather than dismiss these concerns as unimportant, C# includes explicit support for features such as direct pointer manipulation, unsafe type casts, declarative pinning of garbage-collected objects, and direct memory allocation on the stack. Naturally, these features come at a cost, both in terms of the complexity they add and the elevated security privileges required to use them. However, the existence of these features gives C# programmers much more headroom than other, more restrictive languages do.

Lastly, the interop facilities in the .NET Framework make it easy to leverage existing DLLs and COM components from C# code, and to use C# components in classic COM applications. Although not strictly a function of the C# language, this capability reflects a similarly pragmatic world view, in which new functionality coexists peacefully with legacy code for as long as needed.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

1.2 The .NET Framework

The Microsoft .NET Framework consists of two elements: a runtime environment called the Common Language Runtime (CLR), and a class library called the Framework Class Library (FCL). The FCL is built on top of the CLR and provides services needed by modern applications.

While applications targeting the .NET Framework interact directly with the FCL, the CLR serves as the underlying engine. In order to understand the .NET Framework, one first must understand the role of the CLR.

1.2.1 The Common Language Runtime

The CLR is a modern runtime environment that manages the execution of user code, providing services such as JIT compilation, memory management, exception management, debugging and profiling support, and integrated security and permission management.

Essentially, the CLR represents the foundation of Microsoft's computing platform for the next decade. However, it has been a long time in the making. Its origins can be traced back to early 1997, when products such as Microsoft Transaction Server (MTS) were starting to deliver on the promise of a more declarative, service-oriented programming model. This new model allowed developers to declaratively annotate their components at development time, and then rely on the services of a runtime (such as MTS) to hijack component activation and intercept method calls, transparently layering in additional services such as transactions, security, just-in-time (JIT) activation, and more. This need to augment COM type information pushed the limits of what was possible and useful with IDL and type libraries. The COM+ team set out to find a generalized solution to this problem.

The first public discussion of a candidate solution occurred at the 1997 PDC in San Diego, when Mary Kirtland and other members of the COM+ team discussed a future version of COM centered on something called the COM+ Runtime, and providing many of the services such as extensible type information, cross-language integration, implementation inheritance, and automatic memory management that ultimately resurfaced in the CLR.^[1]

^[1] Two sites, <http://www.microsoft.com/msj/1197/complus.aspx> and <http://www.microsoft.com/msj/1297/complus2/complus2.aspx>, contain articles by Mary Kirtland on the COM+ Runtime.

Soon after the 1997 PDC, Microsoft stopped talking publicly about the technology, and the product known as COM+ that was released with Windows 2000 bore little resemblance to the COM+ Runtime originally described. Behind the scenes, however, work was continuing and the scope of the project was expanding significantly as it took on a much larger role within Microsoft.

Initially codenamed Lightning, the project underwent many internal (and some external) renamings, and was known at various times as COM3, COM+ 2.0, the COM+ Runtime, the NGWS Runtime, the Universal Runtime (URT), and the Common Language Runtime. This effort ultimately surfaced as the .NET Framework, announced at the July 2000 PDC in Orlando, Florida. During the following 18 months, the .NET Framework underwent an extensive public beta, culminating in the release of

Version 1.0 of the Microsoft .NET Framework on January 15, 2002.

1.2.2 Compilation and Execution Model

To better understand the CLR, consider how compilers that target the .NET Framework differ from traditional compilers.

Traditional compilers target a specific processor, consuming source files in a specific language, and producing binary files containing streams of instructions in the native language of the target processor. These binary files may then be executed directly on the target processor.

.NET compilers function a little differently, as they do not target a specific native processor. Instead, they consume source files and produce binary files containing an intermediate representation of the source constructs, expressed as a combination of metadata and Common Intermediate Language (CIL). In order for these binaries to be executed, the CLR must be present on the target machine.

When these binaries are executed, they cause the CLR to load. The CLR then takes over and manages execution, providing a range of services such as JIT compilation (converting the CIL as needed into the correct stream of instructions for the underlying processor), memory management (in the form of a garbage collector), exception management, debugger and profiler integration, and security services (stack walking and permission checks).

This compilation and execution model explains why C# is referred to as a *managed language*, why code running in the CLR is referred to as *managed code*, and why the CLR is said to provide *managed execution*.

Although this dependency on a runtime environment might initially appear to be a drawback, substantial benefits arise from this architecture. Since the metadata and CIL representations are processor architecture-neutral, binaries may be used on any machine in which the Common Language Runtime is present, regardless of underlying processor architecture. Additionally, since processor-specific code generation is deferred until runtime, the CLR has the opportunity to perform processor-specific optimizations based on the target architecture the code is running on. As processor technology advances, all applications need to take advantage of these advances is an updated version of the CLR.

Unlike traditional binary representations, which are primarily streams of native processor instructions, the combination of metadata and CIL retains almost all of the original source language constructs. In addition, this representation is source language-neutral, which allows developers to build applications using multiple source languages. They can select the best language for a particular task, rather than being forced to standardize on a particular source language for each application or needing to rely on component technologies, such as COM or CORBA, to mask the differences between the source languages used to build the separate components of an application.

1.2.3 The Common Type System

Ultimately, the CLR exists to safely execute managed code, regardless of source language. In order to provide for cross-language integration, to ensure type safety, and to provide managed execution services such as JIT compilation, garbage collection, exception management, etc., the CLR needs intimate knowledge of the managed code that it is executing.

To meet this requirement, the CLR defines a shared type system called the Common Type System (CTS). The CTS defines the rules by which all types are declared, defined and managed, regardless of source language. The CTS is designed to be rich and flexible enough to support a wide variety of source languages, and is the basis for cross-language integration, type safety, and managed execution services.

Compilers for managed languages that wish to be first-class citizens in the world of the CLR are responsible for mapping source language constructs onto the CTS analogs. In cases in which there is no direct analog, the language designers may decide to either adapt the source language to better match the CTS (ensuring more seamless cross-language integration), or to provide additional plumbing that preserves the original semantics of the source language (possibly at the expense of cross-language integration capabilities).

Since all types are ultimately represented as CTS types, it now becomes possible to combine types authored in different languages in new and interesting ways. For example, since managed languages ultimately declare CTS types, and the CTS supports inheritance, it follows that the CLR supports cross-language inheritance.

1.2.4 The Common Language Specification

Not all languages support the exact same set of constructs, and this can be a barrier to cross-language integration. Consider this example: Language A allows unsigned types (which are supported by the CTS), while Language B does not. How should code written in Language B call a method written in Language A, which takes an unsigned integer as a parameter?

The solution is the Common Language Specification (CLS). The CLS defines the reasonable subset of the CTS that should be sufficient to support cross-language integration, and specifically excludes problem areas such as unsigned integers, operator overloading, and more.

Each managed language decides how much of the CTS to support. Languages that can consume any CLS-compliant type are known as CLS Consumers. Languages which can extend any existing CLS-compliant type are known as CLS Extenders. Naturally, managed languages are free to support CTS features over and above the CLS, and most do. As an example, the C# language is both a CLS Consumer and a CLS Extender, and supports all of the important CTS features.

The combination of the rich and flexible CTS and the widely supported CLS has led to many languages being adapted to target the .NET platform. At the time of this writing, Microsoft was offering compilers for six managed languages (C#, VB.NET, JScript, Managed Extensions for C++, Microsoft IL, and J#), and a host of other commercial vendors and academics were offering managed versions of languages, such as COBOL, Eiffel, Haskell, Mercury, Mondrian, Oberon, Forth, Scheme, Smalltalk, APL, several flavors of Pascal, and more.

Given the level of interest from industry and academia, one might say that .NET has spawned something of a renaissance in programming-language innovation.

1.2.5 The Framework Class Library

Developer needs (and Windows capabilities) have evolved much since Windows 1.0 was introduced in November 1985. As Windows has grown to meet new customer needs, the accompanying APIs have

grown by orders of magnitude over time, becoming ever more complex, increasingly inconsistent, and almost impossible to comprehend in their totality.

Additionally, while modern paradigms such as object orientation, component software, and Internet standards had emerged and, in many cases, joined the mainstream, these advances had not yet been incorporated into the Windows programming model in a comprehensive and consistent manner.

Given the issues, and the degree of change already inherent in the move to a managed execution environment, the time was ripe for a clean start. As a result, the .NET Framework replaces most (though not all) of the traditional Windows API sets with a well-factored, object-oriented class library called the Framework Class Library (FCL).

The FCL provides a diverse array of higher-level software services, addressing the needs of modern applications. Conceptually, these can be grouped into several categories such as:

- Support for core functionality, such as interacting with basic data types and collections; console, network and file I/O; and interacting with other runtime-related facilities
- Support for interacting with databases, consuming and producing XML, and manipulating tabular and tree-structured data
- Support for building web-based (thin client) applications with a rich server-side event model
- Support for building desktop-based (thick client) applications with broad support for the Windows GUI
- Support for building SOAP-based XML web services

The FCL is vast, including more than 3,500 classes. For a more detailed overview of the facilities in the FCL, see [Chapter 5](#).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

1.3 ECMA Standardization

One of the most encouraging aspects about the .NET Framework is the degree of openness that Microsoft has shown during its development. From the earliest public previews, core specifications detailing the C# language, the classes in the FCL, and the inner workings of the CLR have been freely available.

However, this openness was taken to a new level in November 2000 when Microsoft, along with co-sponsors Intel and HP, officially submitted the specifications for the C# language, a subset of the FCL, and the runtime environment to ECMA for standardization.

This action began an intense standardization process. Organizations participating in the effort included Microsoft, HP, Intel, IBM, Fujitsu Software, ISE, Plum Hall, Monash University, and others. The work was performed under the auspices of ECMA technical committee TC39, the same committee that had previously standardized the JavaScript language as ECMAScript.

TC39 chartered two new task groups to perform the actual standardization work: one to focus on the C# language, the other to focus on what became known as the Common Language Infrastructure (CLI).

The CLI consisted of the runtime engine and the subset of the FCL being standardized. Conceptually, Microsoft's CLR is intended to be a conforming commercial implementation of the runtime engine specified in the CLI, and Microsoft's FCL is intended to be a conforming commercial implementation of the class library specified in the CLI (although obviously, it is a massive superset of the 294 classes ultimately specified in the CLI).

After more than a year of intense effort, the task groups completed their standardization work and presented the specifications to the ECMA General Assembly. In December 2001 the General Assembly ratified the C# and CLI specifications, assigning them the ECMA standards numbers of ECMA-334 (C#) and ECMA-335 (the CLI). In late December, 2001, ECMA submitted the standards to the International Organization for Standardization (ISO) via the Fast-Track process, and in April 2003, ISO ratified the standards as ISO/IEC 23270 (C#) and ISO/IEC 23271 (CLI), giving C# and the CLI bona-fide international standard status.

Critics have claimed that the standardization process was merely a ploy by Microsoft to deflect Java's cross-platform advantages. However, the qualifications and seniority of the people working on the standardization effort, and their level of involvement during the lengthy standardization cycle, tell a different story. Microsoft, along with its co-sponsors and the other members of the standardization task groups, committed some of its best and brightest minds to this effort, spending a huge amount of time and attention on the standardization process. Given that this effort occurred concurrently with the development and release of the .NET Framework itself, this level of investment by Microsoft and others flies in the face of the conspiracy theories.

Of course, for standards to have an impact there must be implementations. In addition to the commercial .NET Framework, Microsoft itself has two other CLI implementations: the Shared Source CLI (SSCLI) and the .NET Compact Framework.

In November 2002 Microsoft released the Shared Source CLI (SSCLI)

(<http://msdn.microsoft.com/net/sscli>). Formerly known by its code-name, Rotor, the SSCLI is source code for a working implementation of the CLI and C# standards that builds and runs on Windows XP, FreeBSD, and Mac OS X. Licensed for non-commercial use, the SSCLI provides academics, researchers, and technology enthusiasts a vehicle for teaching and research on the inner workings of a CLI implementation, and it also serves as a valuable resource for CLI implementers. Community response has been very positive: a substantial number of research projects and teaching efforts have been based on the SSCLI, and in April 2003 Cornell University launched a community site (<http://www.sscli.net>) that includes a CVS repository, discussion lists, and a bug tracker to coordinate these efforts.

The .NET Compact Framework, now available with Visual Studio .NET 2003, is an implementation of the CLI designed to target resource-constrained devices, and is initially available for Pocket PC 2000+ and Windows CE 4.1+ operating systems.

However, Microsoft's implementations are not the only game in town. Other CLI implementations include the Mono project and dotGNU.

The Mono project (<http://www.go-mono.com>), started by Ximian Corporation, is aiming to provide an implementation of not only the CLI platform and the C# compiler, but also a larger set of classes selected from Microsoft's .NET Framework FCL. In addition to the internal resources that Ximian has committed to the project, the Mono project has also attracted attention from the broader open source community, and appears to be gathering steam.

Another community effort to create an implementation of the C# and CLI standards is the dotGNU project (<http://www.dotgnu.org>). While not as high-profile as Mono, dotGNU has also been making headway, and includes some interesting and unique concepts. The core of dotGNU is Portable.NET, which was originally developed by a lone developer (Rhys Weatherley) before merging his project with dotGNU in August 2000. There are unique aspects to the dotGNU project, including the fact that it was originally designed around a CIL interpreter rather than a JIT compiler, and the developers' plan to support directly executing Java binaries.

It is very likely that more implementations of the CLI will arise over time. While it is too early to say whether the .NET Framework (in the form of the CLI) will ever be available on as many platforms as Java is, the degree of openness and the level of community interest is very encouraging.

[\[Team LiB \]](#)

[← PREVIOUS](#)[NEXT →](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

1.4 Changes in Visual C# 2003

There have been a few minor additions and changes to the C# language in Visual Studio .NET 2003. Most of these changes were made to tighten the language, to conform more precisely to the ECMA specification of C#, and to address bugs in control flow optimizations made by the compiler. These changes have been included in the language reference. (For example, documentation comments may now use standard `/* ... */` notation. See [Chapter 4](#).)

The 1.1 version of the Framework Class Libraries has some minor changes from 1.0, which are reflected in the updated API reference section of this book. With the exception of signature changes on two methods on the `XslTransform` class, there are no breaking changes that would prevent a 1.0 application from working on the 1.1 Framework.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 2. C# Language Basics

In this chapter, we explain a simple C# program and introduce the basics of the C# language.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

2.1 A First C# Program

Here is a simple C# program:

```
namespace FirstProgram {
    using System;
    class Example {
        static void Main ( ) {
            Console.WriteLine ("Hello world!");
        }
    }
}
```

A C# program is composed of types (typically classes) that we organize into namespaces. Each type contains function members (typically methods and properties), as well as data members (typically fields). Methods contain a series of statements that are executed sequentially. In our program, we define a class named `Example` that contains a method named `Main`, which has a single statement that writes `Hello world!` to the console window. C# recognizes this method as the default entry point of execution, so that's where the program begins.

The `Console` class encapsulates standard input/output functionality, providing methods such as `WriteLine`. To use types from another namespace, use the `using` directive. Since the `Console` class resides in the `System` namespace, we write `using System`; similarly, types from other namespaces could use our `Example` class by `using FirstProgram`.

In C#, there are no standalone functions; they are always associated with a type, or, as we will see, instances of that type. Our program is simple, and makes use of only static members, which means the member is associated with its type, rather than instances of its type. In addition, we make use of only void methods, which means these methods do not return a value.

Throughout this book, most of the examples contain this stub code:

```
using System;
class Test {
    static void Main ( ) {
        ...
    }
}
```

2.2 Identifiers and Keywords

Identifiers are names programmers choose for their types, methods, variables, etc. An identifier must be a whole word, essentially made up of Unicode characters starting with a letter or underscore, and may not clash with a keyword. As a special case, the `@` prefix may be used to avoid a clash with a keyword, but is not considered part of the identifier. For instance, the following two identifiers are equivalent:

```
Kon @Kon
```

C# identifiers are case-sensitive, though for compatibility with other languages, you should not differentiate public or protected identifiers by case alone.

Here is a list of C# keywords:

abstract	as	base	bool	break
byte	case	catch	char	checked
class	const	continue	decimal	default
delegate	do	double	else	enum
event	explicit	extern	false	finally
fixed	float	for	foreach	goto
if	implicit	in	int	interface
internal	is	lock	long	namespace
new	null	object	operator	out
override	params	private	protected	public
readonly	ref	return	sbyte	sealed
short	sizeof	stackalloc	static	string
struct	switch	this	throw	true
try	typeof	uint	ulong	unchecked
unsafe	ushort	using	virtual	void
while				

2.3 Type Basics

A C# program is best understood in terms of three basic elements: functions, data, and types. This book assumes you have some programming experience, so let's start with a brief overview of functions and data (which you should have some familiarity with) and then move on to explain types in more detail.

Functions

A function performs an action by executing a series of statements. For example, you may have a function that returns the distance between two points, or a function that calculates the average of an array of values. A function is a way of manipulating data.

Data

Data is values that functions operate on. For example, you may have data holding the coordinates of a point, or data holding an array of values. Data always has a particular type.

Types

A type has a set of data members and function members. The function members are used to manipulate the data members. The most common types are classes and structs, which provide a template for creating data; data is always an instance of a type.

Types are quite an abstract concept, so let's look at two concrete examples.

2.3.1 The String Class

The string class specifies a sequence of characters. This means you can store values such as ".NET" or "http://oreilly.com". You can also perform functions such as returning the character at a particular position on the string or getting its lowercase representation.

In this example, we output the lower case representation of ".NET" (which will be ".net"), and return the length of the string (which will be 4). To do this, we first create an instance of a string, then use the `ToLower` method and `Length` property, which are function members of that string.

```
using System;
class Test {
    static void Main ( ) {
        string s = ".NET";
        Console.WriteLine (s.ToLower( )); // outputs ".net"
        Console.WriteLine (s.Length); // outputs 4
    }
}
```

2.3.2 The int Struct

The `int` struct specifies a signed integer (a positive or negative whole number) that is 32 bits long. This means you can store values ranging from -2,147,483,648 to 2,147,483,647 (or -2^{n-1} to $2^{n-1}-1$, in which $n=32$). With an `int`, you can perform functions such as adding, multiplying, etc.

In this example, we output the result of multiplying 3 by 4. To do this, we create two instances of the `int`, and then use the `*` operator. The `int` type is actually a built-in type that supports primitive arithmetic functionality (such as `*`), but it is helpful to think of the `*` operator as a function member of the `int` type.

```
using System;
class Example {
    static void Main ( ) {
        int a = 3;
        int b = 4;
        Console.WriteLine (a * b);
    }
}
```

2.3.3 A Custom Type

You can also define custom types in C#. In fact, a program is built by defining new types, each with a set of data members and function members. In this example, we build our own type, called `Counter`:

```
// Imports types from System namespace, such as Console
using System;
class Counter { // New types are typically classes or structs
    // --- Data members ---
    int value; // field of type int
    int scaleFactor; // field of type int

    // Constructor, used to initialize a type instance
    public Counter(int scaleFactor) {
        this.scaleFactor = scaleFactor;
    }
    // Method
    public void Inc( ) {
        value+=scaleFactor;
    }
    // Property
    public int Count {
        get {return value; }
    }
}
class Test {
    // Execution begins here
    static void Main( ) {

        // Create an instance of counter type
        Counter c = new Counter(5);
        c.Inc( );
        c.Inc( );
    }
}
```

```

        Console.WriteLine(c.Count); // prints "10";

        // create another instance of counter type
        Counter d = new Counter(7);
        d.Inc( );
        Console.WriteLine(d.Count); // prints "7";
    }
}

```

2.3.4 Type Instances

Generally, you must create instances of a type to use that type. Data members and function members that require a type to be instantiated in order to be used are called instance members (by default, members are instance members). Data members and function members that can be used on the type itself are called static members.

In this example, the instance method `PrintName` prints the name of a particular panda, while the static method `PrintSpeciesName` prints the name shared by all pandas in the application (`AppDomain`):

```

using System;
class Panda {
    string name;
    static string speciesName = "Ailuropoda melanoleuca";
    // Initializes Panda(See Instance Constructors)
    public Panda(string n) {
        name = n;
    }
    public void PrintName( ) {
        Console.WriteLine(name);
    }
    public static void PrintSpeciesName( ) {
        Console.WriteLine(speciesName);
    }
}
class Test {
    static void Main( ) {
        Panda.PrintSpeciesName( ); // invoke static method
        Panda p1 = new Panda("Petey");
        Panda p2 = new Panda("Jimmy");
        p1.PrintName( ); // invoke instance method
        p2.PrintName( ); // invoke instance method
    }
}

```

Note that the invocation of static members from outside of their enclosing type requires specifying the type name. You may have deduced that `Console`'s `WriteLine` method is a static member. It is associated with the `Console` class, rather than an instance of the `Console` class. A function member should be static when it doesn't rely on any instance data members. Similarly, the `Main` method of all programs is a static member, which means that this method can be called without instantiating the enclosing class.

2.3.5 Conversions

Each type has its own set of rules defining how it can be converted to and from other types. Conversions between types may be implicit or explicit. Implicit conversions can be performed automatically, while explicit conversions require a cast:

```
int x = 123456; // int is a 4-byte integer
long y = x; // implicit conversion to 8-byte integer
short z =(short)x // explicit conversion to 2-byte integer
```

The rationale behind implicit conversions is they are guaranteed to succeed and do not lose information. Conversely, an explicit conversion is required either when runtime circumstances determine whether the conversion will succeed or whether information may be lost during the conversion.

Most conversion rules are supplied by the language, such as the previously shown numeric conversions. Occasionally it is useful for developers to define their own implicit and explicit conversions, explained later in this chapter.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

2.4 Value Types and Reference Types

All C# types fall into the following categories:

- Value types (struct, enum)
- Reference types (class, array, delegate, interface)
- Pointer types

The fundamental difference between the three main categories (value types, reference types, and pointer types) is how they are handled in memory. The following sections explain the essential differences between value types and reference types. Pointer types fall outside mainstream C# usage, and are covered later in [Chapter 4](#).

2.4.1 Value Types

Value types are the easiest types to understand. They directly contain data, such as the `int` type (holds an integer), or the `bool` type (holds a true or false value). A value type's key characteristic is when you assign one value to another, you make a copy of that value. For example:

```
using System;
class Test {
    static void Main ( ) {
        int x = 3;
        int y = x; // assign x to y, y is now a copy of x
        x++; // increment x to 4
        Console.WriteLine (y); // prints 3
    }
}
```

2.4.2 Reference Types

Reference types are a little more complex. A reference type really defines two separate entities: an object, and a reference to that object. This example follows exactly the same pattern as our previous example, but notice how the variable `y` is updated, while in our previous example, `y` remained unchanged:

```
using System;
using System.Text;
class Test {
    static void Main ( ) {
        StringBuilder x = new StringBuilder ("hello");
        StringBuilder y = x;
```

```

        x.Append ( " there");
        Console.WriteLine (y); // prints "hello there"
    }
}

```

This is because the `StringBuilder` type is a reference type, while the `int` type is a value type. When we declared the `StringBuilder` variable, we were actually doing two separate things, which can be separated into these two lines:

```

StringBuilder x;
x = new StringBuilder ("hello");

```

The first line creates a new reference to a `StringBuilder`. The second line assigns a new `StringBuilder` object to the reference. Let's look at the next line:

```

StringBuilder y = x;

```

When we assign `x` to `y`, we are saying, "make `y` point to the same thing that `x` points to." A reference stores the address of an object (an address is a memory location, stored as a four-byte number). We're actually still making a copy of `x`, but we're copying this four-byte number as opposed to the `StringBuilder` object itself.

Let's look at this line:

```

x.Append ( " there");

```

This line actually does two things. It first finds the memory location represented by `x`, and then it tells the `StringBuilder` object that lies at that memory location to append " `there`" to it. We could have achieved exactly the same effect by appending " `there`" to `y`, because `x` and `y` refer to the same object:

```

y.Append ( " there");

```

A reference may point at no object, by assigning the reference to null. In this code sample, we assign `null` to `x`, but can still access the same `StringBuilder` object we created via `y`:

```

using System;
using System.Text;
class Test {
    static void Main ( ) {
        StringBuilder x;
        x = new StringBuilder ("hello");
        StringBuilder y = x;
        x = null;
        y.Append ( " there");
        Console.WriteLine (y); // prints "hello there"
    }
}

```

2.4.3 The Heap and the Stack

The stack is a block of memory that grows each time a function is entered (basically to store local

variables) and shrinks each time a function exits (because the local variables are no longer needed). In our previous example, when the main function finishes executing, the references `x` and `y` go out of scope, as do any value types declared in the function. This is because these values are stored on the stack.

The heap is a block of memory in which reference type objects are stored. Whenever a new object is created, it is allocated on the heap, and returns a reference to that object. During a program's execution, the heap starts filling up as new objects are created. The runtime has a garbage collector that deallocates objects from the heap so your computer does not run out of memory. An object is deallocated when it is determined that it has zero references to it.

You can't explicitly delete objects in C#. An object is either automatically popped off the stack or automatically collected by the garbage collector.

2.4.3.1 Value types and reference types side-by-side

A good way to understand the difference between value types and reference types is to see them side-by-side. In C#, you can define your own reference types or your own value types. If you want to define a simple type such as a number, it makes sense to define a value type, in which efficiency and copy-by-value semantics are desirable. Otherwise you should define a reference type. You can define a new value type by declaring a struct, and define a new reference type by defining a class.

To create a value-type or reference-type instance, the constructor for the type may be called, with the `new` keyword. A value-type constructor simply initializes an object. A reference-type constructor creates a new object on the heap, and then initializes the object:

```
// Reference-type declaration
class PointR {
    public int x, y;
}
// Value-type declaration
struct PointV {
    public int x, y;
}
class Test {
    static void Main( ) {
        PointR a; // Local reference-type variable, uses 4 bytes of
                  // memory on the stack to hold address
        PointV b; // Local value-type variable, uses 8 bytes of
                  // memory on the stack for x and y
        a = new PointR( ); // Assigns the reference to address of new
                           // instance of PointR allocated on the
                           // heap. The object on the heap uses 8
                           // bytes of memory for x and y, and an
                           // additional 8 bytes for core object
                           // requirements, such as storing the
                           // object's type synchronization state
        b = new PointV( ); // Calls the value-type's default
                           // constructor. The default constructor
                           // for both PointR and PointV will set
                           // each field to its default value, which
```

```

        // will be 0 for both x and y.
        a.x = 7;
        b.x = 7;
    }
}
// At the end of the method the local variables a and b go out of
// scope, but the new instance of a PointR remains in memory until
// the garbage collector determines it is no longer referenced

```

Assignment to a reference type copies an object reference, while assignment to a value type copies an object value:

```

...
PointR c = a;
PointV d = b;
c.x = 9;
d.x = 9;
Console.WriteLine(a.x); // Prints 9
Console.WriteLine(b.x); // Prints 7
}
}

```

As with this example, an object on the heap can be pointed at by multiple variables, whereas an object on the stack or inline can only be accessed via the variable it was declared with. "Inline" means that the variable is part of a larger object; i.e., it exists as a data member or an array member.

2.4.4 Type System Unification

C# provides a unified type system, whereby the object class is the ultimate base type for both reference types and value types. This means all types, apart from the occasionally used pointer types, share the same basic set of characteristics.

2.4.4.1 Simple types are value types

Simple types are so called because most have a direct representation in machine code. For example, the floating-point numbers in C# are matched by the floating-point numbers in most processors, such as Pentium processors. For this reason, most languages treat them specially, but in doing so create two separate sets of rules for simple types and user-defined types. In C#, all types follow the same set of rules, resulting in greater programming simplicity.

To do this, the simple types in C# alias structs found in the `System` namespace. For instance, the `int` type aliases the `System.Int32` struct, the `long` type aliases the `System.Int64` struct, etc. Simple types therefore have the same features one would expect any user-defined type to have. For instance, the `int` type has function members:

```

int i = 3;
string s = i.ToString( );

```

This is equivalent to:

```
// This is an explanatory version of System.Int32
namespace System {
    struct Int32 {
        ...
        public string ToString( ) {
            return ...;
        }
    }
}
// This is valid code, but we recommend you use the int alias
System.Int32 i = 5;
string s = i.ToString( );
```

2.4.4.2 Value types expand the set of simple types

Simple types have two useful features: they are efficient, and their copy-by-value semantics are intuitive. Consider again how natural it is assigning one number to another and getting a copy of the value of that number, as opposed to getting a copy of a reference to that number. In C#, value types are defined to expand the set of simple types. In this example, we revisit our `PointV` and `PointR` example, but this time look at efficiency.

Creating an array of 1,000 `ints` is very efficient. This allocates 1,000 `ints` in one contiguous block of memory:

```
int[ ] a = new int[1000];
```

Similarly, creating an array of a value type `PointV` is very efficient too:

```
struct PointV {
    public int x, y
}
PointV[ ] a = new PointV[1000];
```

If we used a reference type `PointR`, we would need to instantiate 1,000 individual points after instantiating the array:

```
class PointR {
    public int x, y;
}
PointR[ ] a = new PointR[1000]; // creates an array of 1000 null references
for (int i=0; i<a.Length; i++)
    a[i] = new PointR( );
```

In Java, only the simple types (`int`, `float`, etc.) can be treated with this efficiency, while in C# one can expand the set of simple types by declaring a struct.

Furthermore, C#'s operators may be overloaded, so that operations that are typically applicable only to simple types are applicable to any class or struct, such as `+`, `-`, etc. (see [Section 4.5](#), in [Chapter 4](#)).

2.4.4.3 Boxing and unboxing value types

So that common operations can be performed on both reference types and value types, each value type has a corresponding hidden reference type. This is created when it is cast to a reference type. This process is called **boxing**. A value type may be cast to the "object" class, which is the ultimate base class for all value types and reference types, or an interface it implements.

In this example, we box and unbox an `int` to and from its corresponding reference type:

```
class Test {
    static void Main ( ) {
        int x = 9;
        object o = x; // box the int
        int y = (int)o; // unbox the int
    }
}
```

When a value type is boxed, a new reference type is created to hold a copy of the value type. Unboxing copies the value from the reference type back into a value type. Unboxing requires an explicit cast, and a check is made to ensure the value type to convert to matches the type contained in the reference type. An `InvalidCastException` is thrown if the check fails. You never need to worry about what happens to boxed objects once you've finished with them; the garbage collector takes care of them for you.

Using collection classes is a good example of boxing and unboxing. In this example, we use the `Queue` class with value types:

```
using System;
using System.Collections;
class Test {
    static void Main ( ) {
        Queue q = new Queue ( );
        q.Enqueue (1); // box an int
        q.Enqueue (2); // box an int
        Console.WriteLine ((int)q.Dequeue( )); // unbox an int
        Console.WriteLine ((int)q.Dequeue( )); // unbox an int
    }
}
```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

2.5 Predefined Types

This section explains each of C#'s predefined types:

- Value types
 - Integer, signed (`sbyte`, `short`, `int`, `long`)
 - Integer, unsigned (`byte`, `ushort`, `uint`, `ulong`)
 - Floating-point (`float`, `decimal`, `double`)
- Reference types
 - Object
 - String

All of these types alias types found in the `System` namespace. For example, there is only a syntactic difference between these two statements:

```
int i = 5;
System.Int32 i = 5;
```

2.5.1 Integral Types

C# type	System type	Size	Signed
<code>sbyte</code>	<code>System.SByte</code>	1 byte	yes
<code>short</code>	<code>System.Int16</code>	2 bytes	yes
<code>int</code>	<code>System.Int32</code>	4 bytes	yes
<code>long</code>	<code>System.Int64</code>	8 bytes	yes
<code>byte</code>	<code>System.Byte</code>	1 byte	no
<code>ushort</code>	<code>System.UInt16</code>	2 bytes	no
<code>uint</code>	<code>System.UInt32</code>	4 bytes	no
<code>ulong</code>	<code>System.UInt64</code>	8 bytes	no

For unsigned integers that are n bits wide, possible values range from 0 to 2^n-1 . For signed integers that are n bits wide, their possible values range from -2^{n-1} to $2^{n-1}-1$. Integer literals can use either decimal or hexadecimal notation:

```
int x = 5;
ulong y = 0x1234AF; // prefix with 0x for hexadecimal
```

When an integral literal is valid for several possible integral types, the default type chosen goes in this order: `int`, `uint`, `long`, and `ulong`. The following suffixes may be used to explicitly specify the chosen type:

```
U
    uint or ulong
L
    long or ulong
U
    ulong
```

2.5.1.1 Integral conversions

An implicit conversion between integral types is permitted when the type to convert to contains every possible value of the type to convert from. Otherwise an explicit conversion is required. For instance, you can implicitly convert an `int` to a `long`, but must explicitly convert an `int` to a `short`:

```
int x = 123456;
long y = x; // implicit, no information lost
short z = (short)x; // explicit, truncates x
```

2.5.2 Floating-Point Types

C# type	System type	Size
<code>float</code>	<code>System.Single</code>	4 Bytes
<code>double</code>	<code>System.Double</code>	8 Bytes

A float can hold values from approximately $\pm 1.5 \times 10^{-45}$ to approximately $\pm 3.4 \times 10^{38}$ with 7 significant figures.

A double can hold values from approximately $\pm 5.0 \times 10^{-324}$ to approximately $\pm 1.7 \times 10^{308}$ with 15-16 significant figures.

Floating-point types can hold the special values +0, -0, $+\infty$, $-\infty$, and NaN (not a number), which represent the outcome of mathematical operations such as division by zero. `float` and `double` implement the specification of the IEEE 754 format types, supported by almost all processors, and defined by the IEEE at <http://www.ieee.org>.

Floating-point literals can use decimal or exponential notation. A float literal requires the suffix `f` or `F`. A double literal may choose to add the suffix `d` or `D`.

```
float x = 9.81f;
double y = 7E-02; // 0.07
```

2.5.2.1 Floating-point conversions

An implicit conversion from a `float` to a `double` loses no information and is permitted, but not vice versa. An implicit conversion from an `int`, `uint`, and `long` to a `float`, and from a `long` to a `double` is allowed, for readability:

```
int strength = 2;
int offset = 3;
float x = 9.53f * strength - offset;
```

If this example uses larger values, precision may be lost. However, the possible range of values is not truncated, since both a `float` and a `double`'s lowest and highest possible values exceed an `int`, `uint`, or `long`'s lowest or highest value. All other conversions between integral and floating-point types must be explicit:

```
float x = 3.53f;
int offset = (int)x;
```

2.5.3 Decimal Type

The `decimal` type can hold values from $\pm 1.0 \times 10^{-28}$ to approximately $\pm 7.9 \times 10^{28}$ with 28-29 significant figures.

The `decimal` type holds 28 digits and the position of the decimal point on those digits. Unlike a floating-point value, it has more precision, but a smaller range. It is typically useful in financial calculations, in which the combination of its high precision and the ability to store a base10 number without rounding errors is very valuable. The number 0.1, for instance, is represented exactly with a decimal, but as a recurring binary number with a floating-point type. There is no concept of $+\infty$, $-\infty$, and `NaN` for a decimal.

A decimal literal requires the suffix `m` or `M`.

```
decimal x = 80603.454327m; // holds exact value
```

2.5.3.1 Decimal conversions

An implicit conversion from all integral types to a decimal type is permitted because a decimal type can represent every possible integer value. A conversion from a decimal to floating type or vice versa requires an explicit conversion, since floating-point types have a bigger range than a decimal, and a decimal has more precision than a floating-point type.

2.5.4 Char Type

C# type	System type	Size
char	System.Char	2 Bytes

The `char` type represents a Unicode character. A `char` literal consists of either a character, Unicode

format, or escape character enclosed in single quote marks:

```
`A' // simple character
`\u0041' // Unicode
`\x0041' // unsigned short hexadecimal
`\n' // escape sequence character
```

[Table 2-1](#) lists the escape sequence characters.

Table 2-1. Escape sequence characters

Char	Meaning	Value
\'	Single quote	0x0027
\"	Double quote	0x0022
\\	Backslash	0x005C
\0	Null	0x0000
\a	Alert	0x0007
\b	Backspace	0x0008
\f	Form feed	0x000C
\n	New line	0x000A
\r	Carriage return	0x000D
\t	Horizontal tab	0x0009
\v	Vertical tab	0x000B

2.5.4.1 Char conversions

An implicit conversion from a `char` to most numeric types works-it's dependent upon whether the numeric type can accommodate an unsigned `short`. If it cannot, an explicit conversion is required.

2.5.5 Bool Type

C# type	System type	Size
<code>bool</code>	<code>System.Boolean</code>	1 Byte / 2Byte

The `bool` type is a logical value that can be assigned the literal `true` or `false`.

Although a boolean value requires only one bit (0 or 1), it occupies one byte of storage, since this is the minimum chunk that addressing on most processor architectures can work with. Each element in

a boolean array uses two bytes of memory.

2.5.5.1 Bool conversions

No conversions can be made from booleans to numeric types or vice versa.

2.5.6 Object Type

C# type	System type	Size
<code>object</code>	<code>System.Object</code>	0 byte/8 byte overhead

The object class is the ultimate base type for both value types and reference types. Value types have no storage overhead from an object. Reference types, which are stored on the heap, intrinsically require an overhead. In the .NET runtime, a reference-type instance has an eight-byte overhead, which stores the object's type, as well as temporary information such as its synchronization lock state or whether it has been fixed from movement by the garbage collector. Note that each reference to a reference-type instance uses four bytes of storage.

For more information about the `System.Object` type, see [Chapter 26](#).

2.5.7 String Type

C# type	System type	Size
<code>string</code>	<code>System.String</code>	20 bytes minimum

The C# string represents an immutable sequence of Unicode characters, and aliases the `System.String` class (see [Chapter 26](#)).

Although `string` is a class, its use is so ubiquitous in programming that it is given special privileges by both the C# compiler and .NET runtime.

Unlike other classes, a new instance can be created using a `string` literal:

```
string a = "Heat";
```

Strings can also be created with verbatim string literals. Verbatim `string` literals start with `@`, and indicate that the string should be used verbatim, even if it spans multiple lines or includes escape characters, i.e. `"\"`. In this example, the pairs `a1` and `a2` represent the same string, and the pairs `b1` and `b2` represent the same string:

```
string a1 = "\\server\\fileshare\\helloworld.cs";  
string a2 = @"\\server\\fileshare\\helloworld.cs";  
Console.WriteLine(a1==a2); // Prints "True"
```

```
string b1 = "First Line\r\nSecond Line";  
string b2 = @"First Line  
Second Line";  
Console.WriteLine(b1==b2); // Prints "True"
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

2.6 Arrays

```
type [*]
+ array-name =
[
    new type [ dimension+ ][*]*; |
    { value1, value2, ... };
]
```

Note that `[*]` is the set: `[] [,] [, ,] ...`

Arrays allow a group of elements of a particular type to be stored in a contiguous block of memory. An array is specified by placing square brackets after the element type. For example:

```
char[ ] vowels = new char[ ] { 'a', 'e', 'i', 'o', 'u' };
Console.WriteLine(vowels [1]); // Prints "e"
```

This prints "e" because array indexes start at 0. To support other languages, .NET can create arrays based on arbitrary start indexes, but all the libraries use zero-based indexing. Once an array has been created, its length cannot be changed. However, the `System.Collection` classes provide dynamically sized arrays, as well as other data structures, such as associative (key/value) arrays.

2.6.1 Multidimensional Arrays

Multidimensional arrays come in two varieties: rectangular and jagged. Rectangular arrays represent an n -dimensional block, while jagged arrays are arrays of arrays. In this example we make use of the `for` loop, which is explained in the statements section. The `for` loops here simply iterate through each item in the arrays.

```
// rectangular
int [ , , ] matrixR = new int [3, 4, 5]; // creates 1 big cube
// jagged
int [ ] [ ] [ ] matrixJ = new int [3] [ ] [ ];
for (int i = 0; i < 3; i++) {
    matrixJ[i] = new int [4] [ ];
    for (int j = 0; j < 4; j++)
        matrixJ[i][j] = new int [5];
}
// assign an element
matrixR [1,1,1] = matrixJ [1][1][1] = 7;
```

2.6.2 Local Field Array Declarations

For convenience, local and field declarations may omit the array type when assigning a known value, since the type is specified in the declaration anyway:


```
int[,] array = {{1,2},{3,4}};
```

2.6.3 Array Length and Rank

Arrays know their own length. For multidimensional array methods, the array's `GetLength` method returns the number of elements for a given dimension, which is from 0 (the outermost) to the array's `rank-1` (the innermost).

```
// single dimensional
for(int i = 0; i < vowels.Length; i++);
// multi-dimensional
for(int i = 0; i < matrixR.GetLength(2); i++);
```

2.6.4 Bounds Checking

All array indexing is bounds-checked by the runtime, with `IndexOutOfRangeException` thrown for invalid indices. Like Java, this prevents program faults and debugging difficulties while enabling code to execute with security restrictions.



Generally, the performance hit from bounds-checking is minor, and the JIT (Just-in-Time compiler) can perform optimizations, such as determining each array index is safe before entering a loop, thus avoiding a check made for each iteration. In addition, C# provides "unsafe" code that can explicitly bypass bounds-checking (see [Section 4.8](#) in [Chapter 4](#)).

2.6.5 Array Conversions

Arrays of reference types may be converted to other arrays, using the same logic you would apply to its element type (this is called *array covariance*). All arrays implement `System.Array`, which provides methods to generically get and set elements regardless of the array type.

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

2.7 Variables and Parameters

A variable represents a typed storage location. A variable can be a local variable, parameter, array element, an instance field, or a static field.

All variables have an associated type, which essentially defines the possible values the variable can have and the operations that can be performed on that variable. C# is strongly typed, which means the set of operations that can be performed on a type are enforced at compile time, rather than at runtime. In addition, C# is type-safe, which ensures that a variable can be operated on only via the correct type with the help of runtime checking (except in unsafe blocks; see [Section 4.8](#) in [Chapter 4](#)).

2.7.1 Definite Assignment

All variables in C# (except in unsafe contexts) must be assigned a value before they are used. A variable is either explicitly assigned a value or automatically assigned a default value. Automatic assignment occurs for static fields, class instance fields, and array elements not explicitly assigned a value. For example:

```
using System;
class Test {
    int v;
    // Constructors that initialize an instance of a Test
    public Test( ) { } // v will be automatically assigned to 0
    public Test(int a) { // explicitly assign v a value
        v = a;
    }
    static void Main( ) {
        Test[] tests = new Test [2]; // declare array
        Console.WriteLine(tests[1]); // ok, elements assigned to null
        Test t;
        Console.WriteLine(t); // error, t not assigned before use
    }
}
```

2.7.2 Default Values

Essentially the default value for all primitive (or atomic) types is zero:

Type	Default value
Numeric types	0
Bool type	false

Type	Default value
Char type	'\0'
Enum types	0
Reference type	null

The default value for each field in a complex (or composite) type is one of these aforementioned values.

2.7.3 Parameters

A method has a sequence of parameters. Parameters define the set of arguments that must be provided for that method. In this example the method `Foo` has a single parameter named `p`, of type `int`:

```
static void Foo(int p) {++p;}
static void Main( ) {
    Foo(8);
}
```

2.7.3.1 Passing arguments by value

By default, arguments in C# are passed by value, which is by far the most common case. This means a copy of the value is created when passed to the method:

```
static void Foo(int p) {++p;}
static void Main( ) {
    int x = 8;
    Foo(x); // make a copy of the value-type x
    Console.WriteLine(x); // x will still be 8
}
```

Assigning `p` a new value does not change the contents of `x`, since `p` and `x` reside in different memory locations.

2.7.3.2 Ref modifier

To pass by reference, C# provides a the parameter modifier `ref`, which allows `p` and `x` to refer to the same memory locations:

```
class Test {
    static void Foo(ref int p) {++p;}
    static void Main ( ) {
        int x = 8;
        Foo(ref x); // send reference of x to Foo
        Console.WriteLine(x); // x is now 9
    }
}
```

```
}
```

Now assigning `p` a new value changes the contents of `x`. This is usually the reason we want to pass by reference, though occasionally it is more efficient when passing large structs. Notice how the `ref` modifier and the method definition are required in the method call. This makes it very clear what's going on, and clears ambiguity since parameter modifiers change the signature of a method.

The `ref` modifier is essential when implementing a swap method:

```
class Test {
    static void Swap (ref string a, ref string b) {
        string temp = a;
        a = b;
        b = temp;
    }
    static void Main ( ) {
        string x = "Bush";
        string y = "Gore";
        Swap(ref x, ref y);
        System.Console.WriteLine("x is {0}, y is {1}", x, y);
    }
}
// outputs: x is Gore, y is Bush
```

2.7.3.3 The out modifier

C# is a language that enforces that variables are assigned before use, so it also provides the `out` modifier, which is the natural complement of the `ref` modifier. While a `ref` modifier requires that a variable is assigned a value before being passed to a method, the `out` modifier requires that a variable is assigned a value before returning from a method:

```
using System;
class Test {
    static void Split(string name, out string firstNames,
                     out string lastName) {
        int i = name.LastIndexOf(' ');
        firstNames = name.Substring(0, i);
        lastName = name.Substring(i+1);
    }
    static void Main( ) {
        string a, b;
        Split("Nuno Bettencourt", out a, out b);
        Console.WriteLine("FirstName:{0}, LastName:{1}", a, b);
    }
}
```

2.7.3.4 The params modifier

The `params` parameter modifier may be specified on the last parameter of a method so that the method accepts any number of parameters of a particular type. For example:

```
using System;
class Test {
    static int Add(params int[] iarr) {
        int sum = 0;
        foreach(int i in iarr)
            sum += i;
        return sum;
    }
    static void Main( ) {
        int i = Add(1, 2, 3, 4);
        Console.WriteLine(i); // 10
    }
}
```

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

2.8 Expressions and Operators

An expression is a sequence of operators and operands that specifies a computation. C# has unary operators, binary operators, and one ternary operator. Complex expressions can be built because an operand may itself be an expression, such as the operand (1 + 2) shown in the following example:

```
((1 + 2) / 3)
```

2.8.1 Operator Precedence

When an expression contains multiple operators, the precedence of the operators controls the order in which the individual operators are evaluated. When the operators are of the same precedence, their associativity determines the order. Binary operators (except for assignment operators) are left-associative; i.e., they are evaluated from left to right. The assignment operators, unary operators, and the conditional operator are right-associative; i.e., they are evaluated from right to left.

For example:

```
1 + 2 + 3 * 4
```

is evaluated as:

```
((1 + 2) + (3 * 4))
```

because * has a higher precedence than +, and + is a binary operator that is left-associative. You can insert parentheses to change the default order of evaluation. C# overloads operators, which means the same operator may have different meanings for different types.

[Table 2-2](#) lists C#'s operators in order of precedence. Operators in the same box have the same precedence, and operators in *italic* may be overloaded for custom types.

Table 2-2. Operator precedence

Category	Operators
Primary	<p>Grouping: <code>(x)</code></p> <p>Member access: <code>x.y</code></p> <p>Struct pointer member access: <code>-></code></p> <p>Method call: <code>f(x)</code></p> <p>Indexing: <code>a[x]</code></p> <p><i>Post increment:</i> <code>x++</code></p> <p><i>Post decrement:</i> <code>x--</code></p> <p>Constructor call: <code>new</code></p> <p>Array stack allocation: <code>stackalloc</code></p> <p>Type retrieval: <code>typeof</code></p> <p>Struct size retrieval: <code>sizeof</code></p> <p>Arithmetic check on: <code>checked</code></p> <p>Arithmetic check off: <code>unchecked</code></p>
Unary	<p><i>Positive value of (passive):</i> <code>+</code></p> <p><i>Negative value of:</i> <code>-</code></p> <p><i>Not:</i> <code>!</code></p> <p><i>Bitwise complement:</i> <code>~</code></p> <p><i>Pre increment:</i> <code>++x</code></p> <p><i>Pre decrement:</i> <code>--x</code></p> <p>Type cast: <code>(T)x</code></p> <p>Value at address: <code>*</code></p> <p>Address of value: <code>&</code></p>
Multiplicative	<p><i>Multiply:</i> <code>*</code></p> <p><i>Divide:</i> <code>/</code></p> <p><i>Division remainder:</i> <code>%</code></p>
Additive	<p><i>Add:</i> <code>+</code></p> <p><i>Subtract:</i> <code>-</code></p>

Category	Operators
Shift	<i>Shift bits left.</i> << <i>Shift bits right.</i> >>
Relational	<i>Less than.</i> < <i>Greater than.</i> > <i>Less than or equal to.</i> <= <i>Greater than or equal to.</i> >= Type equality/compatibility: <code>is</code> Conditional type conversion: <code>as</code>
Equality	<i>Equals.</i> == <i>Not equals.</i> !=
Logical bitwise	<i>And.</i> & <i>Exclusive or.</i> ^ <i>Or.</i>
Logical Boolean	And: && Or: Ternary conditional: ?: e.g., <code>int x = a > b ? 2 : 7;</code> is equivalent to: <code>int x;</code> <code>if (a > b) x = 2;</code> <code>else x = 7;</code>
Assignment	Assign/modify: = *= /= %= += -= <<= >>= &= ^= =

2.8.2 Arithmetic Overflow Check Operators

The syntax for the checked and unchecked operators is:

```
checked (expression)
unchecked (expression)
```


The syntax for the checked and unchecked statements is:

```
checked statement-or-statement-block
unchecked statement-or-statement-block
```

The checked operator tells the runtime to generate an `OverflowException` if an integral expression exceeds the arithmetic limits of that type. The checked operator affects expressions with the `++`, `--`, (unary) `-`, `+`, `-`, `*`, `/`, and explicit conversion operators between integral types. For example:

```
int a = 1000000;
int b = 1000000;

// Check an expression
int c = checked(a*b);

// Check every expression in a statement-block
checked {
    ...
    c = a * b;
    ...
}
```

The checked operator only applies to runtime expressions, since constant expressions are checked during compilation (though this can be turned off with the `/checked [+|-]` command-line switch). The unchecked operator disables arithmetic checking at compile time, and is seldom useful, but does make expressions such as the following compile:

```
const int signedBit = unchecked((int)0x80000000);
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

2.9 Statements

Execution in a C# program is specified by a series of statements that execute sequentially in the textual order in which they appear. All statements in a procedural-based language such as C# are executed for their effect. For instance, a statement may assign an expression to a variable, repeatedly execute a list of statements, or jump to another statement.

So that multiple statements can be grouped together, zero or more statements may be enclosed in braces to form a statement block.

2.9.1 Expression Statements

```
[variable =]? expr;
```

An expression statement evaluates an expression, either assigning its result to a variable or generating side effects (i.e., *invocation*, *new*, *++*, *--*). An expression statement ends in a semicolon. For example:

```
x = 5 + 6; // assign result
x++; // side effect
y = Math.Min(x, 20); // side effect and assign result
Math.Min(x, y); // discards result, but ok, there is a side effect
x = = y; // error, has no side effect, and does not assign result
```

2.9.2 Declaration Statements

The variable declaration syntax is:

```
type [variable [ = expr ]?]+ ;
```

The constant declaration syntax is:

```
const type [variable = constant-expr]+;
```

A declaration statement declares a new variable, optionally assigning the result of an expression to that variable. A declaration statement ends in a semicolon.

The scope of a local or constant variable extends to the end of the current block. You cannot declare another local variable with the same name in the current block or in any nested blocks. For example:

```
bool a = true;
while(a) {
    int x = 5;
    if (x= =5) {
        int y = 7;
```

```

    int x = 2; // error, x already defined
}
Console.WriteLine(y); // error, y is out of scope
}

```

A constant declaration is like a variable declaration, except that the variable cannot be changed after it has been declared:

```

const double speedOfLight = 2.99792458E08;
speedOfLight+=10; // error

```

2.9.3 Selection Statements

C# has many ways to conditionally control the flow of program execution. This section covers the simplest two constructs: the **if-else** statement and the **switch** statement. In addition, C# also provides the conditional operator and loop statements that conditionally execute based on a boolean expression. Finally, C# provides object-oriented ways of conditionally controlling the flow of execution, namely virtual method invocations and delegate invocations.

2.9.3.1 The if-else statement

```

if (Boolean-expr)
    [statement | statement-block]
[ else
    [statement | statement-block] ]?

```

An **if-else** statement executes code depending on whether a boolean expression is true. Unlike in C, only a boolean expression is permitted. In this example, the **Compare** method will return **1** if **a** is greater than **b**, **-1** if **a** is less than **b**, and **0** if **a** is equal to **b**.

```

int Compare(int a, int b) {
    if (a>b)
        return 1;
    else if (a<b)
        return -1;
    return 0;
}

```

It is very common to use the **&&** and **||** and **!** operators to test for **AND**, **OR**, and **NOT** conditions. In this example, our **GetUmbrellaNeeded** method returns an umbrella if it's rainy or sunny (to protect us from the rain or the sun), as long as it's not also windy (since umbrellas are useless in the wind):

```

Umbrella GetUmbrella (bool rainy, bool sunny, bool windy) {
    if ((rainy || sunny) && ! windy)
        return umbrella;
    return null;
}

```

2.9.3.2 The switch statement

```
switch (expr) {
[ case constant-expr : statement* ]*
[ default : statement* ]?
}
```

`switch` statements let you branch program execution based on a selection of possible values a variable may have. `switch` statements may result in cleaner code than multiple `if` statements, since `switch` statements require an expression to be evaluated only once. For instance:

```
void Award(int x) {
    switch(x) {
        case 1:
            Console.WriteLine("Winner!");
            break;
        case 2:
            Console.WriteLine("Runner-up");
            break;
        case 3:
        case 4:
            Console.WriteLine("Highly commended");
            break;
        default:
            Console.WriteLine("Don't quit your day job!");
            break;
    }
}
```

The `switch` statement can only evaluate a predefined type (including the string type) or enum, though user-defined types may provide an implicit conversion to these types.

The end of each case statement must be unreachable. This typically means each case statement ends with a jump statement. The options are:

- Use the `break` statement to jump to the end of the `switch` statement (this is by far the most common option).
- Use the `goto case <constant expression>` or `goto default` statements to jump to either another case statement or to the default case statement.
- Use any other jump statement-namely, `return`, `throw`, `continue`, or `goto label`.

Unlike in Java and C++, the end of a case statement must explicitly state where to go to next. There is no error-prone "default fall through" behavior; not specifying a `break` results in the next case statement being executed:

```
void Greet(string title) {
    switch (title) {
        case null:
            Console.WriteLine("And you are?");
            goto default;
        case "King":
            Console.WriteLine("Greetings your highness");
    }
```

```

        // error, should specify break, otherwise...
    default :
        Console.WriteLine("How's it hanging?");
        break;
    }
}

```

2.9.4 Loop Statements

C# enables a sequence of statements to execute repeatedly with the **while**, **do while**, **for**, and **foreach** statements.

2.9.4.1 while loops

```
while (Boolean-expr)
```

```
[statement | statement-block]
```

while loops repeatedly execute a statement block when a boolean expression is true. The expression is tested before the statement block is executed. For example:

```

int i = 0;
while (i<5) {
    Console.WriteLine (i);
    i++;
}

```

output:

```

0
1
2
3
4

```

2.9.4.2 do-while loops

```

do
    [statement | statement-block]

```

```
while (Boolean-expr);
```

do-while loops differ only in functionality from **while** loops in that they allow the expression to be tested after the statement block has executed. In this example, a **do-while** loop prints 8, while a **while** loop would have not printed anything. For example:

```
int i = 8;
```

```
do {
    Console.WriteLine (i);
    i++;
}
while (i<5);
```

output:
8

2.9.4.3 for loops

```
for (statement?;
    Boolean-expr?;
    statement?)
    [statement | statement-block]
```

`for` loops can be more convenient than `while` loops when you need to maintain an iterator value. As in Java and C, `for` loops contain three parts. The first part is a statement executed before the loop begins, and by convention is used to initialize an iterator variable; the second part is a boolean expression that, while true, will execute the statement block, and the third part is a statement executed after each iteration of the statement block, which convention is used to iterate the iterator variable. For example:

```
for (int i=0; i<10; i++)
    Console.WriteLine(i);
```

Any of the three parts of the `for` statement may be omitted. One can implement an infinite loop such as the following (though `while (true)` may be used instead):

```
for (;;)
    Console.WriteLine("Hell ain't so bad");
```

2.9.4.4 foreach loops

```
foreach ( type-value in IEnumerable )
    [statement | statement-block ]
```

It is very common for `for` loops to iterate over a collection, so C#, like Visual Basic, has a `foreach` statement.

For instance, instead of doing the following:

```
for (int i=0; i<dynamite.Length; i++)
    Console.WriteLine(dynamite [i]);
```

You can perform this action:

```
foreach (Stick stick in dynamite)
    Console.WriteLine(stick);
```

The `foreach` statement works on any collection (including arrays). Although not strictly necessary, all

collections leverage this functionality by supporting `IEnumerable` and `IEnumerator`, which are explained in [Chapter 7](#). Here is an equivalent way to iterate over our collection:

```
IEnumerator ie = dynamite.GetEnumerator( );
while (ie.MoveNext( )) {
    Stick stick = (Stick)ie.Current;
    Console.WriteLine(stick);
}
```

Under the hood, the `foreach` statement also acts as a `using` statement (covered later in this chapter) on the enumerator object (`ie` in the example above). In Visual C# 2003, `Dispose()` will be called on the enumerator, even if the enumerator does not implement `IEnumerable`.

2.9.5 Jump Statements

The C# jump statements are `break`, `continue`, `goto`, `return`, and `throw`. All jump statements obey sensible restrictions imposed by `try` statements (see [Section 4.6](#) in [Chapter 4](#)). First, a jump out of a `try` block always executes the `try`'s `finally` block before reaching the target of the jump. Second, a jump cannot be made from the inside to the outside of a `finally` block.

2.9.5.1 The break statement

```
break;
```

The `break` statement transfers execution from the enclosing `while` loop, `for` loop, or `switch` statement block to the next statement block.

```
int x = 0;
while (true) {
    x++;
    if (x>5)
        break; // break from the loop
}
```

2.9.5.2 The continue statement

```
continue;
```

The `continue` statement forgoes the remaining statements in the loop and makes an early start on the next iteration.

```
int x = 0;
int y = 0;
while (y<100) {
    x++;
    if ((x%7) == 0)
        continue; // continue with next iteration
    y++;
}
```

2.9.5.3 The goto statement

```
goto statement-label;
goto case-constant;
```

The `goto` statement transfers execution to another label within the statement block. A label statement is just a placeholder in a method:

```
int x = 4;
start:
x++;
if (x == 5)
    goto start;
```

The `goto` case statement transfers execution to another case label in a switch block (as explained earlier in the "Switch" section).

2.9.5.4 The return statement

```
return expr?;
```

The `return` statement exits the method, and must return an expression of the method's return type if the method is nonvoid.

```
int CalcX(int a) {
    int x = a * 100;
    return x; // return to the calling method with value
}
```

2.9.5.5 The throw statement

```
throw exception-expr?;
```

The `throw` statement throws an exception to indicate an abnormal condition has occurred (see [Section 4.6](#) in [Chapter 4](#)).

```
if (w == null)
    throw new ArgumentException("w can't be null");
```

2.9.5.6 The lock statement

```
lock (expr)
    [statement / statement-block]
```

The `lock` statement is actually a syntactic shortcut for calling the `Enter` and `Exit` methods of the `Monitor` class (see [Chapter 16](#)).

2.9.5.7 The using statement

```
using (declaration-expr)
    [statement | statement-block]
```

Many classes encapsulate nonmemory resources, such as file handles, graphics handles, or database connections. These classes implement `System.IDisposable`, which defines a single parameterless method named `Dispose` called to clean up these resources. The `using` statement provides an elegant syntax for declaring and then calling the `Dispose` method of variables that implement `IDisposable`. For example:

```
using (FileStream fs = new FileStream (fileName, FileMode.Open)) {
    ...
}
```

This is precisely equivalent to:

```
FileStream fs = new FileStream (fileName, FileMode.Open);
try {
    ...
}
finally {
    if (fs != null)
        ((IDisposable)fs).Dispose( );
}
```

For more on `IDisposable`, see [Chapter 15](#).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

2.10 Namespaces

These are defined in files, organized by namespaces, compiled into a module, then grouped into an assembly.

These organizational units are crosscutting. For example, typically a group of namespaces belong to one assembly, but a single namespace may in fact be spread over multiple assemblies (see [Chapter 12](#)).

2.10.1 Files

File organization is almost of no significance to the C# compiler—a whole project could be merged into one `.cs` file and it would still compile (preprocessor statements are the only exception to this). However, it's generally tidy to have one type in one file, with the filename matching the name of the class and the directory the file is in matching the name of the class's namespace.

2.10.2 Namespaces

```
namespace name+           // Dot-delimited
{
    using-statement*
    [namespace-declaration |
     type-declaration]*    // No delimiters
}
```

A namespace lets you group related types into a hierarchical categorization. Generally the first name is the name of your organization, and it gets more specific from there:

```
namespace MyCompany.MyProduct.Drawing {
    class Point {int x, y, z;}
    delegate void PointInvoker(Point p);
}
```

2.10.2.1 Nesting namespaces

You may also nest namespaces instead of using dots. This example is semantically identical to the previous example:

```
namespace MyCompany {
    namespace MyProduct {
        namespace Drawing {
            class Point {int x, y, z;}
            delegate void PointInvoker(Point p);
        }
    }
}
```

```

    }
}

```

2.10.2.2 Using a type with its fully qualified name

To use the `Point` from another namespace, you may refer to it with its fully qualified name. The namespace a type is within actually becomes part of the type name:

```

namespace TestProject {
    class Test {
        static void Main( ) {
            MyCompany.MyProduct.Drawing.Point x;
        }
    }
}

```

2.10.2.3 The using keyword

The `using` keyword is a convenient way to avoid using the fully qualified name of types in other namespaces. This example is semantically identical to our previous example:

```

namespace TestProject {
    using MyCompany.MyProduct.Drawing;
    class Test {
        static void Main( ) {
            Point x;
        }
    }
}

```

2.10.2.4 Aliasing types and namespaces

Type names must be unique within a namespace. To avoid naming conflicts without having to use fully qualified names, C# allows you to specify an alias for a type or namespace. Here is an example:

```

using sys = System;           // Namespace alias
using txt = System.String;    // Type alias
class Test {
    static void Main( ) {
        txt s = "Hello, World!";
        sys.Console.WriteLine(s); // Hello, World!
        sys.Console.WriteLine(s.GetType( )); // System.String
    }
}

```

2.10.2.5 Global namespace

The global namespace is the outermost level that all namespaces and types are implicitly declared in. When a type is not explicitly declared within a namespace, it may be used without qualification from

any other namespace, since it is a member of the global namespace. However, apart from the smallest programs, it is always good practice to organize types within logical namespaces.

In this example, the class `Test` is declared in the global namespace, so it can be used without qualification from the `Noo` namespace.

```
class Test {  
    public static void Foo ( ) {  
        System.Console.WriteLine ( "hello!" );  
    }  
}  
namespace Noo {  
    class Test2 {  
        static void Main( ) {  
            Test.Foo( );  
        }  
    }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 3. Creating Types in C#

In this chapter, we cover creation of types in C#, including classes, inheritance, access modifiers, structs, interfaces, and enums.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

3.1 Classes

```
attributes? unsafe? access-modifier?
new?
[ abstract | sealed ]?
class class-name
[: base-class |
 : interface+ |
 : base-class, interface+ ]?
{ class-members }
```

In C#, a program is built by defining new types, each with a set of data members and function members. Custom types should form higher-level building blocks that are easy to use, and closely model your problem space.

In this example, we simulate an astronaut jumping on different planets, using three classes, `Planet`, `Astronaut`, and `Test`, to test our simulation.

First, let's define the `Planet` class. By convention, we define the data members of the class at the top of the class declaration. There are two data members here: the `name` and `gravity` fields, which store the name and gravity of a planet. We then define a constructor for the planet. Constructors are function members that allow you to initialize an instance of your class. We initialize the data members with values fed to the parameters of the constructor. Finally, we define two more function members, which are properties that allow us to get the "Name" and "Gravity" of a planet. The `Planet` class looks like this:

```
using System;

class Planet {
    string name; // field
    double gravity; // field
    // constructor
    public Planet (string n, double g) {
        name = n;
        gravity = g;
    }
    // property
    public string Name {
        get {return name;}
    }
    // property
    public double Gravity {
        get {return gravity;}
    }
}
```

Next, we define the `Astronaut` class. As with the `Planet` class, we first define our data members.

Here an astronaut has two fields: the astronaut's fitness, and the current planet the astronaut is on. We then provide a constructor, which initializes the fitness of an astronaut. Next we define a `CurrentPlanet` property that allows us to get or set the planet an astronaut is on. Finally we define a jump method that outputs how far the astronaut jumps, based on the fitness of the astronaut and the planet he is on.

```
using System;

class Astronaut {
    double fitness; // field
    Planet currentPlanet; // field

    // constructor
    public Astronaut (double f) {
        fitness = f;
    }
    // property
    public Planet CurrentPlanet {
        get {
            return currentPlanet;
        }
        set {
            currentPlanet = value;
        }
    }
    // method
    public void Jump ( ) {
        if (currentPlanet == null)
            Console.WriteLine ("Bye Bye!");
        else {
            double distance = fitness/currentPlanet.Gravity;
            Console.WriteLine ("Jumped {0} metres on {1}", distance,
                               currentPlanet.Name);
        }
    }
}
```

Last, we define the `Test` class, which uses the `Planet` and `Astronaut` classes. Here we create two planets, `earth` and `moon`, and one astronaut, `forestGump`. Then we see how far `forestGump` jumps on each of these planets:

```
class Test {
    static void Main ( ) {
        // create a new instance of a planet
        Planet earth = new Planet ("earth", 9.8);
        // create another new instance of a planet
        Planet moon = new Planet ("moon", 1.6);
        // create a new instance of an astronaut
        Astronaut forestGump = new Astronaut (20);
        forestGump.CurrentPlanet = earth;
        forestGump.Jump( );
        forestGump.CurrentPlanet = moon;
```

```

        forestGump.Jump( );
    }
}
// output
Jumped 2.04 metres on earth
Jumped 12.50 metres on moon

```

If a class is designed well, it becomes a new higher-level building block that is easy for someone else to use. The user of a class seldom cares about the data members or implementation details of another class, merely its specification. To use a planet or an astronaut, all you need to know is how to use their public function members.

In the following section, we look at each kind of type members a class can have, namely fields, constants, properties, indexers, methods, operators, constructors, destructors, and nested types. (Operators and events are explained in [Chapter 4](#).)

3.1.1 The this Keyword

The `this` keyword denotes a variable that is a reference to a class or struct instance and is only accessible from within nonstatic function members of the class or struct. The `this` keyword is also used by a constructor to call an overloaded constructor (explained later in this chapter) or declare or access indexers (also explained later in this chapter). A common use of the `this` variable is to distinguish a field name from a parameter name.

```

class Dude {
    string name;
    public Dude (string name) {
        this.name = name;
    }
    public void Introduce(Dude a) {
        if (a!=this)
            Console.WriteLine("Hello, I'm "+name);
    }
}

```

3.1.2 Fields

attributes? unsafe? access-modifier?

```

new?
static?
[readonly | volatile]?
type [ field-name [ = expr]? ]+ ;

```

Fields hold data for a class or struct:

```

class MyClass {
    int x;
    float y = 1, z = 2;
    static readonly int MaxSize = 10;
}

```



```
...
}
```

3.1.2.1 Nonstatic fields

Nonstatic fields are also referred to as instance variables or instance data members. Static variables are also referred to as static variables or static data members.

3.1.2.2 The readonly modifier

As the name suggests, the `readonly` modifier prevents a field from being modified after it has been assigned. Such a field is termed a *read-only field*. A read-only field is always evaluated at runtime, not at compile time. A read-only field must be assigned in its declaration or within the type's constructor in order to compile (see more on constructors, later in this chapter), while non-read-only fields merely generate a warning when left unassigned.

3.1.3 Constants

```
attributes? access-modifier?
new?
const type [constant-name = constant-expr]+;
```

A constant is a field that is evaluated at compile time and is implicitly static. The logical consequence of this is that a constant may not defer evaluation to a method or constructor, and may only be one of a few built-in types. These types are `sbyte`, `byte`, `short`, `ushort`, `int`, `uint`, `long`, `ulong`, `float`, `double`, `decimal`, `bool`, `char`, `string`, and `enum`. For example:

```
public const double PI = 3.14159265358979323846;
```

The benefit of a constant is that it is evaluated at compile time, permitting additional optimization by the compiler. For instance:

```
public static double Circumference(double radius) {
    return 2 * Math.PI * radius;
}
```

evaluates to:

```
public static double Circumference(double radius) {
    return 6.2831853071795862 * radius;
}
```

A read-only field would not make this optimization, but is more versionable. For instance, suppose there was a mistake in calculation of π , and Microsoft releases a patch to their library that contains the `Math` class, which is deployed to each client computer. If your software that uses the `Circumference` method is already deployed on a client machine, then the mistake is not fixed until you recompile your application with the latest version of the `Math` class. With a read-only field, however, this mistake is automatically fixed. Generally, this scenario occurs when a field value changes not as a result of a mistake, but simply because of an upgrade (such as `MaxThreads`

changing from 500 to 1,000).

3.1.4 Properties

```
attributes? unsafe? access-modifier?

[
  [[sealed | abstract]? override] |
  new? [virtual | abstract | static]?
]?
type property-name { [
  attributes? get      // read-only
  statement-block |
  attributes? set      // write-only
  statement-block |
  attributes? get      // read-write
  statement-block
  attributes? set
  statement-block
] }
```

Properties can be characterized as object-oriented fields. Properties promote encapsulation by allowing a class or struct to control access to its data, and by hiding the internal representation of the data. For instance:

```
public class Well {
    decimal dollars; // private field
    public int Cents {
        get { return(int)(dollars * 100); }
        set {
            // value is an implicit variable in a set
            if (value>=0) // typical validation code
                dollars = (decimal)value/100;
        }
    }
}

class Test {
    static void Main( ) {
        Well w = new Well( );
        w.Cents = 25; // set
        int x = w.Cents; // get
        w.Cents += 10; // get and set(throw a dime in the well)
    }
}
```

The `get` accessor returns a value of the property's type. The `set` accessor has an implicit parameter named `value` that is of the property's type. A property can be read-only if it specifies only a `get` method, and write-only if it specifies only a `write` method (though rarely desirable).

Many languages loosely implement properties with a `get/set` method convention, and C# properties

are in fact compiled to `get_XXX/set_XXX` methods. This is the representation in MSIL:

```
public int get_Cents {...}
public void set_Cents (int value) {...}
```



Simple property accessors are inlined by the JIT (Just-In-Time compiler), which means there is no performance difference between a property access and a field access. Inlining is an optimization in which a method call is replaced with the body of that method.

3.1.5 Indexers

attributes? unsafe? access-modifier?

```
[
  [[sealed | abstract]? override] |
  new? [virtual | abstract | static]?
]?
type this [ attributes? [type arg]+ ] {
  attributes? get      // read-only
    statement-block |
  attributes? set      // write-only
    statement-block |
  attributes? get      // read-write
    statement-block
  attributes? set
    statement-block
}
```

Indexers provide a natural way of indexing elements in a class or struct that encapsulate a collection, via an array's `[]` syntax. Indexers are similar to properties, but are accessed via an index, as opposed to a property name. The index can be any number of parameters. In the following example, the `ScoreList` class can be used to maintain the list of scores given by five judges. The indexer uses a single `int` index to get or set a particular judge's score.

```
public class ScoreList {
  int[] scores = new int [5];
  // indexer
  public int this[int index] {
    get {
      return scores[index]; }
    set {
      if(value >= 0 && value <= 10)
        scores[index] = value;
    }
  }
  // property (read-only)
  public int Average {
    get {
      int sum = 0;
```

```

        foreach(int score in scores)
            sum += score;
        return sum / scores.Length;
    }
}
}
class Test {
    static void Main( ) {
        ScoreList sl = new ScoreList( );
        sl[0] = 9;
        sl[1] = 8;
        sl[2] = 7;
        sl[3] = sl[4] = sl[1];
        System.Console.WriteLine(sl.Average);
    }
}

```

A type may declare multiple indexers that take different parameters. Our example could be extended to return the score by a judge's name, as opposed to a numeric index.

Indexers are compiled to `get_Item (...)/set_Item (...)` methods, which is the representation in MSIL.

```

public Story get_Item (int index) {...}
public void set_Item (int index, Story value) {...}

```

3.1.6 Methods

attributes? unsafe? access-modifier?

```

[
    [[sealed | abstract]? override] |
    new? [virtual | abstract |
        static extern?]?
]?
[ void | type ]
    method-name (parameter-list)
        statement-blockParameter list syntax:
[ attributes? [ref | out]? type arg ]*
[ params attributes? type[ ] arg ]?

```

All C# code executes in a method or in a special form of a method. Constructors, destructors, and operators are special types of methods, and properties and indexers are internally implemented with `get/set` methods.

3.1.6.1 Signatures

A method's signature is characterized by the type and modifier of each parameter in its parameter list. The parameter modifiers `ref` and `out` allow arguments to be passed by reference, rather than by value. These characteristics are referred to as a *method signature*, because they uniquely distinguish

one method from another.

3.1.6.2 Overloading methods

A type may overload methods (have multiple methods with the same name), as long as the signatures are different.^[1] For example, the following methods can all coexist in the same type:

^[1] An exception to this rule is that two otherwise identical signatures cannot coexist if one parameter has the `ref` modifier and the other parameter has the `out` modifier.

```
void Foo(int x);
void Foo(double x);
void Foo(int x, float y);
void Foo(float x, int y);
void Foo(ref int x);
```

However, the following pairs of methods cannot coexist in the same type, since the return type and `params` modifier do not qualify as part of a method's signature.

```
void Foo(int x);
float Foo(int x); // compile error
void Goo (int[ ] x);
void Goo (params int[ ] x); // compile error
```

3.1.7 Instance Constructors

```
attributes? unsafe? access-modifier?
class-name (parameter-list)
[ : [ base | this ] (argument-list) ]?
statement-block
```

Constructors allow initialization code to execute for a class or struct. A class constructor first creates a new instance of that class on the heap and then performs initialization, while a struct constructor merely performs initialization.

Unlike ordinary methods, a constructor has the same name as the class or struct and has no return type:

```
class MyClass {
    public MyClass( ) {
        // initialization code
    }
}
```

A class or struct may overload constructors, and may call one of its overloaded constructors before executing its method body using the `this` keyword:

```
class MyClass {
    public int x;
    public MyClass( ) : this(5) { }
    public MyClass(int v) {
```

```

        x = v;
    }
}
MyClass m1 = new MyClass( );
MyClass m2 = new MyClass(10);
Console.WriteLine(m1.x) // 5
Console.WriteLine(m2.x) // 10;

```

If a class does not define any constructors, an implicit parameter-free constructor is created. A struct cannot define a parameter-free constructor, since a constructor that initializes each field with a default value (effectively zero) is always implicitly defined.

3.1.7.1 Field initialization order

Another useful way to perform initialization is to assign fields an initial value in their declaration:

```

class MyClass {
    int x = 5;
}

```

Field assignments are performed before the constructor is executed, and are initialized in the textual order in which they appear.

3.1.7.2 Constructor access modifiers

A class or struct may choose any access modifier for a constructor. It is occasionally useful to specify a private constructor to prevent a class from being constructed. This is appropriate for utility classes made up entirely of static members, such as the `System.Math` class.

3.1.8 Static Constructors

```

attributes? unsafe? extern?
static class-name ( )
statement-block

```

A static constructor allows initialization code to execute before the first instance of a class or struct is created, or before any static member of the class or struct is accessed. A class or struct can define only one static constructor, and it must be parameter-free and have the same name as the class or struct:

```

class Test {
    static Test( ) {
        Console.WriteLine("Test Initialized");
    }
}

```

3.1.8.1 Static field initialization order

Each static field assignment is made before any of the static constructors are called, and are initialized in the textual order in which they appear, which is consistent with instance fields.

```
class Test {
    public static int x = 5;
    public static void Foo( ) { }
    static Test( ) {
        Console.WriteLine("Test Initialized");
    }
}
```

Accessing either `Test.x` or `Test.Foo` assigns 5 to `x`, and then prints `Test Initialized`.

3.1.8.2 Nondeterminism of static constructors

Static constructors cannot be called explicitly, and the runtime may invoke them well before they are first used. Programs should not make any assumptions about the timing of a static constructor's invocation. In this example, `Test Initialized` may be printed after `Test2 Initialized`:

```
class Test2 {
    public static void Foo( ) { }
    static Test2 ( ) {
        Console.WriteLine("Test2 Initialized");
    }
}
Test.Foo( );
Test2.Foo( );
```

3.1.9 Destructors and Finalizers

```
attributes? unsafe?
~class-name ( )
statement-block
```

Destructors are class-only methods that are used to clean up nonmemory resources just before the garbage collector reclaims the memory for an object. Just as a constructor is called when an object is created, a destructor is called when an object is destroyed. C# destructors are very different from C++ destructors, primarily because of the presence of the garbage collector. First, memory is automatically reclaimed with a garbage collector, so a destructor in C# is used solely for nonmemory resources. Second, destructor calls are nondeterministic. The garbage collector calls an object's destructor when it determines it is no longer referenced; however, it may determine this after an undefined period of time has passed after the last reference to the object disappeared.

A destructor is actually a syntactic shortcut for declaring a `Finalize` method (known as a finalizer), and is expanded by the compiler into the following method declaration:

```
protected override void Finalize( ) {
    ...
    base.Finalize( );
}
```

For more details on the garbage collector and finalizers, see [Chapter 18](#).

3.1.10 Nested Types

A nested type is declared within the scope of another type. Nesting a type has three benefits:

- A nested type can access all the members of its enclosing type, regardless of a member's access modifier.
- A nested type can be hidden from other types with type-member access modifiers.
- Accessing a nested type from outside of its enclosing type requires specifying the type name. This is the same principle used for static members.

For example:

```
using System;
class A {
    int x = 3; // private member
    protected internal class Nested { // choose any access-level
        public void Foo ( ) {
            A a = new A ( );
            Console.WriteLine (a.x); //can access A's private members
        }
    }
}
class B {
    static void Main ( ) {
        A.Nested n = new A.Nested ( ); // Nested is scoped to A
        n.Foo ( );
    }
}
// an example of using "new" on a type declaration
class C : A {
    new public class Nested { } // hide inherited type member
}
```



Nested classes in C# are roughly equivalent to static inner classes in Java. There is no C# equivalent to Java's nonstatic inner classes; there is no "outer this" in C#.

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

3.2 Inheritance

A class can inherit from another class to extend or customize the original class. Inheriting from a class allows you to reuse the functionality in that class instead of building it from scratch. A class can inherit from only a single class, but can itself be inherited by many classes, thus forming a class hierarchy. A well-designed class hierarchy is one that reasonably generalizes the nouns in a problem space. For example, there is a class called `Image` in the `System.Drawing` namespace, which the `Bitmap`, `Icon`, and `Metafile` classes inherit from. All classes are ultimately part of a single giant class hierarchy, of which the root is the `Object` class. All classes implicitly inherit from it.

In this example, we start by defining a class called `Location`. This class is very basic, and provides a location with a name property and a way to display itself to the console window:

```
class Location { // Implicitly inherits from object
    string name;

    // The constructor that initializes Location
    public Location(string n) {
        name = n;
    }
    public string Name {get {return name;}}
    public void Display( ) {
        System.Console.WriteLine(Name);
    }
}
```

Next, we define a class called `URL`, which will inherit from `Location`. The `URL` class has all the same members as `Location`, as well as a new member, `Navigate`. Inheriting from a class requires specifying the class to inherit from the class declaration, using the C++ colon notation:

```
class URL : Location { // Inherit from Location
    public void Navigate( ) {
        System.Console.WriteLine("Navigating to "+Name);
    }
    // The constructor for URL, which calls Location's constructor
    public URL(string name) : base(name) { }
}
```

Now, we instantiate a `URL`, then invoke both the `Display` method (which is defined in `Location`) and the `Navigate` method (which is defined in `URL`):

```
class Test {
    static void Main( ) {
        URL u = new URL("http://microsoft.com");
        u.Display( );
        u.Navigate( );
    }
}
```



The specialized class/general class is referred to as the derived class/base class or the subclass/superclass.

3.2.1 Class Conversions

A class \mathcal{D} may be implicitly upcast to the class \mathcal{B} that it derives from, and a class \mathcal{B} may be explicitly downcast to the class \mathcal{D} that derives from it. For instance:

```
URL u = new URL( );
Location l = u; // upcast
u = (URL)l; // downcast
```

If the downcast fails, an `InvalidCastException` is thrown.

3.2.1.1 The as operator

The `as` operator makes a downcast that evaluates to `null` if the downcast fails:

```
u = l as URL;
```

3.2.1.2 The is operator

The `is` operator tests whether an object is or derives from a specified class (or implements an interface). It is often used to perform a test before a downcast:

```
if (l is URL)
    ((URL)l).Navigate( );
```

3.2.2 Polymorphism

Polymorphism is the ability to perform the same operations on many types, as long as each type shares a common subset of characteristics. C# custom types exhibit polymorphism by inheriting classes and implementing interfaces (see [Section 3.5](#) later in this chapter).

To continue with our inheritance example, the `Show` method can perform the operation `Display` on both a `URL` and a `LocalFile`, because both types inherit a `Location`'s set of characteristics:

```
class LocalFile : Location {
    public void Execute( ) {
        System.Console.WriteLine("Executing "+Name);
    }
    // The constructor for LocalFile, which calls URL's constructor
    public LocalFile(string name) : base(name) { }
}
class Test {
    static void Main( ) {
```

```

        URL u = new URL("http://microsoft.com");
        LocalFile l = new LocalFile("c:\\readme.txt");
        Show(u);
        Show(l);
    }
    public static void Show(Location loc) {
        System.Console.WriteLine("Location is: ");
        loc.Display( );
    }
}

```

3.2.3 Virtual Function Members

A key aspect of polymorphism is the ability for each type to exhibit a shared characteristic in its own way. A base class may have virtual function members, which enable a derived class to provide its own implementation for that function member (also see [Section 3.5](#) later in this chapter):

```

class Location {
    public virtual void Display( ) {
        Console.WriteLine(Name);
    }
    ...
}
class URL : Location {
    // chop off the http:// at the start
    public override void Display( ) {
        Console.WriteLine(Name.Substring(6));
    }
    ...
}

```

`URL` now has a custom way of displaying itself. The `Show` method in the `Test` class in the previous section now calls the new implementation of `Display`. The signatures of the overridden method and the virtual method must be identical, but unlike Java and C++, the `override` keyword is also required.

3.2.4 Abstract Classes and Abstract Members

A class may be declared abstract. An abstract class may have abstract members. These are function members without implementation that are implicitly virtual. In our earlier examples, we had a `Navigate` method for the `URL` and an `Execute` method for the `LocalFile`. Instead, `Location` could be an abstract class with an abstract method called `Launch`:

```

abstract class Location {
    public abstract void Launch( );
}
class URL : Location {
    public override void Launch( ) {
        Console.WriteLine("Run Internet Explorer...");
    }
}

```

```

}
class LocalFile : Location {
    public override void Launch( ) {
        Console.WriteLine("Run Win32 Program...");
    }
}

```

A derived class must override all its inherited abstract members, or must itself be declared abstract. An abstract class cannot be instantiated. For instance, if `LocalFile` does not override `Launch`, then `LocalFile` itself must be declared abstract, perhaps so that `Shortcut` and `PhysicalFile` can derive from it.

3.2.5 Sealed Classes

A class may prevent other classes from inheriting from it by specifying the `sealed` modifier in the class declaration:

```

sealed class Math {
    ...
}

```

The most common scenario for sealing a class is when a class is composed of only static members, which is the case with the `Math` class. Another effect of sealing a class is that it enables the compiler to turn all virtual method invocations made on that class into faster nonvirtual method invocations.

3.2.6 Hiding Inherited Members

Aside from calling a constructor, the `new` keyword can also be used to hide the base class data members, function members, and type members of a class. Overriding a virtual method with the `new` keyword hides, rather than overrides, the base class implementation of the method:

```

class B {
    public virtual void Foo( ) { }
}
class D : B {
    public override void Foo( ) { }
}
class N : D {
    public new void Foo( ) { } // hides D's Foo
}
N n = new N( );
n.Foo( ); // calls N's Foo
((D)n).Foo( ); // calls D's Foo
((B)n).Foo( ); // calls D's Foo

```

A method declaration with the same signature as its base class must explicitly state whether it overrides or hides the inherited member.

3.2.7 Advanced Features of Virtual Function Members

This section deals with the subtleties of the virtual function member calling mechanism.

3.2.7.1 Versionioning virtual function members

In C#, a method is compiled with a flag that is `true` if it overrides a virtual method. This flag is important for versioning. Suppose you write a class that derives from a base class in the .NET Framework, and deploy your application to a client computer. Later, the client upgrades the .NET Framework, and that base class now has a virtual method that matches the signature of one of your methods in the derived class:

```
class B { // written by the library people
    virtual void Foo( ) {...} // added in latest update
}
class D : B { // written by you
    void Foo( ) {...}
}
```

In most object-oriented languages such as Java, methods are not compiled with this flag, so a derived class's method with the same signature is assumed to override the base class's virtual method. This means a virtual call is made to D's `Foo`, even though D's `Foo` was unlikely to have been made according to the specification intended by the author of B. This could easily break your application. In C#, the flag for D's `Foo` is `false`, so the runtime knows to treat D's `Foo` as new, which ensures that your application functions as it was originally intended. When you get the chance to recompile with the latest framework, you can add the new modifier to `Foo`, or perhaps rename `Foo` to something else.

3.2.7.2 Sealed virtual function members

An overridden function member may seal its implementation, so that it cannot be overridden. In our earlier virtual function member example, we could have sealed the `URL`'s implementation of `Display`. This prevents a class that derives from `URL` from overriding `Display`, which provides a guarantee on the behavior of a `URL`.

```
class Location {
    public virtual void Display( ) {
        Console.WriteLine(Name);
    }
    ...
}
class URL : Location {
    public sealed override void Display( ) {
        Console.WriteLine(Name.Substring(6));
    }
    ...
}
```

3.2.7.3 Overriding a virtual function member

Very occasionally, it is useful to override a virtual function member with an abstract one. In this example, the abstract `Editor` class overrides the `Text` property to ensure that concrete classes deriving from `Editor` provide an implementation for `Text`.

```
class Control {
    public virtual string Text {
        get {
            return null;
        }
    }
}
abstract class Editor : Control {
    abstract override string Text {get;}
}
```

3.2.8 The base Keyword

The `base` keyword is similar to the `this` keyword, except that it accesses an overridden or hidden base class function member. The `base` keyword is also used to call a base class constructor (see the next section) or access a base class indexer (by using `base` instead of `this`). Calling `base` accesses the next most derived class that defines that member. The following builds upon our example from the section on the `this` keyword:

```
class Hermit : Dude {
    public void new Introduce(Dude a) {
        base.Introduce(a);
        Console.WriteLine("Nice Talking To You");
    }
}
```



There is no way to access an instance member of a specific base class, as with the C++ scope resolution `::` operator.

3.2.9 Constructor and Field Initialization in the Inheritance Chain

Initialization code can execute for each class in an inheritance chain, in constructors as well as field initializers. There are two rules. The first is field initialization occurs before *any* constructor in the inheritance chain is called. The second is the base class executes its initialization code before the derived class does.

A constructor must call its base class constructors first. In a case in which the base class has a parameterless constructor, the constructor is implicitly called. In a case in which the base class provides only constructors that require parameters, the derived class constructor must explicitly call one of the base class constructors with the `base` keyword. A constructor may also call an overloaded constructor (which calls `base` for it):

```
class B {
    public int x ;
    public B(int a) {
        x = a;
    }
    public B(int a, int b) {
        x = a * b;
    }
    // Notice how all of B's constructors need parameters
}
class D : B {
    public D( ) : this(7) { } // call an overloaded constructor
    public D(int a) : base(a) { } // call a base class constructor
}
```

Consistent with instance constructors, static constructors respect the inheritance chain, so each static constructor from the least derived to the most derived is called.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

3.3 Access Modifiers

To promote encapsulation, a type or type member may hide itself from other types or other assemblies by adding one of the following five access modifiers to the declaration:

public

The type or type member is fully accessible. This is the implicit accessibility for enum members (see [Section 3.6](#) later in this chapter) and interface members (see [Section 3.5](#) later in this chapter).

internal

The type or type member in assembly *A* is accessible only from within *A*. This is the default accessibility for nonnested types, and so may be omitted.

private

The type member in type *T* is accessible only from within *T*. This is the default accessibility for class and struct members, and so may be omitted.

protected

The type member in class *C* is accessible only from within *C*, or from within a class that derives from *C*.

protected internal

The type member in class *C* and assembly *A* is accessible only from within *C*, from within a class that derives from *C*, or from within *A*. Note that C# has no concept of protected and internal, whereby "a type member in class *C* and assembly *A* is accessible only from within *C*, or from within a class that both derives from *C* and is within *A*."

Note that a type member may be a nested type. Here is an example of using access modifiers:

```
// Assembly1.dll
using System;
public class A {
    private int x=5;
    public void Foo( ) {Console.WriteLine (x);}
    protected static void Goo( ) { }
    protected internal class NestedType { }
}
internal class B {
    private void Hoo ( ) {
        A a1 = new A ( ); // ok
        Console.WriteLine(a1.x); // error, A.x is private
        A.NestedType n; // ok, A.NestedType is internal
        A.Goo( ); // error, A's Goo is protected
    }
}
```



```
// Assembly2.exe (references Assembly1.dll)
using System;
class C : A { // C defaults to internal
    static void Main( ) { // Main defaults to private
        A a1 = new A( ); // ok
        a1.Foo( ); // ok
        C.Goo( ); // ok, inherits A's protected static member
        new A.NestedType( ); // ok, A.NestedType is protected
        new B( ); // error, Assembly 1's B is internal
        Console.WriteLine(x); // error, A's x is private
    }
}
```

3.3.1 Restrictions on Access Modifiers

A type or type member cannot declare itself to be more accessible than any of the types it uses in the declaration. For instance, a class cannot be public if it derives from an internal class, or a method cannot be protected if the type of one of its parameters is internal to the assembly. The rationale behind this restriction is whatever is accessible to another type is actually usable by that type.

In addition, access modifiers cannot be used when they conflict with the purpose of inheritance modifiers. For example, a virtual (or abstract) member cannot be declared private, since it would be impossible to override. Similarly, a sealed class cannot define new protected members, since there is no class that could benefit from this accessibility.

Finally, to maintain the contract of a base class, a function member with the `override` modifier must have the same accessibility as the virtual member it overrides.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

3.4 Structs

```
attributes? unsafe? access-modifier?  
new?  
struct struct-name [: interface+]?  
{ struct-members }
```

A struct is similar to a class, with the following major differences:

- A class is a reference type, while a struct is a value type. Consequently, structs are typically used to express simple types, in which value-type semantics are desirable (e.g., assignment copies a value rather than a reference).
- A class fully supports inheritance (see [Chapter 5](#)), whereas a struct can inherit only from an object and is implicitly sealed (in the runtime structs actually inherit from `System.ValueType`). Both classes and structs can implement interfaces.
- A class can have a destructor, and a struct cannot.
- A class can define a custom parameterless constructor and initialize instance fields, while a struct cannot. The default parameterless constructor for a struct initializes each field with a default value (effectively zero). If a struct declares a constructor(s), then all of its fields must be assigned in that constructor call.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

3.5 Interfaces

```

attributes? unsafe? access-modifier?
new?
interface interface-name
[ : base-interface+ ]?
{ interface-members }

```

An interface is similar to a class, but with the following major differences:

- An interface provides a specification rather than an implementation for its members. This is similar to a pure abstract class, which is an abstract class consisting of only abstract members.
- A class and struct can implement multiple interfaces, while a class can inherit only from a single class.
- A struct can implement an interface, but a struct cannot inherit from a class.

Earlier in this chapter, we defined polymorphism as the ability to perform the same operations on many types, as long as each type shares a common subset of characteristics. The purpose of an interface is precisely for defining such a set of characteristics.

An interface is comprised of a set of the following members:

- Method
- Property
- Indexer
- Event

These members are always implicitly public and implicitly abstract (and therefore virtual and nonstatic).

3.5.1 Defining an Interface

An interface declaration is like a class declaration, but it provides no implementation for its members, since all its members are implicitly abstract. These members are intended to be implemented by a class or struct that implements the interface. Here is a very simple interface that defines a single method:

```

public interface IDelete {
    void Delete( );
}

```

3.5.2 Implementing an Interface

Classes or structs that implement an interface may be said to "fulfill the contract of the interface." In this example, our `IDelete` interface can be implemented by GUI controls that support the concept of deleting, such as a `TextBox`, `TreeView`, or your own custom GUI control.

```
public class TextBox : IDelete {
    public void Delete( ) {...}
}
public class TreeView : IDelete {
    public void Delete( ) {...}
}
```

If a class inherits from a base class, then each interface implemented must appear after the base class:

```
public class TextBox : Control, IDelete {...}
public class TreeView : Control, IDelete {...}
```

3.5.3 Using an Interface

An interface is useful when you need multiple classes to share characteristics not present in a common base class. In addition, an interface is a good way to ensure that these classes provide their own implementation for the interface member, since interface members are implicitly abstract.

The following example assumes a form containing many GUI controls (including some `TextBox` and `TreeView` controls) in which the currently focused control is accessed with the `ActiveControl` property. When a user clicks Delete on a menu item or toolbar button, the example tests to see whether `ActiveControl` implements `IDelete`, and if so, casts it to `IDelete` to call its `Delete` method:

```
class MyForm {
    ...
    void DeleteClick( ) {
        if (ActiveControl is IDelete)
            PerformDelete ((IDelete)ActiveControl);
    }
}
```

3.5.4 Extending an Interface

Interfaces may extend other interfaces. For instance:

```
ISuperDelete : IDelete {
    bool CanDelete {get;}
    event EventHandler CanDeleteChanged;
}
```

A control implements the `CanDelete` property to indicate that it has something to delete and is not

read-only, and implements the `CanDeleteChanged` event to fire an event whenever its `CanDelete` property changes. This framework allows our application to ghost its Delete menu item and toolbar button when the `ActiveControl` is unable to delete.

3.5.5 Explicit Interface Implementation

If there is a name collision between an interface member and an existing member in the class or struct, C# allows you to explicitly implement an interface member to resolve the conflict. In this example, we resolve a conflict when implementing two interfaces that both define a `Delete` method:

```
public interface IDesignTimeControl {
    ...
    object Delete( );
}
public class TextBox : IDelete, IDesignTimeControl {
    ...
    void IDelete.Delete( ) { }
    object IDesignTimeControl.Delete( ) {...}
    // Note that explicitly implementing just one of them would
    // be enough to resolve the conflict
}
```

Unlike implicit interface implementations, explicit interface implementations can't be declared with `abstract`, `virtual`, `override`, or `new` modifiers. In addition, while an implicit implementation requires the use of the `public` modifier, an explicit implementation has no access modifier. However, to access the method, the class or struct must be cast to the appropriate interface first:

```
TextBox tb = new TextBox( );
IDesignTimeControl idtc = (IDesignTimeControl)tb;
IDelete id = (IDelete)tb;
idtc.Delete( );
id.Delete( );
```

3.5.6 Reimplementing an Interface

If a base class implements an interface member with the `virtual` (or `abstract`) modifier, then a derived class can override it. If not, the derived class must reimplement the interface to override that member:

```
public class RichTextBox : TextBox, IDelete {
    // TextBox's IDelete.Delete is not virtual (since explicit
    // interface implementations cannot be virtual)
    public void Delete( ) { }
}
```

This lets us use a `RichTextBox` as an `IDelete`, and calls `RichTextBox`'s version of `Delete`.

3.5.7 Interface Conversions

A class or struct *T* may be implicitly cast to an interface *I* that *T* implements. Similarly, an interface *X* may be implicitly cast to an interface *I* that *X* inherits from. An interface may be explicitly cast to any other interface or nonsealed class. However, an explicit cast from an interface *I* to a sealed class or struct *T* is permitted only if it is possible that *T* could implement *I*. For example:

```
interface IDelete {...}
interface IDesignTimeControl {...}
class TextBox : IDelete, IDesignTimeControl {...}
sealed class Timer : IDesignTimeControl {...}

TextBox tb1 = new TextBox ( );
IDelete d = tb1; // implicit cast
IDesignTimeControl dtc = (IDesignTimeControl)d;
TextBox tb2 = (TextBox)dtc;
Timer t = (Timer)d; // illegal, a Timer can never implement IDelete
```

Standard boxing conversions happen when converting between structs and interfaces.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

3.6 Enums

```
attributes? access-modifier?
new?
enum enum-name [ : integer-type ]?
{ [attributes? enum-member-name
  [ = value ]? ]* }
```

Enums specify a group of named numeric constants:

```
public enum Direction {North, East, West, South}
```

Unlike in C, enum members must be used with the enum type name. This resolves naming conflicts and makes code clearer:

```
Direction walls = Direction.East;
```

By default, enums are assigned integer constants 0, 1, 2, etc. You may optionally specify an alternative numeric type to base your enum on, and explicitly specify values for each enum member:

```
[Flags]
public enum Direction : byte {
    North=1, East=2, West=4, South=8
}
Direction walls = Direction.North | Direction.West;
if((walls & Direction.North) != 0)
    System.Console.WriteLine("Can't go north!");
```

The `[Flags]` attribute is optional, and informs the runtime that the values in the enum can be bit-combined, and should be decoded accordingly in the debugger or when outputting text to the console. For example:

```
Console.WriteLine(walls.Format( )); // Displays "North|West"
Console.WriteLine(walls); // Calls walls.ToString, displays "5"
```

The `System.Enum` type also provides many useful static methods for enums that allow one to determine the underlying type of an enum, to check if a specific value is supported, to initialize an enum from a string constant, to retrieve a list of the valid values, and other common operations such as conversions. Here is an example of the usage:

```
using System;
public enum Toggle : byte { Off=0, On=1 }
class Test {
    static void Main( ) {
        Type t = Enum.GetUnderlyingType(typeof(Toggle));
        Console.WriteLine(t); // Prints "Byte"

        bool bDimmed = Enum.IsDefined(typeof(Toggle), "Dimmed");
```

```
Console.WriteLine(bDimmed); // Prints "False"

Toggle tog =(Toggle)Enum.Parse(typeof(Toggle), "On");
Console.WriteLine(Enum.Format(typeof(Toggle), tog, "D")); // Prints "1"
Console.WriteLine(tog); // Prints "On"

object[ ] oa = Enum.GetValues(typeof(Toggle));
foreach(Toggle toggle in oa) // Prints "On=1, Off=0"
    Console.WriteLine("{0}={1}", toggle,Enum.Format(typeof(Toggle),
                                                    toggle, "D"));
    }
}
```

3.6.1 Enum Operators

The operators relevant to enums are:

```
=  =  !=  <  >  <=  >=  +  -  ^  &  |  ~
=  +=  -=  ++  --  sizeof
```

3.6.2 Enum Conversions

Enums may be explicitly converted to other enums. Enums and numeric types may be explicitly converted to one another. A special case is the numeric literal `0`, which may be implicitly converted to an enum.

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 4. Advanced C# Features

In this chapter, we cover advanced C# topics, including events, operator overloading, try statements and exceptions, attributes, unsafe code and pointers, preprocessor directives, and XML documentation.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

4.1 Delegates

```
attributes? unsafe? access-modifier?
new?
delegate
[ void | type ]
delegate-name (parameter-list);
```

A *delegate* is a type defining a method signature, so that delegate instances can hold and invoke a method or list of methods that match its signature. A delegate declaration consists of a name and a method signature. For example:

```
using System;
delegate bool Filter (string s);

class Test {
    static void Main( ) {
        Filter f = new Filter(FirstHalfOfAlphabet);
        Display(new String [ ] { "Ant", "Lion", "Yak"}, f);
    }
    static bool FirstHalfOfAlphabet(string s) {
        return "N".CompareTo(s) > 0;
    }
    static void Display(string[ ] names, Filter f) {
        int count = 0;
        foreach(string s in names)
            if(f(s)) // invoke delegate
                Console.WriteLine("Item {0} is {1}", count++, s);
    }
}
```

Note that the signature of a delegate method includes its return type. It also allows the use of a `params` modifier in its parameter list, which expands the list of elements that characterize an ordinary method signature. The actual name of the target method is irrelevant to the delegate.

4.1.1 Multicast Delegates

Delegates can hold and invoke multiple methods. In this example, we declare a very simple delegate called `MethodInvoker`, which we use to hold and then invoke the `Foo` and `Go` methods sequentially. The `+=` method creates a new delegate by adding the right delegate operand to the left delegate operand:

```
using System;
delegate void MethodInvoker( );
class Test {
```

```

static void Main( ) {
    new Test( ); // prints "Foo","Goo"
}
Test ( ) {
    MethodInvoker m = null;
    m += new MethodInvoker(Foo);
    m += new MethodInvoker(Goo);
    m( );
}
void Foo( ) {
    Console.WriteLine("Foo");
}
void Goo( ) {
    Console.WriteLine("Goo");
}
}

```

A delegate can also be removed from another delegate using the -= operator:

```

Test {
    MethodInvoker m = null;
    m += new MethodInvoker(Foo);
    m -= new MethodInvoker(Foo);
    // m is now null
}

```

Delegates are invoked in the order they are added. If a delegate has a nonvoid return type, then the value of the last delegate invoked is returned. Note that the += and -= operations on a delegate are not thread-safe. (For more information on thread safety, see [Chapter 16](#).)



To work with the .NET runtime, C# compiles += and -= operations made on a delegate to the static **Combine** and **Remove** methods of the **System.Delegate** class.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

4.2 Delegates Versus Function Pointers

A delegate is behaviorally similar to a C function pointer (or Delphi closure), but delegates can hold multiple methods, as well as hold the instance associated with each nonstatic method. In addition, delegates, like all other C# constructs used outside unsafe blocks, are type-safe and secure. This means that you're protected from pointing to the wrong type of method or to a method you don't have permission to access.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

4.3 Delegates Versus Interfaces

A problem that can be solved with a delegate can also be solved with an interface. For instance, the following explains how to solve our filter problem using an `IFilter` interface:

```

using System;
interface IFilter {
    bool Filter(string s);
}
class Test {
    class FirstHalfOfAlphabetFilter : IFilter {
        public bool Filter(string s) {
            return ("N".CompareTo(s) > 0);
        }
    }
    static void Main( ) {
        FirstHalfOfAlphabetFilter f = new FirstHalfOfAlphabetFilter( );
        Display(new string [ ] {"Ant", "Lion", "Yak"}, f);
    }
    static void Display(string[ ] names, IFilter f) {
        int count = 0;
        foreach (string s in names)
            if (f.Filter(s))
                Console.WriteLine("Item {0} is {1}", count++, s);
    }
}

```

In this case, the problem is slightly more elegantly handled with a delegate, but generally delegates are best used for event handling.

4.4 Events

Event handling is essentially a process in which one object can notify other objects that an event has occurred. This process is largely encapsulated by multicast delegates, which have this ability built in.

4.4.1 Defining a Delegate for an Event

The .NET Framework provides many event-handling delegates, but you can write your own. For example:

```
delegate void MoveEventHandler(object source, MoveEventArgs e);
```

By convention, the delegate's first parameter denotes the source of the event, and the delegate's second parameter derives from `System.EventArgs` and contains data about the event.

4.4.2 Storing Data for an Event with EventArgs

The `EventArgs` class may be derived from to include information relevant to a particular event:

```
public class MoveEventArgs : EventArgs {
    public int newPosition;
    public bool cancel;
    public MoveEventArgs(int newPosition) {
        this.newPosition = newPosition;
    }
}
```

4.4.3 Declaring and Firing an Event

A class or struct can declare an event by applying the event modifier to a delegate field. In this example, the slider class has a `Position` property that fires a `Move` event whenever its `Position` changes:

```
class Slider {
    int position;
    public event MoveEventHandler Move;
    public int Position {
        get { return position; }
        set {
            if (position != value) { // if position changed
                if (Move != null) { // if invocation list not empty
                    MoveEventArgs args = new MoveEventArgs(value);
                    Move(this, args); // fire event
                }
            }
        }
    }
}
```

```

        if (args.cancel)
            return;
    }
    position = value;
}
}
}
}

```

The `event` keyword promotes encapsulation by ensuring that only the `+=` and `-=` operations can be performed on the delegate. Other classes may act on the event, but only the `Slider` can invoke the delegate (fire the event) or clear the delegate's invocation list.

4.4.4 Acting on an Event with an Event Handler

We are able to act on an event by adding an event handler to it. An event handler is a delegate that wraps the method we want invoked when the event is fired.

In this example, we want our `Form` to act on changes made to a `Slider`'s `Position`. This is done by creating a `MoveEventHandler` delegate that wraps our event-handling method (the `slider_Move` method). This delegate is added to the `Move` event's existing list of `MoveEventHandlers` (which is initially empty). Changing the position on the slider fires the `Move` event, which invokes our `slider_Move` method:

```

using System;
class Form {
    static void Main( ) {
        Slider slider = new Slider( );
        // register with the Move event
        slider.Move += new MoveEventHandler(slider_Move);
        slider.Position = 20;
        slider.Position = 60;
    }
    static void slider_Move(object source, MoveEventArgs e) {
        if(e.NewPosition < 50)
            Console.WriteLine("OK");
        else {
            e.cancel = true;
            Console.WriteLine("Can't go that high!");
        }
    }
}

```

Typically, the `Slider` class is extended so that it fires the `Move` event whenever its `Position` is changed by a mouse movement, keypress, etc.

4.4.5 Event Accessors

attributes? unsafe? access-modifier?

```
[
  [[sealed | abstract]? override] |
  new? [virtual | static]?
]?
event delegate type event-property accessor-name
{
  attributes? add statement-block
  attributes? remove statement-block
}
```



Abstract accessors don't specify an implementation, so they replace an add/remove block with a semicolon.

Similar to the way properties provide controlled access to fields, event accessors provide controlled access to an event. Consider the following field declaration:

```
public event MoveEventHandler Move;
```

Except for the underscore prefix added to the field (to avoid a name collision), this is semantically identical to:

```
private MoveEventHandler _Move;
public event MoveEventHandler Move {
  add {
    _Move += value;
  }
  remove {
    _Move -= value;
  }
}
```

The ability to specify a custom implementation of add and remove handlers for an event allows a class to proxy an event generated by another class, thus acting as a relay for an event rather than the generator of that event. Another advantage of this technique is to eliminate the need to store a delegate as a field, which can be costly in terms of storage space. For instance, a class with 100 event fields would store 100 delegate fields, even though maybe only 4 of those events are actually assigned. Instead, you can store these delegates in a dictionary, and add and remove the delegates from that dictionary (assuming the dictionary holding 4 elements uses less storage space than 100 delegate references).



The **add** and **remove** parts of an event are compiled to **add_XXX** and **remove_XXX** methods.

4.5 Operator Overloading

C# lets you overload operators to work with operands that are custom classes or structs using operators. An operator is a static method with the keyword `operator` preceding the operator to overload (instead of a method name), parameters representing the operands, and return types representing the result of an expression. [Table 4-1](#) lists the available overloadable operators.

Table 4-1. Overloadable operators

+	-	!	~	++
--	+	-	* (binary only)	/
%	& (binary only)		^	<<
>>	= =	!=	>	<
>=	<=			

Literals that also act as overloadable operators are `true` and `false`.

4.5.1 Implementing Value Equality

A pair of references exhibit referential equality when both references point to the same object. By default, the `= =` and `!=` operators will compare two reference-type variables by reference. However, it is occasionally more natural for the `= =` and `!=` operators to exhibit value equality, whereby the comparison is based on the value of the objects that the references point to.

Whenever overloading the `= =` and `!=` operators, you should always override the virtual `Equals` method to route its functionality to the `= =` operator. This allows a class to be used polymorphically (which is essential if you want to take advantage of functionality such as the collection classes). It also provides compatibility with other .NET languages that don't overload operators.



A good guideline for knowing whether to implement the `= =` and `!=` operators is if it is natural for the class to overload other operators too, such as `<`, `>`, `+`, or `-`; otherwise, don't bother-just implement the `Equals` method. For structs, overloading the `= =` and `!=` operators provides a more efficient implementation than the default one.

```
class Note {
    int value;
    public Note(int semitonesFromA) {
        value = semitonesFromA;
    }
}
```

```

    public static bool operator == (Note x, Note y) {
        return x.value == y.value;
    }
    public static bool operator != (Note x, Note y) {
        return x.value != y.value;
    }
    public override bool Equals(object o) {
        if(!(o is Note))
            return false;
        return this == (Note)o;
    }
}
Note a = new Note(4);
Note b = new Note(4);
Object c = a;
Object d = b;

// To compare a and b by reference
Console.WriteLine((object)a == (object)b; // false

//To compare a and b by value:
Console.WriteLine(a == b); // true

//To compare c and d by reference:
Console.WriteLine(c == d); // false

//To compare c and d by value:
Console.WriteLine(c.Equals(d)); // true

```

4.5.2 Logically Paired Operators

The C# compiler enforces operators that are logical pairs to both be defined. These operators are `==`, `!=`, `<`, `>`, and `<=` `>=`.

4.5.3 Custom Implicit and Explicit Conversions

As explained in the discussion on types, the rationale behind implicit conversions is they are guaranteed to succeed and do not lose information during the conversion. Conversely, an explicit conversion is required either when runtime circumstances will determine whether the conversion will succeed or if information may be lost during the conversion. In this example, we define conversions between our musical `Note` type and a `double` (which represents the frequency in hertz of that note):

```

...
// Convert to hertz
public static implicit operator double(Note x) {
    return 440*Math.Pow(2,(double)x.value/12);
}

// Convert from hertz(only accurate to nearest semitone)

```

```
public static explicit operator Note(double x) {
    return new Note((int)(0.5+12*(Math.Log(x/440)/Math.Log(2))));
}
...

Note n =(Note)554.37; // explicit conversion
double x = n; // implicit conversion
```

4.5.4 Three-State Logic Operators

The `true` and `false` keywords are used as operators when defining types with three-state logic to enable these types to work seamlessly with constructs that take boolean expressions—namely, the `if`, `do`, `while`, `for`, and conditional (`?:`) statements. The `System.Data.SqlTypes.SqlBoolean` struct provides this functionality:

```
public struct SqlBoolean ... {
    ...
    public static bool operator true(SqlBoolean x) {
        return x.value == 1;
    }
    public static bool operator false(SqlBoolean x) {
        return x.value == -1;
    }
    public static SqlBoolean operator !(SqlBoolean x) {
        return new SqlBoolean(- x.value);
    }
    public bool IsNull {
        get { return value == 0; }
    }
    ...
}
class Test {
    void Foo(SqlBoolean a) {
        if (a)
            Console.WriteLine("True");
        else if (! a)
            Console.WriteLine("False");
        else
            Console.WriteLine("Null");
    }
}
```

4.5.5 Indirectly Overloadable Operators

The `&&` and `||` operators are automatically evaluated from `&` and `|`, so they do not need to be overloaded. The `[]` operators can be customized with indexers (see [Section 3.1.5](#) in [Chapter 3](#)). The assignment operator `=` cannot be overloaded, but all other assignment operators are automatically evaluated from their corresponding binary operators (e.g., `+=` is evaluated from `+`).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

4.6 Try Statements and Exceptions

```
try statement-block
[catch (exception type value?)?
 statement-block]+ |
finally statement-block |
[catch (exception type value?)?
 statement-block]+
finally statement-block
```

The purpose of a `try` statement is to simplify program execution in exceptional circumstances-typically, an error. A `try` statement does two things. First, it lets the `catch` block catch exceptions thrown during the `try` block's execution. Second, it ensures that execution cannot leave the `try` block without first executing the `finally` block. A `try` block must be followed by a `catch` block(s), a `finally` block, or both. The form of a `try` block looks like this:

```
try {
    ... // exception may be thrown during execution of this function
}
catch (ExceptionA ex) {
    ... // react to exception of type ExceptionA
}
catch (ExceptionB ex) {
    ... // react to exception of type ExceptionB
}
finally {
    ... // code to always run after try block executes, even if
    ... // an exception is not thrown
}
```

4.6.1 Exceptions

C# exceptions are objects that contain information representing the occurrence of an exceptional program state. When an exceptional state has occurred (e.g., a method receives an illegal value), an exception object may be thrown, and the call-stack is unwound until the exception is caught by an exception-handling block. For example:

```
using System;

namespace TryStatementsAndExceptions {
    public class WeightCalculator {
        public static float CalcBMI (float weightKilos, float metersTall) {
            if (metersTall < 0 || metersTall > 3)
                throw new ArgumentException ("Impossible Height", "metersTall");
            if (weightKilos < 0 || weightKilos > 1000)
                throw new ArgumentException ("Impossible Weight", "weightKilos");
```

```

        return weightKilos / (metersTall*metersTall);
    }
}
class Test {
    static void Main ( ) {
        TestIt ( );
    }
    static void TestIt ( ) {
        try {
            float bmi = WeightCalculator.CalcBMI (100, 5);
            Console.WriteLine(bmi);
        }
        catch(ArgumentException ex) {
            Console.WriteLine(ex);
        }
        finally {
            Console.WriteLine ("Thanks for running the program");
        }
        Console.Read( );
    }
}
}

```

In this example, calling `CalcBMI` throws an `ArgumentException` indicating that it's impossible for someone to be five meters tall. Execution leaves `CalcBMI` and returns to the calling method, `TestIt`, which handles the `ArgumentException`, and displays the exception to the Console. Next, the `finally` method is executed, which prints "Thanks for running the program" to the Console. Without our `try` statement, the call stack would have been unwound right back to the `Main` method, and the program would terminate.

4.6.2 The catch Clause

A `catch` clause specifies the exception type (including derived types) to catch. An exception must be of type `System.Exception`, or a type that derives from `System.Exception`. Catching `System.Exception` provides the widest possible net for catching errors, which is useful if your handling of the error is totally generic, such as an error-logging mechanism. Otherwise, you should catch a more specific exception type, to prevent your `catch` block from having to deal with a circumstance it wasn't designed to handle (e.g., an out-of-memory exception).

4.6.2.1 Omitting the exception variable

Specifying only an exception type without a variable name allows an exception to be caught when we don't need to use the exception instance and merely knowing its type is enough. The previous example could be written like this:

```

catch(ArgumentException) { // don't specify variable
    Console.WriteLine("Couldn't calculate ideal weight!");
}

```

4.6.2.2 Omitting the catch expression

You may also entirely omit the `catch` expression. This catches an exception of any type, even types thrown by other non-CLS-compliant languages that are not derived from `System.Exception`. The previous example could be written like this:

```
catch {
    Console.WriteLine("Couldn't calculate ideal weight!");
}
```

4.6.2.3 Specifying multiple catch clauses

When declaring multiple `catch` clauses, only the first `catch` clause with an exception type that matches the thrown exception executes its `catch` block. It is illegal for an exception type B to precede an exception type D if B is a base class of D , since it would be unreachable.

```
try {...}
catch (NullReferenceException) {...}
catch (ArgumentException) {...}
catch {...}
```

4.6.3 The finally Block

A `finally` block is always executed when control leaves the `try` block. A `finally` block is executed at any of the following periods:

- Immediately after the `try` block completes
- Immediately after the `try` block prematurely exits with a jump statement (e.g., `return`, `goto`), and immediately before the target of the jump statement
- Immediately after a `catch` block executes

`finally` blocks can add determinism to a program's execution by ensuring that the specified code always gets executed.

In our main example, if the height passed to the calculator is invalid, an `ArgumentException` is thrown that executes the `catch` block, followed by the `finally` block. However, if anything else goes wrong, the `finally` block is still executed. This ensures that we say goodbye to our user before exiting the program.

4.6.4 Key Properties of System.Exception

Notable properties of `System.Exception` include:

`StackTrace`

A string representing all the methods that are called from the origin of the exception to the `catch` block.

Message

A string with a description of the error.

InnerException

This cascading exception structure can be particularly useful when debugging. Sometimes it is useful to catch an exception, then throw a new, more specific exception. For instance, we may catch an `IOException`, and then throw a `ProblemFootingException` that contains more specific information on what went wrong. In this scenario, the `ProblemFootingException` should include the `IOException` as the `InnerException` argument in its constructor, which is assigned to the `InnerException` property.



Note that in C# all exceptions are runtime exceptions-there is no equivalent to Java's compile-time checked exceptions.

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

4.7 Attributes

```
[[target:]? attribute-name (
positional-param+ |
[named-param = expr]+ |
positional-param+, [named-param = expr]+)?]
```

Attributes are language constructs that can decorate a code element (assemblies, modules, types, members, return values, and parameters) with additional information.

In every language, you specify information associated with the types, methods, parameters, and other elements of your program. For example, a type can specify a list of interfaces it derives from, or a parameter can specify modifiers, such as the `ref` modifier in C#. The limitation of this approach is you can associate information with code elements using only the predefined constructs that the language provides.

Attributes allow programmers to extend the types of information associated with these code elements. For example, serialization in the .NET Framework uses various serialization attributes applied to types and fields to define how these code elements are serialized. This approach is more flexible than requiring the language to have special syntax for serialization.

4.7.1 Attribute Classes

An attribute is defined by a class that inherits (directly or indirectly) from the abstract class `System.Attribute`. When specifying an attribute to an element, the attribute name is the name of the type. By convention, the derived type name ends in `Attribute`, although specifying the suffix is not required when specifying the attribute.

In this example, the `Foo` class is specified as serializable using the `Serializable` attribute:

```
[Serializable]
public class Foo {...}
```

The `Serializable` attribute is actually a type declared in the `System` namespace, as follows:

```
class SerializableAttribute : Attribute {...}
```

We could also specify the `Serializable` attribute using its fully qualified type name, as follows:

```
[System.SerializableAttribute]
public class Foo {...}
```

The preceding two examples of using the `Serializable` attribute are semantically identical.

The C# language and the FCL include a number of predefined attributes. For more information about the other attributes included in the FCL and creating your own attributes, see [Chapter 14](#).

4.7.2 Named and Positional Parameters

Attributes can take parameters, which can specify additional information on the code element beyond the mere presence of the attribute.

In this example, the class `Foo` is specified as obsolete using the `Obsolete` attribute. This attribute allows parameters to be included to specify both a message and whether the compiler should treat the use of this class as an error:

```
[Obsolete("Use Bar class instead", IsError=true)]
public class Foo {...}
```

Attribute parameters fall into one of two categories: positional and named. In the preceding example, `Use Bar class instead` is a positional parameter and `IsError=true` is a named parameter.

The positional parameters for an attribute correspond to the parameters passed to the attribute type's public constructors. The named parameters for an attribute correspond to the set of public read-write or write-only instance properties and fields of the attribute type.

When specifying an attribute of an element, positional parameters are mandatory and named parameters are optional. Since the parameters used to specify an attribute are evaluated at compile time, they are generally limited to constant expressions.

4.7.3 Attribute Targets

Implicitly, the target of an attribute is the code element it immediately precedes, such as with the attributes we have covered so far. Sometimes it is necessary to explicitly specify that the attribute applies to particular target.

Here is an example of using the `CLSCompliant` attribute to specify the level of CLS compliance for an entire assembly:

```
[assembly:CLSCompliant(true)]
```

4.7.4 Specifying Multiple Attributes

Multiple attributes can be specified for a single code element. Each attribute can be listed within the same pair of square brackets (separated by a comma), in separate pairs of square brackets, or in any combination of the two.

Consequently, the following three examples are semantically identical:

```
[Serializable, Obsolete, CLSCompliant(false)]
public class Bar {...}
```

```
[Serializable]
[Obsolete]
[CLSCompliant(false)]
public class Bar {...}
```

```
[Serializable, Obsolete]  
[CLSCompliant(false)]  
public class Bar {...}
```

[\[Team LiB \]](#)

4.8 Unsafe Code and Pointers

C# supports direct memory manipulation via pointers within blocks of code marked unsafe and compiled with the `/unsafe` compiler option. Pointer types are primarily useful for interoperability with C APIs, but may also be used for accessing memory outside the managed heap or for performance-critical hotspots.

4.8.1 Pointer Basics

For every value type or pointer type T , there is a corresponding pointer type T^* . A pointer instance holds the address of a value. This is considered to be of type T , but pointer types can be (unsafely) cast to any other pointer type. [Table 4-2](#) lists the main pointer operators.

Table 4-2. Principal pointer operators

Operator	Meaning
<code>&</code>	The address-of operator returns a pointer to the address of a value.
<code>*</code>	The dereference operator returns the value at the address of a pointer.
<code>-></code>	The pointer-to-member operator is a syntactic shortcut, in which <code>x->y</code> is equivalent to <code>(*x).y</code> .

4.8.2 Unsafe Code

By marking a type, type member, or statement block with the `unsafe` keyword, you're permitted to use pointer types and perform C++ style pointer operations on memory within that scope. Here is an example of using pointers with a managed object:

```
unsafe void RedFilter(int[,] bitmap) {
    const int length = bitmap.Length;
    fixed (int* b = bitmap) {
        int* p = b;
        for(int i = 0; i < length; i++)
            *p++ &= 0xFF;
    }
}
```

Unsafe code typically runs faster than a corresponding safe implementation, which in this case would have required a nested loop with array indexing and bounds checking. An unsafe C# method may also be faster than calling an external C function, since there is no overhead associated with leaving the managed execution environment.

4.8.3 The fixed Statement

```
fixed ([value-type | void ]* name = [&]? expr )
    statement-block
```

The **fixed** statement is required to pin a managed object, such as the bitmap in the previous example. During the execution of a program, many objects are allocated and deallocated from the heap. In order to avoid unnecessary waste or fragmentation of memory, the garbage collector moves objects around. Pointing to an object is futile if its address could change while referencing it, so the **fixed** statement tells the garbage collector to "pin" the object and not move it around. This may have an impact on the efficiency of the runtime, so fixed blocks should be used only briefly, and heap allocation should be avoided within the fixed block.

C# returns a pointer only from a value type, never directly from a reference type. Syntactically, arrays and strings are an exception to this, since they actually return a pointer to their first element (which must be a value type), rather than the objects themselves.

Value types declared inline within reference types require the reference type to be pinned, as follows:

```
class Test {
    int x;
    static void Main( ) {
        Test test = new Test ( );
        unsafe {
            fixed(int* p = &test.x) { // pins test
                *p = 9;
            }
            System.Console.WriteLine(test.x);
        }
    }
}
```

4.8.4 The Pointer-to-Member Operator

In addition to the **&** and ***** operators, C# also provides the C++-style **->** operator, which can be used on structs:

```
struct Test {
    int x;
    unsafe static void Main( ) {
        Test test = new Test( );
        Test* p = &test;
        p->x = 9;
        System.Console.WriteLine(test.x);
    }
}
```

4.8.5 The stackalloc Keyword

Memory can be allocated in a block on the stack explicitly using the `stackalloc` keyword. Since it is allocated on the stack, its lifetime is limited to the execution of the method, just as with any other local variable. The block may use `[]` indexing, but is purely a value type with no additional self-describing information or bounds-checking that an array provides.

```
int* a = stackalloc int [10];
for (int i = 0; i < 10; ++i)
    Console.WriteLine(a[i]); // print raw memory
```

4.8.6 Void*

Rather than pointing to a specific value type, a pointer may make no assumptions about the type of the underlying data. This approach is useful for functions that deal with raw memory. An implicit conversion exists from any pointer type to a `void*`. A `void*` cannot be dereferenced and arithmetic operations cannot be performed on void pointers. For example:

```
class Test {
    unsafe static void Main ( ) {
        short[ ] a = {1,1,2,3,5,8,13,21,34,55};
        fixed (short* p = a) {
            // sizeof returns size of value-type in bytes
            Zap (p, a.Length * sizeof (short));
        }
        foreach (short x in a)
            System.Console.WriteLine (x); // prints all zeros
    }
    unsafe static void Zap (void* memory, int byteCount) {
        byte* b = (byte*)memory;
        for (int i = 0; i < byteCount; i++)
            *b++ = 0;
    }
}
```

4.8.7 Pointers to Unmanaged Code

Pointers are also useful for accessing data outside the managed heap (such as when interacting with C DLLs or COM), or when dealing with data not in the main memory (such as graphics memory or a storage medium on an embedded device).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

4.9 Preprocessor Directives

Preprocessor directives supply the compiler with additional information about regions of code. The most common preprocessor directives are the conditional directives, which provide a way to include or exclude regions of code from compilation. For example:

```
#define DEBUG
class MyClass {
    int x;
    void Foo( ) {
        # if DEBUG
            Console.WriteLine("Testing: x = {0}", x);
        # endif
        ...
    }
}
```

In this class, the statement in `Foo` is compiled as conditionally dependent upon the presence of the `DEBUG` symbol. If we remove the `DEBUG` symbol, the statement is not compiled. Preprocessor symbols can be defined within a source file (as we have done), and they can be passed to the compiler with the `/define:` symbol command-line option. All preprocessor symbols are implicitly true, so the `#define` statement in the previous example is effectively the same as the following:

```
#define DEBUG = true
```

The `#error` and `#warning` symbols prevent accidental misuse of conditional directives by making the compiler generate a warning or error given an undesirable set of compilation symbols. See [Table 4-3](#) for a list of preprocessor directives and their actions.

Table 4-3. Preprocessor directives

Preprocessor directive	Action
<code>#define symbol</code>	Defines <i>symbol</i> .
<code>#undef symbol</code>	Undefines <i>symbol</i> .
<code>#if symbol</code> <code>[operator symbol2]</code> <code>...</code>	<i>symbol</i> to test. <i>operators</i> are =, !=, &&, followed by <code>#else</code> , <code>#elif</code> , and <code>#endif</code> .
<code>#else</code>	Executes code to subsequent <code>#endif</code> .
<code>#elif symbol</code> <code>[operator symbol2]</code>	Combines <code>#else</code> branch and <code>#if</code> test.

Preprocessor directive	Action
#endif	Ends conditional directives.
#warning <i>text</i>	<i>text</i> of the warning to appear in compiler output.
#error <i>text</i>	<i>text</i> of the error to appear in compiler output.
#line [<i>number</i> [" <i>file</i> "] hidden]	<i>number</i> specifies the line in source code; <i>file</i> is the filename to appear in computer output; <i>hidden</i> specifies that the compiler should generate debugger information (this feature was added in Visual C# 2003).
#region <i>name</i>	Marks the beginning of outline.
#end <i>region</i>	Ends an outline region.

[\[Team LiB \]](#)

4.10 XML Documentation

C# offers three different styles of source-code documentation: single-line comments, multiline comments, and documentation comments.

4.10.1 C/C++-Style Comments

Single- and multiline comments use the C++ syntax, `//` and `/*...*/`:

```
int x = 3; // this is a comment
MyMethod( ); /* this is a
comment that spans two lines */
```

The disadvantage of this style of commenting is that there is no predetermined standard for documenting types. Consequently, it cannot be easily parsed to automate the production of documentation. C# improves on this by allowing you to embed documentation comments in the source, and by providing an automated mechanism for extracting and validating documentation at compile time.

4.10.2 Documentation Comments

Documentation comments are composed of embedded XML tags. These tags allow one to mark up the descriptive text to better define the semantics of the type or member, and also to incorporate cross-references. Documentation comments must either start with `///` (that's *three* slashes), or (as of Visual C# 2003) be contained in multiline comments (that's `/* ... */`). They can be applied to any user-defined type or member.

These comments can then be extracted at compile time into a separate output file containing the documentation. The compiler validates the comments for internal consistency, expands cross-references into fully qualified type IDs, and outputs a well-formed XML file. Further processing is left up to you, although a common next step is to run the XML through XSLT, generating HTML documentation.

Here is an example of documentation comments for a very simple type:

```
// Filename: DocTest.cs
using System;
class MyClass {
    /// <summary>
    /// The Foo method is called from
    /// <see cref="Main">Main</see>
    /// </summary>
    /// <mytag>Secret stuff</mytag>
    /// <param name="s">Description for s</param>
```



```
static void Foo(string s) { Console.WriteLine(s); }
static void Main( ) { Foo("42"); }
}
```

4.10.3 XML Documentation Files

When run through the compiler using the `/doc:<filename>` command-line option, the following XML file is generated:

```
<?xml version="1.0"?>
<doc>
  <assembly>
    <name>DocTest</name>
  </assembly>
  <members>
    <member name="M:MyClass.Foo(System.String)">
      <summary>
        The Foo method is called from
        <see cref="M:MyClass.Main">Main</see>
      </summary>
      <mytag>Secret stuff</mytag>
      <param name="s">Description for s</param>
    </member>
  </members>
</doc>
```

The `<?xml...>`, `<doc>`, and `<members>` tags are generated automatically and form the skeleton for the XML file. The `<assembly>` and `<name>` tags indicate the assembly this type lives in. Every member that was preceded by a documentation comment is included in the XML file via a `<member>` tag with a `name` attribute that identifies the member. Note that the `cref` attribute in the `<see>` tag has also been expanded to refer to a fully qualified type and member. The predefined XML documentation tags that were embedded in the documentation comments are also included in the XML file, and have been validated to ensure that all parameters are documented, that the names are accurate, and that any cross-references to other types or members can be resolved. Finally, any additional user-defined tags are transferred verbatim.

4.10.4 Predefined XML Tags

The predefined set of XML tags that can be used to mark up the descriptive text are listed here:

```
<summary>
```

```
<summary>description</summary>
```

This tag describes a type or member. Typically, `<summary>` contains the description of a member at a fairly high level.

```
<remarks>
```

```
<remarks>description</remarks>
```

This tag provides additional information regarding a particular member. Information about side effects within the method, or particular behavior that may not otherwise be intuitive (such as the idea that this method may throw an `ArrayOutOfBoundsException` if a parameter is greater than 5) is listed here.

```
<param>
```

```
<param name="name">description</param>
```

This tag describes a parameter on a method. The `name` attribute is mandatory, and must refer to a parameter on the method. If this tag is applied to any parameter on a method, all of the parameters on that method must be documented. Enclose `name` in double quotation marks ("").

```
<returns>
```

```
<returns>description</returns>
```

This tag describes the return values for a method.

```
<exception>
```

```
<exception [cref="type"]>description</exception>
```

This tag documents the exceptions a method may throw. If present, the optional `cref` attribute should refer to the type of the exception. The type name must be enclosed in double quotation marks ("").

```
<permission>
```

```
<permission [cref="type"]>description</permission>
```

This tag documents the permissions requirement for a type or member. If present, the optional `cref` attribute should refer to the type that represents the permission set required by the member, although the compiler does not validate this. The type name must be enclosed in double quotation marks ("").

```
<example>
```

```
<example>description</example>
```

This tag provides a description and sample source code explaining the use of a type or member. Typically, the `<example>` tag provides the description and contains the `<c>` and `<code>` tags, although they can also be used independently.

```
<c>
```

```
<c>code</c>
```

This tag indicates an inline code snippet. Typically, this tag is used inside an `<example>` block (described previously).

```
<code>
```

`<code>code</code>`

This tag is used to indicate multiline code snippets. Again, this is typically used inside of an `<example>` block (described previously).

`<see>`

`<see cref="member">text</see>`

This tag identifies cross-references in the documentation to other types or members. Typically, the `<see>` tag is used inline within a description (as opposed to the `<seealso>` tag, which is broken out into a separate "See Also" section). This tag is useful because it allows tools to generate cross-references, indexes, and hyperlinked views of the documentation. Member names must be enclosed by double quotation marks ("").

`<seealso>`

`<seealso cref="member">text</seealso>`

This tag identifies cross-references in the documentation to other types or members. Typically, `<seealso>` tags are broken out into a separate "See Also" section. This tag is useful because it allows tools to generate cross-references, indexes, and hyperlinked views of the documentation. Member names must be enclosed by double quotation marks ("").

`<value>`

`<value>description</value>`

This tag describes a property on a class.

`<paramref>`

`<paramref name="name" />`

This tag identifies the use of a parameter name within descriptive text, such as `<remarks>`. The name must be enclosed by double quotation marks ("").

`<list>`

```
<list type=[ bullet | number | table ]>
  <listheader>
    <term>name</term>
    <description>description</description>
  </listheader>
  <item>
    <term>name</term>
    <description>description</description>
  </item>
</list>
```

This tag provides hints to documentation generators about how to format the documentation-in this case, as a list of items.

```
<para>
```

```
<para>text</para>
```

This tag sets off the text as a paragraph to documentation generators.

```
<include>
```

```
<include file='filename' path='path-to-element'>
```

This tag specifies an external file that contains documentation and an XPath path to a specific element in that file. For example, a path of `docs[@id="001"]/*` retrieves whatever is inside of `<docs id="001"/>`. The `filename` and `path` must be enclosed by single quotation marks ('), but you must use double quotation marks (") for the `id` attribute within the `path-to-element` expression.

4.10.5 User-Defined Tags

There is little that is special about the predefined XML tags recognized by the C# compiler, and you are free to define your own. The only special processing done by the compiler is on the `<param>` tag (in which it verifies the parameter name and that all the parameters on the method are documented) and the `cref` attribute (in which it verifies that the attribute refers to a real type or member, and expands it to a fully qualified type or member ID). The `cref` attribute can also be used in your own tags, and is verified and expanded just as it is in the predefined `<exception>`, `<permission>`, `<see>`, and `<seealso>` tags.

4.10.6 Generated Documentation

Once an XML file is generated from documentation comments, it typically requires another step before becoming generally useful to programmers, since most of us aren't quite able to parse and use an XML file "in the raw."

The most common approach is to run the XML output through an XSLT stylesheet to generate some more human-friendly format, such as HTML. (Variations on this idea include generating PDF, RTF, or even Microsoft Word documents.) While Microsoft may publish a standardized XSLT file for this, companies may want to create their own to establish their own "look" for documentation of components they sell. Alternatively, several open source projects have already begun to explore this area, and produce neatly formatted documentation files; one example is <http://ndoc.sourceforge.net>.

The ability to put user-defined tags into the XML documentation sections represents a powerful extensibility point—for example, a company may put implementation details about the method or class inside of `<implementation>` tags and define two XSLT files: one excluding the implementation tags, and the other including it. The non-`<implementation>`-aware files can be distributed publicly, while the `<implementation>`-aware files are used internally by developers. An automated test tool might run tests against those methods or classes described by a `<test name=test-to-run>` tag. Types meant to be stored in the database might use XML documentation tags to indicate the SQL required to create the tables, and a custom tool could be written to extract the necessary SQL from the XML documentation files in order to run it. Non-public information about the code can be

embedded within the code itself or in the documentation comments and processed by an external tool via this mechanism, which makes it quite powerful.

4.10.7 Type or Member Cross-References

Type names and type or member cross-references are translated into IDs that uniquely define the type or member. These names are composed of a prefix that defines what the ID represents and a signature of the type or member.

[Table 4-4](#) lists the set of type or member prefixes.

Table 4-4. XML type ID prefixes

XML type prefix	ID prefixes applied to
N	Namespace
T	Type (class, struct, enum, interface, delegate)
F	Field
P	Property (includes indexers)
M	Method (includes special methods)
E	Event
!	Error

The rules describing how the signatures are generated are well documented, although fairly complex.

Here is an example of a type and the IDs that are generated:

```
// Namespaces do not have independent signatures
namespace NS {
    /// T:NS.MyClass
    class MyClass {
        /// F:NS.MyClass.aField
        string aField;
        /// P:NS.MyClass.aProperty
        short aProperty {get {...} set {...}}
        /// T:NS.MyClass.NestedType
        class NestedType {...};
        /// M:NS.MyClass.X( )
        void X( ) {...}
        /// M:NS.MyClass.Y(System.Int32,System.Double@,System.Decimal@)
        void Y(int p1, ref double p2, out decimal p3) {...}
        /// M:NS.MyClass.Z(System.Char[ ],System.Single[0:,0:])
        void Z(char[ ] l1, float[, ] p2) {...}
        /// M:NS.MyClass.op_Addition(NS.MyClass,NS.MyClass)
```

```
        public static MyClass operator+(MyClass c1, MyClass c2) {...}
        /// M:NS.MyClass.op_Implicit(NS.MyClass)~System.Int32
        public static implicit operator int(MyClass c) {...}
        /// M:NS.MyClass.#ctor
        MyClass( ) {...}
        /// M:NS.MyClass.Finalize
        ~MyClass( ) {...}
        /// M:NS.MyClass.#cctor
        static MyClass( ) {...}
    }

}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Part II: Programming with the .NET Framework

Part II contains:

[Chapter 5](#)

[Chapter 6](#)

[Chapter 7](#)

[Chapter 8](#)

[Chapter 9](#)

[Chapter 10](#)

[Chapter 11](#)

[Chapter 12](#)

[Chapter 13](#)

[Chapter 14](#)

[Chapter 15](#)

[Chapter 16](#)

[Chapter 17](#)

[Chapter 18](#)

[Chapter 19](#)

[Chapter 20](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 5. Framework Class Library Overview

Almost all the capabilities of the .NET Framework are exposed via a set of managed types known as the Framework Class Library (FCL). Because these types are CLS-compliant, they are accessible from almost any .NET language. FCL types are grouped logically by namespace and are packaged in a set of assemblies that are part of the .NET platform. Using these types in a C# application requires you to reference the appropriate assembly when compiling (most essential assemblies are referenced by default; see [Appendix E](#)). In order to work effectively in C# on the .NET platform, it is important to understand the general capabilities in the predefined class library. However, the library is far too large to cover completely in this book, as it encompasses 3,744 types grouped into 124 namespaces and packaged in 34 different assemblies.

Instead, in this chapter, we give an overview of the entire FCL (broken down by logical area) and provide references to relevant types and namespaces so that you can explore their details in the .NET Framework SDK on your own.

The specific types and namespaces mentioned in this overview are based on the 1.1 version of the .NET Framework.

Useful tools for exploring the FCL include the .NET Framework SDK documentation, the Visual Studio .NET documentation, the *WinCV.exe* class browser, and the *ILDasm.exe* disassembler (see [Chapter 23](#)).

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.1 Core Types

The core types are contained in the `System` namespace. This namespace is the heart of the FCL and contains classes, interfaces, and attributes that all other types depend on. The root of the FCL is the type `Object`, from which all other .NET types derive. Other fundamental types are `ValueType` (the base type for structs), `Enum` (the base type for enums), `Convert` (used to convert between base types), `Exception` (the base type for all exceptions), and the boxed versions of the predefined value types. Interfaces that are used throughout the FCL, such as `ICloneable`, `IComparable`, `IFormattable`, and `IConvertible`, are also defined here. Extended types such as `DateTime`, `TimeSpan`, and `DBNull` are available as well. Other classes include support for delegates (see [Section 4.1](#) in [Chapter 4](#)), basic math operations, custom attributes (see [Section 4.7](#) in [Chapter 4](#) and [Chapter 14](#)), and exception handling (see [Section 4.6](#) in [Chapter 4](#)).

For more information, see the `System` namespace.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.2 Text

The FCL provides rich support for text. Important types include the `System.String` class for handling immutable strings, a `StringBuilder` class that provides string-handling operations with support for locale-aware comparison operations and multiple string encoding formats (ASCII, Unicode, UTF-7, and UTF-8), as well as a set of classes that provide regular expression support (see [Chapter 6](#)).

For more information, see the following namespaces:

`System.Text`
`System.Text.RegularExpressions`

An important related type in another namespace is `System.String`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.3 Collections

The FCL provides a set of general-purpose data structures such as `System.Array`, `ArrayList`, `Hashtable`, `Queue`, `Stack`, `BitArray`, and more. Standardized design patterns using common base types and public interfaces allow consistent handling of collections throughout the FCL for both predefined and user-defined collection types (see [Chapter 7](#)).

For more information, see the following namespaces:

`System.Collections`
`System.Collections.Specialized`

An important related type in another namespace is `System.Array`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.4 Streams and I/O

The FCL provides good support for accessing the standard input, output, and error streams. Classes are also provided for performing binary and text file I/O, registering for notification of filesystem events, and for accessing a secure user-specific storage area known as Isolated Storage (see [Chapter 10](#)).

For more information, see the following namespaces:

`System.IO`
`System.IO.IsolatedStorage`

An important related type in another namespace is `System.Console`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.5 Networking

The FCL provides a layered set of classes for communicating over the network using different levels of abstraction, including raw socket access; TCP, UDP, and HTTP protocol support; a high-level request/response mechanism based on URIs and streams; and pluggable protocol handlers (see [Chapter 9](#)).

For more information, see the following namespaces:

`System.Net`
`System.Net.Sockets`

An important related type in another namespace is `System.IO.Stream`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.6 Threading

The FCL provides rich support for building multithreaded applications, including thread and thread-pool management, thread-synchronization mechanisms, such as monitors, mutexes, events, reader/writer locks, etc., and access to such underlying platform features as I/O completion ports and system timers (see [Chapter 16](#)).

For more information, see the following namespaces:

`System.Threading`
`System.Timers`

Important related types in other namespaces include `System.Thread` and `System.ThreadStaticAttribute`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

5.7 Security

The FCL provides classes for manipulating all elements of the .NET Framework's Code Access Security model, including security policies, security principals, permission sets, and evidence. These classes also support cryptographic algorithms such as DES, 3DES, RC2, RSA, DSig, MD5, SHA1, and Base64 encoding for stream transformations.

For more information, see the following namespaces:

```
System.Security  
System.Security.Cryptography  
System.Security.Cryptography.X509Certificates  
System.Security.Cryptography.Xml  
System.Security.Permissions  
System.Security.Policy  
System.Security.Principal
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.8 Reflection and Metadata

The .NET runtime depends heavily on the existence of metadata and the ability to inspect and manipulate it dynamically. The FCL exposes this via a set of abstract classes that mirror the significant elements of an application (assemblies, modules, types, and members) and provide support for creating instances of FCL types and new types on the fly (see [Chapter 13](#)).

For more information, see the following namespaces:

`System.Reflection`
`System.Reflection.Emit`

Important related types in other namespaces include `System.Type`, `System.Activator`, and `System.AppDomain`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.9 Assemblies

The FCL provides attributes that tag the metadata on an assembly with information such as target OS and processor, assembly version, and other information. The FCL also provides classes to manipulate assemblies, modules, and assembly strong names (see [Chapter 12](#)).

For more information, see the following namespace:

`System.Reflection`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.10 Serialization

The FCL includes support for serializing arbitrary object graphs to and from a stream. This serialization can store and transmit complex data structures via files or the network. The default serializers provide binary and XML-based formatting but can be extended with user-defined formatters.

For more information, see the following namespaces:

`System.Runtime.Serialization`
`System.Runtime.Serialization.Formatters`
`System.Runtime.Serialization.Formatters.Binary`
`System.Runtime.Serialization.Formatters.Soap`

Important related types in other namespaces include `System.NonSerializedAttribute` and `System.SerializableAttribute`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

5.11 Remoting

Remoting is the cornerstone of a distributed application, and the FCL provides excellent support for making and receiving remote method calls. Calls may be synchronous or asynchronous, support request/response or one-way modes, delivered over multiple transports (TCP, HTTP, and SMTP), and serialized in multiple formats (SOAP and binary). The remoting infrastructure supports multiple activation models, lease-based object lifetimes, distributed object identity, object marshaling by reference and by value, and message interception. These types can be extended with user-defined channels, serializers, proxies, and call context.

For more information, see the following namespaces:

```
System.Runtime.Remoting
System.Runtime.Remoting.Activation
System.Runtime.Remoting.Channels
System.Runtime.Remoting.Channels.Http
System.Runtime.Remoting.Channels.Tcp
System.Runtime.Remoting.Contexts
System.Runtime.Remoting.Lifetime
System.Runtime.Remoting.Messaging
System.Runtime.Remoting.Metadata
System.Runtime.Remoting.MetadataServices
System.Runtime.Remoting.Proxies
System.Runtime.Remoting.Services
```

Important related types in other namespaces include:

```
System.AppDomain
System.ContextBoundObject
System.ContextStaticAttribute
System.MarshalByRefObject
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.12 Web Services

Logically, web services are simply another form of remoting. In reality, the FCL support for web services is considered part of ASP.NET and is entirely separate from the CLR remoting infrastructure. Classes and attributes exist for describing and publishing web services, discovering what web services are exposed at a particular endpoint (URI), and invoking a web service method.

For more information, see the following namespaces:

System.Web.Services
System.Web.Services.Configuration
System.Web.Services.Description
System.Web.Services.Discovery
System.Web.Services.Protocols

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

5.13 Data Access

The FCL includes a set of classes that access data sources and manage complex data sets. Known as ADO.NET, these classes are the managed replacement for ADO under Win32. ADO.NET supports both connected and disconnected operations, multiple data providers (including nonrelational data sources), and serialization to and from XML.

For more information, see the following namespaces:

```
System.Data  
System.Data.Common  
System.Data.Odbc (.NET 1.1)  
System.Data.OleDb  
System.Data.OracleClient (.NET 1.1)  
System.Data.SqlClient  
System.Data.SqlTypes
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

5.14 XML

The FCL provides broad support for XML 1.0, XML schemas, XML namespaces with two separate XML parsing models (a DOM2-based model and a pull-mode variant of SAX2), and implementations of XSLT, XPath, and SOAP 1.1.

For more information, see the following namespaces:

System.Xml
System.Xml.Schema
System.Xml.Serialization
System.Xml.XPath
System.Xml.Xsl

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.15 Graphics

The FCL includes classes to support working with graphic images. Known as GDI+, these classes are the managed equivalent of GDI under Win32, and include support for brushes, fonts, bitmaps, text rendering, drawing primitives, image conversions, and print-preview capabilities.

For more information, see the following namespaces:

System.Drawing
System.Drawing.Design
System.Drawing.Drawing2D
System.Drawing.Imaging
System.Drawing.Printing
System.Drawing.Text

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.16 Rich Client Applications

The FCL includes support for creating classic GUI applications. This support is known as Windows Forms, and consists of a forms package, a predefined set of GUI components, and a component model suited to RAD designer tools. These classes provide varying degrees of abstraction from low-level message-loop handler classes to high-level layout managers and visual inheritance.

For more information, see the following namespaces:

`System.Windows.Forms`
`System.Windows.Forms.Design`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

5.17 Web-Based Applications

The FCL includes support for creating web-based applications. This support is known as Web Forms, and consists of a server-side forms package that generates browser-specific UI (e.g. HTML, DHTML, WAP for Mobile devices, etc.), a predefined set of HTML-based GUI widgets, and a component model suited to RAD designer tools. The FCL also includes a set of classes that manage session state, security, caching, debugging, tracing, localization, configuration, and deployment for web-based applications. Finally, the FCL includes the classes and attributes that produce and consume web services, which are described previously in this chapter in the "Web Services" section. Collectively, these capabilities are known as ASP.NET and are a complete replacement for ASP under Win32.

For more information, see the following namespaces:

```
System.Web
System.Web.Caching
System.Web.Configuration
System.Web.Hosting
System.Web.Mail
System.Web.Mobile (.NET 1.1)
System.Web.Security
System.Web.SessionState
System.Web.UI
System.Web.UI.Design
System.Web.UI.Design.WebControls
System.Web.UI.HtmlControls
System.Web.UI.MobileControls (.NET 1.1)
System.Web.UI.MobileControls.Adapters (.NET 1.1)
System.Web.UI.WebControls
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.18 Globalization

The FCL provides classes that aid globalization by supporting code-page conversions, locale-aware string operations, date/time conversions, and the use of resource files to centralize localization work.

For more information, see the following namespaces:

`System.Globalization`
`System.Resources`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.19 Configuration

The FCL provides access to the .NET configuration system, which includes a per-user and per-application configuration model with inheritance of configuration settings, and a transacted installer framework. Classes exist both to use the configuration framework and to extend it.

For more information, see the following namespaces:

System.Configuration
System.Configuration.Assemblies
System.Configuration.Install

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.20 Advanced Component Services

The FCL provides support for building on the COM+ services such as distributed transactions, JIT activation, object pooling, queuing, and events. The FCL also includes types that provide access to reliable, asynchronous, one-way messaging via an existing Message Queue infrastructure (MSMQ), in addition to classes that provide access to existing directory services (Active Directory).

For more information, see the following namespaces:

`System.EnterpriseServices`
`System.EnterpriseServices.CompensatingResourceManager`
`System.DirectoryServices`
`System.Messaging`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.21 Diagnostics and Debugging

The FCL includes classes that provide debug tracing with multilistener support, access to the event log, access to process, thread, and stack frame information, and the ability to create and consume performance counters (see [Chapter 19](#)).

For more information, see the following namespaces:

```
System.Diagnostics
System.Diagnostics.SymbolStore
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.22 Interoperating with Unmanaged Code

The .NET runtime supports bidirectional interop with unmanaged code via COM, COM+ , and native Win32 API calls. The FCL provides a set of classes and attributes that support this, including precise control of managed object lifetime, and the option of creating user-defined custommarshallers to handle specific interop situations (see [Chapter 17](#) and [Chapter 18](#)).

For more information, see the following namespaces:

`System.Runtime.InteropServices`
`System.Runtime.InteropServices.CustomMarshalers`
`System.Runtime.InteropServices.Expando`

An important related type in another namespace is `System.Buffer`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

5.23 Compiler and Tool Support

In the .NET runtime, components are distinguished from classes by the presence of additional metadata and other apparatus that facilitates the use of the component forms packages such as Windows Forms and Web Forms. The FCL provides classes and attributes that support both the creation of components and the creation of tools that consume components. These classes also include the ability to generate and compile C#, JScript, and VB.NET source code.

For more information, see the following namespaces:

```
Microsoft.CSharp
Microsoft.JScript
Microsoft.VisualBasic
Microsoft.Vsa
System.CodeDom
System.CodeDom.Compiler
System.ComponentModel
System.ComponentModel.Design
System.ComponentModel.Design.Serialization
System.Runtime.CompilerServices
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.24 Runtime Facilities

The FCL provides classes that can control runtime behavior. The canonical examples are the classes that control the garbage collector and those that provide strong and weak reference support.

For more information, see the following namespace:

`System`

An important related type in another namespace is `System.Runtime.InteropServices.GCHandle`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.25 Native OS Facilities

The FCL provides support for controlling existing NT services and creating new ones. It also provides access to certain native Win32 facilities such as the Windows registry and the Windows Management Instrumentation (WMI).

For more information, see the following namespaces:

Microsoft.Win32
System.Management
System.Management.Instrumentation
System.ServiceProcess

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

5.26 Undocumented Types

The assemblies that make up the .NET Framework also export many types and namespaces that are not documented. These types and namespaces generally represent either implementation details that are subject to change, vestigial code from earlier betas, or tool-specific code that happens to be managed and is therefore subject to examination via reflection. Regardless of the reason, one cannot count on undocumented types, nor expect any support from Microsoft.

That said, there is useful information to be gained from investigating these private implementation details. Examples of this include programmatic access to the GAC, predefined Win32 structures and COM interfaces (internals of *SoapSuds.exe*, *RegAsm.exe*, *TlbImp.exe*, and *TlbExp.exe*), and browser, tool, and OS integration helpers.

Many of the documented namespaces include additional undocumented types. Additionally, the following namespaces are completely undocumented:

```
Accessibility
IEHost.Execute
Microsoft.CLRAdmin
Microsoft.IE
Microsoft.JScript.Vsa
Microsoft.VisualBasic.CompilerServices
Microsoft.VisualBasic.Helpers
Microsoft.VisualBasic.Vsa
Microsoft.VisualBasic
Microsoft.Vsa.Vb.CodeDOM
Microsoft_VsaVb
RegCode
SoapSudsCode
System.Diagnostics.Design
System.EnterpriseServices.Internal
System.Messaging.Design
System.ServiceProcess.Design
System.Web.Handlers
System.Web.RegularExpressions
System.Web.Util
System.Windows.Forms.ComponentModel.Com2Interop
System.Windows.Forms.PropertyGridInternal
TlbExpCode
TlbImpCode
```

To investigate these types and namespaces, use *ILDasm.exe* to examine the metadata and MSIL (see [Appendix E](#) to match DLLs with their namespaces).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 6. String Handling

C# offers a wide range of string-handling features. Support is provided for both mutable and immutable strings, extensible string formatting, locale-aware string comparisons, and multiple string encoding systems. The string handling support also includes regular expression matching and replacement capabilities based on Perl 5 regular expressions, including lazy quantifiers (`??`, `*?`, `+?`, `{n,m}?`), positive and negative look-ahead, and conditional evaluation.

This chapter introduces and demonstrates the most common types you'll use in working with strings. The types mentioned in this section all exist in the `System`, `System.Text`, or `System.Text.RegularExpressions` namespaces (unless otherwise stated).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

6.1 String Class

A C# `string` represents an immutable sequence of characters, and aliases the `System.String` class. Strings have comparison, appending, inserting, conversion, copying, formatting, indexing, joining, splitting, padding, trimming, removing, replacing, and searching methods. The compiler converts addition (+) operations on operands, in which the left operand is a string to `Concat()` methods (assuming it can't fold the concatenation together directly at compile time), and also preevaluates and interns string constants where possible (see [Chapter 6](#) later in this chapter).

6.1.1 Comparing Strings

Although `System.String` is a reference type, the `==` operator is overloaded, so you can easily compare two strings by value, as follows:

```
string a = "abracadabra";
string b = "abracadabra";
Console.WriteLine(a == b); // Prints "True"
```

6.1.2 Immutability of Strings

Strings are *immutable*, which means they can't be modified after creation. Consequently, many of the methods that initially appear to modify a string actually create a new string:

```
string a = "Heat";
string b = a.Insert(3, "r")
Console.WriteLine(b); // Prints Heart
```

If you need a mutable string, see the `StringBuilder` class, discussed later in this chapter.

6.1.3 String Interning

In addition, the immutability of strings enables all strings in an application to be *interned*. Interning is the process in which all the constant strings in an application are stored in a common place and any duplicate strings are eliminated. This saves space at runtime but creates the possibility that multiple string references will point to the same location in memory. This can be the source of unexpected results when comparing two constant strings, as follows:

```
string a = "hello";
string b = "hello";
Console.WriteLine(a == b); // True for String only
Console.WriteLine(a.Equals(b)); // True for all objects
Console.WriteLine((object)a == (object)b); // True!!
```

6.1.4 Formatting Strings

The `Format()` method provides a convenient way to build strings that make use of embedded parameters. Parameters in such strings can be of any type, including both predefined and user-defined types.

The `String.Format()` method takes *a format-specification string*, followed by a variable number of parameters. The format-specification string defines the template for the string; the position and format of each parameter within the string is specified by a *format specifier* for each of its parameters.

The syntax of a format specifier looks like this:

```
{ParamIndex[,MinWidth][:FormatString]}
```

It has the following parameters:

ParamIndex

This is the zero-based index of the parameter to be formatted. This number specifies a position in the parameter list that follows the format-specification string.

MinWidth

This is the minimum number of characters required for the string representation of the parameter, to be padded by spaces if necessary (a negative number is left-justified, a positive number is right-justified). If not specified, the string representation consumes the minimum number of characters possible.

FormatString

This is passed to the `ToString()` method on `IFormattable` to construct the string if the parameter represents an object that implements `IFormattable`. If not, the `ToString()` method on `System.Object` is used to construct the string.



All of the common types (`int`, `string`, `DateTime`, etc.) implement `IFormattable`. A table of the numeric and picture format specifiers supported by the common predefined types is provided in [Appendix B](#).

In the following example, we embed string specifiers for the integer account variable `i` (parameter 0 in the parameter list), and the decimal cash variable `m` (parameter 1 in the parameter list, with `C` = currency) in the format-specification string:

```
Account {0} has {1:C}
```

The parameters themselves are listed immediately following the string template:

```
using System;
class TestFormatting {
    static void Main( ) {
        int i = 2;
        decimal m = 42.73m;
        string s = String.Format("Account {0} has {1:C}.", i, m);
```

```

        Console.WriteLine(s); // Prints "Account 2 has $42.73"
    }
}

```

6.1.5 Indexing Strings

Consistent with all other indexing in the CLR, the characters in a string are accessed with a zero-based index:

```

using System;
class TestIndexing {
    static void Main( ) {
        string s = "Going down?";
        for (int i=0; i<s.Length; i++)
            Console.WriteLine(s[i]); // Prints s vertically
    }
}

```

6.1.6 Encoding Strings

Strings can be converted between different character encodings using the `Encoding` type. The `Encoding` type can't be created directly, but the `ASCII`, `Unicode`, `UTF7`, `UTF8`, and `BigEndianUnicode` static properties on the `Encoding` type return correctly constructed instances.

Here is an example that converts an array of bytes into a `string` using the ASCII encoding:

```

using System;
using System.Text;
class TestEncoding {
    static void Main( ) {
        byte[ ] ba = new byte[ ] { 67, 35, 32, 105, 115,
                                    32, 67, 79, 79, 76, 33 };
        string s = Encoding.ASCII.GetString(ba);
        Console.WriteLine(s);
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

6.2 StringBuilder Class

The `StringBuilder` class represents mutable strings. It starts at a predefined size (16 characters, by default) and grows dynamically as more characters are added. It can grow either unbounded or up to a configurable maximum. For example:

```
using System;
using System.Text;
class TestStringBuilder {
    static void Main( ) {
        StringBuilder sb = new StringBuilder("Hello, ");
        sb.Append("World");
        sb[11] = '!';
        Console.WriteLine(sb); // Hello, World!
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

6.3 Regular Expression Support

Regular expressions have been used in various programming languages and tools for many years. The FCL includes a set of classes for utilizing the power of regular expressions that are designed to be compatible with Perl 5 regular expressions. In addition, the regular expression classes implement some additional functionality, such as named capture groups, right-to-left pattern matching, and expression compilation.

Regular expression knowledge seems to be one of those topics that most programmers have learned and then forgotten more than once. For the purposes of this chapter, we presume some previous use and experience with regular expressions within Perl 5. The .NET regex classes are a superset of Perl 5 functionality, so this will serve as a good conceptual starting point.

For readers new to regular expressions, we suggest starting with some basic Perl 5 introductions. The perl.com site has some great resource materials and introductory tutorials. In addition, the definitive work on regular expressions is *Mastering Regular Expressions*, by Jeffrey E. F. Friedl (O'Reilly & Associates). For those who want to get the most out of working with regular expressions, this book is highly recommended.

6.3.1 The Regex Class

The `Regex` class is the heart of the BCL regular expression support. Used both as an object instance and as a static type, the `Regex` class represents an immutable, compiled instance of a regular expression that can be applied to a string via a matching process.

Internally, the regular expression is stored as either a sequence of internal regular expression bytecodes that are interpreted at match time or as compiled MSIL opcodes that are JIT-compiled by the CLR at runtime. This allows you to make a trade-off between a worsened regular expression startup time and memory utilization versus higher raw match performance at runtime.

The `Regex` class contains several static methods:

Method	Purpose
<code>Escape()</code>	Ignores regex metacharacters within a string
<code>IsMatch()</code>	Methods that return a bool result if the supplied regular expression matches within the string
<code>Match()</code>	Methods that return a Match instance
<code>Matches()</code>	Methods that return a list of Match instances as a collection
<code>Replace()</code>	Methods that replace the matched regular expressions with replacement strings
<code>Split()</code>	Methods that return an array of strings determined by the expression

Method	Purpose
<code>Unescape ()</code>	Unescapes any escaped characters within a string

For more information on the regular-expression options, supported character escapes, substitution patterns, character sets, positioning assertions, quantifiers, grouping constructs, backreferences, and alternation, see [Appendix A](#).

6.3.2 The Match and MatchCollection Classes

The `Match` class represents the result of applying a regular expression to a string, looking for the first successful match. The `MatchCollection` class contains a collection of `Match` instances that represent the result of applying a regular expression to a string recursively until the first unsuccessful match occurs.

6.3.3 The Group Class

The `Group` class represents the results from a single grouping expression. From this class, it is possible to drill down to the individual subexpression matches with the `Captures` property.

6.3.4 The Capture and Capture Collection Classes

The `CaptureCollection` class contains a collection of `Capture` instances, each representing the results of a single subexpression match.

[\[Team LiB \]](#)

6.4 Regular Expression Basics

Let's start with simple expressions using the `Regex` and the `Match` classes.

```
Match m = Regex.Match("abracadabra", "(a|b|r)+");
```

This results in an instance of the `Match` class that can be tested for success without examining the contents of the matched string, as follows:

```
if (m.Success) {
    ...
}
```

To use the matched substring, simply convert it to a string:

```
Console.WriteLine("Match="+m.ToString());
```

The output of this example is the portion of the string that has been successfully matched, as follows:

```
Match=abra
```

Simple string replacements are also very straightforward. For example, consider the following statement:

```
string s = Regex.Replace("abracadabra", "abra", "zzzz");
```

This returns the string `zzzzcadzzzz`, in which all occurrences of the matching pattern are replaced by the replacement string `zzzzz`.

Now let's look at a more complex expression:

```
string s = Regex.Replace(" abra ", @"^\s*(.*?)\s*$", "$1");
```

This returns the string `abra`, with preceding and trailing spaces removed. This pattern is generally useful for removing leading and trailing spaces from any string. We could also have used the literal string quote construct in C#. Within a literal string, the compiler does not process the backslash character (`\`) as an escape character. Consequently, the `@"..."` is very useful when working with regular expressions, and when you are specifying escaped metacharacters with a `\`. Also of note is the use of `$1` as the replacement string. The replacement string can contain only substitutions, which are references to capture groups in the regular expression.

Now let's try a slightly more complex sample by doing a walk-through of a grouping structure. For example:

```
string text = "abracadabralabracadabra2abracadabra3";
string pat = @"
    (          # start the first group
    abra# match the literal 'abra'
    (# start the second (inner) group
```

```

        cad# match the literal 'cad'
    )?# end the second (optional) group
)# end the first group
+# match one or more occurrences
";

// create a new regex that ignores comments
Regex r = new Regex(pat, RegexOptions.IgnorePatternWhitespace);
// get the list of group numbers
int[] gnums = r.GetGroupNumbers( );
// get first match
Match m = r.Match(text);
while (m.Success) {
    // start at group 1
    for (int i = 1; i < gnums.Length; i++) {
        Group g = m.Group(gnums[i]);
    }
    // get the group for this match
    Console.WriteLine("Group"+gnums[i]+"=["+g.ToString( )+"]");
    // get caps for this group
    CaptureCollection cc = g.Captures;
    for (int j = 0; j < cc.Count; j++) {
        Capture c = cc[j];
        Console.WriteLine("Capture" + j + "=["+c.ToString( )
            + "]" Index=" + c.Index + " Length=" + c.Length);
    }
}
// get next match
m = m.NextMatch( );
}

```

The output of this example is:

```

Group1=[abra]
    Capture0=[abracad] Index=0 Length=7
    Capture1=[abra] Index=7 Length=4
Group2=[cad]
    Capture0=[cad] Index=4 Length=3
Group1=[abra]
    Capture0=[abracad] Index=12 Length=7
    Capture1=[abra] Index=19 Length=4
Group2=[cad]
    Capture0=[cad] Index=16 Length=3
Group1=[abra]
    Capture0=[abracad] Index=24 Length=7
    Capture1=[abra] Index=31 Length=4
Group2=[cad]
    Capture0=[cad] Index=28 Length=3

```

We'll first examine the string `pat`, which contains the regular expression. The first capture group is marked by the first parenthesis, and then the expression matches an `abra`, if the regex engine matches the expression to that found in the text. Then the second capture group begins, marked by the second parenthesis, but the definition of the first capture group is still ongoing. What this means is that the first group must match `abracad` and the second group matches the `cad`. So, if we decided

to make the `cad` match an optional occurrence with the `?` metacharacter, then `abra` or `abracad` is matched. Next, we end the first group, and ask the expression to match one or more occurrences by specifying the `+` metacharacter.

During the matching process we create an instance of the expression by calling the `Regex` constructor, which is also where you specify your options. In this case, we used the `RegexOptions.IgnorePatternWhitespace` option, as the regular expression itself includes comments and whitespace for formatting purposes. The `RegexOptions.IgnorePatternWhitespace` option instructs the regex engine to ignore both the comments and all the whitespace that is not explicitly escaped.

Next, we retrieve the list of group numbers (`gnums`) defined in this regular expression. Although this could have been done explicitly, this sample demonstrates a programmatic approach. This approach is also useful if we have specified named groups as a way of quickly indexing through the set of groups.

Then we perform the first match and enter a loop to test for success of the current match. The next step is to iterate through the list of groups starting at group 1. The reason we do not use group 0 in this sample is that group 0 is the fully captured match string, and what we usually (but not always) want to pick out of a string is a subgroup. You might use group 0 if you want to collect the fully matched string as a single string.

Within each group, we iterate through the `CaptureCollection`. There is usually only one capture per match, per group-in this case two captures show for `Group1`: `Capture0` and `Capture1`. And if we ask only for the `ToString` of `Group1`, we receive `abra`, although it does also match the `abracad` sub string. The group `ToString` value is the value of the last `Capture` in its `CaptureCollection`. This is the expected behavior, and if we want the match to stop after just the `abra`, we can remove the `+` from the expression, telling the regular expression engine to match on just the expression.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

6.5 Procedural- and Expression-Based Patterns

Generally, users of regular expressions fall into one of two groups. The first group tends to use minimal regular expressions that provide matching or grouping behaviors, and then write procedural code to perform some iterative behavior. The second group tries to utilize the maximum power and functionality of the expression-processing engine itself, with as little procedural logic as possible. For most of us, the best answer is somewhere in between. We'll now explore the trade-offs in complexity and performance of these two approaches.

6.5.1 Procedural-Based Patterns

A common processing need is to match certain parts of a string and perform some processing. So, here's an example that matches words within a string and capitalizes them:

```
using System;
using System.Text.RegularExpressions;

class ProceduralFun {
    static void Main( ) {
        string txt = "the quick red fox jumped over the lazy brown dog.";
        Console.WriteLine("text=["+txt+"]");
        string res = "";
        string pat = @"\"w+|\"W+";

        // Loop through all the matches
        foreach (Match m in Regex.Matches(txt, pat)) {
            string s = m.ToString( );

            // If the first char is lower case, capitalize it
            if (char.IsLower(s[0]))
                s = char.ToUpper(s[0])+s.Substring(1, s.Length-1);
            res += s; // Collect the text
        }
        Console.WriteLine("result=["+res+"]");
    }
}
```

As you can see, you use the C# `foreach` statement to process the set of matches found, and perform some processing (in this case, creating a new result string).

The output of the sample is:

```
text=[the quick red fox jumped over the lazy brown dog.]
result=[The Quick Red Fox Jumped Over The Lazy Brown Dog.]
```

6.5.2 Expression-Based Patterns

Another way to implement the previous example is by providing a `MatchEvaluator`, which processes it as a single result set.

So the new sample looks like:

```
using System;
using System.Text.RegularExpressions;

class ExpressionFun {
    static string CapText(Match m) {
        // Get the matched string
        string s = m.ToString( );

        // If the first char is lower case, capitalize it
        if (char.IsLower(s[0]))
            return char.ToUpper(s[0]) + s.Substring(1, s.Length-1);
        return s;
    }
    static void Main( ) {
        string txt = "the quick red fox jumped over the lazy brown dog.";
        Console.WriteLine("text=[" + txt + "]);
        string pat = @"\w+";
        MatchEvaluator me = new MatchEvaluator(CapText);
        string res = Regex.Replace(txt, pat, me);
        Console.WriteLine("result=[" + res + "]);
    }
}
```

Also of note is that the pattern is simplified, since we need only to modify the words, not the nonwords.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

6.6 Cookbook Regular Expressions

To wrap up this overview of how regular expressions are used in C# applications, the following is a set of useful expressions that have been used in other environments.^[1]

[1] These expressions were taken from the *Perl Cookbook* by Tom Christiansen and Nathan Torkington (O'Reilly), and updated for the C# environment by Brad Merrill of Microsoft.

- Matching roman numerals:

```
string p1 = "^m*(d?c{0,3}|c[dm])"
    + "(l?x{0,3}|x[lc])(v?i{0,3}|i[vx])$";
string t1 = "vii";
Match m1 = Regex.Match(t1, p1);
```
- Swapping first two words:

```
string t2 = "the quick brown fox";
string p2 = @"(\S+)(\S+)(\S+)";
Regex x2 = new Regex(p2);
string r2 = x2.Replace(t2, "$3$2$1", 1);
```
- Matching "keyword = value" patterns:

```
string t3 = "myval = 3";
string p3 = @"(\w+)\s*=\s*(.*)\s*$";
Match m3 = Regex.Match(t3, p3);
```
- Matching lines of at least 80 characters:

```
string t4 = "*****"
    + "*****"
    + "*****";
string p4 = ".{80,}";
Match m4 = Regex.Match(t4, p4);
```
- Extracting date/time values (MM/DD/YY HH:MM:SS):

```
string t5 = "01/01/01 16:10:01";
string p5 =
    @"(\d+)/(\d+)/(\d+) (\d+):(\d+):(\d+)";
Match m5 = Regex.Match(t5, p5);
```
- Changing directories (for Windows):

```
string t6 =
    @"C:\Documents and Settings\user1\Desktop\";
string r6 = Regex.Replace(t6,
    @"\\user1\\",
    @"\user2\");
```
- Expanding (%nn) hex escapes:

```
string t7 = "%41"; // capital A
```

```
string p7 = "%([0-9A-Fa-f][0-9A-Fa-f])";
// uses a MatchEvaluator delegate
string r7 = Regex.Replace(t7, p7,
    HexConvert);
```

- Deleting C comments (imperfectly):

```
string t8 = @"
/*
 * this is an old cstyle comment block
 */
";
string p8 = @"
    /\* # match the opening delimiter
    .?* # match a minimal number of characters
    \*/ # match the closing delimiter
";
string r8 = Regex.Replace(t8, p8, "", RegexOptions.Singleline
    | RegexOptions.IgnorePatternWhitespace);
```

- Removing leading and trailing whitespace:

```
string t9a = "    leading";
string p9a = @"^\s+";
string r9a = Regex.Replace(t9a, p9a, "");

string t9b = "trailing    ";
string p9b = @"\s+$";
string r9b = Regex.Replace(t9b, p9b, "");
```

- Turning "\n" followed by "n" into a real newline:

```
string t10 = @"\ntest\n";
string r10 = Regex.Replace(t10, @"\n", "\n");
```

- Detecting IP addresses:

```
string t11 = "55.54.53.52";
string p11 = "^" +
    @"([01]?\d\d|2[0-4]\d|25[0-5])\. " +
    @"([01]?\d\d|2[0-4]\d|25[0-5])\. " +
    @"([01]?\d\d|2[0-4]\d|25[0-5])\. " +
    @"([01]?\d\d|2[0-4]\d|25[0-5])" +
    "$";
Match m11 = Regex.Match(t11, p11);
```

- Removing leading path from filename:

```
string t12 = @"c:\file.txt";
string p12 = @"^.*\\";
string r12 = Regex.Replace(t12, p12, "");
```

- Joining lines in multiline strings:

```
string t13 = @"this is
a split line";
string p13 = @"\s*\r?\n\s*";
string r13 = Regex.Replace(t13, p13, " ");
```


- Extracting all numbers from a string:

```
string t14 = @"
test 1
test 2.3
test 47
";
string p14 = @"(\d+\.?\d*|\.\d+)";
MatchCollection mc14 = Regex.Matches(t14, p14);
```

- Finding all caps words:

```
string t15 = "This IS a Test OF ALL Caps";
string p15 = @"(\b[^\Wa-z0-9_]+\b)";
MatchCollection mc15 = Regex.Matches(t15, p15);
```

- Finding all lowercase words:

```
string t16 = "This is A Test of lowercase";
string p16 = @"(\b[^\WA-Z0-9_]+\b)";
MatchCollection mc16 = Regex.Matches(t16, p16);
```

- Finding all initial caps words:

```
string t17 = "This is A Test of Initial Caps";
string p17 = @"(\b[^\Wa-z0-9_][^\WA-Z0-9_]*\b)";
MatchCollection mc17 = Regex.Matches(t17, p17);
```

- Finding links in simple HTML:

```
string t18 = @"
<html>
<a href=""http://windows.oreilly.com/news/first.htm"">first tag text</a>
<a href=""http://windows.oreilly.com/news/next.htm"">next tag text</a>
</html>
";
string p18 = @"<A[^>]*?HREF\s*=\s*["'"]?"
+ @"([^\s">]+?)["'"]?>";
MatchCollection mc18 = Regex.Matches(t18, p18, RegexOptions.IgnoreCase
| RegexOptions.Singleline);
```

- Finding middle initials:

```
string t19 = "Hanley A. Strappman";
string p19 = @"^S+\s+(\S)\S*\s+S";
Match m19 = Regex.Match(t19, p19);
```

- Changing inch marks to quotation marks:

```
string t20 = @"2' 2" " ";
string p20 = "\"([^\"]*)";
string r20 = Regex.Replace(t20, p20, "``$1'");
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 7. Collections

Collections are standard data structures that supplement arrays, which are the only built-in data structures in C#. In this, C# differs from languages such as Perl and Python, which incorporate key/value data structures and dynamically sized arrays into the language itself.

The FCL includes a set of types that provide commonly required data structures and support for creating your own. These types are typically broken down into two categories: interfaces that define a standardized set of design patterns for collection classes in general, and concrete classes that implement these interfaces and provide a usable range of data structures.

This chapter introduces all the concrete collection classes and abstract collection interfaces and provides examples of their use. Unless otherwise stated, the types mentioned in this section all exist in the `System.Collections` or `System.Collections.Specialized` namespaces, which are both documented in the reference section of this book, [Part V](#).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

7.1 Iterating Over Collections

In computing, there are many different kinds of collections ranging from simple data structures, such as arrays or linked lists, to more complex ones, such as red/black trees and priority queues. While the internal implementation and external characteristics of these data structures vary widely, the ability to traverse the contents of the collection is an almost universal need. In the FCL, this is supported via a pair of interfaces (`IEnumerable` and `IEnumerator`) that allow different data structures to expose a common traversal API.

7.1.1 IEnumerable and IEnumerator Interfaces

To expose an enumerator, a collection implements `IEnumerable`. This interface allows clients to retrieve an enumerator, typed as an `IEnumerator` interface reference. The enumerator is a logical cursor that can be used to iterate over the elements of the collection in a forward-only manner. The interfaces look like this:

```
public interface IEnumerable {
    IEnumerator GetEnumerator( );
}
public interface IEnumerator {
    bool MoveNext( );
    object Current {get;}
    void Reset( );
}
```

The `IEnumerable` interface has a single `GetEnumerator()` method that returns an `IEnumerator` interface reference, with the enumerator positioned before the first element in the collection. The `IEnumerator` interface provides standard mechanisms (the `MoveNext()` and `Reset()` methods) to iterate over the collection and to retrieve the current element (the `Current` property) as a generic `object` reference.

The collection can then be enumerated as follows, or as in the next code example:

```
MyCollection mcoll = new MyCollection( );
...
// Using IEnumerator: substitute your typename for XXX
IEnumerator ie = myc.GetEnumerator( );
while (myc.MoveNext( )) {
    XXX item = (XXX)myc.Current;
    Console.WriteLine(item);
    ...
}
```

C# also provides the `foreach` statement, which works on any collection that either implements the `IEnumerable` interface, or provides an accessible `GetEnumerator()` method that returns a type with accessible `MoveNext()` and `Reset()` methods. Using `foreach` can simplify iteration code, as

follows:

```
MyCollection mcoll = new MyCollection
...
// Using foreach: substitute your typename for XXX
foreach (XXX item in mcoll) {
    Console.WriteLine(item);
    ...
}
```

7.1.2 Implementing IEnumerable and IEnumerator

To allow your data types to be enumerated via the standard mechanisms, implement `IEnumerable` and `IEnumerator`, taking care to follow the interface's semantic contract. `IEnumerator` is often implemented as a nested helper type, which is initialized by passing the collection to the constructor of the `IEnumerator`:

```
using System.Collections;
public class MyCollection : IEnumerable {
    // ...
    int[] data;
    public virtual IEnumerator GetEnumerator ( ) {
        return new MyCollection.Enumerator(this);
    }
    private class Enumerator : IEnumerator {
        MyCollection outer;
        int currentIndex = -1;
        internal Enumerator(MyCollection outer) {
            this.outer = outer;
        }
        public object Current {
            get {
                if (currentIndex == outer.data.Length)
                    throw new InvalidOperationException( );
                return outer.data[currentIndex]; // boxed!
            }
        }
        public bool MoveNext( ) {
            if (currentIndex > outer.data.Length)
                throw new InvalidOperationException( );
            return ++currentIndex < outer.data.Length;
        }
        public void Reset( ) {
            currentIndex = -1;
        }
    }
}
```

7.1.3 Optimizing foreach

One of the downsides of implementing `IEnumerable` and `IEnumerator`, as shown in the previous example, is the return type of `IEnumerator.Current` is `object`. This approach has two main disadvantages:

1. Clients need to cast the `object` reference to a more specific type, which is both inefficient compared to a more strongly typed interface for homogenous collections, and may also cause `TypeCastExceptions` to be thrown if the casts fail.
2. When a collection contains value types, returning them as object references results in their being boxed and unboxed, which is inefficient, creates excess garbage on the heap, and makes it impossible to edit the contents of the collection directly.

Fortunately, there are some ways to resolve these issues. Although the `foreach` statement is designed to work with types that implement `IEnumerable` and `IEnumerator`, the C# compiler actually allows `foreach` iteration over types that merely provide a type-compatible subset of the methods and semantics in `IEnumerable` and `IEnumerator`. It does this by looking first at the type used for the collection in the `foreach` statement to see if it has an accessible method called `GetEnumerator()` that takes no parameters, and then returns a publicly accessible type. If it does, it then looks at the return type to see if it has loosely equivalent functionality to the `IEnumerator` interface. To do this, the compiler checks whether the type has an accessible `MoveNext` method (taking no parameters and returning a `bool` result) and an accessible `Current` property (matching the type of the individual element in the `foreach` statement). If all of these requirements are met, the C# compiler emits IL code to use these types and methods directly, without going through the interfaces. This means that client code does not need to downcast from `object`, and in the case of collections returning value types, no boxing occurs. Modifying the previous example to work this way looks like the following:

```
using System.Collections;
public class MyCollection {
    // ...
    int[ ] data;
    public Enumerator GetEnumerator ( ) {
        return new MyCollection.Enumerator(this);
    }
    public class Enumerator {
        MyCollection outer;
        int currentIndex = -1;
        internal Enumerator(MyCollection outer) {
            this.outer = outer;
        }
        public int Current {
            get {
                if (currentIndex == outer.data.Length)
                    throw new InvalidOperationException( );
                return outer.data[currentIndex]; // no boxing!
            }
        }
        public bool MoveNext( ) {
            if (currentIndex > outer.data.Length)
                throw new InvalidOperationException( );
            return ++currentIndex < outer.data.Length;
        }
    }
}
```

```

    }
}

```

The problem with this approach is that when used in languages other than C#, this type does not appear to be a collection since it does not implement the standard interfaces. Fortunately, explicit interface implementation can be used to support both approaches concurrently, as follows:

```

using System.Collections;
public class MyCollection : IEnumerable {
    // ...
    int[] data;
    public Enumerator GetEnumerator( ) {
        return new MyCollection.Enumerator(this);
    }
    IEnumerator IEnumerable.GetEnumerator( ) {
        return this.GetEnumerator();
    }
    public class Enumerator : IEnumerator {
        MyCollection outer;
        int currentIndex = -1;
        internal Enumerator(MyCollection outer) {
            this.outer = outer;
        }
        public int Current {
            get {
                if (currentIndex == outer.data.Length)
                    throw new InvalidOperationException( );
                return outer.data[currentIndex];
            }
        }
        public bool MoveNext( ) {
            if (currentIndex > outer.data.Length)
                throw new InvalidOperationException( );
            return ++currentIndex < outer.data.Length;
        }
        object IEnumerator.Current {
            get { return this.Current; }
        }
        bool IEnumerator.MoveNext( ) {
            return this.MoveNext( );
        }
        void IEnumerator.Reset( ) {
            currentIndex = -1;
        }
    }
}

```

This approach allows C# clients to bind to the more efficient, type-safe version of the methods, while other languages such as VB.NET bind to the more generic interface-based implementations.

7.1.4 IDictionaryEnumerator Interface

Later in this chapter we discuss the use of dictionary data structures. The `IDictionaryEnumerator` interface is a standardized interface used to enumerate over the contents of a dictionary, in which each element has both a key and a value. The `Entry` property is a more type-safe version of the `Current` property, and the `Key` and `Value` properties provide access to the element keys and values directly. The interface looks like this:

```
public interface IDictionaryEnumerator : IEnumerator {  
    DictionaryEntry Entry {get;}  
    object Key {get;}  
    object Value {get;}  
}
```

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

7.2 Standard Collection Interfaces

While `IEnumerable` and `IEnumerator` provide standard ways to access the contents of a collection, they don't provide any way to modify it, nor any way to easily perform other common tasks, such as determine the size, search the collection, etc. The .NET Framework also defines a set of three standardized interfaces (`ICollection`, `IList`, and `IDictionary`), which collections should implement to provide support for these types of operations.

7.2.1 ICollection Interface

The `ICollection` interface is the standard interface for countable collections of objects. It provides the ability to determine the size of a collection, to determine if it can be modified or synchronized, and to copy the collection into an array for sequential processing. Since `ICollection` extends `IEnumerable`, types that implement `ICollection` can also be traversed via `IEnumerable` and `IEnumerator`. The interface looks like this:

```
public interface ICollection : IEnumerable {
    void CopyTo(Array array, int index);
    int Count {get;}
    bool IsReadOnly {get;}
    bool IsSynchronized {get;}
    object SyncRoot {get;}
}
```

7.2.2 IList Interface

The `IList` interface is the standard interface for array-indexable collections. In addition to the functionality inherent in `ICollection` and `IEnumerable`, it also provides the ability to index directly into the collection by position (using the overloaded indexer), to add, remove, and change elements in the collection by position, and to search for elements in the collection. The interface looks like this:

```
public interface IList : ICollection, IEnumerable {
    object this[int index] {get; set;}
    int Add(object o);
    void Clear( );
    bool Contains(object value);
    int IndexOf(object value);
    void Insert(int index, object value);
    void Remove(object value);
    void RemoveAt(int index);
}
```

7.2.3 IDictionary Interface

The `IDictionary` interface is the standard interface for key/value-based collections such as hashtables, maps, and property bags. Similar to the `IList` interface, it provides the functionality inherent in `ICollection` and `IEnumerable`, as well as the ability to access elements in the collection based on key, remove them, search the collection for an element, and access lists of the keys and values already in the collection. The interface looks like this:

```
public interface IDictionary : ICollection, IEnumerable {
    object this[object key] {get; set;};
    ICollection Keys {get;};
    ICollection Values {get;};
    void Clear( );
    bool Contains(object value);
    IDictionaryEnumerator GetEnumerator( );
    void Remove(object key);
}
```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

7.3 Predefined Collection Classes

The FCL provides a reasonably comprehensive set of prebuilt data structures providing concrete implementations of all the interfaces described in this chapter. However, since C# does not yet support generics, the implementations work in terms of the generic object type, which has the same disadvantages (excessive casting, boxing) as the generic `IEnumerator` interface described earlier. If you prefer more type-safe collection classes, you may use one of these predefined types as a starting point for your own type-safe variant.

7.3.1 The Array Class

The `Array` class is the canonical aggregate data structure in the FCL, representing a fixed-size array of object references of uniform type. Since the `Array` data structure is fundamental, the C# language provides explicit array declaration and initialization syntax (for more details, see [Chapter 2](#) and [Chapter 3](#)). The storage for the array is allocated on the GC heap at the time a class is instantiated, and cannot change (see the `ArrayList` class for a growable array-like data structure). The `Array` class implements `ICollection`, `IList`, and `IEnumerator`, so arrays can be treated as lists, generic cloneable collections, or sets of elements that can be enumerated. In addition, the `Array` class supports sorting and searching of the array. Sorting of the array is often accomplished by delegating to `IComparable` implementations on the contained elements, which requires that you implement `IComparable` on types that are intended for use in arrays that need to be sorted. The following is an example of using the `Array` class:

```
string[] strs1 = { "time", "the", "now", "is" };
Array.Reverse(strs1);
Array strs2 = Array.CreateInstance(typeof(string), 4);
strs2.SetValue("for", 0);
strs2.SetValue("all", 1);
strs2.SetValue("good", 2);
strs2.SetValue("men", 3);
Array strings = Array.CreateInstance(typeof(string), 8);
Array.Copy(strs1, strings, 4);
strs2.CopyTo(strings, 4);
foreach (string s in strings)
    Console.WriteLine(s);
```

7.3.2 The ArrayList Class

The `ArrayList` class provides a dynamically sized array of objects that implements the `IList` interface. An `ArrayList` works by maintaining an internal array of objects that is replaced with a larger array when it reaches its capacity of elements. It is very efficient at adding elements (since there is usually a free slot at the end), but is inefficient at inserting elements (since all elements have to be shifted to make a free slot). Searching can be efficient if the `BinarySearch()` method is used on an `ArrayList` that has been sorted, but is otherwise inefficient as it requires that each item is

checked individually. The following is an example of using the `ArrayList` class:

```
ArrayList a = new ArrayList( );
a.Add("Vernon");
a.Add("Corey");
a.Add("William");
a.Add("Muzz");
a.Sort( );
for (int i = 0; i < a.Count; i++)
    Console.WriteLine(a[i]);
```

7.3.3 The Hashtable Class

A `Hashtable` is a standard dictionary (key/value) data structure that uses a hashing algorithm to store and index values efficiently. This hashing algorithm is performed using the hashcode returned by the `GetHashCode()` method on `System.Object`. Types stored in a `Hashtable` should therefore override `GetHashCode()` to return a good hash of the object's internal value. `Hashtable` also implements the `IDictionary` interface, and therefore can also be manipulated as a normal dictionary data structure. The following is an example of using the `Hashtable` class:

```
Hashtable ht = new Hashtable( );
ht["One"] = 1;
ht["Two"] = 2;
ht["Three"] = 3;
Console.WriteLine(ht["Two"]); // Prints "2"
```

7.3.4 The Queue Class

A `Queue` is a standard first-in first-out (FIFO) data structure, providing simple operations to enqueue, dequeue, peek at the element at the top of the queue, etc. The following is an example of using the `Queue` class:

```
Queue q = new Queue( );
q.Enqueue(1);
q.Enqueue(2);
Console.WriteLine(q.Dequeue( )); // Prints "1"
Console.WriteLine(q.Dequeue( )); // Prints "2"
```

7.3.5 The Stack Class

A `Stack` is a standard last-in first-out (LIFO) data structure, providing simple operations to `Push` and `Pop` elements on and off the stack. The following is an example of using the `Stack` class:

```
Stack s = new Stack( );
s.Push(1); // Stack = 1
s.Push(2); // Stack = 1,2
s.Push(3); // Stack = 1,2,3
Console.WriteLine(s.Pop( )); // Prints 3, Stack=1,2
Console.WriteLine(s.Pop( )); // Prints 2, Stack=1
Console.WriteLine(s.Pop( )); // Prints 1, Stack=
```

7.3.6 The BitArray Class

A `BitArray` is a dynamically sized array of `bool` values. It is more memory-efficient than a simple array of `bools`, because it uses only one bit for each value, whereas a `bool` array uses one byte for each value. The following is an example of using the `BitArray` class:

```
BitArray bits = new BitArray( );
bits.Length = 2;
bits[1] = true;
bits.Xor(bits); // Xor the array with itself
```

7.3.7 The SortedList Class

A `SortedList` is a standard dictionary data structure that uses a binary-chop search to index efficiently. `SortedList` implements the `IDictionary` interface and is manipulated like any other dictionary data structure. `SortedList` also implements the `ICollection` and `IEnumerable` interfaces. The following is an example of using a `SortedList`:

```
SortedList s = new SortedList( );
s["Zebra"] = 1;
s["Antelope"] = 2;
s["Eland"] = 3;
s["Giraffe"] = 4;
s["Meerkat"] = 5;
s["Dassie"] = 6;
s["Tokoloshe"] = 7;
Console.WriteLine(s["Meerkat"]); // Prints "5" in 3 lookups
```

7.3.8 The StringCollection Class

The `StringCollection` class is a standard collection data structure for storing strings. `StringCollection` implements the `ICollection` interface and can be manipulated like any other collection data structure. The following is an example of using a `StringCollection`:

```
StringCollection sc = new StringCollection( );
sc.Add("s1");
string[] sarr = { "s2", "s3", "s4" };
sc.AddRange(sarr);
foreach (string s in sc)
    Console.Write("{0} ", s); // s1 s2 s3 s4
```

7.3.9 The StringDictionary Class

The `StringDictionary` class is a dictionary data structure for storing key/value pairs in which the type of the key is a string. This class offers very similar methods to the `Hashtable` class, although the only standard interface it implements is `IEnumerable`. The following is an example of using a `StringDictionary`:

```
StringDictionary sd = new StringDictionary( );  
sd["One"] = 1;  
sd["Two"] = 2;  
sd["Three"] = 3;  
Console.WriteLine(sd["Two"]); // Prints "2"
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

7.4 Ordering Instances

The implementations of the collection classes' sorting and searching capabilities depend on certain facilities in the contained objects themselves. The most common of these are the ability to order the contained objects (used for sorting and efficient searching) and the ability to hash an object (to speed storage and retrieval in dictionary-based structures such as `Hashtable`). As with most other parts of the FCL's collections framework, this is accomplished via standardized interfaces and overridden virtual methods on `System.Object`.

7.4.1 The `IComparable` Interface

The `IComparable` interface allows one object to indicate its ordering relative to another instance of the same type. To allow sorting and searching of your types in an array, implement the `IComparable` interface, which looks like this:

```
public interface IComparable {
    int CompareTo(object rhs);
}
```

Implementation of this interface should follow the following semantic rules:

1. If `a` comes before `b` $\rightarrow a.CompareTo(b) < 0$
2. If `a` is equal `b` $\rightarrow a.CompareTo(b) == 0$
3. If `a` comes after `b` $\rightarrow a.CompareTo(b) > 0$
4. `null` comes first: `a.CompareTo(null) > 0`
5. `a.CompareTo(b) \rightarrow a.GetType() == b.GetType()`

An example implementation of this interface might look like this:

```
public sealed class Person : IComparable {
    public string Name;
    public int Age;
    public int CompareTo(object o) {
// Check for null
        if (o == null) return 1;
// Check for concrete type match
        if (o.GetType() != this.GetType())
            throw new ArgumentException();
// Sort instances by ascending Age
        Person rhs = (Person)o;
        if (Age < rhs.Age) return -1;
    }
}
```

```

        if (Age > rhs.Age) return 1;
        return 0;
    }
}

```

Note that in this example `Person` is marked as `sealed`. This is intended to simplify implementation, which can be complex in the face of future, unexpected inheritance. Remember to always ensure that the rules in the semantic contract are followed, including the one that states you can only compare identical types. One way of enforcing this is by explicitly comparing the types using `GetType()`, as the previous sample does. Additionally, ensure that comparing to a null reference doesn't throw an exception, but returns 0, which sorts the null entries to the front of the list.

Implementing `IComparable` allows you to provide a default ordering for a type. However, sometimes more than one ordering for a type is needed. This can be accomplished using implementations of the `IComparer` interface.

7.4.2 The IComparer Interface

The collection classes actually perform their sorting using an implementation of the `IComparer` interface, which compares two independent object instances for their relative ordering. The `IComparer` interface looks like this:

```

public interface IComparer {
    int Compare(object x, object y);
}

```

You generally don't need to implement this interface, since a default implementation that delegates to the `IComparable` interface is already provided by the `Comparer` type (which is used by the `Array` class by default). However, if you wish to provide additional ordering options for a type, you can provide additional concrete implementations of the `IComparer` interface that performed type-specific comparisons (these are often implemented as nested helper types).

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

7.5 Generating Hash Code

All object instances can provide a signed 32-bit integer hash of their contents via the `GetHashCode()` method on `System.Object`. Good hashes can have a dramatic effect on `Hashtable` speed (they are used to determine which bucket to add entries to in the hashtable), and can also provide a low-fidelity (but possibly more efficient) equivalence test. Using `GetHashCode` in this way is demonstrated in the following examples:

```
void Enroll(Student s, CourseList cl) {
    hashtable.Add(s, cl); // GHC called on key (s)
}
bool FastCompare(Student s1, Student s2) {
    // Use GHC to test for possible equivalence
    if (s1.GetHashCode( ) != s2.GetHashCode( )) return false;

    // Use Equals to test for definite equivalence
    return s1.Equals(s2);
}
```

The default implementation of `GetHashCode()` on `System.Object` returns a semi-unique member #, while the implementation of `GetHashCode()` on `System.ValueType` merely returns the hash of the first field in the value type. Although these defaults work in a lot of cases, there are sometimes performance benefits gained from implementing `GetHashCode()` on your own type. Additionally, if a type overrides the `Equals()` method, it is required to override the `GetHashCode()` method, which means that many framework types override `GetHashCode()`, as shown here:

```
void DumpHashes(object o, int i, Version v) {
    Console.WriteLine(o.GetHashCode( )); // object index
    Console.WriteLine(i.GetHashCode( )); // integer value
    Console.WriteLine(v.GetHashCode( )); // hash of fields
}
```

7.5.1 The Object.GetHashCode Method

The `System.GetHashCode` method is declared as follows:

```
public virtual int GetHashCode( );
```

It is important to understand the general contract for `GetHashCode()`, which looks like this:

1. `A.GetHashCode()` \rightarrow even distribution across all `a`'s
2. `a.Equals(b)` \rightarrow `a.GetHashCode() = b.GetHashCode()`
3. `A` overrides `GetHashCode` \rightarrow `A` overrides `Equals`

4. Safe: no exceptions thrown; no circular references

The idea is that good implementations use all 32 bits to provide a good even distribution and ideally preserve the significance of field ordering (to ensure that `Point(10,20)` hashes differently to `Point(20,10)`). Preserving field ordering is traditionally done by multiplying the hash for each field by some odd prime constant (37 is a popular choice in the Java world, in which a similar construct exists). Additionally, if you have not derived directly from `System.Object`, consider combining the hash of your base type with the hash of your contained members. Lastly, remember that contained aggregate data structures (such as `Arrays`) may not hash their contents correctly, and therefore may need to be hashed by hand. The following is an example implementing some of these rules, in order to provide a good hash distribution that includes all the type's data in the hash calculation.

```
public sealed class Data {
    public readonly short x, y;
    public readonly Color c;
    ArrayList al = new ArrayList( );

    public override int GetHashCode( ) {
        int hc = 1; // base.GetHashCode if base!=object
        hc = 37*hc + x<<16|(ushort)x;
        hc = 37*hc + y.GetHashCode( );
        hc = 37*hc + (c==null ? 0 : c.GetHashCode( ));
        foreach (object o in al)
            hc = 37*hc + o.GetHashCode( );
        return hc;
    }
}
```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 8. XML I/O

XML has, for better or worse, taken the programming industry by storm. It has become, in a matter of a few short years, the *de facto* standard for exchanging data between heterogeneous systems as well as the format of choice for storing just about any kind of data. The .NET runtime uses XML as part of its configuration, and the .NET Framework contains a redesigned set of classes for accessing, consuming, producing, and transforming XML documents.

This chapter introduces the built-in support for XML, explains the relationships between XML and the I/O system in general, demonstrates the consumption and production of XML documents in both node-based and Infoset-based forms, highlights the use of XPath, and finally explores XSLT. All types within this namespace come from the `System.Xml` and `System.Xml.XPath` namespaces and are contained in the `System.Xml.dll` assembly. (When using these types, remember to reference the assembly either at the command line or from Visual Studio's project dialogs.)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

8.1 Accessing XML Documents

Like the I/O mechanism described in [Chapter 10](#), the XML libraries in the .NET FCL follow a pattern of an "abstract base class with concrete backing store implementation classes." The two abstract base classes themselves are `XmlReader` and `XmlWriter`, used respectively for consuming and producing XML.

8.1.1 XmlReader

The `XmlReader` class, as its name implies, provides the ability to consume XML documents. It is an abstract base class, intended to be subclassed for working against a particular source of XML. There are three concrete implementations of `XmlReader` in the FCL: `XmlTextReader` (used for parsing XML from any arbitrary stream of text), `XmlNodeReader` (used for parsing XML from an `XmlNode`), and `XmlValidatingReader`, which is an `XmlReader` that performs DTD and/or Schema validation against the parsed document.

Most often, an `XmlTextReader` is all that's necessary to begin working with XML input, as shown in the following example:

```
using System.Xml;
class XmlFun {
    static void Main( ) {
        XmlTextReader tr = new XmlTextReader("xmlfun.xml");
        // use tr as described later
    }
}
```

This code expects to find a file named `xmlfun.xml` within the current directory. This constructor is a shortcut notation for the more powerful `Stream`-based constructor that `XmlTextReader` also supports:

```
using System.IO;
using System.Xml;
class XmlFun {
    static void Main( ) {
        XmlTextReader tr =
            new XmlTextReader(
                new TextReader(
                    new FileStream("xmlfun.xml", FileMode.Open)));
        // use tr as described later
    }
}
```

This highlights an important point: `XmlTextReader` can pull XML from any `Stream`-based input source, including HTTP URLs and database text columns. For example, it becomes possible to parse XML out of an in-memory `String`-based representation:

```

using System.IO;
using System.Xml;
class XmlFun {
    static void Main( ) {
        string xmlContent =
            "<book>" +
            "    <title>C# in a Nutshell</title>" +
            "    <author>Drayton</author>" +
            "    <author>Neward</author>" +
            "    <author>Albahari</author>" +
            "</book>";

        XmlTextReader tr =
            new XmlTextReader(new StringReader(xmlContent));
    }
}

```

The ability to parse in-memory strings permits the parsing of XML-generated in-process without having to write the XML first to a file. This can be particularly powerful as a means of decoupling between components.

Once the `XmlReader` instance is created, it can be used to extract the XML elements in a pull-driven mode. `XmlReader` itself serves as a cursor to the various XML constructs contained within the stream, such as elements, attributes, and so forth. The current construct can be accessed using a variety of properties: `Name` (to return the qualified name of the element or attribute), `Value` (to return the value of the raw text), and so on. The `Read` method is commonly used to iterate to the next element in the stream; otherwise, one of the various `MoveXXX` methods, such as `MoveToNextElement`, can be used to perform higher-level navigation within the stream. (Note that all navigation must be forward-only; once bypassed, a node cannot be retrieved.) The following code demonstrates how to pull all the XML elements from an XML stream and echo them back to the console:

```

using System;
using System.IO;
using System.Xml;
class XmlFun {
    static void Main( ) {
        try
        {
            string xmlContent =
                "<book>" +
                "    <title>C# in a Nutshell</title>" +
                "    <authors>" +
                "        <author>Drayton</author>" +
                "        <author>Neward</author>" +
                "        <author>Albahari</author>" +
                "    </authors>" +
                "</book>";

            XmlTextReader reader =
                new XmlTextReader(new StringReader(xmlContent));

            //Parse the file and display each of the nodes.

```

```

while (reader.Read( ))
{
    switch (reader.NodeType)
    {
        case XmlNodeType.Element:
            Console.WriteLine("<{0}>", reader.Name);
            break;
        case XmlNodeType.Text:
            Console.WriteLine(reader.Value);
            break;
        case XmlNodeType.CDATA:
            Console.WriteLine("<![CDATA[{0}]]>", reader.Value);
            break;
        case XmlNodeType.ProcessingInstruction:
            Console.WriteLine("<?{0} {1}?>", reader.Name, reader.Value);
            break;
        case XmlNodeType.Comment:
            Console.WriteLine("<!--{0}-->", reader.Value);
            break;
        case XmlNodeType.XmlDeclaration:
            Console.WriteLine("<?xml version='1.0'?>");
            break;
        case XmlNodeType.Document:
            break;
        case XmlNodeType.DocumentType:
            Console.WriteLine("<!DOCTYPE {0} [{1}]\"", reader.Name,
                reader.Value);
            break;
        case XmlNodeType.EntityReference:
            Console.WriteLine(reader.Name);
            break;
        case XmlNodeType.EndElement:
            Console.WriteLine("</{0}>", reader.Name);
            break;
    }
}
}
}
}
}

```

In the preceding example, the actual data of interest is found in either the **Name** or **Value** property of the **XmlTextReader**, depending on the actual type of the Read node.

8.1.2 XmlWriter

Just as **XmlReader** serves as the abstract type for consuming XML, **XmlWriter** serves as an abstract type for producing XML-compliant data. It is always possible to emit XML "in the raw" by creating a **String** and appending XML tags to it, as in the following:

```
string xml = "<greeting>" +
```

```
messageOfTheDay +
"< /greeting>";
```

However, there are numerous problems with this technique, most notably the possibility that typos and accidental programmer errors will render the XML ill-formed and therefore unparseable.

`XmlWriter` provides a less error-prone way of generating well-formed XML. The following code generates the XML data string of the preceding example (without the XML error), complete with document declaration:

```
XmlTextWriter xw = new XmlTextWriter("greetings.xml", null);
xw.Formatting = Formatting.Indented;
xw.Indentation = 2;
xw.WriteStartDocument( );
xw.WriteStartElement("greeting");
xw.WriteString(messageOfTheDay);
xw.WriteEndElement( );
xw.WriteEndDocument( );
xw.Close( );
```

This writes the XML to a file named *greetings.xml*, indenting the code two spaces on each level. To write the data to an in-memory string, pass either a `System.IO.TextWriter` instance into the constructor of `XmlTextWriter`, or else pass a `System.IO.Stream` object and a `System.Text.Encoding` enumeration instance (to tell the `Writer` how to treat character data; by default, it uses UTF-8).

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

8.2 Parsing an XML Stream

Of course, simply reading and writing XML in this form, while of some use, is somewhat limiting. Much of XML's attraction is in its ability to provide structure over data; using `XmlReader` "in the raw," however, hides the very hierarchical structure XML imposes. In many cases, XML data is best viewed as an arranged tree of data, complete with the XML structuring elements (the tags and attributes surrounding the data) found within it.

Fortunately, the .NET XML architecture supports such a view, using the `XmlDocument` class to model the entire XML document itself. To see the hierarchical structure in an XML document, you must first pass the XML into the `XmlDocument` instance for parsing:

```
XmlDocument doc = new XmlDocument( );  
doc.Load(new XmlReader(...));
```

Alternatively, you can use `LoadXml` to parse an arbitrary string instance.

Once the `XmlDocument` is populated with data, the document's document element can be obtained from the `XmlDocument` instance via the `DocumentElement` property. From there, it is a simple matter to walk the various child nodes, all the way to the elements of interest:

```
XmlNode docNode = doc.DocumentElement;  
//print out all the first-level children  
foreach (XmlNode n in docNode.ChildNodes)  
    System.Console.WriteLine(n.Name);
```

At this point, navigation becomes an exercise in using the various properties and methods on `XmlNode`. The `Attributes` property returns an `XmlAttributeCollection` containing the attributes (if any) on this node, the `ChildNodes` property (shown in the previous code snippet) returns an `XmlNodeList` instance containing the child nodes of this node, and the `Name` and `Value` properties return various information depending on the current node's type.

8.3 Selecting Nodes Using XPath

Walking the resulting tree of `XmlNode` instances that is created by XML readers can be tedious and error-prone in its own right, particularly when a specific set of nodes scattered throughout the tree is desired. To address this requirement, the W3C defined a query API called `XPath` for selecting nodes within an Infoset (the tree-like hierarchy a DOM-compliant parser transforms XML input into, according to the W3C Specifications) representation. In the .NET XML libraries, this is implemented by specifying the `IXPathNavigable` interface, with any type that supports the interface in turn supporting XPath queries against it.

Without the availability of XPath, programmers must write code like that in the following example in order to list the author names found in a given `book` element:

```
using System;
using System.IO;
using System.Xml;

class App
{
    public static void Main(string[] args)
    {
        string xmlContent =
            "<book>" +
            "  <title>C# in a Nutshell</title>" +
            "  <authors>" +
            "    <author>Drayton</author>" +
            "    <author>Neward</author>" +
            "    <author>Albahari</author>" +
            "  </authors>" +
            "</book>";

        XmlTextReader xtr =
            new XmlTextReader(new StringReader(xmlContent));

        XmlDocument doc = new XmlDocument( );
        doc.Load(xtr);
        XmlNode docElement = doc.DocumentElement;

        // This gets us title and authors
        foreach (XmlNode n2 in docElement.ChildNodes)
        {
            if (n2.Name == "authors")
            {
                // This gets us author tags
                foreach (XmlNode n3 in n2.ChildNodes)
                {
                    // This gets us the text inside the author tag;
                    // could also get the child element, a text node,
```



```

        // and examine its Value property
        Console.WriteLine(n3.InnerText);
    }
}
}
}
}

```

Because, however, `XmlNode` implements the `IXPathNavigable` interface, we can instead write an XPath query that does the selection for us, as well as returns an `XmlNodeList` that we can walk in the usual fashion:

```

using System;
using System.IO;
using System.Xml;

class App
{
    public static void Main(string[] args)
    {
        string xmlContent =
            "<book>" +
            "  <title>C# in a Nutshell</title>" +
            "  <authors>" +
            "    <author>Drayton</author>" +
            "    <author>Neward</author>" +
            "    <author>Albahari</author>" +
            "  </authors>" +
            "</book>";

        XmlTextReader xtr =
            new XmlTextReader(new StringReader(xmlContent));

        XmlDocument doc = new XmlDocument( );
        doc.Load(xtr);
        XmlNode docElement = doc.DocumentElement;

        XmlNodeList result =
            docElement.SelectNodes("/book/authors/author/text( )");
        foreach (XmlNode n in result)
        {
            Console.WriteLine(n.Value);
        }
    }
}

```

While the preceding code may not seem like much of an improvement over the earlier XPath-free approach, the real power of XPath becomes apparent when doing far more complex queries. For example, consider the following code, which returns the list of books authored by either Drayton or Neward:

```

using System;
using System.IO;

```

```

using System.Xml;

class App
{
    public static void Main(string[] args)
    {
        string xmlContent =
            "<book>" +
            "  <title>C# in a Nutshell</title>" +
            "  <authors>" +
            "    <author>Drayton</author>" +
            "    <author>Neward</author>" +
            "    <author>Albahari</author>" +
            "  </authors>" +
            "</book>";
        XmlTextReader xtr =
            new XmlTextReader(new StringReader(xmlContent));

        XmlDocument doc = new XmlDocument( );
        doc.Load(xtr);
        XmlNode docElement = doc.DocumentElement;

        XmlNodeList result =
            docElement.SelectNodes("/book" +
                                   "[authors/author/text( )='Drayton' or " +
                                   "authors/author/text( )='Neward']" +
                                   "/title/text( )");
        foreach (XmlNode n in result)
        {
            Console.WriteLine(n.Value);
        }
    }
}

```

Notice that in the XPath-related code, the conditional logic is contained within the XPath statement itself-the subquery contained inside the square brackets acts as a predicate constraining the rest of the statement. Writing the code to produce similar results in C# would be at least a page long. You can find more information on XPath in *XML in a Nutshell*, by Elliotte Rusty Harold and W. Scott Means, or *Learning XML*, by Erik T. Ray (both published by O'Reilly).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

8.4 Transforming a Document Using XSLT

A frequent usage of XPath is to find nodes for extraction and possible transformation into other XML documents, or into non-XML data, such as HTML or flat-file format for legacy consumption. While XPath provides a powerful API for selecting nodes from within an Infoset, writing the procedural code to execute query after query, along with the code to execute against each query result, is tedious and error-prone. Again, the W3C has anticipated this need and provided another XML-based standard, the XSL: Transformations specification (in which XSL originally stood for "eXtensible Stylesheet Language: "), for doing precisely this.

In the following example, we continue to use this XML `book` as our source data:

```
<book>
  <title>C# in a Nutshell</title>
  <authors>
    <author>Drayton</author>
    <author>Neward</author>
    <author>Albahari</author>
  </authors>
</book>
```

Suppose you wish to transform this source XML into a format more suitable for end-user consumption, such as HTML. For purely pedagogical reasons, we wish the title to display in bold font in an H1-style heading, with the authors' names displayed in order in italic text.

Certainly, you could write the necessary C# code to execute two XPath queries, one to retrieve the title of the book (`/book/title/text()`) and another to retrieve the list of authors for the book (`/book/authors/author/text()`). You could then take each resulting `XmlNodeList`, walk through the results, and echo the HTML back to the caller. However, it is much simpler to write a single file that describes these transformation rules without having to worry about how the work gets done:

```
<xsl:transform xmlns:xsl="">
  <xsl:template match="title">
    <h1><xsl:value-of select="text( )" /></h1>
  </xsl:template>
  <xsl:template match="author">
    <i><xsl:value-of select="text( )" /></i>
  </xsl:template>
</xsl:transform>
```

When this transform is run through an XSLT engine, the engine starts at the root node of the source XML (our `book` element, in this case), and begins to evaluate each `<xsl:template>` rule specified. Here, the `<xsl:template>` tags specify a criteria (i.e., an XPath set of nodes) that indicate when this template should be invoked. If a match occurs (such as the case when the current node is the `book/title` node against the first template in the XSLT), the body of the `<xsl:template>` tag is fired. Literal text, such as the `<h1>` and `</h1>` text, is copied directly to the XSLT engine's output stream; other XSLT tags are in turn evaluated. The `<xsl:value-of>` tag also specifies an XPath query, but takes the resulting nodes and echoes their "values" (the text in the case of a `text()`

node) to the XSLT engine's output stream. Thus, running an XSLT engine using the `books` that XML input and the XSLT transformation described earlier produces the following:

```
<h1>C# In A Nutshell</h1><i>Drayton</i><i>Neward</i><i>Albahari</i>
```

This is, of course, browseable HTML.

The .NET Framework Class Library support for XML includes the programmatic execution of XSLT, using the `System.Xml.Xsl.XslTransform` class:

```
using System;
using System.IO;
using System.Xml;
using System.Xml.Xsl;

class App
{
    public static void Main(string[] args)
    {
        // Load the transform into the XSLT Engine
        XslTransform transform = new XslTransform( );
        transform.Load("book2html.xsl");

        /* book2html.xsl contains this code:
        <xsl:transform xmlns:xsl="http://www.w3.org/1999/XSL/Transform">
            <xsl:template match="title">
                <h1><xsl:value-of select="text( )" /></h1>
            </xsl:template>
            <xsl:template match="author">
                <i><xsl:value-of select="text( )" /></i>
            </xsl:template>
        </xsl:transform>
        */

        // Obtain the data to transform
        string xmlContent =
            "<book>" +
            "  <title>C# in a Nutshell</title>" +
            "  <authors>" +
            "    <author>Drayton</author>" +
            "    <author>Neward</author>" +
            "    <author>Albahari</author>" +
            "  </authors>" +
            "</book>";

        XmlTextReader xtr =
            new XmlTextReader(new StringReader(xmlContent));
        XmlDocument doc = new XmlDocument( );
        doc.Load(xtr);

        // Define where the results should go
        StringWriter output = new StringWriter( );
```

```
// Transform
transform.Transform(doc, null, output);

Console.WriteLine(output);
}
}
```

This XSLT Engine is quite powerful; the middle argument to the `XsltTransform` object allows the .NET programmer to pass in an argument list, which is a collection of parameters from outside the engine to inside the engine, including callback methods that the XSLT Engine can invoke (using Microsoft-specific extensions) when a particular rule is evaluated. See the `System.Xml.Xsl` namespace for more details on .NET's support for XSLT. See *XSLT*, by Doug Tidwell (O'Reilly) for more general information on XSLT.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 9. Networking

The FCL includes a number of types that make accessing networked resources easy. Offering different levels of abstraction, these types allow an application to ignore much of the detail normally required to access networked resources while retaining a high degree of control.

This chapter describes the core networking support in the FCL, and provides numerous examples leveraging the predefined classes. The types mentioned in this section all exist in the `System.Net` and `System.Net.Sockets` namespaces.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

9.1 Network Programming Models

High-level access is performed using a set of types that implement a generic request/response architecture, which is extensible, to support new protocols. The implementation of this architecture in the FCL also includes HTTP-specific extensions to make interacting with web servers easy.

Should the application require lower-level access to the network, types exist to support the Transmission Control Protocol (TCP) and User Datagram Protocol (UDP). Finally, in situations in which direct transport-level access is required, there are types that provide raw socket access.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

9.2 Generic Request/Response Architecture

The request/response architecture is based on Uniform Resource Indicator (URI) and stream I/O, follows the factory design pattern, and makes good use of abstract types and interfaces. A factory method, `WebRequest.Create()`, parses the URI and creates the appropriate protocol handler to fulfill the request.

Protocol handlers share a common abstract base type (`WebRequest`), which exposes properties that configure the request and methods used to retrieve the response.

Responses are also represented as types and share a common abstract base type (`WebResponse`), which exposes a `NetworkStream`, providing a simple streams-based I/O and easy integration into the rest of the FCL.

This example is a simple implementation of the popular Unix `snarf` utility. It demonstrates the use of the `WebRequest` and `WebResponse` classes to retrieve the contents of a URI and print them to the console:

```
// Snarf.cs
// Run Snarf.exe <http-uri> to retrieve a web page
// e.g. snarf.exe http://www.oreilly.com/catalog/csharpnut/
using System;
using System.IO;
using System.Net;
using System.Text;
class Snarf {
    static void Main(string[] args) {

        // Retrieve the data at the URL with a WebRequest instance
        WebRequest req = WebRequest.Create(args[0]);
        WebResponse resp = req.GetResponse( );

        // Read in the data, performing ASCII->Unicode encoding
        Stream s = resp.GetResponseStream( );
        StreamReader sr = new StreamReader(s, Encoding.ASCII);
        string doc = sr.ReadToEnd( );

        Console.WriteLine(doc); // Print result to console
    }
}
```


9.3 HTTP-Specific Support

The request/response architecture inherently supports protocol-specific extensions via the use of subtyping. Since `WebRequest.Create()` creates and returns the appropriate handler type based on the URI, accessing protocol-specific features is as easy as downcasting the returned `WebRequest` object to the appropriate protocol-specific handler and accessing the extended functionality.

The FCL includes specific support for the HTTP protocol, including the ability to easily access and control elements of an interactive web session, such as the HTTP headers, user-agent strings, proxy support, user credentials, authentication, keep-alives, pipelining, and more.

This example demonstrates the use of the HTTP-specific request/response classes to control the user-agent string for the request and retrieve the server type:

```
// ProbeSvr.cs
// Run ProbeSvr.exe <servername> to retrieve the server type
using System;
using System.Net;
class ProbeSvr {
    static void Main(string[] args) {

        // Get instance of WebRequest ABC, convert to HttpWebRequest
        WebRequest req = WebRequest.Create(args[0]);
        req.Method = "HEAD"; // we're just looking at headers
        HttpWebRequest httpReq = (HttpWebRequest)req;

        // Access HTTP-specific features such as User-Agent
        httpReq.UserAgent = "CSPRProbe/1.0";

        // Retrieve response and print to console
        WebResponse resp = req.GetResponse( );
        HttpWebResponse httpResp = (HttpWebResponse)resp;
        Console.WriteLine(httpResp.Server);

    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

9.4 WebClient

`WebClient` provides a higher-level interface to network resources than `WebRequest`. `DownloadData()` and `DownloadFile()` retrieve resources from a URI into a byte array or a file. `UploadData()` and `UploadFile()` sends the contents of a byte array or a file to a resource identified by a URI. Use `WebClient` to rewrite `Snarf.cs` as:

```
// Snarf2.cs
// Run Snarf.exe <http-uri> to retrieve a web page
using System;
using System.Net;
using System.Text;
class Snarf {
    static void Main(string[] args) {
        WebClient wc = new WebClient( );
        byte[] buffer = wc.DownloadData(args[0]);
        string doc = Encoding.ASCII.GetString(buffer);
        Console.WriteLine(doc);
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

9.5 Adding New Protocol Handlers

Adding handlers to support new protocols is trivial; simply implement a new set of derived types based on `WebRequest` and `WebResponse`, implement the `IWebRequestCreate` interface on your `WebRequest`-derived type, and register it as a new protocol handler with the `WebRequest.RegisterPrefix()` at runtime. Once this is done, any code that uses the request/response architecture can access networked resources using the new URI format (and underlying protocol).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

9.6 Using TCP, UDP, and Sockets

The `System.Net.Sockets` namespace includes types that provide protocol-level support for TCP and UDP. These types are built on the underlying `Socket` type, which is itself directly accessible for transport-level access to the network.

Two classes provide the TCP support: `TcpListener` and `TcpClient`. `TcpListener` listens for incoming connections, creating `Socket` instances that respond to the connection request. `TcpClient` connects to a remote host, hiding the details of the underlying socket in a `Stream`-derived type that allows stream I/O over the network.

A class called `UdpClient` provides the UDP support. `UdpClient` serves as both a client and a listener, and includes multicast support, allowing individual datagrams to be sent and received as byte arrays.

Both the TCP and the UDP classes help to access the underlying network socket (represented by the `Socket` class). The `Socket` class is a thin wrapper over the native Windows sockets functionality and is the lowest level of networking accessible to managed code.

The following example is a simple implementation of the Quote of the Day (qotd) protocol, as defined by the IETF in RFC 865. It demonstrates the use of a TCP listener to accept incoming requests and the use of the lower-level `Socket` type to fulfill the request:

```
// QOTDListener.cs
// Run QOTDListener.exe to service incoming QOTD requests
using System;
using System.Net;
using System.Net.Sockets;
using System.Text;
class QOTDListener {
    static string[ ] quotes =
{"Sufficiently advanced magic is indistinguishable from technology --
Terry Pratchett",
 "Sufficiently advanced technology is indistinguishable from magic --
Arthur C Clarke" };
    static void Main( ) {

        // Start a TCP listener on port 17
        TcpListener l = new TcpListener(17);
        l.Start( );
        Console.WriteLine("Waiting for clients to connect");
        Console.WriteLine("Press Ctrl+C to quit...");
        int numServed = 1;
        while (true) {

            // Block waiting for an incoming socket connect request
            Socket s = l.AcceptSocket( );
```

```
// Encode alternating quotes as bytes for sending
Char[ ] carr = quotes[numServed%2].ToCharArray( );
Byte[ ] barr = Encoding.ASCII.GetBytes(carr);

// Return data to client, then clean up socket & repeat
s.Send(barr, barr.Length, 0);
s.Shutdown(SocketShutdown.Both);
s.Close( );
    Console.WriteLine("{0} quotes served...", numServed++);
}
}
}
```

To test this example, run the listener and try connecting to port 17 on localhost using a telnet client. Under Windows 2000, this can be done from the command line by entering:

```
telnet localhost 17
```

Notice the use of `Socket.Shutdown` and `Socket.Close` at the end of the while loop; this is required to flush and close the socket immediately, rather than wait for the garbage collector to finalize and collect unreachable `Socket` objects later.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

9.7 Using DNS

The networking types in the base class library also support normal and reverse Domain Name System (DNS) resolution. Here's an example using these types:

```
// DNSLookup.cs
// Run DNSLookup.exe <servername> to determine IP addresses
using System;
using System.Net;
class DNSLookup {
    static void Main(string[ ] args) {
        IPEndPoint he = Dns.GetHostByName(args[0]);
        IPAddress[ ] addrs = he.AddressList;
        foreach (IPAddress addr in addrs)
            Console.WriteLine(addr);
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 10. Streams and I/O

Almost all nontrivial programs need to store and retrieve persistent data, whether in a database, on a local or remote file system, or over the network. Since this is a common need, many programming environments define an abstraction called a stream that is used to model reading and writing to/from files on disk. The .NET Framework supports this abstraction fully, and also extends it into other areas such as network I/O, buffering and in-memory operations, and cryptographic services.

This chapter introduces the built-in support for streams and I/O, explains the relationships between the abstract and concrete classes in the streams architecture, demonstrates their usage, and finally explores the filesystem-specific support. Unless otherwise stated, the types mentioned in this chapter all exist in the `System`, `System.IO`, or `System.IO.IsolatedStorage` namespaces.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

10.1 Streams and Backing Stores

The stream is a fundamental abstraction used throughout the .NET Framework to model access to persistent data. A stream represents the flow of data coming in and out of a backing store. A backing store represents the endpoint of a stream. Although a backing store is often a file or network connection, in reality it can represent any medium capable of reading or writing raw data.

A simple example is to use a stream to read and write to a file on disk. However, streams and backing stores are not limited to disk and network I/O. A more sophisticated example is to use the cryptography support in the .NET Framework to encrypt or decrypt a stream of bytes as they move around in memory.

10.1.1 The Abstract Stream Class

`Stream` is an abstract class that defines operations for reading and writing a stream of raw typeless data as bytes. Once a stream is opened, it stays open and can be read from or written to until the stream is flushed and closed. Flushing a stream updates the writes made to the stream; closing a stream first flushes the stream, then closes the stream.

`Stream` has the methods `CanRead`, `CanWrite`, and `CanSeek`, for streams that support only sequential access. If a stream supports random access, the `SetPosition` method can move to a linear position on that stream.

The `Stream` class provides synchronous and asynchronous read and write operations. By default, an asynchronous method calls the stream's corresponding synchronous method by wrapping the synchronous method in a delegate type and starting a new thread. Similarly, by default, a synchronous method calls the stream's corresponding asynchronous method and waits until the thread has completed its operation. Classes that derive from `Stream` must override either the synchronous or asynchronous methods but may override both sets of methods if the need arises.

10.1.2 Concrete Stream-Derived Classes

The framework includes a number of different concrete implementations of the abstract base class `Stream`. Each implementation represents a different storage medium and allows a raw stream of bytes to be read from and written to the backing store.

Examples of this include the `FileStream` class (which reads and writes bytes to and from a file), the `NetworkStream` class (which sends and receives bytes over the network), and the stream returned from the static `Stream.Null` property (which serves as `/dev/null` for this platform).

The following example creates a text file on disk and uses the abstract `File` type to write data to it:

```
using System.IO;
class StreamFun {
```



```
static void Main( ) {  
    Stream s = new FileStream("foo.txt", FileMode.Create);  
    s.WriteByte(67);  
    s.WriteByte(35);  
    s.Close( );  
}  
}
```

In addition, one stream may act as the frontend to another stream, performing additional processing on the underlying stream as needed. Examples of this include stream encryption/decryption and stream buffering.

The following is an example that converts the file output from the previous sample into its Base64 representation using the `CryptoStream` class:

```
using System;  
using System.IO;  
using System.Security.Cryptography;  
class EncoderFun {  
    static void Main( ) {  
        Stream stm = new FileStream("foo.txt", FileMode.Open, FileAccess.Read);  
        ICryptoTransform ict = new ToBase64Transform( );  
        CryptoStream cs = new CryptoStream(stm, ict, CryptoStreamMode.Read);  
        TextReader tr = new StreamReader(cs);  
        string s = tr.ReadToEnd( );  
        Console.WriteLine(s);  
    }  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

10.2 Encapsulating Raw Streams

While the `Stream` class reads and writes raw bytes, most programs prefer to produce and consume data either in the form of native data types or lines of text. To make this easy, the framework includes related pairs of `XXXReader/XXXWriter` classes that provide this higher-level, encapsulated access to the raw underlying data stream.

10.2.1 The `BinaryReader` and `BinaryWriter` Classes

`BinaryReader` and `BinaryWriter` are concrete classes that define operations for reading and writing a stream of native data types. The most fundamental operations of the `BinaryReader` and `BinaryWriter` classes are the methods that read and write instances of the primitive data types: `bool`, `byte`, `char`, `decimal`, `float`, `double`, `short`, `int`, `long`, `sbyte`, `ushort`, `uint`, and `ulong`. Additionally, methods are provided to read and write `strings` and arrays of the primitive data types.

Imagine we have a simple class, defined as follows, that we want to read and write from a stream:

```
public class Student {
    public string Name;
    public int    Age;
    public double GPA;
}
```

Methods that read and write instances of the `Student` class from a stream in a binary format might look like this:

```
void SaveToStream(Stream stm, Student s) {
    BinaryWriter bw = new BinaryWriter(stm);
    bw.Write(s.Name);
    bw.Write(s.Age);
    bw.Write(s.GPA);
    bw.Flush( ); // Ensure the BinaryWriter buffer is empty
}

void ReadFromStream(Stream stm, Student s) {
    BinaryReader br = new BinaryReader(stm);
    s.Name = br.ReadString( );
    s.Age = br.ReadInt32( );
    s.GPA = br.ReadDouble( );
}
```

10.2.2 The `Abstract TextReader` and `TextWriter` Classes

`TextReader` and `TextWriter` are abstract base classes that define operations for reading and writing a stream of characters. The most fundamental operations of the `TextReader` and `TextWriter` classes are the methods that read and write a single character to or from a stream.

The `TextReader` class provides default implementations for methods that read in an array of characters or a string representing a line of characters. The `TextWriter` class provides default implementations for methods that write an array of characters, as well as methods that convert common types (optionally with formatting options) to a sequence of characters.

The framework includes a number of different concrete implementations of the abstract base classes `TextReader` and `TextWriter`. Some of the most prominent include `StreamReader` and `StreamWriter`, and `StringReader` and `StringWriter`.

10.2.3 The StreamReader and StreamWriter Classes

`StreamReader` and `StreamWriter` are concrete classes that derive from `TextReader` and `TextWriter`, respectively, and operate on a `Stream` that may be passed as a constructor parameter.

These classes allow you to combine a `Stream` (which can have a backing store but knows only about raw data) with a `TextReader` or `TextWriter` (which knows about character data, but doesn't have a backing store).

In addition, `StreamReader` and `StreamWriter` can perform special translations between characters and raw bytes. Such translations include translating Unicode characters to ANSI characters to either big-endian or little-endian format.

Assuming the existence of a `Student` class as defined in the previous example, methods to read and write instances of the `Student` class to/from a stream in a binary format might look like this:

```
void SaveToStream(Stream stm, Student s) {
    TextWriter tw = new StreamWriter(stm);
    tw.WriteLine(s.Name);
    tw.WriteLine(s.Age);
    tw.WriteLine(s.GPA);
    tw.Flush( ); // Ensure the TextWriter buffer is empty
}
void ReadFromStream(Stream stm, Student s) {
    TextReader tr = new StreamReader(stm);
    s.Name = tr.ReadLine( );
    s.Age = Int32.Parse(tr.ReadLine( ));
    s.GPA = Double.Parse(tr.ReadLine( ));
}
```

10.2.4 The StringReader and StringWriter Classes

`StringReader` and `StringWriter` are concrete classes that derive from `TextReader` and `TextWriter`, respectively, and operate on a string or `StringBuilder`, which may be passed in as a constructor parameter.

The `StringReader` class can be thought of as the simplest possible read-only backing store, because it simply performs read operations on the underlying string. Also, the `StringWriter` class can be thought of as the simplest possible write-only backing store, because it simply performs write operations on that `StringBuilder`.

The following example uses a `StringWriter` wrapped around an underlying `StringBuilder` backing store to write to a string:

```
using System;
using System.IO;
using System.Text;
class Test {
    static void Main( ) {
        StringBuilder sb = new StringBuilder( );
        StringWriter sw = new StringWriter(sb);
        WriteHello(sw);
        Console.WriteLine(sb);
    }
    static void WriteHello(TextWriter tw) {
        tw.Write("Hello, String I/O!");
    }
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

10.3 Directories and Files

The `File` and `Directory` classes contain static methods and properties that encapsulate the operations typically associated with file I/O, such as copying, moving, deleting, renaming, and enumerating files and directories.

The actual manipulation of the contents of a file is done with a `FileStream`. The `File` class has methods that return a `FileStream`, though you may directly instantiate a `FileStream`.

10.3.1 Reading and Writing Files

This example reads in and prints out the first line of a text file specified on the command line:

```
using System;
using System.IO;
class FileDumper {
    static void Main(string[] args) {
        Stream s = File.OpenRead(args[0]);
        StreamReader sr = new StreamReader(s);
        Console.WriteLine(sr.ReadLine());
        sr.Close();
    }
}
```

10.3.2 Examining Directories

To examine the contents of the filesystem, use the `DirectoryInfo` and `FileInfo` classes, both of which are derived from a common `FileSystemInfo` base class. These provide access to most of the filesystem information, which the following example demonstrates by replicating the results of the `dir` command:

```
using System;
using System.IO;
using System.Text;
class DirCommand {
    static void Main() {
        long numFiles=0, numDirs=0, totalBytes=0;
        string currentDir = Directory.GetCurrentDirectory();
        DirectoryInfo currentDirInfo = new DirectoryInfo(currentDir);
        StringBuilder sb = new StringBuilder();
        sb.AppendFormat(" Directory of {0}\n\n", currentDirInfo.FullName);
        DirectoryInfo rootDirInfo = currentDirInfo.Root;
        if (rootDirInfo != null) {
            sb.AppendFormat("{0:dd/MM/yyyy  hh:mm tt}      <DIR>          .\n",
                           rootDirInfo.LastWriteTime);
        }
    }
}
```

```

        numDirs++;
    }
    DirectoryInfo parentDirInfo = currentDirInfo.Parent;
    if (parentDirInfo != null) {
        sb.AppendFormat("{0:dd/MM/yyyy hh:mm tt}      <DIR>                ..\n",
            parentDirInfo.LastWriteTime);
        numDirs++;
    }
    FileSystemInfo[] fsis = currentDirInfo.GetFileSystemInfos( );
    foreach (FileSystemInfo fsi in fsis) {
        FileInfo fi = fsi as FileInfo;
        if (fi != null) {
            sb.AppendFormat("{0:dd/MM/yyyy hh:mm tt}      {1,14:N0} {2}\n",
                fi.LastWriteTime, fi.Length, fi.Name);
            numFiles++;
            totalBytes += fi.Length;
        }
        DirectoryInfo di = fsi as DirectoryInfo;
        if (di != null) {
            sb.AppendFormat("{0:dd/MM/yyyy hh:mm tt}      <DIR>                {1}\n",
                di.LastWriteTime, di.Name);
            numDirs++;
        }
    }
    sb.AppendFormat("{0,16:G} File(s) {1,14:N0} bytes\n", numFiles,
        totalBytes);
    sb.AppendFormat("{0,16:G} Dir(s)\n", numDirs);
    Console.WriteLine(sb.ToString( ));
}
}

```

10.3.3 Catching Filesystem Events

To monitor a filesystem for changes (creation, modification, or deletion of a file, for example), use a `FileSystemWatcher` with the `FileSystemEventHandler`, `RenamedEventHandler`, and `ErrorEventHandler` delegates. `ErrorEventHandler` does not inform you of filesystem errors. Instead, it indicates that the `FileSystemWatcher`'s event buffer overflowed because it was overwhelmed by `Changed`, `Created`, `Deleted`, or `Renamed` events.

The following example monitors whatever directory you specify on the command line. Run it using the name of an existing directory, and then rename, delete, create, and modify some files in that directory:

```

// WatchFS.cs - use WatchFS.exe <path> to monitor file system
using System;
using System.IO;
using System.Threading;
class WatchFS {
    static void FSErrorCallback(object o, ErrorEventArgs eea) {
        Console.WriteLine("Error: {0}", eea.GetException( ).Message);
    }
}

```

```

static void FSRenamedCallback(object o, RenamedEventArgs rea) {
    Console.WriteLine("Renamed: {0}->{1}", rea.OldFullPath, rea.FullPath);
}
static void FSEventCallback(object o, FileSystemEventArgs fsea) {
    Console.WriteLine("Event: {0}->{1}", fsea.ChangeType, fsea.FullPath);
}
static void Main(string[] args) {
    // Register handlers for file system events
    FileSystemWatcher fsw = new FileSystemWatcher(args[0]);
    fsw.Changed += new FileSystemEventHandler(FSEventCallback);
    fsw.Created += new FileSystemEventHandler(FSEventCallback);
    fsw.Deleted += new FileSystemEventHandler(FSEventCallback);
    fsw.Renamed += new RenamedEventHandler(FSRenamedCallback);
    fsw.Error += new ErrorEventHandler(FSErrorCallback);
    fsw.EnableRaisingEvents = true;

    Console.WriteLine("Listening for events - press <enter> to end");
    Console.ReadLine(); // Wait for keypress to end
}
}

```

10.3.4 Asynchronous I/O

I/O doesn't always happen on your terms—all too often, it takes a lot more time than you would like. Since I/O tasks are not necessarily CPU-bound, your code might be free to do some other things while a large file transfer runs in the background. For example, your CPU could be busy handling user input, rather than hanging while your user saves a 10 MB file across a VPN connection that's riding on top of a 56K dialup session.

The .NET Framework provides an asynchronous I/O for these cases. The first thing to do is create a class to maintain state between asynchronous calls. The following example uses the `ReadState` class to maintain state. It contains a buffer, an input stream, an `AsyncCallback`, and a `StringBuilder`. The first three are needed only during the asynchronous calls. The last, which accumulates the contents of the stream during each call, is also used after all the calls have completed.

The `AsyncCallback` delegate is defined in `IOReadCallback`. It's responsible for pausing the asynchronous operation using `Stream.EndRead()`, appending the contents of the buffer to the `StringBuilder`, and restarting the operation with `Stream.BeginRead()`.

Inside the delegate, the arguments to `BeginRead()` are identical to those used in the first call to `BeginRead()`, which kicks off the asynchronous operation in the `Main()` method. Each call to `BeginRead()` returns an `IAsyncResult` object, which is a token that represents the asynchronous operation. While the asynchronous read is proceeding, the `Main()` method uses `System.Net.WebClient` to download a file. When it's done, it waits on the `IAsyncResult`'s `WaitHandle` until the entire file has been read. Then, it prints out the contents of the file.

```

// AsyncRead.cs - use AsyncRead.exe <filename> to test
using System;
using System.IO;
using System.Text;
class AsyncReadFun {
    class AsyncReadState {

```

```

    public Stream stm; // Underlying stream
    public byte[] buf = new byte[256]; // Read buffer
    public StringBuilder sb = new StringBuilder( ); // Result buffer
    public AsyncCallback acb = new AsyncCallback(AsyncReadCallback);
}
static void AsyncReadCallback(IAsyncResult iar) {
    AsyncReadState ars = (AsyncReadState)iar.AsyncState;
    int bytes = ars.stm.EndRead(iar); // Get count of bytes read
    if (bytes > 0) { // Copy read bytes and restart read
        ars.sb.Append(Encoding.ASCII.GetString(ars.buf, 0, bytes));
        Console.WriteLine("Read chunk of {0} bytes", bytes);
        ars.stm.BeginRead(ars.buf, 0, ars.buf.Length, ars.acb, ars);
    }
}
static void Main(string[] args) {
    // Open the stream & start reading
    Stream s = File.OpenRead(args[0]);
    AsyncReadState ars = new AsyncReadState( );
    ars.stm = s; // Save the stream reference
    IAsyncResult iar = s.BeginRead(ars.buf, 0, ars.buf.Length,
                                   ars.acb, ars);

    // Download a file while we're reading the stream
    System.Net.WebClient wc = new System.Net.WebClient( );
    wc.DownloadFile("http://www.oreilly.com", "index.html");
    Console.WriteLine("Finished downloading index.html.");
    iar.AsyncWaitHandle.WaitOne( ); // Wait until the async read is done
    Console.WriteLine(ars.sb);

}
}

```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

10.4 Isolated Storage

The .NET Framework's isolated storage classes create and manipulate data compartments that are unique to a user and an assembly. For example, suppose that the user *joe* runs the .NET application *someapp.exe*. If *someapp.exe* uses isolated storage to create directories and files, the .NET runtime guarantees that another program (such as *anotherapp.exe*) cannot access those files, even if *joe* runs *anotherapp.exe*. Further, if another user, *bob*, runs *someapp.exe*, he won't be able to access the files that *someapp.exe* created when *joe* ran it.

Isolated storage is limited by a quota, so even if it's manipulated by untrusted mobile code, you don't need to worry about that code performing a denial-of-service attack by filling your disk with useless data.

Where does isolated storage live? This depends on your operating system, but in Windows 2000 and XP, it is either found in *Documents and Settings\<username>\Local Settings\Application Data\Microsoft\IsolatedStorage* (the nonroaming profile) or in *Documents and Settings\<username>\Application Data\Microsoft\IsolatedStorage* (the roaming profile). For other operating systems, such as Windows NT 4.0 or Windows 98, see *Introduction to Isolated Storage* in the .NET Framework SDK documentation.

10.4.1 Reading and Writing Isolated Storage

To create or access a file in isolated storage, create an instance of `IsolatedStorageFileStream` (pass in the desired filename and combination of `FileMode` constants). If your assembly doesn't currently have an area of isolated storage set up, .NET creates it at this time. The following example creates a new file in isolated storage, writes some data to it, and then displays the contents of that file:

```
using System;
using System.IO;
using System.IO.IsolatedStorage;
class Isolated {
    static void WriteToIS( ) {
        // Create a file in isolated storage
        IsolatedStorageFileStream stm =
            new IsolatedStorageFileStream("test.txt", FileMode.Create);
        // Write some text to the stream
        StreamWriter sw = new StreamWriter(stm);
        sw.WriteLine("Hello, World");
        sw.Close( );
        stm.Close( );
    }
    static void ReadFromIS( ) {
        // Open an existing file in isolated storage
        IsolatedStorageFileStream stm =
            new IsolatedStorageFileStream("test.txt", FileMode.Open);
```

```

        // Read the file
        StreamReader sr = new StreamReader(stm);
        string s = sr.ReadToEnd( );
        sr.Close( );
        stm.Close( );
        Console.WriteLine(s);
    }
    static void Main( ) {
        WriteToIS( );
        ReadFromIS( );
    }
}

```

After running this sample you will find the resulting file in the appropriate *IsolatedStorage* folder for your operating system, as described in the previous section.

10.4.2 Enumerating the Contents of Isolated Storage

The .NET Framework includes the *storadm.exe* utility for listing (**/LIST**) the current user's isolated storage or for removing (**/REMOVE**) all of the user's isolated storage.

You can also access the current user's stores using *IsolatedStorageFile*. Use the static *IsolatedStorageFile.GetEnumerator()* method with an argument of *IsolatedStorageScope.User* to enumerate all the isolated storage for the current user. Once you have a store, you can inspect it or modify it, or open one of the files it contains by passing the store to the *IsolatedStorageFileStream* constructor.

```

using System;
using System.Collections;
using System.IO;
using System.IO.IsolatedStorage;
using System.Security.Policy;
class EnumIsolated {
    static void Main( ) {
        // Get all the current user's isolated stores
        IEnumerator ie =
            IsolatedStorageFile.GetEnumerator(IsolatedStorageScope.User);
        while (ie.MoveNext( )) {
            IsolatedStorageFile isf = (IsolatedStorageFile) e.Current;
            // Find the location of the associated assembly
            Url url = (Url)isf.AssemblyIdentity;
            Console.WriteLine("Assembly: {0}", url.Value);
            Console.WriteLine("Size: {0}", isf.CurrentSize);
            // List all the files in the store
            Console.WriteLine("Files:");
            string[] files = isf.GetFileNames("");
            foreach (string file in files) {
                IsolatedStorageFileStream isfs =
                    new IsolatedStorageFileStream(file, FileMode.Open, isf);
                Console.WriteLine(" {0}\t{1} bytes", file, isfs.Length);
            }
        }
    }
}

```

```
}  
}  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 11. Serialization

The .NET Framework includes extensive support for serialization and deserialization, allowing clients to explicitly and implicitly serialize object instances and arbitrarily complex object graphs, and allowing types a wide degree of control over how and where they are serialized and deserialized.

This chapter introduces the support for object serialization and deserialization that is built into the .NET Framework, and shows how clients and objects can participate in the serialization and deserialization process. Unless otherwise stated, the types mentioned in this chapter all exist in the `System` or `System.Runtime.Serialization` namespaces.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

11.1 What Is Serialization?

Some types are like mosquitoes: once instantiated, they live a short life near to where they were born, and then die quietly. Types such as these don't store important nontransient data and are used by clients in the same context they were created in. These types are trivial, and generally don't need serialization. However, many important types are not like this, storing data that needs to be persisted to some backing store (e.g. a database, file, or network), or being passed back and forth between different contexts as parameters in method calls. These types need to support serialization.

Serialization is the act of taking an in-memory object or object graph and flattening it into a stream of bytes that may be stored or transmitted. Deserialization works in reverse, taking a stream of bytes and reconstituting it into an in-memory object instance or object graph. Serialization and deserialization can happen either explicitly or implicitly, but the basic mechanism remains the same.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.2 Serialization Support in the Framework

The .NET Framework includes extensive support for both serialization and deserialization, both from the perspective of clients wanting to serialize and deserialize objects, and from the perspective of types wanting some control over how and where they are serialized. This support is found in two sets of namespaces: `System.Runtime.Serialization.*` and `System.Xml.Serialization.*`.

Each of these namespaces includes a suite of types that, together with your types, form a serialization "engine," which has the ability to serialize one or more objects into a stream of some kind. Additionally, each of these namespaces supports XML as a serialization format (the `System.Runtime.Serialization.*` namespaces also support a binary serialization format).

The primary differences between the two serialization engines are that the one contained in the `System.Runtime.Serialization.*` namespaces supports arbitrary object graphs and can serialize any .NET type using SOAP Section 5 encoding. However, this engine produces XML that is very CLR-centric, describing primitive types using XML namespaces and schemas that assume the reader understands the CLR type system. On the other hand, the serialization engine contained in the `System.Xml.Serialization.*` namespaces produces very clean XSD schemas and matching XML instances, describing primitive types in terms of XSD data types wherever possible. However, it cannot handle arbitrary object graphs, and in some cases doesn't support all of the CLR paradigms naturally.

While both serialization engines fulfill valid (and different) needs, the rest of this chapter concentrates on the `System.Runtime.Serialization.*` serialization support because of its natural advantages for serializing the widest possible range of types in a CLR-centric manner.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.3 Explicit Serialization

Consider a case in which a client wants to serialize a complex graph of objects to a file on disk. Furthermore, let's assume that the objects already support serialization (if not, the client's job is much harder). Fundamentally, there are two things the client needs to initiate an explicit serialization: an **object** reference identifying the root of the object graph, and a **Stream** reference identifying the place to serialize the object graph to.

Given these two references, the client needs some way to initiate the serialization and deserialization process. Since this is a common need, the Framework defines a standard interface called **IFormatter** that provides **Serialize** and **Deserialize** methods that work in terms of **object** and **Stream** references.

The Framework also provides two concrete implementations of this interface: the **BinaryFormatter** class (which lives in the **System.Runtime.Serialization.Formatters.Binary** namespace, and serializes object graphs using a binary format), and the **SoapFormatter** class (which lives in the **System.Runtime.Serialization.Formatters.Soap** namespace, and serializes object graphs as XML using SOAP Section 5 encoding rules).

Using these classes, clients can serialize graphs of objects with almost no code:

```
public void SerializeGraph(string file, object root) {
    Stream stm = new FileStream(file, FileMode.Create);
    IFormatter fmt = new BinaryFormatter( );
    fmt.Serialize(stm, root);
    stm.Flush( );
    stm.Close( );
}
```

When passed a target filename and the root of an object graph supporting serialization, **SerializeGraph** creates a new file and serializes the object graph into it in a binary format. Changing the serialization format to an XML representation of the object graph (using SOAP Section 5 encoding rules) is as simple as replacing the call to instantiate the **BinaryFormatter** with one to instantiate a **SoapFormatter**.

Deserialization is just as simple-the following code assumes an XML serialization format, and deserializes the contents of a file into an in-memory object graph. To use the **object** reference returned by the function in client code, downcast to the appropriate type:

```
public object DeserializeGraph(string file) {
    Stream stm = new FileStream(file, FileMode.Open);
    IFormatter fmt = new SoapFormatter( );
    object o = fmt.Deserialize(stm);
    stm.Close( );
    return o;
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.4 Implicit Serialization

Not all serialization and deserialization is explicit. Consider the following set of serializable classes:

```
[Serializable]
public sealed class Person {
    public string Name;
    public int Age;
}
```

```
[Serializable]
public sealed class Team {
    public string Name;
    public Person[] Players;
}
```

Serializing an instance of `Team` causes the embedded array of `Person` instances to implicitly be serialized.

Additionally, types can be serialized as part of method invocations. For example, imagine a function that merges two `Teams` using some complex algorithm, declared as follows:

```
public Team MergeTeams(Team teamOne, Team teamTwo) {...}
```

If instances of the type containing this method were always created and then used from within the same `AppDomain`, the calling code and the method itself could share the `Team` references. However, if we want to invoke this method from outside the `AppDomain` it was created in (or even from off the machine it was created on), the method invocation needs to be remoted across the `AppDomain` machine boundary.

While the remoting process and the supporting infrastructure in the Framework is rich, powerful, and complex, this chapter doesn't delve into remoting. However, it is helpful to understand that one of the steps in remoting involves turning a method call into a pair of request and response messages that can be transmitted across `AppDomain` or machine boundaries. If the `MergeTeams` method is remoted, the `teamOne` and `teamTwo` parameters are implicitly serialized into the request message by the same serialization infrastructure we used explicitly earlier in the chapter, and the resulting merged `Team` instance is implicitly serialized into the response message on method completion.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.5 [Serializable]

In the preceding examples we assumed for simplicity's sake that the object graph was serializable, and we focused on how serialization and deserialization occurred. Now let's spend some time defining what it means for an object or object graph to be serializable, and how to mark your classes and structs as such.

Types that should support being serialized and deserialized by the runtime must be marked with the `[Serializable]` attribute, as follows:

```
[Serializable]
public sealed class Person {
    public string Name;
    public int Age;
}
```

This sets a special `serializable` bit in the metadata for the type that instructs the runtime to provide serialization and deserialization support. The `[Serializable]` attribute is not inherited, thus derived types are not automatically serializable. To provide for the serialization of derived types, mark each type as `[Serializable]`.

As we saw earlier in the section "Implicit Serialization," serializing a type implicitly serializes all members of the type, recursively. This implies that all members of a type must themselves be serializable for the type to successfully serialize. This is true regardless of the accessibility of the members. For example, if you modify the `Person` class as follows, it will no longer be serializable:

```
[Serializable]
public sealed class Person {
    public string Name;
    public int Age;
    private Company Employer; // Person no longer Serializable!
}

public class Company {...}
```

Attempting to serialize an instance of `Person` now results in a `SerializationException` being thrown.

Although the combination of the `[Serializable]` attribute and the runtime's built-in support for serializing arbitrary object graphs is powerful, it doesn't give you much control over the serialization and deserialization process. However, there are several other ways for a type to participate in serialization, as we shall see.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.6 [NonSerialized]

Even types with large amounts of important nontransient data sometimes contain members that are not appropriate for serialization. Common examples of transient members are fields that hold resources, such as file or window handles, that would not make sense on another machine or at a later time. Other examples of transient members that do not deserve to be serialized are fields that were calculated and cached in the type, but can be recreated from other, nontransient members. Lastly, a type may sometimes need to contain a member that is not serializable, yet still support serialization of the rest of the type.

To instruct the runtime's serialization engine to ignore a member when serializing a type, mark it with the `[NonSerialized]` attribute, as follows:

```
[Serializable]
public sealed class Person {
    public string Name;
    public DateTime DateOfBirth;
    [NonSerialized] public int Age; // Can be calculated
    // Rest of class...
}
```

When serializing an instance of `Person`, the runtime ignores the `Age` member and does not write it to the output stream. Similarly, when deserializing an instance of `Person`, the input stream does not contain data for the `Age` member, which is set to the bit pattern representing 0 (i.e., `null` for references, `0` for integrals, etc.). Consequently, when using an object instance of a type such as `Person` that has been deserialized, remember to watch out for null and zeroed members.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

11.7 IDeserializationCallback

It is helpful to think of deserialization as a special form of constructor call, since the end result is a valid object reference. While the `[NonSerialized]` attribute is useful for controlling which data is stored in the serialized form of the object or sent over the wire on a remoting call, the problem is that the fields marked with `[NonSerialized]` are not assigned meaningful values when the constructor (i.e., the deserialization process) finishes executing. This can result in class invariants being violated, such as the implicit in the preceding sample, in which `Age` is intended to store the `Person`'s age based on the `DateOfBirth`.

One possible solution to this problem is the `IDeserializationCallback` interface. Implementing this interface on your type indicates to the runtime that you wish to participate in the deserialization process. This interface contains a single method, `OnDeserialization`, which the runtime invokes after it has finished constructing your object, but before it returns the fully constructed instance to the client. This method gives you a chance to perform whatever fixups you need to inside the object, and is a way to ensure that class invariants are preserved before clients can access the instance.

Using our sample `Person` class, the `IDeserializationCallback` interface implementation might look like this:

```
[Serializable]
public sealed class Person : IDeserializationCallback {
    public string Name;
    public DateTime DateOfBirth;
    [NonSerialized] public int Age; // Can be calculated
    public void OnDeserialization(object o) {
        TimeSpan ts = DateTime.Now - DateOfBirth;
        Age = ts.Days/365; // Rough age in years
    }

    // Rest of class...
}
```

By combining the `[Serializable]` attribute with the `[NonSerialized]` attribute and the `IDeserializationCallback` interface, it is possible to add serialization support to complex object graphs with relatively little code.

11.8 ISerializable

As flexible as the preceding approaches are, they still constrain the type implementer somewhat. Type implementers who need the serialized format to use different names than the in-memory members, or who need the mapping of members to serialized data to be something other than 1:1, or who would like to serialize as one type and deserialize as another (proxy) type, may want to take control of their own serialization via `ISerializable` and the other interfaces and attributes that make up the serialization architecture.

To indicate to the runtime that it wants to fully control serialization and deserialization, a type implements the `ISerializable` interface, which looks like this:

```
namespace System.Runtime.Serialization {
    public interface ISerializable {
        void GetObjectData(SerializationInfo si, StreamingContext sc);
    }
}
```

The `SerializationInfo` parameter is a reference to a property bag^[1] that you should store the type member values in. Additionally, `SerializationInfo` also contains properties that you can use to control the type and assembly the instance should deserialize as. The `StreamingContext` parameter is a structure that contains, among other things, an enumeration value indicating where the serialized instance is headed (to disk, into the remoting plumbing, etc.).

^[1] A common data structure storing a collection of key/value pairs; also known as a hashtable or dictionary.

In addition to implementing `ISerializable`, a type that is controlling its own serialization needs to provide a deserialization constructor that takes two parameters: a `SerializationInfo` object reference and a `StreamingContext` structure. The accessibility of this constructor is not important, and can even be `private` to prevent other clients from using it to create unofficial instances.

Putting this together with the `Teams` class from the previous example, an implementation of `ISerializable` with a deserialization constructor might look like the following:

```
[Serializable]
public sealed class Team : ISerializable {
    public string Name;
    public Person[] Players;
    public void GetObjectData(SerializationInfo si, StreamingContext sc) {
        si.AddValue("IChangedTheFieldName", Name);
        si.AddValue("Players", Players);
    }
    private Team(SerializationInfo si, StreamingContext sc) {
        Name = si.GetString("IChangedTheFieldName");
        Players = (Person[])si.GetValue("Players", typeof(Person[]));
    }
    // Rest of class...
}
```

This implementation of the deserialization constructor is illustrative, but not robust-real implementations should consider comparing the version of the deserializing type with the version in the `SerializationInfo`'s `AssemblyName` property to detect version mismatches and code accordingly.

[\[Team LiB \]](#)

[← PREVIOUS](#) [NEXT →](#)

11.9 [Serializable] and ISerializable

Eagle-eyed readers will have noticed that in all the preceding examples the classes are **sealed**. This is no accident. Marking a class as **[Serializable]** and deciding whether to implement **ISerializable** has some specific implications for both base and derived types, and deserves separate discussion.

Consider the following serializable class hierarchy:

```
[Serializable]
public class Person {
    public string Name;
    public int Age;
    // Rest of class...
}

[Serializable]
public sealed class Student: Person {
    public string Course;
    // Rest of class...
}
```

In this example both **Person** and **Student** are serializable, and both classes use the default runtime serialization behavior since neither class implements **ISerializable**.

Now imagine that the developer of **Person** decides for some reason to implement **ISerializable** and provide a deserialization constructor to control **Person** serialization. The new version of **Person** might look like this:

```
[Serializable]
public class Person : ISerialization {
    public string Name;
    public int Age;
    public void GetObjectData(SerializationInfo si, StreamingContext sc) {
        si.AddValue("IChangedTheNameFieldName", Name);
        si.AddValue("IChangedTheAgeFieldName", Age);
    }
    protected Person(SerializationInfo si, StreamingContext sc) {
        Name = si.GetString("IChangedTheNameFieldName");
        Age = sc.GetInt32("IChangedTheAgeFieldName");
    }
    // Rest of class...
}
```

Although this works for instances of **Person**, this change breaks serialization of **Student** instances. Serializing a **Student** instance would appear to succeed, but the **Course** field in the **Student** type isn't saved to the stream because the implementation of **ISerializable.GetObjectData** on **Person** has no knowledge of the members of the **Student** derived type. Additionally, deserialization of

`Student` instances throws an exception since the runtime is looking (unsuccessfully) for a deserialization constructor on `Student`.

Fundamentally, if a base class implements `ISerializable` and the other serialization-related interfaces and base classes, derived classes need to follow suit. There are a several ways of accomplishing this. One option is for the base class to declare `GetObjectData` as `virtual`, allowing derived classes to simply override it as needed and call up the base type's `GetObjectData` as needed. Another option is for the derived class to reimplement `ISerializable` using explicit interface implementation, calling up to the base implementation as needed. In all cases, derived types need to provide deserialization constructors, and chain up to the base deserialization constructor as needed. An implementation of `Student` that takes the latter approach looks like this:

```
[Serializable]
public sealed class Student : Person, ISerialization {
    public string Course;
    void ISerialization.GetObjectData(SerializationInfo si,
                                      StreamingContext sc) {
        si.AddValue("IChangedTheCourseFieldName", Course);
        base.GetObjectData(si, sc);
    }
    private Student(SerializationInfo si, StreamingContext sc)
        : base(si, sc) {
        Course = si.GetString("IChangedTheCourseFieldName");
    }
    // Rest of class...
}
```

Now imagine a case in which the developer of `Person` elects not to implement `ISerializable`, relying instead on the default runtime serialization behavior. A derived type such as `Student` wishing to control its serialization by implementing `ISerializable` needs to ensure that the `Person` members are correctly serialized as part of the `GetObjectData` call, and correctly initialized by the `Student` deserialization constructor. While this could be performed manually in the derived type for `public` and `protected` members of the base type, the problem remains for `private` members of the base type that need serialization and deserialization.

The problem is that `Person` does not have an `ISerializable.GetObjectData` method or a deserialization constructor that the `Student` type can delegate to. The solution to this problem is the `FormatterServices` class, which provides a standard way to retrieve the list of all members in a type that need to be serialized (`GetSerializableMembers`), as well as a standard way to retrieve a serialized representation of these members (`GetObjectData`), and a standard way to deserialize this representation back into a new instance (`PopulateObjectMembers`). An implementation of `Student` that uses `FormatterServices` looks like this:

```
[Serializable]
public sealed class Student : Person, ISerializable {
    public string Course;
    public void GetObjectData(SerializationInfo si, StreamingContext sc) {
        Type t = typeof(Person);
        MemberInfo[] mbrs = FormatterServices.GetSerializableMembers(t);
        object[] data = FormatterServices.GetObjectData(this, mbrs);
        si.AddValue("BaseData", data);
        si.AddValue("IChangedTheCourseFieldName", Course);
    }
}
```

```
}  
private Student(SerializationInfo si, StreamingContext sc) {  
    Type t = typeof(Person);  
    MemberInfo[ ] mbrs = FormatterServices.GetSerializableMembers( );  
    object[ ] data = (object[ ])si.GetValue("BaseData", typeof(object[ ]));  
    FormatterServices.PopulateObjectMembers(this, mbrs, data);  
    Course = si.GetString("IChangedTheCourseFieldName");  
}  
// Rest of class...  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 12. Assemblies

An assembly is a logical package (similar to a DLL in Win32) that consists of a manifest, a set of one or more modules, and an optional set of resources. This package forms the basic unit of deployment and versioning, and creates a boundary for type resolution and security permissioning.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

12.1 Elements of an Assembly

Every .NET application consists of at least one assembly, which is in turn built from a number of three basic elements: a manifest, modules, and resources.

The manifest contains a set of metadata that describes everything the runtime needs to know about the assembly. This information includes:

- The simple name of the assembly
- The version number of the assembly
- An optional originator public key and assembly hash
- The list of files in the assembly, with file hashes
- The list of referenced assemblies, including versioning information and an optional public key
- The list of types included in the assembly, with a mapping to the module containing the type
- The set of minimum and optional security permissions requested by the assembly
- The set of security permissions explicitly refused by the assembly
- Culture, processor, and OS information
- A set of custom attributes to capture details such as product name, owner information, etc.

Modules are Portable Executable (PE) files that contain types described using metadata and implemented using MSIL. Additionally, modules have module manifests that define the external assemblies they are dependent on.

Resources contain nonexecutable data that is logically included with the assembly. Examples of this include bitmaps, localizable text, persisted objects, and so on.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.2 Assemblies and Modules

The simplest assembly contains an assembly manifest and a single module containing the application's types, packaged as an EXE with a **Main** entry point. More complex assemblies may be composed of multiple modules (PE files), separate resource files, manifest, etc.

The element that defines the presence of an assembly is termed the assembly manifest. The assembly manifest is not a physical construct, but rather a set of metadata that can either be included in one of the existing PE files in the assembly, or can live in a standalone PE file.

An assembly may also contain multiple modules. This technique can increase the performance of applications that use assemblies that are loaded over the network, since the CLR only loads modules as the types contained within them are needed. In addition, each module can be written in a different language, allowing a mixture of C#, VB.NET, and raw MSIL. Although not common, a single module could also be included in several different assemblies. When using multimodule assemblies, the convention is for the module PE files to have a **.netmodule** extension.

Finally, an assembly may contain a set of resources, which can either be kept in standalone files or included in one of the PE files in the assembly.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.3 Scoping Types and Type References

The assembly boundary also forms a type accessibility boundary: the C# `internal` accessibility modifier allows types to restrict method accessibility to a single assembly.

Additionally, references to types are always scoped by the assembly in which the type resides-the unique reference for a type (known as a `TypeRef`) is the combination of a reference to the assembly it was defined in and the fully qualified type name including any namespaces. For example, this local variable declaration:

```
System.Net.WebRequest wr;
```

is represented in MSIL as follows:

```
.assembly extern System.Net { .ver 1:0:2914:16 ... }  
.locals(class [System.Net]System.Net.WebRequest wr)
```

As you can see from this example, in order to reference a type unambiguously, we need to be able to identify the assembly that contains it unambiguously. The .NET Framework's mechanism for naming assemblies is very powerful, and is a giant step beyond the use of ProgIDs and GUIDs in classic COM development.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.4 Naming and Signing Assemblies

Assemblies are identified with a four-part name, consisting of:

- The simple name of the assembly
- The version number of the assembly
- An optional originator public key (and associated digital signature)
- An optional set of culture information

The assembly's simple name is defined in the assembly manifest, and is generally the same as the name of the module that contains the manifest, minus the extension (i.e., the simple name for the assembly `MyAssembly.dll` is `MyAssembly`).

The assembly's version number is divided into four parts and looks like this:

`<major>.<minor>.<build>.<revision>`

The `System.Reflection.AssemblyVersionAttribute` assembly-level custom attribute allows you to specify either a full or partial version number for the assembly, as well as allowing you to have the `<build>` and `<revision>` portions of the version number automatically change for each build. For example, apply the following custom attribute to an assembly:

```
using System.Reflection;
[assembly: AssemblyVersion("1.0.0.*")]
```

This results in an assembly in which the revision number is different every time the assembly is compiled. This represents the number of seconds since midnight, divided by two, since the day the assembly was built.

Assemblies can also be digitally signed using public-key technology to identify the developer (known as the "originator") and to detect tampering with the assembly after it has been signed. When an assembly is signed, an eight-byte originator ID (known as a public-key token) forms part of the assembly's name.

In order to sign an assembly, the originator needs to first generate an RSA public/private key pair, which can be done using the `sn.exe` utility, as follows:

```
sn.exe -k PublicPrivate.snk
```

This generates a file (`PublicPrivate.snk`) containing both a 128-byte RSA public key and a matching private key.

Once this is done, the `System.Reflection.AssemblyKeyFileAttribute` assembly-level custom attribute is used to tell the compiler where to find the key pair. This attribute also tells the compiler that after generating the assembly it should sign it with the private key, insert the signature into the PE file, and add the public key to the assembly manifest.

```
using System.Reflection;
[assembly:AssemblyKeyFile("PublicPrivate.snk")]
```

The presence of this additional information in the PE file and assembly manifest allows the CLR to, before loading the assembly at runtime, verify that it hasn't been tampered with. The *sn.exe* utility can also be used to manually verify that a signed assembly has not been tampered with, by using the *-v* option:

```
sn.exe -v MyAssembly.dll
```

Additionally, clients that use types from a signed assembly include a simplified 8-byte MD5 hash of the public key (again, this is known as a public key token) directly in the assembly reference.

This further protects clients, since re-signing an assembly that has been tampered with either requires the originator's private key (something most originators guard closely), or the use of a different public/private key pair. In the latter case, the public key token for the new key pair doesn't match the original public key token embedded in the client's assembly reference, and the modified assembly is not loaded.

To determine what the public key token is for a given originator's public/private key pair, use the *sn.exe* utility with the *-T* (for assemblies) or with *-t* (for public-key-only keyfiles), as follows:

```
sn.exe -T MyAssembly.dll
sn.exe -t Public.snk
```

Since the originator's private key is so critical, some organizations prefer to centralize signing authority, and not to distribute the key widely even within the organization. It is also possible to delay-sign an assembly, in which the compiler embeds the public key in the manifest and preserves space in the PE file for the signature, but doesn't actually sign the assembly.

The first step in this procedure is to generate a file that only contains the public key:

```
sn.exe -p PublicPrivate.snk Public.snk
```

The resulting *Public.snk* file can then be used in place of the *PublicPrivate.snk* file. Additionally, the *System.Reflection.AssemblyDelaySign* attribute is used to tell the compiler we wish to delay-sign the assembly:

```
using System.Reflection;
[assembly:AssemblyKeyFile("Public.snk")]
[assembly:AssemblyDelaySign(true)]
```

The resulting assembly can be used almost identically to normally signed assemblies for development purposes, except it cannot be placed in the Global Assembly Cache and it cannot be verified with *sn.exe*.

Delay-signing the assembly means that the compiler (and consequently, the developers) only needs access to the public key. At some later point a trusted member of the organization can use the *sn.exe* tool and the closely guarded private key to re-sign the assembly, which inserts the appropriate digital signature in the PE file. This is done using the *sn.exe* utility, as follows:

```
sn.exe -R MyAssembly.dll PublicPrivate.snk
```

Once the assembly has been re-signed, it can be verified using *sn.exe* and placed in the GAC using *gacutil.exe*.

The final part of the assembly name is the culture information. This is used when the assembly contains only culture-specific resources such as localized strings, dialogs, and other interface elements. The culture is controlled by the presence of the `System.Reflection.AssemblyCulture` custom attribute on the assembly, as follows:

```
using System.Reflection;
[assembly:AssemblyCulture("en-US")]
```

If no culture is specified, the assembly is considered to be culture-neutral.

When combined, the four elements name, version, culture and originator make up a unique identifier (known as an `AssemblyRef`) for an assembly, which is part of a `TypeRef` to unambiguously identify a type.

To allow user code to refer to a unique assembly in this way (e.g., for programmatic loading of assemblies via reflection), these four elements can be combined in a stringified, human-readable format known as the assembly display name. The display name is built up from the four elements like this:

```
<name>, Version=<version>, Culture=<culture>, PublicKeyToken=<originator>
```

The display name may be used as input to the `System.Reflection.Assembly.Load` method, as follows:

```
Assembly a = Assembly.Load(@"MyAssembly, Version="1.0.0.0",
                          Culture=neutral, PublicKeyToken=70e2f3b624e8bfa5");
```

[Team LiB]

[< PREVIOUS](#)
[NEXT >](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.5 Resolving and Loading Assemblies

At the point that the CLR first needs to access the metadata for a type (e.g., when JIT-ing methods that use the type), it must first locate and load the assembly containing the type. The process of determining exactly which assembly to load is called "resolving," and is performed by the assembly resolver. Once the assembly resolver has determined which physical file to load, the assembly loader is responsible for loading it into memory.

The assembly resolver performs a relatively complex set of operations, controlled by application and machine-level configuration files. These configuration files can tell the resolver to bind to a different version of the assembly than specified in the assembly reference, and can give the resolver hints about where to look for the physical file the loader should load (either at a URI endpoint, or in subdirectories under the application directory).

Once the resolver has identified which file to load and has verified that the name, version, culture, and originator information in the assembly manifest in the located file matches what the resolver is expecting, it hands off to the loader, which physically loads and verifies the file.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.6 Deployment

An assembly is the smallest .NET unit of deployment. Due to the self-describing nature of a manifest, deployment can be as simple as copying the assembly (and in the case of a multifile assembly, all the associated files) into the application directory.

This is a vast improvement over traditional COM development, in which components, their supporting DLLs, and their configuration information are spread out over multiple directories and the Windows registry.

In many cases, we want to share assemblies between applications. The foremost way to do this is to sign the assemblies, then place them in the machine-wide global assembly cache (GAC), which all applications have access to. The assembly resolver always consults the GAC before looking elsewhere for the assembly, so this is the fastest option.

Next, assemblies may be deployed at *http:* and *file:* URI endpoints. To do this, deploy them in the correct location and use the application and machine configuration files to tell the assembly resolver where to look using the `<codeBase>` element. (See the .NET Framework SDK documentation for the specific format of the configuration files.)

Lastly, if we do not wish to share assemblies between applications, we can place them in or beneath the application directory. When deployed in this way, the assembly resolver finds them by probing for a file with the name matching the simple name of the assembly and either a *.dll* or *.exe* extension. The directories that the resolver probes in follow a well-defined set of rules (see the .NET Framework SDK documentation for more details) and can be controlled by the configuration files with the `<probing>` element.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

12.7 Security Permissions

The assembly forms a boundary for security permissioning. The assembly manifest contains hashes for any referenced assemblies (determined at compile time), a list of the minimum set of security permissions the assembly requires in order to function, a list of the optional permissions that it requests, and a list of the permissions that it explicitly refuses (i.e., never wants to receive).

To illustrate how these permissions might be used, imagine an email client similar to Microsoft Outlook, developed using the .NET Framework. It probably requires the ability to communicate over the network on ports 110 (POP3), 25 (SMTP), and 143 (IMAP4). It might request the ability to run JavaScript functions in a sandbox to allow full interactivity when presenting HTML emails. Finally, it probably refuses ever being granted the ability to write to disk or read the local address book, thus avoiding scripting attacks such as the ILoveYou virus.

Essentially, the assembly declares its security needs and assumptions, but leaves the final decision on permissioning up to the CLR, which enforces local security policy.

At runtime the CLR uses the hashes to determine whether a dependent assembly has been tampered with, and combines the assembly permission information with local security policy to determine whether to load the assembly and which permissions to grant it.

This mechanism provides fine-grained control over security and is a major advantage of the .NET Framework over traditional Windows applications.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 13. Reflection

Many of the services available in .NET and exposed via C# (such as late binding, serialization, remoting, attributes, etc.) depend on the presence of metadata. Your own programs can also take advantage of this metadata, and even extend it with new information. Examining existing types via their metadata is called *reflection*, and is done using a rich set of types in the `System.Reflection` namespace. It is also possible to dynamically create new types at runtime via the classes in the `System.Reflection.Emit` namespace. You can extend the metadata for existing types with custom attributes. For more information, see [Chapter 14](#).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

13.1 Type Hierarchy


Reflection involves traversing and manipulating an object model that represents an application, including all its compile-time and runtime elements. Consequently, it is important to understand the various logical units of a .NET application and their roles and relationships.

The fundamental units of an application are its types, which contain members and nested types. Types are contained in modules, which are composed into assemblies. All these elements are described with metadata. Metadata is generally produced by the compiler at compile time, although it may also be created on the fly via `Reflection.Emit` (which is described in the later section "Creating New Types at Runtime").

At runtime, these elements are all contained within an `AppDomain`. An `AppDomain` isn't described with metadata, yet it plays an important role in reflection because it forms a logical process that a .NET application runs in.


Each of these elements is exposed via a matching type from the `System` or `System.Reflection` namespaces. [Figure 13-1](#) shows the inheritance hierarchy for key reflection types.

Figure 13-1. Inheritance relationships among the .NET reflection types



Given a reference to any of these elements, you can navigate the relationships between it and the related elements, as shown in [Figure 13-2](#).

Figure 13-2. Traversing the .NET reflection hierarchy



[[Team LiB](#)]

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

13.2 Types, Members, and Nested Types

The most basic element that reflection deals with is the `Type` class. This class represents the metadata for each type declaration in an application (both predefined and user-defined types).

Types contain members, which include constructors, fields, properties, events, and methods. In addition, types may contain nested types, which exist within the scope of an outer type and are typically used as helper classes. Types are grouped into modules, which are, in turn, contained within assemblies.

13.2.1 Assemblies and Modules

Assemblies are the logical equivalent of DLLs in Win32 and the basic unit of deployment, versioning, and reuse for types. In addition, assemblies create a security, visibility, and scope resolution boundary for types (for more information, see [Chapter 12](#)).

A module is a physical file such as a DLL, an EXE, or a resource (such as GIFs or JPGs). While it isn't common practice, an assembly can be composed of multiple modules, allowing you to control application working set size, use multiple languages within one assembly, and share a module across multiple assemblies.

13.2.2 AppDomains

From the perspective of reflection, an `AppDomain` is the root of the type hierarchy and serves as the container for assemblies and types when they are loaded into memory at runtime. A helpful way to think about an `AppDomain` is to view it as the logical equivalent of a process in a Win32 application.

`AppDomains` provide isolation, creating a hard boundary for managed code just like the process boundary under Win32. Similar to processes, `AppDomains` can be started and stopped independently, and application faults take down only the `AppDomain` the fault occurs in, not the process hosting the `AppDomain`.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

13.3 Retrieving the Type for an Instance

At the heart of reflection is `System.Type`, which is an abstract base class that provides access to the metadata of a type.

You can access the `Type` class for any instance using `GetType()`, which is a method implemented on `System.Object`. When you call `GetType()`, the method returns a concrete subtype of `System.Type`, which can reflect over and manipulate the type.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

13.4 Retrieving a Type Directly

You can also retrieve a `Type` class by name (without needing an instance) using the static method `GetType` on the `Type` class. When specifying which type to retrieve, you can provide either the namespace-qualified name of the type, or the assembly-qualified name, as follows:

```
Type t = Type.GetType("System.Int32");  
Type t2 = Type.GetType("MyNamespace.MyType, MyAssembly");
```

In the case in which you provide only the namespace-qualified name, `GetType` looks first in the calling assembly, and then in *mscorlib.dll*.

Finally, C# provides the `typeof` operator, which returns the `Type` class for any type known at compile time:

```
Type t = typeof(System.Int32);
```

The main difference between these two approaches is that `Type.GetType` is evaluated at runtime and thus is more dynamic, binding to a type in an assembly by name, while the `typeof` operator is evaluated at compile time and thus is slightly faster, binding to a type in a specific assembly version via a type token.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

13.5 Reflecting Over a Type Hierarchy

Once you have retrieved a `Type` instance, you can navigate the application hierarchy described earlier, accessing the metadata via types that represent members, modules, assemblies, namespaces, `AppDomains`, and nested types. You can also inspect the metadata and any custom attributes, create new instances of the types, and invoke members.

Here is an example that uses reflection to display the members in three different types:

```
using System;
using System.Reflection;
class Test {
    static void Main( ) {
        object o = new Object( );
        DumpTypeInfo(o.GetType( ));
        DumpTypeInfo(typeof(int));
        DumpTypeInfo(Type.GetType("System.String"));
    }
    static void DumpTypeInfo(Type t) {
        Console.WriteLine("Type: {0}", t);

        // Retrieve the list of members in the type
        MemberInfo[] miarr = t.GetMembers( );

        // Print out details on each of them
        foreach (MemberInfo mi in miarr)
            Console.WriteLine(" {0}={1}", mi.MemberType, mi);
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

13.6 Late Binding

Reflection can also perform late binding, in which the application dynamically loads, instantiates, and uses a type at runtime. This provides greater flexibility at the expense of invocation overhead.

In this section, we create an example that uses very late binding, dynamically discovers new types at runtime, and uses them as well.

In the next example, one or more assemblies are loaded by name (as specified on the command line). The example then iterates through the types in the assembly looking for subtypes of the `Greeting` abstract base class. When one is found, the type is instantiated and its `SayHello()` method invoked, which displays an appropriate greeting.

To perform the runtime discovery of types, we use an abstract base class that's compiled into an assembly as follows (see the source comment for filename and compilation information):

```
// Greeting.cs - compile with /t:library
public abstract class Greeting {
    public abstract void SayHello( );
}
```

Compiling this code produces a file named *Greeting.dll*, which the other parts of the sample can use.

We now create a new assembly containing two concrete subtypes of the abstract type `Greeting`, as follows (see the source comment for filename and compilation information):

```
// English.cs - compile with /t:library /r:Greeting.dll
using System;
public class AmericanGreeting : Greeting {
    private string msg = "Hey, dude. Wassup!";
    public override void SayHello( ) {
        Console.WriteLine(msg);
    }
}
public class BritishGreeting : Greeting {
    private string msg = "Good morning, old chap!";
    public override void SayHello( ) {
        Console.WriteLine(msg);
    }
}
```

Compiling the source file *English.cs* produces a file named *English.dll*, which the main program can now dynamically reflect over and use.

Now we create the main sample, as follows (see the source comment for filename and compilation information):

```
// SayHello.cs - compile with /r:Greeting.dll
```

```
// Run with SayHello.exe <dllname1> <dllname2> ... <dllnameN>
using System;
using System.Reflection;
class Test {
    static void Main (string[ ] args) {

        // Iterate over the cmd-line options,
        // trying to load each assembly
        foreach (string s in args) {
            Assembly a = Assembly.LoadFrom(s);

            // Pick through all the public types, looking for
            // subtypes of the abstract base class Greeting
            foreach (Type t in a.GetTypes( ))
                if (t.IsSubclassOf(typeof(Greeting))) {

                    // Having found an appropriate subtype, create it
                    object o = Activator.CreateInstance(t);

                    // Retrieve the SayHello MethodInfo & invoke it
                    MethodInfo mi = t.GetMethod("SayHello");
                    mi.Invoke(o, null);
                }
            }
        }
    }
}
```

Running the sample now with `SayHello English.dll` produces the following output:

```
Hey, dude. Wassup!
Good morning, old chap!
```

The interesting aspect of the preceding sample is that it's completely late-bound; i.e., long after the *SayHello* program is shipped you can create a new type and have *SayHello* automatically take advantage of it by simply specifying it on the command line. This is one of the key benefits of late binding via reflection. You could use this pattern to develop an application that supports third-party plug-ins. Each plug-in would have to implement the same interface and be stored in its own assembly. Your application could then use `Assembly.LoadFrom()` and `Activator.CreateInstance()` to activate the plug-in.

13.6.1 Activation

In the previous examples, you loaded an assembly by hand and used the `System.Activator` class to create a new instance based on a type. There are many overrides of the `CreateInstance()` method that provide a wide range of creation options, including the ability to short-circuit the process and create a type directly:

```
object o = Activator.CreateInstance("Assem1.dll",
                                     "Friendly.Greeting");
```

Other capabilities of the `Activator` type include creating types on remote machines, creating types

in specific **AppDomains** (sandboxes), and creating types by invoking a specific constructor (rather than using the default constructor as these examples show).

[\[Team LiB \]](#)

13.7 Advanced Uses of Reflection

The preceding example demonstrates the use of reflection, but doesn't perform any tasks you can't accomplish using normal C# language constructs. However, reflection can also manipulate types in ways not supported directly in C#, as demonstrated in this section.

While the CLR enforces access controls on type members (specified using access modifiers such as private and protected), these restrictions don't apply to reflection. Assuming you have the correct set of permissions, you can use reflection to access and manipulate private data and function members, as this example using the **Greeting** subtypes from the previous section shows (see the source comment for filename and compilation information):

```
// InControl.cs - compile with /r:Greeting.dll,English.dll
using System;
using System.Reflection;
class TestReflection {
    // Note: This method requires the ReflectionPermission perm.
    static void ModifyPrivateData(object o, string msg) {

        // Get a FieldInfo type for the private data member
        Type t = o.GetType( );
        FieldInfo fi = t.GetField("msg", BindingFlags.NonPublic|
                                BindingFlags.Instance);

        // Use the FieldInfo to adjust the data member value
        fi.SetValue(o, msg);
    }
    static void Main( ) {
        // Create instances of both types
        BritishGreeting bg = new BritishGreeting( );
        AmericanGreeting ag = new AmericanGreeting( );

        // Adjust the private data via reflection
        ModifyPrivateData(ag, "Things are not the way they seem");
        ModifyPrivateData(bg, "The runtime is in total control!");

        // Display the modified greeting strings
        ag.SayHello( ); // "Things are not the way they seem"
        bg.SayHello( ); // "The runtime is in total control!"
    }
}
```

When run, this sample generates the following output:

```
Things are not the way they seem
The runtime is in total control!
```

This demonstrates that the private `msg` data members in both types are modified via reflection, although there are no public members defined on the types that allow that operation. Note that while this technique can bypass access controls, it still doesn't violate type safety.

Although this is a somewhat contrived example, the capability can be useful when building utilities such as class browsers and test suite automation tools that need to inspect and interact with a type at a deeper level than its public interface.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

13.8 Creating New Types at Runtime

The `System.Reflection.Emit` namespace contains classes that can create entirely new types at runtime. These classes can define a dynamic assembly in memory, define a dynamic module in the assembly, define a new type in the module, including all its members, and emit the MSIL opcodes needed to implement the application logic in the members.

Here is an example that creates and uses a new type called `HelloWorld` with a member called `SayHello`:

```
using System;
using System.Reflection;
using System.Reflection.Emit;
public class Test
{
    static void Main( )
    {
        // Create a dynamic assembly in the current AppDomain
        AppDomain ad = AppDomain.CurrentDomain;
        AssemblyName an = new AssemblyName( );
        an.Name = "DynAssembly";
        AssemblyBuilder ab =
            ad.DefineDynamicAssembly(an, AssemblyBuilderAccess.Run);

        // Create a module in the assembly & a type in the module
        ModuleBuilder modb = ab.DefineDynamicModule("DynModule");
        TypeBuilder tb = modb.DefineType("AgentSmith",
                                         TypeAttributes.Public);

        // Add a SayHello member to the type
        MethodBuilder mb = tb.DefineMethod("SayHello",
                                         MethodAttributes.Public,
                                         null, null);

        // Generate the MSIL for the SayHello Member
        ILGenerator ilg = mb.GetILGenerator( );
        ilg.EmitWriteLine("Never send a human to do a machine's job.");
        ilg.Emit(OpCodes.Ret);

        // Finalize the type so we can create it
        tb.CreateType( );

        // Create an instance of the new type
        Type t = ab.GetType("AgentSmith");
        object o = Activator.CreateInstance(t);

        // Prints "Never send a human to do a machine's job."
```

```
        t.GetMethod("SayHello").Invoke(o, null);  
    }  
}
```

A common example using `Reflection.Emit` is the regular expression support in the FCL, which can emit new types that are tuned to search for specific regular expressions, eliminating the overhead of interpreting the regular expression at runtime.

Other uses of `Reflection.Emit` in the FCL include dynamically generating transparent proxies for remoting and generating types that perform specific XSLT transforms with the minimum runtime overhead.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 14. Custom Attributes

Types, members, modules, and assemblies all have associated metadata that is used by all the major CLR services, is considered an indivisible part of an application, and can be accessed via reflection (see [Chapter 13](#)).

A key characteristic of metadata is it can be extended. Extend the metadata with custom attributes, which allow you to "decorate" a code element with additional information stored in the metadata associated with the element.

This additional information can then be retrieved at runtime and used to build services that work declaratively, which is the way that the CLR implements core features such as serialization and interception.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

14.1 Language Support

Decorating an element with a custom attribute is known as specifying the custom attribute. This is done by writing the name of the attribute enclosed in brackets (`[]`) immediately before the element declaration as follows:

```
[Serializable] public class Foo {...}
```

In this example, the `Foo` class is specified as serializable. This information is saved in the metadata for `Foo`, and affects the way the CLR treats an instance of this class.

A useful way to think about custom attributes is they expand the built-in set of declarative constructs in the C# language, such as `public`, `private`, and `sealed`.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

14.2 Compiler Support

In reality, custom attributes are simply types derived from `System.Attribute` with language constructs for specifying them on an element (see [Section 4.7](#) in [Chapter 4](#)).

These language constructs are recognized by the compiler, which emits a small chunk of data into the metadata. This custom data includes a serialized call to the constructor of the custom attribute type (containing the values for the positional parameters), and a collection of property set operations (containing the values for the named parameters).

The compiler also recognizes a small number of pseudocustom attributes. These are special attributes that have direct representation in metadata and are stored natively (i.e., not as chunks of custom data). This is primarily a runtime performance optimization, although it has some implications for retrieving attributes via reflection, as discussed later.

To understand this, consider the following class with two specified attributes:

```
[Serializable, Obsolete]
class Foo {...}
```

When compiled in MSIL, the metadata for the class `Foo` looks like this:

```
.class private auto ansi serializable beforefieldinit Foo
    extends [mscorlib]System.Object
{
    .custom instance void
        [mscorlib]System.ObsoleteAttribute::.ctor( ) = ( 01 00 00 00 )
    ...
}
```

Compare the different treatment by the compiler of the `Obsolete` attribute, which is a custom attribute and is stored as a serialized constructor call to the `System.ObsoleteAttribute` type, to the treatment of the `Serializable` attribute, which is a pseudocustom attribute represented directly in the metadata with the `serializable` token.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

14.3 Runtime Support

At runtime the core CLR services, such as serialization and remoting, inspect the custom and pseudocustom attributes to determine how to handle an instance of a type.

In the case of custom attributes, this is done by creating an instance of the attribute (invoking the relevant constructor call and property-set operations), then performing whatever steps are needed to determine how to handle an instance of the type.

In the case of pseudocustom attributes, this is done by inspecting the metadata directly and determining how to handle an instance of the type. Consequently, handling pseudocustom attributes is more efficient than handling custom attributes.

Note that none of these steps is initiated until a service or user program actually tries to access the attributes, so there is little runtime overhead unless required.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

14.4 Predefined Attributes

The .NET Framework makes extensive use of attributes for purposes ranging from simple documentation to advanced support for threading, remoting, serialization, and COM interop. These attributes are all defined in the FCL, and can be used, extended, and retrieved by your own code.

However, certain attributes are treated specially by the compiler and the runtime. Three attributes considered general enough to be defined in the C# specification are `AttributeUsage`, `Conditional`, and `Obsolete`. Other attributes, such as `CLSCompliant`, `Serializable`, and `NonSerialized`, are also treated specially.

14.4.1 The AttributeUsage Attribute

```
[AttributeUsage(target-enum
    [, AllowMultiple=[true|false]]?
    [, Inherited=[true|false]]?
    ] (for classes)
```

The `AttributeUsage` attribute is applied to a new attribute class declaration. It controls how the new attribute should be treated by the compiler—specifically, which set of targets (classes, interfaces, properties, methods, parameters, etc.) the new attribute can be specified on. This is true whether multiple instances of this attribute may be applied to the same target, and whether this attribute propagates to subtypes of the target.

target-enum is a bitwise mask of values from the `System.AttributeTargets` enum, which looks like this:

```
namespace System {
    [Flags]
    public enum AttributeTargets {
        Assembly      = 0x0001,
        Module        = 0x0002,
        Class          = 0x0004,
        Struct         = 0x0008,
        Enum           = 0x0010,
        Constructor    = 0x0020,
        Method         = 0x0040,
        Property       = 0x0080,
        Field          = 0x0100,
        Event          = 0x0200,
        Interface      = 0x0400,
        Parameter      = 0x0800,
        Delegate       = 0x1000,
        ReturnValue     = 0x2000,
        All            = 0x3fff,
    }
}
```

```
}
}
```

14.4.2 The Conditional Attribute

```
[Conditional(symbol)] (for methods)
```

The `Conditional` attribute can be applied to any method with a void return type. The presence of this attribute tells the compiler to conditionally omit calls to the method unless *symbol* is defined in the calling code. This is similar to wrapping every call to the method with `#if` and `#endif` preprocessor directives, but `Conditional` has the advantage of needing to be specified only in one place.

14.4.3 The Obsolete Attribute

```
[Obsolete([Message=? message
    IsError= [true|false]]
] (for all attribute targets)
```

Applied to any valid attribute target, the `Obsolete` attribute indicates that the target is obsolete. `Obsolete` can include a message that explains which alternative types or members to use and a flag that tells the compiler to treat the use of this type or member as an error instead of a warning.

For example, referencing type `Bar` in the following example causes the compiler to display an error message and halts compilation:

```
[Obsolete("Don't try this at home", IsError=true)]
class Bar { ... }
```

14.4.4 The CLSCompliant Attribute

```
[CLSCompliant(true|false)]
(for all attribute targets)
```

Applied to an assembly, the `CLSCompliant` attribute tells the compiler whether to validate CLS compliance for all the exported types in the assembly. Applied to any other attribute target, this attribute allows the target to declare if it should be considered CLS-compliant. In order to mark a target as CLS-compliant, the entire assembly needs to be considered as such.

In the following example, the `CLSCompliant` attribute is used to specify an assembly as CLS-compliant and a class within it as *not* CLS-compliant:

```
[assembly:CLSCompliant(true)]

[CLSCompliant(false)]
public class Bar {
    public ushort Answer { get {return 42;} }
}
```

14.4.5 The Serializable Attribute

`[Serializable]`
(for classes, structs, enums, delegates)

Applied to a class, struct, enum, or delegate, the `Serializable` attribute marks it as being serializable. This attribute is a pseudocustom attribute and is represented specially in the metadata.

14.4.6 The NonSerialized attribute

`[NonSerialized]` (for fields)

Applied to a field, the `NonSerialized` attribute prevents it from being serialized along with its containing class or struct. This attribute is a pseudocustom attribute and is represented specially in the metadata.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

14.5 Defining a New Custom Attribute

In addition to using the predefined attributes supplied by the .NET Framework, you can also create your own.

To create a custom attribute, use the following steps:

1. Derive a class from `System.Attribute` or from a descendent of `System.Attribute`. By convention the class name should end with the word `Attribute`, although this isn't required.
2. Provide the class with a public constructor. The parameters to the constructor define the positional parameters of the attribute and are mandatory when specifying the attribute on an element.
3. Declare public-instance fields, public-instance read/write properties, or public-instance write-only properties to specify the named parameters of the attribute. Unlike positional parameters, these are optional when specifying the attribute on an element.

The types that can be used for attribute constructor parameters and properties are `bool`, `byte`, `char`, `double`, `float`, `int`, `long`, `short`, `string`, `object`, the `Type` type, `enum`, or a one-dimensional array of all of these.

4. Finally, as described in the preceding section, define what the attribute may be specified on using the `AttributeUsage` attribute.

Consider the following example of a custom attribute, `CrossRefAttribute`, which removes the limitation that the CLR metadata contains only information about statically linked types, but not dynamically linked ones.

```
// Xref.cs - cross-reference custom attribute
// compile with:
// csc /t:library XRef.cs
using System;
[AttributeUsage(AttributeTargets.All, AllowMultiple=true)]
public class CrossRefAttribute : Attribute {
    Type xref;
    string desc = "";
    public string Description { set { desc=value; } }
    public CrossRefAttribute(Type xref) { this.xref=xref; }
    public override string ToString( ) {
        string tmp = (desc.Length>0) ? " (" +desc+")" : "";
        return "CrossRef to "+xref.ToString( )+tmp;
    }
}
```

From the attribute user's perspective, this attribute can be applied to any target multiple times (note the use of the `AttributeUsage` attribute to control this). `CrossRefAttribute` takes one mandatory

positional parameter (namely the type to cross reference) and one optional named parameter (the description), and is used as follows:

```
[CrossRef(typeof(Bar), Description="Foos often hang around Bars")]  
class Foo {...}
```

Essentially, this attribute embeds cross references to dynamically linked types (with optional descriptions) in the metadata. This information can then be retrieved at runtime by a class browser to present a more complete view of a type's dependencies.

[\[Team LiB \]](#)

14.6 Retrieving a Custom Attribute at Runtime

Retrieving attributes at runtime is done using reflection via one of `System.Attribute`'s `GetCustomAttribute` or `GetCustomAttributes` overloads. Here is an example that uses and inspects the `CrossRefAttribute` using `GetCustomAttribute`:

```
// XRefTest.cs - apply and inspect a CrossRefAttribute
// Compile with: csc /r:XRef.dll XRefTest.cs
using System;
class Bar { }
[CrossRef(typeof(Bar), Description="Foos often hang around Bars")]
class Foo {
    static void Main( ) {
        // Retrieve the custom attribute from type Foo
        Attribute attr =
            Attribute.GetCustomAttribute(typeof(Foo),
                                         typeof(CrossRefAttribute));

        // Display the attribute.
        if (attr != null) {
            CrossRefAttribute cr = (CrossRefAttribute)attr;
            Console.WriteLine(cr);
        }
    }
}
```

This is one of the few circumstances where the difference between custom attributes and pseudocustom attributes becomes apparent, since pseudocustom attributes can't be retrieved with `GetCustomAttribute`. Here is another example that uses reflection to determine which attributes are on a specific type:

```
using System;
[Serializable, Obsolete]
class Test {
    static void Main( ) {
        Type t = typeof(Test);
        object[] caarr = Attribute.GetCustomAttributes(t);
        Console.WriteLine("{0} has {1} custom attribute(s)",
                          t, caarr.Length);
        foreach (object ca in caarr)
            Console.WriteLine(ca);
    }
}
```

Although the `Test` class of the preceding example has two attributes specified, the sample produces the following output:

```
Test has 1 custom attribute(s)
```

System.ObsoleteAttribute

This demonstrates how the `Serializable` attribute (a pseudocustom attribute) isn't accessible via reflection, while the `Obsolete` attribute (a custom attribute) is.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 15. Memory Management

Almost all modern programming languages allocate memory in two places: on the stack and on the heap. Memory allocated on the stack stores local variables, parameters, and return values, and is generally managed automatically by the operating system. Memory allocated on the heap, however, is treated differently by different languages. In C and C++, memory allocated on the heap is managed manually. In C# and Java, however, memory allocated on the heap is managed automatically.

While manual memory management has the advantage of being simple for runtimes to implement, it has drawbacks that tend not to exist in systems that offer automatic memory management. For example, a large percentage of bugs in C and C++ programs stem from using an object after it has been deleted (dangling pointers) or forgetting to delete an object when it is no longer needed (memory leaks).

The process of automatically managing memory is known as garbage collection. While generally more complex for runtimes to implement than traditional manual memory management, garbage collection greatly simplifies development and eliminates many common errors related to manual memory management.

For example, it is almost impossible to generate a traditional memory leak in C#, and common bugs such as circular references in traditional COM development simply go away.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

15.1 The Garbage Collector

C# depends on the CLR for many of its runtime services, and garbage collection is no exception.

The CLR includes a high-performing generational mark-and-compact garbage collector (GC) that performs automatic memory management for type instances stored on the managed heap.

The GC is considered to be a *tracing* garbage collector in that it doesn't interfere with every access to an object, but rather wakes up intermittently and traces the graph of objects stored on the managed heap to determine which objects can be considered garbage and therefore collected.

The GC generally initiates a garbage collection when a memory allocation occurs and memory is too low to fulfill the request. This process can also be initiated manually using the `System.GC` type. Initiating a garbage collection freezes all threads in the process to allow the GC time to examine the managed heap.

The GC begins with the set of object references considered roots, and walks the object graph, marking all the objects it touches as reachable. Once this process is complete, all objects that have not been marked are considered to be garbage.

Objects that are considered garbage and don't have finalizers are immediately discarded, and the memory is reclaimed. Objects that are considered garbage and do have finalizers are flagged for additional asynchronous processing on a separate thread to invoke their `Finalize` methods before they can be considered garbage and reclaimed at the next collection.

Objects considered still live are then shifted down to the bottom of the heap (compacted), hopefully freeing space to allow the memory allocation to succeed.

At this point the memory allocation is attempted again, the threads in the process are unfrozen, and either normal processing continues or an `OutOfMemoryException` is thrown.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

15.2 Optimization Techniques

Although this may sound like an inefficient process compared to simply managing memory manually, the GC incorporates various optimization techniques to reduce the time an application is frozen while waiting for the GC to complete (known as pause time).

The most important of these optimizations is one that makes the GC generational. This technique takes advantage of the fact that while many objects tend to be allocated and discarded rapidly, certain objects are long-lived and thus don't need to be traced during every collection.

Basically, the GC divides the managed heap into three generations. Objects that have just been allocated are considered to be in Gen0, objects that have survived one collection cycle are considered to be in Gen1, and all other objects are considered to be in Gen2.

When it performs a collection, the GC initially collects only Gen0 objects. If not enough memory is reclaimed to fulfill the request, both Gen0 and Gen1 objects are collected; if that fails as well, a full collection of the Gen0, Gen1, and Gen2 objects is attempted.

Many other optimizations are also used to enhance the performance of automatic memory management, and in general a GC-based application can be expected to approach the performance of an application that uses manual memory management.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

15.3 Finalizers

When implementing your own types, you can choose to give them finalizers (by providing C# destructors). Finalizers are methods called asynchronously by the GC once an object is determined to be garbage.

Although this is required in certain cases, in general there are many good technical reasons to avoid the use of finalizers.

As described in the previous section, objects with finalizers incur significant overhead when they are collected, requiring asynchronous invocation of their `Finalize` methods and taking two full GC cycles for their memory to be reclaimed.

Other reasons not to use finalizers include:

- Objects with finalizers take longer to allocate on the managed heap than objects without finalizers.
- Objects with finalizers that refer to other objects (even those without finalizers) can prolong the life of the referred objects unnecessarily.
- It's impossible to predict in what order the finalizers for a set of objects will be called.
- You have limited control over when (or even if!) the finalizer for an object will be called.

In summary, finalizers are somewhat like lawyers-while there are cases in which you really need them, in general you don't want to use them unless absolutely necessary. If you do use them, you need to be 100 percent sure you understand what they are doing for you.

If you have to implement a finalizer, follow these guidelines or have a very good reason for not doing so:

- Ensure that your finalizer executes quickly.
- Never block in your finalizer.
- Free any unmanaged resources you own.
- Don't reference any other objects.
- Don't throw any unhandled exceptions.

15.4 Dispose and Close Methods

Implementing a finalizer gives your type an opportunity to release any external unmanaged resources (such as database connections or file handles) that it may be holding onto. From the perspective of the users of your type, this makes the resource management implicit: they interact with your type, and your type interacts with the resource as needed. However, since GC happens asynchronously and there are no guarantees as to exactly when the finalizers will be called, this level of control may not be sufficient. In these cases, it is good practice to also offer clients explicit resource management controls.

To provide explicit resource management to clients of your type, implement the `IDisposable` interface. This offers clients a `Dispose()` method they can call to explicitly instruct you to release resources. For types in which `Dispose()` doesn't make sense, provide an explicit `Close()` method that optionally forwards to a private implementation of `IDisposable.Dispose`. If your type also has a finalizer (via a C# destructor), your `Dispose()` or `Close()` implementation should include a special call to the static `SuppressFinalize()` method on the `System.GC` type to indicate that the destructor no longer needs to be called. Typically, the real finalizer is written to call the `Dispose/Close` method, as follows:

```
using System;
public class Worker : IDisposable {
    int id;
    public Worker(int id) {
        this.id = id;
    }
    // ...
    protected virtual void Dispose(bool disposing) {
        if (disposing) {
            // Not in finalizer, can reference other managed objects here
            Console.WriteLine("Disposing {0}: Releasing managed resources", id);
            // Call Dispose on other managed resources you're holding refs to
        }
        Console.WriteLine("Disposing {0}: Releasing unmanaged resources", id);
        // Release any unmanaged resources you're holding
    }
    public void Dispose( ) {
        Dispose(true);
        GC.SuppressFinalize(this); // Mark this object finalized
    }
    ~Worker( ) {
        Console.WriteLine("Finalizing {0}: Calling Dispose( )", id);
        Dispose(false);
    }
    public static void Main( ) {
        // create a worker and call Dispose when we're done.
        using(Worker w1 = new Worker(1)) {
            // ...
        }
    }
}
```



```
    }  
    // create a worker that will get cleaned up when the CLR  
    // gets around to it.  
    Worker w2 = new Worker(2);  
}  
}
```

If you run this code, you will see that the finalizer for Worker(1) is never called, since its `Dispose()` method is called once execution leaves the `using` block, and the `Dispose()` method calls `GC.SuppressFinalize()`.

```
Disposing 1: Releasing managed resources  
Disposing 1: Releasing unmanaged resources  
Finalizing 2: Calling Dispose( )  
Disposing 2: Releasing unmanaged resources
```

Worker 2 is finalized and disposed when the CLR gets around to it, but it's never given a chance to clean up other objects. The disposable pattern gives you a way to close or dispose of any external objects you might be using, such as an I/O stream, in a safe and consistent manner.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Chapter 16. Threading

A C# application runs in one or more threads that effectively execute in parallel within the same application. Here is a simple multithreaded application:

```
using System;
using System.Threading;
class ThreadTest {
    static void Main( ) {
        Thread t = new Thread(new ThreadStart(Go));
        t.Start( );
        Go( );
    }
    static void Go( ) {
        for (char c='a'; c<='z'; c++ )
            Console.Write(c);
    }
}
```

In this example, a new thread object is constructed by passing it a `ThreadStart` delegate that wraps the method that specifies where to start execution for that thread. Then start the thread and call `Go`, so two separate threads are running `Go` in parallel. However, there's one problem. Both threads share a common resource: the console. If you run `ThreadTest`, you receive output something like this:

```
abcdabcdefghijklmnopqrsefghijklmnopqrstuvwxyz
```

16.1 Thread Synchronization

Thread synchronization comprises techniques for ensuring that multiple threads coordinate their access to shared resources.

16.1.1 The lock Statement

C# provides the `lock` statement to ensure that only one thread at a time can access a block of code. Consider the following example:

```
using System;
using System.Threading;
class LockTest {
    static void Main( ) {
        LockTest lt = new LockTest ( );
        Thread t = new Thread(new ThreadStart(lt.Go));
        t.Start( );
        lt.Go( );
    }
    void Go( ) {
        lock(this)
            for ( char c='a'; c<='z'; c++)
                Console.Write(c);
    }
}
```

Running `LockTest` produces the following output:

```
abcdefghijklmnopqrstuvwxyzabcdefghijklmnopqrstuvwxyz
```

The `lock` statement acquires a lock on any reference type instance. If another thread has already acquired the lock, the thread doesn't continue until the other thread relinquishes its lock on that instance.

The `lock` statement is actually a syntactic shortcut for calling the `Enter()` and `Exit()` methods of the FCL `Monitor` class (see [Section 16.2.1](#)):

```
System.Threading.Monitor.Enter(expression);
try {
    ...
}
finally {
    System.Threading.Monitor.Exit(expression);
}
```

16.1.2 Pulse and Wait Operations

The next most common threading operations are `Pulse` and `Wait` in combination with locks. These operations let threads communicate with each other via a monitor that maintains a list of threads waiting to grab an object's lock:

```
using System;
using System.Threading;
class MonitorTest {
    static void Main( ) {
        MonitorTest mt = new MonitorTest( );
        Thread t = new Thread(new ThreadStart(mt.Go));
        t.Start( );
        mt.Go( );
    }
    void Go( ) {
        for ( char c='a'; c<='z'; c++)
            lock(this) {
                Console.Write(c);
                Monitor.Pulse(this);
                Monitor.Wait(this);
            }
    }
}
```

Running `MonitorTest` produces the following result:

```
aabbccddeeffgghhiijjkkllmmnnnooppqrrssttuuvvwwxxyyzz
```

The `Pulse` method tells the monitor to wake up the next thread that is waiting to get a lock on that object as soon as the current thread has released it. The current thread typically releases the monitor in one of two ways. First, execution may leave the `lock` statement blocked. Alternatively, calling the `Wait` method temporarily releases the lock on an object and makes the thread fall asleep until another thread wakes it up by pulsing the object.

16.1.3 Deadlocks

The `MonitorTest` example actually contains a type of bug called a deadlock. When you run the program, it prints the correct output, but then the console window locks up. This is because there are two sleeping threads, and neither will wake the other. The deadlock occurs because when printing `z`, each thread goes to sleep but never gets pulsed. Solve the problem by replacing the `Go` method with this new implementation:

```
void Go( ) {
    for ( char c='a'; c<='z'; c++)
        lock(this) {
            Console.Write(c);
            Monitor.Pulse(this);
            if (c<'z')
                Monitor.Wait(this);
        }
}
```

```
}  
}
```

In general, the danger of using locks is that two threads may both end up being blocked waiting for a resource held by the other thread. Most common deadlock situations can be avoided by ensuring that you always acquire resources in the same order.

16.1.4 Atomic Operations

Atomic operations are operations the system promises will not be interrupted. In the previous examples, the `Go` method isn't atomic, because it can be interrupted while it is running so another thread can run. However, updating a variable is atomic, because the operation is guaranteed to complete without control being passed to another thread. The `Interlocked` class provides additional atomic operations, which allow basic operations to perform without requiring a lock. This can be useful, since acquiring a lock is many times slower than a simple atomic operation.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

16.2 Common Thread Types

Much of the functionality of threads is provided through the classes in the `System.Threading` namespace. The most basic thread class to understand is the `Monitor` class, which is explained next.

16.2.1 The Monitor Class

The `System.Threading.Monitor` class provides an implementation of Hoare's Monitor that allows you to use any reference-type instance as a monitor.

16.2.2 The Enter and Exit Methods

The `Enter()` and `Exit()` methods respectively obtain and release a lock on an object. If the object is already held by another thread, `Enter()` waits until the lock is released, or the thread is interrupted by a `ThreadInterruptedException`. Every call to `Enter()` for a given object on a thread should be matched with a call to `Exit()` for the same object on the same thread.

16.2.3 The TryEnter Methods

The `TryEnter()` methods are similar to the `Enter()` method, but they don't require a lock on the object to proceed. These methods return `true` if the lock is obtained, and `false` if it isn't, optionally passing in a timeout parameter that specifies the maximum time to wait for the other threads to relinquish the lock.

16.2.4 The Wait Methods

The thread holding a lock on an object may call one of the `Wait()` methods to temporarily release the lock and block itself, while it waits for another thread to notify it by executing a pulse on the monitor. This approach can tell a worker thread there is work to perform on that object. The overloaded versions of `Wait()` allow you to specify a timeout that reactivates the thread if a pulse hasn't arrived within the specified duration. When the thread wakes up, it reacquires the monitor for the object (potentially blocking until the monitor becomes available). `Wait()` returns `true` if the thread is reactivated by another thread pulsing the monitor and returns `false` if the `Wait()` call times out without receiving a pulse.

16.2.5 The Pulse and PulseAll Methods

A thread holding a lock on an object may call `Pulse()` on that object to wake up a blocked thread

as soon as the thread calling `Pulse()` has released its lock on the monitor. If multiple threads are waiting on the same monitor, `Pulse()` activates only the first in the queue (successive calls to `Pulse()` wake up other waiting threads, one per call). The `PulseAll()` method successively wakes up all the threads.

[\[Team LiB \]](#)

[← PREVIOUS](#) [NEXT →](#)

16.3 Asynchronous Delegates

Sometimes it is desirable to call a method asynchronously, so the call returns immediately while the method executes on a separate thread. The runtime provides a standard way that any method can be called asynchronously, taking into account retrieving return values and ref/in parameters supplied to the method. When the C# compiler encounters a delegate, the delegate derived class it generates contains three key methods:

```
return-type Invoke (parameter-list);
IAsyncResult BeginInvoke (parameter-list, AsyncCallback ac, object state);
return-type EndInvoke (ref/out-only parameter-list, IAsyncResult ac);
```

Calling `Invoke()` calls the method synchronously, and the caller has to wait until the delegate finishes executing (a standard delegate invocation in C# calls `Invoke()`).

Calling `BeginInvoke()` invokes the delegate with the supplied parameter list, then immediately returns. This asynchronous call is performed as soon as a thread is available in the ThreadPoo. Two additional parameters are added to `BeginInvoke()`: an `AsyncCallback` object, to optionally specify a delegate to execute by the ThreadPoo thread just before it returns, and an arbitrary object to hold state. The `AsyncCallback` delegate signature is a void method with a single `IAsyncResult` parameter, which lets you access information about the call.

Calling `EndInvoke()` retrieves the return value of the called method, along with any ref/out parameters that may have been modified.

In the following example, we call `TimeConsumingFunction()` twice asynchronously, whereby the `Main` method can continue executing while work is being done by each `TimeConsumingFunction`. To keep the example simple, these functions happen to execute very fast, but this methodology could be applied to much slower functions such as file I/O functions.

```
using System;
using System.Threading;
using System.Runtime.Remoting.Messaging;

delegate int Compute (string s);

public class Test {
    static int TimeConsumingFunction (string s) {
        return s.Length;
    }

    static void DisplayFunctionResult (IAsyncResult ar) {
        Compute c = (Compute)((AsyncResult)ar).AsyncDelegate;
        int result = c.EndInvoke(ar);
        string s = (string)ar.AsyncState;
        Console.WriteLine ("{0} is {1} characters long", s, result);
    }
}
```



```
static void Main ( ) {  
    Compute c = new Compute (TimeConsumingFunction);  
    AsyncCallback ac = new AsyncCallback (DisplayFunctionResult);  
    string s1 = "Christopher";  
    string s2 = "Nolan";  
    IAsyncResult ar1 = c.BeginInvoke (s1, ac, s1);  
    IAsyncResult ar2 = c.BeginInvoke (s2, ac, s2);  
    Console.WriteLine ("Ready");  
    Console.Read( );  
}  
}
```

The output is:

```
Ready  
Christopher is 11 characters long  
Nolan is 5 characters long
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 17. Integrating with Native DLLs

While it would be convenient if all applications could be written entirely in managed code, and you never had to depend on the services of "legacy" code, this situation is not likely to occur in the immediate future. For the purposes of this discussion, legacy code is defined as any code written in a traditional Microsoft language, such as Visual C++ or VB, for an already released operating system, such as Windows 2000 or Windows XP, or a virtual machine such as the VB runtime. Practically speaking, it is essential that managed code be able to draw on the services of unmanaged code in an efficient and well-integrated manner. Thankfully, the .NET Framework is an over-achiever in this area, providing excellent support for integrating with traditional DLLs as well as COM components and COM+ applications.

This section introduces and demonstrates the facilities for integrating with existing unmanaged code packaged in traditional DLLs. Unless otherwise stated, the types mentioned in this section all exist in either the `System` or `System.Runtime.InteropServices` namespaces.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.1 Calling Into DLLs

PInvoke, short for Platform Invocation Services, lets C# access functions, structs, and callbacks in unmanaged DLLs. For example, perhaps you wish to call the `MessageBox` function in the Windows DLL *user32.dll*.

```
int MessageBox(HWND hWnd, LPCTSTR lpText,
               LPCTSTR lpCaption, UINT uType);
```

To call this function, you can write a `static extern` method decorated with the `DllImport` attribute:

```
using System.Runtime.InteropServices;
class MsgBoxTest {
    [DllImport("user32.dll")]
    static extern int MessageBox(int hWnd, string text,
                                string caption, int type);

    public static void Main( ) {
        MessageBox(0, "Please do not press this button again.",
                  "Attention", 0);
    }
}
```

PInvoke then finds and loads the required Win32 DLLs and resolves the entry point of the requested function. The CLR includes a marshaler that knows how to convert parameters and return values between .NET types and unmanaged types. In this example the `int` parameters translate directly to four-byte integers that the function expects, and the string parameters are converted into null-terminated arrays of characters using one-byte ANSI characters under Win9x, or into two-byte Unicode characters under WinNT/Win2K.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.2 Marshaling Common Types

The CLR marshaler is a .NET facility that knows about the core types used by COM and the Windows API, and provides default translations to CLR types for you. The `bool` type, for instance, can be translated into a two-byte Windows `BOOL` type or a four-byte `Boolean` type. Using the `MarshalAs` attribute, you can override a default translation:

```
using System.Runtime.InteropServices;
static extern int Foo([MarshalAs(UnmanagedType.LPStr)]
                     string s);
```

In this case, the marshaler was told to use `LPStr`, so it will always use ANSI characters. Array classes and the `StringBuilder` class copy the marshaled value from an external function back to the managed value, as follows:

```
using System;
using System.Text;
using System.Runtime.InteropServices;
class Test {
    [DllImport("kernel32.dll")]
    static extern int GetWindowsDirectory(StringBuilder sb,
                                         int maxChars);

    static void Main( ) {
        StringBuilder s = new StringBuilder(256);
        GetWindowsDirectory(s, 256);
        Console.WriteLine(s);
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.3 Marshaling Classes and Structs

Passing a class or struct to a C function requires marking the struct or class with the `StructLayout` attribute:

```
// InteropFun.cs - compile with /nowarn:649 or add "=0;" default
//   initializers to the fields in SystemTime to avoid warnings
using System;
using System.Runtime.InteropServices;
[StructLayout(LayoutKind.Sequential)]
class SystemTime {
    public ushort wYear;
    public ushort wMonth;
    public ushort wDayOfWeek;
    public ushort wDay;
    public ushort wHour;
    public ushort wMinute;
    public ushort wSecond;
    public ushort wMilliseconds;
}
class InteropFun {
    [DllImport("kernel32.dll")]
    static extern void GetSystemTime(SystemTime t);
    static void Main( ) {
        SystemTime t = new SystemTime( );
        GetSystemTime(t);
        Console.WriteLine(t.wYear);
    }
}
```

In both C and C#, fields in an object are located at *n* number of bytes from the address of that object. The difference is that in a C# program, the CLR finds this offset by looking it up using the field name; C field names are compiled directly into offsets. For instance, in C, `wDay` is just a token to represent whatever is at the address of a `SystemTime` instance plus 24 bytes.

For access speed and future widening of a data type, these offsets are usually in multiples of a minimum width, called the *pack size*. For .NET types, the pack size is usually set at the discretion of the runtime, but by using the `StructLayout` attribute, field offsets can be controlled. When using this attribute, the default pack size is 8 bytes, but it can be set to 1, 2, 4, 8, or 16 bytes (pass `Pack=packsize` to the `StructLayout` constructor). There are also explicit options to control individual field offsets (see [Section 17.6](#) later in this chapter). This lets a .NET type pass to a C function.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.4 In and Out Marshaling

The previous Test example works if `SystemTime` is a struct and `t` is a ref parameter, but is actually less efficient:

```
struct SystemTime {...}  
static extern void GetSystemTime(ref SystemTime t);
```

This is because the marshaler must always create fresh values for external parameters, so the previous method copies `t` when going in to the function. It then copies the marshaled `t` when coming out of the function. By default, pass-by-value parameters are copied in, C# ref parameters are copied in/out, and C# out parameters are copied out, but there are exceptions for the types that have custom conversions. For instance, array classes and the `StringBuilder` class require copying when coming out of a function, so they are in/out. It is occasionally useful to override this behavior, with the `In` and `Out` attributes. For example, if an array should be read-only, the `in` modifier indicates to only copy the array going into the function, and not come out of it:

```
static extern void Foo([In] int[] array);
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.5 Callbacks from Unmanaged Code

The P/Invoke layer does its best to present a natural programming model on both sides of the boundary, mapping between the relevant constructs where possible. Since C# not only can call out to C functions but can also be called back from the C functions (via function pointers), the P/Invoke layer needs to map unmanaged function pointers onto something natural for the managed world. The managed equivalent of a function pointer is a delegate, so the P/Invoke layer automatically maps between delegates (in C#) and function pointers (in C). To call a function in a DLL that takes a callback function pointer as a parameter, declare a delegate with the correct signature for the callback function and pass an instance of the delegate when calling the function that performs the callback, as follows:

```
using System;
using System.Runtime.InteropServices;

class CallbackFun {
    delegate bool Callback(int hWnd, int lParam);
    [DllImport("user32.dll")]
    static extern int EnumWindows(Callback hWnd, int lParam);
    static bool PrintWindow(int hWnd, int lParam) {
        Console.WriteLine(hWnd);
        return true;
    }
    static void Main( ) {
        Callback e = new Callback(PrintWindow);
        EnumWindows(e, 0);
    }
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

17.6 Simulating a C Union

Each field in a `struct` is given enough room to store its data. Consider a `struct` containing one `int` and one `char`. The `int` is likely to start at an offset of 0, and is guaranteed at least four bytes. So, the `char` could start at an offset of 4. If, for some reason, the `char` started at an offset of 2, then you'd change the value of the `int` if you assigned a value to the `char`. Sounds like mayhem, doesn't it? Strangely enough, the C language supports a variation on a struct called a *union* that does exactly this. You can simulate this in C# using `LayoutKind.Explicit` and the `FieldOffset` attribute.

It might be hard to think of a case in which this would be useful. However, consider a situation in which you want to create a vast quantity of different primitive types, but store them in one array. You have to store them all in an object array, and the primitive values are boxed every time they go into the array. This means you're going to start using a lot of heap memory, and you'll pay the cost of boxing and unboxing as you go from primitive to object and back again. This example shows how this works with three objects, but if it were thousands or millions of objects, the impact on performance would be noticeable:

```
using System;
public class BoxMe {
    public static void Main( ) {
        // Stuff some primitive values into an array.
        object[ ] a = new object[3];
        a[0] = 1073741824;
        a[1] = 'A';
        a[2] = true;
        // Display each value
        foreach (object o in a) {
            Console.WriteLine("Value: {0}", o);
        }
    }
}
```

To avoid the boxing and unboxing operations, you can use a union to create a *variant type*, which is a type that can take on one value at a time, but can represent a variety of types. Your variant type has a flag field that tells you the type that the variant represents. It also includes one value field for each of the possible types it can take on. Since each value field starts at the same offset, a variant instance never takes up more memory than the largest type plus the size of the flag field (it may also take a couple of bytes to optimally align the fields in memory).

The next example shows the use of a variant struct called `MyVariant`. It can be an `int`, `char`, or `bool`. The value fields `intVal`, `charVal`, and `boolVal` are stored at an offset (`sizeof(byte)`) that sets aside enough memory for the flag field `vType`. This means that the value fields are overlapped. Since the variant can only represent one value at any given time, initializing `charVal` as "A" will produce that same value even if you inspect `intVal`. However, the value is treated as an `int` giving 65, the ASCII value of "A", as shown in this example:

```
using System;
```



```

using System.Runtime.InteropServices;

// Enumerate the possible types for MyVariant
public enum MyVariantType : byte { Int, Char, Bool };

// Define a structure for MyVariant
[StructLayout(LayoutKind.Explicit)]
public struct MyVariant {
    // Type flag
    [FieldOffset (0)] public MyVariantType vType;
    // Start the fields, leaving enough room for vType
    [FieldOffset (sizeof(byte))] public int  intVal;
    [FieldOffset (sizeof(byte))] public char charVal;
    [FieldOffset (sizeof(byte))] public bool boolVal;

    // Return a string representation of this Variant
    public override string ToString( ) {
        switch (vType) {
            case MyVariantType.Int:
                return intVal.ToString( );
            case MyVariantType.Char:
                return charVal.ToString( );
            case MyVariantType.Bool:
                return boolVal.ToString( );
        }
        throw new Exception("Unknown Variant type: " + vType);
    }
}

// Create an array of variants and display their values
public class VariantTest {
    public static void Main( ) {
        MyVariant[ ] a = new MyVariant[3];
        a[0].vType = MyVariantType.Int;
        a[0].intVal = 1073741824;
        a[1].vType = MyVariantType.Char;
        a[1].charVal = 'A';
        a[2].vType = MyVariantType.Bool;
        a[2].boolVal = true;

        // Display each variant's value
        foreach (MyVariant mv in a) {
            Console.WriteLine("Value: {0}", mv);
        }
        // Reinterpret the char as an int
        Console.WriteLine("{0} is: {1}", a[1], a[1].intVal);
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

17.7 Mapping a Struct to a Binary Format

You can use the `LayoutKind.Sequential` argument with the `StructLayout` attribute to tell .NET to ensure that struct fields are laid out in the order in which they are defined. You can use this to create a struct that maps to a binary format, such as a GIF image. If you use this in conjunction with Win32 APIs for mapping a file into memory, you can define such a struct, load a file into memory, and superimpose the struct over that region of memory.

The next example features a struct, `Gif89a`, whose fields map directly to the layout of a GIF image. Because you can't define a fixed-length array in a C# struct, use a sequence of three bytes to hold the GIF signature ("GIF") and the version ("89a"). The `Signature` and `Version` properties each have an accessor method that turns these bytes into a string. The `Dump()` method displays the version and the dimensions of the GIF.

The `Main()` method uses three functions defined in `kernel32.dll` to map a GIF file into memory. Then, it casts that memory region (starting at `baseAddress`) to a `Gif89a`. This maps the struct onto the binary file format, eliminating the need to write code that parses each individual field of the GIF header.

```
// GIFInspects.cs - compile with /unsafe
using System;
using System.IO;
using System.Runtime.InteropServices;

[StructLayout(LayoutKind.Sequential)]
public struct Gif89a {
    byte sig0, sig1, sig2; // Signature
    byte ver0, ver1, ver2; // Version
    public ushort ScreenWidth;
    public ushort ScreenHeight;
    // other members of GIF89a header removed for brevity
    public string Signature { // concatenate the bytes to get a string
        get {
            char[ ] c = {(char) sig0, (char) sig1, (char) sig2};
            return new String(c);
        }
    }
    public string Version {
        get {
            char[ ] c = {(char) ver0, (char) ver1, (char) ver2};
            return new String(c);
        }
    }
    public void Dump( ) {
        Console.WriteLine("Image size: {0}x{1}", ScreenWidth, ScreenHeight);
        Console.WriteLine("GIF Type: {0}{1}", Signature, Version);
    }
}
```

```

}

public class GIFInspect {
    const uint PAGE_READONLY = 0x02; // from winnt.h
    const uint FILE_MAP_READ = 0x04; // from WinBASE.h
    [DllImport("kernel32.dll")]
    private static extern int CreateFileMapping(IntPtr hFile,
                                                int lpAttributes,
                                                uint flProtect,
                                                uint dwMaximumSizeHigh,
                                                uint dwMaximumSizeLow,
                                                string lpName);

    [DllImport("kernel32.dll")]
    private static extern uint MapViewOfFile(int hFileMappingObject,
                                              uint dwDesiredAccess,
                                              uint dwFileOffsetHigh,
                                              uint dwFileOffsetLow,
                                              uint dwNumberOfBytesToMap);

    [DllImport("kernel32.dll")]
    private static extern int CloseHandle(int hObject);

    public static void Main(string[] args) {
        // Open the file
        FileStream fs = new FileStream(args[0],
                                       FileMode.Open,
                                       FileAccess.Read,
                                       FileShare.Read);

        // Map the file into memory
        int hSection = CreateFileMapping(fs.Handle, 0, PAGE_READONLY,
                                         0, 0, null);
        uint baseAddress = MapViewOfFile(hSection, FILE_MAP_READ,
                                         0, 0, 0);

        // Cast the memory at baseAddress to a Gif89a
        unsafe {
            Gif89a* ptr = (Gif89a*) baseAddress;
            ptr->Dump(); // display information about the GIF
        }
        fs.Close();
        CloseHandle(hSection);
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

17.8 Predefined Interop Support Attributes

The FCL provides a set of attributes you can use to mark up your objects with information that is used by the CLR marshaling services to alter their default marshaling behavior.

This section describes the most common attributes you need when interoperating with native Win32 DLLs. These attributes all exist in the `System.Runtime.InteropServices` namespace.

17.8.1 The DllImport Attribute

```
[DllImport (dll-name
    [, EntryPoint=function-name]?
    [, CharSet=charset-enum]?
    [, SetLastError=true|false]?
    [, ExactSpelling=true|false]?
    [, PreserveSig=true|false]?
    [, CallingConvention=callconv-enum?])]
(for methods)
```

The `DllImport` attribute annotates an external function that defines a DLL entry point. The parameters for this attribute are as follows:

`dll-name`

A string specifying the name of the DLL.

`function-name`

A string specifying the function name in the DLL. This is useful if you want the name of your C# function to be different from the name of the DLL function.

`charset-enum`

A `CharSet` enum, specifying how to marshal strings. The default value is `CharSet.Auto`, which converts strings to ANSI characters on Win98, and to Unicode characters on WinNT.

`SetLastError`

If `true`, preserves the Win32 error info. The default is `false`.

`ExactSpelling`

If `true`, the `EntryPoint` must exactly match the function. If `false`, name-matching heuristics are used. The default is `false`.

`PreserveSig`

If `true`, the method signature is preserved exactly as it was defined. If `false`, an HRESULT transformation is performed (see the documentation for "PreserveSigAttribute" in [Chapter 36](#)).

`callconv-enum`

A `CallingConvention` enum, specifying the mode to use with the `EntryPoint`. The default is `StdCall`.

17.8.2 The StructLayout Attribute

```
[StructLayout(layout-enum
    [, Pack=packing-size]?
    [, CharSet=charset-enum]?
    [, Size=absolute-size?])
(for classes, structs)]
```

The `StructLayout` attribute specifies how the data members of a class or struct should be laid out in memory. Although this attribute is commonly used when declaring structures that are passed to or returned from native DLLs, it can also define data structures suited to file and network I/O. The parameters for this attribute are as follows:

`layout-enum`

A `LayoutKind` enum, which can be *sequential* (which lays out fields one after the next with a minimum pack size), *union* (which makes all fields have an offset of 0, so long as they are value types) or *explicit* (which lets each field have a custom offset).

`packing-size`

An int specifying whether the packing size is 1, 2, 4, 8, or 16 bytes. The default value is 8.

`charset-enum`

A `CharSet` enum, specifying how to marshal strings. The default value is `CharSet.Auto`, which converts strings to ANSI characters on Win98, and Unicode characters on WinNT.

`absolute-size`

Specifies the size of the struct or class. This has to be at least as large as the sum of all the members.

17.8.3 The FieldOffset Attribute

```
[FieldOffset (byte-offset)]
(for fields)
```

The `FieldOffset` attribute is used within a class or struct that has explicit field layout. This attribute can be applied to a field and specifies the field offset in bytes from the start of the class or struct. Note that these offsets don't have to be strictly increasing and can overlap, thus creating a union data structure.

17.8.4 The MarshalAs Attribute

```
[MarshalAs(unmanaged-type)
    [, named-parameters]?]
(for fields, parameters, return values)
```

The `MarshalAs` attribute overrides the default marshaling behavior the marshaler applies to a parameter or field. The *unmanaged-type* value is taken from the `UnmanagedType` enum; see the following list for the permissible values:

<code>Bool</code>	<code>LPStr</code>	<code>VByRefStr</code>
<code>I1</code>	<code>LPWStr</code>	<code>AnsiBStr</code>
<code>U1</code>	<code>LPTStr</code>	<code>TBStr</code>
<code>I2</code>	<code>ByValTStr</code>	<code>VariantBool</code>
<code>U2</code>	<code>IUnknown</code>	<code>FunctionPtr</code>
<code>I4</code>	<code>IDispatch</code>	<code>LPVoid</code>
<code>U4</code>	<code>Struct</code>	<code>AsAny</code>
<code>I8</code>	<code>Interface</code>	<code>RPrecise</code>
<code>U8</code>	<code>SafeArray</code>	<code>LPArray</code>
<code>R4</code>	<code>ByValArray</code>	<code>LPStruct</code>
<code>R8</code>	<code>SysInt</code>	<code>CustomMarshaler</code>
<code>BStr</code>	<code>SysUInt</code>	<code>NativeTypeMax</code>
<code>Error</code>		

For a detailed description of how and when to use each of these enum values, as well as other legal *named parameters*, see the .NET Framework SDK documentation.

17.8.5 The In Attribute

`[In]`
(for parameters)

The `In` attribute specifies that data should be marshaled into the caller and can be combined with the `Out` attribute.

17.8.6 The Out Attribute

`[Out]`
(for parameters)

The `Out` attribute specifies that data should be marshaled out from the called method to the caller and can be combined with the `In` attribute.

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 18. Integrating with COM Components

The CLR provides support both for exposing C# objects as COM objects and for using COM objects from C#. Additionally, CLR components can make use of COM+ services and can be used as configured components by CLR and classic COM applications.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

18.1 Binding COM and C# Objects

Interoperating between COM and C# works through either early or late binding. Early binding allows you to program with types known at compile time, while late binding forces you to program with types via dynamic discovery, using reflection on the C# side and **IDispatch** on the COM side.

When calling COM programs from C#, early binding works by providing metadata in the form of an assembly for the COM object and its interfaces. *TlbImp.exe* takes a COM type library and generates the equivalent metadata in an assembly. With the generated assembly, it's possible to instantiate and call methods on a COM object just as you would on any other C# object.

When calling C# programs from COM, early binding works via a type library. Both *TlbExp.exe* and *RegAsm.exe* allow you to generate a COM type library from your assembly. You can then use this type library with tools that support early binding via type libraries such as Visual Basic 6.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

18.2 Exposing COM Objects to C#

When you instantiate a COM object, you are actually working with a proxy known as the Runtime Callable Wrapper (RCW). The RCW is responsible for managing the lifetime requirements of the COM object and translating the methods called on it into the appropriate calls on the COM object. When the garbage collector finalizes the RCW, it releases all references to the object it was holding. For situations in which you need to release the COM object without waiting for the garbage collector to finalize the RCW, you can use the static `ReleaseComObject` method of the `System.Runtime.InteropServices.Marshal` type.

The following example demonstrates how to change your MSN Instant Messenger friendly name using C# via COM Interop:

```
// RenameMe.cs - compile with:
// csc RenameMe.cs /r:Messenger.dll
// Run RenameMe.exe "new name" to change your name
// as it is displayed to other users.
// Run TlbImp.exe "C:\Program Files\Messenger\msmsgs.exe"
// to create Messenger.dll
using System;
using Messenger;
class MSNFun {
    static void Main(string[] args) {
        MsgrObject mo = new MsgrObject( );
        IMsgrService ims = mo.Services.PrimaryService;
        ims.FriendlyName = args[0];
    }
}
```

You can also work with COM objects using the reflection API. This is more cumbersome than using *TlbImp.exe*, but is handy in cases in which it's impossible or inconvenient to run *TlbImp.exe*. To use COM through reflection, you have to get a `Type` from `Type.GetTypeFromProgID()` for each COM type you want to work with. Then, use `Activator.CreateInstance()` to create an instance of the type. To invoke methods or set or get properties, use the reflection API, which is covered in [Chapter 13](#):

```
using System;
using System.Reflection;
public class ComReflect {
    public static void Main( ) {
        object obj_msword; // Microsoft Word Application
        Type wa = Type.GetTypeFromProgID("Word.Application", true);
        // Create an instance of Microsoft Word
        obj_msword = Activator.CreateInstance(wa);

        // Use the reflection API from here on in...
    }
}
```

}

[Team LiB]

◀ PREVIOUS

NEXT ▶

18.3 Exposing C# Objects to COM

Just as an RCW proxy wraps a COM object when you access it from C#, code that accesses a C# object as a COM object must do so through a proxy as well. When your C# object is marshaled out to COM, the runtime creates a COM Callable Wrapper (CCW). The CCW follows the same lifetime rules as other COM objects, and as long as it is alive, a CCW maintains a traceable reference to the object it wraps. This keeps the object alive when the garbage collector is run.

The following example shows how you can export both a class and an interface from C# and control the Global Unique Identifiers (GUIDs) and Dispatch IDs (DISPIDs) assigned. After compiling `IRunInfo` and `StackSnapshot`, you can register both using *RegAsm.exe*.

```
// IRunInfo.cs
// Compile with:
//   csc /t:library IRunInfo.cs
using System;
using System.Runtime.InteropServices;
[GuidAttribute("aa6b10a2-dc4f-4a24-ae5e-90362c2142c1")]
public interface IRunInfo {
    [DispId(1)]
    string GetRunInfo( );
}

// StackSnapshot.cs
//   compile with csc /t:library /r:IRunInfo.dll StackSnapshot.cs
using System;
using System.Runtime.InteropServices;
using System.Diagnostics;
[GuidAttribute("b72ccf55-88cc-4657-8577-72bd0ff767bc")]
public class StackSnapshot : IRunInfo {
    public StackSnapshot( ) {
        st = new StackTrace( );
    }
    [DispId(1)]
    public string GetRunInfo( ) {
        return st.ToString( );
    }
    private StackTrace st;
}
```

18.4 COM Mapping in C#

When you use a COM object from C#, the RCW makes a COM method look like a normal C# instance method. In COM, methods normally return an HRESULT to indicate success or failure and use an out parameter to return a value. In C#, however, methods normally return their result values and use exceptions to report errors. The RCW handles this by checking the HRESULT returned from the call to a COM method and throwing a C# exception when it finds a failure result. With a success result, the RCW returns the parameter marked as the return value in the COM method signature.



For more information on the argument modifiers and default mappings from COM type library types to C# types, see [Appendix A](#).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

18.5 Common COM Interop Support Attributes

The FCL provides a set of attributes you can use to mark up your objects with information needed by the CLR interop services to expose managed types to the unmanaged world as COM objects. See [Chapter 37](#), for documentation about these attributes.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

18.6 COM+ Support

The CLR also includes special plumbing and interop services that allow CLR classes to be deployed as COM+ configured components. This allows both CLR clients and classic COM clients to make use of COM+ services for building scalable applications.

18.6.1 What Is COM+?

COM+ provides a set of services that are designed to help build scalable distributed systems, such as distributed transaction support, object pooling, Just-In-Time activation, synchronization, role-based security, loosely coupled events, and others.

These services are provided by a runtime environment called the COM+ runtime, and are based on the idea of intercepting new COM object creation and (possibly) method calls to layer in the additional services as needed.

COM classes that use COM+ services are called Configured Components because the exact set of services each COM class requires is controlled and configured using declarative attributes that are stored in a metadata repository called the COM+ Catalog.

The COM+ Catalog groups a set of configured components together into something called an Application, which also has metadata settings that control which process the COM components end up in when they are created at runtime (the options here are Library and Server, where Library components end up in the creator's process, while Server components are hosted in a separate process), the security principal the new process runs as, and other settings.

18.6.2 Using COM+ Services with CLR Classes

Naturally, CLR classes can also take advantage of COM+ services. Although the underlying implementation of this is currently the classic COM+ runtime, the mechanics of it are largely hidden from the .NET programmer, who may choose to work almost entirely in terms of normal CLR base classes, interfaces, and custom attributes.

The bulk of the functionality in .NET for using COM+ services is exposed via the `System.EnterpriseServices` namespace. The most important type in this namespace is the `ServiceComponent` class, which is the base class that all CLR classes must derive from if they wish to use COM+ services (i.e., if they want to be configured components).

There is a suite of custom attributes in this namespace that can control almost all of the configuration settings that would otherwise be stored in the COM+ Catalog. Examples of these attributes include both assembly-level attributes which control the settings for the entire COM+ application, the `ApplicationActivationAttributes`, which controls whether the CLR class is deployed in a COM+ Library or Server application, and component-level attributes, which declare and configure the COM+ services the CLR class wishes to be provided at runtime. Examples of component-level custom

attributes include the `TransactionAttribute` (which specifies the COM+ transaction semantics for the class), the `JustInTimeActivationAttribute` (which specifies that the CLR class should have JITA semantics), the `SynchronizationAttribute` (which controls the synchronization behavior of methods), the `ObjectPoolingAttribute` (which controls whether the CLR class is pooled), and many, many others.

Although `ServicedComponent` serves as a special base class which signals the .NET Framework that a class needs COM+ services, it also provides other capabilities. In classic COM+ work, COM classes implement interfaces such as `IObjectConstruct` and `IObjectControl` to customize aspects of their behavior. When using COM+ services in .NET, your classes can override virtual methods provided by `ServicedComponent` that mirror the functionality in `IObjectConstruct` and `IObjectControl`, allowing a very natural, .NET-centric way of accomplishing the same thing.

Other important classes in the `System.EnterpriseServices` namespace include `ContextUtil` and `SecurityCallContext`. These classes provide static methods that allow a CLR-configured component to access COM+ context. This is used to control things like transaction status and to access information such as the security role a caller is in.

Lastly, let's discuss deployment. Deploying traditional COM+ applications requires one to configure the component's COM+ Catalog settings. This is typically done using either the COM+ Explorer (by hand, really only suitable for toy applications) or using custom registration code. When configuring CLR classes, there are two different approaches.

The first approach is using the `RegSvcs.exe` command-line tool. This tool performs all the relevant COM Interop and COM+ Catalog configuration, using both command-line options and the custom attributes applied to your assembly and classes to control the COM+ metadata. While this requires an extra step, arguably this approach is the most powerful and flexible, resulting in CLR-configured classes that can be used from both COM and .NET clients.

Alternatively, the .NET COM+ integration is able to automatically register classes that derive from `ServicedComponent` in the COM+ catalog when they are first instantiated. This has the advantage of not requiring any additional setup, but also has several disadvantages, most notably that the client code that indirectly causes the registration to occur needs elevated privileges, and until the class is configured, it is invisible to COM clients.

A simple C# configured class might look like this:

```
using System;
using System.EnterpriseServices;

[assembly:ApplicationName("MyCOMPlusApplication")]
[assembly:ApplicationActivation(ActivationOption.Server)]

[ObjectPooling(true), Transaction(TransactionOption.Required)]
public class MyConfiguredComponent : ServicedComponent {
    public void DoDBWork( ) {
        ContextUtil.SetAbort( );
        // ... do database work...
        ContextUtil.SetComplete( );
    }
    public override bool CanBePooled( ) {
        return true;
    }
}
```

}

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 19. Diagnostics

Even good applications sometimes have bad things happen to them. When things go wrong, it is important to detect this as soon as possible, and to gather information to aid in diagnosing the source of the problem. On the developer's desktop, the tools for doing this include debuggers and profilers. However, once the application leaves the desktop, these tools are generally no longer available. Consequently, it becomes the application's responsibility to perform this detection and information-gathering role.

Because providing integrated error handling and reporting is such a common need among applications, the .NET Framework provides a diverse set of facilities to monitor application behavior, detect runtime errors, inspect the application environment, report application status, and integrate with debugging tools if available.

This chapter introduces the debugging and diagnostics support in the .NET Framework, which is primarily contained in the `System.Diagnostics` namespace. Unless otherwise stated, the types mentioned in this chapter all exist in either the `System` or `System.Diagnostics` namespaces.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

19.1 Logging and Assertion Facilities

The `Debug` and `Trace` classes provide error logging and assertion capabilities. These two classes are almost identical; the main differentiator is how they are used. The `Debug` class is used primarily in debug builds, while the `Trace` class is used in both debug and release builds.

For error logging and assertion, make use of the `Debug` and `Trace` classes where appropriate, then compile with the `DEBUG` symbol to enable the `Debug` class and the `TRACE` symbol to enable the `Trace` class. This is done using the `/define:symbol` compiler switch, or by using the `#define` preprocessor directive:

```
#define DEBUG // Equivalent to /d:DEBUG, activates Debug class
#define TRACE // Equivalent to /d:TRACE, activates Trace class
```

Note that using the compiler switch defines the symbols for all the source files in the compilation, while using the preprocessor directive defines only the symbol for the source file the directive appears in.

If these symbols are defined, the `Debug` and `Trace` methods function normally. If these symbols are not defined, many of the calls into the `Debug` and `Trace` classes are optimized away by the compiler.

Since the `Debug` and `Trace` classes are almost identical, we will concentrate on the `Debug` class in the rest of this section, identifying anything that is specific to either the `Debug` or `Trace` classes separately.

The `Debug` class maintains a collection of `TraceListener` instances that are responsible for handling (storing, reporting, etc.) application messages. Applications log status messages using the static `Debug.WriteXXX` methods, which forward the messages to each of the listeners in the `Debug.Listeners` collection. By default the `Listeners` collection includes a single listener (`DefaultTraceListener`), which outputs the message to the system debug console. However, the application is free to add and remove listeners to direct the messages elsewhere.

Adding and removing listeners can be done using a custom listener or one of the predefined listeners, such as the `EventLogTraceListener`, which logs messages to the Win32 event log, or the `TextWriterTraceListener`, which logs messages to a file or forwards them to another concrete type via an abstract `TextWriter` or `Stream` class, as the following code fragment demonstrates:

```
// Log messages to a file
Debug.Listeners.Add(new TextWriteTraceListener("Debug.out"));

TextWriter tw = Console.Out; // Get TextWriter for stdout
Debug.Listeners.Add(new TextWriterTraceListener(tw));

Stream stm = GetNetworkStream( ); // Connects to remote listener
Debug.Listeners.Add(new TextWriterTraceListener(stm));
```

Messages are written using the `Write`, `WriteLine`, `WriteIf`, and `WriteLineIf` overloads. Messages may optionally be assigned to a category, allowing listeners to group related messages. Messages

may also be indented. Examples of using these methods are as follows:

```
Debug.Write("Send this to all listeners, uncategorized");
Debug.WriteLine("Error", "Group this message with other errors");

Debug.Indent( );
Debug.WriteLineIf(bLogging, "Hug a tree (indented)"); // conditional
Debug.Unindent( );
```

When using listeners that may require cleanup, such as the `TextWriterTraceListener`, remember to call the `Flush` and `Close` methods on application shutdown, as follows:

```
Debug.Flush( ); // Flush underlying FileStream
Debug.Close( ); // Close Debug.out file
```

A useful technique for detecting error conditions early is using asserts to verify class or method invariants. The `Debug` and `Trace` classes both provide `Assert` and `Fail` methods that test expressions and can optionally invoke the debugger or log messages when an assertion fails, as follows:

```
Debug.Assert(expression); // Use to check class or method invariants
Debug.Assert(false, "Alert the listeners!"); // Log invalid assertions
...
Trace.Fail("Unknown error - about to die horribly");
Trace.Assert(veryImportantInvariant); // Asserts in release builds too...
```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

19.2 Conditional Compilation

The presence or absence of the `DEBUG` and `TRACE` symbols tell the compiler how to handle calls to methods in the `Debug` and `Trace` classes. If the `DEBUG` or `TRACE` symbols are not defined, many of the method calls into the `Debug` and `Trace` classes are optimized away completely. This can be a desirable feature for your own types, and there are a number of ways to accomplish this with the .NET Framework and the C# language.

One option is to bracket the calls with `#if/#endif` preprocessor directives, as follows:

```
void DoWork( ) {
    #if METHODCALL
        Debug.WriteLine("MethodCall", "Entering MyClass::DoWork");
    #endif
    Console.WriteLine("Working...");
}
```

Compiling this function with `/d:METHODCALL,DEBUG` results in a call to `Debug.WriteLine` and a log of the method entry. The downside to this approach is using preprocessor directives such as this is arduous and error-prone, and the code quickly becomes unreadable.

An alternative is to use the `ConditionalAttribute` custom attribute. When placed on a method, this attribute instructs the C# compiler to conditionally omit calls to the method.

Using this approach we can define a reflection-driven logger, as follows:

```
public class Logger {
    [Conditional("METHODCALL")]
    public static void LogMethodCall( ) {
        StackFrame sf = new StackFrame(1); // Get preceding stack frame
        MethodBase mb = sf.GetMethod( ); // Get refl. info for method
        Type t = mb.DeclaringType; // Get refl. info for type
        string s = String.Format("Entering {0}::{1}", t.Name, mb.Name);
        Debug.WriteLine("MethodCall", s); // Dump methodcall
    }
}
```

Client code can simply call this method on method entry, as follows:

```
void DoWork( ) {
    Logger.LogMethodCall( );
    Console.WriteLine("Working...");
}
```

When client code is compiled with `METHODCALL` defined, the C# compiler emits calls to the `LogMethodCall` function. If `METHODCALL` is not defined, the compiler omits the calls entirely.

19.3 Debugger Integration

Sometimes it is useful for an application to interact with a debugger if one is present. This is done using the `System.Diagnostics.Debugger` class. Properties and methods on this class allow one to detect if a debugger is attached (`IsAttached`) and logging messages (`IsLogged`); launch, attach, and signal a debugger (`Launch`); signal an attached debugger, launching one if necessary (`Break`); and log messages to a debugger if one is attached (`Log`).

Additionally, there are two custom attributes (`DebuggerStepThroughAttribute` and `DebuggerHiddenAttribute`) that can be placed on methods to control how the debugger handles the method.

`DebuggerStepThroughAttribute` indicates to the debugger that the method should be automatically stepped through without any user interaction. This attribute is suited for use in proxies and functions where the proxy method or thunk^[1] performs some trivial and/or predictable setup, calls the real method, and then performs some similarly trivial and/or predictable teardown. When single-stepping through code that calls the proxy method or thunk, the debugger automatically steps down into the real method.

^[1] A "thunk" is a small piece of code that forwards a call to another function.

When stepping through the "real" method, the call stack in the debugger still lists the proxy method or thunk. To hide it completely, use the related `DebuggerHiddenAttribute` attribute. These two attributes can be combined on proxies and thunks to help the user focus on debugging the application logic, not the plumbing.

```
void DoWork( ) {...} // Real method...
...
[DebuggerStepThrough, DebuggerHidden]
void DoWorkProxy( ) {
    // setup...
    DoWork( );
    // teardown...
}
...
o.DoWorkProxy( ); // "Step into" passes control into DoWork( )
```

19.4 Processes, Threads, and Stacks

The .NET Framework provides managed execution of code. However, managed applications live alongside unmanaged applications, and need to coexist. It can be useful for a managed application to have access to information about the atoms of unmanaged execution, namely operating system processes and threads. Additionally, since "managed execution" implies the existence of some overarching facility monitoring the execution process itself, it is not unreasonable to wish for access to detailed information about the execution process. Both of these needs are met by the classes in the `System.Diagnostics` namespace, providing access to unmanaged processes and threads, as well as access to managed stack frames. Access to managed threads and `AppDomains`, which are the managed equivalent of processes, is accomplished using the `System` and `System.Threading` namespaces.

19.4.1 Launching a New Process

The `Process` class can be used to launch new operating system processes, enumerate and kill existing ones, and monitor the vital statistics of a running process. The `Process.Start` method has overloads that range from taking the filename of an EXE to launch to taking a populated `ProcessStartInfo` instance, which fully specifies the parameters for process launching. The latter approach can also be used to capture and redirect the launched process's `stdin`, `stdout` and `stderr`, as the following sample demonstrates:

```
public void LaunchDirCommand( ) {
    ProcessStartInfo psi = new ProcessStartInfo( );
    psi.FileName = "cmd.exe";
    psi.Arguments = "/c dir";
    psi.RedirectStandardOutput = true;
    psi.UseShellExecute = false;
    Process p = Process.Start(psi);
    StreamReader stm = p.StandardOutput;
    string s = stm.ReadToEnd( );
    Console.WriteLine(s);
}
```

19.4.2 Examining Running Processes

The `Process.GetProcessXXX` methods allow an application to retrieve a specific process by name or process ID, and to enumerate all running processes. Given a valid process instance, a wealth of properties provide access to the process's vital statistics such as name, ID, priority, memory and processor utilization, window handles, etc. The following sample enumerates some basic information for all the running processes in the system:

```
public void EnumerateRunningProcesses( ) {
    Process[] procs = Process.GetProcesses( );
    foreach (Process p in procs) {
```

```

        Console.WriteLine("{0} ({1})", p.ProcessName, p.Id);
        Console.WriteLine("    Started: {0}", p.StartTime);
        Console.WriteLine("    Working set: {0}", p.WorkingSet);
        Console.WriteLine("    Processor time: {0}", p.TotalProcessorTime);
        Console.WriteLine("    Threads: {0}", p.Threads.Count);
    }
}

```

19.4.3 Examining Threads in a Process

Building on the previous example, it is also possible to retrieve information on the operating system threads in a process using the `Process.Threads` property. This returns a collection of `ProcessThread` instances, each representing an underlying operating system thread (which may or may not have a managed `System.Threading.Thread` counterpart). Given a reference to a `ProcessThread` instance we can discover a host of information about the underlying thread and even control aspects such as thread priority and processor affinity.

```

public void EnumerateThreads(Process p) {
    ProcessThreadCollection ptc = p.Threads;
    foreach (ProcessThread pt in ptc) {
        Console.WriteLine("Thread {0} ({1})", pt.Id, pt.ThreadState);
        Console.WriteLine("    Priority Level: {0}", pt.PriorityLevel);
        Console.WriteLine("    Started: {0}", pt.StartTime);
        Console.WriteLine("    Processor time: {0}", pt.TotalProcessorTime);
    }
}
...
Process p = Process.GetCurrentProcess();
EnumerateThreads(p);

```

19.4.4 Examining Stack Frames for a Thread

One of the benefits of managed execution is that the Execution Engine has visibility into the execution process for managed applications. The `StackTrace` and `StackFrame` classes provide read-only access to some of this information, namely the application call stack and the individual stack frames. This information can be used in exception handling code to determine what led up to the failure, and to improve the quality of error reporting.

```

// Compile with /debug+ to disable JIT inlining, provide src debug info
using System;
using System.Diagnostics;

class DumpStackFrames {
    static void WalkStack( ) {
        StackTrace st = new StackTrace(true); // true= use .PDB if available
        Console.WriteLine("Current stack has {0} frames", st.FrameCount);
        for (int i=0; i<st.FrameCount; i++) {
            StackFrame sf = st.GetFrame(i);
            Console.WriteLine("\nFrame {0}: {1}, ", i, sf.GetMethod( ).Name);
            Console.WriteLine("{0}@{1}", sf.GetFileName( ), sf.GetFileLineNumber( ));
        }
    }
}

```

```
    }  
}  
static void A( ) { B( ); }  
static void B( ) { C( ); }  
static void C( ) { WalkStack( ); }  
static void Main( ) { A( ); }  
}
```

A run of the preceding example produces the following output:

```
Current stack has 5 frames  
Frame 0: WalkStack, c:\CSiaN\Diagnostics\DumpStack.cs@7  
Frame 1: C, c:\CSiaN\Diagnostics\DumpStack.cs@17  
Frame 2: B, c:\CSiaN\Diagnostics\DumpStack.cs@16  
Frame 3: A, c:\CSiaN\Diagnostics\DumpStack.cs@15  
Frame 4: Main, c:\CSiaN\Diagnostics\DumpStack.cs@18
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#)[NEXT ▶](#)

19.5 Event Logs

Useful as the `Debug` and `Trace` classes are, the Win32 platform already provides a logging mechanism in the form of the event log. Classes are provided in the `System.Diagnostics` namespace that allow applications to enumerate the existing event sources and logs, read from and write to an event log manually, use an event log as a backing store for `Trace` or `Debug` output, create and install new event sources, and monitor an event log for changes.

19.5.1 Reading the Event Log

To read an event log, create an instance of the `EventLog` class with the name of the log you wish to access, and optionally the name of the machine on which the log resides and the event source with which to filter the log entries. Once you have a valid `EventLog` instance, it provides a wealth of properties and methods that let you examine and manipulate the log as a whole. To read the individual entries in the log, use the `EventLog.Entries` property to retrieve a collection of `EventLogEntry` instances. The following sample displays information on any log on your system:

```
// DumpLog.cs - use DumpLog <logname>
using System;
using System.Diagnostics;

class DumpLog {
    static void Main(string[] args) {
        // Present the alternatives
        if (args.Length <= 0) {
            EventLog[] ela = EventLog.GetEventLogs();
            Console.WriteLine("Usage:  DumpLog <logname>");
            Console.WriteLine("\n\tWhere <logname> is one of:\n");
            foreach (EventLog el in ela) {
                Console.WriteLine("\t{0}", el.LogDisplayName);
            }
            return;
        }
        // Extract the parameters
        string logName = args[0];
        // Check the log actually exists
        if (!EventLog.Exists(logName)) {
            Console.WriteLine("Unknown log name {0}", logName);
            return;
        }
        // Iterate over the entire log, dumping the events
        EventLog el = new EventLog(logName);
        Console.WriteLine("{0} on {1}", el.LogDisplayName, el.MachineName);
        EventLogEntryCollection elec = el.Entries;
        foreach (EventLogEntry ele in elec) {
```

```

        Console.WriteLine("Event ID {0} ({1}):{2}",
            ele.EventID, ele.EntryType, ele.Message);
        Console.WriteLine("    generated by {0} on {1} for {2}@{3}",
            ele.Source, ele.TimeGenerated, ele.UserName, ele.MachineName);
    }
}
}

```

19.5.2 Writing to the Event Log

Similarly, one can write to the event log using the same `EventLog` class used in the previous example. The only complexity arises because log entries need a source-if the event source doesn't already exist, you need to create it. As the following sample demonstrates, creating a command-line utility to add events to an event log on the local machine is trivial:

```

// WriteLog.cs - use WriteLog <logname> <message>
using System;
using System.Diagnostics;
class WriteLog {
    const string SOURCE = "CSian";
    static void Main(string[] args) {
        // Extract the parameters
        string logName = args[0], message = args[1];
        // Verify the log actually exists
        if (!EventLog.Exists(logName)) {
            Console.WriteLine("Unknown log name '{0}'", logName);
            return;
        }
        // Create the CSian event source if necessary
        if (!EventLog.SourceExists(SOURCE) ) {
            EventLog.CreateEventSource(SOURCE, logName);
        }
        // Write the event to the log on the local machine
        EventLog el = new EventLog(logName, ".", SOURCE);
        el.WriteEntry(message)
    }
}

```

19.5.3 Monitoring the Event Log

In some cases it can be useful to monitor the event log, examining new entries as they are written and taking appropriate action. To do this, register a listener for the `EventLog.EntryWritten` event on a log we are interested in monitoring. As new event log entries are added to the log, you receive callbacks, and can access the details of the new event log entry and take appropriate action. The following sample demonstrates registering a listener to display new events in a log as they are written. (To generate new events in the log, use the preceding `WriteLog` sample.)

```

// WatchLog.cs - use WatchLog <logname>
using System;
using System.Diagnostics;

```

```
class WatchLog {
    static void NewEntryCallback(object o, EntryWrittenEventArgs ewea) {
        // The new entry is included in the event arguments
        EventLogEntry ele = ewea.Entry;
        Console.WriteLine("New event in log: {0}", ele.Message);
    }
    static void Main(string[] args) {
        // Check the arguments and provide help
        if (args.Length != 1) {
            Console.WriteLine("Usage: WatchLog <logname>");
            return;
        }
        // Verify the log actually exists
        string logName = args[0];
        if (!EventLog.Exists(logName)) {
            Console.WriteLine("Unknown log name '{0}'", logName);
            return;
        }
        // Register handler and wait for keypress
        EventLog el = new EventLog(logName);
        el.EntryWritten += new EntryWrittenEventHandler(NewEntryCallback);
        el.EnableRaisingEvents = true;
        Console.WriteLine("Listening for events - press <enter> to end");
        Console.ReadLine();
    }
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

19.6 Performance Counters

Event logs are useful for capturing application status that is not of a time-sensitive nature, yet needs to be recorded for future analysis. However, to gain insight into the current state of an application (or the system as a whole), a more real-time approach is needed.

The Win32 solution to this need is the performance-monitoring infrastructure, which consists of a set of performance counters that the system and applications expose, and the Microsoft Management Console (MMC) snap-ins used to monitor these counters in real time.

Performance counters are grouped into categories such as "System," "Processor," ".NET CLR Memory," and so on. These categories are sometimes also referred to as "performance objects" by the GUI tools. Each category groups a related set of performance counters that monitor one aspect of the system or application. Examples of performance counters in the ".NET CLR Memory" category include "% Time in GC," "# Bytes in All Heaps," and "Allocated bytes/sec."

Each category may optionally have one or more instances that can be monitored independently. For example, this is useful in the "% Processor Time" performance counter in the "Processor" category, which allows one to monitor CPU utilization. On a multiprocessor machine, this counter supports an instance for each CPU, allowing one to monitor the utilization of each CPU independently.

The following sections illustrate how to perform commonly needed tasks, such as determining which counters are exposed, monitoring a counter, and creating your own counters to expose application status information.

19.6.1 Enumerating the Available Counters

In the following example, enumerate all of the available performance counters on the system. To do this, first retrieve a list of the categories, then iterate through the list displaying the counters and instances for each category, as follows:

```
// DumpCounters.cs
using System;
using System.Diagnostics;
class DumpCounters {
    static void Main( ) {
        PerformanceCounterCategory[ ] cats;
        cats = PerformanceCounterCategory.GetCategories( );
        foreach (PerformanceCounterCategory cat in cats) {
            try {
                Console.WriteLine("Category: {0}", cat.CategoryName);
                string[ ] instances = cat.GetInstanceNames( );
                if (instances.Length == 0) {
                    // Dump counters without instances
                    foreach (PerformanceCounter ctr in cat.GetCounters( ))
                        Console.WriteLine("  Counter: {0}", ctr.CounterName);
                }
            }
            catch {
                // Ignore exceptions
            }
        }
    }
}
```

```

    } else {
        // Dump counters with instances
        foreach (string instance in instances) {
            Console.WriteLine("  Instance: {0}", instance);
            foreach (PerformanceCounter ctr in cat.GetCounters(instance))
                Console.WriteLine("    Counter: {0}", ctr.CounterName);
        }
    }
} catch (Exception e) { // Some perf counters don't provide details
    Console.WriteLine("Exception: {0}", e.Message);
}
}
}
}

```

19.6.2 Reading Performance Counter Data

The following sample demonstrates how to retrieve the current value for an arbitrary performance counter. It incorporates error-handling code to illustrate how to verify category, counter, and instance name before attempting to read a performance counter value. Use the preceding `DumpCounters` sample to enumerate the available categories, counters, and instances on your machine, and pass them to the sample on the command line:

```

// WatchCounter.cs - use WatchCounter <category> <counter> [<instance>]
using System;
using System.Threading;
using System.Diagnostics;
class WatchCounter {
    static void Main(string[] args) {
        // Extract the parameters
        string cat = args[0], ctr = args[1];
        string inst = (args.Length == 3) ? args[2] : "";
        // Check the category is OK
        if (!PerformanceCounterCategory.Exists(cat)) {
            Console.WriteLine("Unknown category {0}", cat);
            return;
        }
        // Check the counter is OK
        if (!PerformanceCounterCategory.CounterExists(ctr, cat)) {
            Console.WriteLine("Unknown counter {0}", ctr);
            return;
        }
        // Check the instance is OK
        if (inst.Length > 0 &&
            !PerformanceCounterCategory.InstanceExists(inst, cat)) {
            Console.WriteLine("Unknown instance {0}", inst);
            return;
        }
        // Spin in a loop, dumping the counter
        Console.WriteLine("Press <ctrl+c> to end");
        PerformanceCounter pc = new PerformanceCounter(cat, ctr, inst);
    }
}

```

```

        while (true) {
            Console.WriteLine("Counter value is {0}", pc.NextValue( ));
            Thread.Sleep(1000); // No! Bad programmer!
        }
    }
}

```

19.6.3 Adding a New Performance Counter

To expose real-time status information about your applications, instantiate a read/write `PerformanceCounter` object with the name of an existing category, the name of the new counter, and the name of the new instance, then update the value of the counter as the application status changes. The following sample demonstrates how to create your own counter and expose application status values through it. (To watch the changing counter values, use the preceding `WatchCounter` sample.)

```

// WriteCounter.cs - use WriteCounter <category> <counter> [<instance>]
using System;
using System.Threading;
using System.Diagnostics;
class WriteCounter {
    static void Main(string[ ] args) {
        // Extract the parameters
        string cat = args[0], ctr = args[1];
        string inst = (args.Length== 3) ? args[2] : "";
        // Create the category if it doesn't already exist
        if (!PerformanceCounterCategory.Exists(cat)) {
            PerformanceCounterCategory.Create(cat, "", ctr, "");
        }
        // Check the counter is OK
        if (!PerformanceCounterCategory.CounterExists(ctr, cat)) {
            Console.WriteLine("Unknown counter {0}", ctr);
            return;
        }
        // Create a new read/write counter & instance for an existing category
        PerformanceCounter pc = new PerformanceCounter(cat, ctr, inst, false);
        // Create counter and spin in a loop, incrementing it
        Console.WriteLine("Press <ctrl+c> to end");
        while (true) {
            Console.WriteLine("Incrementing counter...");
            pc.Increment( );
            Thread.Sleep(1000); // No! Bad programmer!
        }
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Chapter 20. C# Language Reference

The following table describes the syntax of various C# language elements. The left column shows the syntax element, and the right column includes one or more examples.

Arrays		
	<pre>type [*] + array-name = [new type [dimension+][*]*; { value1, value2, ... };]</pre>	<pre>byte[] arr1 = new byte[10]; int[] arr2 = {0, 1, 2}; ([*] is the set: [] [,] []</pre>
Attributes		
	<pre>[[target:]? attribute-name (positional-param+ [named-param = expr]+ positional-param+, [named-param = expr]+)?]</pre>	<pre>[assembly:CLSCompliant(false)] [WebMethod(true, Description="My web method")]</pre>
Break statement		
	<pre>break;</pre>	<pre>break;</pre>
Checked/unchecked		
	<pre>checked (expr) unchecked (expr)</pre>	<pre>// throws exception short x = 32767; int i = checked((short) +1); // silently overflows to -32768 short y = 32767; int j = unchecked((short) +1);</pre>
	<pre>checked [statement statement-block] unchecked [statement statement-block]</pre>	<pre>// throws exception public short foo() { short y = 32767; checked { return ++y; } } // silently overflows public short bar() { short y = 32767; unchecked { return ++y; } }</pre>

		}
Class declaration		
	<i>attributes?</i> <i>unsafe?</i> <i>access-modifier?</i> <i>new?</i> [<i>abstract</i> <i>sealed</i>]? <i>class class-name</i> [: <i>base-class</i> : <i>interface+</i> : <i>base-class, interface+</i>]? { <i>class-members</i> }	<i>public class MyClass : Base</i> <i>// ...</i> <i>}</i>
Constant declaration		
	<i>const type</i> [<i>variable = constant-expr</i>]+;	<i>const int xyzzy = 42;</i>
Constant fields		
	<i>attributes?</i> <i>access-modifier?</i> <i>new?</i> <i>const type</i> [<i>constant-name =</i> <i>constant-expr</i>]+;	<i>internal const byte fnord</i>
Continue statement		
	<i>continue;</i>	<i>continue;</i>
Delegates		
	<i>attributes?</i> <i>unsafe?</i> <i>access-modifier?</i> <i>new?</i> <i>delegate</i> [<i>void</i> <i>type</i>] <i>delegate-name</i> (<i>parameter-list</i>);	<i>public delegate void</i> <i>MyHandler(object s, Event</i>
Destructors		
	<i>attributes?</i> <i>unsafe?</i> <i>~class-name</i> () <i>statement-block</i>	<i>~SomeClass() {</i> <i>// destructor code</i> <i>}</i>
Do-While loops		
	<i>do</i> [<i>statement /statement-block</i>] <i>while</i> (<i>Boolean-expr</i>);	<i>int i = 0;</i> <i>do { // print 0 through 9</i> <i>Console.WriteLine(i++);</i> <i>} while(i < 10);</i>
Empty statements		

	<code>;</code>	<code>i = 0; while(i++ < 10) ; // take no action Console.WriteLine(i); // p</code>
Enums		
	<code>attributes? access-modifier? new? enum enum-name [: integer-type]? { [attributes? enum-member-name [= value]?]* }</code>	<code>[Flags] public enum Color Red = 0xff0000, Green = 0x00ff00, Blue = 0x0000ff }; //... // prints "Green, Red" Color yellow = (Color) 0xf Console.WriteLine(yellow);</code>
Events		
	<code>attributes? unsafe? access-modifier? [[[sealed abstract]? override] new? [virtual static]?]? event delegate-type event-name</code>	<code>event MyDelegate OnClicked; // ... OnClickedSomething(arg1, a</code>
Event accessors		
	<code>attributes? unsafe? access-modifier? [[[sealed abstract]? override] new? [virtual static]?]? event delegate-type event-accessor-name { attributes? add statement-block attributes? remove statement-block }</code>	<code>event MyDelegate OnAction add { // ... } remove { // ... } }</code>
Expression statements		
	<code>[variable =]? expr;</code>	<code>a = 10 * 10; a++; b = ++a;</code>
Fields		
	<code>attributes? unsafe? access-modifier? new? static? [readonly volatile]? type [field-name [= expr]?]+ ;</code>	<code>protected int agent = 0x00</code>

Fixed statements		
	<pre>fixed ([value-type void]* name = [&]? expr) statement-block</pre>	<pre>byte[] b = {0, 1, 2}; fixed (byte* p = b) { *p = 100; // b[0] = 100 }</pre>
For loops		
	<pre>for (statement?; Boolean-expr?; statement?) [statement statement-block]</pre>	<pre>// print 0 through 9 for(int j=0; j<10; j++) Console.WriteLine(j);</pre>
Foreach loops		
	<pre>foreach (type-value in IEnumerable) statement or statement-block</pre>	<pre>StringCollection sc = new StringCollection(); sc.Add("Hello"); sc.Add("World"); foreach(String s in sc) Console.WriteLine(s);</pre>
Goto statement		
	<pre>goto statement-label; goto case-constant;</pre>	<pre>i = 0; MyLabel: if(++i < 100) goto MyLabel; Console.WriteLine(i);</pre>
If-Else statement		
	<pre>if (Boolean-expr) [statement statement-block] [else [statement statement-block]]?</pre>	<pre>if(choice == "A") { // ... } else if (choice == "B" // ... } else { // ... }</pre>
Indexers		
	<pre>attributes? unsafe? access-modifier? [[[sealed abstract]? override] new? [virtual abstract static]?]? type this [attributes? [type arg]+] { attributes? get // read-only statement-block attributes? set // write-only statement-block attributes? get // read-write</pre>	<pre>string this[int index] { get { return somevalue; } set { // do something with // implicit "value" arg } }</pre>

	<pre>statement-block attributes? set statement-block }</pre>	<pre>}</pre>
Instance constructors		
	<pre>attributes? unsafe? access-modifier? class-name (parameter-list) [:[base this] (argument-list)]? statement-block</pre>	<pre>MyClass(int i) { // perform initialization } // Initialize with default MyClass() : this(42) { }</pre>
Interfaces		
	<pre>attributes? unsafe? access-modifier? new? interface interface-name [: base-interface+]? { interface-members }</pre>	<pre>interface IFoo : IDisposable, IComparable { // member declarations }</pre>
Lock statement		
	<pre>lock (expr) [statement statement-block]</pre>	<pre>lock(this) { int tmp = a; a = b; b = tmp; }</pre>
Method declaration syntax		
	<pre>attributes? unsafe? access-modifier? [[[sealed abstract]? override] new? [virtual abstract static extern]?]? [void type] method-name (parameter-list) statement-block</pre>	<pre>public abstract int MethA(public virtual void MethB({ // statements... }</pre>
Namespace		
	<pre>namespace name+ { using-statement* [namespace-declaration type-declaration]* } (namespace is dot-delimited)</pre>	<pre>namespace OReilly.CSharp { using System; interface IFoo : IComparable public class MyClass { }</pre>

	(namespace-declaration has no delimiters)	
Parameter list		
	<pre>[attributes? [ref out]? type arg]* [params attributes? type[] arg]?</pre>	<pre>void MethA(ref int a, out int b) { b = ++a; } void MethB(params string[] args) { foreach (string s in args) Console.WriteLine(s); } // ... int a = 20, b; MethA(ref a, out b); Console.WriteLine("a={0}, b={0}", a, b); MethB("hello", "world");</pre>
Properties		
	<pre>attributes? unsafe? access-modifier? [[[sealed abstract]? override] new? [virtual abstract static]?]? type property-name { [attributes? get // read-only statement-block attributes? set // write-only statement-block attributes? get // read-write statement-block attributes? set statement-block] }</pre>	<pre>private string name; public string Name { get { return name; } set { name = value; } }</pre>
Return statement		
	<pre>return expr?;</pre>	<pre>return; return x;</pre>
Statements and statement blocks		
	<pre>statement</pre>	<pre>int x = 100;</pre>
	<pre>statement-block</pre>	<pre>{ int x = 100; Console.WriteLine(x); return x; }</pre>
Static constructors		

	<code>attributes? unsafe? extern? static class-name () statement-block</code>	<code>static MyClass() { // initialize static mem }</code>
Struct declaration		
	<code>attributes? unsafe? access-modifier? new? struct struct-name [: interface+]? { struct-members }</code>	<code>public struct TwoFer { public int part1, part2; }</code>
Switch statement		
	<code>switch (expr) { [case constant-expr : statement*]* [default : statement*]? }</code>	<code>switch(choice) { case "A": // ... do something break; case "B": // ... do something // then branch to A goto case "A"; case "C": case "D": // ... do something break; default: Console.WriteLine("bad break; }</code>
Throw statement		
	<code>throw exception-expr?;</code>	<code>throw new Exception("something's w</code>
Try statements and exceptions		
	<code>try statement-block [catch (exception type value?)? statement-block]+ finally statement-block [catch (exception type value?)? statement-block]+ finally statement-block</code>	<code>try { // do something } catch (Exception) { // recover } finally { // this will always // be called }</code>
Using statement		
	<code>using (declaration-expr) [statement statement-block]</code>	<code>using(StreamReader s = new StreamReader("README { // ... }</code>

		// s is disposed here
Variable declaration		
	<code>type [variable [= expr]?]+ ;</code>	<code>long a, b, c; int x = 100;</code>
While loops		
	<code>while (Boolean-expr) [statement statement-block]</code>	<code>int i = 0; while(i < 10) { // print 0 through 9 Console.WriteLine(i++); }</code>

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Part III: Language and Tools Reference

Part III contains:

[Chapter 21](#)

[Chapter 22](#)

[Chapter 23](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 21. XML Documentation Tag Reference

[Table 21-1](#) lists the predefined set of XML tags that can be used to mark up the descriptive text. [Table 21-2](#) lists possible prefixes for type and member cross-references.

Table 21-1. Predefined XML tags

Tag	Description
<summary>	<p><code><summary>description</summary></code></p> <p>Describes a type or member. Typically, this contains the description of a member at a fairly high level.</p>
<remarks>	<p><code><remarks>description</remarks></code></p> <p>Provides additional information regarding a particular member. Information about side effects within the method, or particular behavior that may not otherwise be intuitive (such as the idea that this method may throw an <code>ArrayOutOfBoundsException</code> if a parameter is greater than 5) should be listed here.</p>
<param>	<p><code><param name="name">description</param></code></p> <p>Describes a parameter on a method. The name attribute is mandatory and must refer to a parameter on the method. If this tag is applied to any parameter on a method, all parameters on that method must be documented. You must enclose <code>name</code> in double quotation marks ("").</p>
<returns>	<p><code><returns>description</returns></code></p> <p>This tag describes the return values for a method.</p>
<exception>	<p><code><exception [cref="type"]>description</exception></code></p> <p>Describes the exceptions a method may throw. If present, the optional <code>cref</code> attribute should refer to the type of exception. You must enclose <code>type</code> in double quotation marks ("").</p>
<permission>	<p><code><permission [cref="type"]>description</permission></code></p> <p>Describes the permission requirements for a type or member. If present, the optional <code>cref</code> attribute should refer to the type that represents the permission set required by the member, although the compiler doesn't validate this. You must</p>

Tag	Description
	enclose <code>type</code> in double quotation marks ("").
<code><example></code>	<code><example>description</example></code> Provide a description and sample source code explaining the use of a type or member. Typically, the <code><example></code> tag provides the description and contains the <code><c></code> and <code><code></code> tags (described next), although these can also be used independently.
<code><c></code>	<code><c>code</c></code> Indicates an inline code snippet. Typically, this is used inside of an <code><example></code> block (just described).
<code><code></code>	<code><code>code</code></code> Used to indicate multiline code snippets. Again, typically used inside of an <code><example></code> block.
<code><see></code>	<code><see cref="member">text</see></code> Identifies cross-references in the documentation to other types or members. Typically, the <code><see></code> tag is used inline within a description (as opposed to the <code><seealso></code> tag, below, which is broken out into a separate "See Also" section). These tags are useful because they allow tools to generate cross-references, indexes, and hyperlinked views of the documentation. Member names must be enclosed by double quotation marks ("").
<code><seealso></code>	<code><seealso cref="member">text</seealso></code> Identifies cross-references in the documentation to other types or members. Typically, <code><seealso></code> tags are broken out into a separate "See Also" section. These tags are useful because they allow tools to generate cross-references, indexes, and hyperlinked views of the documentation. Member names must be enclosed by double quotation marks ("").
<code><value></code>	<code><value>description</value></code> Describes a property on a class.
<code><paramref></code>	<code><paramref name="name" /></code> Identifies the use of a parameter name within descriptive text, such as <code><remarks></code> or <code><summary></code> . The name must be enclosed by double quotation marks ("").
<code><list></code>	<code><list type=[bullet number table]></code> <code><listheader></code> <code><term>name</term></code> <code><description>description</description></code> <code></listheader></code> <code><item></code> <code><term>name</term></code> <code><description>description</description></code>

Tag	Description
	<div></item> </list></div> <p>Provide hints to documentation generators on how to format the documentation-in this case as a list of items.</p>
<para>	<div><para>text</para></div> <p>Sets off the text as a paragraph to documentation generators.</p>
<include>	<div><include file='filename' path='path-to-element'></div> <p>Specifies an external file that contains documentation and an XPath path to a specific element in that file. For example, a path of docs[@id="001"]/* retrieves whatever is inside of <docs id="001"/>. The filename and path must be enclosed by single quotation marks ("").</p>

Table 21-2. XML type ID prefixes

Prefix	Applied to
N	Namespace
T	Type (class, struct, enum, interface, delegate)
F	Field
P	Property (includes indexers)
M	Method (includes special methods)
E	Event
!	Error

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 22. C# Naming and Coding Conventions

Naming conventions have long been understood to be a beneficial practice in software development, for a variety of reasons elucidated more clearly and persuasively elsewhere. The benefits of a naming convention, however, take special meaning in the cross-language environment that .NET offers—for the first time, a class library written in C# can be accessed verbatim from VB, C++, Eiffel, and any other ".NET-consumer" language, compiler, or environment. While "industry practices" are hard to discuss in an industry that has yet to even ship its first release, Microsoft has released some guidelines to its own naming conventions, used predominantly in the Framework Class Library; even if you and your development shop choose to use alternative conventions, understanding the naming conventions of the FCL is key to using it effectively.

There are three elements of naming guidelines:

- Case (capitalization)
- Mechanics (class names, method names, and so on)
- Word choice (consistent terminology and phraseology)

Much of this information can also be found in the Microsoft documentation set.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

22.1 Case

Throughout the years, computer scientists have never been able to agree on one common way in which to express human-readable concepts (including word breaks for compound names such as "XML reader" or "input stream") in arenas in which normal rules of English, such as spaces, cannot apply. As a result, various languages have used different rules and formats to indicate where a logical word break should occur.

A variety of styles have emerged over the years, summarized here:

Pascal

The Pascal language was the first to use this style of capitalization, hence its name. In a compound name (such as "input stream" or "base type"), capitalize the first letter of each word, then eliminate the space. Thus, "input stream" becomes "InputStream" and "base type" becomes "BaseType". Proponents of this style like the fact that each word is distinctly separated (the uppercase letter always signifies a new word), while detractors point out that acronyms become difficult to work with. "xml parser" becomes "XMLParser", and "HTTP IO Factory" becomes "HTTPIOFactory".

Camel

"Camel-casing," as its called, is the style used frequently in Java. Again, in a compound name, the first letter of each word is capitalized, except for the first word, which is left lowercase. This produces, for example, "baseType" and "inputStream". Acronyms become particularly difficult if they come as the first word and styles diverge. The general agreement seems to be to have the entire acronym lowercased, as in "xmlParser".

All-caps

This style is distinctive, if a bit difficult to read. All letters of the word are uppercased (as if typing with the caps-lock key down), and spaces are again eliminated. While it becomes visually distinctive, all-caps identifiers tend to become hard to read—for example "BASETYPE" or "INPUTSTREAM". As a result, aside from die-hard COBOL programmers, all-caps casing tends to be used only sporadically within a modern language.

Underscore-separation

Also known as "C-casing," this style has recently fallen out of favor, particularly in C++ and Java programming circles. C-casing keeps all words in lowercase, using the underscore (`_`) to replace spaces. Proponents like this style because it makes the compound name look nearly identical to the English equivalent ("input_stream" or "base_type"); detractors claim the underscore is overused and abused in names ("prepare_to_accept_the_users_input"). Underscore-separation case doesn't show up in the .NET Framework directly, but will probably appear as legacy C and C++ applications are ported (or simply recompiled) for the .NET environment.

As with many things, no one style fits all, and the Microsoft naming conventions use the first three (particularly Pascal casing) throughout.

Capitalization rules can be mostly summarized as the following:

- Any name which is visible to consumers of the assembly (that is, anything declared with an access specifier of "public" or "protected") should be Pascal-cased. This means class names, properties, methods, and events.
- Names internal to the assembly can be pretty much anything the component developer wishes (subject to corporate standards, of course); however, the Microsoft convention appears to continue the use of Pascal-casing for methods, events and properties. Fields are camel-cased.
- Symbolic constants (the value of pi, the HTTP response code for a "File Not Found" error, and so forth) should be written using all-caps.

Remember that other languages in .NET are not case-sensitive; never differentiate between two C# methods using only case. (On top of being not CLS-compliant, this is just bad form and confusing.)

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

22.2 Mechanics

Mechanics, in this case, refers to the process of selecting a name for a given metadata token in the language such as class, interface, field, parameter, and so on.

Microsoft, in its "Naming Guidelines" topic (under the ".NET Framework Design Guidelines" in the .NET SDK Documentation), contains a list of "Do's" and "Don'ts" regarding naming guidelines. Rather than reprint that list here in either parroted or paraphrased form, we just make the following general suggestions.

Names should be descriptive and concise. More importantly, they should be meaningful to the principal consumers of the name-use syntax, phraseology, and terms that are familiar to the developers who will use the code you are writing.

As suggested, since classes and interfaces and value types are often marked "public," use Pascal-case for their names.

Interfaces should always be prefixed with **I**, following in COM tradition. Following the Pascal-casing rules, make sure the next letter of the interface is also capitalized, as in **IComparable** (indicating an interface that provides comparable behavior). Frequently, interfaces are also descriptive names (**Comparable**, **Disposable**, and so on), rather than nouns.

Other than the **I** for interfaces, do not use any sort of prefixes on names. This is what namespaces are for.

Attributes should always end in the **Attribute** suffix. The C# compiler can use shorthand naming rules (allowing you to leave off the **Attribute** portion of the name when using the attribute) if you follow this convention.

Enums should use Pascal-casing, both for the typename and the values within the enumerated type.

Fields should be named relative to what they store. Microsoft specifically recommends against using Hungarian notation, even the MFC **m_** style; however, this style shows up in a few places inside the FCL. Use what feels right to you and your peers, but be consistent.

Events should be suffixed with **EventHandler**; event argument types should be suffixed with **EventArgs**. Frequently, events are prefixed with an **On**, indicating the event is fired "on button clicks" or "on window closing"; this is not entirely consistent, however.

Exceptions should always be suffixed with **Exception**.

22.3 Word Choice

It's wise to avoid using class names duplicated in heavily used namespaces. For instance, do not use the following for a class name:

System Collections Forms UI

Also avoid using identifiers that conflict with common keywords; remember that all keywords must be escapable (and therefore usable) within any .NET language, but that doesn't mean it's easy to do. Avoid the identifier names listed in [Table 22-1](#).

Table 22-1. Common keywords best avoided in class names

AddHandler	AddressOf	Alias	And	Ansi
As	Assembly	Auto	BitAnd	BitNot
BitOr	BitXor	Boolean	ByRef	Byte
ByVal	Call	Case	Catch	CBool
CByte	CChar	CDate	CDec	CDbl
Char	CInt	Class	CLng	CObj
Const	CShort	CSng	CStr	CType
Date	Decimal	Declare	Default	Delegate
Dim	Do	Double	Each	Else
Elself	End	Enum	Erase	Error
Eval	Event	Exit	Extends	ExternalSource
False	Finally	For	Friend	Function
Get	GetType	Goto	Handles	If
Implements	Imports	In	Inherits	Integer
Interface	Is	InstanceOf	Let	Lib
Like	Long	Loop	Me	Mod
Module	MustInherit	MustOverride	MyBase	MyClass
Namespace	New	Next	Not	Nothing
NotInheritable	NotOverridable	Object	On	Option

Optional	Or	Overloads	Overridable	Overrides
Package	ParamArray	Preserve	Private	Property
Protected	Public	RaiseEvent	ReadOnly	ReDim
Region	REM	RemoveHandler	Resume	Return
Select	Set	Shadows	Shared	Short
Single	Static	Step	Stop	String
Structure	Sub	SyncLock	Then	Throw
To	True	Try	TypeOf	Unicode
Until	Var	Variant	When	While
With	WithEvents	WriteOnly	Xor	

Try to avoid using abbreviations in identifiers (including parameter names), but if doing so renders the name more unintelligible, use camel-casing rules for any abbreviation over two characters, even if this is not the standard abbreviation. (Thus, the compound name "XML reader" should be called "XmlReader").

[\[Team LiB \]](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

22.4 Namespaces

The general pattern to follow when naming namespaces is:

`CompanyName.TechnologyName`

Some examples of well-formed namespaces are:

`Microsoft.Office`
`Corel.OfficePerfect`
`OReilly.CSharpInANutshell`

One problem that may arise, particularly as more companies begin to write code for the .NET platform, is that the "company-level" namespaces may clash. Java sought to avoid this problem by strongly suggesting companies use their reverse-DNS name ("oreilly.com" produces "com.oreilly" top-level namespace names), since DNS names are guaranteed to be unique. Over time, however, this proved to be less of an issue than originally thought, and many companies began to use the "center" name in the DNS name (for instance "oreilly" in "oreilly.com"). There is no reason to believe this convention won't continue to work in .NET.

For legibility, use Pascal case, and separate logical components with periods (for example, `Microsoft.Office.PowerPoint`). However, if your product involves nontraditional capitalization, it's okay to use that system, even if it deviates from normal namespace casing (for example `NeXT.WebObjects`, `OReilly.Network` and `ee.cummings`).

Plural namespace names are recommended where appropriate—for example, use `System.Collections`, not `System.Collection`. Exceptions to this rule are brand names and abbreviations—for example, use `System.IO`, not `System.IOs`.

Never reuse names across namespace and class names—for example, the `System.Debug` namespace should never have a class named `Debug` within it. (Naturally, this is scoped to the namespace itself; it is perfectly acceptable to have a class called `Debug` in the `System.IO` namespace.)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 23. C# Development Tools

The .NET Framework SDK contains many useful programming tools. Here is an alphabetical list of those we have found most useful or necessary for developing C# applications. Unless otherwise noted, the tools in this list can be found either in the *bin* directory of your .NET Framework SDK installation or in the *%SystemRoot%\Microsoft.NET\Framework\VERSION* directory (replace *VERSION* with the framework version). Once the .NET Framework is installed, you can access these tools from any directory. To use any of these tools, invoke a Command Prompt window and enter the name of the desired tool.

This chapter uses the following conventions:

Italic

Used as a placeholder to indicate an item that should be replaced with an actual value.

[item]

The brackets indicate an optional item. In some cases, *[item]* is used to indicate that part of a word is optional. For example, */v[erbose]* indicates that the options */v* and */verbose* are equivalent.

(item1 | item2)

The pipe (*|*) symbol indicates alternation, and the parentheses group the choices together; you must choose one of the specified options.

[item1 | item2]

The pipe (*|*) symbol indicates alternation, and the brackets indicate that the choice is optional; you *may* choose one of the specified options. This is often used with the *+* and *-* symbols. For example, */verbose[+|-]* indicates that you may choose */verbose*, */verbose+*, or */verbose-*. The first two (*/verbose* and */verbose+*) are equivalent.

item1, item2

Comma-separated items indicate equivalent items. For example, the *-C* and *-console* options of the *ADepends.exe* tool are equivalent.

*ADepends.exe**Assembly Dependency Checker*

Synopsis

```
adepends [options] | [file] ...
```

Description

Displays all assemblies that a given assembly is dependent on to load. This is a useful C# program found among the samples in the *Tool Developers Guide* directory beneath the .NET Framework or Visual Studio .NET directory tree. You need to install these samples before you can use them, because they are not installed by default.

Options

- -appbase *path*, -A *path*

Specify a directory path to use for the application base path (see the `BaseDirectory` property of the `System.AppDomain` type).

- -config *configfile*, -O *configfile*

Generate an application configuration file. Requires the `-console` option.

- -console, -C

Send output to the console (standard output).

- -gui, -G

Display output in a window (default).

- -help

Displays usage information and exits.

- -relative *path*, -R *path*

Specify a directory path to use for the relative search path (see the `RelativeSearchPath` property of the `System.AppDomain` type).

- -

Suspends interpretation of command-line arguments as options. Use this if *file* has the same name as an option.

See Also

[ILDasm.exe](#), [WinCV.exe](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

*Al.exe**Assembly Linker*

Synopsis

```
al /out:manifestfile [options] source
```

Description

Creates an assembly manifest from the modules and resources files you name. You can also include Win32 resources files. See [GacUtil.exe](#) for an example of creating an assembly.

Example

```
al /out:c.dll a.netmodule b.netmodule
```

Source

You may specify one or more of these sources:

file

The name of a .NET module, which is produced by using the `/t:module` argument with the C# compiler. These modules typically have the extension `.netmodule`. The resulting *manifestfile* contains a reference to the `.netmodule` file.

file,target

The name of a .NET module, along with a target filename (a .NET assembly, typically a DLL). The target is created and the .NET module is copied into it. The resulting *manifestfile* contains a reference to the target rather than the .NET module.

```
/embed[resource] :file[,name[,Private]]
```

Embeds (copy) a resource file into the file that contains the manifest. Use *name* to associate an internal identifier with the resource. Resources are public by default; use `Private` to hide the resource from other assemblies.

```
/link[resource] :file[,name[,target[,Private]]]
```

Makes a resource file part of the assembly described by the manifest. This links the resource file to the manifest but does not make a copy (see `/embed`). Use *name* to associate an internal identifier with the resource. Use *target* to specify a .NET assembly to copy the resource into (as with *file,target*). Resources are public by default; use `Private` to hide the resource from other assemblies.

Options

`/?`, `/help`

Displays usage information and exits.

`@file`

Specifies a response file containing arguments to *al*.

`/algid:id`

The algorithm for hashing files. Specify the hexadecimal ID of the algorithm (use *WinCV.exe* to inspect the `AssemblyHashAlgorithm` enumeration in the `System.Configuration.Assemblies` namespace). Valid algorithm IDs for the first release of .NET include `0x0000` (None), `0x8003` (MD5), or `0x8004` (SHA1, the default).

`/base[address]:addr`

Specifies the base address at which to load DLLs.

`/bugreport:file`

Generates a text file that contains a bug report. Use this to report a bug in *al.exe*.

`/comp[any]:text`

Specifies the text of the assembly's Company field. This has the same effect as the `System.Reflection.AssemblyCompanyAttribute` custom attribute. This is also used as the Win32 Company resource (unless you specify `/win32res`).

`/config[uration]:text`

Specifies the text of the assembly's Configuration field. This has the same effect as the `System.Reflection.AssemblyConfigurationAttribute` custom attribute.

`/copy[right]:text`

Specifies the text of the assembly's Copyright field. This has the same effect as the `System.Reflection.AssemblyCopyrightAttribute` custom attribute. This is also used as the Win32 Copyright resource (unless you specify `/win32res`).

`/c[ulture]:text`

Specifies the assembly's culture string. This has the same effect as the `System.Reflection.AssemblyCultureAttribute` custom attribute.

`/delay[sign][+|-]`

Use `/delaysign+` or `/delaysign` to partially sign the assembly, and `/delaysign-` (the default) to fully sign it. This option requires the `/keyfile` or `/keyname` option. See the `System.Reflection.AssemblyDelaySignAttribute` custom attribute for more details.

`/descr[iption]:text`

Specifies the assembly's Description field. This has the same effect as the `System.Reflection.AssemblyDescriptionAttribute` custom attribute. This is also used as the Win32 Comments resource (unless you specify `/win32res`).

`/e[vidence]:file`

The name of the security evidence file to embed.

`/fileversion:version`

Specifies the assembly's File Version field in *major.minor.build.revision* format (such as 6.0.2600.0). This has the same effect as the

`System.Reflection.AssemblyFileVersionAttribute` custom attribute. This is also used as the Win32 File Version resource (unless you specify `/win32res`). This version corresponds to the Win32 File Version, and is *not* used to determine compatibility for side-by-side execution.

`/flags :flags`

Specify flags for side-by-side operation. Possible values are `0x0000` (side-by-side compatible), `0x0010` (side-by-side operation is prohibited within the same application domain), `0x0020` (side-by-side operation prohibited within same process), or `0x0030` (side-by-side operation prohibited within the same machine boundary). This has the same effect as the `System.Reflection.AssemblyFlagsAttribute` custom attribute.

`/fullpaths`

Use fully qualified filenames in error messages.

`/keyfile[:file]`

Specifies the name of the file that contains the key or key-pair with which to sign the assembly. This has the same effect as the `System.Reflection.AssemblyKeyFileAttribute` custom attribute. You can generate a key file with the `Sn` utility.

`/keyname[:name]`

Specifies a key container that contains the key-pair with which to sign the assembly. This has the same effect as the `System.Reflection.AssemblyKeyNameAttribute` custom attribute. You can add keys to a container using `sn -i`.

`/main :method`

Specifies the fully qualified method name (`type.method` or `namespace.type.method`) to use as the entry point. Must be used in conjunction with `/target:exe`.

`/nologo`

Suppresses display of the banner and copyright messages.

`/out :file`

Specifies the output filename.

`/product[:text]`

Specifies the assembly's Product field. This has the same effect as the `System.Reflection.AssemblyProductAttribute` custom attribute. This is also used as the Win32 Product resource (unless you specify `/win32res`).

`/productversion[:text]`

Specifies the assembly's Product Version field. This has the same effect as the `System.Reflection.AssemblyInformationalVersionAttribute` custom attribute. This is also used as the Win32 Product Version resource (unless you specify `/win32res`).

`/t[:target] :format`

Specifies the format of the file identified by `/out:file`. The valid formats are `lib[rary]` (DLL library), `exe` (console application), or `win[exe]` (Windows application).

`/template :file`

Specifies another assembly from which to import all metadata (except culture). The assembly must have a strong name.

`/title :text`

Specifies the assembly's Title field. This has the same effect as the `System.Reflection.AssemblyTitleAttribute` custom attribute. This is also used as the Win32 Description resource (unless you specify `/win32res`).

`/trade[mark] :text`

Specifies the assembly's Trademark field. This has the same effect as the `System.Reflection.AssemblyTrademarkAttribute` custom attribute. This is also used as the Win32 Trademark resource (unless you specify `/win32res`).

`/v[ersion] :version`

Specifies the assembly version in *major.minor.build.revision* format. This has the same effect as the `System.Reflection.AssemblyVersionAttribute` custom attribute. This is also used as the Win32 Assembly Version resource (unless you specify `/win32res`). This version is used to determine side-by-side compatibility.

`/win32icon :file`

Specifies an icon (*.ico*) file to be used as the application's icon.

`/win32res :file`

Specifies a Win32 resource (*.res*) file to insert in the output file.

See Also

[*Csc.exe*](#), [*Sn.exe*](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

*Cordbg.exe**Command-line debugger*

Synopsis

```
cordbg [program [program-arguments]] [!command ...]
```

Description

This is a general source-level, command-line debug utility for MSIL programs. It's a very useful tool for C# source debugging (make sure you compiled your program with `/debug`). Source for *cordbg* is available in the *ITool Developers Guide* directory. You can start *cordbg* with the name of a program and the arguments to pass to that program. You can also supply one or more commands (prefixed with `!`) on the command line.

After you launch *cordbg*, you are greeted by the `(cordbg)` prompt, where you can type commands until you exit *cordbg* with the `quit` command.

Sample Sessions

Set a breakpoint, start the program, and step through a few lines of code:

```
c:\home>cordbg Tester.exe
Microsoft (R) Common Language Runtime Test Debugger Shell
Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.

(cordbg) run Tester.exe
Process 2024/0x7e8 created.
Warning: couldn't load symbols for
c:\windows\microsoft.net\framework\v1.0.3617\mscorlib.dll
[thread 0xee8] Thread created.

004:      for (int i = 0; i < 3; i++) {
(cordbg) show
001: using System;
002: class Tester {
003:     public static void Main( ) {
004:*      for (int i = 0; i < 3; i++) {
005:          object o = i;
006:          Console.Write(i + " ");
007:      }
008:      Console.Write("\n");
009:  }
(cordbg) b 6
```

```

Breakpoint #1 has bound to c:\home\Tester.exe.
#1      c:\home\Tester.cs:6  Main+0xb(1l) [active]
(cordbg) go
break at #1      c:\home\Tester.cs:6  Main+0xb(1l) [active]

006:      Console.Write(i + " ");
(cordbg) next
0
004:      for (int i = 0; i < 3; i++) {
(cordbg) step

005:      object o = i;
(cordbg) step
break at #1      c:\home\Tester.cs:6  Main+0xb(1l) [active]

```

Swap two string variables by changing the addresses they refer to:

```

017:      string a = "A";
(cordbg) step

018:      string b = "B";
(cordbg) step

019:      Console.WriteLine(a + ", " + b);
(cordbg) print a
a=(0x00c51abc) "A"
(cordbg) print b
b=(0x00c51ad0) "B"
(cordbg) set a 0x00c51ad0
a=(0x00c51ad0) "B"
(cordbg) set b 0x00c51abc
b=(0x00c51abc) "A"
(cordbg) next
B, A

```

Invoke a static and instance method using `funceval`:

```

014:      TestClass my_instance = new TestClass( );
(cordbg) next

015:      return;
(cordbg) funceval TestClass::MyStaticMethod
In MyStaticMethod( )
Function evaluation complete.
$result=0x0000002a
015:      return;
(cordbg) funceval TestClass::MyInstanceMethod my_instance
In MyInstanceMethod( )
Function evaluation complete.
$result=0x00000017
015:      return;
(cordbg) print $result

```

```
$result=0x00000017
```

Commands

```
? [ command ] , h[elp] [ command ]
```

Displays general help. If *command* is specified, displays help for that command.

```
> [ file ]
```

Writes all subsequent commands to a file. If *file* is not specified, this command stops writing commands to that file.

```
< file
```

Read and execute commands from a file.

```
ap[pdomainenum] [ option ]
```

Lists all the *AppDomains* inside the current process. Valid choices for *option* are *attach* (list all *AppDomains* and prompt for which appdomain to attach to), *detach* (list all *AppDomains* and prompt for which *AppDomain* to detach from), *0* (list the *AppDomains*), or *1* (*AppDomains* and assemblies; the default list).

```
as[sociatesource] (s | b breakpoint) filename
```

Associate the specified source file with the current stackframe (*s*) or an existing breakpoint (*b breakpoint*).

```
a[ttach] pid
```

Attach to a managed process (use *pro[cessenum]* to get a list of *pids*).

```
b[reak] ([ file:] line | [ class::] function[:offset])
```

Set a breakpoint at a given line number or function. With no arguments, lists all breakpoints.

```
ca[tch] [ event ]
```

Specify an event type to suspend execution when that event occurs. Valid types are *e[xceptions]* [*exception-type*] (an exception is thrown), *u[nhandled]* (an exception is thrown that is not handled by the program), *c[lass]* (a class is loaded), *m[odule]* (a module is loaded), or *t[hread]* (a thread is started). With no arguments, *catch* displays a list of event types with the current catch/ignore settings.

```
cont [ count ] , g[o]
```

Continues until the next breakpoint or until the program terminates, whichever comes first. Use *count* to continue over breakpoints multiple times.

```
del[ete] [ breakpoint ... ] , rem[ove] [ breakpoint ... ]
```

Delete the specified breakpoint(s). Use the breakpoint IDs as listed by the *break* command. If you don't specify a breakpoint, all breakpoints are deleted.

```
de[tach]
```

Detach from the current process and let it run to completion.

```
dis[assemble] [0x address] [{+|-} delta] [ lines ]
```

Displays native code disassembly for the current instruction pointer (IP) or address. By default, five lines of surrounding context before and after the IP are shown (use the *lines* argument to

change this).

`d[own] [count]`

Move the stack pointer down one stack frame or the specified number of stack frames. This does not affect the instruction pointer, but it does affect the output of subsequent `show` commands.

`du[mp] address [count]`

Dump memory at the specified address. The optional `count` argument specifies how many bytes to dump.

`f[un]ceval [class::] function [args]`

Execute a function. For instance, with methods, you must supply an instance of the class as the first argument (see Sample Sessions for an example). The return value is stored in the variable `$result`, which you can inspect with the `p[rint]` command.

`ig[nore]`

Specify an event type to ignore when that event occurs (use `catch` to suspend execution whenever that event occurs). See `catch` for a list and description of valid events. With no arguments, `ignore` displays a list of event types with the current catch/ignore settings.

`k[ill]`

Stops the current process, but does not exit the debugger.

`l[ist] option`

Lists the loaded modules (`option=mod`), classes (`option=cl`), or global functions (`option=fu`).

`m[ode] option (0 | 1)`

Sets debugger modes. Type `help mode` for a list of valid modes and their descriptions. With no arguments, `mode` displays current mode settings.

`newo[bj] type`

Creates a new object, stored in the variable `$result`.

`newobjnc type`

Creates a new object without calling the constructor. The new object is stored in the variable `$result`.

`news[tr] "string"`

Creates a new string, stored in the variable `$result`.

`ns[ingle] [count]`

Step to the next native instruction, stepping over function calls. If `count` is specified, steps the next `count` instructions.

`o[ut] [count]`

Steps out of the current function. If `count` is specified, steps out of `count` functions.

`pa[th] [path]`

Sets or (with no argument) displays the path used to search for source code files.

`p[rint] [variable]`

Prints a list of all local variables and their values, or if *variable* is specified, prints the value of that variable.

`pro[cessenum]`

Displays a list of each managed process along with its process id (*pid*).

`q[uit], ex[it]`

Terminates the current process and exits the debugger.

`ref[reshsource] file`

Reloads the source code for the specified file.

`reg[isters]`

Displays the CPU registers and their contents for the current thread.

`re[sume] [~] tid`

With *tid*, resumes the specified thread ID. With *~*, resumes all threads except the specified thread ID. See the `t[hreads]` command.

`r[un] [program [program-arguments]]`

With no arguments, kills and restarts the current process. With arguments, starts a new program with the specified program arguments.

`set variable value`

Set a variable to a given value. You can set the address of a reference type to a valid address for that type (see Sample Sessions). The C# or JIT compiler may perform optimizations that make certain variables unavailable, in which case you see the message "Variable *variable* is in scope but unavailable."

`setip line`

Set the instruction pointer to the specified line number.

`sh[ow] [number-of-lines]`

Displays source code. The current line is shown with an asterisk (*).

`si [count], s[tep] [count], i[n] [count]`

Steps to the next line of code, stepping into functions. If *count* is specified, steps the next *count* lines of code.

`so [count], n[ext]`

Steps to the next line of source code, stepping over functions. If *count* is specified, steps the next *count* lines of code.

`ss[ingle] [count]`

Step to the next native instruction, stepping into function calls. If *count* is specified, steps the next *count* instructions.

`stop`

See `break`.

`su[spend] [~] tid`

With *tid*, suspends the specified thread ID. With *~*, suspends all threads except the specified thread ID. See the `t[hreads]` command.

`t[hreads] [tid]`

With no arguments, lists all threads and their IDs. With the *tid* argument, sets the current thread.

`uc[lear] tid`

Clears the current unmanaged exception for the thread ID specified by *tid*.

`u[p] [count]`

Move the stack pointer up one stack frame or the specified number of stack frames. This does not affect the instruction pointer, but it does affect the output of subsequent `show` commands.

`ut[hreads] [tid]`

With no arguments, lists all unmanaged threads and their IDs. With the *tid* argument, sets the current unmanaged thread.

`uw[here]`

Displays an unmanaged stack trace.

`w[here] [count]`

Displays a stack trace for the currently executing thread. This displays up to 10 (or *count*) stack frames.

`wr[itememory] addresscountbyte1 [byte2 ...]`

Writes *count* bytes to the specified memory address.

`wt`

Steps through the program, one native instruction at a time, and prints a call tree containing a count of instructions in each function.

`x pattern`

Displays symbols matching *pattern*. Use `*` as a wild card character (trailing characters are ignored). The symbol format is `module!symbol`.

IL Debugging

If you'd like to step through the MSIL instead of the C# source code, you can use *ILDasm* to disassemble your program and then use *ILasm* to assemble it into an executable (don't forget the `/debug` switch). Then, run that executable under *corDBG*.

```
C:\home>csc Tester.cs
```

```
Microsoft (R) Visual C# .NET Compiler version 7.10.3052.4
```

```
for Microsoft (R) .NET Framework version 1.1.4322
```

```
Copyright (C) Microsoft Corporation 2001-2002. All rights reserved.
```

```
C:\home>ILDasm /text Tester.exe > TesterIL.il
```

```
C:\home>ILasm /debug TesterIL.il
```

```
Microsoft (R) .NET Framework IL Assembler. Version 1.1.4322.573
```

```
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

```
Assembling 'TesterIL.il' , no listing file, to EXE --> 'TesterIL.EXE'  
Source file is ANSI
```

```
Assembled method Tester::Main  
Assembled method Tester::.ctor  
Creating PE file
```

```
Emitting members:  
Global  
Class 1 Methods: 2;  
Writing PE file  
Operation completed successfully
```

```
C:\home>cordbg TesterIL.exe  
Microsoft (R) Common Language Runtime Test Debugger Shell  
Version 1.1.4322.573  
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

```
(cordbg) run TesterIL.exe  
Process 1004/0x3ec created.  
Warning: couldn't load symbols for  
c:\windows\microsoft.net\framework\v1.0.3617\mscorlib.dll  
[thread 0x61c] Thread created.
```

```
057:      IL_0000:  ldc.i4.0  
(cordbg) show  
052:      .entrypoint  
053:      // Code size          51 (0x33)  
054:      .maxstack  2  
055:      .locals init (int32 V_0,  
056:                  object V_1)  
057:*      IL_0000:  ldc.i4.0  
058:      IL_0001:  stloc.0  
059:      IL_0002:  br.s          IL_0024  
060:  
061:      IL_0004:  ldloc.0  
062:      IL_0005:  box          [mscorlib]System.Int32  
(cordbg)
```

See Also

[*Csc.exe*](#), [*ILAsm.exe*](#), [*ILDasm.exe*](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

*Csc.exe**C# compiler*

Synopsis

```
csc [options] files
```

Description

Compiles C# sources and incorporates resource files and separately compiled modules. Also allows you to specify conditional compilation options, XML documentation, and path information.

Examples

```
csc foo.cs /r:bar.dll /win32res:foo.res
csc foo.cs /debug /define:TEMP
```

Options

```
/? , /help
```

Displays usage information and exits.

```
@file
```

Specifies a response file containing arguments to *csc*.

```
/addmodule:file1[; file2 ...]
```

Imports metadata from one or more named modules (files with the extension *.netmodule*). To create a module, use */target:module*.

```
/baseaddress:addr
```

Specifies the base address at which to load DLLs.

```
/bugreport:file
```

Generates a text file that contains a bug report. Use this to report a bug in *csc.exe*.

```
/checked[+|-]
```

If you specify */checked+*, the runtime throws an exception when an integer operation results in a value outside the range of the associated data type. This only affects code that has not been wrapped in a checked or unchecked block of code. If you specify */checked-*, an exception is not thrown.

```
/codepage:id
```

Specifies the code page to use for all source files.

```
/d[efine]:symbol1[; symbol2 ...]
```


Specify one or more symbols to define. This has the same effect as the `#define` preprocessor directive.

```
/debug[+|-]
```

Enables or disables debugging information. You may specify `/debug` instead of `/debug+`. The default is `/debug-`.

```
/debug:(full|pdbonly)
```

Specifies the debug modes that are supported by the generated assembly. The `full` option is the default and allows you to perform source code debugging when attaching a debugger to the program before or after it is started. The `pdbonly` option only permits source code debugging if you start the program under control of the debugger. If you attach the debugger to the program after it is started, it displays only native assembly in the debugger.

```
/doc:file
```

Specify the XML documentation file to generate.

```
/filealign:size
```

Specifies the size, in bytes, of sections in the output file. Valid sizes are 512, 1024, 2048, 4096, 8192, and 16384.

```
/fullpaths
```

Use fully qualified filenames in error messages.

```
/incr[emental][+|-]
```

Enables or disables incremental compilation. By default, incremental compilation is off.

```
/lib:dir1[; dir2 ...]
```

Specifies directories to search for assemblies imported with the `/reference` option.

```
/linkres[ource]:file[,id]
```

Specifies a .NET resource (and optional identifier) to link to the generated assembly. Not valid with `/target:module`.

```
/m[ain]:type
```

Specifies the name of the type that contains the entry point. This is only valid for executables. The entry point method must be named `Main`, and must be declared static.

```
/noconfig
```

Do not use the global or local configuration file (`csc.rsp`). You can find the global `csc.rsp` file in `%SystemRoot%\Microsoft.NET\Framework\VERSION`, in which `VERSION` is a version of the .NET Framework. This file contains default arguments for the C# compiler, including the list of assemblies that are imported by default. If you create a file named `csc.rsp` in the same directory as your source code, it is processed after the global configuration file.

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/nostdlib[+|-]
```

With `/nostdlib+` or `/nostdlib`, the C# compiler will not import `mscorlib.dll`, which defines the fundamental types used in .NET and most of the System namespace.

```
/nowarn:number1[; number2 ...]
```

Specifies a list of warning numbers to ignore. Do not include the alphabetic part of the warning. For example, to suppress warning *CS0169*, use */nowarn:169*.

/o[ptimize][+|-]

Enables or disables compiler optimizations. By default, optimizations are enabled.

/out:file

Specifies the output filename.

/recurse:wildcard

Recursively searches directories for source code files matching *wildcard* (which may include directory names).

/r[eference]:file1[:file2...]

Imports metadata from one or more named assemblies. Generally used with DLLs, but you may also specify executables.

/res[source]:file[,id]

Specifies a .NET resource (and optional identifier) to embed in the generated assembly.

/t[arget]:format

Specifies the format of the output file. The valid formats are *library* (DLL library), *module* (a library without an assembly manifest), *exe* (console application), or *winexe* (Windows application).

/unsafe[+|-]

Enables or disables (the default) unsafe code. Unsafe code is enclosed in a block marked by the *unsafe* keyword.

/utf8output

Displays compiler console output using UTF-8 encoding.

/w[arn]:level

Sets the compiler warning level from 0 (no warnings) to 4 (the default, all warnings).

/warnaserror[+|-]

Enables or disables (the default) treating warnings as errors (warnings halt compilation).

/win32icon:file

Specifies an icon (*.ico*) file to use as the application's icon.

/win32res:file

Specifies a Win32 resource (*.res*) file to insert in the output file.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DbgCLR.exe

Microsoft CLR Debugger

Synopsis

DbgCLR [options]

Description

Windows-based, source-level debugger. Available in the *IGuiDebug* directory of the .NET Framework SDK installation.

Options

/mdi

Uses multiple document interface.

/sdi

Uses single document interface.

/fn name

Specifies font name.

/fn size

Specifies font size.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

*GacUtil.exe**Global Assembly Cache Utility*

Synopsis

`gacutil command [options]`

Description

Allows you to install, uninstall, and list the contents of the Global Assembly Cache (GAC).

Examples

Create a module, generate a key-pair, build a signed manifest assembly containing the module, and install the assembly in the GAC:

```
C:\home>csc /t:module Example.cs
Microsoft (R) Visual C# .NET Compiler version 7.10.3052.4
for Microsoft (R) .NET Framework version 1.1.4322
Copyright (C) Microsoft Corporation 2001-2002. All rights reserved.
```

```
C:\home>sn -k example.key
```

```
Microsoft (R) .NET Framework Strong Name Utility Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

Key pair written to example.key

```
C:\home>al /keyfile:example.key /out:Example.dll Example.netmodule
Microsoft (R) Assembly Linker version 7.10.3077
for Microsoft (R) .NET Framework version 1.1.4322
Copyright (C) Microsoft Corporation 2001-2002. All rights reserved.
```

```
C:\home>gacutil /i Example.dll
```

```
Microsoft (R) .NET Global Assembly Cache Utility. Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

Assembly successfully added to the cache

Delete all assemblies named Example from the GAC:

```
C:\home>gacutil /u Example
```

```
Microsoft (R) .NET Global Assembly Cache Utility. Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

```
Assembly: Example, Version=2.0.0.0, Culture=neutral,  
PublicKeyToken=9a587aa1499c251f, Custom=null  
Uninstalled: Example, Version=2.0.0.0, Culture=neutral,  
PublicKeyToken=9a587aa1499c251f, Custom=null
```

```
Number of items uninstalled = 1  
Number of failures = 0
```

Find a list of all assemblies named Example and delete a specific version:

```
C:\home>gacutil /l Example
```

```
Microsoft (R) .NET Global Assembly Cache Utility. Version 1.1.4322.573  
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

The Global Assembly Cache contains the following assemblies:

```
Example, Version=1.0.0.0, Culture=neutral,  
PublicKeyToken=093bfe6ba64f6b38, Custom=null  
Example, Version=1.2.0.0, Culture=neutral,  
PublicKeyToken=4644a63cb9786bcc, Custom=null
```

The cache of ngen files contains the following entries:

```
Number of items = 2
```

```
C:\home>gacutil /u Example,Version=1.2.0.0
```

```
Microsoft (R) .NET Global Assembly Cache Utility. Version 1.1.4322.573  
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

```
Assembly: Example, Version=1.2.0.0, Culture=neutral,  
PublicKeyToken=4644a63cb9786bcc, Custom=null  
Uninstalled: Example, Version=1.2.0.0, Culture=neutral,  
PublicKeyToken=4644a63cb9786bcc, Custom=null
```

```
Number of items uninstalled = 1  
Number of failures = 0
```

Commands

```
/?
```

Displays usage information and exits.

```
/cdl
```

Removes all assemblies that were downloaded from the network.

```
/i [/f] [/r] assemblypath
```

Installs the specified assembly into the GAC. The assembly must have a strong name (see [Sn.exe](#)).

```
/il [/f /r] assemblylistfile
```

Installs one or more assemblies into the GAC. *assemblylistfile* is a file that contains a cr/lf-delimited list of assembly file names.

`/l [/r] [name]`

Lists all assemblies in the GAC. If you supply a name, it lists all versions of the named assembly.

`/ldl`

Lists all assemblies that were downloaded from the network.

`/nologo`

Suppresses display of the banner and copyright messages.

`/silent`

Suppresses display of all console output.

`/u [/f] [/r] assembly`

Remove an assembly from the GAC.

`/ul [/r] assemblylistfile`

Removes one or more assemblies from the GAC. *assemblylistfile* is a file that contains a cr/lf-delimited list of assembly file names.

`/ungen assembly`

Removes an assembly from the cache of *ngen*d files (see *Ngen.exe*).

Options

`/f`

Use with the `/i` or `/il` commands to force installation, even if the assembly already exists. With `/u`, `/f` forces removal by uninstalling all traced references (this fails if the assembly is referenced by the Windows Installer).

`/r scheme id description`

Specifies a traced reference (use this with `/i`, `/il`, `/u`, or `/ul`). Valid options for *scheme* are **FILEPATH** (*id* must be a path to a file), **UNINSTALL_KEY** (*id* must be a registry key), or **OPAQUE** (*id* must be an identifier). *id* is the referencing application's identifier (for a scheme of **FILEPATH**, it would be the application's full path), and *description* is a friendly name for the referencing application.

See Also

[Sn.exe](#), [Al.exe](#), [Csc.exe](#)

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

*/Lasm.exe**MSIL Assembler*

Synopsis

```
ilasm [options] file1 [[options] file2 ...]
```

Description

Creates MSIL modules and assemblies directly from an MSIL textual representation. See [// Debugging](#) elsewhere in this chapter for an example that uses */Lasm.exe*.

Options

```
/?
```

Displays usage information and exits.

```
/align[ment]= int
```

Specifies a value for File Alignment in the NT Optional Header. Overrides the MSIL `.alignment` directive.

```
/base[e]= int
```

Specifies a value for `ImageBase` in the NT Optional Header. Overrides the MSIL `.imagebase` directive.

```
/clock
```

Reports on how long the assembly takes.

```
/debug
```

Includes debugging information in the output file.

```
/dll
```

Assembles source file to a DLL.

```
/exe
```

Assembles source file to an executable file (the default).

```
/flags= int
```

Sets `ImageFlags` in the CLR header. Overrides the MSIL `.corflags` directive.

```
/key:file
```

Specifies the name of the file that contains the key or key-pair with which to sign the assembly. You can generate a key file with the *sn* utility.

```
/key:@ text
```

Specifies a key container that contains the key-pair with which to sign the assembly. You can add keys to a container using `sn -i`.

`/lis[ting]`

Emits a listing to the console as the file is assembled.

`/no[logo]`

Suppresses display of the banner and copyright messages.

`/out[put] :file`

Specifies the output filename.

`/qui[et]`

Suppresses display of assembly progress to console.

`/res[ource] :file`

Specifies a Win32 resource (`.res`) file to include in the generated assembly.

`/sub[system]= int`

Specifies a value for the subsystem in the NT Optional Header. Overrides the MSIL `.subsystem` directive.

See Also

[*Csc.exe*](#), [*ILDasm.exe*](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

*ILDasm.exe**MSIL Disassembler*

Synopsis

```
ildasm [options] file [options]
```

Description

Disassembles modules and assemblies. The default is to display a GUI with a tree-style representation, but you can also specify an output file. See [IL Debugging](#) elsewhere in this chapter for an extended example that uses *ILDasm.exe*.

Examples

```
ildasm b.dll
ildasm b.dll /out=b.asm
```

Options

```
/?
```

Displays usage information and exits.

```
/all
```

Combines `/header`, `/bytes`, and `/tokens`. Requires the `/text` or `/out` option.

```
/byt[es]
```

Displays actual bytes (in hexadecimal) as comments amongst the MSIL.

```
/hea[der]
```

Includes file header information. Requires the `/text` or `/out` option.

```
/ite[m]=class[:method(sig)]
```

Disassembles only the specified class or member. Requires `/text` or `/out` option.

```
/lin[enum]
```

Displays references to line numbers from the original source code. To use this option, *file* must be compiled with `/debug`.

```
/nob[ar]
```

By default, *ILDasm* displays a progress bar while disassembling, even with `/text`. Use `/nobar` to suppress that progress bar.

```
/out :file
```

Displays output to a file instead of creating GUI.

`/noi[l]`

Suppresses display of MSIL. Requires the `/text` or `/out` option.

`/pub[only]`

Disassembles only public types (equivalent to `/vis=pub`).

`/quo[teallnames]`

Encloses all names in single quotes.

`/raw[eh]`

Displays exception handling clauses in raw form.

`/sou[rce]`

Displays original source code lines as comments.

`/tex[t]`

Displays output to console instead of creating GUI.

`/tok[ens]`

Displays class and member metadata tokens.

`/uni[code]`

Displays output in UNICODE. Requires the `/text` or `/out` option.

`/utf[8]`

Displays output in UTF-8. Requires the `/text` or `/out` option.

`/vis[ibility]=vis[+vis...]`

Restricts disassembly to types and members matching specified visibility. Available visibilities are **PUB** (public), **PRI** (private), **FAM** (family), **ASM** (assembly), **FAA** (family and assembly), **FOA** (family or assembly), and **PSC** (private scope).

See Also

[*Csc.exe*](#), [*ILasm.exe*](#)

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Synopsis

```
InstallUtil [/u[ninstall]] [options] assembly1 [[options] assembly2] ...
```

Description

Executes installers and uninstallers contained within the assembly. A log file can be written, and state information can be persisted. For complete details, see the *Installer Tool (Installutil.exe)* topic in the .NET Framework SDK Documentation.

Options

```
/? [ assemblypath] , /h[elp] [ assemblypath]
```

Prints a usage message and exits. If *assemblypath* is supplied, it displays help for any additional options supported by installers in the assembly.

```
/logFile= file
```

Logs installation progress to a file (defaults to *assemblyname.InstallLog*).

```
/logToConsole=(true|false)
```

If **true**, logs output to the console. The default is **false**.

```
/showCallStack
```

Prints the call stack to the log file if an exception is thrown during installation.

```
/u[ninstall]
```

Uninstalls assemblies. This option applies to all assemblies specified on the command line.

*Ngen.exe**Native Image Generator*

Synopsis

```
ngen [options] [assembly-path-or-display-name ...]
```

Description

Compiles an assembly to native code and installs a native image in the local computer's native image cache. That native image is used each time you access the original assembly, even though the original assembly contains MSIL. If the runtime can't locate the native image, it falls back on JIT compilation.

Examples

```
ngen foo.exe
ngen foo.dll
```

Options

```
/debug
```

Generates a native image that can be used with a debugger.

```
/debugopt
```

Generates a native image that can be used with a debugger in optimized debugging mode.

```
/delete
```

Deletes native images matching *assembly-path-or-display-name*. Use * for *assembly-path-or-display-name* to delete *a//native* images.

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/prof
```

Generates a native image that can be used with a profiler.

```
/show
```

Lists native images matching *assembly-path-or-display-name*. If *assembly-path-or-display-name* is not supplied, lists all native images.

```
/showversion
```

Displays the version of the .NET runtime that would be used to generate the native image. Does not actually generate the image. (Added in .NET 1.1.)

`/silent`

Suppresses display of success messages.

[\[Team LiB \]](#)

*Nmake.exe**Program Maintenance Utility*

Synopsis

```
nmake [options] [macro=value ...] [targets]
```

Description

Common utility that scripts building of multiple components and source files and tracks rebuild dependency information. If a target is not specified, *Nmake* looks for a target called *all*.

Options

/@ file

Specifies a response file containing arguments to *nmake*.

/?, /help

Displays usage information and exits.

/a

Build all targets, even if they are up-to-date.

/b

Builds if timestamps are equal.

/c

Suppresses output messages.

/d

Displays build information.

/e

Overrides environment variable macros.

/f makefile

Specifies a makefile. The default is *Makefile* in the current directory.

/i

Ignores command exit codes. Continues building even if an error occurs in an external program, such as a compiler.

/k

If an error occurs while building a target, */k* causes *nmake* to continue building other targets.

/n

Displays commands, but does not actually execute them.

`/nologo`

Suppresses display of the banner and copyright messages.

`/p`

Displays *nmake* settings and information about the current makefile.

`/q`

Checks time stamps, but does not perform the build.

`/r`

Ignores predefined rules. (Compare the output of `nmake /pq` to the output of `nmake /p`).

`/s`

Suppresses display of commands as they are executed.

`/t`

Changes timestamps, but does not perform the build

`/u`

Dumps inline files.

`/y`

Disables batch mode.

`/x file`

Sends all standard error messages to *file*.

See Also

Managing Projects with make, by Andrew Oram and Steve Talbott (O'Reilly & Associates).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

*PEVerify.exe**Portable Executable Verifier*

Synopsis

`PEVerify file [options]`

Description

Verifies that your compiler has generated type-safe MSIL. C# always generates type-safe MSIL. Useful for ILASM-generated programs.

Options

`/?`

Displays usage information and exits.

`/break= count`

Aborts execution after *count* errors. The default is one error.

`/clock`

Reports on how long verification took.

`/hresult`

Displays error codes in hexadecimal.

`/ignore= code1[,code2 ...]`

Ignores specified error codes. You must specify the error codes in hexadecimal format (such as 0x0000001F).

`/ignore=@ file`

Specifies a file containing error codes to ignore. The error codes must be in hexadecimal format.

`/il`

Verifies only the PE structure and MSIL.

`/md`

Verifies only the PE structure and metadata.

`/quiet`

Suppresses display of errors.

`/unique`

Ignores duplicate error codes.

See Also

[*//Lasm.exe*](#)

[\[Team LiB \]](#)

*RegAsm.exe**Assembly Registration Utility*

Synopsis

```
RegAsm assembly [options]
```

Description

Registers an assembly in the system registry. This allows COM clients to call managed methods. You can also use it to generate the registry file for future registration. If the assembly is only accessed from one COM client, and that client lives in the same directory as the assembly, you do not need to add the assembly to the GAC. If you want the assembly to be accessible to all COM clients, you should add it to the GAC (see [GacUtil.exe](#)).

Example

```
regasm /regfile:c.reg c.dll
```

Options

```
/? , /help
```

Displays usage information and exits.

```
/codebase
```

Specifies a file path for the assembly. Do not use this if the assembly is in the GAC, or if you later plan to add it to the GAC. The assembly must be signed with a strong name (see [Sn.exe](#)).

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/regfile[ :file]
```

Generates a *.reg* file that you can use to add the assembly to the registry. This option does not change the registry; you need to double-click on the generated *.reg* file to add the assembly to the registry. You cannot use this option with */unregister* or */tlb*.

```
/registered
```

Refers only to type libraries that are already registered.

```
/silent
```

Suppresses display of success messages.

```
/tlb[ :file]
```

Generates a type library (*.tlb*).

`/unregister`

Unregisters the assembly.

`/verbose`

Displays verbose output.

See Also

[*GacUtil.exe*](#), [*Sn.exe*](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Synopsis

```
regsvcs [options] assembly
```

Description

Registers an assembly to COM+, and installs its typelib into a new or existing application. Can also generate a typelib. The assembly must be signed with a strong name (see [Sn.exe](#)).

Example

```
regsvcs foo.dll /appname:comapp /tlb:newfoo.tlb
```

Options

```
/? , /help
```

Displays usage information and exits.

```
/appdir :path
```

Specifies application root directory. (Added in .NET 1.1.)

```
/appname :name
```

Specifies the name of the COM+ application.

```
/c
```

Creates the application.

```
/comonly
```

Configures only components, ignoring methods and interfaces.

```
/exapp
```

Expects that the application already exists. *RegSvcs.exe* fails if the application does not exist.

```
/extlb
```

Uses an existing type library. Requires the `/tlb` option.

```
/fc
```

Finds and uses an existing application or creates a new one if it does not exist. This is the default mode.

```
/nologo
```

Suppresses display of the banner and copyright messages.

`/noreconfig`

Does not reconfigure an existing application.

`/parname :name`

Specifies the name or ID of the COM+ application to find or create.

`/quiet`

Suppresses display of success, banner, and copyright messages.

`/reconfig`

Reconfigures an existing application. This is the default behavior.

`/tlb :file`

Specifies the type library.

`/u`

Uninstall the assembly from the application.

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

*Sn.exe**Strong Name Utility*

Synopsis

sn options

Description

Verifies assemblies and their key information. Also generates key files and manages Cryptographic Service Provider (CSP) containers, which provide a layer of abstraction over key storage and management. CSPs are enumerated in the *HKLM\SOFTWARE\Microsoft\Cryptography\Defaults\Provider* registry key. See [GacUtil.exe](#) for an example of signing an assembly.

Examples

Create a new key-pair:

```
C:\home>sn -k mykey.snk
```

```
Microsoft (R) .NET Framework Strong Name Utility  Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

Key pair written to mykey.snk

Add that key-pair to a container:

```
C:\home>sn -i mykey.snk MyContainer
```

```
Microsoft (R) .NET Framework Strong Name Utility  Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

Key pair installed into 'MyContainer'

Extract the public key from the key in the container:

```
C:\home>sn -pc MyContainer pubkey.out
```

```
Microsoft (R) .NET Framework Strong Name Utility  Version 1.1.4322.573
Copyright (C) Microsoft Corporation 1998-2002. All rights reserved.
```

Public key written to pubkey.out

Options

`-?, help`

Displays usage information and exits.

`-c [csp]`

Sets the default CSP for your machine. With no arguments, resets the CSP to the default.

`-d container`

Deletes the specified key container.

`-D assembly1assembly2`

Compares two assemblies and verifies that they differ only by signature.

`-e assemblyfile`

Extracts an assembly's public key into *file*.

`-i filecontainer`

Installs a key-pair from *file* in the container.

`-k file`

Generates a new key-pair and stores it in *file*.

`-m [y|n]`

With *y*, specifies that key containers are machine-specific. With *n*, specifies that they are user-specific. With no arguments, displays the current settings.

`-o keyfile [csvfile]`

Converts a public key to comma-separated value (CSV) format and stores it in the *csvfile*. If *csvfile* is not specified, stores the data in the clipboard.

`-p infileoutfile`

Extracts the public key from *infile* and stores it in *outfile*. Use the extracted public key for delay signing (see [A1.exe](#)).

`-pc containerfile`

Extracts the public key from the key-pair that is stored in the container. The public key is stored in *file*.

`-q`

Suppresses display of success messages.

`-R assembly file`

Re-signs a previously signed (or delay-signed) assembly.

`-Rc assemblycontainer`

Re-signs a previously signed (or delay-signed) assembly using the key-pair in the specified container.

`-t[p] file`

Displays a public key's token (`-t`) or the token and public key (`-tp`). The file must be generated with `-p`.

`-T[p] assembly`

Displays an assembly's public key token (**-T**) or the token and public key (**-Tp**).

-v[f] *assembly*

Verifies an assembly's strong name. Use **f** to force verification even if you have disabled it with **-Vr**.

-Vl

Lists the machine's current settings for strong name verification.

-Vr *assembly* [*userlist*]

Registers the assembly for verification skipping. You can optionally supply a list of users that this applies to.

-Vu *assembly*

Unregisters the assembly for verification skipping.

-Vx

Unregisters all verification skipping entries.

See Also

[*Al.exe*](#), [*GacUtil.exe*](#)

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

*SoapSuds.exe**SoapSuds Utility*

Synopsis

```
soapsuds (-url:args | -types:args | -is:args | -ia:args) [options]
```

Description

Creates XML schemas for services in an assembly and creates assemblies from a schema. You can also reference the schema via its URL. Use *SoapSuds* to create client applications that communicate with .NET remoting servers. Use *Wsdl.exe* to create clients that communicate with .NET Web Services.

Example

```
soapsuds
  -url:http://localhost/myapp/app.soap?wsdl
  -os:app.xml
```

Options and Arguments

```
-d[omain] :domain
```

Specifies a domain name, if one is required for authentication.

```
-GenerateCode, -gc
```

Generates code (equivalent to `-od:.`).

```
-httpProxyName :name, -hpn :name
```

Specifies an HTTP proxy name (use this when connecting through an HTTP proxy).

```
-httpProxyPort :port, -hpp :port
```

Specifies an HTTP proxy port (use this when connecting through an HTTP proxy).

```
-inputAssemblyFile :file, -ia :file
```

Specifies an input assembly file from which to import types. Do not include the `.exe` or `.dll` extension.

```
-inputDirectory :directory, -id :directory
```

Specifies the directory that contains `.dll` files.

```
-inputSchemaFile :file, -is :file
```

Specifies the input schema file.

```
-NoWrappedProxy, -nowp
```

Creates a proxy that is not wrapped (the default is a wrapped proxy).

`-outputAssemblyFile :file, -oa :file`

Writes output to an assembly file. *SoapSuds* also generates source code.

`-outputDirectory :directory, -od :directory`

Specifies the output directory.

`-outputSchemaFile :file, -os :file`

Writes output to an XML schema file.

`-p[assword] :password`

Specifies a password, if one is required for authentication.

`-proxyNamespace :namespace, -pn :namespace`

Specifies the namespace for generated proxy code. This should only be used for interop namespaces.

`-se[rviseEndpoint] :url`

Specifies the URL for the WSDL's service endpoint.

`-StrongNameFile :file, -sn :file`

Signs the generated assembly using the specified key file. See [Sn.exe](#).

`-types :type1,assembly[,endpoint][; type2,assembly[,endpoint] ...]`

Specifies one or more input types, with optional assembly name and service endpoint.

`-url[ToSchema] :url`

Specifies the location of the XML schema.

`-u[sername] :username`

Specifies a username, if one is required for authentication.

`-WrappedProxy, -wp`

Creates a proxy that is wrapped (this is the default).

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)*TlbExp.exe**Type Library Exporter*

Synopsis

```
tlbexp assembly [options]
```

Description

Exports a COM typelib derived from the public types within the supplied assembly. Differs from *RegAsm.exe* in that it doesn't perform any registration.

Example

```
tlbexp /out:c.tlb c.dll
```

Options

```
/? , /help
```

Displays usage information and exits.

```
/names :file
```

Supplies a filename that controls the capitalization of names in the type library. Each line in *file* should contain one name.

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/out :file
```

Specifies the filename of type library.

```
/silent
```

Suppresses display of success messages.

```
/verbose
```

Displays verbose output.

See Also

[TlbImp.exe](#), [RegAsm.exe](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

*Tlbimp.exe**Type Library Importer*

Synopsis

```
tlbimp file[\resourceid] [options]
```

Description

Creates a managed assembly from the supplied COM typelib, mapping the type definitions to .NET types. You need to import this new assembly into your C# program for use.

Example

```
tlbimp /out:MyOldCom.dll MyCom.tlb
```

Options

```
/? , /help
```

Displays usage information and exits.

```
/asmversion :version
```

Specifies the generated assembly's version in *major.minor.build.revision* format (such as 6.0.2600.0).

```
/delaysign
```

Partially signs the generated assembly. Requires */keycontainer*, */keyfile*, or */publickey*.

```
/keycontainer :name
```

Specifies a key container that contains the key-pair with which to sign the assembly.

```
/keyfile :file
```

Specifies the name of the file that contains the key or key-pair with which to sign the assembly.

```
/namespace :namespace
```

Specifies the namespace of the generated assembly.

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/out :file
```

Specifies the filename of the generated assembly.

```
/primary
```

Generates a primary interop assembly.

`/publickey:file`

Specifies a file that contains a public key with which to sign the assembly. To create such a file, use the `-p` option of the [Sn.exe](#) utility.

`/reference:file`

Specifies an assembly that contains external type definitions.

`/silent`

Suppresses display of success messages.

`/strictref`

Causes *Tlb/mp.exe* to fail if it cannot resolve all references within the imported file or an assembly listed with the `/reference` option.

`/sysarray`

Imports COM SAFEARRAYs as the .NET managed `System.Array` type.

`/transform:name`

Performs the specified transformation. Currently, only `DispRet` is available (performs `[out,retval]` transformation on methods of disp-only interfaces). (Added in .NET 1.1.)

`/unsafe`

Disables security checks in the generated assembly. Use with caution, since this poses a security risk.

`/verbose`

Displays verbose output.

See Also

[TlbExp.exe](#)

[\[Team LIB \]](#)

[◀ PREVIOUS](#)

[NEXT ▶](#)

*Wsdll.exe**Web Services Description Language Utility*

Synopsis

```
wsdl.exe options url-or-path [url-or-path ...]
```

Description

Creates service descriptions and generates proxy clients for ASP.NET web-service methods. See the ASP.NET documentation in the .NET Framework SDK for more detail on web services.

Example

Create the proxy client *Service1.cs* from the .NET web service at the specified URL:

```
wsdl http://localhost/MyService/Service1.asmx?WSDL
```

Options

```
/?
```

Displays usage information and exits.

```
/appsettingbaseurl:url, /baseurl:url
```

Specifies the base URL for calculating the URL fragment. Requires `/appsettingurlkey`.

```
/appsettingurlkey:key, /urlkey:key
```

Specifies application settings configuration key to read the default value for the proxy client's `Url` property.

```
/d[omain]:domain
```

Specifies a domain name, if one is required for authentication.

```
/l[anguage]:language
```

Specifies the language for the generated proxy client. Valid options are **CS** (C#), **VB** (Visual Basic .NET), **JS** (JScript.NET), and **VJS** (J#).

```
/namespace:namespace
```

Specifies a namespace for the generated proxy client class.

```
/nologo
```

Suppresses display of the banner and copyright messages.

```
/o[ut]:file
```

Specifies the filename of the generated proxy client class. If not specified, *Wsd* bases the filename on the name of the web service.

/parsableerrors

Displays error messages using a format similar to that used by the compilers. (Added in .NET 1.1.)

/p[assword] :password

Specifies a password, if one is required for authentication.

/protocol :protocol

Specifies the protocol to implement. Valid protocols are *SOAP* (the default), *SOAP12*, *HttpGet*, or *HttpPost*.

/proxy :url

Specifies the URL of an HTTP proxy server.

/proxydomain :domain, /pd :domain

Specifies a domain name, if one is required for HTTP proxy server authentication.

/proxypassword :password, /pp :password

Specifies a password, if one is required for HTTP proxy server authentication.

/proxyusername :username, /pu :username

Specifies a user name, if one is required for HTTP proxy server authentication.

/server

Generates an abstract class instead of a concrete proxy client class.

/u[sername] :username

Specifies a user name, if one is required for authentication.

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)*WinCV.exe**Windows Class Viewer*

Synopsis

wincv [options]

Description

Searches for matching names within a supplied assembly and displays types and member signatures as C# code. If no assemblies are supplied, it uses the default libraries. The namespaces and classes are displayed in a listbox, and the selected type information is displayed in another window.

Options

/?, /h

Displays usage information and exits.

@file

Specifies a response file containing *WinCV.exe* options.

/hide:option

Hides types matching the specified option. Valid options are **protected**, **private**, **internal**, and **inherited**. You may supply this option multiple times.

/nostdlib[+|-]

Use **/nostdlib+** or **/nostdlib** to suppress loading default assemblies.

/r:file

Specifies an assembly. You may supply this option multiple times to specify multiple assemblies. Use **/nostdlib** to hide everything else but the types in the specified assemblies.

/show:option

Shows types matching the specified option. Valid options are **protected**, **private**, **internal**, and **inherited**. You may supply this option multiple times.

See Also

[*//LDasm.exe*](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

*Xsd.exe**XML Schema Definition Tool*

Synopsis

```
xsd.exe assembly.[dll|exe] [/outputdir:dir] [/type:type1 [/type:type2 ...]]
xsd.exe instance.xml [/outputdir:dir]
xsd.exe schema.xdr [/outputdir:dir]
xsd.exe schema.xsd (/classes|/dataset) [/e] [/l] [/n] [/o] [/uri]
```

Description

Generates XML schemas from XDR, XML files, or class information. Can also generate DataSet or class information from a schema.

Examples

```
xsd foo.xdr
xsd bar.dll
```

Arguments

assembly.[dll|exe]

The name of a .NET assembly. *Xsd.exe* infers a schema from the assembly's types and generates an *.xsd* file.

instance.xml

The name of an XML document. *Xsd.exe* infers a schema from it and generates an *.xsd* file.

schema.xdr

The name of an XML Data Reduced schema document. *Xsd.exe* converts it to an *.xsd* file.

schema.xsd

The name of an XML Schema Description Language schema document. *Xsd.exe* generates either a dataset (*/dataset*) or source code (*/classes*) for types that correspond to the schema.

Options

/c[lasses]

Generates types that correspond to an XML schema.

/d[ataset]

Generates a subclass of DataSet that corresponds to an XML schema.

`/e[lement] : element`

Specifies a particular element in the XML schema. To specify multiple elements, use this option more than once. By default, *Xsd.exe* processes all elements.

`/l[anguage] : language`

Specifies the language for the generated code. Valid options are **CS** (C#), **VB** (Visual Basic .NET), **JS** (JScript.NET), and **VJS** (J#).

`/n[amespace] : namespace`

Specifies the namespace for the generated types.

`/nologo`

Suppresses display of the banner and copyright messages.

`/o[ut] : directory`

Specifies the directory to store generated files.

`/t[type] : type`

Specifies a particular type in the assembly. To specify multiple types, use this option more than once. By default, *Xsd.exe* processes all types.

`/u[ri] : uri`

Specifies the URI of the elements in the schema file to process.

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Part IV: API Quick Reference

Part IV is a succinct but detailed API reference of 21 important namespaces and more than 700 core types and their members. [Chapter 24](#) appears at the beginning of Part IV and explains how to get the most from its content.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 24. How to Use This Quick Reference

The quick-reference section that follows packs a lot of information into a small space. This introduction explains how to get the most out of that information. It describes how the quick reference is organized and how to read the individual quick-ref entries.

[\[Team LiB \]](#)


[◀ PREVIOUS](#) [NEXT ▶](#)

24.1 Finding a Quick-Reference Entry

The quick reference is organized into chapters, one per namespace. Each chapter begins with an overview of the namespace and includes a hierarchy diagram for the types (classes, interfaces, enumerations, delegates, and structs) in the namespace. Following the overview are quick-reference entries for all of the types in the namespace.

[Figure 24-1](#) is a sample diagram showing the notation used in this book. This notation is similar to that used in *Java in a Nutshell*, but borrows some features from UML. Abstract classes are shown as a slanted rectangle, and sealed classes as an octagonal rectangle. Inheritance is shown as a solid line from the subtype, ending with a hollow triangle that points to the supertype. There are two notations that indicate interface implementation. The lollipop notation is used most of the time, since it is easier to read. In some cases, especially where many types implement a given interface, the shaded box notation with the dashed line is used.

Figure 24-1. Class hierarchy notation



Important relationships between types (associations) are shown with a dashed line ending with an arrow. The figures don't show every possible association. Some types have strong containing relationships with one another. For example, a `System.Net.WebException` includes a `System.Net.WebResponse` that represents the HTTP response containing the error details (HTTP status code and error message). To show this relationship, a filled diamond is attached to the containing type with a solid line that points to the contained type.

Entries are organized alphabetically by type *and* namespace, so that related types are grouped near each other. Thus, in order to look up a quick reference entry for a particular type, you must also know the name of the namespace that contains that type. Usually, the namespace is obvious from the context, and you should have no trouble looking up the quick-reference entry you want. Use the tabs on the outside edge of the book and the dictionary-style headers on the upper outside corner of each page to help you find the namespace and type you are looking for.

Occasionally, you may need to look up a type for which you do not already know the namespace. In this case, refer to the [Appendix F](#). This index allows you to look up a type by its name and find out what namespace it is part of.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

24.2 Reading a Quick-Reference Entry

Each quick-reference entry contains quite a bit of information. The sections that follow describe the structure of a quick-reference entry, explaining what information is available, where it is found, and what it means. While reading the descriptions that follow, you will find it helpful to flip through the reference section itself to find examples of the features being described.

24.2.1 Type Name, Namespace, Assembly, Type Category, and Flags

Each quick-reference entry begins with a four-part title that specifies the name, namespace (followed by the assembly in parentheses), and type category of the type, and may also specify various additional flags that describe the type. The type name appears in bold at the upper left of the title. The namespace and assembly appear, in smaller print, in the lower left, below the type name.

The upper-right portion of the title indicates the type category of the type (class, delegate, enum, interface, or struct). The class category may include modifiers such as sealed or abstract.

In the lower-right corner of the title you may find a list of flags that describe the type. The possible flags and their meanings are as follows:

ECMA

The type is part of the ECMA CLI specification.

serializable

The type, or a supertype, implements `System.Runtime.Serialization.ISerializable` or has been flagged with the `System.Serializable` attribute.

marshal by reference

This class, or a superclass, derives from `System.MarshalByRefObject`.

context bound

This class, or a superclass, derives from `System.ContextBoundObject`.

disposable

The type implements the `System.IDisposable` interface.

flag

The enumeration is marked with the `System.FlagsAttribute`.

24.2.2 Description

The title of each quick-reference entry is followed by a short description of the most important features of the type. This description may be anywhere from a couple of sentences to several paragraphs long.

24.2.3 Synopsis

The most important part of every quick-reference entry is the synopsis, which follows the title and description. The synopsis for a type looks a lot like its source code, except that the member bodies are omitted and some additional annotations are added. If you know C# syntax, you know how to read the type synopsis.

The first line of the synopsis contains information about the type itself. It begins with a list of type modifiers, such as `abstract` and `sealed`. These modifiers are followed by the `class`, `delegate`, `enum`, `interface`, or `struct` keyword and then by the name of the type. The type name may be followed by a colon (:) and a supertype or interfaces that the type implements.

The type definition line is followed by a list of the members that the type defines. This list includes only those members that are explicitly declared in the type, are overridden from a base class, or are implementations of an interface member. Members that are simply inherited from a base class are not shown; you will need to look up the base class definition to find those members. Once again, if you understand basic C# syntax, you should have no trouble making sense of these lines. The listing for each member includes the modifiers, type, and name of the member. For methods, the synopsis also includes the type and name of each method parameter. The member names are in boldface, so it is easy to scan the list of members looking for the one you want. The names of method parameters are in italics to indicate that they are not to be used literally. The member listings are printed on alternating gray and white backgrounds to keep them visually separate.

24.2.3.1 Member availability and flags

Each member listing is a single line that defines the API for that member. These listings use C# syntax, so their meaning is immediately clear to any C# programmer. There is some auxiliary information associated with each member synopsis, however, that requires explanation.

The area to the right of the member synopsis is used to display a variety of flags that provide additional information about the member. Some of these flags indicate additional specification details that do not appear in the member API itself.

The following flags may be displayed to the right of a member synopsis:

Overrides

Indicates that a method overrides a method in one of its supertypes. The flag is followed by the name of the supertype that the method overrides.

Implements

Indicates that a method implements a method in an interface. The flag is followed by the name of the interface that is implemented.

=

For enumeration fields and constant fields, this flag is followed by the constant value of the field. Only constants of primitive and `String` types and constants with the value `null` are displayed. Some constant values are specification details, while others are implementation details. Some constants are platform-dependent, such as

`System.BitConverter.IsLittleEndian`. Platform-dependent values shown in this book conform to the `System.PlatformID.Win32NT` platform (32-bit Windows NT, 2000, or XP). The reason that symbolic constants are defined, however, is so you can write code that does not rely directly upon the constant value. Use this flag to help you understand the type, but do not rely upon the constant values in your own programs.

24.2.3.2 Functional grouping of members

Within a type synopsis, the members are not listed in strict alphabetical order. Instead, they are broken down into functional groups and listed alphabetically within each group. Constructors, events, fields, methods, and properties are all listed separately. Instance methods are kept separate from static (class) methods. Public members are listed separately from protected members. Grouping members by category breaks a type down into smaller, more comprehensible segments, making the type easier to understand. This grouping also makes it easier for you to find a desired member.

Functional groups are separated from each other in a type synopsis with C# comments, such as `// Public Constructors`, `// Protected Instance Properties`, and `// Events`. The various functional categories are as follows (in the order in which they appear in a type synopsis):

Constructors

Displays the constructors for the type. Public constructors and protected constructors are displayed separately in subgroupings. If a type defines no constructor at all, the C# compiler adds a default no-argument constructor that is displayed here. If a type defines only private constructors, it cannot be instantiated, so no constructor appears. Constructors are listed first because the first thing you do with most types is instantiate them by calling a constructor.

Fields

Displays all of the fields defined by the type, including constants. Public and protected fields are displayed in separate subgroupings. Fields are listed here, near the top of the synopsis, because constant values are often used throughout the type as legal values for method parameters and return values.

Properties

Lists all the properties of the type, breaking them down into subgroupings for public and protected static properties and public and protected instance properties. After the property name, its accessors (get or set) are shown.

Static Methods

Lists the static methods (class methods) of the type, broken down into subgroupings for public static methods and protected static methods.

Public Instance Methods

Contains all of the public instance methods.

Protected Instance Methods

Contains all of the protected instance methods.

24.2.4 Class Hierarchy

For any type that has a non-trivial inheritance hierarchy, the synopsis is followed by a "Hierarchy" section. This section lists all of the supertype of the type, as well as any interfaces implemented by those supertypes. It will also list any interfaces implemented by an interface. In the hierarchy listing, arrows indicate supertype to subtype relationships, while the interfaces implemented by a type follow the type name in parentheses. For example, the following hierarchy indicates that `System.IO.Stream` implements `IDisposable` and extends `MarshalByRefObject`, which itself extends `Object`:

```
System.Object → System.MarshalByRefObject
System.IO.Stream(System.IDisposable)
```

If a type has subtypes, the "Hierarchy" section is followed by a "Subtypes" section that lists those subtypes. If an interface has implementations, the "Hierarchy" section is followed by an "Implementations" section that lists those implementations. While the "Hierarchy" section shows ancestors of the type, the "Subtypes" or "Implementations" section shows descendants.

24.2.5 Cross References

The hierarchy section of a quick-reference entry is followed by a number of optional cross reference sections that indicate other, related types and methods that may be of interest. These sections are the following:

Passed To

This section lists all of the members (from other types) that are passed an object of this type as an argument, including properties whose values can be set to this type. This is useful when you have an object of a given type and want to know where it can be used.

Returned By

This section lists all of the members that return an object of this type, including properties whose values can take on this type. This is useful when you know that you want to work with an object of this type, but don't know how to obtain one.

Valid On

For attributes, this lists the attribute targets that the attribute can be applied to.

Associated Events

For delegates, lists the events it can handle.

24.2.6 A Note About Type Names

Throughout the quick reference, you'll notice that types are sometimes referred to by type name alone and at other times referred to by type name and namespace. If namespaces were always used, the type synopses would become long and hard to read. On the other hand, if namespaces were never used, it would sometimes be difficult to know what type was being referred to. The rules for including or omitting the namespace name are complex. They can be summarized approximately as follows, however:

- If the type name alone is ambiguous, the namespace name is always used.

- If the type is part of the `System` namespace or is a very commonly used type like `System.Collection.ICollection`, the namespace is omitted.
- If the type being referred to is part of the current namespace (and has a quick-reference entry in the current chapter), the namespace is omitted. The namespace is also omitted if the type being referred to is part of a namespace that contains the current namespace.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 25. The Microsoft.Win32 Namespace

The `Microsoft.Win32` namespace includes types you can use to interact with the Microsoft Windows platform. These types concentrate on two aspects of Windows-specific programming: receiving operating system events and manipulating the registry. Essentially, the classes, delegates, and enumerations in this namespace provide a type-safe object wrapper around a few select functions in the Windows API.

Use the `Registry` class to access the root-level registry keys, which are provided as `RegistryKey` objects. These have built-in methods for retrieving and modifying key values. The `SystemEvents` class allows you to respond to system events such as timers, preference changes, and shutdown operations. All other types in this namespace are used to support the `SystemEvents` class, by providing delegates for each event and custom `System.EventArgs` objects that provide additional information to the corresponding event handlers.

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

PowerModeChangedEventArgs

Microsoft.Win32 (system.dll) *class*

This class creates a custom `System.EventArgs` object for the `PowerModeChangedEventHandler` delegate. It provides additional information to your event handler, identifying the new power mode that the system has entered.

```
public class PowerModeChangedEventArgs : EventArgs {  
    // Public Constructors  
    public PowerModeChangedEventArgs(PowerModes mode);  
    // Public Instance Properties  
    public PowerModes Mode{get; }  
}
```

Hierarchy


`System.Object` → `System.EventArgs` → `PowerModeChangedEventArgs`

Passed To

`PowerModeChangedEventHandler.BeginInvoke(), Invoke()`

[Figure 25-1](#) shows the inheritance diagram for this namespace.

Figure 25-1. The Microsoft.Win32 namespace



[Team LiB]

◀ PREVIOUS NEXT ▶

PowerModeChangedEventHandler serializable

Microsoft.Win32 (system.dll) *delegate*

This delegate defines the signature that an event handler must use to receive the `SystemEvents.PowerModeChanged` event. This event is raised when the computer enters or exits suspend and when the power consumption level changes. A computer requires Advanced Power Management (APM) Advanced Configuration and Power Interface (ACPI) support in order to use these operating system features. APM/ACPI is usually supported on (but not restricted to) portable computers and devices.

```
public delegate void PowerModeChangedEventHandler(object sender, PowerModeChangedEventArgs e);
```

Associated Events

```
SystemEvents.PowerModeChanged( )
```

[Team LiB]

◀ PREVIOUS NEXT ▶

PowerModes

serializable

Microsoft.Win32 (system.dll) *enum*

This enumeration is used for the `PowerModeChangedEventArgs` class. It provides information about the current power modes, such as `Suspend`, which indicates that the computer is preparing to enter suspend mode, and `Resume`, which indicates that the computer is about to leave it. `StatusChange` simply indicates that the power mode status has changed, possibly due to automatic power-down settings, a weak or charging battery, or a transition between AC power and battery power.

```
public enum PowerModes {
    Resume = 1,
    StatusChange = 2,
    Suspend = 3
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `PowerModes`

Returned By

`PowerModeChangedEventArgs.Mode`

Passed To

`PowerModeChangedEventArgs.PowerModeChangedEventArgs()`

Registry

Microsoft.Win32 (mscorlib.dll) *sealed class*

This class is the starting point when using the Windows registry, which is the central repository used by most Windows applications for storing user-specific settings and preferences. Each static field of this class represents a root **RegistryKey** object, which has values and multiple levels of subkeys. These keys are read-only, but can be manipulated using the methods of the **RegistryKey** class.

Most applications store their settings in **CurrentUser** (HKEY_CURRENT_USER). The recommended standard is to use the **Software** subkey, create a subkey for your organization, and then create a subkey for each specific application (for example, Internet Explorer preferences are stored in HKEY_CURRENT_USER\Software\Microsoft\Internet Explorer). Analogous global settings that should affect all users on the current computer can be placed in a similar subkey in **LocalMachine** (HKEY_LOCAL_MACHINE). For example, setup programs often use this key to store information about installed applications. The full collection of user settings for all the users of the current computer can be retrieved from the **Users** key, as can the default settings for new users, which are contained in the **.DEFAULT** subkey of users. **CurrentUser** is actually a mapped subkey of **Users**, much as **CurrentConfig** is a subkey of **LocalMachine**.

The **ClassesRoot** key contains information used for Windows 3.1-compatible DDE and OLE support. Information for file viewers, Windows Explorer extensions, and file associations is also stored in this key. You can use the **PerformanceData** key to retrieve performance-related information. This data is not actually stored in the registry. Instead, it is automatically collected from the appropriate system object managers when this key is accessed. Lastly, the **DynData** key is used to support Virtual Device Drivers (VxDs) and allow them to provide real-time data to remote Win32 applications. It is used only in Windows 95, 98, and ME systems.

Much more information about the system registry is available from Microsoft's Windows platform documentation.

```
public sealed class Registry {
    // Public Static Fields
    public static readonly RegistryKey ClassesRoot;
    // =HKEY_CLASSES_ROOT [0x80000000]
    public static readonly RegistryKey CurrentConfig;
    // =HKEY_CURRENT_CONFIG [0x80000005]
    public static readonly RegistryKey CurrentUser;
    // =HKEY_CURRENT_USER [0x80000001]
    public static readonly RegistryKey DynData;
    // =HKEY_DYN_DATA [0x80000006]
    public static readonly RegistryKey LocalMachine;
    // =HKEY_LOCAL_MACHINE [0x80000002]
    public static readonly RegistryKey PerformanceData;
    // =HKEY_PERFORMANCE_DATA [0x80000004]
    public static readonly RegistryKey Users;
```

```
// =HKEY_USERS [0x80000003]
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

RegistryHive

serializable

Microsoft.Win32 (mscorlib.dll) *enum*

This enumeration provides values for the `RegistryKey.OpenRemoteBaseKey()` method. These values identify a registry key, just like the fields in the `Registry` class.

```
public enum RegistryHive {
    ClassesRoot = 0x80000000 ,
    CurrentUser = 0x80000001 ,
    LocalMachine = 0x80000002 ,
    Users = 0x80000003 ,
    PerformanceData = 0x80000004 ,
    CurrentConfig = 0x80000005 ,
    DynData = 0x80000006
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `RegistryHive`

Passed To

`RegistryKey.OpenRemoteBaseKey()`

RegistryKey marshal by reference, disposable

Microsoft.Win32 (mscorlib.dll) *sealed class*

The `RegistryKey` class contains the core functionality for reading and writing to the Windows registry. Each `RegistryKey` object represents an individual key in the registry. You can use the properties of this class to find out how many values this key contains (`ValueCount`), how many subkeys (`SubKeyCount`) there are, and the fully qualified key name (`Name`).

To open a subkey for modification, use the overloaded version of the `OpenSubKey()` method-which allows you to specify the `writable` parameter-and set it to `true`. You can open subkeys that are several levels deep by separating keys with a backslash (`\`). In C#, the backslash must be escaped, as in `mykey.OpenKey("Software\\Microsoft")`. You can also use methods such as `CreateSubKey()` and `DeleteSubKey()`. In the registry, keys are logical groupings, and values are the entries used to store the actual data. You can use the `GetValue()`, `SetValue()`, and `DeleteValue()` methods to manipulate a named value in the current key.

Changes to the registry are propagated across the system automatically and are flushed to disk automatically by the system. You should never need to use methods such as `Flush()`, unless you require absolute certainty that a registry change has been written to disk. The `OpenRemoteBaseKey()` method opens the registry on a remote computer, provided both machines are running the remote registry service and have remote administration enabled.

```
public sealed class RegistryKey : MarshalByRefObject, IDisposable {
// Public Instance Properties
    public string Name { get; }
    public int SubKeyCount { get; }
    public int ValueCount { get; }
// Public Static Methods
    public static RegistryKey OpenRemoteBaseKey(RegistryHive hKey, string machineName);
// Public Instance Methods
    public void Close();
    public RegistryKey CreateSubKey(string subkey);
    public void DeleteSubKey(string subkey);
    public void DeleteSubKey(string subkey, bool throwOnMissingSubKey);
    public void DeleteSubKeyTree(string subkey);
    public void DeleteValue(string name);
    public void DeleteValue(string name, bool throwOnMissingValue);
    public void Flush();
    public string[] GetSubKeyNames();
    public object GetValue(string name);
    public object GetValue(string name, object defaultValue);
    public string[] GetValueNames();
    public RegistryKey OpenSubKey(string name);
    public RegistryKey OpenSubKey(string name, bool writable);
    public void SetValue(string name, object value);
```

```
    public override string ToString( );  
    // overrides object  
    // Protected Instance Methods  
    protected override void Finalize( );  
    // overrides object  
}
```

Hierarchy

System.Object → System.MarshalByRefObject → RegistryKey(System.IDisposable)

[Team LiB]

SessionEndedEventArgs

Microsoft.Win32 (system.dll) *class*

This class is a custom `System.EventArgs` object for the `SystemEvents.SessionEnded` delegate. It provides additional information to your event handler about why the current session has ended.

```
public class SessionEndedEventArgs : EventArgs {  
    // Public Constructors  
    public SessionEndedEventArgs(SessionEndReasons reason);  
    // Public Instance Properties  
    public SessionEndReasons Reason {get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `SessionEndedEventArgs`

Passed To

```
SessionEndedEventHandler.{BeginInvoke( ), Invoke( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

SessionEndedEventHandler

serializable

Microsoft.Win32 (system.dll)

delegate

This delegate defines the signature that an event handler must use to receive the `SystemEvents.SessionEnded` event. This event is raised just before the system finishes its logoff or shutdown procedure.

```
public delegate void SessionEndedEventHandler(object sender, SessionEndedEventArgs e);
```

Associated Events

```
SystemEvents.SessionEnded( )
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

SessionEndingEventArgs

Microsoft.Win32 (system.dll) *class*

This class is a custom `System.EventArgs` object for the `SystemEvents.SessionEnding` delegate. It provides additional information to your event handler about why the session is ending, and allows you to request that the session continue, by setting the `Cancel` property to `true`. Note that this is only a request, and you may not always be able to successfully cancel a shutdown operation.

```
public class SessionEndingEventArgs : EventArgs {  
    // Public Constructors  
    public SessionEndingEventArgs(SessionEndReasons reason);  
    // Public Instance Properties  
    public bool Cancel {set; get; }  
    public SessionEndReasons Reason {get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `SessionEndingEventArgs`

Passed To

`SessionEndingEventHandler.BeginInvoke(), Invoke()`

[Team LiB]

◀ PREVIOUS NEXT ▶

SessionEndingEventHandler serializable

Microsoft.Win32 (system.dll) *delegate*

This delegate defines the signature that an event handler must use to receive the `SystemEvents.SessionEnding` event. This event is raised when the user has chosen to log off or shutdown the system. It occurs before the `SystemEvents.SessionEnded` event. `SessionEndingEventArgs` provides a `Cancel` property, which you can set in the event handler to cancel the pending shutdown.

```
public delegate void SessionEndingEventHandler(object sender, SessionEndingEventArgs e)
```

Associated Events

```
SystemEvents.SessionEnding( )
```

[Team LiB]

◀ PREVIOUS NEXT ▶

SessionEndReasons

serializable

Microsoft.Win32 (system.dll)

enum

This enumeration specifies information for the `Reason` property of the `SessionEndingEventArgs` and `SessionEndedEventArgs` event arguments. It specifies whether the user who started the current application is logging off (`Logoff`) (in which case the system may continue to run) or whether the operating system is shutting down (`SystemShutdown`).

```
public enum SessionEndReasons {  
    Logoff = 1,  
    SystemShutdown = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `SessionEndReasons`

Returned By

`SessionEndedEventArgs.Reason`, `SessionEndingEventArgs.Reason`

Passed To

`SessionEndedEventArgs.SessionEndedEventArgs()`,
`SessionEndingEventArgs.SessionEndingEventArgs()`

SystemEvents

Microsoft.Win32 (system.dll) *sealed class*

This class provides global events for select Windows operating system events. You can write event handlers to receive these. Some of the events include notifications that occur when user settings are changed (`DisplaySettingsChanged`, `TimeChanged`, and `UserPreferenceChanged`) or when the system state changes (`LowMemory`, `PowerModeChangedSessionEnded`, and `SessionEnding`). You can also receive notifications about new fonts (`InstalledFontsChanged`) and palette switching in 256-color mode (`PaletteChanged`).

System event handlers are executed on a different thread than the rest of your program. For this reason, code in the event handler must be thread-safe. If your event handler needs access to other objects from your program, you can use the static method `InvokeOnEventsThread()` to instantiate these objects on the system event listener thread. This way, they are easily accessible to the event handler code.

Do not perform time-consuming tasks in a system event handler, as it may cause problems with other applications that are also trying to handle the event.

```
public sealed class SystemEvents {
// Public Static Methods
    public static IntPtr CreateTimer(int interval);
    public static void InvokeOnEventsThread(Delegate method);
    public static void KillTimer(IntPtr timerId);
// Events
    public event EventHandler DisplaySettingsChanged;
    public event EventHandler EventsThreadShutdown;
    public event EventHandler InstalledFontsChanged;
    public event EventHandler LowMemory;
    public event EventHandler PaletteChanged;
    public event PowerModeChangedEventHandler PowerModeChanged;
    public event SessionEndedEventHandler SessionEnded;
    public event SessionEndingEventHandler SessionEnding;
    public event EventHandler TimeChanged;
    public event TimerElapsedEventHandler TimerElapsed;
    public event UserPreferenceChangedEventHandler UserPreferenceChanged;
    public event UserPreferenceChangingEventHandler UserPreferenceChanging;
}
```

TimerElapsedEventArgs

Microsoft.Win32 (system.dll) *class*

This class is a custom `System.EventArgs` object used for the `SystemEvents.TimerElapsed` delegate. It provides additional information to your event handler, identifying the ID of the timer that has changed.

```
public class TimerElapsedEventArgs : EventArgs {  
    // Public Constructors  
    public TimerElapsedEventArgs(IntPtr timerId);  
    // Public Instance Properties  
    public IntPtr TimerId { get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `TimerElapsedEventArgs`

Passed To

```
TimerElapsedEventHandler.BeginInvoke( ), Invoke( )
```

[Team LiB]

◀ PREVIOUS NEXT ▶

TimerElapsedEventHandler serializable

Microsoft.Win32 (system.dll) *delegate*

This delegate defines the signature an event handler must use to receive the `SystemEvents.TimerElapsed` event. This event is raised whenever a windows timer interval expires.

```
public delegate void TimerElapsedEventHandler(object sender, TimerElapsedEventArgs e);
```

Associated Events

```
SystemEvents.TimerElapsed( )
```

[Team LiB]

◀ PREVIOUS NEXT ▶

UserPreferenceCategoryserializable

Microsoft.Win32 (system.dll) *enum*

This enumeration is used for the `UserPreferenceChangedEventArgs` class. It provides information identifying the type of preference that was changed.

```
public enum UserPreferenceCategory {
    Accessibility = 1,
    Color = 2,
    Desktop = 3,
    General = 4,
    Icon = 5,
    Keyboard = 6,
    Menu = 7,
    Mouse = 8,
    Policy = 9,
    Power = 10,
    Screensaver = 11,
    Window = 12,
    Locale = 13
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `UserPreferenceCategory`

Returned By

`UserPreferenceChangedEventArgs.Category`, `UserPreferenceChangingEventArgs.Category`

Passed To

`UserPreferenceChangedEventArgs.UserPreferenceChangedEventArgs()`,
`UserPreferenceChangingEventArgs.UserPreferenceChangingEventArgs()`

UserPreferenceChangedEventArgs

Microsoft.Win32 (system.dll) *class*

This class is a custom `System.EventArgs` object used for the `UserPreferenceChangedEventHandler` delegate. It provides additional information to your event handler, identifying the type of preference that was changed.

```
public class UserPreferenceChangedEventArgs : EventArgs {  
    // Public Constructors  
    public UserPreferenceChangedEventArgs(UserPreferenceCategory category);  
    // Public Instance Properties  
    public UserPreferenceCategory Category {get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `UserPreferenceChangedEventArgs`

Passed To

`UserPreferenceChangedEventHandler.BeginInvoke(), Invoke()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UserPreferenceChangedEventHandler serializable

Microsoft.Win32 (system.dll) *delegate*

This delegate defines the signature an event handler must use to receive the `SystemEvents.UserPreferenceChanged` event. This event is raised when a user applies configuration changes, usually through one of the setting modules in the Control Panel. Note that not all changes raise this event, so it is best to first test it to make sure it accomplishes everything you need before you rely on it.

```
public delegate void UserPreferenceChangedEventHandler(object sender,
UserPreferenceChangedEventArgs e);
```

Associated Events

```
SystemEvents.UserPreferenceChanged( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UserPreferenceChangingEventArgs

Microsoft.Win32 (system.dll) *class*

This class represents the event arguments sent to a `UserPreferenceChangingEventHandler`. `Category` specifies the `UserPreferenceCategory` of user preferences that is changing.

```
public class UserPreferenceChangingEventArgs : EventArgs {  
    // Public Constructors  
    public UserPreferenceChangingEventArgs (UserPreferenceCategory category);  
    // Public Instance Properties  
    public UserPreferenceCategory Category {get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `UserPreferenceChangingEventArgs`

Passed To

`UserPreferenceChangingEventHandler.BeginInvoke(), Invoke()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UserPreferenceChangingEventHandler serializable

Microsoft.Win32 (system.dll) *delegate*

This delegate receives the `SystemEvents.UserPreferenceChanging` event, which is similar to `SystemEvents.UserPreferenceChanged`, except it is raised as the event is changing, not after it has changed.

```
public delegate void UserPreferenceChangingEventHandler(object sender,  
UserPreferenceChangingEventArgs e);
```

Associated Events

```
SystemEvents.UserPreferenceChanging( )
```


[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 26. System

In many respects, the `System` namespace serves as the core namespace for the .NET libraries, in much the same way `java.lang` does for Java programmers or `stdlib.h` does for C/C++ programmers. For example, the ECMA-compliant primitive-type value types are defined in the `System` namespace, along with complementary composite types and base types. These are used in the synthesis of type generation, which is done by the compiler on the .NET programmer's behalf (for an example of this on-the-fly type synthesis, see `Array`). [Figure 26-1](#) shows many of the types in this namespace.

Figure 26-1. The System namespace



`System` serves as the home for key base-type definitions, including `Object`, the root of every type in the .NET hierarchy. Every type in the system ultimately extends this class, making it the "root of all evil" in .NET. In addition, this namespace contains `ValueType`, the base type for all value types in .NET (such as the primitive types listed later in this chapter, shown in [Figure 26-5](#)), and `Type`, which in turn represents compile-time type information about other types defined within the .NET environment (the type metadata). More on `Type` can be found in [Chapter 35](#).

ECMA-compliant primitive-type value types include the fundamental types used for all .NET applications, which are basic value types such as `Int32`, `Single`, `Double`, `Decimal`, `Char`, `Byte`, and `Boolean`. All of the primitive types are aliased in C# with keywords such as `int`, `double`, and `bool`. See the description of each type for more details. See also [Section 2.5](#). In addition to these fundamental types, there are composite types such as `DateTime` and `TimeSpan`, used to handle date- and time-based calculations without having to drop down to integer math, and `Uri`, used to represent

references to a Universal Resource Identifier, which is the more generic form of the ubiquitous HTTP URL identifier used on the Web.

In addition to these primitive and composite types, several interfaces defined here are intended as support interfaces. For example, the interfaces `IConvertible`, `IComparable`, and `ICloneable` let types support the same basic operations (conversion, comparison, and cloning, respectively) that the primitive types offer.

Along with the base types described earlier, `System` contains base types that programmers do not directly reference, such as the following:

`System.Array`

The base type for any array-type declaration, allowing .NET developers to refer to any type (or rank) array without having to specify exact type.


`System.Delegate` and `System.MulticastDelegate`

Base types for delegate types (see [Figure 26-2](#)) created using the `delegate` keyword in C#.

`System.Attribute`

The base type required for any type that wishes to be used as an attribute on other types, or methods, fields, etc. (see [Figure 26-2](#)).

Figure 26-2. Attributes and delegates in the System namespace



Because delegates are often used in conjunction with events and event handlers, **System** also contains the definitions for **EventHandler**, the universal delegate type, and **EventArgs**, the base type representing data sent as part of an event-handler call.

System also serves as the heart of the exception-handling hierarchy in .NET, defining the base type **Exception**, which is the base type for all exceptions. The exception hierarchy is then bifurcated into two realms: *system exceptions*, which are exceptions generated by or relating to the runtime itself, and *application exceptions*, which are exceptions relating to the target business domain and typically are used on a per-application basis. **SystemException** serves as the base type for the former, and **ApplicationException** is the base type for the latter. [Figure 26-3](#) and [Figure 26-4](#) show the exceptions in the System namespace.

Figure 26-3. Exceptions in the System namespace





Figure 26-4. Specialized exceptions in the System namespace



`System` also contains two definitions of some importance to the .NET programmer: the `IDisposable` interface, used to help programmers define cleanup and resource-release semantics for their types, and the `GC` class, which gives the .NET programmer access to the CLR garbage collector.

The `System` namespace also contains a few interoperability types. `Guid` represents the OSF UUID type that was made famous by COM. The attributes `STAThreadAttribute` and `MTAThreadAttribute` indicate to the runtime which sort of COM apartment-threading model the .NET component should use (but only when COM interoperability comes into play).

Finally, `System` defines the fundamental types such as `Console` and `Environment`. These give the .NET programmer access to the standard-in/standard-out streams (i.e., the command-shell console) and the environment variables of a given process, respectively. Most .NET applications will use ASP.NET or Windows Forms to present a graphical user interface. However, applications such as compilation tools, XML filters, and batch jobs use console I/O and environment variables extensively.

[[Team LiB](#)]

Activator

CF 1.0

System (mscorlib.dll)


sealed class

This class is used to *activate* objects; that is, it either creates an object or obtains a handle to an existing object used in a variety of specialized conditions. For example, `Activator` can create an object within another `AppDomain` that object. This effectively gives a multidomain container application (such as ASP.NET) the ability to request and perform tasks within that domain (such as closing down the `AppDomain` in the event of a user request to shut down the application).

`Activator`'s methods come in two distinct flavors: `CreateInstance()` and `CreateInstanceFrom()`. The former creates an object given particular criteria (such as the type to create and the assembly from which to create it). The latter obtains `System.Runtime.Remoting.RemotingConfiguration` data to locate another object and obtain a handle to it (for some remote-object method invocations).

All of the methods in `Activator` return a `System.Runtime.Remoting.ObjectHandle`, not the actual object. This is a proxy to the created/remote object. As such, programmers must call `Unwrap()` on the returned `ObjectHandle` to obtain the actual object; that is, an explicit downcast is required, since the return value is declared to be a generic `object`.

Figure 26-5. Value types in the System namespace



```
public sealed class Activator {
    // Public Static Methods
    public static ObjectHandle CreateComInstanceFrom(string assemblyName, string typeName)
    public static ObjectHandle CreateComInstanceFrom(string assemblyName, string typeName,
        byte[] hashValue, System.Configuration.Assemblies.AssemblyHashAlgorithm hashAlgorithm)
    public static object CreateInstance(Type type);
    public static object CreateInstance(Type type, System.Reflection.BindingFlags bindingFlags,
        System.Reflection.Binder binder, object[] args, System.Globalization.CultureInfo cultureInfo);
    public static object CreateInstance(Type type, System.Reflection.BindingFlags bindingFlags,
        System.Reflection.Binder binder, object[] args, System.Globalization.CultureInfo cultureInfo,
        object[] activationAttributes);
    public static object CreateInstance(Type type, bool nonPublic);
    public static object CreateInstance(Type type, object[] args);
}
```

```
public static object CreateInstance(Type type, object[] args, object[] activationA
public static ObjectHandle CreateInstance(string assemblyName, string typeName);
public static ObjectHandle CreateInstance(string assemblyName, string typeName, bool
    System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
    System.Globalization.CultureInfo culture, object[] activationAttributes,
    System.Security.Policy.Evidence securityInfo);
public static ObjectHandle CreateInstance(string assemblyName, string typeName, obje
public static ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName);
public static ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName,
    System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
    System.Globalization.CultureInfo culture, object[] activationAttributes,
    System.Security.Policy.Evidence securityInfo);
public static ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName,
object[] activationAttributes);
public static object GetObject(Type type, string url);
public static object GetObject(Type type, string url, object state);
}
```

[Team LiB]

◀ PREVIOUS NEXT ▶

AppDomain

CF 1.0, ECMA 1.0, marshal by reference

System (mscorlib.dll)

sealed class

This class represents an abstract separation within the executing process, which mimics the separation by the operating system machine. As a result, a single .NET process can host multiple other processes that offer the isolation found in a low overhead of a single process.

Every .NET process created has at least one `AppDomain`, even when running a simple command shell-driven process created by the shim code at the start of a .NET executable file. Applications that act as containers, however, load assemblies into each `AppDomain` independently of one another. This is, in fact, precisely how ASP.NET processes separate from one another, so that an exception thrown from within one won't tear down the entire IIS process.

Creating a new `AppDomain` involves using the static `CreateDomain()` method. This method is overloaded, but simply to pass in a friendly name for the `AppDomain`. When finished with a given `AppDomain`, use the `AppDomain` and all objects stored within it. Should a .NET programmer wish to obtain a reference to the current `AppDomain` within, the static property `CurrentDomain` returns the current `AppDomain`.

Each `AppDomain` contains an entirely separate list of loaded assemblies accessible via the `GetAssemblies()` method. `AppDomains` can also create instances of types within the `CreateInstance()` family of methods. An `AppDomain` can also load and execute the entry point of an assembly, or it can load an assembly directly using one of the `Load()` methods. `AppDomains` even support transient or temporary assemblies through the `DefinedDynamicAssembly()` method.

`AppDomains` also offer a number of .NET events for interested consumers, notifying .NET programmers when an assembly is loaded (`AssemblyLoad`), when an exception has been thrown out of a thread within that assembly (`UnhandledException`), the process containing it is being unloaded and torn down (`DomainUnload` and `ProcessExit`). .NET programs can perform necessary actions, such as loading an assembly from an alternative location when an assembly fails to load.

`AppDomain` also contains a number of properties, which act in a role similar to environment variables with properties are, like environment variables, simple name-value mapping pairs, retrievable in one of two ways: by name or by index. A set of predefined properties on the `AppDomain` class (such as `BaseDirectory`).

```
public sealed class AppDomain : MarshalByRefObject, _AppDomain, System.Security.IEvidence
// Public Static Properties
    public static AppDomain CurrentDomain { get; }
// Public Instance Properties
    public string BaseDirectory { get; }
// implements _AppDomain
    public string DynamicDirectory { get; }
// implements _AppDomain
    public Evidence Evidence { get; }
// implements System.Security.IEvidenceFactory
    public string FriendlyName { get; }
// implements _AppDomain
```

```

    public string RelativeSearchPath{get; }
// implements _AppDomain
    public AppDomainSetup SetupInformation{get; }
    public bool ShadowCopyFiles{get; }
// implements _AppDomain
// Public Static Methods
    public static AppDomain CreateDomain(string friendlyName);
    public static AppDomain CreateDomain(string friendlyName, System.Security.Policy.Evi
    public static AppDomain CreateDomain(string friendlyName, System.Security.Policy.Evi
        AppDomainSetup info);
    public static AppDomain CreateDomain(string friendlyName, System.Security.Policy.Evi
        string appBasePath, string appRelativeSearchPath, bool shadowCopyFiles);
    public static int GetCurrentThreadId( );
    public static void Unload(AppDomain domain);
// Public Instance Methods
    public void AppendPrivatePath(string path);
// implements _AppDomain
    public void ClearPrivatePath( );
// implements _AppDomain
    public void ClearShadowCopyPath( );
// implements _AppDomain
    public ObjectHandle CreateComInstanceFrom(string assemblyName, string typeName);
    public ObjectHandle CreateComInstanceFrom(string assemblyFile, string typeName, byte
        System.Configuration.Assemblies.AssemblyHashAlgorithm hashAlgorithm);
    public ObjectHandle CreateInstance(string assemblyName, string typeName)
// implements _AppDomain
    public ObjectHandle CreateInstance(string assemblyName, string typeName, bool ignore
        System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
        System.Globalization.CultureInfo culture, object[ ] activationAttributes,
        System.Security.Policy.Evidence securityAttributes)
// implements _AppDomain
    public ObjectHandle CreateInstance(string assemblyName, string typeName,
        object[ ] activationAttributes)
// implements _AppDomain
    public object CreateInstanceAndUnwrap(string assemblyName, string typeName);
    public object CreateInstanceAndUnwrap(string assemblyName, string typeName, bool ign
        System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
        System.Globalization.CultureInfo culture, object[ ] activationAttributes,
        System.Security.Policy.Evidence securityAttributes);
    public object CreateInstanceAndUnwrap(string assemblyName, string typeName, object[
    public ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName);
// implements _AppDomain
    public ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName, bool ig
        System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
        System.Globalization.CultureInfo culture, object[ ] activationAttributes,
        System.Security.Policy.Evidence securityAttributes)
// implements _AppDomain
    public ObjectHandle CreateInstanceFrom(string assemblyFile, string typeName,
        object[ ] activationAttributes)

```

```

// implements _AppDomain
public object CreateInstanceFromAndUnwrap(string assemblyName, string typeName);
public object CreateInstanceFromAndUnwrap(string assemblyName, string typeName, bool
    System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder, ob
    System.Globalization.CultureInfo culture, object[ ] activationAttributes,
    System.Security.Policy.Evidence securityAttributes);
public object CreateInstanceFromAndUnwrap(string assemblyName, string typeName, obje
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access);
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, System.Security.Policy.Ev
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, System.Security.Policy.Evi
    System.Security.PermissionSet requiredPermissions, System.Security.PermissionSe
    System.Security.PermissionSet refusedPermissions);
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, System.Security.Permission
    System.Security.PermissionSet optionalPermissions, System.Security.PermissionSet
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, string dir);
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, string dir, System.Securit
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, string dir, System.Securit
    System.Security.PermissionSet requiredPermissions, System.Security.PermissionSe
    System.Security.PermissionSet refusedPermissions);
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, string dir, System.Securit
    System.Security.PermissionSet requiredPermissions, System.Security.PermissionSe
    System.Security.PermissionSet refusedPermissions, bool isSynchronized)
// implements _AppDomain
public AssemblyBuilder DefinedDynamicAssembly(System.Reflection.AssemblyName name,
    System.Reflection.Emit.AssemblyBuilderAccess access, string dir,
    System.Security.PermissionSet requiredPermissions, System.Security.PermissionSe
    System.Security.PermissionSet refusedPermissions)
// implements _AppDomain
public void DoCallback(CrossAppDomainDelegate callBackDelegate)
// implements _AppDomain
public int ExecuteAssembly(string assemblyFile);
// implements _AppDomain
public int ExecuteAssembly(string assemblyFile,
    System.Security.Policy.Evidence assemblySecurity)

```

```

// implements _AppDomain
public int ExecuteAssembly(string assemblyFile, System.Security.Policy.Evidence asse
    string[ ] args);
// implements _AppDomain
public int ExecuteAssembly(string assemblyFile, System.Security.Policy.Evidence asse
    string[ ] args, byte[ ] hashValue, System.Configuration.Assemblies.AssemblyHashi
public Assembly[ ] GetAssemblies( );
// implements _AppDomain
public object GetData(string name);
// implements _AppDomain
public Type GetType( );
// overrides object
public override object InitializeLifetimeService( );
// overrides MarshalByRefObject
public bool IsFinalizingForUnload( );
public Assembly Load(System.Reflection.AssemblyName assemblyRef)
// implements _AppDomain
public Assembly Load(System.Reflection.AssemblyName assemblyRef,
    System.Security.Policy.Evidence assemblySecurity);
// implements _AppDomain
public Assembly Load(byte[ ] rawAssembly);
// implements _AppDomain
public Assembly Load(byte[ ] rawAssembly, byte[ ] rawSymbolStore);
// implements _AppDomain
public Assembly Load(byte[ ] rawAssembly, byte[ ] rawSymbolStore, System.Security.Po
// implements _AppDomain
public Assembly Load(string assemblyString);
// implements _AppDomain
public Assembly Load(string assemblyString, System.Security.Policy.Evidence assembly
// implements _AppDomain
public void SetAppDomainPolicy(System.Security.Policy.PolicyLevel domainPolicy)
// implements _AppDomain
public void SetCachePath(string path);
// implements _AppDomain
public void SetData(string name, object data);
// implements _AppDomain
public void SetDynamicBase(string path);
public void SetPrincipalPolicy(System.Security.Principal.PrincipalPolicy policy)
// implements _AppDomain
public void SetShadowCopyFiles( );
public void SetShadowCopyPath(string path);
// implements _AppDomain
public void SetThreadPrincipal(System.Security.Principal.IPrincipal principal)
// implements _AppDomain
public override string ToString( );
// overrides object
// Events
public event AssemblyLoadEventHandler AssemblyLoad;
// implements _AppDomain

```

```
    public event ResolveEventHandler AssemblyResolve ;  
    // implements _AppDomain  
    public event EventHandler DomainUnload ;  
    // implements _AppDomain  
    public event EventHandler ProcessExit ;  
    // implements _AppDomain  
    public event ResolveEventHandler ResourceResolve ;  
    // implements _AppDomain  
    public event ResolveEventHandler TypeResolve ;  
    // implements _AppDomain  
    public event UnhandledExceptionHandler UnhandledException ;  
    // implements _AppDomain  
}
```

Hierarchy

Object → MarshalByRefObject → AppDomain(_AppDomain, System.Security.IEvidenceFactory)

Returned By

System.Threading.Thread.GetDomain()

[Team LiB]

AppDomainSetup

serializable

System (mscorlib.dll)

sealed class

This class allows you to configure some settings for an application domain before creating an `AppDomain` object. Create an instance of this class, set its properties, and pass it to the appropriate `AppDomain` factory method.

```
public sealed class AppDomainSetup : IAppDomainSetup {
// Public Constructors
    public AppDomainSetup( );
// Public Instance Properties
    public string ApplicationBase {set; get; }
// implements IAppDomainSetup
    public string ApplicationName {set; get; }
// implements IAppDomainSetup
    public string CachePath {set; get; }
// implements IAppDomainSetup
    public string ConfigurationFile {set; get; }
// implements IAppDomainSetup
    public bool DisallowBindingRedirects {set; get; }
    public bool DisallowCodeDownload {set; get; }
    public bool DisallowPublisherPolicy {set; get; }
    public string DynamicBase {set; get; }
// implements IAppDomainSetup
    public string LicenseFile {set; get; }
// implements IAppDomainSetup
    public LoaderOptimization LoaderOptimization {set; get; }
    public string PrivateBinPath {set; get; }
// implements IAppDomainSetup
    public string PrivateBinPathProbe {set; get; }
// implements IAppDomainSetup
    public string ShadowCopyDirectories {set; get; }
// implements IAppDomainSetup
    public string ShadowCopyFiles {set; get; }
// implements IAppDomainSetup
}
```

Returned By

`AppDomain.SetupInformation`

Passed To

```
AppDomain.CreateDomain( )
```

[\[Team LiB \]](#)


AppDomainUnloadedException serializable

System (mscorlib.dll) *class*

This exception signals an attempt to access an `AppDomain` that has been unloaded by `AppDomain.Unload`

```
public class AppDomainUnloadedException : SystemException {
// Public Constructors
    public AppDomainUnloadedException( );
    public AppDomainUnloadedException(string message);
    public AppDomainUnloadedException(string message, Exception innerException);
// Protected Constructors
    protected AppDomainUnloadedException(System.Runtime.Serialization.SerializationInfo
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



ApplicationException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

class

Derive from this class to create your own application-specific exceptions when a system-supplied exception is inappropriate. For example, if an application's methods receive an invalid argument, it makes sense to throw an **ArgumentException**. However, if an internal calculation results in a value that violates your business rules, you might choose to throw an application exception. Application exceptions should be treated as nonfatal.

```
public class ApplicationException : Exception {
// Public Constructors
    public ApplicationException( );
    public ApplicationException(string message);
    public ApplicationException(string message, Exception innerException);
// Protected Constructors
    protected ApplicationException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) →
ApplicationException

Subclasses

System.Reflection.InvalidFilterCriteriaException , TargetException ,
TargetInvocationException , TargetParameterCountException

ArgIterator

System (mscorlib.dll) *struct*

The .NET runtime uses this class to handle methods that take a variable number of parameters (C# uses the `params` keyword; C++ uses `...`; VB.NET uses `ParamArray`). The use of this class is completely hidden by language features. Unless you are writing a language compiler that needs to implement this feature, you do not need to use this class.

```
public struct ArgIterator {
// Public Constructors
    public ArgIterator(RuntimeArgumentHandle arglist);
    public ArgIterator(RuntimeArgumentHandle arglist, void *ptr);
// Public Instance Methods
    public void End( );
    public override bool Equals(object o);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypedReference GetNextArg( );
    public TypedReference GetNextArg(RuntimeTypeHandle rth);
    public RuntimeTypeHandle GetNextArgType( );
    public int GetRemainingCount( );
}
```

Hierarchy



ArgumentException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

class

This exception indicates that illegal data was passed to a method or constructor call. Note that *illegal* data is entirely contextual-the data may be a legitimate .NET value, but inappropriate for the use in question. Although .NET languages are type-safe in that you can't pass a string as a parameter when an integer is expected, there is nothing to keep you from passing a null or invalid value, such as sending (2001, 13, to `Date`Time's constructor. However, there is no 32nd day of the 13th month of the year 2001, and if you to initialize such a date, you'll get an exception.

The `ArgumentException` class (or one of its subclasses, `ArgumentNullException` or `ArgumentOutOfRangeException`) indicates that a method argument violated such a constraint. If you need to implement this exception in your own code, consider using one of its subclasses instead, since they represent common argument exceptions.

```
public class ArgumentException : SystemException {
// Public Constructors
    public ArgumentException( );
    public ArgumentException(string message);
    public ArgumentException(string message, Exception innerException);
    public ArgumentException(string message, string paramName);
    public ArgumentException(string message, string paramName, Exception innerException)
// Protected Constructors
    protected ArgumentException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public override string Message{get; }
// overrides Exception
    public virtual string ParamName{get; }
// Public Instance Methods
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// overrides Exception
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) → SystemException → ArgumentException

Subclasses

ArgumentNullException , ArgumentOutOfRangeException , DuplicateWaitObjectException

[Team LiB]

◀ PREVIOUS NEXT ▶

ArgumentNullException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception is a subclass of `ArgumentException` and indicates that a null parameter value was received by a method that does not accept nulls.

```
public class ArgumentNullException : ArgumentException {  
    // Public Constructors  
    public ArgumentNullException( );  
    public ArgumentNullException(string paramName);  
    public ArgumentNullException(string paramName, string message);  
    // Protected Constructors  
    protected ArgumentNullException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



CF 1.0, ECMA
1.0,
serializable

ArgumentOutOfRangeException


System (mscorlib.dll)

class

This exception is a subclass of `ArgumentException` and indicates that a method received an out-of-range parameter value.

```
public class ArgumentOutOfRangeException : ArgumentException {  
    // Public Constructors  
    public ArgumentOutOfRangeException( );  
    public ArgumentOutOfRangeException(string paramName);  
    public ArgumentOutOfRangeException(string paramName, object actualValue, string mess  
    public ArgumentOutOfRangeException(string paramName, string message);  
    // Protected Constructors  
    protected ArgumentOutOfRangeException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public virtual object ActualValue{get; }  
    public override string Message{get; }  
    // overrides ArgumentException  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context);  
    // overrides ArgumentException  
}
```

Hierarchy



ArithmeticException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This is the base class for all math-related exceptions. You can throw this class from your own code, but use a subclass (if one exists) that specifically addresses the type of error you have encountered.

```
public class ArithmeticException : SystemException {  
    // Public Constructors  
    public ArithmeticException( );  
    public ArithmeticException(string message);  
    public ArithmeticException(string message, Exception innerException);  
    // Protected Constructors  
    protected ArithmeticException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

DivideByZeroException , NotFiniteNumberException , OverflowException

Array

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

abstract class

Unlike other environments (such as C++), .NET has arrays of first-class type, in that all array types are `Array`. All methods are available on any array type, regardless of its declaration. In fact, the CLR is required to match the declaration. Thus, when you declare a variable of type `string[]`, the CLR creates an `Array` specifically for storing Strings in a one-dimensional array.

The `Array` class has a number of useful array-related methods, such as checking for bounds violations (a of the array that isn't in the array's declared size) and retrieval of array length. In addition, because `Array` implements `ICloneable`, `System.Collections.IList`, `System.Collections.ICollection`, and `System.Collections.IEnumerable`, arrays can be used anywhere these interface types are expected.

Starting with .NET 1.1, `Array` now has support for 64-bit indexer values, meaning that an array can stretch to hold 2⁶³ elements. As a result, several methods, including `Copy()`, `GetValue()`, and `SetValue()`, among others, now accept `Int32` values.

Arrays are reference types. This means that the statement `ArrayB = ArrayA` results in two objects that both point to the same array. To create a duplicate copy of an array, you must use `ArrayB = ArrayA.Clone()` to create a shallow copy with identical references. To create a deep copy in which each array has its own copy of subobjects, you must loop through the array and copy each element.

The `Array` class also contains useful static methods. These include `IndexOf()`, which returns the offset of an object in an array. For one-dimensional arrays, you can also use `Reverse()` to reverse a subset of the array (provided the objects in the array implement the `IComparable` interface). If the objects implement `IComparable`, you can implement `System.Collections.IComparer` in a custom class and pass an instance of it to `Reverse()`.

The static `Copy()` method works like the C function `memcpy`: it copies a portion of an array to a different array (or to a different array). When copying between multidimensional arrays, the array is treated like a long one-dimensional array, where each element occupies a separate row. (For example, if an array has three columns, copying five elements copies all three elements in the first row and the first two elements from the second row.) The source and destination arrays must not overlap without causing a problem.

Note that you can create both multidimensional arrays and ragged arrays (arrays of arrays). Arrays are first-class, although you can use the `CreateInstance()` method to create an array with a different lower bound. As the array won't be CLS (Common Language Specification)-compliant. Lastly, if you need a dynamically resizable collection `System.Collections.ArrayList`, which provides `Add()` and `Remove()` methods.

```
public abstract class Array : ICloneable, IList, ICollection, IEnumerable {
    // Public Instance Properties
    public virtual bool IsFixedSize {get; }
    // implements IList
    public virtual bool IsReadOnly {get; }
    // implements IList
    public virtual bool IsSynchronized {get; }
    // implements ICollection
    public int Length {get; }
```

```

    public long LongLength{get; }
    public int Rank{get; }
    public virtual object SyncRoot{get; }
// implements ICollection
// Public Static Methods
    public static int BinarySearch(Array array, int index, int length, object value);
    public static int BinarySearch(Array array, int index, int length, object value,
        System.Collections.IComparer comparer);
    public static int BinarySearch(Array array, object value);
    public static int BinarySearch(Array array, object value, System.Collections.ICompar
    public static void Clear(Array array, int index, int length);
    public static void Copy(Array sourceArray, Array destinationArray, int length);
    public static void Copy(Array sourceArray, Array destinationArray, long length);
    public static void Copy(Array sourceArray, int sourceIndex, Array destinationArray, :
        int length);
    public static void Copy(Array sourceArray, long sourceIndex, Array destinationArray,
        long length);
    public static Array CreateInstance(Type elementType, int length);
    public static Array CreateInstance(Type elementType, params int[ ] lengths);
    public static Array CreateInstance(Type elementType, int[ ] lengths, int[ ] lowerBou
    public static Array CreateInstance(Type elementType, int length1, int length2);
    public static Array CreateInstance(Type elementType, int length1, int length2, int l
    public static Array CreateInstance(Type elementType, params long[ ] lengths);
    public static int IndexOf(Array array, object value);
    public static int IndexOf(Array array, object value, int startIndex);
    public static int IndexOf(Array array, object value, int startIndex, int count);
    public static int LastIndexOf(Array array, object value);
    public static int LastIndexOf(Array array, object value, int startIndex);
    public static int LastIndexOf(Array array, object value, int startIndex, int count);
    public static void Reverse(Array array);
    public static void Reverse(Array array, int index, int length);
    public static void Sort(Array array);
    public static void Sort(Array keys, Array items);
    public static void Sort(Array keys, Array items, System.Collections.IComparer compar
    public static void Sort(Array keys, Array items, int index, int length);
    public static void Sort(Array keys, Array items, int index, int length, System.Colle
    public static void Sort(Array array,
        System.Collections.IComparer comparer);
    public static void Sort(Array array, int index, int length);
    public static void Sort(Array array, int index, int length, System.Collections.IComp
// Public Instance Methods
    public virtual object Clone( );
// implements ICloneable
    public virtual void CopyTo(Array array, int index);
// implements ICollection
    public virtual void CopyTo(Array array, long index);
    public virtual IEnumerator GetEnumerator( );
// implements IEnumerable
    public int GetLength(int dimension);

```

```
public long GetLongLength(int dimension);
public int GetLowerBound(int dimension);
public int GetUpperBound(int dimension);
public object GetValue(int index);
public object GetValue(params int[ ] indices);
public object GetValue(int index1, int index2);
public object GetValue(int index1, int index2, int index3);
public object GetValue(long index);
public object GetValue(params long[ ] indices);
public object GetValue(long index1, long index2);
public object GetValue(long index1, long index2, long index3);
public void Initialize( );
public void SetValue(object value, int index);
public void SetValue(object value, params int[ ] indices);
public void SetValue(object value, int index1, int index2);
public void SetValue(object value, int index1, int index2, int index3);
public void SetValue(object value, long index);
public void SetValue(object value, params long[ ] indices);
public void SetValue(object value, long index1, long index2);
public void SetValue(object value, long index1, long index2, long index3);
}
```

Returned By

`System.Collections.ArrayList.ToArray()` , `Enum.GetValues()`

Passed To

Multiple types

[Team LiB]

CF 1.0, ECMA
1.0,
serializable

ArrayTypeMismatchException


System (mscorlib.dll)

class

This exception is thrown when you store an element in an array that has a different type than the array's declared type. For example, trying to store a `String` object into an array declared to hold `Int32` instance causes this exception to be thrown.

```
public class ArrayTypeMismatchException : SystemException {  
    // Public Constructors  
    public ArrayTypeMismatchException( );  
    public ArrayTypeMismatchException(string message);  
    public ArrayTypeMismatchException(string message, Exception innerException);  
    // Protected Constructors  
    protected ArrayTypeMismatchException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



AssemblyLoadEventArgs

ECMA 1.0

System (mscorlib.dll) *class*

This class is used by the .NET Framework to pass information to the `AppDomain.AssemblyLoad` event. This information consists of a `System.Reflection.Assembly` object that represents the newly loaded assembly.

```
public class AssemblyLoadEventArgs : EventArgs {  
    // Public Constructors  
    public AssemblyLoadEventArgs(System.Reflection.Assembly loadedAssembly);  
    // Public Instance Properties  
    public Assembly LoadedAssembly {get; }  
}
```

Hierarchy

Object → EventArgs → AssemblyLoadEventArgs

Passed To

```
AssemblyLoadEventHandler.{BeginInvoke( ), Invoke( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

AssemblyLoadEventHandler

ECMA 1.0,
serializable

System (mscorlib.dll)

delegate

This delegate represents the event-handler method for the `AppDomain.AssemblyLoad` event.

```
public delegate void AssemblyLoadEventHandler(object sender, AssemblyLoadEventArgs args)
```

Associated Events

```
AppDomain.AssemblyLoad( )
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

AsyncCallback CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *delegate*

This delegate type is used as part of asynchronous operations on delegates in general. As described in [Chapter 16](#), delegates can be executed in an asynchronous fashion, using a random thread out of the system-managed thread pool. Frequently, however, programmers desire notification of the asynchronously executing delegate's completion, and the **AsyncCallback** is used to achieve that.

Using an **AsyncCallback** is fairly straightforward. At the asynchronous delegate's invocation, pass in an instance of this delegate (referring to a void-returning **IAAsyncResult**-accepting method) as part of the **BeginInvoke()** call. When the asynchronously executing delegate has finished execution, the method on the other end of the **AsyncCallback** is invoked, with an **IAAsyncResult** object as the sole parameter. (This **IAAsyncResult** object contains the output parameters from the delegate's call: the return value, along with any **out** or **ref** parameters declared as part of the method's signature.)

```
public delegate void AsyncCallback(IAAsyncResult ar);
```

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Attribute CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

abstract class

This is the base class for all custom attributes. Attributes are the .NET programmer's means of inserting a type's definition. For example, the .NET Serialization mechanism uses an attribute to indicate which field be serialized (see the `System.Reflection.FieldAttributes.NotSerialized` enumeration value). .NET to create their own attributes (called *custom attributes*, although from a certain perspective all attribute by creating a new type that claims `Attribute` as its base class type.

By themselves, attributes offer no modification to a type's behavioral semantics; that is, attributes don't methods or execution in any way. In fact, attribute instances aren't even created until they are retrieved metadata via the Reflection APIs. The entire purpose of an attribute is to act as a marker inside the type's consumption by some other API, library, or facility. For example, the Serialization APIs in the .NET Framework use the `Serializable` attribute to indicate which types are serializable. However, by themselves, the attributes don't perform the actual act of serialization. This must be done by passing the instance of the type into instance classes, in which the attribute is retrieved and examined, and "appropriate" action is taken.

Attributes can be attached to any metadata component in the .NET system. This means fields, methods, types (classes and value types), assemblies, modules, and more can all be the target of attribute declaration. The `AttributeTargets` enumeration indicates which types it is restricted to by using the `AttributeTargets` enumeration.)

The base `Attribute` class provides helper functions for testing custom attributes, including the `IsDefined` method. `IsDefined` examines a code element and indicates whether its metadata is decorated with a specified type of attribute. You must provide the element using the appropriate reflection type (e.g., `System.Reflection.Assembly`, `System.Reflection.ParameterInfo`). You can also use the `GetCustomAttribute` method to get a reference to a specified type, or the `GetCustomAttributes` method to get an array that contains all matching attributes. To a class or class member, these methods consider all ancestors. To disable this default behavior, use overloads of these methods that allows you to supply the `inherit` parameter, and set it to `false`.

Custom attributes should override the `TypeId` property so that it supplies a user-defined identifier that uniquely identifies an instance of this attribute on the type. This is entirely because more than one instance of an attribute can be applied to a particular metadata-token (field, type, parameter, and so on) instance.

```
public abstract class Attribute {
    // Protected Constructors
    protected Attribute();
    // Public Instance Properties
    public virtual object TypeId { get; }
    // Public Static Methods
    public static Attribute GetCustomAttribute(System.Reflection.Assembly element,
        Type attributeType);
    public static Attribute GetCustomAttribute(System.Reflection.Assembly element,
        Type attributeType, bool inherit);
    public static Attribute GetCustomAttribute(System.Reflection.MemberInfo element,
        Type attributeType);
}
```

```

public static Attribute GetCustomAttribute(System.Reflection.MemberInfo element,
    Type attributeType, bool inherit);
public static Attribute GetCustomAttribute(System.Reflection.Module element,
    Type attributeType);
public static Attribute GetCustomAttribute(System.Reflection.Module element,
    Type attributeType, bool inherit);
public static Attribute GetCustomAttribute(System.Reflection.ParameterInfo element,
    Type attributeType);
public static Attribute GetCustomAttribute(System.Reflection.ParameterInfo element,
    Type attributeType, bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.Assembly element);
public static Attribute[] GetCustomAttributes(System.Reflection.Assembly element,
    bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.Assembly element,
    Type attributeType);
public static Attribute[] GetCustomAttributes(System.Reflection.Assembly element,
    Type attributeType, bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.MemberInfo element);
public static Attribute[] GetCustomAttributes(System.Reflection.MemberInfo element,
    bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.MemberInfo element,
    Type type);
public static Attribute[] GetCustomAttributes(System.Reflection.MemberInfo element,
    Type type, bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.Module element);
public static Attribute[] GetCustomAttributes(System.Reflection.Module element,
    bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.Module element,
    Type attributeType);
public static Attribute[] GetCustomAttributes(System.Reflection.Module element,
    Type attributeType, bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.ParameterInfo eleme.
public static Attribute[] GetCustomAttributes(System.Reflection.ParameterInfo eleme.
    bool inherit);
public static Attribute[] GetCustomAttributes(System.Reflection.ParameterInfo eleme.
    Type attributeType);
public static Attribute[] GetCustomAttributes(System.Reflection.ParameterInfo eleme.
    Type attributeType, bool inherit);
public static bool IsDefined(System.Reflection.Assembly element, Type attributeType)
public static bool IsDefined(System.Reflection.Assembly element, Type attributeType,
public static bool IsDefined(System.Reflection.MemberInfo element, Type attributeTyp
public static bool IsDefined(System.Reflection.MemberInfo element, Type attributeTyp
public static bool IsDefined(System.Reflection.Module element, Type attributeType);
public static bool IsDefined(System.Reflection.Module element, Type attributeType, b
public static bool IsDefined(System.Reflection.ParameterInfo element, Type attribute
public static bool IsDefined(System.Reflection.ParameterInfo element, Type attribute
// Public Instance Methods
public override bool Equals(object obj);
// overrides object

```

```
public override int GetHashCode( );  
// overrides object  
public virtual bool IsDefaultAttribute( );  
public virtual bool Match(object obj);  
}
```

Subclasses

Multiple types

Valid On

All

[Team LiB]

AttributeTargets

CF 1.0, ECMA 1.0,
serializable, flag

System (mscorlib.dll)

enum

This enumeration is used to set the `AttributeUsageAttribute.ValidOn` property when creating a custom attribute. It allows you to specify the code elements for which a custom attribute can be used. You can use a bitwise combination of these values to specify multiple elements.

Using this attribute is the only means by which a custom attribute can declare a restriction of its usage against various metadata types. For example, when using the `System.Reflection.AssemblyKeyFileAttribute` attribute, which simply tells the compiler which public/private keyfile to use to sign the assembly, it makes no sense to apply to any other metadata type besides the assembly. Therefore, the `AssemblyKeyFileAttribute` attribute has an `AttributeUsageAttribute` (see the `AttributeUsageAttribute` entry) declared on it with the value `Assembly`. As a result, any attempt to use the `AssemblyKeyFileAttribute` attribute on anything other than an assembly results in a compilation error.

```
public enum AttributeTargets {
    Assembly = 0x00000001 ,
    Module = 0x00000002 ,
    Class = 0x00000004 ,
    Struct = 0x00000008 ,
    Enum = 0x00000010 ,
    Constructor = 0x00000020 ,
    Method = 0x00000040 ,
    Property = 0x00000080 ,
    Field = 0x00000100 ,
    Event = 0x00000200 ,
    Interface = 0x00000400 ,
    Parameter = 0x00000800 ,
    Delegate = 0x00001000 ,
    ReturnValue = 0x00002000 ,
    All = 0x00003FFF
}
```

Hierarchy

Object → ValueType → Enum(IComparable, IFormattable, IConvertible) → AttributeTargets

Returned By

`AttributeUsageAttribute.ValidOn`

Passed To

AttributeUsageAttribute.AttributeUsageAttribute()

[\[Team LiB \]](#)

AttributeUsageAttribute

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

sealed class

This attribute is used when developing a custom attribute class. It allows you to specify how your custom attribute must be used. The `ValidOn` property uses a bitwise combination of values from `AttributeTargets` to specify the code elements that can use your custom attribute. It's read-only and must be initialized using the constructor, as in `[AttributeUsage(AttributeTargets.Field | AttributeTargets.Property)]`.

The `AllowMultiple` property specifies whether the attribute can be used more than once for the same element. The `Inherited` attribute specifies whether your custom attribute will be applied to derived classes and overridden members. These are indicated using the usual *named parameter* syntax supported by attributes, as in `[AttributeUsage(Inherited = true, AllowMultiple = true)]`.

```
public sealed class AttributeUsageAttribute : Attribute {  
    // Public Constructors  
    public AttributeUsageAttribute(AttributeTargets validOn);  
    // Public Instance Properties  
    public bool AllowMultiple {set; get; }  
    public bool Inherited {set; get; }  
    public AttributeTargets ValidOn {get; }  
}
```

Hierarchy



Valid On

Class

BadImageFormatException

ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception occurs when .NET tries to load a DLL or executable that is either corrupt or invalid for the platform on which you are running.

```
public class BadImageFormatException : SystemException {  
    // Public Constructors  
    public BadImageFormatException( );  
    public BadImageFormatException(string message);  
    public BadImageFormatException(string message, Exception inner);  
    public BadImageFormatException(string message, string fileName);  
    public BadImageFormatException(string message, string fileName, Exception inner);  
    // Protected Constructors  
    protected BadImageFormatException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public string FileName{get; }  
    public string FusionLog{get; }  
    public override string Message{get; }  
    // overrides Exception  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // overrides Exception  
    public override string ToString( );  
    // overrides Exception  
}
```

Hierarchy



BitConverter

CF 1.0

System (mscorlib.dll)

sealed class

This class provides static methods that can be used to convert portions of a byte array to simple value types. It also contains the overloaded `GetBytes()` method, which converts simple data types to byte arrays. These functions can be useful for creating custom reader and writer classes. For example, a typical writer class might take specific data, convert it to a byte array, then pass the byte array to some type of stream object.

```
public sealed class BitConverter {
// Public Static Fields
    public static readonly bool IsLittleEndian;
// =True
// Public Static Methods
    public static long DoubleToInt64Bits(double value);
    public static byte[] GetBytes(bool value);
    public static byte[] GetBytes(char value);
    public static byte[] GetBytes(double value);
    public static byte[] GetBytes(short value);
    public static byte[] GetBytes(int value);
    public static byte[] GetBytes(long value);
    public static byte[] GetBytes(float value);
    public static byte[] GetBytes(ushort value);
    public static byte[] GetBytes(uint value);
    public static byte[] GetBytes(ulong value);
    public static double Int64BitsToDouble(long value);
    public static bool ToBoolean(byte[] value, int startIndex);
    public static char ToChar(byte[] value, int startIndex);
    public static double ToDouble(byte[] value, int startIndex);
    public static short.ToInt16(byte[] value, int startIndex);
    public static int.ToInt32(byte[] value, int startIndex);
    public static long.ToInt64(byte[] value, int startIndex);
    public static float.ToSingle(byte[] value, int startIndex);
    public static string ToString(byte[] value);
    public static string ToString(byte[] value, int startIndex);
    public static string ToString(byte[] value, int startIndex, int length);
    public static ushort.ToUInt16(byte[] value, int startIndex);
    public static uint.ToUInt32(byte[] value, int startIndex);
    public static ulong.ToUInt64(byte[] value, int startIndex);
}
```

Boolean

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This is a simple value type that contains either `true` or `false`. When converting to or from a string or comparing with a string, the `TrueString` and `FalseString` fields are used (these return `True` and `False`). This type is available in C# through the `bool` alias.

```
public struct Boolean : IComparable, IConvertible {
    // Public Static Fields
    public static readonly string FalseString;
    // =False
    public static readonly string TrueString;
    // =True
    // Public Static Methods
    public static bool Parse(string value);
    // Public Instance Methods
    public int CompareTo(object obj);
    // implements IComparable
    public override bool Equals(object obj);
    // overrides ValueType
    public override int GetHashCode();
    // overrides ValueType
    public TypeCode GetTypeCode();
    // implements IConvertible
    public override string ToString();
    // overrides ValueType
    public string ToString(IFormatProvider provider);
    // implements IConvertible
}
```

Hierarchy

Object → ValueType → Boolean(IComparable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

Buffer

CF 1.0

System (mscorlib.dll)

sealed class

The **Buffer** class provides static methods used to manipulate a region of unmanaged memory as though it were an array of **Byte**s. **Byte** arrays are traditionally used in unmanaged code to represent blocks of contiguous memory. This class includes the **ByteLength**() method, which indicates the total number of bytes in an array, and the **GetByte**() and **SetByte**() methods, which allow you to retrieve or set a specific **Byte** object in an array by specifying a zero-based index. Additionally, the **BlockCopy**() method can be used to move contiguous groups of bytes from one position in a buffer to another.

Note that **BlockCopy**() ignores types when conducting its byte-shuffling operations. If you use **BlockCopy**() to insert an otherwise incompatible type into the buffer, the copy goes through, but unpredictable results will arise later when you try to work with the buffer as its original type. For example, if you use the **BlockCopy**() method to insert an **Int32** into an array of **String** objects, the copy goes through, but the next time the array is accessed, there is no longer a **String** reference. It is an **Int32**, and what the CLR will do at that point is undocumented.

```
public sealed class Buffer {  
    // Public Static Methods  
    public static void BlockCopy(Array src, int srcOffset, Array dst, int dstOffset,  
        int count);  
    public static int ByteLength(Array array);  
    public static byte GetByte(Array array, int index);  
    public static void SetByte(Array array, int index, byte value);  
}
```

Byte

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This simple value type represents an unsigned 8-bit integer that can vary in value from 0 to 255. The `Parse()` method converts a number in a string (such as `122`) into a `Byte` object. This type is available in C# through the `byte` alias.

```
public struct Byte : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const byte MaxValue;
// =255
    public const byte MinValue;
// =0
// Public Static Methods
    public static byte Parse(string s);
    public static byte Parse(string s, IFormatProvider provider);
    public static byte Parse(string s, System.Globalization.NumberStyles style);
    public static byte Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider);
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Byte(IComparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)


CannotUnloadAppDomainException ECMA 1.0, serializable

System (mscorlib.dll) *class*

This exception signals that an attempt to invoke `AppDomain.Unload()` failed. This indicates that you either unload the default application domain (`AppDomain.CurrentDomain`), the domain has a thread that cannot be stopped, or the domain has already been unloaded.

```
public class CannotUnloadAppDomainException : SystemException {
// Public Constructors
    public CannotUnloadAppDomainException( );
    public CannotUnloadAppDomainException(string message);
    public CannotUnloadAppDomainException(string message, Exception innerException);
// Protected Constructors
    protected CannotUnloadAppDomainException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



Char

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This simple value type represents a 16-bit Unicode character (from hexadecimal 0x0000 to 0xFFFF). You can convert a character to upper- or lowercase and get its numeric representation using the methods of a `Char` object. You can also test if it is a number, letter, or symbol by using the methods prefixed with `Is`. For exact information, use the `GetUnicodeCategory()` method to get an enumerated value from `System.Globalization.UnicodeCategory`. This classifies the character into one of about thirty categories.

This type is aliased as `char` in C#. If you need an array of chars, use the `String` class.

```
public struct Char : IComparable, IConvertible {
// Public Static Fields
    public const char MaxValue;
// =0x0000FFFF
    public const char MinValue;
// =0x00000000
// Public Static Methods
    public static double GetNumericValue(char c);
    public static double GetNumericValue(string s, int index);
    public static UnicodeCategory GetUnicodeCategory(char c);
    public static UnicodeCategory GetUnicodeCategory(string s, int index);
    public static bool IsControl(char c);
    public static bool IsControl(string s, int index);
    public static bool IsDigit(char c);
    public static bool IsDigit(string s, int index);
    public static bool IsLetter(char c);
    public static bool IsLetter(string s, int index);
    public static bool IsLetterOrDigit(char c);
    public static bool IsLetterOrDigit(string s, int index);
    public static bool IsLower(char c);
    public static bool IsLower(string s, int index);
    public static bool IsNumber(char c);
    public static bool IsNumber(string s, int index);
    public static bool IsPunctuation(char c);
    public static bool IsPunctuation(string s, int index);
    public static bool IsSeparator(char c);
    public static bool IsSeparator(string s, int index);
    public static bool IsSurrogate(char c);
    public static bool IsSurrogate(string s, int index);
    public static bool IsSymbol(char c);
    public static bool IsSymbol(string s, int index);
    public static bool IsUpper(char c);
```

```

    public static bool IsUpper(string s, int index);
    public static bool IsWhiteSpace(char c);
    public static bool IsWhiteSpace(string s, int index);
    public static char Parse(string s);
    public static char ToLower(char c);
    public static char ToLower(char c, System.Globalization.CultureInfo culture);
    public static string ToString(char c);
    public static char ToUpper(char c);
    public static char ToUpper(char c, System.Globalization.CultureInfo culture);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
}

```

Hierarchy

Object → ValueType → Char(IComparable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

CharEnumerator

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

sealed class

This class allows you to access and iterate through individual chars in an array. You can manually retrieve a `CharEnumerator` from a `String` object using the `String.GetEnumerator()` method and then using the `MoveNext()` method to step through the string. However, C# provides built-in support with the convenient `foreach` statement, which uses a `CharEnumerator` transparently.

By convention, a `CharEnumerator` starts just before the first character. When using a `CharEnumerator` manually, you need to call the `MoveNext()` method before you can access the first character.

```
public sealed class CharEnumerator : IEnumerator, ICloneable {  
    // Public Instance Properties  
    public char Current {get; }  
    // Public Instance Methods  
    public object Clone( );  
    // implements ICloneable  
    public bool MoveNext( );  
    // implements IEnumerator  
    public void Reset( );  
    // implements IEnumerator  
}
```

Returned By

```
String.GetEnumerator( )
```

CLSCompliantAttribute

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

sealed class

This attribute indicates that a program element is compliant with the CLS. If you use non-CLS-compliant classes (such as `UInt32`) in a class marked as compliant, the compiler generates a compliance warning.

By default, types without this attribute are not CLS-compliant unless they are contained in a CLS-compliant type or assembly. You can specifically mark non-CLS-compliant members inside a CLS-compliant type using `[CLSCompliant(false)]`.

```
public sealed class CLSCompliantAttribute : Attribute {  
    // Public Constructors  
    public CLSCompliantAttribute(bool isCompliant);  
    // Public Instance Properties  
    public bool IsCompliant {get; }  
}
```

Hierarchy



Valid On

All

Console

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

The **Console** class provides static methods that allow you to create console, or command-line, applications. If you attempt to use these methods in a Windows Forms application, they are ignored. For a console application, data is transmitted through three streams. Input is received from the *standard input stream*, output is written through the *standard output stream*, and error data is written to the *standard error output stream*. These streams are provided through the **In** property, which is a **System.IO.TextReader** object, and through the **Out** and **Error** properties, which are **System.IO.TextWriter** objects. You can use the methods of these objects directly, or you can use the methods provided by the **Console** class. For example, you can use the **Write()** method to write any basic data type to the console window (or use **WriteLine()** to write data with a trailing hard return). You can also use the **ReadLine()** method to cause the console window to wait for input. When the user presses the Enter key, this method returns with a string containing the input characters (except the final hard return).

You can use the **SetIn()**, **SetOut()**, and **SetError()** methods to bind the console to different stream objects, such as **System.IO.FileStream**. To reset the streams to their default objects, use the methods prefixed with **OpenStandard**.

```
public sealed class Console {
// Public Static Properties
    public static TextWriter Error {get; }
    public static TextReader In {get; }
    public static TextWriter Out {get; }
// Public Static Methods
    public static Stream OpenStandardError( );
    public static Stream OpenStandardError(int bufferSize);
    public static Stream OpenStandardInput( );
    public static Stream OpenStandardInput(int bufferSize);
    public static Stream OpenStandardOutput( );
    public static Stream OpenStandardOutput(int bufferSize);
    public static int Read( );
    public static string ReadLine( );
    public static void SetError(System.IO.TextWriter newError);
    public static void SetIn(System.IO.TextReader newIn);
    public static void SetOut(System.IO.TextWriter newOut);
    public static void Write(bool value);
    public static void Write(char value);
    public static void Write(char[ ] buffer);
    public static void Write(char[ ] buffer, int index, int count);
    public static void Write(decimal value);
    public static void Write(double value);
    public static void Write(int value);
```

```

public static void Write(long value);
public static void Write(object value);
public static void Write(float value);
public static void Write(string value);
public static void Write(string format, object arg0);
public static void Write(string format, params object[] arg);
public static void Write(string format, object arg0, object arg1);
public static void Write(string format, object arg0, object arg1, object arg2);
public static void Write(string format, object arg0, object arg1, object arg2,
    object arg3);
public static void Write(uint value);
public static void Write(ulong value);
public static void WriteLine( );
public static void WriteLine(bool value);
public static void WriteLine(char value);
public static void WriteLine(char[] buffer);
public static void WriteLine(char[] buffer, int index, int count);
public static void WriteLine(decimal value);
public static void WriteLine(double value);
public static void WriteLine(int value);
public static void WriteLine(long value);
public static void WriteLine(object value);
public static void WriteLine(float value);
public static void WriteLine(string value);
public static void WriteLine(string format, object arg0);
public static void WriteLine(string format, params object[] arg);
public static void WriteLine(string format, object arg0, object arg1);
public static void WriteLine(string format, object arg0, object arg1, object arg2);
public static void WriteLine(string format, object arg0, object arg1, object arg2,
    object arg3);
public static void WriteLine(uint value);
public static void WriteLine(ulong value);
}

```

[Team LIB]

◀ PREVIOUS NEXT ▶

ContextBoundObject

serializable, marshal by
reference, context
bound

System (mscorlib.dll)

abstract class

An object inheriting from `ContextBoundObject` shares characteristics with an object inheriting from `MarshalByRefObject`. The difference is that a context further subdivides a domain. While instances of `MarshalByRefObject` are passed to other domains by reference and must interact through proxy objects, instances of `ContextBoundObject` are passed by reference to other contexts, even in the same domain. Unlike domains, contexts can provide a rich environment with other services such as synchronization, transactions, just-in-time activation, and security.

For more information, consult the `System.Runtime.Remoting.Contexts` namespace.

```
public abstract class ContextBoundObject : MarshalByRefObject {  
    // Protected Constructors  
    protected ContextBoundObject( );  
}
```

Hierarchy



ContextMarshalException

serializable


System (mscorlib.dll)

class

This exception is thrown when a marshaler fails to move an object across a context boundary. This is usually the case if a nonserializable object is passed as a parameter to a cross-context call, such as an instance of the [CrossAppDomainDelegate](#) .

```
public class ContextMarshalException : SystemException {  
    // Public Constructors  
    public ContextMarshalException( );  
    public ContextMarshalException(string message);  
    public ContextMarshalException(string message,  
        Exception inner);  
    // Protected Constructors  
    protected ContextMarshalException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ContextStaticAttribute

serializable


System (mscorlib.dll)

class

This attribute designates that a static field should not be shared between contexts. Each context accesses a separate copy of this field and is able to set and retrieve values without accidentally overwriting data set by another context. Just as thread-local storage is used to store data in a per-thread fashion, this is used to store static data in a per-context fashion.

```
public class ContextStaticAttribute : Attribute {  
    // Public Constructors  
    public ContextStaticAttribute( );  
}
```

Hierarchy



Valid On

Field

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Convert

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

This class provides static helper methods that convert base data types to other base data types. You can convert objects to base data types, provided they implement the `IConvertible` interface and cast object different types with the `ChangeType()` method.

CLR languages typically allow widening conversions (e.g., `Int16` to `Int32`) through direct assignment. N conversions require the `Convert` class or explicit casting. The `Convert` class does not generate an except you lose numeric precision, but it does throw an overflow exception if the source value is too large for the destination data type.

Note that implicit and explicit conversions can return different results than the `Convert` class. Namely, th truncate significant digits in a narrowing conversion (for example, changing 32.6 to the integer 32), while `Convert` class rounds the number automatically (converting 32.6 to 33). The `Convert` class uses banker's meaning that the fraction 1/2 is rounded down for even numbers (so 4.5 becomes 4) and rounded up for numbers (so 5.5 becomes 6). This helps combat rounding bias.

The `ToString()` methods are functionally equivalent to the `Object.ToString()` method of the corresp base data types. The conversions from strings to numeric or date data are functionally equivalent to the method of the appropriate data type (e.g., `Int32.Parse()`). For string conversions, you can also supp `IFormatProvider` object to specify culture-specific formatting information used to interpret or encode a :

For Boolean conversions, any nonzero number becomes `true` , except for strings, which are compared ag `Boolean.TrueString` and `Boolean.FalseString` fields. When converted to a number, a Boolean `false` l 0, and a Boolean `true` becomes a 1.

Some conversion methods are provided only for symmetry and always throw an `InvalidCastException` include any conversion between date and any data type other than string.

```
public sealed class Convert {
// Public Static Fields
    public static readonly object DBNull;
// Public Static Methods
    public static object ChangeType(object value, Type conversionType);
    public static object ChangeType(object value, TypeCode typeCode);
    public static object ChangeType(object value, TypeCode typeCode, IFormatProvider pro
    public static object ChangeType(object value, Type conversionType, IFormatProvider p
    public static byte[] FromBase64CharArray(char[] inArray, int offset, int length);
    public static byte[] FromBase64String(string s);
    public static TypeCode GetTypeCode(object value);
    public static bool IsDBNull(object value);
    public static int ToBase64CharArray(byte[] inArray, int offsetIn, int length,
        char[] outArray, int offsetOut);
    public static string ToBase64String(byte[] inArray);
```



```
public static string ToBase64String(byte[ ] inArray, int offset, int length);
public static bool ToBoolean(bool value);
public static bool ToBoolean(byte value);
public static bool ToBoolean(char value);
public static bool ToBoolean(DateTime value);
public static bool ToBoolean(decimal value);
public static bool ToBoolean(double value);
public static bool ToBoolean(short value);
public static bool ToBoolean(int value);
public static bool ToBoolean(long value);
public static bool ToBoolean(object value);
public static bool ToBoolean(object value, IFormatProvider provider);
public static bool ToBoolean(sbyte value);
public static bool ToBoolean(float value);
public static bool ToBoolean(string value);
public static bool ToBoolean(string value, IFormatProvider provider);
public static bool ToBoolean(ushort value);
public static bool ToBoolean(uint value);
public static bool ToBoolean(ulong value);
public static byte ToByte(bool value);
public static byte ToByte(byte value);
public static byte ToByte(char value);
public static byte ToByte(DateTime value);
public static byte ToByte(decimal value);
public static byte ToByte(double value);
public static byte ToByte(short value);
public static byte ToByte(int value);
public static byte ToByte(long value);
public static byte ToByte(object value);
public static byte ToByte(object value, IFormatProvider provider);
public static byte ToByte(sbyte value);
public static byte ToByte(float value);
public static byte ToByte(string value);
public static byte ToByte(string value, IFormatProvider provider);
public static byte ToByte(string value, int fromBase);
public static byte ToByte(ushort value);
public static byte ToByte(uint value);
public static byte ToByte(ulong value);
public static char ToChar(bool value);
public static char ToChar(byte value);
public static char ToChar(char value);
public static char ToChar(DateTime value);
public static char ToChar(decimal value);
public static char ToChar(double value);
public static char ToChar(short value);
public static char ToChar(int value);
public static char ToChar(long value);
public static char ToChar(object value);
public static char ToChar(object value, IFormatProvider provider);
```

```
public static char ToChar(sbyte value);
public static char ToChar(float value);
public static char ToChar(string value);
public static char ToChar(string value, IFormatProvider provider);
public static char ToChar(ushort value);
public static char ToChar(uint value);
public static char ToChar(ulong value);
public static DateTime ToDateTime(bool value);
public static DateTime ToDateTime(byte value);
public static DateTime ToDateTime(char value);
public static DateTime ToDateTime(DateTime value);
public static DateTime ToDateTime(decimal value);
public static DateTime ToDateTime(double value);
public static DateTime ToDateTime(short value);
public static DateTime ToDateTime(int value);
public static DateTime ToDateTime(long value);
public static DateTime ToDateTime(object value);
public static DateTime ToDateTime(object value, IFormatProvider provider);
public static DateTime ToDateTime(sbyte value);
public static DateTime ToDateTime(float value);
public static DateTime ToDateTime(string value);
public static DateTime ToDateTime(string value, IFormatProvider provider);
public static DateTime ToDateTime(ushort value);
public static DateTime ToDateTime(uint value);
public static DateTime ToDateTime(ulong value);
public static decimal ToDecimal(bool value);
public static decimal ToDecimal(byte value);
public static decimal ToDecimal(char value);
public static decimal ToDecimal(DateTime value);
public static decimal ToDecimal(decimal value);
public static decimal ToDecimal(double value);
public static decimal ToDecimal(short value);
public static decimal ToDecimal(int value);
public static decimal ToDecimal(long value);
public static decimal ToDecimal(object value);
public static decimal ToDecimal(object value, IFormatProvider provider);
public static decimal ToDecimal(sbyte value);
public static decimal ToDecimal(float value);
public static decimal ToDecimal(string value);
public static decimal ToDecimal(string value, IFormatProvider provider);
public static decimal ToDecimal(ushort value);
public static decimal ToDecimal(uint value);
public static decimal ToDecimal(ulong value);
public static double ToDouble(bool value);
public static double ToDouble(byte value);
public static double ToDouble(char value);
public static double ToDouble(DateTime value);
public static double ToDouble(decimal value);
public static double ToDouble(double value);
```

```
public static double ToDouble(short value);
public static double ToDouble(int value);
public static double ToDouble(long value);
public static double ToDouble(object value);
public static double ToDouble(object value, IFormatProvider provider);
public static double ToDouble(sbyte value);
public static double ToDouble(float value);
public static double ToDouble(string value);
public static double ToDouble(string value, IFormatProvider provider);
public static double ToDouble(ushort value);
public static double ToDouble(uint value);
public static double ToDouble(ulong value);
public static short ToInt16(bool value);
public static short ToInt16(byte value);
public static short ToInt16(char value);
public static short ToInt16(DateTime value);
public static short ToInt16(decimal value);
public static short ToInt16(double value);
public static short ToInt16(short value);
public static short ToInt16(int value);
public static short ToInt16(long value);
public static short ToInt16(object value);
public static short ToInt16(object value, IFormatProvider provider);
public static short ToInt16(sbyte value);
public static short ToInt16(float value);
public static short ToInt16(string value);
public static short ToInt16(string value, IFormatProvider provider);
public static short ToInt16(string value, int fromBase);
public static short ToInt16(ushort value);
public static short ToInt16(uint value);
public static short ToInt16(ulong value);
public static int ToInt32(bool value);
public static int ToInt32(byte value);
public static int ToInt32(char value);
public static int ToInt32(DateTime value);
public static int ToInt32(decimal value);
public static int ToInt32(double value);
public static int ToInt32(short value);
public static int ToInt32(int value);
public static int ToInt32(long value);
public static int ToInt32(object value);
public static int ToInt32(object value, IFormatProvider provider);
public static int ToInt32(sbyte value);
public static int ToInt32(float value);
public static int ToInt32(string value);
public static int ToInt32(string value, IFormatProvider provider);
public static int ToInt32(string value, int fromBase);
public static int ToInt32(ushort value);
public static int ToInt32(uint value);
```

```
public static int ToInt32(ulong value);
public static long ToInt64(bool value);
public static long ToInt64(byte value);
public static long ToInt64(char value);
public static long ToInt64(DateTime value);
public static long ToInt64(decimal value);
public static long ToInt64(double value);
public static long ToInt64(short value);
public static long ToInt64(int value);
public static long ToInt64(long value);
public static long ToInt64(object value);
public static long ToInt64(object value, IFormatProvider provider);
public static long ToInt64(sbyte value);
public static long ToInt64(float value);
public static long ToInt64(string value);
public static long ToInt64(string value, IFormatProvider provider);
public static long ToInt64(string value, int fromBase);
public static long ToInt64(ushort value);
public static long ToInt64(uint value);
public static long ToInt64(ulong value);
public static sbyte ToSByte(bool value);
public static sbyte ToSByte(byte value);
public static sbyte ToSByte(char value);
public static sbyte ToSByte(DateTime value);
public static sbyte ToSByte(decimal value);
public static sbyte ToSByte(double value);
public static sbyte ToSByte(short value);
public static sbyte ToSByte(int value);
public static sbyte ToSByte(long value);
public static sbyte ToSByte(object value);
public static sbyte ToSByte(object value, IFormatProvider provider);
public static sbyte ToSByte(sbyte value);
public static sbyte ToSByte(float value);
public static sbyte ToSByte(string value);
public static sbyte ToSByte(string value, IFormatProvider provider);
public static sbyte ToSByte(string value, int fromBase);
public static sbyte ToSByte(ushort value);
public static sbyte ToSByte(uint value);
public static sbyte ToSByte(ulong value);
public static float ToSingle(bool value);
public static float ToSingle(byte value);
public static float ToSingle(char value);
public static float ToSingle(DateTime value);
public static float ToSingle(decimal value);
public static float ToSingle(double value);
public static float ToSingle(short value);
public static float ToSingle(int value);
public static float ToSingle(long value);
public static float ToSingle(object value);
```

```

public static float ToSingle(object value, IFormatProvider provider);
public static float ToSingle(sbyte value);
public static float ToSingle(float value);
public static float ToSingle(string value);
public static float ToSingle(string value, IFormatProvider provider);
public static float ToSingle(ushort value);
public static float ToSingle(uint value);
public static float ToSingle(ulong value);
public static string ToString(bool value);
public static string ToString(bool value, IFormatProvider provider);
public static string ToString(byte value);
public static string ToString(byte value, IFormatProvider provider);
public static string ToString(byte value, int toBase);
public static string ToString(char value);
public static string ToString(char value, IFormatProvider provider);
public static string ToString(DateTime value);
public static string ToString(DateTime value, IFormatProvider provider);
public static string ToString(decimal value);
public static string ToString(decimal value, IFormatProvider provider);
public static string ToString(double value);
public static string ToString(double value, IFormatProvider provider);
public static string ToString(short value);
public static string ToString(short value, IFormatProvider provider);
public static string ToString(short value, int toBase);
public static string ToString(int value);
public static string ToString(int value, IFormatProvider provider);
public static string ToString(int value, int toBase);
public static string ToString(long value);
public static string ToString(long value, IFormatProvider provider);
public static string ToString(long value, int toBase);
public static string ToString(object value);
public static string ToString(object value, IFormatProvider provider);
public static string ToString(sbyte value);
public static string ToString(sbyte value, IFormatProvider provider);
public static string ToString(float value);
public static string ToString(float value, IFormatProvider provider);
public static string ToString(string value);
public static string ToString(string value, IFormatProvider provider);
public static string ToString(ushort value);
public static string ToString(ushort value, IFormatProvider provider);
public static string ToString(uint value);
public static string ToString(uint value, IFormatProvider provider);
public static string ToString(ulong value);
public static string ToString(ulong value, IFormatProvider provider);
public static ushort ToUInt16(bool value);
public static ushort ToUInt16(byte value);
public static ushort ToUInt16(char value);
public static ushort ToUInt16(DateTime value);
public static ushort ToUInt16(decimal value);

```

```
public static ushort ToUInt16(double value);
public static ushort ToUInt16(short value);
public static ushort ToUInt16(int value);
public static ushort ToUInt16(long value);
public static ushort ToUInt16(object value);
public static ushort ToUInt16(object value, IFormatProvider provider);
public static ushort ToUInt16(sbyte value);
public static ushort ToUInt16(float value);
public static ushort ToUInt16(string value);
public static ushort ToUInt16(string value, IFormatProvider provider);
public static ushort ToUInt16(string value, int fromBase);
public static ushort ToUInt16(ushort value);
public static ushort ToUInt16(uint value);
public static ushort ToUInt16(ulong value);
public static uint ToUInt32(bool value);
public static uint ToUInt32(byte value);
public static uint ToUInt32(char value);
public static uint ToUInt32(DateTime value);
public static uint ToUInt32(decimal value);
public static uint ToUInt32(double value);
public static uint ToUInt32(short value);
public static uint ToUInt32(int value);
public static uint ToUInt32(long value);
public static uint ToUInt32(object value);
public static uint ToUInt32(object value, IFormatProvider provider);
public static uint ToUInt32(sbyte value);
public static uint ToUInt32(float value);
public static uint ToUInt32(string value);
public static uint ToUInt32(string value, IFormatProvider provider);
public static uint ToUInt32(string value, int fromBase);
public static uint ToUInt32(ushort value);
public static uint ToUInt32(uint value);
public static uint ToUInt32(ulong value);
public static ulong ToUInt64(bool value);
public static ulong ToUInt64(byte value);
public static ulong ToUInt64(char value);
public static ulong ToUInt64(DateTime value);
public static ulong ToUInt64(decimal value);
public static ulong ToUInt64(double value);
public static ulong ToUInt64(short value);
public static ulong ToUInt64(int value);
public static ulong ToUInt64(long value);
public static ulong ToUInt64(object value);
public static ulong ToUInt64(object value, IFormatProvider provider);
public static ulong ToUInt64(sbyte value);
public static ulong ToUInt64(float value);
public static ulong ToUInt64(string value);
public static ulong ToUInt64(string value, IFormatProvider provider);
public static ulong ToUInt64(string value, int fromBase);
```

```
public static ulong ToUInt64(ushort value);  
public static ulong ToUInt64(uint value);  
public static ulong ToUInt64(ulong value);  
}
```

[Team LiB]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

CrossAppDomainDelegate serializable

System (mscorlib.dll) *delegate*

This delegate invokes a method in a different application domain using the `AppDomain.DoCallBack()` method. You can then invoke a delegate instance within another `AppDomain`, which provides you with the ability to check on an `AppDomain`'s status or information.

```
public delegate void CrossAppDomainDelegate( );
```

Passed To

```
AppDomain.DoCallBack( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DateTime CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This simple value type represents a moment in time from 12:00:00 A.M., 1/1/0001 C.E. (Common Era), to 11:59:59 P.M., 12/31/9999 C.E., which is measured to the nearest *tick*, or 100-nanosecond interval. You use this type in greater-than/less-than comparisons, sorting, and in calculations using other `DateTime` or `TimeSpan` instances. You can also use convenient `Add. . .` methods, such as `AddSeconds()`, with a positive or negative value.

To extract part of a date, use properties such as `Day` and `Minute`. All properties except `Ticks` represent a single component of a compound date, not the whole date. You can convert a string into a `DateTime` using the static `Parse()` or `ParseExact()` methods, which require that the date match the pattern specified by the supplied `format` string.

The `DateTime` class also provides valuable static functions that can determine the number of days in a month (`DaysInMonth()`), evaluate whether a year is a leap year (`IsLeapYear()`), and retrieve the date stored in a file (`FromFileTime()`). You can also get the current date from the static property `Today` (or `UtcNow` for the coordinated universal time).

```
public struct DateTime : IComparable, IFormattable, IConvertible {
// Public Constructors
    public DateTime(int year, int month, int day);
    public DateTime(int year, int month, int day, System.Globalization.Calendar calendar);
    public DateTime(int year, int month, int day, int hour, int minute, int second);
    public DateTime(int year, int month, int day, int hour, int minute, int second,
        System.Globalization.Calendar calendar);
    public DateTime(int year, int month, int day, int hour, int minute, int second,
        int millisecond);
    public DateTime(int year, int month, int day, int hour, int minute, int second,
        int millisecond, System.Globalization.Calendar calendar);
    public DateTime(long ticks);
// Public Static Fields
    public static readonly DateTime MaxValue;
// =12/31/9999 11:59:59 PM
    public static readonly DateTime MinValue;
// =1/1/0001 12:00:00 AM
// Public Static Properties
    public static DateTime Now {get; }
    public static DateTime Today {get; }
    public static DateTime UtcNow {get; }
// Public Instance Properties
    public DateTime Date {get; }
    public int Day {get; }
    public DayOfWeek DayOfWeek {get; }
```

```

    public int DayOfYear {get; }
    public int Hour {get; }
    public int Millisecond {get; }
    public int Minute {get; }
    public int Month {get; }
    public int Second {get; }
    public long Ticks {get; }
    public TimeSpan TimeOfDay {get; }
    public int Year {get; }
// Public Static Methods
    public static int Compare(DateTime t1, DateTime t2);
    public static int DaysInMonth(int year, int month);
    public static bool Equals(DateTime t1, DateTime t2);
    public static DateTime FromFileTime(long fileTime);
    public static DateTime FromFileTimeUtc(long fileTime);
    public static DateTime FromODate(double d);
    public static bool IsLeapYear(int year);
    public static DateTime Parse(string s);
    public static DateTime Parse(string s, IFormatProvider provider);
    public static DateTime Parse(string s, IFormatProvider provider,
        System.Globalization.DateTimeStyles styles);
    public static DateTime ParseExact(string s, string[] formats, IFormatProvider provi
        System.Globalization.DateTimeStyles style);
    public static DateTime ParseExact(string s, string format, IFormatProvider provider)
    public static DateTime ParseExact(string s, string format, IFormatProvider provider,
        System.Globalization.DateTimeStyles style);
    public static DateTime operator -(DateTime d, TimeSpan t);
    public static TimeSpan operator -(DateTime d1, DateTime d2);
    public static DateTime operator +(DateTime d, TimeSpan t);
    public static bool operator !=(DateTime d1, DateTime d2);
    public static bool operator <(DateTime t1, DateTime t2);
    public static bool operator <=(DateTime t1, DateTime t2);
    public static bool operator ==(DateTime d1, DateTime d2);
    public static bool operator >(DateTime t1, DateTime t2);
    public static bool operator >=(DateTime t1, DateTime t2);
// Public Instance Methods
    public DateTime Add(TimeSpan value);
    public DateTime AddDays(double value);
    public DateTime AddHours(double value);
    public DateTime AddMilliseconds(double value);
    public DateTime AddMinutes(double value);
    public DateTime AddMonths(int months);
    public DateTime AddSeconds(double value);
    public DateTime AddTicks(long value);
    public DateTime AddYears(int value);
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object value);
// overrides ValueType

```

```
public string[ ] GetDateTimeFormats( );  
public string[ ] GetDateTimeFormats(char format);  
public string[ ] GetDateTimeFormats(char format, IFormatProvider provider);  
public string[ ] GetDateTimeFormats(IFormatProvider provider);  
public override int GetHashCode( );  
// overrides ValueType  
public TypeCode GetTypeCode( );  
// implements IConvertible  
public DateTime Subtract(TimeSpan value);  
public TimeSpan Subtract(DateTime value);  
public long ToFileTime( );  
public long ToFileTimeUtc( );  
public DateTime ToLocalTime( );  
public string ToLongDateString( );  
public string ToLongTimeString( );  
public double ToOADate( );  
public string ToShortDateString( );  
public string ToShortTimeString( );  
public override string ToString( );  
// overrides ValueType  
public string ToString(IFormatProvider provider);  
// implements IConvertible  
public string ToString(string format);  
public string ToString(string format, IFormatProvider provider)  
// implements IFormattable  
public DateTime ToUniversalTime( );  
}
```

Hierarchy

Object → ValueType → DateTime(Comparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[Team LiB]

DayOfWeek CF 1.0, serializable

System (mscorlib.dll) *enum*

This enumeration is used by the `DateTime.DayOfWeek` property.

```
public enum DayOfWeek {  
    Sunday = 0 ,  
    Monday = 1 ,  
    Tuesday = 2 ,  
    Wednesday = 3 ,  
    Thursday = 4 ,  
    Friday = 5 ,  
    Saturday = 6  
}
```

Hierarchy



Returned By

```
DateTime.DayOfWeek, System.Globalization.Calendar.GetDayOfWeek( ),  
System.Globalization.DateTimeFormatInfo.FirstDayOfWeek
```

Passed To

```
System.Globalization.Calendar.GetWeekOfYear( ),  
System.Globalization.DateTimeFormatInfo.{FirstDayOfWeek, GetAbbreviatedDayName( ),  
GetDayName( )}
```

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

DBNull

CF 1.0, serializable

System (mscorlib.dll)

sealed class

DBNull indicates the absence of information, typically in a database application in which a field does not contain any data. The types in the **System.Data.SqlTypes** namespace have built-in support for **DBNull**.

Note that **Value** is not the same as the **null** keyword in C#. The **null** keyword can be used to release an object by clearing the reference. **System.DbNull.Value**, on the other hand, is a reference to a special value (a member of the singleton class **DBNull**) that is used to indicate missing information.

This class has some other uses, namely in COM Interop, in which it represents a **VT_EMPTY** variant (as opposed to a **VT_NULL** variant, which is a null reference).

```
public sealed class DBNull : System.Runtime.Serialization.ISerializable, IConvertible {  
    // Public Static Fields  
    public static readonly DBNull Value;  
    // Public Instance Methods  
    public void GetObjectData(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context)  
    // implements ISerializable  
    public TypeCode GetTypeCode( );  
    // implements IConvertible  
    public override string ToString( );  
    // overrides object  
    public string ToString(IFormatProvider provider);  
    // implements IConvertible  
}
```

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

Decimal

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This simple value type is commonly used for financial calculations, which can preserve a significant number of fractional digits with no round-off error. Decimals are stored as 12-byte signed integers scaled by a variable power of 10. This means that a decimal data type can effectively hold 28 significant digits without losing any information. With a scale of 0 (no decimal places), the largest possible value is approximately 7.92×10^{28} . This type is available in C# through the `decimal` alias.

```
public struct Decimal : IFormattable, IComparable, IConvertible {
// Public Constructors
    public Decimal(double value);
    public Decimal(int value);
    public Decimal(int[] bits);
    public Decimal(int lo, int mid, int hi, bool isNegative, byte scale);
    public Decimal(long value);
    public Decimal(float value);
    public Decimal(uint value);
    public Decimal(ulong value);
// Public Static Fields
    public static readonly decimal MaxValue;
// =79228162514264337593543950335
    public static readonly decimal MinusOne;
// =-1
    public static readonly decimal MinValue;
// =-79228162514264337593543950335
    public static readonly decimal One;
// =1
    public static readonly decimal Zero;
// =0
// Public Static Methods
    public static decimal Add(decimal d1, decimal d2);
    public static int Compare(decimal d1, decimal d2);
    public static decimal Divide(decimal d1, decimal d2);
    public static bool Equals(decimal d1, decimal d2);
    public static decimal Floor(decimal d);
    public static decimal FromOACurrency(long cy);
    public static int[] GetBits(decimal d);
    public static decimal Multiply(decimal d1, decimal d2);
    public static decimal Negate(decimal d);
    public static decimal Parse(string s);
    public static decimal Parse(string s, IFormatProvider provider);
    public static decimal Parse(string s, System.Globalization.NumberStyles style);
```

```

public static decimal Parse(string s, System.Globalization.NumberStyles style,
    IFormatProvider provider);
public static decimal Remainder(decimal d1, decimal d2);
public static decimal Round(decimal d, int decimals);
public static decimal Subtract(decimal d1, decimal d2);
public static byte ToByte(decimal value);
public static double ToDouble(decimal d);
public static short ToInt16(decimal value);
public static int ToInt32(decimal d);
public static long ToInt64(decimal d);
public static long ToOACurrency(decimal value);
public static sbyte TosByte(decimal value);
public static float ToSingle(decimal d);
public static ushort ToUInt16(decimal value);
public static uint ToUInt32(decimal d);
public static ulong ToUInt64(decimal d);
public static decimal Truncate(decimal d);
public static decimal operator %(decimal d1, decimal d2);
public static decimal operator *(decimal d1, decimal d2);
public static decimal operator /(decimal d1, decimal d2);
public static decimal operator --(decimal d);
public static decimal operator -(decimal d);
public static decimal operator -(decimal d1, decimal d2);
public static decimal operator +(decimal d);
public static decimal operator +(decimal d1, decimal d2);
public static decimal operator ++(decimal d);
public static bool operator !=(decimal d1, decimal d2);
public static bool operator <(decimal d1, decimal d2);
public static bool operator <=(decimal d1, decimal d2);
public static bool operator ==(decimal d1, decimal d2);
public static bool operator >(decimal d1, decimal d2);
public static bool operator >=(decimal d1, decimal d2);
public static explicit operator byte(decimal value);
public static explicit operator char(decimal value);
public static explicit operator decimal(double value);
public static explicit operator decimal(float value);
public static explicit operator double(decimal value);
public static explicit operator short(decimal value);
public static explicit operator int(decimal value);
public static explicit operator long(decimal value);
public static explicit operator sbyte(decimal value);
public static explicit operator float(decimal value);
public static explicit operator ushort(decimal value);
public static explicit operator uint(decimal value);
public static explicit operator ulong(decimal value);
public static implicit operator decimal(byte value);
public static implicit operator decimal(char value);
public static implicit operator decimal(short value);
public static implicit operator decimal(int value);

```

```

    public static implicit operator decimal(long value);
    public static implicit operator decimal(sbyte value);
    public static implicit operator decimal(ushort value);
    public static implicit operator decimal(uint value);
    public static implicit operator decimal(ulong value);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object value);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}

```

Hierarchy

Object → ValueType → Decimal(IFormattable, IComparable, IConvertible)

Returned By

```

Convert.ToDecimal( ), IConvertible.ToDecimal( ), System.IO.BinaryReader.ReadDecimal(
), System.Runtime.InteropServices.CurrencyWrapper.WrappedObject,
System.Runtime.Serialization.FormatterConverter.ToDecimal( ),
System.Runtime.Serialization.IFormatterConverter.ToDecimal( ),
System.Runtime.Serialization.SerializationInfo.GetDecimal( ),
System.Xml.XmlConvert.ToDecimal( )

```

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Delegate

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

abstract class

A delegate is used to provide a decoupling of caller from callee; that is, a delegate points to a given method (instance or static) in a class, and callers can call through the delegate without having to know the target of the call. In many respects, the delegate is conceptually similar to the C/C++ *function pointer*, with a number of important advantages. A delegate is strongly typed, meaning that only methods that match the delegate's declared signature are acceptable when constructing the delegate instance, and the compiler enforces the delegate's declared signature when called. A delegate can distinguish between a static and an instance method. This avoids the C++ application associated with pointers to member functions, which require a *literal* pointer to the object upon which to invoke the method.

Delegates are usually constructed by the language compiler, varying in syntax from language to language. In C#, the construct `public delegate void CallbackDelegate(int param1, string param2);` declares a new type that derives from the `Delegate` type (its immediate superclass is actually `MulticastDelegate`). This new `CallbackDelegate` type is also declared with a constructor (to take the method to call when the delegate is invoked) and an `Invoke` method (to do the actual call), along with asynchronous versions of `Invoke` (the `BeginInvoke` and `EndInvoke` methods).

In many cases, you will want to use delegates as an *invocation chain*, where a single call to the delegate should result in a series of calls against a collection of delegate targets. (This is most easily seen in .NET's publish-subscribe event-handling idiom-C#'s `event` keyword.) To achieve this, `Delegate` contains static methods allowing delegates to combine into a single delegate instance that calls into multiple delegate targets. The `Combine()` method takes two existing delegate instances (with identical signatures) and returns a single delegate instance that calls both targets when invoked. (There is another form of `Combine()` that takes an array of delegates instead of just a pair.) `Remove()` does the opposite of `Combine()`, removing a delegate from the multicast call chain. (See the `MulticastDelegate` entry for more information on multicast delegates.)

Delegates can also be invoked using the `DynamicInvoke()` method, without knowing the actual concrete generated `Delegate` subtype. This method expects an array of object references, whose type should match those of the expected parameters to the delegate. If any of the parameters to `DynamicInvoke()` do not match those expected by the target method, an exception is thrown. Delegates can also be constructed in the same generic fashion using one of the overloaded forms of `CreateDelegate()`.

Delegates can be invoked either synchronously or asynchronously. To invoke a delegate synchronously (that is, block until the call(s) return), simply use the delegate as if it is a method, as shown in Section 4.1. The call to a delegate is executed completely before execution resumes in the calling method. Should you wish the call to the delegate to occur in parallel with the calling method, use the `BeginInvoke` method to start execution and the `EndInvoke` method to wait for the asynchronous delegate call's completion (if it hasn't finished by the time the `EndInvoke` call is made). If any of the delegate's parameters are declared as `ref` or `out` parameters, these parameters will be available on the parameter list to `EndInvoke`.

```
public abstract class Delegate : ICloneable, System.Runtime.Serialization.ISerializable
// Protected Constructors
    protected Delegate(object target, string method);
```

```

    protected Delegate(Type target, string method);
// Public Instance Properties
    public MethodInfo Method{get; }
    public object Target{get; }
// Public Static Methods
    public static Delegate Combine(Delegate[] delegates);
    public static Delegate Combine(Delegate a, Delegate b);
    public static Delegate CreateDelegate(Type type, System.Reflection.MethodInfo method);
    public static Delegate CreateDelegate(Type type, object target, string method);
    public static Delegate CreateDelegate(Type type, object target, string method,
        bool ignoreCase);
    public static Delegate CreateDelegate(Type type, Type target, string method);
    public static Delegate Remove(Delegate source, Delegate value);
    public static Delegate RemoveAll(Delegate source, Delegate value);
    public static bool operator !=(Delegate d1, Delegate d2);
    public static bool operator =(Delegate d1, Delegate d2);
// Public Instance Methods
    public virtual object Clone( );
// implements ICloneable
    public object DynamicInvoke(object[] args);
    public override bool Equals(object obj);
// overrides object
    public override int GetHashCode( );
// overrides object
    public virtual Delegate[] GetInvocationList( );
    public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
// Protected Instance Methods
    protected virtual Delegate CombineImpl(Delegate d);
    protected virtual object DynamicInvokeImpl(object[] args);
    protected virtual MethodInfo GetMethodImpl( );
    protected virtual Delegate RemoveImpl(Delegate d);
}

```

Subclasses

MulticastDelegate

Returned By

MulticastDelegate.{CombineImpl(), GetInvocationList(), RemoveImpl()}

Passed To

Microsoft.Win32.SystemEvents.InvokeOnEventsThread(), MulticastDelegate.{CombineImpl(), RemoveImpl()}, System.Reflection.EventInfo.{AddEventHandler(), RemoveEventHandler()}, System.Runtime.InteropServices.Expando.IExpando.AddMethod()

[Team LiB]

◀ PREVIOUS

NEXT ▶

DivideByZeroException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception is thrown when a math operation attempts to divide by zero.

```
public class DivideByZeroException : ArithmeticException {  
    // Public Constructors  
    public DivideByZeroException( );  
    public DivideByZeroException(string message);  
    public DivideByZeroException(string message, Exception innerException);  
    // Protected Constructors  
    protected DivideByZeroException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



DllNotFoundException

CF 1.0, serializable

System (mscorlib.dll) *class*

This exception indicates that the file specified in a DLL import could not be found (see `System.Runtime.InteropServices.DllImportAttribute`). This exception is thrown only when you attempt to link against a method declared using the P/Invoke features of .NET. Any managed DLL (such as those produced by C# or Visual Basic .NET) that cannot be found instead generates `TypeLoadException`s when you attempt to resolve types out of an assembly that cannot be found.

```
public class DllNotFoundException : TypeLoadException {
// Public Constructors
    public DllNotFoundException( );
    public DllNotFoundException(string message);
    public DllNotFoundException(string message, Exception inner);
// Protected Constructors
    protected DllNotFoundException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) → SystemException
→ TypeLoadException → DllNotFoundException

Double

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This represents a 64-bit double-precision floating number as a value type. The value of a double can range, approximately from -1.8×10^{308} to 1.8×10^{308} and can be set to one of the following fields: `PositiveInfinity`, `NegativeInfinity`, and `NaN` (not a number). This type is aliased as `double` in C#.

```
public struct Double : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const double Epsilon;
// =4.94065645841247E-324
    public const double MaxValue;
// =1.79769313486232E+308
    public const double MinValue;
// =-1.79769313486232E+308
    public const double NaN;
// =NaN
    public const double NegativeInfinity;
// =-Infinity
    public const double PositiveInfinity;
// =Infinity
// Public Static Methods
    public static bool IsInfinity(double d);
    public static bool IsNaN(double d);
    public static bool IsNegativeInfinity(double d);
    public static bool IsPositiveInfinity(double d);
    public static double Parse(string s);
    public static double Parse(string s, IFormatProvider provider);
    public static double Parse(string s, System.Globalization.NumberStyles style);
    public static double Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
    public static bool TryParse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider, out double result);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
```

```
// overrides ValueType
public string ToString(IFormatProvider provider);
// implements IConvertible
public string ToString(string format);
public string ToString(string format, IFormatProvider provider);
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Double(IComparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

DuplicateWaitObjectException


ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This exception is thrown when an object shows up more than once in the array passed to `System.Threading.WaitHandle.WaitAll()` or `System.Threading.WaitHandle.WaitAny()`.

```
public class DuplicateWaitObjectException : ArgumentException {  
    // Public Constructors  
    public DuplicateWaitObjectException( );  
    public DuplicateWaitObjectException(string parameterName);  
    public DuplicateWaitObjectException(string parameterName, string message);  
    // Protected Constructors  
    protected DuplicateWaitObjectException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



[Team LiB]

◀ PREVIOUS NEXT ▶

CF 1.0, ECMA
1.0,
serializable

EntryPointNotFoundException


System (mscorlib.dll)

class

This exception indicates that an entry point could not be found when .NET loaded an assembly flagged for execution; that is, an `AppDomain` was instructed to execute an assembly, but no method in that assembly marked with the `.entrypoint` metadata flag.

```
public class EntryPointNotFoundException : TypeLoadException {  
    // Public Constructors  
    public EntryPointNotFoundException( );  
    public EntryPointNotFoundException(string message);  
    public EntryPointNotFoundException(string message, Exception inner);  
    // Protected Constructors  
    protected EntryPointNotFoundException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



[Team LiB]

◀ PREVIOUS NEXT ▶

Enum

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

abstract class

This is the base class for all enumerations. In C#, you can use the `enum` keyword to create an enumeration type consisting of named constants and their values. By default, the underlying type used for enumeration elements is `Int32`, but you can use any integer data type.

```
public abstract class Enum : ValueType : IComparable, IFormattable, IConvertible {
// Protected Constructors
    protected Enum( );
// Public Static Methods
    public static string Format(Type enumType, object value, string format);
    public static string GetName(Type enumType, object value);
    public static string[] GetNames(Type enumType);
    public static Type GetUnderlyingType(Type enumType);
    public static Array GetValues(Type enumType);
    public static bool IsDefined(Type enumType, object value);
    public static object Parse(Type enumType, string value);
    public static object Parse(Type enumType, string value, bool ignoreCase);
    public static object ToObject(Type enumType, byte value);
    public static object ToObject(Type enumType, short value);
    public static object ToObject(Type enumType, int value);
    public static object ToObject(Type enumType, long value);
    public static object ToObject(Type enumType, object value);
    public static object ToObject(Type enumType, sbyte value);
    public static object ToObject(Type enumType, ushort value);
    public static object ToObject(Type enumType, uint value);
    public static object ToObject(Type enumType, ulong value);
// Public Instance Methods
    public int CompareTo(object target);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
```

```
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Enum(Comparable, IFormattable, IConvertible)

Subclasses

Multiple types

[\[Team LiB \]](#)

Environment

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

This class represents an application's operating environment, which includes details about the operating system, the current user, and other environment variables. This information is provided through static properties and some helper methods.

You can retrieve command-line arguments as a string from `CommandLine` or as an array of strings using `GetCommandLineArgs()`. Use the `GetLogicalDrives()` method to get an array of strings containing drive names (for example, `C:\`), and use the `GetFolderPath()` method to get the physical location of a special system folder. You can also retrieve environment variables by key name using the `GetEnvironmentVariable()` method and automatically replace environment variables in a string with the `ExpandEnvironmentVariables()` method, as long as they are delimited with the percent sign (%). For example, on a system with the environment variable `MAC_ADDR` set to `123456789012`, the string `MAC_ADDR=%MAC_ADDR%` would be converted to `MAC_ADDR=123456789012`.

```
public sealed class Environment {
// Public Static Properties
    public static string CommandLine {get; }
    public static string CurrentDirectory {set; get; }
    public static int ExitCode {set; get; }
    public static bool HasShutdownStarted {get; }
    public static string MachineName {get; }
    public static string NewLine {get; }
    public static OperatingSystem OSVersion {get; }
    public static string StackTrace {get; }
    public static string SystemDirectory {get; }
    public static int TickCount {get; }
    public static string UserDomainName {get; }
    public static bool UserInteractive {get; }
    public static string UserName {get; }
    public static Version Version {get; }
    public static long WorkingSet {get; }
// Public Static Methods
    public static void Exit(int exitCode);
    public static string ExpandEnvironmentVariables(string name);
    public static string[] GetCommandLineArgs( );
    public static string GetEnvironmentVariable(string variable);
    public static IDictionary GetEnvironmentVariables( );
    public static string GetFolderPath(SpecialFolder folder);
    public static string[] GetLogicalDrives( );
}
```


Environment.SpecialFolder serializable

System (mscorlib.dll) *enum*

This enumeration is used by the `Environment.GetFolderPath()` method to allow you to retrieve the physical path of commonly used system (or "special") folders, including everything from the Internet cache to the Start menu.

```
public enum Environment.SpecialFolder {
    Desktop = 0,
    Programs = 2,
    Personal = 5,
    Favorites = 6,
    Startup = 7,
    Recent = 8,
    SendTo = 9,
    StartMenu = 11,
    MyMusic = 13,
    DesktopDirectory = 16,
    MyComputer = 17,
    Templates = 21,
    ApplicationData = 26,
    LocalApplicationData = 28,
    InternetCache = 32,
    Cookies = 33,
    History = 34,
    CommonApplicationData = 35,
    System = 37,
    ProgramFiles = 38,
    MyPictures = 39,
    CommonProgramFiles = 43
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

EventArgs CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *class*

See the [EventHandler](#) entry for details regarding the [EventArgs/EventHandler](#) idiom for delegates in .NET. If .NET developers wish to follow this idiom, they should create new subtypes of [EventArgs](#) for each new collection of data to be sent to interested parties; otherwise, they should pass [Empty](#), indicating that no event data is to be passed as part of this event notification.

```
public class EventArgs {  
    // Public Constructors  
    public EventArgs( );  
    // Public Static Fields  
    public static readonly EventArgs Empty;  
    // =System.EventArgs  
}
```

Subclasses

Multiple types

Passed To

```
EventHandler.{BeginInvoke( ), Invoke( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

EventHandler CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

delegate

Shortly after Beta 1 of .NET was released, Microsoft .NET developers realized that prolific use of delegates could easily lead to type-bloat; since each declared delegate created a new type in the system, a large number of delegates would lead to a huge number of types to load, verify, and initialize. In Beta 2, Microsoft introduced an idiom that, it's hoped, will keep type-bloat down to reasonable levels in .NET.

Microsoft defines two types, **EventHandler** (a delegate type) and **EventArgs**, a glorified C construct. **EventHandler** is declared to expect two parameters: an object reference indicating the **sender** of the event, and an **event data** parameter (the **EventArgs** or some derived-type instance).

This delegate represents the base type for .NET event handlers. (In Beta 2 and later, all .NET Framework Class Library types with declared events use this same idiom, so as to remain consistent.) Its arguments include a **sender** parameter, which refers to the object that issued the event, and an **e** parameter, which contains additional event data. Events that do not require additional information use the **EventHandler** delegate directly.

Events that need to send additional information derive their own custom delegate from this type. Custom event delegates look similar, except that they replace the **EventArgs** parameter with a custom object derived from **EventArgs**. This object contains additional properties or methods that are specific to the event.

```
public delegate void EventHandler(object sender,  
    EventArgs e);
```

Associated Events

Multiple types

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Exception CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

class

This is the base class for all .NET exceptions. .NET Framework exceptions are generally derived from `SystemException`, and user-defined exceptions are generally derived from `ApplicationException`.

In some cases, one exception may throw another; this is often the case when using layered architectures. For example, a persistence layer may throw a persistence-related exception (`DatabaseNotFoundException`), whose semantics are undefined at a higher level (such as the UI layer). In this case, a middle layer may throw a new exception-derived type (such as `PersistenceException`), but doesn't wish to lose the original source of the exception—instead, it wraps the original exception by setting it to be the `InnerException`. In this way, a layer can communicate a lower-level exception to higher layers without losing information or violating encapsulation.

The `StackTrace` property is a string containing the stacktrace. This permits determination of the call sequence leading up to the line that threw the exception. `HelpLink` contains a link to a help file with information about the exception. `Message` contains a text message that describes the exception.

```
public class Exception : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public Exception( );
    public Exception(string message);
    public Exception(string message, Exception innerException);
// Protected Constructors
    protected Exception(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public virtual string HelpLink{set; get; }
    public Exception InnerException{get; }
    public virtual string Message{get; }
    public virtual string Source{set; get; }
    public virtual string StackTrace{get; }
    public MethodBase TargetSite{get; }
// Protected Instance Properties
    protected int HResult{set; get; }
// Public Instance Methods
    public virtual Exception GetBaseException( );
    public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
    public override string ToString( );
// overrides object
}
```


Subclasses

`ApplicationException` , `SystemException` , `System.IO.IsolatedStorage.IsolatedStorageException`

Returned By

`System.IO.ErrorEventArgs.GetException()` ,
`System.Reflection.ReflectionTypeLoadException.LoaderExceptions` ,
`System.Threading.ThreadExceptionEventArgs.Exception`

Passed To

Multiple types

[Team LiB]

[◀ PREVIOUS](#)

[NEXT ▶](#)

ExecutionEngineException

ECMA 1.0,
serializable


System (mscorlib.dll)

sealed class

This exception indicates that an error has occurred deep within the innards of the .NET CLR.

```
public sealed class ExecutionEngineException : SystemException {  
    // Public Constructors  
    public ExecutionEngineException( );  
    public ExecutionEngineException(string message);  
    public ExecutionEngineException(string message, Exception innerException);  
}
```

Hierarchy




FieldAccessException ECMA 1.0, serializable

System (mscorlib.dll) *class*

This exception is thrown when you try to access a protected or private field that you would not normally have access to. Most compilers will not let you compile code that does this directly. However, late-bound code can sneak by the compiler and throw this exception at runtime. For example, if you lack sufficient privileges to modify a field using `System.Reflection.FieldInfo.SetValue()`, this exception is thrown.

```
public class FieldAccessException : MemberAccessException {  
    // Public Constructors  
    public FieldAccessException( );  
    public FieldAccessException(string message);  
    public FieldAccessException(string message, Exception inner);  
    // Protected Constructors  
    protected FieldAccessException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



FlagsAttribute CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *class*

This attribute indicates that an enumeration should be treated as a set of on/off flags (i.e., a bit field). Unlike enumerated constants, bit fields can be combined with a bitwise **OR** operation.

```
public class FlagsAttribute : Attribute {  
    // Public Constructors  
    public FlagsAttribute( );  
}
```

Hierarchy



Valid On

Enum

FormatException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception signals that an error occurred during the handling of a format string. Format strings are used by methods such as `Console.WriteLine()` to replace a format specification with one or more parameters. This exception may be triggered by supplying too few arguments to replace all the format strings (for example, supplying only two arguments to `Console.WriteLine()` when your format string is "{0} {1} {2}"). See [Appendix B](#) for more information on format strings.

```
public class FormatException : SystemException {  
    // Public Constructors  
    public FormatException( );  
    public FormatException(string message);  
    public FormatException(string message, Exception innerException);  
    // Protected Constructors  
    protected FormatException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

UriFormatException, System.Net.CookieException,
System.Reflection.CustomAttributeFormatException

GC

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

This class allows you to control garbage collection programmatically. Garbage collection is the .NET service that periodically scans for unreferenced objects and reclaims the memory they occupy.

The garbage-collection service distinguishes between older and more recently allocated memory using *generations*. The most recently allocated memory is considered generation zero, and the oldest memory is in generation **MaxGeneration**. Because new allocations are likely to be freed before long-standing memory allocations, the garbage collector improves its performance by concentrating on lower generations of memory. You can find out the generation of an object using the **GetGeneration()** method. You can also get the number of memory bytes that are currently allocated using the **GetTotalMemory()** method. A **forceFullCollection** parameter indicates whether this method should wait a short interval before returning to collect and finalize some objects.

To force a *full sweep* garbage collection, use the **Collect()** method. You can improve performance by specifying the maximum **generation** that will be examined. Generally, it is best to let .NET perform garbage collection automatically when the system is idle.

Some developers have lamented a noticeable lack of *deterministic finalization* within a garbage-collected system; that is, because the object's lifetime is under the control of the garbage collector, there is no guarantee that an object is destroyed as soon as it becomes unreferenced. One approach used to try to compensate for this phenomenon is to call **GC** repeatedly in an effort to force the object's cleanup. This is both time-consuming and wasteful of the garbage collector's efforts, since a collection may involve not only recollection, but readjustment of object locations in memory. If a programmer requires more explicit control over when an object is cleaned up, the class can be declared as implementing the **IDisposable** interface (which consists of a single method, **Dispose()**). This interface allows the object to participate in a **using** declaration, which guarantees that the object's **Dispose()** method is invoked when control leaves the declared scope block (see [Section 2.9.5.7](#)). Use of **IDisposable** is recommended over the use of **Finalize()** methods. This is due to a variety of reasons too numerous to explore here.

The **KeepAlive()** method is used to preserve the life of an object that is not strongly referenced. This is sometimes required when interacting with methods in unmanaged code (such as Win32 APIs or COM). The **KeepAlive()** method works in an unusual manner: it makes an object ineligible for garbage collection from the start of the current routine to the point where the **KeepAlive()** method is called. This unusual system prevents problems that could otherwise be created by compiler optimizations.

```
public sealed class GC {
// Public Static Properties
    public static int MaxGeneration{get; }
// Public Static Methods
    public static void Collect( );
    public static void Collect(int generation);
```

```
public static int GetGeneration(object obj);  
public static int GetGeneration(WeakReference wo);  
public static long GetTotalMemory(bool forceFullCollection);  
public static void KeepAlive(object obj);  
public static void ReRegisterForFinalize(object obj);  
public static void SuppressFinalize(object obj);  
public static void WaitForPendingFinalizers( );  
}
```

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

Guid

CF 1.0, serializable

System (mscorlib.dll)

struct

This value type represents a Globally Unique Identifier (GUID). A GUID is a 128-bit integer (16 bytes) that be used across all computers and networks and will be statistically unique (for all practical purposes, the number cannot be duplicated coincidentally). GUIDs are used to identify COM (but not .NET) objects uniquely for registration purposes.

```
public struct Guid : IFormattable, IComparable {
    // Public Constructors
    public Guid(byte[] b);
    public Guid(int a, short b, short c, byte[] d);
    public Guid(int a, short b, short c, byte d, byte e, byte f, byte g, byte h, byte i,
        byte j, byte k);
    public Guid(string g);
    public Guid(uint a, ushort b, ushort c, byte d, byte e, byte f, byte g, byte h, byte
        byte j, byte k);
    // Public Static Fields
    public static readonly Guid Empty;
    // =00000000-0000-0000-0000-000000000000
    // Public Static Methods
    public static Guid.NewGuid();
    public static bool operator !=(Guid a, Guid b);
    public static bool operator == (Guid a, Guid b);
    // Public Instance Methods
    public int CompareTo(object value);
    // implements IComparable
    public override bool Equals(object o);
    // overrides ValueType
    public override int GetHashCode();
    // overrides ValueType
    public byte[] ToByteArray();
    public override string ToString();
    // overrides ValueType
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
    // implements IFormattable
}
```

Hierarchy

Object → ValueType → Guid(IFormattable, IComparable)

Returned By

```
System.Reflection.Emit.UnmanagedMarshal.IIDGuid ,
System.Runtime.InteropServices.IRegistrationServices.GetManagedCategoryGuid( ) ,
System.Runtime.InteropServices.Marshal.{GenerateGuidForType( ) , GetTypeLibGuid( ) ,
GetTypeLibGuidForAssembly( )} ,
System.Runtime.InteropServices.RegistrationServices.GetManagedCategoryGuid( ) ,Type.GUID
System.Xml.XmlConvert.ToGuid( )
```

Passed To

```
System.Reflection.Emit.ModuleBuilder.DefineDocument( )
,System.Runtime.InteropServices.IRegistrationServices.RegisterTypeForComClients( ) ,
System.Runtime.InteropServices.Marshal.QueryInterface( ) ,
System.Runtime.InteropServices.RegistrationServices.RegisterTypeForComClients( ) ,
Type.GetTypeFromCLSID( ) , System.Xml.XmlConvert.ToString( )
```

[Team LiB]

[◀ PREVIOUS](#) [NEXT ▶](#)

IAsyncResult

CF 1.0, ECMA 1.0

System (mscorlib.dll)

interface

This interface is used in asynchronous programming to act as a placeholder for the result of the async call. It is most commonly used when an instance of a delegate type is fired using the `BeginInvoke` method. (This idiom is used extensively throughout the .NET Framework Class Library.)

Asynchronous method calls can be harvested in a number of ways. A programmer can poll the call by checking the `IsCompleted` property of the `IAsyncResult` object to see if the call has completed yet. This, while perhaps the simplest approach, is also likely the most wasteful, as the caller needs to be in some sort of spin loop, repeatedly checking the property until a `true` is received.

A variant of the polling spin loop is to use the `AsyncWaitHandle` property of `IAsyncResult`. This is a standard Win32 handle that can be used in some of the synchronization primitives provided in the `System.Threading` namespace. Specifically, this property is a `System.Threading.WaitHandle` instance, meaning that the programmer can call any of the `Wait` methods: `WaitOne()`, `WaitAny()`, or `WaitAll()`. The net effect is the same-put the calling thread to sleep until the async call completes.

Although not formally part of the `IAsyncResult` interface, a corresponding `EndInvoke` method is supported by delegates. The `EndInvoke` method blocks the calling thread until the async call completes. Alternatively, at the point of the async delegate call, a programmer can specify a callback delegate to call when the async call completes. This callback, a delegate instance of type `AsyncCallback`, is passed this `IAsyncResult` instance as part of the call. An optional generic argument can also be passed in as part of the async call, and this generic argument is available on the `IAsyncResult` through the `AsyncState` property. For an example of using `IAsyncResult`, see [Section 16.3](#).

```
public interface IAsyncResult {
// Public Instance Properties
    public object AsyncState {get; }
    public WaitHandle AsyncWaitHandle {get; }
    public bool CompletedSynchronously {get; }
    public bool IsCompleted {get; }
}
```

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ICloneable

CF 1.0, ECMA 1.0

System (mscorlib.dll) *interface*

ICloneable is a marker interface, indicating that an object can be cloned (that is, have a completely identical copy created). It consists of a single method, **Clone()**, which is called by clients wishing to create a complete copy of the **ICloneable**-implementing class.

When speaking of cloning, the terms *deep copy cloning* and *shallow copy cloning* indicate how deeply into the object graph a clone operation will carry itself. A deep copy not only clones the object called, but in turn seeks to clone any objects to which it holds reference. This sort of operation must be handled by the programmer, usually by calling **Clone()** in turn on each object this object references. A shallow copy is a complete bitwise copy of this object; any objects referenced by this object are also referenced by the cloned object.

The simplest way to implement a shallow clone is to use the **Object.MemberwiseClone()** method to copy this object's fields directly and then return. A deep clone also calls **MemberwiseClone()**, but then also asks each object reference held within this object to **Clone()** itself.

```
public interface ICloneable {  
    // Public Instance Methods  
    public object Clone( );  
}
```

Implemented By

Multiple types

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IComparable

CF 1.0, ECMA 1.0

System (mscorlib.dll)

interface

This interface is implemented by classes that can be ordered in a list. Classes such as `String` and `Int32` implement this interface. You can also implement it in your own classes to create a type-specific method that allows your objects to be sorted in arrays. This interface does not allow classes to be compared with the greater-than and less-than operators; that requires operator overloading. This interface simply provides a well-known protocol for doing comparisons of objects. (Of course, nothing prevents a C# programmer from defining overloaded comparison operations and calling `CompareTo()` as the implementation.)

To implement `IComparable`, override the `CompareTo()` method. This method accepts another instance of your `IComparable` object and returns an integer that indicates the result of the comparison. (Zero means equal, less than zero indicates that the supplied object is less than the current instance, and greater than zero indicates that the object is greater than the current instance.) Note that the actual value of the integer is irrelevant other than its positive, negative, or zero status (similar to the way `strcmp` works in C). Also note that because `CompareTo()` accepts an argument of `IComparable` type, care must be taken to ensure that it is a legitimate comparison-for example, `myInt.CompareTo(myString)` throws an `ArgumentException`.

```
public interface IComparable {
    // Public Instance Methods
    public int CompareTo(object obj);
}
```

Implemented By

Multiple types

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IConvertible

CF 1.0

System (mscorlib.dll) *interface*

The **IConvertible** interface allows conversion of an object to basic data types and allows the conversion methods in the **Convert** class to use that object. When implementing the **IConvertible** interface, create your own type-specific methods for each of the supplied conversion methods.

Note that **IConvertible** allows one-way conversion from a custom type to other data types, but does not allow a conversion from a basic data type to a custom type.

```
public interface IConvertible {
// Public Instance Methods
    public TypeCode GetTypeCode( );
    public bool ToBoolean(IFormatProvider provider);
    public byte ToByte(IFormatProvider provider);
    public char ToChar(IFormatProvider provider);
    public DateTime ToDateTime(IFormatProvider provider);
    public decimal ToDecimal(IFormatProvider provider);
    public double ToDouble(IFormatProvider provider);
    public short.ToInt16(IFormatProvider provider);
    public int.ToInt32(IFormatProvider provider);
    public long.ToInt64(IFormatProvider provider);
    public sbyte ToSByte(IFormatProvider provider);
    public float ToSingle(IFormatProvider provider);
    public string ToString(IFormatProvider provider);
    public object ToType(Type conversionType, IFormatProvider provider);
    public ushort ToUInt16(IFormatProvider provider);
    public uint ToUInt32(IFormatProvider provider);
    public ulong ToUInt64(IFormatProvider provider);
}
```

Implemented By

Multiple types

I CustomFormatter

CF 1.0

System (mscorlib.dll) *interface*

This interface provides a custom formatter, which returns string information for supplied objects based on custom criteria. The `I CustomFormatter` interface contains a single `Format()` method. This method accepts a `format` string and an `IFormatProvider` object and uses this criteria to determine which string to return for the specified object.

```
public interface ICustomFormatter {  
    // Public Instance Methods  
    public string Format(string format, object arg, IFormatProvider formatProvider);  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

I Disposable

CF 1.0, ECMA 1.0

System (mscorlib.dll)

interface

This interface provides a last-ditch cleanup hook with well-known timing semantics (similar in concept to a C++ destructor). This is called *deterministic finalization*.

As part of normal garbage-collection operation, the CLR looks for (and calls if available) the object's **Finalize** method right before it removes an object from heap memory. Unfortunately, because the CLR may not garbage-collect the object as soon as it becomes available for collection, objects may hold onto resources for longer than necessary. The **IDisposable** interface is intended to work with language constructs to let you ensure that key resources are released in a time-efficient manner.

Any object whose type implements the **IDisposable** interface must have a corresponding **Dispose()** method defined for it. This in turn makes the object eligible for use in the C# **using** block declaration. For more details, see "Using Statement" in [Chapter 2](#).

If a type provides a **Finalize** method, then it should also inherit this interface and provide a corresponding **Dispose()** method. In addition, once the **Dispose()** method is called, part of its implementation should be to call the **GC.SuppressFinalize()** method to prevent the garbage collector from finalizing this object again when garbage collection occurs.

```
public interface IDisposable {
    // Public Instance Methods
    public void Dispose( );
}
```

Implemented By

Multiple types

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IFormatProvider

CF 1.0, ECMA 1.0

System (mscorlib.dll) *interface*

This interface provides a way to retrieve an object that controls formatting through the `GetFormat()` method. For example, the `System.Globalization.CultureInfo` class can return a `System.Globalization.NumberFormatInfo` object, a `System.Globalization.DateTimeFormatInfo` object, or a null reference, depending on the supplied `formatType` parameter.

```
public interface IFormatProvider {  
    // Public Instance Methods  
    public object GetFormat(Type formatType);  
}
```

Implemented By

```
System.Globalization.{CultureInfo, DateTimeFormatInfo, NumberFormatInfo}
```

Returned By

```
System.IO.TextWriter.FormatProvider
```

Passed To

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

I Formattable

CF 1.0, ECMA 1.0

System (mscorlib.dll) *interface*

This interface is implemented in your objects to provide a custom `ToString()` method that accepts a `format` string and an `IFormatProvider` instance. You can then use this information to determine how the return string should be rendered. All numeric value types in the `System` namespace implement this interface.

```
public interface IFormattable {  
    // Public Instance Methods  
    public string ToString(string format, IFormatProvider formatProvider);  
}
```

Implemented By

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)


IndexOutOfRangeException CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *sealed class*

This exception signals an attempt to access an index beyond the bounds of a collection or array.

```
public sealed class IndexOutOfRangeException : SystemException {  
    // Public Constructors  
    public IndexOutOfRangeException( );  
    public IndexOutOfRangeException(string message);  
    public IndexOutOfRangeException(string message, Exception innerException);  
}
```

Hierarchy



Int16

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This is the value type for 16-bit integers (which can range from -32768 to 32767). This is also available in C# through the `short` alias.

```
public struct Int16 : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const short MaxValue;
// =32767
    public const short MinValue;
// =-32768
// Public Static Methods
    public static short Parse(string s);
    public static short Parse(string s, IFormatProvider provider);
    public static short Parse(string s, System.Globalization.NumberStyles style);
    public static short Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Int16(IComparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Int32

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This is the value type for 32-bit integers (which can range from -2,147,483,648 to 2,147,483,647). This is also available in C# through the `int` alias.

```
public struct Int32 : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const int MaxValue;
// =2147483647
    public const int MinValue;
// =-2147483648
// Public Static Methods
    public static int Parse(string s);
    public static int Parse(string s, IFormatProvider provider);
    public static int Parse(string s, System.Globalization.NumberStyles style);
    public static int Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Int32(IComparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Int64

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This is the value type for 64-bit integers (which can range, approximately, from -9.22×10^{18} to 9.22×10^{18}). This is also available in C# through the `long` alias.

```
public struct Int64 : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const long MaxValue;
//    =9223372036854775807
    public const long MinValue;
//    =-9223372036854775808
// Public Static Methods
    public static long Parse(string s);
    public static long Parse(string s, IFormatProvider provider);
    public static long Parse(string s, System.Globalization.NumberStyles style);
    public static long Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
// Public Instance Methods
    public int CompareTo(object value);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Int64(IComparable, IFormattable, IConvertible)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

IntPtr

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This is the value type used to store unmanaged pointers or handles (e.g., `IntPtr` objects are used in the `System.IO.FileStream` class to hold file handles).

Using this type allows your pointers to be platform-independent, as `IntPtr` is automatically mapped to a 32-bit integer on 32-bit operating systems and to a 64-bit integer on 64-bit operating systems. The `IntPtr` type is CLS-compliant and should be used in preference of the `UIntPtr`.

```
public struct IntPtr : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public IntPtr(int value);
    public IntPtr(long value);
    public IntPtr(void *value);
// Public Static Fields
    public static readonly IntPtr Zero;
// =0
// Public Static Properties
    public static int Size{get; }
// Public Static Methods
    public static bool operator !=(IntPtr value1, IntPtr value2);
    public static bool operator ==(IntPtr value1, IntPtr value2);
    public static explicit operator int(IntPtr value);
    public static explicit operator long(IntPtr value);
    public static explicit operator IntPtr(int value);
    public static explicit operator IntPtr(long value);
    public static explicit operator IntPtr(void *value);
    public static explicit operator Void(IntPtr value);
// Public Instance Methods
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public int ToInt32( );
    public long ToInt64( );
    public void* ToPointer( );
    public override string ToString( );
// overrides ValueType
}
```

Hierarchy

Object → ValueType → IntPtr(System.Runtime.Serialization.ISerializable)

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

InvalidCastException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception signals a failure during a cast or explicit conversion.

```
public class InvalidCastException : SystemException {  
    // Public Constructors  
    public InvalidCastException( );  
    public InvalidCastException(string message);  
    public InvalidCastException(string message, Exception innerException);  
    // Protected Constructors  
    protected InvalidCastException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



InvalidOperationException


CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This exception indicates that a user attempted to use a method when the object was not in an appropriate state. For example, this exception is thrown if you attempt to write data with a `System.Xml.XmlTextWriter` that is already closed.

```
public class InvalidOperationException : SystemException {  
    // Public Constructors  
    public InvalidOperationException( );  
    public InvalidOperationException(string message);  
    public InvalidOperationException(string message, Exception innerException);  
    // Protected Constructors  
    protected InvalidOperationException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

ObjectDisposedException, System.Net.{ProtocolViolationException, WebException}

InvalidProgramException


CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *sealed class*

This exception indicates that the .NET execution engine found some invalid code or metadata in a program. This can be caused by a compiler bug that generates malformed MSIL (Microsoft Intermediate Language) instructions.

```
public sealed class InvalidProgramException : SystemException {  
    // Public Constructors  
    public InvalidProgramException( );  
    public InvalidProgramException(string message);  
    public InvalidProgramException(string message, Exception inner);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IServiceProvider

CF 1.0

System (mscorlib.dll) *interface*

This interface defines a mechanism for retrieving a service object. A class implementing this interface provides a service object to other objects through its `GetService()` method.

```
public interface IServiceProvider {  
    // Public Instance Methods  
    public object GetService(Type serviceType);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

LoaderOptimization

serializable

System (mscorlib.dll)

enum

This enumeration is used for the `LoaderOptimizationAttribute` constructor. It specifies whether your application will use more than one `AppDomain`. Use the `MultiDomain` value if your application contains many domains that use the same code, and use `MultiDomainHost` if your application hosts multiple domains with unique code-in which case resources are shared for globally available assemblies only. `NotSpecified` reverts to `SingleDomain`, unless the default domain or host specifies otherwise.

```
public enum LoaderOptimization {
    NotSpecified = 0,
    SingleDomain = 1,
    MultiDomain = 2,
    MultiDomainHost = 3,
    DomainMask = 3,
    DisallowBindings = 4
}
```

Hierarchy

Object → ValueType → Enum(IComparable, IFormattable, IConvertible) → LoaderOptimization

Returned By

`AppDomainSetup.LoaderOptimization, LoaderOptimizationAttribute.Value`

Passed To

`AppDomainSetup.LoaderOptimization,`
`LoaderOptimizationAttribute.LoaderOptimizationAttribute()`

LoaderOptimizationAttribute

System (mscorlib.dll) *sealed class*

This attribute can be used only on your application's **Main** method. It sets the type of default optimization used to share internal resources across application domains. It is most relevant when you use the **AppDomain** class to create more than one domain from your application. By default, if you do not use this attribute, the .NET Framework makes optimizations with the assumption that your application has only a single domain.

```
public sealed class LoaderOptimizationAttribute : Attribute {  
    // Public Constructors  
    public LoaderOptimizationAttribute(byte value);  
    public LoaderOptimizationAttribute(LoaderOptimization value);  
    // Public Instance Properties  
    public LoaderOptimization Value {get; }  
}
```

Hierarchy

Object → Attribute → LoaderOptimizationAttribute

Valid On

Method

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

LocalDataStoreSlot

CF 1.0

System (mscorlib.dll)

sealed class

The CLR allocates a multislot local data store to each process when it starts. These slots are used for thread-specific and context-specific data, and are not shared between threads or contexts. The `LocalDataStoreSlot` class encapsulates one of these slots. It's used by the `GetData()` and `SetData()` methods in the `System.Threading.Thread` and `System.Runtime.Remoting.Contexts.Context` classes.

```
public sealed class LocalDataStoreSlot {  
    // Protected Instance Methods  
    protected override void Finalize( );  
    // overrides object  
}
```

Returned By

```
System.Threading.Thread.{AllocateDataSlot( ), AllocateNamedDataSlot( ),  
    GetNamedDataSlot( )}
```

Passed To

```
System.Threading.Thread.{GetData( ), SetData( )}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

CF 1.0, ECMA 1.0, MarshalByRefObject serializable, marshal by reference

System (mscorlib.dll)

abstract class

MarshalByRefObject is the base class for objects that are marshaled by reference across **AppDomain** boundaries. If you attempt to transmit an object that derives from this class to another domain (e.g., as a parameter in a method call to a remote machine), an object reference is sent. (In actuality, this is an object proxy, which provides the same interface-methods, properties, and so forth.) If the other domain uses this reference (e.g., sets an object property or calls one of its methods), the call is automatically marshaled back to the original domain in which the object was created, and it is invoked there, using the proxy object the .NET Framework creates automatically.

You can inherit from this class to create a remotable object. Values that should be marshaled by reference include unmanaged pointers and file handles, which do not have any meaning in another domain. Objects that are marshaled by reference live until their lifetime lease expires. The **MarshalByRefObject** class includes methods for getting and setting the **ILease** object from the **System.Runtime.Remoting.Lifetime** namespace. More information about remoting can be found in the **System.Runtime.Remoting** namespace.

```
public abstract class MarshalByRefObject {  
    // Protected Constructors  
    protected MarshalByRefObject( );  
    // Public Instance Methods  
    public virtual ObjRef CreateObjRef(Type requestedType);  
    public object GetLifetimeService( );  
    public virtual object InitializeLifetimeService( );  
}
```

Subclasses

Multiple types

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Math

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

This class provides static helper functions for many trigonometric, logarithmic, and other mathematical operations, including methods for rounding numbers, getting absolute values, retrieving the largest whole divisor (`Floor()`), and determining the remainder (`IEEERemainder()`). The constants π and e are provided as fields.

```
public sealed class Math {
// Public Static Fields
    public const double E;
// =2.71828182845905
    public const double PI;
// =3.14159265358979
// Public Static Methods
    public static decimal Abs(decimal value);
    public static double Abs(double value);
    public static short Abs(short value);
    public static int Abs(int value);
    public static long Abs(long value);
    public static sbyte Abs(sbyte value);
    public static float Abs(float value);
    public static double Acos(double d);
    public static double Asin(double d);
    public static double Atan(double d);
    public static double Atan2(double y, double x);
    public static long BigMul(int a, int b);
    public static double Ceiling(double a);
    public static double Cos(double d);
    public static double Cosh(double value);
    public static int DivRem(int a, int b, out int result);
    public static long DivRem(long a, long b, out long result);
    public static double Exp(double d);
    public static double Floor(double d);
    public static double IEEERemainder(double x, double y);
    public static double Log(double d);
    public static double Log(double a, double newBase);
    public static double Log10(double d);
    public static byte Max(byte val1, byte val2);
    public static decimal Max(decimal val1, decimal val2);
    public static double Max(double val1, double val2);
    public static short Max(short val1, short val2);
    public static int Max(int val1, int val2);
}
```

```
public static long Max(long val1, long val2);
public static sbyte Max(sbyte val1, sbyte val2);
public static float Max(float val1, float val2);
public static ushort Max(ushort val1, ushort val2);
public static uint Max(uint val1, uint val2);
public static ulong Max(ulong val1, ulong val2);
public static byte Min(byte val1, byte val2);
public static decimal Min(decimal val1, decimal val2);
public static double Min(double val1, double val2);
public static short Min(short val1, short val2);
public static int Min(int val1, int val2);
public static long Min(long val1, long val2);
public static sbyte Min(sbyte val1, sbyte val2);
public static float Min(float val1, float val2);
public static ushort Min(ushort val1, ushort val2);
public static uint Min(uint val1, uint val2);
public static ulong Min(ulong val1, ulong val2);
public static double Pow(double x, double y);
public static decimal Round(decimal d);
public static decimal Round(decimal d, int decimals);
public static double Round(double a);
public static double Round(double value, int digits);
public static int Sign(decimal value);
public static int Sign(double value);
public static int Sign(short value);
public static int Sign(int value);
public static int Sign(long value);
public static int Sign(sbyte value);
public static int Sign(float value);
public static double Sin(double a);
public static double Sinh(double value);
public static double Sqrt(double d);
public static double Tan(double a);
public static double Tanh(double value);
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

MemberAccessException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This is the superclass of several exceptions that indicate a failed attempt to access a class member.

```
public class MemberAccessException : SystemException {  
    // Public Constructors  
    public MemberAccessException( );  
    public MemberAccessException(string message);  
    public MemberAccessException(string message, Exception inner);  
    // Protected Constructors  
    protected MemberAccessException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

FieldAccessException , MethodAccessException , MissingMemberException

MethodAccessException

ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception indicates a failed attempt to access a method.

```
public class MethodAccessException : MemberAccessException {  
    // Public Constructors  
    public MethodAccessException( );  
    public MethodAccessException(string message);  
    public MethodAccessException(string message, Exception inner);  
    // Protected Constructors  
    protected MethodAccessException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



MissingFieldException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

MissingMemberException indicates an attempt to access a nonexistent field.

```
public class MissingFieldException : MissingMemberException {  
    // Public Constructors  
    public MissingFieldException( );  
    public MissingFieldException(string message);  
    public MissingFieldException(string message, Exception inner);  
    public MissingFieldException(string className, string fieldName);  
    // Protected Constructors  
    protected MissingFieldException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public override string Message {get; }  
    // overrides MissingMemberException  
}
```

Hierarchy



MissingMemberException


CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This is the superclass of several exceptions that indicate an attempt to access a nonexistent member. Although the compiler detects explicit attempts of this sort, it does not protect against attempts to access nonexistent members using reflection.

```
public class MissingMemberException : MemberAccessException {
// Public Constructors
    public MissingMemberException( );
    public MissingMemberException(string message);
    public MissingMemberException(string message, Exception inner);
    public MissingMemberException(string className, string memberName);
// Protected Constructors
    protected MissingMemberException(System.Runtime.Serialization.SerializationInfo info
        System.Runtime.Serialization.StreamingContext context);
// Protected Instance Fields
    protected string ClassName;
    protected string MemberName;
    protected byte[ ] Signature;
// Public Instance Properties
    public override string Message{get; }
// overrides Exception
// Public Instance Methods
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in
        System.Runtime.Serialization.StreamingContext context)
// overrides Exception
}
```

Hierarchy



Subclasses

MissingFieldException , MissingMethodException

MissingMethodException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

class

This exception indicates an attempt to access a nonexistent method.

```
public class MissingMethodException : MissingMemberException {  
    // Public Constructors  
    public MissingMethodException( );  
    public MissingMethodException(string message);  
    public MissingMethodException(string message, Exception inner);  
    public MissingMethodException(string className, string methodName);  
    // Protected Constructors  
    protected MissingMethodException(System.Runtime.Serialization.SerializationInfo info  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public override string Message{get; }  
    // overrides MissingMemberException  
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) → SystemException →
MemberAccessException → MissingMemberException → MissingMethodException

MTAThreadAttribute

System (mscorlib.dll) *sealed class*

This attribute is used entirely for COM interoperability in .NET; it has no effect on a pure .NET application or system.

This attribute can be used only on the **Main** method of the application. It sets the default threading model to MTA (multithreaded apartment). Alternatively, you can use the **STAThreadAttribute** attribute for a single-threaded apartment model.

```
public sealed class MTAThreadAttribute : Attribute {  
    // Public Constructors  
    public MTAThreadAttribute( );  
}
```

Hierarchy



Valid On

Method

MulticastDelegate

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

abstract class

This is the base class for multicast delegates. Multicast delegates are identical to normal delegates, except that their invocation list can hold more than one method at a time. You can use `Delegate.Combine()` to add a method to the list and `Delegate.Remove()` to remove one. In C#, you can also use the `+` operator (or `+=`) to add methods. When you invoke a multicast delegate, the methods are invoked synchronously after the other. An error in one method can prevent the delegate from calling the other methods in its list.

Multicast delegates can also be invoked asynchronously, meaning that the entire call chain is invoked serially by a single thread out of the system thread pool. If it is desirable to invoke each delegate in the chain on its own asynchronous thread instead, then use `GetInvocationList()` to obtain the list of delegates and asynchronously invoke each one.

```
public abstract class MulticastDelegate : Delegate {
    // Protected Constructors
    protected MulticastDelegate(object target, string method);
    protected MulticastDelegate(Type target, string method);
    // Public Static Methods
    public static bool operator !=(MulticastDelegate d1, MulticastDelegate d2);
    public static bool operator ==(MulticastDelegate d1, MulticastDelegate d2);
    // Public Instance Methods
    public sealed override bool Equals(object obj);
    // overrides Delegate
    public sealed override int GetHashCode( );
    // overrides Delegate
    public sealed override Delegate[] GetInvocationList( );
    // overrides Delegate
    public override void GetObjectData( System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
    // overrides Delegate
    // Protected Instance Methods
    protected sealed override Delegate CombineImpl( Delegate follow)
    // overrides Delegate
    protected sealed override object DynamicInvokeImpl(object[] args)
    // overrides Delegate
    protected sealed override Delegate RemoveImpl(Delegate value)
    // overrides Delegate
}
```

Hierarchy

Object → Delegate(ICloneable , System.Runtime.Serialization.ISerializable) →
MulticastDelegate

Subclasses

Multiple types

[Team LiB]

◀ PREVIOUS

NEXT ▶

MulticastNotSupportedException

CF 1.0,
serializable


System (mscorlib.dll)

sealed class

This exception is thrown when two uncombinable delegates are combined; see `Delegate` and `MulticastDelegate` for details regarding what constitutes *combinable* delegates.

```
public sealed class MulticastNotSupportedException : SystemException {  
    // Public Constructors  
    public MulticastNotSupportedException( );  
    public MulticastNotSupportedException(string message);  
    public MulticastNotSupportedException(string message, Exception inner);  
}
```

Hierarchy



NonSerializedAttribute

CF 1.0


System (mscorlib.dll) *sealed class*

This attribute lets you mark properties of fields in a class as nonserializable, so that they are ignored during a serialization operation. Typical examples of nonserializable data include pointers, handles, and other data structures that can't be re-created during deserialization.

By default, a class is not eligible for serialization unless it implements `System.Runtime.Serialization.ISerializable` or is marked with a `SerializableAttribute`. Once a class is marked as serializable, you must mark all fields or properties that are not to be serialized with a `NonSerializedAttribute`.

```
public sealed class NonSerializedAttribute : Attribute {  
    // Public Constructors  
    public NonSerializedAttribute( );  
}
```

Hierarchy



Valid On

Field

NotFiniteNumberException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This exception is thrown when certain languages encounter floating-point infinity or NaN (not a number) values. These values can be represented in C# with `Double.NegativeInfinity`, `Double.PositiveInfinity`, and `Double.NaN`. (Similar fields are available in `Single`.)

```
public class NotFiniteNumberException : ArithmeticException {  
    // Public Constructors  
    public NotFiniteNumberException( );  
    public NotFiniteNumberException(double offendingNumber);  
    public NotFiniteNumberException(string message);  
    public NotFiniteNumberException(string message, double offendingNumber);  
    public NotFiniteNumberException(string message, double offendingNumber,  
        Exception innerException);  
    // Protected Constructors  
    protected NotFiniteNumberException(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public double OffendingNumber {get; }  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) → SystemException →
ArithmeticException → NotFiniteNumberException

NotImplementedException

ECMA 1.0,
serializable

System (mscorlib.dll)


class

This exception signals an attempt to access an unimplemented method or operation.

Suppose you have a base class with a number of unimplemented methods. You may have reason not to mark them as abstract (perhaps you want to let programmers develop subclasses that only implement some of the base class methods). You can throw this exception in those methods, letting users of the subclass know that they are not implemented.

```
public class NotImplementedException : SystemException {  
    // Public Constructors  
    public NotImplementedException( );  
    public NotImplementedException(string message);  
    public NotImplementedException(string message, Exception inner);  
    // Protected Constructors  
    protected NotImplementedException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



NotSupportedException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception indicates an attempt to use an unsupported method. For example, if you try to seek on a stream that is based on unidirectional input-for example, a standard input stream from a console utility such as *sort.exe*-this exception could be thrown.

```
public class NotSupportedException : SystemException {  
    // Public Constructors  
    public NotSupportedException( );  
    public NotSupportedException(string message);  
    public NotSupportedException(string message, Exception innerException);  
    // Protected Constructors  
    protected NotSupportedException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

PlatformNotSupportedException

NullReferenceException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception is thrown when you try to dereference a null pointer (for example, accessing an instance field on an object reference that currently points to no instance).

```
public class NullReferenceException : SystemException {  
    // Public Constructors  
    public NullReferenceException( );  
    public NullReferenceException(string message);  
    public NullReferenceException(string message, Exception innerException);  
    // Protected Constructors  
    protected NullReferenceException(System.Runtime.Serialization.SerializationInfo info  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Object

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

class

This class is the root of all .NET types, including value types and reference types. Some CLR languages such as C# and VB.NET do not require a type to inherit from **Object** explicitly. If no base type is listed in a class declaration, it is assumed that the type is to inherit from **Object**. Therefore, all types derive from it implicitly and can use any of its methods.

Use the **GetType()** method to obtain a description of your object's internal metadata as a **Type** object. Use the **ToString()** method to get a **String** that represents your object. By default, this is the fully qualified type name of your object, but most classes override this method to provide something more useful, such as a string representation of the object's content. For example, **System.Drawing.Point.ToString()** might return **(10, 5)**.

The **MemberwiseClone()** method returns a new object of the same type that is a member-by-member duplicate. This object is called a shallow copy because any subobjects are not copied. Instead, the references are duplicated, meaning that both the original and cloned type refer to the same subobjects. **MemberwiseClone()** is protected, so it can be called only from methods of your derived object. Usually, you will implement the **ICloneable** interface for your objects and call **MemberwiseClone()** from a customized **ICloneable.Clone()** method.

Use the **Equals()** method to test for reference equality. Derived value-type classes override this method to provide value equality (which returns **true** for identical content, even if it is stored in different objects at different memory addresses). Note that the equality operator (**=** in C#, **=** in VB.NET) does not call **Equals()** unless the equality operator is overloaded for the appropriate type (as it is with **String**, for example).

The **ReferenceEquals()** method, while perhaps seeming somewhat similar, compares object identity rather than object equality. That is, while **Equals()** might return **true** for two independent objects that contain the same state, **ReferenceEquals()** checks to see if the two references passed to it point to the same object. These two objects are identical, which is only the case when both references point to the same location in memory. Because the **=** operator compares references by default, but could be changed later to compare state (or anything else), **ReferenceEquals()** is the only safe way to test references for identity.

The **GetHashCode()** method returns a hash code so the object can be used as a key in a **System.Collections.Hashtable** collection. By default, **GetHashCode()** returns a unique hash code for each object, which is sufficient for reference types but must be overridden by all value types so that equivalent types return identical hash codes.

```
public class Object {
// Public Constructors
    public Object( );
// Public Static Methods
    public static bool Equals(object objA, object objB);
    public static bool ReferenceEquals(object objA, object objB);
}
```

```
// Public Instance Methods
public virtual bool Equals(object obj);
public virtual int GetHashCode( );
public Type GetType( );
public virtual string ToString( );
// Protected Instance Methods
protected override void Finalize( );
protected object MemberwiseClone( );
}
```

Subclasses

Multiple types

Returned By

Multiple types

Passed To

Multiple types

[\[Team LiB \]](#)

ObjectDisposedException


CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This exception is thrown when certain operations are performed on an object that has been disposed. For example, trying to read from an I/O stream that has been closed by the `System.IO.Stream.Close()` method should raise this exception.

```
public class ObjectDisposedException : InvalidOperationException {  
    // Public Constructors  
    public ObjectDisposedException(string objectName);  
    public ObjectDisposedException(string objectName, string message);  
    // Protected Constructors  
    protected ObjectDisposedException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public override string Message{get; }  
    // overrides Exception  
    public string ObjectName{get; }  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
}
```

Hierarchy



ObsoleteAttribute

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

sealed class

This attribute is used to mark program elements that will be removed in future versions or are no longer fully supported. The use of an element with this attribute (e.g., calling a method or setting a property marked with **ObsoleteAttribute**) causes a compile-time warning. You can set the **Message** property to supply a string to display to the user, typically specifying a workaround or the program element that should be used as a replacement. You can also use the **IsError** property to specify that the compiler treats the use of this element as an error. The default is **false**. These properties are set through the constructor, as in `[Obsolete ("OldMethod has been replaced by NewMethod", true)]`.

```
public sealed class ObsoleteAttribute : Attribute {  
    // Public Constructors  
    public ObsoleteAttribute( );  
    public ObsoleteAttribute(string message);  
    public ObsoleteAttribute(string message, bool error);  
    // Public Instance Properties  
    public bool IsError{get; }  
    public string Message{get; }  
}
```

Hierarchy

Object → Attribute → ObsoleteAttribute

Valid On

Class, Struct, Enum, Constructor, Method, Property, Field, Event, Interface, Delegate

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

OperatingSystem

CF 1.0, serializable

System (mscorlib.dll)

sealed class

This class represents the current operating system by combining an instance of the PlatformID and Version classes. It is returned by the Environment.OSVersion property.

```
public sealed class OperatingSystem : ICloneable {  
    // Public Constructors  
    public OperatingSystem(PlatformID platform, Version version);  
    // Public Instance Properties  
    public PlatformID Platform{get; }  
    public Version Version{get; }  
    // Public Instance Methods  
    public object Clone( );  
    // implements ICloneable  
    public override string ToString( );  
    // overrides object  
}
```

Returned By

Environment.OSVersion

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

OutOfMemoryException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception indicates that the .NET runtime has exhausted all available memory and usually means the CLR is in deep danger of dying altogether.

```
public class OutOfMemoryException : SystemException {  
    // Public Constructors  
    public OutOfMemoryException( );  
    public OutOfMemoryException(string message);  
    public OutOfMemoryException(string message, Exception innerException);  
    // Protected Constructors  
    protected OutOfMemoryException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



OverflowException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception indicates an attempt to store a value that exceeds the limit of the target type. This could be caused by an arithmetic operation, cast, or conversion.

```
public class OverflowException : ArithmeticException {  
    // Public Constructors  
    public OverflowException( );  
    public OverflowException(string message);  
    public OverflowException(string message, Exception innerException);  
    // Protected Constructors  
    protected OverflowException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



ParamArrayAttribute

CF 1.0, ECMA 1.0

System (mscorlib.dll)

sealed class

This attribute is used on a method to indicate that it can accept a variable number of parameters. The method has an array as its last parameter, and the list of values passed to the method are stored in the array. In C#, use the `params` keyword to create methods with a variable number of arguments, rather than using this attribute directly.

```
public sealed class ParamArrayAttribute : Attribute {  
    // Public Constructors  
    public ParamArrayAttribute( );  
}
```

Hierarchy

Object → Attribute → ParamArrayAttribute

Valid On

Parameter

PlatformID

CF 1.0, serializable

System (mscorlib.dll)

enum

This enumerated value indicates the type of operating platform that .NET is currently running on and is returned by the `OperatingSystem.Platform` property. `Win32Windows` indicates a Windows 9x-based operating system, while `Win32NT` indicates an operating system based on Windows NT, including Windows 2000, XP, and .NET Server. `Win32S` is a layer that can run on 16-bit versions of Windows (Windows 3.x) to provide access to some 32-bit applications, and `WinCE` represents the Pocket PC flavor of the Win32 operating system.

```
public enum PlatformID {  
    Win32S = 0,  
    Win32Windows = 1,  
    Win32NT = 2,  
    WinCE = 3  
}
```

Hierarchy



Returned By

```
OperatingSystem.Platform
```

Passed To

```
OperatingSystem.OperatingSystem( )
```

PlatformNotSupportedException

CF 1.0,
serializable


System (mscorlib.dll)

class

This exception signals an attempt to access a class or member that is not available on the current platform. For example, many properties from `System.Diagnostics.Process` are not available on Windows 95, 98, or 10.

```
public class PlatformNotSupportedException : NotSupportedException {
// Public Constructors
    public PlatformNotSupportedException( );
    public PlatformNotSupportedException(string message);
    public PlatformNotSupportedException(string message, Exception inner);
// Protected Constructors
    protected PlatformNotSupportedException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



Random CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *class*

This class encapsulates a *pseudorandom number* (one chosen from a list of pregenerated numbers, but that is statistically random). After creating an instance of this class, use the `Next()`, `NextDouble()`, or `NextBytes()` methods to return random information. `NextDouble()` returns a fraction value between 0.0 and 1.0, while `Next()` returns an integer between and the maximum bound that you specify. `NextBytes()` fills a supplied array of bytes with random numbers.

When creating a `Random` object, you supply a seed value to the constructor, which determines the place on the list from where the random number is drawn. If you supply the same seed value to multiple `Random` instances, you will receive the same random number. Computers are incapable of generating truly random numbers, and `Random` should not be used for cryptographic algorithms. For a cryptographically strong random number generator, see the `System.Security.Cryptography.RandomNumberGenerator` in the .NET Framework SDK Documentation.

```
public class Random {  
    // Public Constructors  
    public Random( );  
    public Random(int Seed);  
    // Public Instance Methods  
    public virtual int Next( );  
    public virtual int Next(int maxValue);  
    public virtual int Next(int minValue, int maxValue);  
    public virtual void NextBytes(byte[] buffer);  
    public virtual double NextDouble( );  
    // Protected Instance Methods  
    protected virtual double Sample( );  
}
```


RankException CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *class*

This exception signals an attempt to send an array of the wrong rank to a method. For example, this exception is thrown when you pass a multidimensional array to `Array.Sort()` or `Array.Reverse()`.

```
public class RankException : SystemException {
// Public Constructors
    public RankException( );
    public RankException(string message);
    public RankException(string message, Exception innerException);
// Protected Constructors
    protected RankException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization. StreamingContext context);
}
```

Hierarchy



ResolveEventArgs

System (mscorlib.dll) *class*

This object is provided to methods with the `ResolveEventHandler` signature, indicating additional information about the reference that could not be resolved in the `Name` property.

```
public class ResolveEventArgs : EventArgs {  
    // Public Constructors  
    public ResolveEventArgs(string name);  
    // Public Instance Properties  
    public string Name { get; }  
}
```

Hierarchy



Passed To

```
System.Reflection.ModuleResolveEventHandler.{BeginInvoke( ), Invoke( )},  
ResolveEventHandler.{BeginInvoke( ), Invoke( )}
```


[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ResolveEventHandler

serializable

System (mscorlib.dll)

delegate

This delegate defines the event handler that can be created to respond to `AppDomain.TypeResolve`, `AppDomain.ResourceResolve`, and `AppDomain.AssemblyResolve` events. These events are raised when the runtime cannot find a type, assembly, or resource. Use this delegate to catch that event, then find and return the assembly that contains the missing type, resource, or assembly.

```
public delegate Assembly ResolveEventHandler(object sender, ResolveEventArgs args);
```

Associated Events

```
AppDomain.{AssemblyResolve( ), ResourceResolve( ), TypeResolve( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

RuntimeTypeHandle

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *struct*

This structure is a handle to the internal metadata representation of a type. The `Value` property provides an `IntPtr` reference. You can use this class with the `Type.GetTypeFromHandle()` static method.

```
public struct RuntimeTypeHandle : System.Runtime.Serialization.ISerializable {  
    // Public Instance Properties  
    public IntPtr Value { get; }  
    // Public Instance Methods  
    public void GetObjectData(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context)  
    // implements ISerializable  
}
```

Hierarchy

Object → ValueType → RuntimeTypeHandle(System.Runtime.Serialization.ISerializable)

Returned By

`ArgIterator.GetNextArgType(), Type.{GetTypeHandle(), TypeHandle}`

Passed To

`ArgIterator.GetNextArg(), Type.GetTypeFromHandle()`

SByte

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This structure represents an 8-bit signed integer (from -128 to 127). It is not CLS-compliant. Use `Int16` instead. In C#, this type is aliased as `sbyte`.

```
public struct SByte : IComparable, IFormattable, IConvertible {
// Public Static Fields
    public const sbyte MaxValue;
// =127
    public const sbyte MinValue;
// =-128
// Public Static Methods
    public static sbyte Parse(string s);
    public static sbyte Parse(string s, IFormatProvider provider);
    public static sbyte Parse(string s, System.Globalization.NumberStyles style);
    public static sbyte Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
// Public Instance Methods
    public int CompareTo(object obj);
// implements IComparable
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TypeCode GetTypeCode( );
// implements IConvertible
    public override string ToString( );
// overrides ValueType
    public string ToString(IFormatProvider provider);
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}
```

Hierarchy

Object → ValueType → SByte(IComparable, IFormattable, IConvertible)

Returned By

Convert.ToSByte(), Decimal.ToSByte(), IConvertible.ToSByte(),

```
System.IO.BinaryReader.ReadSByte( ), Math.{Abs( ), Max( ), Min( )},  
System.Runtime.Serialization.FormatterConverter.ToSByte( ),  
System.Runtime.Serialization.IFormatterConverter.ToSByte( ),  
System.Runtime.Serialization.SerializationInfo.GetSByte( ),  
System.Xml.XmlConvert.ToSByte( )
```

Passed To

Multiple types

[\[Team LiB \]](#)

SerializableAttribute

System (mscorlib.dll) *sealed class*

This attribute is used in the class definition to indicate that a class can be serialized. By default, all fields in the class are serialized except for the fields that are marked with a `NonSerializedAttribute`.

It is not necessary to use this attribute if a given type implements the `System.Runtime.Serialization.ISerializable` interface, which indicates that a class provides its own methods for serialization.

```
public sealed class SerializableAttribute : Attribute {  
    // Public Constructors  
    public SerializableAttribute( );  
}
```

Hierarchy

`Object` → `Attribute` → `SerializableAttribute`

Valid On

Class, Struct, Enum, Delegate

Single CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This represents a 32-bit single-precision floating number as a value type. The value of a single can range approximately from -3.4×10^{38} to 3.4×10^{38} , and can also be set to one of the following fields: `PositiveInfinity`, `NegativeInfinity`, and `NaN` (not a number). In C#, this type is aliased as `float`.

```
public struct Single : IComparable, IFormattable, IConvertible {
    // Public Static Fields
    public const float Epsilon;
    // =1.401298E-45
    public const float MaxValue;
    // =3.402823E+38
    public const float MinValue;
    // =-3.402823E+38
    public const float NaN;
    // =NaN
    public const float NegativeInfinity;
    // =-Infinity
    public const float PositiveInfinity;
    // =Infinity
    // Public Static Methods
    public static bool IsInfinity(float f);
    public static bool IsNaN(float f);
    public static bool IsNegativeInfinity(float f);
    public static bool IsPositiveInfinity(float f);
    public static float Parse(string s);
    public static float Parse(string s, IFormatProvider provider);
    public static float Parse(string s, System.Globalization.NumberStyles style);
    public static float Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
    // Public Instance Methods
    public int CompareTo(object value);
    // implements IComparable
    public override bool Equals(object obj);
    // overrides ValueType
    public override int GetHashCode( );
    // overrides ValueType
    public TypeCode GetTypeCode( );
    // implements IConvertible
    public override string ToString( );
    // overrides ValueType
    public string ToString(IFormatProvider provider);
```

```
// implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
// implements IFormattable
}
```

Hierarchy

Object → ValueType → Single(IComparable, IFormattable, IConvertible)

Returned By

```
BitConverter.ToSingle( ), Convert.ToSingle( ), Decimal.ToSingle( ),
System.Diagnostics.CounterSample.Calculate( ),
System.Diagnostics.CounterSampleCalculator.ComputeCounterValue( ),
System.Diagnostics.PerformanceCounter.NextValue( ), IConvertible.ToSingle( ),
System.IO.BinaryReader.ReadSingle( ),
System.Runtime.Serialization.FormatterConverter.ToSingle( ),
System.Runtime.Serialization.IFormatterConverter.ToSingle( ),
System.Runtime.Serialization.SerializationInfo.GetSingle( ),
System.Xml.XmlConvert.ToSingle( )
```

Passed To

Multiple types

[\[Team LiB \]](#)

StackOverflowException

CF 1.0, ECMA 1.0,
serializable


System (mscorlib.dll)

sealed class

This exception indicates that the .NET runtime environment experienced a stack overflow. This can be caused by pathologically deep recursion.

```
public sealed class StackOverflowException : SystemException {  
    // Public Constructors  
    public StackOverflowException( );  
    public StackOverflowException(string message);  
    public StackOverflowException(string message, Exception innerException);  
}
```

Hierarchy



STAThreadAttribute

System (mscorlib.dll) *sealed class*

This attribute can be used only on the **Main** method of an application. It sets the default threading model to **STA** (single-threaded apartment). Alternatively, you can use the **MTAThreadAttribute** attribute to use a multithreaded apartment model. See [Chapter 17](#).

Like its counterpart, **MTAThreadAttribute**, this attribute has no meaning outside of COM interoperability.

```
public sealed class STAThreadAttribute : Attribute {  
    // Public Constructors  
    public STAThreadAttribute( );  
}
```

Hierarchy



Valid On

Method

String

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

sealed class

This class consists of an immutable array of `Char` characters and built-in helper functions. Methods that modify a string, such as `Concat()`, actually create and return a new `String` object. To modify a string use the `System.Text.StringBuilder` class. This can enhance performance in some routines that make inter string-manipulation operations. In C#, `String` is aliased as `string`.

A string is slightly unusual because it is a reference type that behaves like a value type for comparison and assignment operations. Two `String` objects with the same content but different locations in memory return `false` when tested for equality. Also, assigning one `String` to another clones the string itself, rather than just a reference.

On the other hand, a `String` is a fully featured object with a `Length` property and a wide variety of methods following: padding or trimming specified characters on either side, converting case, performing inline substitution (with `Replace()`), and dividing a string into an array of strings (with `Split()`). There's also a default indexer that lets you retrieve a single character. Note that strings are zero-based, and the first character is `string[0]`.

You can create a string made up of a single repeated character by using an alternate constructor and specifying the number of repetitions.

```
public sealed class String : IComparable, ICloneable, IConvertible, IEnumerable {
// Public Constructors
    public String(char *value);
    public String(char *value, int startIndex, int length);
    public String(char[] value);
    public String(char[] value, int startIndex, int length);
    public String(char c, int count);
    public String(sbyte *value);
    public String(sbyte *value, int startIndex, int length);
    public String(sbyte *value, int startIndex, int length, System.Text.Encoding enc);
// Public Static Fields
    public static readonly string Empty;
// Public Instance Properties
    public int Length {get; }
    public char this[int index] {get; }
// Public Static Methods
    public static int Compare(string strA, int indexA, string strB, int indexB, int length,
        bool ignoreCase);
    public static int Compare(string strA, int indexA, string strB, int indexB, int length,
        bool ignoreCase, System.Globalization.CultureInfo culture);
    public static int Compare(string strA, string strB);
    public static int Compare(string strA, string strB, bool ignoreCase);
```

```

    public static int Compare(string strA, string strB, bool ignoreCase,
        System.Globalization.CultureInfo culture);
    public static int CompareOrdinal(string strA, int indexA, string strB, int indexB, bool ignoreCase);
    public static int CompareOrdinal(string strA, string strB);
    public static string Concat(object arg0);
    public static string Concat(params object[ ] args);
    public static string Concat(object arg0, object arg1);
    public static string Concat(object arg0, object arg1, object arg2);
    public static string Concat(object arg0, object arg1, object arg2, object arg3);
    public static string Concat(params string[ ] values);
    public static string Concat(string str0, string str1);
    public static string Concat(string str0, string str1, string str2);
    public static string Concat(string str0, string str1, string str2, string str3);
    public static string Copy(string str);
    public static bool Equals(string a, string b);
    public static string Format(IFormatProvider provider, string format, params object[ ] args);
    public static string Format(string format, object arg0);
    public static string Format(string format, params object[ ] args);
    public static string Format(string format, object arg0, object arg1);
    public static string Format(string format, object arg0, object arg1, object arg2);
    public static string Intern(string str);
    public static string IsInterned(string str);
    public static string Join(string separator, string[ ] value);
    public static string Join(string separator, string[ ] value, int startIndex, int count);
    public static bool operator !=(string a, string b);
    public static bool operator =(string a, string b);
// Public Instance Methods
    public object Clone( );
// implements ICloneable
    public int CompareTo(object value);
// implements IComparable
    public int CompareTo(string strB);
    public void CopyTo(int sourceIndex, char[ ] destination, int destinationIndex, int count);
    public bool EndsWith(string value);
    public override bool Equals(object obj);
// overrides object
    public bool Equals(string value);
    public CharEnumerator GetEnumerator( );
    public override int GetHashCode( );
// overrides object
    public TypeCode GetTypeCode( );
// implements IConvertible
    public int IndexOf(char value);
    public int IndexOf(char value, int startIndex);
    public int IndexOf(char value, int startIndex, int count);
    public int IndexOf(string value);
    public int IndexOf(string value, int startIndex);
    public int IndexOf(string value, int startIndex, int count);
    public int IndexOfAny(char[ ] anyOf);

```

```

public int IndexOfAny(char[ ] anyOf, int startIndex);
public int IndexOfAny(char[ ] anyOf, int startIndex, int count);
public string Insert(int startIndex, string value);
public int LastIndexOf(char value);
public int LastIndexOf(char value, int startIndex);
public int LastIndexOf(char value, int startIndex, int count);
public int LastIndexOf(string value);
public int LastIndexOf(string value, int startIndex);
public int LastIndexOf(string value, int startIndex, int count);
public int LastIndexOfAny(char[ ] anyOf);
public int LastIndexOfAny(char[ ] anyOf, int startIndex);
public int LastIndexOfAny(char[ ] anyOf, int startIndex, int count);
public string PadLeft(int totalWidth);
public string PadLeft(int totalWidth, char paddingChar);
public string PadRight(int totalWidth);
public string PadRight(int totalWidth, char paddingChar);
public string Remove(int startIndex, int count);
public string Replace(char oldChar, char newChar);
public string Replace(string oldValue, string newValue);
public string[ ] Split(params char[ ] separator);
public string[ ] Split(char[ ] separator, int count);
public bool StartsWith(string value);
public string Substring(int startIndex);
public string Substring(int startIndex, int length);
public char[ ] ToCharArray( );
public char[ ] ToCharArray(int startIndex, int length);
public string ToLower( );
public string ToLower(System.Globalization.CultureInfo culture);
public override string ToString( );
// overrides object
public string ToString(IFormatProvider provider);
// implements IConvertible
public string ToUpper( );
public string ToUpper(System.Globalization.CultureInfo culture);
public string Trim( );
public string Trim(params char[ ] trimChars);
public string TrimEnd(params char[ ] trimChars);
public string TrimStart(params char[ ] trimChars);
}

```

Returned By

Multiple types

Passed To

Multiple types

[Team LiB]

◀ PREVIOUS

NEXT ▶

SystemException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll) *class*

This class is the base class of exceptions that represent .NET runtime errors. In contrast, `ApplicationException` is the base class for user-defined exceptions.

```
public class SystemException : Exception {  
    // Public Constructors  
    public SystemException( );  
    public SystemException(string message);  
    public SystemException(string message, Exception innerException);  
    // Protected Constructors  
    protected SystemException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy

Object → `Exception(System.Runtime.Serialization.ISerializable)` → `SystemException`

Subclasses

Multiple types

ThreadStaticAttribute

serializable


System (mscorlib.dll)

class

This attribute designates that a static field should not be shared between threads. Each thread receives a separate instance of this field and can set and retrieve values for it without causing potential synchronization problems. This also means that each thread has a copy of the static field that may contain different values.

```
public class ThreadStaticAttribute : Attribute {  
    // Public Constructors  
    public ThreadStaticAttribute( );  
}
```

Hierarchy



Valid On

Field

TimeSpan CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This class encapsulates a positive or negative interval of time that can be used for arithmetic operations and greater-than or less-than comparisons. Internally, the `TimeSpan` is stored as a number of *ticks*, each of which is equal to 100 nanoseconds. You can convert a string into a `TimeSpan` using the static `Parse()` method.

You can evaluate a time span in terms of days, hours, seconds, and so on, by using the appropriate `Total` property. The corresponding properties that are not preceded with the word `Total` return only one component of the time span. (For example, the `TotalHours` property returns 1.5 for a time span of an hour and a half, while `Hours` returns 1 for a time span of one hour.)

The `TimeSpan` static methods prefixed with `From` are useful for quickly creating a time span for use as an argument for a method call, as in `myApp.SetTimeSpan(TimeSpan.FromMinutes(10))`.

```
public struct TimeSpan : IComparable {
// Public Constructors
    public TimeSpan(int hours, int minutes, int seconds);
    public TimeSpan(int days, int hours, int minutes, int seconds);
    public TimeSpan(int days, int hours, int minutes, int seconds, int milliseconds);
    public TimeSpan(long ticks);
// Public Static Fields
    public static readonly TimeSpan MaxValue;
// =10675199.02:48:05.4775807
    public static readonly TimeSpan MinValue;
// =-10675199.02:48:05.4775808
    public const long TicksPerDay;
// =8640000000000
    public const long TicksPerHour;
// =360000000000
    public const long TicksPerMillisecond;
// =10000
    public const long TicksPerMinute;
// =600000000
    public const long TicksPerSecond;
// =1000000
    public static readonly TimeSpan Zero;
// =00:00:00
// Public Instance Properties
    public int Days{get; }
    public int Hours{get; }
    public int Milliseconds{get; }
    public int Minutes{get; }
    public int Seconds{get; }
```



```

    public long Ticks{get; }
    public double TotalDays{get; }
    public double TotalHours{get; }
    public double TotalMilliseconds{get; }
    public double TotalMinutes{get; }
    public double TotalSeconds{get; }
// Public Static Methods
    public static int Compare(TimeSpan t1, TimeSpan t2);
    public static bool Equals(TimeSpan t1, TimeSpan t2);
    public static TimeSpan FromDays(double value);
    public static TimeSpan FromHours(double value);
    public static TimeSpan FromMilliseconds(double value);
    public static TimeSpan FromMinutes(double value);
    public static TimeSpan FromSeconds(double value);
    public static TimeSpan FromTicks(long value);
    public static TimeSpan Parse(string s);
    public static TimeSpan operator -(TimeSpan t);
    public static TimeSpan operator -(TimeSpan t1, TimeSpan t2);
    public static TimeSpan operator +(TimeSpan t);
    public static TimeSpan operator +(TimeSpan t1, TimeSpan t2);
    public static bool operator !=(TimeSpan t1, TimeSpan t2);
    public static bool operator <(TimeSpan t1, TimeSpan t2);
    public static bool operator <=(TimeSpan t1, TimeSpan t2);
    public static bool operator ==(TimeSpan t1, TimeSpan t2);
    public static bool operator >(TimeSpan t1, TimeSpan t2);
    public static bool operator >=(TimeSpan t1, TimeSpan t2);
// Public Instance Methods
    public TimeSpan Add(TimeSpan ts);
    public int CompareTo(object value);
// implements IComparable
    public TimeSpan Duration( );
    public override bool Equals(object value);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public TimeSpan Negate( );
    public TimeSpan Subtract(TimeSpan ts);
    public override string ToString( );
// overrides ValueType
}

```

Hierarchy

Object → ValueType → TimeSpan(IComparable)

Returned By

DateTime.{Subtract(), TimeOfDay},
 System.Diagnostics.Process.{PrivilegedProcessorTime, TotalProcessorTime,

```
UserProcessorTime}, System.Diagnostics.ProcessThread. {PrivilegedProcessorTime,
TotalProcessorTime, UserProcessorTime}, System.Globalization.DaylightTime.Delta,
TimeZone.GetUtcOffset( ), System.Xml.XmlConvert.ToTimeSpan( )
```

Passed To

Multiple types

[\[Team LiB \]](#)

TimeZone

CF 1.0, serializable

System (mscorlib.dll)

abstract class

This abstract class encapsulates a time zone. You cannot create a `TimeZone` instance directly because different time zones require different implementations of methods that involve time offsets due to daylight savings time. The most useful member of the `TimeZone` class is the static `CurrentTimeZone` property, which provides a `TimeZone` object based on the localization settings of the current system.

```
public abstract class TimeZone {
// Protected Constructors
    protected TimeZone( );
// Public Static Properties
    public static TimeZone CurrentTimeZone {get; }
// Public Instance Properties
    public abstract string DaylightName {get; }
    public abstract string StandardName {get; }
// Public Static Methods
    public static bool IsDaylightSavingTime(DateTime time,
        System.Globalization.DaylightTime daylightTimes);
// Public Instance Methods
    public abstract DaylightTime GetDaylightChanges(int year);
    public abstract TimeSpan GetUtcOffset(DateTime time);
    public virtual bool IsDaylightSavingTime(DateTime time);
    public virtual DateTime ToLocalTime(DateTime time);
    public virtual DateTime ToUniversalTime(DateTime time);
}
```

Type

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

abstract class

Type is an abstract base class that encapsulates the metadata for any .NET type. You can get a **Type** object by the `GetType()` method, which is inherited by all .NET types, or by the `typeof` operator in C#.

The **Type** is used most often for reflection. You can get a complete description of an object's metadata, including methods, fields, properties, and events of a class, as well as the module and the assembly in which the class is defined. The `GetMethods()` method, such as `GetEvents()` and `GetConstructors()`, which return arrays of the objects. You can use the singular methods, such as `GetEvent()`, to retrieve a single type object that matches specific criteria, including inherited, private, and protected members.

```
public abstract class Type : System.Reflection.MemberInfo, System.Reflection.IReflect {
    // Protected Constructors
    protected Type( );
    // Public Static Fields
    public static readonly char Delimiter;
    // =0x0000002E
    public static readonly Type[] EmptyTypes;
    // =System.Type[]
    public static readonly MemberFilter FilterAttribute;
    // =System.Reflection.MemberFilter
    public static readonly MemberFilter FilterName;
    // =System.Reflection.MemberFilter
    public static readonly MemberFilter FilterNameIgnoreCase;
    // =System.Reflection.MemberFilter
    public static readonly object Missing;
    // =System.Reflection.Missing
    // Public Static Properties
    public static Binder DefaultBinder{get; }
    // Public Instance Properties
    public abstract Assembly Assembly{get; }
    public abstract string AssemblyQualifiedName{get; }
    public TypeAttributes Attributes{get; }
    public abstract Type BaseType{get; }
    public override Type DeclaringType{get; }
    // overrides System.Reflection.MemberInfo
    public abstract string FullName{get; }
    public abstract Guid GUID{get; }
    public bool HasElementType{get; }
    public bool IsAbstract{get; }
    public bool IsAnsiClass{get; }
    public bool IsArray{get; }
    public bool IsAutoClass{get; }
    public bool IsAutoLayout{get; }
```

```

public bool IsByRef{get; }
public bool IsClass{get; }
public bool IsCOMObject{get; }
public bool IsContextful{get; }
public bool IsEnum{get; }
public bool IsExplicitLayout{get; }
public bool IsImport{get; }
public bool IsInterface{get; }
public bool IsLayoutSequential{get; }
public bool IsMarshalByRef{get; }
public bool IsNestedAssembly{get; }
public bool IsNestedFamANDAssem{get; }
public bool IsNestedFamily{get; }
public bool IsNestedFamORAssem{get; }
public bool IsNestedPrivate{get; }
public bool IsNestedPublic{get; }
public bool IsNotPublic{get; }
public bool IsPointer{get; }
public bool IsPrimitive{get; }
public bool IsPublic{get; }
public bool IsSealed{get; }
public bool IsSerializable{get; }
public bool IsSpecialName{get; }
public bool IsUnicodeClass{get; }
public bool IsValueType{get; }
public override MemberTypes MemberType{get; }
// overrides System.Reflection.MemberInfo
public abstract Module Module{get; }
public abstract string Namespace{get; }
public override Type ReflectedType{get; }
// overrides System.Reflection.MemberInfo
public abstract RuntimeTypeHandle TypeHandle{get; }
public ConstructorInfo TypeInitializer{get; }
public abstract Type UnderlyingSystemType{get; }
// implements System.Reflection.IReflect
// Public Static Methods
public static Type GetType(string typeName);
public static Type GetType(string typeName, bool throwOnError);
public static Type GetType(string typeName, bool throwOnError, bool ignoreCase);
public static Type[] GetTypeArray(object[] args);
public static TypeCode GetTypeCode(Type type);
public static Type GetTypeFromCLSID(Guid clsid);
public static Type GetTypeFromCLSID(Guid clsid, bool throwOnError);
public static Type GetTypeFromCLSID(Guid clsid, string server);
public static Type GetTypeFromCLSID(Guid clsid, string server, bool throwOnError);
public static Type GetTypeFromHandle(RuntimeTypeHandle handle);
public static Type GetTypeFromProgID(string progID);
public static Type GetTypeFromProgID(string progID, bool throwOnError);
public static Type GetTypeFromProgID(string progID, string server);
public static Type GetTypeFromProgID(string progID, string server, bool throwOnError);
public static RuntimeTypeHandle GetTypeHandle(object o);

```

```

// Public Instance Methods
public override bool Equals(object o);
// overrides object
public bool Equals(Type o);
public virtual Type[ ] FindInterfaces(System.Reflection.TypeFilter filter,
    object filterCriteria);
public virtual MemberInfo[ ] FindMembers(System.Reflection.MemberTypes memberType,
    System.ReflectionSystemobject filterCriteria);.Reflection.MemberFilter filter,
    .BindingFlags bindingAttr,
public virtual int GetArrayRank( );
public ConstructorInfo GetConstructor(System.Reflection.BindingFlags bindingAttr, Sy
    Type[ System.Reflection.ParameterModifier[ ] modifiers); ] types,
    System.Reflection.CallingConventions callConvention,
public ConstructorInfo GetConstructor(System.Reflection.BindingFlags bindingAttr,
    System.Reflection.ParameterModifier[ ] modifiers); System.Reflection.Binder bin
    Type[ ] types,
public ConstructorInfo GetConstructor(Type[ ] types);
public ConstructorInfo[ ] GetConstructors( );
public abstract ConstructorInfo[ ] GetConstructors(System.Reflection.BindingFlags bi
public virtual MemberInfo[ ] GetDefaultMembers( );
public abstract Type GetElementType( );
public EventInfo GetEvent(string name);
public abstract EventInfo GetEvent(string name, System.Reflection.BindingFlags bindi
public virtual EventInfo[ ] GetEvents( );
public abstract EventInfo[ ] GetEvents(System.Reflection.BindingFlags bindingAttr);
public FieldInfo GetField(string name);
public abstract FieldInfo GetField(string name, System.Reflection.BindingFlags bindi
// implements System.Reflection.IReflect
public FieldInfo[ ] GetFields( );
public abstract FieldInfo[ ] GetFields(System.Reflection.BindingFlags bindingAttr)
// implements System.Reflection.IReflect
public override int GetHashCode( );
// overrides object
public Type GetInterface(string name);
public abstract Type GetInterface(string name, bool ignoreCase);
public virtual InterfaceMapping GetInterfaceMap(Type interfaceType);
public abstract Type[ ] GetInterfaces( );
public MemberInfo[ ] GetMember(string name);
public virtual MemberInfo[ ] GetMember(string name, System.Reflection.BindingFlags b
// implements System.Reflection.IReflect
public virtual MemberInfo[ ] GetMember(string name, System.Reflection.MemberTypes ty
    System.Reflection.BindingFlags bindingAttr);
public MemberInfo[ ] GetMembers( );
public abstract MemberInfo[ ] GetMembers(System.Reflection.BindingFlags bindingAttr)
// implements System.Reflection.IReflect
public MethodInfo GetMethod(string name);
public MethodInfo GetMethod(string name, System.Reflection.BindingFlags bindingAttr)
// implements System.Reflection.IReflect

```

```

    public MethodInfo GetMethod(string name, System.Reflection.BindingFlags bindingAttr,
        System.Reflection.BinderSystem.Reflection.ParameterModifier[ ] modifiers); bind
        System.Reflection.CallingConventions callConvention,
    public MethodInfo GetMethod(string name, System.Reflection.BindingFlags bindingAttr
System.Reflection.Binder binder, Type[ ] types, System.Reflection.ParameterModifier[ ] ;
// implements System.Reflection.IReflect
    public MethodInfo GetMethod(string name, Type[ ] types);
    public MethodInfo GetMethod(string name, Type[ ] types, System.Reflection.ParameterM
    public MethodInfo[ ] GetMethods( );
    public abstract MethodInfo[ ] GetMethods(System.Reflection.BindingFlags bindingAttr)
// implements System.Reflection.IReflect
    public Type GetNestedType(string name);
    public abstract Type GetNestedType(string name, System.Reflection.BindingFlags bindi
    public Type[ ] GetNestedTypes( );
    public abstract Type[ ] GetNestedTypes(System.Reflection.BindingFlags bindingAttr);
    public PropertyInfo[ ] GetProperties( );
    public abstract PropertyInfo[ ] GetProperties(System.Reflection.BindingFlags bindingAt
// implements System.Reflection.IReflect
    public PropertyInfo GetProperty(string name);
    public PropertyInfo GetProperty(string name, System.Reflection.BindingFlags bindingA
// implements System.Reflection.IReflect
    public PropertyInfo GetProperty(string name, System.Reflection.BindingFlags bindingA
        System.Reflection.Binder binder, Type returnType, Type[ ] types,
        System.Reflection.ParameterModifier[ ] modifiers)
// implements System.Reflection.IReflect
    public PropertyInfo GetProperty(string name, Type returnType);
    public PropertyInfo GetProperty(string name, Type[ ] types);
    public PropertyInfo GetProperty(string name, Type returnType, Type[ ] types);
    public PropertyInfo GetProperty(string name, Type returnType, Type[ ] types,
        System.Reflection.ParameterModifier[ ] modifiers);
    public object InvokeMember(string name, System.Reflection.BindingFlags invokeAttr,
        System.Reflection.Binder binder, object target, object[ ] args);
    public object InvokeMember(string name, System.Reflection.BindingFlags invokeAttr,
        System.Reflection.Binder binder, object target, object[ ] args,
        System.Globalization.CultureInfo culture);
    public abstract object InvokeMember(string name, System.Reflection.BindingFlags invo
        System.Reflection.Binder binder, object target, object[ ] args,
        System.Reflection.ParameterModifier[ ] modifiers System.Globalization.Culture
// implements System.Reflection.IReflect
    public virtual bool IsAssignableFrom(Type c);
    public virtual bool IsInstanceOfType(object o);
    public virtual bool IsSubclassOf(Type c);
    public override string ToString( );
// overrides object
// Protected Instance Methods
    protected abstract TypeAttributes GetAttributeFlagsImpl( );
    protected abstract ConstructorInfo GetConstructorImpl(System.Reflection.BindingFlags
        System.Reflection.Binder binder, System.Reflection.CallingConventions callConve
        System.Reflection.ParameterModifier[ ] modifiers);

```

```
protected abstract MethodInfo GetMethodImpl(string name,
    System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder,
    System.Reflection.CallingConventions callConvention, Type[] types, System.Refle
protected abstract PropertyInfo GetPropertyImpl(string name, System.Reflection.Bindi
    System.Reflection.Binder binder, Type returnType, Type[] types, System.Reflect
protected abstract bool HasElementTypeImpl( );
protected abstract bool IsArrayImpl( );
protected abstract bool IsByRefImpl( );
protected abstract bool IsCOMObjectImpl( );
protected virtual bool IsContextfulImpl( );
protected virtual bool IsMarshalByRefImpl( );
protected abstract bool IsPointerImpl( );
protected abstract bool IsPrimitiveImpl( );
protected virtual bool IsValueTypeImpl( );
}
```

Hierarchy

Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvider) → 1

Subclasses

System.Reflection.TypeDelegator , System.Reflection.Emit.{EnumBuilder , TypeBuilder}

Returned By

Multiple types

Passed To

Multiple types

[Team LiB]

TypeCode

CF 1.0, serializable

System (mscorlib.dll)

enum

This enumeration specifies the type of an object. It is available for all objects that implement the `IConvertible` interface. If the object does not implement this interface, use its `GetType()` method (derived from `System.Object`) to return an instance of the `Type` class, which provides a `Type.GetTypeCode()` method.

The `TypeCode` enumeration includes members for most simple value types. If you use this method on an object that is not explicitly represented in this enumeration, the catch-all value `Object` is returned.

```
public enum TypeCode {
    Empty = 0,
    Object = 1,
    DBNull = 2,
    Boolean = 3,
    Char = 4,
    SByte = 5,
    Byte = 6,
    Int16 = 7,
    UInt16 = 8,
    Int32 = 9,
    UInt32 = 10,
    Int64 = 11,
    UInt64 = 12,
    Single = 13,
    Double = 14,
    Decimal = 15,
    DateTime = 16,
    String = 18
}
```

Hierarchy

Object → ValueType → Enum(IComparable, IFormattable, IConvertible) → TypeCode

Returned By

Multiple types

Passed To

`Convert.ChangeType(), System.Runtime.Serialization.FormatterConverter.Convert(),`

System.Runtime.Serialization.IFormatterConverter.Convert()

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

TypeInitializationException

ECMA 1.0,
serializable


System (mscorlib.dll)

sealed class

This class provides a wrapper around an exception thrown by the .NET class initializer. The underlying exception is accessible through `InnerException`.

```
public sealed class TypeInitializationException : SystemException {  
    // Public Constructors  
    public TypeInitializationException(string fullTypeName, Exception innerException);  
    // Public Instance Properties  
    public string TypeName{get; }  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
}
```

Hierarchy



TypeLoadException

CF 1.0, ECMA 1.0,
serializable

System (mscorlib.dll)

class

This exception signals that a class (or its assembly) cannot be found or loaded by the .NET runtime.

```
public class TypeLoadException : SystemException {  
    // Public Constructors  
    public TypeLoadException( );  
    public TypeLoadException(string message);  
    public TypeLoadException(string message, Exception inner);  
    // Protected Constructors  
    protected TypeLoadException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public override string Message{get; }  
    // overrides Exception  
    public string TypeName{get; }  
    // Public Instance Methods  
    public override void GetObjectData( System.Runtime.Serialization.SerializationInfo i.  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
}
```

Hierarchy

Object → Exception(System.Runtime.Serialization.ISerializable) → SystemException →
TypeLoadException

Subclasses

DllNotFoundException , EntryPointNotFoundException

TypeUnloadedException

ECMA 1.0,
serializable


System (mscorlib.dll)

class

This exception signals an attempt to access a **Type** that has been unloaded.

```
public class TypeUnloadedException : SystemException {  
    // Public Constructors  
    public TypeUnloadedException( );  
    public TypeUnloadedException(string message);  
    public TypeUnloadedException(string message, Exception innerException);  
    // Protected Constructors  
    protected TypeUnloadedException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



UInt16

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This structure is the value type for 16-bit unsigned integers (which range from 0 to 65,535). It is not CLS-compliant (although `Int16` is). This is also available in C# through the `ushort` alias.

```
public struct UInt16 : IComparable, IFormattable, IConvertible {
    // Public Static Fields
    public const ushort MaxValue;
    // =65535
    public const ushort MinValue;
    // =0
    // Public Static Methods
    public static ushort Parse(string s);
    public static ushort Parse(string s, IFormatProvider provider);
    public static ushort Parse(string s, System.Globalization.NumberStyles style);
    public static ushort Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
    // Public Instance Methods
    public int CompareTo(object value);
    // implements IComparable
    public override bool Equals(object obj);
    // overrides ValueType
    public override int GetHashCode( );
    // overrides ValueType
    public TypeCode GetTypeCode( );
    // implements IConvertible
    public override string ToString( );
    // overrides ValueType
    public string ToString(IFormatProvider provider);
    // implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
    // implements IFormattable
}
```

Hierarchy

Object → ValueType → UInt16(IComparable, IFormattable, IConvertible)

Returned By

BitConverter.ToUInt16(), Convert.ToUInt16(), Decimal.ToUInt16(),

```
IConvertible.ToInt16( ), System.IO.BinaryReader.ReadUInt16( ),  
System.Runtime.Serialization.FormatterConverter.ToInt16( ),  
System.Runtime.Serialization.IFormatterConverter.ToInt16( ),  
System.Runtime.Serialization.SerializationInfo.GetUInt16( ),  
System.Xml.XmlConvert.ToInt16( )
```

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

UInt32

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This structure is the value type for 32-bit unsigned integers (which range from 0 to 4,294,967,295). It is not CLS-compliant (although `Int32` is). This structure is also available in C# through the `uint` alias.

```
public struct UInt32 : IComparable, IFormattable, IConvertible {
    // Public Static Fields
    public const uint MaxValue;
    // =4294967295
    public const uint MinValue;
    // =0
    // Public Static Methods
    public static uint Parse(string s);
    public static uint Parse(string s, IFormatProvider provider);
    public static uint Parse(string s, System.Globalization.NumberStyles style);
    public static uint Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
    // Public Instance Methods
    public int CompareTo(object value);
    // implements IComparable
    public override bool Equals(object obj);
    // overrides ValueType
    public override int GetHashCode( );
    // overrides ValueType
    public TypeCode GetTypeCode( );
    // implements IConvertible
    public override string ToString( );
    // overrides ValueType
    public string ToString(IFormatProvider provider);
    // implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
    // implements IFormattable
}
```

Hierarchy

Object → ValueType → UInt32(IComparable, IFormattable, IConvertible)

Returned By


```
BitConverter.ToInt32( ), Convert.ToInt32( ), Decimal.ToInt32( ),  
IConvertible.ToInt32( ), System.IO.BinaryReader.ReadUInt32( ),  
System.Reflection.AssemblyAlgorithmIdAttribute.AlgorithmId,  
System.Reflection.AssemblyFlagsAttribute.Flags,  
System.Runtime.Serialization.FormatterConverter.ToInt32( ),  
System.Runtime.Serialization.IFormatterConverter.ToInt32( ),  
System.Runtime.Serialization.SerializationInfo.GetUInt32( ), UIntPtr.ToInt32( ),  
System.Xml.XmlConvert.ToInt32( )
```

Passed To

Multiple types

[\[Team LiB \]](#)

UInt64

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This structure is the value type for 64-bit unsigned integers (which range from 0 to 1.84×10^{20}). It is not CLS-compliant (although `Int64` is). This structure is also available in C# through the `ulong` alias.

```
public struct UInt64 : IComparable, IFormattable, IConvertible {
    // Public Static Fields
    public const ulong MaxValue;
    // =18446744073709551615
    public const ulong MinValue;
    // =0
    // Public Static Methods
    public static ulong Parse(string s);
    public static ulong Parse(string s,
        IFormatProvider provider);
    public static ulong Parse(string s, System.Globalization.NumberStyles style);
    public static ulong Parse(string s, System.Globalization.NumberStyles style,
        IFormatProvider provider);
    // Public Instance Methods
    public int CompareTo(object value);
    // implements IComparable
    public override bool Equals(object obj);
    // overrides ValueType
    public override int GetHashCode( );
    // overrides ValueType
    public TypeCode GetTypeCode( );
    // implements IConvertible
    public override string ToString( );
    // overrides ValueType
    public string ToString(IFormatProvider provider);
    // implements IConvertible
    public string ToString(string format);
    public string ToString(string format, IFormatProvider provider)
    // implements IFormattable
}
```

Hierarchy

Object → ValueType → UInt64(IComparable, IFormattable, IConvertible)

Returned By

```
BitConverter.ToInt64( ), Convert.ToInt64( ), Decimal.ToInt64( ),  
IConvertible.ToInt64( ), System.IO.BinaryReader.ReadUInt64( ),  
System.IO.IsolatedStorage.IsolatedStorage.{CurrentSize, MaximumSize},  
System.Runtime.Serialization.FormatterConverter.ToInt64( ),  
System.Runtime.Serialization.IFormatterConverter.ToInt64( ),  
System.Runtime.Serialization.SerializationInfo.GetUInt64( ), UIntPtr.ToInt64( ),  
System.Xml.XmlConvert.ToInt64( )
```

Passed To

Multiple types

[\[Team LIB \]](#)

UIntPtr

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

struct

This structure is provided mainly for symmetry with `IntPtr`. Use `IntPtr`, which is CLS-compliant, instead.

```
public struct UIntPtr : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public UIntPtr(uint value);
    public UIntPtr(ulong value);
    public UIntPtr(void *value);
// Public Static Fields
    public static readonly UIntPtr Zero;
// =0
// Public Static Properties
    public static int Size{get; }
// Public Static Methods
    public static bool operator !=(UIntPtr value1, UIntPtr value2);
    public static bool operator ==(UIntPtr value1, UIntPtr value2);
    public static explicit operator uint(UIntPtr value);
    public static explicit operator ulong(UIntPtr value);
    public static explicit operator UIntPtr(uint value);
    public static explicit operator UIntPtr(ulong value);
    public static explicit operator UIntPtr(void *value);
    public static explicit operator Void(UIntPtr value);
// Public Instance Methods
    public override bool Equals(object obj);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public void* ToPointer( );
    public override string ToString( );
// overrides ValueType
    public uint ToUInt32( );
    public ulong ToUInt64( );
}
```

Hierarchy

Object → ValueType → UIntPtr(System.Runtime.Serialization.ISerializable)

Passed To

```
System.Threading.Thread.{VolatileRead( ), VolatileWrite( )}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

UnauthorizedAccessException

CF 1.0, ECMA
1.0,
serializable


System (mscorlib.dll)

class

This exception signals a failed attempt to access a resource (for example, trying to delete a read-only file

```
public class UnauthorizedAccessException : SystemException {  
    // Public Constructors  
    public UnauthorizedAccessException( );  
    public UnauthorizedAccessException(string message);  
    public UnauthorizedAccessException(string message,  
        Exception inner);  
    // Protected Constructors  
    protected UnauthorizedAccessException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



UnhandledExceptionEventArgs

ECMA 1.0,
serializable

System (mscorlib.dll)

class

This class is passed as an argument to an `UnhandledExceptionHandler` event handler. Its `IsTerminating` property specifies whether the CLR is in the process of shutting down.

```
public class UnhandledExceptionEventArgs : EventArgs {  
    // Public Constructors  
    public UnhandledExceptionEventArgs(object exception, bool isTerminating);  
    // Public Instance Properties  
    public object ExceptionObject {get; }  
    public bool IsTerminating {get; }  
}
```

Hierarchy



Passed To

```
UnhandledExceptionHandler.{BeginInvoke( ), Invoke( )}
```

UnhandledExceptionHandler

ECMA 1.0,
serializable

System (mscorlib.dll)

delegate

This delegate specifies the signature for an event handler that responds to the `AppDomain.UnhandledException` event. This event is triggered by an exception that is not handled by the application domain.

```
public delegate void UnhandledExceptionHandler(object sender, UnhandledExceptionEventArgs e);
```

Associated Events

```
AppDomain.UnhandledException += UnhandledExceptionHandler;
```


Uri CF 1.0, ECMA 1.0, serializable, marshal by reference

System (system.dll)

class

This class encapsulates a complete URI (Uniform Resource Identifier) and provides various parts of it through properties. For example, you can get the **Scheme** (e.g., http, https, mailto) and the **Port** number. For http, the default port is 80, if not specified in the **Uri** (ftp uses port 21, https uses 443, and mailto uses 25). You can also retrieve the query-string arguments-including the initial question mark-from the **Query** property, or the fragment portion-including the fragment marker (#)-from the **Fragment** property. Some Boolean properties include **IsLoopback**, which indicates **true** if the **Uri** references the local host, and **IsUnc**, which indicates **true** if the **Uri** is a UNC path (such as `\\server\folder`).

The **Uri** constructors perform some basic cleanup of your parameters before creating a **Uri**, including converting the scheme and hostname to lowercase, removing default and blank port numbers, and removing the trailing slash (/). Instances of **Uri** have read-only properties. To modify a **Uri**, use a **UriBuilder** object.

The **Uri** class also provides static helper methods such as **EscapeString**(), which converts a string to a valid URL by converting all characters with an ASCII value greater than 127 to hexadecimal representation. The **CheckHostName**() and **CheckSchemeName**() methods accept a string and check if it is syntactically valid for the given property (although they do not attempt to determine if a host or URI exists).

The **Uri** class is used by many .NET types, including some in ASP.NET, although you may find many other uses for it as a type-safe way to store and exchange URL information.

```
public class Uri : MarshalByRefObject , System.Runtime.Serialization.ISerializable {
// Public Constructors
    public Uri(string uriString);
    public Uri(string uriString, bool dontEscape);
    public Uri(Uri baseUri, string relativeUri);
    public Uri(Uri baseUri, string relativeUri, bool dontEscape);
// Protected Constructors
    protected Uri(System.Runtime.Serialization.SerializationInfo serializationInfo,
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Static Fields
    public static readonly string SchemeDelimiter;
// =:/
    public static readonly string UriSchemeFile;
// =file
    public static readonly string UriSchemeFtp;
// =ftp
    public static readonly string UriSchemeGopher;
```

```

// =gopher
    public static readonly string UriSchemeHttp;
// =http
    public static readonly string UriSchemeHttps;
// =https
    public static readonly string UriSchemeMailto;
// =mailto
    public static readonly string UriSchemeNews;
// =news
    public static readonly string UriSchemeNntp;
// =nntp
// Public Instance Properties
    public string AbsolutePath{get; }
    public string AbsoluteUri{get; }
    public string Authority{get; }
    public string Fragment{get; }
    public string Host{get; }
    public UriHostNameType HostNameType{get; }
    public bool IsDefaultPort{get; }
    public bool IsFile{get; }
    public bool IsLoopback{get; }
    public bool IsUnc{get; }
    public string LocalPath{get; }
    public string PathAndQuery{get; }
    public int Port{get; }
    public string Query{get; }
    public string Scheme{get; }
    public string[] Segments{get; }
    public bool UserEscaped{get; }
    public string UserInfo{get; }
// Public Static Methods
    public static UriHostNameType CheckHostName(string name);
    public static bool CheckSchemeName(string schemeName);
    public static int FromHex(char digit);
    public static string HexEscape(char character);
    public static char HexUnescape(string pattern, ref int index);
    public static bool IsHexDigit(char character);
    public static bool IsHexEncoding(string pattern, int index);
// Protected Static Methods
    protected static string EscapeString(string str);
    protected static bool IsExcludedCharacter(char character);
// Public Instance Methods
    public override bool Equals(object comparand);
// overrides object
    public override int GetHashCode( );
// overrides object
    public string GetLeftPart(UriPartial part);
    public string MakeRelative(Uri toUri);
    public override string ToString( );
// overrides object

```

```
// Protected Instance Methods
protected virtual void Canonicalize( );
protected virtual void CheckSecurity( );
protected virtual void Escape( );
protected virtual bool IsBadFileSystemCharacter(char character);
protected virtual bool IsReservedCharacter(char character);
protected virtual void Parse( );
protected virtual string Unescape(string path);
}
```

Hierarchy

Object → MarshalByRefObject → Uri(System.Runtime.Serialization.ISerializable)

Returned By

```
System.Net.Cookie.CommentUri, System.Net.HttpWebRequest.Address,
System.Net.IWebProxy.GetProxy( ), System.Net.ServicePoint.Address,
System.Net.WebProxy.{Address, GetProxy( )}, System.Net.WebRequest.RequestUri,
System.Net.WebResponse.ResponseUri, UriBuilder.Uri, System.Xml.XmlResolver.ResolveUri(
)
```

Passed To

Multiple types

[\[Team LiB \]](#)

UriBuilder

ECMA 1.0

System (system.dll)

class

Every instance of `Uri` is immutable. This class wraps a `Uri` object and allows you to modify some of its properties without needing to create a new `Uri`. It is analogous to the `System.Text.StringBuilder` class for strings.

```
public class UriBuilder {
// Public Constructors
    public UriBuilder( );
    public UriBuilder(string uri);
    public UriBuilder(string schemeName, string hostName);
    public UriBuilder(string scheme, string host, int portNumber);
    public UriBuilder(string scheme, string host, int port, string pathValue);
    public UriBuilder(string scheme, string host, int port, string path, string extraValue);
    public UriBuilder(Uri uri);
// Public Instance Properties
    public string Fragment{set; get; }
    public string Host{set; get; }
    public string Password{set; get; }
    public string Path{set; get; }
    public int Port{set; get; }
    public string Query{set; get; }
    public string Scheme{set; get; }
    public Uri Uri{get; }
    public string UserName{set; get; }
// Public Instance Methods
    public override bool Equals(object rparam);
// overrides object
    public override int GetHashCode( );
// overrides object
    public override string ToString( );
// overrides object
}
```

UriFormatException

CF 1.0, ECMA 1.0,
serializable


System (system.dll)

class

This exception indicates that you attempted to use an invalid URI, usually in the `Uri` constructor. For a d of the URI format, see <http://www.ietf.org/rfc/rfc2396.txt> .

```
public class UriFormatException : FormatException {  
    // Public Constructors  
    public UriFormatException( );  
    public UriFormatException(string textString);  
    // Protected Constructors  
    protected UriFormatException(System.Runtime.Serialization.SerializationInfo serializ.  
        System.Runtime.Serialization.StreamingContext streamingContext);  
}
```

Hierarchy



UriHostNameType

CF 1.0, ECMA 1.0,
serializable


System (system.dll)

enum

This enumeration is used for the `Uri.CheckHostName()` method. `Basic` indicates that the host is set, but cannot be determined.

```
public enum UriHostNameType {  
    Unknown = 0 ,  
    Basic = 1 ,  
    Dns = 2 ,  
    IPv4 = 3 ,  
    IPv6 = 4  
}
```

Hierarchy



Returned By

```
Uri.{CheckHostName( ), HostNameType}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UriPartial CF 1.0, ECMA 1.0, serializable

System (system.dll) *enum*

This enumeration is used for the `Uri.GetLeftPart()` method. For example, the URL `http://www.oreilly.com/index.html#toch` has a **Scheme** of `http://`, an **Authority** of `www.oreilly.com`, and a **Path** of `http://www.oreilly.com/index.html` (everything up to, but not including, the query delimiter `?` or the fragment delimiter `#`).

```
public enum UriPartial {  
    Scheme = 0,  
    Authority = 1,  
    Path = 2  
}
```

Hierarchy

Object → ValueType → Enum(IComparable, IFormattable, IConvertible) → UriPartial

Passed To

`Uri.GetLeftPart()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ValueType

CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *abstract class*

This is the base class for all value types. A value type is a simple data structure, such as `UInt32`, or an enumeration. It is differentiated from a reference type (or object). Value types are stored on the stack rather than the .NET managed heap and are accessed directly rather than through a reference. Value types also behave differently from reference types, most notably in assignment operations (which create a copy of the data, not a duplicate reference to the same data) and comparison operations (which return `true` as long as the content of the two value types is the same). To define your own simple value types, use the `struct` keyword (use the `enum` keyword to define an enumeration). Value types are implicitly sealed.

```
public abstract class ValueType {
    // Protected Constructors
    protected ValueType( );
    // Public Instance Methods
    public override bool Equals(object obj);
    // overrides object
    public override int GetHashCode( );
    // overrides object
    public override string ToString( );
    // overrides object
}
```

Subclasses

Multiple types

Version CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll)

sealed class

This class represents a version number. The .NET framework uses it as the version of assemblies, operating systems, and network protocols. A version number consists of as many as four parts: a major, minor, build, and revision number. For some applications, such as the HTTP protocol, only the first two numbers (major and minor) are used.

```
public sealed class Version : ICloneable, IComparable {
// Public Constructors
    public Version( );
    public Version(int major, int minor);
    public Version(int major, int minor, int build);
    public Version(int major, int minor, int build, int revision);
    public Version(string version);
// Public Instance Properties
    public int Build{get; }
    public int Major{get; }
    public int Minor{get; }
    public int Revision{get; }
// Public Static Methods
    public static bool operator !=(Version v1, Version v2);
    public static bool operator <(Version v1, Version v2);
    public static bool operator <=(Version v1, Version v2);
    public static bool operator ==(Version v1, Version v2);
    public static bool operator >(Version v1, Version v2);
    public static bool operator >=(Version v1, Version v2);
// Public Instance Methods
    public object Clone( );
// implements ICloneable
    public int CompareTo(object version);
// implements IComparable
    public override bool Equals(object obj);
// overrides object
    public override int GetHashCode( );
// overrides object
    public override string ToString( );
// overrides object
    public string ToString(int fieldCount);
}
```

Returned By

```
Environment.Version, System.Net.HttpWebRequest.ProtocolVersion,  
System.Net.HttpWebResponse.ProtocolVersion, System.Net.ServicePoint.ProtocolVersion,  
OperatingSystem.Version, System.Reflection.AssemblyName.Version
```

Passed To

```
System.Net.HttpWebRequest.ProtocolVersion, OperatingSystem.OperatingSystem( ),  
System.Reflection.Assembly.GetSatelliteAssembly( ),  
System.Reflection.AssemblyName.Version
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Void CF 1.0, ECMA 1.0, serializable

System (mscorlib.dll) *struct*

This structure indicates that a method does not return any information, as in `public void Main()`. This type is available in C# through the `void` alias.

```
public struct Void {  
    // No public or protected members  
}
```

Hierarchy

Object → ValueType → Void

Returned By

Multiple types

Passed To

```
ArgIterator.ArgIterator( ), IntPtr.IntPtr( ), System.Reflection.Pointer.Box( ),  
UIntPtr.UIntPtr( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WeakReference

CF 1.0, serializable

System (mscorlib.dll)

class

This class encapsulates a *weak reference* to an object. By default, when you instantiate a .NET class, you create a strong reference, which prevents the garbage collector from removing the object and reclaiming memory. A weak reference, however, does not prevent an object from being released.

Objects that are weakly referenced can still be kept alive as long as there is at least one strong reference to them. That means a weak reference allows you to access an object as long as it is in use by another part of your application. For example, objects can be stored in a collection using a weak reference, but not kept alive just because they are in the collection.

To create a weakly referenced object, pass the name of the object to the **WeakReference** constructor. You can use the **IsAlive** property to check if the reference is valid, and the **Target** property to get a reference to the actual object. Assigning the **Target** property to another variable creates a strong reference.

You can set the **TrackResurrection** property to **true** in the constructor to maintain a *long* weak reference, which tracks an object during (or after) finalization.

```
public class WeakReference : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public WeakReference(object target);
    public WeakReference(object target, bool trackResurrection);
// Protected Constructors
    protected WeakReference(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public virtual bool IsAlive {get; }
    public virtual object Target {set; get; }
    public virtual bool TrackResurrection {get; }
// Public Instance Methods
    public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
// Protected Instance Methods
    protected override void Finalize( );
// overrides object
}
```

Passed To

```
GC.GetGeneration( )
```

Chapter 27. System.Collections

The `System.Collections` namespace provides basic functionality for collections of objects. It defines interfaces, base classes, and implementations for collections such as dictionaries, sorted lists, queues, and stacks. The base classes can also be extended to create specialized collection types. However, the `System.Collections.Specialized` namespace contains a set of extended collection types based on this namespace, so check there before creating your own types. [Figure 27-1](#) and [Figure 27-2](#) show the types in this namespace.

On first observation, the design of these collections seems somewhat awkward—for example, why does a "list" seem to be broken into two pieces: the `ICollection` interface and the `ArrayList` implementation? On top of this, the namespace defines a number of other interfaces, such as `IEnumerable` and `IEnumerator`, that seem unnecessary.

In fact, the design of the collection types in this namespace is quite similar to the designs of other container libraries such as the STL (Standard Template Library) in C++ and the Java Collections library in JDK 1.2. By separating the interface of a collection type (the concept of "list-ness" or "dictionary-ness") from the actual implementation, you are free to assume only the absolute minimum about the actual implementation used, and instead focus only on what is needed in order to carry out the work. For example, C#'s `foreach` construct works by silently using the `IEnumerable` interface to obtain an object that inherits the `IEnumerator` interface. Thus, a programmer could, if desired, create a custom type (perhaps modeling a hand of cards) that acts just as any other collection class does. Alternatively, the iterator (the type that inherits from `IEnumerator`) could be a "smart" iterator, knowing how to walk through (or skip past) types in the container itself. All this is possible solely because the interface is separated from the implementation; it is *decoupled*.

Figure 27-1. Collection types implementing `ICollection` and `IEnumerable`





Figure 27-2. More types from the System.Collections namespace



ArrayList CF 1.0, ECMA 1.0, serializable

System.Collections (mscorlib.dll) *class*

This class is similar to an array, but it can grow or shrink as needed. The **Capacity** property returns the maximum number of elements the **ArrayList** can hold. You can reduce the size by setting **Capacity** explicitly or using the **TrimToSize()** method. An **ArrayList** can be constructed empty or with an integer argument that sets its initial size. You can also pass the constructor an object that implements **ICollection** to fill the **ArrayList** with the contents of that object.

A number of methods are provided to modify the contents of the **ArrayList**. The **Add()** and **AddRange** methods add elements to the end of the list. **Insert()** and **InsertRange()** add new elements at a specified location within the list.

```
public class ArrayList : IList, ICollection, IEnumerable, ICloneable {
// Public Constructors
    public ArrayList( );
    public ArrayList(ICollection c);
    public ArrayList(int capacity);
// Public Instance Properties
    public virtual int Capacity{set; get; }
    public virtual int Count{get; }
// implements ICollection
    public virtual bool IsFixedSize{get; }
// implements IList
    public virtual bool IsReadOnly{get; }
// implements IList
    public virtual bool IsSynchronized{get; }
// implements ICollection
    public virtual object SyncRoot{get; }
// implements ICollection
    public virtual object this[object key]{set; get; }
// implements IList
// Public Static Methods
    public static ArrayList Adapter(IList list);
    public static ArrayList FixedSize(ArrayList list);
    public static IList FixedSize(IList list);
    public static ArrayList ReadOnly(ArrayList list);
    public static IList ReadOnly(IList list);
    public static ArrayList Repeat(object value, int count);
    public static ArrayList Synchronized(ArrayList list);
    public static IList Synchronized(IList list);
// Public Instance Methods
    public virtual int Add(object value);
// implements IList
```



```

    public virtual void AddRange(ICollection c);
    public virtual int BinarySearch(int index, int count, object value, IComparer comparer);
    public virtual int BinarySearch(object value);
    public virtual int BinarySearch(object value, IComparer comparer);
    public virtual void Clear( );
    // implements IList
    public virtual object Clone( );
    // implements ICloneable
    public virtual bool Contains(object item);
    // implements IList
    public virtual void CopyTo(Array array);
    public virtual void CopyTo(Array array, int arrayIndex);
    // implements ICollection
    public virtual void CopyTo(int index, Array array, int arrayIndex, int count);
    public virtual IEnumerator GetEnumerator( );
    // implements IEnumerable
    public virtual IEnumerator GetEnumerator(int index, int count);
    public virtual ArrayList GetRange(int index, int count);
    public virtual int IndexOf(object value);
    // implements IList
    public virtual int IndexOf(object value, int startIndex);
    public virtual int IndexOf(object value, int startIndex, int count);
    public virtual void Insert(int index, object value);
    // implements IList
    public virtual void InsertRange(int index, ICollection c);
    public virtual int LastIndexOf(object value);
    public virtual int LastIndexOf(object value, int startIndex);
    public virtual int LastIndexOf(object value, int startIndex, int count);
    public virtual void Remove(object obj);
    // implements IList
    public virtual void RemoveAt(int index);
    // implements IList
    public virtual void RemoveRange(int index, int count);
    public virtual void Reverse( );
    public virtual void Reverse(int index, int count);
    public virtual void SetRange(int index, ICollection c);
    public virtual void Sort( );
    public virtual void Sort(IComparer comparer);
    public virtual void Sort(int index, int count, IComparer comparer);
    public virtual Array ToArray(Type type);
    public virtual object[ ] ToArray( );
    public virtual void TrimToSize( );
}

```

Returned By

CollectionBase.InnerList , ReadOnlyCollectionBase.InnerList ,
System.Net.WebProxy.BypassArrayList

[Team LiB]

◀ PREVIOUS

NEXT ▶

BitArray

CF 1.0, serializable

System.Collections (mscorlib.dll) *sealed class*

This class stores a collection of bit values as Boolean types. The constructor takes many different forms of input to build the initial array, including arguments that specify the initial values and the size of the array. You can construct the `BitArray` with an existing array of bools, or with a byte or integer array. With an integer array, each `int` value becomes 32 bits of the `BitArray`, with the least significant bit mapped to the lowest index value (`MyBitArray[0]`) of the 32-bit range. A byte array uses 8 bits for each value in a similar fashion. A "bare" array can be constructed by simply providing an integer value for the number of bits in the `BitArray`, which are all set to `false` by default. Provide an additional Boolean value as a second argument to set the default values to either `true` or `false`.

The main functions of the `BitArray` class allow you to perform bitwise operations with two `BitArrays` of the same length. There are methods for `And()`, `Or()`, and `Xor()` that correspond to their respective bitwise operations. The `Not()` method inverts each bit value in the `BitArray`.

```
public sealed class BitArray : ICollection, IEnumerable, ICloneable {
// Public Constructors
    public BitArray(BitArray bits);
    public BitArray(bool[] values);
    public BitArray(byte[] bytes);
    public BitArray(int length);
    public BitArray(int[] values);
    public BitArray(int length, bool defaultValue);
// Public Instance Properties
    public int Count {get; }
// implements ICollection
    public bool IsReadOnly {get; }
    public bool IsSynchronized {get; }
// implements ICollection
    public int Length {set; get; }
    public object SyncRoot {get; }
// implements ICollection
    public bool this[int index] {set; get; }
// Public Instance Methods
    public BitArray And(BitArray value);
    public object Clone( );
// implements ICloneable
    public void CopyTo(Array array, int index);
// implements ICollection
    public bool Get(int index);
    public IEnumerator GetEnumerator( );
// implements IEnumerable
    public BitArray Not( );
```

```
public BitArray Or(BitArray value);  
public void Set(int index, bool value);  
public void SetAll(bool value);  
public BitArray Xor(BitArray value);  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

CaseInsensitiveComparer CF 1.0, serializable

System.Collections (mscorlib.dll) *class*

This type provides a means for case-insensitive comparison of string objects. This class implements the `Comparer.Compare()` method. You can obtain a standard comparer that uses the `System.Globalization.InvariantCulture` rules for string comparisons by using the `CaseInsensitiveComparer` instance returned from the static `DefaultInvariant` property.

```
public class CaseInsensitiveComparer : IComparer {
// Public Constructors
    public CaseInsensitiveComparer( );
    public CaseInsensitiveComparer(System.Globalization.CultureInfo culture);
// Public Static Properties
    public static CaseInsensitiveComparer Default{get; }
    public static CaseInsensitiveComparer DefaultInvariant{get; }
// Public Instance Methods
    public int Compare(object a, object b);
// implements IComparer
}
```

CaseInsensitiveHashCodeProvider

CF 1.0,
serializable

System.Collections (mscorlib.dll) *class*

When this object is passed to a `Hashtable` constructor, it overrides the `GetHashCode()` method to allow string comparison without regard to case. If you pass an instance of this type into the `Hashtable` constructor, you should also pass in an instance of `CaseInsensitiveComparer` to ensure that any comparison operations (such as sorting) are also performed in a case-insensitive fashion. You can obtain a standard provider that uses the `System.Globalization.InvariantCulture` rules for generating hashcodes by using the `CaseInsensitiveComparer` instance returned from the static `DefaultInvariant` property.

```
public class CaseInsensitiveHashCodeProvider : IHashCodeProvider {
// Public Constructors
    public CaseInsensitiveHashCodeProvider( );
    public CaseInsensitiveHashCodeProvider(System.Globalization.CultureInfo culture);
// Public Static Properties
    public static CaseInsensitiveHashCodeProvider Default{get; }
    public static CaseInsensitiveHashCodeProvider DefaultInvariant{get; }
// Public Instance Methods
    public int GetHashCode(object obj);
// implements IHashCodeProvider
}
```

CollectionBase

CF 1.0, serializable

System.Collections
(mscorlib.dll)*abstract
class*

This base collection type must be extended to create strongly typed collection objects. **CollectionBase** provides a modifiable collection. For a read-only collection of objects, use **ReadOnlyCollectionBase**. Many special collection types throughout the .NET framework derive from this class.

```
public abstract class CollectionBase : IList, ICollection, IEnumerable {
// Protected Constructors
    protected CollectionBase( );
// Public Instance Properties
    public int Count{get; }
// implements ICollection
// Protected Instance Properties
    protected ArrayList InnerList{get; }
    protected IList List{get; }
// Public Instance Methods
    public void Clear( );
// implements IList
    public IEnumerator GetEnumerator( );
// implements IEnumerable
    public void RemoveAt(int index);
// implements IList
// Protected Instance Methods
    protected virtual void OnClear( );
    protected virtual void OnClearComplete( );
    protected virtual void OnInsert(int index, object value);
    protected virtual void OnInsertComplete(int index, object value);
    protected virtual void OnRemove(int index, object value);
    protected virtual void OnRemoveComplete(int index, object value);
    protected virtual void OnSet(int index, object oldValue, object newValue);
    protected virtual void OnSetComplete(int index, object oldValue, object newValue);
    protected virtual void OnValidate(object value);
}
```

Subclasses

System.Diagnostics.{CounterCreationDataCollection, EventLogPermissionEntryCollection, PerformanceCounterPermissionEntryCollection}

[Team LiB]

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Comparer CF 1.0, ECMA 1.0, serializable

System.Collections (mscorlib.dll) *sealed class*

The **Comparer** class is used to compare two objects of the same type. The **Compare()** method takes two objects. If the first object is less than the second, a negative value is returned. If the first object is greater than the second, a positive value is returned. If the objects are equal, zero is returned. The comparisons of strings are case-sensitive. For case-insensitive string comparisons, use **CaseInsensitiveComparer**. You can obtain a standard comparer that uses the **System.Globalization.InvariantCulture** rules for string comparisons by using the **CaseInsensitiveComparer** instance returned from the static **DefaultInvariant** property.

```
public sealed class Comparer : IComparer {
// Public Constructors
    public Comparer(System.Globalization.CultureInfo culture);
// Public Static Fields
    public static readonly Comparer Default;
// =System.Collections.Comparer
    public static readonly Comparer DefaultInvariant;
// =System.Collections.Comparer
// Public Instance Methods
    public int Compare(object a, object b);
// implements IComparer
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

DictionaryBase

serializable

System.Collections
(mscorlib.dll)*abstract
class*

This abstract base class is used to implement specialized dictionary style collections. Classes derived from **DictionaryBase** allow for strongly typed key and value pairs. A set of protected instance methods is defined to be overridden by derived classes. These methods allow a class to specify customized processes when functions are performed on the derived object. For example, **OnSet()** lets you perform a function before you set a new element in the dictionary, while **OnSetComplete()** lets you perform a function after a value is set.

```
public abstract class DictionaryBase : IDictionary, ICollection, IEnumerable {
// Protected Constructors
    protected DictionaryBase( );
// Public Instance Properties
    public int Count{get; }
// implements ICollection
// Protected Instance Properties
    protected IDictionary Dictionary{get; }
    protected Hashtable InnerHashtable{get; }
// Public Instance Methods
    public void Clear( );
// implements IDictionary
    public void CopyTo(Array array, int index);
// implements ICollection
    public IDictionaryEnumerator GetEnumerator( );
// implements IDictionary
// Protected Instance Methods
    protected virtual void OnClear( );
    protected virtual void OnClearComplete( );
    protected virtual object OnGet(object key, object currentValue);
    protected virtual void OnInsert(object key, object value);
    protected virtual void OnInsertComplete(object key, object value);
    protected virtual void OnRemove(object key, object value);
    protected virtual void OnRemoveComplete(object key, object value);
    protected virtual void OnSet(object key, object oldValue, object newValue);
    protected virtual void OnSetComplete(object key, object oldValue, object newValue);
    protected virtual void OnValidate(object key, object value);
}
```

Subclasses

```
System.Diagnostics.{InstanceDataCollection, InstanceDataCollectionCollection}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)


DictionaryEntry CF 1.0, ECMA 1.0, serializable

System.Collections (mscorlib.dll) *struct*

This structure defines the special value type used for the elements of a dictionary collection. This type consists of a key and a value. A `DictionaryEntry` is retrieved by the `IDictionaryEnumerator.Entry` property.

```
public struct DictionaryEntry {  
    // Public Constructors  
    public DictionaryEntry(object key, object value);  
    // Public Instance Properties  
    public object Key{set; get; }  
    public object Value{set; get; }  
}
```

Hierarchy



Returned By

`IDictionaryEnumerator.Entry`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Hashtable CF 1.0, ECMA 1.0, serializable

System.Collections (mscorlib.dll) *class*

A *hashtable* is an associative array (dictionary) that contains key-value pairs. Each value is identified and key that is transformed into an integer value called a *hashcode*.

A hashtable is an efficient way to store and retrieve values in memory. It uses a fast algorithm to convert hash key. This hash key is used internally to determine which "bucket" a hashtable entry belongs to. Although it selects a bucket quickly, each bucket may contain more than one value. In this case, a linear search based on its hashcode. However, the fast bucket search offers such an advantage that a subsequent linear search has negligible impact on the overall performance of the hashtable.

Initially, a 1-to-1 ratio of buckets to values applies (called the *load factor*). However, as more items are added, the load factor is changed, and each bucket ends up holding more elements. Greater load factors reduce the number of buckets required to store the hashtable, but increase lookup time.

The first argument to the `Hashtable` constructor gives a value for its initial size or provides an existing `IList` of values will fill the `Hashtable`. A `Hashtable` automatically increases its size when all buckets are full. The `loadFactor` is optionally used to specify the load factor; the default is 1.0. You can also provide references to `IHashCodeProvider` and `IComparer` instances in the constructor to provide custom hashcode and key-sorting functionality.

Keys of varying types can be used as in a regular dictionary collection. A hashing algorithm is used to convert keys to a hashcode. This is accomplished by the `GetHashCode()` method of each key object, which is a virtual method of `Object`. `GetHashCode()` can be overridden to use a custom algorithm instead of the default hashing algorithm of the CLR. (See `CaseInsensitiveHashCodeProvider`.)

The `Keys` and `Values` properties retrieve `ICollection` objects containing the keys and values, respectively.

The `Hashtable` indexer allows you to get or retrieve a value by specific key. If a key already exists, its value is returned. The `Add()` method can also add a new key and value to a `Hashtable`, but throws an exception if the key already exists.

```
public class Hashtable : IDictionary, ICollection, IEnumerable, System.Runtime.Serialization.ISerializable,
    System.Runtime.Serialization.IDeserializationCallback, ICloneable {
// Public Constructors
    public Hashtable();
    public Hashtable(IDictionary d);
    public Hashtable(IDictionary d, IHashCodeProvider hcp, IComparer comparer);
    public Hashtable(IDictionary d, float loadFactor);
    public Hashtable(IDictionary d, float loadFactor, IHashCodeProvider hcp, IComparer comparer);
    public Hashtable(IHashCodeProvider hcp, IComparer comparer);
    public Hashtable(int capacity);
    public Hashtable(int capacity, IHashCodeProvider hcp, IComparer comparer);
    public Hashtable(int capacity, float loadFactor);
    public Hashtable(int capacity, float loadFactor, IHashCodeProvider hcp, IComparer comparer);
// Protected Constructors
```

```

        protected Hashtable(System.Runtime.Serialization.SerializationInfo info,
            System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public virtual int Count{get; }
// implements ICollection
    public virtual bool IsFixedSize{get; }
// implements IDictionary
    public virtual bool IsReadOnly{get; }
// implements IDictionary
    public virtual bool IsSynchronized{get; }
// implements ICollection
    public virtual ICollection Keys{get; }
// implements IDictionary
    public virtual object SyncRoot{get; }
// implements ICollection
    public virtual object this[object key]{set; get; }
// implements IDictionary
    public virtual ICollection Values{get; }
// implements IDictionary
// Protected Instance Properties
    protected IComparer comparer{set; get; }
    protected IHashCodeProvider hcp{set; get; }
// Public Static Methods
    public static Hashtable Synchronized(Hashtable table);
// Public Instance Methods
    public virtual void Add(object key, object value);
// implements IDictionary
    public virtual void Clear( );
// implements IDictionary
    public virtual object Clone( );
// implements ICloneable
    public virtual bool Contains(object key);
// implements IDictionary
    public virtual bool ContainsKey(object key);
    public virtual bool ContainsValue(object value);
    public virtual void CopyTo(Array array, int arrayIndex);
// implements ICollection
    public virtual IDictionaryEnumerator GetEnumerator( );
// implements IDictionary
    public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
    public virtual void OnDeserialization(object sender)
// implements System.Runtime.Serialization.IDeserializationCallback
    public virtual void Remove(object key);
// implements IDictionary
// Protected Instance Methods
    protected virtual int GetHash(object key);
    protected virtual bool KeyEquals(object item, object key);
}

```

Returned By

DictionaryBase.InnerHashtable ,
System.Collections.Specialized.CollectionsUtil.CreateCaseInsensitiveHashtable()

[Team LiB]

◀ PREVIOUS

NEXT ▶

ICollection

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface defines the basic characteristics of collection objects and implements three properties. **Count** gets the number of elements contained in a collection; **IsSynchronized** indicates whether the collection is thread-safe, and **SyncRoot** returns an object that synchronizes access to the collection (this is the object itself if the implementing class does not provide a **Synchronized()** method). **ICollection** also implements the **CopyTo()** method for copying elements to an **Array** object at a specified index.

```
public interface ICollection : IEnumerable {  
    // Public Instance Properties  
    public int Count {get; }  
    public bool IsSynchronized {get; }  
    public object SyncRoot {get; }  
    // Public Instance Methods  
    public void CopyTo(Array array, int index);  
}
```

Implemented By

Multiple types

Returned By

Multiple types

Passed To

```
ArrayList.{AddRange( ), ArrayList( ), InsertRange( ), SetRange( )}, Queue.Queue( ),  
Stack.Stack( )
```


IComparer

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface implements a method for comparing objects. `Compare()` determines whether an object is greater than (positive return value), less than (negative return value), or equal (zero) to another object. This interface is required for classes that need to sort elements or search collections.

```
public interface IComparer {  
    // Public Instance Methods  
    public int Compare(object x, object y);  
}
```

Implemented By

`CaseInsensitiveComparer`, `Comparer`

Returned By

`Hashtable.comparer`

Passed To

```
System.Array.{BinarySearch( ), Sort( )}, ArrayList.{BinarySearch( ), Sort( )},  
Hashtable.{comparer, Hashtable( )}, SortedList.SortedList( ),  
System.Collections.Specialized.ListDictionary.ListDictionary( ),  
System.Collections.Specialized.NameObjectCollectionBase.NameObjectCollectionBase( ),  
System.Collections.Specialized.NameValueCollection.NameValueCollection( ),  
System.Xml.XPath.XPathExpression.AddSort( )
```

I Dictionary

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This base interface for a collection of key/value elements defines the indexer (in C#, the `this` property; in VB.NET, the property marked as `Default`), as well as the `Keys` and `Values` properties that return collections containing the dictionary's keys or values, respectively. This interface also defines the methods by which the entries may be modified, such as `Add()`, `Clear()`, and `Remove()`.

```
public interface IDictionary : ICollection, IEnumerable {
    // Public Instance Properties
    public bool IsFixedSize {get; }
    public bool IsReadOnly {get; }
    public ICollection Keys {get; }
    public object this[object key]{set; get; }
    public ICollection Values {get; }
    // Public Instance Methods
    public void Add(object key, object value);
    public void Clear( );
    public bool Contains(object key);
    public IDictionaryEnumerator GetEnumerator( );
    public void Remove(object key);
}
```

Implemented By

DictionaryBase, Hashtable, SortedList,
System.Collections.Specialized.{HybridDictionary, ListDictionary}

Returned By

DictionaryBase.Dictionary, System.Environment.GetEnvironmentVariables()

Passed To

Hashtable.Hashtable(), SortedList.SortedList(),
System.Collections.Specialized.CollectionsUtil.CreateCaseInsensitiveHashtable(),
System.Diagnostics.EventLogInstaller.{Install(), Rollback(), Uninstall()}

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

I DictionaryEnumerator

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface is an enumerator for **Dictionary** collections. It defines three read-only properties that can be obtained from the currently selected element of the collection. The **Entry** property gets an entry (key and value) in the form of a **DictionaryEntry** object. **Key** and **Value** return the key and value of the current element.

```
public interface IDictionaryEnumerator : IEnumerator {  
    // Public Instance Properties  
    public DictionaryEntry Entry{get; }  
    public object Key{get; }  
    public object Value{get; }  
}
```

Returned By

```
DictionaryBase.GetEnumerator( ), Hashtable.GetEnumerator( ),  
IDictionary.GetEnumerator( ), SortedList.GetEnumerator( ),  
System.Collections.Specialized.HybridDictionary.GetEnumerator( ),  
System.Collections.Specialized.ListDictionary.GetEnumerator( )
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IEnumerable

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll)

interface

This interface exposes an enumerator to iterate over a collection. The `GetEnumerator()` method returns an `IEnumerator` for the object.

```
public interface IEnumerable {  
    // Public Instance Methods  
    public IEnumerator GetEnumerator( );  
}
```

Implemented By

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

I Enumerator

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface provides an enumerator to iterate over the elements of a collection. The **Current** property gets the current element in the iteration. **MoveNext()** advances to the next collection element. **Reset()** returns the position of the iteration to the start of the collection, just before the first element; an initial call to **MoveNext()** is necessary to retrieve the first element of the collection.

```
public interface IEnumerator {  
    // Public Instance Properties  
    public object Current{get; }  
    // Public Instance Methods  
    public bool MoveNext( );  
    public void Reset( );  
}
```

Implemented By

IDictionaryEnumerator, System.CharEnumerator,
System.Globalization.TextElementEnumerator,
System.Runtime.Serialization.SerializationInfoEnumerator

Returned By

Multiple types

IHashCodeProvider

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface implements a custom hash function to supply a hashcode to an object. Normally hashtables use `System.Object.GetHashCode()` for hash keys. However, if a `Hashtable` is constructed using an object that implements this interface, `GetHashCode()` can be used to provide a customized hash function. `CaseInsensitiveHashCodeProvider` is an example of a custom hash function.

```
public interface IHashCodeProvider {  
    // Public Instance Methods  
    public int GetHashCode(object obj);  
}
```

Implemented By

`CaseInsensitiveHashCodeProvider`

Returned By

`Hashtable.hcp`

Passed To

```
Hashtable.{Hashtable( ), hcp},  
System.Collections.Specialized.NameObjectCollectionBase.NameObjectCollectionBase( ),  
System.Collections.Specialized.NameValueCollection.NameValueCollection( )
```

IList

CF 1.0, ECMA 1.0

System.Collections (mscorlib.dll) *interface*

This interface defines the basic characteristics of an indexable collection of objects. All array and collection classes implement this interface. **IList** defines methods by adding an element to the end of a list (**Add**()), inserting or removing an element at a specific index (**Insert**() and **RemoveAt**()), or removing all elements. **Remove**() removes the first occurrence of a specific object from a list. Changing the elements of a list requires that the class be resizable and modifiable (see the **IsFixedSize** property). The **Contains**() method checks to see if a given value is contained in the list, while **IndexOf**() returns the index of an existing list value.

```
public interface IList : ICollection, IEnumerable {
    // Public Instance Properties
    public bool IsFixedSize{get; }
    public bool IsReadOnly{get; }
    public object this[int index]{set; get; }
    // Public Instance Methods
    public int Add(object value);
    public void Clear( );
    public bool Contains(object value);
    public int IndexOf(object value);
    public void Insert(int index, object value);
    public void Remove(object value);
    public void RemoveAt(int index);
}
```

Implemented By

```
ArrayList, CollectionBase, System.Array,
System.Collections.Specialized.StringCollection,
System.Diagnostics.TraceListenerCollection
```

Returned By

```
ArrayList.{FixedSize( ), ReadOnly( ), Synchronized( )}, CollectionBase.List,
SortedList.{GetKeyList( ), GetValueList( )}
```

Passed To

```
ArrayList.{Adapter( ), FixedSize( ), ReadOnly( ), Synchronized( )},
System.Net.Sockets.Socket.Select( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Queue

CF 1.0, serializable

System.Collections (mscorlib.dll)

class

This class describes a collection manipulated on a first-in, first-out basis. The newest elements are added to one end with the `Enqueue()` method, and the oldest are taken off the other end with `Dequeue()`. A `Queue` can be constructed as an empty collection or with the elements of an existing collection. The initial capacity can also be specified, although the default for an empty queue is 32. Normally, a `Queue` automatically increases its capacity when new elements exceed the current capacity, using a default growth factor of 2.0. (The growth factor is multiplied by the current capacity to determine the new capacity.) You may specify your own growth factor when you specify an initial capacity for the `Queue`.

The `Dequeue()` method returns the element at the beginning of the `Queue`, and simultaneously removes it. You can get the first element without removal by using `Peek()`. The contents of a `Queue` can be copied to an existing `Array` object using the `CopyTo()` method. `ToArray()` creates a new `Array` object with the contents of the `Queue`.

The `Queue` is not threadsafe. The `Synchronize()` method provides a wrapper for thread safety.

```
public class Queue : ICollection, IEnumerable, ICloneable {
// Public Constructors
    public Queue( );
    public Queue(ICollection col);
    public Queue(int capacity);
    public Queue(int capacity, float growFactor);
// Public Instance Properties
    public virtual int Count{get; }
// implements ICollection
    public virtual bool IsSynchronized{get; }
// implements ICollection
    public virtual object SyncRoot{get; }
// implements ICollection
// Public Static Methods
    public static Queue Synchronized(Queue queue);
// Public Instance Methods
    public virtual void Clear( );
    public virtual object Clone( );
// implements ICloneable
    public virtual bool Contains(object obj);
    public virtual void CopyTo(Array array, int index);
// implements ICollection
    public virtual object Dequeue( );
    public virtual void Enqueue(object obj);
    public virtual IEnumerator GetEnumerator( );
```

```
// implements IEnumerable
public virtual object Peek( );
public virtual object[ ] ToArray( );
public virtual void TrimToSize( );
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

ReadOnlyCollectionBase

serializable

System.Collections
(mscorlib.dll)

*abstract
class*

This abstract base class is for read-only collections, similar to `CollectionBase`.

```
public abstract class ReadOnlyCollectionBase : ICollection, IEnumerable {  
    // Protected Constructors  
    protected ReadOnlyCollectionBase( );  
    // Public Instance Properties  
    public int Count{get; }  
    // implements ICollection  
    // Protected Instance Properties  
    protected ArrayList InnerList{get; }  
    // Public Instance Methods  
    public IEnumerator GetEnumerator( );  
    // implements IEnumerable  
}
```

Subclasses

System.Diagnostics.{ProcessModuleCollection, ProcessThreadCollection}

SortedList

serializable

System.Collections (mscorlib.dll)

class

This class is a dictionary collection in which values can be retrieved either by associated key or by index (meaning that the elements are specifically ordered). Keys are sorted based on their object type (e.g., strings are alphabetically sorted). You can override the default key comparison methods by providing your own `IComparer`-implementing object to the `SortedList` constructor.

Many methods are defined to allow you to retrieve values by either key name or index value. The `IndexOfKey()` and `IndexOfValue()` methods return the zero-based index value of the specified key or value. `GetByIndex()` and `SetByIndex()` use the index values for their functionality.

```
public class SortedList : IDictionary, ICollection, IEnumerable, ICloneable {
// Public Constructors
    public SortedList( );
    public SortedList(IComparer comparer);
    public SortedList(IComparer comparer, int capacity);
    public SortedList(IDictionary d);
    public SortedList(IDictionary d, IComparer comparer);
    public SortedList(int initialCapacity);
// Public Instance Properties
    public virtual int Capacity{set; get; }
    public virtual int Count{get; }
// implements ICollection
    public virtual bool IsFixedSize{get; }
// implements IDictionary
    public virtual bool IsReadOnly{get; }
// implements IDictionary
    public virtual bool IsSynchronized{get; }
// implements ICollection
    public virtual ICollection Keys{get; }
// implements IDictionary
    public virtual object SyncRoot{get; }
// implements ICollection
    public virtual object this[object key]{set; get; }
// implements IDictionary
    public virtual ICollection Values{get; }
// implements IDictionary
// Public Static Methods
    public static SortedList Synchronized(SortedList list);
// Public Instance Methods
    public virtual void Add(object key, object value);
// implements IDictionary
    public virtual void Clear( );
```

```
// implements IDictionary
    public virtual object Clone( );
// implements ICloneable
    public virtual bool Contains(object key);
// implements IDictionary
    public virtual bool ContainsKey(object key);
    public virtual bool ContainsValue(object value);
    public virtual void CopyTo(Array array, int arrayIndex);
// implements ICollection
    public virtual object GetByIndex(int index);
    public virtual IDictionaryEnumerator GetEnumerator( );
// implements IDictionary
    public virtual object GetKey(int index);
    public virtual IList GetKeyList( );
    public virtual IList GetValueList( );
    public virtual int IndexOfKey(object key);
    public virtual int IndexOfValue(object value);
    public virtual void Remove(object key);
// implements IDictionary
    public virtual void RemoveAt(int index);
    public virtual void SetByIndex(int index, object value);
    public virtual void TrimToSize( );
}
```

Returned By

System.Collections.Specialized.CollectionsUtil.CreateCaseInsensitiveSortedList()

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Stack

CF 1.0, serializable

System.Collections (mscorlib.dll) *class*

This class implements a collection of objects manipulated in a last-in, first-out manner. The primary methods of a **Stack** are **Push()** and **Pop()**. **Push()** adds an element to the top of a stack and **Pop()** removes the top element from the stack. **Peek()** returns the top element without removing it from the stack.

```
public class Stack : ICollection, IEnumerable, ICloneable {
// Public Constructors
    public Stack( );
    public Stack(ICollection col);
    public Stack(int initialCapacity);
// Public Instance Properties
    public virtual int Count{get; }
// implements ICollection
    public virtual bool IsSynchronized{get; }
// implements ICollection
    public virtual object SyncRoot{get; }
// implements ICollection
// Public Static Methods
    public static Stack Synchronized(Stack stack);
// Public Instance Methods
    public virtual void Clear( );
    public virtual object Clone( );
// implements ICloneable
    public virtual bool Contains(object obj);
    public virtual void CopyTo(Array array, int index);
// implements ICollection
    public virtual IEnumerator GetEnumerator( );
// implements IEnumerable
    public virtual object Peek( );
    public virtual object Pop( );
    public virtual void Push(object obj);
    public virtual object[] ToArray( );
}
```

Chapter 28.


System.Collections.Specialized

The types defined in the `System.Collections` namespace are fine as general-purpose collection types, but frequently programmers require specialized semantics around a collection class; for example, a collection of booleans could be more efficiently stored as a single `System.Int64`, whereas simply placing `System.Boolean` instances into a general-purpose collection is far more wasteful, in both memory and processing time.

Additionally, programmers often grow frustrated with the lack of type-safety in the general-purpose containers; not only does a programmer have to typecast any object obtained out of the container, but the container itself holds no intrinsic logic to "screen out" unwanted types being inserted into the container. (This is in marked contrast to C++ template-based collections such as the STL, in which the attempt to put a string into a container of integers causes a compile-time error.)

Container specialization isn't limited to storage type; at times, a programmer desires different processing behavior than the general-purpose container provides. As an example, consider the `System.Collections.IDictionary` interface. Note that it clearly defines a mapping of keys to values; however, it is only implicitly understood that the exact same key must be produced to obtain the value desired. In most cases, this is exactly what's needed; however, there are times when a less stringent retrieval mechanism is preferred. For example, perhaps a case-insensitive match is wanted instead of doing an exact match for a string key. The `System.Collections.Specialized` namespace includes collections designed to address these cases. [Figure 28-1](#) shows the types in this namespace.

Figure 28-1. The `System.Collections.Specialized` namespace



BitVector32

CF 1.0

System.Collections.Specialized (system.dll)

struct

This structure defines a lightweight bit vector that can store booleans and 16-bit integers in a 32-bit structure. **Sections** hold single 16-bit integer values and are the building blocks of a BitVector32. Sections are created with **CreateSection()**. Each section is constructed with a maximum value for the integer it can hold. Except for the initial section, each subsequent section must provide a reference to the previous section in addition to the maximum value.

The indexer takes two forms. When indexed by a section name, that section's value can be set or retrieved. When indexed by an integer that specifies a bit in the vector, you can determine whether that bit is set or not (**true** or **false**).

```
public struct BitVector32 {
// Public Constructors
    public BitVector32(BitVector32 value);
    public BitVector32(int data);
// Public Instance Properties
    public int Data{get; }
    public int this(Section section){set; get; }
    public bool this[int bit]{set; get; }
// Public Static Methods
    public static int CreateMask( );
    public static int CreateMask(int previous);
    public static Section CreateSection(short maxValue);
    public static Section CreateSection(short maxValue, Section previous);
    public static string ToString(BitVector32 value);
// Public Instance Methods
    public override bool Equals(object o);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public override string ToString( );
// overrides ValueType
}
```

Hierarchy

System.Object → System.ValueType → BitVector32

BitVector32.Section

CF 1.0

System.Collections.Specialized
(system.dll)

struct

This structure represents a section of a bit vector that holds a single integer value. A `BitVector32.Section` instance is created by the `BitVector32.CreateSection()` method, which specifies the maximum value the `Section` can hold, and references the preceding `Section`, unless it is the first `Section` in the vector.

```
public struct BitVector32.Section {
// Public Instance Properties
    public short Mask{get; }
    public short Offset{get; }
// Public Static Methods
    public static string ToString(Section value);
// Public Instance Methods
    public override bool Equals(object o);
// overrides ValueType
    public override int GetHashCode( );
// overrides ValueType
    public override string ToString( );
// overrides ValueType
}
```

Hierarchy



CollectionsUtil

System.Collections.Specialized (system.dll) *class*

This class defines static methods to create special collections in which keys are sorted without respect to `CreateCaseInsensitiveHashtable()` creates a `Hashtable` , and `CreateCaseInsensitiveSortedList` creates a `System.Collections.SortedList` .

```
public class CollectionsUtil {  
    // Public Constructors  
    public CollectionsUtil( );  
    // Public Static Methods  
    public static Hashtable CreateCaseInsensitiveHashtable( );  
    public static Hashtable CreateCaseInsensitiveHashtable(System.Collections.IDictionary dictionary);  
    public static Hashtable CreateCaseInsensitiveHashtable(int capacity);  
    public static SortedList CreateCaseInsensitiveSortedList( );  
}
```

HybridDictionary

CF 1.0, serializable

System.Collections.Specialized
(system.dll)*class*

This class implements a standard dictionary collection with built-in capability for case-insensitive key comparison. Case-insensitivity can be specified during construction with a Boolean argument.

```
public class HybridDictionary : IDictionary, ICollection, IEnumerable {
// Public Constructors
    public HybridDictionary( );
    public HybridDictionary(bool caseInsensitive);
    public HybridDictionary(int initialSize);
    public HybridDictionary(int initialSize, bool caseInsensitive);
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public bool IsFixedSize{get; }
// implements System.Collections.IDictionary
    public bool IsReadOnly{get; }
// implements System.Collections.IDictionary
    public bool IsSynchronized{get; }
// implements ICollection
    public ICollection Keys{get; }
// implements System.Collections.IDictionary
    public object SyncRoot{get; }
// implements ICollection
    public object this[object key]{set; get; }
// implements System.Collections.IDictionary
    public ICollection Values{get; }
// implements System.Collections.IDictionary
// Public Instance Methods
    public void Add(object key, object value);
// implements System.Collections.IDictionary
    public void Clear( );
// implements System.Collections.IDictionary
    public bool Contains(object key);
// implements System.Collections.IDictionary
    public void CopyTo(Array array, int index);
// implements ICollection
    public IDictionaryEnumerator GetEnumerator( );
// implements System.Collections.IDictionary
    public void Remove(object key);
// implements System.Collections.IDictionary
```

}

[Team LiB]

◀ PREVIOUS

NEXT ▶

ListDictionary

CF 1.0, serializable

System.Collections.Specialized
(system.dll)*class*

This class is a simple implementation of a dictionary collection (`System.Collections.IDictionary`) for small lists. It implements the `IDictionary` methods and properties, and it is suggested for use with a small number of elements (less than 10). The overloaded constructor can optionally pass an `System.Collections.IComparer` reference, which may be used for case-insensitive key comparison or other special key type conversions.

```
public class ListDictionary : IDictionary, ICollection, IEnumerable {
// Public Constructors
    public ListDictionary( );
    public ListDictionary(System.Collections.IComparer comparer);
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public bool IsFixedSize{get; }
// implements System.Collections.IDictionary
    public bool IsReadOnly{get; }
// implements System.Collections.IDictionary
    public bool IsSynchronized{get; }
// implements ICollection
    public ICollection Keys{get; }
// implements System.Collections.IDictionary
    public object SyncRoot{get; }
// implements ICollection
    public object this[object key]{set; get; }
// implements System.Collections.IDictionary
    public ICollection Values{get; }
// implements System.Collections.IDictionary
// Public Instance Methods
    public void Add(object key, object value);
// implements System.Collections.IDictionary
    public void Clear( );
// implements System.Collections.IDictionary
    public bool Contains(object key);
// implements System.Collections.IDictionary
    public void CopyTo(Array array, int index);
// implements ICollection
    public IDictionaryEnumerator GetEnumerator( );
// implements System.Collections.IDictionary
    public void Remove(object key);
```

```
// implements System.Collections.IDictionary  
}
```

[\[Team LiB \]](#)

NameObjectCollectionBase

CF 1.0,
serializableSystem.Collections.Specialized
(system.dll)*abstract
class*

This abstract base class is for a hashtable-based collection of key/value pairs, in which the key is specific defines methods to be overridden by derived classes that allow for special comparing and sorting of key s

```
public abstract class NameObjectCollectionBase : ICollection, IEnumerable, System.Runtime
System.Runtime.Serialization.IDeserializationCallback {
// Protected Constructors
protected NameObjectCollectionBase( );
protected NameObjectCollectionBase(System.Collections.IHashCodeProvider hashProvider
System.Collections.IComparer comparer);
protected NameObjectCollectionBase(int capacity);
protected NameObjectCollectionBase(int capacity, System.Collections.IHashCodeProvide
System.Collections.IComparer comparer);
protected NameObjectCollectionBase(System.Runtime.Serialization.SerializationInfo in
System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
public virtual int Count{get; }
// implements ICollection
public virtual KeysCollection Keys{get; }
// Protected Instance Properties
protected bool IsReadOnly{set; get; }
// Public Instance Methods
public IEnumerator GetEnumerator( );
// implements IEnumerable
public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info
System.Runtime.Serialization.StreamingContext context);
// implements ISerializable
public virtual void OnDeserialization(object sender);
// implements System.Runtime.Serialization.IDeserializationCallback
// Protected Instance Methods
protected void BaseAdd(string name, object value);
protected void BaseClear( );
protected object BaseGet(int index);
protected object BaseGet(string name);
protected string[ ] BaseGetAllKeys( );
protected object[ ] BaseGetAllValues( );
protected object[ ] BaseGetAllValues(Type type);
protected string BaseGetKey(int index);
protected bool BaseHasKeys( );
```



```
protected void BaseRemove(string name);  
protected void BaseRemoveAt(int index);  
protected void BaseSet(int index, object value);  
protected void BaseSet(string name, object value);  
}
```

Subclasses

NameValueCollection

[Team LiB]

NameObjectCollectionBase.KeysCollection

CF 1.0,
serializable

System.Collections.Specialized (system.dll)

class

This class is a collection of key strings retrieved by the `NameObjectCollectionBase.Keys` property.

```
public class NameObjectCollectionBase.KeysCollection : ICollection, IEnumerable {  
    // Public Instance Properties  
    public int Count { get; }  
    // implements ICollection  
    public string this[int index] { get; }  
    // Public Instance Methods  
    public virtual string Get(int index);  
    public IEnumerator GetEnumerator( );  
    // implements IEnumerable  
}
```

NameValueCollection

CF 1.0, ECMA 1.0,
serializableSystem.Collections.Specialized
(system.dll)*class*

This class is a collection of keys and associated values composed of strings in which a single key may have multiple values associated with it. A multivalued entry is stored as a comma-separated list of the string values. Use the `Add()` method to append new values to existing values of a key. Using `Set()` or setting the value of a key name overwrites the existing value. You can use a string containing a comma-separated list to assign multiple values to a key.

The `GetValues()` method returns a string array containing all the values of the specified key (or index). An example of how this class is used is `System.Net.WebHeaderCollection`, which derives from it. A `WebHeaderCollection` contains the collection of various HTTP header names as key strings and their values. Headers such as `Accept` : often have multiple values (for example, MIME types for `Accept`).

```
public class NameValueCollection : NameObjectCollectionBase {
// Public Constructors
    public NameValueCollection( );
    public NameValueCollection(System.Collections.IHashCodeProvider hashProvider,
        System.Collections.IComparer comparer);
    public NameValueCollection(int capacity);
    public NameValueCollection(int capacity, System.Collections.IHashCodeProvider hashPr
        System.Collections.IComparer comparer);
    public NameValueCollection(int capacity, NameValueCollection col);
    public NameValueCollection(NameValueCollection col);
// Protected Constructors
    protected NameValueCollection(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public virtual string[] AllKeys{get; }
    public string this[int index]{get; }
    public string this[string name]{set; get; }
// Public Instance Methods
    public void Add(NameValueCollection c);
    public virtual void Add(string name, string value);
    public void Clear( );
    public void CopyTo(Array dest, int index);
// implements ICollection
    public virtual string Get(int index);
    public virtual string Get(string name);
    public virtual string GetKey(int index);
    public virtual string[] GetValues(int index);
}
```

```
public virtual string[ ] GetValues(string name);  
public bool HasKeys( );  
public virtual void Remove(string name);  
public virtual void Set(string name, string value);  
// Protected Instance Methods  
protected void InvalidateCachedArrays( );  
}
```

Hierarchy

```
System.Object → NameObjectCollectionBase(System.Collections.ICollection ,  
System.Collections.IEnumerable , System.Runtime.Serialization.ISerializable ,  
System.Runtime.Serialization.IDeserializationCallback) → NameValueCollection
```

Subclasses

```
System.Net.WebHeaderCollection
```

Returned By

```
System.Net.WebClient.QueryString
```

Passed To

```
System.Net.WebClient.{QueryString , UploadValues( )}
```

[Team LiB]

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

StringCollection

serializable

System.Collections.Specialized (system.dll)

class

This class is a special collection in which the elements are strings.

```
public class StringCollection : IList, ICollection, IEnumerable {  
    // Public Constructors  
    public StringCollection( );  
    // Public Instance Properties  
    public int Count{get; }  
    // implements ICollection  
    public bool IsReadOnly{get; }  
    // implements IList  
    public bool IsSynchronized{get; }  
    // implements ICollection  
    public object SyncRoot{get; }  
    // implements ICollection  
    public string this[int index]{set; get; }  
    // Public Instance Methods  
    public int Add(string value);  
    public void AddRange(string[] value);  
    public void Clear( );  
    // implements IList  
    public bool Contains(string value);  
    public void CopyTo(string[] array, int index);  
    public StringEnumerator GetEnumerator( );  
    public int IndexOf(string value);  
    public void Insert(int index, string value);  
    public void Remove(string value);  
    public void RemoveAt(int index);  
    // implements IList  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

StringDictionary

System.Collections.Specialized
(system.dll)

class

This class is a dictionary collection in which keys and values are all strings.

```

public class StringDictionary : IEnumerable {
// Public Constructors
    public StringDictionary( );
// Public Instance Properties
    public virtual int Count{get; }
    public virtual bool IsSynchronized{get; }
    public virtual ICollection Keys{get; }
    public virtual object SyncRoot{get; }
    public virtual string this[string key]{set; get; }
    public virtual ICollection Values{get; }
// Public Instance Methods
    public virtual void Add(string key, string value);
    public virtual void Clear( );
    public virtual bool ContainsKey(string key);
    public virtual bool ContainsValue(string value);
    public virtual void CopyTo(Array array, int index);
    public virtual IEnumerator GetEnumerator( );
// implements IEnumerable
    public virtual void Remove(string key);
}

```

Returned By

System.Diagnostics.ProcessStartInfo.EnvironmentVariables

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

StringEnumerator

System.Collections.Specialized
(system.dll) *class*

This type implements an enumerator for a `StringCollection`. This is returned by `StringCollection.GetEnumerator()`.

```
public class StringEnumerator {  
    // Public Instance Properties  
    public string Current {get; }  
    // Public Instance Methods  
    public bool MoveNext( );  
    public void Reset( );  
}
```

Returned By

`StringCollection.GetEnumerator()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 29. System.Diagnostics

Diagnostics are an important part of any software system. In addition to the obvious necessity of debugging the code, diagnostics can keep track of application performance and liveness, thus indicating a problem proactively, rather than waiting for the phone call from the system administrators.

Diagnostics means more than just compiling with debug symbols turned on. Certain code paths might want to execute only when diagnostics are turned on to full power, indicated by a compile-time switch. At other times, particularly in long-running systems (such as WebService-based systems), developers want to keep a log of the system's actions; frequently, debug reports from users are sketchy ("Um, when I clicked the button, it all just crashed"), and having a complete log of the system's actions can be invaluable in tracking the problem down. Not only can the log consist of custom-written messages (usually to a file), but the Windows Event Log is also available for use from within this namespace.

Diagnostics also includes the ability to track the health and performance of the application; under Windows 2000 and XP, this means interaction with the Performance utility. This is a powerful tool that can be launched from the Administrative Tools program group (under Windows NT, it is called Performance Monitor). By creating appropriate performance counters within the application, .NET programmers can give the system support staff (system administrators and production monitoring personnel, among others) the ability to monitor and track the application, even remotely. In addition to its diagnostic facilities, this namespace exposes operating system processes using the `Process` type. Use this type to launch new processes or take control of processes currently running on the system. The `ProcessThread` type lets you drill down into each thread that's running within a process for fine-grained control over running applications.

Most of the functionality in this namespace is disabled at runtime unless you've enabled debugging. If you are using command-line compilers, you can pass the `/d:DEBUG` switch to enable debugging (to enable tracing, use `/d:TRACE`). Alternatively, you can use the preprocessor directives `#define TRACE` or `#define DEBUG`. The advantage here is that you can leave all your debugging code in, and it does not affect your release builds. The related `/debug` switch adds debug symbols to your program. You need the debug symbols to obtain source file and line number information in stack traces or to run your program under the control of a debugger. In Visual Studio .NET, you can enable debugging and debug symbols by creating a debug build of your application.

Some diagnostic settings can be controlled using the application configuration file (`appname.exe.config`). This lets you control trace and debugging behavior without having to recompile. The root element in an application configuration file is the `<configuration>` element. Create a `<system.diagnostics>` element within that root element. All the settings mentioned in this chapter must be contained in that `<system.diagnostics>` element. [Figure 29-1](#), [Figure 29-2](#), [Figure 29-3](#), and [Figure 29-4](#) show the types in this namespace.

BooleanSwitch

System.Diagnostics (system.dll) *class*

This class provides a simple on/off switch for debugging and tracing. Consult `Enabled` to check if the switch has been set. You can configure a Boolean switch using the application configuration file (see `Switch`). To use a `BooleanSwitch`, you must enable tracing or debugging at compilation time.

```
public class BooleanSwitch : Switch {  
    // Public Constructors  
    public BooleanSwitch(string displayName, string description);  
    // Public Instance Properties  
    public bool Enabled {set; get; }  
}
```

Hierarchy

System.Object → Switch → BooleanSwitch

ConditionalAttribute

CF 1.0, ECMA 1.0,
serializable

System.Diagnostics
(mscorlib.dll)

sealed class

This attribute marks a method as callable only if a compilation variable, given by `conditionString`, is set. Compilation variables can be set by supplying `/define:VARIABLE` as a command-line argument to the compiler or by supplying `#define VARIABLE` directives in the source code itself. If the compilation variable is not set, calls to the marked method are ignored.

```
public sealed class ConditionalAttribute : Attribute {  
    // Public Constructors  
    public ConditionalAttribute(string conditionString);  
    // Public Instance Properties  
    public string ConditionString {get; }  
}
```


Hierarchy



Valid On

Method

Figure 29-1. Process, EventLog, and related classes



CounterCreationDataserializable

System.Diagnostics (system.dll)class

This class is used to specify a type, name, and help string for a custom counter.

```
public class CounterCreationData {  
    // Public Constructors  
    public CounterCreationData( );  
    public CounterCreationData(string counterName, string counterHelp,  
        PerformanceCounterType counterType);  
    // Public Instance Properties  
    public string CounterHelp{set; get; }  
    public string CounterName{set; get; }  
    public PerformanceCounterType CounterType{set; get; }  
}
```

Returned By

CounterCreationDataCollection.this

Passed To

CounterCreationDataCollection.{Add(), AddRange(), Contains(), CopyTo(),
CounterCreationDataCollection(), IndexOf(), Insert(), Remove(), this}


CounterCreationDataCollection serializable

System.Diagnostics (system.dll) *class*

This class is a strongly-typed collection of `CounterCreationData` objects. Use `Add()` and `AddRange()` to add single or multiple values respectively to the end of the collection. `Insert()` allows you to add an item at any position in the collection. `Remove()` and `RemoveAt()` allow you to remove items from the collection.

```
public class CounterCreationDataCollection : CollectionBase {
// Public Constructors
    public CounterCreationDataCollection( );
    public CounterCreationDataCollection(CounterCreationData[] value);
    public CounterCreationDataCollection(CounterCreationDataCollection value);
// Public Instance Properties
    public CounterCreationData this[int index]{set; get; }
// Public Instance Methods
    public int Add(CounterCreationData value);
    public void AddRange(CounterCreationData[] value);
    public void AddRange(CounterCreationDataCollection value);
    public bool Contains(CounterCreationData value);
    public void CopyTo(CounterCreationData[] array, int index);
    public int IndexOf(CounterCreationData value);
    public void Insert(int index, CounterCreationData value);
    public virtual void Remove(CounterCreationData value);
// Protected Instance Methods
    protected override void OnInsert(int index, object value);
// overrides System.Collections.CollectionBase
}
```

Hierarchy




Returned By

PerformanceCounterInstaller.Counters

Passed To

PerformanceCounterCategory.Create()

Figure 29-2. More classes from the System.Diagnostics namespace




CounterSample

System.Diagnostics (system.dll) *struct*

This structure contains a performance counter's raw data. It represents a sample taken at a particular point in time (as indicated by the `CounterTimeStamp` property). `Calculate()` returns a counter's performance data as a `float` value. The `CalculateAverage()` method returns values for calculated performance counters, such as averages.

`TimeStamp` and `TimeStamp100nSec` return the system timestamp, with varying degrees of accuracy. (`TimeStamp` is most precise, reporting a timestamp within .1 milliseconds.) `BaseValue` specifies a base raw value for several multiple counters. `RawValue` contains the sample's numeric value. `SystemFrequency` represents how often the system counter is updated, and `CounterFrequency` represents how often samples are taken by the counter. Both frequencies are in milliseconds..

Figure 29-3. TraceListener and related classes



```
public struct CounterSample {
// Public Constructors
    public CounterSample(long rawValue, long baseValue, long counterFrequency, long syst
        long timeStamp, long timeStamp100nSec, PerformanceCounterType counterType);
    public CounterSample(long rawValue, long baseValue, long counterFrequency, long syst
        long timeStamp, long timeStamp100nSec, PerformanceCounterType counterType, long
// Public Static Fields
    public static CounterSample Empty;
// =System.Diagnostics.CounterSample
// Public Instance Properties
    public long BaseValue{get; }
```

```
public long CounterFrequency{get; }
public long CounterTimeStamp{get; }
public PerformanceCounterType CounterType{get; }
public long RawValue{get; }
public long SystemFrequency{get; }
public long TimeStamp{get; }
public long TimeStamp100nSec {get; }
// Public Static Methods
public static float Calculate(CounterSample counterSample);
public static float Calculate(CounterSample counterSample, CounterSample nextCounter,
}
```

Hierarchy

System.Object → System.ValueType → CounterSample


Returned By

InstanceData.Sample , PerformanceCounter.NextSample()

Passed To

CounterSampleCalculator.ComputeCounterValue() , InstanceData.InstanceData()

Figure 29-4. CodeAccessSecurityAttributes, collections, and relate



[Team LiB]

◀ PREVIOUS

NEXT ▶

[Team LiB]

◀ PREVIOUS

NEXT ▶

CounterSampleCalculator

System.Diagnostics (system.dll) *sealed class*

This class provides `ComputeCounterValue()`, which interprets `CounterSample` structures. It returns a floating-point value that represents the data contained in one or two samples.

```
public sealed class CounterSampleCalculator {  
    // Public Static Methods  
    public static float ComputeCounterValue(CounterSample newSample);  
    public static float ComputeCounterValue(CounterSample oldSample, CounterSample newSa  
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

Debug

CF 1.0

System.Diagnostics (system.dll) *sealed class*

This class provides methods that allow you to print debugging information and use assertions. The `Listeners` collection contains a set of listeners that are responsible for reporting debugging operations through the user interface or trace log. That collection initially includes an instance of `DefaultTraceListener`. Add a `TraceListener` using the `Add()` method of the `Listeners` property. Use `Close()` or `Flush()` to close or flush all listeners that write output to a file, such as the `TextWriterTraceListener`. Set `AutoFlush` to `true` to automatically flush each listener after a write operation.

`Assert()` specifies a condition and an optional error message to display if the condition is `false`. If the `DefaultTraceListener`'s `AssertUiEnabled` property is `true`, the error message is displayed as a dialog, and the user has the opportunity to abort the program, retry (test the assertion again), or ignore the failed assertion. Otherwise, the error message is written to `DefaultTraceListener.LogFileName`. `Fail()` acts like an assertion in which the condition is always `false`.

`Indent()` and `Unindent()` allow you to set the level of indentation when you call `WriteLine()`. Use `IndentSize` to set the number of spaces corresponding to indented text. `Write()` and `WriteLine()` send output to each `TraceListener` in the `Listeners` collection, and `WriteIf()` and `WriteLineIf()` allow you to conditionally output debug information.

You can use the application configuration file to add or remove trace listeners. Look up `System.Diagnostics.TraceListener` in the .NET Framework SDK Documentation for details.

```
public sealed class Debug {
// Public Static Properties
    public static bool AutoFlush {set; get; }
    public static int IndentLevel {set; get; }
    public static int IndentSize {set; get; }
    public static TraceListenerCollection Listeners {get; }
// Public Static Methods
    public static void Assert(bool condition);
    public static void Assert(bool condition, string message);
    public static void Assert(bool condition, string message, string detailMessage);
    public static void Close( );
    public static void Fail(string message);
    public static void Fail(string message, string detailMessage);
    public static void Flush( );
    public static void Indent( );
    public static void Unindent( );
    public static void Write(object value);
    public static void Write(object value, string category);
    public static void Write(string message);
}
```

```
public static void Write(string message, string category);
public static void WriteIf(bool condition, object value);
public static void WriteIf(bool condition, object value, string category);
public static void WriteIf(bool condition, string message);
public static void WriteIf(bool condition, string message, string category);
public static void WriteLine(object value);
public static void WriteLine(object value, string category);
public static void WriteLine(string message);
public static void WriteLine(string message, string category);
public static void WriteLineIf(bool condition, object value);
public static void WriteLineIf(bool condition, object value, string category);
public static void WriteLineIf(bool condition, string message);
public static void WriteLineIf(bool condition, string message, string category);
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DebuggableAttribute

CF 1.0

System.Diagnostics
(mscorlib.dll)

sealed class

This attribute contains two properties that indicate if code can be debugged. `IsJITOptimizerDisabled` indicates whether optimization has been turned off, and `IsJITTrackingEnabled` indicates whether debug symbols have been placed in the code. This attribute is automatically applied by the compiler, with `isJITTrackingEnabled` set to `false` and `isJITOptimizerDisabled` set to `true`. Use the `/debug` command-line compiler switch to include debug symbols (`isJITTrackingEnabled=true`), and use `/optimize` to enable compile-time optimizations (`isJITOptimizerDisabled=false`).

```
public sealed class DebuggableAttribute : Attribute {  
    // Public Constructors  
    public DebuggableAttribute(bool isJITTrackingEnabled, bool isJITOptimizerDisabled);  
    // Public Instance Properties  
    public bool IsJITOptimizerDisabled {get; }  
    public bool IsJITTrackingEnabled {get; }  
}
```

Hierarchy

System.Object → System.Attribute → DebuggableAttribute

Valid On

Assembly, Module

Debugger

CF 1.0

System.Diagnostics (mscorlib.dll)

sealed class

This class enables you to control the debugger from the debugged code. If a debugger is executing your code, `IsAttached` returns `true`. `Break()` sets a breakpoint and causes the debugger to pause. `Log()` logs output to the debugger window. The `Launch()` method launches the debugger and attaches it to your process, returning `true` if successful or if the debugger is already attached. `Launch()` returns `false` if the debugger could not be attached.

```
public sealed class Debugger {  
    // Public Constructors  
    public Debugger( );  
    // Public Static Fields  
    public static readonly string DefaultCategory;  
    // Public Static Properties  
    public static bool IsAttached { get; }  
    // Public Static Methods  
    public static void Break( );  
    public static bool IsLogging( );  
    public static bool Launch( );  
    public static void Log(int level, string category, string message);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DebuggerHiddenAttribute

serializable

System.Diagnostics
(mscorlib.dll)

sealed class

This attribute is used by the Visual Studio debugger. Visual Studio does not allow you to set a breakpoint in a method marked with this attribute, nor does it stop inside such a method.

```
public sealed class DebuggerHiddenAttribute : Attribute {  
    // Public Constructors  
    public DebuggerHiddenAttribute( );  
}
```

Hierarchy



Valid On

Constructor, Method, Property

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DebuggerStepThroughAttribute

CF 1.0,
serializable

System.Diagnostics
(mscorlib.dll)

sealed class

This attribute is used by the Visual Studio debugger. Visual Studio does not stop in a method marked with this attribute, but it does allow you to set a breakpoint in such a method.

```
public sealed class DebuggerStepThroughAttribute : Attribute {  
    // Public Constructors  
    public DebuggerStepThroughAttribute( );  
}
```

Hierarchy

System.Object → System.Attribute → DebuggerStepThroughAttribute

Valid On

Class, Struct, Constructor, Method

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DefaultTraceListener

CF 1.0, marshal by reference, disposable

System.Diagnostics (system.dll) *class*

This class provides the default `TraceListener`. By default, an instance of this class is available in the `Listeners` collection of the `Debug` and `Trace` classes. The `Write()` and `WriteLine()` methods output to the log and to the active debugger (if any) via the Win32 API function `OutputDebugString`. The log file is initially unset, so output goes only to the debugger. To specify a log file, set `LogFileName`. You may also set a logfile in the `<assert>` element of the application configuration file's `<system.diagnostics>` section, as in `<assert logfile="logfile.log"/>`.

`AssertUiEnabled` determines whether to use the user interface for failed assertions. If `true`, .NET uses a dialog box with the options Abort, Retry, or Fail. Whether this property is set to `true` or `false`, .NET always writes messages to the `LogFileName`, if one is specified. The `AssertUiEnabled` property can be set using the `<assert>` element, as in `<assert assertuienabled="false"/>` (the default is `true`).

```
public class DefaultTraceListener : TraceListener {
// Public Constructors
    public DefaultTraceListener( );
// Public Instance Properties
    public bool AssertUiEnabled{set; get; }
    public string LogFileName{set; get; }
// Public Instance Methods
    public override void Fail(string message);
// overrides TraceListener
    public override void Fail(string message, string detailMessage);
// overrides TraceListener
    public override void Write(string message);
// overrides TraceListener
    public override void WriteLine(string message);
// overrides TraceListener
}
```

Hierarchy

System.Object → System.MarshalByRefObject → TraceListener(System.IDisposable) → DefaultTraceListener

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

EntryWrittenEventArgs

System.Diagnostics (system.dll) *class*

These event arguments are passed by an `EventLog.EntryWritten` event.

```
public class EntryWrittenEventArgs : EventArgs {  
    // Public Constructors  
    public EntryWrittenEventArgs( );  
    public EntryWrittenEventArgs(EventLogEntry entry);  
    // Public Instance Properties  
    public EventLogEntry Entry{get; }  
}
```

Hierarchy

System.Object → System.EventArgs → EntryWrittenEventArgs

Passed To

```
EntryWrittenEventHandler.{BeginInvoke( ), Invoke( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

EntryWrittenEventHandler

serializable

System.Diagnostics (system.dll)

delegate

This delegate supports the `EventLog.EntryWritten` event.

```
public delegate void EntryWrittenEventHandler(object sender, EntryWrittenEventArgs e);
```

Associated Events

```
EventLog.EntryWritten( )
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

EventLog marshal by reference, disposable

System.Diagnostics (system.dll) *class*

This class accesses Windows event logs that are accessible through the *Event Viewer* administrative tool. It contains three logs by default: the Application Log, System Log, and Security Log. The Security Log is read-only; you can't write events to it. Whenever you need to raise an event, you must select a system-wide unique event source. The source name can be any keyword, as long as it is unique. To write an event to the Application log, use the static method `WriteEntry()`, supplying the source name and message as string arguments. If the source name is not already registered, it is automatically registered.

You can manually register a new event source several ways. First, call `CreateEventSource()`. If you do not specify a log name, then your events are registered with the generic Application Log. Otherwise, a new `.evt` file is created in the `%SystemRoot%\system32\config` directory). Alternatively, create a new `EventLog` object, and set `SourceName` to the appropriate values. To delete a source, call `DeleteEventSource()`. `Delete()` deletes the entire log, but be careful not to delete one of the Windows event logs! `GetEventLogs()` allows you to find all event logs in the system, and `LogNameFromSourceName()` allows you to determine the log file for a given source.

You can interact with a log in many ways. Add to it using `WriteEntry()` and remove all log entries by calling `Clear()`. Examine the `Entries` property to view the individual log entries. An `EventLog` can raise the `EntryWritten` event. Set `EnableRaisingEvents` to `true`.

```
public class EventLog : System.ComponentModel.Component, System.ComponentModel.ISupportEvents
// Public Constructors
    public EventLog();
    public EventLog(string logName);
    public EventLog(string logName, string machineName);
    public EventLog(string logName, string machineName, string source);
// Public Instance Properties
    public bool EnableRaisingEvents {set; get; }
    public EventLogEntryCollection Entries {get; }
    public string Log {set; get; }
    public string LogDisplayName {get; }
    public string MachineName {set; get; }
    public string Source {set; get; }
    public ISynchronizeInvoke SynchronizingObject {set; get; }
// Public Static Methods
    public static void CreateEventSource(string source, string logName);
    public static void CreateEventSource(string source, string logName, string machineName);
    public static void Delete(string logName);
    public static void Delete(string logName, string machineName);
    public static void DeleteEventSource(string source);
    public static void DeleteEventSource(string source, string machineName);
    public static bool Exists(string logName);
    public static bool Exists(string logName, string machineName);
    public static EventLog[] GetEventLogs();
```

```

    public static EventLog[ ] GetEventLogs(string machineName);
    public static string LogNameFromSourceName(string source, string machineName);
    public static bool SourceExists(string source);
    public static bool SourceExists(string source, string machineName);
    public static void WriteEntry(string source, string message);
    public static void WriteEntry(string source, string message, EventLogEntryType type)
    public static void WriteEntry(string source, string message, EventLogEntryType type,
    public static void WriteEntry(string source, string message, EventLogEntryType type,
        short category);
    public static void WriteEntry(string source, string message, EventLogEntryType type,
        short category, byte[ ] rawData);
// Public Instance Methods
    public void BeginInit( );
// implements System.ComponentModel.ISupportInitialize
    public void Clear( );
    public void Close( );
    public void EndInit( );
// implements System.ComponentModel.ISupportInitialize
    public void WriteEntry(string message);
    public void WriteEntry(string message, EventLogEntryType type);
    public void WriteEntry(string message, EventLogEntryType type, int eventID);
    public void WriteEntry(string message, EventLogEntryType type, int eventID,
        short category);
    public void WriteEntry(string message, EventLogEntryType type, int eventID,
        short category, byte[ ] rawData);
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides System.ComponentModel.Component
// Events
    public event EntryWrittenEventHandler EntryWritten;
}

```

Hierarchy

System.Object → System.MarshalByRefObject →
 System.ComponentModel.Component(System.ComponentModel.IComponent, System.IDisposable) —
 EventLog(System.ComponentModel.ISupportInitialize)

Returned By

EventLogTraceListener.EventLog

Passed To

EventLogTraceListener.{EventLog, EventLogTraceListener()}

[Team LiB]

◀ PREVIOUS NEXT ▶

EventLogEntry

serializable, marshal by
reference, disposable

System.Diagnostics (system.dll) *sealed class*

This class represents an individual entry from an `EventLog`. A collection of these objects is available through `EventLog.Entries`. This class exposes all the properties of an event log entry.

```
public sealed class EventLogEntry : System.ComponentModel.Component,
    System.Runtime.Serialization.ISerializable {
// Public Instance Properties
    public string Category {get; }
    public short CategoryNumber {get; }
    public byte[] Data {get; }
    public EventLogEntryType EntryType {get; }
    public int EventID {get; }
    public int Index {get; }
    public string MachineName {get; }
    public string Message {get; }
    public string[] ReplacementStrings {get; }
    public string Source {get; }
    public DateTime TimeGenerated {get; }
    public DateTime TimeWritten {get; }
    public string Username {get; }
// Public Instance Methods
    public bool Equals(EventLogEntry otherEntry);
}
```

Hierarchy

```
System.Object → System.MarshalByRefObject →
System.ComponentModel.Component(System.ComponentModel.IComponent,
System.IDisposable) → EventLogEntry(System.Runtime.Serialization.ISerializable)
```

Returned By

```
EntryWrittenEventArgs.Entry, EventLogEntryCollection.this
```

Passed To

```
EntryWrittenEventArgs.EntryWrittenEventArgs( ), EventLogEntryCollection.CopyTo( )
```

EventLogEntryCollection

System.Diagnostics (system.dll) *class*

This class is an `ICollection` implementation for `EventLogEntry` objects.

```
public class EventLogEntryCollection : ICollection, IEnumerable {  
    // Public Instance Properties  
    public int Count{get; }  
    // implements ICollection  
    public virtual EventLogEntry this[int index]){get; }  
    // Public Instance Methods  
    public void CopyTo(EventLogEntry[ ] entries, int index);  
    public IEnumerator GetEnumerator( );  
    // implements IEnumerable  
}
```

Returned By

`EventLog.Entries`

EventLogEntryType

serializable

System.Diagnostics (system.dll)

enum

This enumeration represents an event log entry's severity level. **Error** indicates that the message contains an error. **SuccessAudit** and **FailureAudit** indicate that an audited access attempt, such as a user login, has succeeded or failed. **Information** represents that a significant operation, such as starting or stopping a service, has taken place. **Warning** indicates that a problem has occurred. **Warnings** are not as serious as **Errors**, but they should be investigated and resolved whenever possible, so your log does not fill up with warning messages.

```
public enum EventLogEntryType {  
    Error = 1,  
    Warning = 2,  
    Information = 4,  
    SuccessAudit = 8,  
    FailureAudit = 16  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → EventLogEntryType

Returned By

EventLogEntry.EntryType

Passed To

EventLog.WriteEntry()

EventLogInstaller

marshal by reference,
disposable

System.Diagnostics (system.configuration.install.dll) *class*

This class is a `System.Configuration.Install.Installer` to install `EventLog` s. To install a new source `Source` and `Log` properties.

```
public class EventLogInstaller : System.Configuration.Install.ComponentInstaller {
// Public Constructors
    public EventLogInstaller( );
// Public Instance Properties
    public string Log{set; get; }
    public string Source{set; get; }
    public UninstallAction UninstallAction{set; get; }
// Public Instance Methods
    public override void CopyFromComponent(System.ComponentModel.IComponent component)
// overrides System.Configuration.Install.ComponentInstaller
    public override void Install(System.Collections.IDictionary stateSaver)
// overrides System.Configuration.Install.Installer
    public override bool IsEquivalentInstaller(System.Configuration.Install.ComponentInst
// overrides System.Configuration.Install.ComponentInstaller
    public override void Rollback(System.Collections.IDictionary savedState)
// overrides System.Configuration.Install.Installer
    public override void Uninstall(System.Collections.IDictionary savedState)
// overrides System.Configuration.Install.Installer
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
System.ComponentModel.Component(System.ComponentModel.IComponent, System.IDisposable) —
System.Configuration.Install.Installer → System.Configuration.Install.ComponentInstall
EventLogInstaller

EventLogPermission


serializable

System.Diagnostics (system.dll) *sealed class*

This class is a `System.Security.Permissions.ResourcePermissionBase` object, which indicates whether executing code has permission to access the Windows event logs.

```
public sealed class EventLogPermission : System.Security.Permissions.ResourcePermissionBase
// Public Constructors
    public EventLogPermission( );
    public EventLogPermission(EventLogPermissionAccess permissionAccess, string machineName);
    public EventLogPermission(EventLogPermissionEntry[] permissionAccessEntries);
    public EventLogPermission(System.Security.Permissions.PermissionState state);
// Public Instance Properties
    public EventLogPermissionEntryCollection PermissionEntries {get; }
}
```

Hierarchy



EventLogPermissionAccess serializable, flag

System.Diagnostics (system.dll) *enum*

This enumeration is used by `EventLogPermissionAttribute`. `None` indicates no access, and `Browse` allows you to read logs. `Instrument` allows reading and writing. `Audit` represents the highest level of access. It lets you read logs, clear a log, monitor events, respond to entries, delete logs and event sources, and enumerate a collection of all logs.

```
public enum EventLogPermissionAccess {  
    None = 0x00000000 ,  
    Browse = 0x00000002 ,  
    Instrument = 0x00000006 ,  
    Audit = 0x0000000A  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `EventLogPermissionAccess`

Returned By

`EventLogPermissionAttribute.PermissionAccess`,
`EventLogPermissionEntry.PermissionAccess`

Passed To

`EventLogPermission.EventLogPermission()`,
`EventLogPermissionAttribute.PermissionAccess`,
`EventLogPermissionEntry.EventLogPermissionEntry()`

EventLogPermissionAttribute serializable

System.Diagnostics (system.dll) *class*

This security attribute specifies the `EventLogPermissionAccess` required by your code.

```
public class EventLogPermissionAttribute : System.Security.Permissions.CodeAccessSecurityAttribute
// Public Constructors
    public EventLogPermissionAttribute(System.Security.Permissions.SecurityAction action)
// Public Instance Properties
    public string MachineName { get; set; }
    public EventLogPermissionAccess PermissionAccess { get; set; }
// Public Instance Methods
    public override IPermission CreatePermission();
// overrides System.Security.Permissions.SecurityAttribute
}
```

Hierarchy

System.Object → System.Attribute → System.Security.Permissions.SecurityAttribute → System.Security.Permissions.CodeAccessSecurityAttribute → EventLogPermissionAttribute

Valid On

Assembly, Class, Struct, Constructor, Method, Event

EventLogPermissionEntry

serializable

System.Diagnostics (system.dll)

class

This class represents a single permission from an `EventLogPermission`'s `PermissionEntries` collection. `MachineName` checks the machine name the entry is for, and `PermissionAccess` gets an `EventLogPermissionAccess` that represents the granted permissions.

```
public class EventLogPermissionEntry {
// Public Constructors
    public EventLogPermissionEntry(EventLogPermissionAccess permissionAccess, string mac.
// Public Instance Properties
    public string MachineName{get; }
    public EventLogPermissionAccess PermissionAccess{get; }
}
```

Returned By

`EventLogPermissionEntryCollection.this`

Passed To

`EventLogPermission.EventLogPermission()`, `EventLogPermissionEntryCollection.{Add(), AddContains(), CopyTo(), IndexOf(), Insert(), Remove(), this}`

EventLogPermissionEntryCollection serializable

System.Diagnostics (system.dll) *class*

A strongly typed collection that contains `EventLogPermissionEntry` objects.

```
public class EventLogPermissionEntryCollection : CollectionBase {
// Public Instance Properties
    public EventLogPermissionEntry this(int index){set; get; }
// Public Instance Methods
    public int Add(EventLogPermissionEntry value);
    public void AddRange(EventLogPermissionEntry[] value);
    public void AddRange(EventLogPermissionEntryCollection value);
    public bool Contains(EventLogPermissionEntry value);
    public void CopyTo(EventLogPermissionEntry[] array, int index);
    public int IndexOf(EventLogPermissionEntry value);
    public void Insert(int index, EventLogPermissionEntry value);
    public void Remove(EventLogPermissionEntry value);
// Protected Instance Methods
    protected override void OnClear( );
// overrides System.Collections.CollectionBase
    protected override void OnInsert(int index, object value);
// overrides System.Collections.CollectionBase
    protected override void OnRemove(int index, object value);
// overrides System.Collections.CollectionBase
    protected override void OnSet(int index, object oldValue, object newValue)
// overrides System.Collections.CollectionBase
}
```

Hierarchy

System.Object → System.Collections.CollectionBase(System.Collections.IList,
System.Collections ICollection, System.Collections.IEnumerable) →
EventLogPermissionEntryCollection

Returned By

EventLogPermission.PermissionEntries


EventLogTraceListener marshal by reference, disposable

System.Diagnostics (system.dll) *sealed class*

To capture trace and debug output to an `EventLog`, add an instance of this class to `Debug.Listeners`, or `Trace.Listeners`. You can specify an `EventLog` instance in the constructor or the name of an event source as a string.

```
public sealed class EventLogTraceListener : TraceListener {
// Public Constructors
    public EventLogTraceListener( );
    public EventLogTraceListener(EventLog eventLog);
    public EventLogTraceListener(string source);
// Public Instance Properties
    public EventLog EventLog{set; get; }
    public override string Name{set; get; }
// overrides TraceListener
// Public Instance Methods
    public override void Close( );
// overrides TraceListener
    public override void Write(string message);
// overrides TraceListener
    public override void WriteLine(string message);
// overrides TraceListener
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides TraceListener
}
```

Hierarchy



FileVersionInfo

System.Diagnostics (system.dll) *sealed class*

This class provides access to the attributes specific to binary files. Use `GetVersionInfo()` to obtain a reference to a file, and then inspect the object's properties to determine information about the file.

```
public sealed class FileVersionInfo {
    // Public Instance Properties
    public string Comments{get; }
    public string CompanyName{get; }
    public int FileBuildPart{get; }
    public string FileDescription{get; }
    public int FileMajorPart{get; }
    public int FileMinorPart{get; }
    public string FileName{get; }
    public int FilePrivatePart{get; }
    public string FileVersion{get; }
    public string InternalName{get; }
    public bool IsDebug{get; }
    public bool IsPatched{get; }
    public bool IsPreRelease{get; }
    public bool IsPrivateBuild{get; }
    public bool IsSpecialBuild{get; }
    public string Language{get; }
    public string LegalCopyright{get; }
    public string LegalTrademarks{get; }
    public string OriginalFilename{get; }
    public string PrivateBuild{get; }
    public int ProductBuildPart{get; }
    public int ProductMajorPart{get; }
    public int ProductMinorPart{get; }
    public string ProductName{get; }
    public int ProductPrivatePart{get; }
    public string ProductVersion{get; }
    public string SpecialBuild{get; }
    // Public Static Methods
    public static FileVersionInfo GetVersionInfo(string fileName);
    // Public Instance Methods
    public override string ToString( );
    // overrides object
}
```

Returned By

ProcessModule.FileVersionInfo

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

InstanceData

System.Diagnostics (system.dll) *class*

This type represents the instance data for a performance counter sample. `InstanceName` returns the `InstanceData`'s name. `RawValue` returns the sample's raw data. `Sample` returns the `CounterSample` responsible for the data.

```
public class InstanceData {  
    // Public Constructors  
    public InstanceData(string instanceName, CounterSample sample);  
    // Public Instance Properties  
    public string InstanceName {get; }  
    public long RawValue {get; }  
    public CounterSample Sample {get; }  
}
```

Returned By

`InstanceDataCollection.this`

Passed To

`InstanceDataCollection.CopyTo()`


InstanceDataCollection

System.Diagnostics (system.dll) *class*

This type is a strongly typed collection of `InstanceData` objects.

```
public class InstanceDataCollection : DictionaryBase {
// Public Constructors
    public InstanceDataCollection(string counterName);
// Public Instance Properties
    public string CounterName{get; }
    public ICollection Keys{get; }
// implements System.Collections.IDictionary
    public InstanceData this[string instanceName]{get; }
    public ICollection Values{get; }
// implements System.Collections.IDictionary
// Public Instance Methods
    public bool Contains(string instanceName);
    public void CopyTo(InstanceData[] instances, int index);
}
```

Hierarchy



Returned By

InstanceDataCollectionCollection.this

Passed To

InstanceDataCollectionCollection.CopyTo()


InstanceDataCollectionCollection

System.Diagnostics (system.dll) *class*

This type is a strongly typed collection of `InstanceDataCollection` objects (e.g., a collection of collections).

```
public class InstanceDataCollectionCollection : DictionaryBase {  
    // Public Constructors  
    public InstanceDataCollectionCollection( );  
    // Public Instance Properties  
    public ICollection Keys {get; }  
    // implements System.Collections.IDictionary  
    public InstanceDataCollection this[string counterName] {get; }  
    public ICollection Values {get; }  
    // implements System.Collections.IDictionary  
    // Public Instance Methods  
    public bool Contains(string counterName);  
    public void CopyTo(InstanceDataCollection[] counters, int index);  
}
```

Hierarchy



Returned By

```
PerformanceCounterCategory.ReadCategory( )
```


MonitoringDescriptionAttribute

System.Diagnostics (system.dll) *class*

This type is a `System.ComponentModel.DescriptionAttribute` that holds an informative description of one of the `System.Diagnostics` monitoring members.

```
public class MonitoringDescriptionAttribute : System.ComponentModel.DescriptionAttribute
// Public Constructors
    public MonitoringDescriptionAttribute(string description);
// Public Instance Properties
    public override string Description{get; }
// overrides System.ComponentModel.DescriptionAttribute
}
```

Hierarchy



Valid On

All

PerformanceCounter marshal by reference, disposable

System.Diagnostics (system.dll) *sealed class*

This class represents a Windows NT, 2000, or XP performance counter that can be accessed using the Performance Administrative Tool. `PerformanceCounter` s already exist for system devices, such as process disk, or memory usage, as well as for system resources, such as processes or threads. Using the `PerformanceCounter` class, you can both read from and write performance data to existing custom coun

To create your own custom performance counters, use `PerformanceCounterCategory.Create()`. You write to a performance counter by using one of the `PerformanceCounter` constructors that takes the `readOnly` argument. Set that argument to `false` to create a performance counter that you can write to. set the value of a performance counter, call `IncrementBy()`, `Increment()`, or `Decrement()`, or set `RawValue` to the desired value.

To access an existing performance counter, create an instance of `PerformanceCounter` with the `CategoryName` and `CounterName` set to that of an available category and an existing performance counter. The category and counter names are case-insensitive, so you could sample the available memory by calling the constructor as `PerformanceCounter("memory", "available mbytes")`. Consult the Performance Administrative Tool for the available performance counters. You can explicitly set the `CategoryName` and `CounterName` (and the optional `InstanceName` and `MachineName`) properties, if you choose not to set the using the constructor.

To obtain a new data sample for a counter, call either `NextValue()` or `NextSample()`. `NextSample()` returns a `CounterSample` structure that represents the raw captured performance data. `NextValue()` fetches the next sample and calculates its value based on the raw data it contains. To permanently remove counter, call `RemoveInstance()`. If you attempt to modify or remove a counter in which the `ReadOnly` property is set to `true`, an `InvalidOperationException` is returned.

```
public sealed class PerformanceCounter : System.ComponentModel.Component,
    System.ComponentModel.ISupportInitialize {
// Public Constructors
    public PerformanceCounter( );
    public PerformanceCounter(string categoryName, string counterName);
    public PerformanceCounter(string categoryName, string counterName, bool readOnly);
    public PerformanceCounter(string categoryName, string counterName, string instanceName);
    public PerformanceCounter(string categoryName, string counterName, string instanceName,
        bool readOnly);
    public PerformanceCounter(string categoryName, string counterName, string instanceName,
        string machineName);
// Public Static Fields
    public static int DefaultFileMappingSize;
// =524288
// Public Instance Properties
```

```

    public string CategoryName{set; get; }
    public string CounterHelp{get; }
    public string CounterName{set; get; }
    public PerformanceCounterType CounterType{get; }
    public string InstanceName{set; get; }
    public string MachineName{set; get; }
    public long RawValue{set; get; }
    public bool ReadOnly{set; get; }
// Public Static Methods
    public static void CloseSharedResources( );
// Public Instance Methods
    public void BeginInit( );
// implements System.ComponentModel.ISupportInitialize
    public void Close( );
    public long Decrement( );
    public void EndInit( );
// implements System.ComponentModel.ISupportInitialize
    public long Increment( );
    public long IncrementBy(long value);
    public CounterSample NextSample( );
    public float NextValue( );
    public void RemoveInstance( );
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides System.ComponentModel.Component
}

```

Hierarchy

```

System.Object → System.MarshalByRefObject →
System.ComponentModel.Component(System.ComponentModel.IComponent, System.IDisposable) —
PerformanceCounter(System.ComponentModel.ISupportInitialize)

```

Returned By

```
PerformanceCounterCategory.GetCounters( )
```

[Team LiB]

◀ PREVIOUS NEXT ▶

PerformanceCounterCategory

System.Diagnostics (system.dll) *sealed class*

This class allows you to create and manage categories of performance counters. You can see the categories by your system when you use the Performance Administrative Tool. When you attempt to add a counter, categories listed in the **Performance** object drop-list, such as Processor, Memory, Thread, and Network I

Use **Create()** to add a new category. The three-argument form lets you supply a category name, a description, and a collection of **CounterCreationData** objects. Each **CounterCreationData** object describes a counter to create in the new category. Use the four-argument form of **Create()** to create a new category with only one counter.

Delete() removes a counter category, and **Exists()** checks whether a given category exists. If you want to check if a specific counter exists in a category, call **CounterExists()**. To check for an instance in a category, call **InstanceExists()**. **GetCategories()** returns all the categories recognized by the system.

The **CategoryHelp**, **CategoryName**, and **MachineName** properties provide access to the name, help text, and machine name for a given category. You can use the nonstatic versions of **CounterExists()** and **InstanceExists()** to check if a specified counter or instance exists in the inspected category. **GetCounters()** and **GetInstanceNames()** return a list of the counters and instances in a category.

```
public sealed class PerformanceCounterCategory {
// Public Constructors
    public PerformanceCounterCategory( );
    public PerformanceCounterCategory(string categoryName);
    public PerformanceCounterCategory(string categoryName, string machineName);
// Public Instance Properties
    public string CategoryHelp{get; }
    public string CategoryName{set; get; }
    public string MachineName{set; get; }
// Public Static Methods
    public static bool CounterExists(string counterName, string categoryName);
    public static bool CounterExists(string counterName, string categoryName, string machineName);
    public static PerformanceCounterCategory Create(string categoryName, string categoryDescription,
        CounterCreationDataCollection counterData);
    public static PerformanceCounterCategory Create(string categoryName, string categoryDescription,
        string counterName, string counterHelp);
    public static void Delete(string categoryName);
    public static bool Exists(string categoryName);
    public static bool Exists(string categoryName, string machineName);
    public static PerformanceCounterCategory[] GetCategories( );
    public static PerformanceCounterCategory[] GetCategories(string machineName);
    public static bool InstanceExists(string instanceName, string categoryName);
    public static bool InstanceExists(string instanceName, string categoryName, string machineName);
}
```



```
// Public Instance Methods
public bool CounterExists(string counterName);
public PerformanceCounter[ ] GetCounters( );
public PerformanceCounter[ ] GetCounters(string instanceName);
public string[ ] GetInstanceNames( );
public bool InstanceExists(string instanceName);
public InstanceDataCollectionCollection ReadCategory( );
}
```

[Team LiB]

PerformanceCounterInstaller

marshal by
reference,
disposable


System.Diagnostics (system.configuration.install.dll)

class

This is an installer for a **PerformanceCounter** component. **CategoryName** and **CategoryHelp** contain the and help text pertinent to the category to install the counters into, and **Counters** contains the counters that will be installed.

```
public class PerformanceCounterInstaller : System.Configuration.Install.ComponentInstaller
// Public Constructors
    public PerformanceCounterInstaller( );
// Public Instance Properties
    public string CategoryHelp{set; get; }
    public string CategoryName{set; get; }
    public CounterCreationDataCollection Counters{get; }
    public UninstallAction UninstallAction{set; get; }
// Public Instance Methods
    public override void CopyFromComponent(System.ComponentModel.IComponent component)
// overrides System.Configuration.Install.ComponentInstaller
    public override void Install(System.Collections.IDictionary stateSaver)
// overrides System.Configuration.Install.Installer
    public override void Rollback(System.Collections.IDictionary savedState)
// overrides System.Configuration.Install.Installer
    public override void Uninstall(System.Collections.IDictionary savedState)
// overrides System.Configuration.Install.Installer
}
```

Hierarchy




PerformanceCounterPermission serializable

System.Diagnostics (system.dll) *sealed class*

This class is a `System.Security.CodeAccessPermission` object that specifies code access to `PerformanceCounter` instances. The `PermissionEntries` property returns a collection of `PerformanceCounterPermissionEntry` representing the specific permissions granted.

```
public sealed class PerformanceCounterPermission : System.Security.Permissions.Resource
// Public Constructors
    public PerformanceCounterPermission( );
    public PerformanceCounterPermission(PerformanceCounterPermissionAccess permissionAccess,
        string machineName, string categoryName);
    public PerformanceCounterPermission(PerformanceCounterPermissionEntry[] permissionEntries);
    public PerformanceCounterPermission(System.Security.Permissions.PermissionState state);
// Public Instance Properties
    public PerformanceCounterPermissionEntryCollection PermissionEntries {get; }
}
```

Hierarchy



PerformanceCounterPermissionAccess serializable, flag

System.Diagnostics (system.dll) enum

This enumeration represents the different types of access that can be granted to executing code. **Administer** allows full control over a **PerformanceCounter**, while **Browse** allows you to view, but not modify, **PerformanceCounter** data. **Instrument** allows the code to act as a performance counter (you may read and write, but not create, categories). **None** explicitly denies access to a **PerformanceCounterCategory**.

```
public enum PerformanceCounterPermissionAccess {
    None = 0x00000000 ,
    Browse = 0x00000002 ,
    Instrument = 0x00000006 ,
    Administer = 0x0000000E
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → PerformanceCounterPermissionAccess

Returned By

PerformanceCounterPermissionAttribute.PermissionAccess,
PerformanceCounterPermissionEntry.PermissionAccess

Passed To

PerformanceCounterPermission.PerformanceCounterPermission(),
PerformanceCounterPermissionAttribute.PermissionAccess,
PerformanceCounterPermissionEntry.PerformanceCounterPermissionEntry()


PerformanceCounterPermissionAttribute serializable

System.Diagnostics (system.dll) *class*

This class is a `System.Security.Permissions.SecurityAttribute` that explicitly allows you to set requ counter permissions. You can use the `CategoryName` , `MachineName` , and `PermissionAccess` properties permissions for a specific `PerformanceCounter` .

```
public class PerformanceCounterPermissionAttribute : System.Security.Permissions.CodeAc
// Public Constructors
    public PerformanceCounterPermissionAttribute(System.Security.Permissions.SecurityAct:
// Public Instance Properties
    public string CategoryName{set; get; }
    public string MachineName{set; get; }
    public PerformanceCounterPermissionAccess PermissionAccess{set; get; }
// Public Instance Methods
    public override IPermission CreatePermission( );
// overrides System.Security.Permissions.SecurityAttribute
}
```

Hierarchy



Valid On

Assembly, Class, Struct, Constructor, Method, Event

PerformanceCounterPermissionEntry serializable

System.Diagnostics (system.dll) *class*

This class holds the necessary information for a given permission. The `PermissionAccess` property sets the `PerformanceCounterPermissionAccess` level for a specific `CategoryName` and `MachineName`.

```
public class PerformanceCounterPermissionEntry {  
    // Public Constructors  
    public PerformanceCounterPermissionEntry(PerformanceCounterPermissionAccess permissionAccess, string machineName, string categoryName);  
    // Public Instance Properties  
    public string CategoryName { get; }  
    public string MachineName { get; }  
    public PerformanceCounterPermissionAccess PermissionAccess { get; }  
}
```

Returned By

`PerformanceCounterPermissionEntryCollection.this`

Passed To

`PerformanceCounterPermission.Permission()`,
`PerformanceCounterPermissionEntryCollection.Add()`, `AddRange()`, `Contains()`, `CopyTo()`, `IndexOf()`, `Insert()`, `Remove()`, `this`

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

PerformanceCounterPermissionEntryCollection serializable

System.Diagnostics (system.dll) *class*

This strongly typed collection contains `PerformanceCounterPermissionEntry` objects.

```

public class PerformanceCounterPermissionEntryCollection : CollectionBase {
// Public Instance Properties
    public PerformanceCounterPermissionEntry this[int index]{set; get; }
// Public Instance Methods
    public int Add(PerformanceCounterPermissionEntry value);
    public void AddRange(PerformanceCounterPermissionEntry[] value);
    public void AddRange(PerformanceCounterPermissionEntryCollection value);
    public bool Contains(PerformanceCounterPermissionEntry value);
    public void CopyTo(PerformanceCounterPermissionEntry[] array, int index);
    public int IndexOf(PerformanceCounterPermissionEntry value);
    public void Insert(int index, PerformanceCounterPermissionEntry value);
    public void Remove(PerformanceCounterPermissionEntry value);
// Protected Instance Methods
    protected override void OnClear( );
// overrides System.Collections.CollectionBase
    protected override void OnInsert(int index, object value);
// overrides System.Collections.CollectionBase
    protected override void OnRemove(int index, object value);
// overrides System.Collections.CollectionBase
    protected override void OnSet(int index, object oldValue, object newValue)
// overrides System.Collections.CollectionBase
}

```

Hierarchy

```

System.Object → System.Collections.CollectionBase(System.Collections.IList,
System.Collections ICollection, System.Collections.IEnumerable) →
PerformanceCounterPermissionEntryCollection

```

Returned By

`PerformanceCounterPermission.PermissionEntries`

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

PerformanceCounterType serializable

System.Diagnostics (system.dll) *enum*

This enumeration represents the different types of performance counters available. Look up `System.Diagnostics.PerformanceCounterType` in the .NET Framework SDK Documentation for complete details.

```
public enum PerformanceCounterType {
    NumberOfItemsHEX32 = 0 ,
    NumberOfItemsHEX64 = 256 ,
    NumberOfItems32 = 65536 ,
    NumberOfItems64 = 65792 ,
    CounterDelta32 = 4195328 ,
    CounterDelta64 = 4195584 ,
    SampleCounter = 4260864 ,
    CountPerTimeInterval32 = 4523008 ,
    CountPerTimeInterval64 = 4523264 ,
    RateOfCountsPerSecond32 = 272696320 ,
    RateOfCountsPerSecond64 = 272696576 ,
    RawFraction = 537003008 ,
    CounterTimer = 541132032 ,
    Timer100Ns = 542180608 ,
    SampleFraction = 549585920 ,
    CounterTimerInverse = 557909248 ,
    Timer100NsInverse = 558957824 ,
    CounterMultiTimer = 574686464 ,
    CounterMultiTimer100Ns = 575735040 ,
    CounterMultiTimerInverse = 591463680 ,
    CounterMultiTimer100NsInverse = 592512256 ,
    AverageTimer32 = 805438464 ,
    ElapsedTime = 807666944 ,
    AverageCount64 = 1073874176 ,
    SampleBase = 1073939457 ,
    AverageBase = 1073939458 ,
    RawBase = 1073939459 ,
    CounterMultiBase = 1107494144
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → PerformanceCounterType

Returned By


```
CounterCreationData.CounterType, CounterSample.CounterType,  
PerformanceCounter.CounterType
```

Passed To

```
CounterCreationData.{CounterCreationData( ), CounterType},  
CounterSample.CounterSample( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Process marshal by reference, disposable

System.Diagnostics (system.dll) *class*

This class represents a system process. Use it to start, stop, and interact with a process. To launch a new process, create an instance of `ProcessStartInfo`, set its properties, and pass it to the single-argument form of the static `Start()` method. This offers a great deal of control over process creation. To launch a process without customizing its `StartInfo`, simply call the one-string or two-string argument form of the static `Start()` method. The first string argument is the name of the program, batch file, or document to start, and the optional second argument contains any command-line arguments. You can also explicitly create a new instance of `Process`, set its `StartInfo` property, and call the `Start()` method to start the process.

`GetCurrentProcess()` creates a `Process` instance that represents the current process. Enumerate all running processes on the system by using `GetProcesses()`. Use `GetProcessesByName()` to get all processes for a given program. `GetProcessById()` retrieves a `Process` given its process ID.

Use `CloseMainWindow()` to shut down a process that has a user interface. You can terminate a process with `Kill()`, but this forces an abnormal termination, which may result in data corruption. If you would like to raise an event when the process finishes executing, use `Exited` (`EnableRaisingEvents` must be set to `true`).

Most of the properties allow you to access general information about the running process. However, this information is populated at the time you associate a `Process` object with a running process. You can call `Refresh()` each time you need to update this information. `Modules` allows you to inspect the code modules the process has loaded into memory, and `MainModule` returns the module that started the process. `StandardInput`, `StandardOutput`, and `StandardError` allow access to the default I/O streams (see the `ProcessStartInfo.Redirect*` methods). `Threads` returns the threads in use by the process, and `WorkingSet` returns the physical memory usage of the process.

```
public class Process : System.ComponentModel.Component {
// Public Constructors
    public Process();
// Public Instance Properties
    public int BasePriority {get;}
    public bool EnableRaisingEvents {set; get;}
    public int ExitCode {get;}
    public DateTime ExitTime {get;}
    public IntPtr Handle {get;}
    public int HandleCount {get;}
    public bool HasExited {get;}
    public int Id {get;}
    public string MachineName {get;}
    public ProcessModule MainModule {get;}
    public IntPtr MainWindowHandle {get;}
    public string MainWindowTitle {get;}
```


```

public IntPtr MaxWorkingSet{set; get; }
public IntPtr MinWorkingSet{set; get; }
public ProcessModuleCollection Modules{get; }
public int NonpagedSystemMemorySize{get; }
public int PagedMemorySize{get; }
public int PagedSystemMemorySize{get; }
public int PeakPagedMemorySize{get; }
public int PeakVirtualMemorySize{get; }
public int PeakWorkingSet{get; }
public bool PriorityBoostEnabled{set; get; }
public ProcessPriorityClass PriorityClass{set; get; }
public int PrivateMemorySize{get; }
public TimeSpan PrivilegedProcessorTime{get; }
public string ProcessName{get; }
public IntPtr ProcessorAffinity{set; get; }
public bool Responding{get; }
public StreamReader StandardError{get; }
public StreamWriter StandardInput{get; }
public StreamReader StandardOutput{get; }
public ProcessStartInfo StartInfo{set; get; }
public DateTime StartTime{get; }
public ISynchronizeInvoke SynchronizingObject{set; get; }
public ProcessThreadCollection Threads{get; }
public TimeSpan TotalProcessorTime{get; }
public TimeSpan UserProcessorTime{get; }
public int VirtualMemorySize{get; }
public int WorkingSet{get; }
// Public Static Methods
public static void EnterDebugMode( );
public static Process GetCurrentProcess( );
public static Process GetProcessById(int processId);
public static Process GetProcessById(int processId, string machineName);
public static Process[ ] GetProcesses( );
public static Process[ ] GetProcesses(string machineName);
public static Process[ ] GetProcessesByName(string processName);
public static Process[ ] GetProcessesByName(string processName, string machineName);
public static void LeaveDebugMode( );
public static Process Start(ProcessStartInfo startInfo);
public static Process Start(string fileName);
public static Process Start(string fileName, string arguments);
// Public Instance Methods
public void Close( );
public bool CloseMainWindow( );
public void Kill( );
public void Refresh( );
public bool Start( );
public override string ToString( );
// overrides System.ComponentModel.Component
public bool WaitForExit(int milliseconds);
public void WaitForExit( );
public bool WaitForInputIdle( );

```

```
    public bool WaitForInputIdle(int milliseconds);  
    // Protected Instance Methods  
    protected override void Dispose(bool disposing);  
    // overrides System.ComponentModel.Component  
    protected void OnExited( );  
    // Events  
    public event EventHandler Exited;  
}
```

Hierarchy



ProcessModule


marshal by reference,
disposable

System.Diagnostics (system.dll) *class*

This class represents a **DLL** or **EXE** file loaded by a process. **BaseAddress** returns the starting memory address of the loaded module and **EntryPointAddress** returns the memory address of the module's entry point (such as **Main()**, **WinMain()**, or **DllMain()**). You can also check the size of the loaded module by checking **ModuleMemorySize**. **FileName** returns the full path to the file of a loaded module, and **FileVersionInfo** allows you to access the version information of a file. Lastly, you can view the name of the module with **ModuleName**.

```
public class ProcessModule : System.ComponentModel.Component {  
    // Public Instance Properties  
    public IntPtr BaseAddress{get; }  
    public IntPtr EntryPointAddress{get; }  
    public string FileName{get; }  
    public FileVersionInfo FileVersionInfo{get; }  
    public int ModuleMemorySize{get; }  
    public string ModuleName{get; }  
    // Public Instance Methods  
    public override string ToString( );  
    // overrides System.ComponentModel.Component  
}
```

Hierarchy



Returned By

Process.MainModule, ProcessModuleCollection.this

Passed To

ProcessModuleCollection.{Contains(), CopyTo(), IndexOf(), ProcessModuleCollection()}


ProcessModuleCollection

System.Diagnostics (system.dll) *class*

This class is a strongly typed collection that contains `ProcessModule` objects.

```
public class ProcessModuleCollection : ReadOnlyCollectionBase {  
    // Public Constructors  
    public ProcessModuleCollection(ProcessModule[] processModules);  
    // Protected Constructors  
    protected ProcessModuleCollection( );  
    // Public Instance Properties  
    public ProcessModule this[int index]{get; }  
    // Public Instance Methods  
    public bool Contains(ProcessModule module);  
    public void CopyTo(ProcessModule[] array, int index);  
    public int IndexOf(ProcessModule module);  
}
```

Hierarchy



Returned By

`Process.Modules`

ProcessPriorityClass

serializable

System.Diagnostics (system.dll)


enum

This enumeration represents the different priorities given to a process. Process priorities, along with thread priorities, determine how processor time is allocated. Most processes run with **Normal** priority. Use **Idle** to specify that processor time should be allocated to a process only when the processor is idle. **AboveNormal** and **BelowNormal** allow you to set priorities slightly above or below **Normal**, but are not supported by Windows 95, 98, or Me. An exception is thrown if you attempt to use them.

High should be used only for time-critical tasks, but use care in choosing this priority because little time will be available to other applications. **RealTime** is the maximum allowable priority. When this priority is used, the process runs with higher priority than even the operating system. Assigning **High** and **RealTime** to a process will almost certainly make your system's user interface unresponsive. For this reason, be careful when using these.

```
public enum ProcessPriorityClass {  
    Normal = 32 ,  
    Idle = 64 ,  
    High = 128 ,  
    RealTime = 256 ,  
    BelowNormal = 16384 ,  
    AboveNormal = 32768  
}
```

Hierarchy



Returned By

Process.PriorityClass

Passed To

Process.PriorityClass

ProcessStartInfo

System.Diagnostics (system.dll) *sealed class*

This class is used to configure how a process is started or to view the settings a process was started with. To start a process, set **FileName** to the full path of the application or file, then pass the **ProcessStartInfo** instance to **Process.Start()**. **FileName** is the only property you must set. Use the other properties for more control. (Use **Arguments** to specify the command-line arguments.)

In Windows, each document type has a verb that you can use to do different things with (for example, a Microsoft Word document has an **open** and a **print** verb). To consult the possible verbs for a specific file, enumerate the **Verbs** property after you set **FileName**. To start a process with a specific verb, set **Verb**.

To change the standard error, input, or output source or targets (usually the system console), set one or more of **RedirectStandardError**, **RedirectStandardInput**, or **RedirectStandardOutput** to **true**. This enables the **Process.StandardError**, **Process.StandardInput**, and **Process.StandardOutput** properties, which you can then set as needed. Set the **EnvironmentVariables** and **WorkingDirectory** to change the default process start behavior. If the process cannot be started, you can display an error dialog window by setting **ErrorDialog** (set the handle of the dialog's parent window with **ErrorDialogParentHandle**). If you set **CreateNoWindow**, a new window is not created to start the new process. However, if you want a window, set its style by setting **WindowStyle**. You can also specify that the file should be executed from a Windows command prompt with **UseShellExecute**.

```
public sealed class ProcessStartInfo {
// Public Constructors
    public ProcessStartInfo( );
    public ProcessStartInfo(string fileName);
    public ProcessStartInfo(string fileName, string arguments);
// Public Instance Properties
    public string Arguments{set; get; }
    public bool CreateNoWindow{set; get; }
    public StringDictionary EnvironmentVariables{get; }
    public bool ErrorDialog{set; get; }
    public IntPtr ErrorDialogParentHandle{set; get; }
    public string FileName{set; get; }
    public bool RedirectStandardError{set; get; }
    public bool RedirectStandardInput{set; get; }
    public bool RedirectStandardOutput{set; get; }
    public bool UseShellExecute{set; get; }
    public string Verb{set; get; }
    public string[] Verbs{get; }
    public ProcessWindowStyle WindowStyle{set; get; }
    public string WorkingDirectory{set; get; }
}
```


Returned By

```
Process.StartInfo
```

Passed To

```
Process.{Start( ), StartInfo}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

ProcessThread marshal by reference, disposable

System.Diagnostics (system.dll) *class*

This class represents a thread, the smallest unit of execution under Win32. Use `Process.Threads` to get an array of all the threads contained within a given process. As with processes, a thread runs with a given priority. `BasePriority` represents the base priority for a thread. From time to time, the operating system changes a thread's priority; a thread's current priority is available from `CurrentPriority`. Threads in background applications run with a lower priority, as do threads that are sleeping. `BasePriorityPriorityLevel` specifies a range of appropriate priorities for a thread.

If a process is `ProcessPriorityClass.Normal`, `ProcessPriorityClass.High`, or `ProcessPriorityClass.RealTime`, you can set a thread's `PriorityBoostEnabled` to `true`. This gives the thread an extra boost whenever the user is interacting with the program's user interface. You can make a thread prefer one processor over another by setting the value of `IdealProcessor`. `ProcessorAffinity` allows you to set up a bitfield that represents one or more preferred processors. Bit 0 represents the first processor, bit 1 the second, and so on. For example, a `ProcessorAffinity` of `0x0005` (bits 0 and 2 on) indicates that the first and third processor are preferred. Use `ResetIdealProcessor()` to tell the thread that it can run on any processor, leaving the processor choice up to the operating system.

The current state of a thread is returned by `ThreadState`. If a thread is waiting, you can retrieve the reason the thread is waiting via `WaitReason`. `PrivilegedProcessorTime` and `UserProcessorTime` return the privileged and user processor time, and `TotalProcessorTime` returns the sum of those two.

The `ProcessThread` class differs from the `System.Threading.Thread` type. `ProcessThread` represents the view of a thread from an administrative viewpoint, while `System.Threading.Thread` represents a thread from its creator's viewpoint. When you want to enumerate and interact with the threads of an external process, use `ProcessThread`. When you need to create a new thread in your own program, use `System.Threading.Thread`.

```
public class ProcessThread : System.ComponentModel.Component {
    // Public Instance Properties
    public int BasePriority {get; }
    public int CurrentPriority {get; }
    public int Id {get; }
    public int IdealProcessor {set; }
    public bool PriorityBoostEnabled {set; get; }
    public ThreadPriorityLevel PriorityLevel {set; get; }
    public TimeSpan PrivilegedProcessorTime {get; }
    public IntPtr ProcessorAffinity {set; }
    public IntPtr StartAddress {get; }
    public DateTime StartTime {get; }
    public ThreadState ThreadState {get; }
```

```
    public TimeSpan TotalProcessorTime{get; }
    public TimeSpan UserProcessorTime{get; }
    public ThreadWaitReason WaitReason{get; }
// Public Instance Methods
    public void ResetIdealProcessor( );
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
System.ComponentModel.Component(System.ComponentModel.IComponent,
System.IDisposable) → ProcessThread

Returned By

ProcessThreadCollection.this

Passed To

ProcessThreadCollection.{Add(), Contains(), CopyTo(), IndexOf(), Insert(),
ProcessThreadCollection(), Remove()}

[\[Team LiB \]](#)


ProcessThreadCollection

System.Diagnostics (system.dll) *class*

This strongly typed collection contains `ProcessThread` objects.

```
public class ProcessThreadCollection : ReadOnlyCollectionBase {  
    // Public Constructors  
    public ProcessThreadCollection(ProcessThread[] processThreads);  
    // Protected Constructors  
    protected ProcessThreadCollection( );  
    // Public Instance Properties  
    public ProcessThread this[int index]{get; }  
    // Public Instance Methods  
    public int Add(ProcessThread thread);  
    public bool Contains(ProcessThread thread);  
    public void CopyTo(ProcessThread[] array, int index);  
    public int IndexOf(ProcessThread thread);  
    public void Insert(int index, ProcessThread thread);  
    public void Remove(ProcessThread thread);  
}
```

Hierarchy



Returned By

`Process.Threads`

ProcessWindowStyle

serializable

System.Diagnostics (system.dll)

enum

This enumeration contains the window states you can choose from when starting a `Process`.

```
public enum ProcessWindowStyle {  
    Normal = 0,  
    Hidden = 1,  
    Minimized = 2,  
    Maximized = 3  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → ProcessWindowStyle

Returned By

ProcessStartInfo.WindowStyle

Passed To

ProcessStartInfo.WindowStyle

StackFrame

serializable

System.Diagnostics (mscorlib.dll)

class

A stack frame is an abstraction of the current state of an executing method. Use `StackTrace` to enumerate all the stack frames that led up to the current process. Use `GetMethod()` to obtain information about the method represented by a stack frame. Use `GetFileName()` to retrieve the name of the module that contains the method. The column and line numbers of the method, which are determined from debugging symbols, can be accessed with `GetFileColumnNumber()` and `GetFileLineNumber()`. To obtain the location in memory of the `StackFrame`, use `GetNativeOffset()`, or, alternatively, for the offset of IL code, call `GetILOffset()`. If the JIT compiler is not generating debugging symbols, this number is approximated by the runtime.

```
public class StackFrame {
// Public Constructors
    public StackFrame( );
    public StackFrame(bool fNeedFileInfo);
    public StackFrame(int skipFrames);
    public StackFrame(int skipFrames, bool fNeedFileInfo);
    public StackFrame(string fileName, int lineNumber);
    public StackFrame(string fileName, int lineNumber, int colNumber);
// Public Static Fields
    public const int OFFSET_UNKNOWN;
// = -1
// Public Instance Methods
    public virtual int GetFileColumnNumber( );
    public virtual int GetFileLineNumber( );
    public virtual string GetFileName( );
    public virtual int GetILOffset( );
    public virtual MethodBase GetMethod( );
    public virtual int GetNativeOffset( );
    public override string ToString( );
// overrides object
}
```

Returned By

```
StackTrace.GetFrame( )
```

Passed To

```
StackTrace.StackTrace( )
```

StackTrace

serializable

System.Diagnostics (mscorlib.dll)

class

A stack trace is an ordered list of `StackFrame` objects. Call the constructor to create a stack trace that starts with a `StackFrame` corresponding to the current method. The optional boolean argument `fNeedFileInfo` indicates that the stack trace should include the filename as well as the line and column number. (The program must have been compiled with `/debug` to get this information.)

When one method calls another, a new stack frame is created and `FrameCount` is incremented. To get a specific `StackFrame`, use `GetFrame()`. The static constant `METHODS_TO_SKIP` returns the number of methods skipped at the beginning of the `StackTrace`.

```
public class StackTrace {
// Public Constructors
    public StackTrace( );
    public StackTrace(bool fNeedFileInfo);
    public StackTrace(Exception e);
    public StackTrace(Exception e, bool fNeedFileInfo);
    public StackTrace(Exception e, int skipFrames);
    public StackTrace(Exception e, int skipFrames, bool fNeedFileInfo);
    public StackTrace(int skipFrames);
    public StackTrace(int skipFrames, bool fNeedFileInfo);
    public StackTrace(StackFrame frame);
    public StackTrace(System.Threading.Thread targetThread, bool needFileInfo);
// Public Static Fields
    public const int METHODS_TO_SKIP;
// =0
// Public Instance Properties
    public virtual int FrameCount{get; }
// Public Instance Methods
    public virtual StackFrame GetFrame(int index);
    public override string ToString( );
// overrides object
}
```

Switch

System.Diagnostics (system.dll)

abstract class

Consult this class in a conditional statement to execute special tracing or debugging code. To use a switch you must have debugging enabled. Each **Switch** has a **DisplayName** and **Description**. **SwitchSetting** contains the current setting.

Specify the value of a switch in the application configuration file. Under the `<system.diagnostics>` element, add an element `<switches>` to hold all the switches. Within the `<switches>` element, define each switch you want with `<add name="switchname" value="value"/>`. For a **BooleanSwitch**, any nonzero value sets **BooleanSwitch.Enabled** to **true**. For a **TraceSwitch**, use a value from the **TraceLevel** enumeration.

```
public abstract class Switch {
// Protected Constructors
    protected Switch(string displayName, string description);
// Public Instance Properties
    public string Description{get; }
    public string DisplayName{get; }
// Protected Instance Properties
    protected int SwitchSetting{set; get; }
// Protected Instance Methods
    protected virtual void OnSwitchSettingChanged( );
}
```

Subclasses

BooleanSwitch, **TraceSwitch**

TextWriterTraceListener

marshal by
reference,
disposable

System.Diagnostics (system.dll) *class*

This class writes to a `System.IO.TextWriter`. Use `Writer` to set or change the `TextWriter`.

```
public class TextWriterTraceListener : TraceListener {
// Public Constructors
    public TextWriterTraceListener( );
    public TextWriterTraceListener(System.IO.Stream stream);
    public TextWriterTraceListener(System.IO.Stream stream, string name);
    public TextWriterTraceListener(string fileName);
    public TextWriterTraceListener(string fileName, string name);
    public TextWriterTraceListener(System.IO.TextWriter writer);
    public TextWriterTraceListener(System.IO.TextWriter writer, string name);
// Public Instance Properties
    public TextWriter Writer{set; get; }
// Public Instance Methods
    public override void Close( );
// overrides TraceListener
    public override void Flush( );
// overrides TraceListener
    public override void Write(string message);
// overrides TraceListener
    public override void WriteLine(string message);
// overrides TraceListener
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides TraceListener
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ThreadPriorityLevel

serializable

System.Diagnostics (system.dll)

enum

This enumeration represents the different thread priority levels. A thread's priority level is computed relative to the process priority level using `ProcessThread.PriorityLevel`.

```
public enum ThreadPriorityLevel {  
    Normal = 0 ,  
    AboveNormal = 1 ,  
    Highest = 2 ,  
    TimeCritical = 15 ,  
    Idle = -15 ,  
    Lowest = -2 ,  
    BelowNormal = -1  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ThreadPriorityLevel`

Returned By

`ProcessThread.PriorityLevel`

Passed To

`ProcessThread.PriorityLevel`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ThreadState

serializable

System.Diagnostics (system.dll)

enum

This enumeration represents the different thread states as recognized by the operating system. They mostly correspond to the states defined by `System.Threading.ThreadState`, but also include `Transition` for when a thread is waiting on something other than the CPU (it might be waiting on disk I/O, for example).

```
public enum ThreadState {  
    Initialized = 0 ,  
    Ready = 1 ,  
    Running = 2 ,  
    Standby = 3 ,  
    Terminated = 4 ,  
    Wait = 5 ,  
    Transition = 6 ,  
    Unknown = 7  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ThreadState`

Returned By

`ProcessThread.ThreadState`

ThreadWaitReason

serializable

System.Diagnostics (system.dll)

enum

This enumeration specifies the reason a thread is waiting. **VirtualMemory** indicates that a thread is waiting for virtual memory to be allocated, and **PageIn** and **PageOut** indicate that a thread is waiting for virtual memory to page in or out, respectively. **FreePage** is for threads waiting for a free virtual memory page. **EventPairHigh** and **EventPairLow** signal that the thread is waiting on events. **LpcReceive** indicates that a thread is waiting for a local procedure call, and **LpcReply** means that it is waiting for a reply to a local procedure call. If thread execution has been suspended or delayed, you will see either **Suspended** or **ExecutionDelay**. **SystemAllocation** means that the thread is waiting for a system allocation, and **Executive** indicates that it is waiting for the scheduler. **Unknown** is for when the operating system cannot report why a thread is waiting.

```
public enum ThreadWaitReason {
    Executive = 0,
    FreePage = 1,
    PageIn = 2,
    SystemAllocation = 3,
    ExecutionDelay = 4,
    Suspended = 5,
    UserRequest = 6,
    EventPairHigh = 7,
    EventPairLow = 8,
    LpcReceive = 9,
    LpcReply = 10,
    VirtualMemory = 11,
    PageOut = 12,
    Unknown = 13
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → ThreadWaitReason

Returned By

ProcessThread.WaitReason

Trace

CF 1.0

System.Diagnostics (system.dll) *sealed class*

This class supplies static methods and properties to provide tracing ability. The calls to the **Trace** methods and properties are executed only if tracing is enabled. (See the introduction to this chapter for instructions on enabling tracing.)

The static properties allow you to adjust the settings that are used when you call the methods. You can specify that output be indented a certain amount with **IndentLevel** or increase or decrease the **IndentLevel** by one using **Indent()** and **Unindent()**. You can also adjust the number of spaces each indent level adds using **IndentSize**. **AutoFlush** makes sure that after each use of a **Trace** method, the **Listeners** are flushed.

Write() and **WriteLine()** simply write to each **TraceListener** in the **Listeners** collection (by default, this collection includes an instance of **DefaultTraceListener**). **WriteIf()** and **WriteLineIf()** do the same, but only if the specified condition evaluates to **true**. **Assert()** emits an error message if a condition evaluates to **false**, and **Fail()** always emits an error message.

One possible point of confusion is that **Listeners** is read-only. This means that you may not point **Listeners** to a different collection. You can, however, add new **TraceListener** objects to the **TraceListenerCollection** with the **TraceListenerCollection.Add()** method.

You can use the application configuration file to configure this class. Under the **<system.diagnostics>** element, add a **<trace>** element. You can set attributes for this element that correspond to **Trace** properties, as in **<trace autoflush="true" indentsize="4"/>**.

```
public sealed class Trace {
// Public Static Properties
    public static bool AutoFlush{set; get; }
    public static int IndentLevel{set; get; }
    public static int IndentSize{set; get; }
    public static TraceListenerCollection Listeners{get; }
// Public Static Methods
    public static void Assert(bool condition);
    public static void Assert(bool condition, string message);
    public static void Assert(bool condition, string message, string detailMessage);
    public static void Close( );
    public static void Fail(string message);
    public static void Fail(string message, string detailMessage);
    public static void Flush( );
    public static void Indent( );
    public static void Unindent( );
    public static void Write(object value);
    public static void Write(object value, string category);
    public static void Write(string message);
}
```

```
public static void Write(string message, string category);  
public static void WriteIf(bool condition, object value);  
public static void WriteIf(bool condition, object value, string category);  
public static void WriteIf(bool condition, string message);  
public static void WriteIf(bool condition, string message, string category);  
public static void WriteLine(object value);  
public static void WriteLine(object value, string category);  
public static void WriteLine(string message);  
public static void WriteLine(string message, string category);  
public static void WriteLineIf(bool condition, object value);  
public static void WriteLineIf(bool condition, object value, string category);  
public static void WriteLineIf(bool condition, string message);  
public static void WriteLineIf(bool condition, string message, string category);  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

TraceLevel

serializable

System.Diagnostics (system.dll) *enum*

This enumeration represents the possible levels for a trace. Use a `TraceSwitch` to inspect a switch's current level. `Error` indicates that tracing code should emit messages for error conditions, while `Warning` indicates that tracing code should emit both warnings and error messages. `Info` adds to `Warning` by including informational messages along with warnings and errors. `Verbose` indicates that *all* trace messages should be emitted. Turn tracing messages off with `Off`.

```
public enum TraceLevel {  
    Off = 0,  
    Error = 1,  
    Warning = 2,  
    Info = 3,  
    Verbose = 4  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `TraceLevel`

Returned By

`TraceSwitch.Level`

Passed To

`TraceSwitch.Level`

TraceListener

CF 1.0, marshal by reference,
disposable

System.Diagnostics
(system.dll)

abstract class

This abstract class **TraceListener** is associated with a trace through inclusion in the **Trace.Listeners** collection. Each **TraceListener** is responsible for sending trace output somewhere. For example, when you call **Trace.WriteLine()**, each **TraceListener** sends the same output to its respective output destination. Use **Name** to give a name to your **TraceListener** instances.

Use **IndentLevel** to control the level of indentation in the output. **IndentSize** specifies the number of spaces in each level of indent. **NeedIndent** toggles whether to indent the output at all. Use **Write()** and **WriteLine()** to send output to the **TraceListener**'s destination. **WriteIndent()** emits whitespace according to the current **IndentLevel** and **IndentSize**. It has the side effect of setting **NeedIndent** to false, so the next time you call one of the **Write*** methods, it will not emit extra indentation.

You can use the application configuration file to add or remove **TraceListeners**. Look up **System.Diagnostics.TraceListener** in the .NET Framework SDK Documentation for details.

```
public abstract class TraceListener : MarshalByRefObject, IDisposable {
// Protected Constructors
    protected TraceListener( );
    protected TraceListener(string name);
// Public Instance Properties
    public int IndentLevel{set; get; }
    public int IndentSize{set; get; }
    public virtual string Name{set; get; }
// Protected Instance Properties
    protected bool NeedIndent{set; get; }
// Public Instance Methods
    public virtual void Close( );
    public void Dispose( );
// implements IDisposable
    public virtual void Fail(string message);
    public virtual void Fail(string message, string detailMessage);
    public virtual void Flush( );
    public virtual void Write(object o);
    public virtual void Write(object o, string category);
    public abstract void Write(string message);
    public virtual void Write(string message, string category);
    public virtual void WriteLine(object o);
    public virtual void WriteLine(object o, string category);
}
```



```
public abstract void WriteLine(string message);
public virtual void WriteLine(string message, string category);
// Protected Instance Methods
protected virtual void Dispose(bool disposing);
protected virtual void WriteIndent( );
}
```

Hierarchy

System.Object → System.MarshalByRefObject → TraceListener(System.IDisposable)

Subclasses

DefaultTraceListener, EventLogTraceListener, TextWriterTraceListener

Returned By

TraceListenerCollection.this

Passed To

TraceListenerCollection.{Add(), AddRange(), Contains(), CopyTo(), IndexOf(),
Insert(), Remove(), this}

[\[Team LiB \]](#)

TraceListenerCollection

CF 1.0

System.Diagnostics (system.dll) *class*

This class is a strongly typed, thread-safe collection that contains `TraceListener` objects.

```

public class TraceListenerCollection : IList, ICollection, IEnumerable {
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public TraceListener this[string name]{get; }
    public TraceListener this[int i]{set; get; }
// Public Instance Methods
    public int Add(TraceListener listener);
    public void AddRange(TraceListener[] value);
    public void AddRange(TraceListenerCollection value);
    public void Clear( );
// implements IList
    public bool Contains(TraceListener listener);
    public void CopyTo(TraceListener[] listeners, int index);
    public IEnumerator GetEnumerator( );
// implements IEnumerable
    public int IndexOf(TraceListener listener);
    public void Insert(int index, TraceListener listener);
    public void Remove(string name);
    public void Remove(TraceListener listener);
    public void RemoveAt(int index);
// implements IList
}

```

Returned By

Debug.Listeners, Trace.Listeners

TraceSwitch

System.Diagnostics (system.dll) *class*

This class provides a switch that can be set to one of the values in the `TraceLevel` enumeration. These values are inclusive and cumulative (for example, if `Level` is set to `TraceLevel.Info`, then `TraceInfo`, `TraceWarning`, and `TraceError` are true). See `TraceLevel` for more details. You can configure a trace switch using the application configuration file (see `Switch`).

```
public class TraceSwitch : Switch {
// Public Constructors
    public TraceSwitch(string displayName, string description);
// Public Instance Properties
    public TraceLevel Level{set; get; }
    public bool TraceError{get; }
    public bool TraceInfo{get; }
    public bool TraceVerbose{get; }
    public bool TraceWarning{get; }
// Protected Instance Methods
    protected override void OnSwitchSettingChanged( );
// overrides Switch
}
```

Hierarchy


System.Object → Switch → TraceSwitch

Chapter 30. System.Globalization

The `System.Globalization` namespace provides classes that assist in localization of applications based on language and culture. The `CultureInfo` class is the primary container for a set of resources that is used for a specified language and culture implementation. It describes how strings are sorted, the specifics of calendars and date and time formats, as well as language and dialect code pages. An application obtains its culture information based on either the `CultureInfo` specified by the current thread or from the user or local machine's preferences. Specific cultural information is contained in resource files deployed in satellite assemblies. `System.Resources.ResourceManager` marshals these resource files into `System.Resources.ResourceSets` that provide the objects and methods specific to a localization.

The `System.Globalization` namespace provides a base `Calendar` class, as well as specific calendar implementations for major cultures. `CompareInfo` defines how string comparison and sorting are handled. `DateTimeFormatInfo` defines how `DateTime` values are formatted, and `NumberFormatInfo` defines various formatting styles, such as currency symbols and decimal and grouping separators. [Figure 30-1](#) shows the types in this namespace.

Figure 30-1. The System.Globalization namespace



Calendar

CF 1.0, serializable

System.Globalization
(mscorlib.dll)*abstract
class*

This abstract class determines the division and measurement of time in units, such as day, months, year, and eras. It is an abstract base class for culture-specific calendar implementations included in this namespace. Derived classes store the specific information about a calendar's eras, lengths of years and months, and the sometimes esoteric rules for calculating leap years. These properties get used by `DateTimeFormatInfo` to properly display a date and time string from a specific `DateTime` value.

```
public abstract class Calendar {
// Protected Constructors
    protected Calendar( );
// Public Static Fields
    public const int CurrentEra;
// =0
// Public Instance Properties
    public abstract int[ ] Eras{get; }
    public virtual int TwoDigitYearMax{set; get; }
// Public Instance Methods
    public virtual DateTime AddDays(DateTime time, int days);
    public virtual DateTime AddHours(DateTime time, int hours);
    public virtual DateTime AddMilliseconds(DateTime time, double milliseconds);
    public virtual DateTime AddMinutes(DateTime time, int minutes);
    public abstract DateTime AddMonths(DateTime time, int months);
    public virtual DateTime AddSeconds(DateTime time, int seconds);
    public virtual DateTime AddWeeks(DateTime time, int weeks);
    public abstract DateTime AddYears(DateTime time, int years);
    public abstract int GetDayOfMonth(DateTime time);
    public abstract DayOfWeek GetDayOfWeek(DateTime time);
    public abstract int GetDayOfYear(DateTime time);
    public virtual int GetDaysInMonth(int year, int month);
    public abstract int GetDaysInMonth(int year, int month, int era);
    public virtual int GetDaysInYear(int year);
    public abstract int GetDaysInYear(int year, int era);
    public abstract int GetEra(DateTime time);
    public virtual int GetHour(DateTime time);
    public virtual double GetMilliseconds(DateTime time);
    public virtual int GetMinute(DateTime time);
    public abstract int GetMonth(DateTime time);
    public virtual int GetMonthsInYear(int year);
    public abstract int GetMonthsInYear(int year, int era);
    public virtual int GetSecond(DateTime time);
```

```
public virtual int GetWeekOfYear(DateTime time, CalendarWeekRule rule,
    DayOfWeek firstDayOfWeek);
public abstract int GetYear(DateTime time);
public virtual bool IsLeapDay(int year, int month, int day);
public abstract bool IsLeapDay(int year, int month, int day, int era);
public virtual bool IsLeapMonth(int year, int month);
public abstract bool IsLeapMonth(int year, int month, int era);
public virtual bool IsLeapYear(int year);
public abstract bool IsLeapYear(int year, int era);
public virtual DateTime ToDateTime(int year, int month, int day, int hour, int minute,
    int second, int millisecond);
public abstract DateTime ToDateTime(int year, int month, int day, int hour, int minute,
    int second, int millisecond, int era);
public virtual int ToFourDigitYear(int year);
}
```

Subclasses

GregorianCalendar , HebrewCalendar , HijriCalendar , JapaneseCalendar , JulianCalendar , KoreanCalendar , TaiwanCalendar , ThaiBuddhistCalendar

Returned By

CultureInfo.{Calendar , OptionalCalendars} , DateTimeFormatInfo.Calendar

Passed To

System.DateTime.ToDateTime() , DateTimeFormatInfo.Calendar

[Team LiB]

CalendarWeekRule CF 1.0, serializable

System.Globalization (mscorlib.dll) *enum*

This enumeration contains values that specify how the first week of a calendar year is determined. Each calendar requires that the starting day of a week is designated (i.e., Sunday in the Gregorian calendar). The value `FirstDay` designates that the first calendar week begins on the first day of the year regardless of the number of days left in the week. The `FirstFourDayWeek` specifies the first week that has at least four days in it. `FirstFullWeek` uses the first complete week as the first in the calendar.

```
public enum CalendarWeekRule {  
    FirstDay = 0 ,  
    FirstFullWeek = 1 ,  
    FirstFourDayWeek = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `CalendarWeekRule`

Returned By

`DateTimeFormatInfo.CalendarWeekRule`

Passed To

`Calendar.GetWeekOfYear(), DateTimeFormatInfo.CalendarWeekRule`

CompareInfo

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class defines methods of string comparison that follow culture-specific rules. The `CultureInfo.Compare` contains an instance of this class. The `Compare()` method and other string searching methods, such as `IsPrefix()`, can be passed a set of `CompareOptions`, which provide culture-specific flags related to string comparison. The `GetCompareInfo()` method is used instead of a public constructor to retrieve an instance of this class.

```
public class CompareInfo : System.Runtime.Serialization.IDeserializationCallback {
// Public Instance Properties
    public int LCID{get; }
// Public Static Methods
    public static CompareInfo GetCompareInfo(int culture);
    public static CompareInfo GetCompareInfo(int culture, System.Reflection.Assembly assembly);
    public static CompareInfo GetCompareInfo(string name);
    public static CompareInfo GetCompareInfo(string name, System.Reflection.Assembly assembly);
// Public Instance Methods
    public virtual int Compare(string string1, int offset1, int length1, string string2,
        int offset2, int length2);
    public virtual int Compare(string string1, int offset1, int length1, string string2,
        int offset2, int length2, CompareOptions options);
    public virtual int Compare(string string1, int offset1, string string2, int offset2);
    public virtual int Compare(string string1, int offset1, string string2, int offset2,
        CompareOptions options);
    public virtual int Compare(string string1, string string2);
    public virtual int Compare(string string1, string string2, CompareOptions options);
    public override bool Equals(object value);
// overrides object
    public override int GetHashCode( );
// overrides object
    public virtual SortKey GetSortKey(string source);
    public virtual SortKey GetSortKey(string source, CompareOptions options);
    public virtual int IndexOf(string source, char value);
    public virtual int IndexOf(string source, char value, CompareOptions options);
    public virtual int IndexOf(string source, char value, int startIndex);
    public virtual int IndexOf(string source, char value, int startIndex, CompareOptions options);
    public virtual int IndexOf(string source, char value, int startIndex, int count);
    public virtual int IndexOf(string source, char value, int startIndex, int count,
        CompareOptions options);
    public virtual int IndexOf(string source, string value);
    public virtual int IndexOf(string source, string value, CompareOptions options);
    public virtual int IndexOf(string source, string value, int startIndex);
    public virtual int IndexOf(string source, string value, int startIndex, CompareOptions options);
}
```

```
public virtual int IndexOf(string source, string value, int startIndex, int count);
public virtual int IndexOf(string source, string value, int startIndex, int count,
    CompareOptions options);
public virtual bool IsPrefix(string source, string prefix);
public virtual bool IsPrefix(string source, string prefix, CompareOptions options);
public virtual bool IsSuffix(string source, string suffix);
public virtual bool IsSuffix(string source, string suffix, CompareOptions options);
public virtual int LastIndexOf(string source, char value);
public virtual int LastIndexOf(string source, char value, CompareOptions options);
public virtual int LastIndexOf(string source, char value, int startIndex);
public virtual int LastIndexOf(string source, char value, int startIndex, CompareOptions options);
public virtual int LastIndexOf(string source, char value, int startIndex, int count);
public virtual int LastIndexOf(string source, char value, int startIndex, int count,
    CompareOptions options);
public virtual int LastIndexOf(string source, string value);
public virtual int LastIndexOf(string source, string value, CompareOptions options);
public virtual int LastIndexOf(string source, string value, int startIndex);
public virtual int LastIndexOf(string source, string value, int startIndex, CompareOptions options);
public virtual int LastIndexOf(string source, string value, int startIndex, int count);
public virtual int LastIndexOf(string source, string value, int startIndex, int count,
    CompareOptions options);
public override string ToString( );
// overrides object
}
```

Returned By

CultureInfo.CompareInfo

[Team LiB]

CompareOptions CF 1.0, serializable, flag

System.Globalization (mscorlib.dll) *enum*

This enumeration defines a set of constants that set culture-specific behavior on string comparisons in the `CompareInfo` class. `IgnoreKanaType` treats phonetic Japanese symbols the same whether they are in hiragana or katagana characters. `IgnoreNonSpace` disregards nonspacing characters such as diacritics. `Ordinal` specifies that comparison is done with Unicode values.

```
public enum CompareOptions {
    None = 0x00000000 ,
    IgnoreCase = 0x00000001 ,
    IgnoreNonSpace = 0x00000002 ,
    IgnoreSymbols = 0x00000004 ,
    IgnoreKanaType = 0x00000008 ,
    IgnoreWidth = 0x00000010 ,
    StringSort = 0x20000000 ,
    Ordinal = 0x40000000
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `CompareOptions`

Passed To

```
CompareInfo.{Compare( ), GetSortKey( ), IndexOf( ), IsPrefix( ), IsSuffix( ),
LastIndexOf( )}
```

CultureInfo CF 1.0, ECMA 1.0, serializable

System.Globalization (mscorlib.dll) *class*

The **CultureInfo** class encapsulates information about handling information according to the special requirements of a particular culture and language. Culture information is identified by language and country/region codes as specified in RFC 1766. For example, U.S. English is identified as **en-US**. The two-letter, lowercase language codes are defined in ISO 639-1. The two-letter, uppercase region codes are defined in ISO 3166.

The specific **CultureInfo** to use at runtime can be found in a number of ways. The class provides four public properties that return the current **CultureInfo** instance. **CurrentCulture** returns the value of **Thread.CurrentCulture**, which is the **CultureInfo** used by the current thread. **CurrentUICulture** returns the **CultureInfo** used by the **System.Resources.ResourceManager**. This can be a user, machine, or application-based locale setting. It is set in **Thread.CurrentUICulture**. **InstalledUICulture** gets the default **CultureInfo** used by the **ResourceManager** and represents the locale of the Operating system. **InvariantCulture** returns the **CultureInfo** for the invariant locale, which is non-culture-specific, as well as in the default OS language. This is used with non-culture-specific functions such as system-level calls.

The instance properties of the class provide a number of ways to retrieve the culture name. For example, **NativeName** gets the culture name in the language of that culture. **LCID** gets the NLS-specified number for a culture name. Other properties get or set the various class instances used for localization. **Calendar**, **CompareInfo**, **DateTimeFormat**, **NumberFormat**, and **TextInfo** return instances of the analogous classes that set their functionality.

```
public class CultureInfo : ICloneable, IFormatProvider {
// Public Constructors
    public CultureInfo(int culture);
    public CultureInfo(int culture, bool useUserOverride);
    public CultureInfo(string name);
    public CultureInfo(string name, bool useUserOverride);
// Public Static Properties
    public static CultureInfo CurrentCulture {get; }
    public static CultureInfo CurrentUICulture {get; }
    public static CultureInfo InstalledUICulture {get; }
    public static CultureInfo InvariantCulture {get; }
// Public Instance Properties
    public virtual Calendar Calendar {get; }
    public virtual CompareInfo CompareInfo {get; }
    public virtual DateTimeFormatInfo DateTimeFormat {set; get; }
    public virtual string DisplayName {get; }
    public virtual string EnglishName {get; }
    public virtual bool IsNeutralCulture {get; }
    public bool IsReadOnly {get; }
    public virtual int LCID {get; }
```

```

    public virtual string Name{get; }
    public virtual string NativeName{get; }
    public virtual NumberFormatInfo NumberFormat{set; get; }
    public virtual Calendar[ ] OptionalCalendars{get; }
    public virtual CultureInfo Parent{get; }
    public virtual TextInfo TextInfo{get; }
    public virtual string ThreeLetterISOLanguageName{get; }
    public virtual string ThreeLetterWindowsLanguageName{get; }
    public virtual string TwoLetterISOLanguageName{get; }
    public bool UseUserOverride{get; }
// Public Static Methods
    public static CultureInfo CreateSpecificCulture(string name);
    public static CultureInfo[ ] GetCultures(CultureTypes types);
    public static CultureInfo ReadOnly(CultureInfo ci);
// Public Instance Methods
    public void ClearCachedData( );
    public virtual object Clone( );
// implements ICloneable
    public override bool Equals(object value);
// overrides object
    public virtual object GetFormat(Type formatType);
// implements IFormatProvider
    public override int GetHashCode( );
// overrides object
    public override string ToString( );
// overrides object
}

```

Returned By

System.Reflection.AssemblyName.CultureInfo, System.Threading.Thread.{CurrentCulture, CurrentUICulture}

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

CultureTypes CF 1.0, serializable, flag

System.Globalization (mscorlib.dll) *enum*

The values of this enumeration determine which cultures are returned by `CultureInfo.GetCultures()`. `NeutralCultures` specifies language-specific cultures without any regional or country association. `SpecificCultures` specifies cultures that are identified by both language and region.

```
public enum CultureTypes {  
    NeutralCultures = 0x00000001 ,  
    SpecificCultures = 0x00000002 ,  
    InstalledWin32Cultures = 0x00000004 ,  
    AllCultures = 0x00000007  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `CultureTypes`

Passed To

`CultureInfo.GetCultures()`

DateTimeFormatInfo

CF 1.0, ECMA 1.0,
serializableSystem.Globalization
(mscorlib.dll)*sealed*
class

This class defines how **DateTime** values are formatted for a culture. Several standard patterns are defined with the default property values. These standard patterns are designated by a format character. The format character provides a shortcut to specify the format of a **DateTime** with the **ToString()** method. You can create custom formats using a set of format pattern characters. These characters represent different styles of day and time representations and allow you to build customized pattern strings. To create custom patterns, first you need to construct a writable instance of **DateTimeFormatInfo** by using its constructor. Use **InvariantInfo** to fetch a culture-independent, read-only instance of this class.

```
public sealed class DateTimeFormatInfo : ICloneable, IFormatProvider {
// Public Constructors
    public DateTimeFormatInfo( );
// Public Static Properties
    public static DateTimeFormatInfo CurrentInfo{get; }
    public static DateTimeFormatInfo InvariantInfo{get; }
// Public Instance Properties
    public string[ ] AbbreviatedDayNames{set; get; }
    public string[ ] AbbreviatedMonthNames{set; get; }
    public string AMDesignator{set; get; }
    public Calendar Calendar{set; get; }
    public CalendarWeekRule CalendarWeekRule{set; get; }
    public string DateSeparator{set; get; }
    public string[ ] DayNames{set; get; }
    public DayOfWeek FirstDayOfWeek{set; get; }
    public string FullDateTimePattern{set; get; }
    public bool IsReadOnly{get; }
    public string LongDatePattern{set; get; }
    public string LongTimePattern{set; get; }
    public string MonthDayPattern{set; get; }
    public string[ ] MonthNames{set; get; }
    public string PMDesignator{set; get; }
    public string RFC1123Pattern{get; }
    public string ShortDatePattern{set; get; }
    public string ShortTimePattern{set; get; }
    public string SortableDateTimePattern{get; }
    public string TimeSeparator{set; get; }
    public string UniversalSortableDateTimePattern{get; }
    public string YearMonthPattern{set; get; }
// Public Static Methods
```

```
    public static DateTimeFormatInfo GetInstance(IFormatProvider provider);  
    public static DateTimeFormatInfo ReadOnly(DateTimeFormatInfo dtfi);  
    // Public Instance Methods  
    public object Clone( );  
    // implements ICloneable  
    public string GetAbbreviatedDayName(DayOfWeek dayofweek);  
    public string GetAbbreviatedEraName(int era);  
    public string GetAbbreviatedMonthName(int month);  
    public string[ ] GetAllDateTimePatterns( );  
    public string[ ] GetAllDateTimePatterns(char format);  
    public string GetDayName(DayOfWeek dayofweek);  
    public int GetEra(string eraName);  
    public string GetEraName(int era);  
    public object GetFormat(Type formatType);  
    // implements IFormatProvider  
    public string GetMonthName(int month);  
}
```

Returned By

CultureInfo.DateTimeFormat

Passed To

CultureInfo.DateTimeFormat

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

DateTimeStyles

CF 1.0, ECMA 1.0,
serializable, flag

System.Globalization (mscorlib.dll) *enum*

This enumeration provides several formatting options for the `DateTime.Parse()` and `DateTime.ParseExact()` methods to use. The values supplied mostly determine how whitespace is dealt with when a string is parsed into a `DateTime` value by `ParseExact()`. When the string is compared to a format pattern, some whitespace can be disregarded if it is not exactly aligned with the pattern. `Parse()` ignores whitespace by default, so `AdjustToUniversal` and `NoCurrentDateDefault` are the only relevant values for that method. If the string to parse does not include a date with `NoCurrentDateDefault`, its result is created with day, month, and year values all set to 1. The date and time are converted to coordinated universal time (UTC) with `AdjustToUniversal`.

```
public enum DateTimeStyles {
    None = 0x00000000 ,
    AllowLeadingWhite = 0x00000001 ,
    AllowTrailingWhite = 0x00000002 ,
    AllowInnerWhite = 0x00000004 ,
    AllowWhiteSpaces = 0x00000007 ,
    NoCurrentDateDefault = 0x00000008 ,
    AdjustToUniversal = 0x00000010
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → DateTimeStyles

Passed To

System.DateTime.{Parse(), ParseExact()}

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DaylightTime

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This setting defines when daylight saving time begins and ends. It uses three properties: **Start** is the time when daylight saving time begins; **End** is when standard time resumes; and **Delta** is the length of time (measured in ticks) that the clock is adjusted from standard time during this period. **Delta** is a **System.TimeSpan** value measured in "ticks," or 100-nanosecond periods.

```
public class DaylightTime {  
    // Public Constructors  
    public DaylightTime(DateTime start, DateTime end, TimeSpan delta);  
    // Public Instance Properties  
    public TimeSpan Delta {get; }  
    public DateTime End {get; }  
    public DateTime Start {get; }  
}
```

Returned By

```
System.TimeZone.GetDaylightChanges( )
```

Passed To

```
System.TimeZone.IsDaylightSavingTime( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

GregorianCalendar

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class implements the standard Western calendar, and also the default culture-invariant calendar. It defines two eras (B.C./B.C.E. and A.D./C.E.), 12 months per year. A leap year occurs every 4 years except for years divisible by 100. However, years divisible by 400 are leap years. Only the current era (A.D./C.E.) is recognized by .NET's implementation of the Gregorian calendar.

```
public class GregorianCalendar : Calendar {
// Public Constructors
    public GregorianCalendar( );
    public GregorianCalendar(GregorianCalendarTypes type);
// Public Static Fields
    public const int ADEra;
// =1
// Public Instance Properties
    public virtual GregorianCalendarTypes CalendarType{set; get; }
    public override int[ ] Eras{get; }
// overrides Calendar
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months);
// overrides Calendar
    public override DateTime AddWeeks(DateTime time, int weeks)
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
```

```
// overrides Calendar
public override int GetYear(DateTime time);
// overrides Calendar
public override bool IsLeapDay(int year, int month, int day, int era)
// overrides Calendar
public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
public override bool IsLeapYear(int year, int era);
// overrides Calendar
public override DateTime ToDateTime(int year, int month, int day,
    int hour, int minute, int second, int millisecond, int era)
// overrides Calendar
public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → GregorianCalendar

[\[Team LiB \]](#)

GregorianCalendarTypes CF 1.0, serializable

System.Globalization (mscorlib.dll) *enum*

This enumeration specifies some language-specific variations of the Gregorian calendar that can be set with the `GregorianCalendar.CalendarType` property.

```
public enum GregorianCalendarTypes {  
    Localized = 1 ,  
    USEnglish = 2 ,  
    MiddleEastFrench = 9 ,  
    Arabic = 10 ,  
    TransliteratedEnglish = 11 ,  
    TransliteratedFrench = 12  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `GregorianCalendarTypes`

Returned By

`GregorianCalendar.CalendarType`

Passed To

`GregorianCalendar.{CalendarType, GregorianCalendar()}`

HebrewCalendar

serializable

System.Globalizatiion (mscorlib.dll) *class*

This calendar class implements the Hebrew calendar. This complicated calendar determines leap years within a 19-year cycle. The 3rd, 6th, 8th, 11th, 14th, 17th, and 19th years are leap years. Regular years have 12 months and between 353 and 355 days, and leap years have 13 months and between 383 and 385 days; the variance is determined by the placement of Jewish holidays. This implementation recognizes the years 5343 to 6000 (A.M.), which is equivalent to the Gregorian years 1582 to 2240.

```
public class HebrewCalendar : Calendar {
// Public Constructors
    public HebrewCalendar( );
// Public Static Fields
    public static readonly int HebrewEra;
// =1
// Public Instance Properties
    public override int[ ] Eras{get; }
// overrides Calendar
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months);
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
```

```
// overrides Calendar
public override bool IsLeapDay(int year, int month, int day, int era)
// overrides Calendar
public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
public override bool IsLeapYear(int year, int era);
// overrides Calendar
public override DateTime ToDateTime(int year, int month, int day, int hour,
    int minute, int second, int millisecond, int era)
// overrides Calendar
public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → HebrewCalendar

[\[Team LiB \]](#)

HijriCalendar

serializable

System.Globalization (mscorlib.dll) *class*

This calendar class implements the Islamic Hijri calendar. This calendar is based from the time of Mohammed's migration from Mecca (denoted as A.H.). Regular years have 12 months and 354 days. Leap years have 355 days. Leap years are calculated in 30-year cycles, occurring in the 2nd, 5th, 7th, 10th, 13th, 16th, 18th, 21st, 24th, 26th, and 29th years.

```
public class HijriCalendar : Calendar {
// Public Constructors
    public HijriCalendar( );
// Public Static Fields
    public static readonly int HijriEra;
// =1
// Public Instance Properties
    public override int[ ] Eras{get; }
// overrides Calendar
    public int HijriAdjustment{set; get; }
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months)
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era);
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
// overrides Calendar
```



```
        public override bool IsLeapDay(int year, int month, int day, int era);  
// overrides Calendar  
        public override bool IsLeapMonth(int year, int month, int era);  
// overrides Calendar  
        public override bool IsLeapYear(int year, int era);  
// overrides Calendar  
        public override DateTime ToDateTime(int year, int month, int day,  
            int hour, int minute, int second, int millisecond, int era);  
// overrides Calendar  
        public override int ToFourDigitYear(int year);  
// overrides Calendar  
    }  
}
```

Hierarchy

System.Object → Calendar → HijriCalendar

[\[Team LiB \]](#)

JapaneseCalendar

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This calendar class implements the Japanese or Wareki calendar. This calendar follows the same rules and settings as the Gregorian calendar, except that it is divided into eras based on the reign of each Japanese Emperor.

```
public class JapaneseCalendar : Calendar {
// Public Constructors
    public JapaneseCalendar( );
// Public Instance Properties
    public override int[] Eras {get; }
// overrides Calendar
    public override int TwoDigitYearMax {set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months)
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
// overrides Calendar
    public override bool IsLeapDay(int year, int month, int day, int era)
// overrides Calendar
    public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
    public override bool IsLeapYear(int year, int era);
```

```
// overrides Calendar
    public override DateTime ToDateTime(int year, int month, int day,
        int hour,int minute, int second, int millisecond, int era)
// overrides Calendar
    public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → JapaneseCalendar

[\[Team LIB \]](#)

JulianCalendar

serializable

System.Globalization (mscorlib.dll) *class*

This calendar class implements the calendar created by a decree from Julius Caesar in 45 B.C.E. The calendar recognizes a leap year every four years without exception, but in all other respects is the same as the Gregorian calendar, which replaced it in 1582 C.E. Due to the difference in leap-year calculation, the Julian calendar is currently 12 days behind the Gregorian calendar.

```
public class JulianCalendar : Calendar {
    // Public Constructors
    public JulianCalendar( );
    // Public Static Fields
    public static readonly int JulianEra;
    // =1
    // Public Instance Properties
    public override int[ ] Eras{get; }
    // overrides Calendar
    public override int TwoDigitYearMax{set; get; }
    // overrides Calendar
    // Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months)
    // overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
    // overrides Calendar
    public override int GetDayOfMonth(DateTime time);
    // overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
    // overrides Calendar
    public override int GetDayOfYear(DateTime time);
    // overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
    // overrides Calendar
    public override int GetDaysInYear(int year, int era);
    // overrides Calendar
    public override int GetEra(DateTime time);
    // overrides Calendar
    public override int GetMonth(DateTime time);
    // overrides Calendar
    public override int GetMonthsInYear(int year, int era);
    // overrides Calendar
    public override int GetYear(DateTime time);
    // overrides Calendar
    public override bool IsLeapDay(int year, int month, int day, int era)
```

```
// overrides Calendar
public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
public override bool IsLeapYear(int year, int era);
// overrides Calendar
public override DateTime ToDateTime(int year, int month, int day, int hour,
    int minute, int second, int millisecond, int era)
// overrides Calendar
public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → JulianCalendar

[\[Team LiB \]](#)

KoreanCalendar

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This calendar class implements the Korean calendar. The Korean calendar is the same as the Gregorian calendar except that the eras are defined differently. 01 January, 2001 on the Gregorian calendar is 01 January, 4334 on the Korean calendar.

```
public class KoreanCalendar : Calendar {
// Public Constructors
    public KoreanCalendar( );
// Public Static Fields
    public const int KoreanEra;
// =1
// Public Instance Properties
    public override int[ ] Eras{get; }
// overrides Calendar
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time,
// overrides Calendar
        int months);
    public override DateTime AddYears(DateTime time,
// overrides Calendar
        int years);
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month,
        int era);
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
```

```
// overrides Calendar
    public override bool IsLeapDay(int year, int month,
// overrides Calendar
        int day, int era);
    public override bool IsLeapMonth(int year, int month,
        int era);
// overrides Calendar
    public override bool IsLeapYear(int year, int era);
// overrides Calendar
    public override DateTime ToDateTime(int year, int month,
        int day, int hour, int minute, int second, int millisecond, int era);
// overrides Calendar
    public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → KoreanCalendar

[\[Team LIB \]](#)

NumberFormatInfo

CF 1.0, ECMA 1.0,
serializable

System.Globalization
(mscorlib.dll)

sealed
class

This class defines how numbers are displayed according to culture and language. Formats for currency and its symbols and types of numeric formats, such as scientific and hexadecimal notations and their separators, are described by the properties of this class. As with `DateTimeFormatInfo`, a set of standard numeric formats is predefined and specified by format characters.

The default property values apply to the invariant culture settings. The culture-specific `NumberFormatInfo` instance is retrieved by `CurrentInfo`, which is determined by the `CultureInfo` of the current thread or environment.

```
public sealed class NumberFormatInfo : ICloneable, IFormatProvider {
// Public Constructors
    public NumberFormatInfo( );
// Public Static Properties
    public static NumberFormatInfo CurrentInfo{get; }
    public static NumberFormatInfo InvariantInfo{get; }
// Public Instance Properties
    public int CurrencyDecimalDigits{set; get; }
    public string CurrencyDecimalSeparator{set; get; }
    public string CurrencyGroupSeparator{set; get; }
    public int[] CurrencyGroupSizes{set; get; }
    public int CurrencyNegativePattern{set; get; }
    public int CurrencyPositivePattern{set; get; }
    public string CurrencySymbol{set; get; }
    public bool IsReadOnly{get; }
    public string NaNSymbol{set; get; }
    public string NegativeInfinitySymbol{set; get; }
    public string NegativeSign{set; get; }
    public int NumberDecimalDigits{set; get; }
    public string NumberDecimalSeparator{set; get; }
    public string NumberGroupSeparator{set; get; }
    public int[] NumberGroupSizes{set; get; }
    public int NumberNegativePattern{set; get; }
    public int PercentDecimalDigits{set; get; }
    public string PercentDecimalSeparator{set; get; }
    public string PercentGroupSeparator{set; get; }
    public int[] PercentGroupSizes{set; get; }
    public int PercentNegativePattern{set; get; }
    public int PercentPositivePattern{set; get; }
    public string PercentSymbol{set; get; }
```



```
public string PerMilleSymbol{set; get; }
public string PositiveInfinitySymbol{set; get; }
public string PositiveSign{set; get; }
// Public Static Methods
public static NumberFormatInfo GetInstance(IFormatProvider formatProvider);
public static NumberFormatInfo ReadOnly(NumberFormatInfo nfi);
// Public Instance Methods
public object Clone( );
// implements ICloneable
public object GetFormat(Type formatType);
// implements IFormatProvider
}
```

Returned By

CultureInfo.NumberFormat

Passed To

CultureInfo.NumberFormat

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

NumberStyles CF 1.0, ECMA 1.0, serializable, flag

System.Globalization (mscorlib.dll) *enum*

This enumeration specifies a number of style rules that may be used when a numeric type uses the `Parse()` method to convert a string into a number.

```
public enum NumberStyles {
    None = 0x00000000 ,
    AllowLeadingWhite = 0x00000001 ,
    AllowTrailingWhite = 0x00000002 ,
    AllowLeadingSign = 0x00000004 ,
    Integer = 0x00000007 ,
    AllowTrailingSign = 0x00000008 ,
    AllowParentheses = 0x00000010 ,
    AllowDecimalPoint = 0x00000020 ,
    AllowThousands = 0x00000040 ,
    Number = 0x0000006F ,
    AllowExponent = 0x00000080 ,
    Float = 0x000000A7 ,
    AllowCurrencySymbol = 0x00000100 ,
    Currency = 0x0000017F ,
    Any = 0x000001FF ,
    AllowHexSpecifier = 0x00000200 ,
    HexNumber = 0x00000203
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → NumberStyles

Passed To

System.Byte.Parse(), System.Decimal.Parse(), System.Double.{Parse(), TryParse()}, System.Int16.Parse(), System.Int32.Parse(), System.Int64.Parse(), System.SByte.Parse(), System.Single.Parse(), System.UInt16.Parse(), System.UInt32.Parse(), System.UInt64.Parse()

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

RegionInfo

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class contains properties for the selected region or country settings. It stores information on the name and standard letter codes for the region, the currency symbol, and whether the metric system is used or not. The region names are the two- and three-letter codes defined in ISO 3166. Currency strings are defined by ISO 4217.

```
public class RegionInfo {
// Public Constructors
    public RegionInfo(int culture);
    public RegionInfo(string name);
// Public Static Properties
    public static RegionInfo CurrentRegion {get; }
// Public Instance Properties
    public virtual string CurrencySymbol {get; }
    public virtual string DisplayName {get; }
    public virtual string EnglishName {get; }
    public virtual bool IsMetric {get; }
    public virtual string ISOCurrencySymbol {get; }
    public virtual string Name {get; }
    public virtual string ThreeLetterISORegionName {get; }
    public virtual string ThreeLetterWindowsRegionName {get; }
    public virtual string TwoLetterISORegionName {get; }
// Public Instance Methods
    public override bool Equals(object value);
// overrides object
    public override int GetHashCode( );
// overrides object
    public override string ToString( );
// overrides object
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

SortKey

serializable

System.Globalization (mscorlib.dll)

class

This class represents a set of weighted classifications used to sort individual elements of a string.

```
public class SortKey {  
    // Public Instance Properties  
    public virtual byte[ ] KeyData{get; }  
    public virtual string OriginalString{get; }  
    // Public Static Methods  
    public static int Compare(SortKey sortkey1, SortKey sortkey2);  
    // Public Instance Methods  
    public override bool Equals(object value);  
    // overrides object  
    public override int GetHashCode( );  
    // overrides object  
    public override string ToString( );  
    // overrides object  
}
```

Returned By

CompareInfo.GetSortKey()

StringInfo

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class allows you to manipulate a string by its individual elements. Each separately displayed character is considered a text element. This includes base characters and the Unicode-defined surrogate pairs and combining character sequences. The class provides enumeration of the elements in the string, as well as a means of further identifying combining characters. `ParseCombiningCharacters()` returns only the indexes of the base characters, high surrogates, and combined characters within a string.

```
public class StringInfo {  
    // Public Constructors  
    public StringInfo( );  
    // Public Static Methods  
    public static string GetNextTextElement(string str);  
    public static string GetNextTextElement(string str, int index);  
    public static TextElementEnumerator GetTextElementEnumerator(string str);  
    public static TextElementEnumerator GetTextElementEnumerator(string str, int index);  
    public static int[ ] ParseCombiningCharacters(string str);  
}
```

TaiwanCalendar

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class implements the Taiwanese calendar. This calendar works like the Gregorian calendar, except for difference in the year and era. 2001 in the Gregorian calendar is the year 90 in the Taiwanese calendar.

```
public class TaiwanCalendar : Calendar {
// Public Constructors
    public TaiwanCalendar( );
// Public Instance Properties
    public override int[ ] Eras{get; }
// overrides Calendar
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonths(DateTime time, int months)
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
// overrides Calendar
    public override bool IsLeapDay(int year, int month, int day, int era)
// overrides Calendar
    public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
    public override bool IsLeapYear(int year, int era);
```

```
// overrides Calendar
    public override DateTime ToDateTime(int year, int month, int day, int hour,
        int minute, int second, int millisecond, int era)
// overrides Calendar
    public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → TaiwanCalendar

[\[Team LIB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TextElementEnumerator CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class provides enumeration for individual text elements in a string composed of complex characters. This enumerator is retrieved by `StringInfo.GetTextElementEnumerator()`.

```
public class TextElementEnumerator : IEnumerator {  
    // Public Instance Properties  
    public object Current{get; }  
    // implements IEnumerator  
    public int ElementIndex{get; }  
    // Public Instance Methods  
    public string GetTextElement( );  
    public bool MoveNext( );  
    // implements IEnumerator  
    public void Reset( );  
    // implements IEnumerator  
}
```

Returned By

```
StringInfo.GetTextElementEnumerator( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TextInfo

CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class is used to describe certain properties of the writing system in use by a culture. The properties of this class specify system-specific and standardized code pages for text, as well as the `ListSeparator` string (a "," for the invariant culture). `TextInfo` defines methods that determine casing semantics per culture. For example, `ToLower()` returns the lowercase version of the specified character or string. The `ToTitleCase()` method capitalizes the first letter of each word in a string.

```
public class TextInfo : System.Runtime.Serialization.IDeserializationCallback {
// Public Instance Properties
    public virtual int ANSICodePage{get; }
    public virtual int EBCDICCodePage{get; }
    public virtual string ListSeparator{get; }
    public virtual int MacCodePage{get; }
    public virtual int OEMCodePage{get; }
// Public Instance Methods
    public override bool Equals(object obj);
// overrides object
    public override int GetHashCode( );
// overrides object
    public virtual char ToLower(char c);
    public virtual string ToLower(string str);
    public override string ToString( );
// overrides object
    public string ToTitleCase(string str);
    public virtual char ToUpper(char c);
    public virtual string ToUpper(string str);
}
```

Returned By

CultureInfo.TextInfo

ThaiBuddhistCalendar CF 1.0, serializable

System.Globalization (mscorlib.dll) *class*

This class implements the Thai Buddhist calendar. This calendar works like the Gregorian calendar except for the year and era. 2001 in the Gregorian calendar is the year 2544 in the Thai Buddhist calendar.

```
public class ThaiBuddhistCalendar : Calendar {
// Public Constructors
    public ThaiBuddhistCalendar( );
// Public Static Fields
    public const int ThaiBuddhistEra;
// =1
// Public Instance Properties
    public override int[ ] Eras{get; }
// overrides Calendar
    public override int TwoDigitYearMax{set; get; }
// overrides Calendar
// Public Instance Methods
    public override DateTime AddMonth4s(DateTime time, int months)
// overrides Calendar
    public override DateTime AddYears(DateTime time, int years)
// overrides Calendar
    public override int GetDayOfMonth(DateTime time);
// overrides Calendar
    public override DayOfWeek GetDayOfWeek(DateTime time);
// overrides Calendar
    public override int GetDayOfYear(DateTime time);
// overrides Calendar
    public override int GetDaysInMonth(int year, int month, int era)
// overrides Calendar
    public override int GetDaysInYear(int year, int era);
// overrides Calendar
    public override int GetEra(DateTime time);
// overrides Calendar
    public override int GetMonth(DateTime time);
// overrides Calendar
    public override int GetMonthsInYear(int year, int era);
// overrides Calendar
    public override int GetYear(DateTime time);
// overrides Calendar
    public override bool IsLeapDay(int year, int month, int day, int era)
// overrides Calendar
```

```
    public override bool IsLeapMonth(int year, int month, int era)
// overrides Calendar
    public override bool IsLeapYear(int year, int era);
// overrides Calendar
    public override DateTime ToDateTime(int year, int month, int day, int hour,
        int minute, int second, int millisecond, int era)
// overrides Calendar
    public override int ToFourDigitYear(int year);
// overrides Calendar
}
```

Hierarchy

System.Object → Calendar → ThaiBuddhistCalendar

[\[Team LiB \]](#)

UnicodeCategory


CF 1.0, ECMA 1.0,
serializable

System.Globalization (mscorlib.dll) *enum*

The values of this enumeration specify the specific category of a character defined by the Unicode standard. This enumeration supports the `System.Char` class in determining properties of Unicode characters such as case with regard to the `CultureInfo` setting.

```
public enum UnicodeCategory {
    UppercaseLetter = 0 ,
    LowercaseLetter = 1 ,
    TitlecaseLetter = 2 ,
    ModifierLetter = 3 ,
    OtherLetter = 4 ,
    NonSpacingMark = 5 ,
    SpacingCombiningMark = 6 ,
    EnclosingMark = 7 ,
    DecimalDigitNumber = 8 ,
    LetterNumber = 9 ,
    OtherNumber = 10 ,
    SpaceSeparator = 11 ,
    LineSeparator = 12 ,
    ParagraphSeparator = 13 ,
    Control = 14 ,
    Format = 15 ,
    Surrogate = 16 ,
    PrivateUse = 17 ,
    ConnectorPunctuation = 18 ,
    DashPunctuation = 19 ,
    OpenPunctuation = 20 ,
    ClosePunctuation = 21 ,
    InitialQuotePunctuation = 22 ,
    FinalQuotePunctuation = 23 ,
    OtherPunctuation = 24 ,
    MathSymbol = 25 ,
    CurrencySymbol = 26 ,
    ModifierSymbol = 27 ,
    OtherSymbol = 28 ,
    OtherNotAssigned = 29
}
```

Hierarchy



System.IFormattable, System.IConvertible) → UnicodeCategory

Returned By

System.Char.GetUnicodeCategory()

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

Chapter 31. System.IO

The `System.IO` types serve as the primary means for stream-oriented I/O-files, principally, although the abstract types defined here serve as base classes for other forms of I/O, such as the XML stack in `System.Xml`. The `System.IO` namespace is shown in [Figure 31-1](#) and [Figure 31-2](#).

The `System.IO` namespace can be seen as two distinct partitions: a set of utility types for using and working with the local machine's filesystem, and a protocol stack for working with bytestream-oriented input and output. The former partition is the collection of classes such as `Directory` and `FileSystemWatcher`, whereas the latter partition is the set of `Stream` and `Reader/Writer` types.

The `Stream` types in `System.IO` follow a basic object model, similar to the I/O model used by the C/C++ runtime library: all serial byte access is a stream, and there are different sources and sinks for this serialized byte data. In the `System.IO` package, this is represented directly by the abstract base type `Stream`; its concrete subtypes represent the actual I/O access: `FileStream` represents I/O to a file, and `MemoryStream` represents I/O to a literal array of bytes (whose size is dynamically managed) in memory. Other packages within the .NET Framework Class Library offer up their own `Stream`-derived types. For example, in the `System.Net` namespace, socket connections and HTTP responses are offered up as `Stream`-derived types, giving .NET programmers the ability to treat any sort of input or output data as "just a stream."

Simply reading and writing to these streams is not enough of an abstraction, however. In particular, programmers often need to perform one of two sorts of I/O: binary I/O, which is writing actual binary representations of objects or data to disk, or text I/O, which is writing the textual representations of that data. These operations are fundamentally different-writing the text representation of the integer value 5 produces the literal text "5" within the stream, whereas writing the binary value generates the hex value 0x00000005 (represented as four bytes, 05 00 00 00, in the file). In the .NET libraries, because these types of I/O operations are different from one another, these operations are abstracted out into two sets of abstract base types. `BinaryReader` and `BinaryWriter` are for reading and writing binary values to streams, and `TextReader` and `TextWriter` are for reading and writing character-based data.

Figure 31-1. The System.IO namespace





Figure 31-2. Exceptions, delegates, event arguments, and components in the System.IO namespace



Note that the `System.IO` namespace also offers some interesting stream-on-stream options. Like the Java `java.io` package, `Stream` types can layer on top of other `Stream` types to offer additional functionality-this is the Decorator pattern (from the *Design Patterns* book). The sole example of this in the `System.IO` namespace is the `BufferedStream`, which maintains a buffer on top of the `Stream` object passed to it in its constructor.

All of these types work together to provide some powerful abstraction and composite behaviors. For example, when working with random-access data, create a `BinaryReader` around a `BufferedStream`, which in turn wraps around a `FileStream`. If you decide later to store the random-access data in memory for optimization's sake, change the `BufferedStream/FileStream` pair to a `MemoryStream`. When reading a configuration file, choose to declare the `ReadConfiguration` method you have written to take an arbitrary `TextReader`, rather than ask for a string containing the filename. This allows for flexibility later-perhaps the configuration wants to be stored into a CLOB field in an RDBMS. Simply change the actual `Stream` instance passed into the `TextReader`, and start

reading the configuration out of the RDBMS, off of a socket request, or out of the HTTP response sent to a web server. Similarly, when planning to extend the `System.IO` namespace's capabilities, try to follow this same model. If you want to add compression to save on a configuration file's size, just build a `CompressingStream` that wraps another `Stream` in the manner `BufferedStream` does. If you want to have some interprocess communication with an existing "legacy" Win32 app (perhaps communicate over an NT Named Pipe), simply build a `NamedPipeStream`. In general, there is no particular reason to take specific derivatives of `Stream` as parameters-by limiting expected parameters to be of type `Stream`, .NET programmers can gain an incredible amount of flexibility regarding where and how data lives.

All this notwithstanding, certain programmatic tasks simply require access to the filesystem. The underlying filesystem is a hierarchical one, and there will be times there is simply no escaping that fact. For these tasks, the .NET `System.IO` namespace provides the filesystem types: `Directory`, `DirectoryInfo`, `File`, `FileInfo` and its associated enumerations, `FileSystemInfo`, `FileSystemWatcher`, and `Path` (finally, a class that understands directory paths in all their various incarnations!). These classes should be used for mostly "meta-file" operations (enumerating files, discovering attributes about a file, creating or destroying a directory, and so on) rather than for operations on the contents of the file (for which the `Stream`-based types described earlier are more appropriate).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

BinaryReader

CF 1.0, disposable

System.IO (mscorlib.dll)

class

This class allows you to read data from a `Stream`. When using a `BinaryReader`, the data represented by a `Stream` is regarded as a binary format, and bits are merely read from the stream and copied into the appropriate types. The methods prefixed with `Read()` allow you to grab data of a specific type from the front of the `Stream` and advance the current position. The next table shows how many bytes each of these methods reads in from a stream.

Method	Bytes read	Method	Bytes read
<code>Read</code>	variable	<code>ReadInt32</code>	4
<code>ReadBoolean</code>	1	<code>ReadInt64</code>	8
<code>ReadByte</code>	1	<code>ReadSByte</code>	1
<code>ReadBytes</code>	variable	<code>ReadSingle</code>	4
<code>ReadChar</code>	2	<code>ReadString</code>	variable
<code>ReadChars</code>	variable	<code>ReadUInt16</code>	2
<code>ReadDecimal</code>	16	<code>ReadUInt32</code>	4
<code>ReadDouble</code>	8	<code>ReadUInt64</code>	8

`ReadString()` uses the current encoding of the `BinaryReader`, which can be set when you call the constructor. Strings are prefixed with their length. `PeekChar()` allows you to look at the first character of a stream (a `System.Char`, which is two bytes) without advancing the position of the `Stream`. Because a binary reader may hold on to resources that should be freed when not needed, the `BinaryReader` must be closed using `Close()` or by wrapping it in a `using` block (which calls the protected `Dispose()` method to do the cleanup at the end of the `using` block).

```
public class BinaryReader : IDisposable {
// Public Constructors
    public BinaryReader(Stream input);
    public BinaryReader(Stream input,
        System.Text.Encoding encoding);
// Public Instance Properties
    public virtual Stream BaseStream{get; }
// Public Instance Methods
    public virtual void Close( );
    public virtual int PeekChar( );
    public virtual int Read( );
    public virtual int Read(byte[] buffer, int index, int count);
}
```

```
public virtual int Read(char[ ] buffer, int index, int count);
public virtual bool ReadBoolean( );
public virtual byte ReadByte( );
public virtual byte[ ] ReadBytes(int count);
public virtual char ReadChar( );
public virtual char[ ] ReadChars(int count);
public virtual decimal ReadDecimal( );
public virtual double ReadDouble( );
public virtual short ReadInt16( );
public virtual int ReadInt32( );
public virtual long ReadInt64( );
public virtual sbyte ReadSByte( );
public virtual float ReadSingle( );
public virtual string ReadString( );
public virtual ushort ReadUInt16( );
public virtual uint ReadUInt32( );
public virtual ulong ReadUInt64( );
// Protected Instance Methods
protected virtual void Dispose(bool disposing);
protected virtual void FillBuffer(int numBytes);
protected int Read7BitEncodedInt( );
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

BinaryWriter CF 1.0, serializable, disposable

System.IO (mscorlib.dll)

class

This class complements `BinaryReader`. To write binary data, simply call `Write()` and pass data of the desired type; the method is overloaded for all "primitive types" (but not the generic `System.Object` type-that is the subject of the `System.Runtime.Serialization` namespaces). Be aware, however, that because `BinaryWriter` is not the actual destination of the data (the wrapped `Stream` object is) the data may be cached in a buffer somewhere between the `BinaryWriter` and the sink. To ensure data is completely written, call the `Flush()` method. When working with a `BinaryWriter` in a sensitive code area, consider placing it in a `using` block to ensure cleanup (in this case, release of the `Stream` it wraps after flushing the data).

```
public class BinaryWriter : IDisposable {
    // Public Constructors
    public BinaryWriter(Stream output);
    public BinaryWriter(Stream output,
        System.Text.Encoding encoding);
    // Protected Constructors
    protected BinaryWriter( );
    // Public Static Fields
    public static readonly BinaryWriter Null;
    // =System.IO.BinaryWriter
    // Protected Instance Fields
    protected Stream OutputStream;
    // Public Instance Properties
    public virtual Stream BaseStream {get; }
    // Public Instance Methods
    public virtual void Close( );
    public virtual void Flush( );
    public virtual long Seek(int offset, SeekOrigin origin);
    public virtual void Write(bool value);
    public virtual void Write(byte value);
    public virtual void Write(byte[] buffer);
    public virtual void Write(byte[] buffer, int index, int count);
    public virtual void Write(char ch);
    public virtual void Write(char[] chars);
    public virtual void Write(char[] chars, int index, int count);
    public virtual void Write(decimal value);
    public virtual void Write(double value);
    public virtual void Write(short value);
    public virtual void Write(int value);
    public virtual void Write(long value);
    public virtual void Write(sbyte value);
    public virtual void Write(float value);
}
```

```
    public virtual void Write(string value);  
    public virtual void Write(ushort value);  
    public virtual void Write(uint value);  
    public virtual void Write(ulong value);  
    // Protected Instance Methods  
    protected virtual void Dispose(bool disposing);  
    protected void Write7BitEncodedInt (int value);  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

BufferedStream

marshal by reference,
disposable

System.IO (mscorlib.dll)

sealed class

This type buffers read and write operations to a stream. Because the I/O devices are usually the slowest part of the machine, it usually makes sense to write larger amounts of data at a time, so buffering can improve I/O performance dramatically.

Note that many of the **Stream**-based types automatically buffer data or represent resources that also buffer data, not only in the **System.IO** namespace, but also in other namespaces. For example, the filesystem usually has several buffers in place at various levels. This type, however, offers some optimization capabilities, since data won't be sent to the underlying **Stream** until this object's buffer is full. This can help with accidental flushing in the middle of sensitive operations, such as a tightly executing loop.

```

public sealed class BufferedStream : Stream {
// Public Constructors
    public BufferedStream(Stream stream);
    public BufferedStream(Stream stream, int bufferSize);
// Public Instance Properties
    public override bool CanRead{get; }
// overrides Stream
    public override bool CanSeek{get; }
// overrides Stream
    public override bool CanWrite{get; }
// overrides Stream
    public override long Length{get; }
// overrides Stream
    public override long Position{set; get; }
// overrides Stream
// Public Instance Methods
    public override void Close( );
// overrides Stream
    public override void Flush( );
// overrides Stream
    public override int Read(in byte[] array, int offset, int count)
// overrides Stream
    public override int ReadByte( );
// overrides Stream
    public override long Seek(long offset, SeekOrigin origin);
// overrides Stream
    public override void SetLength(long value);
// overrides Stream
    public override void Write(byte[] array, int offset, int count)

```

```
// overrides Stream
public override void WriteByte(byte value);
// overrides Stream
}
```

Hierarchy



[[Team LiB](#)]

Directory

CF 1.0, ECMA 1.0

System.IO (mscorlib.dll)

sealed class

This class provides many static methods for working with filesystem directories. Most of the methods behave as expected. `GetLogicalDrives()` returns an array of all of the drives of a system in the format "k:", in which "k" is the drive letter. `GetParent()` returns the parent path of the specified path, and `GetDirectoryRoot()` returns the root directory of the specified path.

```
public sealed class Directory {
// Public Static Methods
    public static DirectoryInfo CreateDirectory(string path);
    public static void Delete(string path);
    public static void Delete(string path, bool recursive);
    public static bool Exists(string path);
    public static DateTime GetCreationTime(string path);
    public static DateTime GetCreationTimeUtc(string path);
    public static string GetCurrentDirectory( );
    public static string[] GetDirectories(string path);
    public static string[] GetDirectories(string path, string searchPattern);
    public static string GetDirectoryRoot(string path);
    public static string[] GetFiles(string path);
    public static string[] GetFiles(string path, string searchPattern);
    public static string[] GetFileSystemEntries(string path);
    public static string[] GetFileSystemEntries(string path, string searchPattern);
    public static DateTime GetLastAccessTime(string path);
    public static DateTime GetLastAccessTimeUtc(string path);
    public static DateTime GetLastWriteTime(string path);
    public static DateTime GetLastWriteTimeUtc(string path);
    public static string[] GetLogicalDrives( );
    public static DirectoryInfo GetParent(string path);
    public static void Move(string sourceDirName, string destDirName);
    public static void SetCreationTime(string path, DateTime creationTime);
    public static void SetCreationTimeUtc(string path, DateTime creationTimeUtc);
    public static void SetCurrentDirectory(string path);
    public static void SetLastAccessTime(string path, DateTime lastAccessTime);
    public static void SetLastAccessTimeUtc(string path, DateTime lastAccessTimeUtc);
    public static void SetLastWriteTime(string path, DateTime lastWriteTime);
    public static void SetLastWriteTimeUtc(string path, DateTime lastWriteTimeUtc);
}
```


DirectoryInfo CF 1.0, serializable, marshal by reference

System.IO (mscorlib.dll)

sealed class

This class provides the same functionality as `Directory`, but in a strongly typed, object-oriented manner. An instance of this type represents a single directory. This class extends `FileSystemInfo` and implements all its methods. In addition, it adds `Parent` and `Root` properties to return the parent and root directories, respectively. Similarly, it also supplies `GetDirectories()` and `GetFiles()`, to retrieve its subdirectories and files, as well as `GetFileSystemInfos()`, which returns both the files and subdirectories contained by the current directory. `MoveTo()` allows you to move a directory from one place to another.

Given the similarity between this type and the `Directory` type, it may not be clear when one should be used in place of the other. The key difference is the `Directory` class is a collection of static utility functions, whereas a `DirectoryInfo` object is an actual object, maintaining state and identity in the classic style of all objects. (In fact, the `DirectoryInfo` methods often map over to use the corresponding `Directory` methods.)

```
public sealed class DirectoryInfo : FileSystemInfo {
    // Public Constructors
    public DirectoryInfo(string path);
    // Public Instance Properties
    public override bool Exists {get; }
    // overrides FileSystemInfo
    public override string Name {get; }
    // overrides FileSystemInfo
    public DirectoryInfo Parent {get; }
    public DirectoryInfo Root {get; }
    // Public Instance Methods
    public void Create( );
    public DirectoryInfo CreateSubdirectory(string path);
    public override void Delete( );
    // overrides FileSystemInfo
    public void Delete(bool recursive);
    public DirectoryInfo[] GetDirectories( );
    public DirectoryInfo[] GetDirectories(string searchPattern);
    public FileInfo[] GetFiles( );
    public FileInfo[] GetFiles(string searchPattern);
    public FileSystemInfo[] GetFileSystemInfos( );
    public FileSystemInfo[] GetFileSystemInfos(string searchPattern);
    public void MoveTo(string destDirName);
    public override string ToString( );
    // overrides object
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
FileSystemInfo(System.Runtime.Serialization.ISerializable) → DirectoryInfo

Returned By

Directory.{CreateDirectory(), GetParent()}, FileInfo.Directory

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

DirectoryNotFoundException


CF 1.0, ECMA 1.0, serializable

System.IO (mscorlib.dll) *class*

This exception is thrown if you attempt to access a directory that does not exist.

```
public class DirectoryNotFoundException : IOException {  
    // Public Constructors  
    public DirectoryNotFoundException( );  
    public DirectoryNotFoundException(string message);  
    public DirectoryNotFoundException(string message, Exception innerException);  
    // Protected Constructors  
    protected DirectoryNotFoundException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



EndOfStreamException

CF 1.0, ECMA 1.0,
serializable


System.IO (mscorlib.dll)

class

This exception is thrown if you attempt to read data from a stream at its end position.

```
public class EndOfStreamException : IOException {  
    // Public Constructors  
    public EndOfStreamException( );  
    public EndOfStreamException(string message);  
    public EndOfStreamException(string message,  
        Exception innerException);  
    // Protected Constructors  
    protected EndOfStreamException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



ErrorEventArgs

System.IO (system.dll) *class*

This type defines the event arguments that are passed when a `FileSystemWatcher.Error` event occurs. It contains the exception that was raised by the error, which you can access by calling `GetException()`.

```
public class ErrorEventArgs : EventArgs {  
    // Public Constructors  
    public ErrorEventArgs(Exception exception);  
    // Public Instance Methods  
    public virtual Exception GetException( );  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `ErrorEventArgs`

Passed To

`ErrorEventHandler.BeginInvoke(), Invoke()`, `FileSystemWatcher.OnError()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ErrorEventHandler

serializable

System.IO (system.dll)

delegate

This is a delegate for the `FileSystemWatcher.Error` event.

```
public delegate void ErrorEventHandler(object sender,
    EventArgs e);
```

Associated Events

```
FileSystemWatcher.Error( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

File

CF 1.0, ECMA 1.0

System.IO (mscorlib.dll)

sealed class

Like the `Directory` type, this type offers a collection of static utility methods for working with files on the file system. In most cases, these methods are simply shortcuts for working with the `System.IO` types directly; for example, the `AppendText()` method returns a `StreamWriter` that can append text to the file specified in the `path` argument. This could be accomplished just as easily by creating a `StreamWriter` around a `FileStream` opened to the file with the `FileMode.Append` flag passed into the constructor.

That stated, there are methods on this type that aren't available through the `Stream`-based API. For example, file's creation time, last-accessed time, last-modified times, and attributes are all available via this type, and such corresponding call exists on the `Stream` type.

```
public sealed class File {
// Public Static Methods
    public static StreamWriter AppendText(string path);
    public static void Copy(string sourceFileName, string destFileName);
    public static void Copy(string sourceFileName, string destFileName, bool overwrite);
    public static FileStream Create(string path);
    public static FileStream Create(string path, int bufferSize);
    public static StreamWriter CreateText(string path);
    public static void Delete(string path);
    public static bool Exists(string path);
    public static FileAttributes GetAttributes(string path);
    public static DateTime GetCreationTime(string path);
    public static DateTime GetCreationTimeUtc(string path);
    public static DateTime GetLastAccessTime(string path);
    public static DateTime GetLastAccessTimeUtc(string path);
    public static DateTime GetLastWriteTime(string path);
    public static DateTime GetLastWriteTimeUtc(string path);
    public static void Move(string sourceFileName, string destFileName);
    public static FileStream Open(string path, FileMode mode);
    public static FileStream Open(string path, FileMode mode, FileAccess access);
    public static FileStream Open(string path, FileMode mode, FileAccess access, FileShare share);
    public static FileStream OpenRead(string path);
    public static StreamReader OpenText(string path);
    public static FileStream OpenWrite(string path);
    public static void SetAttributes(string path, FileAttributes fileAttributes);
    public static void SetCreationTime(string path, DateTime creationTime);
    public static void SetCreationTimeUtc(string path, DateTime creationTimeUtc);
    public static void SetLastAccessTime(string path, DateTime lastAccessTime);
    public static void SetLastAccessTimeUtc(string path, DateTime lastAccessTimeUtc);
    public static void SetLastWriteTime(string path, DateTime lastWriteTime);
}
```

```
public static void SetLastWriteTimeUtc(string path, DateTime lastWriteTimeUtc);  
}
```

[Team LiB]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

FileAccess CF 1.0, ECMA 1.0, serializable, flag

System.IO (mscorlib.dll) *enum*

This enumeration represents the various access levels a program can exercise on a file. Programs can either read, write, or do both.

```
public enum FileAccess {  
    Read = 0x00000001 ,  
    Write = 0x00000002 ,  
    ReadWrite = 0x00000003  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → FileAccess

Passed To

```
File.Open( ), FileInfo.Open( ), FileStream.FileStream( ),  
System.IO.IsolatedStorage.IsolatedStorageFileStream.IsolatedStorageFileStream( ),  
System.Net.Sockets.NetworkStream.NetworkStream( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

FileAttributes

CF 1.0, serializable, flag

System.IO (mscorlib.dll)

enum

This enumeration represents the various attributes a file can have in the .NET environment; many, if not most, of these attributes parallel the standard Win32 filesystem attributes of the same name.

```
public enum FileAttributes {
    ReadOnly = 0x00000001 ,
    Hidden = 0x00000002 ,
    System = 0x00000004 ,
    Directory = 0x00000010 ,
    Archive = 0x00000020 ,
    Device = 0x00000040 ,
    Normal = 0x00000080 ,
    Temporary = 0x00000100 ,
    SparseFile = 0x00000200 ,
    ReparsePoint = 0x00000400 ,
    Compressed = 0x00000800 ,
    Offline = 0x00001000 ,
    NotContentIndexed = 0x00002000 ,
    Encrypted = 0x00004000
}
```

Hierarchy

```
System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → FileAttributes
```

Returned By

```
File.GetAttributes( ), FileSystemInfo.Attributes
```

Passed To

```
File.SetAttributes( ), FileSystemInfo.Attributes
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

File Info


CF 1.0, serializable, marshal by reference

System.IO (mscorlib.dll) *sealed class*

Like the parallels between `Directory` and `DirectoryInfo`, this class offers an object-centric spin on the static functions offered in the `File` type.

```
public sealed class FileInfo : FileSystemInfo {
// Public Constructors
    public FileInfo(string fileName);
// Public Instance Properties
    public DirectoryInfo Directory {get; }
    public string DirectoryName {get; }
    public override bool Exists {get; }
// overrides FileSystemInfo
    public long Length {get; }
    public override string Name {get; }
// overrides FileSystemInfo
// Public Instance Methods
    public StreamWriter AppendText( );
    public FileInfo CopyTo(string destFileName);
    public FileInfo CopyTo(string destFileName, bool overwrite);
    public FileStream Create( );
    public StreamWriter CreateText( );
    public override void Delete( );
// overrides FileSystemInfo
    public void MoveTo(string destFileName);
    public FileStream Open(FileMode mode);
    public FileStream Open(FileMode mode, FileAccess access);
    public FileStream Open(FileMode mode, FileAccess access, FileShare share);
    public FileStream OpenRead( );
    public StreamReader OpenText( );
    public FileStream OpenWrite( );
    public override string ToString( );
// overrides object
}
```

Hierarchy



Returned By

DirectoryInfo.GetFiles()

[[Team LiB](#)]

[◀ PREVIOUS](#) [NEXT ▶](#)

FileLoadException

ECMA 1.0, serializable

System.IO (mscorlib.dll)

class

This exception is thrown when a file cannot be loaded.

```
public class FileLoadException : IOException {  
    // Public Constructors  
    public FileLoadException( );  
    public FileLoadException(string message);  
    public FileLoadException(string message, Exception inner);  
    public FileLoadException(string message, string fileName);  
    public FileLoadException(string message, string fileName, Exception inner);  
    // Protected Constructors  
    protected FileLoadException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public string FileName{get; }  
    public string FusionLog{get; }  
    public override string Message{get; }  
    // overrides Exception  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
    public override string ToString( );  
    // overrides Exception  
}
```

Hierarchy

System.Object → System.Exception(System.Runtime.Serialization.ISerializable) →
System.SystemException → IOException → FileLoadException

FileMode CF 1.0, ECMA 1.0, serializable

System.IO (mscorlib.dll) *enum*

This enumeration allows you to specify how you want to open a file. If you use **Create**, and the file already exists, an **IOException** is thrown. If you use **CreateNew**, any file that currently exists is overwritten. **OpenOrCreate** indicates that if a file already exists, it must be opened; otherwise, a new file must be created. Similarly, **Truncate** indicates that the file must be opened and all its data erased (writing then begins at the first byte in the file). **Append** indicates that the file must be opened and the "file position" set to the end of the file (the opposite of Truncate).

```
public enum FileMode {  
    CreateNew = 1 ,  
    Create = 2 ,  
    Open = 3 ,  
    OpenOrCreate = 4 ,  
    Truncate = 5 ,  
    Append = 6  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → FileMode

Passed To

File.Open(), FileInfo.Open(), FileStream.FileStream(),
System.IO.IsolatedStorage.IsolatedStorageFileStream.IsolatedStorageFileStream()

FileNotFoundException


CF 1.0, ECMA 1.0,
serializable

System.IO (mscorlib.dll) *class*

This exception is thrown when you attempt to access a file that does not exist.

```
public class FileNotFoundException : IOException {  
    // Public Constructors  
    public FileNotFoundException( );  
    public FileNotFoundException(string message);  
    public FileNotFoundException(string message, Exception innerException);  
    public FileNotFoundException(string message, string fileName);  
    public FileNotFoundException(string message, string fileName, Exception innerExcepti  
    // Protected Constructors  
    protected FileNotFoundException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public string FileName{get; }  
    public string FusionLog{get; }  
    public override string Message{get; }  
    // overrides Exception  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
    public override string ToString( );  
    // overrides Exception  
}
```

Hierarchy



FileShare CF 1.0, ECMA 1.0, serializable, flag

System.IO (mscorlib.dll) *enum*

This enumeration defines how two different processes can access the same file. If one process is using `ReadWrite` or `Write`, no other process can use the file. Similarly, if another process is using `Read`, then other processes can read from the file, but not write to it.

```
public enum FileShare {  
    None = 0x00000000 ,  
    Read = 0x00000001 ,  
    Write = 0x00000002 ,  
    ReadWrite = 0x00000003 ,  
    Inheritable = 0x00000010  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → FileShare

Passed To

File.Open(), FileInfo.Open(), FileStream.FileStream(),
System.IO.IsolatedStorage.IsolatedStorageFileStream.IsolatedStorageFileStream()

FileStream

CF 1.0, ECMA 1.0, marshal by reference, disposable

System.IO (mscorlib.dll) *class*

This class is the basic implementation of `Stream` for files. It implements `Stream`, and adds a few methods specifically for working with files. `Handle` allows you to grab the underlying system handle to the file resource. `IsAsync` tells you if the file was opened asynchronously or synchronously. If you want to prevent other processes from accessing parts (or all) of the file, call `Lock()`. Subsequently, to free the lock, call `Unlock()`.

Note that using the `Lock()` or `Unlock()` methods is not the same as using the `lock` keyword in C#. The `lock` action locks only for this process, whereas the file-range locks used in the `Lock/Unlock` methods are implemented at the filesystem level and are therefore a cross-process mechanism.

```
public class FileStream : Stream {
// Public Constructors
    public FileStream(IntPtr handle, FileAccess access);
    public FileStream(IntPtr handle, FileAccess access, bool ownsHandle);
    public FileStream(IntPtr handle, FileAccess access, bool ownsHandle, int bufferSize)
    public FileStream(IntPtr handle, FileAccess access, bool ownsHandle, int bufferSize,
        bool isAsync);
    public FileStream(string path, FileMode mode);
    public FileStream(string path, FileMode mode, FileAccess access);
    public FileStream(string path, FileMode mode, FileAccess access, FileShare share);
    public FileStream(string
path, FileMode mode, FileAccess access, FileShare share,
        int bufferSize);
    public FileStream(string path, FileMode mode, FileAccess access, FileShare share,
        int bufferSize, bool useAsync);
// Public Instance Properties
    public override bool CanRead {get; }
// overrides Stream
    public override bool CanSeek {get; }
// overrides Stream
    public override bool CanWrite {get; }
// overrides Stream
    public virtual IntPtr Handle {get; }
    public virtual bool IsAsync {get; }
    public override long Length {get; }
// overrides Stream
    public string Name {get; }
    public override long Position {set; get; }
// overrides Stream
// Public Instance Methods
```

```

        public override IAsyncResult BeginRead(byte[ ] array, int offset, int numBytes,
            AsyncCallback userCallback, object stateObject)
// overrides Stream
        public override IAsyncResult BeginWrite(byte[ ] array, int offset, int numBytes,
            AsyncCallback userCallback, object stateObject)
// overrides Stream
        public override void Close( );
// overrides Stream
        public override int EndRead(IAsyncResult asyncResult);
// overrides Stream
        public override void EndWrite(IAsyncResult asyncResult);
// overrides Stream
        public override void Flush( );
// overrides Stream
        public virtual void Lock(long position, long length);
        public override int Read(in byte[ ] array, int offset, int count)
// overrides Stream
        public override int ReadByte( );
// overrides Stream
        public override long Seek(long offset, SeekOrigin origin);
// overrides Stream
        public override void SetLength(long value);
// overrides Stream
        public virtual void Unlock(long position, long length);
        public override void Write(byte[ ] array, int offset, int count)
// overrides Stream
        public override void WriteByte(byte value);
// overrides Stream
// Protected Instance Methods
        protected virtual void Dispose(bool disposing);
        protected override void Finalize( );
// overrides object
    }

```

Hierarchy

System.Object → System.MarshalByRefObject → Stream(System.IDisposable) → FileStream

Subclasses

System.IO.IsolatedStorage.IsolatedStorageFileStream

Returned By

File.{Create(), Open(), OpenRead(), OpenWrite()}, FileInfo.{Create(), Open(), OpenRead(), OpenWrite()}, System.Reflection.Assembly.{GetFile(), GetFiles()}

Passed To

System.Reflection.StrongNameKeyPair.StrongNameKeyPair()

[Team LiB]

◀ PREVIOUS

NEXT ▶

FileSystemEventArgs

System.IO (system.dll) *class*

This class offers the arguments for a `FileSystemEventHandler` .

```
public class FileSystemEventArgs : EventArgs {  
    // Public Constructors  
    public FileSystemEventArgs(WatcherChangeTypes changeType, string directory, string n  
    // Public Instance Properties  
    public WatcherChangeTypes ChangeType{get; }  
    public string FullPath{get; }  
    public string Name{get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `FileSystemEventArgs`

Subclasses

`RenamedEventArgs`

Passed To

`FileSystemEventHandler`.{`BeginInvoke()`, `Invoke()`}, `FileSystemWatcher`.{`OnChanged()`, `OnCreated()`, `OnDeleted()`}

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

FileSystemEventHandler

serializable

System.IO (system.dll)

delegate

This delegate is for the `FileSystemWatcher.Changed`, `FileSystemWatcher.Created`, and `FileSystemWatcher.Deleted` events.

```
public delegate void FileSystemEventHandler(object sender, FileSystemEventArgs e);
```

Associated Events

```
FileSystemWatcher.{Changed( ), Created( ), Deleted( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

FileSystemInfo

CF 1.0, serializable, marshal
by reference

System.IO (mscorlib.dll) *abstract class*

This serves as the base class for both `FileInfo` and `DirectoryInfo`, and allows access to the basic files relating to both.

```
public abstract class FileSystemInfo : MarshalByRefObject, System.Runtime.Serialization
// Protected Constructors
    protected FileSystemInfo( );
    protected FileSystemInfo(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Protected Instance Fields
    protected string FullPath;
    protected string OriginalPath;
// Public Instance Properties
    public FileAttributes Attributes{set; get; }
    public DateTime CreationTime{set; get; }
    public DateTime CreationTimeUtc{set; get; }
    public abstract bool Exists{get; }
    public string Extension{get; }
    public virtual string FullName{get; }
    public DateTime LastAccessTime{set; get; }
    public DateTime LastAccessTimeUtc{set; get; }
    public DateTime LastWriteTime{set; get; }
    public DateTime LastWriteTimeUtc{set; get; }
    public abstract string Name{get; }
// Public Instance Methods
    public abstract void Delete( );
    public virtual void GetObjectData(// implements ISerializable
        System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
    public void Refresh( );
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
 FileSystemInfo(System.Runtime.Serialization.ISerializable)

Subclasses

`DirectoryInfo`, `FileInfo`

Returned By

```
DirectoryInfo.GetFileSystemInfos( )
```

[Team LiB]

FileSystemWatcher

marshal by reference,
disposable

System.IO (system.dll) *class*


This class allows you to listen to the filesystem and respond to different operations on it. To register a watch on a directory, first set **Path** to the path you wish to watch. Next, set the **Filter** property. If you want to watch all files, set it to an empty ("") string. To watch an individual file, set **Filter** to the filename. You can also use wildcards to filter the filename. You must then also set **NotifyFilter** to register the types of events you wish to be notified of. To monitor the subdirectories as well, set **IncludeSubdirectories** . **EnableRaisingEvents** allows you to enable or disable the **FileSystemWatcher** . The watcher then exposes the following events: **Changed** , **Created** , **Deleted** , **DirectoryRenamed** . An **Error** is raised if too many events occur on a filesystem for the watcher to correctly monitor.

```
public class FileSystemWatcher : System.ComponentModel.Component, System.ComponentModel.IComponent
// Public Constructors
    public FileSystemWatcher( );
    public FileSystemWatcher(string path);
    public FileSystemWatcher(string path, string filter);
// Public Instance Properties
    public bool EnableRaisingEvents{set; get; }
    public string Filter{set; get; }
    public bool IncludeSubdirectories{set; get; }
    public int InternalBufferSize{set; get; }
    public NotifyFilters NotifyFilter{set; get; }
    public string Path{set; get; }
    public override ISite Site{set; get; }
// overrides System.ComponentModel.Component
    public ISynchronizeInvoke SynchronizingObject{set; get; }
// Public Instance Methods
    public void BeginInit( );
// implements System.ComponentModel.ISupportInitialize
    public void EndInit( );
// implements System.ComponentModel.ISupportInitialize
    public WaitForChangedResult WaitForChanged(WatcherChangeTypes changeType);
    public WaitForChangedResult WaitForChanged(WatcherChangeTypes changeType, int timeout);
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides System.ComponentModel.Component
    protected void OnChanged(FileSystemEventArgs e);
    protected void OnCreated(FileSystemEventArgs e);
    protected void OnDeleted(FileSystemEventArgs e);
    protected void OnError(ErrorEventArgs e);
    protected void OnRenamed(RenamedEventArgs e);
// Events
    public event FileSystemEventHandler Changed;
```



```
public event FileSystemEventHandler Created;  
public event FileSystemEventHandler Deleted;  
public event EventHandler Error;  
public event RenamedEventHandler Renamed;  
}
```

Hierarchy




InternalBufferOverflowException serializable

System.IO (system.dll) *class*

This exception is passed by a `FileSystemWatcher.Error` event. This occurs when the internal buffer of a `FileSystemWatcher` overflows because too many events have occurred.

```
public class InternalBufferOverflowException : SystemException {  
    // Public Constructors  
    public InternalBufferOverflowException( );  
    public InternalBufferOverflowException(string message);  
    public InternalBufferOverflowException(string message, Exception inner);  
    // Protected Constructors  
    protected InternalBufferOverflowException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy




IODescriptionAttribute

System.IO (system.dll) *class*

This custom attribute describes an I/O property or event.

```
public class IODescriptionAttribute : System.ComponentModel.DescriptionAttribute {  
    // Public Constructors  
    public IODescriptionAttribute(string description);  
    // Public Instance Properties  
    public override string Description {get; }  
    // overrides System.ComponentModel.DescriptionAttribute  
}
```

Hierarchy



Valid On

All

IOException CF 1.0, ECMA 1.0, serializable

System.IO (mscorlib.dll) class

This is the base class of all the I/O related exceptions.

```
public class IOException : SystemException {  
    // Public Constructors  
    public IOException( );  
    public IOException(string message);  
    public IOException(string message, Exception innerException);  
    public IOException(string message, int hresult);  
    // Protected Constructors  
    protected IOException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Subclasses

DirectoryNotFoundException, EndOfStreamException, FileLoadException,
FileNotFoundException, PathTooLongException

MemoryStream

CF 1.0, ECMA 1.0,
serializable, marshal by
reference, disposable

System.IO (mscorlib.dll) *class*

This class is a stream that keeps its data in memory as opposed to on the disk (as a `FileStream` does). In addition to the `Stream` methods, `ToArray()` writes the entire stream to a byte array, and `WriteTo()` dumps the contents of this stream to a different one.

```
public class MemoryStream : Stream {
// Public Constructors
    public MemoryStream( );
    public MemoryStream(byte[] buffer);
    public MemoryStream(byte[] buffer, bool writable);
    public MemoryStream(byte[] buffer, int index, int count);
    public MemoryStream(byte[] buffer, int index, int count, bool writable);
    public MemoryStream(byte[] buffer, int index, int count, bool writable,
        bool publiclyVisible);
    public MemoryStream(int capacity);
// Public Instance Properties
    public override bool CanRead {get; }
// overrides Stream
    public override bool CanSeek {get; }
// overrides Stream
    public override bool CanWrite {get; }
// overrides Stream
    public virtual int Capacity {set; get; }
    public override long Length {get; }
// overrides Stream
    public override long Position {set; get; }
// overrides Stream
// Public Instance Methods
    public override void Close( );
// overrides Stream
    public override void Flush( );
// overrides Stream
    public virtual byte[] GetBuffer( );
    public override int Read(in byte[] buffer, int offset, int count)
// overrides Stream
    public override int ReadByte( );
// overrides Stream
    public override long Seek(long offset, SeekOrigin loc);
// overrides Stream
```

```
    public override void SetLength(long value);  
// overrides Stream  
    public virtual byte[ ] ToArray( );  
    public override void Write(byte[ ] buffer, int offset, int count)  
// overrides Stream  
    public override void WriteByte(byte value);  
// overrides Stream  
    public virtual void WriteTo(Stream stream);  
}
```

Hierarchy



[\[Team LIB \]](#)

NotifyFiltersserializable, flag

System.IO (system.dll)enum

This type represents the different types of filesystem events you can use a `FileSystemWatcher` to look for. `NotifyFilters` allows you to indicate what kind of changes a `FileSystemWatcher` should respond to.

```
public enum NotifyFilters {
    FileName = 0x00000001 ,
    DirectoryName = 0x00000002 ,
    Attributes = 0x00000004 ,
    Size = 0x00000008 ,
    LastWrite = 0x00000010 ,
    LastAccess = 0x00000020 ,
    CreationTime = 0x00000040 ,
    Security = 0x00000100
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `NotifyFilters`

Returned By

`FileSystemWatcher.NotifyFilter`

Passed To

`FileSystemWatcher.NotifyFilter`

Path

CF 1.0, ECMA 1.0

System.IO (mscorlib.dll)

sealed class

This class provides many static methods for processing strings representing file paths in a platform-independent manner. The static properties allow you to inspect the file conventions of the system on which the software is running. The static methods supply an implementation of the frequently performed path manipulations. `ChangeExtension()` allows you to change the extension of a file, and `GetExtension()` allows you to retrieve it. `Combine()` combines two file paths (the second argument cannot contain a UNC or a drive letter). `GetTempPath()` returns the current system temporary storage folder, and the infinitely cooler `GetTempFileName()` creates a unique temporary filename, then creates a zero-byte file there. `IsPathRooted()` checks to see if a path contains a root, which can also be retrieved by calling `GetPathRoot()`.

```
public sealed class Path {
// Public Static Fields
    public static readonly char AltDirectorySeparatorChar;
// =0x0000002F
    public static readonly char DirectorySeparatorChar;
// =0x0000005C
    public static readonly char[] InvalidPathChars;
// =System.Char[]
    public static readonly char PathSeparator;
// =0x0000003B
    public static readonly char VolumeSeparatorChar;
// =0x0000003A
// Public Static Methods
    public static string ChangeExtension(string path, string extension);
    public static string Combine(string path1, string path2);
    public static string GetDirectoryName(string path);
    public static string GetExtension(string path);
    public static string GetFileName(string path);
    public static string GetFileNameWithoutExtension(string path);
    public static string GetFullPath(string path);
    public static string GetPathRoot(string path);
    public static string GetTempFileName( );
    public static string GetTempPath( );
    public static bool HasExtension(string path);
    public static bool IsPathRooted(string path);
}
```


PathTooLongException

CF 1.0, ECMA 1.0,
serializable


System.IO (mscorlib.dll)

class

This exception is thrown when you attempt to access or create a file with a name that is too long for the filesystem.

```
public class PathTooLongException : IOException {
// Public Constructors
    public PathTooLongException( );
    public PathTooLongException(string message);
    public PathTooLongException(string message, Exception innerException);
// Protected Constructors
    protected PathTooLongException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



RenamedEventArgs

System.IO (system.dll) *class*

This type represents the arguments passed by a `FileSystemWatcher.Renamed` event.

```
public class RenamedEventArgs : FileSystemEventArgs {  
    // Public Constructors  
    public RenamedEventArgs(WatcherChangeTypes changeType, string directory, string name  
        string oldName);  
    // Public Instance Properties  
    public string OldFullPath{get; }  
    public string OldName{get; }  
}
```

Hierarchy

System.Object → System.EventArgs → FileSystemEventArgs → RenamedEventArgs

Passed To

```
FileSystemWatcher.OnRenamed( ), RenamedEventHandler.{BeginInvoke( ), Invoke( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

RenamedEventHandler

serializable

System.IO (system.dll)

delegate

This delegate is for the `FileSystemWatcher.Renamed` event.

```
public delegate void RenamedEventHandler(object sender, RenamedEventArgs e);
```

Associated Events

```
FileSystemWatcher.Renamed( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SeekOrigin CF 1.0, ECMA 1.0, serializable

System.IO (mscorlib.dll) *enum*

This enumeration is used by the `Stream.Seek()` method. You can specify that you want to seek either from the beginning with `Begin`, from the current position with `Current`, or end with `End`.

```
public enum SeekOrigin {  
    Begin = 0,  
    Current = 1,  
    End = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `SeekOrigin`

Passed To

`BinaryWriter.Seek(), Stream.Seek()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Stream

CF 1.0, ECMA 1.0, serializable,
marshal by reference, disposable

System.IO (mscorlib.dll) *abstract class*

This class is the basic building block of I/O in the .NET Framework. Many types of application use a **Stream** in one way or another. When calling `System.Console.WriteLine()`, you use a `TextWriter`, which contains a `StreamWriter`. When you design an ASP.NET application, the `System.Web.UI.Page` uses a `System.Net.Sockets.NetworkStream`. In fact, whenever you access a remote database server you are using a `NetworkStream`.

To determine whether a given **Stream** can read, write, or seek, check `CanRead`, `CanWrite`, or `CanSeek`, respectively. If your stream can seek, you may seek forward or backward using `Seek()`. `Length` reveals the length of the stream, which can also be set by calling `SetLength()`, and `Position` allows you to check your current position in the stream.

To perform asynchronous I/O, call `BeginRead()` or `BeginWrite()`. Notification of an asynchronous operation comes in two ways: either via an `System.AsyncCallback` delegate callback passed in as part of the `BeginRead()/BeginWrite()` call, or else by calling the `EndRead()` or `EndWrite()` method explicitly, which blocks the calling thread until the async operation completes.

Streams usually hold on to a precious resource (a network connection or a file handle), which should be freed as soon as it is not needed any more. Because destruction is completely nondeterministic with garbage collection, be sure to call `Close()` at the end of the **Stream**'s useful lifetime. (Alternatively, wrap the use of the **Stream** in a `using` block to have the compiler generate the call to `Dispose()`-which in turn calls `Close()`-when the block finishes.)

```
public abstract class Stream : MarshalByRefObject, IDisposable {
    // Protected Constructors
    protected Stream( );
    // Public Static Fields
    public static readonly Stream Null;
    // =System.IO.Stream+NullStream
    // Public Instance Properties
    public abstract bool CanRead{get; }
    public abstract bool CanSeek{get; }
    public abstract bool CanWrite{get; }
    public abstract long Length{get; }
    public abstract long Position{set; get; }
    // Public Instance Methods
    public virtual IAsyncResult BeginRead(byte[ ] buffer, int offset, int count,
        AsyncCallback callback, object state);
    public virtual IAsyncResult BeginWrite(byte[ ] buffer, int offset, int count,
        AsyncCallback callback, object state);
    public virtual void Close( );
    public virtual int EndRead(IAsyncResult asyncResult);
```

```
public virtual void EndWrite(IAsyncResult asyncResult);
public abstract void Flush( );
public abstract int Read(in byte[ ] buffer, int offset, int count);
public virtual int ReadByte( );
public abstract long Seek(long offset, SeekOrigin origin);
public abstract void SetLength(long value);
public abstract void Write(byte[ ] buffer, int offset, int count);
public virtual void WriteByte(byte value);
// Protected Instance Methods
protected virtual WaitHandle CreateWaitHandle( );
}
```

Hierarchy

System.Object → System.MarshalByRefObject → Stream(System.IDisposable)

Subclasses

BufferedStream, FileStream, MemoryStream, System.Net.Sockets.NetworkStream

Returned By

Multiple types

Passed To

Multiple types

[\[Team LIB \]](#)

CF 1.0, ECMA 1.0, serializable, StreamReader marshal by reference, disposable

System.IO (mscorlib.dll) *class*

This class is an extension of a `TextReader` and provides implementations for all its methods. `CurrentEncoding` returns the current encoding the `StreamReader` is using. If you would like to discard the buffered data (so it isn't written to a disk or other resource), call `DiscardBufferedData()`.

This class is a quick way to open a file for reading. Simply call the constructor with a string containing the filename, and you can immediately begin reading from the file with methods such as `Read()`, `ReadLine()`, or `ReadToEnd()`.

```
public class StreamReader : TextReader {
// Public Constructors
    public StreamReader(Stream stream);
    public StreamReader(Stream stream, bool detectEncodingFromByteOrderMarks);
    public StreamReader(Stream stream, System.Text.Encoding encoding);
    public StreamReader(Stream stream, System.Text.Encoding encoding,
        bool detectEncodingFromByteOrderMarks);
    public StreamReader(Stream stream, System.Text.Encoding encoding,
        bool detectEncodingFromByteOrderMarks, int bufferSize);
    public StreamReader(string path);
    public StreamReader(string path, bool detectEncodingFromByteOrderMarks);
    public StreamReader(string path, System.Text.Encoding encoding);
    public StreamReader(string path, System.Text.Encoding encoding,
        bool detectEncodingFromByteOrderMarks);
    public StreamReader(string path, System.Text.Encoding encoding,
        bool detectEncodingFromByteOrderMarks, int bufferSize);
// Public Static Fields
    public static readonly StreamReader Null;
// =System.IO.StreamReader+NullStreamReader
// Public Instance Properties
    public virtual Stream BaseStream {get; }
    public virtual Encoding CurrentEncoding {get; }
// Public Instance Methods
    public override void Close();
// overrides TextReader
    public void DiscardBufferedData();
    public override int Peek();
// overrides TextReader
    public override int Read();
}
```

```
// overrides TextReader
public override int Read(in char[ ] buffer, int index, int count)
// overrides TextReader
public override string ReadLine( );
// overrides TextReader
public override string ReadToEnd( );
// overrides TextReader
// Protected Instance Methods
protected override void Dispose(bool disposing);
// overrides TextReader
}
```

Hierarchy



Returned By

```
System.Diagnostics.Process.{StandardError, StandardOutput}, File.OpenText( ),
FileInfo.OpenText( )
```

[\[Team LiB \]](#)

CF 1.0, ECMA 1.0, serializable, StreamWriter marshal by reference, disposable

System.IO (mscorlib.dll) *class*

This class implements `TextWriter` and provides all its methods. If you set the `AutoFlush` property, every `Write()` or `WriteLine()` flushes the buffer.

This class is a quick way to open a file for writing. Call the constructor with a string containing the filename you can immediately begin writing to the file with `Write()` or `WriteLine()`.

```
public class StreamWriter : TextWriter {
// Public Constructors
    public StreamWriter(Stream stream);
    public StreamWriter(Stream stream, System.Text.Encoding encoding);
    public StreamWriter(Stream stream, System.Text.Encoding encoding, int bufferSize);
    public StreamWriter(string path);
    public StreamWriter(string path, bool append);
    public StreamWriter(string path, bool append, System.Text.Encoding encoding);
    public StreamWriter(string path, bool append, System.Text.Encoding encoding, int buf.
// Public Static Fields
    public static readonly StreamWriter Null;
// =System.IO.StreamWriter
// Public Instance Properties
    public virtual bool AutoFlush {set; get; }
    public virtual Stream BaseStream {get; }
    public override Encoding Encoding {get; }
// overrides TextWriter
// Public Instance Methods
    public override void Close( );
// overrides TextWriter
    public override void Flush( );
// overrides TextWriter
    public override void Write(char value);
// overrides TextWriter
    public override void Write(char[ ] buffer);
// overrides TextWriter
    public override void Write(char[ ] buffer, int index, int count)
// overrides TextWriter
    public override void Write(string value);
// overrides TextWriter
// Protected Instance Methods
    protected override void Dispose(bool disposing);
```

```
// overrides TextWriter
protected override void Finalize( );
// overrides object
}
```

Hierarchy

System.Object → System.MarshalByRefObject → TextWriter(System.IDisposable) → Stream

Returned By

```
System.Diagnostics.Process.StandardInput , File.{AppendText( ) , CreateText( )} ,
FileInfo.{AppendText( ) , CreateText( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

StringReader

CF 1.0, ECMA 1.0, serializable,
marshal by reference,
disposable

System.IO (mscorlib.dll)

class

This class implements `TextReader` and provides all its methods. It is useful when you would like to deal with a `System.String` in the same way you would work with a `TextReader`.

```
public class StringReader : TextReader {  
    // Public Constructors  
    public StringReader(string s);  
    // Public Instance Methods  
    public override void Close( );  
    // overrides TextReader  
    public override int Peek( );  
    // overrides TextReader  
    public override int Read( );  
    // overrides TextReader  
    public override int Read(in char[ ] buffer, int index, int count)  
    // overrides TextReader  
    public override string ReadLine( );  
    // overrides TextReader  
    public override string ReadToEnd( );  
    // overrides TextReader  
    // Protected Instance Methods  
    protected override void Dispose(bool disposing);  
    // overrides TextReader  
}
```

Hierarchy



StringWriter

CF 1.0, ECMA 1.0, serializable,
marshal by reference, disposable

System.IO (mscorlib.dll) *class*

This class provides an alternative to using a `System.Text.StringBuilder` to create a string. This allows you to create a string in the exact same manner you would create a text file, which can be very useful. It implements all of the `TextWriter` methods.

```
public class StringWriter : TextWriter {  
    // Public Constructors  
    public StringWriter( );  
    public StringWriter(IFormatProvider formatProvider);  
    public StringWriter(System.Text.StringBuilder sb);  
    public StringWriter(System.Text.StringBuilder sb, IFormatProvider formatProvider);  
    // Public Instance Properties  
    public override Encoding Encoding{get; }  
    // overrides TextWriter  
    // Public Instance Methods  
    public override void Close( );  
    // overrides TextWriter  
    public virtual StringBuilder GetStringBuilder( );  
    public override string ToString( );  
    // overrides object  
    public override void Write(char value);  
    // overrides TextWriter  
    public override void Write(char[ ] buffer, int index, int count)  
    // overrides TextWriter  
    public override void Write(string value);  
    // overrides TextWriter  
    // Protected Instance Methods  
    protected override void Dispose(bool disposing)  
    // overrides TextWriter  
}
```

Hierarchy



TextReader

CF 1.0, ECMA 1.0, serializable,
marshal by reference, disposable

System.IO (mscorlib.dll) *abstract class*

This class is optimized to read a stream of sequential characters. The `Read()` methods read data from the front of a stream, and `Peek()` looks at the first character without advancing the position of an associated stream. If you need a thread-safe `TextReader`, use `Synchronized()` to create a thread-safe copy of a `TextReader`.

```
public abstract class TextReader : MarshalByRefObject, IDisposable {  
    // Protected Constructors  
    protected TextReader( );  
    // Public Static Fields  
    public static readonly TextReader Null;  
    // =System.IO.TextReader+NullTextReader  
    // Public Static Methods  
    public static TextReader Synchronized(TextReader reader);  
    // Public Instance Methods  
    public virtual void Close( );  
    public virtual int Peek( );  
    public virtual int Read( );  
    public virtual int Read(in char[ ] buffer, int index, int count);  
    public virtual int ReadBlock(in char[ ] buffer, int index, int count);  
    public virtual string ReadLine( );  
    public virtual string ReadToEnd( );  
    // Protected Instance Methods  
    protected virtual void Dispose(bool disposing);  
}
```

Hierarchy

System.Object → System.MarshalByRefObject → TextReader(System.IDisposable)

Subclasses

StreamReader, StringReader

Returned By

System.Console.In, System.Xml.XmlTextReader.GetRemainder()

Passed To

```
System.Console.SetIn( ), System.Xml.XmlDocument.Load( ),  
System.Xml.XmlTextReader.XmlTextReader( ),  
System.Xml.XPath.XPathDocument.XPathDocument( )
```

[\[Team LiB \]](#)

TextWriter

CF 1.0, ECMA 1.0, serializable,
marshal by reference, disposable

System.IO (mscorlib.dll)

abstract class

This class writes strings of characters to a stream. **Encoding** sets the encoding of the produced text; change the object that provides formatting by setting **FormatProvider**. To change the newline character produced in your text, set the **NewLine** property. To write to a stream, call either **Write()** or **WriteLine()**. To clear the current buffer of characters, use **Flush()**. As always, **Close()** allows you to free the resources in use by the **TextWriter**.

```
public abstract class TextWriter : MarshalByRefObject, IDisposable {
// Protected Constructors
    protected TextWriter( );
    protected TextWriter(IFormatProvider formatProvider);
// Public Static Fields
    public static readonly TextWriter Null;
// =System.IO.TextWriter+NullTextWriter
// Protected Instance Fields
    protected char[ ] CoreNewLine;
// Public Instance Properties
    public abstract Encoding Encoding{get; }
    public virtual IFormatProvider FormatProvider{get; }
    public virtual string NewLine{set; get; }
// Public Static Methods
    public static TextWriter Synchronized(TextWriter writer);
// Public Instance Methods
    public virtual void Close( );
    public virtual void Flush( );
    public virtual void Write(bool value);
    public virtual void Write(char value);
    public virtual void Write(char[ ] buffer);
    public virtual void Write(char[ ] buffer, int index, int count);
    public virtual void Write(decimal value);
    public virtual void Write(double value);
    public virtual void Write(int value);
    public virtual void Write(long value);
    public virtual void Write(object value);
    public virtual void Write(float value);
    public virtual void Write(string value);
    public virtual void Write(string format, object arg0);
    public virtual void Write(string format, params object[ ] arg);
    public virtual void Write(string format, object arg0, object arg1);
    public virtual void Write(string format, object arg0, object arg1, object arg2);
}
```

```

public virtual void Write(uint value);
public virtual void Write(ulong value);
public virtual void WriteLine( );
public virtual void WriteLine(bool value);
public virtual void WriteLine(char value);
public virtual void WriteLine(char[ ] buffer);
public virtual void WriteLine(char[ ] buffer, int index, int count);
public virtual void WriteLine(decimal value);
public virtual void WriteLine(double value);
public virtual void WriteLine(int value);
public virtual void WriteLine(long value);
public virtual void WriteLine(object value);
public virtual void WriteLine(float value);
public virtual void WriteLine(string value);
public virtual void WriteLine(string format, object arg0);
public virtual void WriteLine(string format, params object[ ] arg);
public virtual void WriteLine(string format, object arg0, object arg1);
public virtual void WriteLine(string format, object arg0, object arg1, object arg2);
public virtual void WriteLine(uint value);
public virtual void WriteLine(ulong value);
// Protected Instance Methods
protected virtual void Dispose(bool disposing);
}

```

Hierarchy

System.Object → System.MarshalByRefObject → TextWriter(System.IDisposable)

Subclasses

StreamWriter, StringWriter

Returned By

System.Console.{Error, Out}, System.Diagnostics.TextWriterTraceListener.Writer

Passed To

System.Console.{SetError(), SetOut()},
 System.Diagnostics.TextWriterTraceListener.{TextWriterTraceListener(), Writer},
 System.Xml.XmlDocument.Save(), System.Xml.XmlTextWriter.XmlTextWriter(),
 System.Xml.Xsl.XslTransform.Transform()

[Team LiB]

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WaitForChangedEventArgs

System.IO (system.dll) *struct*

This structure contains the changes on a file. This is used to construct `FileSystemEventArgs` and `RenamedEventArgs`.

```
public struct WaitForChangedEventArgs {  
    // Public Instance Properties  
    public WatcherChangeTypes ChangeType {set; get; }  
    public string Name {set; get; }  
    public string OldName {set; get; }  
    public bool TimedOut {set; get; }  
}
```

Hierarchy

System.Object → System.ValueType → WaitForChangedEventArgs

Returned By

`FileSystemWatcher.WaitForChanged()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WatcherChangeTypes serializable, flag

System.IO (system.dll) *enum*

This enumeration represents the different types of changes that can occur on a file. It is used by `FileSystemEventArgs`.

```
public enum WatcherChangeTypes {  
    Created = 0x00000001 ,  
    Deleted = 0x00000002 ,  
    Changed = 0x00000004 ,  
    Renamed = 0x00000008 ,  
    All = 0x0000000F  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `WatcherChangeTypes`

Returned By

`FileSystemEventArgs.ChangeType`, `WaitForChangedResult.ChangeType`

Passed To

`FileSystemEventArgs.FileSystemEventArgs()`, `FileSystemWatcher.WaitForChanged()`, `RenamedEventArgs.RenamedEventArgs()`, `WaitForChangedResult.ChangeType`

Chapter 32. System.IO.IsolatedStorage

`System.IO.IsolatedStorage` allows you to access an isolated area of a filesystem for your application. This is useful when access to the `System.IO` classes is not possible. The security settings of the .NET Framework prohibit web applications and downloaded controls from accessing the local filesystem directly, but those settings allow them to use `System.IO.IsolatedStorage`. Applications' storage areas are isolated from one another, so anything in isolated storage is protected from untrusted applications. The size of isolated storage is limited, so an untrusted application cannot create a denial-of-service condition by filling your hard disk with data.

When you use isolated storage, the runtime sets aside disk space for a given level of isolation (specified using `IsolatedStorageScope`). If you use Windows 2000 or XP, `<SYSTEMDRIVE>\Documents and Settings\<user>\Application Data` contains the isolated storage area if roaming is turned on, and `<SYSTEMDRIVE>\Documents and Settings\<user>\Local Settings\Application Data` contains the storage area if roaming is not on. Applications can use this area as a data store for their particular persistence needs. [Figure 32-1](#) shows the inheritance diagram for this namespace. For more information, see [Section 10.4](#) in [Chapter 10](#).

I NormalizeForIsolatedStorage


System.IO.IsolatedStorage

(mscorlib.dll)

interface

This interface exposes `Normalize()`, which returns a normalized copy of the object on which it is called. You usually use this method if you are inheriting from `IsolatedStorage` and you want to see if a store already exists.

Figure 32-1. The System.IO.IsolatedStorage namespace



```
public interface INormalizeForIsolatedStorage {  
    // Public Instance Methods  
    public object Normalize( );  
}
```

IsolatedStorage

marshal by reference

System.IO.IsolatedStorage
(mscorlib.dll)

*abstract
class*

This is the abstract base class from which all isolated storage classes must inherit. **AssemblyIdentity** returns the assembly identity associated with the isolated store, and **DomainIdentity** returns the domain associated store. Use **CurrentSize** to detect how much space the store takes up on the disk, and use **MaximumSize** the maximum storage allowed. **Scope** returns an **IsolatedStorageScope** enumeration for the store. If you delete the isolated store and all its contents completely, call **Remove()**.

```
public abstract class IsolatedStorage : MarshalByRefObject {  
    // Protected Constructors  
    protected IsolatedStorage( );  
    // Public Instance Properties  
    public object AssemblyIdentity {get; }  
    public virtual ulong CurrentSize {get; }  
    public object DomainIdentity {get; }  
    public virtual ulong MaximumSize {get; }  
    public IsolatedStorageScope Scope {get; }  
    // Protected Instance Properties  
    protected virtual char SeparatorExternal {get; }  
    protected virtual char SeparatorInternal {get; }  
    // Public Instance Methods  
    public abstract void Remove( );  
    // Protected Instance Methods  
    protected abstract IsolatedStoragePermission GetPermission(System.Security.Permission  
    protected void InitStore(IsolatedStorageScope scope, Type domainEvidenceType,  
        Type assemblyEvidenceType);  
}
```

Hierarchy

System.Object → System.MarshalByRefObject → IsolatedStorage

Subclasses

IsolatedStorageFile

IsolatedStorageException

serializable

System.IO.IsolatedStorage
(mscorlib.dll)

class

This exception represents isolated storage errors.

```
public class IsolatedStorageException : Exception {  
    // Public Constructors  
    public IsolatedStorageException( );  
    public IsolatedStorageException(string message);  
    public IsolatedStorageException(string message, Exception inner);  
    // Protected Constructors  
    protected IsolatedStorageException(System.Runtime.Serialization.SerializationInfo in  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



IsolatedStorageFile

marshal by reference, disposable

System.IO.IsolatedStorage
(mscorlib.dll)

*sealed
class*

This class represents an isolated-storage filesystem area that can contain files and directories. The static current store. Call `GetStore()` only with the proper `IsolatedStorageScope` enumerations set. There are `GetUserStoreForAssembly()` returns the same store as `GetStore()` with `IsolatedStorageScope.UserStoreForAssembly` as its first argument, and `GetUserStoreForDomain()` returns as though `GetStore()` was called with `IsolatedStorageScope.Domain`. `GetStore()` returns all valid specified assembly and domain.

The rest of the methods for this class allow you to work with files and directories. `CreateDirectory()` & `DeleteDirectory()` create and delete directories, just as `DeleteFile()` allows you to delete files (use an `IsolatedStorageFile` allows you to close a store opened with `GetStore()`. `GetFileNames()` returns an array of filenames in

```
public sealed class IsolatedStorageFile : IsolatedStorage, IDisposable {
// Public Instance Properties
    public override ulong CurrentSize {get; }
// overrides IsolatedStorage
    public override ulong MaximumSize {get; }
// overrides IsolatedStorage
// Public Static Methods
    public static IEnumerable GetEnumerators(IsolatedStorageScope scope);
    public static IsolatedStorageFile GetStore(IsolatedStorageScope scope, System.Security
        Type domainEvidenceType, System.Security.Policy.Evidence assemblyEvidence,
        Type assemblyEvidenceType);
    public static IsolatedStorageFile GetStore(IsolatedStorageScope scope, object domain
        object assemblyIdentity);
    public static IsolatedStorageFile GetStore(IsolatedStorageScope scope, Type domainEvi
        Type assemblyEvidenceType);
    public static IsolatedStorageFile GetUserStoreForAssembly( );
    public static IsolatedStorageFile GetUserStoreForDomain( );
    public static void Remove(IsolatedStorageScope scope);
// Public Instance Methods
    public void Close( );
    public void CreateDirectory(string dir);
    public void DeleteDirectory(string dir);
    public void DeleteFile(string file);
    public void Dispose( );
// implements IDisposable
    public string[] GetDirectoryNames(string searchPattern);
    public string[] GetFileNames(string searchPattern);
}
```

```
        public override void Remove( );  
// overrides IsolatedStorage  
// Protected Instance Methods  
        protected override void Finalize( );  
// overrides object  
        protected override IsolatedStoragePermission  
            GetPermission(System.Security.PermissionSet ps)  
// overrides IsolatedStorage  
    }
```

Hierarchy

System.Object → System.MarshalByRefObject → IsolatedStorage → IsolatedStorageFile(S

Passed To

IsolatedStorageFileStream.IsolatedStorageFileStream()

[Team LiB]

IsolatedStorageFileStream

marshal by
reference,
disposable

System.IO.IsolatedStorage (mscorlib.dll)

class

This class is simply a `System.IO.FileStream` implementation for isolated storage. Use it to create and manage storage files.

```
public class IsolatedStorageFileStream : System.IO.FileStream {
// Public Constructors
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, System.IO.FileAccess access, System.IO.FileShare share);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, System.IO.FileAccess access, System.IO.FileShare share, int bufferSize);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, System.IO.FileAccess access, System.IO.FileShare share, int bufferSize, IsolatedStorageFile isf);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, System.IO.FileAccess access, System.IO.FileShare share, IsolatedStorageFile isf);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, System.IO.FileAccess access, IsolatedStorageFile isf);
    public IsolatedStorageFileStream(string path, System.IO.FileMode mode, IsolatedStorageFile isf);
// Public Instance Properties
    public override bool CanRead {get; }
// overrides System.IO.FileStream
    public override bool CanSeek {get; }
// overrides System.IO.FileStream
    public override bool CanWrite {get; }
// overrides System.IO.FileStream
    public override IntPtr Handle {get; }
// overrides System.IO.FileStream
    public override bool IsAsync {get; }
// overrides System.IO.FileStream
    public override long Length {get; }
// overrides System.IO.FileStream
    public override long Position {set; get; }
// overrides System.IO.FileStream
// Public Instance Methods
    public override IAsyncResult BeginRead(byte[] buffer, int offset, int numBytes, AsyncCallback userCallback, object stateObject)
```

```

// overrides System.IO.FileStream
public override IAsyncResult BeginWrite(byte[ ] buffer, int offset, int numBytes,
    AsyncCallback userCallback, object stateObject)
// overrides System.IO.FileStream
public override void Close( );
// overrides System.IO.FileStream
public override int EndRead(IAsyncResult asyncResult);
// overrides System.IO.FileStream
public override void EndWrite(IAsyncResult asyncResult);
// overrides System.IO.FileStream
public override void Flush( );
// overrides System.IO.FileStream
public override int Read(byte[ ] buffer, int offset, int count)
// overrides System.IO.FileStream
public override int ReadByte( );
// overrides System.IO.FileStream
public override long Seek(long offset, System.IO.SeekOrigin origin)
// overrides System.IO.FileStream
public override void SetLength(long value);
// overrides System.IO.FileStream
public override void Write(byte[ ] buffer, int offset, int count)
// overrides System.IO.FileStream
public override void WriteByte(byte value);
// overrides System.IO.FileStream
// Protected Instance Methods
protected override void Dispose(bool disposing);
// overrides System.IO.FileStream
}

```

Hierarchy

System.Object → System.MarshalByRefObject → System.IO.Stream(System.IDisposable) →
 System.IO.FileStream → IsolatedStorageFileStream

[Team LiB]

◀ PREVIOUS NEXT ▶


IsolatedStorageScope serializable, flag

System.IO.IsolatedStorage (mscorlib.dll) *enum*

This enumeration allows you to specify the levels of isolation an `IsolatedStorageFile` store should have. For example, if you call `IsolatedStorageFile.GetStore()` with `Assembly`, the isolated storage cannot be accessed by code from another assembly. `Roaming` allows the isolated store to be placed in a roaming profile; without it, the store does not roam with the user.

```
public enum IsolatedStorageScope {
    None = 0x00000000 ,
    User = 0x00000001 ,
    Domain = 0x00000002 ,
    Assembly = 0x00000004 ,
    Roaming = 0x00000008
}
```

Hierarchy



Returned By

```
IsolatedStorage.Scope
```

Passed To

```
IsolatedStorage.InitStore( ), IsolatedStorageFile.{GetEnumerator( ), GetStore( ), Remove( )}
```

Chapter 33. System.Net

`System.Net` supports a high-level API for working with common Internet protocols (HTTP being the principal example) without having to deal with low-level details (such as the actual protocol format). In addition, this namespace provides some high-level constructs for working with networks-TCP/IP in particular.

Most .NET programmers will work with either the `WebClient` type, which provides the most high-level view of doing HTTP-style request/response communications over a TCP/IP network (such as the Internet), or else the slightly lower-level `WebRequest` and `WebResponse` types. The choice between the two is really not all that difficult: for most high-level, protocol-agnostic work, `WebClient` will likely be the preferred choice. If protocol-specific actions need to be taken (such as specifying additional headers as part of an HTTP request, for example), then likely the .NET programmer will want to work with `WebRequest` and `WebResponse`. To be specific, the .NET programmer will work with the concrete derived types `HttpWebRequest` and `HttpWebResponse`.

As shipped, the .NET Framework Class Library provides implementations for three URI protocol schemes: HTTP, HTTPS, and files (`http:`, `https:`, and `file:`, respectively). For support of other URI types (such as FTP, NNTP, or POP3), a new derivative of `WebRequest` and `WebResponse` must be written, an Abstract Factory type implementing the `IWebRequestCreate` interface must be created, and an instance of it (along with the protocol scheme prefix) must be registered with `WebRequest.RegisterPrefix()`. [Figure 33-1](#) shows the collaborations between the concrete classes `HttpWebRequest`, `HttpWebResponse`, `FileWebRequest`, and `FileWebResponse`.

[Figure 33-2](#) shows the composition of the `ServicePoint` class, and [Figure 33-3](#) shows the remaining types in this namespace.

Figure 33-1. The abstract `WebRequest`, `WebResponse`, and related concrete types




Figure 33-2. Endpoints, service points, and associated types





Figure 33-3. Other classes in the System.Net namespace



[Team LiB]

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

AuthenticationManager

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This class is responsible for finding an authentication module to authorize access to network resources. You do not need to use this class unless you have defined your own authentication scheme. By default, Basic, Digest, NTLM, and Kerberos authentication schemes are supported. This, for the most part, covers the needs of all .NET programmers in the world. Kerberos is not supported on Windows 95/98 or on Windows Me..

```
public class AuthenticationManager {  
    // Public Static Properties  
    public static IEnumerable RegisteredModules {get; }  
    // Public Static Methods  
    public static Authorization Authenticate(string challenge, WebRequest request,  
        ICredentials credentials);  
    public static Authorization PreAuthenticate(WebRequest request, ICredentials credent  
    public static void Register(IAuthenticationModule authenticationModule);  
    public static void Unregister(IAuthenticationModule authenticationModule);  
    public static void Unregister(string authenticationScheme);  
}
```

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Authorization

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This class encapsulates an authentication message that **AuthenticationManager** sends to a remote server. The **Message** property contains the string that is sent to the server in response to its authentication challenge.

The **Authorization** class is used by implementations of **IAAuthenticationModule** and by **AuthenticationManager**. You should not need to use it directly unless you have implemented your own authentication scheme.

```
public class Authorization {
// Public Constructors
    public Authorization(string token);
    public Authorization(string token, bool finished);
    public Authorization(string token, bool finished, string connectionGroupId);
// Public Instance Properties
    public bool Complete {get; }
    public string ConnectionGroupId {get; }
    public string Message {get; }
    public string[] ProtectionRealm {set; get; }
}
```

Returned By

```
AuthenticationManager.{Authenticate( ), PreAuthenticate( )},
IAAuthenticationModule.{Authenticate( ), PreAuthenticate( )}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Cookie

serializable

System.Net (system.dll)

sealed class

This class represents an HTTP cookie, as standardized by RFC 2965 ([ftp://ftp.isi.edu/in-notes/rfc2965.txt](http://ftp.isi.edu/in-notes/rfc2965.txt)). A cookie represents a simple name-value pair that is sent back by the HTTP User-Agent on each subsequent request to the URL host that set the cookie. The rules governing the visibility, scope, and lifetime of cookies is well documented in the RFC; see that document for details. The `Cookie` has properties defined on it corresponding to the settable values in the RFC: principally, the `Value` property sets the value of the cookie, and the `Name` property sets the name by which the cookie's value can be retrieved.

As a User-Agent, adding a `Cookie` to an `HttpRequest` is as simple as adding the `Cookie` instance to the `HttpRequest.CookieContainer` property. When you receive a response from an HTTP server, it may contain one or more cookies. Use the `HttpResponse.Cookies` collection to obtain the cookies that the HTTP server sent you.

Note that, as a User-Agent (the client), it is the .NET programmer's responsibility for maintaining all the semantics of the RFC—that is, the cookie must only be sent back to the host that set it, the cookie can only be sent back if it obeys the "path" prefix set on the cookie, and so forth. Failure to do so could result in different hosts viewing cookies that they didn't set, which is a potential security hole (albeit only if a host puts sensitive material into the cookie in the first place). None of this is implemented in the `HttpRequest` or `Cookie` types.

```
public sealed class Cookie {
// Public Constructors
    public Cookie( );
    public Cookie(string name, string value);
    public Cookie(string name, string value, string path);
    public Cookie(string name, string value, string path, string domain);
// Public Instance Properties
    public string Comment {set; get; }
    public Uri CommentUri {set; get; }
    public bool Discard {set; get; }
    public string Domain {set; get; }
    public bool Expired {set; get; }
    public DateTime Expires {set; get; }
    public string Name {set; get; }
    public string Path {set; get; }
    public string Port {set; get; }
    public bool Secure {set; get; }
    public DateTime Timestamp {get; }
    public string Value {set; get; }
    public int Version {set; get; }
// Public Instance Methods
    public override bool Equals(object comparand);
```

```
// overrides object
public override int GetHashCode( );
// overrides object
public override string ToString( );
// overrides object
}
```

Returned By

```
CookieCollection.this
```

Passed To

```
CookieCollection.Add( ), CookieContainer.Add( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

CookieCollection

serializable

System.Net (system.dll)

class

This class is a specialized collection for holding cookies. It's used by `HttpWebResponse` to represent a set of cookies returned by a server. By default, the `IsReadOnly` property is set to `true`.

```
public class CookieCollection : ICollection, IEnumerable {
// Public Constructors
    public CookieCollection( );
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public bool IsReadOnly{get; }
    public bool IsSynchronized{get; }
// implements ICollection
    public object SyncRoot{get; }
// implements ICollection
    public Cookie this[int index]{get; }
    public Cookie this[string name]{get; }
// Public Instance Methods
    public void Add(Cookie cookie);
    public void Add(CookieCollection cookies);
    public void CopyTo(Array array, int index);
// implements ICollection
    public IEnumerator GetEnumerator( );
// implements IEnumerable
}
```

Returned By

```
CookieContainer.GetCookies( ), HttpWebResponse.Cookies
```

Passed To

```
CookieContainer.Add( ), HttpWebResponse.Cookies
```

CookieContainer

serializable

System.Net (system.dll)

class

This class is a container that holds cookies and organizes them by URI. You can add a **Cookie** or **CookieCollection** to a container using the simplest forms of the **Add()** method, or you can use the forms of the **Add()** method that take a **System.Uri** argument. You can retrieve all the cookies for a given URI using the **GetCookies()** method.

```
public class CookieContainer {
// Public Constructors
    public CookieContainer( );
    public CookieContainer(int capacity);
    public CookieContainer(int capacity, int perDomainCapacity, int maxCookieSize);
// Public Static Fields
    public const int DefaultCookieLengthLimit;
// =4096
    public const int DefaultCookieLimit;
// =300
    public const int DefaultPerDomainCookieLimit;
// =20
// Public Instance Properties
    public int Capacity{set; get; }
    public int Count{get; }
    public int MaxCookieSize{set; get; }
    public int PerDomainCapacity{set; get; }
// Public Instance Methods
    public void Add(Cookie cookie);
    public void Add(CookieCollection cookies);
    public void Add(Uri uri, Cookie cookie);
    public void Add(Uri uri, CookieCollection cookies);
    public string GetCookieHeader(Uri uri);
    public CookieCollection GetCookies(Uri uri);
    public void SetCookies(Uri uri, string cookieHeader);
}
```

Returned By

HttpRequest.CookieContainer

Passed To

HttpRequest.CookieContainer

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

CookieException


serializable

System.Net (system.dll) *class*

This exception signals an error encountered during a cookie-related operation.

```
public class CookieException : FormatException {  
    // Public Constructors  
    public CookieException( );  
    // Protected Constructors  
    protected CookieException(System.Runtime.Serialization.SerializationInfo serializationInfo,  
        System.Runtime.Serialization.StreamingContext streamingContext);  
}
```

Hierarchy



[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

CredentialCache

ECMA 1.0

System.Net (system.dll)

class

This class maintains credentials for multiple network resources. If you are developing a client application that needs to authenticate itself to more than one server, you can store an instance of this class in the `WebRequest.Credentials` property.

After you create an instance of this class, use the `Add()` method to associate `NetworkCredential` objects with a URI and authentication type (using a string such as "Basic" or "Digest"). Then you can assign the `CredentialCache` instance to the `WebRequest.Credentials` property to use the credentials for future web requests.

```
public class CredentialCache : ICredentials, IEnumerable {  
    // Public Constructors  
    public CredentialCache( );  
    // Public Static Properties  
    public static ICredentials DefaultCredentials {get; }  
    // Public Instance Methods  
    public void Add(Uri uriPrefix, string authType, NetworkCredential cred);  
    public NetworkCredential GetCredential(Uri uriPrefix, string authType)  
    // implements ICredentials  
    public IEnumerator GetEnumerator( );  
    // implements IEnumerable  
    public void Remove(Uri uriPrefix, string authType);  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Dns

CF 1.0, ECMA 1.0

System.Net (system.dll)

sealed class

This type offers up a collection of static methods for resolving DNS (Domain Name Service) operations. Because IP addresses (such as 192.168.0.1) can be difficult for humans to remember, DNS servers take human-friendly names (such as "www.oreilly.com") and in turn translate them into IP addresses and/or back again. This can be useful in a variety of scenarios, including the simple logging of clients who have visited a web site receive that this is not a secure way of tracking usage—even a simple attacker can spoof the return address of a response so don't rely on this mechanism for any kind of security validation or audit trail.)

The `GetHostByName()` method takes a hostname (such as "www.oreilly.com") and returns the corresponding `IPHostEntry` instance; this `IPHostEntry` instance is used later in several of the `System.Net` and `System.Net.Sockets` types. This method (along with the paired method `Resolve()`) can be invoked asynchronously using the `BeginGetHostByName()` or `BeginResolve()` methods. Like all asynchronous methods in the .NET Framework, they take two additional parameters: an `AsyncCallback` object, and a generic `object` that is passed to the `AsyncCallback` when the call completes.

At the surface, there would appear to be no difference between calling `Resolve()` or `GetHostByName()`; the `Resolve()` method calls into `GetHostByName()` after doing a small amount of preprocessing to check if the string passed is either a standard host name ("www.oreilly.com") or a dotted-quad IP address ("192.168.0.1"). `GetHostByName()` requires a hostname. (For those familiar with the Berkeley sockets API, the `GetHostByName` method is a wrapper around the native BSD `gethostbyname` function.)

```
public sealed class Dns {
    // Public Static Methods
    public static IAsyncResult BeginGetHostByName(string hostName, AsyncCallback requestCallback, object stateObject);
    public static IAsyncResult BeginResolve(string hostName, AsyncCallback requestCallback, object stateObject);
    public static IPHostEntry EndGetHostByName(IAsyncResult asyncResult);
    public static IPHostEntry EndResolve(IAsyncResult asyncResult);
    public static IPHostEntry GetHostByAddress(IPAddress address);
    public static IPHostEntry GetHostByAddress(string address);
    public static IPHostEntry GetHostByName(string hostName);
    public static string GetHostName( );
    public static IPHostEntry Resolve(string hostName);
}
```


DnsPermission

ECMA 1.0, serializable

System.Net (system.dll)


sealed class

This class controls access to DNS services. The constructor accepts one argument, either `System.Security.Permissions.PermissionState.None` (no access to DNS services) or `System.Security.Permissions.PermissionState.Unrestricted` (all access).

This permission is `Demand()`ed by all of the methods on the `Dns` class.

```
public sealed class DnsPermission : System.Security.CodeAccessPermission,
    System.Security.Permissions.IUnrestrictedPermission {
// Public Constructors
    public DnsPermission(System.Security.Permissions.PermissionState state);
// Public Instance Methods
    public override IPermission Copy();
// overrides CodeAccessPermission
    public override void FromXml(System.Security.SecurityElement securityElement)
// overrides CodeAccessPermission
    public override IPermission Intersect(System.Security.IPermission target)
// overrides CodeAccessPermission
    public override bool IsSubsetOf(System.Security.IPermission target);
// overrides CodeAccessPermission
    public bool IsUnrestricted();
// implements IUnrestrictedPermission
    public override SecurityElement ToXml();
// overrides CodeAccessPermission
    public override IPermission Union(System.Security.IPermission target)
// overrides CodeAccessPermission
}
```

Hierarchy



[Team LiB]

◀ PREVIOUS NEXT ▶

DnsPermissionAttribute

ECMA 1.0,
serializable


System.Net (system.dll)

sealed class

This attribute is used to declare in metadata that the attributed method or class requires `DnsPermission` form.

```
public sealed class DnsPermissionAttribute : System.Security.Permissions.CodeAccessSecu:
// Public Constructors
    public DnsPermissionAttribute(System.Security.Permissions.SecurityAction action);
// Public Instance Methods
    public override IPermission CreatePermission( );
// overrides System.Security.Permissions.SecurityAttribute
}
```

Hierarchy



Valid On

Assembly, Class, Struct, Constructor, Method

[Team LiB]

◀ PREVIOUS NEXT ▶

EndPoint CF 1.0, ECMA 1.0, serializable

System.Net (system.dll) *abstract class*

This abstract class represents a network address. It is extended by [IPEndPoint](#), which represents an IP network address. It could later be extended to represent other kinds of networking endpoints for other protocol stacks beyond TCP/IP.

```
public abstract class EndPoint {  
    // Protected Constructors  
    protected EndPoint( );  
    // Public Instance Properties  
    public virtual AddressFamily AddressFamily{get; }  
    // Public Instance Methods  
    public virtual EndPoint Create(SocketAddress socketAddress);  
    public virtual SocketAddress Serialize( );  
}
```

Subclasses

[IPEndPoint](#)

Returned By

[IPEndPoint.Create\(\), System.Net.Sockets.Socket.{LocalEndPoint, RemoteEndPoint},
System.Net.Sockets.TcpListener.LocalEndpoint](#)

Passed To

[System.Net.Sockets.Socket.{BeginConnect\(\), BeginReceiveFrom\(\), BeginSendTo\(\), Bind\(\), Connect\(\), EndReceiveFrom\(\), ReceiveFrom\(\), SendTo\(\)}](#)

EndpointPermission

serializable

System.Net (system.dll) *class*

This permission is `Demand()`ed by all of the methods on the `EndPoint` class.

```
public class EndpointPermission {  
    // Public Instance Properties  
    public string Hostname{get; }  
    public int Port{get; }  
    public TransportType Transport{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides object  
    public override int GetHashCode( );  
    // overrides object  
    public override string ToString( );  
    // overrides object  
}
```

FileWebRequest

serializable, marshal by reference

System.Net (system.dll) *class*

This subclass of `WebRequest` provides access to resources that use the `file` URL scheme (such as a file c local filesystem). Use `WebRequest.Create()` with a `file://`URL to create an instance of this class. The `WebRequest.Create()` method returns an instance of this class as a reference of type `WebRequest` .

You may feel a small sense of confusion regarding this type and the "file:" protocol scheme; if a program access to a file on the filesystem, why not simply open a `System.IO.FileStream` instead of using `WebRequest.Create("file://...")` ? In terms of straight functionality, the `System.IO.FileStream` call closely represents the fact that this resource is coming from disk; however, due to the ubiquity of HTTP UR filesystem paths within an arbitrary context. For example, a configuration file might be used to indicate v retrieve user preferences; by specifying the location as a URL rather than an absolute file location, storag user preferences is permitted on a centralized server without any additional code. (This allows a kind of " preferences" capability within the system.) Many of the .NET tools also use this approach to identify "files upon via command-line parameters.

```
public class FileWebRequest : WebRequest {
// Protected Constructors
    protected FileWebRequest(System.Runtime.Serialization.SerializationInfo serializatio
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
    public override string ConnectionGroupName{set; get; }
// overrides WebRequest
    public override long ContentLength{set; get; }
// overrides WebRequest
    public override string ContentType{set; get; }
// overrides WebRequest
    public override ICredentials Credentials{set; get; }
// overrides WebRequest
    public override WebHeaderCollection Headers{get; }
// overrides WebRequest
    public override string Method{set; get; }
// overrides WebRequest
    public override bool PreAuthenticate{set; get; }
// overrides WebRequest
    public override IWebProxy Proxy{set; get; }
// overrides WebRequest
    public override Uri RequestUri{get; }
// overrides WebRequest
    public override int Timeout{set; get; }
// overrides WebRequest
```

```
// Public Instance Methods
public override IAsyncResult BeginGetRequestStream(AsyncCallback callback, object st
// overrides WebRequest
public override IAsyncResult BeginGetResponse(AsyncCallback callback, object state)
// overrides WebRequest
public override Stream EndGetRequestStream(IAsyncResult asyncResult)
// overrides WebRequest
public override WebResponse EndGetResponse(IAsyncResult asyncResult)
// overrides WebRequest
public override Stream GetRequestStream( );
// overrides WebRequest
public override WebResponse GetResponse( );
// overrides WebRequest
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
WebRequest(System.Runtime.Serialization.ISerializable) → FileWebRequest

[Team LiB]

◀ PREVIOUS

NEXT ▶

FileWebResponse

serializable, marshal by
reference, disposable


System.Net (system.dll)

class

This subclass of `WebResponse` is returned by `WebRequest.GetResponse()` when you request access to a URI. Since this subclass does not add any new methods, there's no need to cast the return value to a `FileWebResponse`; the `GetResponseStream()` method returns a `System.IO.Stream` from which the file contents can be retrieved.

```
public class FileWebResponse : WebResponse {
// Protected Constructors
    protected FileWebResponse(System.Runtime.Serialization.SerializationInfo serializati
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
    public override long ContentLength{get; }
// overrides WebResponse
    public override string ContentType{get; }
// overrides WebResponse
    public override WebHeaderCollection Headers{get; }
// overrides WebResponse
    public override Uri ResponseUri{get; }
// overrides WebResponse
// Public Instance Methods
    public override void Close( );
// overrides WebResponse
    public override Stream GetResponseStream( );
// overrides WebResponse
// Protected Instance Methods
    protected virtual void Dispose(bool disposing);
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

GlobalProxySelection

CF 1.0, ECMA 1.0

System.Net (system.dll) *class*

This class holds the default **IWebProxy** object used by all HTTP requests. To change it, set the **Select** property to an instance of **WebProxy**.

```
public class GlobalProxySelection {  
    // Public Constructors  
    public GlobalProxySelection( );  
    // Public Static Properties  
    public static IWebProxy Select {set; get; }  
    // Public Static Methods  
    public static IWebProxy GetEmptyWebProxy( );  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

HttpContinueDelegate

CF 1.0, ECMA 1.0,
serializable

System.Net (system.dll)

delegate

The `HttpWebRequest.ContinueDelegate` property uses this class to handle `HttpStatusCode.Continue` responses. These responses are sent when the server receives the HTTP request, is able to process it, and wishes to notify the client that the request was successfully received. (Most HTTP servers will send this on the request processing would take longer than expected.)

```
public delegate void HttpContinueDelegate(int StatusCode, WebHeaderCollection httpHeade:
```

Returned By

`HttpWebRequest.ContinueDelegate`

Passed To

`HttpWebRequest.ContinueDelegate`

[Team LiB]

◀ PREVIOUS

NEXT ▶

HttpStatusCode

CF 1.0, ECMA 1.0,
serializable

System.Net (system.dll)

enum

This enumeration contains HTTP 1.1 status codes as defined in RFC 2616 (<http://ftp.isi.edu/in-notes/rfc2616.txt>).

```
public enum HttpStatusCode {  
    Continue = 100 ,  
    SwitchingProtocols = 101 ,  
    OK = 200 ,  
    Created = 201 ,  
    Accepted = 202 ,  
    NonAuthoritativeInformation = 203 ,  
    NoContent = 204 ,  
    ResetContent = 205 ,  
    PartialContent = 206 ,  
    MultipleChoices = 300 ,  
    Ambiguous = 300 ,  
    MovedPermanently = 301 ,  
    Moved = 301 ,  
    Found = 302 ,  
    Redirect = 302 ,  
    SeeOther = 303 ,  
    RedirectMethod = 303 ,  
    NotModified = 304 ,  
    UseProxy = 305 ,  
    Unused = 306 ,  
    TemporaryRedirect = 307 ,  
    RedirectKeepVerb = 307 ,  
    BadRequest = 400 ,  
    Unauthorized = 401 ,  
    PaymentRequired = 402 ,  
    Forbidden = 403 ,  
    NotFound = 404 ,  
    MethodNotAllowed = 405 ,  
    NotAcceptable = 406 ,  
    ProxyAuthenticationRequired = 407 ,  
    RequestTimeout = 408 ,  
    Conflict = 409 ,  
    Gone = 410 ,  
    LengthRequired = 411 ,  
    PreconditionFailed = 412 ,  
    RequestEntityTooLarge = 413 ,  
    RequestUriTooLong = 414 ,  
}
```

```
    UnsupportedMediaType = 415 ,  
    RequestedRangeNotSatisfiable = 416 ,  
    ExpectationFailed = 417 ,  
    InternalServerError = 500 ,  
    NotImplemented = 501 ,  
    BadGateway = 502 ,  
    ServiceUnavailable = 503 ,  
    GatewayTimeout = 504 ,  
    HttpVersionNotSupported = 505  
}
```

Hierarchy

```
System.Object → System.ValueType → System.Enum(System.IComparable,  
System.IFormattable, System.IConvertible) → HttpStatusCode
```

Returned By

```
HttpWebResponse.StatusCode
```

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

HttpVersion

CF 1.0, ECMA 1.0

System.Net (system.dll) *class*

This class contains `System.Version` values that represent versions for HTTP 1.0 and 1.1.

```
public class HttpVersion {  
    // Public Constructors  
    public HttpVersion( );  
    // Public Static Fields  
    public static readonly Version Version10 ;  
    // =1.0  
    public static readonly Version Version11 ;  
    // =1.1  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

HttpWebRequest

CF 1.0, ECMA 1.0,
serializable, marshal by
reference

System.Net (system.dll) *class*

This is a subclass of `WebRequest`. .NET uses this subclass to request documents from the `http` and `https` schemes (RFCs 2616 and 2818, respectively). An instance of this type is returned by `WebRequest.Create` when a URI starting with the `http://` or `https://` prefix is passed in. Since that method's return value is `WebRequest`, cast it to `HttpWebRequest` if you need access to any of the methods or properties that are to this class (and the HTTP or HTTPS protocol).

The properties on this type correspond directly to the headers documented in the RFC standard document see that document for details regarding their contents. Note that because these headers are sent as part HTTP request, any modification of the headers must be done before the request is sent to the remote host. (Calling either `GetResponse()` or `BeginGetResponse()`, the asynchronous version of `GetResponse()` sends the request.)

When a `WebRequest` encounters an error, a `WebException` is thrown.

```
public class HttpWebRequest : WebRequest {
    // Protected Constructors
    protected HttpWebRequest(System.Runtime.Serialization.SerializationInfo serializatio.
        System.Runtime.Serialization.StreamingContext streamingContext);
    // Public Static Properties
    public static int DefaultMaximumResponseHeadersLength{set; get; }
    // Public Instance Properties
    public string Accept{set; get; }
    public Uri Address{get; }
    public bool AllowAutoRedirect{set; get; }
    public bool AllowWriteStreamBuffering{set; get; }
    public X509CertificateCollection ClientCertificates{get; }
    public string Connection{set; get; }
    public override string ConnectionGroupName{set; get; }
    //overrides WebRequest
    public override long ContentLength{set; get; }
    // overrides WebRequest
    public override string ContentType{set; get; }
    // overrides WebRequest
    public HttpContinueDelegate ContinueDelegate{set; get; }
    public CookieContainer CookieContainer{set; get; }
    public override ICredentials Credentials{set; get; }
    // overrides WebRequest
    public string Expect{set; get; }
    public bool HaveResponse{get; }
```

```

    public override WebHeaderCollection Headers{set; get; }
// overrides WebRequest
    public DateTime IfModifiedSince{set; get; }
    public bool KeepAlive{set; get; }
    public int MaximumAutomaticRedirections{set; get; }
    public int MaximumResponseHeadersLength{set; get; }
    public string MediaType{set; get; }
    public override string Method{set; get; }
// overrides WebRequest
    public bool Pipelined{set; get; }
    public override bool PreAuthenticate{set; get; }
// overrides WebRequest
    public Version ProtocolVersion{set; get; }
    public override IWebProxy Proxy{set; get; }
// overrides WebRequest
    public int ReadWriteTimeout{set; get; }
    public string Referer{set; get; }
    public override Uri RequestUri{get; }
// overrides WebRequest
    public bool SendChunked{set; get; }
    public ServicePoint ServicePoint{get; }
    public override int Timeout{set; get; }
// overrides WebRequest
    public string TransferEncoding{set; get; }
    public bool UnsafeAuthenticatedConnectionSharing{set; get; }
    public string UserAgent{set; get; }
// Public Instance Methods
    public override void Abort( );
// overrides WebRequest
    public void AddRange(int range);
    public void AddRange(int from, int to);
    public void AddRange(string rangeSpecifier, int range);
    public void AddRange(string rangeSpecifier, int from, int to);
    public override IAsyncResult BeginGetRequestStream(AsyncCallback callback, object st
// overrides WebRequest
    public override IAsyncResult BeginGetResponse(AsyncCallback callback, object state)
// overrides WebRequest
    public override Stream EndGetRequestStream(IAsyncResult asyncResult)
// overrides WebRequest
    public override WebResponse EndGetResponse(IAsyncResult asyncResult)
// overrides WebRequest
    public override int GetHashCode( );
// overrides object
    public override Stream GetRequestStream( );
// overrides WebRequest
    public override WebResponse GetResponse( );
// overrides WebRequest
}

```

Hierarchy

System.Object → System.MarshalByRefObject →
WebRequest(System.Runtime.Serialization.ISerializable) → HttpWebRequest

[Team LiB]

◀ PREVIOUS NEXT ▶

HttpWebResponse


CF 1.0, ECMA 1.0,
serializable, marshal by
reference, disposable

System.Net (system.dll) *class*

This class represents a response from an HTTP server. This is usually returned from `WebRequest.GetResponse()` or `WebRequest.EndGetResponse()`. Use `GetResponseStream()` to obtain a `System.IO.Stream` object containing the response body. Use `GetResponseHeader()` to fetch a specific HTTP header.

```
public class HttpWebResponse : WebResponse {
// Protected Constructors
    protected HttpWebResponse(System.Runtime.Serialization.SerializationInfo serializationInfo,
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
    public string CharacterSet {get; }
    public string ContentEncoding {get; }
    public override long ContentLength {get; }
// overrides WebResponse
    public override string ContentType {get; }
// overrides WebResponse
    public CookieCollection Cookies {set; get; }
    public override WebHeaderCollection Headers {get; }
// overrides WebResponse
    public DateTime LastModified {get; }
    public string Method {get; }
    public Version ProtocolVersion {get; }
    public override Uri ResponseUri {get; }
// overrides WebResponse
    public string Server {get; }
    public HttpStatusCode StatusCode {get; }
    public string StatusDescription {get; }
// Public Instance Methods
    public override void Close();
// overrides WebResponse
    public override int GetHashCode();
// overrides object
    public string GetResponseHeader(string headerName);
    public override Stream GetResponseStream();
// overrides WebResponse
// Protected Instance Methods
    protected virtual void Dispose(bool disposing);
}
```


Hierarchy



[Team LiB]

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

IAuthenticationModule CF 1.0, ECMA 1.0

System.Net (system.dll) *interface*

This interface is implemented by all authentication modules. If you develop a custom authentication module, implement this interface and register an instance of your module with `AuthenticationManager.Register`

```
public interface IAuthenticationModule {
    // Public Instance Properties
    public string AuthenticationType {get; }
    public bool CanPreAuthenticate {get; }
    // Public Instance Methods
    public Authorization Authenticate(string challenge, WebRequest request, ICredentials credentials);
    public Authorization PreAuthenticate(WebRequest request, ICredentials credentials);
}
```

Passed To

```
AuthenticationManager.{Register( ), Unregister( )}
```

[Team LiB]

[< PREVIOUS](#) [NEXT >](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

ICertificatePolicy

CF 1.0

System.Net (system.dll)

interface

This interface validates the certificates that web servers present to your applications. If you create a web request that uses the `https` protocol, the .NET Framework uses the default certificate policy to validate the server's certificate.

You can implement this interface to create your own custom certificate policy. Unlike authentication modules, only one certificate policy may be active at a time. To set this, create an instance of your implementation and assign it to `ServicePointManager.CertificatePolicy`.

```
public interface ICertificatePolicy {  
    // Public Instance Methods  
    public bool CheckValidationResult(ServicePoint srvPoint,  
        System.Security.Cryptography.X509Certificates.X509Certificate certificate,  
        WebRequest request, int certificateProblem);  
}
```

Returned By

`ServicePointManager.CertificatePolicy`

Passed To

`ServicePointManager.CertificatePolicy`[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

ICredentials

CF 1.0, ECMA 1.0

System.Net (system.dll) *interface*

This interface is implemented by all web-client credentials. The class `NetworkCredential` works with authentication schemes such as Basic and Digest authentication, NTLM, and Kerberos. If you need to implement a client authentication scheme not supported by .NET (such as SSL client certificates), you need to implement `ICredentials` and add a new instance of your implementation to your application's credential cache. For more information on using a credential cache, see `CredentialCache`.

```
public interface ICredentials {  
    // Public Instance Methods  
    public NetworkCredential GetCredential(Uri uri, string authType);  
}
```

Implemented By

`CredentialCache`, `NetworkCredential`

Returned By

`CredentialCache.DefaultCredentials`, `IWebProxy.Credentials`, `WebClient.Credentials`, `WebProxy.Credentials`, `WebRequest.Credentials`

Passed To

`AuthenticationManager.Authenticate()`, `PreAuthenticate()`,
`IAuthenticationModule.Authenticate()`, `PreAuthenticate()`, `IWebProxy.Credentials`,
`WebClient.Credentials`, `WebProxy.Credentials`, `WebProxy()`, `WebRequest.Credentials`,
`System.Xml.XmlResolver.Credentials`

IPAddress CF 1.0, ECMA 1.0, serializable

System.Net (system.dll) *class*

This class represents an IP address. Use the `Parse()` method to turn a dotted-quad string (such as "192.168.0.1") into an `IPAddress`. Use the `ToString()` method to convert an `IPAddress` into a string.

```
public class IPAddress {
// Public Constructors
    public IPAddress(byte[] address);
    public IPAddress(byte[] address, long scopeid);
    public IPAddress(long newAddress);
// Public Static Fields
    public static readonly IPAddress Any;
// =0.0.0.0
    public static readonly IPAddress Broadcast;
// =255.255.255.255
    public static readonly IPAddress IPv6Any;
    public static readonly IPAddress IPv6Loopback;
    public static readonly IPAddress IPv6None;
    public static readonly IPAddress Loopback;
// =127.0.0.1
    public static readonly IPAddress None;
// =255.255.255.255
// Public Instance Properties
    public long Address{set; get; }
// obsolete
    public AddressFamily AddressFamily{get; }
    public long ScopeId{set; get; }
// Public Static Methods
    public static short HostToNetworkOrder(short host);
    public static int HostToNetworkOrder(int host);
    public static long HostToNetworkOrder(long host);
    public static bool IsLoopback(IPAddress address);
    public static short NetworkToHostOrder(short network);
    public static int NetworkToHostOrder(int network);
    public static long NetworkToHostOrder(long network);
    public static IPAddress Parse(string ipString);
// Public Instance Methods
    public override bool Equals(object comparand);
// overrides object
    public byte[] GetAddressBytes( );
    public override int GetHashCode( );
// overrides object
```

```
        public override string ToString( );  
        // overrides object  
    }
```

Returned By

```
IPEndPoint.Address, IPEndPoint.AddressList,  
System.Net.Sockets.Ipv6MulticastOption.Group,  
System.Net.Sockets.MulticastOption.{Group, LocalAddress}
```

Passed To

Multiple types

[\[Team LiB \]](#)

IPEndPoint CF 1.0, ECMA 1.0, serializable

System.Net (system.dll) *class*

This class represents a network endpoint as a combination of `IPAddress` and an integer port number. The static fields `MinPort` and `MaxPort` represent the minimum and maximum acceptable values for `Port`. These values are operating system-dependent.

This class does not represent an open socket connection, which contains two endpoints (local and remote). To create a socket, use `System.Net.Sockets.Socket`.

```
public class IPEndPoint : EndPoint {
// Public Constructors
    public IPEndPoint(long address, int port);
    public IPEndPoint(IPAddress address, int port);
// Public Static Fields
    public const int MaxPort;
// =65535
    public const int MinPort;
// =0
// Public Instance Properties
    public IPAddress Address{set; get; }
    public override AddressFamily AddressFamily{get; }
// overrides EndPoint
    public int Port{set; get; }
// Public Instance Methods
    public override EndPoint Create(SocketAddress socketAddress)
// overrides EndPoint
    public override bool Equals(object comparand);
// overrides object
    public override int GetHashCode( );
// overrides object
    public override SocketAddress Serialize( );
// overrides EndPoint
    public override string ToString( );
// overrides object
}
```

Hierarchy

System.Object → EndPoint → IPEndPoint

Passed To

```
System.Net.Sockets.TcpClient.{Connect( ), TcpClient( )},  
System.Net.Sockets.TcpListener.TcpListener( ), System.Net.Sockets.UdpClient.{Connect(  
) , Receive( ), Send( ), UdpClient( )}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IPEndPoint

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

The `Dns` class uses this class to represent hosts. A host is named by its `HostName` property, and its aliases are stored in the `Aliases` property. The `AddressList` property contains all the IP addresses for that host.

```
public class IPHostEntry {  
    // Public Constructors  
    public IPHostEntry( );  
    // Public Instance Properties  
    public IPAddress[] AddressList {set; get; }  
    public string[] Aliases {set; get; }  
    public string HostName {set; get; }  
}
```

Returned By

```
Dns.{EndGetHostByName( ), EndResolve( ), GetHostByAddress( ), GetHostByName( ), Resolve(  
    )}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IWebProxy

CF 1.0, ECMA 1.0

System.Net (system.dll) *interface*

IWebProxy defines the interface used by the **WebProxy** class. Parties interested in creating customized proxy handlers would implement this interface to do so, but the **WebProxy** implementation is sufficient for most HTTP access purposes.

To use an implementation of **IWebProxy**, see the **GlobalProxySelection** class or the **WebRequest.Proxy** property.

```
public interface IWebProxy {  
    // Public Instance Properties  
    public ICredentials Credentials{set; get; }  
    // Public Instance Methods  
    public Uri GetProxy(Uri destination);  
    public bool IsBypassed(Uri host);  
}
```

Implemented By

WebProxy

Returned By

GlobalProxySelection.{**GetEmptyWebProxy**(), **Select**}, **WebRequest.Proxy**

Passed To

GlobalProxySelection.**Select**, **ServicePointManager**.**FindServicePoint**(), **WebRequest.Proxy**

IWebRequestCreate

CF 1.0, ECMA 1.0

System.Net (system.dll) *interface*

This interface is for objects that create protocol-specific instances of `WebRequest`. For example, the private class `HttpRequestCreator` is the underlying class that implements this interface. `WebRequest` uses that class under the hood to create instances of `HttpWebRequest` when an application connects to an `http` or `https` URI.

If you create your own protocol-specific implementation of this interface, you can register it with the `WebRequest.RegisterPrefix()` static method.

```
public interface IWebRequestCreate {  
    // Public Instance Methods  
    public WebRequest Create(Uri uri);  
}
```

Passed To

```
WebRequest.RegisterPrefix( )
```

NetworkAccess ECMA 1.0, serializable

System.Net (system.dll) *enum*

This enumeration specifies network access permissions. **Accept** indicates that an application has permission to accept network connections. **Connect** indicates that the application can connect to network hosts.

Both **WebPermission** and **SocketPermission** use this enumeration.

```
public enum NetworkAccess {  
    Connect = 64 ,  
    Accept = 128  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → NetworkAccess

Passed To

```
SocketPermission.{AddPermission( ), SocketPermission( )}, WebPermission{AddPermission(  
) , WebPermission( )}
```

NetworkCredential

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This class is an implementation of `ICredentials` for authentication schemes that use passwords, such as basic and digest authentication, NTLM, and Kerberos. See `CredentialCache` for more details.

```
public class NetworkCredential : ICredentials {
// Public Constructors
    public NetworkCredential( );
    public NetworkCredential(string userName, string password);
    public NetworkCredential(string userName, string password, string domain);
// Public Instance Properties
    public string Domain{set; get; }
    public string Password{set; get; }
    public string UserName{set; get; }
// Public Instance Methods
    public NetworkCredential GetCredential(Uri uri, string authType)
// implements ICredentials
}
```

Returned By

```
CredentialCache.GetCredential( ), ICredentials.GetCredential( )
```

Passed To

```
CredentialCache.Add( )
```

ProtocolViolationException

CF 1.0, ECMA 1.0,
serializable

System.Net (system.dll) *class*

This exception is thrown when a network protocol error occurs.

```
public class ProtocolViolationException : InvalidOperationException {  
    // Public Constructors  
    public ProtocolViolationException( );  
    public ProtocolViolationException(string message);  
    // Protected Constructors  
    protected ProtocolViolationException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext streamingContext);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SecurityProtocolType .NET 1.1, serializable, flag

System.Net (system.dll) *enum*

This enumeration specifies the available security protocol types.

```
public enum SecurityProtocolType {  
    Ssl3 = 0x00000030 ,  
    Tls = 0x000000C0  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → SecurityProtocolType

Returned By

ServicePointManager.SecurityProtocol

Passed To

ServicePointManager.SecurityProtocol

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

ServicePoint

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This class is used by `ServicePointManager` to manage connections to remote hosts. The .NET Framework reuses service points for all requests to a given URI. The lifetime of a given `ServicePoint` is governed by its `MaxIdleTime` property.

The `ServicePoint` class is a high-level abstraction of the underlying implementation. Details of the implementation, such as the sockets used for HTTP transport, are not publicly exposed.

```
public class ServicePoint {
// Public Instance Properties
    public Uri Address {get; }
    public X509Certificate Certificate {get; }
    public X509Certificate ClientCertificate {get; }
    public int ConnectionLimit {set; get; }
    public string ConnectionName {get; }
    public int CurrentConnections {get; }
    public bool Expect100Continue {set; get; }
    public DateTime IdleSince {get; }
    public int MaxIdleTime {set; get; }
    public virtual Version ProtocolVersion {get; }
    public bool SupportsPipelining {get; }
    public bool UseNagleAlgorithm {set; get; }
// Public Instance Methods
    public override int GetHashCode( );
// overrides object
}
```

Returned By

```
HttpRequest.ServicePoint, ServicePointManager.FindServicePoint( )
```

Passed To

```
ICertificatePolicy.CheckValidationResult( )
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

ServicePointManager

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This class is responsible for managing `ServicePoint` instances. As your applications make HTTP connections to network resources, this class is working behind the scenes to maintain the connections. When your application makes many connections to the same server, this class eliminates the overhead of making a new connection each time you connect.

The `ServicePointManager` also sets the default certificate policy for new connections. In most cases, the default certificate policy should suit your needs. If you need to change it, see `ICertificatePolicy` for more details.

```
public class ServicePointManager {
// Public Static Fields
    public const int DefaultNonPersistentConnectionLimit;
// =4
    public const int DefaultPersistentConnectionLimit;
// =2
// Public Static Properties
    public static ICertificatePolicy CertificatePolicy{set; get; }
    public static bool CheckCertificateRevocationList{set; get; }
    public static int DefaultConnectionLimit{set; get; }
    public static bool Expect100Continue {set; get; }
    public static int MaxServicePointIdleTime{set; get; }
    public static int MaxServicePoints{set; get; }
    public static SecurityProtocolType SecurityProtocol{set; get; }
    public static bool UseNagleAlgorithm{set; get; }
// Public Static Methods
    public static ServicePoint FindServicePoint(string uriString, IWebProxy proxy);
    public static ServicePoint FindServicePoint(Uri address);
    public static ServicePoint FindServicePoint(Uri address, IWebProxy proxy);
}
```

SocketAddress

CF 1.0, ECMA 1.0

System.Net (system.dll)

class

This type defines an address of a particular socket; in particular, it defines the family of networking protocols to which the address belongs (for example, IP or IPv6), as well as the size of the address itself. This type can be safely ignored for most high-level (and, arguably, most low-level) networking operations.

```
public class SocketAddress {  
    // Public Constructors  
    public SocketAddress(System.Net.Sockets.AddressFamily family);  
    public SocketAddress(System.Net.Sockets.AddressFamily family, int size);  
    // Public Instance Properties  
    public AddressFamily Family {get; }  
    public int Size {get; }  
    public byte this[int offset] {set; get; }  
    // Public Instance Methods  
    public override bool Equals(object comparand);  
    // overrides object  
    public override int GetHashCode( );  
    // overrides object  
    public override string ToString( );  
    // overrides object  
}
```

Returned By

```
EndPoint.Serialize( )
```

Passed To

```
EndPoint.Create( )
```

SocketPermission

ECMA 1.0, serializable

System.Net (system.dll)

sealed class

This permission controls whether code can make or accept socket connections for a given **NetworkAccess**, hostname, and port number (see the four-argument form of the constructor). The static field **AllPorts** represents permission to all ports and can be used as the port argument to the constructor.

```
public sealed class SocketPermission : System.Security.CodeAccessPermission,
    System.Security.Permissions.IUnrestrictedPermission {
// Public Constructors
    public SocketPermission(NetworkAccess access, TransportType transport, string hostName,
        int portNumber);
    public SocketPermission(System.Security.Permissions.PermissionState state);
// Public Static Fields
    public const int AllPorts;
// ==-1
// Public Instance Properties
    public IEnumerator AcceptList{get; }
    public IEnumerator ConnectList{get; }
// Public Instance Methods
    public void AddPermission(NetworkAccess access, TransportType transport, string hostName);
    public override IPermission Copy( );
// overrides CodeAccessPermission
    public override void FromXml(System.Security.SecurityElement securityElement)
// overrides CodeAccessPermission
    public override IPermission Intersect(System.Security.IPermission target)
// overrides CodeAccessPermission
    public override bool IsSubsetOf(System.Security.IPermission target)
// overrides CodeAccessPermission
    public bool IsUnrestricted( );
// implements IUnrestrictedPermission
    public override SecurityElement ToXml( );
// overrides CodeAccessPermission
    public override IPermission Union(System.Security.IPermission target)
// overrides CodeAccessPermission
}
```

Hierarchy

System.Object → System.Security.CodeAccessPermission(System.Security.IPermission, System.Security.ISecurityEncodable, System.Security.IStackWalk) → SocketPermission(System.Security.Permissions.IUnrestrictedPermission)

[Team LiB]

SocketPermissionAttribute

ECMA 1.0,
serializable


System.Net (system.dll)

sealed class

This attribute is used to declare in metadata that the attributed method or class requires `SocketPermission` form.

```
public sealed class SocketPermissionAttribute : System.Security.Permissions.CodeAccessS
// Public Constructors
    public SocketPermissionAttribute(System.Security.Permissions.SecurityAction action);
// Public Instance Properties
    public string Access{set; get; }
    public string Host{set; get; }
    public string Port{set; get; }
    public string Transport{set; get; }
// Public Instance Methods
    public override IPermission CreatePermission( );
// overrides System.Security.Permissions.SecurityAttribute
}
```

Hierarchy



Valid On

Assembly, Class, Struct, Constructor, Method

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TransportType ECMA 1.0, serializable

System.Net (system.dll) *enum*

This enumeration defines the transport protocols that can be used to communicate over a socket.

```
public enum TransportType {  
    Udp = 1,  
    Connectionless = 1 ,  
    Tcp = 2 ,  
    ConnectionOriented = 2 ,  
    All = 3  
}
```

Hierarchy

```
System.Object → System.ValueType → System.Enum(System.IComparable,  
System.IFormattable, System.IConvertible) → TransportType
```

Returned By

```
EndpointPermission.Transport
```

Passed To

```
SocketPermission.{AddPermission( ), SocketPermission( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WebClient

ECMA 1.0, marshal by reference, disposable

System.Net (system.dll) *sealed class*

This class is a simple HTTP User-Agent. Use `DownloadData()` to fetch a document as an array of bytes. a document and stores it in a file. You can upload data to a URI using `UploadFile()` or `UploadData()` array).

Before connecting to a URI, invoke the `Add()` method of the `QueryString` or `Headers` properties to add string or HTTP request headers. Set the credentials property to authenticate the `WebClient` to the remot

```
public sealed class WebClient : System.ComponentModel.Component {
// Public Constructors
    public WebClient( );
// Public Instance Properties
    public string BaseAddress{set; get; }
    public ICredentials Credentials{set; get; }
    public WebHeaderCollection Headers{set; get; }
    public NameValueCollection QueryString{set; get; }
    public WebHeaderCollection ResponseHeaders{get; }
// Public Instance Methods
    public byte[] DownloadData(string address);
    public void DownloadFile(string address, string fileName);
    public Stream OpenRead(string address);
    public Stream OpenWrite(string address);
    public Stream OpenWrite(string address, string method);
    public byte[] UploadData(string address, byte[] data);
    public byte[] UploadData(string address, string method, byte[] data);
    public byte[] UploadFile(string address, string fileName);
    public byte[] UploadFile(string address, string method, string fileName);
    public byte[] UploadValues(string address, System.Collections.Specialized.NameValue
    public byte[] UploadValues(string address, string method, System.Collections.Specia
}
```

Hierarchy

System.Object → System.MarshalByRefObject → System.ComponentModel.Component(System.Cc
System.IDisposable) → WebClient


WebException CF 1.0, ECMA 1.0, serializable

System.Net (system.dll) *class*

This exception represents an error that occurred while using a protocol-specific implementation of `WebRequest`. In the case of some protocols, such as HTTP, the exception's `Response` property contains information about the error that occurred.

```
public class WebException : InvalidOperationException {
// Public Constructors
    public WebException( );
    public WebException(string message);
    public WebException(string message, Exception innerException);
    public WebException(string message, Exception innerException, WebExceptionStatus status,
        WebResponse response);
    public WebException(string message, WebExceptionStatus status);
// Protected Constructors
    protected WebException(System.Runtime.Serialization.SerializationInfo serializationInfo,
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
    public WebResponse Response {get; }
    public WebExceptionStatus Status {get; }
}
```

Hierarchy



WebExceptionStatus

CF 1.0, ECMA 1.0,
serializable

System.Net (system.dll)

enum

This enumeration defines constants for the status codes used in `WebException.Status`.

```
public enum WebExceptionStatus {  
    Success = 0 ,  
    NameResolutionFailure = 1 ,  
    ConnectFailure = 2 ,  
    ReceiveFailure = 3 ,  
    SendFailure = 4 ,  
    PipelineFailure = 5 ,  
    RequestCanceled = 6 ,  
    ProtocolError = 7 ,  
    ConnectionClosed = 8 ,  
    TrustFailure = 9 ,  
    SecureChannelFailure = 10 ,  
    ServerProtocolViolation = 11 ,  
    KeepAliveFailure = 12 ,  
    Pending = 13 ,  
    Timeout = 14 ,  
    ProxyNameResolutionFailure = 15 ,  
    UnknownError = 16 ,  
    MessageLengthLimitExceeded = 17  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `WebExceptionStatus`

Returned By

`WebException.Status`

Passed To

`WebException.WebException()`

WebHeaderCollection

CF 1.0, ECMA 1.0,
serializable

System.Net (system.dll)

class

This class contains the headers that are part of a [WebRequest](#) or [WebResponse](#). Some headers should not be accessed through this collection. Instead, use the corresponding properties of the [WebRequest](#) or [WebResponse](#) (HTTP-specific subclasses). These headers are Accept, Connection, Content-Length, Content-Type, Date, Location, Range, Referer, Transfer-Encoding, and User-Agent.

```
public class WebHeaderCollection : System.Collections.Specialized.NameValueCollection {
// Public Constructors
    public WebHeaderCollection( );
// Protected Constructors
    protected WebHeaderCollection(System.Runtime.Serialization.SerializationInfo seriali.
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Static Methods
    public static bool IsRestricted(string headerName);
// Public Instance Methods
    public void Add(string header);
    public override void Add(string name, string value);
// overrides NameValueCollection
    public override string[] GetValues(string header);
// overrides NameValueCollection
    public override void OnDeserialization(object sender);
// overrides System.Collections.Specialized.NameObjectCollectionBase
    public override void Remove(string name);
// overrides NameValueCollection
    public override void Set(string name, string value);
// overrides NameValueCollection
    public byte[] ToByteArray( );
    public override string ToString( );
// overrides object
// Protected Instance Methods
    protected void AddWithoutValidate(string headerName, string headerValue);
}
```

Hierarchy

```
System.Object →
System.Collections.Specialized.NameObjectCollectionBase(System.Collections.ICollection ,
System.Collections.IEnumerable , System.Runtime.Serialization.ISerializable ,
System.Runtime.Serialization.IDeserializationCallback) →
System.Collections.Specialized.NameValueCollection → WebHeaderCollection
```

Returned By

`WebClient.Headers , ResponseHeaders } , WebRequest.Headers , WebResponse.Headers`

Passed To

`HttpContinueDelegate.BeginInvoke() , Invoke() } , WebClient.Headers , WebRequest.Headers`

[Team LiB]

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

WebPermission

ECMA 1.0, serializable

System.Net (system.dll)

sealed class

This permission controls which connections an application can make or accept.

```
public sealed class WebPermission : System.Security.CodeAccessPermission,
    System.Security.Permissions.IUnrestrictedPermission {
// Public Constructors
    public WebPermission( );
    public WebPermission(NetworkAccess access, System.Text.RegularExpressions.Regex uriR
    public WebPermission(NetworkAccess access, string uriString);
    public WebPermission(System.Security.Permissions.PermissionState state);
// Public Instance Properties
    public IEnumerable AcceptList{get; }
    public IEnumerable ConnectList{get; }
// Public Instance Methods
    public void AddPermission(NetworkAccess access, System.Text.RegularExpressions.Regex
    public void AddPermission(NetworkAccess access, string uriString);
    public override IPermission Copy( );
// overrides CodeAccessPermission
    public override void FromXml(System.Security.SecurityElement securityElement)
// overrides CodeAccessPermission
    public override IPermission Intersect(System.Security.IPermission target)
// overrides CodeAccessPermission
    public override bool IsSubsetOf(System.Security.IPermission target)
// overrides CodeAccessPermission
    public bool IsUnrestricted( );
// implements IUnrestrictedPermission
    public override SecurityElement ToXml( );
// overrides CodeAccessPermission
    public override IPermission Union(System.Security.IPermission target)
// overrides CodeAccessPermission
}
```

Hierarchy

System.Object → System.Security.CodeAccessPermission(System.Security.IPermission ,
 System.Security.ISecurityEncodable , System.Security.IStackWalk) →
 WebPermission(System.Security.Permissions.IUnrestrictedPermission)

[Team LiB]

◀ PREVIOUS

NEXT ▶

WebPermissionAttribute

ECMA 1.0,
serializable


System.Net (system.dll)

sealed class

This attribute is used to declare in metadata that the attributed method or class requires **WebPermission** form.

```
public sealed class WebPermissionAttribute : System.Security.Permissions.CodeAccessSecu:
// Public Constructors
    public WebPermissionAttribute(System.Security.Permissions.SecurityAction action);
// Public Instance Properties
    public string Accept{set; get; }
    public string AcceptPattern{set; get; }
    public string Connect{set; get; }
    public string ConnectPattern{set; get; }
// Public Instance Methods
    public override IPermission CreatePermission( );
// overrides System.Security.Permissions.SecurityAttribute
}
```

Hierarchy



Valid On

Assembly, Class, Struct, Constructor, Method

[Team LiB]

◀ PREVIOUS

NEXT ▶

WebProxy CF 1.0, ECMA 1.0, serializable

System.Net (system.dll) *class*

This implementation of `IWebProxy` supports HTTP proxies. Use the one-argument form of the constructor of the proxy server. The second argument, `BypassOnLocal`, if set to true, bypasses the proxy server for addresses. Other forms of the constructor allow you to specify an array that lists servers for which you skip proxy (this list can contain regular expression strings containing URI patterns to match). You can also supply credentials to authenticate your application to the proxy server.

See `GlobalProxySelection` or the `WebRequest.Proxy` property for details on configuring a proxy.

```
public class WebProxy : IWebProxy, System.Runtime.Serialization.ISerializable {
// Public Constructors
    public WebProxy( );
    public WebProxy(string Address);
    public WebProxy(string Address, bool BypassOnLocal);
    public WebProxy(string Address, bool BypassOnLocal, string[] BypassList);
    public WebProxy(string Address, bool BypassOnLocal, string[] BypassList, ICredentials
    public WebProxy(string Host, int Port);
    public WebProxy(Uri Address);
    public WebProxy(Uri Address, bool BypassOnLocal);
    public WebProxy(Uri Address, bool BypassOnLocal, string[] BypassList);
    public WebProxy(Uri Address, bool BypassOnLocal, string[] BypassList, ICredentials
// Protected Constructors
    protected WebProxy(System.Runtime.Serialization.SerializationInfo serializationInfo,
        System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
    public Uri Address{set; get; }
    public ArrayList BypassArrayList{get; }
    public string[] BypassList{set; get; }
    public bool BypassProxyOnLocal{set; get; }
    public ICredentials Credentials{set; get; }
// implements IWebProxy
// Public Static Methods
    public static WebProxy GetDefaultProxy( );
// Public Instance Methods
    public Uri GetProxy(Uri destination);
// implements IWebProxy
    public bool IsBypassed(Uri host);
// implements IWebProxy
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

WebRequest

CF 1.0, ECMA 1.0, serializable, marshal by reference

System.Net (system.dll) *abstract class*

Because many Internet protocols are request-response synchronous protocols, this class serves as a base and all request-response style of network communication. As such, a .NET programmer will never create `WebRequest` type directly-instead, a static method on this class, `Create()`, is used as a "virtual constructor" to create a subtype of `WebRequest` that matches the protocol scheme requested. For example, if the string `http://www.oreilly.com` is passed to `Create()`, an instance of `HttpWebRequest` is handed back. Out of "http", "https", and "file" are supported.

Once obtained, a .NET programmer can manipulate the common properties of the `WebRequest` type to cover aspects of the request. Alternatively, downcast the generic `WebRequest` reference to the concrete type to access protocol-specific aspects of that protocol-for example, the returned object from `WebRequest.Create("http://www.oreilly.com")` will be a `HttpWebRequest`, so it is safe to cast it as `HttpWebRequest` allows access to the `Accept` and `SendChunked` properties/headers in the request. Be sure to manipulate these properties before the request is sent, or the modifications will have no effect.

Use the `GetResponse()` method to obtain a `WebResponse` object corresponding to the response that the server sent. This means that the request is sent, and the response harvested. The methods `BeginGetResponse` and `EndGetResponse()` are asynchronous versions of `GetResponse()`.

By default, `WebRequest` uses the proxy server specified in `GlobalProxySelection.Select`. Override this by assigning an `IWebProxy` implementation to the `Proxy` property.

```
public abstract class WebRequest : MarshalByRefObject, System.Runtime.Serialization.ISerializable
// Protected Constructors
protected WebRequest( );
protected WebRequest(System.Runtime.Serialization.SerializationInfo serializationInfo,
    System.Runtime.Serialization.StreamingContext streamingContext);
// Public Instance Properties
public virtual string ConnectionGroupName {set; get; }
public virtual long ContentLength {set; get; }
public virtual string ContentType {set; get; }
public virtual ICredentials Credentials {set; get; }
public virtual WebHeaderCollection Headers {set; get; }
public virtual string Method {set; get; }
public virtual bool PreAuthenticate {set; get; }
public virtual IWebProxy Proxy {set; get; }
public virtual Uri RequestUri {get; }
public virtual int Timeout {set; get; }
// Public Static Methods
public static WebRequest Create(string requestUriString);
public static WebRequest Create(Uri requestUri);
public static WebRequest CreateDefault(Uri requestUri);
```

```
    public static bool RegisterPrefix(string prefix, IWebRequestCreate creator);  
    // Public Instance Methods  
    public virtual void Abort( );  
    public virtual IAsyncResult BeginGetRequestStream(AsyncCallback callback, object state);  
    public virtual IAsyncResult BeginGetResponse(AsyncCallback callback, object state);  
    public virtual Stream EndGetRequestStream(IAsyncResult asyncResult);  
    public virtual WebResponse EndGetResponse(IAsyncResult asyncResult);  
    public virtual Stream GetRequestStream( );  
    public virtual WebResponse GetResponse( );  
}
```

Hierarchy

System.Object → System.MarshalByRefObject →
WebRequest(System.Runtime.Serialization.ISerializable)

Subclasses

FileWebRequest , HttpWebRequest

Returned By

IWebRequestCreate.Create()

Passed To

AuthenticationManager.{Authenticate(), PreAuthenticate()}, IAuthenticationModule.{Auth
, PreAuthenticate()}, ICertificatePolicy.CheckValidationResult()

[Team LiB]

CF 1.0, ECMA 1.0, serializable, WebResponse marshal by reference, disposable


System.Net (system.dll) *abstract class*

This class represents a response received from a `WebRequest`. A response consists of headers (stored as pairs in the `Headers` property) and a response body. You can obtain the response body as a `System.IO.` the `GetResponseStream()` method.

When you are finished with the response, call its `Close()` method; this releases any open resources still `WebResponse` without having to wait for garbage collection to do so (which could take longer than desired).

```
public abstract class WebResponse : MarshalByRefObject, System.Runtime.Serialization.ISerializable,
    IDisposable {
    // Protected Constructors
    protected WebResponse();
    protected WebResponse(System.Runtime.Serialization.SerializationInfo serializationInfo,
        System.Runtime.Serialization.StreamingContext streamingContext);
    // Public Instance Properties
    public virtual long ContentLength {get; set;}
    public virtual string ContentType {get; set;}
    public virtual WebHeaderCollection Headers {get;}
    public virtual Uri ResponseUri {get;}
    // Public Instance Methods
    public virtual void Close();
    public virtual Stream GetResponseStream();
}
```

Hierarchy



Subclasses

FileWebResponse, HttpWebResponse

Returned By

WebException.Response, WebRequest.{EndGetResponse(), GetResponse()}

Passed To

WebException.WebException()

[Team LiB]

Chapter 34. System.Net.Sockets

The `System.Net.Sockets` namespace classes implement standard Berkeley sockets APIs for cross-process/cross-host communication. Sockets are low-level objects (abstractions, really) that provide the foundation for most Internet networking. A socket binds to a local address and port, and either waits for a connection from a remote address or connects to a remote address and exchanges data across the network. Two socket implementations are made available in this namespace, TCP/IP and UDP/IP. Most Internet applications, such as FTP clients and web browsers, are built upon socket connections.

Although many system-level programmers feel a close kinship with these types, .NET programmers are greatly encouraged to consider using higher-level constructs, such as HTTP (see the `System.Net` namespace) or the `System.Runtime.Remoting` types, to facilitate remote communications. If you need to work at the socket level, consider using `TcpClient` or `TcpListener`. These are high-level abstractions of the socket API that support client and server functionality.

For more details regarding many of the options mentioned in this namespace, consult a low-level sockets reference, such as W. Richard Stevens' *Network Programming in the Unix Environment* (Volumes 1 and 2) or *TCP/IP Illustrated* (Volumes 1, 2, and 3). Although the books were written for a Unix environment, .NET faithfully mirrors much, if not all, of the Berkeley sockets API (which originally came from Unix). [Figure 34-1](#) shows the types in this namespace.

Figure 34-1. The System.Net.Sockets namespace

AddressFamily CF 1.0, ECMA 1.0, serializable

System.Net.Sockets (system.dll)

enum

```
public enum AddressFamily {
    Unspecified = 0 ,
    Unix = 1 ,
    InterNetwork = 2 ,
    ImpLink = 3 ,
    Pup = 4 ,
    Chaos = 5 ,
    Ipx = 6 ,
    NS = 6 ,
    Iso = 7 ,
    Osi = 7 ,
    Ecma = 8 ,
    DataKit = 9 ,
    Ccitt = 10 ,
    Sna = 11 ,
    DecNet = 12 ,
    DataLink = 13 ,
    Lat = 14 ,
    HyperChannel = 15 ,
    AppleTalk = 16 ,
    NetBios = 17 ,
    VoiceView = 18 ,
    FireFox = 19 ,
    Banyan = 21 ,
    Atm = 22 ,
    InterNetworkV6 = 23 ,
    Cluster = 24 ,
    Ieee12844 = 25 ,
    Irda = 26 ,
    NetworkDesigners = 28 ,
    Max = 29 ,
    Unknown = -1
}
```

This enumeration contains values to specify the address family used by a socket. This indicates to which family of addressing schemes the address of the socket belongs. Note that the standard four-digit IP scheme falls under the enumeration `InterNetwork`, and its successor, IPv6, under the enumeration `InterNetworkV6`.

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable,`

System.IFormattable, System.IConvertible) → AddressFamily

Returned By

System.Net.EndPoint.AddressFamily, System.Net.IPAddress.AddressFamily,
System.Net.SocketAddress.Family, Socket.AddressFamily

Passed To

System.Net.SocketAddress.SocketAddress(), Socket.Socket(), TcpClient.TcpClient(),
UdpClient.UdpClient()

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IPv6MulticastOption

.NET 1.1

System.Net.Sockets (system.dll)

class

This class specifies an IPv6 version of the `MulticastOption` class, described later in this chapter.

```
public class IPv6MulticastOption {  
    // Public Constructors  
    public IPv6MulticastOption (System.Net.IPAddress group);  
    public IPv6MulticastOption (System.Net.IPAddress group, long ifindex);  
    // Public Instance Properties  
    public IPAddress Group {set; get; }  
    public long InterfaceIndex {set; get; }  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

LingerOption

CF 1.0, ECMA 1.0

System.Net.Sockets (system.dll) *class*

This class is a socket option object that enables a socket to continue to send queued data after a call to `Socket.Close()`. If the `Enabled` property is `True`, the connection lingers for the number of seconds given by `LingerTime`. The `LingerOption` object is set on a socket with the `Socket.SetSocketOption()` method and a `SocketOptionName` of `SocketOptionName.Linger`.

```
public class LingerOption {  
    // Public Constructors  
    public LingerOption(bool enable, int seconds);  
    // Public Instance Properties  
    public bool Enabled{set; get; }  
    public int LingerTime{set; get; }  
}
```

Returned By

`TcpClient.LingerState`

Passed To

`TcpClient.LingerState`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MulticastOption

CF 1.0, ECMA 1.0

System.Net.Sockets (system.dll) *class*

This class specifies an IP address for IP-multicast packets. IP-multicast addresses must be in the range of 224.0.0.0 to 239.255.255.255. The `MulticastOption` is set on a socket using the `SocketOptionName.AddMembership` value with `Socket.SetSocketOption()`. You can drop multicast with `SocketOptionName.DropMembership`.

```
public class MulticastOption {  
    // Public Constructors  
    public MulticastOption(System.Net.IPAddress group);  
    public MulticastOption(System.Net.IPAddress group, System.Net.IPAddress mcint);  
    // Public Instance Properties  
    public IPAddress Group{set; get; }  
    public IPAddress LocalAddress{set; get; }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

NetworkStream

CF 1.0, ECMA 1.0, marshal by reference, disposable

System.Net.Sockets (system.dll) *class*

This class creates a basic network stream from an underlying socket. It allows for simple data access to the stream and supports permissions settings.

```
public class NetworkStream : System.IO.Stream {
// Public Constructors
    public NetworkStream(Socket socket);
    public NetworkStream(Socket socket, bool ownsSocket);
    public NetworkStream(Socket socket, System.IO.FileAccess access);
    public NetworkStream(Socket socket, System.IO.FileAccess access, bool ownsSocket);
// Public Instance Properties
    public override bool CanRead{get; }
// overrides System.IO.Stream
    public override bool CanSeek{get; }
// overrides System.IO.Stream
    public override bool CanWrite{get; }
// overrides System.IO.Stream
    public virtual bool DataAvailable{get; }
    public override long Length{get; }
// overrides System.IO.Stream
    public override long Position{set; get; }
// overrides System.IO.Stream
// Protected Instance Properties
    protected bool Readable{set; get; }
    protected Socket Socket{get; }
    protected bool Writeable{set; get; }
// Public Instance Methods
    public override IAsyncResult BeginRead(byte[] buffer, int offset, int size,
        AsyncCallback callback, object state)
// overrides System.IO.Stream
    public override IAsyncResult BeginWrite(byte[] buffer, int offset, int size,
        AsyncCallback callback, object state)
// overrides System.IO.Stream
    public override void Close( );
// overrides System.IO.Stream
    public override int EndRead(IAsyncResult asyncResult);
// overrides System.IO.Stream
    public override void EndWrite(IAsyncResult asyncResult);
// overrides System.IO.Stream
    public override void Flush( );
```

```

// overrides System.IO.Stream
public override int Read(in byte[ ] buffer, int offset, int size);
// overrides System.IO.Stream
public override long Seek(long offset, System.IO.SeekOrigin origin)
// overrides System.IO.Stream
public override void SetLength(long value);
// overrides System.IO.Stream
public override void Write(byte[ ] buffer, int offset, int size)
// overrides System.IO.Stream
// Protected Instance Methods
protected virtual void Dispose(bool disposing);
protected override void Finalize( );
// overrides object
}

```

Hierarchy

System.Object → System.MarshalByRefObject → System.IO.Stream(System.IDisposable)
 → NetworkStream

Returned By

TcpClient.GetStream()

[Team LiB]

◀ PREVIOUS

NEXT ▶


ProtocolFamily CF 1.0, serializable

System.Net.Sockets (system.dll) *enum*

This enumeration contains settings for the protocol family of a socket.

```
public enum ProtocolFamily {
    Unspecified = 0 ,
    Unix = 1 ,
    InterNetwork = 2 ,
    ImpLink = 3 ,
    Pup = 4 ,
    Chaos = 5 ,
    Ipx = 6 ,
    NS = 6 ,
    Iso = 7 ,
    Osi = 7 ,
    Ecma = 8 ,
    DataKit = 9 ,
    Ccitt = 10 ,
    Sna = 11 ,
    DecNet = 12 ,
    DataLink = 13 ,
    Lat = 14 ,
    HyperChannel = 15 ,
    AppleTalk = 16 ,
    NetBios = 17 ,
    VoiceView = 18 ,
    FireFox = 19 ,
    Banyan = 21 ,
    Atm = 22 ,
    InterNetworkV6 = 23 ,
    Cluster = 24 ,
    Ieee12844 = 25 ,
    Irda = 26 ,
    NetworkDesigners = 28 ,
    Max = 29 ,
    Unknown = -1
}
```

Hierarchy



ProtocolType CF 1.0, ECMA 1.0, serializable

System.Net.Sockets (system.dll) *enum*

This enumeration contains settings for the protocol type of a socket. A protocol type must be specified for every `Socket` instance.

```
public enum ProtocolType {
    Unspecified = 0,
    IP = 0,
    Icmp = 1,
    Igmp = 2,
    Ggp = 3,
    Tcp = 6,
    Pup = 12,
    Udp = 17,
    Idp = 22,
    IPv6 = 41,
    ND = 77,
    Raw = 255,
    Ipx = 1000,
    Spx = 1256,
    SpxII = 1257,
    Unknown = -1
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ProtocolType`

Returned By

`Socket.ProtocolType`

Passed To

`Socket.Socket()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SelectMode CF 1.0, ECMA 1.0, serializable

System.Net.Sockets (system.dll) *enum*

This enumeration contains the settings for polling modes used by `Socket.Poll()`.

```
public enum SelectMode {
    SelectRead = 0,
    SelectWrite = 1,
    SelectError = 2
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `SelectMode`

Passed To

`Socket.Poll()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Socket

CF 1.0, ECMA 1.0, disposable

System.Net.Sockets (system.dll)

class

This class implements a standard Berkeley socket. Each socket is constructed with the address family to use (datagram or stream), and the protocol that the socket will use. Every socket must be bound to a local endpoint. The `Bind()` method takes a `System.Net.IPEndPoint` object that contains the local IP address and port. `Bind()` must be called before any connection can be made through the socket. To establish a connection to a remote address, use `Connect()`.

To listen for connections from remote clients, use `Listen()` to set the socket in listening mode where it accepts incoming connections. The integer argument to `Listen()` specifies how many remote connection requests can be queued for a socket connection. A call to `Accept()` returns a new socket that connects to the first pending connection in the queue. This new socket exists only for this connection and is destroyed once the connection is closed.

You can interrogate the socket to determine if it supports IPv4 (standard TCP/IP quad-style addresses) by examining the `SupportsIPv4` property; similarly, you can determine if the socket supports IPv6 by examining `SupportsIPv6`.

Data is written to a socket using `Send()`. Data from a specified buffer is sent through the socket to its destination. Data is read from a socket using `Receive()`. `Receive()` gets data from the socket connection and stores it in a specified buffer.

You can set several socket options to control the behavior of a socket with `SetSocketOption()`. This method takes a `SocketOptionLevel` value, which determines the type of socket option to set. For example, `SocketOptionLevel.Socket` options related to an IP socket. The `SocketOptionName` value gives the specific option, which must be an `SocketOptionLevel`. The last argument to `SetSocketOption()` provides the value of the option. `SetSocketOption()` features such as `SocketOptionName.KeepAlive`, in which a connection is maintained even when no data is being sent; `SocketOptionName.MaxConnections`, which sets the maximum permitted size of a listen queue.

When a session is finished, the connection can be gracefully closed with `Shutdown()`. When send or receive operations are no longer allowed on the socket, they are no longer allowed on the socket. A call to `Close()` terminates the socket.

```
public class Socket : IDisposable {
    // Public Constructors
    public Socket(AddressFamily addressFamily, SocketType socketType, ProtocolType protocolType) { }

    // Public Static Properties
    public static bool SupportsIPv4 {get; }
    public static bool SupportsIPv6 {get; }

    // Public Instance Properties
    public AddressFamily AddressFamily {get; }
    public int Available {get; }
    public bool Blocking {set; get; }
    public bool Connected {get; }
    public IntPtr Handle {get; }
    public EndPoint LocalEndPoint {get; }
    public ProtocolType ProtocolType {get; }
    public EndPoint RemoteEndPoint {get; }
    public SocketType SocketType {get; }
```

```

// Public Static Methods
public static void Select(System.Collections.IList checkRead, System.Collections.IList
    System.Collections.IList checkError, int microseconds);
// Public Instance Methods
public Socket Accept( );
public IAsyncResult BeginAccept(AsyncCallback callback, object state);
public IAsyncResult BeginConnect(System.Net.EndPoint remoteEP, AsyncCallback callback,
public IAsyncResult BeginReceive(byte[] buffer, int offset, int size, SocketFlags socketFlags,
    AsyncCallback callback, object state);
public IAsyncResult BeginReceiveFrom(byte[] buffer, int offset, int size, SocketFlags socketFlags,
    ref System.Net.EndPoint remoteEP, AsyncCallback callback, object state);
public IAsyncResult BeginSend(byte[] buffer, int offset, int size, SocketFlags socketFlags,
    AsyncCallback callback, object state);
public IAsyncResult BeginSendTo(byte[] buffer, int offset, int size, SocketFlags socketFlags,
    System.Net.EndPoint remoteEP, AsyncCallback callback, object state);
public void Bind(System.Net.EndPoint localEP);
public void Close( );
public void Connect(System.Net.EndPoint remoteEP);
public Socket EndAccept(IAsyncResult asyncResult);
public void EndConnect(IAsyncResult asyncResult);
public int EndReceive(IAsyncResult asyncResult);
public int EndReceiveFrom(IAsyncResult asyncResult, ref System.Net.EndPoint endPoint);
public int EndSend(IAsyncResult asyncResult);
public int EndSendTo(IAsyncResult asyncResult);
public override int GetHashCode( );
// overrides object
public byte[] GetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionName,
    int optionLength);
public object GetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionName,
public void GetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionName,
    byte[] optionValue);
public int IOControl(int ioControlCode, byte[] optionInValue, byte[] optionOutValue);
public void Listen(int backlog);
public bool Poll(int microseconds, SelectMode mode);
public int Receive(byte[] buffer);
public int Receive(byte[] buffer, int offset, int size, SocketFlags socketFlags);
public int Receive(byte[] buffer, int size, SocketFlags socketFlags);
public int Receive(byte[] buffer, SocketFlags socketFlags);
public int ReceiveFrom(byte[] buffer, ref System.Net.EndPoint remoteEP);
public int ReceiveFrom(byte[] buffer, int offset, int size, SocketFlags socketFlags,
    ref System.Net.EndPoint remoteEP);
public int ReceiveFrom(byte[] buffer, int size, SocketFlags socketFlags, ref System
public int ReceiveFrom(byte[] buffer, SocketFlags socketFlags, ref System.Net.EndPo
public int Send(byte[] buffer);
public int Send(byte[] buffer, int offset, int size, SocketFlags socketFlags);
public int Send(byte[] buffer, int size, SocketFlags socketFlags);
public int Send(byte[] buffer, SocketFlags socketFlags);
public int SendTo(byte[] buffer, System.Net.EndPoint remoteEP);
public int SendTo(byte[] buffer, int offset, int size, SocketFlags socketFlags,

```



```
        System.Net.EndPoint remoteEP);  
    public int SendTo(byte[ ] buffer, int size, SocketFlags socketFlags, System.Net.EndP  
    public int SendTo(byte[ ] buffer, SocketFlags socketFlags, System.Net.EndPoint remot  
    public void SetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionNa  
        byte[ ] optionValue);  
    public void SetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionNa  
        int optionValue);  
    public void SetSocketOption(SocketOptionLevel optionLevel, SocketOptionName optionNa  
        object optionValue);  
    public void Shutdown(SocketShutdown how);  
    // Protected Instance Methods  
    protected virtual void Dispose(bool disposing);  
    protected override void Finalize( );  
    // overrides object  
}
```

Returned By

NetworkStream.Socket , TcpClient.Client , TcpListener.{AcceptSocket() , Server} , UdpClient

Passed To

NetworkStream.NetworkStream() , TcpClient.Client , UdpClient.Client

[Team LiB]

[◀ PREVIOUS](#) [NEXT ▶](#)

SocketException


CF 1.0, ECMA 1.0,
serializable

System.Net.Sockets (system.dll) *class*

This exception represents a socket-related error.

```
public class SocketException : System.ComponentModel.Win32Exception {  
    // Public Constructors  
    public SocketException( );  
    public SocketException(int errorCode);  
    // Protected Constructors  
    protected SocketException(System.Runtime.Serialization.SerializationInfo serializati  
        System.Runtime.Serialization.StreamingContext streamingContext);  
    // Public Instance Properties  
    public override int ErrorCode{get; }  
    // overrides System.Runtime.InteropServices.ExternalException  
}
```

Hierarchy



SocketFlags

CF 1.0, ECMA 1.0, serializable, flag

System.Net.Sockets (system.dll) *enum*

This enumeration contains values for setting flags for socket messages. `SocketFlags` are provided to `Socket.Send()` and `Socket.Receive()` to specify parameters for how data is transferred. The `OutOfBand` flag tells the socket to process out-of-band data in the stream. `DontRoute` tells the socket to send data to the remote endpoint without using routing tables.

```
public enum SocketFlags {  
    None = 0x00000000 ,  
    OutOfBand = 0x00000001 ,  
    Peek = 0x00000002 ,  
    DontRoute = 0x00000004 ,  
    MaxIOVectorLength = 0x00000010 ,  
    Partial = 0x00008000  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `SocketFlags`

Passed To

`Socket.BeginReceive(), BeginReceiveFrom(), BeginSend(), BeginSendTo(), Receive(), ReceiveFrom(), Send(), SendTo()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SocketOptionLevel

CF 1.0, ECMA 1.0,
serializable

System.Net.Sockets (system.dll)

enum

This enumeration contains values for the type of socket option specified in `Socket.SetSocketOption()`.

```
public enum SocketOptionLevel {  
    IP = 0,  
    Tcp = 6,  
    Udp = 17,  
    IPv6 = 41,  
    Socket = 65535  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → SocketOptionLevel

Passed To

Socket.{GetSocketOption(), SetSocketOption()}

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SocketOptionName

CF 1.0, ECMA 1.0,
serializable

System.Net.Sockets (system.dll) *enum*

This enumeration contains the names of socket options set by `Socket.SetSocketOption()`. The socket option named must be applicable to the option level from `SocketOptionLevel`.

```
public enum SocketOptionName {
    IPOptions = 1 ,
    Debug = 1 ,
    NoDelay = 1 ,
    NoChecksum = 1 ,
    HeaderIncluded = 2 ,
    AcceptConnection = 2 ,
    Expedited = 2 ,
    BsdUrgent = 2 ,
    TypeOfService = 3 ,
    ReuseAddress = 4 ,
    IpTimeToLive = 4 ,
    KeepAlive = 8 ,
    MulticastInterface = 9 ,
    MulticastTimeToLive = 10 ,
    MulticastLoopback = 11 ,
    AddMembership = 12 ,
    DropMembership = 13 ,
    DontFragment = 14 ,
    AddSourceMembership = 15 ,
    DropSourceMembership = 16 ,
    DontRoute = 16 ,
    BlockSource = 17 ,
    UnblockSource = 18 ,
    PacketInformation = 19 ,
    ChecksumCoverage = 20 ,
    Broadcast = 32 ,
    UseLoopback = 64 ,
    Linger = 128 ,
    OutOfBandInline = 256 ,
    SendBuffer = 4097 ,
    ReceiveBuffer = 4098 ,
    SendLowWater = 4099 ,
    ReceiveLowWater = 4100 ,
    SendTimeout = 4101 ,
    ReceiveTimeout = 4102 ,
    Error = 4103 ,
    Type = 4104 ,
```

```
MaxConnections = 2147483647 ,  
DontLinger = -129 ,  
ExclusiveAddressUse = -5  
}
```

Hierarchy

```
System.Object → System.ValueType → System.Enum(System.IComparable,  
System.IFormattable, System.IConvertible) → SocketOptionName
```

Passed To

```
Socket.{GetSocketOption( ), SetSocketOption( )}
```

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SocketShutdown

CF 1.0, ECMA 1.0,
serializable

System.Net.Sockets (system.dll) *enum*

This enumeration provides values used by `Socket.Shutdown()`. `Receive` specifies that receiving will be disabled on a socket. `Send` specifies that sending will be disabled. `Both` disables sending and receiving.

```
public enum SocketShutdown {  
    Receive = 0 ,  
    Send = 1 ,  
    Both = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `SocketShutdown`

Passed To

`Socket.Shutdown()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SocketType CF 1.0, ECMA 1.0, serializable

System.Net.Sockets (system.dll) *enum*

This enumeration contains the names for the type of socket that is created.

```
public enum SocketType {
    Stream = 1,
    Dgram = 2,
    Raw = 3,
    Rdm = 4,
    Seqpacket = 5,
    Unknown = -1
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → SocketType

Returned By

Socket.SocketType

Passed To

Socket.Socket()

TcpClient

CF 1.0, disposable

System.Net.Sockets (system.dll)

class

This class provides a client-side abstraction of the sockets API. The zero-argument form of the constructor creates the client. Connect to a remote server with the `Connect()` method (you must specify an existing `System.Net.IPEndPoint` or a remote IP address and port number). Alternatively, use an overloaded form of the constructor to simultaneously create the client and make the connection.

This class completely obscures the underlying socket. However, the `GetStream()` method returns a `NetworkStream` that you can use to send and receive data across the network.

```
public class TcpClient : IDisposable {
// Public Constructors
    public TcpClient( );
    public TcpClient(AddressFamily family);
    public TcpClient(System.Net.IPEndPoint localEP);
    public TcpClient(string hostname, int port);
// Public Instance Properties
    public LingerOption LingerState{set; get; }
    public bool NoDelay{set; get; }
    public int ReceiveBufferSize{set; get; }
    public int ReceiveTimeout{set; get; }
    public int SendBufferSize{set; get; }
    public int SendTimeout{set; get; }
// Protected Instance Properties
    protected bool Active{set; get; }
    protected Socket Client{set; get; }
// Public Instance Methods
    public void Close( );
    public void Connect(System.Net.IPAddress address, int port);
    public void Connect(System.Net.IPEndPoint remoteEP);
    public void Connect(string hostname, int port);
    public NetworkStream GetStream( );
// Protected Instance Methods
    protected virtual void Dispose(bool disposing);
    protected override void Finalize( );
// overrides object
}
```

Returned By

TcpListener.AcceptTcpClient()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TcpListener

CF 1.0

System.Net.Sockets (system.dll)

class

This class provides a server-side abstraction of the sockets API. The `TcpListener` is constructed with a local address and port to which it is automatically bound. A call to `Start()` initiates listening for connection requests. When a request is received, either `AcceptSocket()` or `AcceptTcpClient()` accepts the connection and returns a `Socket` or a `TcpClient` you can use to exchange data with the remote client.

```
public class TcpListener {
// Public Constructors
    public TcpListener(int port);
// obsolete
    public TcpListener(System.Net.IPAddress localaddr, int port);
    public TcpListener(System.Net.IPEndPoint localEP);
// Public Instance Properties
    public EndPoint LocalEndpoint {get; }
// Protected Instance Properties
    protected bool Active {get; }
    protected Socket Server {get; }
// Public Instance Methods
    public Socket AcceptSocket( );
    public TcpClient AcceptTcpClient( );
    public bool Pending( );
    public void Start( );
    public void Stop( );
// Protected Instance Methods
    protected override void Finalize( );
// overrides object
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

UdpClient

CF 1.0, disposable

System.Net.Sockets (system.dll) *class*

This class is used to create UDP client sockets. UDP-based clients transmit messages called datagrams across a connection. Unlike TCP, control data is not sent to ensure the integrity and order of the data (so UDP is faster than TCP, but not as reliable). UDP is often used to broadcast media streams, such as video, and to support multicasting. The `UdpClient` can be constructed with a binding to a local address and port, or it can be constructed given the IP address and port number of the remote server to which it connects.

The `JoinMulticastGroup()` method sets the address of an IP-multicast group to join. `DropMulticastGroup()` drops the client from the group.

```
public class UdpClient : IDisposable {
// Public Constructors
    public UdpClient( );
    public UdpClient(AddressFamily family);
    public UdpClient(int port);
    public UdpClient(int port, AddressFamily family);
    public UdpClient(System.Net.IPEndPoint localEP);
    public UdpClient(string hostname, int port);
// Protected Instance Properties
    protected bool Active{set; get; }
    protected Socket Client{set; get; }
// Public Instance Methods
    public void Close( );
    public void Connect(System.Net.IPAddress addr, int port);
    public void Connect(System.Net.IPEndPoint endPoint);
    public void Connect(string hostname, int port);
    public void DropMulticastGroup(System.Net.IPAddress multicastAddr);
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 35. System.Reflection

`System.Reflection` is the API that exposes the full-fidelity metadata of the .NET environment to the .NET programmer. In short, it permits complete access to compile-time data at runtime. Everything is available, including fields, methods, constructors, properties, delegate types, and events. The reflection API (as exposed by the `System.Reflection` namespace) offers some truly unique capabilities unavailable in other compile-time bound languages such as C++. The closest the average COM programmer has come to using reflection is the `IDispatch` interface and/or type libraries. Reflection, fortunately, is at once both easier to use and far more powerful.

Reflection offers up a number of possible approaches to use. Introspection is the act of using the reflection APIs to discover information about a component assembly (and its constituent types) at runtime without any prior (compile-time) knowledge of it. This approach was first popularized by tools such as Visual Basic and numerous Java IDEs that offered GUI-based construction of visual interfaces. The third-party component was dropped into some well-known location, and the IDE "discovered" it and offered it on a toolbar the next time the IDE was started.

Along similar lines, reflection is often used as part of development tools; for example, the .NET utility *xsd.exe* uses metadata to generate XML Schema documents that correspond to .NET declared types. A .NET programmer could use reflection to generate SQL (Structured Query Language) statements for storing object instances into a relational database, or even into the SQL DDL (Data Definition Language) itself. Other tools could produce remoting proxies, transparently adding the necessary code to marshal and unmarshal parameters and return values across a network connection, even for types that weren't designed to be remoted in the first place.

Lastly, reflection isn't just a read-only view of a type's construction; the reflective APIs in .NET also allow for manipulation of methods and state (although not the rewriting of code-once loaded, a type's methods remain exactly as they were defined). The most prevalent example of this sort of usage of reflection is in the .NET Object Serialization code (in the `System.Runtime.Serialization` namespace). Serialization takes an existing object instance, uses reflection to suck out the object's state, transforms it into a binary representation, and stores that representation (a stream of bytes) to some source, such as a file on disk, a socket, a binary column in a database, and so on. Later, serialization can also take that same stream of bytes and rehydrate the serialized object back into existence.

Careful readers will note that last sentence and wonder, if only for a moment, how it could be possible for code to reach into an object and directly manipulate its state; after all, any object-oriented developer worthy of the name knows to mark all fields as "private," which should make said fields completely inaccessible. The fact is, reflection can violate even these most sacrosanct of boundaries—it can reach in and manipulate any private member it finds—thus it is highly sensitive to any changes in the definition of fields inside of a type.

[Figure 35-1](#) shows the inheritance diagram for this namespace. [Figure 35-2](#) shows the exceptions, delegates, and attributes from this namespace.

Figure 35-1. The System.Reflection namespace





Figure 35-2. Exceptions, delegates, and attributes from System.Reflection



AmbiguousMatchException


CF 1.0, ECMA 1.0,
serializable

System.Reflection (mscorlib.dll) *sealed class*

This exception is thrown when you attempt to bind to a method with the **Binder** and the given criteria matches more than one method; this is the case, for example, when binding against an overloaded method solely by its name.

```
public sealed class AmbiguousMatchException : SystemException {  
    // Public Constructors  
    public AmbiguousMatchException( );  
    public AmbiguousMatchException(string message);  
    public AmbiguousMatchException(string message, Exception inner);  
}
```

Hierarchy



Assembly CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll) *class*

In the .NET environment, assemblies are the fundamental units of development and deployment; although .NET programmer to work with elements as fine-grained as classes or functions, these types must belong to an assembly and be loaded and used. Consequently, the assembly is the core of the component model in .NET.

The **Assembly** type is the Reflection API object representing the assembly. An assembly (either a .DLL or an EXE) consists of one or more modules; most assemblies are in fact single-module assemblies. (Multiple modules are possible, but usually not necessary for most developers' needs. As such, they are not discussed here.) .NET uses the **Assembly** class to discover information about a particular assembly—for example, an assembly's name, the types contained within it, and each module knows the types defined and bound to that module. Thus, for any assembly, you can enumerate each type defined inside that assembly. This is, in fact, what the *WinCV.exe* sample program (located in the *WinCV* subdirectory) does. (The *ILDasm.exe* application provides similar results, but uses unmanaged APIs to view assembly information via Reflection.)

The **Assembly** API can be broken into two collections: those representing operations against a particular **Assembly** instance), and those that work independently of a particular instance—loading an assembly into the CLR.

The instance-specific methods of **Assembly** are, for the most part, self-describing. The properties of **Assembly** are straightforward. **CodeBase** describes the URL from which this assembly was loaded, **EntryPoint** describes the assembly's entry point, if it has one, **Evidence** is the security information regarding this particular assembly, and **GetNameInfo** (name, culture, version info, and public key token) for this assembly. The remaining two properties are **GlobalAssemblyCache** is a simple boolean value indicating whether this assembly was loaded out of the Global Assembly Cache. **Location** describes the location of the manifest file (which may be in a different file if this is a multimodule assembly). In the 1.1 .NET release, a new property, **ImageRuntimeVersion**, returns the version number of the CLR used to load the assembly. Against a 1.0-compiled assembly, it may return illegal strings like "v1.x86ret" or "retail" instead of the 1.0.

Some instance methods of **Assembly** require a bit more in the way of explanation. **GetName()** returns the assembly's name as an **AssemblyName** instance, rather than a string. Because an **Assembly** is also a **System.Type** (such as **AssemblyVersionAttribute** or **AssemblyKeyFileAttribute**), **Assembly** also has the **GetAttribute()** method. In addition, the **IsDefined()** method can be used to find a particular attribute type defined in this assembly. It returns a true/false value, whereas **GetCustomAttributes()** returns the instance(s) of the attribute itself. A list of all assemblies that this assembly references can be found by calling **GetReferencedAssemblies()**.

In addition to code, assemblies can contain arbitrary "resources." (Here the term "resource" means "any data." Resources are contained as **.file** references in the assembly's manifest file and can be discovered from the **GetManifestResourceNames()**. Information about the persistence scheme used for the resources is available from **GetManifestResourceInfo()**. The actual resource itself can be obtained by calling **GetManifestResourceStream()**, which returns a **System.IO.Stream** object containing or pointing to the file's contents. In addition, a list of all files (both manifest and resource files) can be obtained by calling **GetFiles()**, and a particular file can be opened by calling **GetFile()**.

An assembly consists of one or more modules; the list of modules bound to this assembly are available via the **Modules** property. A particular module can be obtained as a **Module** instance by calling **GetModule()** against the assembly. Enumerating all modules until required, **Assembly** also provides the **GetLoadedModules()** to list the modules of this assembly. To load a module into the CLR. Going the other direction, the **LoadModule()** call forces the CLR to load the given module name.

for the usual on-demand loading policy of the CLR. Should a module-load fail for some reason, the CLR signals against the `Assembly` instance's `ModuleResolve` event.

Frequently, a .NET programmer will not be interested in the modules that comprise the assembly, only that at the end, the `Assembly` type has a couple of "shortcut" methods to get the types. `GetTypes()` returns an assembly as an array of `System.Type` references. `GetType()` (or an overload is used) returns a particular `System.Type`, or throws an exception if the type cannot be found. Take note that the parameterless version of `GetType()` from `System.Object`; it returns the `System.Type` reference for `Assembly`, not any types defined in the assembly (the `GetTypes()` call returns a list of all types defined in the assembly, even those declared as private, which normally should not be seen by assembly consumers); to see a list of only the "public" types, call `GetExportedTypes()`.

Once a particular type within the assembly has been located, an instance of that type can be created by using the system activator (see `System.Activator`) to create an instance of that type and hand it back as an object. For example, calling `object o = typeof(Object).Assembly.CreateInstance("DateTime");` is a roundabout way to get a `System.DateTime`; the `typeof(Object)` returns the `System.Type` for `System.Object`. That type lives in the `mscorlib.dll` assembly. Calling `CreateInstance("DateTime")` succeeds because `DateTime` is defined within that assembly. .NET uses this method when building a container application (such as ASP.NET) that will be creating instances of objects.

The `Assembly` type also contains a number of static methods for use in referencing assemblies as a collection. `GetAssembly()` call returns the `Assembly` in which a particular `Type` is defined. (Knowing this, we could write a method to read `object o = Assembly.GetAssembly(typeof(object)).CreateInstance("DateTime");` longer.) Likewise, the `GetExecutingAssembly()` returns the assembly in which the current code is executing. `CallingAssembly` returns the assembly whose code called the methods in this assembly. (These methods by themselves do not implement the idea of walking the call-stack, as Code Access Security does, is considered.)

However, the two most important static methods on the `Assembly` class by far are `Load()` and `LoadFrom()`. `LoadFrom()` is the simpler of the two, taking a filename and loading the assembly into the CLR, no questions asked. `Load()` goes through the assembly-load algorithm and checks the private proxy cache before giving up on finding the assembly. (Note that if an assembly-load request fails, the appropriate `AppDomain` instance is signaled.) In addition, starting with the 1.1 release, these two are joined by a new `LoadFromAssemblyPath()` method, which will load an assembly specified by a file location passed as a string.

```
public class Assembly : System.Security.IEvidenceFactory, ICustomAttributeProvider,
    System.Runtime.Serialization.ISerializable {
// Public Instance Properties
    public virtual string CodeBase {get; }
    public virtual MethodInfo EntryPoint {get; }
    public virtual string EscapedCodeBase {get; }
    public virtual Evidence Evidence {get; }
// implements System.Security.IEvidenceFactory
    public virtual string FullName {get; }
    public bool GlobalAssemblyCache {get; }
    public virtual string ImageRuntimeVersion {get; }
    public virtual string Location {get; }
// Public Static Methods
    public static string CreateQualifiedName(string assemblyName, string typeName);
    public static Assembly GetAssembly(Type type);
    public static Assembly GetCallingAssembly();
    public static Assembly GetEntryAssembly();
    public static Assembly GetExecutingAssembly();
    public static Assembly Load(AssemblyName assemblyRef);
    public static Assembly Load(AssemblyName assemblyRef, System.Security.Policy.Evidence evidence);
}
```

```

public static Assembly Load(byte[] rawAssembly);
public static Assembly Load(byte[] rawAssembly, byte[] rawSymbolStore);
public static Assembly Load(byte[] rawAssembly, byte[] rawSymbolStore,
    System.Security.Policy.Evidence securityEvidence);
public static Assembly Load(string assemblyString);
public static Assembly Load(string assemblyString, System.Security.Policy.Evidence a
public static Assembly LoadFile(string path);
public static Assembly LoadFile(string path, System.Security.Policy.Evidence securit
public static Assembly LoadFrom(string assemblyFile);
public static Assembly LoadFrom(string assemblyFile, System.Security.Policy.Evidence
public static Assembly LoadFrom(string assemblyFile, System.Security.Policy.Evidence
    byte[] hashValue, System.Configuration.Assemblies.AssemblyHashAlgorithm hashAlg
public static Assembly LoadWithPartialName(string partialName);
public static Assembly LoadWithPartialName(string partialName, System.Security.Polic
// Public Instance Methods
public object CreateInstance(string typeName);
public object CreateInstance(string typeName, bool ignoreCase);
public object CreateInstance(string typeName, bool ignoreCase, BindingFlags bindingA
    Binder binder, object[] args, System.Globalization.CultureInfo culture, object[]
public virtual object[] GetCustomAttributes(bool inherit);
// implements ICustomAttributeProvider
public virtual object[] GetCustomAttributes(Type attributeType, bool inherit)
// implements ICustomAttributeProvider
public virtual Type[] GetExportedTypes();
public virtual FileStream GetFile(string name);
public virtual FileStream[] GetFiles();
public virtual FileStream[] GetFiles(bool getResourceModules);
public Module[] GetLoadedModules();
public Module[] GetLoadedModules(bool getResourceModules);
public virtual ManifestResourceInfo GetManifestResourceInfo(string resourceName);
public virtual string[] GetManifestResourceNames();
public virtual Stream GetManifestResourceStream(string name);
public virtual Stream GetManifestResourceStream(Type type, string name);
public Module GetModule(string name);
public Module[] GetModules();
public Module[] GetModules(bool getResourceModules);
public virtual AssemblyName GetName();
public virtual AssemblyName GetName(bool copiedName);
public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
    System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
public AssemblyName[] GetReferencedAssemblies();
public Assembly GetSatelliteAssembly(System.Globalization.CultureInfo culture);
public Assembly GetSatelliteAssembly(System.Globalization.CultureInfo culture, Versi
public virtual Type GetType(string name);
public virtual Type GetType(string name, bool throwOnError);
public Type GetType(string name, bool throwOnError, bool ignoreCase);
public virtual Type[] GetTypes();
public virtual bool IsDefined(Type attributeType, bool inherit);

```

```
// implements ICustomAttributeProvider
public Module LoadModule(string moduleName, byte[ ] rawModule);
public Module LoadModule(string moduleName, byte[ ] rawModule, byte[ ] rawSymbolStore);
public override string ToString( );
// overrides object
// Events
public event ModuleResolveEventHandler ModuleResolve;
}
```

Subclasses

System.Reflection.Emit.AssemblyBuilder

Returned By

System.AppDomain.{GetAssemblies(), Load()}, System.AssemblyLoadEventArgs.LoadedAssembly, ManifestResourceInfo.ReferencedAssembly, Module.Assembly, System.ResolveEventHandler.{Error, ErrorEventArgs}
System.Type.Assembly

Passed To

Multiple types

[Team LiB]

AssemblyAlgorithmIdAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

The assembly manifest contains a hash of all of the files in the assembly. This attribute allows you to specify which hashing algorithm is used to hash these files.

```
public sealed class AssemblyAlgorithmIdAttribute : Attribute {  
    // Public Constructors  
    public AssemblyAlgorithmIdAttribute(System.Configuration.Assemblies.AssemblyHashAlgorithm algorithmId);  
    public AssemblyAlgorithmIdAttribute(uint algorithmId);  
    // Public Instance Properties  
    public uint AlgorithmId { get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyAlgorithmIdAttribute

Valid On

Assembly

AssemblyCompanyAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute is applied on an assembly that allows you to specify the company that created the assembly.

```
public sealed class AssemblyCompanyAttribute : Attribute {  
    // Public Constructors  
    public AssemblyCompanyAttribute(string company);  
    // Public Instance Properties  
    public string Company {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyCompanyAttribute

Valid On

Assembly

AssemblyConfigurationAttribute CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute allows you to specify a configuration for the assembly (such as debug, release, beta, etc.).

```
public sealed class AssemblyConfigurationAttribute : Attribute {  
    // Public Constructors  
    public AssemblyConfigurationAttribute(string configuration);  
    // Public Instance Properties  
    public string Configuration {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyConfigurationAttribute

Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyCopyrightAttribute CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute string contains copyright information.

```
public sealed class AssemblyCopyrightAttribute : Attribute {  
    // Public Constructors  
    public AssemblyCopyrightAttribute(string copyright);  
    // Public Instance Properties  
    public string Copyright{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyCopyrightAttribute

Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyCultureAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute specifies the supported culture of an assembly.

```
public sealed class AssemblyCultureAttribute : Attribute {  
    // Public Constructors  
    public AssemblyCultureAttribute(string culture);  
    // Public Instance Properties  
    public string Culture {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyCultureAttribute

Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyDefaultAliasAttribute CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute specifies a friendly name for an assembly. This is useful when assemblies have cryptic names such as GUIDs, as COM components do.

```
public sealed class AssemblyDefaultAliasAttribute : Attribute {  
    // Public Constructors  
    public AssemblyDefaultAliasAttribute(string defaultAlias);  
    // Public Instance Properties  
    public string DefaultAlias{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyDefaultAliasAttribute

Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyDelaySignAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

When an assembly designer does not have access to a key-pair to sign a component, this attribute reserves space in the manifest to be filled by a signing utility. The framework's `sn.exe` utility has a command-line switch (`-R` or `-Rc`) just for this purpose.

```
public sealed class AssemblyDelaySignAttribute : Attribute {  
    // Public Constructors  
    public AssemblyDelaySignAttribute(bool delaySign);  
    // Public Instance Properties  
    public bool DelaySign {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyDelaySignAttribute

Valid On

Assembly

AssemblyDescriptionAttribute CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute allows a description to be stored with an assembly.

```
public sealed class AssemblyDescriptionAttribute : Attribute {  
    // Public Constructors  
    public AssemblyDescriptionAttribute(string description);  
    // Public Instance Properties  
    public string Description{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyDescriptionAttribute

Valid On

Assembly

AssemblyFileVersionAttribute

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute stores a given version number in the assembly's Win32 VERSIONINFO resource. This is not the same as the assembly's version (given by the [AssemblyVersionAttribute](#)).

```
public sealed class AssemblyFileVersionAttribute : Attribute {  
    // Public Constructors  
    public AssemblyFileVersionAttribute(string version);  
    // Public Instance Properties  
    public string Version{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyFileVersionAttribute

Valid On

Assembly

AssemblyFlagsAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

Use this attribute to specify the side-by-side execution behavior of this assembly. The `flags` parameter may take one of the following values: `0x0000` (side-by-side compatible), `0x0010` (side-by-side operation is prohibited within the same application domain), `0x0020` (side-by-side operation prohibited within same process), or `0x0030` (side-by-side operation prohibited within the same machine boundary).

```
public sealed class AssemblyFlagsAttribute : Attribute {  
    // Public Constructors  
    public AssemblyFlagsAttribute(int assemblyFlags);  
    public AssemblyFlagsAttribute(uint flags);  
    // Public Instance Properties  
    public int AssemblyFlags {get; }  
    public uint Flags {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyFlagsAttribute

Valid On

Assembly

AssemblyInformationalVersionAttribute

CF
1.0

System.Reflection (mscorlib.dll)

sealed class

This custom attribute allows a version number to be stored. This stored version is purely for documentation and is not used by the runtime.

```
public sealed class AssemblyInformationalVersionAttribute : Attribute {  
    // Public Constructors  
    public AssemblyInformationalVersionAttribute(string informationalVersion);  
    // Public Instance Properties  
    public string InformationalVersion {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyInformationalVersionAttribute

Valid On

Assembly

AssemblyKeyFileAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

To create a strong-named assembly, use this attribute, specifying a file containing a key-pair. Alternatively, you could use an [AssemblyDelaySignAttribute](#) or an [AssemblyKeyNameAttribute](#).

```
public sealed class AssemblyKeyFileAttribute : Attribute {  
    // Public Constructors  
    public AssemblyKeyFileAttribute(string keyFile);  
    // Public Instance Properties  
    public string KeyFile{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyKeyFileAttribute

Valid On

Assembly

AssemblyKeyNameAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This attribute serves the same purpose as an `AssemblyKeyFileAttribute`, but allows you to specify a key container instead of a file.

```
public sealed class AssemblyKeyNameAttribute : Attribute {  
    // Public Constructors  
    public AssemblyKeyNameAttribute(string keyName);  
    // Public Instance Properties  
    public string KeyName {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyKeyNameAttribute

Valid On

Assembly

AssemblyName

CF 1.0, serializable

System.Reflection (mscorlib.dll) *sealed class*

This class represents an assembly's fully qualified name, which makes it unique. An assembly's identity consists of a simple name (the **Name** property), supported culture (**CultureInfo**), version number, and key pair. The version number itself has four parts: major version, minor version, build number, and revision number. The **Flags** property allows you to set the flags for an assembly (see the **AssemblyNameFlags** enumeration). Use **HashAlgorithm** to access the hash algorithm used with the manifest to verify that the files of an assembly are correct. **VersionCompatibility** is a **System.Configuration.Assemblies.AssemblyVersionCompatibility** enumeration, which allows specification of the compatibility between versions.

Both **FullName** and **ToString()** return a comma-delimited string formatted, such as **Name** , **Culture** = **CultureInfo** , **Version** = **Version Number** , **SN** = **StrongName** , **PK** = **Public Key Token** . Any of the parameters except **Name** are optional. **SetPublicKey()** and **SetPublicKeyToken()** allow you to specify public key for an originator or the strong name, respectively, and the complementary **Get** methods allow you to retrieve the same information.

```
public sealed class AssemblyName : ICloneable, System.Runtime.Serialization.ISerializable,
    System.Runtime.Serialization.IDeserializationCallback {
// Public Constructors
    public AssemblyName( );
// Public Instance Properties
    public string CodeBase{set; get; }
    public CultureInfo CultureInfo{set; get; }
    public string EscapedCodeBase{get; }
    public AssemblyNameFlags Flags{set; get; }
    public string FullName{get; }
    public AssemblyHashAlgorithm HashAlgorithm{set; get; }
    public StrongNameKeyPair KeyPair{set; get; }
    public string Name{set; get; }
    public Version Version{set; get; }
    public AssemblyVersionCompatibility VersionCompatibility{set; get; }
// Public Static Methods
    public static AssemblyName GetAssemblyName(string assemblyFile);
// Public Instance Methods
    public object Clone( );
// implements ICloneable
    public void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
    public byte[] GetPublicKey( );
    public byte[] GetPublicKeyToken( );
    public void OnDeserialization(object sender);
// implements System.Runtime.Serialization.IDeserializationCallback
```

```
public void SetPublicKey(byte[] publicKey);  
public void SetPublicKeyToken(byte[] publicKeyToken);  
public override string ToString( );  
// overrides object  
}
```

Returned By

```
Assembly.{GetName( ), GetReferencedAssemblies( )} , AssemblyNameProxy.GetAssemblyName( )
```

Passed To

```
System.AppDomain.{DefineDynamicAssembly( ), Load( )} , Assembly.Load( ) ,  
System.Text.RegularExpressions.Regex.CompileToAssembly( )
```

[Team LiB]

AssemblyNameFlags CF 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

This enumeration represents the possible flags for an `AssemblyName`. `AssemblyName.Flags` can either be set to `None` or `PublicKey`. `PublicKey` specifies that the originator is fully given by the public key, rather than by a token. `Retargetable` indicates that the assembly can be retargeted at runtime to an assembly from a different publisher, meaning we can "alias" the assembly to a third-party assembly (that, implicitly, would have a different public key token than this one).

```
public enum AssemblyNameFlags {  
    None = 0x00000000 ,  
    PublicKey = 0x00000001 ,  
    Retargetable = 0x00000100  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `AssemblyNameFlags`

Returned By

`AssemblyName.Flags`

Passed To

`AssemblyName.Flags`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyNameProxy marshal by reference

System.Reflection (mscorlib.dll) *class*

This class is a remotable wrapper around `AssemblyName`. To access the underlying `AssemblyName`, call `AssemblyName.GetAssemblyName()`.

```
public class AssemblyNameProxy : MarshalByRefObject {  
    // Public Constructors  
    public AssemblyNameProxy( );  
    // Public Instance Methods  
    public AssemblyName GetAssemblyName(string assemblyFile);  
}
```

Hierarchy

System.Object → System.MarshalByRefObject → AssemblyNameProxy

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyProductAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This class is a custom attribute for the product name.

```
public sealed class AssemblyProductAttribute : Attribute {  
    // Public Constructors  
    public AssemblyProductAttribute(string product);  
    // Public Instance Properties  
    public string Product{get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyProductAttribute

Valid On

Assembly

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

AssemblyTitleAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This class is a custom attribute for an assembly title.

```
public sealed class AssemblyTitle : Attribute {  
    // Public Constructors  
    public AssemblyTitle(string title);  
    // Public Instance Properties  
    public string Title {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyTitle

Valid On

Assembly

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyTrademarkAttribute

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

This custom attribute is used to add a trademark.

```
public sealed class AssemblyTrademarkAttribute : Attribute {  
    // Public Constructors  
    public AssemblyTrademarkAttribute(string trademark);  
    // Public Instance Properties  
    public string Trademark {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyTrademarkAttribute

Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyVersionAttribute

CF 1.0

System.Reflection (mscorlib.dll)

sealed class

This attribute is the version of the assembly. This version is used by the framework to check compatibility and determine if side-by-side execution is needed.

```
public sealed class AssemblyVersionAttribute : Attribute {  
    // Public Constructors  
    public AssemblyVersionAttribute(string version);  
    // Public Instance Properties  
    public string Version {get; }  
}
```

Hierarchy

System.Object → System.Attribute → AssemblyVersionAttribute

Valid On

Assembly

Binder CF 1.0, ECMA 1.0, serializable

System.Reflection
(mscorlib.dll)

abstract class

This type is used by the .NET runtime for method argument conversion. It is responsible for such things as pass a **short** to a method that takes a **long** parameter. If you need to override .NET's default conversion (however, most programmers will never need to do this). For more details, see the .NET Framework SDK

```
public abstract class Binder {
// Protected Constructors
    protected Binder( );
// Public Instance Methods
    public abstract FieldInfo BindToField(BindingFlags bindingAttr, FieldInfo[ ] match,
        object value, System.Globalization.CultureInfo culture);
    public abstract MethodBase BindToMethod(BindingFlags
        bindingAttr,
        MethodBase[ ] match, ref object[ ] args, ParameterModifier[ ] modifiers, System.
        string[ ] names, out object state);
    public abstract object ChangeType(object value, Type type, System.Globalization.Cult
    public abstract void ReorderArgumentArray(ref object[ ] args, object state);
    public abstract MethodBase SelectMethod(BindingFlags bindingAttr, MethodBase[ ] matc.
        Type[ ] types, ParameterModifier[ ] modifiers);
    public abstract PropertyInfo SelectProperty(BindingFlags bindingAttr, PropertyInfo[
        Type returnType, Type[ ] indexes, ParameterModifier[ ] modifiers);
}
```

Returned By

System.Type.DefaultBinder

Passed To

Multiple types

BindingFlags

CF 1.0, ECMA 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

This enumeration specifies how reflection searches for members. It is used by many types in the `System` and `System.Reflection` namespaces. The following list describes each enumeration member:

- `CreateInstance`

Tells reflection to call a constructor that matches the specified arguments. If a member name is supplied, it is ignored.
- `DeclaredOnly`

Specifies to search only from the declared methods, and not from the inherited ones.
- `Default`

Specifies that all the default search parameters should be used.
- `ExactBinding`

Ensures that arguments must match exactly (no downcasting is performed).
- `Static`

Allows static members to match.
- `FlattenHierarchy`

Allows matching of static methods from inherited classes.
- `GetField`

Specify that the value of a specified field or property should be returned.
- `GetProperty`
- `SetField`
- `SetProperty`
- `IgnoreCase`

Allow you to set fields and properties.
- `IgnoreReturn`

Causes the search to be case-insensitive.
- `Public`

Tells the search to ignore the return value. This is used primarily for COM Interop.
- `Instance`

Allows public members to be searched.

Specifies that instance members must be searched.

`NonPublic`

Allows nonpublic members to be searched.

`InvokeMethod`

Says that a method that is not a constructor should be invoked.

`OptionalParamBinding`

Allows matching based on the number of parameters for methods with optional arguments.

`SuppressChangeType`

Specifies that the CLR should not perform type coercions to invoke a method (as of this writing, `SuppressChangeType` is unimplemented).

`PutDispProperty`

`PutRefDispProperty`

Allow you to call the COM accessors. If the put method expects a COM intrinsic type, use `PutDispProperty`; if the put method expects a COM object, use `PutRefDispProperty`.

```
public enum BindingFlags {
    Default = 0x00000000 ,
    IgnoreCase = 0x00000001 ,
    DeclaredOnly = 0x00000002 ,
    Instance = 0x00000004 ,
    Static = 0x00000008 ,
    Public = 0x00000010 ,
    NonPublic = 0x00000020 ,
    FlattenHierarchy = 0x00000040 ,
    InvokeMethod = 0x00000100 ,
    CreateInstance = 0x00000200 ,
    GetField = 0x00000400 ,
    SetField = 0x00000800 ,
    GetProperty = 0x00001000 ,
    SetProperty = 0x00002000 ,
    PutDispProperty = 0x00004000 ,
    PutRefDispProperty = 0x00008000 ,
    ExactBinding = 0x00010000 ,
    SuppressChangeType = 0x00020000 ,
    OptionalParamBinding = 0x00040000 ,
    IgnoreReturn = 0x01000000
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `BindingFlags`

Passed To

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#)

[NEXT ▶](#)

CallingConventions CF 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

Calling conventions are the rules that govern the semantics of how method arguments and return values are passed. They also specify which registers to use, and designate what this method does with the stack. The following list describes each enumeration member:

Standard

Designates the default CLR conventions.

VarArgs

Allows variable arguments.

Any

Allows either convention.

HasThis

Passes the target method the `this` (or `Me`) reference as the first argument and cannot be used for static methods.

ExplicitThis

Represents a call to a nonstatic method and is a function pointer (for delegates). If `ExplicitThis` is set, `HasThis` must also be set.

```
public enum CallingConventions {  
    Standard = 0x00000001 ,  
    VarArgs = 0x00000002 ,  
    Any = 0x00000003 ,  
    HasThis = 0x00000020 ,  
    ExplicitThis = 0x00000040  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → CallingConventions

Returned By

MethodBase.CallingConvention

Passed To

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ConstructorInfo

CF 1.0, ECMA 1.0,
serializable

System.Reflection (mscorlib.dll)

abstract class

This class is an implementation of `MethodBase` explicitly for constructors. It adds the two static read-only properties `ConstructorName` and `TypeConstructorName`, which are defined in metadata as methods of name `.ctor` and `.cctor`, respectively. (Recall that a "type constructor" is executed as soon as the type loaded into the CLR; hence the name "class constructor"-`cctor` for short.)

```
public abstract class ConstructorInfo : MethodBase {
// Protected Constructors
    protected ConstructorInfo( );
// Public Static Fields
    public static readonly string ConstructorName;
// =.ctor
    public static readonly string TypeConstructorName;
// =.cctor
// Public Instance Properties
    public override MemberTypes MemberType{get; }
// overrides MemberInfo
// Public Instance Methods
    public abstract object Invoke(BindingFlags invokeAttr, Binder binder, object[ ] parameters,
        System.Globalization.CultureInfo culture);
    public object Invoke(object[ ] parameters);
}
```

Hierarchy

System.Object → MemberInfo(ICustomAttributeProvider) → MethodBase → ConstructorInfo

Subclasses

System.Reflection.Emit.ConstructorBuilder

Returned By

System.Type.{GetConstructor(), GetConstructorImpl(), GetConstructors(), TypeInitializ

Passed To

Multiple types

[Team LiB]

◀ PREVIOUS

NEXT ▶

CustomAttributeFormatException

CF 1.0,
serializable

System.Reflection (mscorlib.dll) *class*

This exception is thrown when the binary format of an attribute of a type cannot be read. This can occur custom attributes and types are created at runtime.

```
public class CustomAttributeFormatException : FormatException {  
    // Public Constructors  
    public CustomAttributeFormatException( );  
    public CustomAttributeFormatException(string message);  
    public CustomAttributeFormatException(string message, Exception inner);  
    // Protected Constructors  
    protected CustomAttributeFormatException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy

System.Object → System.Exception(System.Runtime.Serialization.ISerializable) →
System.SystemException → System.FormatException → CustomAttributeFormatException

DefaultMemberAttribute

CF 1.0, ECMA 1.0,
serializable

System.Reflection (mscorlib.dll) *sealed class*

This attribute allows you to specify the default member of a class. It corresponds to the VB.NET `Default` keyword. C# does not permit the use of default members as part of the language, although other .NET languages (most notably VB.NET) do.

```
public sealed class DefaultMemberAttribute : Attribute {  
    // Public Constructors  
    public DefaultMemberAttribute(string memberName);  
    // Public Instance Properties  
    public string MemberName {get; }  
}
```

Hierarchy

System.Object → System.Attribute → DefaultMemberAttribute

Valid On

Class, Struct, Interface

EventAttributes

CF 1.0, ECMA 1.0,
serializable, flag

System.Reflection (mscorlib.dll) *enum*

This is an enumeration of the attributes that can be placed on events. **None** specifies no attributes. **ReservedMask** is a reserved flag for use only by the runtime. **SpecialName** indicates that the event is described by the name. **RTSpecialName** is similar, but states that the runtime should check the encoding of the name.

```
public enum EventAttributes {  
    None = 0x00000000 ,  
    SpecialName = 0x00000200 ,  
    ReservedMask = 0x00000400 ,  
    RTSpecialName = 0x00000400  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → EventAttributes

Returned By

EventInfo.Attributes

Passed To

System.Reflection.Emit.TypeBuilder.DefineEvent()

EventInfo

CF 1.0, ECMA 1.0

System.Reflection (mscorlib.dll)

abstract class

This class allows you to access events through reflection and is, itself, an implementation of `MemberInfo`. `Attributes` gets the `EventAttributes` object, and `EventHandlerType` gets the `System.Type` of the event-handler delegate for the event. `IsMulticast` returns true if the event is multicast, and `IsSpecialName` indicates whether this has special meaning. `AddEventHandler()` adds the passed delegate to the event handler, and `GetAddMethod()`, `GetRaiseMethod()`, and `GetRemoveMethod()` return a `MethodInfo` for the method used to add an event handler, raise an event, or remove an event handler, respectively.

```
public abstract class EventInfo : MemberInfo {
// Protected Constructors
    protected EventInfo( );
// Public Instance Properties
    public abstract EventAttributes Attributes{get; }
    public Type EventHandlerType{get; }
    public bool IsMulticast{get; }
    public bool IsSpecialName{get; }
    public override MemberTypes MemberType{get; }
// overrides MemberInfo
// Public Instance Methods
    public void AddEventHandler(object target, Delegate handler);
    public MethodInfo GetAddMethod( );
    public abstract MethodInfo GetAddMethod(bool nonPublic);
    public MethodInfo GetRaiseMethod( );
    public abstract MethodInfo GetRaiseMethod(bool nonPublic);
    public MethodInfo GetRemoveMethod( );
    public abstract MethodInfo GetRemoveMethod(bool nonPublic);
    public void RemoveEventHandler(object target, Delegate handler);
}
```

Hierarchy

System.Object → MemberInfo(ICustomAttributeProvider) → EventInfo

Returned By

System.Type.{GetEvent(), GetEvents()}


FieldAttributes CF 1.0, ECMA 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

This is an enumeration of the attributes that can be specified on a field. **Assembly** means that the field is internal (that is, private to the assembly); **Family** indicates that the field is protected. **Private**, **Public**, and **Static** are self-explanatory. If the field has a default value, **HasDefault** is marked; if a field is constant, **Literal** is marked. **InitOnly** indicates that the field can only be set on object initialization. To exclude a field from being serialized, **NotSerialized** should be asserted. **HasFieldMarshal** specifies that the field has special marshaling information.

```
public enum FieldAttributes {
    PrivateScope = 0x00000000 ,
    Private = 0x00000001 ,
    FamANDAssem = 0x00000002 ,
    Assembly = 0x00000003 ,
    Family = 0x00000004 ,
    FamORAssem = 0x00000005 ,
    Public = 0x00000006 ,
    FieldAccessMask = 0x00000007 ,
    Static = 0x00000010 ,
    InitOnly = 0x00000020 ,
    Literal = 0x00000040 ,
    NotSerialized = 0x00000080 ,
    HasFieldRVA = 0x00000100 ,
    SpecialName = 0x00000200 ,
    RTSpecialName = 0x00000400 ,
    HasFieldMarshal = 0x00001000 ,
    PinvokeImpl = 0x00002000 ,
    HasDefault = 0x00008000 ,
    ReservedMask = 0x00009500
}
```

Hierarchy



Returned By

FieldInfo.Attributes

Passed To

```
System.Reflection.Emit.ModuleBuilder.{DefineInitializedData( ),
DefineUninitializedData( )}, System.Reflection.Emit.TypeBuilder.{DefineField( ),
DefineInitializedData( ), DefineUninitializedData( )}
```

[\[Team LiB \]](#)

FieldInfo

CF 1.0, ECMA 1.0, serializable

System.Reflection

(mscorlib.dll)

abstract class

This class is an implementation of `MemberInfo` and allows access to an instance field. Note that, like all reflection objects, the `FieldInfo` instance refers to the metadata concept of the field within the type, not a particular instance of that type. (This is important when working with or manipulating the value of object instance fields.)

`IsAssembly`, `IsFamily`, `IsFamilyAndAssembly`, `IsFamilyOrAssembly`, `IsPublic`, and `IsPrivate` all check the visibility of the field. `FieldType` returns the declared type of this field. `FieldHandle` is a `System.RuntimeFieldHandle`. Use `Attributes` to retrieve the attributes. To see if the `FieldInfo` has `NotSerialized` or `PinvokeImplFieldAttributes` set, inspect the `IsNotSerialized` and `IsPinvokeImpl`. If the field is static, `IsStatic` is true. The `Set` and `Get` methods allow you set the values, and the ones with their name take a typed reference as opposed to an object.

```
public abstract class FieldInfo : MemberInfo {
    // Protected Constructors
    protected FieldInfo( );

    // Public Instance Properties
    public abstract FieldAttributes Attributes {get; }
    public abstract RuntimeFieldHandle FieldHandle {get; }
    public abstract Type FieldType {get; }
    public bool IsAssembly {get; }
    public bool IsFamily {get; }
    public bool IsFamilyAndAssembly {get; }
    public bool IsFamilyOrAssembly {get; }
    public bool IsInitOnly {get; }
    public bool IsLiteral {get; }
    public bool IsNotSerialized {get; }
    public bool IsPinvokeImpl {get; }
    public bool IsPrivate {get; }
    public bool IsPublic {get; }
    public bool IsSpecialName {get; }
    public bool IsStatic {get; }
    public override MemberTypes MemberType {get; }

    // overrides MemberInfo
    // Public Static Methods
    public static FieldInfo GetFieldFromHandle(RuntimeFieldHandle handle);

    // Public Instance Methods
    public abstract object GetValue(object obj);
    public virtual object GetValueDirect(TypedReference obj);
    public void SetValue(object obj, object value);
    public abstract void SetValue(object obj, object value, BindingFlags invokeAttr, Bin
```



```
        System.Globalization.CultureInfo culture);  
    public virtual void SetValueDirect(TypedReference obj, object value);  
}
```

Hierarchy

```
System.Object → MemberInfo(ICustomAttributeProvider) → FieldInfo
```

Subclasses

```
System.Reflection.Emit.FieldBuilder
```

Returned By

```
Binder.BindToField( ), IReflect.{GetField( ), GetFields( )}, Module.{GetField( ), GetFie  
System.Runtime.InteropServices.Expando.IExpando.AddField( ), System.Type.{GetField( ), (
```

Passed To

```
Binder.BindToField( ), System.Reflection.Emit.CustomAttributeBuilder.CustomAttributeBuil  
System.Reflection.Emit.ILGenerator.{Emit( ), EmitWriteLine( )},  
System.Reflection.Emit.ModuleBuilder.GetFieldToken( )
```

ICustomAttributeProvider

CF 1.0

System.Reflection (mscorlib.dll) *interface*

This interface is implemented if an object supports custom attributes. `GetCustomAttributes()` returns the custom attributes, and `IsDefined()` returns true if an attribute of a passed `System.Type` is defined on this member.

```
public interface ICustomAttributeProvider {  
    // Public Instance Methods  
    public object[ ] GetCustomAttributes(bool inherit);  
    public object[ ] GetCustomAttributes(Type attributeType, bool inherit);  
    public bool IsDefined(Type attributeType, bool inherit);  
}
```

Implemented By

`Assembly`, `MemberInfo`, `Module`, `ParameterInfo`

Returned By

`MethodInfo.ReturnTypeCustomAttributes`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

InterfaceMapping

System.Reflection (mscorlib.dll) *struct*

This value type allows you to retrieve information about interfaces. To access the **Type** for an interface, use **InterfaceType**. **TargetType** contains the **Type** of the implementing class. Similarly, **InterfaceMethods** and **TargetMethods** return the methods of the interface and the implementing class, respectively.

```
public struct InterfaceMapping {  
    // Public Instance Fields  
    public MethodInfo[ ] InterfaceMethods;  
    public Type InterfaceType;  
    public MethodInfo[ ] TargetMethods;  
    public Type TargetType;  
}
```

Hierarchy

System.Object → System.ValueType → InterfaceMapping

Returned By

System.Type.GetInterfaceMap()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)


InvalidFilterCriteriaException serializable

System.Reflection (mscorlib.dll) *class*

This exception is thrown when the filter criteria passed to `System.Type.FindMembers()` is invalid.

```
public class InvalidFilterCriteriaException : ApplicationException {  
    // Public Constructors  
    public InvalidFilterCriteriaException( );  
    public InvalidFilterCriteriaException(string message);  
    public InvalidFilterCriteriaException(string message, Exception inner);  
    // Protected Constructors  
    protected InvalidFilterCriteriaException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



I Reflect

System.Reflection (mscorlib.dll) *interface*

This interface defines how types are reflected and provides all the relevant information about the members (methods, fields, and properties). The **Get** methods allow access to these members. The methods **GetField**, **GetMethod**(), **GetProperty**(), and **GetMember**() return single members of the specified type by name. The methods **GetFields**(), **GetMethods**(), **GetProperties**(), and **GetMembers**() return all of the members contained by the class.

```
public interface IReflect {
    // Public Instance Properties
    public Type UnderlyingSystemType {get; }
    // Public Instance Methods
    public FieldInfo GetField(string name, BindingFlags bindingAttr);
    public FieldInfo[] GetFields(BindingFlags bindingAttr);
    public MemberInfo[] GetMember(string name, BindingFlags bindingAttr);
    public MemberInfo[] GetMembers(BindingFlags bindingAttr);
    public MethodInfo GetMethod(string name, BindingFlags bindingAttr);
    public MethodInfo GetMethod(string name, BindingFlags bindingAttr, Binder binder,
        Type[] types, ParameterModifier[] modifiers);
    public MethodInfo[] GetMethods(BindingFlags bindingAttr);
    public PropertyInfo[] GetProperties(BindingFlags bindingAttr);
    public PropertyInfo GetProperty(string name, BindingFlags bindingAttr);
    public PropertyInfo GetProperty(string name, BindingFlags bindingAttr, Binder binder,
        Type returnType, Type[] types, ParameterModifier[] modifiers);
    public object InvokeMember(string name, BindingFlags invokeAttr, Binder binder, object[] args,
        ParameterModifier[] modifiers, System.Globalization.CultureInfo culture, string[] namedParameters);
}
```

Implemented By

System.Type , System.Runtime.InteropServices.Expando.IExpando

ManifestResourceInfo

System.Reflection (mscorlib.dll) *class*

This class represents a resource from an assembly manifest. As assemblies can span multiple files, this resource represents one file from an assembly. The `FileName` returns the name of the file containing the resource if it is not the same as the file containing the manifest. `ResourceLocation` allows you to inspect the `ResourceLocation` enumeration for this resource, telling you whether the resource is contained in the same file as the manifest. `ReferencedAssembly` returns the `Assembly` object representing the specified assembly.

```
public class ManifestResourceInfo {  
    // Public Instance Properties  
    public virtual string FileName {get; }  
    public virtual Assembly ReferencedAssembly {get; }  
    public virtual ResourceLocation ResourceLocation {get; }  
}
```

Returned By

```
Assembly.GetManifestResourceInfo( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MemberFilter

serializable

System.Reflection (mscorlib.dll) *delegate*

This delegate defines a function that is used to filter an array of `MemberInfo` objects. This method is run for each `MemberInfo` and should return true to include the `MemberInfo`. The second parameter, `filterCriteria`, is an arbitrary argument that you may specify to be passed to the filter.

This delegate is used from the `System.Type.FindMembers()` method and is designed to allow for high-level "searches" of a type's members (fields, methods, properties, and so on) without having to code the actual looping logic itself.

```
public delegate bool MemberFilter(MemberInfo m, object filterCriteria);
```

Passed To

```
System.Type.FindMembers( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MemberInfo CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll)

abstract class

This class is the base type for all reflective types defined in the .NET environment; it defines the basic data associated with any member (field, method, property, event, nested type) of a given type. Note that even `System.Type` itself inherits from this class.

By itself, `MemberInfo` is a fairly simple type. It consists of four properties: `DeclaringType` (a reference to the `System.Type` in which this member was declared, which might be a base type to the class being reflected over), `MemberType` (an enumeration describing the type of the member), `Name`, and `ReflectedType` (the `System.Type` instance from which this `MemberInfo` object was received in the first place). `MemberInfo` also consists of two methods, `GetCustomAttributes()` and `IsDefined()`, both of which deal with any custom attributes defined on this member.

```
public abstract class MemberInfo : ICustomAttributeProvider {
    // Protected Constructors
    protected MemberInfo( );
    // Public Instance Properties
    public abstract Type DeclaringType {get; }
    public abstract MemberTypes MemberType {get; }
    public abstract string Name {get; }
    public abstract Type ReflectedType {get; }
    // Public Instance Methods
    public abstract object[ ] GetCustomAttributes( bool inherit);
    // implements ICustomAttributeProvider
    public abstract object[ ] GetCustomAttributes(Type attributeType, bool inherit)
    // implements ICustomAttributeProvider
    public abstract bool IsDefined(Type attributeType, bool inherit)
    // implements ICustomAttributeProvider
}
```

Subclasses

EventInfo, FieldInfo, MethodBase, PropertyInfo, System.Type

Returned By

```
IRectect.{GetMember( ), GetMembers( )}, ParameterInfo.Member,
System.Runtime.InteropServices.Marshal.GetMethodInfoForComSlot( ),
System.Runtime.Serialization.FormatterServices.GetSerializableMembers( ),
System.Type.{FindMembers( ), GetDefaultMembers( ), GetMember( ), GetMembers( )}
```


Passed To

```
System.Attribute.{GetCustomAttribute( ), GetCustomAttributes( ), IsDefined( )},  
MemberFilter.{BeginInvoke( ), Invoke( )},  
System.Runtime.InteropServices.Expando.IExpando.RemoveMember( ),  
System.Runtime.InteropServices.Marshal.GetComSlotForMethodInfo( ),  
System.Runtime.Serialization.FormatterServices.{GetObjectData( ),  
PopulateObjectMembers( )}, System.Runtime.Serialization.ObjectManager.{RecordFixup(  
) , RegisterObject( )}
```

[\[Team LiB \]](#)

MemberTypes CF 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

This enumeration represents the different types of `MemberInfo` objects. `All` specifies all member types, and `Custom` specifies a custom member type. All of the other enumerated values specify the type of the `MemberInfo` object. For example, `Field` designates that the `MemberInfo` object is actually a `FieldInfo` object.

```
public enum MemberTypes {
    Constructor = 0x00000001 ,
    Event = 0x00000002 ,
    Field = 0x00000004 ,
    Method = 0x00000008 ,
    Property = 0x00000010 ,
    TypeInfo = 0x00000020 ,
    Custom = 0x00000040 ,
    NestedType = 0x00000080 ,
    All = 0x000000BF
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `MemberTypes`

Returned By

`MemberInfo.MemberType`

Passed To

`System.Type.FindMembers(), GetMember()`

MethodAttributes

CF 1.0, ECMA 1.0,
serializable, flag

System.Reflection (mscorlib.dll) *enum*

These attributes can be placed on methods. The behavior of most of these is obvious and the same as for `FieldAttributes`. The others are used for specifying the structure of the object `vTable`.

```
public enum MethodAttributes {
    ReuseSlot = 0x00000000 ,
    PrivateScope = 0x00000000 ,
    Private = 0x00000001 ,
    FamANDAssem = 0x00000002 ,
    Assembly = 0x00000003 ,
    Family = 0x00000004 ,
    FamORAssem = 0x00000005 ,
    Public = 0x00000006 ,
    MemberAccessMask = 0x00000007 ,
    UnmanagedExport = 0x00000008 ,
    Static = 0x00000010 ,
    Final = 0x00000020 ,
    Virtual = 0x00000040 ,
    HideBySig = 0x00000080 ,
    NewSlot = 0x00000100 ,
    VtableLayoutMask = 0x00000100 ,
    CheckAccessOnOverride = 0x00000200 ,
    Abstract = 0x00000400 ,
    SpecialName = 0x00000800 ,
    RTSpecialName = 0x00001000 ,
    PinvokeImpl = 0x00002000 ,
    HasSecurity = 0x00004000 ,
    RequireSecObject = 0x00008000 ,
    ReservedMask = 0x0000D000
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → MethodAttributes

Returned By

MethodBase.Attributes

Passed To

```
System.Reflection.Emit.ModuleBuilder.{DefineGlobalMethod( ), DefinePInvokeMethod( )},
System.Reflection.Emit.TypeBuilder.{DefineConstructor( ), DefineDefaultConstructor(
), DefineMethod( ), DefinePInvokeMethod( )}
```

[\[Team LiB \]](#)

MethodBase CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll)

abstract class

This is an abstract base class representing executable method calls, which fall into two categories: regular methods and constructors. `GetCurrentMethod()` and `GetMethodFromHandle()` are static methods that return the currently executing method and a method represented by a `System.RuntimeMethodHandle` object, respectively. The `MethodHandle` returns the handle for a specific method instance.

The properties prefixed by `Is` return boolean values, allowing inspection of the modifiers of the reflected method. Only some require explanation: `IsAssembly` returns true if the method is `internal` , and `IsFamily` returns true for protected methods. If a member of exactly the same name and signature is hidden by a derived class, `IsHideBySig` is true. `IsSpecialName` indicates whether this method has a special name, such as a property accessor, `get_PropertyName` or `set_PropertyName` .

Similarly, the attributes on a given method can be inspected from the `Attributes` property. `GetParameters()` returns the parameters of a method or constructor, and `GetMethodImplementationFlags()` returns the `MethodImplAttributes` flags set on the method.

In addition to introspecting on a method, the `MethodBase` also allows for reflective invocation of a method, using the `Invoke()` method. Note that `Invoke()` requires both the object instance against which to invoke the method (or `null` if the method is declared `static`), as well as an array of `object` references containing the arguments to the method, in their proper order. Should the argument array mismatch in any way (wrong number of arguments, wrong type of arguments, wrong order of arguments, and so on), an exception is thrown and the method call is not even attempted. Method invocation in this manner is much slower than direct compile-time-bound method execution.

```
public abstract class MethodBase : MemberInfo {
    // Protected Constructors
    protected MethodBase( );
    // Public Instance Properties
    public abstract MethodAttributes Attributes {get; }
    public virtual CallingConventions CallingConvention {get; }
    public bool IsAbstract {get; }
    public bool IsAssembly {get; }
    public bool IsConstructor {get; }
    public bool IsFamily {get; }
    public bool IsFamilyAndAssembly {get; }
    public bool IsFamilyOrAssembly {get; }
    public bool IsFinal {get; }
    public bool IsHideBySig {get; }
    public bool IsPrivate {get; }
    public bool IsPublic {get; }
    public bool IsSpecialName {get; }
```

```
public bool IsStatic{get; }
public bool IsVirtual{get; }
public abstract RuntimeMethodHandle MethodHandle{get; }
// Public Static Methods
public static MethodBase GetCurrentMethod( );
public static MethodBase GetMethodFromHandle(RuntimeMethodHandle handle);
// Public Instance Methods
public abstract MethodImplAttributes GetMethodImplementationFlags( );
public abstract ParameterInfo[ ] GetParameters( );
public abstract object Invoke(object obj, BindingFlags invokeAttr, Binder binder,
    object[ ] parameters, System.Globalization.CultureInfo culture);
public object Invoke(object obj, object[ ] parameters);
}
```

Hierarchy

System.Object → MemberInfo(ICustomAttributeProvider) → MethodBase

Subclasses

ConstructorInfo , MethodInfo

Returned By

System.Diagnostics.StackFrame.GetMethod() , System.Exception.TargetSite ,
Binder.{BindToMethod() , SelectMethod()}

Passed To

Binder.{BindToMethod() , SelectMethod()}

[Team LiB]

MethodImplAttributes

CF 1.0, serializable, flag

System.Reflection (mscorlib.dll) *enum*

These flags specify how a method has been implemented. **Managed**, **Unmanaged**, and **ManagedMask** indicate whether the method is managed or unmanaged code. If a method allows only one thread to execute it at a time, then its **Synchronized** flag is set. **ForwardRef** specifies that the method has not been defined, and **InternalCall** indicates that the method is an internal call. **IL** and **OPTIL** specify that the code is IL or optimized IL. If the method is provided by the runtime, **Runtime** should be set, and if the method implementation is native, **Native** is marked. When a method should not be inlined during optimization, **NoInlining** is set. When the method signature should be exported exactly as specified, **PreserveSig** is set.

```
public enum MethodImplAttributes {
    Managed = 0x00000000 ,
    IL = 0x00000000 ,
    Native = 0x00000001 ,
    OPTIL = 0x00000002 ,
    Runtime = 0x00000003 ,
    CodeTypeMask = 0x00000003 ,
    Unmanaged = 0x00000004 ,
    ManagedMask = 0x00000004 ,
    NoInlining = 0x00000008 ,
    ForwardRef = 0x00000010 ,
    Synchronized = 0x00000020 ,
    PreserveSig = 0x00000080 ,
    InternalCall = 0x00001000 ,
    MaxMethodImplVal = 0x0000FFFF
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → MethodImplAttributes

Returned By

MethodBase.GetMethodImplementationFlags()

Passed To

System.Reflection.Emit.ConstructorBuilder.SetImplementationFlags(),
System.Reflection.Emit.MethodBuilder.SetImplementationFlags()

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

MethodInfo CF 1.0, ECMA 1.0, serializable

System.Reflection
(mscorlib.dll)

abstract class

This class is an implementation of `MethodBase` for methods (`ConstructorInfo` is the other implementation for constructors). It adds two properties: `ReturnType` and `ReturnTypeCustomAttributes`, which allow access to the `System.Type` object of the value returned and to the custom attributes set on that value. If the method is overridden from a base class, then `GetBaseDefinition()` returns the `MethodInfo` for the overridden method.

```
public abstract class MethodInfo : MethodBase {
// Protected Constructors
    protected MethodInfo( );
// Public Instance Properties
    public override MemberTypes MemberType {get; }
// overrides MemberInfo
    public abstract Type ReturnType {get; }
    public abstract ICustomAttributeProvider ReturnTypeCustomAttributes {get; }
// Public Instance Methods
    public abstract MethodInfo GetBaseDefinition( );
}
```

Hierarchy

System.Object → MemberInfo(ICustomAttributeProvider) → MethodBase → MethodInfo

Subclasses

System.Reflection.Emit.MethodBuilder

Returned By

Multiple types

Passed To

```
System.Delegate.CreateDelegate( ),
System.Reflection.Emit.AssemblyBuilder.SetEntryPoint( ),
System.Reflection.Emit.ILGenerator.{Emit( ), EmitCall( )},
System.Reflection.Emit.ModuleBuilder.{GetMethodToken( ), SetUserEntryPoint( )},
System.Reflection.Emit.TypeBuilder.DefineMethodOverride( ),
System.Runtime.InteropServices.Marshal.{NumParamBytes( ), Prelink( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Missing

CF 1.0

System.Reflection (mscorlib.dll) *sealed class*

Because C# (as well as some other languages) does not allow optional parameters, **Missing** allows those languages to pass this value to indicate that a value will not be specified for those optional parameters. The only way to access an instance of this class-there can only be one-is by the return value of the static field, called **Value**.

```
public sealed class Missing {  
    // Public Static Fields  
    public static readonly Missing Value;  
    // =System.Reflection.Missing  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Module CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll) *class*

Modules are .NET executable files (either .EXE or .DLL files) consisting of classes or interfaces. One or more and other resources (such as graphics) make up an assembly. The `Module` class allows reflection of these types by name. The first is case-sensitive, and the second is case-insensitive. `Assembly` returns the appropriate `Assembly` object that this is part of. `Name` returns the filename of this module and `FullyQualifiedName` returns the filename as well as the full path. Use `FindTypes()` to return a list of types from a module accepted by a delegate. The methods prefixed with `Get` return the specific methods, types, or fields contained in this module. `IsDefined()` checks whether a specific attribute is defined on the module.

```
public class Module : System.Runtime.Serialization.ISerializable, ICustomAttributeProvider
// Public Static Fields
    public static readonly TypeFilter FilterTypeName;
// =System.Reflection.TypeFilter
    public static readonly TypeFilter FilterTypeNameIgnoreCase;
// =System.Reflection.TypeFilter
// Public Instance Properties
    public Assembly Assembly {get; }
    public virtual string FullyQualifiedName {get; }
    public string Name {get; }
    public string ScopeName {get; }
// Public Instance Methods
    public virtual Type[] FindTypes(TypeFilter filter, object filterCriteria);
    public virtual object[] GetCustomAttributes(bool inherit);
// implements ICustomAttributeProvider
    public virtual object[] GetCustomAttributes(Type attributeType, bool inherit)
// implements ICustomAttributeProvider
    public FieldInfo GetField(string name);
    public FieldInfo GetField(string name, BindingFlags bindingAttr);
    public FieldInfo[] GetFields( );
    public MethodInfo GetMethod(string name);
    public MethodInfo GetMethod(string name, BindingFlags bindingAttr, Binder binder,
        CallingConventions callConvention, Type[] types, ParameterModifier[] modifiers);
    public MethodInfo GetMethod(string name, Type[] types);
    public MethodInfo[] GetMethods( );
    public virtual void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// implements ISerializable
    public X509Certificate GetSignerCertificate( );
    public virtual Type GetType(string className);
    public virtual Type GetType(string className, bool ignoreCase);
    public virtual Type GetType(string className, bool throwOnError, bool ignoreCase);
```

```
public virtual Type[ ] GetTypes( );  
public virtual bool IsDefined(Type attributeType, bool inherit)  
// implements ICustomAttributeProvider  
public bool IsResource( );  
public override string ToString( );  
// overrides object  
// Protected Instance Methods  
protected virtual MethodInfo GetMethodImpl(string name, BindingFlags bindingAttr, Bi  
        CallingConventions callConvention, Type[ ] types, ParameterModifier[ ] modifier  
}
```

Subclasses

System.Reflection.Emit.ModuleBuilder

Returned By

Assembly.{GetLoadedModules(), GetModule(), GetModules(), LoadModule()},
System.Reflection.Emit.ConstructorBuilder.GetModule(),
System.Reflection.Emit.MethodBuilder.GetModule(), ModuleResolveEventHandler.{EndInvoke(
)}, System.Type.Module

Passed To

System.Attribute.{GetCustomAttribute(), GetCustomAttributes(), IsDefined()},
System.Reflection.Emit.SignatureHelper.{GetFieldSigHelper(), GetLocalVarSigHelper(),
GetMethodSigHelper(), GetPropertySigHelper()},
System.Runtime.InteropServices.Marshal.GetHINSTANCE()

[Team LiB]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ModuleResolveEventHandler serializable

System.Reflection (mscorlib.dll) *delegate*

This delegate is used as an event handler by **Assembly** when it cannot resolve a reference to a module that is part of an assembly. One instance in which this might occur is if one resource is not present.

```
public delegate Module ModuleResolveEventHandler(object sender, ResolveEventArgs e);
```

Associated Events

```
Assembly.ModuleResolve( ), System.Reflection.Emit.AssemblyBuilder.ModuleResolve( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ParameterAttributes

CF 1.0, ECMA 1.0,
serializable, flag

System.Reflection (mscorlib.dll) *enum*

These attributes are specified on a parameter. When the parameter has a default value, `HasDefault` is asserted. `Optional`, `Out`, `In`, and `RetVal` all behave as you would expect them to. If a parameter has no attribute, `None` must be marked alone. If the parameter contains locale identifying information, `Lcid` should be set. Lastly, if the parameter is for marshaling information, `HasFieldMarshal` is asserted.

```
public enum ParameterAttributes {
    None = 0x00000000 ,
    In = 0x00000001 ,
    Out = 0x00000002 ,
    Lcid = 0x00000004 ,
    Retval = 0x00000008 ,
    Optional = 0x00000010 ,
    HasDefault = 0x00001000 ,
    HasFieldMarshal = 0x00002000 ,
    Reserved3 = 0x00004000 ,
    Reserved4 = 0x00008000 ,
    ReservedMask = 0x0000F000
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → ParameterAttributes

Returned By

ParameterInfo.Attributes

Passed To

System.Reflection.Emit.ConstructorBuilder.DefineParameter(),
System.Reflection.Emit.MethodBuilder.DefineParameter()

ParameterInfo CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll) *class*

This class allows the inspection of the type and behavior of a method parameter. Because parameters can have custom attributes on them, the class implements `ICustomAttributeProvider`. `Attributes` returns the attributes defined on this parameter. If the parameter has a default, it is stored in `DefaultValue`. Retrieve the name, type, and member the parameter is from by inspecting `Name`, `ParameterType`, and `Member`. `Position` returns the ordinal position of this parameter. `IsOptional` returns `true` if the parameter is optional, and `IsLcid` indicates when the parameter is a locale identifier.

A parameter is passed by reference if the `IsByRef` property of its `ParameterType` property is `true` and the `IsOut` property is `false` (*out* parameters have `IsByRef` and `IsOut` set to `true`). A parameter that has been marked as `[In]` has `IsOut` set to `false` and `IsIn` set to `true`.

```
public class ParameterInfo : ICustomAttributeProvider {
// Protected Constructors
    protected ParameterInfo( );
// Protected Instance Fields
    protected ParameterAttributes AttrsImpl;
    protected Type ClassImpl;
    protected object DefaultValueImpl;
    protected MemberInfo MemberImpl;
    protected string NameImpl;
    protected int PositionImpl;
// Public Instance Properties
    public virtual ParameterAttributes Attributes {get; }
    public virtual object DefaultValue {get; }
    public bool IsIn {get; }
    public bool IsLcid {get; }
    public bool IsOptional {get; }
    public bool IsOut {get; }
    public bool IsRetVal {get; }
    public virtual MemberInfo Member {get; }
    public virtual string Name {get; }
    public virtual Type ParameterType {get; }
    public virtual int Position {get; }
// Public Instance Methods
    public virtual object[] GetCustomAttributes(bool inherit);
// implements ICustomAttributeProvider
    public virtual object[] GetCustomAttributes(Type attributeType, bool inherit)
// implements ICustomAttributeProvider
    public virtual bool IsDefined(Type attributeType, bool inherit);
// implements ICustomAttributeProvider
}
```


Returned By

MethodBase.GetParameters(), PropertyInfo.GetIndexParameters()

Passed To

System.Attribute.{GetCustomAttribute(), GetCustomAttributes(), IsDefined()}

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ParameterModifier

CF 1.0, ECMA 1.0,
serializable

System.Reflection (mscorlib.dll) *struct*

This value type acts much like an array of boolean values. It can be constructed to a certain size, and then each index can be set or retrieved.

```
public struct ParameterModifier {  
    // Public Constructors  
    public ParameterModifier(int parameterCount);  
    // Public Instance Properties  
    public bool this[int index]{set; get; }  
}
```

Hierarchy

System.Object → System.ValueType → ParameterModifier

Passed To

Multiple types

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Pointer

System.Reflection (mscorlib.dll) *sealed class*

This class allows access to direct pointers to .NET objects through two static methods. `Unbox()` returns a `void*` pointer to the passed object and pins it, not allowing the garbage collector to move its place in memory, and `Box()` returns control over the object to the .NET runtime.

```
public sealed class Pointer : System.Runtime.Serialization.ISerializable {  
    // Public Static Methods  
    public static object Box(void *ptr, Type type);  
    public static void* Unbox(object ptr);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PropertyAttributes

CF 1.0, ECMA 1.0,
serializable, flag

System.Reflection (mscorlib.dll) *enum*

Specifies the attributes that can be placed on properties. The important ones that you will encounter are `None` and `HasDefault`, which specify either the absence of attributes or that there is a default.

```
public enum PropertyAttributes {  
    None = 0x00000000 ,  
    SpecialName = 0x00000200 ,  
    RTSpecialName = 0x00000400 ,  
    HasDefault = 0x00001000 ,  
    Reserved2 = 0x00002000 ,  
    Reserved3 = 0x00004000 ,  
    Reserved4 = 0x00008000 ,  
    ReservedMask = 0x0000F400  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `PropertyAttributes`

Returned By

`PropertyInfo.Attributes`

Passed To

`System.Reflection.Emit.TypeBuilder.DefineProperty()`

PropertyInfo CF 1.0, ECMA 1.0, serializable

System.Reflection (mscorlib.dll) *abstract class*

This class implements `MemberInfo` and represents a declared property on a type. `CanRead` and `CanWrite` check whether this property has `get` or `set` behaviors defined. These methods can be inspected directly (as `MethodInfo` instances) by calling `GetGetMethod()` and `GetSetMethod()`, or together by calling `GetAccessors()`, which returns an array of all defined accessors. If the property is an indexer, `GetIndexParameters()` returns parameters to access the indexer. `GetValue()` and `SetValue()` allow the instance of this property to be set or retrieved; these act as a shortcut to calling `Invoke` on the methods returned from `GetGetMethod()` or `GetSetMethod()`.

```
public abstract class PropertyInfo : MemberInfo {
    // Protected Constructors
    protected PropertyInfo( );
    // Public Instance Properties
    public abstract PropertyAttributes Attributes {get; }
    public abstract bool CanRead {get; }
    public abstract bool CanWrite {get; }
    public bool IsSpecialName {get; }
    public override MemberTypes MemberType {get; }
    // overrides MemberInfo
    public abstract Type PropertyType {get; }
    // Public Instance Methods
    public MethodInfo[ ] GetAccessors( );
    public abstract MethodInfo[ ] GetAccessors(bool nonPublic);
    public MethodInfo GetGetMethod( );
    public abstract MethodInfo GetGetMethod(bool nonPublic);
    public abstract ParameterInfo[ ] GetIndexParameters( );
    public MethodInfo GetSetMethod( );
    public abstract MethodInfo GetSetMethod(bool nonPublic);
    public abstract object GetValue(object obj, BindingFlags invokeAttr, Binder binder,
        object[ ] index, System.Globalization.CultureInfo culture);
    public virtual object GetValue(object obj, object[ ] index);
    public abstract void SetValue(object obj, object value, BindingFlags invokeAttr,
        Binder binder, object[ ] index, System.Globalization.CultureInfo culture);
    public virtual void SetValue(object obj, object value, object[ ] index);
}
```

Hierarchy

System.Object → MemberInfo(ICustomAttributeProvider) → PropertyInfo

Subclasses

`System.Reflection.Emit.PropertyBuilder`

Returned By

```
Binder.SelectProperty( ), IReflect.{GetProperties( ), GetProperty( )} ,  
System.Runtime.InteropServices.Expando.IExpando.AddProperty( ),  
System.Type.{GetProperties( ), GetProperty( ), GetPropertyImpl( )}
```

Passed To

```
Binder.SelectProperty( ),  
System.Reflection.Emit.CustomAttributeBuilder.CustomAttributeBuilder( )
```

[Team LiB]

[◀ PREVIOUS](#) [NEXT ▶](#)


ReflectionTypeLoadException serializable

System.Reflection (mscorlib.dll) *sealed class*

This exception is thrown if any of the types from a module cannot be loaded when `Module.GetTypes()` called. This exception provides access to the correctly loaded classes via `Types` .

```
public sealed class ReflectionTypeLoadException : SystemException {
// Public Constructors
    public ReflectionTypeLoadException(Type[] classes, Exception[] exceptions);
    public ReflectionTypeLoadException(Type[] classes, Exception[] exceptions,
        string message);
// Public Instance Properties
    public Exception[] LoaderExceptions{get; }
    public Type[] Types{get; }
// Public Instance Methods
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in,
        System.Runtime.Serialization.StreamingContext context)
// overrides Exception
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ResourceAttributes serializable, flag

System.Reflection (mscorlib.dll) *enum*

This enumeration includes the only two flags that can be placed on resources: `Public` and `Private`.

```
public enum ResourceAttributes {  
    Public = 0x00000001 ,  
    Private = 0x00000002  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ResourceAttributes`

Passed To

```
System.Reflection.Emit.AssemblyBuilder.{AddResourceFile( ), DefineResource( )},  
System.Reflection.Emit.ModuleBuilder.DefineResource( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ResourceLocation

serializable, flag

System.Reflection (mscorlib.dll)

enum

This enumeration returns the location of a resource relative to the assembly.

```
public enum ResourceLocation {  
    Embedded = 0x00000001 ,  
    ContainedInAnotherAssembly = 0x00000002 ,  
    ContainedInManifestFile = 0x00000004  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → ResourceLocation

Returned By

ManifestResourceInfo.ResourceLocation

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

StrongNameKeyPair

serializable

System.Reflection (mscorlib.dll) *class*

This property allows reflection of an assembly's strong name. Use `PublicKey` to decrypt the encrypted name to verify the authenticity of the assembly.

```
public class StrongNameKeyPair {  
    // Public Constructors  
    public StrongNameKeyPair(byte[] keyPairArray);  
    public StrongNameKeyPair(System.IO.FileStream keyPairFile);  
    public StrongNameKeyPair(string keyPairContainer);  
    // Public Instance Properties  
    public byte[] PublicKey {get; }  
}
```

Returned By

`AssemblyName.KeyPair`

Passed To

`AssemblyName.KeyPair`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)


TargetException ECMA 1.0, serializable

System.Reflection (mscorlib.dll) *class*

This exception is thrown when you attempt to invoke a nonstatic method on a `null` object reference. (Note that in Beta1 of the .NET SDK, it was permissible to call a nonvirtual method against a `null` reference, so long as that method didn't access any of the fields in the type. In Beta2 and beyond, this "feature" has been closed and removed.)

```
public class TargetException : ApplicationException {
// Public Constructors
    public TargetException( );
    public TargetException(string message);
    public TargetException(string message, Exception inner);
// Protected Constructors
    protected TargetException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



TargetInvocationException


CF 1.0, ECMA 1.0,
serializable

System.Reflection (mscorlib.dll) *sealed class*

This exception is thrown by methods invoked via Reflection when they raise exceptions. Check `InnerException` to view the actual exception raised.

```
public sealed class TargetInvocationException : ApplicationException {  
    // Public Constructors  
    public TargetInvocationException(Exception inner);  
    public TargetInvocationException(string message, Exception inner);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

CF 1.0,
ECMA 1.0,
serializable


TargetException

System.Reflection (mscorlib.dll) *sealed class*

This exception is thrown when a method is invoked with an incorrect number of parameters. Note that this can only come when invoking methods via reflection, since the compiler detects any normal parameter count errors.

```
public sealed class TargetException : ApplicationException {  
    // Public Constructors  
    public TargetException( );  
    public TargetException(string message);  
    public TargetException(string message, Exception inner);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TypeAttributes CF 1.0, ECMA 1.0, serializable, flag

System.Reflection (mscorlib.dll) enum

These attributes can be applied to a type. A type is either a class or interface, so either **Class** or **Interface** must be set. Most of the modifiers share the same keywords with C# and VB.NET, so they are easy to understand. The values prefixed with **Nested** indicate a class that is nested as well as its visibility.

```
public enum TypeAttributes {
    Class = 0x00000000 ,
    AutoLayout = 0x00000000 ,
    AnsiClass = 0x00000000 ,
    NotPublic = 0x00000000 ,
    Public = 0x00000001 ,
    NestedPublic = 0x00000002 ,
    NestedPrivate = 0x00000003 ,
    NestedFamily = 0x00000004 ,
    NestedAssembly = 0x00000005 ,
    NestedFamANDAssem = 0x00000006 ,
    VisibilityMask = 0x00000007 ,
    NestedFamORAssem = 0x00000007 ,
    SequentialLayout = 0x00000008 ,
    ExplicitLayout = 0x00000010 ,
    LayoutMask = 0x00000018 ,
    Interface = 0x00000020 ,
    ClassSemanticsMask = 0x00000020 ,
    Abstract = 0x00000080 ,
    Sealed = 0x00000100 ,
    SpecialName = 0x00000400 ,
    RTSpecialName = 0x00000800 ,
    Import = 0x00001000 ,
    Serializable = 0x00002000 ,
    UnicodeClass = 0x00010000 ,
    AutoClass = 0x00020000 ,
    StringFormatMask = 0x00030000 ,
    HasSecurity = 0x00040000 ,
    ReservedMask = 0x00040800 ,
    BeforeFieldInit = 0x00100000
}
```

Hierarchy



`System.IFormattable, System.IConvertible) → TypeAttributes`

Returned By

`System.Type. {Attributes, GetAttributeFlagsImpl()}`

Passed To

`System.Reflection.Emit.ModuleBuilder. {DefineEnum(), DefineType()},
System.Reflection.Emit.TypeBuilder. DefineNestedType()`

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

TypeDelegator

serializable

System.Reflection (mscorlib.dll)

class

Because `System.Type` is an abstract class, `TypeDelegator` simply wraps `System.Type` methods and provides necessary implementations.

```
public class TypeDelegator : Type {
// Public Constructors
    public TypeDelegator(Type delegatingType);
// Protected Constructors
    protected TypeDelegator( );
// Protected Instance Fields
    protected Type typeImpl;
// Public Instance Properties
    public override Assembly Assembly{get; }
// overrides Type
    public override string AssemblyQualifiedName{get; }
// overrides Type
    public override Type BaseType{get; }
// overrides Type
    public override string FullName{get; }
// overrides Type
    public override Guid GUID{get; }
// overrides Type
    public override Module Module{get; }
// overrides Type
    public override string Name{get; }
// overrides MemberInfo
    public override string Namespace{get; }
// overrides Type
    public override RuntimeTypeHandle TypeHandle{get; }
// overrides Type
    public override Type UnderlyingSystemType{get; }
// overrides Type
// Public Instance Methods
    public override ConstructorInfo[ ] GetConstructors(BindingFlags bindingAttr)
// overrides Type
    public override object[ ] GetCustomAttributes(bool inherit)
// overrides MemberInfo
    public override object[ ] GetCustomAttributes(Type attributeType, bool inherit)
// overrides MemberInfo
    public override Type GetElementType( );
// overrides Type
    public override EventInfo GetEvent(string name, BindingFlags bindingAttr);
```



```

// overrides Type
public override EventInfo[ ] GetEvents( );
// overrides Type
public override EventInfo[ ] GetEvents(BindingFlags bindingAttr);
// overrides Type
public override FieldInfo GetField(string name, BindingFlags bindingAttr);
// overrides Type
public override FieldInfo[ ] GetFields(BindingFlags bindingAttr)
// overrides Type
public override Type GetInterface(string name, bool ignoreCase);
// overrides Type
public override InterfaceMapping GetInterfaceMap(Type interfaceType)
// overrides Type
public override Type[ ] GetInterfaces( );
// overrides Type
public override MemberInfo[ ] GetMember(string name, MemberTypes type,
    BindingFlags bindingAttr)
// overrides Type
public override MemberInfo[ ] GetMembers(BindingFlags bindingAttr)
// overrides Type
public override MethodInfo[ ] GetMethods(BindingFlags bindingAttr)
// overrides Type
public override Type GetNestedType(string name, BindingFlags bindingAttr);
// overrides Type
public override Type[ ] GetNestedTypes(BindingFlags bindingAttr)
// overrides Type
public override PropertyInfo[ ] GetProperties(BindingFlags bindingAttr)
// overrides Type
public override object InvokeMember(string name, BindingFlags invokeAttr,
    Binder binder, object target, object[ ] args, ParameterModifier[ ] modifiers,
    System.Globalization.CultureInfo culture, string[ ] namedParameters)
// overrides Type
public override bool IsDefined(Type attributeType, bool inherit)
// overrides MemberInfo
// Protected Instance Methods
protected override TypeAttributes GetAttributeFlagsImpl( );
// overrides Type
protected override ConstructorInfo GetConstructorImpl(BindingFlags bindingAttr, Bind
    CallingConventions callConvention, Type[ ] types, ParameterModifier[ ] modifiers
// overrides Type
protected override MethodInfo GetMethodImpl(string name, BindingFlags bindingAttr,
    Binder binder, CallingConventions callConvention, Type[ ] types,
    ParameterModifier[ ] modifiers)
// overrides Type
protected override PropertyInfo GetPropertyImpl(string name, BindingFlags bindingAtt.
    Binder binder, Type returnType, Type[ ] types,
    ParameterModifier[ ] modifiers)
// overrides Type
protected override bool HasElementTypeImpl( );

```

```
// overrides Type
protected override bool IsArrayImpl( );
// overrides Type
protected override bool IsByRefImpl( );
// overrides Type
protected override bool IsCOMObjectImpl( );
// overrides Type
protected override bool IsPointerImpl( );
// overrides Type
protected override bool IsPrimitiveImpl( );
// overrides Type
protected override bool IsValueTypeImpl( );
// overrides Type
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TypeFilter

serializable

System.Reflection (mscorlib.dll) *delegate*

This delegate maps to a function that will be applied individually to a list of `System.Type` objects. A filter runs through the list, and if this delegate returns `true`, the filtered list includes this object; otherwise it is excluded.

```
public delegate bool TypeFilter(Type m, object filterCriteria);
```

Passed To

```
Module.FindTypes( ), System.Type.FindInterfaces( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 36. System.Reflection.Emit


There are several ways to use reflection in .NET. Reflection can be used for runtime-type inspection and late-bound object creation using the types in the `System.Reflection` namespace. Reflection can also be used for dynamic code creation, which is supported by the types in this namespace, `System.Reflection.Emit`. Dynamic code creation means a programmer can programmatically create code constructs such as methods and events from within code, using the appropriate corresponding type (for example, `MethodBuilder` and `EventBuilder`). These code elements are all ingredients that can be added to a dynamic assembly, represented by an `AssemblyBuilder` object. Dynamic assemblies can be saved to disk as PE (Portable Executable) files, typically in DLL form. Or, alternatively, emit it directly to memory for immediate use, at the expense of persistence (memory-only types disappear when the containing `AppDomain` terminates).

The `ILGenerator` class allows you to emit the MSIL (Microsoft Intermediate Language) for your code, using the corresponding `GetILGenerator()` method from a *builder* class. This process (sometimes known as "baking") allows you to convert the information in the builder object into a legitimate .NET type. You can then instantiate this newly created type on the spot.

The primary use of the `System.Reflection.Emit` namespace is to create compilers and script hosts, although many other uses are possible, including programs that dynamically create code that is fine-tuned to process a specific regular expression (see `System.Text.RegularExpressions.Regex.CompileToAssembly()`). When creating dynamic types, you generally begin by creating an `AssemblyBuilder`, which contains one or more `ModuleBuilder` objects. This in turn contains `TypeBuilder` instances. `TypeBuilder` objects contain most of the other ingredients in this namespace, including classes for building events, properties, methods, and enumerations.

Many of the builder classes in this namespace use similar methods and properties for retrieving information about the containing module (for example, `ConstructorBuilder.GetModule()`), getting an internal handle to the metadata (for example, `EnumBuilder.TypeHandle()`), and retrieving attributes (`MethodBuilder.Attributes`). Also note that though the builder classes derive from the corresponding "-Info" class (for example, `MethodBuilder` derives from `System.Reflection.MethodInfo`), not all of the inherited properties are currently supported. This includes methods such as `Invoke()`. To use these methods, you may need to reflect on the object with `System.Type.GetType()`. [Figure 36-1](#) shows the types in this namespace.

Figure 36-1. The System.Reflection.Emit namespace



AssemblyBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamic assembly. A dynamic assembly is the root container for all the builder of `System.Reflection.Emit` namespace. You can create an `AssemblyBuilder` object by using the `DefineE` method of the `System.AppDomain` class. When you create a dynamic assembly, specify a name and the a `AssemblyBuilderAccess` enumeration. If you plan to save the assembly to disk using the the `Save()` or `AssemblyBuilderAccess.Save` or `AssemblyBuilderAccess.RunAndSave` .

A dynamic assembly can contain one or more modules, which are defined by `ModuleBuilder` objects. Use `DefineDynamicModule()` method to define, create, and return a `ModuleBuilder` object, as in `ModuleBu myAssemblyB.DefineDynamicModule("ModuleName");` . By default, this is a transient module that cannc the `AssemblyBuilderAccess` specified. To create a module that can be saved to disk, use a version of th `DefineDynamicModule()` that requires a `fileName` argument. You can also use other methods to add a assembly, add or create managed and unmanaged resources, and retrieve a `System.IO.FileStream` obj the assembly.

When you are finished creating an assembly and all its members, you can use the `Save()` method. This filename as a parameter, which can't include directory or drive information. To use a different directory o the path when you create the dynamic assembly by using the appropriate constructor. When you save a nontransient modules are saved using the filename specified when you created them. By default, the ass file (as if you had used the `/target:library` command-line compiler switch). To change this, use the `Se` to specify the assembly's startup method and to specify `PEFileKinds` .

```
public sealed class AssemblyBuilder : System.Reflection.Assembly {
// Public Instance Properties
    public override string CodeBase{get; }
// overrides System.Reflection.Assembly
    public override MethodInfo EntryPoint{get; }
// overrides System.Reflection.Assembly
    public override string ImageRuntimeVersion{get; }
// overrides System.Reflection.Assembly
    public override string Location{get; }
// overrides System.Reflection.Assembly
// Public Instance Methods
    public void AddResourceFile(string name, string fileName);
    public void AddResourceFile(string name, string fileName, System.Reflection.Resource
    public ModuleBuilder DefineDynamicModule(string name);
    public ModuleBuilder DefineDynamicModule(string name, bool emitSymbolInfo);
    public ModuleBuilder DefineDynamicModule(string name, string fileName);
    public ModuleBuilder DefineDynamicModule(string name, string fileName, bool emitSymb
    public IResourceWriter DefineResource(string name, string description, string fileNa
    public IResourceWriter DefineResource(string name, string description, string fileNa
```

```

        System.Reflection.ResourceAttributes attribute);
    public void DefineUnmanagedResource(byte[] resource);
    public void DefineUnmanagedResource(string resourceFileName);
    public void DefineVersionInfoResource( );
    public void DefineVersionInfoResource(string product, string productVersion, string
        string copyright, string trademark);
    public ModuleBuilder GetDynamicModule(string name);
    public override Type[] GetExportedTypes( );
    // overrides System.Reflection.Assembly
    public override FileStream GetFile(string name);
    // overrides System.Reflection.Assembly
    public override FileStream[] GetFiles(bool getResourceModules)
    // overrides System.Reflection.Assembly
    public override ManifestResourceInfo GetManifestResourceInfo(string resourceName)
    // overrides System.Reflection.Assembly
    public override string[] GetManifestResourceNames( );
    // overrides System.Reflection.Assembly
    public override Stream GetManifestResourceStream(string name)
    // overrides System.Reflection.Assembly
    public override Stream GetManifestResourceStream(Type type, string name);
    // overrides System.Reflection.Assembly
    public void Save(string assemblyFileName);
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con, byte[] binary);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetEntryPoint(System.Reflection.MethodInfo entryMethod);
    public void SetEntryPoint(System.Reflection.MethodInfo entryMethod, PEFileKinds file
}

```

Hierarchy

System.Object → System.Reflection.Assembly(System.Security.IEvidenceFactory ,
System.Reflection.ICustomAttributeProvider , System.Runtime.Serialization.ISerializable)

Returned By

System.AppDomain.DefineDynamicAssembly()

[Team LiB]

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

AssemblyBuilderAccess serializable, flag

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration is used by the `System.AppDomain.DefineDynamicAssembly()` method. It specifies whether a dynamic assembly will support dynamic execution only (`Run`), save to disk only (`Save`), or both (`RunAndSave`).

```
public enum AssemblyBuilderAccess {  
    Run = 0x00000001 ,  
    Save = 0x00000002 ,  
    RunAndSave = 0x00000003  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `AssemblyBuilderAccess`

Passed To

`System.AppDomain.DefineDynamicAssembly()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ConstructorBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created constructor method. Create a constructor and add it to a type using either the `TypeBuilder.DefineConstructor()` method or the `TypeBuilder.DefineDefaultConstructor()` method. The default constructor accepts no parameters, and just calls the constructor of the parent class. You cannot use the `ILGenerator` class with a default constructor, because its code is provided by the runtime. Generally, a default constructor does not need to be created, as the CLR provides it for you.

If you create a custom constructor with `TypeBuilder.DefineConstructor()`, you can specify the constructor's parameters as an array of `System.Type` objects. Alternatively, you can use the `DefineParameter()` method to create a `ParameterBuilder`. You can also add MSIL code to the constructor using the `GetILGenerator()` method.

```
public sealed class ConstructorBuilder : System.Reflection.ConstructorInfo {
    // Public Instance Properties
    public override MethodAttributes Attributes {get; }
    // overrides System.Reflection.MethodBase
    public override Type DeclaringType {get; }
    // overrides System.Reflection.MemberInfo
    public bool InitLocals {set; get; }
    public override RuntimeMethodHandle MethodHandle {get; }
    // overrides System.Reflection.MethodBase
    public override string Name {get; }
    // overrides System.Reflection.MemberInfo
    public override Type ReflectedType {get; }
    // overrides System.Reflection.MemberInfo
    public Type ReturnType {get; }
    public string Signature {get; }
    // Public Instance Methods
    public void AddDeclarativeSecurity(System.Security.Permissions.SecurityAction action,
        System.Security.PermissionSet pset);
    public ParameterBuilder DefineParameter(int iSequence,
        System.Reflection.ParameterAttributes attributes, string strParamName);
    public override object[] GetCustomAttributes(bool inherit)
    // overrides System.Reflection.MemberInfo
    public override object[] GetCustomAttributes(Type attributeType, bool inherit)
    // overrides System.Reflection.MemberInfo
    public ILGenerator GetILGenerator( );
    public override MethodImplAttributes GetMethodImplementationFlags( )
    // overrides System.Reflection.MethodBase
    public Module GetModule( );
}
```

```

    public override ParameterInfo[ ] GetParameters( )
// overrides System.Reflection.MethodBase
    public MethodToken GetToken( );
    public override object Invoke(System.Reflection.BindingFlags invokeAttr,
        System.Reflection.Binder binder, object[ ] parameters,
        System.Globalization.CultureInfo culture);
// overrides System.Reflection.ConstructorInfo
    public override object Invoke(object obj, System.Reflection.BindingFlags invokeAttr,
        System.Reflection.Binder binder, object[ ] parameters,
        System.Globalization.CultureInfo culture)
// overrides System.Reflection.MethodBase
    public override bool IsDefined(Type attributeType, bool inherit)
// overrides System.Reflection.MemberInfo
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con,
        byte[ ] binaryAttribute);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetImplementationFlags(System.Reflection.MethodImplAttributes attributes)
    public void SetSymCustomAttribute(string name, byte[ ] data);
    public override string ToString( );
// overrides object
}

```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvide
 → System.Reflection.MethodBase → System.Reflection.ConstructorInfo →
 ConstructorBuilder

Returned By

TypeBuilder.{DefineConstructor(), DefineDefaultConstructor(), DefineTypeInitializer()

[Team LiB]

◀ PREVIOUS NEXT ▶

CustomAttributeBuilder

System.Reflection.Emit (mscorlib.dll) *class*

This class represents a dynamically created custom attribute. To apply a custom attribute, pass an instance to the `SetCustomAttribute()` method for the appropriate builder (`PropertyBuilder.SetCustomAttribute()`, `MethodBuilder.SetCustomAttribute()`, for example). The constructor allows you to specify the custom named properties and fields, their values, and a constructor.

```
public class CustomAttributeBuilder {
// Public Constructors
    public CustomAttributeBuilder(System.Reflection.ConstructorInfo con, object[] const:
    public CustomAttributeBuilder(System.Reflection.ConstructorInfo con, object[] const:
        System.Reflection.FieldInfo[] namedFields, object[] fieldValues);
    public CustomAttributeBuilder(System.Reflection.ConstructorInfo con, object[] const:
        System.Reflection.PropertyInfo[] namedProperties, object[] propertyValues);
    public CustomAttributeBuilder(System.Reflection.ConstructorInfo con, object[] const:
        System.Reflection.PropertyInfo[] namedProperties, object[] propertyValues,
        System.Reflection.FieldInfo[] namedFields, object[] fieldValues);
}
```

Passed To

```
AssemblyBuilder.SetCustomAttribute( ), ConstructorBuilder.SetCustomAttribute( ),
EnumBuilder.SetCustomAttribute( ), EventBuilder.SetCustomAttribute( ),
FieldBuilder.SetCustomAttribute( ), MethodBuilder.SetCustomAttribute( ),
ModuleBuilder.SetCustomAttribute( ), ParameterBuilder.SetCustomAttribute( ),
PropertyBuilder.SetCustomAttribute( ), TypeBuilder.SetCustomAttribute( ),
System.Text.RegularExpressions.Regex.CompileToAssembly( )
```

EnumBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created enumeration. Enumerations are created at module scope using `ModuleBuilder.DefineEnum()` method. Before using a dynamically created enumeration, you must use `EnumBuilder` method to complete it.

```
public sealed class EnumBuilder : Type {
// Public Instance Properties
    public override Assembly Assembly {get; }
// overrides Type
    public override string AssemblyQualifiedName {get; }
// overrides Type
    public override Type BaseType {get; }
// overrides Type
    public override Type DeclaringType {get; }
// overrides Type
    public override string FullName {get; }
// overrides Type
    public override Guid GUID {get; }
// overrides Type
    public override Module Module {get; }
// overrides Type
    public override string Name {get; }
// overrides System.Reflection.MemberInfo
    public override string Namespace {get; }
// overrides Type
    public override Type ReflectedType {get; }
// overrides Type
    public override RuntimeTypeHandle TypeHandle {get; }
// overrides Type
    public TypeToken TypeToken {get; }
    public FieldBuilder UnderlyingField {get; }
    public override Type UnderlyingSystemType {get; }
// overrides Type
// Public Instance Methods
    public Type CreateType( );
    public FieldBuilder DefineLiteral(string literalName, object literalValue);
    public override ConstructorInfo[] GetConstructors(System.Reflection.BindingFlags bi
// overrides Type
    public override object[] GetCustomAttributes(bool inherit)
// overrides System.Reflection.MemberInfo
    public override object[] GetCustomAttributes(Type attributeType, bool inherit)
```

```

// overrides System.Reflection.MemberInfo
public override Type GetElementType( );
// overrides Type
public override EventInfo GetEvent(string name, System.Reflection.BindingFlags bindi.
// overrides Type
public override EventInfo[ ] GetEvents( );
// overrides Type
public override EventInfo[ ] GetEvents(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override FieldInfo GetField(string name, System.Reflection.BindingFlags bindi.
// overrides Type
public override FieldInfo[ ] GetFields(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override Type GetInterface(string name, bool ignoreCase)
// overrides Type
public override InterfaceMapping GetInterfaceMap(Type interfaceType)
// overrides Type
public override Type[ ] GetInterfaces( );
// overrides Type
public override MemberInfo[ ] GetMember(string name, System.Reflection.MemberTypes t.
    System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override MemberInfo[ ] GetMembers(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override MethodInfo[ ] GetMethods(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override Type GetNestedType(string name, System.Reflection.BindingFlags bindi.
// overrides Type
public override Type[ ] GetNestedTypes(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override PropertyInfo[ ] GetProperties(System.Reflection.BindingFlags binding.
// overrides Type
public override object InvokeMember(string name, System.Reflection.BindingFlags invo.
    System.Reflection.Binder binder, object target, object[ ] args,
    System.Reflection.ParameterModifier[ ] modifiers,
    System.Globalization.CultureInfo culture, string[ ] namedParameters)
// overrides Type
public override bool IsDefined(Type attributeType, bool inherit)
// overrides System.Reflection.MemberInfo
public void SetCustomAttribute(System.Reflection.ConstructorInfo con, byte[ ] binary.
public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
// Protected Instance Methods
protected override TypeAttributes GetAttributeFlagsImpl( );
// overrides Type
protected override ConstructorInfo GetConstructorImpl(System.Reflection.BindingFlags
    System.Reflection.Binder binder, System.Reflection.CallingConventions callConven
    Type[ ] types, System.Reflection.ParameterModifier[ ] modifiers)
// overrides Type
protected override MethodInfo GetMethodImpl(string name, System.Reflection.BindingFl

```

```

        System.Reflection.Binder binder, System.Reflection.CallingConventions callConven
        System.Reflection.ParameterModifier[ ] modifiers)
// overrides Type
protected override PropertyInfo GetPropertyImpl(string name,
    System.Reflection.BindingFlags bindingAttr,
    System.Reflection.Binder binder, Type returnType, Type[ ] types,
    System.Reflection.ParameterModifier[ ] modifiers)
// overrides Type
protected override bool HasElementTypeImpl( );
// overrides Type
protected override bool IsArrayImpl( );
// overrides Type
protected override bool IsByRefImpl( );
// overrides Type
protected override bool IsCOMObjectImpl( );
// overrides Type
protected override bool IsPointerImpl( );
// overrides Type
protected override bool IsPrimitiveImpl( );
// overrides Type
protected override bool IsValueTypeImpl( );
// overrides Type
}

```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvide
 System.Type(System.Reflection.IReflect) → EnumBuilder

Returned By

ModuleBuilder.DefineEnum()

[Team LiB]

◀ PREVIOUS NEXT ▶

EventBuilder

System.Reflection.Emit
(mscorlib.dll)

sealed
class

This class represents a dynamically created event. Events are created with the `TypeBuilder.DefineEvent()` method. You can then attach a `MethodBuilder` object to represent one of three methods: the method used to raise the event (`SetRaiseMethod()`), the method used to subscribe to the event (`SetAddOnMethod()`), and the method used to unsubscribe (`SetRemoveOnMethod()`).

```
public sealed class EventBuilder {  
    // Public Instance Methods  
    public void AddOtherMethod(MethodBuilder mdBuilder);  
    public EventToken GetEventToken( );  
    public void SetAddOnMethod(MethodBuilder mdBuilder);  
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con,  
        byte[] binaryAttribute);  
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);  
    public void SetRaiseMethod(MethodBuilder mdBuilder);  
    public void SetRemoveOnMethod(MethodBuilder mdBuilder);  
}
```

Returned By

`TypeBuilder.DefineEvent()`

EventToken

serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for an event. A token is a 4-byte number that points to the metadata description of a program element in MSIL. The first byte in the token identifies the metadata table, which depends on the type of program element. The remaining 3 bytes specify the row in the metadata table. For example, the token 0x06000004 specifies that the corresponding metadata is stored in the fourth row of table 0x06 (the **MethodDef** table).

```
public struct EventToken {  
    // Public Static Fields  
    public static readonly EventToken Empty;  
    // =System.Reflection.Emit.EventToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy



Returned By

```
EventBuilder.GetEventToken( )
```


FieldBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created field. Fields are created with the `TypeBuilder.DefineField()` which allows you to specify the field's characteristics using the `System.Reflection.FieldAttributes` or `FieldAttributes`. The `TypeBuilder.DefineField()` method also determines the name and type of the field. Fields must have a data type such as a string or integer. Use `SetConstant()` to set the default value of the field.

```
public sealed class FieldBuilder : System.Reflection.FieldInfo {
    // Public Instance Properties
    public override FieldAttributes Attributes {get; }
    // overrides System.Reflection.FieldInfo
    public override Type DeclaringType {get; }
    // overrides System.Reflection.MemberInfo
    public override RuntimeFieldHandle FieldHandle {get; }
    //overrides System.Reflection.FieldInfo
    public override Type FieldType {get; }
    // overrides System.Reflection.FieldInfo
    public override string Name {get; }
    // overrides System.Reflection.MemberInfo
    public override Type ReflectedType {get; }
    // overrides System.Reflection.MemberInfo
    // Public Instance Methods
    public override object[] GetCustomAttributes(bool inherit)
    // overrides System.Reflection.MemberInfo
    public override object[] GetCustomAttributes(Type attributeType, bool inherit)
    // overrides System.Reflection.MemberInfo
    public FieldToken GetToken();
    public override object GetValue(object obj);
    // overrides System.Reflection.FieldInfo
    public override bool IsDefined(Type attributeType, bool inherit)
    // overrides System.Reflection.MemberInfo
    public void SetConstant(object defaultValue);
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con, byte[] binary);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetMarshal(UnmanagedMarshal unmanagedMarshal);
    public void SetOffset(int iOffset);
    public override void SetValue(object obj, object val, System.Reflection.BindingFlags
        System.Reflection.Binder binder, System.Globalization.CultureInfo culture);
    // overrides System.Reflection.FieldInfo
}
```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvide
System.Reflection.FieldInfo → FieldBuilder

Returned By

EnumBuilder.{DefineLiteral(), UnderlyingField} , ModuleBuilder.{DefineInitializedData()
DefineUninitializedData()} , TypeBuilder.{DefineField() , DefineInitializedData() ,
DefineUninitializedData()}

[Team LiB]

◀ PREVIOUS NEXT ▶

FieldToken serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a field. See [EventToken](#) for more details on tokens.

```
public struct FieldToken {  
    // Public Static Fields  
    public static readonly FieldToken Empty;  
    // =System.Reflection.Emit.FieldToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → FieldToken

Returned By

FieldBuilder.GetToken(), ModuleBuilder.GetFieldToken()

FlowControl

serializable

System.Reflection.Emit (mscorlib.dll)

enum

This enumeration is used by the `OpCode.FlowControl` property. It describes how the instruction alters the flow of control. `Next` indicates a normal flow of control, while `Cond_Branch` indicates a conditional branch instruction. The `Meta` value provides information about a subsequent instruction.

```
public enum FlowControl {
    Branch = 0,
    Break = 1,
    Call = 2,
    Cond_Branch = 3,
    Meta = 4,
    Next = 5,
    Phi = 6,
    Return = 7,
    Throw = 8
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `FlowControl`

Returned By

`OpCode.FlowControl`

ILGenerator

System.Reflection.Emit (mscorlib.dll) *class*

This class generates MSIL (Microsoft Intermediate Language) instructions. You receive an `ILGenerator` via the `GetILGenerator` method in a builder class. For example, you can use the `ConstructorBuilder.GetILGenerator` to create MSIL instructions for a constructor, or `MethodBuilder.GetILGenerator` to create MSIL instructions for a method. You can use `BeginScope` and `EndScope` to start and stop a lexical scope.

To emit instructions, use the `Emit` method. The `Emit` method requires an `OpCode` object. The easiest way is by using one of the constant fields from `OpCodes`, as in `myGenerator.Emit(OpCodes.Ret);`. You can also emit MSIL code required to call `System.Console.WriteLine` with the supplied variable. You can also define instruction stream (`DefineLabel` and `MarkLabel`), emit an instruction for throwing an exception (`Throw`) and define local variables (`DeclareLocal`).

Emit error handling blocks with `BeginExceptionBlock` and `EndExceptionBlock` (which emits the statement), `BeginCatchBlock` (which emits the equivalent of the `catch` statement), and `BeginFinallyBlock` (which emits the equivalent of the `finally` statement). You must end the exception block using `EndExceptionBlock`.

```
public class ILGenerator {
// Public Instance Methods
    public virtual void BeginCatchBlock(Type exceptionType);
    public virtual void BeginExceptFilterBlock();
    public virtual Label BeginExceptionBlock();
    public virtual void BeginFaultBlock();
    public virtual void BeginFinallyBlock();
    public virtual void BeginScope();
    public LocalBuilder DeclareLocal(Type localType);
    public virtual Label DefineLabel();
    public virtual void Emit(OpCode opcode);
    public virtual void Emit(OpCode opcode, byte arg);
    public virtual void Emit(OpCode opcode, System.Reflection.ConstructorInfo con);
    public virtual void Emit(OpCode opcode, double arg);
    public virtual void Emit(OpCode opcode, System.Reflection.FieldInfo field);
    public virtual void Emit(OpCode opcode, short arg);
    public virtual void Emit(OpCode opcode, int arg);
    public virtual void Emit(OpCode opcode, long arg);
    public virtual void Emit(OpCode opcode, Label label);
    public virtual void Emit(OpCode opcode, Label[] labels);
    public virtual void Emit(OpCode opcode, LocalBuilder local);
    public virtual void Emit(OpCode opcode, System.Reflection.MethodInfo meth);
    public void Emit(OpCode opcode, sbyte arg);
    public virtual void Emit(OpCode opcode, SignatureHelper signature);
    public virtual void Emit(OpCode opcode, float arg);
    public virtual void Emit(OpCode opcode, string str);
}
```

```
public virtual void Emit(OpCode opcode, Type cls);
public void EmitCall(OpCode opcode, System.Reflection.MethodInfo methodInfo,
    Type[] optionalParameterTypes);
public void EmitCalli(OpCode opcode, System.Reflection.CallingConventions callingCon
    Type returnType, Type[] parameterTypes, Type[] optionalParameterTypes);
public void EmitCalli(OpCode opcode, System.Runtime.InteropServices.CallingConventio
    Type returnType, Type[] parameterTypes);
public virtual void EmitWriteLine(System.Reflection.FieldInfo fld);
public virtual void EmitWriteLine(LocalBuilder localBuilder);
public virtual void EmitWriteLine(string value);
public virtual void EndExceptionBlock( );
public virtual void EndScope( );
public virtual void MarkLabel(Label loc);
public virtual void MarkSequencePoint(System.Diagnostics.SymbolStore.ISymbolDocumentV
    int startLine, int startColumn, int endLine, int endColumn);
public virtual void ThrowException(Type excType);
public void UsingNamespace(string usingNamespace);
}
```

Returned By

```
ConstructorBuilder.GetILGenerator( ) , MethodBuilder.GetILGenerator( )
```

[Team LiB]

Label

serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents a label in the MSIL instruction stream. You can create a label with `ILGenerator.DefineLabel()` and place it in the stream with `ILGenerator.MarkLabel()`.

```
public struct Label {  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → Label

Returned By

`ILGenerator.BeginExceptionBlock(), DefineLabel()`

Passed To

`ILGenerator.Emit(), MarkLabel()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

LocalBuilder

System.Reflection.Emit
(mscorlib.dll)

sealed
class

This class represents a dynamically created local variable. Local variables are created for methods and constructors through the `ILGenerator` object, using the `ILGenerator.DeclareLocal()`.

```
public sealed class LocalBuilder {  
    // Public Instance Properties  
    public Type LocalType {get; }  
    // Public Instance Methods  
    public void SetLocalSymInfo(string name);  
    public void SetLocalSymInfo(string name, int startOffset, int endOffset);  
}
```

Returned By

```
ILGenerator.DeclareLocal( )
```

Passed To

```
ILGenerator.{Emit( ), EmitWriteLine( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MethodBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created method. Methods are created with `TypeBuilder.DefineMethod` a method, specify the name, parameters, and return type. You can also specify other characteristics of the method, whether it is static, abstract, or virtual, by using the `System.Reflection.MethodAttributes` enumeration. Using the `SetMarshalMethod` method, you can specify how the return value will be marshaled to unmanaged code using `SetMarshalMethod`. You can also declarative security using `AddDeclarativeSecurity()`. You must specify the security action (such as `SecurityActionDeny`) using the `System.Security.Permissions.SecurityAction` enumeration and the permissions required to use the method using the `System.Security.PermissionSet` collection class. You can call `AddDeclarativeSecurity()` several times to add multiple security actions.

To create a global method builder, use `ModuleBuilder.DefineGlobalMethod()`. You must also use `ModuleBuilder.CreateGlobalFunctions()` to finish creating global methods before you persist or use the assembly. Global methods must be static. You can also create a global native method using `ModuleBuilder.DefinePInvokeMethod`. PInvoke methods cannot be abstract or virtual.

```
public sealed class MethodBuilder : System.Reflection.MethodInfo {
    // Public Instance Properties
    public override MethodAttributes Attributes {get; }
    // overrides System.Reflection.MethodBase
    public override CallingConventions CallingConvention {get; }
    // overrides System.Reflection.MethodBase
    public override Type DeclaringType {get; }
    // overrides System.Reflection.MemberInfo
    public bool InitLocals {set; get; }
    public override RuntimeMethodHandle MethodHandle {get; }
    // overrides System.Reflection.MethodBase
    public override string Name {get; }
    // overrides System.Reflection.MemberInfo
    public override Type ReflectedType {get; }
    // overrides System.Reflection.MemberInfo
    public override Type ReturnType {get; }
    // overrides System.Reflection.MethodInfo
    public override ICustomAttributeProvider ReturnTypeCustomAttributes {get; }
    // overrides System.Reflection.MethodInfo
    public string Signature {get; }
    // Public Instance Methods
    public void AddDeclarativeSecurity(System.Security.Permissions.SecurityAction action,
        System.Security.PermissionSet pset);
    public void CreateMethodBody(byte[] il, int count);
    public ParameterBuilder DefineParameter(int position, System.Reflection.ParameterAttribute
        string strParamName);
}
```

```

    public override bool Equals(object obj);
// overrides object
    public override MethodInfo GetBaseDefinition( );
// overrides System.Reflection.MethodInfo
    public override object[ ] GetCustomAttributes(bool inherit)
// overrides System.Reflection.MemberInfo
    public override object[ ] GetCustomAttributes(Type attributeType,bool inherit)
// overrides System.Reflection.MemberInfo
    public override int GetHashCode( );
// overrides object
    public ILGenerator GetILGenerator( );
    public ILGenerator GetILGenerator(int size);
    public override MethodImplAttributes GetMethodImplementationFlags( )
// overrides System.Reflection.MethodBase
    public Module GetModule( );
    public override ParameterInfo[ ] GetParameters( );
// overrides System.Reflection.MethodBase
    public MethodToken GetToken( );
    public override object Invoke(object obj, System.Reflection.BindingFlags invokeAttr,
        System.Reflection.Binder binder,
        object[ ] parameters, System.Globalization.CultureInfo culture)
// overrides System.Reflection.MethodBase
    public override bool IsDefined(Type attributeType, bool inherit);
// overrides System.Reflection.MemberInfo
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con, byte[ ] binary)
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetImplementationFlags(System.Reflection.MethodImplAttributes attributes)
    public void SetMarshal(UnmanagedMarshal unmanagedMarshal);
    public void SetSymCustomAttribute(string name, byte[ ] data);
    public override string ToString( );
// overrides object
}

```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvide
 System.Reflection.MethodBase → System.Reflection.MethodInfo → MethodBuilder

Returned By

ModuleBuilder.{DefineGlobalMethod(), DefinePInvokeMethod()}, TypeBuilder.{DefineMethod
 DefinePInvokeMethod()}

Passed To

EventBuilder.{AddOtherMethod(), SetAddOnMethod(), SetRaiseMethod(), SetRemoveOnMethod
 PropertyBuilder.{AddOtherMethod(), SetGetMethod(), SetSetMethod()}

[Team LiB]

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

MethodRental

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class can be used to swap a method "body" (the MSIL code inside the method). To do this, use the static `SwapMethodBody()` method and specify the target `Type`, the token of the method that should receive the new body, a pointer to the new method, the size of the new method, and a `flag` specifying the type of compilation using the appropriate field constant (either `JitImmediate` or `JitOnDemand`). The `IntPtr` to the new method body should point to an array of `bytes` that contain the IL for the method's header and body.

```
public sealed class MethodRental {  
    // Public Static Fields  
    public const int JitImmediate;  
    // =1  
    public const int JitOnDemand;  
    // =0  
    // Public Static Methods  
    public static void SwapMethodBody(Type cls, int methodtoken, IntPtr rgIL,  
        int methodSize, int flags);  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

MethodToken

serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a method. See [EventToken](#) for more details on tokens.

```
public struct MethodToken {  
    // Public Static Fields  
    public static readonly MethodToken Empty;  
    // =System.Reflection.Emit.MethodToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → MethodToken

Returned By

```
ConstructorBuilder.GetToken( ), MethodBuilder.GetToken( ),  
ModuleBuilder.{GetArrayMethodToken( ), GetConstructorToken( ), GetMethodToken( )}
```

ModuleBuilder

System.Reflection.Emit (mscorlib.dll) *class*

This class represents a dynamically created module inside a dynamic assembly. Dynamic modules are created by the `AssemblyBuilder.DefineDynamicModule()` method. A dynamic module can be either transient or persisted to disk as part of a PE file. To create a persistable module, use a version of the `AssemblyBuilder.DefineDynamicModule()` that allows you to specify a filename.

You can use the methods that begin with `Define` to create types, managed and unmanaged resources, global (global native) methods.

```
public class ModuleBuilder : System.Reflection.Module {
    // Public Instance Properties
    public override string FullyQualifiedName {get; }
    // overrides System.Reflection.Module
    // Public Instance Methods
    public void CreateGlobalFunctions( );
    public ISymbolDocumentWriter DefineDocument(string url, Guid language, Guid language
        Guid documentType);
    public EnumBuilder DefineEnum(string name, System.Reflection.TypeAttributes visibility,
        Type underlyingType);
    public MethodBuilder DefineGlobalMethod(string name, System.Reflection.MethodAttributes attributes,
        System.Reflection.CallingConventions callingConvention, Type returnType, Type[ ] parameterTypes);
    public MethodBuilder DefineGlobalMethod(string name, System.Reflection.MethodAttributes attributes,
        Type returnType, Type[ ] parameterTypes);
    public FieldBuilder DefineInitializedData(string name, byte[ ] data,
        System.Reflection.FieldAttributes attributes);
    public MethodBuilder DefinePInvokeMethod(string name, string dllName,
        System.Reflection.MethodAttributes attributes,
        System.Reflection.CallingConventions callingConvention,
        Type returnType,
        Type[ ] parameterTypes, System.Runtime.InteropServices.CallingConvention nativeCallingConvention,
        System.Runtime.InteropServices.CharSet nativeCharSet);
    public MethodBuilder DefinePInvokeMethod(string name, string dllName, string entryName,
        System.Reflection.MethodAttributes attributes,
        System.Reflection.CallingConventions callingConvention,
        Type returnType, Type[ ] parameterTypes, System.Runtime.InteropServices.CallingConvention nativeCallingConvention,
        System.Runtime.InteropServices.CharSet nativeCharSet);
    public IResourceWriter DefineResource(string name, string description);
    public IResourceWriter DefineResource(string name, string description,
        System.Reflection.ResourceAttributes attribute);
    public TypeBuilder DefineType(string name);
    public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr);
}
```

```

public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr, Type
public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr, Type
    int typesize);
public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr, Type
    PackingSize packsize);
public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr, Type
    PackingSize packingSize, int typesize);
public TypeBuilder DefineType(string name, System.Reflection.TypeAttributes attr, Type
    Type[] interfaces);
public FieldBuilder DefineUninitializedData(string name, int size, System.Reflection
public void DefineUnmanagedResource(byte[] resource);
public void DefineUnmanagedResource(string resourceFileName);
public MethodInfo GetArrayMethod(Type arrayClass, string methodName,
    System.Reflection.CallingConventions callingConvention, Type returnType, Type[]
public MethodToken GetArrayMethodToken(Type arrayClass, string methodName,
    System.Reflection.CallingConventions callingConvention, Type returnType, Type[]
public MethodToken GetConstructorToken(System.Reflection.ConstructorInfo con);
public FieldToken GetFieldToken(System.Reflection.FieldInfo field);
public MethodToken GetMethodToken(System.Reflection.MethodInfo method);
public SignatureToken GetSignatureToken(byte[] sigBytes, int sigLength);
public SignatureToken GetSignatureToken(SignatureHelper sigHelper);
public StringToken GetStringConstant(string str);
public ISymbolWriter GetSymWriter( );
public override Type GetType(string className);
// overrides System.Reflection.Module
public override Type GetType(string className, bool ignoreCase);
// overrides System.Reflection.Module
public override Type GetType(string className, bool throwOnError, bool ignoreCase)
// overrides System.Reflection.Module
public override Type[] GetTypes( );
// overrides System.Reflection.Module
public TypeToken GetTypeToken(string name);
public TypeToken GetTypeToken(Type type);
public bool IsTransient( );
public void SetCustomAttribute(System.Reflection.ConstructorInfo con,
    byte[] binaryAttribute);
public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
public void SetSymCustomAttribute(string name, byte[] data);
public void SetUserEntryPoint(System.Reflection.MethodInfo entryPoint);
}

```

Hierarchy

System.Object → System.Reflection.Module(System.Runtime.Serialization.ISerializable ,
System.Reflection.ICustomAttributeProvider) → ModuleBuilder

Returned By

```
AssemblyBuilder.{DefineDynamicModule( ), GetDynamicModule( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

OpCode

System.Reflection.Emit (mscorlib.dll) *struct*

This structure describes a single MSIL instruction. It is used by the `ILGenerator.Emit()` method. Alternatively, use a field from the `OpCodes` class to supply a specific instruction without needing to create an `OpCode` object. Instructions are characterized by several pieces of information, represented as properties, such as `OpCode`, `Operand`, and flow control.

```
public struct OpCode {  
    // Public Instance Properties  
    public FlowControl FlowControl {get; }  
    public string Name {get; }  
    public OpCodeType OpCodeType {get; }  
    public OperandType OperandType {get; }  
    public int Size {get; }  
    public StackBehaviour StackBehaviourPop {get; }  
    public StackBehaviour StackBehaviourPush {get; }  
    public short Value {get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
    public override string ToString( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → OpCode

Passed To

ILGenerator.{Emit(), EmitCall(), EmitCalli()}, OpCodes.TakesSingleByteArgument()

OpCodes

System.Reflection.Emit (mscorlib.dll) *class*

This class provides the set of MSIL instructions through static fields. Each field returns the `OpCode` object that represents the corresponding instruction, and can be used in the `ILGenerator.Emit()` method. For a detailed description of these opcodes, see *Partition III, CIL* of the ECMA CLI specification (<http://msdn.microsoft.com/net/ecma/>).

```
public class OpCodes {
// Public Static Fields
    public static readonly OpCode Add;
// =add
    public static readonly OpCode Add_Ovf;
// =add.ovf
    public static readonly OpCode Add_Ovf_Un;
// =add.ovf.un
    public static readonly OpCode And;
// =and
    public static readonly OpCode Arglist;
// =arglist
    public static readonly OpCode Beq;
// =beq
    public static readonly OpCode Beq_S;
// =beq.s
    public static readonly OpCode Bge;
// =bge
    public static readonly OpCode Bge_S;
// =bge.s
    public static readonly OpCode Bge_Un;
// =bge.un
    public static readonly OpCode Bge_Un_S;
// =bge.un.s
    public static readonly OpCode Bgt;
// =bgt
    public static readonly OpCode Bgt_S;
// =bgt.s
    public static readonly OpCode Bgt_Un;
// =bgt.un
    public static readonly OpCode Bgt_Un_S;
// =bgt.un.s
    public static readonly OpCode Ble;
// =ble
    public static readonly OpCode Ble_S;
// =ble.s
```

```

    public static readonly OpCode Ble_Un;
// =ble.un
    public static readonly OpCode Ble_Un_S;
// =ble.un.s
    public static readonly OpCode Blt;
// =blt
    public static readonly OpCode Blt_S;
// =blt.s
    public static readonly OpCode Blt_Un;
// =blt.un
    public static readonly OpCode Blt_Un_S;
// =blt.un.s
    public static readonly OpCode Bne_Un;
// =bne.un
    public static readonly OpCode Bne_Un_S;
// =bne.un.s
    public static readonly OpCode Box;
// =box
    public static readonly OpCode Br;
// =br
    public static readonly OpCode Br_S;
// =br.s
    public static readonly OpCode Break;
// =break
    public static readonly OpCode Brfalse;
// =brfalse
    public static readonly OpCode Brfalse_S;
// =brfalse.s
    public static readonly OpCode Brtrue;
// =brtrue
    public static readonly OpCode Brtrue_S;
// =brtrue.s
    public static readonly OpCode Call;
// =call
    public static readonly OpCode Calli;
// =calli
    public static readonly OpCode Callvirt;
// =callvirt
    public static readonly OpCode Castclass;
// =castclass
    public static readonly OpCode Ceq;
// =ceq
    public static readonly OpCode Cgt;
// =cgt
    public static readonly OpCode Cgt_Un;
// =cgt.un
    public static readonly OpCode Ckfinite;
// =ckfinite
    public static readonly OpCode Clt;
// =clt

```

```

    public static readonly OpCode Clt_Un;
// =clt.un
    public static readonly OpCode Conv_I;
// =conv.i
    public static readonly OpCode Conv_I1;
// =conv.i1
    public static readonly OpCode Conv_I2;
// =conv.i2
    public static readonly OpCode Conv_I4;
// =conv.i4
    public static readonly OpCode Conv_I8;
// =conv.i8
    public static readonly OpCode Conv_Ovf_I;
// =conv.ovf.i
    public static readonly OpCode Conv_Ovf_I_Un;
// =conv.ovf.i.un
    public static readonly OpCode Conv_Ovf_I1;
// =conv.ovf.i1
    public static readonly OpCode Conv_Ovf_I1_Un;
// =conv.ovf.i1.un
    public static readonly OpCode Conv_Ovf_I2;
// =conv.ovf.i2
    public static readonly OpCode Conv_Ovf_I2_Un;
// =conv.ovf.i2.un
    public static readonly OpCode Conv_Ovf_I4;
// =conv.ovf.i4
    public static readonly OpCode Conv_Ovf_I4_Un;
// =conv.ovf.i4.un
    public static readonly OpCode Conv_Ovf_I8;
// =conv.ovf.i8
    public static readonly OpCode Conv_Ovf_I8_Un;
// =conv.ovf.i8.un
    public static readonly OpCode Conv_Ovf_U;
// =conv.ovf.u
    public static readonly OpCode Conv_Ovf_U_Un;
// =conv.ovf.u.un
    public static readonly OpCode Conv_Ovf_U1;
// =conv.ovf.u1
    public static readonly OpCode Conv_Ovf_U1_Un;
// =conv.ovf.u1.un
    public static readonly OpCode Conv_Ovf_U2;
// =conv.ovf.u2
    public static readonly OpCode Conv_Ovf_U2_Un;
// =conv.ovf.u2.un
    public static readonly OpCode Conv_Ovf_U4;
// =conv.ovf.u4
    public static readonly OpCode Conv_Ovf_U4_Un;
// =conv.ovf.u4.un
    public static readonly OpCode Conv_Ovf_U8;
// =conv.ovf.u8

```

```

    public static readonly OpCode Conv_Ovf_U8_Un ;
// =conv.ovf.u8.un
    public static readonly OpCode Conv_R_Un ;
// =conv.r.un
    public static readonly OpCode Conv_R4 ;
// =conv.r4
    public static readonly OpCode Conv_R8 ;
// =conv.r8
    public static readonly OpCode Conv_U ;
// =conv.u
    public static readonly OpCode Conv_U1 ;
// =conv.u1
    public static readonly OpCode Conv_U2 ;
// =conv.u2
    public static readonly OpCode Conv_U4 ;
// =conv.u4
    public static readonly OpCode Conv_U8 ;
// =conv.u8
    public static readonly OpCode Cpblk ;
// =cpblk
    public static readonly OpCode Cpobj ;
// =cpobj
    public static readonly OpCode Div ;
// =div
    public static readonly OpCode Div_Un ;
// =div.un
    public static readonly OpCode Dup ;
// =dup
    public static readonly OpCode Endfilter ;
// =endfilter
    public static readonly OpCode Endfinally ;
// =endfinally
    public static readonly OpCode Initblk ;
// =initblk
    public static readonly OpCode Initobj ;
// =initobj
    public static readonly OpCode Isinst ;
// =isinst
    public static readonly OpCode Jump ;
// =jmp
    public static readonly OpCode Ldarg ;
// =ldarg
    public static readonly OpCode Ldarg_0 ;
// =ldarg.0
    public static readonly OpCode Ldarg_1 ;
// =ldarg.1
    public static readonly OpCode Ldarg_2 ;
// =ldarg.2
    public static readonly OpCode Ldarg_3 ;
// =ldarg.3

```

```

    public static readonly OpCode Ldarg_S;
// =ldarg.s
    public static readonly OpCode Ldarga;
// =ldarga
    public static readonly OpCode Ldarga_S;
// =ldarga.s
    public static readonly OpCode Ldc_I4;
// =ldc.i4
    public static readonly OpCode Ldc_I4_0;
// =ldc.i4.0
    public static readonly OpCode Ldc_I4_1;
// =ldc.i4.1
    public static readonly OpCode Ldc_I4_2;
// =ldc.i4.2
    public static readonly OpCode Ldc_I4_3;
// =ldc.i4.3
    public static readonly OpCode Ldc_I4_4;
// =ldc.i4.4
    public static readonly OpCode Ldc_I4_5;
// =ldc.i4.5
    public static readonly OpCode Ldc_I4_6;
// =ldc.i4.6
    public static readonly OpCode Ldc_I4_7;
// =ldc.i4.7
    public static readonly OpCode Ldc_I4_8;
// =ldc.i4.8
    public static readonly OpCode Ldc_I4_M1;
// =ldc.i4.m1
    public static readonly OpCode Ldc_I4_S;
// =ldc.i4.s
    public static readonly OpCode Ldc_I8;
// =ldc.i8
    public static readonly OpCode Ldc_R4;
// =ldc.r4
    public static readonly OpCode Ldc_R8;
// =ldc.r8
    public static readonly OpCode Ldelem_I;
// =ldelem.i
    public static readonly OpCode Ldelem_I1;
// =ldelem.i1
    public static readonly OpCode Ldelem_I2;
// =ldelem.i2
    public static readonly OpCode Ldelem_I4;
// =ldelem.i4
    public static readonly OpCode Ldelem_I8;
// =ldelem.i8
    public static readonly OpCode Ldelem_R4;
// =ldelem.r4
    public static readonly OpCode Ldelem_R8;
// =ldelem.r8

```

```

    public static readonly OpCode Ldelem_Ref;
// =ldelem.ref
    public static readonly OpCode Ldelem_U1;
// =ldelem.u1
    public static readonly OpCode Ldelem_U2;
// =ldelem.u2
    public static readonly OpCode Ldelem_U4;
// =ldelem.u4
    public static readonly OpCode Ldelema;
// =ldelema
    public static readonly OpCode Ldfld;
// =ldfld
    public static readonly OpCode Ldflda;
// =ldflda
    public static readonly OpCode Ldftn;
// =ldftn
    public static readonly OpCode Ldind_I;
// =ldind.i
    public static readonly OpCode Ldind_I1;
// =ldind.i1
    public static readonly OpCode Ldind_I2;
// =ldind.i2
    public static readonly OpCode Ldind_I4;
// =ldind.i4
    public static readonly OpCode Ldind_I8;
// =ldind.i8
    public static readonly OpCode Ldind_R4;
// =ldind.r4
    public static readonly OpCode Ldind_R8;
// =ldind.r8
    public static readonly OpCode Ldind_Ref;
// =ldind.ref
    public static readonly OpCode Ldind_U1;
// =ldind.u1
    public static readonly OpCode Ldind_U2;
// =ldind.u2
    public static readonly OpCode Ldind_U4;
// =ldind.u4
    public static readonly OpCode Ldlen;
// =ldlen
    public static readonly OpCode Ldloc;
// =ldloc
    public static readonly OpCode Ldloc_0;
// =ldloc.0
    public static readonly OpCode Ldloc_1;
// =ldloc.1
    public static readonly OpCode Ldloc_2;
// =ldloc.2
    public static readonly OpCode Ldloc_3;
// =ldloc.3

```

```

    public static readonly OpCode Ldloc_S;
// =ldloc.s
    public static readonly OpCode Ldloca;
// =ldloca
    public static readonly OpCode Ldloca_S;
// =ldloca.s
    public static readonly OpCode Ldnull;
// =ldnull
    public static readonly OpCode Ldobj;
// =ldobj
    public static readonly OpCode Ldsfld;
// =ldsfld
    public static readonly OpCode Ldsflda;
// =ldsflda
    public static readonly OpCode Ldstr;
// =ldstr
    public static readonly OpCode Ldtoken;
// =ldtoken
    public static readonly OpCode Ldvirtftn;
// =ldvirtftn
    public static readonly OpCode Leave;
// =leave
    public static readonly OpCode Leave_S;
// =leave.s
    public static readonly OpCode Localloc;
// =localloc
    public static readonly OpCode Mkrefany;
// =mkrefany
    public static readonly OpCode Mul;
// =mul
    public static readonly OpCode Mul_Ovf;
// =mul.ovf
    public static readonly OpCode Mul_Ovf_Un;
// =mul.ovf.un
    public static readonly OpCode Neg;
// =neg
    public static readonly OpCode Newarr;
// =newarr
    public static readonly OpCode Newobj;
// =newobj
    public static readonly OpCode Nop;
// =nop
    public static readonly OpCode Not;
// =not
    public static readonly OpCode Or;
// =or
    public static readonly OpCode Pop;
// =pop
    public static readonly OpCode Prefix1;
// =prefix1

```

```

    public static readonly OpCode Prefix2;
// =prefix2
    public static readonly OpCode Prefix3;
// =prefix3
    public static readonly OpCode Prefix4;
// =prefix4
    public static readonly OpCode Prefix5;
// =prefix5
    public static readonly OpCode Prefix6;
// =prefix6
    public static readonly OpCode Prefix7;
// =prefix7
    public static readonly OpCode Prefixref;
// =prefixref
    public static readonly OpCode Refanytype;
// =refanytype
    public static readonly OpCode Refanyval;
// =refanyval
    public static readonly OpCode Rem;
// =rem
    public static readonly OpCode Rem_Un;
// =rem.un
    public static readonly OpCode Ret;
// =ret
    public static readonly OpCode Rethrow;
// =rethrow
    public static readonly OpCode Shl;
// =shl
    public static readonly OpCode Shr;
// =shr
    public static readonly OpCode Shr_Un;
// =shr.un
    public static readonly OpCode Sizeof;
// =sizeof
    public static readonly OpCode Starg;
// =starg
    public static readonly OpCode Starg_S;
// =starg.s
    public static readonly OpCode Stelem_I;
// =stelem.i
    public static readonly OpCode Stelem_I1;
// =stelem.i1
    public static readonly OpCode Stelem_I2;
// =stelem.i2
    public static readonly OpCode Stelem_I4;
// =stelem.i4
    public static readonly OpCode Stelem_I8;
// =stelem.i8
    public static readonly OpCode Stelem_R4;
// =stelem.r4

```



```

    public static readonly OpCode Stelem_R8 ;
// =stelem.r8
    public static readonly OpCode Stelem_Ref ;
// =stelem.ref
    public static readonly OpCode Stfld ;
// =stfld
    public static readonly OpCode Stind_I ;
// =stind.i
    public static readonly OpCode Stind_I1 ;
// =stind.i1
    public static readonly OpCode Stind_I2 ;
// =stind.i2
    public static readonly OpCode Stind_I4 ;
// =stind.i4
    public static readonly OpCode Stind_I8 ;
// =stind.i8
    public static readonly OpCode Stind_R4 ;
// =stind.r4
    public static readonly OpCode Stind_R8 ;
// =stind.r8
    public static readonly OpCode Stind_Ref ;
// =stind.ref
    public static readonly OpCode Stloc ;
// =stloc
    public static readonly OpCode Stloc_0 ;
// =stloc.0
    public static readonly OpCode Stloc_1 ;
// =stloc.1
    public static readonly OpCode Stloc_2 ;
// =stloc.2
    public static readonly OpCode Stloc_3 ;
// =stloc.3
    public static readonly OpCode Stloc_S ;
// =stloc.s
    public static readonly OpCode Stobj ;
// =stobj
    public static readonly OpCode Stsfld ;
// =stsfld
    public static readonly OpCode Sub ;
// =sub
    public static readonly OpCode Sub_Ovf ;
// =sub.ovf
    public static readonly OpCode Sub_Ovf_Un ;
// =sub.ovf.un
    public static readonly OpCode Switch ;
// =switch
    public static readonly OpCode Tailcall ;
// =tail.
    public static readonly OpCode Throw ;
// =throw

```

```
    public static readonly OpCode Unaligned;  
    // =unaligned.  
    public static readonly OpCode Unbox;  
    // =unbox  
    public static readonly OpCode Volatile;  
    // =volatile.  
    public static readonly OpCode Xor;  
    // =xor  
    // Public Static Methods  
    public static bool TakesSingleByteArgument(OpCode inst);  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

OpCodeType

serializable

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration specifies the type of an MSIL OpCode, which is provided through the `OpCode.OpCodeType` property. These types include `Annotation` (an instruction that carries extra information for specific MSIL processors, but can usually be ignored), `Macro` (a synonym for another MSIL instruction), `Nternal` (a reserved instruction), `Objmodel` (an instruction that applies to objects), `Prefix` (an instruction that specifies an action that must be taken before the next instruction is executed), and `Primitive` (a built-in instruction).

```
public enum OpCodeType {
    Annotation = 0,
    Macro = 1,
    Nternal = 2,
    Objmodel = 3,
    Prefix = 4,
    Primitive = 5
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `OpCodeType`

Returned By

`OpCode.OpCodeType`

OperandType

serializable

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration specifies the operand type of an MSIL OpCode, which is provided through the `OpCode.OperandType` property. Operands include tokens (`InlineField`, `InlineMethod`, `InlineType`, and `InlineTok`) and integers (`InlineI8`, `InlineI8`, `ShortInlineI`, and `ShortInlineR`).

```
public enum OperandType {
    InlineBrTarget = 0 ,
    InlineField = 1 ,
    InlineI = 2 ,
    InlineI8 = 3 ,
    InlineMethod = 4 ,
    InlineNone = 5 ,
    InlinePhi = 6 ,
    InlineR = 7 ,
    InlineSig = 9 ,
    InlineString = 10 ,
    InlineSwitch = 11 ,
    InlineTok = 12 ,
    InlineType = 13 ,
    InlineVar = 14 ,
    ShortInlineBrTarget = 15 ,
    ShortInlineI = 16 ,
    ShortInlineR = 17 ,
    ShortInlineVar = 18
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `OperandType`

Returned By

`OpCode.OperandType`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PackingSize serializable, flag

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration defines the packing size for a type and is set in the `ModuleBuilder.DefineType()` and `TypeBuilder.DefineNestedType()` methods. The digit at the end of each value name in this enumeration specifies a number of bytes.

```
public enum PackingSize {
    Unspecified = 0x00000000 ,
    Size1 = 0x00000001 ,
    Size2 = 0x00000002 ,
    Size4 = 0x00000004 ,
    Size8 = 0x00000008 ,
    Size16 = 0x00000010
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `PackingSize`

Returned By

`TypeBuilder.PackingSize`

Passed To

`ModuleBuilder.DefineType()`, `TypeBuilder.DefineNestedType()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ParameterBuilder

System.Reflection.Emit (mscorlib.dll) *class*

This class represents a dynamically created parameter, which is created through the `MethodBuilder.DefineParameter()` or `ConstructorBuilder.DefineParameter()` method. When creating a `ParameterBuilder` with these methods, specify the name of the parameter and its position in the list of arguments. This list is 1-based, so the first parameter is given an index of 1. Use the `SetMarshal()` method to specify how the parameter is marshaled from unmanaged code. The `SetConstant()` method specifies the default value for a parameter.

```
public class ParameterBuilder {
    // Public Instance Properties
    public virtual int Attributes {get; }
    public bool IsIn {get; }
    public bool IsOptional {get; }
    public bool IsOut {get; }
    public virtual string Name {get; }
    public virtual int Position {get; }
    // Public Instance Methods
    public virtual ParameterToken GetToken( );
    public virtual void SetConstant(object defaultValue);
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con,
        byte[] binaryAttribute);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public virtual void SetMarshal(UnmanagedMarshal unmanagedMarshal);
}
```

Returned By

`ConstructorBuilder.DefineParameter()`, `MethodBuilder.DefineParameter()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ParameterToken serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a parameter. See [EventToken](#) for more details on tokens.

```
public struct ParameterToken {  
    // Public Static Fields  
    public static readonly ParameterToken Empty;  
    // =System.Reflection.Emit.ParameterToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → ParameterToken

Returned By

ParameterBuilder.GetToken()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PEFileKinds

serializable

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration is used by the `AssemblyBuilder.SetEntryPoint()` method. It specifies the type of PE file that will be created by the `AssemblyBuilder`.

```
public enum PEFileKinds {  
    Dll = 1,  
    ConsoleApplication = 2 ,  
    WindowApplication = 3  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `PEFileKinds`

Passed To

`AssemblyBuilder.SetEntryPoint()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PropertyBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created property. To create a `PropertyBuilder` object, use the `TypeBuilder.DefineProperty()` method and specify the parameter types, return value type, and any settings through the `System.Reflection.PropertyAttributes` enumeration. You can specify `MethodBuilder` the property `get` and property `set` methods using `SetGetMethod()` and `SetSetMethod()`. You can also property's default value using the `SetConstant()` method.

```
public sealed class PropertyBuilder : System.Reflection.PropertyInfo {
// Public Instance Properties
    public override PropertyAttributes Attributes{get; }
// overrides System.Reflection.PropertyInfo
    public override bool CanRead{get; }
// overrides System.Reflection.PropertyInfo
    public override bool CanWrite{get; }
// overrides System.Reflection.PropertyInfo
    public override Type DeclaringType{get; }
// overrides System.Reflection.MemberInfo
    public override string Name{get; }
// overrides System.Reflection.MemberInfo
    public PropertyToken PropertyToken{get; }
    public override Type PropertyType{get; }
// overrides System.Reflection.PropertyInfo
    public override Type ReflectedType{get; }
// overrides System.Reflection.MemberInfo
// Public Instance Methods
    public void AddOtherMethod(MethodBuilder mdBuilder);
    public override MethodInfo[] GetAccessors(bool nonPublic);
// overrides System.Reflection.PropertyInfo
    public override object[] GetCustomAttributes(bool inherit)
// overrides System.Reflection.MemberInfo
    public override object[] GetCustomAttributes(Type attributeType, bool inherit)
// overrides System.Reflection.MemberInfo
    public override MethodInfo GetGetMethod(bool nonPublic);
// overrides System.Reflection.PropertyInfo
    public override ParameterInfo[] GetIndexParameters( );
// overrides System.Reflection.PropertyInfo
    public override MethodInfo GetSetMethod(bool nonPublic);
// overrides System.Reflection.PropertyInfo
    public override object GetValue(object obj, System.Reflection.BindingFlags invokeAttr
        System.Reflection.Binder binder,
```

```

        object[ ] index, System.Globalization.CultureInfo culture);
// overrides System.Reflection.PropertyInfo
    public override object GetValue(object obj, object[ ] index);
// overrides System.Reflection.PropertyInfo
    public override bool IsDefined(Type attributeType, bool inherit)
// overrides System.Reflection.MemberInfo
    public void SetConstant(object defaultValue);
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con, byte[ ] binary);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetGetMethod(MethodBuilder mdBuilder);
    public void SetSetMethod(MethodBuilder mdBuilder);
    public override void SetValue(object obj, object value, System.Reflection.BindingFlags flags,
        System.Reflection.Binder binder, object[ ] index, System.Globalization.CultureInfo culture);
// overrides System.Reflection.PropertyInfo
    public override void SetValue(object obj, object value, object[ ] index);
// overrides System.Reflection.PropertyInfo
}

```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvider)
 System.Reflection.PropertyInfo → PropertyBuilder

Returned By

TypeBuilder.DefineProperty()

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PropertyToken serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a property. See `EventToken` for more details on tokens.

```
public struct PropertyToken {  
    // Public Static Fields  
    public static readonly PropertyToken Empty;  
    // =System.Reflection.Emit.PropertyToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → PropertyToken

Returned By

PropertyBuilder.PropertyToken

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

SignatureHelper

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class contains helper functions that allow you to build a signature for a method, such as `AddArgument`. Use one of the static methods to get a `SignatureHelper`, which you can pass to `ILGenerator.Emit()`.

```
public sealed class SignatureHelper {
// Public Static Methods
    public static SignatureHelper GetFieldSigHelper(System.Reflection.Module mod);
    public static SignatureHelper GetLocalVarSigHelper(System.Reflection.Module mod);
    public static SignatureHelper GetMethodSigHelper(System.Reflection.Module mod,
        System.Reflection.CallingConventions callingConvention, Type returnType);
    public static SignatureHelper GetMethodSigHelper(System.Reflection.Module mod,
        System.Runtime.InteropServices.CallingConvention unmanagedCallConv, Type returnType);
    public static SignatureHelper GetMethodSigHelper(System.Reflection.Module mod,
        Type returnType, Type[] parameterTypes);
    public static SignatureHelper GetPropertySigHelper(System.Reflection.Module mod,
        Type returnType, Type[] parameterTypes);
// Public Instance Methods
    public void AddArgument(Type clsArgument);
    public void AddSentinel();
    public override bool Equals(object obj);
// overrides object
    public override int GetHashCode();
// overrides object
    public byte[] GetSignature();
    public override string ToString();
// overrides object
}
```

Passed To

```
ILGenerator.Emit(), ModuleBuilder.GetSignatureToken()
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

SignatureToken

serializable

System.Reflection.Emit (mscorlib.dll)

struct

This class represents the token for a method signature. See [EventToken](#) for more details on tokens.

```
public struct SignatureToken {  
    // Public Static Fields  
    public static readonly SignatureToken Empty;  
    // =System.Reflection.Emit.SignatureToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy



Returned By

```
ModuleBuilder.GetSignatureToken( )
```

StackBehaviour

serializable

System.Reflection.Emit (mscorlib.dll) *enum*

This enumeration is used to set the `OpCode.StackBehaviourPush()` and `OpCode.StackBehaviourPop()` methods, which determine how an MSIL instruction pushes an operand onto the stack and pops it off.

```
public enum StackBehaviour {
    Pop0 = 0,
    Pop1 = 1,
    Pop1_pop1 = 2,
    Popi = 3,
    Popi_pop1 = 4,
    Popi_popi = 5,
    Popi_popi8 = 6,
    Popi_popi_popi = 7,
    Popi_popr4 = 8,
    Popi_popr8 = 9,
    Popref = 10,
    Popref_pop1 = 11,
    Popref_popi = 12,
    Popref_popi_popi = 13,
    Popref_popi_popi8 = 14,
    Popref_popi_popr4 = 15,
    Popref_popi_popr8 = 16,
    Popref_popi_popref = 17,
    Push0 = 18,
    Push1 = 19,
    Push1_push1 = 20,
    Pushi = 21,
    Pushi8 = 22,
    Pushr4 = 23,
    Pushr8 = 24,
    Pushref = 25,
    Varpop = 26,
    Varpush = 27
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → StackBehaviour

Returned By

```
OpCode. {StackBehaviourPop, StackBehaviourPush}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

StringToken

serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a string constant in a module's constant pool. See [EventToken](#) for more details on tokens.

```
public struct StringToken {  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → StringToken

Returned By

ModuleBuilder.GetStringConstant()

TypeBuilder

System.Reflection.Emit
(mscorlib.dll)

*sealed
class*

This class represents a dynamically created type in a dynamic module (`ModuleBuilder` object). Generally class or an interface. To create a `TypeBuilder`, use the overloaded `ModuleBuilder.DefineType()` method which overload you use, you can specify different information including the type name, superclass, and its interfaces. You can also use the `System.Reflection.TypeAttributes` enumeration to specify other options making a class sealed, abstract, or public, or defining it as an interface. Once the type is created, you can add such as constructors, events, fields, properties, methods, and other nested types, using the corresponding

Before using a type you created, you must use the `CreateType()` method to get a `Type` object. After that, instantiate the `Type` with the `System.Activator.CreateInstance()` method, and invoke members of the `System.Type.InvokeMember()` method. After creating a type, you can no longer use `TypeBuilder` methods to change the type, such as a `Define` method.

```
public sealed class TypeBuilder : Type {
    // Public Static Fields
    public const int UnspecifiedTypeSize;
    // =0
    // Public Instance Properties
    public override Assembly Assembly {get; }
    // overrides Type
    public override string AssemblyQualifiedName {get; }
    // overrides Type
    public override Type BaseType {get; }
    // overrides Type
    public override Type DeclaringType {get; }
    // overrides Type
    public override string FullName {get; }
    // overrides Type
    public override Guid GUID {get; }
    // overrides Type
    public override Module Module {get; }
    // overrides Type
    public override string Name {get; }
    // overrides System.Reflection.MemberInfo
    public override string Namespace {get; }
    // overrides Type
    public PackingSize PackingSize {get; }
    public override Type ReflectedType {get; }
    // overrides Type
    public int Size {get; }
    public override RuntimeTypeHandle TypeHandle {get; }
```

```

// overrides Type
public TypeToken TypeToken{get; }
public override Type UnderlyingSystemType{get; }
// overrides Type
// Public Instance Methods
public void AddDeclarativeSecurity(System.Security.Permissions.SecurityAction action,
    System.Security.PermissionSet pset);
public void AddInterfaceImplementation(Type interfaceType);
public Type CreateType( );
public ConstructorBuilder DefineConstructor(System.Reflection.MethodAttributes attributes,
    System.Reflection.CallingConventions callingConvention, Type[] parameterTypes);
public ConstructorBuilder DefineDefaultConstructor(System.Reflection.MethodAttributes attributes);
public EventBuilder DefineEvent(string name, System.Reflection.EventAttributes attributes,
    Type eventType);
public FieldBuilder DefineField(string fieldName, Type type,
    System.Reflection.FieldAttributes attributes);
public FieldBuilder DefineInitializedData(string name, byte[] data,
    System.Reflection.FieldAttributes attributes);
public MethodBuilder DefineMethod(string name, System.Reflection.MethodAttributes attributes,
    System.Reflection.CallingConventions callingConvention, Type returnType, Type[] parameterTypes);
public MethodBuilder DefineMethod(string name, System.Reflection.MethodAttributes attributes,
    Type returnType, Type[] parameterTypes);
public void DefineMethodOverride(System.Reflection.MethodInfo methodInfoBody,
    System.Reflection.MethodInfo methodInfoDeclaration);
public TypeBuilder DefineNestedType(string name);
public TypeBuilder DefineNestedType(string name, System.Reflection.TypeAttributes attributes);
public TypeBuilder DefineNestedType(string name, System.Reflection.TypeAttributes attributes,
    Type parent);
public TypeBuilder DefineNestedType(string name, System.Reflection.TypeAttributes attributes,
    Type parent, int typeSize);
public TypeBuilder DefineNestedType(string name, System.Reflection.TypeAttributes attributes,
    Type parent, PackingSize packSize);
public TypeBuilder DefineNestedType(string name, System.Reflection.TypeAttributes attributes,
    Type parent, Type[] interfaces);
public MethodBuilder DefinePInvokeMethod(string name, string dllName,
    System.Reflection.MethodAttributes attributes,
    System.Reflection.CallingConventions callingConvention,
    Type returnType, Type[] parameterTypes,
    System.Runtime.InteropServices.CallingConvention nativeCallConv,
    System.Runtime.InteropServices.CharSet nativeCharSet);
public MethodBuilder DefinePInvokeMethod(string name, string dllName, string entryName,
    System.Reflection.MethodAttributes attributes,
    System.Reflection.CallingConventions callingConvention,
    Type returnType, Type[] parameterTypes,
    System.Runtime.InteropServices.CallingConvention nativeCallConv,
    System.Runtime.InteropServices.CharSet nativeCharSet);
public PropertyBuilder DefineProperty(string name,
    System.Reflection.PropertyAttributes attributes,
    Type returnType, Type[] parameterTypes);

```

```

public ConstructorBuilder DefineTypeInitializer( );
public FieldBuilder DefineUninitializedData(string name, int size,
    System.Reflection.FieldAttributes attributes);
public override ConstructorInfo[ ] GetConstructors(System.Reflection.BindingFlags bi
// overrides Type
public override object[ ] GetCustomAttributes( bool inherit)
// overrides System.Reflection.MemberInfo
public override object[ ] GetCustomAttributes(Type attributeType,bool inherit)
// overrides System.Reflection.MemberInfo
public override Type GetElementType( );
// overrides Type
public override EventInfo GetEvent(string name, System.Reflection.BindingFlags bindi
// overrides Type
public override EventInfo[ ] GetEvents( );
// overrides Type
public override EventInfo[ ] GetEvents(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override FieldInfo GetField(string name, System.Reflection.BindingFlags bindi
// overrides Type
public override FieldInfo[ ] GetFields(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override Type GetInterface(string name, bool ignoreCase)
// overrides Type
public override InterfaceMapping GetInterfaceMap(Type interfaceType)
// overrides Type
public override Type[ ] GetInterfaces( );
// overrides Type
public override MemberInfo[ ] GetMember(string name, System.Reflection.MemberTypes t
    System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override MemberInfo[ ] GetMembers(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override MethodInfo[ ] GetMethods(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override Type GetNestedType(string name, System.Reflection.BindingFlags bindi
// overrides Type
public override Type[ ] GetNestedTypes(System.Reflection.BindingFlags bindingAttr)
// overrides Type
public override PropertyInfo[ ] GetProperties(System.Reflection.BindingFlags binding
// overrides Type
public override object InvokeMember(string name, System.Reflection.BindingFlags invo
    System.Reflection.Binder binder, object target, object[ ] args,
    System.Reflection.ParameterModifier[ ] modifiers,
    System.Globalization.CultureInfo culture, string[ ] namedParameters)
// overrides Type
public override bool IsAssignableFrom(Type c);
// overrides Type
public override bool IsDefined(Type attributeType, bool inherit)
// overrides System.Reflection.MemberInfo

```

```

    public override bool IsSubclassOf(Type c);
// overrides Type
    public void SetCustomAttribute(System.Reflection.ConstructorInfo con,
        byte[] binaryAttribute);
    public void SetCustomAttribute(CustomAttributeBuilder customBuilder);
    public void SetParent(Type parent);
    public override string ToString( );
// overrides Type
// Protected Instance Methods
    protected override TypeAttributes GetAttributeFlagsImpl( );
// overrides Type
    protected override ConstructorInfo GetConstructorImpl(System.Reflection.BindingFlags
        System.Reflection.Binder binder, System.Reflection.CallingConventions callConven
        Type[] types,
        System.Reflection.ParameterModifier[] modifiers)
// overrides Type
    protected override MethodInfo GetMethodImpl(string name, System.Reflection.BindingFl
        System.Reflection.Binder binder, System.Reflection.CallingConventions callConven
        Type[] types,
        System.Reflection.ParameterModifier[] modifiers)
// overrides Type
    protected override PropertyInfo GetPropertyImpl(string name,
        System.Reflection.BindingFlags bindingAttr, System.Reflection.Binder binder,
        Type returnType, Type[] types,
        System.Reflection.ParameterModifier[] modifiers)
// overrides Type
    protected override bool HasElementTypeImpl( );
// overrides Type
    protected override bool IsArrayImpl( );
// overrides Type
    protected override bool IsByRefImpl( );
// overrides Type
    protected override bool IsCOMObjectImpl( );
// overrides Type
    protected override bool IsPointerImpl( );
// overrides Type
    protected override bool IsPrimitiveImpl( );
// overrides Type
}

```

Hierarchy

System.Object → System.Reflection.MemberInfo(System.Reflection.ICustomAttributeProvide
 System.Type(System.Reflection.IReflect) → TypeBuilder

Returned By

ModuleBuilder.DefineType()

[Team LiB]

TypeToken

serializable

System.Reflection.Emit (mscorlib.dll) *struct*

This class represents the token for a type. See `EventToken` for more details on tokens.

```
public struct TypeToken {  
    // Public Static Fields  
    public static readonly TypeToken Empty;  
    // =System.Reflection.Emit.TypeToken  
    // Public Instance Properties  
    public int Token{get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy

System.Object → System.ValueType → TypeToken

Returned By

`EnumBuilder.TypeToken`, `ModuleBuilder.GetTypeToken()`, `TypeBuilder.TypeToken`

UnmanagedTypeMarshal

serializable

System.Reflection.Emit (mscorlib.dll)

*sealed
class*

This class defines how parameters or fields should be marshaled in function calls to unmanaged code. By applies certain format conversions automatically during this marshaling (for example, it might change a `string` to an unmanaged BSTR). Use this class to override this default behavior.

To create an instance of this class, use one of the static methods to define the unmanaged type you want to use. `DefineUnmanagedTypeMarshal()` for this purpose and specify the unmanaged type using the `System.Runtime.InteropServices.UnmanagedType` enumeration. Alternatively, use `DefineByValTStr()` for marshaling to a string in a fixed array buffer, and specify the other methods for various types of unmanaged types. All static methods all return an `UnmanagedTypeMarshal` object, with its read-only properties set accordingly. Last use `UnmanagedTypeMarshal` with the appropriate type using the `SetMarshal()` method for the `ParameterBuilder` or `FieldBuilder` class.

```
public sealed class UnmanagedTypeMarshal {  
    // Public Instance Properties  
    public UnmanagedType BaseType {get; }  
    public int ElementCount {get; }  
    public UnmanagedType GetUnmanagedType {get; }  
    public Guid IIDGuid {get; }  
    // Public Static Methods  
    public static UnmanagedTypeMarshal DefineByValArray(int elemCount);  
    public static UnmanagedTypeMarshal DefineByValTStr(int elemCount);  
    public static UnmanagedTypeMarshal DefineLPArray(System.Runtime.InteropServices.UnmanagedType unmanagedType, int elemCount);  
    public static UnmanagedTypeMarshal DefineSafeArray(System.Runtime.InteropServices.UnmanagedType unmanagedType, int elemCount);  
    public static UnmanagedTypeMarshal DefineUnmanagedTypeMarshal(UnmanagedType unmanagedType, System.Runtime.InteropServices.UnmanagedType unmanagedType);  
}
```

Passed To

`FieldBuilder.SetMarshal()`, `MethodBuilder.SetMarshal()`, `ParameterBuilder.SetMarshal()`

[\[Team LiB \]](#)[< PREVIOUS](#) [NEXT >](#)

Chapter 37. System.Runtime.InteropServices

The types in this namespace work with unmanaged code using either PInvoke or COM. PInvoke (short for Platform Invoke) lets you access functions that reside in underlying operating system-specific shared libraries (on Win32, these are DLLs). COM (Component Object Model) is a Win32 legacy component architecture that is used throughout Windows and Windows applications. Many programmers experience COM through the object models of applications such as Microsoft Office, Exchange, and SQL Server. The COM support in .NET lets you access COM components as though they were native .NET classes. For an overview of PInvoke, see [Chapter 17](#) and [Chapter 18](#). Many of the types in this namespace are custom attributes. For information on how the flags and properties of a custom attribute map to its actual usage, see [Chapter 14](#).

We have omitted some of the more esoteric parts of this namespace, so there are some classes that aren't discussed here. For the most part, you will not need those classes unless you are developing specialized code that handles marshaling data types between managed and unmanaged code. If so, you should consult the MSDN .NET reference materials. Figures [Figure 37-1](#) and [Figure 37-2](#) show the types in this namespace.

[\[Team LiB \]](#)[< PREVIOUS](#) [NEXT >](#)

ArrayWithOffset


System.Runtime.InteropServices

(mscorlib.dll)

struct

This class converts an array of value type instances to an unmanaged array. Your unmanaged code accesses this array as a pointer that initially points to the first array element. Each time the pointer increments, it points to the next element in the array. The constructor takes a mandatory `offset` argument that specifies which element should be the first element in the unmanaged array. If you want to pass the whole array, specify an offset of zero.

Figure 37-1. The System.Runtime.InteropServices namespace



```
public struct ArrayWithOffset {
```

```
// Public Constructors
public ArrayWithOffset(object array, int offset);
// Public Instance Methods
public override bool Equals(object obj);
// overrides ValueType
public object GetArray( );
public override int GetHashCode( );
// overrides ValueType
public int GetOffset( );
}
```

Hierarchy

System.Object → System.ValueType → ArrayWithOffset

[\[Team LiB \]](#)

◀ PREVIOUS


NEXT ▶

AssemblyRegistrationFlags serializable, flag

System.Runtime.InteropServices (mscorlib.dll) *enum*

This enumeration specifies the flags you can use with `IRegistrationServices.RegisterAssembly()`.

Figure 37-2. Attributes and delegates from System.Runtime.InteropServices



```
public enum AssemblyRegistrationFlags {  
    None = 0x00000000 ,  
    SetCodeBase = 0x00000001  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable,`

System.IFormattable, System.IConvertible) → AssemblyRegistrationFlags

Passed To

IRegistrationServices.RegisterAssembly(), RegistrationServices.RegisterAssembly()

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

BestFitMappingAttribute.NET 1.1

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This class determines whether Unicode characters are converted to ANSI characters by selecting the closest matching character.

```
public sealed class BestFitMappingAttribute : Attribute {  
    // Public Constructors  
    public BestFitMappingAttribute(bool BestFitMapping);  
    // Public Instance Fields  
    public bool ThrowOnUnmappableChar;  
    // Public Instance Properties  
    public bool BestFitMapping {get; }  
}
```

Hierarchy

System.Object → System.Attribute → BestFitMappingAttribute

Valid On

Assembly, Class, Struct, Interface

CallingConvention

CF 1.0, ECMA 1.0,
serializable

System.Runtime.InteropServices
(mscorlib.dll)

enum

This enumeration specifies the calling convention to use when you invoke a function. `DllImportAttribute` uses this in its `CallingConvention` parameter.

`Cdecl` specifies the standard calling convention used by C++ and C programs. This is required for functions that take a variable number of arguments, such as `printf()`. `FastCall` attempts to put function arguments into registers. `StdCall` is the convention used for calling Win32 API functions. `ThisCall` is the calling convention used by C++ member functions taking fixed arguments. Use the `Winapi` calling convention for function calls that use `PASCAL` or `_ _far _ _pascal`.

```
public enum CallingConvention {  
    Winapi = 1 ,  
    Cdecl = 2 ,  
    StdCall = 3 ,  
    ThisCall = 4 ,  
    FastCall = 5  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → CallingConvention

Passed To

```
System.Reflection.Emit.ILGenerator.EmitCalli( ),  
System.Reflection.Emit.ModuleBuilder.DefinePInvokeMethod( ),  
System.Reflection.Emit.SignatureHelper.GetMethodSigHelper( ),  
System.Reflection.Emit.TypeBuilder.DefinePInvokeMethod( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

CharSet

CF 1.0, ECMA 1.0, serializable

System.Runtime.InteropServices (mscorlib.dll)

enum

This enumeration specifies the character set that is used for marshaled strings. It is used by `DllImportAttribute` and `StructLayoutAttribute`.

`Ansi` marshals strings using one-byte ANSI characters, while `Unicode` uses two bytes to represent a single Unicode character. The `Auto` value is used only for `PInvoke` and specifies that `PInvoke` should decide how to marshal the strings based on your operating system (Unicode for Windows NT/2000/XP and ANSI for Windows 9x/Me).

```
public enum CharSet {
    None = 1,
    Ansi = 2,
    Unicode = 3,
    Auto = 4
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `CharSet`

Passed To

```
System.Reflection.Emit.ModuleBuilder.DefinePInvokeMethod( ),
System.Reflection.Emit.TypeBuilder.DefinePInvokeMethod( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

ClassInterfaceAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute specifies the interface that should be exposed to COM when you generate a type library. See `ClassInterfaceType` for the possible arguments to this attribute.

```
public sealed class ClassInterfaceAttribute : Attribute {  
    // Public Constructors  
    public ClassInterfaceAttribute(ClassInterfaceType classInterfaceType);  
    public ClassInterfaceAttribute(short classInterfaceType);  
    // Public Instance Properties  
    public ClassInterfaceType Value {get; }  
}
```

Hierarchy



Valid On

Assembly, Class

ClassInterfaceType

serializable

System.Runtime.InteropServices
(mscorlib.dll)

enum

This enumeration contains values to use as arguments for `ClassInterfaceAttribute`. `AutoDispatch` specifies that a dispatch-only interface should be generated. `AutoDual` specifies that a dual interface should be generated, and `None` specifies that no interface should be generated.

```
public enum ClassInterfaceType {  
    None = 0,  
    AutoDispatch = 1,  
    AutoDual = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ClassInterfaceType`

Returned By

`ClassInterfaceAttribute.Value`

Passed To

`ClassInterfaceAttribute.ClassInterfaceAttribute()`

CoClassAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute describes the class ID of a coclass that was imported from a type library.

```
public sealed class CoClassAttribute : Attribute {  
    // Public Constructors  
    public CoClassAttribute(Type coClass);  
    // Public Instance Properties  
    public Type CoClass {get; }  
}
```

Hierarchy

System.Object → System.Attribute → CoClassAttribute

Valid On

Interface

ComAliasNameAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is automatically added when COM type libraries are imported into the .NET runtime. COM uses alias names for various data types (such as `typedef [public] int SHOE_SIZE`). When you import a COM object that uses such an alias, .NET automatically decorates each parameter, property, field, and return value with this attribute. If you need to know the name of the COM alias, use the `System.Reflection` API to see if this custom attribute has been attached to the parameter, property, field, or return value you are interested in.

Since .NET automatically converts COM aliases to the underlying .NET types when it imports a type library, you do not need to use this attribute for typical applications (tool developers will find this attribute useful, though).

```
public sealed class ComAliasNameAttribute : Attribute {  
    // Public Constructors  
    public ComAliasNameAttribute(string alias);  
    // Public Instance Properties  
    public string Value { get; }  
}
```

Hierarchy

System.Object → System.Attribute → ComAliasNameAttribute

Valid On

Property, Field, Parameter, ReturnValue

ComCompatibleVersionAttribute .NET 1.1

System.Runtime.InteropServices *sealed*
(mscorlib.dll) *class*

This attribute tells COM clients that the types in the assembly are backward-compatible with those from an earlier version.

```
public sealed class ComCompatibleVersionAttribute : Attribute {  
    // Public Constructors  
    public ComCompatibleVersionAttribute(int major, int minor, int build, int revision);  
    // Public Instance Properties  
    public int BuildNumber{get; }  
    public int MajorVersion{get; }  
    public int MinorVersion{get; }  
    public int RevisionNumber{get; }  
}
```

Hierarchy

System.Object → System.Attribute → ComCompatibleVersionAttribute

Valid On

Assembly

ComConversionLossAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

The presence of this attribute indicates that information about a type was lost as it was imported from a type library.

```
public sealed class ComConversionLossAttribute : Attribute {  
    // Public Constructors  
    public ComConversionLossAttribute( );  
}
```

Hierarchy



Valid On

All

COMException

serializable

System.Runtime.InteropServices


(mscorlib.dll)

class

When a COM error occurs, .NET tries to map it to an exception in the .NET Framework and throws that exception. If the COM error does not map to any exception in the .NET Framework, this exception is thrown instead. It's the "couldn't find an exception" exception.

```
public class COMException : ExternalException {
// Public Constructors
    public COMException( );
    public COMException(string message);
    public COMException(string message, Exception inner);
    public COMException(string message, int errorCode);
// Protected Constructors
    protected COMException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Methods
    public override string ToString( );
// overrides Exception
}
```

Hierarchy



ComImportAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class


This attribute indicates that the type decorated by this attribute is in fact an unmanaged type defined in a previously published type library and should be treated differently internally to support that.

This attribute is necessary only if the .NET type definition-the class definition in C#-This interface indicates a type whose members can be removed or added. The members are represented as `System.Reflection.MemberInfo` objects.

is merely a "shim" for interacting with the unmanaged version. In most cases, .NET programmers only use this type when interacting with existing COM APIs, such as when building Explorer Shell Extensions.

```
public sealed class ComImportAttribute : Attribute {  
    // Public Constructors  
    public ComImportAttribute( );  
}
```

Hierarchy



Valid On

Class, Interface

ComInterfaceType

serializable

System.Runtime.InteropServices
(mscorlib.dll)

enum

This enumeration specifies the COM interface type. Use this attribute with `InterfaceTypeAttribute` to specify how your .NET interfaces are exposed to COM.

```
public enum ComInterfaceType {  
    InterfaceIsDual = 0 ,  
    InterfaceIsIUnknown = 1 ,  
    InterfaceIsIDispatch = 2  
}
```

Hierarchy

System.Object | aut System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → ComInterfaceType

Returned By

InterfaceTypeAttribute.Value

Passed To

InterfaceTypeAttribute.InterfaceTypeAttribute()

ComMemberType

serializable

System.Runtime.InteropServices (mscorlib.dll)

enum

This enumeration describes a COM member. **Method** indicates that the member is an ordinary method. **PropGet** and **PropSet** identify methods that get and set the values of properties (getters and setters).

```
public enum ComMemberType {  
    Method = 0 ,  
    PropGet = 1 ,  
    PropSet = 2  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → ComMemberType

Passed To

Marshal.GetMethodInfoForComSlot()

ComRegisterFunctionAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a static method to indicate that it should be invoked when the enclosing assembly is registered with COM. The method should take two string arguments. The first is the name of the registry key being updated, and the second is the namespace-qualified name of the type being registered (such as `System.String`). There can only be one registration function in each assembly.

Microsoft suggests that you do not use this feature and includes it only for backward compatibility. If you use this feature to specify a registration method, you must also specify an unregistration method (see `ComUnregisterFunctionAttribute`) that reverses all changes you made in the registration function.

```
public sealed class ComRegisterFunctionAttribute : Attribute {  
    // Public Constructors  
    public ComRegisterFunctionAttribute( );  
}
```

Hierarchy



Valid On

Method

ComSourceInterfacesAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute indicates the unmanaged event (using the COM IConnectionPoint architecture) interfaces that are available on the decorated type. For each method defined in the COM interface, the type must provide a corresponding "event" instance that the COM architecture will plug into.

This attribute is only necessary when building .NET objects for plugging into COM event-aware systems, such as ActiveX control containers.

```
public sealed class ComSourceInterfacesAttribute : Attribute {  
    // Public Constructors  
    public ComSourceInterfacesAttribute(string sourceInterfaces);  
    public ComSourceInterfacesAttribute(Type sourceInterface);  
    public ComSourceInterfacesAttribute(Type sourceInterface1, Type sourceInterface2);  
    public ComSourceInterfacesAttribute(Type sourceInterface1, Type sourceInterface2,  
        Type sourceInterface3);  
    public ComSourceInterfacesAttribute(Type sourceInterface1, Type sourceInterface2,  
        Type sourceInterface3, Type sourceInterface4);  
    // Public Instance Properties  
    public string Value{get; }  
}
```

Hierarchy



Valid On

Class

ComUnregisterFunctionAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a static method to indicate that it should be invoked when the enclosing assembly is unregistered from COM. There can only be one unregistration function in each assembly.

For more details, see [ComRegisterFunctionAttribute](#).

```
public sealed class ComUnregisterFunctionAttribute : Attribute {  
    // Public Constructors  
    public ComUnregisterFunctionAttribute( );  
}
```

Hierarchy



Valid On

Method

ComVisibleAttribute

CF 1.0

System.Runtime.InteropServices
(mscorlib.dll) *sealed class*

By default, all public assemblies, types, and members that are registered with COM are visible to COM. This attribute is used with a false argument to hide an assembly, type, or member from COM. This attribute has a cascading effect: if you hide an assembly, all the public types in that assembly are hidden as well.

You can override this attribute on individual types. If, for example, you want to make only one public type visible from an assembly, add the attribute `[ComVisible(false)]` to the assembly, but also add `[ComVisible(true)]` to the one type that you want to expose.

```
public sealed class ComVisibleAttribute : Attribute {  
    // Public Constructors  
    public ComVisibleAttribute(bool visibility);  
    // Public Instance Properties  
    public bool Value {get; }  
}
```

Hierarchy

System.Object → System.Attribute → ComVisibleAttribute

Valid On

Assembly, Class, Struct, Enum, Method, Property, Field, Interface, Delegate

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

CurrencyWrapper

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This class is used to create a wrapper around a decimal value. Then, when you pass the newly created **CurrencyWrapper** to an unmanaged method, the object is marshaled as the **VT_CURRENCY** type.

```
public sealed class CurrencyWrapper {  
    // Public Constructors  
    public CurrencyWrapper(decimal obj);  
    public CurrencyWrapper(object obj);  
    // Public Instance Properties  
    public decimal WrappedObject {get; }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DispatchWrapper

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

By default, objects are passed to unmanaged methods as the `VT_UNKNOWN` type. This wrapper is used to send an object as type `VT_DISPATCH`.

```
public sealed class DispatchWrapper {  
    // Public Constructors  
    public DispatchWrapper(object obj);  
    // Public Instance Properties  
    public object WrappedObject {get; }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DispIdAttribute

CF 1.0

System.Runtime.InteropServices
(mscorlib.dll) *sealed class*

Specifies a member's **DispId** when it is exposed to COM.

```
public sealed class DispIdAttribute : Attribute {  
    // Public Constructors  
    public DispIdAttribute(int dispId);  
    // Public Instance Properties  
    public int Value{get; }  
}
```

Hierarchy

System.Object → System.Attribute → DispIdAttribute

Valid On

Method, Property, Field, Event

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

DllImportAttribute

CF 1.0, ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)*sealed*
class

This attribute (and, in C#, the keyword "extern") specifies that a method definition is implemented externally (usually in a DLL). Apply this attribute to a method that has been declared (but not defined) to specify the DLL name and entry point in which the method can be found.

The attribute can be customized in a number of different ways to help control the binding against the external method. The `CallingConvention` value dictates how the parameters to the call (and return value coming back) should be sent to the function. `CallingConvention.StdCall` (used for calling into `_stdcall`-declared functions, which is most of the Win32 API set) and `CallingConvention.Cdecl` (used for calling functions declared directly from C or C++) are the two most common values. The `CharSet` value indicates which character set parameters to the call are expected to be, either two-byte Unicode or one-byte ANSI. `EntryPoint` indicates the name of the exported function from the DLL to bind to (normally this is guessed from the name of the .NET-declared method), and `ExactSpelling` indicates whether the .NET compiler should attempt to "best match" a declared `DllImport` method against a possible set of exported functions. The `PreserveSig` value indicates how .NET should treat `[out]`-declared and `[retval]`-declared parameters. By default, the .NET compilers ignore the HRESULT return value on IDL-declared methods and use the `[retval]`-declared parameter as the return value; setting `PreserveSig` to `true` turns this off. `BestFitMapping` is used to define whether the CLR should try to "best fit" Unicode characters to ANSI equivalents, and is turned on by default. `ThrowOnUnmappableChar` indicates whether an exception should be thrown when the interop marshaler attempts to convert an unmappable character, and is turned off by default. Finally, because many Win32 APIs use the `GetLastError` API call to note the exact reason a call fails, the `SetLastError` value indicates whether the caller should use that API to discover the reason for failures.

```
public sealed class DllImportAttribute : Attribute {
// Public Constructors
    public DllImportAttribute(string dllName);
// Public Instance Fields
    public bool BestFitMapping;
    public CallingConvention CallingConvention;
    public CharSet CharSet;
    public string EntryPoint;
    public bool ExactSpelling;
    public bool PreserveSig;
    public bool SetLastError;
    public bool ThrowOnUnmappableChar;
// Public Instance Properties
    public string Value{get; }
}
```

Hierarchy

System.Object → System.Attribute → DllImportAttribute

Valid On

Method

[[Team LiB](#)]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ErrorWrapper

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This wrapper is used to force an integer, `Exception`, or other object to be marshaled as type `VT_ERROR`.

```
public sealed class ErrorWrapper {  
    // Public Constructors  
    public ErrorWrapper(Exception e);  
    public ErrorWrapper(int errorCode);  
    public ErrorWrapper(object errorCode);  
    // Public Instance Properties  
    public int ErrorCode{get; }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

ExtensibleClassFactory

System.Runtime.InteropServices
(mscorlib.dll)

*sealed
class*

This class exposes the method `RegisterObjectCreationCallback()`, which specifies a delegate that manufactures instances of a managed type. Use this to build managed types that extend unmanaged types. Since a managed type cannot directly inherit from an unmanaged type, the managed type needs to aggregate an instance of the unmanaged type. The delegate that you register with `RegisterObjectCreationCallback()` takes care of creating the unmanaged type.

```
public sealed class ExtensibleClassFactory {  
    // Public Static Methods  
    public static void RegisterObjectCreationCallback(ObjectCreationDelegate callback);  
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶


ExternalException CF 1.0, serializable

System.Runtime.InteropServices (mscorlib.dll) *class*

This is the base class for COM interop and SEH (Structured Exception Handler) exceptions.

```
public class ExternalException : SystemException {
// Public Constructors
    public ExternalException( );
    public ExternalException(string message);
    public ExternalException(string message, Exception inner);
    public ExternalException(string message, int errorCode);
// Protected Constructors
    protected ExternalException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public virtual int ErrorCode{get; }
}
```

Hierarchy



Subclasses

COMException, SEHException

FieldOffsetAttribute

ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute controls the offset, in bytes, of a field. Use it to match your .NET types to the layout of C and C++ structures exactly. This attribute can be used only within classes that have the `StructLayoutAttribute` attribute where `LayoutKind.Explicit` was used.

```
public sealed class FieldOffsetAttribute : Attribute {  
    // Public Constructors  
    public FieldOffsetAttribute(int offset);  
    // Public Instance Properties  
    public int Value {get; }  
}
```

Hierarchy

System.Object → System.Attribute → FieldOffsetAttribute

Valid On

Field

GCHandle

CF 1.0, ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

struct

This class is used when you need to pass a managed object to unmanaged code. To use this class, pass an instance of a .NET-managed type to the `Alloc()` method. The single-argument form of `Alloc()` creates the `GCHandle` with `GCHandleType.Normal`, which ensures that the object will not be freed by the garbage collector. (This means that some kind of user code must also call the `Free()` method in order to release the object.) Managed code can use the `Target` property to access the underlying object.

```
public struct GCHandle {  
    // Public Instance Properties  
    public bool IsAllocated { get; }  
    public object Target { set; get; }  
    // Public Static Methods  
    public static GCHandle Alloc(object value);  
    public static GCHandle Alloc(object value, GCHandleType type);  
    public static explicit operator GCHandle(IntPtr value);  
    public static explicit operator IntPtr(GCHandle value);  
    // Public Instance Methods  
    public IntPtr AddrOfPinnedObject( );  
    public void Free( );  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

GCHandleType CF 1.0, ECMA 1.0, serializable

System.Runtime.InteropServices (mscorlib.dll) *enum*

This enumeration contains values for the two-argument form of `GCHandle.Alloc()`. `Normal` protects the object from being garbage collected, and `Pinned` does the same (but it also enables the `GCHandle.AddrOfPinnedObject()` method). `Weak` and `WeakTrackResurrection` both allow the object to be garbage-collected. However, `Weak` causes the object to be zeroed out before the finalizer runs, but `WeakTrackResurrection` does not zero the object, so the object's finalizer can safely resurrect it.

```
public enum GCHandleType {
    Weak = 0,
    WeakTrackResurrection = 1,
    Normal = 2,
    Pinned = 3
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `GCHandleType`

Passed To

`GCHandle.Alloc()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

GuidAttribute

CF 1.0

System.Runtime.InteropServices

(mscorlib.dll)

sealed
class

This attribute is used to specify the GUID of assemblies, modules, or types you expose to COM. If you don't use this attribute to specify a GUID, one is automatically generated. When you apply this attribute, use its full name ([**GuidAttribute**()]) rather than [**Guid**()]) to avoid clashes with the **System.Guid** type.

```
public sealed class GuidAttribute : Attribute {  
    // Public Constructors  
    public GuidAttribute(string guid);  
    // Public Instance Properties  
    public string Value{get; }  
}
```

Hierarchy

System.Object → System.Attribute → GuidAttribute

Valid On

Assembly, Class, Struct, Enum, Interface, Delegate

HandleRef

System.Runtime.InteropServices
(mscorlib.dll)

struct

When you pass a managed object into unmanaged code using `Pinvoke`, there is a chance that the garbage collector will finalize the object before the unmanaged code is finished with it. This can only happen when your managed code does not reference the object after the `Pinvoke` call. Because the garbage collector's reach does not extend into unmanaged code, this fools the garbage collector into thinking that you are finished with it.

This class is used to wrap your managed object before passing it into unmanaged code, and you are guaranteed that the garbage collector will not touch it until the `Pinvoke` call returns.

```
public struct HandleRef {  
    // Public Constructors  
    public HandleRef(object wrapper, IntPtr handle);  
    // Public Instance Properties  
    public IntPtr Handle{get; }  
    public object Wrapper{get; }  
    // Public Static Methods  
    public static explicit operator IntPtr(HandleRef value);  
}
```

Hierarchy



IDispatchImplAttribute

System.Runtime.InteropServices

(mscorlib.dll)

sealed
class

There are multiple implementations of `IDispatch` available for you to expose dual interfaces and dispinterfaces to COM. Attach this attribute to a class or an assembly to specify which `IDispatch` implementation to use. If you apply this attribute to an assembly, it applies to all classes within that assembly. For a list of available `IDispatch` implementations, see `IDispatchImplType`.

```
public sealed class IDispatchImplAttribute : Attribute {  
    // Public Constructors  
    public IDispatchImplAttribute(IDispatchImplType implType);  
    public IDispatchImplAttribute(short implType);  
    // Public Instance Properties  
    public IDispatchImplType Value {get; }  
}
```

Hierarchy



Valid On

Assembly, Class

I DispatchImplTypeserializable

System.Runtime.InteropServices
(mscorlib.dll)*enum*

This enumeration contains the values used by `IDispatchImplAttribute`. `SystemDefinedImpl` tells the runtime to decide which `IDispatch` implementation to use. `InternalImpl` tells .NET to use its own `IDispatch` implementation, and `CompatibleImpl` uses an `IDispatch` implementation that is compatible with OLE automation. If you use this last implementation, it requires static type information. Because this information is automatically generated at runtime, `CompatibleImpl` may have an adverse impact on performance.

```
public enum IDispatchImplType {
    SystemDefinedImpl = 0 ,
    InternalImpl = 1 ,
    CompatibleImpl = 2
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → IDispatchImplType

Returned By

`IDispatchImplAttribute.Value`

Passed To

`IDispatchImplAttribute.IDispatchImplAttribute()`

InAttribute

CF 1.0, ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a parameter to marshal it as an **in** parameter. By default, parameters are marshaled based on their modifiers, so this attribute is only necessary if you want to override the defaults. Parameters with no modifiers are marshaled as **[In]**. Parameters with the **ref** modifier are marshaled as **[In, Out]**. Parameters with the **out** modifier are marshaled as **[Out]**.

```
public sealed class InAttribute : Attribute {  
    // Public Constructors  
    public InAttribute( );  
}
```

Hierarchy



Valid On

Parameter

InterfaceTypeAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is used to create a .NET interface that maps a COM interface into your managed application. See [ComInterfaceType](#) for the available values.

```
public sealed class InterfaceTypeAttribute : Attribute {  
    // Public Constructors  
    public InterfaceTypeAttribute(ComInterfaceType interfaceType);  
    public InterfaceTypeAttribute(short interfaceType);  
    // Public Instance Properties  
    public ComInterfaceType Value{get; }  
}
```

Hierarchy



Valid On

Interface


InvalidComObjectException serializable

System.Runtime.InteropServices
(mscorlib.dll) *class*

This exception signals that an invalid COM object has been used.

```
public class InvalidComObjectException : SystemException {  
    // Public Constructors  
    public InvalidComObjectException( );  
    public InvalidComObjectException(string message);  
    public InvalidComObjectException(string message, Exception inner);  
    // Protected Constructors  
    protected InvalidComObjectException(System.Runtime.Serialization.SerializationInfo i,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy




InvalidOleVariantTypeException serializable

System.Runtime.InteropServices
(mscorlib.dll) *class*

This exception signals that the marshaler failed in an attempt to marshal a variant to managed code.

```
public class InvalidOleVariantTypeException : SystemException {  
    // Public Constructors  
    public InvalidOleVariantTypeException( );  
    public InvalidOleVariantTypeException(string message);  
    public InvalidOleVariantTypeException(string message, Exception inner);  
    // Protected Constructors  
    protected InvalidOleVariantTypeException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



IRegistrationServices

System.Runtime.InteropServices (mscorlib.dll) *interface*

This interface defines the interface used by classes that register and unregister assemblies with COM.

```
public interface IRegistrationServices {  
    // Public Instance Methods  
    public Guid GetManagedCategoryGuid( );  
    public string GetProgIdForType(Type type);  
    public Type[] GetRegistrableTypesInAssembly(System.Reflection.Assembly assembly);  
    public bool RegisterAssembly(System.Reflection.Assembly assembly,  
        AssemblyRegistrationFlags flags);  
    public void RegisterTypeForComClients(Type type, ref Guid g);  
    public bool TypeRepresentsComType(Type type);  
    public bool TypeRequiresRegistration(Type type);  
    public bool UnregisterAssembly(System.Reflection.Assembly assembly);  
}
```

Implemented By

RegistrationServices

LayoutKind CF 1.0, ECMA 1.0, serializable

System.Runtime.InteropServices (mscorlib.dll) *enum*

This enumeration is used to specify how objects are laid out when they are passed to unmanaged code. **Auto** specifies that .NET should choose the best method to lay out the objects. **Explicit** gives you complete control over how the object's data members are laid out. You must use **FieldOffsetAttribute** with each member if you specify **Explicit**. **Sequential** lays out the object's members one after the other, in the same order that they are defined in the class definition.

```
public enum LayoutKind {  
    Sequential = 0,  
    Explicit = 2,  
    Auto = 3  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → LayoutKind

Returned By

StructLayoutAttribute.Value

Passed To

StructLayoutAttribute.StructLayoutAttribute()

LCIDConversionAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute indicates that a parameter within the method's unmanaged signature expects an [lcid] argument. Pass an integer value to the constructor to specify which parameter, starting with 0 for the first parameter.

```
public sealed class LCIDConversionAttribute : Attribute {  
    // Public Constructors  
    public LCIDConversionAttribute(int lcid);  
    // Public Instance Properties  
    public int Value {get; }  
}
```

Hierarchy



Valid On

Method

Marshal

CF 1.0

System.Runtime.InteropServices
(mscorlib.dll)*sealed
class*

This class offers a collection of static methods for working with unmanaged memory and converting managed types to unmanaged types. Unless you are developing specialized code for marshaling types between managed and unmanaged code, you probably do not need to use any of these methods.

`GetHRForException()` converts a .NET exception to a COM HRESULT. If you are curious about the platform you are running on, you can find out the size of a character with the `SystemDefaultCharSize` field, which is 1 on an ANSI platform (Windows 9x/Me) and 2 on a Unicode platform (Windows NT, 2000, and XP).

Use the `IsComObject()` method to determine whether an object is actually an unmanaged COM object. `AddRef()` method increments a COM object's reference count.

```
public sealed class Marshal {
// Public Static Fields
    public static readonly int SystemDefaultCharSize;
// =2
    public static readonly int SystemMaxDBCSCharSize;
// =1
// Public Static Methods
    public static int AddRef(IntPtr pUnk);
    public static IntPtr AllocCoTaskMem(int cb);
    public static IntPtr AllocHGlobal(int cb);
    public static IntPtr AllocHGlobal(IntPtr cb);
    public static object BindToMoniker(string monikerName);
    public static void ChangeWrapperHandleStrength(object otp, bool fIsWeak);
    public static void Copy(byte[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(char[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(double[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(short[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(int[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(long[] source, int startIndex, IntPtr destination, int length);
    public static void Copy(IntPtr source, byte[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, char[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, double[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, short[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, int[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, long[] destination, int startIndex, int length);
    public static void Copy(IntPtr source, float[] destination, int startIndex, int length);
    public static void Copy(float[] source, int startIndex, IntPtr destination, int length);
    public static object CreateWrapperOfType(object o, Type t);
```

```

public static void DestroyStructure(IntPtr ptr, Type structuretype);
public static void FreeBSTR(IntPtr ptr);
public static void FreeCoTaskMem(IntPtr ptr);
public static void FreeHGlobal(IntPtr hglobal);
public static Guid GenerateGuidForType(Type type);
public static string GenerateProgIdForType(Type type);
public static object GetActiveObject(string progID);
public static IntPtr GetComInterfaceForObject(object o, Type T);
public static object GetComObjectData(object obj, object key);
public static int GetComSlotForMethodInfo(System.Reflection.MemberInfo m);
public static int GetEndComSlot(Type t);
public static int GetExceptionCode( );
public static IntPtr GetExceptionPointers( );
public static IntPtr GetHINSTANCE(System.Reflection.Module m);
public static int GetHRForException(Exception e);
public static int GetHRForLastWin32Error( );
public static IntPtr GetIDispatchForObject(object o);
public static IntPtr GetITypeInfoForType(Type t);
public static IntPtr GetIUnknownForObject(object o);
public static int GetLastWin32Error( );
public static IntPtr GetManagedThunkForUnmanagedMethodPtr(IntPtr pfnMethodToWrap,
    IntPtr pbSignature, int cbSignature);
public static MemberInfo GetMethodInfoForComSlot(Type t, int slot,
    ref ComMemberType memberType);
public static void GetNativeVariantForObject(object obj, IntPtr pDstNativeVariant);
public static object GetObjectForIUnknown(IntPtr pUnk);
public static object GetObjectForNativeVariant(IntPtr pSrcNativeVariant);
public static object[ ] GetObjectsForNativeVariants(IntPtr aSrcNativeVariant, int cV
public static int GetStartComSlot(Type t);
public static Thread GetThreadFromFiberCookie(int cookie);
public static object GetTypedObjectForIUnknown(IntPtr pUnk, Type t);
public static Type GetTypeForITypeInfo(IntPtr piTypeInfo);
public static string GetTypeInfoName(UCOMITypeInfo pTI);
public static Guid GetTypeLibGuid(UCOMITypeLib pTLB);
public static Guid GetTypeLibGuidForAssembly(System.Reflection.Assembly asm);
public static int GetTypeLibLcid(UCOMITypeLib pTLB);
public static string GetTypeLibName(UCOMITypeLib pTLB);
public static IntPtr GetUnmanagedThunkForManagedMethodPtr(IntPtr pfnMethodToWrap,
    IntPtr pbSignature, int cbSignature);
public static bool IsComObject(object o);
public static bool IsTypeVisibleFromCom(Type t);
public static int NumParamBytes(System.Reflection.MethodInfo m);
public static IntPtr OffsetOf(Type t, string fieldName);
public static void Prelink(System.Reflection.MethodInfo m);
public static void PrelinkAll(Type c);
public static string PtrToStringAnsi(IntPtr ptr);
public static string PtrToStringAnsi(IntPtr ptr, int len);
public static string PtrToStringAuto(IntPtr ptr);
public static string PtrToStringAuto(IntPtr ptr, int len);

```

```

public static string PtrToStringBSTR(IntPtr ptr);
public static string PtrToStringUni(IntPtr ptr);
public static string PtrToStringUni(IntPtr ptr, int len);
public static object PtrToStructure(IntPtr ptr, Type structureType);
public static void PtrToStructure(IntPtr ptr, object structure);
public static int QueryInterface(IntPtr pUnk, ref Guid iid, out IntPtr ppv);
public static byte ReadByte(IntPtr ptr);
public static byte ReadByte(IntPtr ptr, int ofs);
public static byte ReadByte(in object ptr, int ofs);
public static short ReadInt16(IntPtr ptr);
public static short ReadInt16(IntPtr ptr, int ofs);
public static short ReadInt16(in object ptr, int ofs);
public static int ReadInt32(IntPtr ptr);
public static int ReadInt32(IntPtr ptr, int ofs);
public static int ReadInt32(in object ptr, int ofs);
public static long ReadInt64(IntPtr ptr);
public static long ReadInt64(IntPtr ptr, int ofs);
public static long ReadInt64(in object ptr, int ofs);
public static IntPtr ReadIntPtr(IntPtr ptr);
public static IntPtr ReadIntPtr(IntPtr ptr, int ofs);
public static IntPtr ReadIntPtr(in object ptr, int ofs);
public static IntPtr ReAllocCoTaskMem(IntPtr pv, int cb);
public static IntPtr ReAllocHGlobal(IntPtr pv, IntPtr cb);
public static int Release(IntPtr pUnk);
public static int ReleaseComObject(object o);
public static void ReleaseThreadCache( );
public static bool SetComObjectData(object obj, object key, object data);
public static int SizeOf(object structure);
public static int SizeOf(Type t);
public static IntPtr StringToBSTR(string s);
public static IntPtr StringToCoTaskMemAnsi(string s);
public static IntPtr StringToCoTaskMemAuto(string s);
public static IntPtr StringToCoTaskMemUni(string s);
public static IntPtr StringToHGlobalAnsi(string s);
public static IntPtr StringToHGlobalAuto(string s);
public static IntPtr StringToHGlobalUni(string s);
public static void StructureToPtr(object structure, IntPtr ptr, bool fDeleteOld);
public static void ThrowExceptionForHR(int errorCode);
public static void ThrowExceptionForHR(int errorCode, IntPtr errorInfo);
public static IntPtr UnsafeAddrOfPinnedArrayElement(Array arr, int index);
public static void WriteByte(IntPtr ptr, byte val);
public static void WriteByte(IntPtr ptr, int ofs, byte val);
public static void WriteByte(in object ptr, int ofs, byte val);
public static void WriteInt16(IntPtr ptr, char val);
public static void WriteInt16(IntPtr ptr, short val);
public static void WriteInt16(IntPtr ptr, int ofs, char val);
public static void WriteInt16(IntPtr ptr, int ofs, short val);
public static void WriteInt16(in object ptr, int ofs, char val);
public static void WriteInt16(in object ptr, int ofs, short val);

```

```
public static void WriteInt32(IntPtr ptr, int val);  
public static void WriteInt32(IntPtr ptr, int ofs, int val);  
public static void WriteInt32(in object ptr, int ofs, int val);  
public static void WriteInt64(IntPtr ptr, int ofs, long val);  
public static void WriteInt64(IntPtr ptr, long val);  
public static void WriteInt64(in object ptr, int ofs, long val);  
public static void WriteIntPtr(IntPtr ptr, int ofs, IntPtr val);  
public static void WriteIntPtr(IntPtr ptr, IntPtr val);  
public static void WriteIntPtr(in object ptr, int ofs, IntPtr val);  
}
```

[Team LiB]

[◀ PREVIOUS](#)[NEXT ▶](#)

MarshalAsAttribute

ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

*sealed
class*

This optional attribute is used to explicitly specify the unmanaged type a parameter, field, or return value should be marshaled to. If you do not specify this attribute, .NET uses the type's default marshaler. The `UnmanagedType` enumeration contains the unmanaged types you can marshal to with this attribute.

```
public sealed class MarshalAsAttribute : Attribute {  
    // Public Constructors  
    public MarshalAsAttribute(short unmanagedType);  
    public MarshalAsAttribute(UnmanagedType unmanagedType);  
    // Public Instance Fields  
    public UnmanagedType ArraySubType;  
    public string MarshalCookie;  
    public string MarshalType;  
    public Type MarshalTypeRef;  
    public VarEnum SafeArraySubType;  
    public Type SafeArrayUserDefinedSubType;  
    public int SizeConst;  
    public short SizeParamIndex;  
    // Public Instance Properties  
    public UnmanagedType Value{get; }  
}
```

Hierarchy

System.Object → System.Attribute → MarshalAsAttribute

Valid On

Field, Parameter, ReturnValue

MarshalDirectiveException

serializable


System.Runtime.InteropServices
(mscorlib.dll)

class

This exception is thrown when the marshaler encounters an unsupported `MarshalAsAttribute` .

```
public class MarshalDirectiveException : SystemException {  
    // Public Constructors  
    public MarshalDirectiveException( );  
    public MarshalDirectiveException(string message);  
    public MarshalDirectiveException(string message, Exception inner);  
    // Protected Constructors  
    protected MarshalDirectiveException(System.Runtime.Serialization.SerializationInfo i,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ObjectCreationDelegate serializable

System.Runtime.InteropServices (mscorlib.dll) *delegate*

Use this delegate with the `ExtensibleClassFactory.RegisterObjectCreationCallback()` method to create a COM object.

```
public delegate IntPtr ObjectCreationDelegate(IntPtr aggregator);
```

Passed To

```
ExtensibleClassFactory.RegisterObjectCreationCallback( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

OptionalAttribute


System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a parameter to indicate that it is optional.

```
public sealed class OptionalAttribute : Attribute {  
    // Public Constructors  
    public OptionalAttribute( );  
}
```

Hierarchy



Valid On

Parameter

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

OutAttribute

CF 1.0, ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a parameter to cause it to be marshaled as an **out** parameter. See **InAttribute** for more details, including information on the default behavior.

```
public sealed class OutAttribute : Attribute {  
    // Public Constructors  
    public OutAttribute( );  
}
```

Hierarchy

System.Object → System.Attribute → OutAttribute

Valid On

Parameter

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

PreserveSigAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

When .NET converts a managed method signature to an unmanaged signature, it changes the return value to a parameter that has the `out` and `retval` COM attributes. Instead of the original return value, the unmanaged method returns a COM HRESULT. If you want to override this behavior, attach the `PreserveSigAttribute` to the method.

Something similar happens when you call unmanaged methods from managed code. In that case, the `[out, retval]` parameter on the COM side becomes the return value, and an HRESULT that indicates an error condition is translated into a .NET exception. If you want to be able to access the HRESULT as a `long` return value, use the `PreserveSigAttribute` on the methods in your COM interface declaration (see `InterfaceTypeAttribute`).

```
public sealed class PreserveSigAttribute : Attribute {  
    // Public Constructors  
    public PreserveSigAttribute( );  
}
```

Hierarchy

System.Object → System.Attribute → PreserveSigAttribute

Valid On

Method

ProgIdAttribute

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

This attribute is attached to a class to specify its COM ProgID.

```
public sealed class ProgIdAttribute : Attribute {  
    // Public Constructors  
    public ProgIdAttribute(string progId);  
    // Public Instance Properties  
    public string Value {get; }  
}
```

Hierarchy



Valid On

Class

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

RegistrationServices

System.Runtime.InteropServices (mscorlib.dll)

class

This class is responsible for registering and unregistering assemblies with COM.

```
public class RegistrationServices : IRegistrationServices {  
    // Public Constructors  
    public RegistrationServices( );  
    // Public Instance Methods  
    public virtual Guid GetManagedCategoryGuid( );  
    // implements IRegistrationServices  
    public virtual string GetProgIdForType(Type type);  
    // implements IRegistrationServices  
    public virtual Type[ ] GetRegistrableTypesInAssembly(System.Reflection.Assembly asse  
    // implements IRegistrationServices  
    public virtual bool RegisterAssembly(System.Reflection.Assembly assembly,  
        AssemblyRegistrationFlags flags);  
    // implements IRegistrationServices  
    public virtual void RegisterTypeForComClients(Type type, ref Guid g);  
    // implements IRegistrationServices  
    public virtual bool TypeRepresentsComType(Type type);  
    // implements IRegistrationServices  
    public virtual bool TypeRequiresRegistration(Type type);  
    // implements IRegistrationServices  
    public virtual bool UnregisterAssembly(System.Reflection.Assembly assembly)  
    // implements IRegistrationServices  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

RuntimeEnvironment

System.Runtime.InteropServices (mscorlib.dll) *class*

This type exposes static methods you can use to get information about the CLR's environment.

```
public class RuntimeEnvironment {  
    // Public Constructors  
    public RuntimeEnvironment( );  
    // Public Static Properties  
    public static string SystemConfigurationFile {get; }  
    // Public Static Methods  
    public static bool FromGlobalAccessCache(System.Reflection.Assembly a);  
    public static string GetRuntimeDirectory( );  
    public static string GetSystemVersion( );  
}
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶


SafeArrayRankMismatchException serializable

System.Runtime.InteropServices
(mscorlib.dll) *class*

This exception signals that a **SAFEARRAY** 's rank does not match the rank in the method signature; it might be thrown when invoking a managed method.

```
public class SafeArrayRankMismatchException : SystemException {
// Public Constructors
    public SafeArrayRankMismatchException( );
    public SafeArrayRankMismatchException(string message);
    public SafeArrayRankMismatchException(string message, Exception inner);
// Protected Constructors
    protected SafeArrayRankMismatchException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy




SafeArrayTypeMismatchException serializable

System.Runtime.InteropServices (mscorlib.dll) *class*

This exception signals that a **SAFEARRAY** 's type does not match the type in the method signature; it might be thrown when invoking a managed method.

```
public class SafeArrayTypeMismatchException : SystemException {
// Public Constructors
    public SafeArrayTypeMismatchException( );
    public SafeArrayTypeMismatchException(string message);
    public SafeArrayTypeMismatchException(string message, Exception inner);
// Protected Constructors
    protected SafeArrayTypeMismatchException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



SEHException


serializable

System.Runtime.InteropServices (mscorlib.dll) *class*

This class is used as a wrapper for an unmanaged C++ exception that was thrown.

```
public class SEHException : ExternalException {
// Public Constructors
    public SEHException( );
    public SEHException(string message);
    public SEHException(string message, Exception inner);
// Protected Constructors
    protected SEHException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Methods
    public virtual bool CanResume( );
}
```

Hierarchy



StructLayoutAttribute

CF 1.0, ECMA 1.0

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

Use this attribute to control how the members of a class are laid out in memory. See [LayoutKind](#) for the possible values you can use with this attribute.

```
public sealed class StructLayoutAttribute : Attribute {  
    // Public Constructors  
    public StructLayoutAttribute(short layoutKind);  
    public StructLayoutAttribute(LayoutKind layoutKind);  
    // Public Instance Fields  
    public CharSet CharSet;  
    public int Pack;  
    public int Size;  
    // Public Instance Properties  
    public LayoutKind Value{get; }  
}
```

Hierarchy

System.Object → System.Attribute → StructLayoutAttribute

Valid On

Class, Struct

TypeLibVersionAttribute.NET 1.1

System.Runtime.InteropServices *sealed*
(mscorlib.dll) *class*

This attribute specifies the exported type library's version.

```
public sealed class TypeLibVersionAttribute : Attribute {  
    // Public Constructors  
    public TypeLibVersionAttribute(int major, int minor);  
    // Public Instance Properties  
    public int MajorVersion{get; }  
    public int MinorVersion{get; }  
}
```

Hierarchy



Valid On

Assembly

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UnknownWrapper

System.Runtime.InteropServices
(mscorlib.dll)

sealed
class

Use this wrapper to pass a managed object into unmanaged code as type `VT_UNKNOWN`.

```
public sealed class UnknownWrapper {  
    // Public Constructors  
    public UnknownWrapper(object obj);  
    // Public Instance Properties  
    public object WrappedObject {get; }  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

UnmanagedType

CF 1.0, ECMA 1.0,
serializable

System.Runtime.InteropServices (mscorlib.dll)

enum

This enumeration contains constant values that represent various unmanaged types.

```
public enum UnmanagedType {  
    Bool = 2 ,  
    I1 = 3 ,  
    U1 = 4 ,  
    I2 = 5 ,  
    U2 = 6 ,  
    I4 = 7 ,  
    U4 = 8 ,  
    I8 = 9 ,  
    U8 = 10 ,  
    R4 = 11 ,  
    R8 = 12 ,  
    Currency = 15 ,  
    BStr = 19 ,  
    LPStr = 20 ,  
    LPWStr = 21 ,  
    LPTStr = 22 ,  
    ByValTStr = 23 ,  
    IUnknown = 25 ,  
    IDispatch = 26 ,  
    Struct = 27 ,  
    Interface = 28 ,  
    SafeArray = 29 ,  
    ByValArray = 30 ,  
    SysInt = 31 ,  
    SysUInt = 32 ,  
    VBByRefStr = 34 ,  
    AnsiBStr = 35 ,  
    TBStr = 36 ,  
    VariantBool = 37 ,  
    FunctionPtr = 38 ,  
    AsAny = 40 ,  
    LPArray = 42 ,  
    LPStruct = 43 ,  
    CustomMarshaler = 44 ,  
    Error = 45  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `UnmanagedType`

Returned By

`System.Reflection.Emit.UnmanagedMarshal.{BaseType, GetUnmanagedType}, MarshalAsAttribute.Value`

Passed To

`System.Reflection.Emit.UnmanagedMarshal.{DefineLPArray(), DefineSafeArray(), DefineUnmanagedType()}, MarshalAsAttribute.MarshalAsAttribute()`

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

VarEnum

serializable

System.Runtime.InteropServices (mscorlib.dll)

enum

This enumeration contains constants that can be used with `MarshalAsAttribute.SafeArraySubType` to specify how to marshal arrays that are passed from managed to unmanaged code.

```
public enum VarEnum {
    VT_EMPTY = 0 ,
    VT_NULL = 1 ,
    VT_I2 = 2 ,
    VT_I4 = 3 ,
    VT_R4 = 4 ,
    VT_R8 = 5 ,
    VT_CY = 6 ,
    VT_DATE = 7 ,
    VT_BSTR = 8 ,
    VT_DISPATCH = 9 ,
    VT_ERROR = 10 ,
    VT_BOOL = 11 ,
    VT_VARIANT = 12 ,
    VT_UNKNOWN = 13 ,
    VT_DECIMAL = 14 ,
    VT_I1 = 16 ,
    VT_UI1 = 17 ,
    VT_UI2 = 18 ,
    VT_UI4 = 19 ,
    VT_I8 = 20 ,
    VT_UI8 = 21 ,
    VT_INT = 22 ,
    VT_UINT = 23 ,
    VT_VOID = 24 ,
    VT_HRESULT = 25 ,
    VT_PTR = 26 ,
    VT_SAFEARRAY = 27 ,
    VT_CARRAY = 28 ,
    VT_USERDEFINED = 29 ,
    VT_LPSTR = 30 ,
    VT_LPWSTR = 31 ,
    VT_RECORD = 36 ,
    VT_FILETIME = 64 ,
    VT_BLOB = 65 ,
    VT_STREAM = 66 ,
    VT_STORAGE = 67 ,
    VT_STREAMED_OBJECT = 68 ,
```

```
VT_STORED_OBJECT = 69 ,  
VT_BLOB_OBJECT = 70 ,  
VT_CF = 71 ,  
VT_CLSID = 72 ,  
VT_VECTOR = 4096 ,  
VT_ARRAY = 8192 ,  
VT_BYREF = 16384  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → VarEnum

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

I Expando

System.Runtime.InteropServices.Expando *interface* (mscorlib.dll)

This interface indicates a type whose members can be removed or added. The members are represented as `System.Reflection.MemberInfo` objects.

```
public interface IExpando : System.Reflection.IReflect {  
    // Public Instance Methods  
    public FieldInfo AddField(string name);  
    public MethodInfo AddMethod(string name, Delegate method);  
    public PropertyInfo AddProperty(string name);  
    public void RemoveMember(System.Reflection.MemberInfo m);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 38. System.Runtime.Serialization

The act of serialization transforms an object (and all of its associated objects and/or data elements) into a stream of bytes, suitable for storage or transmission across a network. The reverse of this act, called deserialization, is to take the same stream of bytes and reconstitute the objects exactly as they were at the time of serialization.

This act, which sounds simple in theory, encompasses a number of points that must be addressed. For starters, the serialization libraries must provide complete reference semantics-that is, if an object holds two references to other objects, both of which happen to point to the same object, then the serialization mechanism needs to keep that in place. Therefore, when the stream is deserialized, both references point to the same object again.

In addition, the actual format of the stream of bytes may be different from application to application. For example, for storage into a binary column in a database, the serialized representation must be as compact and succinct as possible-no "wasted" bytes. But if we want to send the serialized data over an HTTP link to a non-.NET process, then a binary format is entirely inappropriate, and an XML-based one is more useful.


The `System.Runtime.Serialization` namespace and its child namespace, `System.Runtime.Serialization.Formatters` (with its own two child namespaces, `System.Runtime.Serialization.Formatters.Binary` and `System.Runtime.Serialization.Formatters.Soap`), directly addresses these needs. `System.Runtime.Serialization` contains the types necessary to perform the serialization of an object into a stream of bytes, using an alternative object (which implements the `IFormatter` interface) to actually format the bytes into either binary or XML form. While it is certainly feasible to write your own custom formatters, most .NET programmers have no real practical need to do so, since a binary format and an XML format cover most needs.

Serialization does not necessarily come for free, however-there are a few things a .NET programmer must do in order to take advantage of the Serialization mechanism. For starters, a type must be marked as serializable in order to be eligible for serialization; this requires adding the `System.SerializableAttribute` to the type's declaration. By default, when a type becomes serializable, all nonstatic fields within that type are transformed into bytes when serialized. If a field is itself nonserializable, an exception is thrown; fields that wish to remain unserialized (that is, remain empty during the serialization process) must be marked with the `System.NonSerializedAttribute` in the type declaration.

It is possible to take greater control over the serialization process by implementing the `ISerializable` interface and providing definitions for the methods declared there; however, most .NET programmers are generally satisfied with the default serialization behavior.

[Figure 38-1](#) shows the types in this namespace.

Figure 38-1. The System.Runtime.Serialization namespace



Formatter

serializable

System.Runtime.Serialization
(mscorlib.dll)*abstract
class*

This is the abstract base class for all runtime serialization formatters. It implements the `IFormatter` interface, which provides the properties that select the binder, surrogates, and streaming context of the formatter. This interface also implements the `Serialize()` and `Deserialize()` methods.

Additionally, the `Formatter` manages the queue of objects to serialize and provides a set of `Write*` methods for writing types to the stream.

```
public abstract class Formatter : IFormatter {
// Protected Constructors
    protected Formatter( );
// Protected Instance Fields
    protected ObjectIDGenerator m_idGenerator;
    protected Queue m_objectQueue;
// Public Instance Properties
    public abstract SerializationBinder Binder{set; get; }
//implements IFormatter
    public abstract StreamingContext Context{set; get; }
// implements IFormatter
    public abstract ISurrogateSelector SurrogateSelector{set; get; }
// implements IFormatter
// Public Instance Methods
    public abstract object Deserialize(System.IO.Stream serializationStream)
// implements IFormatter
    public abstract void Serialize(System.IO.Stream serializationStream, object graph)
// implements IFormatter
// Protected Instance Methods
    protected virtual object GetNext(out long objID);
    protected virtual long Schedule(object obj);
    protected abstract void WriteArray(object obj, string name, Type memberType);
    protected abstract void WriteBoolean(bool val, string name);
    protected abstract void WriteByte(byte val, string name);
    protected abstract void WriteChar(char val, string name);
    protected abstract void WriteDateTime(DateTime val, string name);
    protected abstract void WriteDecimal(decimal val, string name);
    protected abstract void WriteDouble(double val, string name);
    protected abstract void WriteInt16(short val, string name);
    protected abstract void WriteInt32(int val, string name);
    protected abstract void WriteInt64(long val, string name);
    protected virtual void WriteMember(string memberName, object data);
```

```
protected abstract void WriteObjectRef(object obj, string name, Type memberType);
protected abstract void WriteSByte(sbyte val, string name);
protected abstract void WriteSingle(float val, string name);
protected abstract void WriteTimeSpan(TimeSpan val, string name);
protected abstract void WriteUInt16(ushort val, string name);
protected abstract void WriteUInt32(uint val, string name);
protected abstract void WriteUInt64(ulong val, string name);
protected abstract void WriteValueType(object obj, string name, Type memberType);
}
```

FormatterConverter

System.Runtime.Serialization (mscorlib.dll)

class

This class is a basic implementation of the `IFormatterConverter` interface. It provides a formatter with a means to convert values to different base types. The generic `Convert()` method converts a value into a specified type. The various `To*` methods convert values into specific types.

```
public class FormatterConverter : IFormatterConverter {
// Public Constructors
    public FormatterConverter( );
// Public Instance Methods
    public object Convert(object value, Type type);
// implements IFormatterConverter
    public object Convert(object value, TypeCode typeCode);
// implements IFormatterConverter
    public bool ToBoolean(object value);
// implements IFormatterConverter
    public byte ToByte(object value);
// implements IFormatterConverter
    public char ToChar(object value);
// implements IFormatterConverter
    public DateTime ToDateTime(object value);
// implements IFormatterConverter
    public decimal ToDecimal(object value);
// implements IFormatterConverter
    public double ToDouble(object value);
// implements IFormatterConverter
    public short ToInt16(object value);
// implements IFormatterConverter
    public int ToInt32(object value);
// implements IFormatterConverter
    public long ToInt64(object value);
// implements IFormatterConverter
    public sbyte ToSByte(object value);
// implements IFormatterConverter
    public float ToSingle(object value);
// implements IFormatterConverter
    public string ToString(object value);
// implements IFormatterConverter
    public ushort ToUInt16(object value);
// implements IFormatterConverter
    public uint ToUInt32(object value);
```



```
// implements IFormatterConverter
public ulong ToUInt64(object value);
// implements IFormatterConverter
}
```

[\[Team LiB \]](#)

FormatterServices

System.Runtime.Serialization (mscorlib.dll)

*sealed
class*

The methods of this sealed class provide some background functionality to a formatter when serializing a deserializing objects. For example, `GetObjectData()` creates an array of `System.Reflection.MemberInfo` data. `GetSerializableMembers()` retrieves all the serializable members of a given class. `PopulateObject()` is the basic deserialization method, using a `MemberInfo` array of member names and an array of corresponding values to repopulate a specified object.

```
public sealed class FormatterServices {  
    // Public Static Methods  
    public static void CheckTypeSecurity(Type t,  
        System.Runtime.Serialization.Formatters.TypeFilterLevel securityLevel);  
    public static object[] GetObjectData(object obj, System.Reflection.MemberInfo[] members);  
    public static object GetSafeUninitializedObject(Type type);  
    public static MemberInfo[] GetSerializableMembers(Type type);  
    public static MemberInfo[] GetSerializableMembers(Type type, StreamingContext context);  
    public static Type GetTypeFromAssembly(System.Reflection.Assembly assembly, string name);  
    public static object GetUninitializedObject(Type type);  
    public static object PopulateObjectMembers(object obj, System.Reflection.MemberInfo[] members,  
        object[] data);  
}
```

I DeserializationCallback

System.Runtime.Serialization
(mscorlib.dll)

interface

This interface implements a notification triggered when deserialization of an object is completed. Specify callback functionality with the `OnDeserialization()` method. This class is useful for restoring members that can be computed after deserialization, instead of serializing them and using more storage resources.

```
public interface IDeserializationCallback {  
    // Public Instance Methods  
    public void OnDeserialization(object sender);  
}
```

Implemented By

System.Collections.Hashtable,
System.Collections.Specialized.NameObjectCollectionBase,
System.Globalization.{CompareInfo, TextInfo}, System.Reflection.AssemblyName

IFormatter

System.Runtime.Serialization
(mscorlib.dll)

interface

This interface defines the basic serialization and deserialization functionality for a formatter. Its three properties determine the `SerializationBinder`, `StreamingContext`, and `SurrogateSelector` of the formatter. It also defines the two basic methods of `Serialize()` and `Deserialize()`.

```
public interface IFormatter {  
    // Public Instance Properties  
    public SerializationBinder Binder{set; get; }  
    public StreamingContext Context{set; get; }  
    public ISurrogateSelector SurrogateSelector{set; get; }  
    // Public Instance Methods  
    public object Deserialize(System.IO.Stream serializationStream);  
    public void Serialize(System.IO.Stream serializationStream, object graph);  
}
```

Implemented By

Formatter, System.Runtime.Serialization.Formatters.Binary.BinaryFormatter,
System.Runtime.Serialization.Formatters.Soap.SoapFormatter

IFormatterConverter

System.Runtime.Serialization
(mscorlib.dll)

interface

This interface defines the basic methods that convert serializable data into base class types. These conversion methods are used to parse the data contained in `SerializationInfo` instances.

```
public interface IFormatterConverter {  
    // Public Instance Methods  
    public object Convert(object value, Type type);  
    public object Convert(object value, TypeCode typeCode);  
    public bool ToBoolean(object value);  
    public byte ToByte(object value);  
    public char ToChar(object value);  
    public DateTime ToDateTime(object value);  
    public decimal ToDecimal(object value);  
    public double ToDouble(object value);  
    public short.ToInt16(object value);  
    public int.ToInt32(object value);  
    public long.ToInt64(object value);  
    public sbyte ToSByte(object value);  
    public float ToSingle(object value);  
    public string ToString(object value);  
    public ushort.ToInt16(object value);  
    public uint.ToInt32(object value);  
    public ulong.ToInt64(object value);  
}
```

Implemented By

FormatterConverter

Passed To

SerializationInfo.SerializationInfo()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IObjectReference

System.Runtime.Serialization
(mscorlib.dll)

interface

This interface indicates that an object references another object. Use of this interface means that during deserialization, the object must be dereferenced during fixup so the "real" object is placed in the object graph.

```
public interface IObjectReference {  
    // Public Instance Methods  
    public object GetRealObject(StreamingContext context);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

I Serializable

System.Runtime.Serialization
(mscorlib.dll)

interface

Indicates that an object is serializable and provides serialization information to the formatter. This interface defines `GetObjectData()`, which specifies the member information that will be provided to a `SerializationInfo` instance in a specific `StreamingContext`. Classes that implement `ISerializable` must also provide a constructor that takes the same arguments as `GetObjectData()`. The constructor must use those arguments to deserialize an instance of the class.

```
public interface ISerializable {  
    // Public Instance Methods  
    public void GetObjectData(SerializationInfo info, StreamingContext context);  
}
```

Implemented By

Multiple types

I SerializationSurrogate

System.Runtime.Serialization
(mscorlib.dll)

interface

Objects that implement this interface can be delegated to perform the serialization and deserialization of another object by providing customized methods for `GetObjectData()` and `SetObjectData()`. `GetObjectData()` gets the member information to create a `SerializationInfo` instance, while `SetObjectData()` uses information from a `SerializationInfo` instance to recreate an object.

```
public interface ISerializationSurrogate {  
    // Public Instance Methods  
    public void GetObjectData(object obj, SerializationInfo info, StreamingContext conte  
    public object SetObjectData(object obj, SerializationInfo info, StreamingContext con  
        ISurrogateSelector selector);  
}
```

Returned By

```
ISurrogateSelector.GetSurrogate( ), SurrogateSelector.GetSurrogate( )
```

Passed To

```
SurrogateSelector.AddSurrogate( )
```


[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

I SurrogateSelector

System.Runtime.Serialization
(mscorlib.dll)

interface

This interface is implemented by classes that help the formatter decide the appropriate surrogate to serialize or deserialize a particular type.

```
public interface ISurrogateSelector {
    // Public Instance Methods
    public void ChainSelector(ISurrogateSelector selector);
    public ISurrogateSelector GetNextSelector( );
    public ISerializationSurrogate GetSurrogate(Type type, StreamingContext context,
        out ISurrogateSelector selector);
}
```

Implemented By

SurrogateSelector

Returned By

Formatter.SurrogateSelector,
System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.SurrogateSelector,
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.SurrogateSelector,
IFormatter.SurrogateSelector, SurrogateSelector.GetNextSelector()

Passed To

Formatter.SurrogateSelector,
System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.{BinaryFormatter(),
SurrogateSelector},
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.{SoapFormatter(),
SurrogateSelector}, IFormatter.SurrogateSelector,
ISerializationSurrogate.SetObjectData(), ObjectManager.ObjectManager(),
SurrogateSelector.{ChainSelector(), GetSurrogate()}

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ObjectIDGenerator

serializable

System.Runtime.Serialization
(mscorlib.dll)

class

This class is used by formatters to identify objects within a serialized stream in order to track object references. The IDs are 64-bit numbers that are generated when an object is referenced or is referencing another. (An ID with a zero value is a null reference.) The `GetId()` method creates and returns an ID for an object if it does not already have one.

```
public class ObjectIDGenerator {  
    // Public Constructors  
    public ObjectIDGenerator( );  
    // Public Instance Methods  
    public virtual long GetId(object obj, out bool firstTime);  
    public virtual long HasId(object obj, out bool firstTime);  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ObjectManager

System.Runtime.Serialization (mscorlib.dll)

class

This class is used by a formatter to manage object references during deserialization. Objects in the stream refer to already deserialized objects. This causes the formatter to ask the **ObjectManager** to complete the reference after the deserialization is completed (i.e., on "fixup").

```
public class ObjectManager {
// Public Constructors
    public ObjectManager(ISurrogateSelector selector, StreamingContext context);
// Public Instance Methods
    public virtual void DoFixups( );
    public virtual object GetObject(long objectID);
    public virtual void RaiseDeserializationEvent( );
    public virtual void RecordArrayElementFixup(long arrayToBeFixed, int[] indices,
        long objectRequired);
    public virtual void RecordArrayElementFixup(long arrayToBeFixed, int index,
        long objectRequired);
    public virtual void RecordDelayedFixup(long objectToBeFixed, string memberName,
        long objectRequired);
    public virtual void RecordFixup(long objectToBeFixed, System.Reflection.MemberInfo member,
        long objectRequired);
    public virtual void RegisterObject(object obj, long objectID);
    public void RegisterObject(object obj, long objectID, SerializationInfo info);
    public void RegisterObject(object obj, long objectID, SerializationInfo info,
        long idOfContainingObj, System.Reflection.MemberInfo member);
    public void RegisterObject(object obj, long objectID, SerializationInfo info,
        long idOfContainingObj, System.Reflection.MemberInfo member,
        int[] arrayIndex);
}
```

SerializationBinder

serializable

System.Runtime.Serialization
(mscorlib.dll)

abstract
class

This abstract base class provides a binder to a formatter that controls which classes are loaded during deserialization according to assembly information.

```
public abstract class SerializationBinder {  
    // Protected Constructors  
    protected SerializationBinder( );  
    // Public Instance Methods  
    public abstract Type BindToType(string assemblyName, string typeName);  
}
```

Returned By

```
Formatter.Binder,  
System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.Binder,  
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.Binder, IFormatter.Binder
```

Passed To

```
Formatter.Binder,  
System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.Binder,  
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.Binder, IFormatter.Binder
```

SerializationEntry


System.Runtime.Serialization
(mscorlib.dll)

struct

This class encapsulates the information used for a single member stored within `SerializationInfo`. This object stores the `Name` of the object, its `Value`, and the `ObjectType`. `SerializationEntry` instances are the elements returned via the `SerializationInfoEnumerator`.

```
public struct SerializationEntry {  
    // Public Instance Properties  
    public string Name{get; }  
    public Type ObjectType{get; }  
    public object Value{get; }  
}
```

Hierarchy



Returned By

`SerializationInfoEnumerator.Current`

SerializationException


serializable

System.Runtime.Serialization (mscorlib.dll) *class*

This class contains the exceptions thrown on serialization and deserialization errors.

```
public class SerializationException : SystemException {  
    // Public Constructors  
    public SerializationException( );  
    public SerializationException(string message);  
    public SerializationException(string message, Exception innerException);  
    // Protected Constructors  
    protected SerializationException(SerializationInfo info, StreamingContext context);  
}
```

Hierarchy



SerializationInfo

System.Runtime.Serialization
(mscorlib.dll)

*sealed
class*

`SerializationInfo` objects are used by classes that customize serialization behavior. The data required for each member is the name of the member, its type, and its value. Within a class's `ISerializable.GetObjectData()` block, the `AddValue()` method is used to add member data. Deserialization is defined within a deserialization constructor (see `ISerializable`). It is specified by retrieving member data with `GetValue()`, or one of the many other `Get*` methods, and assigning the data to the appropriate members.

```
public sealed class SerializationInfo {
// Public Constructors
    public SerializationInfo(Type type, IFormatterConverter converter);
// Public Instance Properties
    public string AssemblyName{set; get; }
    public string FullName{set; get; }
    public int MemberCount{get; }
// Public Instance Methods
    public void AddValue(string name, bool value);
    public void AddValue(string name, byte value);
    public void AddValue(string name, char value);
    public void AddValue(string name, DateTime value);
    public void AddValue(string name, decimal value);
    public void AddValue(string name, double value);
    public void AddValue(string name, short value);
    public void AddValue(string name, int value);
    public void AddValue(string name, long value);
    public void AddValue(string name, object value);
    public void AddValue(string name, object value, Type type);
    public void AddValue(string name, sbyte value);
    public void AddValue(string name, float value);
    public void AddValue(string name, ushort value);
    public void AddValue(string name, uint value);
    public void AddValue(string name, ulong value);
    public bool GetBoolean(string name);
    public byte GetByte(string name);
    public char GetChar(string name);
    public DateTime GetDateTime(string name);
    public decimal GetDecimal(string name);
    public double GetDouble(string name);
    public SerializationInfoEnumerator GetEnumerator( );
    public short GetInt16(string name);
```

```
public int GetInt32(string name);  
public long GetInt64(string name);  
public sbyte GetSByte(string name);  
public float GetSingle(string name);  
public string GetString(string name);  
public ushort GetUInt16(string name);  
public uint GetUInt32(string name);  
public ulong GetUInt64(string name);  
public object GetValue(string name, Type type);  
public void SetType(Type type);  
}
```

Passed To

Multiple types

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

SerializationInfoEnumerator

System.Runtime.Serialization
(mscorlib.dll)

sealed
class

This class provides an enumerator to iterate over the elements contained in the `SerializationInfo`. Each element is of type `SerializationEntry`.

```
public sealed class SerializationInfoEnumerator : IEnumerator {  
    // Public Instance Properties  
    public SerializationEntry Current{get; }  
    public string Name{get; }  
    public Type ObjectType{get; }  
    public object Value{get; }  
    // Public Instance Methods  
    public bool MoveNext( );  
    // implements IEnumerator  
    public void Reset( );  
    // implements IEnumerator  
}
```

Returned By

```
SerializationInfo.GetEnumerator( )
```

StreamingContext

serializable


System.Runtime.Serialization (mscorlib.dll)

struct

This class describes the source or destination of a serialized stream. The context can determine how classes are serialized and require special parsing during deserialization. The **State** property holds a value from **StreamingContextStates** that indicates the destination of object data during serialization and the source of data during deserialization. This could indicate that you are serializing data to a file, for example, or deserializing data that came from another process.

```
public struct StreamingContext {  
    // Public Constructors  
    public StreamingContext(StreamingContextStates state);  
    public StreamingContext(StreamingContextStates state, object additional);  
    // Public Instance Properties  
    public object Context {get; }  
    public StreamingContextStates State {get; }  
    // Public Instance Methods  
    public override bool Equals(object obj);  
    // overrides ValueType  
    public override int GetHashCode( );  
    // overrides ValueType  
}
```

Hierarchy



Returned By

```
Formatter.Context,  
System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.Context,  
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.Context,  
IFormatter.Context
```

Passed To

Multiple types


StreamingContextStates serializable, flag

System.Runtime.Serialization (mscorlib.dll) *enum*

This enumeration contains values that describe types of streams that serialized data derives from or targets.

```
public enum StreamingContextStates {  
    CrossProcess = 0x00000001 ,  
    CrossMachine = 0x00000002 ,  
    File = 0x00000004 ,  
    Persistence = 0x00000008 ,  
    Remoting = 0x00000010 ,  
    Other = 0x00000020 ,  
    Clone = 0x00000040 ,  
    CrossAppDomain = 0x00000080 ,  
    All = 0x000000FF  
}
```

Hierarchy



Returned By

StreamingContext.State

Passed To

StreamingContext.StreamingContext()

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

SurrogateSelector

System.Runtime.Serialization
(mscorlib.dll)

class

This class is the basic implementation of the `ISurrogateSelector` interface. A formatter uses this class to find the appropriate surrogate object to serialize or deserialize an object of a specific type, assembly, or container.

```
public class SurrogateSelector : ISurrogateSelector {  
    // Public Constructors  
    public SurrogateSelector( );  
    // Public Instance Methods  
    public virtual void AddSurrogate(Type type, StreamingContext context,  
        ISerializationSurrogate surrogate);  
    public virtual void ChainSelector(ISurrogateSelector selector)  
    // implements ISurrogateSelector  
    public virtual ISurrogateSelector GetNextSelector( );  
    // implements ISurrogateSelector  
    public virtual ISerializationSurrogate GetSurrogate(Type type, StreamingContext context,  
        out ISurrogateSelector selector)  
    // implements ISurrogateSelector  
    public virtual void RemoveSurrogate(Type type, StreamingContext context);  
}
```


[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

Chapter 39.

System.Runtime.Serialization.Formatters

This chapter covers the `System.Runtime.Serialization.Formatters` namespace, which contains a number of types that are used by serialization formatters. [Figure 39-1](#) shows the types in this namespace. This chapter also features `BinaryFormatter` and `SoapFormatter`, two formatters that live in their own namespace and rely on the types in the `System.Runtime.Serialization.Formatters` namespace.

Figure 39-1. The `System.Runtime.Serialization.Formatters` namespace



BinaryFormatter

System.Runtime.Serialization.Formatter.Binary *sealed class* (mscorlib.dll)

This formatter uses a binary format to serialize or deserialize a single object or an object graph.

```
public sealed class BinaryFormatter : System.Runtime.Remoting.Messaging.IRemotingFormat
    System.Runtime.Serialization.IFormatter {
// Public Constructors
    public BinaryFormatter( );
    public BinaryFormatter(System.Runtime.Serialization.ISurrogateSelector selector,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public FormatterAssemblyStyle AssemblyFormat{set; get; }
    public SerializationBinder Binder{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public StreamingContext Context{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public TypeFilterLevel FilterLevel{set; get; }
    public ISurrogateSelector SurrogateSelector{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public FormatterTypeStyle TypeFormat{set; get; }
// Public Instance Methods
    public object Deserialize(System.IO.Stream serializationStream)
// implements System.Runtime.Serialization.IFormatter
    public object Deserialize(System.IO.Stream serializationStream,
        System.Runtime.Remoting.Messaging.HeaderHandler handler);
// implements System.Runtime.Remoting.Messaging.IRemotingFormatter
    public object DeserializeMethodResponse(System.IO.Stream serializationStream,
        System.Runtime.Remoting.Messaging.HeaderHandler handler,
        System.Runtime.Remoting.Messaging.IMethodCallMessage methodCallMessage);
    public void Serialize(System.IO.Stream serializationStream, object graph);
// implements System.Runtime.Serialization.IFormatter
    public void Serialize(System.IO.Stream serializationStream, object graph,
        System.Runtime.Remoting.Messaging.Header[ ] headers);
// implements System.Runtime.Remoting.Messaging.IRemotingFormatter
    public object UnsafeDeserialize(System.IO.Stream serializationStream,
        System.Runtime.Remoting.Messaging.HeaderHandler handler);
    public object UnsafeDeserializeMethodResponse(System.IO.Stream serializationStream,
        System.Runtime.Remoting.Messaging.HeaderHandler handler,
        System.Runtime.Remoting.Messaging.IMethodCallMessage methodCallMessage);
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

FormatterAssemblyStyle serializable

System.Runtime.Serialization.Formatters (mscorlib.dll) *enum*

This enumeration controls how assembly names are serialized. **Simple** serializes assemblies using only the assembly name. The default, **Full**, includes the assembly name, its culture, public key token, and version.

```
public enum FormatterAssemblyStyle {  
    Simple = 0,  
    Full = 1  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → **FormatterAssemblyStyle**

Returned By

System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.AssemblyFormat,
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.AssemblyFormat

Passed To

System.Runtime.Serialization.Formatters.Binary.BinaryFormatter.AssemblyFormat,
System.Runtime.Serialization.Formatters.Soap.SoapFormatter.AssemblyFormat

FormatterTypeStyle

serializable

System.Runtime.Serialization.FormatterTypes (mscorlib.dll) *enum*

This enumeration controls how type information is specified for members. **TypesAlways** specifies that type information be placed in the serialization stream for all object members. The default, **TypesWhenNeeded**, places type information in the stream for the following: object arrays, members of type **System.Object**, and nonprimitive value types (such as structs and enums) that implement the **ISerializable** interface. **XsdString** can be bitwise-ORed with another option to specify that strings are represented with the XSD format instead of the SOAP format.

```
public enum FormatterTypeStyle {
    TypesWhenNeeded = 0 ,
    TypesAlways = 1 ,
    XsdString = 2
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → FormatterTypeStyle

Returned By

System.Runtime.Serialization.FormatterTypes.Binary.BinaryFormatter.TypeFormat, System.Runtime.Serialization.FormatterTypes.Soap.SoapFormatter.TypeFormat

Passed To

System.Runtime.Serialization.FormatterTypes.Binary.BinaryFormatter.TypeFormat, System.Runtime.Serialization.FormatterTypes.Soap.SoapFormatter.TypeFormat

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

IFieldInfo

System.Runtime.Serialization.Formatter (mscorlib.dll) *interface*

This interface can expose the field names and types of serialized objects. It is used to supply parameter type information to the `SoapFormatter` when deserializing in SOAP RPC format.

```
public interface IFieldInfo {  
    // Public Instance Properties  
    public string[ ] FieldNames{set; get; }  
    public Type[ ] FieldTypes{set; get; }  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

I SoapMessage

System.Runtime.Serialization.Formatter (mscorlib.dll) *interface*

This type defines the interface used by `SoapMessage`. This interface is used to serialize and deserialize SOAP in RPC format.

```
public interface ISoapMessage {  
    // Public Instance Properties  
    public Header[] Headers {set; get; }  
    public string MethodName {set; get; }  
    public string[] ParamNames {set; get; }  
    public Type[] ParamTypes {set; get; }  
    public object[] ParamValues {set; get; }  
    public string XmlNamespace {set; get; }  
}
```

Implemented By

`SoapMessage`

Returned By

`System.Runtime.Serialization.Formatter.Soap.SoapFormatter.TopObject`

Passed To

`System.Runtime.Serialization.Formatter.Soap.SoapFormatter.TopObject`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ServerFault

serializable

System.Runtime.Serialization.FormatterServices *sealed*
(mscorlib.dll) *class*

This class represents an error that was thrown from a remote server to the client. It is placed in the **Detail** section of a **SoapFault** object.

```
public sealed class ServerFault {  
    // Public Constructors  
    public ServerFault(string exceptionType, string message, string stackTrace);  
    // Public Instance Properties  
    public string ExceptionMessage {set; get; }  
    public string ExceptionType {set; get; }  
    public string StackTrace {set; get; }  
}
```

Passed To

SoapFault.ServerFault()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[Team LiB]

◀ PREVIOUS

NEXT ▶

SoapFault

serializable

System.Runtime.Serialization.FormatterServices *sealed* (mscorlib.dll) *class*

This class represents a SOAP fault.

```
public sealed class SoapFault : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public SoapFault( );
    public SoapFault(string faultCode, string faultString, string faultActor, ServerFault
// Public Instance Properties
    public object Detail{set; get; }
    public string FaultActor{set; get; }
    public string FaultCode{set; get; }
    public string FaultString{set; get; }
// Public Instance Methods
    public void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// implements ISerializable
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

[Team LiB]

◀ PREVIOUS

NEXT ▶

SoapFormatter

System.Runtime.Serialization.Formatter.S Soap *sealed*
(system.runtime.serialization.formatters.soap.dll) *class*

This formatter performs SOAP serialization or deserialization on a single object or an object graph.

```
public sealed class SoapFormatter : System.Runtime.Remoting.Messaging.IRemotingFormatte
    System.Runtime.Serialization.IFormatter {
// Public Constructors
    public SoapFormatter( );
    public SoapFormatter(System.Runtime.Serialization.ISurrogateSelector selector,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public FormatterAssemblyStyle AssemblyFormat{set; get; }
    public SerializationBinder Binder{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public StreamingContext Context{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public TypeFilterLevel FilterLevel{set; get; }
    public ISurrogateSelector SurrogateSelector{set; get; }
// implements System.Runtime.Serialization.IFormatter
    public ISoapMessage TopObject{set; get; }
    public FormatterTypeStyle TypeFormat{set; get; }
// Public Instance Methods
    public object Deserialize(System.IO.Stream serializationStream)
// implements System.Runtime.Serialization.IFormatter
    public object Deserialize(System.IO.Stream serializationStream,
        System.Runtime.Remoting.Messaging.HeaderHandler handler);
// implements System.Runtime.Remoting.Messaging.IRemotingFormatter
    public void Serialize(System.IO.Stream serializationStream,
        object graph);
// implements System.Runtime.Serialization.IFormatter

    public void Serialize(System.IO.Stream serializationStream, object graph,
        System.Runtime.Remoting.Messaging.Header[ ] headers);
// implements System.Runtime.Remoting.Messaging.IRemotingFormatter
}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

SoapMessage

serializable

System.Runtime.Serialization.FormatterServices *class*
(mscorlib.dll)

This type encapsulates a message sent as part of a SOAP RPC (Remote Procedure Call).

```
public class SoapMessage : ISoapMessage {
// Public Constructors
    public SoapMessage( );
// Public Instance Properties
    public Header[] Headers{set; get; }
// implements ISoapMessage
    public string MethodName{set; get; }
// implements ISoapMessage
    public string[] ParamNames{set; get; }
// implements ISoapMessage
    public Type[] ParamTypes{set; get; }
// implements ISoapMessage
    public object[] ParamValues{set; get; }
// implements ISoapMessage
    public string XmlNamespace{set; get; }
// implements ISoapMessage
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TypeFilterLevel .NET 1.1, serializable

System.Runtime.Serialization.Formatter (mscorlib.dll) *enum*

This enumeration lists the possible values for the levels of automatic deserialization. **Low** provides some security by only supporting basic remoting types.

```
public enum TypeFilterLevel {  
    Low = 2,  
    Full = 3  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → TypeFilterLevel

Returned By

System.Runtime.Serialization.Formatter.Binary.BinaryFormatter.FilterLevel,
System.Runtime.Serialization.Formatter.Soap.SoapFormatter.FilterLevel


Passed To

System.Runtime.Serialization.Formatter.Binary.BinaryFormatter.FilterLevel,
System.Runtime.Serialization.Formatter.Soap.SoapFormatter.FilterLevel,
System.Runtime.Serialization.FormatterServices.CheckTypeSecurity()

Chapter 40. System.Text

The `System.Text` namespace provides encoding and decoding capabilities for arrays of bytes and characters. These classes allow you to convert characters easily from different subsets of Unicode encodings, such as ASCII, UTF-8, and UTF-16. Additionally, a string-building class allows you to modify strings without creating intermediate string objects. [Figure 40-1](#) shows the types in this namespace.

Figure 40-1. The System.Text namespace



ASCIIEncoding CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll) *class*

This class is a character encoding that encodes Unicode characters as 7-bit ASCII characters. ASCII uses first 128 chayracters of a Unicode encoding.

```
public class ASCIIEncoding : Encoding {
// Public Constructors
    public ASCIIEncoding( );
// Public Instance Methods
    public override int GetByteCount(char[ ] chars, int index, int count)
// overrides Encoding
    public override int GetByteCount(string chars);
// overrides Encoding
    public override int GetBytes(char[ ] chars, int charIndex, int charCount, byte[ ] by
        int byteIndex)
// overrides Encoding
    public override int GetBytes(string chars, int charIndex, int charCount, byte[ ] byt
        int byteIndex)
// overrides Encoding
    public override int GetCharCount(byte[ ] bytes, int index, int count)
// overrides Encoding
    public override int GetChars(byte[ ] bytes, int byteIndex, int byteCount, char[ ] ch
        int charIndex)
// overrides Encoding
    public override int GetMaxByteCount(int charCount);
// overrides Encoding
    public override int GetMaxCharCount(int byteCount);
// overrides Encoding
    public override string GetString(byte[ ] bytes);
// overrides Encoding
    public override string GetString(byte[ ] bytes,
// overrides Encoding
        int byteIndex, int byteCount);
}
```

Hierarchy

System.Object → Encoding → ASCIIEncoding

[Team LiB]

◀ PREVIOUS

NEXT ▶

Decoder

CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll)

abstract class

This class converts byte arrays to character arrays using the encoding class from which it was constructed. A `Decoder` is returned by the `GetDecoder()` method of an `Encoding` subclass. `Decoder` saves its state between calls to `GetChars()`, so leftover bytes from previous input byte arrays are remembered and used in subsequent calls.

```
public abstract class Decoder {
    // Protected Constructors
    protected Decoder( );
    // Public Instance Methods
    public abstract int GetCharCount(byte[ ] bytes, int index, int count);
    public abstract int GetChars(byte[ ] bytes, int byteIndex, int byteCount, char[ ] c
        int charIndex);
}
```

Returned By

`Encoding.GetDecoder()`

[Team LiB]

◀ PREVIOUS

NEXT ▶

Encoder CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll) *abstract class*

`Encoding.GetEncoder()` returns an instance of this type, which converts character arrays to byte array using the encoding subclass from which it was constructed. This class exposes the `GetBytes()` method, converts a sequence of character blocks into a sequence of byte blocks. Since `Encoder` maintains state between calls to `GetBytes()`, it can deal with partial sequences that occur at block boundaries.

The last argument to `GetBytes()` is a boolean that specifies whether the internal buffer is flushed after method is called. If `true`, state information on the object is lost between blocks. If `false` (the default), the buffer is maintained. A call with flushing set to `true` is needed on the final call to `Encoding.GetBytes()` to close the byte array properly.

```
public abstract class Encoder {
// Protected Constructors
    protected Encoder( );
// Public Instance Methods
    public abstract int GetByteCount(char[ ] chars, int index, int count, bool flush);
    public abstract int GetBytes(char[ ] chars, int charIndex, int charCount, byte[ ] by
        int byteIndex, bool flush);
}
```

Returned By

`Encoding.GetEncoder()`

Encoding CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll) *abstract class*

This class converts strings of Unicode characters to and from byte arrays. Derived classes implement specific encoding types. The `GetBytes()` method takes an array of characters and returns the corresponding array of bytes. The `GetChars()` method does the opposite conversion. `GetByteCount()` and `GetCharCount()` allow you to get the exact size of the encoding or decoding to size the output buffer appropriately.

The `GetEncoder()` and `GetDecoder()` methods create `Encoder` and `Decoder` instances that allow you to encode across sequential blocks in which partial byte codes may remain in the buffer.

```
public abstract class Encoding {
// Protected Constructors
    protected Encoding( );
    protected Encoding(int codePage);
// Public Static Properties
    public static Encoding ASCII{get; }
    public static Encoding BigEndianUnicode{get; }
    public static Encoding Default{get; }
    public static Encoding Unicode{get; }
    public static Encoding UTF7{get; }
    public static Encoding UTF8{get; }
// Public Instance Properties
    public virtual string BodyName{get; }
    public virtual int CodePage{get; }
    public virtual string EncodingName{get; }
    public virtual string HeaderName{get; }
    public virtual bool IsBrowserDisplay{get; }
    public virtual bool IsBrowserSave{get; }
    public virtual bool IsMailNewsDisplay{get; }
    public virtual bool IsMailNewsSave{get; }
    public virtual string WebName{get; }
    public virtual int WindowsCodePage{get; }
// Public Static Methods
    public static byte[] Convert(Encoding srcEncoding, Encoding dstEncoding, byte[] bytes,
        int index, int count);
    public static Encoding GetEncoding(int codepage);
    public static Encoding GetEncoding(string name);
// Public Instance Methods
    public override bool Equals(object value);
// overrides object
    public virtual int GetByteCount(char[] chars);
    public abstract int GetByteCount(char[] chars, int index, int count);
    public virtual int GetByteCount(string s);
```

```

public virtual byte[ ] GetBytes(char[ ] chars);
public virtual byte[ ] GetBytes(char[ ] chars, int index, int count);
public virtual byte[ ] GetBytes(string s);
public abstract int GetBytes(char[ ] chars, int charIndex, int charCount, byte[ ] bytes,
    int byteIndex);
public virtual int GetBytes(string s, int charIndex, int charCount, byte[ ] bytes,
    int byteIndex);
public virtual int GetCharCount(byte[ ] bytes);
public abstract int GetCharCount(byte[ ] bytes, int index, int count);
public virtual char[ ] GetChars(byte[ ] bytes);
public virtual char[ ] GetChars(byte[ ] bytes, int index, int count);
public abstract int GetChars(byte[ ] bytes, int byteIndex, int byteCount, char[ ] chars,
    int charIndex);
public virtual Decoder GetDecoder( );
public virtual Encoder GetEncoder( );
public override int GetHashCode( );
// overrides object
public abstract int GetMaxByteCount(int charCount);
public abstract int GetMaxCharCount(int byteCount);
public virtual byte[ ] GetPreamble( );
public virtual string GetString(byte[ ] bytes);
public virtual string GetString(byte[ ] bytes, int index, int count);
}

```

Subclasses

ASCIIEncoding , UnicodeEncoding , UTF7Encoding , UTF8Encoding

Returned By

System.IO.StreamReader.CurrentEncoding , System.IO.TextWriter.Encoding ,
 System.Xml.XmlParserContext.Encoding , System.Xml.XmlTextReader.Encoding ,
 System.Xml.XmlValidatingReader.Encoding

Passed To

System.IO.BinaryReader.BinaryReader(), System.IO.BinaryWriter.BinaryWriter(),
 System.IO.StreamReader.StreamReader(), System.IO.StreamWriter.StreamWriter(),
 System.String.String(), System.Xml.XmlParserContext.{Encoding , XmlParserContext()} ,
 System.Xml.XmlTextWriter.XmlTextWriter()

[Team LiB]

◀ PREVIOUS NEXT ▶

StringBuilder CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll)

sealed class

This **String** helper class enables in-place modification of a string without having to create new string instances. Since strings are immutable, their values cannot change once set. (Attempts to assign a new value to an existing string succeed, but at the expense of destroying and re-creating the original string.) The **StringBuilder** constructor sets the size of the **StringBuilder** and specifies the initial string it contains. The **Insert()** methods (in various overloads) insert (of varying types) into the **StringBuilder** at a specified position. **Append()** adds data to the end of a **StringBuilder**. The **ToString()** method converts the **StringBuilder** into a real string.

```
public sealed class StringBuilder {
// Public Constructors
    public StringBuilder( );
    public StringBuilder(int capacity);
    public StringBuilder(int capacity, int maxCapacity);
    public StringBuilder(string value);
    public StringBuilder(string value, int capacity);
    public StringBuilder(string value, int startIndex, int length, int capacity);
// Public Instance Properties
    public int Capacity{set; get; }
    public int Length{set; get; }
    public int MaxCapacity{get; }
    public char this[int index]{set; get; }
// Public Instance Methods
    public StringBuilder Append(bool value);
    public StringBuilder Append(byte value);
    public StringBuilder Append(char value);
    public StringBuilder Append(char[ ] value);
    public StringBuilder Append(char[ ] value, int startIndex, int charCount);
    public StringBuilder Append(char value, int repeatCount);
    public StringBuilder Append(decimal value);
    public StringBuilder Append(double value);
    public StringBuilder Append(short value);
    public StringBuilder Append(int value);
    public StringBuilder Append(long value);
    public StringBuilder Append(object value);
    public StringBuilder Append(sbyte value);
    public StringBuilder Append(float value);
    public StringBuilder Append(string value);
    public StringBuilder Append(string value, int startIndex, int count);
    public StringBuilder Append(ushort value);
    public StringBuilder Append(uint value);
    public StringBuilder Append(ulong value);
    public StringBuilder AppendFormat(IFormatProvider provider, string format, params ob
```

```

public StringBuilder AppendFormat(string format, object arg0);
public StringBuilder AppendFormat(string format,
    params object[ ] args);
public StringBuilder AppendFormat(string format, object arg0, object arg1);
public StringBuilder AppendFormat(string format, object arg0, object arg1, object ar
public int EnsureCapacity(int capacity);
public bool Equals(StringBuilder sb);
public StringBuilder Insert(int index, bool value);
public StringBuilder Insert(int index, byte value);
public StringBuilder Insert(int index, char value);
public StringBuilder Insert(int index, char[ ] value);
public StringBuilder Insert(int index, char[ ] value, int startIndex, int charCount)
public StringBuilder Insert(int index, decimal value);
public StringBuilder Insert(int index, double value);
public StringBuilder Insert(int index, short value);
public StringBuilder Insert(int index, int value);
public StringBuilder Insert(int index, long value);
public StringBuilder Insert(int index, object value);
public StringBuilder Insert(int index, sbyte value);
public StringBuilder Insert(int index, float value);
public StringBuilder Insert(int index, string value);
public StringBuilder Insert(int index, string value, int count);
public StringBuilder Insert(int index, ushort value);
public StringBuilder Insert(int index, uint value);
public StringBuilder Insert(int index, ulong value);
public StringBuilder Remove(int startIndex, int length);
public StringBuilder Replace(char oldChar, char newChar);
public StringBuilder Replace(char oldChar, char newChar, int startIndex, int count);
public StringBuilder Replace(string oldValue, string newValue);
public StringBuilder Replace(string oldValue, string newValue, int startIndex, int c
public override string ToString( );
// overrides object
public string ToString(int startIndex, int length);
}

```

Returned By

System.IO.StringWriter.GetStringBuilder()

Passed To

System.IO.StringWriter.StringWriter()

[Team LIB]

◀ PREVIOUS

NEXT ▶

UnicodeEncoding

CF 1.0, ECMA 1.0,
serializable

System.Text (mscorlib.dll)

class

This class encodes Unicode characters as UTF-16, two-byte characters. This class supports little-endian and big-endian encodings. With zero arguments, the overloaded constructor for this class uses little-endian byte order by default. The two-argument constructor can use a boolean `true` as the first argument to specify little-endian byte order. If set to `true`, the second boolean argument specifies the inclusion of the Unicode byte order mark in the resulting string. A `UnicodeEncoding` can also be obtained from two `Encoding` properties. A little-endian encoding is returned by `Encoding.Unicode`. A big-endian encoding is returned by `Encoding.BigEndianUnicode`.

```
public class UnicodeEncoding : Encoding {
    // Public Constructors
    public UnicodeEncoding( );
    public UnicodeEncoding(bool bigEndian, bool byteOrderMark);
    // Public Static Fields
    public const int CharSize;
    // =2
    // Public Instance Methods
    public override bool Equals(object value);
    // overrides Encoding
    public override int GetByteCount(char[] chars, int index, int count)
    // overrides Encoding
    public override int GetByteCount(string s);
    // overrides Encoding
    public override byte[] GetBytes(string s);
    // overrides Encoding
    public override int GetBytes(char[] chars, int charIndex, int charCount, byte[] bytes,
        int byteIndex)
    // overrides Encoding
    public override int GetBytes(string s, int charIndex, int charCount, byte[] bytes,
        int byteIndex)
    // overrides Encoding
    public override int GetCharCount(byte[] bytes, int index, int count)
    // overrides Encoding
    public override int GetChars(byte[] bytes, int byteIndex, int byteCount, char[] chars,
        int charIndex)
    // overrides Encoding
    public override Decoder GetDecoder( );
    // overrides Encoding
    public override int GetHashCode( );
    // overrides Encoding
```

```
        public override int GetMaxByteCount(int charCount);  
        // overrides Encoding  
        public override int GetMaxCharCount(int byteCount);  
        // overrides Encoding  
        public override byte[ ] GetPreamble( );  
        // overrides Encoding  
    }
```

Hierarchy

System.Object → Encoding → UnicodeEncoding

[Team LiB]

UTF7Encoding

CF 1.0, serializable

System.Text (mscorlib.dll) *class*

This class encodes Unicode characters as UTF-7, 7-bit characters. UTF-7 is a Unicode Transformation of the ASCII character set, designed for safe use over common Internet mail and news gateways. RFC 2152, which defines UTF-7, specifies an optional set of characters in the character set, which may or may not be encoded because they may interfere with mail-transfer header fields. The overloaded constructor has two forms that take this into account. With no arguments, the encoding object disallows the use of optional characters (such as exclamation points and dollar signs). With a single boolean argument set to `true`, these optional characters are allowed in the encoding.

```
public class UTF7Encoding : Encoding {
    // Public Constructors
    public UTF7Encoding( );
    public UTF7Encoding(bool allowOptionals);
    // Public Instance Methods
    public override int GetByteCount(char[] chars, int index, int count);
    // overrides Encoding
    public override int GetBytes(char[] chars, int charIndex, int charCount, byte[] bytes,
        int byteIndex)
    // overrides Encoding
    public override int GetCharCount(byte[] bytes, int index, int count)
    // overrides Encoding
    public override int GetChars(byte[] bytes, int byteIndex, int byteCount, char[] chars,
        int charIndex)
    // overrides Encoding
    public override Decoder GetDecoder( );
    // overrides Encoding
    public override Encoder GetEncoder( );
    // overrides Encoding
    public override int GetMaxByteCount(int charCount);
    // overrides Encoding
    public override int GetMaxCharCount(int byteCount);
    // overrides Encoding
}
```

Hierarchy

System.Object → Encoding → UTF7Encoding

UTF8Encoding CF 1.0, ECMA 1.0, serializable

System.Text (mscorlib.dll) *class*

This class encodes Unicode characters as UTF-8, 8-bit characters. The overloaded constructor allows zero, one, or two boolean parameters. The first argument indicates whether the encoder should both emit the byte order mark code and recognize it. The second boolean argument specifies whether to throw an exception when invalid bytes are encountered.

```
public class UTF8Encoding : Encoding {
    // Public Constructors
    public UTF8Encoding( );
    public UTF8Encoding(bool encoderShouldEmitUTF8Identifier);
    public UTF8Encoding(bool encoderShouldEmitUTF8Identifier, bool throwOnInvalidBytes)
    // Public Instance Methods
    public override bool Equals(object value);
    // overrides Encoding
    public override int GetByteCount(char[] chars, int index, int count)
    // overrides Encoding
    public override int GetByteCount(string chars);
    // overrides Encoding
    public override byte[] GetBytes(string s);
    // overrides Encoding
    public override int GetBytes(char[] chars, int charIndex, int charCount, byte[] bytes,
        int byteIndex)
    // overrides Encoding
    public override int GetBytes(string s, int charIndex, int charCount, byte[] bytes,
        int byteIndex)
    // overrides Encoding
    public override int GetCharCount(byte[] bytes, int index, int count)
    // overrides Encoding
    public override int GetChars(byte[] bytes, int byteIndex, int byteCount, char[] chars,
        int charIndex)
    // overrides Encoding
    public override Decoder GetDecoder( );
    // overrides Encoding
    public override Encoder GetEncoder( );
    // overrides Encoding
    public override int GetHashCode( );
    // overrides Encoding
    public override int GetMaxByteCount(int charCount);
    // overrides Encoding
    public override int GetMaxCharCount(int byteCount);
    // overrides Encoding
```

```
    public override byte[ ] GetPreamble( );  
    // overrides Encoding  
}
```

Hierarchy



[Team LiB]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 41.

System.Text.RegularExpressions

`System.Text.RegularExpressions` implements an object-oriented system for encapsulating regular expressions. The classes allow you to compile expressions and store matches that can be used with any .NET implementation regardless of the programming language. This namespace supports a regular expression syntax similar to Perl 5. Matches to the regular expression from an input string can be retrieved in fine granularity, allowing you to discern substring captures, groups, and multiple matches. [Figure 41-1](#) shows the classes in this namespace.

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Capture

CF 1.0, serializable

System.Text.RegularExpressions (system.dll)

class

This class represents a single result from a capturing group, which is a segment of a regular expression that is delineated, usually by parentheses. The parentheses signal .NET's regular expression engine to save that segment's result for later use. **Capture** objects compose the collection returned by **Group.Captures**. The **Value** property gets the captured substring. The **Index** property contains the starting position of the capture in the input string, while **Length** contains the length of the captured string.

```
public class Capture {  
    // Public Instance Properties  
    public int Index {get; }  
    public int Length {get; }  
    public string Value {get; }  
    // Public Instance Methods  
    public override string ToString( );  
    // overrides object  
}
```


Subclasses

Group

Returned By

CaptureCollection.this

Figure 41-1. The System.Text.RegularExpressions namespace



CaptureCollection

CF 1.0, serializable

System.Text.RegularExpressions (system.dll) *class*

This class contains a set of captures acquired by a single capturing group. A **CaptureCollection** is returned by **Group.Captures**. An integer indexer returns a single **Capture** object from this collection. The **Count** property gets the number of captures in the collection.

```
public class CaptureCollection : ICollection, IEnumerable {
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public bool IsReadOnly{get; }
    public bool IsSynchronized{get; }
// implements ICollection
    public object SyncRoot{get; }
// implements ICollection
    public Capture this[int i]{get; }
// Public Instance Methods
    public void CopyTo(Array array, int arrayIndex);
// implements ICollection
    public IEnumerator GetEnumerator( );
// implements IEnumerable
}
```

Returned By

Group.Captures

Group

CF 1.0, serializable

System.Text.RegularExpressions (system.dll) *class*

This class contains a group of results from a capturing group in a regular expression. A capturing group can return zero or more results depending on the use of quantifiers or nested groupings of a subexpression. `Captures` returns a `CaptureCollection` composed of individual `Capture` objects. `Captures` can use an indexer to return single results from the `CaptureCollection`.

You can treat a `Group` as an instance of its parent class (`Capture`) to get quick access to the last captured substring (an instance of `Group` is equal to the last item in its `Captures` property).

```
public class Group : Capture {  
    // Public Instance Properties  
    public CaptureCollection Captures {get; }  
    public bool Success {get; }  
    // Public Static Methods  
    public static Group Synchronized(Group inner);  
}
```

Hierarchy

`System.Object` → `Capture` → `Group`

Subclasses

`Match`

Returned By

`GroupCollection.this`

GroupCollection

CF 1.0, serializable

System.Text.RegularExpressions
(system.dll)*class*

This class is a collection of the captured groups in a regular expression. A **GroupCollection** is indexed by either a string with the name of the capture group, or with an integer number of the capture group as determined in the regular expression (give a name to a capture group by putting ? <name> immediately after the opening parenthesis). So, **Match.Groups["name"]** would retrieve a capture from the subexpression (?<name>expr), and **Match.Groups[1]** would be the result from the first explicitly grouped subexpression. The entire regular expression is the zero-indexed group (an expression without any groupings is treated as a single group). A **GroupCollection** is returned by **Match.Groups**.

```
public class GroupCollection : ICollection, IEnumerable {
// Public Instance Properties
    public int Count{get; }
// implements ICollection
    public bool IsReadOnly{get; }
    public bool IsSynchronized{get; }
// implements ICollection
    public object SyncRoot{get; }
// implements ICollection
    public Group this[string groupname]{get; }
    public Group this[int groupnum]{get; }
// Public Instance Methods
    public void CopyTo(Array array, int arrayIndex);
// implements ICollection
    public IEnumerator GetEnumerator( );
// implements IEnumerable
}
```

Returned By

Match.Groups

Match

CF 1.0, serializable

System.Text.RegularExpressions (system.dll) *class*

This class is a single match result of a regular expression. As with `Capture` and `Group`, `Match` has no public constructor. It is returned by `Regex.Match()` or as a member of a `MatchCollection` returned by `Regex.Matches()`. A `Match` instance contains the groups that have been captured in a `GroupCollection` returned by `Groups`. A `Match` inherits from `Group` and is equivalent to the zero-indexed group in its `GroupCollection` (the same as `Groups[0]`).

The `NextMatch()` method finds the next match result in the search string, starting at the end of the previous match. This method disregards any zero-width assertions on the tail of an expression and begins explicitly after the position of the last character of the previous result (even an empty result).

The `Result()` method takes a replacement pattern and returns the resulting string based on the current match. A replacement pattern is an expression that uses the group replacement syntax, such as `$1` or `${name}`. `Result()` expands the replacement variables corresponding to the captured groups, within its current result, and returns the string.

```
public class Match : Group {
// Public Static Properties
    public static Match Empty {get; }
// Public Instance Properties
    public virtual GroupCollection Groups {get; }
// Public Static Methods
    public static Match Synchronized(Match inner);
// Public Instance Methods
    public Match NextMatch( );
    public virtual string Result(string replacement);
}
```

Hierarchy

System.Object → Capture → Group → Match

Returned By

`MatchCollection.this`, `Regex.Match()`

Passed To

`MatchEvaluator.{BeginInvoke(), Invoke()}`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MatchCollection

CF 1.0, serializable

System.Text.RegularExpressions (system.dll) *class*

This class is a collection of **Match** objects returned by **Regex.Matches()**. This collection contains each match that an expression finds in the search string. The **Count** property returns the number of matches found in the string.

```
public class MatchCollection : ICollection, IEnumerable {  
    // Public Instance Properties  
    public int Count{get; }  
    // implements ICollection  
    public bool IsReadOnly{get; }  
    public bool IsSynchronized{get; }  
    // implements ICollection  
    public object SyncRoot{get; }  
    // implements ICollection  
    public virtual Match this[int i]{get; }  
    // Public Instance Methods  
    public void CopyTo(Array array, int arrayIndex);  
    // implements ICollection  
    public IEnumerator GetEnumerator( );  
    // implements IEnumerable  
}
```

Returned By

Regex.Matches()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

MatchEvaluator CF 1.0, serializable

System.Text.RegularExpressions *delegate* (system.dll)

This delegate can be called when a match is found during a `replace` operation. Several versions of the overloaded `Regex.Replace()` method take a `MatchEvaluator` as a parameter. `Regex.Replace()` walks through a search string looking for matches to a given expression and replaces each match using a specified replacement string. The `MatchEvaluator` delegate can be called on each match, getting passed the match result as a `Match` object.

```
public delegate string MatchEvaluator(Match match);
```

Passed To

```
Regex.Replace( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Regex

CF 1.0, serializable

System.Text.RegularExpressions
(system.dll)*class*

This class represents a regular expression. Use it to search for patterns in string data. It provides static methods that search for a pattern without explicitly creating `Regex` instances as well as instance methods that allow to interact with a `Regex` object.

The various static methods employed by `Regex` take the input string to search for as the first argument and a regular expression pattern string as the second. This is equivalent to constructing a `Regex` instance with the pattern string, using it, and destroying it immediately. Most methods are overloaded as instance methods as well. These do not require a pattern argument, as this is provided with the constructor.

The `Match()` and `Matches()` methods search an input string for a single match or all matches. Their overloads are the same. The first argument is the input string. You can specify which position in the string the search should start at using a second integer parameter. `Match()` also lets you specify the length of substring to search after that position. `IsMatch()` works the same way as `Match()`, except that it returns a boolean indicating whether the string contains a match.

The `Split()` method acts like the `System.String.Split()` method. It uses the `Regex` pattern as a delimiter to split the input string into an array of substrings. (The delimiter is not included in the substrings.) You can provide a maximum number of substrings to return, in which case the last substring returned is the remainder of the input string. You can also specify the position to start in the input string and a `RegexOptions` parameter.

The `Replace()` method uses a replacement string to replace each pattern match in an input string. The replacement string can include regular characters and backreference variable constructs (e.g., `$1` or `${n}`). `Replace()` can iterate through every match found in the input string, or it can specify a maximum number of replacements to perform. `Replace()` can also take an argument specifying a `MatchEvaluator` delegate that is called every time a match is found.

Two additional static methods can transform strings used with regular expressions. `Escape()` converts a string containing regular expression metacharacters by replacing them with escaped equivalents (for example, `.` be changed to `\.`). The set of metacharacters converted is `\, *, +, ?, |, {, [, (,), ^, $, ., #`, and whitespace. The `Unescape()` method replaces escaped characters within a string with their unescaped equivalents. Use `Escape()` and `Unescape()` when you need to use one of these metacharacters as a literal in a regular expression.

A set of instance methods for `Regex` provides information on the capturing groups contained in the expression. `GetGroupNames()` and `GetGroupNumbers()` each return an array containing the names of all the capturing groups or numbers of all capture groups, respectively. The `GroupNameFromNumber()` and `GroupNumberFromName()` methods return the corresponding name or number from the argument given them.

`CompileToAssembly()` allows you to create your own type for a regular expression object and save it to disk as an assembly. This is a static method that takes a `RegexCompilationInfo` object and an assembly name to build the type. The `RegexCompilationInfo` object contains the regular expression pattern and additional

information needed for the compilation.

```

public class Regex : System.Runtime.Serialization.ISerializable {
// Public Constructors
    public Regex(string pattern);
    public Regex(string pattern, RegexOptions options);
// Protected Constructors
    protected Regex( );
// Public Instance Properties
    public RegexOptions Options{get; }
    public bool RightToLeft{get; }
// Public Static Methods
    public static void CompileToAssembly(RegexCompilationInfo[ ] regexinfos,
        System.Reflection.AssemblyName assemblyname);
    public static void CompileToAssembly(RegexCompilationInfo[ ] regexinfos,
        System.Reflection.AssemblyName assemblyname,
        System.Reflection.Emit.CustomAttributeBuilder[ ] attributes);
    public static void CompileToAssembly(RegexCompilationInfo[ ] regexinfos,
        System.Reflection.AssemblyName assemblyname,
        System.Reflection.Emit.CustomAttributeBuilder[ ] attributes, string resourceFile);
    public static string Escape(string str);
    public static bool IsMatch(string input, string pattern);
    public static bool IsMatch(string input, string pattern, RegexOptions options);
    public static Match Match(string input, string pattern);
    public static Match Match(string input, string pattern, RegexOptions options);
    public static MatchCollection Matches(string input, string pattern);
    public static MatchCollection Matches(string input, string pattern, RegexOptions opt);
    public static string Replace(string input, string pattern, MatchEvaluator evaluator);
    public static string Replace(string input, string pattern, MatchEvaluator evaluator,
        RegexOptions options);
    public static string Replace(string input, string pattern, string replacement);
    public static string Replace(string input, string pattern, string replacement,
        RegexOptions options);
    public static string[ ] Split(string input, string pattern);
    public static string[ ] Split(string input, string pattern, RegexOptions options);
    public static string Unescape(string str);
// Public Instance Methods
    public string[ ] GetGroupNames( );
    public int[ ] GetGroupNumbers( );
    public string GroupNameFromNumber(int i);
    public int GroupNumberFromName(string name);
    public bool IsMatch(string input);
    public bool IsMatch(string input, int startat);
    public Match Match(string input);
    public Match Match(string input, int startat);
    public Match Match(string input, int beginning, int length);
    public MatchCollection Matches(string input);
    public MatchCollection Matches(string input, int startat);
    public string Replace(string input, MatchEvaluator evaluator);

```

```

    public string Replace(string input, MatchEvaluator evaluator, int count);
    public string Replace(string input, MatchEvaluator evaluator, int count, int startat);
    public string Replace(string input, string replacement);
    public string Replace(string input, string replacement, int count);
    public string Replace(string input, string replacement, int count, int startat);
    public string[ ] Split(string input);
    public string[ ] Split(string input, int count);
    public string[ ] Split(string input, int count, int startat);
    public override string ToString( );
// overrides object
// Protected Instance Methods
    protected override void Finalize( );
// overrides object
    protected void InitializeReferences( );
    protected bool UseOptionC( );
    protected bool UseOptionR( );
}

```

Passed To

System.Net.WebPermission.{AddPermission(), WebPermission()}

[Team LiB]

◀ PREVIOUS

NEXT ▶

RegexCompilationInfo

serializable

System.Text.RegularExpressions (system.dll)

class

This class holds the information that is needed to compile a regular expression to an assembly with `Regex.CompileToAssembly()`. The constructor takes five arguments, which correspond to its available properties: the pattern string, the `RegexOptions` option set, the name of the compiled type, the namespace for the type, and a boolean indicating if the type is public (`true`) or private (`false`).

```
public class RegexCompilationInfo {  
    // Public Constructors  
    public RegexCompilationInfo(string pattern, RegexOptions options, string name,  
                                string fullnamespace, bool ispublic);  
    // Public Instance Properties  
    public bool IsPublic{set; get; }  
    public string Name{set; get; }  
    public string Namespace{set; get; }  
    public RegexOptions Options{set; get; }  
    public string Pattern{set; get; }  
}
```

Passed To

```
Regex.CompileToAssembly( )
```


RegexOptions CF 1.0, serializable, flag

System.Text.RegularExpressions (system.dll) *enum*

This enumeration contains various options that affect the behavior of pattern matching in various methods from the `System.Text.RegularExpressions` namespace. The values of this enumeration are passed to these methods as a bitwise-OR combination of the specified options.

```
public enum RegexOptions {
    None = 0x00000000 ,
    IgnoreCase = 0x00000001 ,
    Multiline = 0x00000002 ,
    ExplicitCapture = 0x00000004 ,
    Compiled = 0x00000008 ,
    Singleline = 0x00000010 ,
    IgnorePatternWhitespace = 0x00000020 ,
    RightToLeft = 0x00000040 ,
    ECMAScript = 0x00000100 ,
    CultureInvariant = 0x00000200
}
```

Hierarchy



Returned By

Regex.Options, RegexCompilationInfo.Options

Passed To

Regex.{IsMatch(), Match(), Matches(), Regex(), Replace(), Split()},
RegexCompilationInfo.{Options, RegexCompilationInfo()}

Chapter 42. System.Threading

A "thread" is an abstraction of the platform, providing the impression that the CPU is performing multiple tasks simultaneously; in essence, it offers to the programmer the ability to walk and chew gum at the same time. The .NET framework makes heavy use of threads throughout the system, both visibly and invisibly. The `System.Threading` namespace contains most of the baseline threading concepts, usable either directly or to help build higher-level constructs (as the .NET Framework Class Library frequently does).

The "thread" itself is sometimes referred to as a "lightweight process" (particularly within the Unix communities). This is because the thread, like the concept of a process, is simply an operating system (or, in the case of .NET, a CLR) abstraction. In the case of Win32 threads, the operating system is responsible for "switching" the necessary execution constructs (the registers and thread stack) on the CPU in order to execute the code on the thread, just as the OS does for multiple programs running simultaneously on the machine. The key difference between a process and a thread, however, is that each process gets its own inviolable memory space-its "process space"-that other processes cannot touch. All threads belong to a single process and share the same process space; therefore, threads can operate cooperatively on a single object. However, this is both an advantage and a disadvantage-if multiple threads can all access a single object, there arises the possibility that the threads will be acting concurrently against the object, leading to some interesting (and unrepeatable) results.

For example, one common problem in VB and MFC code was the inability to process user input while carrying out some other function; this was because the one (and only) thread used to process user input events (button clicks, menu selections, and so on) was also used to carry out the requests to the database, the calculation of results, the generation of pi to the millionth decimal place, and so on. Users could not negate actions ("Oh, shoot, I didn't mean to click that...."), because the user's UI actions-clicking a "Cancel" button, for example-wouldn't be processed until the non-UI action finished first. This would lead the user to believe that the program has "hung."

The first reaction might be to simply fire off every "action" from a UI event in its own thread; this would be a naive reaction at best, as a huge source of bugs and data corruption is more likely. Consider, for a moment, a simple UI that runs off to the database and performs a query when the user clicks a button. It would be tempting to simply spin the database query off in its own thread and update the UI if and when the database query completes.

The problems come up when the query returns-when do we put the results up? If the user has the ability to update the information (before the query results are returned), then does the new data overwrite the user's input? Or should the user's input overwrite the query results? What happens if the user clicks the button again? Should we fire off another query? Worse yet, what happens if the user has moved to a different part of the application? Should the UI "suddenly" flip back to the place from which the query was originated and update the values there? This would make it appear to the user that "some weird bug just took over" the program. But if the query silently updates the data, the user may wonder whether that query ever actually finished.

As is common with such capabilities, however, with power comes responsibility. Callous use of threads within an application can not only create these sorts of conundrums regarding UI design, but

also lead to mysterious and inexplicable data corruption. Consider the simple expression $x = x + 5$. If x is a single object living in the heap, and two threads both simultaneously execute this code, one of several things can occur.

In the first case, the two threads are slightly ahead of or behind one another; the first thread obtains the value of x , adds 5, and stores that value back to x . The second thread, right behind it, does the same. x is incremented by 10. Consider the case, however, when both threads are in exactly the same place in the code. The first thread obtains the value of x (call it 10). The second thread gets switched in and loads the value of x (again, still 10). The first thread switches back in and increments its local value for x (which is 10, now 15). The second thread switches in and increments its local value for x (which is 10, now 15). The first thread stores its new local value for x back into x (15). The second thread switches in and stores its new local value for x (15). Both threads executed, yet the value of x grows by only 5, not 10, as should have happened.

For this reason, threads must often be held up in certain areas of code, in order to wait until another thread is finished. This is called "thread synchronization," sometimes colloquially referred to as "locks." It is the programmer's responsibility to ensure that any thread-sensitive code (such as the previous $x = x + 5$ example) is properly thread-synchronized. Within C++ and VB 6, this could only be done by making use of Win32 synchronization objects such as events and critical sections; however, a simpler mechanism is available in the CLR.

Each object can have a corresponding "monitor" associated with it. This monitor serves as thread-synchronization primitive, since only one thread within the CLR can "own" the monitor. Synchronization is then achieved by forcing threads to wait to acquire the monitor on the object before being allowed to continue; this is very similar to the Win32 critical section. (This monitor is an instance of the `Monitor` type; see that type for more details.)

Anytime locks are introduced into a system, however, two dangers occur: safety and liveness. *Safety* refers to the presence of the kind of data corruption discussed earlier-the lack of enough thread synchronization. *Liveness* is the actual time the threads spend executing, and often represents the opposite danger as safety (the presence of too much thread synchronization, particularly the danger of *deadlock*: two threads frozen forever, each waiting for a lock the other one already holds). An excellent discussion of these two concepts can be found in Doug Lea's book *Concurrent Programming in Java: Design Principles and Pattern, Second Edition* (Addison Wesley). (Despite Java code samples, 99% of his discussion pertains to threading in .NET as well.)

Frequently programmers wish to perform some sort of asynchronous operation. One approach is to simply create a `Thread` object and start it off. Unfortunately, this is also somewhat wasteful, since the cost of creating a thread and destroying it (when the thread has finished executing) is quite high. For this reason, it is often more performant to "borrow" an existing and unused thread-this is the purpose of the `ThreadPool` type, and one such pool already exists for use by the CLR runtime for processes such as the asynchronous execution of delegates (see `System.Delegate` for more details).

[Figure 42-1](#) shows many of the classes in this namespace. [Figure 42-2](#) shows the delegates, exceptions, and event arguments. [Figure 42-3](#) shows a state diagram for threads.

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

ApartmentState

serializable

System.Threading (mscorlib.dll) *enum*


This type is entirely unnecessary for "normal" .NET code; it is needed only for COM interoperability capability.

Apartments are a COM-threading construct. There are two threading apartments: *single-threaded* (**STA**) and *multithreaded* (**MTA**). Once a thread joins an apartment, it cannot join another one. If you want to create or access a COM object from a thread, that thread must belong to an apartment. Further, a given COM component may only be compatible with a certain apartment state.

What if an **STA** thread needs to call a method on a COM object that is only compatible with **MTA** threads? In that case, a different thread that is already in the **MTA** state must service the request. The COM Service Control Manager either creates a new thread or uses one allocated for servicing remote procedure calls to accomplish this

Threads in an **MTA** apartment cannot directly access **STA** threads either. Instead, the **STA** thread contains a message sink, and the method is invoked when the thread in that apartment is free. .NET objects do away with this requirement; however, if some of the threads call COM objects, they must first join an apartment. The **Thread** class usually handles this automatically, but you can join an apartment directly by assigning a parameter from this enumeration to the **Thread.ApartmentState** property. **Unknown** indicates that the thread has not joined an apartment.

Figure 42-1. The System.Threading namespace



```
public enum ApartmentState {
    STA = 0,
    MTA = 1,
    Unknown = 2
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → ApartmentState


Returned By

Thread.ApartmentState

Passed To

Thread.ApartmentState

Figure 42-2. Delegates, exceptions, and event arguments in the System.Threading namespace



AutoResetEvent

CF 1.0, marshal by reference,
disposable

System.Threading (mscorlib.dll) *sealed class*


This class presents a `WaitHandle` with two states: signaled and nonsignaled. If nonsignaled, waiting threads block; otherwise they continue executing. It is constructed with an initial signal value and can be `Set()` to signaled or `Reset()` to nonsignaled. When signaled, the `AutoResetEvent` automatically resets to nonsignaled once a single blocking thread has been released. Calling `Set()` with no blocking threads causes it to remain signaled until another thread waits on it.

```
public sealed class AutoResetEvent : WaitHandle {  
    // Public Constructors  
    public AutoResetEvent(bool initialState);  
    // Public Instance Methods  
    public bool Reset( );  
    public bool Set( );  
}
```

Hierarchy



Figure 42-3. Thread state transitions



[Team LiB]

[< PREVIOUS](#)
[NEXT >](#)

Interlocked

CF 1.0, ECMA 1.0

System.Threading (mscorlib.dll) *sealed class*

The static members of this class provide thread safety for common built-in arithmetic operations, such as increasing and decreasing a variable by one, and exchanging variables.

If two threads increment the same variable, one thread could be interrupted after both have retrieved the value of the variable. If this happens, then both operations store the same value, meaning that the variable has been incremented once instead of twice. The **Interlocked** methods protect against this kind of error.

Increment() and **Decrement**() increase and decrease a variable by one, respectively, and **Exchange**() switches two variables. **CompareExchange**() compares the first two variables and, if **true**, assigns the first value to the first variable.

```
public sealed class Interlocked {
// Public Static Methods
    public static int CompareExchange(ref int location1, int value, int comparand);
    public static object CompareExchange(ref object location1, object value, object comparand);
    public static float CompareExchange(ref float location1, float value, float comparand);
    public static int Decrement(ref int location);
    public static long Decrement(ref long location);
    public static int Exchange(ref int location1, int value);
    public static object Exchange(ref object location1, object value);
    public static float Exchange(ref float location1, float value);
    public static int Increment(ref int location);
    public static long Increment(ref long location);
}
```

[Team LiB]

[< PREVIOUS](#)
[NEXT >](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IOCompletionCallback

serializable

System.Threading (mscorlib.dll)

delegate

This delegate is used to communicate with thread pools that are created using the Win32 API. This is a delegate to a method that will be called by an unmanaged process.

```
public delegate void IOCompletionCallback(uint errorCode, uint numBytes,
    NativeOverlapped *pOVERLAP);
```

Passed To

```
Overlapped.{Pack( ), UnsafePack( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

LockCookie

serializable

System.Threading (mscorlib.dll)

struct

This structure returns a `LockCookie` representing the type of lock (read or write) released. The same type of lock can be restored by calling `ReaderWriterLock.RestoreLock()`.

```
public struct LockCookie {  
    // No public or protected members  
}
```

Hierarchy



Returned By

```
ReaderWriterLock.{ReleaseLock( ), UpgradeToWriterLock( )}
```

Passed To

```
ReaderWriterLock.{DowngradeFromWriterLock( ), RestoreLock( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ManualResetEvent

CF 1.0, marshal by
reference, disposable

System.Threading (mscorlib.dll)

sealed class

This class is a `WaitHandle` with two states: signaled and nonsignaled. If nonsignaled, waiting threads block. If signaled, they continue executing. It is constructed with an initial signal value and can be `Set()` to signaled or `Reset()` to nonsignaled. Once signaled, you must manually (hence the name of this type) call `Reset()` to revert it to nonsignaled.

```
public sealed class ManualResetEvent : WaitHandle {  
    // Public Constructors  
    public ManualResetEvent(bool initialState);  
    // Public Instance Methods  
    public bool Reset( );  
    public bool Set( );  
}
```

Hierarchy



Monitor

CF 1.0, ECMA 1.0

System.Threading (mscorlib.dll) *sealed class*

This class contains static methods for thread communication and synchronization. The `Enter()` and `Exit()` methods allow you to obtain and release a lock on an object, respectively. If an object lock has already been obtained by another thread, `Enter()` blocks and resumes executing when the lock is released.

Various languages have the ability to silently emit calls on this type as language built-in primitives. C#'s `lock{ }` syntax translates into these two methods: the beginning of the `lock` block is transformed into a call to `Enter()`, and the close of the block calls `Exit()`. (In the presence of exceptions and return calls, the C# compiler must ensure the release of the monitor regardless of how the code exits the `lock` block.)

`TryEnter()` attempts to obtain an object lock, but it continues executing and returns false if unsuccessful. `Wait()` releases an object lock and causes the current thread to wait until another thread calls `Pulse()` or `PulseAll()` on the same object. `Wait()` must be executed from a synchronized block of code.

```
public sealed class Monitor {
// Public Static Methods
    public static void Enter(object obj);
    public static void Exit(object obj);
    public static void Pulse(object obj);
    public static void PulseAll(object obj);
    public static bool TryEnter(object obj);
    public static bool TryEnter(object obj, int millisecondsTimeout);
    public static bool TryEnter(object obj, TimeSpan timeout);
    public static bool Wait(object obj);
    public static bool Wait(object obj, int millisecondsTimeout);
    public static bool Wait(object obj, int millisecondsTimeout, bool exitContext);
    public static bool Wait(object obj, TimeSpan timeout);
    public static bool Wait(object obj, TimeSpan timeout, bool exitContext);
}
```


Mutex

CF 1.0, marshal by reference, disposable

System.Threading (mscorlib.dll) *sealed class*

A **Mutex** is an implementation of a **WaitHandle**. **ReleaseMutex()** releases a lock on a **WaitHandle**. A thread that owns a **Mutex** lock can call any of the **Wait()** methods (defined in the parent class, **WaitHandle**) without blocking, but must then release the **Mutex** the same number of times as the **Mutex** was obtained.

```
public sealed class Mutex : WaitHandle {  
    // Public Constructors  
    public Mutex( );  
    public Mutex(bool initiallyOwned);  
    public Mutex(bool initiallyOwned, string name);  
    public Mutex(bool initiallyOwned, string name, out bool createdNew);  
    // Public Instance Methods  
    public void ReleaseMutex( );  
}
```

Hierarchy



NativeOverlapped

System.Threading (mscorlib.dll) *struct*

This structure has the same layout as the Win32 **OVERLAPPED** structure, with extra reserved data at the end, which is provided for backward compatibility. Create a **NativeOverlapped** instance by calling **Overlapped.Pack()**. Each time an instance is created, it must be freed by calling the static method **Overlapped.Free()** to avoid a memory leak.

```
public struct NativeOverlapped {  
    // Public Instance Fields  
    public int EventHandle;  
    public int InternalHigh;  
    public int InternalLow;  
    public int OffsetHigh;  
    public int OffsetLow;  
}
```

Hierarchy

System.Object → System.ValueType → NativeOverlapped

Returned By

```
Overlapped.{Pack( ), UnsafePack( )}
```

Passed To

```
IOCompletionCallback.{BeginInvoke( ), Invoke( )}, Overlapped.{Free( ), Unpack( )}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Overlapped

System.Threading (mscorlib.dll) *class*

This class encapsulates the Win32 API `OVERLAPPED` structure. `NativeOverlapped` is needed to mimic the structure the API expects, but this class encapsulates the overlapped structure into a .NET class. You can create `NativeOverlapped` structures by calling `Pack()`, and create `Overlapped` objects with the static `Unpack()` method. To avoid a memory leak, each `NativeOverlapped` that you create must also be freed by calling the static `Free()` method. `Unpack()` does *not* free the memory.

```
public class Overlapped {
// Public Constructors
    public Overlapped( );
    public Overlapped(int offsetLo, int offsetHi, int hEvent, IAsyncResult ar);
// Public Instance Properties
    public IAsyncResult AsyncResult {set; get; }
    public int EventHandle {set; get; }
    public int OffsetHigh {set; get; }
    public int OffsetLow {set; get; }
// Public Static Methods
    public static void Free(NativeOverlapped *nativeOverlappedPtr);
    public static Overlapped Unpack(NativeOverlapped *nativeOverlappedPtr);
// Public Instance Methods
    public NativeOverlapped* Pack(IOCompletionCallback iocb);
    public NativeOverlapped* UnsafePack(IOCompletionCallback iocb);
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

ReaderWriterLock

System.Threading (mscorlib.dll) *sealed class*

This class defines a lock that allows multiple readers, but only one writer. A thread can acquire a lock by calling `AcquireReaderLock()` or `AcquireWriterLock()`. `ReleaseReaderLock()` and `ReleaseWriterLock()` release the specific locks. Calling `ReleaseReaderLock()` on a writer lock releases both the writer lock and the reader lock. However, calling `ReleaseWriterLock()` on a reader lock throws a `System.ApplicationException`.

`ReleaseLock()` causes any lock to be released, but it returns a `LockCookie`, which represents the type of lock that `RestoreLock` can use to obtain the same lock. `UpgradeToWriterLock()` upgrades a reader lock to a writer lock, and returns a `LockCookie` representing the original reader lock. Pass that cookie to `DowngradeFromWriterLock()` to restore the original reader lock.

```
public sealed class ReaderWriterLock {
// Public Constructors
    public ReaderWriterLock( );
// Public Instance Properties
    public bool IsReaderLockHeld {get; }
    public bool IsWriterLockHeld {get; }
    public int WriterSeqNum {get; }
// Public Instance Methods
    public void AcquireReaderLock(int millisecondsTimeout);
    public void AcquireReaderLock(TimeSpan timeout);
    public void AcquireWriterLock(int millisecondsTimeout);
    public void AcquireWriterLock(TimeSpan timeout);
    public bool AnyWritersSince(int seqNum);
    public void DowngradeFromWriterLock(ref LockCookie lockCookie);
    public LockCookie ReleaseLock( );
    public void ReleaseReaderLock( );
    public void ReleaseWriterLock( );
    public void RestoreLock(ref LockCookie lockCookie);
    public LockCookie UpgradeToWriterLock(int millisecondsTimeout);
    public LockCookie UpgradeToWriterLock(TimeSpan timeout);
}
```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

RegisteredWaitHandle marshal by reference

System.Threading (mscorlib.dll) *sealed class*

`ThreadPool.RegisterWaitForSingleObject()` returns a `RegisteredWaitHandle`. To cancel a registered wait (either a new one or one that continuously executes), use `Unregister()`.

```
public sealed class RegisteredWaitHandle : MarshalByRefObject {  
    // Public Instance Methods  
    public bool Unregister(WaitHandle waitObject);  
    // Protected Instance Methods  
    protected override void Finalize( );  
    // overrides object  
}
```

Hierarchy

`System.Object` → `System.MarshalByRefObject` → `RegisteredWaitHandle`

Returned By

`ThreadPool.{RegisterWaitForSingleObject(), UnsafeRegisterWaitForSingleObject()}`

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

SynchronizationLockException


ECMA 1.0,
serializable

System.Threading (mscorlib.dll) *class*

This exception is thrown when `Monitor.Exit()`, `Monitor.Pulse()`, `Monitor.PulseAll()`, or `Monitor.Wait()` is called from unsynchronized code.

```
public class SynchronizationLockException : SystemException {  
    // Public Constructors  
    public SynchronizationLockException( );  
    public SynchronizationLockException(string message);  
    public SynchronizationLockException(string message, Exception innerException);  
    // Protected Constructors  
    protected SynchronizationLockException(System.Runtime.Serialization.SerializationInfo  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy



Thread

CF 1.0, ECMA 1.0

System.Threading (mscorlib.dll) *sealed class*

Most interaction with the `System.Threading` namespace occurs via the `Thread` type. This type encapsulates most of the logic needed to control the way threads behave.

The most commonly used static methods, usually referred to as *thread relative statics*, are methods and properties that refer to the currently executing thread. `Sleep()` causes the calling thread to sleep for a specified amount of time. If for some reason the thread gets woken up, a `ThreadInterruptedException` is thrown. Because this method can only be called by the current thread and not on a reference to a thread that may also be executing, the thread sleeps immediately and does not need to wait for a safe point for garbage collection as the `Suspend()` method does (see later in this entry).

`GetData()` retrieves data from a specified slot in *thread local storage*. To use this method, slots need to be initialized already (see later in this section). `SetData()` stores data in *thread local storage* to be retrieved using `GetData()`. `AllocateDataSlot()` and `AllocateNamedDataSlot()` allocate a data slot for use with the previous two methods.

The `Thread` class also provides the static property `CurrentThread`, which returns a reference to the `Thread` object for the currently running thread. The current thread can then access any of the following instance methods or properties on itself: `Abort()` causes a thread to abort, throwing a `ThreadAbortException` and executing any `finally` blocks. You may catch the `ThreadAbortException`, but it is automatically rethrown unless you invoke `ResetAbort()`, which countermands the `Abort()` and lets the thread continue to live. `Interrupt()` interrupts a thread that is in the `ThreadState.WaitSleepJoin` state. If a thread is not in the `ThreadState.WaitSleepJoin` state, it is interrupted when it next attempts to enter that state (`Join()` causes the calling thread to enter that state). The calling thread only starts again once the referenced thread finishes executing and enters the `ThreadState.Stopped` state. `Suspend()` suspends a thread. The thread is suspended once it has reached a safe point for garbage collection. The current thread can then access any of the following instance methods or properties on itself. `Resume()` resumes a thread that is in the suspended state. Threads in the suspended state are resumed regardless of how many times `Suspend()` was called. `Start()` tells a thread to start executing.

Starting with .NET 1.1, the `Thread` class provides three new methods (with appropriate overloads) that allow for direct access without respect to any per-processor or per-thread inherent caching mechanism; the `VolatileRead()` and `VolatileWrite()` methods will fetch and set "the value of a field... the latest written by any processor in a computer, regardless of the number of processors or the state of the processor cache" (from the MSDN documentation). This bears some explanation to make sense. Each CPU within the CLR, in the interests of efficiency, is allowed to cache values of objects and data within a thread-local cache, so that requests to access those fields doesn't require a full trip out to the garbage-collected heap. Unfortunately, doing so tends to lead to situations where multiple threads accessing the same fields on the same object (since these values are cached on a per-CPU basis) lead to different values across threads executing on those different CPUs, which is obviously a bad idea. Normally, by using the `lock` block within C#, a memory barrier is set up,

meaning the thread is now required to synchronize its processor cache with the global heap settings, thus forcing the processor-cached field values to match what's in the global heap. These methods (`VolatileRead()` and `VolatileWrite()`) force a trip out to the heap, rather than relying on processor cache, useful in situations where an explicit `lock` is not desired, yet accurate reflection of the object's state is necessary. In addition, the `MemoryBarrier()` method provides the same flushing of cache data to the central heap, but again, this same behavior is seen when using the `lock` syntax or the `Monitor` class, both of which provide the same semantics but are clearer and easier to use. For the most part, programmers are encouraged to use `lock` and/or `Monitor` where accessing shared data across threads.

```
public sealed class Thread {
    // Public Constructors
    public Thread(ThreadStart start);
    // Public Static Properties
    public static Context CurrentContext {get; }
    public static IPrincipal CurrentPrincipal {set; get; }
    public static Thread CurrentThread {get; }
    // Public Instance Properties
    public ApartmentState ApartmentState {set; get; }
    public CultureInfo CurrentCulture {set; get; }
    public CultureInfo CurrentUICulture {set; get; }
    public bool IsAlive {get; }
    public bool IsBackground {set; get; }
    public bool IsThreadPoolThread {get; }
    public string Name {set; get; }
    public ThreadPriority Priority {set; get; }
    public ThreadState ThreadState {get; }
    // Public Static Methods
    public static LocalDataStoreSlot AllocateDataSlot( );
    public static LocalDataStoreSlot AllocateNamedDataSlot(string name);
    public static void FreeNamedDataSlot(string name);
    public static object GetData(LocalDataStoreSlot slot);
    public static AppDomain GetDomain( );
    public static int GetDomainID( );
    public static LocalDataStoreSlot GetNamedDataSlot(string name);
    public static void MemoryBarrier( );
    public static void ResetAbort( );
    public static void SetData(LocalDataStoreSlot slot, object data);
    public static void Sleep(int millisecondsTimeout);
    public static void Sleep(TimeSpan timeout);
    public static void SpinWait(int iterations);
    public static byte VolatileRead(ref byte address);
    public static double VolatileRead(ref double address);
    public static short VolatileRead(ref short address);
    public static int VolatileRead(ref int address);
    public static long VolatileRead(ref long address);
    public static IntPtr VolatileRead(ref IntPtr address);
    public static object VolatileRead(ref object address);
    public static sbyte VolatileRead(ref sbyte address);
    public static float VolatileRead(ref float address);
    public static ushort VolatileRead(ref ushort address);
}
```



```

    public static uint VolatileRead(ref uint address);
    public static ulong VolatileRead(ref ulong address);
    public static UIntPtr VolatileRead(ref UIntPtr address);
    public static void VolatileWrite(ref byte address, byte value);
    public static void VolatileWrite(ref double address, double value);
    public static void VolatileWrite(ref short address, short value);
    public static void VolatileWrite(ref int address, int value);
    public static void VolatileWrite(ref long address, long value);
    public static void VolatileWrite(ref IntPtr address, IntPtr value);
    public static void VolatileWrite(ref object address, object value);
    public static void VolatileWrite(ref sbyte address, sbyte value);
    public static void VolatileWrite(ref float address, float value);
    public static void VolatileWrite(ref ushort address, ushort value);
    public static void VolatileWrite(ref uint address, uint value);
    public static void VolatileWrite(ref ulong address, ulong value);
    public static void VolatileWrite(ref UIntPtr address, UIntPtr value);
// Public Instance Methods
    public void Abort( );
    public void Abort(object stateInfo);
    public void Interrupt( );
    public bool Join(int millisecondsTimeout);
    public bool Join(TimeSpan timeout);
    public void Join( );
    public void Resume( );
    public void Start( );
    public void Suspend( );
// Protected Instance Methods
    protected override void Finalize( );
// overrides object
}

```

Returned By

System.Runtime.InteropServices.Marshal.GetThreadFromFiberCookie()

Passed To

System.Diagnostics.StackTrace.StackTrace()

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶


ThreadAbortException ECMA 1.0, serializable

System.Threading (mscorlib.dll) *sealed class*

This exception is thrown on a running thread when `Thread.Abort()` is called. This exception is catchable, but it is automatically rethrown (see `Thread` for more details).

```
public sealed class ThreadAbortException : SystemException {  
    // Public Instance Properties  
    public object ExceptionState {get; }  
}
```

Hierarchy



ThreadExceptionEventArgs

System.Threading (system.dll) *class*

This class represents the event arguments passed to a `ThreadExceptionHandler`. `Exception` contains the exception raised.

```
public class ThreadExceptionEventArgs : EventArgs {  
    // Public Constructors  
    public ThreadExceptionEventArgs(Exception t);  
    // Public Instance Properties  
    public Exception Exception {get; }  
}
```

Hierarchy

System.Object → System.EventArgs → ThreadExceptionEventArgs

Passed To

`ThreadExceptionHandler.BeginInvoke(), Invoke()`

[Team LiB]

◀ PREVIOUS

NEXT ▶

ThreadExceptionHandler serializable

System.Threading (system.dll) *delegate*

This event handler allows an event to be raised whenever a thread exception occurs. The `System.Windows.Forms.Application.ThreadException` property allows you to set one of these handlers which takes the sender and `ThreadExceptionEventArgs` as arguments. The `ThreadExceptionEventArgs` object contains the exception raised.

```
public delegate void ThreadExceptionHandler(object sender, ThreadExceptionEventArgs e);
```

[Team LiB]

◀ PREVIOUS

NEXT ▶


ThreadInterruptedException serializable

System.Threading (mscorlib.dll) *class*

This exception is thrown on a thread in the `ThreadState.WaitSleepJoin` state when `Thread.Interrupt` is called.

```
public class ThreadInterruptedException : SystemException {
// Public Constructors
    public ThreadInterruptedException( );
    public ThreadInterruptedException(string message);
    public ThreadInterruptedException(string message, Exception innerException);
// Protected Constructors
    protected ThreadInterruptedException(System.Runtime.Serialization.SerializationInfo
        System.Runtime.Serialization.StreamingContext context);
}
```

Hierarchy



ThreadPool

CF 1.0

System.Threading (mscorlib.dll) *sealed class*

Creating or destroying a thread takes a fair amount of work. Therefore, if you pool threads, your program efficiently since you get rid of the overhead associated with creating and destroying threads. There is one process. To queue work to execute by this pool of *worker threads*, call any of the `ThreadPool` static methods. `QueueUserWorkItem()` queues a delegate to execute when one of the pool's threads becomes free. `RegisterWaitForSingleObject()` takes a `WaitHandle` and executes the specified method either when signaled state or when a time-out occurs. `BindHandle()` and `UnsafeQueueUserWorkItem()` are provided for the Win32 API.

```
public sealed class ThreadPool {
// Public Static Methods
    public static bool BindHandle(IntPtr osHandle);
    public static void GetAvailableThreads(out int workerThreads, out int completionPort);
    public static void GetMaxThreads(out int workerThreads, out int completionPortThread);
    public static void GetMinThreads(out int workerThreads, out int completionPortThread);
    public static bool QueueUserWorkItem(WaitCallback callBack);
    public static bool QueueUserWorkItem(WaitCallback callBack, object state);
    public static RegisteredWaitHandle RegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, int millisecondsTimeoutInterval, bool executeOnlyOn);
    public static RegisteredWaitHandle RegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, long millisecondsTimeoutInterval, bool executeOnlyOn);
    public static RegisteredWaitHandle RegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, TimeSpan timeout, bool executeOnlyOn);
    public static RegisteredWaitHandle RegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, uint millisecondsTimeoutInterval, bool executeOnlyOn);
    public static bool SetMinThreads(int workerThreads, int completionPortThreads);
    public static bool UnsafeQueueUserWorkItem(WaitCallback callBack, object state);
    public static RegisteredWaitHandle UnsafeRegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, int millisecondsTimeoutInterval, bool executeOnlyOn);
    public static RegisteredWaitHandle UnsafeRegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, long millisecondsTimeoutInterval, bool executeOnlyOn);
    public static RegisteredWaitHandle UnsafeRegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, TimeSpan timeout, bool executeOnlyOn);
    public static RegisteredWaitHandle UnsafeRegisterWaitForSingleObject(WaitHandle waitObject,
        WaitOrTimerCallback callBack, object state, uint millisecondsTimeoutInterval, bool executeOnlyOn);
}
```

ThreadPriority CF 1.0, ECMA 1.0, serializable

System.Threading (mscorlib.dll) *enum*

This enumeration encapsulates the various thread priorities. Threads are scheduled to be executed based on their priority; they default to **Normal** priority. The runtime can also update thread priorities if a program window is moved between the foreground and background. This is done automatically when you create windowed applications.

```
public enum ThreadPriority {
    Lowest = 0,
    BelowNormal = 1,
    Normal = 2,
    AboveNormal = 3,
    Highest = 4
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → ThreadPriority

Returned By

Thread.Priority

Passed To

Thread.Priority

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ThreadStart CF 1.0, ECMA 1.0, serializable

System.Threading (mscorlib.dll) *delegate*

This delegate specifies a method for a thread to start executing.

```
public delegate void ThreadStart( );
```

Passed To

```
Thread.Thread( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ThreadState

ECMA 1.0, serializable, flag

System.Threading (mscorlib.dll)

enum

This enumeration encapsulates the various states a thread may be in. A thread starts in the `Unstarted` state. Once the `Thread.Start()` method is called, a thread enters the `Running` state. If another thread calls `Thread.Abort()` at any time, the thread shifts into the `AbortRequested` state, and then into `Aborted` once the thread reaches a safe point for garbage collection.

If the running thread calls either the static method `Thread.Sleep()`, any of the `Wait()` methods on a `WaitHandle`, or `Thread.Join()` on another thread, the executing thread enters the `WaitSleepJoin` state.

If another thread calls `Thread.Interrupt()` on a thread in the `WaitSleepJoin` state, the thread again enters the `Running` state. When another thread calls `Thread.Suspend()` on a thread, it enters the `SuspendRequested` state. Once a thread in the `SuspendRequested` state reaches a safe point for garbage collection, it enters the `Suspended` state. A thread then leaves the `Suspended` state and enters the running state when another thread calls `Thread.Resume()` on it. When a thread has finished running, it enters the `Stopped` state.

Once a thread has started, it cannot return to the `Unstarted` state. Similarly, once a thread has aborted or stopped, it cannot return to the `Running` state. This enumeration is marked with a `[Flags()]` attribute, which allows a thread to be in more than one state at a time. For example, if a thread is in the `WaitSleepJoin` and another thread calls `Thread.Abort()` on it, it will be in both the `WaitSleepJoin` and `AbortRequested` states at the same time.

```
public enum ThreadState {
    Running = 0x00000000 ,
    StopRequested = 0x00000001 ,
    SuspendRequested = 0x00000002 ,
    Background = 0x00000004 ,
    Unstarted = 0x00000008 ,
    Stopped = 0x00000010 ,
    WaitSleepJoin = 0x00000020 ,
    Suspended = 0x00000040 ,
    AbortRequested = 0x00000080 ,
    Aborted = 0x00000100
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ThreadState`

Returned By

Thread.ThreadState

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

ThreadStateException

CF 1.0, ECMA 1.0,
serializable

System.Threading (mscorlib.dll) *class*

This exception is thrown when an invalid method is called on a thread. For example, once a thread has started, it cannot reenter the `ThreadState.Unstarted` state. Therefore, an attempt to call `Thread.Start()` on that thread throws this exception.

```
public class ThreadStateException : SystemException {  
    // Public Constructors  
    public ThreadStateException( );  
    public ThreadStateException(string message);  
    public ThreadStateException(string message, Exception innerException);  
    // Protected Constructors  
    protected ThreadStateException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
}
```

Hierarchy

System.Object → System.Exception(System.Runtime.Serialization.ISerializable) →
System.SystemException → ThreadStateException

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Timeout

CF 1.0, ECMA 1.0

System.Threading (mscorlib.dll) *sealed class*

This class provides a static `Infinite` property, which is defined as -1 for use with methods that stop a thread's execution for a specific time period.

```
public sealed class Timeout {  
    // Public Static Fields  
    public const int Infinite;  
    // ==-1  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Timer

CF 1.0, ECMA 1.0, marshal by
reference, disposable

System.Threading (mscorlib.dll) *sealed class*

This class can execute actions on a periodic basis. Actions can be performed once or multiple times. The constructor takes a **TimerCallback** delegate, a state **object**, a due time, and a period. Both due time and period are measured in milliseconds. Use the state argument to hold state information between delegate calls, or pass in **null** if you don't have any state to maintain. After the timer is created, it begins counting down until due time has expired, and then it invokes the delegate. The period is the amount of time to wait between delegate invocations before resuming the countdown again.

If the period is zero, the timer executes only once. If either due time or period are negative (and not equal to **Timeout.Infinite**), the constructor fails, throwing an **System.ArgumentOutOfRangeException**. **Change()** changes the due time and period after the timer is created. Specify a due time of **Timeout.Infinite** to halt the timer. An **Infinite** period prevents the timer from being raised repeatedly.

```
public sealed class Timer : MarshalByRefObject, IDisposable {
// Public Constructors
    public Timer(TimerCallback callback, object state, int dueTime, int period);
    public Timer(TimerCallback callback, object state, long dueTime, long period);
    public Timer(TimerCallback callback, object state, TimeSpan dueTime, TimeSpan period);
    public Timer(TimerCallback callback, object state, uint dueTime, uint period);
// Public Instance Methods
    public bool Change(int dueTime, int period);
    public bool Change(long dueTime, long period);
    public bool Change(TimeSpan dueTime, TimeSpan period);
    public bool Change(uint dueTime, uint period);
    public bool Dispose(WaitHandle notifyObject);
    public void Dispose();
// implements IDisposable
// Protected Instance Methods
    protected override void Finalize();
// overrides object
}
```

Hierarchy

System.Object → System.MarshalByRefObject → Timer(System.IDisposable)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

TimerCallback CF 1.0, ECMA 1.0, serializable

System.Threading (mscorlib.dll) *delegate*

Use this delegate with `Timer`.

```
public delegate void TimerCallback(object state);
```

Passed To

```
Timer.Timer( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WaitCallback CF 1.0, serializable

System.Threading (mscorlib.dll) *delegate*

This delegate is for a `ThreadPool` work item.

```
public delegate void WaitCallback(object state);
```

Passed To

```
ThreadPool.{QueueUserWorkItem( ), UnsafeQueueUserWorkItem( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WaitHandle

CF 1.0, ECMA 1.0, marshal by reference, disposable

System.Threading
(mscorlib.dll)

abstract class

This class encapsulates much of the logic for dealing with synchronization handles, which allow much more synchronization control than simple thread locking. Once you have references to one or more **WaitHandle**, use the static **WaitOne()** or **WaitAny()** methods to obtain a lock on any single handle or all of the handles respectively. The **WaitOne()** instance method acquires the lock for a specific **WaitHandle**. If a thread cannot obtain the necessary locks, it enters the **ThreadState.WaitSleepJoin** state until the locks can be

```
public abstract class WaitHandle : MarshalByRefObject, IDisposable {
// Public Constructors
    public WaitHandle( );
// Public Static Fields
    public const int WaitTimeout;
// =258
// Protected Static Fields
    protected static readonly IntPtr InvalidHandle;
// =-1
// Public Instance Properties
    public virtual IntPtr Handle {set; get; }
// Public Static Methods
    public static bool WaitAll(WaitHandle[] waitHandles);
    public static bool WaitAll(WaitHandle[] waitHandles, int millisecondsTimeout, bool exitContext);
    public static bool WaitAll(WaitHandle[] waitHandles, TimeSpan timeout, bool exitContext);
    public static int WaitAny(WaitHandle[] waitHandles);
    public static int WaitAny(WaitHandle[] waitHandles, int millisecondsTimeout, bool exitContext);
    public static int WaitAny(WaitHandle[] waitHandles, TimeSpan timeout, bool exitContext);
// Public Instance Methods
    public virtual void Close( );
    public virtual bool WaitOne( );
    public virtual bool WaitOne(int millisecondsTimeout, bool exitContext);
    public virtual bool WaitOne(TimeSpan timeout, bool exitContext);
// Protected Instance Methods
    protected virtual void Dispose(bool explicitDisposing);
    protected override void Finalize( );
// overrides object
}
```

Hierarchy

System.Object → System.MarshalByRefObject → WaitHandle(System.IDisposable)

Subclasses

AutoResetEvent , ManualResetEvent , Mutex

Returned By

System.IAsyncResult.AsyncWaitHandle , System.IO.Stream.CreateWaitHandle()

Passed To

RegisteredWaitHandle.Unregister() , ThreadPool.{RegisterWaitForSingleObject() ,
UnsafeRegisterWaitForSingleObject()} , Timer.Dispose()

[Team LIB]

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

WaitOrTimerCallback

serializable

System.Threading (mscorlib.dll)

delegate

This delegate is passed to a `ThreadPool`. If the `wasSignaled` parameter is `true`, then the delegate is invoked in response to a signal; otherwise, it is invoked because the handle timed out.

```
public delegate void WaitOrTimerCallback(object state, bool timedOut);
```

Passed To

```
ThreadPool.RegisterWaitForSingleObject( ), UnsafeRegisterWaitForSingleObject( )}
```


[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 43. System.Timers

The `System.Timers` namespace provides the `Timer` class, which periodically raises an `Elapsed` event. It is a server-based component designed to be used in a multithreaded environment and is thus more accurate than many other Windows-based timers. Unlike `System.Windows.Forms.Timer`, a server-based timer is not dependent on a user interface message pump. [Figure 43-1](#) shows the class diagram for this namespace.

Figure 43-1. The System.Timers namespace



ElapsedEventArgs

System.Timers (system.dll) *class*

This class offers the arguments for an `ElapsedEventHandler`.

```
public class ElapsedEventArgs : EventArgs {  
    // Public Instance Properties  
    public DateTime SignalTime {get; }  
}
```

Hierarchy

`System.Object` → `System.EventArgs` → `ElapsedEventArgs`

Passed To

```
ElapsedEventHandler. {BeginInvoke( ), Invoke( )}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

ElapsedEventHandler

serializable

System.Timers (system.dll)

delegate

This delegate is used for the `Timer.Elapsed` event.

```
public delegate void ElapsedEventHandler(object sender, ElapsedEventArgs e);
```

Associated Events

`Timer.Elapsed()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)


Timer marshal by reference, disposable

System.Timers (system.dll) *class*

This class raises an event at regular intervals. It is a server-based timer, which provides much more accurate normal Windows timers and ensures that the event is raised at the proper time. To use a `Timer`, set the event, the `Interval` property, and `Enabled` to `true`. `Start()` and `Stop()` provide shortcuts, which reassign `true` and `false` to `Enabled`. `AutoReset` allows you to specify whether the event should be raised or periodically. The default is `true`, which makes the `Timer` periodic.

```
public class Timer : System.ComponentModel.Component, System.ComponentModel.ISupportIni
// Public Constructors
    public Timer( );
    public Timer(double interval);
// Public Instance Properties
    public bool AutoReset{set; get; }
    public bool Enabled{set; get; }
    public double Interval{set; get; }
    public override ISite Site{set; get; }
// overrides System.ComponentModel.Component
    public ISynchronizeInvoke SynchronizingObject{set; get; }
// Public Instance Methods
    public void BeginInit( );
// implements System.ComponentModel.ISupportInitialize
    public void Close( );
    public void EndInit( );
// implements System.ComponentModel.ISupportInitialize
    public void Start( );
    public void Stop( );
// Protected Instance Methods
    protected override void Dispose(bool disposing);
// overrides System.ComponentModel.Component
// Events
    public event ElapsedEventHandler Elapsed;
}
```

Hierarchy



TimersDescriptionAttribute

System.Timers (system.dll) *class*

This class provides a `System.ComponentModel.DescriptionAttribute` description for a given timer. It can be used by visual tools to display a helpful description of the component.

```
public class TimersDescriptionAttribute : System.ComponentModel.DescriptionAttribute {  
    // Public Constructors  
    public TimersDescriptionAttribute(string description);  
    // Public Instance Properties  
    public override string Description {get; }  
    // overrides System.ComponentModel.DescriptionAttribute  
}
```

Hierarchy

System.Object → System.Attribute → System.ComponentModel.DescriptionAttribute → TimersDescriptionAttribute

Valid On

All

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 44. System.Xml

The `System.Xml` namespace provides support for managing XML documents according to a set of standards defined by the World Wide Web Consortium (W3C). The classes implement objects that comply with the XML 1.0 specification and the Document Object Model (DOM) Core Level 1 and Core Level 2. Additional support is provided for XML Schemas (the `System.Xml.Schema` namespace), XSLT (`System.Xml.Xsl`), and XPath (`System.Xml.XPath`).

Figures [Figure 44-1](#) and [Figure 44-2](#) show the types in this namespace. For more information on these technologies and their use, please consult *XML in a Nutshell*, by Eliotte Rusty Harold and W. Scott Means (O'Reilly), or *Essential XML: Beyond Markup*, by Don Box (Addison Wesley).

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

EntityHandling

CF 1.0, serializable

System.Xml (system.xml.dll)

enum

This enumeration defines how entities are expanded. `ExpandCharEntities` expands only character entities, returning the entity text, while general entities are returned as nodes. `ExpandEntities` expands all entities; this is the default.

```
public enum EntityHandling {  
    ExpandEntities = 1,  
    ExpandCharEntities = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable,
System.IFormattable, System.IConvertible)` → `EntityHandling`


Returned By

`XmlValidatingReader.EntityHandling`

Passed To

`XmlValidatingReader.EntityHandling`

Figure 44-1. XmlNode and related types



Formatting CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll) *enum*

This enumeration specifies whether element content that is output from `XmlTextWriter` is indented. This is only of interest to human consumers of XML; if the destination of the XML document is another machine or software process, the additional whitespace adds only to the file size.

```
public enum Formatting {  
    None = 0,  
    Indented = 1  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `Formatting`


Returned By

`XmlTextWriter.Formatting`

Passed To

`XmlTextWriter.Formatting`

Figure 44-2. More types from System.Xml



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IHasXmlNode

System.Xml (system.xml.dll) *interface*

This interface is used to get the current or context node from an implementing class, such as `XmlDocument` or `System.Xml.XPath.XPathNavigator`. The `GetNode()` method returns the `XmlNode` that the navigator is currently positioned on.

```
public interface IHasXmlNode {  
    // Public Instance Methods  
    public XmlNode GetNode( );  
}
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

IXmlLineInfo

CF 1.0

System.Xml (system.xml.dll) *interface*

This interface allows XML reader classes ([XmlTextReader](#) and [XmlValidatingReader](#)) to return line and position information currently being read. If the class is reading data from a stream or other form of input, the [HasLineInfo\(\)](#) method returns a boolean indicating if line information is provided.

```
public interface IXmlLineInfo {  
    // Public Instance Properties  
    public int LineNumber{get; }  
    public int LinePosition{get; }  
    // Public Instance Methods  
    public bool HasLineInfo( );  
}
```

Implemented By

[XmlTextReader](#), [XmlValidatingReader](#)

NameTable

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *class*

This class is a concrete implementation of the `XmlNameTable` type (described later in this chapter). It is entirely an optimization within the .NET XML stack; it provides a table of string objects for element and attribute names used in an XML document. The XML parser uses these string objects for efficient manipulation of repeated element and attribute names. See `XmlNameTable` for more discussion of its behavior and usage.

Normally .NET applications have no need to use this class directly. At most, a new instance is passed in blindly when constructing various XML-related types, such as `XmlNamespaceManager`.

```
public class NameTable : XmlNameTable {
// Public Constructors
    public NameTable( );
// Public Instance Methods
    public override string Add(char[ ] key, int start, int len)
// overrides XmlNameTable
    public override string Add(string key);
// overrides XmlNameTable
    public override string Get(char[ ] key, int start, int len);
// overrides XmlNameTable
    public override string Get(string value);
// overrides XmlNameTable
}
```

Hierarchy

System.Object → XmlNameTable → NameTable

Passed To

System.Xml.Xsl.XsltContext.XsltContext()

ReadState CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll) *enum*

This enumeration identifies the current state of an `XmlReader` instance: closed (`Closed`); not yet started (`Initial`); an error is preventing further reading within the document (`Error`); the read is in process (`Interactive`); or the end of file (or stream, or wherever the XML is coming from) has been reached (`EndOfFile`).

```
public enum ReadState {  
    Initial = 0,  
    Interactive = 1,  
    Error = 2,  
    EndOfFile = 3,  
    Closed = 4  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ReadState`

Returned By

`XmlReader.ReadState`

ValidationType

serializable

System.Xml (system.xml.dll)

enum

This enumeration is used by `XmlValidatingReader` to determine the type of validation requested: DTD, schema, XDR, or no validation. If the type is set to `Auto`, the validation type is determined from the document; if there is a reference to a DTD, then DTD-style validation is performed. This is also true if the document contains references to XML Schema types, and so on. (See `XmlValidatingReader` for details.)

```
public enum ValidationType {  
    None = 0,  
    Auto = 1,  
    DTD = 2,  
    XDR = 3,  
    Schema = 4  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `ValidationType`

Returned By

`XmlValidatingReader.ValidationType`

Passed To

`XmlValidatingReader.ValidationType`

WhitespaceHandling

CF 1.0, ECMA 1.0,
serializable


System.Xml (system.xml.dll)

enum

This enumeration contains settings that determine if whitespace is preserved in text sections of XML documents. This is important if the XML document contains whitespace-sensitive text nodes; for example, HTML is a whitespace-insensitive language.

```
public enum WhitespaceHandling {  
    All = 0,  
    Significant = 1,  
    None = 2  
}
```

Hierarchy



Returned By

```
XmlTextReader.WhitespaceHandling
```

Passed To

```
XmlTextReader.WhitespaceHandling
```

WriteState CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll) *enum*

As its name implies, this enumeration specifies the state of an XmlWriter instance: closed (**Closed**), not yet started (**Start**), or in the process of writing some portion of the XML document (**Attribute**, **Content**, **Element**, or **Prolog**).

```
public enum WriteState {  
    Start = 0,  
    Prolog = 1,  
    Element = 2,  
    Attribute = 3,  
    Content = 4,  
    Closed = 5  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → WriteState

Returned By

XmlWriter.WriteState

XmlAttribute

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a single attribute of an element. The `OwnerElement` property returns the element node that contains this attribute. The `Specified` property indicates if the value was explicitly set or if a default value was used.

```
public class XmlAttribute : XmlNode {
// Protected Constructors
    protected internal XmlAttribute(string prefix, string localName, string namespaceURI,
        XmlDocument doc);
// Public Instance Properties
    public override string BaseURI {get; }
// overrides XmlNode
    public override string InnerText {set; get; }
// overrides XmlNode
    public override string InnerXml {set; get; }
// overrides XmlNode
    public override string LocalName {get; }
// overrides XmlNode
    public override string Name {get; }
// overrides XmlNode
    public override string NamespaceURI {get; }
// overrides XmlNode
    public override XmlNodeType NodeType {get; }
// overrides XmlNode
    public override XmlDocument OwnerDocument {get; }
// overrides XmlNode
    public virtual XmlElement OwnerElement {get; }
    public override XmlNode ParentNode {get; }
// overrides XmlNode
    public override string Prefix {set; get; }
// overrides XmlNode
    public virtual bool Specified {get; }
    public override string Value {set; get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable , System.Collections.IEnumerable , System.Xml.XPath.IXPathNavigable) → XmlAttribute

Returned By

XmlAttributeCollection.{Append() , InsertAfter() , InsertBefore() , Prepend() , Remove(RemoveAt() , this} , XmlDocument.CreateAttribute() , XmlElement.{GetAttributeNode() , RemoveAttributeNode() , SetAttributeNode() }

Passed To

XmlAttributeCollection.{Append() , CopyTo() , InsertAfter() , InsertBefore() , Prepend(Remove() } , XmlElement.{RemoveAttributeNode() , SetAttributeNode() }

[Team LiB]

◀ PREVIOUS

NEXT ▶

XmlAttributeCollection

CF 1.0


System.Xml (system.xml.dll)

class

This class defines a collection of attributes for an `XmlElement` node. An `XmlAttributeCollection` is returned by the `XmlElement.Attributes` property. The collection contains `XmlAttribute` objects that can be specified by either an object name or a zero-based index. Attribute nodes can be added and removed from the collection with methods, such as `InsertBefore()`, `InsertAfter()`, `Prepend()`, and `RemoveAt()`.

```
public class XmlAttributeCollection, XmlNamedNodeMap : ICollection {
// Public Instance Properties
    public virtual XmlAttribute this[string localName, string namespaceURI]{get; }
    public virtual XmlAttribute this[string name]{get; }
    public virtual XmlAttribute this[int i]{get; }
// Public Instance Methods
    public virtual XmlAttribute Append(XmlAttribute node);
    public void CopyTo(XmlAttribute[] array, int index);
    public virtual XmlAttribute InsertAfter(XmlAttribute newNode, XmlAttribute refNode);
    public virtual XmlAttribute InsertBefore(XmlAttribute newNode, XmlAttribute refNode);
    public virtual XmlAttribute Prepend(XmlAttribute node);
    public virtual XmlAttribute Remove(XmlAttribute node);
    public virtual void RemoveAll( );
    public virtual XmlAttribute RemoveAt(int i);
    public override XmlNode SetNamedItem(XmlNode node);
// overrides XmlNamedNodeMap
}
```

Hierarchy



Returned By

`XmlNode.Attributes`

XmlCDATASection

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a CDATA (character data) section node of a document. A CDATA section is element content that is unparsed, i.e., entities and markup are ignored.

```
public class XmlCDATASection : XmlCharacterData {
// Protected Constructors
    protected internal XmlCDATASection(string data, XmlDocument doc);
// Public Instance Properties
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData → XmlCDATASection

Returned By

XmlDocument.CreateCDATASection()

XmlCharacterData

CF 1.0

System.Xml (system.xml.dll) *abstract class*

This class is an abstract parent class for the character data node types: `XmlCDataSection`, `XmlComment`, `XmlSignificantWhitespace`, `XmlText`, and `XmlWhitespace`. It defines methods for manipulating the text-based data of these nodes.

```
public abstract class XmlCharacterData : XmlLinkedNode {  
    // Protected Constructors  
    protected internal XmlCharacterData(string data, XmlDocument doc);  
    // Public Instance Properties  
    public virtual string Data{set; get; }  
    public override string InnerText{set; get; }  
    // overrides XmlNode  
    public virtual int Length{get; }  
    public override string Value{set; get; }  
    // overrides XmlNode  
    // Public Instance Methods  
    public virtual void AppendData(string strData);  
    public virtual void DeleteData(int offset, int count);  
    public virtual void InsertData(int offset, string strData);  
    public virtual void ReplaceData(int offset, int count, string strData);  
    public virtual string Substring(int offset, int count);  
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData

Subclasses

XmlCDataSection, XmlComment, XmlSignificantWhitespace, XmlText, XmlWhitespace

XmlComment

CF 1.0

System.Xml (system.xml.dll)

class

This class represents an `XmlComment` node. An XML comment is contained within `<!--` and `-->` markup symbols and is not represented in the resulting XML Infoset tree.

```
public class XmlComment : XmlCharacterData {
// Protected Constructors
    protected internal XmlComment(string comment, XmlDocument doc);
// Public Instance Properties
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData → XmlComment

Returned By

XmlDocument.CreateComment()

XmlConvert

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll)

class

This type is used to convert XML elements into other, non-XML types, such as CLR objects. In particular, it is used to convert XSD types into CLR types, for easy transformation of schema-valid XML documents into .NET objects and back again. It is also used within a variety of other areas, including ADO.NET (for automatic conversion of XML documents into relational tables and rows).

For the most part, .NET programmers use this type indirectly as part of the .NET Web Services stack or else directly in order to convert between XML documents and CLR objects (as part of a home-grown XML-to-RDBMS system, for example).

Note that although a constructor is provided, all methods of any interest are declared static and therefore require no instance to use. In essence, this type is a collection of C-style functions.

```
public class XmlConvert {
// Public Constructors
    public XmlConvert( );
// Public Static Methods
    public static string DecodeName(string name);
    public static string EncodeLocalName(string name);
    public static string EncodeName(string name);
    public static string EncodeNmToken(string name);
    public static bool ToBoolean(string s);
    public static byte ToByte(string s);
    public static char ToChar(string s);
    public static DateTime ToDateTime(string s);
    public static DateTime ToDateTime(string s, string format);
    public static DateTime ToDateTime(string s, string[] formats);
    public static decimal ToDecimal(string s);
    public static double ToDouble(string s);
    public static Guid ToGuid(string s);
    public static short.ToInt16(string s);
    public static int.ToInt32(string s);
    public static long.ToInt64(string s);
    public static sbyte ToSByte(string s);
    public static float ToSingle(string s);
    public static string ToString(bool value);
    public static string ToString(byte value);
    public static string ToString(char value);
    public static string ToString(DateTime value);
    public static string ToString(DateTime value, string format);
    public static string ToString(decimal value);
    public static string ToString(double value);
```

```
public static string ToString(Guid value);
public static string ToString(short value);
public static string ToString(int value);
public static string ToString(long value);
public static string ToString(sbyte value);
public static string ToString(float value);
public static string ToString(TimeSpan value);
public static string ToString(ushort value);
public static string ToString(uint value);
public static string ToString(ulong value);
public static TimeSpan ToTimeSpan(string s);
public static ushort ToUInt16(string s);
public static uint ToUInt32(string s);
public static ulong ToUInt64(string s);
public static string VerifyName(string name);
public static string VerifyNCName(string name);
}
```

[\[Team LIB \]](#)

◀ PREVIOUS

NEXT ▶

XmlDataDocument

System.Xml (system.data.dll) *class*

The `XmlDataDocument` is a marriage of XML and RDBMS technology; it is an `XmlDocument` -inheriting class that particularly understands ADO.NET `DataSet` objects. This offers a variety of opportunities to the .NET programmer—for example, a `DataSet` can be loaded into the `XmlDataDocument`, and then navigated using traditional DOM-style navigation using the `XmlNode` API. In fact, because `XmlDataDocument` also inherits the `System.Xml.XPath.IXPathNavigable` interface, XPath queries can be issued against the `DataSet` data, just as if it were an XML document.

In order to build this relationship, construct the `XmlDataDocument` with the `DataSet` holding the data as its constructor parameter. Alternatively, use the `Load()` method to read in the data via an `XmlReader`. The XML can also then be written out to another medium with the `WriteTo()` method.

```
public class XmlDataDocument : XmlDocument {
// Public Constructors
    public XmlDataDocument();
    public XmlDataDocument(System.Data.DataSet dataset);
// Public Instance Properties
    public DataSet DataSet {get; }
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlDocument
    public override XmlElement CreateElement(string prefix, string localName, string namespaceUri);
// overrides XmlDocument
    public override XmlEntityReference CreateEntityReference(string name);
// overrides XmlDocument
    public override XmlElement GetElementById(string elemId);
// overrides XmlDocument
    public XmlElement GetElementFromRow(System.Data.DataRow r);
    public DataRow GetRowFromElement(XmlElement e);
    public override void Load(System.IO.Stream inStream);
// overrides XmlDocument
    public override void Load(string filename);
// overrides XmlDocument
    public override void Load(System.IO.TextReader txtReader);
// overrides XmlDocument
    public override void Load(XmlReader reader);
// overrides XmlDocument
// Protected Instance Methods
    protected override XPathNavigator CreateNavigator(XmlNode node);
// overrides XmlDocument
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable , System.Collections.IEnumerable ,
System.Xml.XPath.IXPathNavigable) → XmlDocument → XmlDataDocument

[Team LiB]

◀ PREVIOUS

NEXT ▶

XmlDeclaration

CF 1.0

System.Xml (system.xml.dll) *class*

This class contains the XML declaration of a document, which is the first element of an XML document containing version number, encoding, and other optional information about the file.

```
public class XmlDeclaration : XmlNode {  
    // Protected Constructors  
    protected internal XmlDeclaration(string version, string encoding, string standalone)  
    // Public Instance Properties  
    public string Encoding{set; get; }  
    public override string InnerText{set; get; }  
    // overrides XmlNode  
    public override string LocalName{get; }  
    // overrides XmlNode  
    public override string Name{get; }  
    // overrides XmlNode  
    public override XmlNodeType NodeType{get; }  
    // overrides XmlNode  
    public string Standalone{set; get; }  
    public override string Value{set; get; }  
    // overrides XmlNode  
    public string Version{get; }  
    // Public Instance Methods  
    public override XmlNode CloneNode(bool deep);  
    // overrides XmlNode  
    public override void WriteContentTo(XmlWriter w);  
    // overrides XmlNode  
    public override void WriteTo(XmlWriter w);  
    // overrides XmlNode  
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable , System.Collections.IEnumerable , System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlDeclaration

Returned By

XmlDocument.CreateXmlDeclaration()

XmlDocument

CF 1.0

System.Xml (system.xml.dll)

class

This class represents an XML document according to the W3C DOM (Document Object Model) specification. A document is represented as a node tree, in which elements and attributes (and their values) are stored and contain relational information (e.g., parent, child, siblings). **XmlDocument** derives from the generic **XmlNode** and therefore has a node-type of Document.

The set of **Create*** methods create new objects of any type of node. These objects are created within the **XmlDocument**; they share the document properties and name table of the parent document. However, they are inserted into the document. To do this, you need to use the methods for node insertion from **XmlNode**. A **XmlNode** is created from the root node of the **XmlDocument**; then methods for walking the node tree and appending nodes can be used to alter the source document.

Events are noted when any nodes (even created node objects that have not been inserted into the document) change. Register an instance of the **XmlNodeChangedEventHandler** delegate with any of the following types on **XmlDocument** to receive the corresponding notification: **NodeChanged** or **NodeChanging** for notification when a node has or is in the middle of changing (the element name is being modified, an attribute is being modified or removed, and so on); **NodeInserted** or **NodeInserting** for notifications of new nodes having been or in the process of being added to the document; and **NodeRemoved** or **NodeRemoving** for nodes removed or in the process of being removed. The **XmlNodeChangedEventHandler** takes two arguments: the object sending the notification (the **XmlDocument**) and an **XmlNodeChangedEventArgs** instance containing information about the change.

```
public class XmlDocument : XmlNode {
// Public Constructors
    public XmlDocument( );
    public XmlDocument(XmlNameTable nt);
// Protected Constructors
    protected internal XmlDocument(XmlImplementation imp);
// Public Instance Properties
    public override string BaseURI {get; }
// overrides XmlNode
    public XmlElement DocumentElement {get; }
    public virtual XmlDocumentType DocumentType {get; }
    public XmlImplementation Implementation {get; }
    public override string InnerXml {set; get; }
// overrides XmlNode
    public override bool IsReadOnly {get; }
// overrides XmlNode
    public override string LocalName {get; }
// overrides XmlNode
    public override string Name {get; }
// overrides XmlNode
    public XmlNameTable NameTable {get; }
    public override XmlNodeType NodeType {get; }
```

```

// overrides XmlNode
public override XmlDocument OwnerDocument{get; }
// overrides XmlNode
public bool PreserveWhitespace{set; get; }
public virtual XmlResolver XmlResolver{set; }
// Public Instance Methods
public override XmlNode CloneNode(bool deep);
// overrides XmlNode
public XmlAttribute CreateAttribute(string name);
public XmlAttribute CreateAttribute(string qualifiedName, string namespaceURI);
public virtual XmlAttribute CreateAttribute(string prefix, string localName,
    string namespaceURI);
public virtual XmlCDataSection CreateCDataSection(string data);
public virtual XmlComment CreateComment(string data);
public virtual XmlDocumentFragment CreateDocumentFragment( ); internalSubset);
public virtual XmlDocumentType CreateDocumentType(string name, string publicId,
    string systemId, string
public XmlElement CreateElement(string name);
public XmlElement CreateElement(string qualifiedName, string namespaceURI);
public virtual XmlElement CreateElement(string prefix, string localName, string name
public virtual XmlEntityReference CreateEntityReference(string name);
public virtual XmlNode CreateNode(string nodeTypeString, string name, string namespa
public virtual XmlNode CreateNode(XmlNodeType type, string name, string namespaceURI
public virtual XmlNode CreateNode(XmlNodeType type, string prefix, string name,
    string namespaceURI);
public virtual XmlProcessingInstruction CreateProcessingInstruction(string target, s
public virtual XmlSignificantWhitespace CreateSignificantWhitespace(string text);
public virtual XmlText CreateTextNode(string text);
public virtual XmlWhitespace CreateWhitespace(string text);
public virtual XmlDeclaration CreateXmlDeclaration(string version, string encoding,
    string standalone);
public virtual XmlElement GetElementById(string elementId);
public virtual XmlNodeList GetElementsByTagName(string name);
public virtual XmlNodeList GetElementsByTagName(string localName, string namespaceUR
public virtual XmlNode ImportNode(XmlNode node, bool deep);
public virtual void Load(System.IO.Stream inStream);
public virtual void Load(string filename);
public virtual void Load(System.IO.TextReader txtReader);
public virtual void Load(XmlReader reader);
public virtual void LoadXml(string xml);
public virtual XmlNode ReadNode(XmlReader reader);
public virtual void Save(System.IO.Stream outStream);
public virtual void Save(string filename);
public virtual void Save(System.IO.TextWriter writer);
public virtual void Save(XmlWriter w);
public override void WriteContentTo(XmlWriter xw);
// overrides XmlNode
public override void WriteTo(XmlWriter w);
// overrides XmlNode

```



```
// Protected Instance Methods
protected internal virtual XmlAttribute CreateDefaultAttribute(string prefix, string
    string namespaceURI);
protected internal virtual XPathNavigator CreateNavigator(XmlNode node);
// Events
public event XmlNodeChangedEventHandler NodeChanged;
public event XmlNodeChangedEventHandler NodeChanging;
public event XmlNodeChangedEventHandler NodeInserted;
public event XmlNodeChangedEventHandler NodeInserting;
public event XmlNodeChangedEventHandler NodeRemoved;
public event XmlNodeChangedEventHandler NodeRemoving;
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable , System.Collections.IEnumerable ,
System.Xml.XPath.IXPathNavigable)  XmlDocument

Subclasses

XmlDataDocument

Returned By

XmlImplementation.CreateDocument() , XmlNode.OwnerDocument

XmlDocumentFragment

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a lightweight piece or tree section of an XML document. A document fragment has a null parent node. This object is useful for tree insert operations that use the `ImportNode()` method of the `XmlDocument` class. To create an `XmlDocumentFragment`, use the `XmlDocument.CreateDocumentFragment()` method of an `XmlDocument` instance.

```
public class XmlDocumentFragment : XmlNode {
// Protected Constructors
    protected internal XmlDocumentFragment(XmlDocument ownerDocument);
// Public Instance Properties
    public override string InnerXml {set; get; }
// overrides XmlNode
    public override string LocalName {get; }
// overrides XmlNode
    public override string Name {get; }
// overrides XmlNode
    public override XmlNodeType NodeType {get; }
// overrides XmlNode
    public override XmlDocument OwnerDocument {get; }
// overrides XmlNode
    public override XmlNode ParentNode {get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlDocumentFragment

Returned By

`XmlDocument.CreateDocumentFragment()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlDocumentType

System.Xml (system.xml.dll) *class*

This class represents the **DOCTYPE** element of an XML document and its contents.

```

public class XmlDocumentType : XmlLinkedNode {
    // Protected Constructors
    protected internal XmlDocumentType(string name, string publicId, string systemId,
        string internalSubset, XmlDocument doc);
    // Public Instance Properties
    public XmlNamedNodeMap Entities {get; }
    public string InternalSubset {get; }
    public override bool IsReadOnly {get; }
    // overrides XmlNode
    public override string LocalName {get; }
    // overrides XmlNode
    public override string Name {get; }
    // overrides XmlNode
    public override XmlNodeType NodeType {get; }
    // overrides XmlNode
    public XmlNamedNodeMap Notations {get; }
    public string PublicId {get; }
    public string SystemId {get; }
    // Public Instance Methods
    public override XmlNode CloneNode(bool deep);
    // overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
    // overrides XmlNode
    public override void WriteTo(XmlWriter w);
    // overrides XmlNode
}

```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlDocumentType

Returned By

XmlDocument.CreateDocumentType(), DocumentType

XmlElement

CF 1.0

System.Xml (system.xml.dll)

class

This class represents an element in an XML document.

```
public class XmlElement : XmlLinkedNode {
// Protected Constructors
    protected internal XmlElement(string prefix, string localName, string namespaceURI,
        XmlDocument doc);
// Public Instance Properties
    public override XmlAttributeCollection Attributes{get; }
// overrides XmlNode
    public virtual bool HasAttributes{get; }
    public override string InnerText{set; get; }
// overrides XmlNode
    public override string InnerXml{set; get; }
// overrides XmlNode
    public bool IsEmpty{set; get; }
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override string NamespaceURI{get; }
// overrides XmlNode
    public override XmlNode NextSibling{get; }
// overrides XmlLinkedNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public override XmlDocument OwnerDocument{get; }
// overrides XmlNode
    public override string Prefix{set; get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public virtual string GetAttribute(string name);
    public virtual string GetAttribute(string localName, string namespaceURI);
    public virtual XmlAttribute GetAttributeNode(string name);
    public virtual XmlAttribute GetAttributeNode(string localName, string namespaceURI);
    public virtual XmlNodeList GetElementsByTagName(string name);
    public virtual XmlNodeList GetElementsByTagName(string localName, string namespaceUR
    public virtual bool HasAttribute(string name);
    public virtual bool HasAttribute(string localName, string namespaceURI);
    public override void RemoveAll( );
```

```

// overrides XmlNode
public virtual void RemoveAllAttributes( );
public virtual void RemoveAttribute(string name);
public virtual void RemoveAttribute(string localName, string namespaceURI);
public virtual XmlNode RemoveAttributeAt(int i);
public virtual XmlAttribute RemoveAttributeNode(string localName, string namespaceUR
public virtual XmlAttribute RemoveAttributeNode(XmlAttribute oldAttr);
public virtual string SetAttribute(string localName, string namespaceURI, string val
public virtual void SetAttribute(string name, string value);
public virtual XmlAttribute SetAttributeNode(string localName, string namespaceURI);
public virtual XmlAttribute SetAttributeNode(XmlAttribute newAttr);
public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
public override void WriteTo(XmlWriter w);
// overrides XmlNode
}

```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlElement

Returned By

XmlAttribute.OwnerElement, XmlDataDocument.GetElementFromRow(), XmlDocument.{CreateElement, DocumentElement, GetElementById()}, XmlNode.this

Passed To

XmlDataDocument.GetRowFromElement()

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

XmlEntity

System.Xml (system.xml.dll)

class

This class represents an entity in an XML document.

```

public class XmlEntity : XmlNode {
// Public Instance Properties
    public override string BaseURI{get; }
// overrides XmlNode
    public override string InnerText{set; get; }
// overrides XmlNode
    public override string InnerXml{set; get; }
// overrides XmlNode
    public override bool IsReadOnly{get; }
// overrides XmlNode
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public string NotationName{get; }
    public override string OuterXml{get; }
// overrides XmlNode
    public string PublicId{get; }
    public string SystemId{get; }
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}

```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable,
System.Xml.XPath.IXPathNavigable) → XmlEntity

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

XmlEntityReference

CF 1.0

System.Xml (system.xml.dll)

class

This class represents an entity reference in an XML document.

```
public class XmlEntityReference : XmlNode {
// Protected Constructors
    protected internal XmlEntityReference(string name, XmlDocument doc);
// Public Instance Properties
    public override string BaseURI{get; }
// overrides XmlNode
    public override bool IsReadOnly{get; }
// overrides XmlNode
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public override string Value{set; get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlEntityReference

Returned By

XmlDocument.CreateEntityReference()


XmlException CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll) *class*

This class contains the error thrown by XML-parsing operations. The `LineNumber` and `LinePosition` properties indicate the location of the error in the source document, and `Message` describes the reason for the error.

```
public class XmlException : SystemException {
// Public Constructors
    public XmlException( );
    public XmlException(string message);
    public XmlException(string message, Exception innerException);
    public XmlException(string message, Exception innerException, int lineNumber, int linePosition);
// Protected Constructors
    protected XmlException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public int LineNumber{get; }
    public int LinePosition{get; }
    public override string Message{get; }
// overrides Exception
// Public Instance Methods
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context)
// overrides Exception
}
```

Hierarchy



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlImplementation

CF 1.0

System.Xml (system.xml.dll) *class*

This class instantiates a new `XmlDocument` object using the same `XmlNameTable` of an existing `XmlDocument`.

```
public class XmlImplementation {  
    // Public Constructors  
    public XmlImplementation( );  
    // Public Instance Methods  
    public virtual XmlDocument CreateDocument( );  
    public bool HasFeature(string strFeature, string strVersion);  
}
```

Returned By

`XmlDocument.Implementation`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlNode

CF 1.0

System.Xml (system.xml.dll) *abstract class*

This type of node class is the base class for node types that are not top-level (i.e., nodes that require a parent). For example, `XmlAttribute` and `XmlElement` are derived from `XmlNode`.

```
public abstract class XmlNode : XmlNode {  
    // Public Instance Properties  
    public override XmlNode NextSibling {get; }  
    // overrides XmlNode  
    public override XmlNode PreviousSibling {get; }  
    // overrides XmlNode  
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable,
System.Xml.XPath.IXPathNavigable) → XmlNode

Subclasses

XmlAttribute, XmlDeclaration, XmlDocumentType, XmlElement, XmlEntityReference,
XmlProcessingInstruction

XmlNamedNodeMap

CF 1.0

System.Xml (system.xml.dll) *class*

This class represents a collection of nodes accessed by index or name. This is the abstract parent class of `XmlAttributeCollection`.

```
public class XmlNamedNodeMap : IEnumerable {  
    // Public Instance Properties  
    public virtual int Count{get; }  
    // Public Instance Methods  
    public virtual IEnumerator GetEnumerator( );  
    // implements IEnumerable  
    public virtual XmlNode GetNamedItem(string name);  
    public virtual XmlNode GetNamedItem(string localName, string namespaceURI);  
    public virtual XmlNode Item(int index);  
    public virtual XmlNode RemoveNamedItem(string name);  
    public virtual XmlNode RemoveNamedItem(string localName, string namespaceURI);  
    public virtual XmlNode SetNamedItem(XmlNode node);  
}
```

Subclasses

`XmlAttributeCollection`

Returned By

`XmlDocumentType.Entities, Notations`

XmlNamespaceManager

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll)

class

This class represents a collection of namespace prefixes and namespace URIs that are used to manage and resolve namespace information. The namespace manager is constructed using an `XmlNameTable`. `XmlNamespaceManager` is used internally by `XmlReader` to resolve namespace prefixes and track the current scope. `XmlNamespaceManager` maintains scope in a stack, which can be manipulated with `PopScope()` and `PushScope()`. Namespaces must be added explicitly to the namespace manager with `AddNamespace()`, even if you use an existing `XmlNameTable`.

```
public class XmlNamespaceManager : IEnumerable {
// Public Constructors
    public XmlNamespaceManager(XmlNameTable nameTable);
// Public Instance Properties
    public virtual string DefaultNamespace{get; }
    public XmlNameTable NameTable{get; }
// Public Instance Methods
    public virtual void AddNamespace(string prefix, string uri);
    public virtual IEnumerator GetEnumerator( );
// implements IEnumerable
    public virtual bool HasNamespace(string prefix);
    public virtual string LookupNamespace(string prefix);
    public virtual string LookupPrefix(string uri);
    public virtual bool PopScope( );
    public virtual void PushScope( );
    public virtual void RemoveNamespace(string prefix, string uri);
}
```

Subclasses

`System.Xml.Xsl.XsltContext`

Returned By

`XmlParserContext.NamespaceManager`

Passed To

```
XmlNode.{SelectNodes( ), SelectSingleNode( )}, XmlParserContext.{NamespaceManager,
XmlParserContext( )}, System.Xml.XPath.XPathExpression.SetContext( )
```

XmlNameTable

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *abstract class*

This class presents a table of string objects (for element and attribute names) used in an XML document. The XML parser uses these string objects for efficient manipulation of repeated element and attribute names. An `XmlNameTable` exists for every `XmlDocument` you create. The `XmlImplementation` class instantiates a new `XmlDocument` with the `XmlNameTable` of another existing `XmlDocument`.

```
public abstract class XmlNameTable {
// Protected Constructors
    protected XmlNameTable( );
// Public Instance Methods
    public abstract string Add(char[ ] array, int offset, int length);
    public abstract string Add(string array);
    public abstract string Get(char[ ] array, int offset, int length);
    public abstract string Get(string array);
}
```

Subclasses

`NameTable`

Returned By

`XmlDocument.NameTable`, `XmlNamespaceManager.NameTable`, `XmlParserContext.NameTable`, `XmlReader.NameTable`, `System.Xml.XPath.XPathNavigator.NameTable`

Passed To

`XmlDocument.XmlDocument()`, `XmlNamespaceManager.XmlNamespaceManager()`, `XmlParserContext.{NameTable, XmlParserContext()}`, `XmlTextReader.XmlTextReader()`

XmlNode

CF 1.0

System.Xml (system.xml.dll) *abstract class*

This abstract class represents a node in a document. A node is the basic object described by the Document Object Model for XML. A node can be an element, an element's attributes, the **DOCTYPE** declaration, a comment, or the entire document itself. Nodes are ordered in a hierarchical tree in which child, parent, a sibling relationships are "known" by each node.

The **XmlNode** class is the parent object of the specific node type classes. The properties of this class expose the intrinsic values of the node: **NamespaceURI** , **NodeType** , parent, child, sibling nodes, etc. The methods allow a node to add to or removed from a node tree (in the context of an **XmlDocument** or **XmlDocumentFragment**), with respect to a reference node.

```
public abstract class XmlNode : ICloneable, IEnumerable, System.Xml.XPath.IXPathNavigable
// Public Instance Properties
    public virtual XmlAttributeCollection Attributes{get; }
    public virtual string BaseURI{get; }
    public virtual XmlNodeList ChildNodes{get; }
    public virtual XmlNode FirstChild{get; }
    public virtual bool HasChildNodes{get; }
    public virtual string InnerText{set; get; }
    public virtual string InnerXml{set; get; }
    public virtual bool IsReadOnly{get; }
    public virtual XmlNode LastChild{get; }
    public abstract string LocalName{get; }
    public abstract string Name{get; }
    public virtual string NamespaceURI{get; }
    public virtual XmlNode NextSibling{get; }
    public abstract XmlNodeType NodeType{get; }
    public virtual string OuterXml{get; }
    public virtual XmlDocument OwnerDocument{get; }
    public virtual XmlNode ParentNode{get; }
    public virtual string Prefix{set; get; }
    public virtual XmlNode PreviousSibling{get; }
    public virtual XmlElement this[string name]{get; }
    public virtual XmlElement this[string localname, string ns]{get; }
    public virtual string Value{set; get; }
// Public Instance Methods
    public virtual XmlNode AppendChild(XmlNode newChild);
    public virtual XmlNode Clone( );
    public abstract XmlNode CloneNode(bool deep);
    public XPathNavigator CreateNavigator( );
// implements System.Xml.XPath.IXPathNavigable
    public IEnumerator GetEnumerator( );
// implements IEnumerable
```

```

    public virtual string GetNamespaceOfPrefix(string prefix);
    public virtual string GetPrefixOfNamespace(string namespaceURI);
    public virtual XmlNode InsertAfter(XmlNode newChild, XmlNode refChild);
    public virtual XmlNode InsertBefore(XmlNode newChild, XmlNode refChild);
    public virtual void Normalize( );
    public virtual XmlNode PrependChild(XmlNode newChild);
    public virtual void RemoveAll( );
    public virtual XmlNode RemoveChild(XmlNode oldChild);
    public virtual XmlNode ReplaceChild(XmlNode newChild, XmlNode oldChild);
    public XmlNodeList SelectNodes(string xpath);
    public XmlNodeList SelectNodes(string xpath, XmlNamespaceManager nsmgr);
    public XmlNode SelectSingleNode(string xpath);
    public XmlNode SelectSingleNode(string xpath, XmlNamespaceManager nsmgr);
    public virtual bool Supports(string feature, string version);
    public abstract void WriteContentTo(XmlWriter w);
    public abstract void WriteTo(XmlWriter w);
}

```

Subclasses

XmlAttribute , XmlDocument , XmlDocumentFragment , XmlEntity , XmlLinkedNode , XmlNotation

Returned By

Multiple types

Passed To

XmlDataDocument.CreateNavigator(), XmlDocument.ImportNode(),
 XmlNamedNodeMap.SetNamedItem(), XmlNodeReader.XmlNodeReader()

[Team LiB]

◀ PREVIOUS NEXT ▶

XmlNodeChangedAction CF 1.0, serializable

System.Xml (system.xml.dll) *enum*

This simple enumeration that describes the change that has occurred within an `XmlDocument` instance can be one of the following: `Change`, which indicates that a node within the document has changed in some way; `Insert`, which indicates that a node has been inserted into the document; or `Remove`, which indicates that a node has been removed. This is one of the properties specified in the `XmlNodeChangedEventArgs` parameter to the `XmlNodeChangedEventHandler` delegate instance registered with the `XmlDocument`.

```
public enum XmlNodeChangedAction {  
    Insert = 0,  
    Remove = 1,  
    Change = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `XmlNodeChangedAction`

Returned By

`XmlNodeChangedEventArgs.Action`

XmlNodeChangedEventArgs

CF 1.0

System.Xml (system.xml.dll)

class

This type contains information about the changes to a node that are passed when an `XmlDocument` calls through an `XmlNodeChangedEventHandler` delegate instance. It contains the changed or changing node, the old and new parents to that node, and an enumeration describing the change (modification, insertion, or removal).

```
public class XmlNodeChangedEventArgs {  
    // Public Instance Properties  
    public XmlNodeChangedAction Action {get; }  
    public XmlNode NewParent {get; }  
    public XmlNode Node {get; }  
    public XmlNode OldParent {get; }  
}
```

Passed To

```
XmlNodeChangedEventHandler.BeginInvoke( ), Invoke( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

XmlNodeChangedEventHandler

CF 1.0,
serializable

System.Xml (system.xml.dll)

delegate

This declared delegate type must be used to receive event notifications from the `XmlDocument` instance if code wishes to be notified of changes to the document as they occur.

```
public delegate void XmlNodeChangedEventHandler(object sender, XmlNodeChangedEventArgs
```

Associated Events

```
XmlDataDocument.{NodeChanged( ), NodeChanging( ), NodeInserted( ), NodeInserting( ),  
NodeRemoved( ), NodeRemoving( )}, XmlDocument.{NodeChanged( ), NodeChanging( ),  
NodeInserted( ), NodeInserting( ), NodeRemoved( ), NodeRemoving( )}
```

[Team LiB]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

XmlNodeList

CF 1.0

System.Xml (system.xml.dll) *abstract class*

This class is an enumerated collection of nodes returned by `XmlDocument.GetElementsByTagName()`. Nodes contained in the list can be retrieved by index or iterated through via the `IEnumerator` returned by `GetEnumerator()`. Changes to the nodes in the list are immediately reflected in the `XmlNodeList`'s properties and methods. For example, if you add a sibling to a node in the list, it appears in the list.

```
public abstract class XmlNodeList : IEnumerable {  
    // Protected Constructors  
    protected XmlNodeList( );  
    // Public Instance Properties  
    public abstract int Count {get; }  
    public virtual XmlNode this[int i]{get; }  
    // Public Instance Methods  
    public abstract IEnumerator GetEnumerator( );  
    // implements IEnumerable  
    public abstract XmlNode Item(int index);  
}
```

Returned By

```
XmlDocument.GetElementsByTagName( ), XmlElement.GetElementsByTagName( ),  
XmlNode.{ChildNodes, SelectNodes( )}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlNodeOrder

serializable

System.Xml (system.xml.dll) *enum*

These values describe the position of one node relative to another, with respect to document order.

```
public enum XmlNodeOrder {  
    Before = 0,  
    After = 1,  
    Same = 2,  
    Unknown = 3  
}
```

Hierarchy

```
System.Object → System.ValueType → System.Enum(System.IComparable,  
System.IFormattable, System.IConvertible) → XmlNodeOrder
```

Returned By

```
System.Xml.XPath.XPathNavigator.ComparePosition( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlNodeReader

CF 1.0

System.Xml (system.xml.dll)

class

This class is a non-cached, forward-only reader that accesses the contents of an `XmlNode`. This class can read a DOM subtree, but doesn't provide full-document support such as validation.

```
public class XmlNodeReader : XmlReader {
// Public Constructors
    public XmlNodeReader(XmlNode node);
// Public Instance Properties
    public override int AttributeCount {get; }
// overrides XmlReader
    public override string BaseURI {get; }
// overrides XmlReader
    public override bool CanResolveEntity {get; }
// overrides XmlReader
    public override int Depth {get; }
// overrides XmlReader
    public override bool EOF {get; }
// overrides XmlReader
    public override bool HasAttributes {get; }
// overrides XmlReader
    public override bool HasValue {get; }
// overrides XmlReader
    public override bool IsDefault {get; }
// overrides XmlReader
    public override bool IsEmptyElement {get; }
// overrides XmlReader
    public override string LocalName {get; }
// overrides XmlReader
    public override string Name {get; }
// overrides XmlReader
    public override string NamespaceURI {get; }
// overrides XmlReader
    public override XmlNameTable NameTable {get; }
// overrides XmlReader
    public override XmlNodeType NodeType {get; }
// overrides XmlReader
    public override string Prefix {get; }
// overrides XmlReader
    public override char QuoteChar {get; }
// overrides XmlReader
    public override ReadState ReadState {get; }
// overrides XmlReader
```

```

    public override string this[string name, string namespaceURI]{get; }
// overrides XmlReader
    public override string this[int i]{get; }
// overrides XmlReader
    public override string this[string name]{get; }
// overrides XmlReader
    public override string Value{get; }
// overrides XmlReader
    public override string XmlLang{get; }
// overrides XmlReader
    public override XmlSpace XmlSpace{get; }
// overrides XmlReader
// Public Instance Methods
    public override void Close( );
// overrides XmlReader
    public override string GetAttribute(int attributeIndex);
// overrides XmlReader
    public override string GetAttribute(string name);
// overrides XmlReader
    public override string GetAttribute(string name, string namespaceURI)
// overrides XmlReader
    public override string LookupNamespace(string prefix);
// overrides XmlReader
    public override bool MoveToAttribute(string name);
// overrides XmlReader
    public override bool MoveToAttribute(string name, string namespaceURI)
// overrides XmlReader
    public override void MoveToAttribute(int attributeIndex);
// overrides XmlReader
    public override bool MoveToElement( );
// overrides XmlReader
    public override bool MoveToFirstAttribute( );
// overrides XmlReader
    public override bool MoveToNextAttribute( );
// overrides XmlReader
    public override bool Read( );
// overrides XmlReader
    public override bool ReadAttributeValue( );
// overrides XmlReader
    public override string ReadString( );
// overrides XmlReader
    public override void ResolveEntity( );
// overrides XmlReader
    public override void Skip( );
// overrides XmlReader
}

```

Hierarchy

System.Object → XmlReader → XmlNodeReader

[[Team LIB](#)]

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

XmlNodeType CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll)

enum

This enumeration contains identifiers for node types. All DOM Core Level 2 types are included.

```

public enum XmlNodeType {
    None = 0,
    Element = 1,
    Attribute = 2,
    Text = 3,
    CDATA = 4,
    EntityReference = 5,
    Entity = 6,
    ProcessingInstruction = 7,
    Comment = 8,
    Document = 9,
    DocumentType = 10,
    DocumentFragment = 11,
    Notation = 12,
    Whitespace = 13,
    SignificantWhitespace = 14,
    EndElement = 15,
    EndEntity = 16,
    XmlDeclaration = 17
}

```

Hierarchy

```

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → XmlNodeType

```

Returned By

```

XmlNode.NodeType, XmlReader.{MoveToContent( ), NodeType}

```

Passed To

```

XmlDocument.CreateNode( ), XmlTextReader.XmlTextReader( ),
XmlValidatingReader.XmlValidatingReader( )

```

[\[Team LiB \]](#)[◀ PREVIOUS](#)[NEXT ▶](#)

XmlNotation

System.Xml (system.xml.dll) *class*

This class represents a notation declaration (<!NOTATION ...>) in an XML document.

```

public class XmlNotation : XmlNode {
// Public Instance Properties
    public override string InnerXml{set; get; }
// overrides XmlNode
    public override bool IsReadOnly{get; }
// overrides XmlNode
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public override string OuterXml{get; }
// overrides XmlNode
    public string PublicId{get; }
    public string SystemId{get; }
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}

```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable,
System.Xml.XPath.IXPathNavigable) → XmlNotation

XmlParserContext

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll)

class

This class contains document context information normally provided by both the XML declaration and **DOC** elements for parsing XML fragments. **XmlTextReader** and **XmlValidatingReader** use the **XmlParserContext** to get the base URI, internal subset, public and system identifiers, etc.

```
public class XmlParserContext {
// Public Constructors
    public XmlParserContext(XmlNameTable
        nt, XmlNamespaceManager
        nsMgr, string
        docTypeName,
            string pubId, string sysId, string internalSubset,
            string baseURI, string xmlLang, XmlSpace xmlSpace);
    public XmlParserContext(XmlNameTable nt, XmlNamespaceManager nsMgr, string docTypeNa
        string pubId,
            string sysId, string internalSubset, string baseURI, string xmlLang, XmlSpace xm
            System.Text.Encoding enc);
    public XmlParserContext(XmlNameTable nt, XmlNamespaceManager nsMgr, string xmlLang,
        XmlSpace xmlSpace);
    public XmlParserContext(XmlNameTable nt, XmlNamespaceManager nsMgr, string xmlLang,
        XmlSpace xmlSpace, System.Text.Encoding enc);
// Public Instance Properties
    public string BaseURI{set; get; }
    public string DocTypeName{set; get; }
    public Encoding Encoding{set; get; }
    public string InternalSubset{set; get; }
    public XmlNamespaceManager NamespaceManager{set; get; }
    public XmlNameTable NameTable{set; get; }
    public string PublicId{set; get; }
    public string SystemId{set; get; }
    public string XmlLang{set; get; }
    public XmlSpace XmlSpace{set; get; }
}
```

Passed To

XmlTextReader.XmlTextReader(), **XmlValidatingReader.XmlValidatingReader()**

XmlProcessingInstruction

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a processing instruction in an XML document.

```
public class XmlProcessingInstruction : XmlNode {
// Protected Constructors
    protected internal XmlProcessingInstruction(string target, string data, XmlDocument d) { }
// Public Instance Properties
    public string Data{set; get; }
    public override string InnerText{set; get; }
// overrides XmlNode
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public string Target{get; }
    public override string Value{set; get; }
// overrides XmlNode
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable , System.Collections.IEnumerable , System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlProcessingInstruction

Returned By

XmlDocument.CreateProcessingInstruction()

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

XmlQualifiedName

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a namespace-qualified local name. This looks like `namespace:name` within a document. An `XmlQualifiedName` object is constructed with the element's name and its namespace as string arguments. The namespace field may be empty, in which case the default namespace of the document is assumed.

```
public class XmlQualifiedName {
// Public Constructors
    public XmlQualifiedName( );
    public XmlQualifiedName(string name);
    public XmlQualifiedName(string name, string ns);
// Public Static Fields
    public static readonly XmlQualifiedName Empty;
// Public Instance Properties
    public bool IsEmpty{get; }
    public string Name{get; }
    public string Namespace{get; }
// Public Static Methods
    public static string ToString(string name, string ns);
    public static bool operator !=(XmlQualifiedName a, XmlQualifiedName b);
    public static bool operator ==(XmlQualifiedName a, XmlQualifiedName b);
// Public Instance Methods
    public override bool Equals(object other);
// overrides object
    public override int GetHashCode( );
// overrides object
    public override string ToString( );
// overrides object
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

XmlReader

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *abstract class*

This class is a simple reader for XML documents. `XmlReader` provides a non-cached, forward-only navigation through an XML data stream. It does not provide validation, nor does it expand general entities. Two derived classes provide these features: `XmlTextReader` and `XmlValidatingReader`.

The `XmlReader` class parses XML in a streaming-based approach (exemplified by the SAX specification). This means the XML parser presents "interesting pieces" (elements, attributes, namespace declarations, and so forth) in a linear order. Within `XmlReader`, this ordering of nodes is done using successive calls to the `Read()` method. An `XmlReader` is not positioned on a node at first—an initial call to `Read()` is required to move to the root node of a document. Subsequent calls to `Read()` move the reader sequentially through the nodes. The `NodeType` property tells you which type of node the reader is currently positioned on, returning values from the `XmlNodeType` enumeration. A special node-type value for `XmlReader` is `EndElement`. As `Read()` moves through the stream, it can be positioned on an element's end tag after it has stepped through the element's children. This is not a real node, in the DOM sense, but is required for `XmlReader` to parse XML data properly. The `Skip()` method steps through data node by node. A call to `Skip()` moves the reader to the next real node, disregarding the current node's children.

XML documents can also be parsed in a tree-based approach, using the `XmlDocument` type.

```
public abstract class XmlReader {
// Protected Constructors
    protected XmlReader( );
// Public Instance Properties
    public abstract int AttributeCount {get; }
    public abstract string BaseURI {get; }
    public virtual bool CanResolveEntity {get; }
    public abstract int Depth {get; }
    public abstract bool EOF {get; }
    public virtual bool HasAttributes {get; }
    public abstract bool HasValue {get; }
    public abstract bool IsDefault {get; }
    public abstract bool IsEmptyElement {get; }
    public abstract string LocalName {get; }
    public abstract string Name {get; }
    public abstract string NamespaceURI {get; }
    public abstract XmlNameTable NameTable {get; }
    public abstract XmlNodeType NodeType {get; }
    public abstract string Prefix {get; }
    public abstract char QuoteChar {get; }
    public abstract ReadState ReadState {get; }
    public abstract string this[string name, string namespaceURI] {get; }
    public abstract string this[int i] {get; }
```

```

    public abstract string this[string name]{get; }
    public abstract string Value{get; }
    public abstract string XmlLang{get; }
    public abstract XmlSpace XmlSpace{get; }
// Public Static Methods
    public static bool IsName(string str);
    public static bool IsNameToken(string str);
// Public Instance Methods
    public abstract void Close( );
    public abstract string GetAttribute(int i);
    public abstract string GetAttribute(string name);
    public abstract string GetAttribute(string name, string namespaceURI);
    public virtual bool IsStartElement( );
    public virtual bool IsStartElement(string name);
    public virtual bool IsStartElement(string localname, string ns);
    public abstract string LookupNamespace(string prefix);
    public abstract bool MoveToAttribute(string name);
    public abstract bool MoveToAttribute(string name, string ns);
    public abstract void MoveToAttribute(int i);
    public virtual XmlNodeType MoveToContent( );
    public abstract bool MoveToElement( );
    public abstract bool MoveToFirstAttribute( );
    public abstract bool MoveToNextAttribute( );
    public abstract bool Read( );
    public abstract bool ReadAttributeValue( );
    public virtual string ReadElementString( );
    public virtual string ReadElementString(string name);
    public virtual string ReadElementString(string localname, string ns);
    public virtual void ReadEndElement( );
    public virtual string ReadInnerXml( );
    public virtual string ReadOuterXml( );
    public virtual void ReadStartElement( );
    public virtual void ReadStartElement(string name);
    public virtual void ReadStartElement(string localname, string ns);
    public virtual string ReadString( );
    public abstract void ResolveEntity( );
    public virtual void Skip( );
}

```

Subclasses

XmlNodeReader, XmlTextReader, XmlValidatingReader

Returned By

XmlValidatingReader.Reader, System.Xml.Xsl.XslTransform.Transform()

Passed To

```
XmlDocument.{Load( ), ReadNode( )}, XmlValidatingReader.XmlValidatingReader( ),  
XmlWriter.{WriteAttributes( ), WriteNode( )},  
System.Xml.XPath.XPathDocument.XPathDocument( ), System.Xml.Xsl.XslTransform.Load( )
```

[\[Team LiB \]](#)

XmlResolver

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *abstract class*

This class resolves external resources according to their URIs. This class is used to retrieve an external DTD or Schema in XML documents and also obtains resources from imported stylesheets (<xsl:import>) and included files (<xml:include>). This abstract class is implemented by [XmlUrlResolver](#).

```
public abstract class XmlResolver {  
    // Protected Constructors  
    protected XmlResolver( );  
    // Public Instance Properties  
    public abstract ICredentials Credentials{set; }  
    // Public Instance Methods  
    public abstract object GetEntity(Uri absoluteUri, string role, Type ofObjectToReturn  
    public virtual Uri ResolveUri(Uri baseUri, string relativeUri);  
}
```

Subclasses

[XmlSecureResolver](#) , [XmlUrlResolver](#)

Passed To

```
XmlDocument.XmlResolver , XmlSecureResolver.XmlSecureResolver( ) ,  
XmlTextReader.XmlResolver , XmlValidatingReader.XmlResolver ,  
System.Xml.Xsl.XslTransform.{Load(Transform( ) , XmlResolver}
```

XmlSecureResolver

.NET 1.1

System.Xml (system.xml.dll)

class

This class decorates an `XmlResolver` instance to provide security restrictions on the normal behavior of a `XmlResolver`. For example, it can prevent resolving URI references that reference other domains embedded within an XML document. See `XmlUrlResolver` for the concrete implementation this class will usually wrap around.

```
public class XmlSecureResolver : XmlResolver {
// Public Constructors
    public XmlSecureResolver(XmlResolver resolver, System.Security.Policy.Evidence evidence)
    public XmlSecureResolver(XmlResolver resolver, System.Security.PermissionSet permissions)
    public XmlSecureResolver(XmlResolver resolver, string securityUrl);
// Public Instance Properties
    public override ICredentials Credentials {set; }
// overrides XmlResolver
// Public Static Methods
    public static Evidence CreateEvidenceForUrl(string securityUrl);
// Public Instance Methods
    public override object GetEntity(Uri absoluteUri, string role, Type ofObjectToReturn)
// overrides XmlResolver
    public override Uri ResolveUri(Uri baseUri, string relativeUri)
// overrides XmlResolver
}
```

Hierarchy

System.Object → XmlResolver → XmlSecureResolver

XmlSignificantWhitespace

CF 1.0

System.Xml (system.xml.dll) *class*

This class represents a whitespace node in mixed content data, if whitespace is preserved in the XML document (`XmlDocument.PreserveWhitespace` is `True`).

```
public class XmlSignificantWhitespace : XmlCharacterData {  
    // Protected Constructors  
    protected internal XmlSignificantWhitespace(string strData, XmlDocument doc);  
    // Public Instance Properties  
    public override string LocalName{get; }  
    // overrides XmlNode  
    public override string Name{get; }  
    // overrides XmlNode  
    public override XmlNodeType NodeType{get; }  
    // overrides XmlNode  
    public override string Value{set; get; }  
    // overrides XmlCharacterData  
    // Public Instance Methods  
    public override XmlNode CloneNode(bool deep);  
    // overrides XmlNode  
    public override void WriteContentTo(XmlWriter w);  
    // overrides XmlNode  
    public override void WriteTo(XmlWriter w);  
    // overrides XmlNode  
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData → XmlSignificantWhitespace

Returned By

XmlDocument.CreateSignificantWhitespace()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlSpace CF 1.0, ECMA 1.0, serializable

System.Xml (system.xml.dll) *enum*

This enumeration provides values for the `xml:space` scope. Used by `XmlParserContext.XmlSpace`.

```
public enum XmlSpace {  
    None = 0,  
    Default = 1,  
    Preserve = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `XmlSpace`

Returned By

`XmlParserContext.XmlSpace`, `XmlReader.XmlSpace`, `XmlWriter.XmlSpace`

Passed To

`XmlParserContext.XmlParserContext(), XmlSpace`,
`System.Xml.XPath.XPathDocument.XPathDocument()`

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlText

CF 1.0

System.Xml (system.xml.dll)

class

This class represents a text node in an XML document. **XmlText** is derived from the **XmlCharacterData** class and contains the text content of an element.

```
public class XmlText : XmlCharacterData {
// Protected Constructors
    protected internal XmlText(string strData, XmlDocument doc);
// Public Instance Properties
    public override string LocalName{get; }
// overrides XmlNode
    public override string Name{get; }
// overrides XmlNode
    public override XmlNodeType NodeType{get; }
// overrides XmlNode
    public override string Value{set; get; }
// overrides XmlCharacterData
// Public Instance Methods
    public override XmlNode CloneNode(bool deep);
// overrides XmlNode
    public virtual XmlText SplitText(int offset);
    public override void WriteContentTo(XmlWriter w);
// overrides XmlNode
    public override void WriteTo(XmlWriter w);
// overrides XmlNode
}
```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData → XmlText

Returned By

XmlDocument.CreateTextNode()

XmlTextReader

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll)

class

This class is a text-based reader for XML documents derived from `XmlReader`. `XmlTextReader` checks for and expands entities, but does not validate data according to a DTD or schema.

```
public class XmlTextReader : XmlReader : IXmlLineInfo {
// Public Constructors
    public XmlTextReader(System.IO.Stream input);
    public XmlTextReader(System.IO.Stream input, XmlNameTable nt);
    public XmlTextReader(System.IO.Stream xmlFragment, XmlNodeType fragType, XmlParserCo
    public XmlTextReader(string url);
    public XmlTextReader(string url, System.IO.Stream input);
    public XmlTextReader(string url, System.IO.Stream input, XmlNameTable nt);
    public XmlTextReader(string url, System.IO.TextReader input);
    public XmlTextReader(string url, System.IO.TextReader input, XmlNameTable nt);
    public XmlTextReader(string url, XmlNameTable nt);
    public XmlTextReader(string xmlFragment, XmlNodeType fragType, XmlParserContext cont
    public XmlTextReader(System.IO.TextReader input);
    public XmlTextReader(System.IO.TextReader input, XmlNameTable nt);
// Protected Constructors
    protected XmlTextReader( );
    protected XmlTextReader(XmlNameTable nt);
// Public Instance Properties
    public override int AttributeCount{get; }
// overrides XmlReader
    public override string BaseURI{get; }
// overrides XmlReader
    public override int Depth{get; }
// overrides XmlReader
    public Encoding Encoding{get; }
    public override bool EOF{get; }
// overrides XmlReader
    public override bool HasValue{get; }
// overrides XmlReader
    public override bool IsDefault{get; }
// overrides XmlReader
    public override bool IsEmptyElement{get; }
// overrides XmlReader
    public int LineNumber{get; }
// implements IXmlLineInfo
    public int LinePosition{get; }
// implements IXmlLineInfo
    public override string LocalName{get; }
```

```

// overrides XmlReader
public override string Name{get; }
// overrides XmlReader
public bool Namespaces{set; get; }
public override string NamespaceURI{get; }
// overrides XmlReader
public override XmlNameTable NameTable{get; }
// overrides XmlReader
public override XmlNodeType NodeType{get; }
// overrides XmlReader
public bool Normalization{set; get; }
public override string Prefix{get; }
// overrides XmlReader
public override char QuoteChar{get; }
// overrides XmlReader
public override ReadState ReadState{get; }
// overrides XmlReader
public override string this[int i]{get; }
// overrides XmlReader
public override string this[string name]{get; }
// overrides XmlReader
public override string this[string name, string namespaceURI]{get; }
// overrides XmlReader
public override string Value{get; }
// overrides XmlReader
public WhitespaceHandling WhitespaceHandling{set; get; }
public override string XmlLang{get; }
// overrides XmlReader
public XmlResolver XmlResolver{set; }
public override XmlSpace XmlSpace{get; }
// overrides XmlReader
// Public Instance Methods
public override void Close( );
// overrides XmlReader
public override string GetAttribute(int i);
// overrides XmlReader
public override string GetAttribute(string name);
// overrides XmlReader
public override string GetAttribute(string localName, string namespaceURI)
// overrides XmlReader
public TextReader GetRemainder( );
public override string LookupNamespace(string prefix);
// overrides XmlReader
public override bool MoveToAttribute(string name);
// overrides XmlReader
public override bool MoveToAttribute(string localName, string namespaceURI)
// overrides XmlReader
public override void MoveToAttribute(int i);
// overrides XmlReader
public override bool MoveToElement( );

```

```
// overrides XmlReader
public override bool MoveToFirstAttribute( );
// overrides XmlReader
public override bool MoveToNextAttribute( );
// overrides XmlReader
public override bool Read( );
// overrides XmlReader
public override bool ReadAttributeValue( );
// overrides XmlReader
public int ReadBase64(byte[ ] array, int offset, int len);
public int ReadBinHex(byte[ ] array, int offset, int len);
public int ReadChars(char[ ] buffer, int index, int count);
public void ResetState( );
public override void ResolveEntity( );
// overrides XmlReader
}
```

Hierarchy

System.Object → XmlReader → XmlTextReader(IXmlLineInfo)

[Team LiB]

[< PREVIOUS](#)[NEXT >](#)

XmlTextWriter

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll)

class

This class adds basic formatting to the text output and is derived from `XmlWriter`. The `Formatting` property uses its values to indicate if the output is to be `Indented` (`None` is the default). If `Formatting` is set to `Formatting.Indented`, the value of the `Indentation` property is the number of characters to indent each successive level (or child element) in the output. `IndentChar` sets the character to use for indentation, which must be a valid whitespace character (the default is space). `QuoteChar` is the character to use to quote attributes and is either a single or double quote.

```
public class XmlTextWriter : XmlWriter {
    // Public Constructors
    public XmlTextWriter(System.IO.Stream w, System.Text.Encoding encoding);
    public XmlTextWriter(string filename, System.Text.Encoding encoding);
    public XmlTextWriter(System.IO.TextWriter w);
    // Public Instance Properties
    public Stream BaseStream {get; }
    public Formatting Formatting {set; get; }
    public int Indentation {set; get; }
    public char IndentChar {set; get; }
    public bool Namespaces {set; get; }
    public char QuoteChar {set; get; }
    public override WriteState WriteState {get; }
    // overrides XmlWriter
    public override string XmlLang {get; }
    // overrides XmlWriter
    public override XmlSpace XmlSpace {get; }
    // overrides XmlWriter
    // Public Instance Methods
    public override void Close();
    // overrides XmlWriter
    public override void Flush();
    // overrides XmlWriter
    public override string LookupPrefix(string ns);
    // overrides XmlWriter
    public override void WriteBase64(byte[] buffer, int index, int count)
    // overrides XmlWriter
    public override void WriteBinHex(byte[] buffer, int index, int count)
    // overrides XmlWriter
    public override void WriteCData(string text);
    // overrides XmlWriter
    public override void WriteCharEntity(char ch);
    // overrides XmlWriter
    public override void WriteChars(char[] buffer, int index, int count)
```

```

// overrides XmlWriter
    public override void WriteComment(string text);
// overrides XmlWriter
    public override void WriteDocType(string name, string pubid, string sysid, string su
// overrides XmlWriter
    public override void WriteEndAttribute( );
// overrides XmlWriter
    public override void WriteEndDocument( );
// overrides XmlWriter
    public override void WriteEndElement( );
// overrides XmlWriter
    public override void WriteEntityRef(string name);
// overrides XmlWriter
    public override void WriteFullEndElement( );
// overrides XmlWriter
    public override void WriteName(string name);
// overrides XmlWriter
    public override void WriteNmToken(string name);
// overrides XmlWriter
    public override void WriteProcessingInstruction(string name, string text)
// overrides XmlWriter
    public override void WriteQualifiedName(string localName, string ns)
// overrides XmlWriter
    public override void WriteRaw(char[ ] buffer, int index, int count)
// overrides XmlWriter
    public override void WriteRaw(string data);
// overrides XmlWriter
    public override void WriteStartAttribute(string prefix, string localName, string ns)
// overrides XmlWriter
    public override void WriteStartDocument( );
// overrides XmlWriter
    public override void WriteStartDocument(bool standalone);
// overrides XmlWriter
    public override void WriteStartElement(string prefix, string localName, string ns)
// overrides XmlWriter
    public override void WriteString(string text);
// overrides XmlWriter
    public override void WriteSurrogateCharEntity(char lowChar, char highChar)
// overrides XmlWriter
    public override void WriteWhitespace(string ws);
// overrides XmlWriter
}

```

Hierarchy

System.Object → XmlWriter → XmlTextWriter

[Team LiB]

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlTokenizedType

serializable

System.Xml (system.xml.dll) *enum*

This is an enumeration of XML string types based on the XML 1.0 specification.

```
public enum XmlTokenizedType {
    CDATA = 0 ,
    ID = 1 ,
    IDREF = 2 ,
    IDREFS = 3 ,
    ENTITY = 4 ,
    ENTITIES = 5 ,
    NMTOKEN = 6 ,
    NMTOKENS = 7 ,
    NOTATION = 8 ,
    ENUMERATION = 9 ,
    QName = 10 ,
    NCName = 11 ,
    None = 12
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → XmlTokenizedType

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlUriResolver

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *class*

This class resolves URLs of external resources and retrieves them for parsing. `XmlUriResolver` implements `XmlResolver` and provides methods for retrieving external DTDs, schemas, and imported stylesheets via a URL. To retrieve resources on a network, the `Credentials` property can be set to provide usernames and passwords, as well as define authentication schemes. You can set this property by supplying a `System.Net.ICredentials` object. By default, this property is set for anonymous access to a URI resource.

```
public class XmlUriResolver : XmlResolver {  
    // Public Constructors  
    public XmlUriResolver( );  
    // Public Instance Properties  
    public override ICredentials Credentials{set; }  
    // overrides XmlResolver  
    // Public Instance Methods  
    public override object GetEntity(Uri absoluteUri, string role, Type ofObjectToReturn  
    // overrides XmlResolver  
}
```

Hierarchy



XmlValidatingReader

System.Xml (system.xml.dll)

class

This class is an XML reader that supports DTD and schema validation. The type of validation to perform is `ValidationType` property, which can be `DTD` , `Schema` , `XDR` , or `Auto` . `Auto` is the default and determine validation is required, if any, based on the document. If the `DOCTYPE` element contains DTD information, attribute exists or there is an inline `<schema>` , that schema is used.

This class implements an event handler that you can set to warn of validation errors during `Read()` open delegate instance of type `System.Xml.Schema.ValidationEventHandler` can be set for the `Validation` this class. This delegate instance is invoked whenever the `XmlValidatingReader` finds an schema-invalid document it is reading, giving the delegate a chance to perform whatever error-handling is appropriate. If registered, an `XmlException` is thrown instead on the first error.

```
public class XmlValidatingReader: XmlReader, IXmlLineInfo {
// Public Constructors
    public XmlValidatingReader(System.IO.Stream xmlFragment, XmlNodeType fragType, XmlPa
    public XmlValidatingReader(string xmlFragment, XmlNodeType fragType, XmlParserContex
    public XmlValidatingReader(XmlReader reader);
// Public Instance Properties
    public override int AttributeCount {get; }
// overrides XmlReader
    public override string BaseURI {get; }
// overrides XmlReader
    public override bool CanResolveEntity {get; }
// overrides XmlReader
    public override int Depth {get; }
// overrides XmlReader
    public Encoding Encoding {get; }
    public EntityHandling EntityHandling {set; get; }
    public override bool EOF {get; }
// overrides XmlReader
    public override bool HasValue {get; }
// overrides XmlReader
    public override bool IsDefault {get; }
// overrides XmlReader
    public override bool IsEmptyElement {get; }
// overrides XmlReader
    public override string LocalName {get; }
// overrides XmlReader
    public override string Name {get; }
// overrides XmlReader
    public bool Namespaces {set; get; }
    public override string NamespaceURI {get; }
```

```

// overrides XmlReader
public override XmlNameTable NameTable{get; }
// overrides XmlReader
public override XmlNodeType NodeType{get; }
// overrides XmlReader
public override string Prefix{get; }
// overrides XmlReader
public override char QuoteChar{get; }
// overrides XmlReader
public XmlReader Reader{get; }
public override ReadState ReadState{get; }
// overrides XmlReader
public XmlSchemaCollection Schemas{get; }
public object SchemaType{get; }
public override string this[int i]{get; }
// overrides XmlReader
public override string this[string name]{get; }
// overrides XmlReader
public override string this[string name, string namespaceURI]{get; }
// overrides XmlReader
public ValidationType ValidationType{set; get; }
public override string Value{get; }
// overrides XmlReader
public override string XmlLang{get; }
// overrides XmlReader
public XmlResolver XmlResolver{set; }
public override XmlSpace XmlSpace{get; }
// overrides XmlReader
// Public Instance Methods
public override void Close( );
// overrides XmlReader
public override string GetAttribute(int i);
// overrides XmlReader
public override string GetAttribute(string name)
// overrides XmlReader
public override string GetAttribute(string localName, string namespaceURI)
// overrides XmlReader
public override string LookupNamespace(string prefix);
// overrides XmlReader
public override bool MoveToAttribute(string name);
// overrides XmlReader
public override bool MoveToAttribute(string localName, string namespaceURI)
// overrides XmlReader
public override void MoveToAttribute(int i);
// overrides XmlReader
public override bool MoveToElement( );
// overrides XmlReader
public override bool MoveToFirstAttribute( );
// overrides XmlReader
public override bool MoveToNextAttribute( );

```

```
// overrides XmlReader
public override bool Read( );
// overrides XmlReader
public override bool ReadAttributeValue( );
// overrides XmlReader
public override string ReadString( );
// overrides XmlReader
public object ReadTypedValue( );
public override void ResolveEntity( );
// overrides XmlReader
// Events
public event ValidationEventHandler ValidationEventHandler;
}
```

Hierarchy

System.Object → XmlReader → XmlValidatingReader(IXmlLineInfo)

[Team LiB]

XmlWhitespace

CF 1.0

System.Xml (system.xml.dll) *class*

This class represents whitespace in element content. Whitespace is ignored if `XmlDocument.PreserveWhitespace` is not set to `true`.

```

public class XmlWhitespace : XmlCharacterData {
    // Protected Constructors
    protected internal XmlWhitespace(string strData, XmlDocument doc);
    // Public Instance Properties
    public override string LocalName{get; }
    // overrides XmlNode
    public override string Name{get; }
    // overrides XmlNode
    public override XmlNodeType NodeType{get; }
    // overrides XmlNode
    public override string Value{set; get; }
    // overrides XmlCharacterData
    // Public Instance Methods
    public override XmlNode CloneNode(bool deep);
    // overrides XmlNode
    public override void WriteContentTo(XmlWriter w);
    // overrides XmlNode
    public override void WriteTo(XmlWriter w);
    // overrides XmlNode
}

```

Hierarchy

System.Object → XmlNode(System.ICloneable, System.Collections.IEnumerable, System.Xml.XPath.IXPathNavigable) → XmlLinkedNode → XmlCharacterData → XmlWhitespace

Returned By

`XmlDocument.CreateWhitespace()`

XmlWriter

CF 1.0, ECMA 1.0

System.Xml (system.xml.dll) *abstract class*

This class is a fast writer used to output XML data to a stream or file. Two methods work with input from `XmlReader` object to produce output from the currently positioned node. `WriteAttributes()` outputs all node's attributes. `WriteNode()` dumps the entire current node to the output stream and moves the `Xml` to the next node.

The remaining `Write*` methods of this class take string arguments that are output as properly formed XML markup. For example, `WriteComment()` takes a string and outputs it within `<!-- ... -->` markup. `WriteStartElement()` and `WriteStartAttribute()` provide some flexibility when writing elements and attributes. These two methods provide the opening contents of each type, given the name, prefix, and namespace. The next call can then provide the value of the element or attribute by other means. For example you can use `WriteString()` for a simple string value, or another `WriteStartElement()` to begin a child element. `WriteEndElement()` and `WriteEndAttribute()` close the writing.

The derived `XmlTextWriter` class provides formatting functionality to the output data.

```
public abstract class XmlWriter {
// Protected Constructors
    protected XmlWriter( );
// Public Instance Properties
    public abstract WriteState WriteState{get; }
    public abstract string XmlLang{get; }
    public abstract XmlSpace XmlSpace{get; }
// Public Instance Methods
    public abstract void Close( );
    public abstract void Flush( );
    public abstract string LookupPrefix(string ns);
    public virtual void WriteAttributes(XmlReader reader, bool defattr);
    public void WriteAttributeString(string localName, string value);
    public void WriteAttributeString(string localName, string ns, string value);
    public void WriteAttributeString(string prefix, string localName, string ns, string value);
    public abstract void WriteBase64(byte[] buffer, int index, int count);
    public abstract void WriteBinHex(byte[] buffer, int index, int count);
    public abstract void WriteCData(string text);
    public abstract void WriteCharEntity(char ch);
    public abstract void WriteChars(char[] buffer, int index, int count);
    public abstract void WriteComment(string text);
    public abstract void WriteDocType(string name, string pubid, string sysid, string subset);
    public void WriteElementString(string localName, string value);
    public void WriteElementString(string localName, string ns, string value);
    public abstract void WriteEndElement( );
    public abstract void WriteEndDocument( );
}
```

```

public abstract void WriteEndElement( );
public abstract void WriteEntityRef(string name);
public abstract void WriteFullEndElement( );
public abstract void WriteName(string name);
public abstract void WriteNmToken(string name);
public virtual void WriteNode(XmlReader reader, bool defattr);
public abstract void WriteProcessingInstruction(string name, string text);
public abstract void WriteQualifiedName(string localName, string ns);
public abstract void WriteRaw(char[ ] buffer, int index, int count);
public abstract void WriteRaw(string data);
public void WriteStartAttribute(string localName, string ns);
public abstract void WriteStartAttribute(string prefix, string localName, string ns)
public abstract void WriteStartDocument( );
public abstract void WriteStartDocument(bool standalone);
public void WriteStartElement(string localName);
public void WriteStartElement(string localName, string ns);
public abstract void WriteStartElement(string prefix, string localName, string ns);
public abstract void WriteString(string text);
public abstract void WriteSurrogateCharEntity(char lowChar, char highChar);
public abstract void WriteWhitespace(string ws);
}

```

Subclasses

XmlTextWriter

Passed To

```

XmlDocument.Save( ), XmlNode.{WriteContentTo( ), WriteTo( )},
System.Xml.Xsl.XslTransform.Transform( )

```

[Team LiB]

◀ PREVIOUS NEXT ▶

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

Chapter 45. System.Xml.XPath

XPath is a W3C specification for locating nodes in an XML document. It provides an expression syntax that can determine a node based on its type, location, and relation to other nodes in a document. XPath is generally not useful alone, but works in conjunction with other tools, especially XSLT. [Figure 45-1](#) shows the types in this namespace.

`System.Xml.XPath` provides types that evaluate expressions and match nodes in XML documents. `XPathDocument` is a document object designed to provide fast document navigation through XPath and is used by the `System.Xml.Xsl` classes for XSLT transformations. `XPathNavigator` is the core entry point for doing XPath expressions; it is abstract, allowing for more than just XML documents to be XPath-navigated. For example, an ADO.NET provider could, if it desired, implement the `IXPathNavigable` interface and return an `XPathNavigator` that translated XPath queries into a SQL SELECT statement. (See Aaron Skonnard's MSDN Magazine article "Writing XML Providers for Microsoft .NET" for more details about using XML-based technologies over data sources other than XML documents.)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

IXPathNavigable

System.Xml.XPath (system.xml.dll) *interface*

This is an interface to `XPathNavigator` implemented by `XPathDocument`, `System.Xml.XmlNode`, and derived classes. It implements one method, `CreateNavigator()`, which creates an `XPathNavigator` instance for the document object.

```
public interface IXPathNavigable {  
    // Public Instance Methods  
    public XPathNavigator CreateNavigator( );  
}
```


Implemented By

`XPathDocument`, `System.Xml.XmlNode`

Passed To

`System.Xml.Xsl.XslTransform.{Load(), Transform()}`

Figure 45-1. The System.Xml.XPath namespace



[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlCaseOrder

serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration specifies how nodes are sorted with respect to case. A value of **None** indicates that case is to be ignored when ordering nodes.

```
public enum XmlCaseOrder {  
    None = 0,  
    UpperFirst = 1,  
    LowerFirst = 2  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable,
System.IFormattable, System.IConvertible) → XmlCaseOrder

Passed To

XPathExpression.AddSort()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlDataType

serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration specifies whether to sort node values by type as numeric value (**Number**) or alphabetically (**Text**).

```
public enum XmlDataType {  
    Text = 1,  
    Number = 2  
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → XmlDataType

Passed To

```
XPathExpression.AddSort( )
```

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

XmlSortOrder

serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration specifies how nodes are sorted by numerical value, either ascending or descending.

```
public enum XmlSortOrder {  
    Ascending = 1,  
    Descending = 2  
}
```

Hierarchy

system.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → XmlSortOrder

Passed To

XPathExpression.AddSort()

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

XPathDocument

System.Xml.XPath (system.xml.dll) *class*

This class is a concrete implementation of `IXPathNavigable` for creating an `XPathNavigator` that knows how to scan through an XML document. There are overloaded forms of the constructor designed to pull an XML document from various sources—a `System.IO.Stream`, a string, a `System.IO.TextReader` (which presumably is pulling from some other valid data source), or a `System.Xml.XmlReader`. Note that if the `XmlReader` is currently positioned on top of a particular node within a document, the constructed `XPathDocument` instance is only valid for that element and its children. This allows partial XPath scans of a given document.

This class serves no other purpose than as a factory for producing `XPathNavigator` instances.

```
public class XPathDocument : IXPathNavigable {  
    // Public Constructors  
    public XPathDocument(System.IO.Stream stream);  
    public XPathDocument(string uri);  
    public XPathDocument(string uri, System.Xml.XmlSpace space);  
    public XPathDocument(System.IO.TextReader reader);  
    public XPathDocument(System.Xml.XmlReader reader);  
    public XPathDocument(System.Xml.XmlReader reader, System.Xml.XmlSpace space);  
    // Public Instance Methods  
    public XPathNavigator CreateNavigator( );  
    // implements IXPathNavigable  
}
```

[\[Team LiB \]](#)[◀ PREVIOUS](#) [NEXT ▶](#)

XPathException


serializable

System.Xml.XPath (system.xml.dll) *class*

This exception indicates a problem with an `XPathExpression` , such as an invalid prefix.

```
public class XPathException : SystemException {
// Public Constructors
    public XPathException(string message, Exception innerException);
// Protected Constructors
    protected XPathException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public override string Message{get; }
// overrides Exception
// Public Instance Methods
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in
        System.Runtime.Serialization.StreamingContext context)
// overrides Exception
}
```

Hierarchy



XPathExpression

System.Xml.XPath
(system.xml.dll)

*abstract
class*

This class represents a compiled XPath expression. An `XPathExpression` is returned by the `Compile()` method of `XPathNavigator` from an XPath expression string. The `AddSort()` method allows you to specify the order of returned nodes from the expression. `SetContext()` sets the namespace to use in the evaluation of the expression.

```
public abstract class XPathExpression {  
    // Public Instance Properties  
    public abstract string Expression {get; }  
    public abstract XPathResultType ReturnType {get; }  
    // Public Instance Methods  
    public abstract void AddSort(object expr, System.Collections.IComparer comparer);  
    public abstract void AddSort(object expr, XmlSortOrder order, XmlCaseOrder caseOrder,  
        string lang,  
        XmlDataType dataType);  
    public abstract XPathExpression Clone( );  
    public abstract void SetContext(System.Xml.XmlNamespaceManager nsManager);  
}
```

Returned By

```
XPathNavigator.Compile( )
```

Passed To

```
XPathNavigator.{Evaluate( ), Matches( ), Select( )}
```

XPathNamespaceScope serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration defines the namespace scope for certain `XPathNavigator` operations. `All` includes all namespaces within the scope of the current node (including the `xmlns:xml` namespace, whether defined explicitly or not). `ExcludeXml` includes all namespaces within the scope of the current node, *except* the `xmlns:xml` namespace. `Local` includes all locally defined namespaces within the scope of the current node.

```
public enum XPathNamespaceScope {  
    All = 0,  
    ExcludeXml = 1,  
    Local = 2  
}
```

Hierarchy

`System.Object` → `System.ValueType` → `System.Enum(System.IComparable, System.IFormattable, System.IConvertible)` → `XPathNamespaceScope`

Passed To

`XPathNavigator.MoveToFirstNamespace()`, `MoveToNextNamespace()`

XPathNavigator

System.Xml.XPath
(system.xml.dll)

*abstract
class*

This class is a read-only representation of an `XPathDocument` based on the `IXPathNavigable` interface. It provides an easy-to-use data object for quick XPath-based navigation, particularly for XSLT transformations.

An `XPathNavigator` instance maintains its state with the current node position to provide the proper context for any XPath expression evaluation. Initially, the current node is the root node. The current node is changed by using the `Select()` method or the various `MoveTo*` methods. If the XPath expression evaluates to a set of nodes, the first node of the set is the current node for the `XPathNavigator`. All the `Select*` methods return an `XPathNodeIterator` object containing the set of nodes returned by the function. Except for plain old `Select()`, the `Select*` functions do not change the current node of the `XPathNavigator` they are used on. Any actions on the `XPathNodeIterator` objects that they return also not affect the originating object.

The `Compile()` method takes an XPath expression string and encapsulates it into a compiled `XPathExpression` object. `XPathExpression` objects are used by `Select()`, `Evaluate()`, and `Match` as input to search a node list.

```
public abstract class XPathNavigator : ICloneable {
    // Protected Constructors
    protected XPathNavigator();

    // Public Instance Properties
    public abstract string BaseURI {get; }
    public abstract bool HasAttributes {get; }
    public abstract bool HasChildren {get; }
    public abstract bool IsEmptyElement {get; }
    public abstract string LocalName {get; }
    public abstract string Name {get; }
    public abstract string NamespaceURI {get; }
    public abstract XmlNameTable NameTable {get; }
    public abstract XPathNodeType NodeType {get; }
    public abstract string Prefix {get; }
    public abstract string Value {get; }
    public abstract string XmlLang {get; }

    // Public Instance Methods
    public abstract XPathNavigator Clone();
    public virtual XmlNodeOrder ComparePosition(XPathNavigator nav);
    public virtual XPathExpression Compile(string xpath);
    public virtual object Evaluate(string xpath);
    public virtual object Evaluate(XPathExpression expr);
    public virtual object Evaluate(XPathExpression expr, XPathNodeIterator context);
    public abstract string GetAttribute(string localName, string namespaceURI);
}
```

```

public abstract string GetNamespace(string name);
public virtual bool IsDescendant(XPathNavigator nav);
public abstract bool IsSamePosition(XPathNavigator other);
public virtual bool Matches(string xpath);
public virtual bool Matches(XPathExpression expr);
public abstract bool MoveTo(XPathNavigator other);
public abstract bool MoveToAttribute(string localName, string namespaceURI);
public abstract bool MoveToFirst( );
public abstract bool MoveToFirstAttribute( );
public abstract bool MoveToFirstChild( );
public bool MoveToFirstNamespace( );
public abstract bool MoveToFirstNamespace(XPathNamespaceScope namespaceScope);
public abstract bool MoveToId(string id);
public abstract bool MoveToNamespace(string name);
public abstract bool MoveToNext( );
public abstract bool MoveToNextAttribute( );
public bool MoveToNextNamespace( );
public abstract bool MoveToNextNamespace(XPathNamespaceScope namespaceScope);
public abstract bool MoveToParent( );
public abstract bool MoveToPrevious( );
public abstract void MoveToRoot( );
public virtual XPathNodeIterator Select(string xpath);
public virtual XPathNodeIterator Select(XPathExpression expr);
public virtual XPathNodeIterator SelectAncestors(string name, string namespaceURI,
    bool matchSelf);
public virtual XPathNodeIterator SelectAncestors(XPathNodeType type, bool matchSelf);
public virtual XPathNodeIterator SelectChildren(string name, string namespaceURI);
public virtual XPathNodeIterator SelectChildren(XPathNodeType type);
public virtual XPathNodeIterator SelectDescendants(string name, string namespaceURI,
    bool matchSelf);
public virtual XPathNodeIterator SelectDescendants(XPathNodeType type, bool matchSel
public override string ToString( );
// overrides object
}

```

Returned By

System.Xml.XmlDataDocument.CreateNavigator(), System.Xml.XmlNode.CreateNavigator(),
 XPathNavigator.CreateNavigator(), XPathDocument.CreateNavigator(),
 XPathNodeIterator.Current

Passed To

System.Xml.Xsl.IXsltContextFunction.Invoke(),
 System.Xml.Xsl.XsltContext.PreserveWhitespace(), System.Xml.Xsl.XslTransform.{Load(),
 Transform()}

[Team LiB]

◀ PREVIOUS NEXT ▶

XPathNodeIterator

System.Xml.XPath
(system.xml.dll)

*abstract
class*

This class is a node-set constructed from a compiled XPath expression. This type is returned by the `Select*` methods of `XPathNavigator`. The `MoveNext()` method moves to the next node of the node set in document order and does not affect the `XPathNavigator` on which the `Select()` was called.

```
public abstract class XPathNodeIterator : ICloneable {  
    // Protected Constructors  
    protected XPathNodeIterator( );  
    // Public Instance Properties  
    public virtual int Count {get; }  
    public abstract XPathNavigator Current {get; }  
    public abstract int CurrentPosition {get; }  
    // Public Instance Methods  
    public abstract XPathNodeIterator Clone( );  
    public abstract bool MoveNext( );  
}
```

Returned By

```
XPathNavigator.{Select( ), SelectAncestors( ), SelectChildren( ), SelectDescendants( )}
```

Passed To

```
XPathNavigator.Evaluate( )
```

XPathNodeType

serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration contains the types of nodes that can be listed with the `XPathNavigator.NodeType` property.

```
public enum XPathNodeType {
    Root = 0,
    Element = 1,
    Attribute = 2,
    Namespace = 3,
    Text = 4,
    SignificantWhitespace = 5,
    Whitespace = 6,
    ProcessingInstruction = 7,
    Comment = 8,
    All = 9
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → XPathNodeType

Returned By

`XPathNavigator.NodeType`

Passed To

`XPathNavigator.{SelectAncestors(), SelectChildren(), SelectDescendants()}`

XPathResultType

serializable

System.Xml.XPath (system.xml.dll) *enum*

This enumeration contains the result types used by the `XPathExpression.ReturnType` property.

```
public enum XPathResultType {
    Number = 0,
    String = 1,
    Navigator = 1,
    Boolean = 2,
    NodeSet = 3,
    Any = 5,
    Error = 6
}
```

Hierarchy

System.Object → System.ValueType → System.Enum(System.IComparable, System.IFormattable, System.IConvertible) → XPathResultType

Returned By

XPathExpression.ReturnType, System.Xml.Xsl.IXsltContextFunction.{ArgTypes, ReturnType}, System.Xml.Xsl.IXsltContextVariable.VariableType

Passed To


System.Xml.Xsl.XsltContext.ResolveFunction()

Chapter 46. System.Xml.Xsl

The `System.Xml.Xsl` namespace provides support to Extensible Stylesheet Language Transformations (XSLT). XSLT is a W3C specification that describes how to transform one XML document into another with the use of stylesheet templates. For example, a common use of XSLT is to transform an XML document into standard HTML by transforming the specific elements of the input XML document into comparable HTML elements. XSLT templates use XPath expression syntax to specify which nodes of the input XML are transformed.

The `XsltTransform` class constructs the transform object. It loads a stylesheet and applies its templates to an XML document to output the transformed data. The `XsltArgumentList` class creates objects for XSLT parameters that can be loaded into the stylesheet at runtime. `XsltContext` provides the XSLT processor with the current context node information used for XPath expression resolution. [Figure 46-1](#) shows the types in this namespace.

Figure 46-1. The System.Xml.Xsl namespace



I XsltContextFunction

System.Xml.Xsl (system.xml.dll) *interface*

The Microsoft .NET XSLT engine, like many other XSLT engines, allows custom functions inside of an XSLT providing an "extension object" to an `XsltArgumentList` instance, an XSLT stylesheet can "call out" to the `XsltArgumentList` description for an example.

```
public interface IXsltContextFunction {  
    // Public Instance Properties  
    public XPathResultType[] ArgTypes {get; }  
    public int Maxargs {get; }  
    public int Minargs {get; }  
    public XPathResultType ReturnType {get; }  
    // Public Instance Methods  
    public object Invoke(XsltContext xsltContext, object[] args, System.Xml.XPath.XPath)
```

Returned By

```
XsltContext.ResolveFunction( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

IXsltContextVariable

System.Xml.Xsl (system.xml.dll) *interface*

As with `IXsltContextFunction`, this interface is used to help the XSLT engine resolve data objects bound into the XSLT engine's executing context while processing an XML document. See the `XsltArgumentList` method description for an example of how context functions and variables are used with an XSLT instance.

```
public interface IXsltContextVariable {
    // Public Instance Properties
    public bool IsLocal {get; }
    public bool IsParam {get; }
    public XPathResultType VariableType {get; }
    // Public Instance Methods
    public object Evaluate(XsltContext xsltContext);
}
```

Returned By

```
XsltContext.ResolveVariable( )
```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

XsltArgumentList

System.Xml.Xsl (system.xml.dll) *sealed class*

The `XsltArgumentList` class constructs lists of parameters and node fragment objects that can be called from stylesheets. This type is called as the second argument to the `Transform()` method of `XslTransform`. Parameters are associated with namespace-qualified names, and objects are associated with their namespace URIs.

The `XsltArgumentList` can also be used to bind functions and variables into the XSLT engine's execution space—commonly called the XSLT context—for use by the XSLT stylesheet during processing. See this book's website, <http://www.oreilly.com/catalog/csharpnut2/> for an example program that demonstrates this.

```
public sealed class XsltArgumentList {
// Public Constructors
    public XsltArgumentList( );
// Public Instance Methods
    public void AddExtensionObject(string namespaceUri, object extension);
    public void AddParam(string name, string namespaceUri, object parameter);
    public void Clear( );
    public object GetExtensionObject(string namespaceUri);
    public object GetParam(string name, string namespaceUri);
    public object RemoveExtensionObject(string namespaceUri);
    public object RemoveParam(string name, string namespaceUri);
}
```

Passed To

`XslTransform.Transform()`

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

XsltCompileException

serializable


System.Xml.Xsl (system.xml.dll)

class

The `XsltTransform.Load()` method throws this exception when it encounters an error in an XSLT docun

```
public class XsltCompileException : XsltException {
// Public Constructors
    public XsltCompileException(Exception inner, string sourceUri, int lineNumber, int l
// Protected Constructors
    protected XsltCompileException(System.Runtime.Serialization.SerializationInfo info,
        System.Runtime.Serialization.StreamingContext context);
// Public Instance Properties
    public override string Message{get; }
// overrides XsltException
// Public Instance Methods
    public override void GetObjectData( System.Runtime.Serialization.SerializationInfo i
        System.Runtime.Serialization.StreamingContext context)
// overrides XsltException
}
```

Hierarchy



XsltContext

System.Xml.Xsl
(system.xml.dll)

*abstract
class*

This class provides a way to resolve namespaces and determine the current context for XPath variables and expressions. It inherits `System.Xml.XmlNamespaceManager` and its namespace functions. Additional methods defined for this class resolve variables (`ResolveVariable()`) as well as references to XPath functions invoked during execution (`ResolveFunction()`).

```
public abstract class XsltContext : System.Xml.XmlNamespaceManager {
// Public Constructors
    public XsltContext( );
    public XsltContext(System.Xml.NameTable table);
// Public Instance Properties
    public abstract bool Whitespace{get; }
// Public Instance Methods
    public abstract int CompareDocument(string baseUri, string nextbaseUri);
    public abstract bool PreserveWhitespace(System.Xml.XPath.XPathNavigator node);
    public abstract IXsltContextFunction ResolveFunction(string prefix, string name,
        System.Xml.XPath.XPathResultType[ ] ArgTypes);
    public abstract IXsltContextVariable ResolveVariable(string prefix, string name);
}
```

Hierarchy



Passed To

IXsltContextFunction.Invoke(), IXsltContextVariable.Evaluate()

XsltException

serializable

System.Xml.Xsl (system.xml.dll) *class*

This class returns XSLT exception errors thrown by `XsltTransform.Transform()`.

```
public class XsltException : SystemException {  
    // Public Constructors  
    public XsltException(string message, Exception innerException);  
    // Protected Constructors  
    protected XsltException(System.Runtime.Serialization.SerializationInfo info,  
        System.Runtime.Serialization.StreamingContext context);  
    // Public Instance Properties  
    public int LineNumber{get; }  
    public int LinePosition{get; }  
    public override string Message{get; }  
    // overrides Exception  
    public string SourceUri{get; }  
    // Public Instance Methods  
    public override void GetObjectData(System.Runtime.Serialization.SerializationInfo in,  
        System.Runtime.Serialization.StreamingContext context)  
    // overrides Exception  
}
```

Hierarchy

System.Object → System.Exception(System.Runtime.Serialization.ISerializable) →
System.SystemException → XsltException

Subclasses

XsltCompileException

XslTransform

System.Xml.Xsl (system.xml.dll) *sealed class*

This object uses the `Load()` method to input a stylesheet from either a URL, an `XPathNavigator` object implementing `IXPathNavigable`, or an `XmlReader` object (remember, an XSL stylesheet is an XML document). The `Transform()` method takes a URL, an `XPathNavigator` object, or an object implementing `IXPathNavigator` as its first argument, which contains the XML document to transform. The second argument is an `XsltArgumentList` object; see `XsltArgumentList` for an example of using bound functions and/or variables.

The transformed result is output to an `XmlReader` object by default, or you can specify either a `System.Xml.XmlWriter`, or `XmlTextWriter` object in the third argument for the output.

Note that in the .NET 1.1 release, any method or constructor of this class which does not take an `XmlResolver` instance has been marked obsolete, in favor of overloads that take an `XmlResolver` instance to resolve entities (DTD references, entity references, and so on). Change any legacy (pre-1.1) code using those methods to take an `XmlResolver` instance in the method or constructor call, as these obsolete methods could disappear in a future version of the framework.

```
public sealed class XslTransform {
// Public Constructors
    public XslTransform( );
// Public Instance Properties
    public XmlResolver XmlResolver {set; }
// obsolete
// Public Instance Methods
    public void Load(System.Xml.XPath.IXPathNavigable stylesheet);
// obsolete
    public void Load(// obsolete
        System.Xml.XPath.IXPathNavigable stylesheet, System.Xml.XmlResolver resolver);
    public void Load(System.Xml.XPath.IXPathNavigable stylesheet, System.Xml.XmlResolver
        System.Security.Policy.Evidence evidence);
    public void Load(string url);
    public void Load(string url, System.Xml.XmlResolver resolver);
    public void Load(System.Xml.XmlReader stylesheet);
// obsolete
    public void Load(System.Xml.XmlReader stylesheet, System.Xml.XmlResolver resolver);
// obsolete
    public void Load(System.Xml.XmlReader stylesheet, System.Xml.XmlResolver resolver,
        System.Security.Policy.Evidence evidence);
    public void Load(System.Xml.XPath.XPathNavigator stylesheet);
// obsolete
    public void Load(System.Xml.XPath.XPathNavigator stylesheet, System.Xml.XmlResolver
        System.Security.Policy.Evidence evidence);
// obsolete
    public void Load(System.Xml.XPath.XPathNavigator stylesheet, System.Xml.XmlResolver
        System.Security.Policy.Evidence evidence);
}
```



```

        System.Security.Policy.Evidence evidence);
    public void Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList args,
        System.IO.Stream output)
// obsolete
    public void Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList args,
        System.IO.Stream output, System.Xml.XmlResolver resolver);
    public void Transform( System.Xml.XPath.IXPathNavigable input, XsltArgumentList args
        System.IO.TextWriter output)
// obsolete
    public void Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList args,
        System.IO.TextWriter output, System.Xml.XmlResolver resolver);
    public void Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList args,
        System.Xml.XmlWriter output)
// obsolete
    public void Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList args,
        System.Xml.XmlWriter output, System.Xml.XmlResolver resolver);
    public void Transform(string inputfile, string outputfile)
// obsolete
    public void Transform(string inputfile, string outputfile, System.Xml.XmlResolver re
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.IO.Stream output)
// obsolete
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.IO.Stream output, System.Xml.XmlResolver resolver);
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.IO.TextWriter output)
// obsolete
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.IO.TextWriter output, System.Xml.XmlResolver resolver);
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.Xml.XmlWriter output)
// obsolete
    public void Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList args,
        System.Xml.XmlWriter output, System.Xml.XmlResolver resolver);
    public XmlReader Transform(// obsolete
        System.Xml.XPath.IXPathNavigable input, XsltArgumentList args);
    public XmlReader Transform(System.Xml.XPath.IXPathNavigable input, XsltArgumentList
        System.Xml.XmlResolver resolver);
    public XmlReader Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList a
// obsolete
    public XmlReader Transform(System.Xml.XPath.XPathNavigator input, XsltArgumentList a
        System.Xml.XmlResolver resolver);
}

```

[Team LiB]

[< PREVIOUS](#)
[NEXT >](#)

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Part V: Appendixes

Part V includes reference tables for regular expression syntax ([Appendix A](#)); format specifiers ([Appendix B](#)); C#-to-COM default data mapping ([Appendix C](#)); a glossary of C# keywords ([Appendix D](#)); and an alphabetical list of .NET namespaces and the DLLs that expose them ([Appendix E](#)). You can also look up a method or field and find what type it is defined in the [Appendix F](#).

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Appendix A. Regular Expressions

The following tables summarize the regular-expression grammar and syntax supported by the regular-expression classes in `System.Text.RegularExpressions`. Each of the modifiers and qualifiers in the tables can substantially change the behavior of the matching and searching patterns. For further information on regular expressions, we recommend the definitive *Mastering Regular Expressions* by Jeffrey E. F. Friedl (O'Reilly & Associates, 1997).

All the syntax described in the tables should match the Perl5 syntax, with specific exceptions noted.

Table A-1. Character escapes

Escape code sequence	Meaning	Hexadecimal equivalent
<code>\a</code>	Bell	<code>\u0007</code>
<code>\b</code>	Backspace	<code>\u0008</code>
<code>\t</code>	Tab	<code>\u0009</code>
<code>\r</code>	Carriage return	<code>\u000A</code>
<code>\v</code>	Vertical tab	<code>\u000B</code>
<code>\f</code>	Form feed	<code>\u000C</code>
<code>\n</code>	Newline	<code>\u000D</code>
<code>\e</code>	Escape	<code>\u001B</code>
<code>\040</code>	ASCII character as octal	
<code>\x20</code>	ASCII character as hex	
<code>\cC</code>	ASCII control character	
<code>\u0020</code>	Unicode character as hex	
<code>\non-escape</code>	A nonescape character	

Special case: within a regular expression, `\b` means word boundary, except in a `[]` set, in which `\b` means the backspace character.

Table A-2. Substitutions

Expression	Meaning
<code>\$group-number</code>	Substitutes last substring matched by group-number
<code>\${group-name}</code>	Substitutes last substring matched by (<code>?<group-name></code>)

Substitutions are specified only within a replacement pattern.

Table A-3. Character sets

Expression	Meaning
<code>.</code>	Matches any character except <code>\n</code>
<code>[characterlist]</code>	Matches a single character in the list
<code>[^characterlist]</code>	Matches a single character not in the list
<code>[char0-char1]</code>	Matches a single character in a range
<code>\w</code>	Matches a word character; same as <code>[a-zA-Z_0-9]</code>
<code>\W</code>	Matches a nonword character
<code>\s</code>	Matches a space character; same as <code>[\n\r\t\f]</code>
<code>\S</code>	Matches a nonspace character
<code>\d</code>	Matches a decimal digit; same as <code>[0-9]</code>
<code>\D</code>	Matches a nondigit

Table A-4. Positioning assertions

Expression	Meaning
<code>^</code>	Beginning of line
<code>\$</code>	End of line
<code>\A</code>	Beginning of string
<code>\Z</code>	End of line or string
<code>\z</code>	Exactly the end of string
<code>\G</code>	Where search started
<code>\b</code>	On a word boundary
<code>\B</code>	Not on a word boundary


Table A-5. Quantifiers

Quantifier	Meaning
*	0 or more matches
+	1 or more matches
?	0 or 1 matches
{ <i>n</i> }	Exactly <i>n</i> matches
{ <i>n</i> ,}	At least <i>n</i> matches
{ <i>n</i> , <i>m</i> }	At least <i>n</i> , but no more than <i>m</i> matches
*?	Lazy *, finds first match that has minimum repeats
+?	Lazy +, minimum repeats, but at least 1
??	Lazy ?, zero or minimum repeats
{ <i>n</i> }?	Lazy { <i>n</i> }, exactly <i>n</i> matches
{ <i>n</i> ,}?	Lazy { <i>n</i> }, minimum repeats, but at least <i>n</i>
{ <i>n</i> , <i>m</i> }?	Lazy { <i>n</i> , <i>m</i> }, minimum repeats, but at least <i>n</i> , and no more than <i>m</i>

Table A-6. Grouping constructs

Syntax	Meaning
()	Capture matched substring
(?< <i>name</i> >)	Capture matched substring into group <i>name</i> ^[1]
(?< <i>number</i> >)	Capture matched substring into group <i>number</i> *
(?< <i>name1</i> - <i>name2</i> >)	Undefine <i>name2</i> , and store interval and current group into <i>name1</i> ; if <i>name2</i> is undefined, matching backtracks; <i>name1</i> is optional
(? :)	Noncapturing group
(?imnsx-imnsx:)	Apply or disable matching options
(? =)	Continue matching only if subexpression matches on right
(? !)	Continue matching only if subexpression doesn't match on right
(? < =)	Continue matching only if subexpression matches on left
(? < !)	Continue matching only if subexpression doesn't match on left
(? >)	Subexpression is matched once, but isn't backtracked

[1] Single quotes may be used instead of angle brackets-for example (? 'name').



The named capturing group syntax follows a suggestion made by Friedl in *Mastering Regular Expressions*. All other grouping constructs use the Perl5 syntax.

Table A-7. Back references

Parameter syntax	Meaning
<code>\count</code>	Back reference count occurrences
<code>\k<name></code>	Named back reference

Table A-8. Alternation

Expression syntax	Meaning
<code> </code>	Logical OR
<code>(?(<i>expression</i>)yes no)</code>	Matches <i>yes</i> if expression matches, else <i>no</i> ; the <i>no</i> is optional
<code>(?(<i>name</i>)yes no)</code>	Matches <i>yes</i> if named string has a match, else <i>no</i> ; the <i>no</i> is optional

Table A-9. Miscellaneous Constructs

Expression syntax	Meaning
<code>(?<i>imnsx-imnsx</i>)</code>	Set or disable options in midpattern
<code>(?#)</code>	Inline comment
<code># [to end of line]</code>	X-mode comment

Table A-10. Regular expression options

Option	Meaning
<code>i</code>	Case-insensitive match
<code>m</code>	Multiline mode; changes <code>^</code> and <code>\$</code> so they match beginning and ending of any line
<code>n</code>	Capture explicitly named or numbered groups
<code>c</code>	Compile to MSIL
<code>s</code>	Single-line mode; changes meaning of <code>.</code> so it matches every character

Option	Meaning
x	Eliminates unescaped whitespace from the pattern
r	Search from right to left; can't be specified in midstream

[\[Team LiB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Appendix B. Format Specifiers

Table B-1 lists the numeric format specifiers supported by the `Format` method on the predefined numeric types.

Table B-1. Numeric Format Specifiers

Specifier	String result	Datatype
<code>C[n]</code>	<code>\$XX,XX.XX</code> <code>(\$XX,XXX.XX)</code>	Currency
<code>D[n]</code>	<code>[-]XXXXXXX</code>	Decimal
<code>E[n]</code> or <code>e[n]</code>	<code>[-]X.XXXXXXXE+xxx</code> <code>[-]X.XXXXXXXe+xxx</code> <code>[-]X.XXXXXXXE-xxx</code> <code>[-]X.XXXXXXXe-xxx</code>	Exponent
<code>F[n]</code>	<code>[-]XXXXXXX.XX</code>	Fixed point
<code>G[n]</code>	General or scientific	General
<code>N[n]</code>	<code>[-]XX,XXX.XX</code>	Number
<code>X[n]</code> or <code>x[n]</code>	Hex representation	Hex

This example uses numeric format specifiers without precision specifiers:

```
using System;
class TestDefaultFormats {
    static void Main( ) {
        int i = 654321;
        Console.WriteLine("{0:C}", i); // $654,321.00
        Console.WriteLine("{0:D}", i); // 654321
        Console.WriteLine("{0:E}", i); // 6.543210E+005
        Console.WriteLine("{0:F}", i); // 654321.00
        Console.WriteLine("{0:G}", i); // 654321
        Console.WriteLine("{0:N}", i); // 654,321.00
        Console.WriteLine("{0:X}", i); // 9FBF1
        Console.WriteLine("{0:x}", i); // 9fbf1
    }
}
```



```
}
```

This example uses numeric format specifiers with precision specifiers on a variety of `int` values:

```
using System;
class TestIntegerFormats {
    static void Main( ) {
        int i = 123;
        Console.WriteLine("{0:C6}", i); // $123.000000
        Console.WriteLine("{0:D6}", i); // 000123
        Console.WriteLine("{0:E6}", i); // 1.230000E+002
        Console.WriteLine("{0:G6}", i); // 123
        Console.WriteLine("{0:N6}", i); // 123.000000
        Console.WriteLine("{0:X6}", i); // 00007B
        i = -123;
        Console.WriteLine("{0:C6}", i); // ($123.000000)
        Console.WriteLine("{0:D6}", i); // -000123
        Console.WriteLine("{0:E6}", i); // -1.230000E+002
        Console.WriteLine("{0:G6}", i); // -123
        Console.WriteLine("{0:N6}", i); // -123.000000
        Console.WriteLine("{0:X6}", i); // FFFF85
        i = 0;
        Console.WriteLine("{0:C6}", i); // $0.000000
        Console.WriteLine("{0:D6}", i); // 000000
        Console.WriteLine("{0:E6}", i); // 0.000000E+000
        Console.WriteLine("{0:G6}", i); // 0
        Console.WriteLine("{0:N6}", i); // 0.000000
        Console.WriteLine("{0:X6}", i); // 000000
    }
}
```

This example uses numeric format specifiers with precision specifiers on a variety of `double` values:

```
using System;
class TestDoubleFormats {
    static void Main( ) {
        double d = 1.23;
        Console.WriteLine("{0:C6}", d); // $1.230000
        Console.WriteLine("{0:E6}", d); // 1.230000E+000
        Console.WriteLine("{0:G6}", d); // 1.23
        Console.WriteLine("{0:N6}", d); // 1.230000
        d = -1.23;
        Console.WriteLine("{0:C6}", d); // ($1.230000)
        Console.WriteLine("{0:E6}", d); // -1.230000E+000
        Console.WriteLine("{0:G6}", d); // -1.23
        Console.WriteLine("{0:N6}", d); // -1.230000
        d = 0;
        Console.WriteLine("{0:C6}", d); // $0.000000
        Console.WriteLine("{0:E6}", d); // 0.000000E+000
        Console.WriteLine("{0:G6}", d); // 0
        Console.WriteLine("{0:N6}", d); // 0.000000
    }
}
```

}

[Team LiB]

◀ PREVIOUS

NEXT ▶

B.1 Picture Format Specifiers

Table B-2 lists the valid picture format specifiers supported by the `Format` method on the predefined numeric types (see the documentation for `System.IFormattable` in the .NET SDK).

Table B-2. Picture Format Specifiers

Specifier	String result
0	Zero placeholder
#	Digit placeholder
.	Decimal point
,	Group separator or multiplier
%	Percent notation
E+0, E-0 e+0, e-0	Exponent notation
\	Literal character quote
'xx' "xx"	Literal string quote
;	Section separator

This example uses picture-format specifiers on some `int` values:

```
using System;
class TestIntegerCustomFormats {
    static void Main( ) {
        int i = 123;
        Console.WriteLine("{0:#0}", i);           // 123
        Console.WriteLine("{0:#0;(#0)}", i);       // 123
        Console.WriteLine("{0:#0;(#0);<zero>}", i); // 123
        Console.WriteLine("{0:##}", i);            // 12300%
        i = -123;
        Console.WriteLine("{0:#0}", i);           // -123
        Console.WriteLine("{0:#0;(#0)}", i);       // (123)
        Console.WriteLine("{0:#0;(#0);<zero>}", i); // (123)
        Console.WriteLine("{0:##}", i);            // -12300%
        i = 0;
        Console.WriteLine("{0:#0}", i);           // 0
        Console.WriteLine("{0:#0;(#0)}", i);       // 0
        Console.WriteLine("{0:#0;(#0);<zero>}", i); // <zero>
        Console.WriteLine("{0:##}", i);            // %
    }
}
```

```

    }
}

```

The following example uses these picture format specifiers on a variety of `double` values:

```

using System;
class TestDoubleCustomFormats {
    static void Main( ) {
        double d = 1.23;
        Console.WriteLine("{0:#.000E+00}", d);    // 1.230E+00
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00)}", d);        // 1.230E+00
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00);<zero>}", d); // 1.230E+00
        Console.WriteLine("{0:##%}", d);            // 123%
        d = -1.23;
        Console.WriteLine("{0:#.000E+00}", d);    // -1.230E+00
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00)}", d);        // (1.230E+00)
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00);<zero>}", d); // (1.230E+00)
        Console.WriteLine("{0:##%}", d);            // -123%
        d = 0;
        Console.WriteLine("{0:#.000E+00}", d);    // 0.000E-01
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00)}", d);        // 0.000E-01
        Console.WriteLine(
            "{0:#.000E+00;(#.000E+00);<zero>}", d); // <zero>
        Console.WriteLine("{0:##%}", d);            // %
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

B.2 DateTime Format Specifiers

Table B-3 lists the valid format specifiers supported by the `Format` method on the `DateTime` type (see `System.IFormattable`).

Table B-3. DateTime Format Specifiers

Specifier	String result
d	MM/dd/yyyy
D	dddd, MMMM dd, yyyy
f	dddd, MMMM dd, yyyy HH:mm
F	dddd, MMMM dd, yyyy HH:mm:ss
g	MM/dd/yyyy HH:mm
G	MM/dd/yyyy HH:mm:ss
m, M	MMMM dd
r, R	Ddd, dd MMM yyyy HH':'mm':'ss 'GMT'
s	yyyy-MM-dd HH:mm:ss
S	yyyy-MM-dd HH:mm:ss GMT
t	HH:mm
T	HH:mm:ss
u	yyyy-MM-dd HH:mm:ss
U	dddd, MMMM dd, yyyy HH:mm:ss
y, Y	MMMM, yyyy

Here's an example that uses these custom format specifiers on a `DateTime` value:

```
using System;
class TestDateTimeFormats {
    static void Main( ) {
        DateTime dt = new DateTime(2000, 10, 11, 15, 32, 14);
        // Prints "2000-10-11T15:32:14"
        Console.WriteLine(dt.ToString( ));
        // Prints "Wednesday, October 11, 2000"
        Console.WriteLine("{0}", dt);
        // Prints "10/11/2000"
```

```

        Console.WriteLine("{0:d}", dt);
        // Prints "Wednesday, October 11, 2000"
        Console.WriteLine("{0:D}", dt);
        // Prints "Wednesday, October 11, 2000 3:32 PM"
        Console.WriteLine("{0:f}", dt);
        // Prints "Wednesday, October 11, 2000 3:32:14 PM"
        Console.WriteLine("{0:F}", dt);
        // Prints "10/11/2000 3:32 PM"
        Console.WriteLine("{0:g}", dt);
        // Prints "10/11/2000 3:32:14 PM"
        Console.WriteLine("{0:G}", dt);
        // Prints "October 11"
        Console.WriteLine("{0:m}", dt);
        // Prints "October 11"
        Console.WriteLine("{0:M}", dt);
        // Prints "Wed, 11 Oct 2000 22:32:14 GMT"
        Console.WriteLine("{0:r}", dt);
        // Prints "Wed, 11 Oct 2000 22:32:14 GMT"
        Console.WriteLine("{0:R}", dt);
        // Prints "3:32 PM"
        Console.WriteLine("{0:t}", dt);
        // Prints "3:32:14 PM"
        Console.WriteLine("{0:T}", dt);
        // Prints "2000-10-11 22:32:14Z"
        Console.WriteLine("{0:u}", dt);
        // Prints "Wednesday, October 11, 2000 10:32:14 PM"
        Console.WriteLine("{0:U}", dt);
        // Prints "October, 2000"
        Console.WriteLine("{0:y}", dt);
        // Prints "October, 2000"
        Console.WriteLine("{0:Y}", dt);
        // Prints "Wednesday the 11 day of October in the year 2000"
        Console.WriteLine(
            "{0:dddd 'the' d 'day of' MMMM 'in the year' yyyy}", dt);
    }
}

```

[\[Team LiB \]](#)

◀ PREVIOUS

NEXT ▶

Appendix C. Data Marshaling

When calling between the runtime environment and existing COM interfaces, the CLR performs automatic data marshaling for CLR types into compatible COM types. Table C-1 describes the C# to COM default data type mapping.

Table C-1. C# type to COM type mapping

C# type	COM type
bool	VARIANT_BOOL
char	unsigned short
sbyte	Char
byte	Unsigned char
short	Short
ushort	Unsigned short
int	Int
uint	Unsigned int
long	Hyper
ulong	Unsigned hyper
float	Single
double	Double
decimal	DECIMAL
object	VARIANT
string	BSTR
System.DateTime	DATE ^[1]
System.Guid	GUID
System.Currency	CURRENCY
1-dimensional arrays	SAFEARRAY
Value types	Equivalently named struct
enum	Equivalently named enum

C# type	COM type
interface	Equivalently named interface
class	Equivalently named CoClass

[1] COM dates are less precise, causing comparison problems.

Table C-2. C# modifier/COM attribute mapping

C# modifier	COM attribute
<no modifier>	[in]
out	[out]
ref	[in, out]
<return value>	[out, retval]

[\[Team LiB \]](#)

Appendix D. C# Keywords

`abstract`

A class modifier that specifies that the class must be derived from to be instantiated.

`operator`

A binary operator type that casts the left operand to the type specified by the right operand and that returns `null` rather than throwing an exception if the cast fails.

`base`

A variable with the same meaning as `this`, except that it accesses a base-class implementation of a member.

`bool`

A logical datatype that can be `true` or `false`.

`break`

A jump statement that exits a loop or `switch` statement block.

`byte`

A one-byte, unsigned integral data type.

`case`

A selection statement that defines a particular choice in a `switch` statement.

`catch`

The part of a `try` statement that catches exceptions of a specific type defined in the `catch` clause.

`char`

A two-byte, Unicode character data type.

`checked`

A statement or operator that enforces arithmetic bounds checking on an expression or statement block.

`class`

An extendable reference type that combines data and functionality into one unit.

`const`

A modifier for a local variable or field declaration that indicates that the value is a constant. A `const` is evaluated at compile time and can be only a predefined type.

`continue`

A jump statement that skips the remaining statements in a statement block and continues to the next iteration in a loop.

`decimal`

A 16-byte precise decimal datatype.

`default`

A marker in a `switch` statement specifying the action to take when no `case` statements match the `switch` expression.

`delegate`

A type for defining a method signature so delegate instances can hold and invoke a method or list of methods that match its signature.

`do`

A loop statement to iterate a statement block until an expression at the end of the loop evaluates to `false`.

`double`

An 8-byte, floating-point data type.

`else`

A conditional statement that defines the action to take when a preceding `if` expression evaluates to `false`.

`enum`

A value type that defines a group of named numeric constants.

`event`

A member modifier for a delegate field or property that indicates that only the `+=` and `-=` methods of the delegate can be accessed.

`explicit`

An operator that defines an explicit conversion.

`extern`

A method modifier that indicates that the method is implemented with unmanaged code.

`false`

A Boolean literal.

`finally`

The part of a `try` statement to execute whenever control leaves the scope of the `try` block.

`fixed`

A statement to pin down a reference type so the garbage collector won't move it during pointer arithmetic operations.

`float`

A four-byte floating-point data type.

`for`

A loop statement that combines an initialization statement, continuation condition, and iterative statement into one statement.

`foreach`

A loop statement that iterates over collections that implement `IEnumerable`.

`get`

The name of the accessor that returns the value of a property.

`goto`

A `jump` statement that jumps to a label within the same method and same scope as the jump point.

`if`

A conditional statement that executes its statement block if its expression evaluates to `true`.

`implicit`

An operator that defines an implicit conversion.

`in`

The operator between a type and an `IEnumerable` in a `foreach` statement.

`int`

A four-byte, signed integral data type.

`interface`

A contract that specifies the members that a class or struct may implement to receive generic services for that type.

`internal`

An access modifier that indicates that a type or type member is accessible only to other types in the same assembly.

`is`

A relational operator that evaluates to `true` if the left operand's type matches, is derived from, or implements the type specified by the right operand.

`lock`

A statement that acquires a lock on a reference-type object to help multiple threads cooperate.

`long`

An eight-byte, signed integral data type.

`namespace`

A keyword that maps a set of types to a common name.

`new`

An operator that calls a constructor on a type, allocating a new object on the heap if the type is a reference type, or initializing the object if the type is a value type. The keyword is overloaded to hide an inherited member.

`null`

A reference-type literal that indicates that no object is referenced.

`object`

The type all other types derive from.

`operator`

A method modifier that overloads operators.

`out`

A parameter modifier that specifies that the parameter is passed by reference and must be assigned by the method being called.

`override`

A method modifier that indicates that a method of a class overrides a virtual method of a class or interface.

`params`

A parameter modifier that specifies that the last parameter of a method may accept multiple parameters of the same type.

`private`

An access modifier that indicates that only the containing type can access the member.

`protected`

An access modifier that indicates that only the containing type or derived types can access the member.

`public`

An access modifier that indicates that a type or type member is accessible to all other types.

`readonly`

A field modifier specifying that a field can be assigned only once, either in its declaration or in its containing type's constructor.

`ref`

A parameter modifier that specifies that the parameter is passed by reference and is assigned before being passed to the method.

`return`

A jump statement that exits a method, specifying a return value when the method is nonvoid.

`sbyte`

A one-byte, signed integral data type.

`sealed`

A class modifier that indicates a class cannot be derived from.

`set`

The name of the accessor that sets the value of a property.

`short`

A two-byte, signed integral data type.

`sizeof`

An operator that returns the size in bytes of a struct.

`stackalloc`

An operator that returns a pointer to a specified number of value types allocated on the stack.

`static`

A type member modifier that indicates that the member applies to the type rather than to an

instance of the type.

`string`

A predefined reference type that represents an immutable sequence of Unicode characters.

`struct`

A value type that combines data and functionality in one unit.

`switch`

A selection statement that allows a selection of choices to be made based on the value of a predefined type.

`this`

A variable that references the current instance of a class or struct.

`throw`

A jump statement that throws an exception when an abnormal condition has occurred.

`true`

A boolean literal.

`try`

A statement that provides a way to handle an exception or a premature exit in a statement block.

`typeof`

An operator that returns the type of an object as a `System.Type` object.

`uint`

A four-byte, unsigned integral data type.

`ulong`

An eight-byte, unsigned integral data type.

`unchecked`

A statement or operator that prevents arithmetic bounds checking on an expression.

`unsafe`

A method modifier or statement that permits pointer arithmetic to be performed within a particular block.

`ushort`

A two-byte, unsigned integral data type.

`using`

A directive that specifies that types in a particular namespace can be referred to without requiring their fully qualified type names. The keyword is overloaded as a statement that allows an object that implements `IDisposable` to be disposed of at the end of the statement's scope.

`value`

The name of the implicit variable set by the set accessor of a property.

`virtual`

A class method modifier that indicates that a method can be overridden by a derived class.

`void`

A keyword used in place of a type for methods that don't have a return value.

`volatile`

A field modifier indicating that a field's value may be modified in a multithreaded scenario; neither the compiler nor runtime should perform optimizations with that field.

`while`

A loop statement to iterate a statement block while an expression at the start of each iteration evaluates to `false`.

[\[Team LIB \]](#)

[◀ PREVIOUS](#) [NEXT ▶](#)

Appendix E. Namespaces and Assemblies

This appendix allows you to look up a namespace and determine which assemblies export that namespace information is helpful when constructing the appropriate `/reference:<file list>` command-line option compiler. However, commonly used assemblies are referenced by default.

For a complete list of default assemblies, see the global C# response file, `csc.rsp`, in `%SystemRoot%\Microsoft.NET\Framework\VERSION`, where `VERSION` is the version number of the framework. The first release of .NET is v1.0.3705, and 1.1 is v1.1.4322). You can modify `csc.rsp` to affect all compilations on a particular machine, or you can create a local `csc.rsp` in your current directory. The local response file is processed after the global one. You can use the `/noconfig` switch with `csc.exe` to disable the local and global `csc.rsp` files entirely.

Namespace	DLLs
Accessibility	Accessibility.dll
EnvDTE	envdte.dll
IEHost.Execute	IEExecRemote.dll
Microsoft.CLRAdmin	mscorlib.dll
Microsoft.CSharp	cscorlib.dll System.dll
Microsoft.IE	IEHost.dll IIEHost.dll
Microsoft.JScript	Microsoft.JScript.dll
Microsoft.JScript.Vsa	Microsoft.JScript.Vsa.dll
Microsoft.Office.Core	office.dll
Microsoft.VisualBasic	Microsoft.VisualBasic.dll System.dll
Microsoft.VisualBasic.Compatibility.VB6	Microsoft.VisualBasic.Compatibility.Da Microsoft.VisualBasic.Compatibility.dll
Microsoft.VisualBasic.CompilerServices	Microsoft.VisualBasic.dll
Microsoft.VisualBasic.Vsa	Microsoft.VisualBasic.Vsa.dll
Microsoft.VisualBasic	Microsoft.VisualBasic.dll

Namespace	DLLs
Microsoft.Vsa	Microsoft.JScript.dll Microsoft.Vsa.dll
Microsoft.Vsa.Vb.CodeDOM	Microsoft.Vsa.Vb.CodeDOMProcessor.dll
Microsoft.Win32	mscorlib.dll System.dll
Microsoft_VsaVb	Microsoft_VsaVb.dll
RegCode	RegCode.dll
System	mscorlib.dll System.dll
System.CodeDom	System.dll
System.CodeDom.Compiler	System.dll
System.Collections	mscorlib.dll
System.Collections.Specialized	System.dll
System.ComponentModel	System.dll
System.ComponentModel.Design	System.Design.dll System.dll
System.ComponentModel.Design.Serialization	System.Design.dll System.dll
System.Configuration	System.dll
System.Configuration.Assemblies	mscorlib.dll
System.Configuration.Install	System.Configuration.Install.dll
System.Data	System.Data.dll
System.Data.Common	System.Data.dll
System.Data.Odbc	System.Data.dll
System.Data.OleDb	System.Data.dll
System.Data.OracleClient	System.Data.OracleClient.dll
System.Data.SqlClient	System.Data.dll
System.Data.SqlTypes	System.Data.dll
System.Diagnostics	mscorlib.dll System.Configuration.Install.dll

Namespace	DLLs
System.Diagnostics.Design	<i>System.Design.dll</i>
System.Diagnostics.SymbolStore	<i>ISymWrapper.dll</i> <i>mscorlib.dll</i>
System.DirectoryServices	<i>System.DirectoryServices.dll</i>
System.Drawing	<i>System.Drawing.dll</i>
System.Drawing.Design	<i>System.Drawing.Design.dll</i> <i>System.Drawing.dll</i>
System.Drawing.Drawing2D	<i>System.Drawing.dll</i>
System.Drawing.Imaging	<i>System.Drawing.dll</i>
System.Drawing.Printing	<i>System.Drawing.dll</i>
System.Drawing.Text	<i>System.Drawing.dll</i>
System.EnterpriseServices	<i>System.EnterpriseServices.dll</i>
System.EnterpriseServices.CompensatingResourceManager	<i>System.EnterpriseServices.dll</i>
System.EnterpriseServices.Internal	<i>System.EnterpriseServices.dll</i>
System.Globalization	<i>mscorlib.dll</i>
System.IO	<i>mscorlib.dll</i> <i>System.dll</i>
System.IO.IsolatedStorage	<i>mscorlib.dll</i>
System.Management	<i>System.Management.dll</i>
System.Management.Instrumentation	<i>System.Management.dll</i>
System.Messaging	<i>System.Messaging.dll</i>
System.Messaging.Design	<i>System.Design.dll</i> <i>System.Messaging.dll</i>
System.Net	<i>System.dll</i>
System.Net.Sockets	<i>System.dll</i>
System.Reflection	<i>mscorlib.dll</i>
System.Reflection.Emit	<i>mscorlib.dll</i>
System.Resources	<i>mscorlib.dll</i> <i>System.Windows.Forms.dll</i>
System.Runtime.CompilerServices	<i>mscorlib.dll</i>

Namespace	DLLs
System.Runtime.InteropServices	<i>mscorlib.dll</i>
System.Runtime.InteropServices.CustomMarshalers	<i>CustomMarshalers.dll</i>
System.Runtime.InteropServices.Expando	<i>mscorlib.dll</i>
System.Runtime.Remoting	<i>mscorlib.dll</i>
System.Runtime.Remoting.Activation	<i>mscorlib.dll</i>
System.Runtime.Remoting.Channels	<i>mscorlib.dll</i> <i>System.Runtime.Remoting.dll</i>
System.Runtime.Remoting.Channels.Http	<i>System.Runtime.Remoting.dll</i>
System.Runtime.Remoting.Channels.Tcp	<i>System.Runtime.Remoting.dll</i>
System.Runtime.Remoting.Contexts	<i>mscorlib.dll</i>
System.Runtime.Remoting.Lifetime	<i>mscorlib.dll</i>
System.Runtime.Remoting.Messaging	<i>mscorlib.dll</i>
System.Runtime.Remoting.Metadata	<i>mscorlib.dll</i>
System.Runtime.Remoting.Metadata.W3cXsd2001	<i>mscorlib.dll</i>
System.Runtime.Remoting.MetadataServices	<i>System.Runtime.Remoting.dll</i>
System.Runtime.Remoting.Proxies	<i>mscorlib.dll</i>
System.Runtime.Remoting.Services	<i>mscorlib.dll</i> <i>System.Runtime.Remoting.dll</i>
System.Runtime.Serialization	<i>mscorlib.dll</i>
System.Runtime.Serialization.Formatter	<i>mscorlib.dll</i>
System.Runtime.Serialization.Formatter.Binary	<i>mscorlib.dll</i>
System.Runtime.Serialization.Formatter.Soap	<i>System.Runtime.Serialization.Formatter</i>
System.Security	<i>mscorlib.dll</i>
System.Security.Cryptography	<i>mscorlib.dll</i>
System.Security.Cryptography.X509Certificates	<i>mscorlib.dll</i> <i>System.dll</i>
System.Security.Cryptography.Xml	<i>System.Security.dll</i>
System.Security.Permissions	<i>mscorlib.dll</i> <i>System.dll</i>
System.Security.Policy	<i>mscorlib.dll</i>

Namespace	DLLs
System.Security.Principal	<i>mscorlib.dll</i>
System.ServiceProcess	<i>System.ServiceProcess.dll</i>
System.ServiceProcess.Design	<i>System.Design.dll</i>
	<i>System.ServiceProcess.dll</i>
System.Text	<i>mscorlib.dll</i>
System.Text.RegularExpressions	<i>System.dll</i>
System.Threading	<i>mscorlib.dll</i>
	<i>System.dll</i>
System.Timers	<i>System.dll</i>
System.Web	<i>System.Web.dll</i>
System.Web.Caching	<i>System.Web.dll</i>
System.Web.Configuration	<i>System.Web.dll</i>
System.Web.Handlers	<i>System.Web.dll</i>
System.Web.Hosting	<i>System.Web.dll</i>
System.Web.Mobile	<i>System.Web.Mobile.dll</i>
System.Web.Mail	<i>System.Web.dll</i>
System.Web.RegularExpressions	<i>System.Web.RegularExpressions.dll</i>
System.Web.Security	<i>System.Web.dll</i>
System.Web.Services	<i>System.Web.Services.dll</i>
System.Web.Services.Configuration	<i>System.Web.Services.dll</i>
System.Web.Services.Description	<i>System.Web.Services.dll</i>
System.Web.Services.Discovery	<i>System.Web.Services.dll</i>
System.Web.Services.Protocols	<i>System.Web.Services.dll</i>
System.Web.SessionState	<i>System.Web.dll</i>
System.Web.UI	<i>System.Web.dll</i>
System.Web.UI.Design	<i>System.Design.dll</i>
System.Web.UI.Design.MobileControls	<i>System.Web.Mobile.dll</i>
System.Web.UI.Design.WebControls	<i>System.Design.dll</i>
System.Web.UI.HtmlControls	<i>System.Web.dll</i>
System.Web.UI.MobileControls	<i>System.Web.Mobile.dll</i>

Namespace	DLLs
System.Web.UI.WebControls	System.Web.dll
System.Web.Util	System.Web.dll
System.Windows.Forms	System.Windows.Forms.dll
System.Windows.Forms.ComponentModel.Com2Interop	System.Windows.Forms.dll
System.Windows.Forms.Design	System.Design.dll
	System.Windows.Forms.dll
System.Windows.Forms.PropertyGridInternal	System.Windows.Forms.dll
System.Xml	System.Data.dll
	System.XML.dll
System.Xml.Schema	System.XML.dll
System.Xml.Serialization	System.XML.dll
System.Xml.XPath	System.XML.dll
System.Xml.Xsl	System.XML.dll

Appendix F. Type, Method, Property, Event, and Field Index

Use this index to look up a type or member and see where it is defined. For a type (a class or interface), you can find the enclosing namespace. If you know the name of a member (a method, property, event, or field), you can find all the types that define it.

[A-D](#)

[E-I](#)

[J-R](#)

[S-Z](#)

A-D

AbbreviatedDayNames:

DateTimeFormatInfo

AbbreviatedMonthNames:

DateTimeFormatInfo

Abort():

HttpRequest, Thread, WebRequest

Aborted:

ThreadState

AbortRequested:

ThreadState

AboveNormal:

ProcessPriorityClass, ThreadPriority, ThreadPriorityLevel

Abs():

Math

AbsolutePath:

Uri

AbsoluteUri:

Uri

Abstract:

MethodAttributes, TypeAttributes

Accept:

HttpRequest, NetworkAccess, WebPermissionAttribute

Accept():

Socket

AcceptConnection:

SocketOptionName

Accepted:

HttpStatusCode

AcceptList:

SocketPermission, WebPermission

AcceptPattern:

WebPermissionAttribute

AcceptSocket():

TcpListener

AcceptTcpClient():

TcpListener

Access:

SocketPermissionAttribute

Accessibility:

UserPreferenceCategoryf

Acos():

Math

AcquireReaderLock():

ReaderWriterLock

AcquireWriterLock():

ReaderWriterLock

Action:

XmlNodeChangedEventArgs

Activator:

System

ActualValue:

ArgumentOutOfRangeException

Adapter():

ArrayList

Add:

OpCodes

Add():

ArrayList, CookieCollection, CookieContainer, CounterCreationDataCollection, CredentialCache, DateTime, Decimal, EventLogPermissionEntryCollection, Hashtable, HybridDictionary, IDictionary, IList, ListDictionary, NameTable, NameValueCollection, PerformanceCounterPermissionEntryCollection, ProcessThreadCollection, SortedList, StringCollection, StringDictionary, TimeSpan, TraceListenerCollection, WebHeaderCollection, XmlNameTable

Add_Ovf:

OpCodes

Add_Ovf_Un:

OpCodes

AddArgument():

SignatureHelper

AddDays():

Calendar, DateTime

AddDeclarativeSecurity():

ConstructorBuilder, MethodBuilder, TypeBuilder

AddEventHandler():

EventInfo

AddExtensionObject():

XsltArgumentList

AddHours():

Calendar, DateTime

AddInterfaceImplementation():

TypeBuilder

AddMembership():

SocketOptionName

AddMilliseconds():

Calendar, DateTime

AddMinutes():

Calendar, DateTime

AddMonths():

Calendar, DateTime, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

AddNamespace():

XmlNamespaceManager

AddOtherMethod():

EventBuilder, PropertyBuilder

AddParam():

XsltArgumentList

AddPermission():

SocketPermission, WebPermission

AddRange():

ArrayList, CounterCreationDataCollection, EventLogPermissionEntryCollection, HttpWebRequest, PerformanceCounterPermissionEntryCollection, StringCollection, TraceListenerCollection

AddRef():

Marshal

AddResourceFile():

AssemblyBuilder

Address:

HttpRequest, IPAddress, IPEndPoint, ServicePoint, WebProxy

AddressFamily:

EndPoint, IPAddress, IPEndPoint, Socket, System.Net.Sockets

AddressList:

IPHostEntry

AddrOfPinnedObject():

GCHandle

AddSeconds():

Calendar, DateTime

AddSentinel():

SignatureHelper

AddSort():

XPathExpression

AddSourceMembership:

SocketOptionName

AddSurrogate():

SurrogateSelector

AddTicks():

DateTime

AddValue():

SerializationInfo

AddWeeks():

Calendar, GregorianCalendar

AddWithoutValidate():

WebHeaderCollection

AddYears():

Calendar, DateTime, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

ADEra:

GregorianCalendar

AdjustToUniversal:

DateTimeStyles

Administer:

PerformanceCounterPermissionAccess

After:

XmlNodeOrder

AlgorithmId:

AssemblyAlgorithmIdAttribute

Aliases:

IHostEntry

All:

AttributeTargets, MemberTypes, StreamingContextStates, TransportType,
WatcherChangeTypes, WhitespaceHandling, XPathNamespaceScope, XPathNodeType

AllCultures:

CultureTypes

AllKeys:

NameValueCollection

Alloc():

GCHandle

AllocateDataSlot():

Thread

AllocateNamedDataSlot():

Thread

AllocCoTaskMem():

Marshal

AllocHGlobal():

Marshal

AllowAutoRedirect:

HttpRequest

AllowCurrencySymbol:

NumberStyles

AllowDecimalPoint:

NumberStyles

AllowExponent:

NumberStyles

AllowHexSpecifier:

NumberStyles

AllowInnerWhite:

DateTimeStyles

AllowLeadingSign:

NumberStyles

AllowLeadingWhite:

DateTimeStyles, NumberStyles

AllowMultiple:

AttributeUsageAttribute

AllowParentheses:

NumberStyles

AllowThousands:

NumberStyles

AllowTrailingSign:

NumberStyles

AllowTrailingWhite:

DateTimeStyles, NumberStyles

AllowWhiteSpaces:

DateTimeStyles

AllowWriteStreamBuffering:

HttpRequest

AllPorts:

SocketPermission

AltDirectorySeparatorChar:

Path

Ambiguous:

HttpStatusCode

AmbiguousMatchException:

System.Reflection

AMDesignator:

DateTimeFormatInfo

And:

OpCodes

And():

BitArray

Annotation:

OpCodeType

Ansi:

CharSet

AnsiBStr:

UnmanagedType

AnsiClass:

TypeAttributes

ANSI CodePage:

TextInfo

Any:

CallingConventions, IPAddress, NumberStyles, XPathResultType

AnyWritersSince():

ReaderWriterLock

ApartmentState:

System.Threading, Thread

AppDomain:

System

AppDomainSetup:

System

AppDomainUnloadedException:

System

Append:

FileMode

Append():

StringBuilder, XmlAttributeCollection

AppendChild():

XmlNode

AppendData():

XmlCharacterData

AppendFormat():

StringBuilder

AppendPrivatePath():

AppDomain

AppendText():

File, FileInfo

AppleTalk:

AddressFamily, ProtocolFamily

ApplicationBase:

AppDomainSetup

ApplicationData:

SpecialFolder

ApplicationException:

System

ApplicationName:

AppDomainSetup

Arabic:

GregorianCalendarTypes

Archive:

FileAttributes

ArgIterator:

System

Arglist:

OpCodes

ArgTypes:

IXsltContextFunction

ArgumentException:

System

ArgumentNullException:

System

ArgumentOutOfRangeException:

System

Arguments:

ProcessStartInfo

ArithmeticException:

System

Array:

System

ArrayList:

System.Collections

ArraySubType:

MarshalAsAttribute

ArrayTypeMismatchException:

System

ArrayWithOffset:

System.Runtime.InteropServices

AsAny:

UnmanagedType

Ascending:

XmlSortOrder

ASCII:

Encoding

ASCIIEncoding:

System.Text

Asin():

Math

Assembly:

AttributeTargets, EnumBuilder, FieldAttributes, IsolatedStorageScope, MethodAttributes,
Module, System.Reflection, Type, TypeBuilder, TypeDelegator

AssemblyAlgorithmIdAttribute:

System.Reflection

AssemblyBuilder:

System.Reflection.Emit

AssemblyBuilderAccess:

System.Reflection.Emit

AssemblyCompanyAttribute:

System.Reflection

AssemblyConfigurationAttribute:

System.Reflection

AssemblyCopyrightAttribute:

System.Reflection

AssemblyCultureAttribute:

System.Reflection

AssemblyDefaultAliasAttribute:

System.Reflection

AssemblyDelaySignAttribute:

System.Reflection

AssemblyDescriptionAttribute:

System.Reflection

AssemblyFileVersionAttribute:

System.Reflection

AssemblyFlags:

AssemblyFlagsAttribute

AssemblyFlagsAttribute:

System.Reflection

AssemblyIdentity:

IsolatedStorage

AssemblyInformationalVersionAttribute:

System.Reflection

AssemblyKeyFileAttribute:

System.Reflection

AssemblyKeyNameAttribute:

System.Reflection

AssemblyLoad:

AppDomain

AssemblyLoadEventArgs:

System

AssemblyLoadEventHandler:

System

AssemblyName:

SerializationInfo, System.Reflection

AssemblyNameFlags:

System.Reflection

AssemblyNameProxy:

System.Reflection

AssemblyProductAttribute:

System.Reflection

AssemblyQualifiedName:

EnumBuilder, Type, TypeBuilder, TypeDelegator

AssemblyRegistrationFlags:

System.Runtime.InteropServices

AssemblyResolve:

AppDomain

AssemblyTitleAttribute:

System.Reflection

AssemblyTrademarkAttribute:

System.Reflection

AssemblyVersionAttribute:

System.Reflection

Assert():

Debug, Trace

AssertUiEnabled:

DefaultTraceListener

AsyncCallback:

System

AsyncResult:

Overlapped

AsyncState:

IAsyncResult

AsyncWaitHandle:

IAsyncResult

Atan():

Math

Atan2():

Math

Atm:

AddressFamily, ProtocolFamily

Attribute:

System, WriteState, XmlNodeType, XPathNodeType

AttributeCount:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

Attributes:

ConstructorBuilder, EventInfo, FieldBuilder, FieldInfo, FileSystemInfo, MethodBase,
MethodBuilder, NotifyFilters, ParameterBuilder, ParameterInfo, PropertyBuilder, PropertyInfo,
Type, XmlElement, XmlNode

AttributeTargets:

System

AttributeUsageAttribute:

System

AttrsImpl:

ParameterInfo

Audit:

EventLogPermissionAccess

Authenticate():

AuthenticationManager, IAuthenticationModule

AuthenticationManager:

System.Net

AuthenticationType:

IAuthenticationModule

Authority:

Uri, UriPartial

Authorization:

System.Net

Auto:

CharSet, LayoutKind, ValidationType

AutoClass:

TypeAttributes

AutoDispatch:

ClassInterfaceType

AutoDual:

ClassInterfaceType

AutoFlush:

Debug, StreamWriter, Trace

AutoLayout:

TypeAttributes

AutoReset:

Timer

AutoResetEvent:

System.Threading

Available:

Socket

AverageBase:

PerformanceCounterType

AverageCount64:

PerformanceCounterType

AverageTimer32:

PerformanceCounterType

Background:

ThreadState

BadGateway:

HttpStatusCode

BadImageFormatException:

System

BadRequest:

HttpStatusCode

Banyan:

AddressFamily, ProtocolFamily
BaseAdd():

NameObjectCollectionBase
BaseAddress:

ProcessModule, WebClient
BaseClear():

NameObjectCollectionBase
BaseDirectory:

AppDomain
BaseGet():

NameObjectCollectionBase
BaseGetAllKeys():

NameObjectCollectionBase
BaseGetAllValues():

NameObjectCollectionBase
BaseGetKey():

NameObjectCollectionBase
BaseHasKeys():

NameObjectCollectionBase
BasePriority:

Process, ProcessThread
BaseRemove():

NameObjectCollectionBase
BaseRemoveAt():

NameObjectCollectionBase
BaseSet():

NameObjectCollectionBase
BaseStream:

BinaryReader, BinaryWriter, StreamReader, StreamWriter, XmlTextWriter
BaseType:

EnumBuilder, Type, TypeBuilder, TypeDelegator, UnmanagedMarshal
BaseURI:

XmlAttribute, XmlDocument, XmlEntity, XmlEntityReference, XmlNode, XmlNodeReader,
 XmlParserContext, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator
BaseValue:

CounterSample

Basic:

UriHostNameType

Before:

XmlNodeOrder

BeforeFieldInit:

TypeAttributes

Begin:

SeekOrigin

BeginAccept():

Socket

BeginCatchBlock():

ILGenerator

BeginConnect():

Socket

BeginExceptFilterBlock():

ILGenerator

BeginExceptionBlock():

ILGenerator

BeginFaultBlock():

ILGenerator

BeginFinallyBlock():

ILGenerator

BeginGetHostByName():

Dns

BeginGetRequestStream():

FileWebRequest, HttpWebRequest, WebRequest

BeginGetResponse():

FileWebRequest, HttpWebRequest, WebRequest

BeginInit():

EventLog, FileSystemWatcher, PerformanceCounter, Timer

BeginInvoke():

AssemblyLoadEventHandler, AsyncCallback, CrossAppDomainDelegate, ElapsedEventHandler, EntryWrittenEventHandler, ErrorEventHandler, EventHandler, FileSystemEventHandler, HttpContinueDelegate, IOCompletionCallback, MatchEvaluator, MemberFilter, ModuleResolveEventHandler, ObjectCreationDelegate, PowerModeChangedEventHandler, RenamedEventHandler, ResolveEventHandler, SessionEndedEventHandler, SessionEndingEventHandler, ThreadExceptionHandler, ThreadStart, TimerCallback,

TimerElapsedEventHandler, TypeFilter, UnhandledExceptionEventHandler,
UserPreferenceChangedEventHandler, UserPreferenceChangingEventHandler, WaitCallback,
WaitOrTimerCallback, XmlNodeChangedEventHandler

BeginRead():

FileStream, IsolatedStorageFileStream, NetworkStream, Stream

BeginReceive():

Socket

BeginReceiveFrom():

Socket

BeginResolve():

Dns

BeginScope():

ILGenerator

BeginSend():

Socket

BeginSendTo():

Socket

BeginWrite():

FileStream, IsolatedStorageFileStream, NetworkStream, Stream

BelowNormal:

ProcessPriorityClass, ThreadPriority, ThreadPriorityLevel

Beq:

OpCodes

Beq_S:

OpCodes

BestFitMapping:

BestFitMappingAttribute, DllImportAttribute

BestFitMappingAttribute:

System.Runtime.InteropServices

Bge:

OpCodes

Bge_S:

OpCodes

Bge_Un:

OpCodes

Bge_Un_S:

OpCodes

Bgt:

OpCodes

Bgt_S:

OpCodes

Bgt_Un:

OpCodes

Bgt_Un_S:

OpCodes

BigEndianUnicode:

Encoding

BigMul():

Math

BinaryReader:

System.IO

BinarySearch():

Array, ArrayList

BinaryWriter:

System.IO

Bind():

Socket

Binder:

Formatter, IFormatter, System.Reflection

BindHandle():

ThreadPool

BindingFlags:

System.Reflection

BindToField():

Binder

BindToMethod():

Binder

BindToMoniker():

Marshal

BindToType():

SerializationBinder

BitArray:

System.Collections

BitConverter:

System

BitVector32:

System.Collections.Specialized

Ble:

OpCodes

Ble_S:

OpCodes

Ble_Un:

OpCodes

Ble_Un_S:

OpCodes

BlockCopy():

Buffer

Blocking:

Socket

BlockSource:

SocketOptionName

Blt:

OpCodes

Blt_S:

OpCodes

Blt_Un:

OpCodes

Blt_Un_S:

OpCodes

Bne_Un:

OpCodes

Bne_Un_S:

OpCodes

BodyName:

Encoding

Bool:

UnmanagedType

Boolean:

System, TypeCode, XPathResultType

BooleanSwitch:

System.Diagnostics

Both:

SocketShutdown

Box:

OpCodes

Box():

Pointer

Br:

OpCodes

Br_S:

OpCodes

Branch:

FlowControl

Break:

FlowControl, OpCodes

Break():

Debugger

Brfalse:

OpCodes

Brfalse_S:

OpCodes

Broadcast:

IPAddress, SocketOptionName

Browse:

EventLogPermissionAccess, PerformanceCounterPermissionAccess

Brtrue:

OpCodes

Brtrue_S:

OpCodes

BsdUrgent:

SocketOptionName

BStr:

UnmanagedType

Buffer:

System

BufferedStream:

System.IO

Build:

Version

BuildNumber:

ComCompatibleVersionAttribute

BypassArrayList:

WebProxy

BypassList:

WebProxy

BypassProxyOnLocal:

WebProxy

Byte:

System, TypeCode

ByteLength():

Buffer

ByValArray:

UnmanagedType

ByValTStr:

UnmanagedType

CachePath:

AppDomainSetup

Calculate():

CounterSample

Calendar:

CultureInfo, DateTimeFormatInfo, System.Globalization

CalendarType:

GregorianCalendar

CalendarWeekRule:

DateTimeFormatInfo, System.Globalization

Call:

FlowControl, OpCodes

Calli:

OpCodes

CallingConvention:

DllImportAttribute, MethodBase, MethodBuilder, System.Runtime.InteropServices

CallingConventions:

System.Reflection

Callvirt:

OpCodes

Cancel:

SessionEndingEventArgs

CannotUnloadAppDomainException:

System

Canonicalize():

Uri

CanPreAuthenticate:

IAuthenticationModule

CanRead:

BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream,
PropertyBuilder, PropertyInfo, Stream

CanResolveEntity:

XmlNodeReader, XmlReader, XmlValidatingReader

CanResume():

SEHException

CanSeek:

BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream,
Stream

CanWrite:

BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream,
PropertyBuilder, PropertyInfo, Stream

Capacity:

ArrayList, CookieContainer, MemoryStream, SortedList, StringBuilder

Capture:

System.Text.RegularExpressions

CaptureCollection:

System.Text.RegularExpressions

Captures:

Group

CaseInsensitiveComparer:

System.Collections

CaseInsensitiveHashCodeProvider:

System.Collections

Castclass:

OpCodes

Category:

EventLogEntry, UserPreferenceChangedEventArgs, UserPreferenceChangingEventArgs

CategoryHelp:

PerformanceCounterCategory, PerformanceCounterInstaller

CategoryName:

PerformanceCounter, PerformanceCounterCategory, PerformanceCounterInstaller,
PerformanceCounterPermissionAttribute, PerformanceCounterPermissionEntry

CategoryNumber:

EventLogEntry

Ccitt:

AddressFamily, ProtocolFamily

CDATA:

XmlNodeType, XmlTokenizedType

Cdecl:

CallingConvention

Ceiling():

Math

Ceq:

OpCodes

Certificate:

ServicePoint

CertificatePolicy:

ServicePointManager

Cgt:

OpCodes

Cgt_Un:

OpCodes

ChainSelector():

ISurrogateSelector, SurrogateSelector

Change:

XmlNodeChangedAction

Change():

Timer

Changed:

FileSystemWatcher, WatcherChangeTypes

ChangeExtension():

Path

ChangeType:

FileSystemEventArgs, WaitForChangedResult

ChangeType():

Binder, Convert

ChangeWrapperHandleStrength():

Marshal

Chaos:

AddressFamily, ProtocolFamily

Char:

System, TypeCode

CharacterSet:

HttpWebResponse

CharEnumerator:

System

Chars:

String, StringBuilder

CharSet:

DllImportAttribute, StructLayoutAttribute, System.Runtime.InteropServices

CharSize:

UnicodeEncoding

CheckAccessOnOverride:

MethodAttributes

CheckCertificateRevocationList:

ServicePointManager

CheckHostName():

Uri

CheckSchemeName():

Uri

CheckSecurity():

Uri

ChecksumCoverage:

SocketOptionName

CheckTypeSecurity():

FormatterServices

CheckValidationResult():

ICertificatePolicy

ChildNodes:

XmlNode

Ckfinite:

OpCodes

Class:

AttributeTargets, TypeAttributes

ClassesRoot:

Registry, RegistryHive

ClassImpl:

ParameterInfo

ClassInterfaceAttribute:

System.Runtime.InteropServices

ClassInterfaceType:

System.Runtime.InteropServices

ClassName:

MissingMemberException

ClassSemanticsMask:

TypeAttributes

Clear():

Array, ArrayList, CollectionBase, DictionaryBase, EventLog, Hashtable, HybridDictionary, IDictionary, IList, ListDictionary, NameValueCollection, Queue, SortedList, Stack, StringCollection, StringDictionary, TraceListenerCollection, XsltArgumentList

ClearCache:

GC

ClearCachedData():

CultureInfo

ClearPrivatePath():

AppDomain

ClearShadowCopyPath():

AppDomain

ClientCertificate:

ServicePoint

ClientCertificates:

HttpWebRequest

Clone:

StreamingContextStates

Clone():

Array, ArrayList, AssemblyName, BitArray, CharEnumerator, CultureInfo, DateTimeFormatInfo, Delegate, Hashtable, ICloneable, NumberFormatInfo, OperatingSystem, Queue, SortedList, Stack, String, Version, XmlNode, XPathExpression, XPathNavigator, XPathNodeIterator

CloneNode():

XmlAttribute, XmlCDataSection, XmlComment, XmlDataDocument, XmlDeclaration, XmlDocument, XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference, XmlNode, XmlNotation, XmlProcessingInstruction, XmlSignificantWhitespace, XmlText, XmlWhitespace

Close():

BinaryReader, BinaryWriter, BufferedStream, Debug, EventLog, EventLogTraceListener, FileStream, FileWebResponse, HttpWebResponse, IsolatedStorageFile, IsolatedStorageFileStream, MemoryStream, NetworkStream, PerformanceCounter, Process, RegistryKey, Socket, Stream, StreamReader, StreamWriter, StringReader, StringWriter, TcpClient, TextReader, TextWriter, TextWriterTraceListener, Timer, Trace, TraceListener, UdpClient, WaitHandle, WebResponse, XmlNodeReader, XmlReader, XmlTextReader, XmlTextWriter, XmlValidatingReader, XmlWriter

Closed:

ReadState, WriteState

CloseMainWindow():

Process

ClosePunctuation:

UnicodeCategory

CloseSharedResources():

PerformanceCounter

CLSCompliantAttribute:

System

Clt:

OpCodes

Clt_Un:

OpCodes

Cluster:

AddressFamily, ProtocolFamily

CoClass:

CoClassAttribute

CoClassAttribute:

System.Runtime.InteropServices

CodeBase:

Assembly, AssemblyBuilder, AssemblyName

CodePage:

Encoding

CodeTypeMask:

MethodImplAttributes

Collect():

GC

CollectionBase:

System.Collections

CollectionsUtil:

System.Collections.Specialized

Color:

UserPreferenceCategory

ComAliasNameAttribute:

System.Runtime.InteropServices

Combine():

Delegate, Path

CombineImpl():

Delegate, MulticastDelegate

ComCompatibleVersionAttribute:

System.Runtime.InteropServices

ComConversionLossAttribute:

System.Runtime.InteropServices

COMException:

System.Runtime.InteropServices

ComImportAttribute:

System.Runtime.InteropServices

ComInterfaceType:

System.Runtime.InteropServices

CommandLine:

Environment

ComMemberType:

System.Runtime.InteropServices

Comment:

Cookie, XmlNodeType, XPathNodeType

Comments:

FileVersionInfo

CommentUri:

Cookie

CommonApplicationData:

SpecialFolder

CommonProgramFiles:

SpecialFolder

Company:

AssemblyCompanyAttribute

CompanyName:

FileVersionInfo

Compare():

CaseInsensitiveComparer, CompareInfo, Comparer, DateTime, Decimal, IComparer, SortKey, String, TimeSpan

CompareDocument():

XsltContext

CompareExchange():

Interlocked

CompareInfo:

CultureInfo, System.Globalization

CompareOptions:

System.Globalization

CompareOrdinal():

String

ComparePosition():

XPathNavigator

Comparer:

System.Collections

CompareTo():

Boolean, Byte, Char, DateTime, Decimal, Double, Enum, Guid, IComparable, Int16, Int32, Int64, SByte, Single, String, TimeSpan, UInt16, UInt32, UInt64, Version

CompatibleImpl:

IDispatchImplType

Compile():

XPathNavigator

Compiled:

RegexOptions

CompileToAssembly():

Regex

Complete:

Authorization

CompletedSynchronously:

IAsyncResult

Compressed:

FileAttributes

CompressedStack:

System.Threading

ComputeCounterValue():

CounterSampleCalculator

ComRegisterFunctionAttribute:

System.Runtime.InteropServices

ComSourceInterfacesAttribute:

System.Runtime.InteropServices

ComUnregisterFunctionAttribute:

System.Runtime.InteropServices

ComVisibleAttribute:

System.Runtime.InteropServices

Concat():

String

Cond_Branch:

FlowControl

ConditionalAttribute:

System.Diagnostics

ConditionString:

ConditionalAttribute

Configuration:

AssemblyConfigurationAttribute

ConfigurationFile:

AppDomainSetup

Conflict:

HttpStatusCode

Connect:

NetworkAccess, WebPermissionAttribute

Connect():

Socket, TcpClient, UdpClient

Connected:

Socket

ConnectFailure:

WebExceptionStatus

Connection:

HttpWebRequest

ConnectionClosed:

WebExceptionStatus

ConnectionGroupId:

Authorization

ConnectionGroupName:

FileWebRequest, HttpWebRequest, WebRequest

Connectionless:

TransportType

ConnectionLimit:

ServicePoint

ConnectionName:

ServicePoint

ConnectionOriented:

TransportType

ConnectList:

SocketPermission, WebPermission

ConnectorPunctuation:

UnicodeCategory

ConnectPattern:

WebPermissionAttribute

Console:

System

ConsoleApplication:

PEFileKinds

Constructor:

AttributeTargets, MemberTypes

ConstructorBuilder:

System.Reflection.Emit

ConstructorInfo:

System.Reflection

ConstructorName:

ConstructorInfo

ContainedInAnotherAssembly:

ResourceLocation

ContainedInManifestFile:

ResourceLocation

Contains():

ArrayList, CounterCreationDataCollection, EventLogPermissionEntryCollection, Hashtable, HybridDictionary, IDictionary, IList, InstanceDataCollection, InstanceDataCollectionCollection, ListDictionary, PerformanceCounterPermissionEntryCollection, ProcessModuleCollection, ProcessThreadCollection, Queue, SortedList, Stack, StringCollection, TraceListenerCollection

ContainsKey():

Hashtable, SortedList, StringDictionary

ContainsValue():

Hashtable, SortedList, StringDictionary

Content:

WriteState

ContentEncoding:

HttpWebResponse

ContentLength:

FileWebRequest, FileWebResponse, HttpWebRequest, HttpWebResponse, WebRequest, WebResponse

ContentType:

FileWebRequest, FileWebResponse, HttpWebRequest, HttpWebResponse, WebRequest, WebResponse

Context:

Formatter, IFormatter, StreamingContext

ContextBoundObject:

System

ContextMarshalException:

System

ContextStaticAttribute:

System

Continue:

HttpStatusCode

ContinueDelegate:

HttpRequest

Control:

UnicodeCategory

Conv_1:

OpCodes

Conv_11:

OpCodes

Conv_12:

OpCodes

Conv_14:

OpCodes

Conv_18:

OpCodes

Conv_Ovf_1:

OpCodes

Conv_Ovf_1_Un:

OpCodes

Conv_Ovf_11:

OpCodes

Conv_Ovf_11_Un:

OpCodes

Conv_Ovf_12:

OpCodes

Conv_Ovf_12_Un:

OpCodes

Conv_Ovf_14:

OpCodes

Conv_Ovf_14_Un:

OpCodes

Conv_Ovf_18:

OpCodes

Conv_Ovf_18_Un:

OpCodes

Conv_Ovf_U:

OpCodes

Conv_Ovf_U_Un:

OpCodes
Conv_Ovf_U1:

OpCodes
Conv_Ovf_U1_Un:

OpCodes
Conv_Ovf_U2:

OpCodes
Conv_Ovf_U2_Un:

OpCodes
Conv_Ovf_U4:

OpCodes
Conv_Ovf_U4_Un:

OpCodes
Conv_Ovf_U8:

OpCodes
Conv_Ovf_U8_Un:

OpCodes
Conv_R_Un:

OpCodes
Conv_R4:

OpCodes
Conv_R8:

OpCodes
Conv_U:

OpCodes
Conv_U1:

OpCodes
Conv_U2:

OpCodes
Conv_U4:

OpCodes
Conv_U8:

OpCodes
Convert:

System
Convert():

Encoding, FormatterConverter, IFormatterConverter

Cookie:

System.Net

CookieCollection:

System.Net

CookieContainer:

HttpRequest, System.Net

CookieException:

System.Net

Cookies:

HttpResponse, SpecialFolder

Copy():

Array, DnsPermission, File, Marshal, SocketPermission, String, WebPermission

CopyFromComponent():

EventLogInstaller, PerformanceCounterInstaller

Copyright:

AssemblyCopyrightAttribute

CopyTo():

Array, ArrayList, BitArray, CaptureCollection, CookieCollection, CounterCreationDataCollection, DictionaryBase, EventLogEntryCollection, EventLogPermissionEntryCollection, FileInfo, GroupCollection, Hashtable, HybridDictionary, ICollection, InstanceDataCollection, InstanceDataCollectionCollection, ListDictionary, MatchCollection, NameValueCollection, PerformanceCounterPermissionEntryCollection, ProcessModuleCollection, ProcessThreadCollection, Queue, SortedList, Stack, String, StringCollection, StringDictionary, TraceListenerCollection, XmlAttributeCollection

CoreNewLine:

TextWriter

Cos():

Math

Cosh():

Math

Count:

ArrayList, BitArray, CaptureCollection, CollectionBase, CookieCollection, CookieContainer, DictionaryBase, EventLogEntryCollection, GroupCollection, Hashtable, HybridDictionary, ICollection, KeysCollection, ListDictionary, MatchCollection, NameObjectCollectionBase, Queue, ReadOnlyCollectionBase, SortedList, Stack, StringCollection, StringDictionary, TraceListenerCollection, XmlNamedNodeMap, XmlNodeList, XPathNodeIterator

CounterCreationData:

System.Diagnostics

CounterCreationDataCollection:

System.Diagnostics

CounterDelta32:

PerformanceCounterType

CounterDelta64:

PerformanceCounterType

CounterExists():

PerformanceCounterCategory

CounterFrequency:

CounterSample

CounterHelp:

CounterCreationData, PerformanceCounter

CounterMultiBase:

PerformanceCounterType

CounterMultiTimer:

PerformanceCounterType

CounterMultiTimer100Ns:

PerformanceCounterType

CounterMultiTimer100NsInverse:

PerformanceCounterType

CounterMultiTimerInverse:

PerformanceCounterType

CounterName:

CounterCreationData, InstanceDataCollection, PerformanceCounter

Counters:

PerformanceCounterInstaller

CounterSample:

System.Diagnostics

CounterSampleCalculator:

System.Diagnostics

CounterTimer:

PerformanceCounterType

CounterTimerInverse:

PerformanceCounterType

CounterTimeStamp:

CounterSample

CounterType:

CounterCreationData, CounterSample, PerformanceCounter
CountPerTimeInterval32:

PerformanceCounterType
CountPerTimeInterval64:

PerformanceCounterType
Cpblk:

OpCodes
Cpobj:

OpCodes
Create:

FileMode
Create():

DirectoryInfo, EndPoint, File, FileInfo, IPEndPoint, IWebRequestCreate,
PerformanceCounterCategory, WebRequest
CreateAttribute():

XmlDocument
CreateCaseInsensitiveHashtable():

CollectionsUtil
CreateCaseInsensitiveSortedList():

CollectionsUtil
CreateCDATASection():

XmlDocument
CreateComInstanceFrom():

Activator, AppDomain
CreateComment():

XmlDocument
Created:

FileSystemWatcher, HttpStatusCode, WatcherChangeTypes
CreateDefault():

WebRequest
CreateDelegate():

Delegate
CreateDirectory():

Directory, IsolatedStorageFile
CreateDocument():

XmlImplementation
CreateDocumentFragment():

XmlDocument

CreateDocumentType():

XmlDocument

CreateDomain():

AppDomain

CreateElement():

XmlDataDocument, XmlDocument

CreateEntityReference():

XmlDataDocument, XmlDocument

CreateEventSource():

EventLog

CreateEvidenceForUrl():

XmlSecureResolver

CreateGlobalFunctions():

ModuleBuilder

CreateInstance:

BindingFlags

CreateInstance():

Activator, AppDomain, Array, Assembly

CreateInstanceAndUnwrap():

AppDomain

CreateInstanceFrom():

Activator, AppDomain

CreateInstanceFromAndUnwrap():

AppDomain

CreateMask():

BitVector32

CreateMethodBody():

MethodBuilder

CreateNavigator():

IXPathNavigable, XmlDataDocument, XmlNode, XPathDocument

CreateNew:

FileMode

CreateNode():

XmlDocument

CreateNoWindow:

ProcessStartInfo

CreateObjRef():

MarshalByRefObject

CreatePermission():

DnsPermissionAttribute, EventLogPermissionAttribute, PerformanceCounterPermissionAttribute,
SocketPermissionAttribute, WebPermissionAttribute

CreateProcessingInstruction():

XmlDocument

CreateQualifiedName():

Assembly

CreateSection():

BitVector32

CreateSignificantWhitespace():

XmlDocument

CreateSpecificCulture():

CultureInfo

CreateSubdirectory():

DirectoryInfo

CreateSubKey():

RegistryKey

CreateText():

File, FileInfo

CreateTextNode():

XmlDocument

CreateTimer():

SystemEvents

CreateType():

EnumBuilder, TypeBuilder

CreateWaitHandle():

Stream

CreateWhitespace():

XmlDocument

CreateWrapperOfType():

Marshal

CreateXmlDeclaration():

XmlDocument

CreationTime:

FileSystemInfo, NotifyFilters

CreationTimeUtc:

FileSystemInfo

CredentialCache:

System.Net

Credentials:

FileWebRequest, HttpWebRequest, IWebProxy, WebClient, WebProxy, WebRequest,
XmlResolver, XmlSecureResolver, XmlUrlResolver

CrossAppDomain:

StreamingContextStates

CrossAppDomainDelegate:

System

CrossMachine:

StreamingContextStates

CrossProcess:

StreamingContextStates

Culture:

AssemblyCultureAttribute

CultureInfo:

AssemblyName, System.Globalization

CultureInvariant:

RegexOptions

CultureTypes:

System.Globalization

Currency:

NumberStyles, UnmanagedType

CurrencyDecimalDigits:

NumberFormatInfo

CurrencyDecimalSeparator:

NumberFormatInfo

CurrencyGroupSeparator:

NumberFormatInfo

CurrencyGroupSizes:

NumberFormatInfo

CurrencyNegativePattern:

NumberFormatInfo

CurrencyPositivePattern:

NumberFormatInfo

CurrencySymbol:

NumberFormatInfo, RegionInfo, UnicodeCategory

CurrencyWrapper:

System.Runtime.InteropServices

Current:

CharEnumerator, IEnumerator, SeekOrigin, SerializationInfoEnumerator, StringEnumerator, TextElementEnumerator, XPathNodeIterator

CurrentConfig:

Registry, RegistryHive

CurrentConnections:

ServicePoint

CurrentContext:

Thread

CurrentCulture:

CultureInfo, Thread

CurrentDirectory:

Environment

CurrentDomain:

AppDomain

CurrentEncoding:

StreamReader

CurrentEra:

Calendar

CurrentInfo:

DateTimeFormatInfo, NumberFormatInfo

CurrentPosition:

XPathNodeIterator

CurrentPrincipal:

Thread

CurrentPriority:

ProcessThread

CurrentRegion:

RegionInfo

CurrentSize:

IsolatedStorage, IsolatedStorageFile

CurrentThread:

Thread

CurrentTimeZone:

TimeZone

CurrentUICulture:

CultureInfo, Thread

CurrentUser:

Registry, RegistryHive

Custom:

MemberTypes

CustomAttributeBuilder:

System.Reflection.Emit

CustomAttributeFormatException:

System.Reflection

CustomMarshaler:

UnmanagedType

DashPunctuation:

UnicodeCategory

Data:

BitVector32, EventLogEntry, XmlCharacterData, XmlProcessingInstruction

DataAvailable:

NetworkStream

DataKit:

AddressFamily, ProtocolFamily

DataLink:

AddressFamily, ProtocolFamily

DataSet:

XmlDataDocument

Date:

DateTime

DateSeparator:

DateTimeFormatInfo

DateTime:

System, TypeCode

DateTimeFormat:

CultureInfo

DateTimeFormatInfo:

System.Globalization

DateTimeStyles:

System.Globalization

Day:

DateTime

DaylightName:

TimeZone

DaylightTime:

System.Globalization

DayNames:

DateTimeFormatInfo

DayOfWeek:

DateTime, System

DayOfYear:

DateTime

Days:

TimeSpan

DaysInMonth():

DateTime

DBNull:

Convert, System, TypeCode

Debug:

SocketOptionName, System.Diagnostics

DebuggableAttribute:

System.Diagnostics

Debugger:

System.Diagnostics

DebuggerHiddenAttribute:

System.Diagnostics

DebuggerStepThroughAttribute:

System.Diagnostics

Decimal:

System, TypeCode

DecimalDigitNumber:

UnicodeCategory

DeclaredOnly:

BindingFlags

DeclareLocal():

ILGenerator

DeclaringType:

ConstructorBuilder, EnumBuilder, FieldBuilder, MemberInfo, MethodBuilder, PropertyBuilder,
Type, TypeBuilder

DecNet:

AddressFamily, ProtocolFamily

DecodeName():

XmlConvert

Decoder:

System.Text

Decrement():

Interlocked, PerformanceCounter

Default:

BindingFlags, CaseInsensitiveComparer, CaseInsensitiveHashCodeProvider, Comparer,
Encoding, XmlSpace

DefaultAlias:

AssemblyDefaultAliasAttribute

DefaultBinder:

Type

DefaultCategory:

Debugger

DefaultConnectionLimit:

ServicePointManager

DefaultCookieLengthLimit:

CookieContainer

DefaultCookieLimit:

CookieContainer

DefaultCredentials:

CredentialCache

DefaultFileMappingSize:

PerformanceCounter

DefaultInvariant:

CaseInsensitiveComparer, CaseInsensitiveHashCodeProvider, Comparer

DefaultMaximumResponseHeadersLength:

HttpWebRequest

DefaultMemberAttribute:

System.Reflection

DefaultNamespace:

XmlNamespaceManager

DefaultNonPersistentConnectionLimit:

ServicePointManager

DefaultPerDomainCookieLimit:

CookieContainer

DefaultPersistentConnectionLimit:

ServicePointManager

DefaultTraceListener:

System.Diagnostics

DefaultValue:

ParameterInfo

DefaultValueImpl:

ParameterInfo

DefineByValArray():

UnmanagedMarshal

DefineByValTStr():

UnmanagedMarshal

DefineConstructor():

TypeBuilder

DefineDefaultConstructor():

TypeBuilder

DefineDocument():

ModuleBuilder

DefineDynamicAssembly():

AppDomain

DefineDynamicModule():

AssemblyBuilder

DefineEnum():

ModuleBuilder

DefineEvent():

TypeBuilder

DefineField():

TypeBuilder

DefineGlobalMethod():

ModuleBuilder

DefineInitializedData():

ModuleBuilder, TypeBuilder

DefineLabel():

ILGenerator

DefineLiteral():

EnumBuilder

DefineLPArray():

UnmanagedMarshal

DefineMethod():

TypeBuilder

DefineMethodOverride():

TypeBuilder

DefineNestedType():

TypeBuilder

DefineParameter():

ConstructorBuilder, MethodBuilder

DefinePInvokeMethod():

ModuleBuilder, TypeBuilder

DefineProperty():

TypeBuilder

DefineResource():

AssemblyBuilder, ModuleBuilder

DefineSafeArray():

UnmanagedMarshal

DefineType():

ModuleBuilder

DefineTypeInitializer():

TypeBuilder

DefineUninitializedData():

ModuleBuilder, TypeBuilder

DefineUnmanagedMarshal():

UnmanagedMarshal

DefineUnmanagedResource():

AssemblyBuilder, ModuleBuilder

DefineVersionInfoResource():

AssemblyBuilder

DelaySign:

AssemblyDelaySignAttribute

Delegate:

AttributeTargets, System

Delete():

Directory, DirectoryInfo, EventLog, File, FileInfo, FileSystemInfo, PerformanceCounterCategory

Deleted:

FileSystemWatcher, WatcherChangeTypes

DeleteData():

XmlCharacterData

DeleteDirectory():

IsolatedStorageFile

DeleteEventSource():

EventLog

DeleteFile():

IsolatedStorageFile

DeleteSubKey():

RegistryKey

DeleteSubKeyTree():

RegistryKey

DeleteValue():

RegistryKey

Delimiter:

Type

Delta:

DaylightTime

Depth:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

Dequeue():

Queue

Descending:

XmlSortOrder

Description:

AssemblyDescriptionAttribute, IODescriptionAttribute, MonitoringDescriptionAttribute, Switch, TimersDescriptionAttribute

Deserialize():

Formatter, IFormatter

Desktop:

SpecialFolder, UserPreferenceCategory

DesktopDirectory:

SpecialFolder

DestroyStructure():

Marshal

Detail:

SoapFault

Device:

FileAttributes

Dgram:

SocketType

DictionaryBase:

System.Collections

DictionaryEntry:

System.Collections

Directory:

FileAttributes, FileInfo, System.IO

DirectoryInfo:

System.IO

DirectoryName:

FileInfo, NotifyFilters

DirectoryNotFoundException:

System.IO

DirectorySeparatorChar:

Path

DisallowBindingRedirects:

AppDomainSetup

DisallowBindings:

LoaderOptimization

DisallowCodeDownload:

AppDomainSetup

DisallowPublisherPolicy:

AppDomainSetup

Discard:

Cookie

DiscardBufferedData():

StreamReader

DispatchWrapper:

System.Runtime.InteropServices

DispldAttribute:

System.Runtime.InteropServices

DisplayName:

CultureInfo, RegionInfo, Switch

DisplaySettingsChanged:

SystemEvents

Dispose():

BinaryReader, BinaryWriter, EventLog, EventLogTraceListener, FileStream, FileSystemWatcher, FileWebResponse, HttpWebResponse, IDisposable, IsolatedStorageFile, IsolatedStorageFileStream, NetworkStream, PerformanceCounter, Process, Socket, StreamReader, StreamWriter, StringReader, StringWriter, TcpClient, TextReader, TextWriter, TextWriterTraceListener, Timer, TraceListener, WaitHandle

Div:

OpCodes

Div_Un:

OpCodes

Divide():

Decimal

DivideByZeroException:

System

DivRem():

Math

Dll:

PEFileKinds

DllImportAttribute:

System.Runtime.InteropServices

DllNotFoundException:

System

Dns:

System.Net, UriHostNameType

DnsPermission:

System.Net

DnsPermissionAttribute:

System.Net

DoCallBack():

AppDomain

DocTypeName:

XmlParserContext

Document:

XmlNodeType

DocumentElement:

XmlDocument

DocumentFragment:

XmlNodeType

DocumentType:

XmlDocument, XmlNodeType

DoFixups():

ObjectManager

Domain:

Cookie, IsolatedStorageScope, NetworkCredential

DomainIdentity:

IsolatedStorage

DomainMask:

LoaderOptimization

DomainUnload:

AppDomain

DontFragment:

SocketOptionName

DontLinger:

SocketOptionName

DontRoute:

SocketFlags, SocketOptionName

Double:

System, TypeCode

DoubleToInt64Bits():

BitConverter

DowngradeFromWriterLock():

ReaderWriterLock

DownloadData():

WebClient

DownloadFile():

WebClient

DropMembership:

SocketOptionName

DropMulticastGroup():

UdpClient

DropSourceMembership:

SocketOptionName

DTD:

ValidationType

Dup:

OpCodes

DuplicateWaitObjectException:

System

Duration():

TimeSpan

DynamicBase:

AppDomainSetup

DynamicDirectory:

AppDomain

DynamicInvoke():

Delegate

DynamicInvokeImpl():

Delegate, MulticastDelegate

DynData:

Registry, RegistryHive

[\[Team LIB \]](#)

◀ PREVIOUS NEXT ▶

E-I

E:

Math

EBCDICCodePage:

TextInfo

Ecma:

AddressFamily, ProtocolFamily

ECMAScript:

RegexOptions

Elapsed:

Timer

ElapsedEventArgs:

System.Timers

ElapsedEventHandler:

System.Timers

ElapsedTime:

PerformanceCounterType

Element:

WriteState, XmlNodeType, XPathNodeType

ElementCount:

UnmanagedMarshal

ElementIndex:

TextElementEnumerator

Embedded:

ResourceLocation

Emit():

ILGenerator

EmitCall():

ILGenerator

EmitCalli():

ILGenerator

EmitWriteLine():

ILGenerator

Empty:

CounterSample, EventArgs, EventToken, FieldToken, Guid, Match, MethodToken, ParameterToken, PropertyToken, SignatureToken, String, TypeCode, TypeToken, XmlQualifiedName

EmptyTypes:

Type

Enabled:

BooleanSwitch, LingerOption, Timer

EnableRaisingEvents:

EventLog, FileSystemWatcher, Process

EnclosingMark:

UnicodeCategory

EncodeLocalName():

XmlConvert

EncodeName():

XmlConvert

EncodeNmToken():

XmlConvert

Encoder:

System.Text

Encoding:

StreamWriter, StringWriter, System.Text, TextWriter, XmlDeclaration, XmlParserContext, XmlTextReader, XmlValidatingReader

EncodingName:

Encoding

Encrypted:

FileAttributes

End:

DaylightTime, SeekOrigin

End():

ArgIterator

EndAccept():

Socket

EndConnect():

Socket

EndElement:

XmlNodeType

EndEntity:

XmlNodeType

EndExceptionBlock():

ILGenerator

Endfilter:

OpCodes

Endfinally:

OpCodes

EndGetHostByName():

Dns

EndGetRequestStream():

FileWebRequest, HttpWebRequest, WebRequest

EndGetResponse():

FileWebRequest, HttpWebRequest, WebRequest

EndInit():

EventLog, FileSystemWatcher, PerformanceCounter, Timer

EndInvoke():

AssemblyLoadEventHandler, AsyncCallback, CrossAppDomainDelegate, ElapsedEventHandler, EntryWrittenEventHandler, ErrorEventHandler, EventHandler, FileSystemEventHandler, HttpContinueDelegate, IOCompletionCallback, MatchEvaluator, MemberFilter, ModuleResolveEventHandler, ObjectCreationDelegate, PowerModeChangedEventHandler, RenamedEventHandler, ResolveEventHandler, SessionEndedEventHandler, SessionEndingEventHandler, ThreadExceptionHandler, ThreadStart, TimerCallback, TimerElapsedEventHandler, TypeFilter, UnhandledExceptionEventHandler, UserPreferenceChangedEventHandler, UserPreferenceChangingEventHandler, WaitCallback, WaitOrTimerCallback, XmlNodeChangedEventHandler

EndOfFile:

ReadState

EndOfStreamException:

System.IO

EndPoint:

System.Net

EndpointPermission:

System.Net

EndRead():

FileStream, IsolatedStorageFileStream, NetworkStream, Stream

EndReceive():

Socket

EndReceiveFrom():

Socket

EndResolve():

Dns

EndScope():

ILGenerator

EndSend():

Socket

EndSendTo():

Socket

EndsWith():

String

EndWrite():

FileStream, IsolatedStorageFileStream, NetworkStream, Stream

EnglishName:

CultureInfo, RegionInfo

Enqueue():

Queue

EnsureCapacity():

StringBuilder

Enter():

Monitor

EnterDebugMode():

Process

Entities:

XmlDocumentType

ENTITIES:

XmlTokenizedType

Entity:

XmlNodeType

ENTITY:

XmlTokenizedType

EntityHandling:

System.Xml, XmlValidatingReader

EntityReference:

XmlNodeType

Entries:

EventLog

Entry:

EntryWrittenEventArgs, IDictionaryEnumerator

EntryPoint:

Assembly, AssemblyBuilder, DllImportAttribute

EntryPointAddress:

ProcessModule

EntryPointNotFoundException:

System

EntryType:

EventLogEntry

EntryWritten:

EventLog

EntryWrittenEventArgs:

System.Diagnostics

EntryWrittenEventHandler:

System.Diagnostics

Enum:

AttributeTargets, System

EnumBuilder:

System.Reflection.Emit

ENUMERATION:

XmlTokenizedType

Environment:

System

EnvironmentVariables:

ProcessStartInfo

EOF:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

Epsilon:

Double, Single

Equals():

ArgIterator, ArrayWithOffset, Attribute, BitVector32, Boolean, Byte, Char, CompareInfo, Cookie, CultureInfo, DateTime, Decimal, Delegate, Double, Encoding, EndpointPermission, Enum, EventLogEntry, EventToken, FieldToken, Guid, Int16, Int32, Int64, IntPtr, IPAddress, IPEndPoint, Label, MethodBuilder, MethodToken, MulticastDelegate, Object, OpCode,

ParameterToken, PropertyToken, RegionInfo, SByte, Section, SignatureHelper, SignatureToken, Single, SocketAddress, SortKey, StreamingContext, String, StringBuilder, StringToken, TextInfo, TimeSpan, Type, TypeToken, UInt16, UInt32, UInt64, UIntPtr, UnicodeEncoding, Uri, UriBuilder, UTF8Encoding, ValueType, Version, XmlQualifiedName

Eras:

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

Error:

Console, EventLogEntryType, FileSystemWatcher, ReadState, SocketOptionName, TraceLevel, UnmanagedType, XPathResultType

ErrorCode:

ErrorWrapper, ExternalException, SocketException

ErrorDialog:

ProcessStartInfo

ErrorDialogParentHandle:

ProcessStartInfo

ErrorEventArgs:

System.IO

ErrorEventHandler:

System.IO

ErrorWrapper:

System.Runtime.InteropServices

Escape():

Regex, Uri

EscapedCodeBase:

Assembly, AssemblyName

EscapeString():

Uri

Evaluate():

IXsltContextVariable, XPathNavigator

Event:

AttributeTargets, MemberTypes

EventArgs:

System

EventArgs:

System.Reflection

EventBuilder:

System.Reflection.Emit

EventHandle:

NativeOverlapped, Overlapped

EventHandler:

System

EventHandlerType:

EventInfo

EventID:

EventLogEntry

EventInfo:

System.Reflection

EventLog:

EventLogTraceListener, System.Diagnostics

EventLogEntry:

System.Diagnostics

EventLogEntryCollection:

System.Diagnostics

EventLogEntryType:

System.Diagnostics

EventLogInstaller:

System.Diagnostics

EventLogPermission:

System.Diagnostics

EventLogPermissionAccess:

System.Diagnostics

EventLogPermissionAttribute:

System.Diagnostics

EventLogPermissionEntry:

System.Diagnostics

EventLogPermissionEntryCollection:

System.Diagnostics

EventLogTraceListener:

System.Diagnostics

EventPairHigh:

ThreadWaitReason

EventPairLow:

ThreadWaitReason

EventsThreadShutdown:

SystemEvents

EventToken:

System.Reflection.Emit

Evidence:

AppDomain, Assembly

ExactBinding:

BindingFlags

ExactSpelling:

DllImportAttribute

Exception:

System, ThreadExceptionEventArgs

ExceptionMessage:

ServerFault

ExceptionObject:

UnhandledExceptionEventArgs

ExceptionState:

ThreadAbortException

ExceptionType:

ServerFault

Exchange():

Interlocked

ExcludeXml:

XPathNamespaceScope

ExclusiveAddressUse:

SocketOptionName

ExecuteAssembly():

AppDomain

ExecutionDelay:

ThreadWaitReason

ExecutionEngineException:

System

Executive:

ThreadWaitReason

Exists:

DirectoryInfo, FileInfo, FileSystemInfo

Exists():

Directory, EventLog, File, PerformanceCounterCategory

Exit():

Environment, Monitor

ExitCode:

Environment, Process

Exited:

Process

ExitTime:

Process

Exp():

Math

ExpandCharEntities:

EntityHandling

ExpandEntities:

EntityHandling

ExpandEnvironmentVariables():

Environment

Expect:

HttpRequest

Expect100Continue:

ServicePoint, ServicePointManager

ExpectationFailed:

HttpStatusCode

Expedited:

SocketOptionName

Expired:

Cookie

Expires:

Cookie

Explicit:

LayoutKind

ExplicitCapture:

RegexOptions

ExplicitLayout:

TypeAttributes

ExplicitThis:

CallingConventions

Expression:

XPathExpression

ExtensibleClassFactory:

System.Runtime.InteropServices

Extension:

FileSystemInfo

ExternalException:

System.Runtime.InteropServices

Fail():

Debug, DefaultTraceListener, Trace, TraceListener

FailureAudit:

EventLogEntryType

FalseString:

Boolean

FamANDAssem:

FieldAttributes, MethodAttributes

Family:

FieldAttributes, MethodAttributes, SocketAddress

FamORAssem:

FieldAttributes, MethodAttributes

FastCall:

CallingConvention

FaultActor:

SoapFault

FaultCode:

SoapFault

FaultString:

SoapFault

Favorites:

SpecialFolder

Field:

AttributeTargets, MemberTypes

FieldAccessException:

System

FieldAccessMask:

FieldAttributes

FieldAttributes:

System.Reflection

FieldBuilder:

System.Reflection.Emit

FieldHandle:

FieldBuilder, FieldInfo

FieldInfo:

System.Reflection

FieldNames:

IFieldInfo

FieldOffsetAttribute:

System.Runtime.InteropServices

FieldToken:

System.Reflection.Emit

FieldType:

FieldBuilder, FieldInfo

FieldTypes:

IFieldInfo

File:

StreamingContextStates, System.IO

FileAccess:

System.IO

FileAttributes:

System.IO

FileBuildPart:

FileVersionInfo

FileDescription:

FileVersionInfo

FileInfo:

System.IO

FileLoadException:

System.IO

FileMajorPart:

FileVersionInfo

FileMinorPart:

FileVersionInfo

FileMode:

System.IO

FileName:

BadImageFormatException, FileLoadException, FileNotFoundException, FileVersionInfo,
ManifestResourceInfo, NotifyFilters, ProcessModule, ProcessStartInfo

FileNotFoundException:

System.IO

FilePrivatePart:

FileVersionInfo

FileShare:

System.IO

FileStream:

System.IO

FileSystemEventArgs:

System.IO

FileSystemEventHandler:

System.IO

FileSystemInfo:

System.IO

FileSystemWatcher:

System.IO

FileVersion:

FileVersionInfo

FileVersionInfo:

ProcessModule, System.Diagnostics

FileWebRequest:

System.Net

FileWebResponse:

System.Net

FillBuffer():

BinaryReader

Filter:

FileSystemWatcher

FilterAttribute:

Type

FilterName:

Type

FilterNameIgnoreCase:

Type

FilterTypeName:

Module

FilterTypeNameIgnoreCase:

Module

Final:

MethodAttributes

Finalize():

CompressedStack, FileStream, IsolatedStorageFile, LocalDataStoreSlot, NetworkStream, Object, Regex, RegisteredWaitHandle, RegistryKey, Socket, StreamWriter, TcpClient, TcpListener, Thread, Timer, WaitHandle, WeakReference

FinalQuotePunctuation:

UnicodeCategory

FindInterfaces():

Type

FindMembers():

Type

FindServicePoint():

ServicePointManager

FindTypes():

Module

FireFox:

AddressFamily, ProtocolFamily

FirstChild:

XmlNode

FirstDay:

CalendarWeekRule

FirstDayOfWeek:

DateTimeFormatInfo

FirstFourDayWeek:

CalendarWeekRule

FirstFullWeek:

CalendarWeekRule

FixedSize():

ArrayList

Flags:

AssemblyFlagsAttribute, AssemblyName

FlagsAttribute:

System

FlattenHierarchy:

BindingFlags

Float:

NumberStyles

Floor():

Decimal, Math

FlowControl:

OpCode, System.Reflection.Emit

Flush():

BinaryWriter, BufferedStream, Debug, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream, RegistryKey, Stream, StreamWriter, TextWriter, TextWriterTraceListener, Trace, TraceListener, XmlTextWriter, XmlWriter

Forbidden:

HttpStatusCode

Format:

UnicodeCategory

Format():

Enum, ICustomFormatter, String

FormatException:

System

FormatProvider:

TextWriter

Formatter:

System.Runtime.Serialization

FormatterAssemblyStyle:

System.Runtime.Serialization.Formatters

FormatterConverter:

System.Runtime.Serialization

FormatterServices:

System.Runtime.Serialization

FormatterTypeStyle:

System.Runtime.Serialization.Formatter

Formatting:

System.Xml, XmlTextWriter

ForwardRef:

MethodImplAttributes

Found:

HttpStatusCode

Fragment:

Uri, UriBuilder

FrameCount:

StackTrace

Free():

GCHandle, Overlapped

FreeBSTR():

Marshal

FreeCoTaskMem():

Marshal

FreeHGlobal():

Marshal

FreeNamedDataSlot():

Thread

FreePage:

ThreadWaitReason

Friday:

DayOfWeek

FriendlyName:

AppDomain

FromBase64CharArray():

Convert

FromBase64String():

Convert

FromDays():

TimeSpan

FromFileTime():

DateTime

FromFileTimeUtc():

DateTime

FromGlobalAccessCache():

RuntimeEnvironment

FromHex():

Uri

FromHours():

TimeSpan

FromMilliseconds():

TimeSpan

FromMinutes():

TimeSpan

FromOACurrency():

Decimal

FromOADate():

DateTime

FromSeconds():

TimeSpan

FromTicks():

TimeSpan

FromXml():

DnsPermission, SocketPermission, WebPermission

Full:

FormatterAssemblyStyle, TypeFilterLevel

FullDateTimePattern:

DateTimeFormatInfo

FullName:

Assembly, AssemblyName, EnumBuilder, FileSystemInfo, Type, TypeBuilder, TypeDelegator

FullPath:

FileSystemEventArgs, FileSystemInfo

FullTypeName:

SerializationInfo

FullyQualifiedName:

Module, ModuleBuilder

FunctionPtr:

UnmanagedType

FusionLog:

BadImageFormatException, FileLoadException, FileNotFoundException

GatewayTimeout:

HttpStatusCode

GC:

System

GCHandle:

System.Runtime.InteropServices

GCHandleType:

System.Runtime.InteropServices

General:

UserPreferenceCategory

GenerateGuidForType():

Marshal

GenerateProgIdForType():

Marshal

Get():

BitArray, KeysCollection, NameTable, NameValueCollection, XmlNameTable

GetAbbreviatedDayName():

DateTimeFormatInfo

GetAbbreviatedEraName():

DateTimeFormatInfo

GetAbbreviatedMonthName():

DateTimeFormatInfo

GetAccessors():

PropertyBuilder, PropertyInfo

GetActiveObject():

Marshal

GetAddMethod():

EventInfo

GetAddressBytes():

IPAddress

GetAllDateTimePatterns():

DateTimeFormatInfo

GetArray():

ArrayWithOffset

GetArrayMethod():

ModuleBuilder

GetArrayMethodToken():

ModuleBuilder

GetArrayRank():

Type

GetAssemblies():

AppDomain

GetAssembly():

Assembly

GetAssemblyName():

AssemblyName, AssemblyNameProxy

GetAttribute():

XmlElement, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader,
XPathNavigator

GetAttributeFlagsImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetAttributeNode():

XmlElement

GetAttributes():

File

GetAvailableThreads():

ThreadPool

GetBaseDefinition():

MethodBuilder, MethodInfo

GetBaseException():

Exception

GetBits():

Decimal

GetBoolean():

SerializationInfo

GetBuffer():

MemoryStream

GetByIndex():

SortedList

GetByte():

Buffer, SerializationInfo

GetByteCount():

ASCIIEncoding, Encoder, Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding
GetBytes():

ASCIIEncoding, BitConverter, Encoder, Encoding, UnicodeEncoding, UTF7Encoding,
UTF8Encoding
GetCallingAssembly():

Assembly
GetCategories():

PerformanceCounterCategory
GetChar():

SerializationInfo
GetCharCount():

ASCIIEncoding, Decoder, Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding
GetChars():

ASCIIEncoding, Decoder, Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding
GetComInterfaceForObject():

Marshal
GetCommandLineArgs():

Environment
GetComObjectData():

Marshal
GetCompareInfo():

CompareInfo
GetComSlotForMethodInfo():

Marshal
GetConstructor():

Type
GetConstructorImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator
GetConstructors():

EnumBuilder, Type, TypeBuilder, TypeDelegator
GetConstructorToken():

ModuleBuilder
GetCookieHeader():

CookieContainer
GetCookies():

CookieContainer
GetCounters():

PerformanceCounterCategory

GetCreationTime():

Directory, File

GetCreationTimeUtc():

Directory, File

GetCredential():

CredentialCache, ICredentials, NetworkCredential

GetCultures():

CultureInfo

GetCurrentDirectory():

Directory

GetCurrentMethod():

MethodBase

GetCurrentProcess():

Process

GetCurrentThreadId():

AppDomain

GetCustomAttribute():

Attribute

GetCustomAttributes():

Assembly, Attribute, ConstructorBuilder, EnumBuilder, FieldBuilder, ICustomAttributeProvider, MemberInfo, MethodBuilder, Module, ParameterInfo, PropertyBuilder, TypeBuilder, TypeDelegator

GetData():

AppDomain, Thread

GetDateTime():

SerializationInfo

GetDateTimeFormats():

DateTime

GetDaylightChanges():

TimeZone

GetDayName():

DateTimeFormatInfo

GetDayOfMonth():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetDayOfWeek():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetDayOfYear():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetDaysInMonth():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetDaysInYear():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetDecimal():

SerializationInfo

GetDecoder():

Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding

GetDefaultMembers():

Type

GetDefaultProxy():

WebProxy

GetDirectories():

Directory, DirectoryInfo

GetDirectoryName():

Path

GetDirectoryNames():

IsolatedStorageFile

GetDirectoryRoot():

Directory

GetDomain():

Thread

GetDomainID():

Thread

GetDouble():

SerializationInfo

GetDynamicModule():

AssemblyBuilder

GetElementById():

XmlDataDocument, XmlDocument

GetElementFromRow():

XmlDataDocument

GetElementsByTagName():

XmlDocument, XmlElement

GetElementType():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetEmptyWebProxy():

GlobalProxySelection

GetEncoder():

Encoding, UTF7Encoding, UTF8Encoding

GetEncoding():

Encoding

GetEndComSlot():

Marshal

GetEntity():

XmlResolver, XmlSecureResolver, XmlUriResolver

GetEntryAssembly():

Assembly

GetEnumerator():

Array, ArrayList, BitArray, CaptureCollection, CollectionBase, CookieCollection, CredentialCache, DictionaryBase, EventLogEntryCollection, GroupCollection, Hashtable, HybridDictionary, IDictionary, IEnumerable, IsolatedStorageFile, KeysCollection, ListDictionary, MatchCollection, NameObjectCollectionBase, Queue, ReadOnlyCollectionBase, SerializationInfo, SortedList, Stack, String, StringCollection, StringDictionary, TraceListenerCollection, XmlNamedNodeMap, XmlNamespaceManager, XmlNode, XmlNodeList

GetEnvironmentVariable():

Environment

GetEnvironmentVariables():

Environment

GetEra():

Calendar, DateTimeFormatInfo, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetEraName():

DateTimeFormatInfo

GetEvent():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetEventLogs():

EventLog

GetEvents():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetEventToken():

EventBuilder

GetException():

ErrorEventArgs

GetExceptionCode():

Marshal

GetExceptionPointers():

Marshal

GetExecutingAssembly():

Assembly

GetExportedTypes():

Assembly, AssemblyBuilder

GetExtension():

Path

GetExtensionObject():

XsltArgumentList

GetField:

BindingFlags

GetField():

EnumBuilder, IReflect, Module, Type, TypeBuilder, TypeDelegator

GetFieldFromHandle():

FieldInfo

GetFields():

EnumBuilder, IReflect, Module, Type, TypeBuilder, TypeDelegator

GetFieldSigHelper():

SignatureHelper

GetFieldToken():

ModuleBuilder

GetFile():

Assembly, AssemblyBuilder

GetFileColumnNumber():

StackFrame

GetFileLineNumber():

StackFrame

GetFileName():

Path, StackFrame

GetFileNames():

IsolatedStorageFile

GetFileNameWithoutExtension():

Path

GetFiles():

Assembly, AssemblyBuilder, Directory, DirectoryInfo

GetFileSystemEntries():

Directory

GetFileSystemInfos():

DirectoryInfo

GetFolderPath():

Environment

GetFormat():

CultureInfo, DateTimeFormatInfo, IFormatProvider, NumberFormatInfo

GetFrame():

StackTrace

GetFullPath():

Path

GetGeneration():

GC

GetMethod():

PropertyBuilder, PropertyInfo

GetGroupNames():

Regex

GetGroupNumbers():

Regex

GetHash():

Hashtable

GetHashCode():

ArgIterator, ArrayWithOffset, Attribute, BitVector32, Boolean, Byte, CaseInsensitiveHashCodeProvider, Char, CompareInfo, Cookie, CultureInfo, DateTime, Decimal, Delegate, Double, Encoding, EndpointPermission, Enum, EventToken, FieldToken, Guid, HttpRequest, HttpResponse, IHashCodeProvider, Int16, Int32, Int64, IntPtr, IPAddress, IPEndPoint, Label, MethodBuilder, MethodToken, MulticastDelegate, Object, OpCode, ParameterToken, PropertyToken, RegionInfo, SByte, Section, ServicePoint, SignatureHelper, SignatureToken, Single, Socket, SocketAddress, SortKey, StreamingContext,

String, StringToken, TextInfo, TimeSpan, Type, TypeToken, UInt16, UInt32, UInt64, UIntPtr, UnicodeEncoding, Uri, UriBuilder, UTF8Encoding, ValueType, Version, XmlQualifiedName
GetHINSTANCE():

Marshal
GetHostByAddress():

Dns
GetHostByName():

Dns
GetHostName():

Dns
GetHour():

Calendar
GetHRForException():

Marshal
GetHRForLastWin32Error():

Marshal
GetId():

ObjectIDGenerator
GetIDispatchForObject():

Marshal
GetILGenerator():

ConstructorBuilder, MethodBuilder
GetILOffset():

StackFrame
GetIndexParameters():

PropertyBuilder, PropertyInfo
GetInstance():

DateTimeFormatInfo, NumberFormatInfo
GetInstanceNames():

PerformanceCounterCategory
GetInt16():

SerializationInfo
GetInt32():

SerializationInfo
GetInt64():

SerializationInfo
GetInterface():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetInterfaceMap():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetInterfaces():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetInvocationList():

Delegate, MulticastDelegate

GetTypeInfoForType():

Marshal

GetUnknownForObject():

Marshal

GetKey():

NameValueCollection, SortedList

GetKeyList():

SortedList

GetLastAccessTime():

Directory, File

GetLastAccessTimeUtc():

Directory, File

GetLastWin32Error():

Marshal

GetLastWriteTime():

Directory, File

GetLastWriteTimeUtc():

Directory, File

GetLeftPart():

Uri

GetLength():

Array

GetLifetimeService():

MarshalByRefObject

GetLoadedModules():

Assembly

GetLocalVarSigHelper():

SignatureHelper

GetLogicalDrives():

Directory, Environment

GetLongLength():

Array

GetLowerBound():

Array

GetManagedCategoryGuid():

IRegistrationServices, RegistrationServices

GetManagedThunkForUnmanagedMethodPtr():

Marshal

GetManifestResourceInfo():

Assembly, AssemblyBuilder

GetManifestResourceNames():

Assembly, AssemblyBuilder

GetManifestResourceStream():

Assembly, AssemblyBuilder

GetMaxByteCount():

ASCIIEncoding, Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding

GetMaxCharCount():

ASCIIEncoding, Encoding, UnicodeEncoding, UTF7Encoding, UTF8Encoding

GetMaxThreads():

ThreadPool

GetMember():

EnumBuilder, IReflect, Type, TypeBuilder, TypeDelegator

GetMembers():

EnumBuilder, IReflect, Type, TypeBuilder, TypeDelegator

GetMethod():

IReflect, Module, StackFrame, Type

GetMethodFromHandle():

MethodBase

GetMethodImpl():

Delegate, EnumBuilder, Module, Type, TypeBuilder, TypeDelegator

GetMethodImplementationFlags():

ConstructorBuilder, MethodBase, MethodBuilder

GetMethodInfoForComSlot():

Marshal

GetMethods():

EnumBuilder, IReflect, Module, Type, TypeBuilder, TypeDelegator

GetMethodSigHelper():

SignatureHelper

GetMethodToken():

ModuleBuilder

GetMilliseconds():

Calendar

GetMinThreads():

ThreadPool

GetMinute():

Calendar

GetModule():

Assembly, ConstructorBuilder, MethodBuilder

GetModules():

Assembly

GetMonth():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar,
JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetMonthName():

DateTimeFormatInfo

GetMonthsInYear():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar,
JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

GetName():

Assembly, Enum

GetNamedDataSlot():

Thread

GetNamedItem():

XmlNamedNodeMap

GetNames():

Enum

GetNamespace():

XPathNavigator

GetNamespaceOfPrefix():

XmlNode

GetNativeOffset():

StackFrame

GetNativeVariantForObject():

Marshal

GetNestedType():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetNestedTypes():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetNext():

Formatter

GetNextArg():

ArgIterator

GetNextArgType():

ArgIterator

GetNextSelector():

ISurrogateSelector, SurrogateSelector

GetNextTextElement():

StringInfo

GetNode():

IHasXmlNode

GetNumericValue():

Char

GetObject():

Activator, ObjectManager

GetObjectData():

ArgumentException, ArgumentOutOfRangeException, Assembly, AssemblyName, BadImageFormatException, DBNull, Delegate, Exception, FileLoadException, FileNotFoundException, FileSystemInfo, FormatterServices, Hashtable, ISerializable, ISerializationSurrogate, MissingMemberException, Module, MulticastDelegate, NameObjectCollectionBase, NotFiniteNumberException, ObjectDisposedException, ReflectionTypeLoadException, RuntimeTypeHandle, SoapFault, TypeInitializationException, TypeLoadException, WeakReference, XmlException, XPathException, XsltCompileException, XsltException

GetObjectForUnknown():

Marshal

GetObjectForNativeVariant():

Marshal

GetObjectsForNativeVariants():

Marshal

GetOffset():

ArrayWithOffset

GetParam():

XsltArgumentList

GetParameters():

ConstructorBuilder, MethodBase, MethodBuilder

GetParent():

Directory

GetPathRoot():

Path

GetPermission():

IsolatedStorage, IsolatedStorageFile

GetPreamble():

Encoding, UnicodeEncoding, UTF8Encoding

GetPrefixOfNamespace():

XmlNode

GetProcessById():

Process

GetProcesses():

Process

GetProcessesByName():

Process

GetProgIdForType():

IRegistrationServices, RegistrationServices

GetProperties():

EnumBuilder, IReflect, Type, TypeBuilder, TypeDelegator

GetProperty:

BindingFlags

GetProperty():

IReflect, Type

GetPropertyImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator

GetPropertySigHelper():

SignatureHelper

GetProxy():

IWebProxy, WebProxy

GetPublicKey():

AssemblyName
GetPublicKeyToken():

AssemblyName
GetRaiseMethod():

EventInfo
GetRange():

ArrayList
GetRealObject():

IObjectReference
GetReferencedAssemblies():

Assembly
GetRegistrableTypesInAssembly():

IRegistrationServices, RegistrationServices
GetRemainder():

XmlTextReader
GetRemainingCount():

ArgIterator
GetRemoveMethod():

EventInfo
GetRequestStream():

FileWebRequest, HttpWebRequest, WebRequest
GetResponse():

FileWebRequest, HttpWebRequest, WebRequest
GetResponseHeader():

HttpWebResponse
GetResponseStream():

FileWebResponse, HttpWebResponse, WebResponse
GetRowFromElement():

XmlDataDocument
GetRuntimeDirectory():

RuntimeEnvironment
GetSafeUninitializedObject():

FormatterServices
GetSatelliteAssembly():

Assembly
GetSByte():

SerializationInfo

GetSecond():

Calendar

GetSerializableMembers():

FormatterServices

GetService():

IServiceProvider

GetSetMethod():

PropertyBuilder, PropertyInfo

GetSignature():

SignatureHelper

GetSignatureToken():

ModuleBuilder

GetSignerCertificate():

Module

GetSingle():

SerializationInfo

GetSocketOption():

Socket

GetSortKey():

CompareInfo

GetStartComSlot():

Marshal

GetStore():

IsolatedStorageFile

GetStream():

TcpClient

GetString():

ASCIIEncoding, Encoding, SerializationInfo

GetStringBuilder():

StringWriter

GetStringConstant():

ModuleBuilder

GetSubKeyNames():

RegistryKey

GetSurrogate():

ISurrogateSelector, SurrogateSelector

GetSymWriter():

ModuleBuilder

GetSystemVersion():

RuntimeEnvironment

GetTempFileName():

Path

GetTempPath():

Path

GetTextElement():

TextElementEnumerator

GetTextElementEnumerator():

StringInfo

GetThreadFromFiberCookie():

Marshal

GetToken():

ConstructorBuilder, FieldBuilder, MethodBuilder, ParameterBuilder

GetTotalMemory():

GC

GetType():

AppDomain, Assembly, Module, ModuleBuilder, Object, Type

GetTypeArray():

Type

GetTypeCode():

Boolean, Byte, Char, Convert, DateTime, DBNull, Decimal, Double, Enum, IConvertible, Int16, Int32, Int64, SByte, Single, String, Type, UInt16, UInt32, UInt64

GetTypedObjectForUnknown():

Marshal

GetTypeForTypeInfo():

Marshal

GetTypeFromAssembly():

FormatterServices

GetTypeFromCLSID():

Type

GetTypeFromHandle():

Type

GetTypeFromProgID():

Type

GetTypeHandle():

Type

GetTypeInfoName():

Marshal

GetTypeLibGuid():

Marshal

GetTypeLibGuidForAssembly():

Marshal

GetTypeLibLcid():

Marshal

GetTypeLibName():

Marshal

GetTypes():

Assembly, Module, ModuleBuilder

GetTypeToken():

ModuleBuilder

GetUInt16():

SerializationInfo

GetUInt32():

SerializationInfo

GetUInt64():

SerializationInfo

GetUnderlyingType():

Enum

GetUnicodeCategory():

Char

GetUninitializedObject():

FormatterServices

GetUnmanagedThunkForManagedMethodPtr():

Marshal

GetUnmanagedType:

UnmanagedType

GetUpperBound():

Array

GetUserStoreForAssembly():

IsolatedStorageFile

GetUserStoreForDomain():

IsolatedStorageFile

GetUtcOffset():

TimeZone

GetValue():

Array, FieldBuilder, FieldInfo, PropertyBuilder, PropertyInfo, RegistryKey, SerializationInfo

GetValueDirect():

FieldInfo

GetValueList():

SortedList

GetValueNames():

RegistryKey

GetValues():

Enum, NameValueCollection, WebHeaderCollection

GetVersionInfo():

FileVersionInfo

GetWeekOfYear():

Calendar

GetYear():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

Ggp:

ProtocolType

GlobalAssemblyCache:

Assembly

GlobalProxySelection:

System.Net

Gone:

HttpStatusCode

GregorianCalendar:

System.Globalization

GregorianCalendarTypes:

System.Globalization

Group:

IPv6MulticastOption, MulticastOption, System.Text.RegularExpressions

GroupCollection:

System.Text.RegularExpressions
GroupNameFromNumber():

Regex
GroupNumberFromName():

Regex
Groups:

Match
Guid:

System
GUID:

EnumBuilder, Type, TypeBuilder, TypeDelegator
GuidAttribute:

System.Runtime.InteropServices
Handle:

FileStream, HandleRef, IsolatedStorageFileStream, Process, Socket, WaitHandle
HandleCount:

Process
HandleRef:

System.Runtime.InteropServices
HasAttribute():

XmlElement
HasAttributes:

XmlElement, XmlNodeReader, XmlReader, XPathNavigator
HasChildNodes:

XmlNode
HasChildren:

XPathNavigator
HasDefault:

FieldAttributes, ParameterAttributes, PropertyAttributes
HasElementType:

Type
HasElementTypeImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator
HasExited:

Process
HasExtension():

Path

HasFeature():

XmlImplementation

HasFieldMarshal:

FieldAttributes, ParameterAttributes

HasFieldRVA:

FieldAttributes

HashAlgorithm:

AssemblyName

Hashtable:

System.Collections

HasId():

ObjectIDGenerator

HasKeys():

NameValueCollection

HasLineInfo():

IXmlLineInfo

HasNamespace():

XmlNamespaceManager

HasSecurity:

MethodAttributes, TypeAttributes

HasShutdownStarted:

Environment

HasThis:

CallingConventions

HasValue:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

HaveResponse:

HttpRequest

HeaderIncluded:

SocketOptionName

HeaderName:

Encoding

Headers:

FileWebRequest, FileWebResponse, HttpRequest, HttpResponse, ISoapMessage,
SoapMessage, WebClient, WebRequest, WebResponse

HebrewCalendar:

System.Globalization

HebrewEra:

HebrewCalendar

HelpLink:

Exception

HexEscape():

Uri

HexNumber:

NumberStyles

HexUnescape():

Uri

Hidden:

FileAttributes, ProcessWindowStyle

HideBySig:

MethodAttributes

High:

ProcessPriorityClass

Highest:

ThreadPriority, ThreadPriorityLevel

HijriAdjustment:

HijriCalendar

HijriCalendar:

System.Globalization

HijriEra:

HijriCalendar

History:

SpecialFolder

Host:

SocketPermissionAttribute, Uri, UriBuilder

Hostname:

EndpointPermission

HostName:

IPHostEntry

HostNameType:

Uri

HostToNetworkOrder():

IPAddress

Hour:

DateTime

Hours:

TimeSpan

HttpContinueDelegate:

System.Net

HttpStatusCode:

System.Net

HttpVersion:

System.Net

HttpVersionNotSupported:

HttpStatusCode

HttpWebRequest:

System.Net

HttpWebResponse:

System.Net

HybridDictionary:

System.Collections.Specialized

HyperChannel:

AddressFamily, ProtocolFamily

/1:

UnmanagedType

/2:

UnmanagedType

/4:

UnmanagedType

/8:

UnmanagedType

AsyncResult:

System

AuthenticationModule:

System.Net

CertificatePolicy:

System.Net

ICloneable:

System

Icmp:

ProtocolType

ICollection:

System.Collections

IComparable:

System

IComparer:

System.Collections

Icon:

UserPreferenceCategory

IConvertible:

System

ICredentials:

System.Net

ICustomAttributeProvider:

System.Reflection

ICustomFormatter:

System

Id:

Process, ProcessThread

ID:

XmlTokenizedType

IdealProcessor:

ProcessThread

IDeserializationCallback:

System.Runtime.Serialization

IDictionary:

System.Collections

IDictionaryEnumerator:

System.Collections

IDispatch:

UnmanagedType

IDispatchImplAttribute:

System.Runtime.InteropServices

IDispatchImplType:

System.Runtime.InteropServices

IDisposable:

System

Idle:

ProcessPriorityClass, ThreadPriorityLevel

IdleSince:

ServicePoint

Idp:

ProtocolType

IDREF:

XmlTokenizedType

IDREFS:

XmlTokenizedType

IEEE12844:

AddressFamily, ProtocolFamily

IEEERemainder():

Math

IEnumerable:

System.Collections

IEnumerator:

System.Collections

FieldInfo:

System.Runtime.Serialization.Formatter

IfModifiedSince:

HttpRequest

IFormatProvider:

System

IFormattable:

System

IFormatter:

System.Runtime.Serialization

FormatterConverter:

System.Runtime.Serialization

Gmp:

ProtocolType

IgnoreCase:

BindingFlags, CompareOptions, RegexOptions

IgnoreKanaType:

CompareOptions

IgnoreNonSpace:

CompareOptions

IgnorePatternWhitespace:

RegexOptions

IgnoreReturn:

BindingFlags

IgnoreSymbols:

CompareOptions

IgnoreWidth:

CompareOptions

IHashCodeProvider:

System.Collections

IHasXmlNode:

System.Xml

IIDGuid:

UnmanagedMarshal

IL:

MethodImplAttributes

ILGenerator:

System.Reflection.Emit

ILList:

System.Collections

ImageRuntimeVersion:

Assembly, AssemblyBuilder

Implementation:

XmlDocument

ImpLink:

AddressFamily, ProtocolFamily

Import:

TypeAttributes

ImportNode():

XmlDocument

In:

Console, ParameterAttributes

InAttribute:

System.Runtime.InteropServices

IncludeSubdirectories:

FileSystemWatcher

Increment():

Interlocked, PerformanceCounter

IncrementBy():

PerformanceCounter

Indent():

Debug, Trace

Indentation:

XmlTextWriter

IndentChar:

XmlTextWriter

Indented:

Formatting

IndentLevel:

Debug, Trace, TraceListener

IndentSize:

Debug, Trace, TraceListener

Index:

Capture, EventLogEntry

IndexOf():

Array, ArrayList, CompareInfo, CounterCreationDataCollection,
EventLogPermissionEntryCollection, IList, PerformanceCounterPermissionEntryCollection,
ProcessModuleCollection, ProcessThreadCollection, String, StringCollection,
TraceListenerCollection

IndexOfAny():

String

IndexOfKey():

SortedList

IndexOfValue():

SortedList

IndexOutOfRangeException:

System

Infinite:

Timeout

Info:

TraceLevel

Information:

EventLogEntryType

InformationalVersion:

AssemblyInformationalVersionAttribute

Inheritable:

FileShare

Inherited:

AttributeUsageAttribute

Initblk:

OpCodes

Initial:

ReadState

Initialize():

Array

Initialized:

ThreadState

InitializeLifetimeService():

AppDomain, MarshalByRefObject

InitializeReferences():

Regex

InitialQuotePunctuation:

UnicodeCategory

InitLocals:

ConstructorBuilder, MethodBuilder

Initobj:

OpCodes

InitOnly:

FieldAttributes

InitStore():

IsolatedStorage

InlineBrTarget:

OperandType

InlineField:

OperandType

InlineI:

OperandType

InlineI8:

OperandType

InlineMethod:

OperandType

InlineNone:

OperandType

InlinePhi:

OperandType

InlineR:

OperandType

InlineSig:

OperandType

InlineString:

OperandType

InlineSwitch:

OperandType

InlineTok:

OperandType

InlineType:

OperandType

InlineVar:

OperandType

InnerException:

Exception

InnerText:

XmlAttribute, XmlCharacterData, XmlDeclaration, XmlElement, XmlEntity, XmlNode,
XmlProcessingInstruction

InnerXml:

XmlAttribute, XmlDocument, XmlDocumentFragment, XmlElement, XmlEntity, XmlNode,
XmlNotation

NormalizeForIsolatedStorage:

System.IO.IsolatedStorage

Insert:

XmlNodeChangedAction

Insert():

ArrayList, CounterCreationDataCollection, EventLogPermissionEntryCollection, IList, PerformanceCounterPermissionEntryCollection, ProcessThreadCollection, String, StringBuilder, StringCollection, TraceListenerCollection

InsertAfter():

XmlAttributeCollection, XmlNode

InsertBefore():

XmlAttributeCollection, XmlNode

InsertData():

XmlCharacterData

InsertRange():

ArrayList

Install():

EventLogInstaller, PerformanceCounterInstaller

InstalledFontsChanged:

SystemEvents

InstalledUICulture:

CultureInfo

InstalledWin32Cultures:

CultureTypes

Instance:

BindingFlags

InstanceData:

System.Diagnostics

InstanceDataCollection:

System.Diagnostics

InstanceDataCollectionCollection:

System.Diagnostics

InstanceExists():

PerformanceCounterCategory

InstanceName:

InstanceData, PerformanceCounter

Instrument:

EventLogPermissionAccess, PerformanceCounterPermissionAccess

Int16:

System, TypeCode

Int32:

System, TypeCode
Int64:

System, TypeCode
Int64BitsToDouble():

BitConverter
Integer:

NumberStyles
Interactive:

ReadState
Interface:

AttributeTargets, TypeAttributes, UnmanagedType
InterfaceIndex:

IPv6MulticastOption
InterfaceIsDual:

ComInterfaceType
InterfaceIsDispatch:

ComInterfaceType
InterfaceIsUnknown:

ComInterfaceType
InterfaceMapping:

System.Reflection
InterfaceMethods:

InterfaceMapping
InterfaceType:

InterfaceMapping
InterfaceTypeAttribute:

System.Runtime.InteropServices
Interlocked:

System.Threading
Intern():

String
InternalBufferOverflowException:

System.IO
InternalBufferSize:

FileSystemWatcher
InternalCall:

MethodImplAttributes

InternalHigh:

NativeOverlapped

InternalImpl:

IDispatchImplType

InternalLow:

NativeOverlapped

InternalName:

FileVersionInfo

InternalServerError:

HttpStatusCode

InternalSubset:

XmlDocumentType, XmlParserContext

InternalValidationEventHandler:

XmlValidatingReader

InternetCache:

SpecialFolder

InterNetwork:

AddressFamily, ProtocolFamily

InterNetworkV6:

AddressFamily, ProtocolFamily

Interrupt():

Thread

Intersect():

DnsPermission, SocketPermission, WebPermission

Interval:

Timer

IntPtr:

System

InvalidateCachedArrays():

NameValueCollection

InvalidCastException:

System

InvalidComObjectException:

System.Runtime.InteropServices

InvalidFilterCriteriaException:

System.Reflection

InvalidHandle:

WaitHandle

InvalidOleVariantTypeException:

System.Runtime.InteropServices

InvalidOperationException:

System

InvalidPathChars:

Path

InvalidProgramException:

System

InvariantCulture:

CultureInfo

InvariantInfo:

DateTimeFormatInfo, NumberFormatInfo

Invoke():

AssemblyLoadEventHandler, AsyncCallback, ConstructorBuilder, ConstructorInfo, CrossAppDomainDelegate, ElapsedEventHandler, EntryWrittenEventHandler, ErrorEventHandler, EventHandler, FileSystemEventHandler, HttpContinueDelegate, IOCompletionCallback, IXsltContextFunction, MatchEvaluator, MemberFilter, MethodBase, MethodBuilder, ModuleResolveEventHandler, ObjectCreationDelegate, PowerModeChangedEventHandler, RenamedEventHandler, ResolveEventHandler, SessionEndedEventHandler, SessionEndingEventHandler, ThreadExceptionHandler, ThreadStart, TimerCallback, TimerElapsedEventHandler, TypeFilter, UnhandledExceptionHandler, UserPreferenceChangedEventHandler, UserPreferenceChangingEventHandler, WaitCallback, WaitOrTimerCallback, XmlNodeChangedEventHandler

InvokeMember():

EnumBuilder, IReflect, Type, TypeBuilder, TypeDelegator

InvokeMethod:

BindingFlags

InvokeOnEventsThread():

SystemEvents

IObjectReference:

System.Runtime.Serialization

IOCompletionCallback:

System.Threading

IOControl():

Socket

IODescriptionAttribute:

System.IO

IOException:

System.IO

IP:

ProtocolType, SocketOptionLevel

IPAddress:

System.Net

EndPoint:

System.Net

HostEntry:

System.Net

Options:

SocketOptionName

TimeToLive:

SocketOptionName

IPv4:

UriHostNameType

IPv6:

ProtocolType, SocketOptionLevel, UriHostNameType

IPv6Any:

IPAddress

IPv6Loopback:

IPAddress

IPv6MulticastOption:

System.Net.Sockets

IPv6None:

IPAddress

px:

AddressFamily, ProtocolFamily, ProtocolType

Ida:

AddressFamily, ProtocolFamily

Reflect:

System.Reflection

RegistrationServices:

System.Runtime.InteropServices

Abstract:

MethodBase, Type

IsAlive:

Thread, WeakReference

IsAllocated:

GCHandle

IsAnsiClass:

Type

IsArray:

Type

IsArrayImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator

IsAssembly:

FieldInfo, MethodBase

IsAssignableFrom():

Type, TypeBuilder

IsAsync:

FileStream, IsolatedStorageFileStream

IsAttached:

Debugger

IsAutoClass:

Type

IsAutoLayout:

Type

IsBackground:

Thread

IsBadFileSystemCharacter():

Uri

IsBrowserDisplay:

Encoding

IsBrowserSave:

Encoding

IsBypassed():

IWebProxy, WebProxy

IsByRef:

Type

IsByRefImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator

IsClass:

Type

IsCOMObject:

Type

IsComObject():

Marshal

IsCOMObjectImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator

IsCompleted:

IAsyncResult

IsCompliant:

CLSCompliantAttribute

IsConstructor:

MethodBase

IsContextful:

Type

IsContextfullImpl():

Type

IsControl():

Char

IsDaylightSavingTime():

TimeZone

IsDBNull():

Convert

IsDebug:

FileVersionInfo

IsDefault:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

IsDefaultAttribute():

Attribute

IsDefaultPort:

Uri

IsDefined():

Assembly, Attribute, ConstructorBuilder, Enum, EnumBuilder, FieldBuilder,
ICustomAttributeProvider, MemberInfo, MethodBuilder, Module, ParameterInfo,
PropertyBuilder, TypeBuilder, TypeDelegator

IsDescendant():

XPathNavigator

IsDigit():

Char

IsEmpty:

XmlElement, XmlQualifiedName

IsEmptyElement:

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

IsEnum:

Type

IsEquivalentInstaller():

EventLogInstaller

ISerializable:

System.Runtime.Serialization

ISerializationSurrogate:

System.Runtime.Serialization

IsError:

ObsoleteAttribute

IServiceProvider:

System

IsExcludedCharacter():

Uri

IsExplicitLayout:

Type

IsFamily:

FieldInfo, MethodBase

IsFamilyAndAssembly:

FieldInfo, MethodBase

IsFamilyOrAssembly:

FieldInfo, MethodBase

IsFile:

Uri

IsFinal:

MethodBase

IsFinalizingForUnload():

AppDomain

IsFixedSize:

Array, ArrayList, Hashtable, HybridDictionary, IDictionary, IList, ListDictionary, SortedList

IsHexDigit():

Uri

IsHexEncoding():

Uri

IsHideBySig:

MethodBase

IsImport:

Type

IsIn:

ParameterBuilder, ParameterInfo

IsInfinity():

Double, Single

IsInitOnly:

FieldInfo

Isinst:

OpCodes

IsInstanceOfType():

Type

IsInterface:

Type

IsInterned():

String

IsJITOptimizerDisabled:

DebuggableAttribute

IsJITTrackingEnabled:

DebuggableAttribute

IsLayoutSequential:

Type

IsLcid:

ParameterInfo

IsLeapDay():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

IsLeapMonth():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

IsLeapYear():

Calendar, DateTime, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

IsLetter():

Char

IsLetterOrDigit():

Char

IsLiteral:

FieldInfo

IsLittleEndian:

BitConverter

IsLocal:

IXsltContextVariable

IsLogging():

Debugger

IsLoopback:

Uri

IsLoopback():

IPAddress

IsLower():

Char

IsMailNewsDisplay:

Encoding

IsMailNewsSave:

Encoding

IsMarshalByRef:

Type

IsMarshalByRefImpl():

Type

IsMatch():

Regex

IsMetric:

RegionInfo

IsMulticast:

EventInfo

IsName():

XmlReader

IsNameToken():

XmlReader

IsNaN():

Double, Single

IsNegativeInfinity():

Double, Single

IsNestedAssembly:

Type

IsNestedFamANDAssem:

Type

IsNestedFamily:

Type

IsNestedFamORAssem:

Type

IsNestedPrivate:

Type

IsNestedPublic:

Type

IsNeutralCulture:

CultureInfo

IsNotPublic:

Type

IsNotSerialized:

FieldInfo

IsNumber():

Char

Iso:

AddressFamily, ProtocolFamily

IsSoapMessage:

System.Runtime.Serialization.Formatter

ISOCurrencySymbol:

RegionInfo

IsolatedStorage:

System.IO.IsolatedStorage

IsolatedStorageException:

System.IO.IsolatedStorage
IsolatedStorageFile:

System.IO.IsolatedStorage
IsolatedStorageFileStream:

System.IO.IsolatedStorage
IsolatedStorageScope:

System.IO.IsolatedStorage
IsOptional:

ParameterBuilder, ParameterInfo
IsOut:

ParameterBuilder, ParameterInfo
IsParam:

IXsltContextVariable
IsPatched:

FileVersionInfo
IsPathRooted():

Path
IsPinvokeImpl:

FieldInfo
IsPointer:

Type
IsPointerImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator
IsPositiveInfinity():

Double, Single
IsPrefix():

CompareInfo
IsPreRelease:

FileVersionInfo
IsPrimitive:

Type
IsPrimitiveImpl():

EnumBuilder, Type, TypeBuilder, TypeDelegator
IsPrivate:

FieldInfo, MethodBase

IsPrivateBuild:

FileVersionInfo

IsPublic:

FieldInfo, MethodBase, RegexCompilationInfo, Type

IsPunctuation():

Char

IsReaderLockHeld:

ReaderWriterLock

IsReadOnly:

Array, ArrayList, BitArray, CaptureCollection, CookieCollection, CultureInfo, DateTimeFormatInfo, GroupCollection, Hashtable, HybridDictionary, IDictionary, IList, ListDictionary, MatchCollection, NumberFormatInfo, SortedList, StringCollection, XmlDocument, XmlDocumentType, XmlEntity, XmlEntityReference, XmlNode, XmlNotation

IsReservedCharacter():

Uri

IsResource():

Module

IsRestricted():

WebHeaderCollection

IsRetVal:

ParameterInfo

IsSamePosition():

XPathNavigator

IsSealed:

Type

IsSeparator():

Char

IsSerializable:

Type

IsSpecialBuild:

FileVersionInfo

IsSpecialName:

EventInfo, FieldInfo, MethodBase, PropertyInfo, Type

IsStartElement():

XmlReader

IsStatic:

FieldInfo, MethodBase

IsSubclassOf():

Type, TypeBuilder

IsSubsetOf():

DnsPermission, SocketPermission, WebPermission

IsSuffix():

CompareInfo

IsSurrogate():

Char

IsSymbol():

Char

IsSynchronized:

Array, ArrayList, BitArray, CaptureCollection, CookieCollection, GroupCollection, Hashtable, HybridDictionary, ICollection, ListDictionary, MatchCollection, Queue, SortedList, Stack, StringCollection, StringDictionary

IsTerminating:

UnhandledExceptionEventArgs

IsThreadPoolThread:

Thread

IsTransient():

ModuleBuilder

IsTypeVisibleFromCom():

Marshal

IsUnc:

Uri

IsUnicodeClass:

Type

IsUnrestricted():

DnsPermission, SocketPermission, WebPermission

IsUpper():

Char

IsSurrogateSelector:

System.Runtime.Serialization

IsValueType:

Type

IsValueTypeImpl():

EnumBuilder, Type, TypeDelegator

IsVirtual:

MethodBase

IsWhiteSpace():

Char

IsWriterLockHeld:

ReaderWriterLock

Item:

ArrayList, BitArray, BitVector32, CaptureCollection, CookieCollection, CounterCreationDataCollection, EventLogEntryCollection, EventLogPermissionEntryCollection, GroupCollection, Hashtable, HybridDictionary, IDictionary, IList, InstanceDataCollection, InstanceDataCollectionCollection, KeysCollection, ListDictionary, MatchCollection, NameValueCollection, ParameterModifier, PerformanceCounterPermissionEntryCollection, ProcessModuleCollection, ProcessThreadCollection, SocketAddress, SortedList, StringCollection, StringDictionary, TraceListenerCollection, XmlNode, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

Item():

XmlNamedNodeMap, XmlNodeList

ItemOf:

XmlAttributeCollection, XmlNodeList

Unknown:

UnmanagedType

WebProxy:

System.Net

WebRequestCreate:

System.Net

XmlLineInfo:

System.Xml

XPathNavigable:

System.Xml.XPath

XsltContextFunction:

System.Xml.Xsl

XsltContextVariable:

System.Xml.Xsl

[\[Team LiB \]](#)

J-R

JapaneseCalendar:

System.Globalization

JitImmediate:

MethodRental

JitOnDemand:

MethodRental

Jmp:

OpCodes

Join():

String, Thread

JoinMulticastGroup():

UdpClient

JulianCalendar:

System.Globalization

JulianEra:

JulianCalendar

KeepAlive:

HttpWebRequest, SocketOptionName

KeepAlive():

GC

KeepAliveFailure:

WebExceptionStatus

Key:

DictionaryEntry, IDictionaryEnumerator

Keyboard:

UserPreferenceCategory

KeyData:

SortKey

KeyEquals():

Hashtable

KeyFile:

AssemblyKeyFileAttribute

KeyName:

AssemblyKeyNameAttribute

KeyPair:

AssemblyName

Keys:

Hashtable, HybridDictionary, IDictionary, InstanceDataCollection,
InstanceDataCollectionCollection, ListDictionary, NameObjectCollectionBase, SortedList,
StringDictionary

KeysCollection:

System.Collections.Specialized

Kill():

Process

KillTimer():

SystemEvents

KoreanCalendar:

System.Globalization

KoreanEra:

KoreanCalendar

Label:

System.Reflection.Emit

Language:

FileVersionInfo

LastAccess:

NotifyFilters

LastAccessTime:

FileSystemInfo

LastAccessTimeUtc:

FileSystemInfo

LastChild:

XmlNode

LastIndexOf():

Array, ArrayList, CompareInfo, String

LastIndexOfAny():

String

LastModified:

HttpWebResponse

LastWrite:

NotifyFilters

LastWriteTime:

FileSystemInfo

LastWriteTimeUtc:

FileSystemInfo

Lat:

AddressFamily, ProtocolFamily

Launch():

Debugger

LayoutKind:

System.Runtime.InteropServices

LayoutMask:

TypeAttributes

Lcid:

ParameterAttributes

LCID:

CompareInfo, CultureInfo

LCIDConversionAttribute:

System.Runtime.InteropServices

Ldarg:

OpCodes

Ldarg_0:

OpCodes

Ldarg_1:

OpCodes

Ldarg_2:

OpCodes

Ldarg_3:

OpCodes

Ldarg_S:

OpCodes

Ldarga:

OpCodes

Ldarga_S:

OpCodes

Ldc_14:

OpCodes
Ldc_14_0:

OpCodes
Ldc_14_1:

OpCodes
Ldc_14_2:

OpCodes
Ldc_14_3:

OpCodes
Ldc_14_4:

OpCodes
Ldc_14_5:

OpCodes
Ldc_14_6:

OpCodes
Ldc_14_7:

OpCodes
Ldc_14_8:

OpCodes
Ldc_14_M1:

OpCodes
Ldc_14_5:

OpCodes
Ldc_18:

OpCodes
Ldc_R4:

OpCodes
Ldc_R8:

OpCodes
Ldelem_1:

OpCodes
Ldelem_11:

OpCodes
Ldelem_12:

OpCodes

Ldelem_I4:
 OpCodes
Ldelem_I8:
 OpCodes
Ldelem_R4:
 OpCodes
Ldelem_R8:
 OpCodes
Ldelem_Ref:
 OpCodes
Ldelem_U1:
 OpCodes
Ldelem_U2:
 OpCodes
Ldelem_U4:
 OpCodes
Ldelema:
 OpCodes
Ldfld:
 OpCodes
Ldflda:
 OpCodes
Ldftn:
 OpCodes
Ldind_I:
 OpCodes
Ldind_I1:
 OpCodes
Ldind_I2:
 OpCodes
Ldind_I4:
 OpCodes
Ldind_I8:
 OpCodes
Ldind_R4:
 OpCodes

Ldind_R8:
OpCodes
Ldind_Ref:
OpCodes
Ldind_U1:
OpCodes
Ldind_U2:
OpCodes
Ldind_U4:
OpCodes
Ldlen:
OpCodes
Ldloc:
OpCodes
Ldloc_0:
OpCodes
Ldloc_1:
OpCodes
Ldloc_2:
OpCodes
Ldloc_3:
OpCodes
Ldloc_S:
OpCodes
Ldloca:
OpCodes
Ldloca_S:
OpCodes
Ldnull:
OpCodes
Ldobj:
OpCodes
Ldsfld:
OpCodes
Ldsflda:
OpCodes

Ldstr:

OpCodes

Ldtoken:

OpCodes

Ldvirtftn:

OpCodes

Leave:

OpCodes

Leave_S:

OpCodes

LeaveDebugMode():

Process

LegalCopyright:

FileVersionInfo

LegalTrademarks:

FileVersionInfo

Length:

Array, BitArray, BufferedStream, Capture, FileInfo, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream, Stream, String, StringBuilder, XmlCharacterData

LengthRequired:

HttpStatusCode

LetterNumber:

UnicodeCategory

Level:

TraceSwitch

LicenseFile:

AppDomainSetup

LineNumber:

IXmlLineInfo, XmlException, XmlTextReader, XsltException

LinePosition:

IXmlLineInfo, XmlException, XmlTextReader, XsltException

LineSeparator:

UnicodeCategory

Linger:

SocketOptionName

LingerOption:

System.Net.Sockets

LingerState:

TcpClient

LingerTime:

LingerOption

ListDictionary:

System.Collections.Specialized

Listen():

Socket

Listeners:

Debug, Trace

ListSeparator:

TextInfo

Literal:

FieldAttributes

Load():

AppDomain, Assembly, XmlDocumentDocument, XmlDocument, XslTransform

LoadedAssembly:

AssemblyLoadEventArgs

LoaderExceptions:

ReflectionTypeLoadException

LoaderOptimization:

AppDomainSetup, System

LoaderOptimizationAttribute:

System

LoadFile():

Assembly

LoadFrom():

Assembly

LoadModule():

Assembly

LoadWithPartialName():

Assembly

LoadXml():

XmlDocument

Local:

XPathNamespaceScope

LocalAddress:

MulticastOption

LocalApplicationData:

SpecialFolder

LocalBuilder:

System.Reflection.Emit

LocalDataStoreSlot:

System

Locale:

UserPreferenceCategory

LocalEndpoint:

TcpListener

LocalEndPoint:

Socket

Localized:

GregorianCalendarTypes

Localloc:

OpCodes

LocalMachine:

Registry, RegistryHive

LocalName:

XmlAttribute, XmlCDataSection, XmlComment, XmlDeclaration, XmlDocument, XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference, XmlNode, XmlNodeReader, XmlNotation, XmlProcessingInstruction, XmlReader, XmlSignificantWhitespace, XmlText, XmlTextReader, XmlValidatingReader, XmlWhitespace, XPathNavigator

LocalPath:

Uri

LocalType:

LocalBuilder

Location:

Assembly, AssemblyBuilder

Lock():

FileStream

LockCookie:

System.Threading

Log:

EventLog, EventLogInstaller

Log():

Debugger, Math

Log10():

Math

LogDisplayName:

EventLog

LogFileName:

DefaultTraceListener

LogNameFromSourceName():

EventLog

Logoff:

SessionEndReasons

LongDatePattern:

DateTimeFormatInfo

LongLength:

Array

LongTimePattern:

DateTimeFormatInfo

LookupNamespace():

XmlNamespaceManager, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

LookupPrefix():

XmlNamespaceManager, XmlTextWriter, XmlWriter

Loopback:

IPAddress

Low:

TypeFilterLevel

LowercaseLetter:

UnicodeCategory

LowerFirst:

XmlCaseOrder

Lowest:

ThreadPriority, ThreadPriorityLevel

LowMemory:

SystemEvents

LPCArray:

UnmanagedType

LpcReceive:

ThreadWaitReason

LpcReply:

ThreadWaitReason

LPStr:

UnmanagedType

LPStruct:

UnmanagedType

LPTStr:

UnmanagedType

LPWStr:

UnmanagedType

m_idGenerator:

Formatter

m_objectQueue:

Formatter

MacCodePage:

TextInfo

MachineName:

Environment, EventLog, EventLogEntry, EventLogPermissionAttribute,
EventLogPermissionEntry, PerformanceCounter, PerformanceCounterCategory,
PerformanceCounterPermissionAttribute, PerformanceCounterPermissionEntry, Process

Macro:

OpCodeType

MainModule:

Process

MainWindowHandle:

Process

MainWindowTitle:

Process

Major:

Version

MajorVersion:

ComCompatibleVersionAttribute, TypeLibVersionAttribute

MakeRelative():

Uri

Managed:

MethodImplAttributes

ManagedMask:

MethodImplAttributes

ManifestResourceInfo:

System.Reflection

ManualResetEvent:

System.Threading

MarkLabel():

ILGenerator

MarkSequencePoint():

ILGenerator

Marshal:

System.Runtime.InteropServices

MarshalAsAttribute:

System.Runtime.InteropServices

MarshalByRefObject:

System

MarshalCookie:

MarshalAsAttribute

MarshalDirectiveException:

System.Runtime.InteropServices

MarshalType:

MarshalAsAttribute

MarshalTypeRef:

MarshalAsAttribute

Mask:

Section

Match:

System.Text.RegularExpressions

Match():

Attribute, Regex

MatchCollection:

System.Text.RegularExpressions

Matches():

Regex, XPathNavigator

MatchEvaluator:

System.Text.RegularExpressions

Math:

System

MathSymbol:

UnicodeCategory

Max:

AddressFamily, ProtocolFamily

Max():

Math

Maxargs:

IXsltContextFunction

MaxCapacity:

StringBuilder

MaxConnections:

SocketOptionName

MaxCookieSize:

CookieContainer

MaxGeneration:

GC

MaxIdleTime:

ServicePoint

Maximized:

ProcessWindowStyle

MaximumAutomaticRedirections:

HttpRequest

MaximumResponseHeadersLength:

HttpRequest

MaximumSize:

IsolatedStorage, IsolatedStorageFile

MaxIOVectorLength:

SocketFlags

MaxMethodImplVal:

MethodImplAttributes

MaxPort:

EndPoint

MaxServicePointIdleTime:

ServicePointManager

MaxServicePoints:

ServicePointManager

MaxValue:

Byte, Char, DateTime, Decimal, Double, Int16, Int32, Int64, SByte, Single, TimeSpan, UInt16, UInt32, UInt64

MaxWorkingSet:

Process

MediaType:

HttpRequest

Member:

ParameterInfo

MemberAccessException:

System

MemberAccessMask:

MethodAttributes

MemberCount:

SerializationInfo

MemberFilter:

System.Reflection

MemberImpl:

ParameterInfo

MemberInfo:

System.Reflection

MemberName:

DefaultMemberAttribute, MissingMemberException

MemberType:

ConstructorInfo, EventInfo, FieldInfo, MemberInfo, MethodInfo, PropertyInfo, Type

MemberTypes:

System.Reflection

MemberwiseClone():

Object

MemoryBarrier():

Thread

MemoryStream:

System.IO

Menu:

UserPreferenceCategory

Message:

ArgumentException, ArgumentOutOfRangeException, Authorization,
BadImageFormatException, EventLogEntry, Exception, FileLoadException,
FileNotFoundException, MissingFieldException, MissingMemberException,
MissingMethodException, ObjectDisposedException, ObsoleteAttribute, TypeLoadException,
XmlException, XPathException, XsltCompileException, XsltException

MessageLengthLimitExceeded:

WebExceptionStatus

Meta:

FlowControl

Method:

AttributeTargets, ComMemberType, Delegate, FileWebRequest, HttpWebRequest,
HttpWebResponse, MemberTypes, WebRequest

MethodAccessException:

System

MethodAttributes:

System.Reflection

MethodBase:

System.Reflection

MethodBuilder:

System.Reflection.Emit

MethodHandle:

ConstructorBuilder, MethodBase, MethodBuilder

MethodImplAttributes:

System.Reflection

MethodInfo:

System.Reflection

MethodName:

ISoapMessage, SoapMessage

MethodNotAllowed:

HttpStatusCode

MethodRental:

System.Reflection.Emit

METHODS_TO_SKIP:

StackTrace

MethodToken:

System.Reflection.Emit

MiddleEastFrench:

GregorianCalendarTypes

Millisecond:

DateTime

Milliseconds:

TimeSpan

Min():

Math

Minargs:

IXsltContextFunction

Minimized:

ProcessWindowStyle

Minor:

Version

MinorVersion:

ComCompatibleVersionAttribute, TypeLibVersionAttribute

MinPort:

IPEndPoint

MinusOne:

Decimal

Minute:

DateTime

Minutes:

TimeSpan

MinValue:

Byte, Char, DateTime, Decimal, Double, Int16, Int32, Int64, SByte, Single, TimeSpan, UInt16, UInt32, UInt64

MinWorkingSet:

Process

Missing:

System.Reflection, Type

MissingFieldException:

System

MissingMemberException:

System

MissingMethodException:

System

Mkrefany:

OpCodes

Mode:

PowerModeChangedEventArgs

ModifierLetter:

UnicodeCategory

ModifierSymbol:

UnicodeCategory

Module:

AttributeTargets, EnumBuilder, System.Reflection, Type, TypeBuilder, TypeDelegator

ModuleBuilder:

System.Reflection.Emit

ModuleMemorySize:

ProcessModule

ModuleName:

ProcessModule

ModuleResolve:

Assembly

ModuleResolveEventHandler:

System.Reflection

Modules:

Process

Monday:

DayOfWeek

Monitor:

System.Threading

MonitoringDescriptionAttribute:

System.Diagnostics

Month:

DateTime

MonthDayPattern:

DateTimeFormatInfo

MonthNames:

DateTimeFormatInfo

Mouse:

UserPreferenceCategory

Move():

Directory, File

Moved:

HttpStatusCode

MovedPermanently:

HttpStatusCode

MoveNext():

CharEnumerator, IEnumerator, SerializationInfoEnumerator, StringEnumerator,
TextElementEnumerator, XPathNodeIterator

MoveTo():

DirectoryInfo, FileInfo, XPathNavigator

MoveToAttribute():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

MoveToContent():

XmlReader

MoveToElement():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

MoveToFirst():

XPathNavigator

MoveToFirstAttribute():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

MoveToFirstChild():

XPathNavigator

MoveToFirstNamespace():

XPathNavigator

MoveToId():

XPathNavigator

MoveToNamespace():

XPathNavigator

MoveToNext():

XPathNavigator

MoveToNextAttribute():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

MoveToNextNamespace():

XPathNavigator
MoveToParent():

XPathNavigator
MoveToPrevious():

XPathNavigator
MoveToRoot():

XPathNavigator
MTA:

ApartmentState
MTAThreadAttribute:

System
Mul:

OpCodes
Mul_Ovf:

OpCodes
Mul_Ovf_Un:

OpCodes
MulticastDelegate:

System
MulticastInterface:

SocketOptionName
MulticastLoopback:

SocketOptionName
MulticastNotSupportedException:

System
MulticastOption:

System.Net.Sockets
MulticastTimeToLive:

SocketOptionName
MultiDomain:

LoaderOptimization
MultiDomainHost:

LoaderOptimization
Multiline:

RegexOptions
MultipleChoices:

HttpStatusCode

Multiply():

Decimal

Mutex:

System.Threading

MyComputer:

SpecialFolder

MyMusic:

SpecialFolder

MyPictures:

SpecialFolder

Name:

AssemblyName, ConstructorBuilder, Cookie, CultureInfo, DirectoryInfo, EnumBuilder, EventLogTraceListener, FieldBuilder, FileInfo, FileStream, FileSystemEventArgs, FileSystemInfo, MemberInfo, MethodBuilder, Module, OpCode, ParameterBuilder, ParameterInfo, PropertyBuilder, RegexCompilationInfo, RegionInfo, RegistryKey, ResolveEventArgs, SerializationEntry, SerializationInfoEnumerator, Thread, TraceListener, TypeBuilder, TypeDelegator, WaitForChangedResult, XmlAttribute, XmlCDATASection, XmlComment, XmlDeclaration, XmlDocument, XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference, XmlNode, XmlNodeReader, XmlNotation, XmlProcessingInstruction, XmlQualifiedName, XmlReader, XmlSignificantWhitespace, XmlText, XmlTextReader, XmlValidatingReader, XmlWhitespace, XPathNavigator

NameImpl:

ParameterInfo

NameObjectCollectionBase:

System.Collections.Specialized

NameResolutionFailure:

WebExceptionStatus

Namespace:

EnumBuilder, RegexCompilationInfo, Type, TypeBuilder, TypeDelegator, XmlQualifiedName, XPathNodeType

NamespaceManager:

XmlParserContext

Namespaces:

XmlTextReader, XmlTextWriter, XmlValidatingReader

NamespaceURI:

XmlAttribute, XmlElement, XmlNode, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

NameTable:

System.Xml, XmlDocument, XmlNamespaceManager, XmlNodeReader, XmlParserContext,

XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator
NameValueCollection:

System.Collections.Specialized
NaN:

Double, Single
NaNSymbol:

NumberFormatInfo
Native:

MethodImplAttributes
NativeName:

CultureInfo
NativeOverlapped:

System.Threading
Navigator:

XPathResultType
NCName:

XmlTokenizedType
ND:

ProtocolType
Neg:

OpCodes
Negate():

Decimal, TimeSpan
NegativeInfinity:

Double, Single
NegativeInfinitySymbol:

NumberFormatInfo
NegativeSign:

NumberFormatInfo
NestedAssembly:

TypeAttributes
NestedFamANDAssem:

TypeAttributes
NestedFamily:

TypeAttributes
NestedFamORAssem:

TypeAttributes

NestedPrivate:

TypeAttributes

NestedPublic:

TypeAttributes

NestedType:

MemberTypes

NetBios:

AddressFamily, ProtocolFamily

NetworkAccess:

System.Net

NetworkCredential:

System.Net

NetworkDesigners:

AddressFamily, ProtocolFamily

NetworkStream:

System.Net.Sockets

NetworkToHostOrder():

IPAddress

NeutralCultures:

CultureTypes

Newarr:

OpCodes

NewGuid():

Guid

NewLine:

Environment, TextWriter

Newobj:

OpCodes

NewParent:

XmlNodeChangedEventArgs

NewSlot:

MethodAttributes

Next:

FlowControl

Next():

Random

NextBytes():

Random

NextDouble():

Random

NextMatch():

Match

NextSample():

PerformanceCounter

NextSibling:

XmlElement, XmlLinkedNode, XmlNode

NextValue():

PerformanceCounter

NMTOKEN:

XmlTokenizedType

NMTOKENS:

XmlTokenizedType

NoChecksum:

SocketOptionName

NoContent:

HttpStatusCode

NoCurrentDateDefault:

DateTimeStyles

Node:

XmlNodeChangedEventArgs

NodeChanged:

XmlDocument

NodeChanging:

XmlDocument

NodeInserted:

XmlDocument

NodeInserting:

XmlDocument

NoDelay:

SocketOptionName, TcpClient

NodeRemoved:

XmlDocument

NodeRemoving:

XmlDocument

NodeSet:

XPathResultType

NodeType:

XmlAttribute, XmlCDATASection, XmlComment, XmlDeclaration, XmlDocument, XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference, XmlNode, XmlNodeReader, XmlNotation, XmlProcessingInstruction, XmlReader, XmlSignificantWhitespace, XmlText, XmlTextReader, XmlValidatingReader, XmlWhitespace, XPathNavigator

NoInlining:

MethodImplAttributes

NonAuthoritativeInformation:

HttpStatusCode

None:

AssemblyNameFlags, AssemblyRegistrationFlags, CharSet, ClassInterfaceType, CompareOptions, DateTimeStyles, EventAttributes, EventLogPermissionAccess, FileShare, Formatting, IPAddress, IsolatedStorageScope, NumberStyles, ParameterAttributes, PerformanceCounterPermissionAccess, PropertyAttributes, RegexOptions, SocketFlags, ValidationType, WhitespaceHandling, XmlCaseOrder, XmlNodeType, XmlSpace, XmlTokenizedType

NonpagedSystemMemorySize:

Process

NonPublic:

BindingFlags

NonSerializedAttribute:

System

NonSpacingMark:

UnicodeCategory

Nop:

OpCodes

Normal:

FileAttributes, GCHandleType, ProcessPriorityClass, ProcessWindowStyle, ThreadPriority, ThreadPriorityLevel

Normalization:

XmlTextReader

Normalize():

INormalizeForIsolatedStorage, XmlNode

Not:

OpCodes

Not():

BitArray

NotAcceptable:

HttpStatusCode

Notation:

XmlNodeType

NOTATION:

XmlTokenizedType

NotationName:

XmlEntity

Notations:

XmlDocumentType

NotContentIndexed:

FileAttributes

NotFiniteNumberException:

System

NotFound:

HttpStatusCode

NotifyFilter:

FileSystemWatcher

NotifyFilters:

System.IO

NotImplemented:

HttpStatusCode

NotImplementedException:

System

NotModified:

HttpStatusCode

NotPublic:

TypeAttributes

NotSerialized:

FieldAttributes

NotSpecified:

LoaderOptimization

NotSupportedException:

System

Now:

DateTime

NS:

AddressFamily, ProtocolFamily

Nternal:

OpCodeType

Null:

BinaryWriter, Stream, StreamReader, StreamWriter, TextReader, TextWriter

NullReferenceException:

System

Number:

NumberStyles, XmlDataType, XPathResultType

NumberDecimalDigits:

NumberFormatInfo

NumberDecimalSeparator:

NumberFormatInfo

NumberFormat:

CultureInfo

NumberFormatInfo:

System.Globalization

NumberGroupSeparator:

NumberFormatInfo

NumberGroupSizes:

NumberFormatInfo

NumberNegativePattern:

NumberFormatInfo

NumberOfItems32:

PerformanceCounterType

NumberOfItems64:

PerformanceCounterType

NumberOfItemsHEX32:

PerformanceCounterType

NumberOfItemsHEX64:

PerformanceCounterType

NumberStyles:

System.Globalization
NumParamBytes():

Marshal
Object:

System, TypeCode
ObjectCreationDelegate:

System.Runtime.InteropServices
ObjectDisposedException:

System
ObjectIDGenerator:

System.Runtime.Serialization
ObjectManager:

System.Runtime.Serialization
ObjectName:

ObjectDisposedException
ObjectType:

SerializationEntry, SerializationInfoEnumerator
Objmodel:

OpCodeType
ObsoleteAttribute:

System
OEMCodePage:

TextInfo
Off:

TraceLevel
OffendingNumber:

NotFiniteNumberException
Offline:

FileAttributes
Offset:

Section
OFFSET_UNKNOWN:

StackFrame
OffsetHigh:

NativeOverlapped, Overlapped
OffsetLow:

NativeOverlapped, Overlapped

OffsetOf():

Marshal

OK:

HttpStatusCode

OldFullPath:

RenamedEventArgs

OldName:

RenamedEventArgs, WaitForChangedEventArgs

OldParent:

XmlNodeChangedEventArgs

OnChanged():

FileSystemWatcher

OnClear():

CollectionBase, DictionaryBase, EventLogPermissionEntryCollection,
PerformanceCounterPermissionEntryCollection

OnClearComplete():

CollectionBase, DictionaryBase

OnCreated():

FileSystemWatcher

OnDeleted():

FileSystemWatcher

OnDeserialization():

AssemblyName, Hashtable, IDeserializationCallback, NameObjectCollectionBase,
WebHeaderCollection

One:

Decimal

OnError():

FileSystemWatcher

OnExited():

Process

OnGet():

DictionaryBase

OnInsert():

CollectionBase, CounterCreationDataCollection, DictionaryBase,
EventLogPermissionEntryCollection, PerformanceCounterPermissionEntryCollection

OnInsertComplete():

CollectionBase, DictionaryBase

OnRemove():

CollectionBase, DictionaryBase, EventLogPermissionEntryCollection,
PerformanceCounterPermissionEntryCollection

OnRemoveComplete():

CollectionBase, DictionaryBase

OnRenamed():

FileSystemWatcher

OnSet():

CollectionBase, DictionaryBase, EventLogPermissionEntryCollection,
PerformanceCounterPermissionEntryCollection

OnSetComplete():

CollectionBase, DictionaryBase

OnSwitchSettingChanged():

Switch, TraceSwitch

OnValidate():

CollectionBase, DictionaryBase

OpCode:

System.Reflection.Emit

OpCodes:

System.Reflection.Emit

OpCodeType:

OpCode, System.Reflection.Emit

Open:

FileMode

Open():

File, FileInfo

OpenOrCreate:

FileMode

OpenPunctuation:

UnicodeCategory

OpenRead():

File, FileInfo, WebClient

OpenRemoteBaseKey():

RegistryKey

OpenStandardError():

Console

OpenStandardInput():

Console

OpenStandardOutput():

Console

OpenSubKey():

RegistryKey

OpenText():

File, FileInfo

OpenWrite():

File, FileInfo, WebClient

OperandType:

OpCode, System.Reflection.Emit

OperatingSystem:

System

OPTIL:

MethodImplAttributes

Optional:

ParameterAttributes

OptionalAttribute:

System.Runtime.InteropServices

OptionalCalendars:

CultureInfo

OptionalParamBinding:

BindingFlags

Options:

Regex, RegexCompilationInfo

Or:

OpCodes

Or():

BitArray

Ordinal:

CompareOptions

OriginalFilename:

FileVersionInfo

OriginalPath:

FileSystemInfo

OriginalString:

SortKey

Osi:

AddressFamily, ProtocolFamily

OSVersion:

Environment

Other:

StreamingContextStates

OtherLetter:

UnicodeCategory

OtherNotAssigned:

UnicodeCategory

OtherNumber:

UnicodeCategory

OtherPunctuation:

UnicodeCategory

OtherSymbol:

UnicodeCategory

Out:

Console, ParameterAttributes

OutAttribute:

System.Runtime.InteropServices

OuterXml:

XmlEntity, XmlNode, XmlNotation

OutOfBand:

SocketFlags

OutOfBandInline:

SocketOptionName

OutOfMemoryException:

System

OutputStream:

BinaryWriter

OverflowException:

System

Overlapped:

System.Threading

OwnerDocument:

XmlAttribute, XmlDocument, XmlDocumentFragment, XmlElement, XmlNode

OwnerElement:

XmlAttribute

Pack:

StructLayoutAttribute

Pack():

Overlapped

PacketInformation:

SocketOptionName

PackingSize:

System.Reflection.Emit, TypeBuilder

PadLeft():

String

PadRight():

String

PagedMemorySize:

Process

PagedSystemMemorySize:

Process

PageIn:

ThreadWaitReason

PageOut:

ThreadWaitReason

PaletteChanged:

SystemEvents

ParagraphSeparator:

UnicodeCategory

ParamArrayAttribute:

System

Parameter:

AttributeTargets

ParameterAttributes:

System.Reflection

ParameterBuilder:

System.Reflection.Emit

ParameterInfo:

System.Reflection

ParameterModifier:

System.Reflection

ParameterToken:

System.Reflection.Emit

ParameterType:

ParameterInfo

ParamName:

ArgumentException

ParamNames:

ISoapMessage, SoapMessage

ParamTypes:

ISoapMessage, SoapMessage

ParamValues:

ISoapMessage, SoapMessage

Parent:

CultureInfo, DirectoryInfo

ParentNode:

XmlAttribute, XmlDocumentFragment, XmlNode

Parse():

Boolean, Byte, Char, DateTime, Decimal, Double, Enum, Int16, Int32, Int64, IPAddress, SByte, Single, TimeSpan, UInt16, UInt32, UInt64, Uri

ParseCombiningCharacters():

StringInfo

ParseExact():

DateTime

Partial:

SocketFlags

PartialContent:

HttpStatusCode

Password:

NetworkCredential, UriBuilder

Path:

Cookie, FileSystemWatcher, System.IO, UriBuilder, UriPartial

PathAndQuery:

Uri

PathSeparator:

Path

PathTooLongException:

System.IO

Pattern:

RegexCompilationInfo

PaymentRequired:

HttpStatusCode

PeakPagedMemorySize:

Process

PeakVirtualMemorySize:

Process

PeakWorkingSet:

Process

Peek:

SocketFlags

Peek():

Queue, Stack, StreamReader, StringReader, TextReader

PeekChar():

BinaryReader

PEFileKinds:

System.Reflection.Emit

Pending:

WebExceptionStatus

Pending():

TcpListener

PercentDecimalDigits:

NumberFormatInfo

PercentDecimalSeparator:

NumberFormatInfo

PercentGroupSeparator:

NumberFormatInfo

PercentGroupSizes:

NumberFormatInfo

PercentNegativePattern:

NumberFormatInfo
PercentPositivePattern:

NumberFormatInfo
PercentSymbol:

NumberFormatInfo
PerDomainCapacity:

CookieContainer
PerformanceCounter:

System.Diagnostics
PerformanceCounterCategory:

System.Diagnostics
PerformanceCounterInstaller:

System.Diagnostics
PerformanceCounterPermission:

System.Diagnostics
PerformanceCounterPermissionAccess:

System.Diagnostics
PerformanceCounterPermissionAttribute:

System.Diagnostics
PerformanceCounterPermissionEntry:

System.Diagnostics
PerformanceCounterPermissionEntryCollection:

System.Diagnostics
PerformanceCounterType:

System.Diagnostics
PerformanceData:

Registry, RegistryHive
PerMilleSymbol:

NumberFormatInfo
PermissionAccess:

EventLogPermissionAttribute, EventLogPermissionEntry,
PerformanceCounterPermissionAttribute, PerformanceCounterPermissionEntry
PermissionEntries:

EventLogPermission, PerformanceCounterPermission
Persistence:

StreamingContextStates
Personal:

SpecialFolder

Phi:

FlowControl

Pl:

Math

Pinned:

GCHandleType

PinvokeImpl:

FieldAttributes, MethodAttributes

Pipelined:

HttpRequest

PipelineFailure:

WebExceptionStatus

Platform:

OperatingSystem

PlatformID:

System

PlatformNotSupportedException:

System

PMDesignator:

DateTimeFormatInfo

Pointer:

System.Reflection

Policy:

UserPreferenceCategory

Poll():

Socket

Pop:

OpCodes

Pop():

Stack

Pop0:

StackBehaviour

Pop1:

StackBehaviour

Pop1_pop1:

StackBehaviour

Popi:

StackBehaviour

Popi_pop1:

StackBehaviour

Popi_popi:

StackBehaviour

Popi_popi_popi:

StackBehaviour

Popi_popi8:

StackBehaviour

Popi_popr4:

StackBehaviour

Popi_popr8:

StackBehaviour

Popref:

StackBehaviour

Popref_pop1:

StackBehaviour

Popref_popi:

StackBehaviour

Popref_popi_popi:

StackBehaviour

Popref_popi_popi8:

StackBehaviour

Popref_popi_popr4:

StackBehaviour

Popref_popi_popr8:

StackBehaviour

Popref_popi_popref:

StackBehaviour

PopScope():

XmlNamespaceManager

PopulateObjectMembers():

FormatterServices

Port:

Cookie, EndpointPermission, IPEndPoint, SocketPermissionAttribute, Uri, UriBuilder

Position:

BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream, ParameterBuilder, ParameterInfo, Stream

PositionImpl:

ParameterInfo

PositiveInfinity:

Double, Single

PositiveInfinitySymbol:

NumberFormatInfo

PositiveSign:

NumberFormatInfo

Pow():

Math

Power:

UserPreferenceCategory

PowerModeChanged:

SystemEvents

PowerModeChangedEventArgs:

Microsoft.Win32

PowerModeChangedEventHandler:

Microsoft.Win32

PowerModes:

Microsoft.Win32

PreAuthenticate:

FileWebRequest, HttpWebRequest, WebRequest

PreAuthenticate():

AuthenticationManager, IAuthenticationModule

PreconditionFailed:

HttpStatusCode

Prefix:

OpCodeType, XmlAttribute, XmlElement, XmlNode, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader, XPathNavigator

Prefix1:

OpCodes

Prefix2:

OpCodes

Prefix3:

OpCodes

Prefix4:

OpCodes

Prefix5:

OpCodes

Prefix6:

OpCodes

Prefix7:

OpCodes

Prefixref:

OpCodes

Prelink():

Marshal

PrelinkAll():

Marshal

Prepend():

XmlAttributeCollection

PrependChild():

XmlNode

Preserve:

XmlSpace

PreserveSig:

DllImportAttribute, MethodImplAttributes

PreserveSigAttribute:

System.Runtime.InteropServices

PreserveWhitespace:

XmlDocument

PreserveWhitespace():

XsltContext

PreviousSibling:

XmlLinkedNode, XmlNode

Primitive:

OpCodeType

Priority:

Thread

PriorityBoostEnabled:

Process, ProcessThread

PriorityClass:

Process

PriorityLevel:

ProcessThread

Private:

FieldAttributes, MethodAttributes, ResourceAttributes

PrivateBinPath:

AppDomainSetup

PrivateBinPathProbe:

AppDomainSetup

PrivateBuild:

FileVersionInfo

PrivateMemorySize:

Process

PrivateScope:

FieldAttributes, MethodAttributes

PrivateUse:

UnicodeCategory

PrivilegedProcessorTime:

Process, ProcessThread

Process:

System.Diagnostics

ProcessExit:

AppDomain

ProcessingInstruction:

XmlNodeType, XPathNodeType

ProcessModule:

System.Diagnostics

ProcessModuleCollection:

System.Diagnostics

ProcessName:

Process

ProcessorAffinity:

Process, ProcessThread

ProcessPriorityClass:

System.Diagnostics

ProcessStartInfo:

System.Diagnostics

ProcessThread:

System.Diagnostics

ProcessThreadCollection:

System.Diagnostics

ProcessWindowStyle:

System.Diagnostics

Product:

AssemblyProductAttribute

ProductBuildPart:

FileVersionInfo

ProductMajorPart:

FileVersionInfo

ProductMinorPart:

FileVersionInfo

ProductName:

FileVersionInfo

ProductPrivatePart:

FileVersionInfo

ProductVersion:

FileVersionInfo

ProgIdAttribute:

System.Runtime.InteropServices

ProgramFiles:

SpecialFolder

Programs:

SpecialFolder

Prolog:

WriteState

Property:

AttributeTargets, MemberTypes

PropertyAttributes:

System.Reflection

PropertyBuilder:

System.Reflection.Emit

PropertyInfo:

System.Reflection

PropertyToken:

PropertyBuilder, System.Reflection.Emit

PropertyType:

PropertyBuilder, PropertyInfo

PropGet:

ComMemberType

PropSet:

ComMemberType

ProtectionRealm:

Authorization

ProtocolError:

WebExceptionStatus

ProtocolFamily:

System.Net.Sockets

ProtocolType:

Socket, System.Net.Sockets

ProtocolVersion:

HttpRequest, HttpResponse, ServicePoint

ProtocolViolationException:

System.Net

Proxy:

FileWebRequest, HttpRequest, WebRequest

ProxyAuthenticationRequired:

HttpStatusCode

ProxyNameResolutionFailure:

WebExceptionStatus

PtrToStringAnsi():

Marshal

PtrToStringAuto():

Marshal

PtrToStringBSTR():

Marshal

PtrToStringUni():

Marshal

PtrToStructure():

Marshal

Public:

BindingFlags, FieldAttributes, MethodAttributes, ResourceAttributes, TypeAttributes

PublicId:

XmlDocumentType, XmlEntity, XmlNotation, XmlParserContext

PublicKey:

AssemblyNameFlags, StrongNameKeyPair

Pulse():

Monitor

PulseAll():

Monitor

Pup:

AddressFamily, ProtocolFamily, ProtocolType

Push():

Stack

Push0:

StackBehaviour

Push1:

StackBehaviour

Push1_push1:

StackBehaviour

Pushi:

StackBehaviour

Pushi8:

StackBehaviour

Pushr4:

StackBehaviour

Pushr8:

StackBehaviour

Pushref:

StackBehaviour

PushScope():

XmlNamespaceManager

PutDispProperty:

BindingFlags

PutRefDispProperty:

BindingFlags

QName:

XmlTokenizedType

Query:

Uri, UriBuilder

QueryInterface():

Marshal

QueryString:

WebClient

Queue:

System.Collections

QueueUserWorkItem():

ThreadPool

QuoteChar:

XmlNodeReader, XmlReader, XmlTextReader, XmlTextWriter, XmlValidatingReader

R4:

UnmanagedType

R8:

UnmanagedType

RaiseDeserializationEvent():

ObjectManager

Random:

System

Rank:

Array

RankException:

System

RateOfCountsPerSecond32:

PerformanceCounterType

RateOfCountsPerSecond64:

PerformanceCounterType

Raw:

ProtocolType, SocketType

RawBase:

PerformanceCounterType

RawFraction:

PerformanceCounterType

RawValue:

CounterSample, InstanceData, PerformanceCounter

Rdm:

SocketType

Read:

FileAccess, FileShare

Read():

BinaryReader, BufferedStream, Console, FileStream, IsolatedStorageFileStream,
MemoryStream, NetworkStream, Stream, StreamReader, StringReader, TextReader,
XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

Read7BitEncodedInt():

BinaryReader

ReadAttributeValue():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

ReadBase64():

XmlTextReader

ReadBinHex():

XmlTextReader

ReadBlock():

TextReader

ReadBoolean():

BinaryReader

ReadByte():

BinaryReader, BufferedStream, FileStream, IsolatedStorageFileStream, Marshal,
MemoryStream, Stream

ReadBytes():

BinaryReader

ReadCategory():

PerformanceCounterCategory

ReadChar():

BinaryReader

ReadChars():

BinaryReader, XmlTextReader

ReadDecimal():

BinaryReader

ReadDouble():

BinaryReader

ReadElementString():

XmlReader

ReadEndElement():

XmlReader

Reader:

XmlValidatingReader

ReaderWriterLock:

System.Threading

ReadInnerXml():

XmlReader

ReadInt16():

BinaryReader, Marshal

ReadInt32():

BinaryReader, Marshal

ReadInt64():

BinaryReader, Marshal

ReadIntPtr():

Marshal

ReadLine():

Console, StreamReader, StringReader, TextReader

ReadNode():

XmlDocument

ReadOnly:

FileAttributes, PerformanceCounter

ReadOnly():

ArrayList, CultureInfo, DateTimeFormatInfo, NumberFormatInfo

ReadOnlyCollectionBase:

System.Collections

ReadOuterXml():

XmlReader

ReadSByte():

BinaryReader

ReadSingle():

BinaryReader

ReadStartElement():

XmlReader

ReadState:

System.Xml, XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

ReadString():

BinaryReader, XmlNodeReader, XmlReader, XmlValidatingReader

ReadToEnd():

StreamReader, StringReader, TextReader

ReadTypedValue():

XmlValidatingReader

ReadUInt16():

BinaryReader

ReadUInt32():

BinaryReader

ReadUInt64():

BinaryReader

ReadWrite:

FileAccess, FileShare

ReadWriteTimeout:

HttpRequest

Ready:

ThreadState

ReAllocCoTaskMem():

Marshal

ReAllocHGlobal():

Marshal

RealTime:

ProcessPriorityClass

Reason:

SessionEndedEventArgs, SessionEndingEventArgs

Receive:

SocketShutdown

Receive():

Socket, UdpClient

ReceiveBuffer:

SocketOptionName

ReceiveBufferSize:

TcpClient

ReceiveFailure:

WebExceptionStatus

ReceiveFrom():

Socket

ReceiveLowWater:

SocketOptionName

ReceiveTimeout:

SocketOptionName, TcpClient

Recent:

SpecialFolder

RecordArrayElementFixup():

ObjectManager

RecordDelayedFixup():

ObjectManager

RecordFixup():

ObjectManager

Redirect:

HttpStatusCode

RedirectKeepVerb:

HttpStatusCode

RedirectMethod:

HttpStatusCode

RedirectStandardError:

ProcessStartInfo

RedirectStandardInput:

ProcessStartInfo

RedirectStandardOutput:

ProcessStartInfo

Refanytype:

OpCodes

Refanyval:

OpCodes

ReferencedAssembly:

ManifestResourceInfo

ReferenceEquals():

Object

Referer:

HttpRequest

ReflectedType:

ConstructorBuilder, EnumBuilder, FieldBuilder, MemberInfo, MethodBuilder, PropertyBuilder,
Type, TypeBuilder

ReflectionTypeLoadException:

System.Reflection

Refresh():

FileInfo, Process

Regex:

System.Text.RegularExpressions

RegexCompilationInfo:

System.Text.RegularExpressions

RegexOptions:

System.Text.RegularExpressions

RegionInfo:

System.Globalization

Register():

AuthenticationManager

RegisterAssembly():

IService, RegistrationServices

RegisteredModules:

AuthenticationManager

RegisteredWaitHandle:

System.Threading

RegisterObject():

ObjectManager

RegisterObjectCreationCallback():

ExtensibleClassFactory

RegisterPrefix():

WebRequest

RegisterTypeForComClients():

RegistrationServices, RegistrationServices

RegisterWaitForSingleObject():

ThreadPool

RegistrationServices:

System.Runtime.InteropServices

Registry:

Microsoft.Win32

RegistryHive:

Microsoft.Win32

RegistryKey:

Microsoft.Win32

RelativeSearchPath:

AppDomain

Release():

Marshal

ReleaseComObject():

Marshal

ReleaseLock():

ReaderWriterLock

ReleaseMutex():

Mutex

ReleaseReaderLock():

ReaderWriterLock

ReleaseThreadCache():

Marshal

ReleaseWriterLock():

ReaderWriterLock

Rem:

OpCodes

Rem_Un:

OpCodes

Remainder():

Decimal

RemoteEndPoint:

Socket

Remoting:

StreamingContextStates

Remove:

XmlNodeChangedAction

Remove():

ArrayList, CounterCreationDataCollection, CredentialCache, Delegate,
 EventLogPermissionEntryCollection, Hashtable, HybridDictionary, IDictionary, IList,
 IsolatedStorage, IsolatedStorageFile, ListDictionary, NameValueCollection,
 PerformanceCounterPermissionEntryCollection, ProcessThreadCollection, SortedList, String,
 StringBuilder, StringCollection, StringDictionary, TraceListenerCollection, WebHeaderCollection,
 XmlAttributeCollection

RemoveAll():

Delegate, XmlAttributeCollection, XmlElement, XmlNode

RemoveAllAttributes():

XmlElement

RemoveAt():

ArrayList, CollectionBase, IList, SortedList, StringCollection, TraceListenerCollection,
 XmlAttributeCollection

RemoveAttribute():

XmlElement

RemoveAttributeAt():

XmlElement

RemoveAttributeNode():

XmlElement

RemoveChild():

XmlNode

RemoveEventHandler():

EventInfo

RemoveExtensionObject():

XsltArgumentList

RemoveImpl():

Delegate, MulticastDelegate

RemoveInstance():

PerformanceCounter

RemoveNamedItem():

XmlNamedNodeMap

RemoveNamespace():

XmlNamespaceManager

RemoveParam():

XsltArgumentList

RemoveRange():

ArrayList

RemoveSurrogate():

SurrogateSelector

Renamed:

FileSystemWatcher, WatcherChangeTypes

RenamedEventArgs:

System.IO

RenamedEventHandler:

System.IO

ReorderArgumentArray():

Binder

ReparsedPoint:

FileAttributes

Repeat():

ArrayList

Replace():

Regex, String, StringBuilder

ReplaceChild():

XmlNode

ReplaceData():

XmlCharacterData

ReplacementStrings:

EventLogEntry

RequestCanceled:

WebExceptionStatus

RequestedRangeNotSatisfiable:

HttpStatusCode

RequestEntityTooLarge:

HttpStatusCode

RequestTimeout:

HttpStatusCode

RequestUri:

FileWebRequest, HttpWebRequest, WebRequest

RequestUriTooLong:

HttpStatusCode

RequireSecObject:

MethodAttributes

ReRegisterForFinalize():

GC

Reserved2:

PropertyAttributes

Reserved3:

ParameterAttributes, PropertyAttributes

Reserved4:

ParameterAttributes, PropertyAttributes

ReservedMask:

EventAttributes, FieldAttributes, MethodAttributes, ParameterAttributes, PropertyAttributes,
TypeAttributes

Reset():

AutoResetEvent, CharEnumerator, IEnumerator, ManualResetEvent,
SerializationInfoEnumerator, StringEnumerator, TextElementEnumerator

ResetAbort():

Thread

ResetContent:

HttpStatusCode

ResetIdealProcessor():

ProcessThread

ResetState():

XmlTextReader

Resolve():

Dns

ResolveEntity():

XmlNodeReader, XmlReader, XmlTextReader, XmlValidatingReader

ResolveEventArgs:

System

ResolveEventHandler:

System

ResolveFunction():

XsltContext

ResolveUri():

XmlResolver, XmlSecureResolver

ResolveVariable():

XsltContext

ResourceAttributes:

System.Reflection

ResourceLocation:

ManifestResourceInfo, System.Reflection

ResourceResolve:

AppDomain

Responding:

Process

Response:

WebException

ResponseHeaders:

WebClient

ResponseUri:

FileWebResponse, HttpWebResponse, WebResponse

RestoreLock():

ReaderWriterLock

Result():

Match

Resume:

PowerModes

Resume():

Thread

Ret:

OpCodes

Retargetable:

AssemblyNameFlags

Rethrow:

OpCodes

Return:

FlowControl

ReturnType:

ConstructorBuilder, IXsltContextFunction, MethodBuilder, MethodInfo, XPathExpression

ReturnTypeCustomAttributes:

MethodBuilder, MethodInfo

ReturnValue:

AttributeTargets

RetVal:

ParameterAttributes

ReuseAddress:

SocketOptionName

ReuseSlot:

MethodAttributes

Reverse():

Array, ArrayList

Revision:

Version

RevisionNumber:

ComCompatibleVersionAttribute

RFC1123Pattern:

DateTimeFormatInfo

RightToLeft:

Regex, RegexOptions

Roaming:

IsolatedStorageScope

Rollback():

EventLogInstaller, PerformanceCounterInstaller

Root:

DirectoryInfo, XPathNodeType

Round():

Decimal, Math

RTSpecialName:

EventAttributes, FieldAttributes, MethodAttributes, PropertyAttributes, TypeAttributes

Run:

AssemblyBuilderAccess

RunAndSave:

AssemblyBuilderAccess

Running:

ThreadState

Runtime:

MethodImplAttributes

RuntimeEnvironment:

System.Runtime.InteropServices

RuntimeTypeHandle:

System

[\[Team LiB \]](#)

◀ PREVIOUS NEXT ▶

S-Z

SafeArray:

UnmanagedType

SafeArrayRankMismatchException:

System.Runtime.InteropServices

SafeArraySubType:

MarshalAsAttribute

SafeArrayTypeMismatchException:

System.Runtime.InteropServices

SafeArrayUserDefinedSubType:

MarshalAsAttribute

Same:

XmlNodeOrder

Sample:

InstanceData

Sample():

Random

SampleBase:

PerformanceCounterType

SampleCounter:

PerformanceCounterType

SampleFraction:

PerformanceCounterType

Saturday:

DayOfWeek

Save:

AssemblyBuilderAccess

Save():

AssemblyBuilder, XmlDocument

SByte:

System, TypeCode

Schedule():

Formatter

Schema:

ValidationType

Schemas:

XmlValidatingReader

SchemaType:

XmlValidatingReader

Scheme:

Uri, UriBuilder, UriPartial

SchemeDelimiter:

Uri

Scope:

IsolatedStorage

ScopeId:

IPAddress

ScopeName:

Module

Screensaver:

UserPreferenceCategory

Sealed:

TypeAttributes

Second:

DateTime

Seconds:

TimeSpan

Section:

System.Collections.Specialized

Secure:

Cookie

SecureChannelFailure:

WebExceptionStatus

Security:

NotifyFilters

SecurityProtocol:

ServicePointManager

SecurityProtocolType:

System.Net

Seek():

BinaryWriter, BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream,
NetworkStream, Stream

SeekOrigin:

System.IO

SeeOther:

HttpStatusCode

Segments:

Uri

SEHException:

System.Runtime.InteropServices

Select:

GlobalProxySelection

Select():

Socket, XPathNavigator

SelectAncestors():

XPathNavigator

SelectChildren():

XPathNavigator

SelectDescendants():

XPathNavigator

SelectError:

SelectMode

SelectMethod():

Binder

SelectMode:

System.Net.Sockets

SelectNodes():

XmlNode

SelectProperty():

Binder

SelectRead:

SelectMode

SelectSingleNode():

XmlNode

SelectWrite:

SelectMode

Send:

SocketShutdown

Send():

Socket, UdpClient

SendBuffer:

SocketOptionName

SendBufferSize:

TcpClient

SendChunked:

HttpWebRequest

SendFailure:

WebExceptionStatus

SendLowWater:

SocketOptionName

SendTimeout:

SocketOptionName, TcpClient

SendTo:

SpecialFolder

SendTo():

Socket

Seqpacket:

SocketType

Sequential:

LayoutKind

SequentialLayout:

TypeAttributes

Serializable:

TypeAttributes

SerializableAttribute:

System

SerializationBinder:

System.Runtime.Serialization

SerializationEntry:

System.Runtime.Serialization

SerializationException:

System.Runtime.Serialization

SerializationInfo:

System.Runtime.Serialization

SerializationInfoEnumerator:

System.Runtime.Serialization

Serialize():

EndPoint, Formatter, IFormatter, IPEndPoint

Server:

HttpWebResponse

ServerFault:

System.Runtime.Serialization.Formatters

ServerProtocolViolation:

WebExceptionStatus

ServicePoint:

HttpWebRequest, System.Net

ServicePointManager:

System.Net

ServiceUnavailable:

HttpStatusCode

SessionEnded:

SystemEvents

SessionEndedEventArgs:

Microsoft.Win32

SessionEndedEventHandler:

Microsoft.Win32

SessionEnding:

SystemEvents

SessionEndingEventArgs:

Microsoft.Win32

SessionEndingEventHandler:

Microsoft.Win32

SessionEndReasons:

Microsoft.Win32

Set():

AutoResetEvent, BitArray, ManualResetEvent, NameValueCollection, WebHeaderCollection

SetAddOnMethod():

EventBuilder

SetAll():

BitArray

SetAppDomainPolicy():

AppDomain

SetAttribute():

XmlElement

SetAttributeNode():

XmlElement

SetAttributes():

File

SetByIndex():

SortedList

SetByte():

Buffer

SetCachePath():

AppDomain

SetCodeBase():

AssemblyRegistrationFlags

SetComObjectData():

Marshal

SetConstant():

FieldBuilder, ParameterBuilder, PropertyBuilder

SetContext():

XPathExpression

SetCookies():

CookieContainer

SetCreationTime():

Directory, File

SetCreationTimeUtc():

Directory, File

SetCurrentDirectory():

Directory

SetCustomAttribute():

AssemblyBuilder, ConstructorBuilder, EnumBuilder, EventBuilder, FieldBuilder, MethodBuilder,
ModuleBuilder, ParameterBuilder, PropertyBuilder, TypeBuilder

SetData():

AppDomain, Thread

SetDynamicBase():

AppDomain

SetEntryPoint():

AssemblyBuilder

SetError():

Console

SetField:

BindingFlags

SetGetMethod():

PropertyBuilder

SetImplementationFlags():

ConstructorBuilder, MethodBuilder

SetIn():

Console

SetLastAccessTime():

Directory, File

SetLastAccessTimeUtc():

Directory, File

SetLastError:

DllImportAttribute

SetLastWriteTime():

Directory, File

SetLastWriteTimeUtc():

Directory, File

SetLength():

BufferedStream, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream,
Stream

SetLocalSymInfo():

LocalBuilder

SetMarshal():

FieldBuilder, MethodBuilder, ParameterBuilder

SetMinThreads():

ThreadPool

SetNamedItem():

XmlAttributeCollection, XmlNamedNodeMap

SetObjectData():

ISerializationSurrogate

SetOffset():

FieldBuilder

SetOut():

Console

SetParent():

TypeBuilder

SetPrincipalPolicy():

AppDomain

SetProperty:

BindingFlags

SetPublicKey():

AssemblyName

SetPublicKeyToken():

AssemblyName

SetRaiseMethod():

EventBuilder

SetRange():

ArrayList

SetRemoveOnMethod():

EventBuilder

SetSetMethod():

PropertyBuilder

SetShadowCopyFiles():

AppDomain

SetShadowCopyPath():

AppDomain

SetSocketOption():

Socket

SetSymCustomAttribute():

ConstructorBuilder, MethodBuilder, ModuleBuilder

SetThreadPrincipal():

AppDomain

SetType():

SerializationInfo

SetupInformation:

AppDomain
SetUserEntryPoint():

ModuleBuilder
SetValue():

Array, FieldBuilder, FieldInfo, PropertyBuilder, PropertyInfo, RegistryKey
SetValueDirect():

FieldInfo
ShadowCopyDirectories:

AppDomainSetup
ShadowCopyFiles:

AppDomain, AppDomainSetup
Shl:

OpCodes
ShortDatePattern:

DateTimeFormatInfo
ShortInlineBrTarget:

OperandType
ShortInlinel:

OperandType
ShortInlineR:

OperandType
ShortInlineVar:

OperandType
ShortTimePattern:

DateTimeFormatInfo
Shr:

OpCodes
Shr_Un:

OpCodes
Shutdown():

Socket
Sign():

Math
SignalTime:

ElapsedEventArgs
Signature:

ConstructorBuilder, MethodBuilder, MissingMemberException

SignatureHelper:

System.Reflection.Emit

SignatureToken:

System.Reflection.Emit

Significant:

WhitespaceHandling

SignificantWhitespace:

XmlNodeType, XPathNodeType

Simple:

FormatterAssemblyStyle

Sin():

Math

Single:

System, TypeCode

SingleDomain:

LoaderOptimization

Singleline:

RegexOptions

Sinh():

Math

Site:

FileSystemWatcher, Timer

Size:

IntPtr, NotifyFilters, OpCode, SocketAddress, StructLayoutAttribute, TypeBuilder, UIntPtr

Size1:

PackingSize

Size16:

PackingSize

Size2:

PackingSize

Size4:

PackingSize

Size8:

PackingSize

SizeConst:

MarshalAsAttribute

Sizeof:

OpCodes

SizeOf():

Marshal

SizeParamIndex:

MarshalAsAttribute

Skip():

XmlNodeReader, XmlReader

Sleep():

Thread

Sna:

AddressFamily, ProtocolFamily

SoapFault:

System.Runtime.Serialization.Formatter

SoapMessage:

System.Runtime.Serialization.Formatter

Socket:

SocketOptionLevel, System.Net.Sockets

SocketAddress:

System.Net

SocketException:

System.Net.Sockets

SocketFlags:

System.Net.Sockets

SocketOptionLevel:

System.Net.Sockets

SocketOptionName:

System.Net.Sockets

SocketPermission:

System.Net

SocketPermissionAttribute:

System.Net

SocketShutdown:

System.Net.Sockets

SocketType:

Socket, System.Net.Sockets

Sort():

Array, ArrayList

SortableDateTimePattern:

DateTimeFormatInfo

SortedList:

System.Collections

SortKey:

System.Globalization

Source:

EventLog, EventLogEntry, EventLogInstaller, Exception

SourceExists():

EventLog

SourceUri:

XsltException

SpaceSeparator:

UnicodeCategory

SpacingCombiningMark:

UnicodeCategory

SparseFile:

FileAttributes

SpecialBuild:

FileVersionInfo

SpecialFolder:

System

SpecialName:

EventAttributes, FieldAttributes, MethodAttributes, PropertyAttributes, TypeAttributes

SpecificCultures:

CultureTypes

Specified:

XmlAttribute

SpinWait():

Thread

Split():

Regex, String

SplitText():

XmlText

Spx:

ProtocolType

Spx/I:

ProtocolType

Sqrt():

Math

Ss/3:

SecurityProtocolType

STA:

ApartmentState

Stack:

System.Collections

StackBehaviour:

System.Reflection.Emit

StackBehaviourPop:

OpCode

StackBehaviourPush:

OpCode

StackFrame:

System.Diagnostics

StackOverflowException:

System

StackTrace:

Environment, Exception, ServerFault, System.Diagnostics

Standalone:

XmlDeclaration

Standard:

CallingConventions

StandardError:

Process

StandardInput:

Process

StandardName:

TimeZone

StandardOutput:

Process

Standby:

ThreadState

Starg:

OpCodes

Starg_S:

OpCodes

Start:

DaylightTime, WriteState

Start():

Process, TcpListener, Thread, Timer

StartAddress:

ProcessThread

StartInfo:

Process

StartMenu:

SpecialFolder

StartsWith():

String

StartTime:

Process, ProcessThread

Startup:

SpecialFolder

State:

StreamingContext

STAThreadAttribute:

System

Static:

BindingFlags, FieldAttributes, MethodAttributes

Status:

WebException

StatusChange:

PowerModes

StatusCode:

HttpWebResponse

StatusDescription:

HttpWebResponse

StdCall:

CallingConvention

Stelem_I:

OpCodes

Stelem_I1:

OpCodes

Stelem_I2:

OpCodes

Stelem_I4:

OpCodes

Stelem_I8:

OpCodes

Stelem_R4:

OpCodes

Stelem_R8:

OpCodes

Stelem_Ref:

OpCodes

Stfld:

OpCodes

Stind_I:

OpCodes

Stind_I1:

OpCodes

Stind_I2:

OpCodes

Stind_I4:

OpCodes

Stind_I8:

OpCodes

Stind_R4:

OpCodes

Stind_R8:

OpCodes

Stind_Ref:

OpCodes

Stloc:

OpCodes

Stloc_0:

OpCodes

Stloc_1:

OpCodes

Stloc_2:

OpCodes

Stloc_3:

OpCodes

Stloc_S:

OpCodes

Stobj:

OpCodes

Stop():

TcpListener, Timer

Stopped:

ThreadState

StopRequested:

ThreadState

Stream:

SocketType, System.IO

StreamingContext:

System.Runtime.Serialization

StreamingContextStates:

System.Runtime.Serialization

StreamReader:

System.IO

StreamWriter:

System.IO

String:

System, TypeCode, XPathResultType

StringBuilder:

System.Text

StringCollection:

System.Collections.Specialized
StringDictionary:

System.Collections.Specialized
StringEnumerator:

System.Collections.Specialized
StringFormatMask:

TypeAttributes
StringInfo:

System.Globalization
StringReader:

System.IO
StringSort:

CompareOptions
StringToBSTR():

Marshal
StringToCoTaskMemAnsi():

Marshal
StringToCoTaskMemAuto():

Marshal
StringToCoTaskMemUni():

Marshal
StringToHGlobalAnsi():

Marshal
StringToHGlobalAuto():

Marshal
StringToHGlobalUni():

Marshal
StringToken:

System.Reflection.Emit
StringWriter:

System.IO
StrongNameKeyPair:

System.Reflection
Struct:

AttributeTargets, UnmanagedType
StructLayoutAttribute:

System.Runtime.InteropServices
StructureToPtr():

Marshal
Stsfd:

OpCodes
Sub:

OpCodes
Sub_Ovf:

OpCodes
Sub_Ovf_Un:

OpCodes
SubKeyCount:

RegistryKey
Substring():

String, XmlCharacterData
Subtract():

DateTime, Decimal, TimeSpan
Success:

Group, WebExceptionStatus
SuccessAudit:

EventLogEntryType
Sunday:

DayOfWeek
Supports():

XmlNode
SupportsIPv4:

Socket
SupportsIPv6:

Socket
SupportsPipelining:

ServicePoint
SuppressChangeType:

BindingFlags
SuppressFinalize():

GC
Surrogate:

UnicodeCategory

SurrogateSelector:

Formatter, IFormatter, System.Runtime.Serialization

Suspend:

PowerModes

Suspend():

Thread

Suspended:

ThreadState, ThreadWaitReason

SuspendRequested:

ThreadState

SwapMethodBody():

MethodRental

Switch:

OpCodes, System.Diagnostics

SwitchingProtocols:

HttpStatusCode

SynchronizationLockException:

System.Threading

Synchronized:

MethodImplAttributes

Synchronized():

ArrayList, Group, Hashtable, Match, Queue, SortedList, Stack, TextReader, TextWriter

SynchronizingObject:

EventLog, FileSystemWatcher, Process, Timer

SyncRoot:

Array, ArrayList, BitArray, CaptureCollection, CookieCollection, GroupCollection, Hashtable, HybridDictionary, ICollection, ListDictionary, MatchCollection, Queue, SortedList, Stack, StringCollection, StringDictionary

Sys/Int:

UnmanagedType

System:

FileAttributes, SpecialFolder

SystemAllocation:

ThreadWaitReason

SystemConfigurationFile:

RuntimeEnvironment

SystemDefaultCharSize:

Marshal

SystemDefinedImpl:

IDispatchImplType

SystemDirectory:

Environment

SystemEvents:

Microsoft.Win32

SystemException:

System

SystemFrequency:

CounterSample

SystemId:

XmlDocumentType, XmlEntity, XmlNotation, XmlParserContext

SystemMaxDBCSCharSize:

Marshal

SystemShutdown:

SessionEndReasons

SysUInt:

UnmanagedType

Tailcall:

OpCodes

TaiwanCalendar:

System.Globalization

TakesSingleByteArgument():

OpCodes

Tan():

Math

Tanh():

Math

Target:

Delegate, GCHandle, WeakReference, XmlProcessingInstruction

TargetException:

System.Reflection

TargetInvocationException:

System.Reflection

TargetMethods:

InterfaceMapping

TargetParameterCountException:

System.Reflection

TargetSite:

Exception

TargetType:

InterfaceMapping

TBStr:

UnmanagedType

Tcp:

ProtocolType, SocketOptionLevel, TransportType

TcpClient:

System.Net.Sockets

TcpListener:

System.Net.Sockets

Templates:

SpecialFolder

Temporary:

FileAttributes

TemporaryRedirect:

HttpStatusCode

Terminated:

ThreadState

Text:

XmlDataType, XmlNodeType, XPathNodeType

TextElementEnumerator:

System.Globalization

TextInfo:

CultureInfo, System.Globalization

TextReader:

System.IO

TextWriter:

System.IO

TextWriterTraceListener:

System.Diagnostics

ThaiBuddhistCalendar:

System.Globalization

ThaiBuddhistEra:

ThaiBuddhistCalendar

ThisCall:

CallingConvention

Thread:

System.Threading

ThreadAbortException:

System.Threading

ThreadExceptionEventArgs:

System.Threading

ThreadExceptionHandler:

System.Threading

ThreadInterruptedException:

System.Threading

ThreadPool:

System.Threading

ThreadPriority:

System.Threading

ThreadPriorityLevel:

System.Diagnostics

Threads:

Process

ThreadStart:

System.Threading

ThreadState:

ProcessThread, System.Diagnostics, System.Threading, Thread

ThreadStateException:

System.Threading

ThreadStaticAttribute:

System

ThreadWaitReason:

System.Diagnostics

ThreeLetterISOLanguageName:

CultureInfo

ThreeLetterISORegionName:

RegionInfo

ThreeLetterWindowsLanguageName:

CultureInfo

ThreeLetterWindowsRegionName:

RegionInfo

Throw:

FlowControl, OpCodes

ThrowException():

ILGenerator

ThrowExceptionForHR():

Marshal

ThrowOnUnmappableChar:

BestFitMappingAttribute, DllImportAttribute

Thursday:

DayOfWeek

TickCount:

Environment

Ticks:

DateTime, TimeSpan

TicksPerDay:

TimeSpan

TicksPerHour:

TimeSpan

TicksPerMillisecond:

TimeSpan

TicksPerMinute:

TimeSpan

TicksPerSecond:

TimeSpan

TimeChanged:

SystemEvents

TimeCritical:

ThreadPriorityLevel

TimedOut:

WaitForChangedResult

TimeGenerated:

EventLogEntry

TimeOfDay:

DateTime

Timeout:

FileWebRequest, HttpWebRequest, System.Threading, WebExceptionStatus, WebRequest

Timer:

System.Threading, System.Timers

Timer100Ns:

PerformanceCounterType

Timer100NsInverse:

PerformanceCounterType

TimerCallback:

System.Threading

TimerElapsed:

SystemEvents

TimerElapsedEventArgs:

Microsoft.Win32

TimerElapsedEventHandler:

Microsoft.Win32

TimerId:

TimerElapsedEventArgs

TimersDescriptionAttribute:

System.Timers

TimeSeparator:

DateTimeFormatInfo

TimeSpan:

System

TimeStamp:

Cookie, CounterSample

TimeStamp100nSec:

CounterSample

TimeWritten:

EventLogEntry

TimeZone:

System

Title:

AssemblyTitleAttribute

TitlecaseLetter:

UnicodeCategory

Tls:

SecurityProtocolType

ToArray():

ArrayList, MemoryStream, Queue, Stack

ToBase64CharArray():

Convert

ToBase64String():

Convert

ToBoolean():

BitConverter, Convert, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToByte():

Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToByteArray():

Guid, WebHeaderCollection

ToChar():

BitConverter, Convert, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToCharArray():

String

ToDateTime():

Calendar, Convert, FormatterConverter, GregorianCalendar, HebrewCalendar, HijriCalendar, IConvertible, IFormatterConverter, JapaneseCalendar, JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar, XmlConvert

Today:

DateTime

ToDecimal():

Convert, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToDouble():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToFileTime():

DateTime

ToFileTimeUtc():

DateTime

ToFourDigitYear():

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar,
JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

ToGuid():

XmlConvert

ToInt16():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter,
XmlConvert

ToInt32():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter,
IntPtr, XmlConvert

ToInt64():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter,
IntPtr, XmlConvert

Token:

EventToken, FieldToken, MethodToken, ParameterToken, PropertyToken, SignatureToken,
StringToken, TypeToken

ToLocalTime():

DateTime, TimeZone

ToLongDateString():

DateTime

ToLongTimeString():

DateTime

ToLower():

Char, String, TextInfo

ToOACurrency():

Decimal

ToOADate():

DateTime

ToObject():

Enum

ToPointer():

IntPtr, UIntPtr

ToSByte():

Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToShortDateString():

DateTime

ToShortTimeString():

DateTime

ToSingle():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToString():

AppDomain, Assembly, AssemblyName, BadImageFormatException, BitConverter, BitVector32, Boolean, Byte, Capture, Char, COMException, CompareInfo, ConstructorBuilder, Convert, Cookie, CultureInfo, DateTime, DBNull, Decimal, DirectoryInfo, Double, EndpointPermission, Enum, Exception, FileInfo, FileLoadException, FileNotFoundEventArgs, FileVersionInfo, FormatterConverter, Guid, IConvertible, IFormattable, IFormatterConverter, Int16, Int32, Int64, IntPtr, IPAddress, IPEndPoint, MethodBuilder, Module, Object, OpCode, OperatingSystem, Process, ProcessModule, Regex, RegionInfo, RegistryKey, SByte, Section, SignatureHelper, Single, SocketAddress, SortKey, StackFrame, StackTrace, String, StringBuilder, StringWriter, TextInfo, TimeSpan, Type, TypeBuilder, UInt16, UInt32, UInt64, UIntPtr, Uri, UriBuilder, ValueType, Version, WebHeaderCollection, XmlConvert, XmlQualifiedName, XPathNavigator

TotalDays:

TimeSpan

TotalHours:

TimeSpan

TotalMilliseconds:

TimeSpan

TotalMinutes:

TimeSpan

TotalProcessorTime:

Process, ProcessThread

TotalSeconds:

TimeSpan

ToTimeSpan():

XmlConvert

ToTitleCase():

TextInfo

ToType():

IConvertible

ToUInt16():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, XmlConvert

ToUInt32():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter, UIntPtr, XmlConvert

ToUInt64():

BitConverter, Convert, Decimal, FormatterConverter, IConvertible, IFormatterConverter,
UIntPtr, XmlConvert

ToUniversalTime():

DateTime, TimeZone

ToUpper():

Char, String, TextInfo

ToXml():

DnsPermission, SocketPermission, WebPermission

Trace:

System.Diagnostics

TraceError:

TraceSwitch

TraceInfo:

TraceSwitch

TraceLevel:

System.Diagnostics

TraceListener:

System.Diagnostics

TraceListenerCollection:

System.Diagnostics

TraceSwitch:

System.Diagnostics

TraceVerbose:

TraceSwitch

TraceWarning:

TraceSwitch

TrackResurrection:

WeakReference

Trademark:

AssemblyTrademarkAttribute

TransferEncoding:

HttpWebRequest

Transform():

XslTransform

Transition:

ThreadState

TransliteratedEnglish:

GregorianCalendarTypes

TransliteratedFrench:

GregorianCalendarTypes

Transport:

EndpointPermission, SocketPermissionAttribute

TransportType:

System.Net

Trim():

String

TrimEnd():

String

TrimStart():

String

TrimToSize():

ArrayList, Queue, SortedList

TrueString:

Boolean

Truncate:

FileMode

Truncate():

Decimal

TrustFailure:

WebExceptionStatus

TryEnter():

Monitor

TryParse():

Double

Tuesday:

DayOfWeek

TwoDigitYearMax:

Calendar, GregorianCalendar, HebrewCalendar, HijriCalendar, JapaneseCalendar,
JulianCalendar, KoreanCalendar, TaiwanCalendar, ThaiBuddhistCalendar

TwoLetterISOLanguageName:

CultureInfo

TwoLetterISORegionName:

RegionInfo

Type:

SocketOptionName, System

TypeAttributes:

System.Reflection

TypeBuilder:

System.Reflection.Emit

TypeCode:

System

TypeConstructorName:

ConstructorInfo

TypeDelegator:

System.Reflection

TypeFilter:

System.Reflection

TypeFilterLevel:

System.Runtime.Serialization.Formatter

TypeHandle:

EnumBuilder, Type, TypeBuilder, TypeDelegator

TypeId:

Attribute

typeImpl:

TypeDelegator

TypeInfo:

MemberTypes

TypeInitializationException:

System

TypeInitializer:

Type

TypeLibVersionAttribute:

System.Runtime.InteropServices

TypeLoadException:

System

TypeName:

TypeInitializationException, TypeLoadException

TypeOfService:

SocketOptionName

TypeRepresentsComType():

IRegistrationServices, RegistrationServices

TypeRequiresRegistration():

IRegistrationServices, RegistrationServices

TypeResolve:

AppDomain

Types:

ReflectionTypeLoadException

TypesAlways:

FormatterTypeStyle

TypesWhenNeeded:

FormatterTypeStyle

TypeToken:

EnumBuilder, System.Reflection.Emit, TypeBuilder

TypeUnloadedException:

System

U1:

UnmanagedType

U2:

UnmanagedType

U4:

UnmanagedType

U8:

UnmanagedType

Udp:

ProtocolType, SocketOptionLevel, TransportType

UdpClient:

System.Net.Sockets

UInt16:

System, TypeCode

UInt32:

System, TypeCode

UInt64:

System, TypeCode

IntPtr:

System

Unaligned:

OpCodes

Unauthorized:

HttpStatusCode

UnauthorizedAccessException:

System

UnblockSource:

SocketOptionName

Unbox:

OpCodes

Unbox():

Pointer

UnderlyingField:

EnumBuilder

UnderlyingSystemType:

EnumBuilder, IReflect, Type, TypeBuilder, TypeDelegator

Unescape():

Regex, Uri

UnhandledException:

AppDomain

UnhandledExceptionEventArgs:

System

UnhandledExceptionEventHandler:

System

Unicode:

CharSet, Encoding

UnicodeCategory:

System.Globalization

UnicodeClass:

TypeAttributes

UnicodeEncoding:

System.Text

Unindent():

Debug, Trace

Uninstall():

EventLogInstaller, PerformanceCounterInstaller
UninstallAction:

EventLogInstaller, PerformanceCounterInstaller
Union():

DnsPermission, SocketPermission, WebPermission
UniversalSortableDateTimePattern:

DateTimeFormatInfo
Unix:

AddressFamily, ProtocolFamily
Unknown:

AddressFamily, ApartmentState, ProtocolFamily, ProtocolType, SocketType, ThreadState,
ThreadWaitReason, UriHostNameType, XmlNodeOrder
UnknownError:

WebExceptionStatus
UnknownWrapper:

System.Runtime.InteropServices
Unload():

AppDomain
Unlock():

FileStream
Unmanaged:

MethodImplAttributes
UnmanagedExport:

MethodAttributes
UnmanagedMarshal:

System.Reflection.Emit
UnmanagedType:

System.Runtime.InteropServices
Unpack():

Overlapped
Unregister():

AuthenticationManager, RegisteredWaitHandle
UnregisterAssembly():

IRegistrationServices, RegistrationServices
UnsafeAddrOfPinnedArrayElement():

Marshal
UnsafeAuthenticatedConnectionSharing:

HttpRequest
UnsafePack():

Overlapped
UnsafeQueueUserWorkItem():

ThreadPool
UnsafeRegisterWaitForSingleObject():

ThreadPool
Unspecified:

AddressFamily, PackingSize, ProtocolFamily, ProtocolType
UnspecifiedTypeSize:

TypeBuilder
Unstarted:

ThreadState
UnsupportedMediaType:

HttpStatusCode
Unused:

HttpStatusCode
UpgradeToWriterLock():

ReaderWriterLock
UploadData():

WebClient
UploadFile():

WebClient
UploadValues():

WebClient
UppercaseLetter:

UnicodeCategory
UpperFirst:

XmlCaseOrder
Uri:

System, UriBuilder
UriBuilder:

System
UriFormatException:

System
UriHostNameType:

System

UriPartial:

System

UriSchemeFile:

Uri

UriSchemeFtp:

Uri

UriSchemeGopher:

Uri

UriSchemeHttp:

Uri

UriSchemeHttps:

Uri

UriSchemeMailto:

Uri

UriSchemeNews:

Uri

UriSchemeNntp:

Uri

UseLoopback:

SocketOptionName

UseNagleAlgorithm:

ServicePoint, ServicePointManager

USEnglish:

GregorianCalendarTypes

UseOptionC():

Regex

UseOptionR():

Regex

UseProxy:

HttpStatusCode

User:

IsolatedStorageScope

UserAgent:

HttpWebRequest

UserDomainName:

Environment

UserEscaped:

Uri

UserInfo:

Uri

UserInteractive:

Environment

UserName:

Environment, EventLogEntry, NetworkCredential, UriBuilder

UserPreferenceCategory:

Microsoft.Win32

UserPreferenceChanged:

SystemEvents

UserPreferenceChangedEventArgs:

Microsoft.Win32

UserPreferenceChangedEventHandler:

Microsoft.Win32

UserPreferenceChanging:

SystemEvents

UserPreferenceChangingEventArgs:

Microsoft.Win32

UserPreferenceChangingEventHandler:

Microsoft.Win32

UserProcessorTime:

Process, ProcessThread

UserRequest:

ThreadWaitReason

Users:

Registry, RegistryHive

UseShellExecute:

ProcessStartInfo

UseUserOverride:

CultureInfo

UsingNamespace():

ILGenerator

UtcNow:

DateTime

UTF7:

Encoding

UTF7Encoding:

System.Text

UTF8:

Encoding

UTF8Encoding:

System.Text

ValidationEventHandler:

XmlTextReader, XmlValidatingReader

ValidationType:

System.Xml, XmlValidatingReader

ValidOn:

AttributeUsageAttribute

Value:

Capture, ClassInterfaceAttribute, ComAliasNameAttribute, ComSourceInterfacesAttribute, ComVisibleAttribute, Cookie, DBNull, DictionaryEntry, DispIdAttribute, DllImportAttribute, FieldOffsetAttribute, GuidAttribute, IDictionaryEnumerator, IDispatchImplAttribute, InterfaceTypeAttribute, LCIDConversionAttribute, LoaderOptimizationAttribute, MarshalAsAttribute, Missing, OpCode, ProgIdAttribute, RuntimeTypeHandle, SerializationEntry, SerializationInfoEnumerator, StructLayoutAttribute, XmlAttribute, XmlCharacterData, XmlDeclaration, XmlEntityReference, XmlNode, XmlNodeReader, XmlProcessingInstruction, XmlReader, XmlSignificantWhitespace, XmlText, XmlTextReader, XmlValidatingReader, XmlWhitespace, XPathNavigator

value_ _:

AddressFamily, ApartmentState, AssemblyBuilderAccess, AssemblyNameFlags, AssemblyRegistrationFlags, AttributeTargets, BindingFlags, CalendarWeekRule, CallingConvention, CallingConventions, CharSet, ClassInterfaceType, ComInterfaceType, ComMemberType, CompareOptions, CultureTypes, DateTimeStyles, DayOfWeek, EntityHandling, EventAttributes, EventLogEntryType, EventLogPermissionAccess, FieldAttributes, FileAccess, FileAttributes, FileMode, FileShare, FlowControl, FormatterAssemblyStyle, FormatterTypeStyle, Formatting, GCHandleType, GregorianCalendarTypes, HttpStatusCode, IDispatchImplType, IsolatedStorageScope, LayoutKind, LoaderOptimization, MemberTypes, MethodAttributes, MethodImplAttributes, NetworkAccess, NotifyFilters, NumberStyles, OpCodeType, OperandType, PackingSize, ParameterAttributes, PEFileKinds, PerformanceCounterPermissionAccess, PerformanceCounterType, PlatformID, PowerModes, ProcessPriorityClass, ProcessWindowStyle, PropertyAttributes, ProtocolFamily, ProtocolType, ReadState, RegexOptions, RegistryHive, ResourceAttributes, ResourceLocation, SecurityProtocolType, SeekOrigin, SelectMode, SessionEndReasons, SocketFlags, SocketOptionLevel, SocketOptionName, SocketShutdown, SocketType, SpecialFolder, StackBehaviour, StreamingContextStates, ThreadPriority, ThreadPriorityLevel, ThreadState, ThreadWaitReason, TraceLevel, TransportType, TypeAttributes, TypeCode, TypeFilterLevel, UnicodeCategory, UnmanagedType,

UriHostNameType, UriPartial, UserPreferenceCategory, ValidationType, VarEnum, WatcherChangeTypes, WebExceptionStatus, WhitespaceHandling, WriteState, XmlCaseOrder, XmlDataType, XmlNodeChangedAction, XmlNodeOrder, XmlNodeType, XmlSortOrder, XmlSpace, XmlTokenizedType, XPathNamespaceScope, XPathNodeType, XPathResultType

ValueCount:

RegistryKey

Values:

Hashtable, HybridDictionary, IDictionary, InstanceDataCollection, InstanceDataCollectionCollection, ListDictionary, SortedList, StringDictionary

ValueType:

System

VarArgs:

CallingConventions

VarEnum:

System.Runtime.InteropServices

VariableType:

IXsltContextVariable

VariantBool:

UnmanagedType

Varpop:

StackBehaviour

Varpush:

StackBehaviour

VBByRefStr:

UnmanagedType

Verb:

ProcessStartInfo

Verbose:

TraceLevel

Verbs:

ProcessStartInfo

VerifyName():

XmlConvert

VerifyNCName():

XmlConvert

Version:

AssemblyFileVersionAttribute, AssemblyName, AssemblyVersionAttribute, Cookie, Environment, OperatingSystem, System, XmlDeclaration

Version10:

HttpVersion

Version11:

HttpVersion

VersionCompatibility:

AssemblyName

Virtual:

MethodAttributes

VirtualMemory:

ThreadWaitReason

VirtualMemorySize:

Process

VisibilityMask:

TypeAttributes

VoiceView:

AddressFamily, ProtocolFamily

Void:

System

Volatile:

OpCodes

VolatileRead():

Thread

VolatileWrite():

Thread

VolumeSeparatorChar:

Path

VT_ARRAY:

VarEnum

VT_BLOB:

VarEnum

VT_BLOB_OBJECT:

VarEnum

VT_BOOL:

VarEnum

VT_BSTR:

VarEnum

VT_BYREF:

VarEnum

VT_CARRAY:

VarEnum

VT_CF:

VarEnum

VT_CLSID:

VarEnum

VT_CY:

VarEnum

VT_DATE:

VarEnum

VT_DECIMAL:

VarEnum

VT_DISPATCH:

VarEnum

VT_EMPTY:

VarEnum

VT_ERROR:

VarEnum

VT_FILETIME:

VarEnum

VT_HRESULT:

VarEnum

VT_I1:

VarEnum

VT_I2:

VarEnum

VT_I4:

VarEnum

VT_I8:

VarEnum

VT_INT:

VarEnum

VT_LPSTR:

VarEnum

VT_LPWSTR:

VarEnum
VT_NULL:

VarEnum
VT_PTR:

VarEnum
VT_R4:

VarEnum
VT_R8:

VarEnum
VT_RECORD:

VarEnum
VT_SAFEARRAY:

VarEnum
VT_STORAGE:

VarEnum
VT_STORED_OBJECT:

VarEnum
VT_STREAM:

VarEnum
VT_STREAMED_OBJECT:

VarEnum
VT_UI1:

VarEnum
VT_UI2:

VarEnum
VT_UI4:

VarEnum
VT_UI8:

VarEnum
VT_UINT:

VarEnum
VT_UNKNOWN:

VarEnum
VT_USERDEFINED:

VarEnum

VT_VARIANT:

VarEnum

VT_VECTOR:

VarEnum

VT_VOID:

VarEnum

VtableLayoutMask:

MethodAttributes

Wait:

ThreadState

Wait():

Monitor

WaitAll():

WaitHandle

WaitAny():

WaitHandle

WaitCallback:

System.Threading

WaitForChanged():

FileSystemWatcher

WaitForChangedResult:

System.IO

WaitForExit():

Process

WaitForInputIdle():

Process

WaitForPendingFinalizers():

GC

WaitHandle:

System.Threading

WaitOne():

WaitHandle

WaitOrTimerCallback:

System.Threading

WaitReason:

ProcessThread

WaitSleepJoin:

ThreadState

WaitTimeout:

WaitHandle

Warning:

EventLogEntryType, TraceLevel

WatcherChangeTypes:

System.IO

Weak:

GCHandleType

WeakReference:

System

WeakTrackResurrection:

GCHandleType

WebClient:

System.Net

WebException:

System.Net

WebExceptionStatus:

System.Net

WebHeaderCollection:

System.Net

WebName:

Encoding

WebPermission:

System.Net

WebPermissionAttribute:

System.Net

WebProxy:

System.Net

WebRequest:

System.Net

WebResponse:

System.Net

Wednesday:

DayOfWeek

Whitespace:

XmlNodeType, XPathNodeType, XsltContext

WhitespaceHandling:

System.Xml, XmlTextReader

Win32NT:

PlatformID

Win32S:

PlatformID

Win32Windows:

PlatformID

Winapi:

CallingConvention

WinCE:

PlatformID

Window:

UserPreferenceCategory

WindowApplication:

PEFileKinds

WindowsCodePage:

Encoding

WindowStyle:

ProcessStartInfo

WorkingDirectory:

ProcessStartInfo

WorkingSet:

Environment, Process

WrappedObject:

CurrencyWrapper, DispatchWrapper, UnknownWrapper

Wrapper:

HandleRef

Write:

FileAccess, FileShare

Write():

BinaryWriter, BufferedStream, Console, Debug, DefaultTraceListener, EventLogTraceListener, FileStream, IsolatedStorageFileStream, MemoryStream, NetworkStream, Stream, StreamWriter, StringWriter, TextWriter, TextWriterTraceListener, Trace, TraceListener

Write7BitEncodedInt():

BinaryWriter

WriteArray():

Formatter

WriteAttributes():

XmlWriter

WriteAttributeString():

XmlWriter

WriteBase64():

XmlTextWriter, XmlWriter

WriteBinHex():

XmlTextWriter, XmlWriter

WriteBoolean():

Formatter

WriteByte():

BufferedStream, FileStream, Formatter, IsolatedStorageFileStream, Marshal, MemoryStream,
Stream

WriteCData():

XmlTextWriter, XmlWriter

WriteChar():

Formatter

WriteCharEntity():

XmlTextWriter, XmlWriter

WriteChars():

XmlTextWriter, XmlWriter

WriteComment():

XmlTextWriter, XmlWriter

WriteContentTo():

XmlAttribute, XmlCDataSection, XmlComment, XmlDeclaration, XmlDocument,
XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference,
XmlNode, XmlNotation, XmlProcessingInstruction, XmlSignificantWhitespace, XmlText,
XmlWhitespace

WriteDateTime():

Formatter

WriteDecimal():

Formatter

WriteDocType():

XmlTextWriter, XmlWriter

WriteDouble():

Formatter

WriteElementString():

XmlWriter

WriteEndAttribute():

XmlTextWriter, XmlWriter

WriteEndDocument():

XmlTextWriter, XmlWriter

WriteEndElement():

XmlTextWriter, XmlWriter

WriteEntityRef():

XmlTextWriter, XmlWriter

WriteEntry():

EventLog

WriteFullEndElement():

XmlTextWriter, XmlWriter

WriteIf():

Debug, Trace

WriteIndent():

TraceListener

WriteInt16():

Formatter, Marshal

WriteInt32():

Formatter, Marshal

WriteInt64():

Formatter, Marshal

WriteIntPtr():

Marshal

WriteLine():

Console, Debug, DefaultTraceListener, EventLogTraceListener, TextWriter,

TextWriterTraceListener, Trace, TraceListener

WriteLineIf():

Debug, Trace

WriteMember():

Formatter

WriteName():

XmlTextWriter, XmlWriter
WriteNmToken():

XmlTextWriter, XmlWriter
WriteNode():

XmlWriter
WriteObjectRef():

Formatter
WriteProcessingInstruction():

XmlTextWriter, XmlWriter
WriteQualifiedName():

XmlTextWriter, XmlWriter
Writer:

TextWriterTraceListener
WriteRaw():

XmlTextWriter, XmlWriter
WriterSeqNum:

ReaderWriterLock
WriteSByte():

Formatter
WriteSingle():

Formatter
WriteStartAttribute():

XmlTextWriter, XmlWriter
WriteStartDocument():

XmlTextWriter, XmlWriter
WriteStartElement():

XmlTextWriter, XmlWriter
WriteState:

System.Xml, XmlTextWriter, XmlWriter
WriteString():

XmlTextWriter, XmlWriter
WriteSurrogateCharEntity():

XmlTextWriter, XmlWriter
WriteTimeSpan():

Formatter
WriteTo():

MemoryStream, XmlAttribute, XmlCDataSection, XmlComment, XmlDeclaration, XmlDocument, XmlDocumentFragment, XmlDocumentType, XmlElement, XmlEntity, XmlEntityReference, XmlNode, XmlNotation, XmlProcessingInstruction, XmlSignificantWhitespace, XmlText, XmlWhitespace

WriteUInt16():

Formatter

WriteUInt32():

Formatter

WriteUInt64():

Formatter

WriteValueType():

Formatter

WriteWhitespace():

XmlTextWriter, XmlWriter

XDR:

ValidationType

XmlAttribute:

System.Xml

XmlAttributeCollection:

System.Xml

XmlCaseOrder:

System.Xml.XPath

XmlCDataSection:

System.Xml

XmlCharacterData:

System.Xml

XmlComment:

System.Xml

XmlConvert:

System.Xml

XmlDataDocument:

System.Xml

XmlDataType:

System.Xml.XPath

XmlDeclaration:

System.Xml, XmlNodeType

XmlDocument:

System.Xml

XmlDocumentFragment:

System.Xml

XmlDocumentType:

System.Xml

XmlElement:

System.Xml

XmlEntity:

System.Xml

XmlEntityReference:

System.Xml

XmlException:

System.Xml

XmlImplementation:

System.Xml

XmlLang:

XmlNodeReader, XmlParserContext, XmlReader, XmlTextReader, XmlTextWriter,
XmlValidatingReader, XmlWriter, XPathNavigator

XmlLinkedNode:

System.Xml

XmlNamedNodeMap:

System.Xml

XmlNameSpace:

ISoapMessage, SoapMessage

XmlNamespaceManager:

System.Xml

XmlNameTable:

System.Xml

XmlNode:

System.Xml

XmlNodeChangedAction:

System.Xml

XmlNodeChangedEventArgs:

System.Xml

XmlNodeChangedEventHandler:

System.Xml

XmlNodeList:

System.Xml
XmlNodeOrder:

System.Xml
XmlNodeReader:

System.Xml
XmlNodeType:

System.Xml
XmlNotation:

System.Xml
XmlParserContext:

System.Xml
XmlProcessingInstruction:

System.Xml
XmlQualifiedName:

System.Xml
XmlReader:

System.Xml
XmlResolver:

System.Xml, XmlDocument, XmlTextReader, XmlValidatingReader, XslTransform
XmlSecureResolver:

System.Xml
XmlSignificantWhitespace:

System.Xml
XmlSortOrder:

System.Xml.XPath
XmlSpace:

System.Xml, XmlNodeReader, XmlParserContext, XmlReader, XmlTextReader, XmlTextWriter,
XmlValidatingReader, XmlWriter
XmlText:

System.Xml
XmlTextReader:

System.Xml
XmlTextWriter:

System.Xml
XmlTokenizedType:

System.Xml
XmlUriResolver:

System.Xml
XmlValidatingReader:

System.Xml
XmlWhitespace:

System.Xml
XmlWriter:

System.Xml
Xor:

OpCodes
Xor():

BitArray
XPathDocument:

System.Xml.XPath
XPathException:

System.Xml.XPath
XPathExpression:

System.Xml.XPath
XPathNamespaceScope:

System.Xml.XPath
XPathNavigator:

System.Xml.XPath
XPathNodeIterator:

System.Xml.XPath
XPathNodeType:

System.Xml.XPath
XPathResultType:

System.Xml.XPath
XsdString:

FormatterTypeStyle
XsltArgumentList:

System.Xml.Xsl
XsltCompileException:

System.Xml.Xsl
XsltContext:

System.Xml.Xsl
XsltException:

System.Xml.Xsl
XslTransform:

System.Xml.Xsl
Year:

DateTime
YearMonthPattern:

DateTimeFormatInfo
Zero:

Decimal, IntPtr, TimeSpan, UIntPtr

[\[Team LiB \]](#)

[\[Team LiB \]](#)[◀ PREVIOUS](#)

Colophon

Our look is the result of reader comments, our own experimentation, and feedback from distribution channels. Distinctive covers complement our distinctive approach to technical topics, breathing personality and life into potentially dry subjects.

The animal on the cover of *C# in a Nutshell, Second Edition* is a numidian crane. The numidian crane (*Antropoides virgō*) is also called the demoiselle crane because of its grace and symmetry. This species of crane is native to Europe and Asia and migrates to India, Pakistan, and northeast Africa in the winter.

Though numidian cranes are the smallest cranes, they defend their territories as aggressively as other crane species, using their loud voices to warn others of trespassing. If necessary, they will fight. Numidian cranes nest in uplands rather than wetlands and will even live in the desert if there is water within 200 to 500 meters. They sometimes make nests out of pebbles in which to lay their eggs, though more often they will lay eggs directly on the ground, protected only by spotty vegetation.

Numidian cranes are considered a symbol of good luck in some countries and are sometimes even protected by law.

Philip Dangler was the production editor, and Leanne Soylemez was the proofreader for *C# in a Nutshell, Second Edition*. Emily Quill and Claire Cloutier provided quality control. Interior composition was done by Mary Agner and Jamie Peppard. Johnna and Tom Dinse wrote the index.

Emma Colby designed the cover of this book, based on a series design by Edie Freedman. The cover image is an original engraving from the 19th century. Emma Colby produced the cover layout with QuarkXPress 4.1 using Adobe's ITC Garamond font.

David Futato designed the interior layout. He also designed the CD label with QuarkXPress 4.1 using Adobe's ITC Garamond font. This book was converted by Joe Wizda to FrameMaker 5.5.6 with a format conversion tool created by Erik Ray, Jason McIntosh, Neil Walls, and Mike Sierra that uses Perl and XML technologies. The text font is Linotype Birka; the heading font is Adobe Myriad Condensed; and the code font is LucasFont's TheSans Mono Condensed. The illustrations that appear in the book were produced by Robert Romano and Jessamyn Read using Macromedia FreeHand 9 and Adobe Photoshop 6. This colophon was written by Linley Dolby.

The online edition of this book was created by the Safari production group (John Chodacki, Becki Maisch, and Madeleine Newell) using a set of Frame-to-XML conversion and cleanup tools written and maintained by Erik Ray, Benn Salter, John Chodacki, and Jeff Liggett.

[\[Team LiB \]](#)[◀ PREVIOUS](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[\[Team LiB \]](#)

[Team LiB]

[SYMBOL] [A] [B] [C] [D] [E] [F] [G] [H] [I] [J] [K] [L] [M] [N] [O] [P] [Q] [R] [S] [T] [U] [V] [W] [X]

- [#error, conditional directives and](#)
- [#warning, conditional directives and](#)
- [<c> tag, XML](#)
- [<code> tag, XML](#)
- [<example> tag, XML](#)
- [<exception> tag, XML](#)
- [<include> tag, XML](#)
- [<list> tag, XML](#)
- [<para> tag, XML](#)
- [<param> tag, XML](#)
- [<paramref> tag, XML](#)
- [<permission> tag, XML](#)
- [<remarks> tag, XML](#)
- [<returns> tag, XML](#)
- [<see> tag, XML](#)
- [<seealso> tag, XML](#)
- [<summary> tag, XML](#)
- [<value> tag, XML](#)
- [.NET Framework SDK](#)
 - [downloading](#)
- [@ prefix, identifiers](#)

[Team LiB]

[[Team LiB](#)]

[[SYMBOL](#)] [[A](#)] [[B](#)] [[C](#)] [[D](#)] [[E](#)] [[F](#)] [[G](#)] [[H](#)] [[I](#)] [[J](#)] [[K](#)] [[L](#)] [[M](#)] [[N](#)] [[O](#)] [[P](#)] [[Q](#)] [[R](#)] [[S](#)] [[T](#)] [[U](#)] [[V](#)] [[W](#)] [[X](#)]

[abstract classes](#)

[Stream](#)

System

[Array](#)

[Attribute](#)

[ContextBoundObject](#)

[Delegate](#)

[Enum](#)

[MarshalByRefObject](#)

[MulticastDelegate](#)

[TimeZone](#)

[Type](#)

[ValueType](#)

System.Diagnostics

[Switch](#)

[TraceListener](#)

[System.Globalization, Calendar](#)

System.IO

[FileSystemInfo](#)

[Stream](#)

[TextReader](#)

[TextWriter](#)

[System.IO.IsolatedStorage, IsolatedStorage](#)

System.Net

[EndPoint](#)

[WebRequest](#)

[WebResponse](#)

System.Runtime.Serialization

[Formatter](#)

[SerializationBinder](#)

System.Text

[Decoder](#)

[Encoder](#)

[Encoding](#)

[System.Threading, WaitHandle](#)

System.Xml

[XmlCharacterData](#)

[XmlLinkedNode](#)

[XmlNameTable](#)

[XmlNode](#)

[XmlNodeList](#)

[XmlReader](#)

[XmlResolver](#)

[XmlWriter](#)

System.Xml.XPath

[XPathExpression](#)

[XPathNavigator](#)

- [XPathNodeIterator](#)
- [System.Xml.Xsl](#)
- [XsltContext](#)
- [System.Collections](#)
 - [CollectionBase](#)
 - [DictionaryBase](#)
 - [ReadOnlyCollectionBase](#)
- [System.Collections.Specialized, NameObjectCollectionBase](#)
- [System.Reflection API](#)
 - [Binder](#)
 - [ConstructorInfo](#)
 - [EventInfo](#)
 - [FieldInfo](#)
 - [MemberInfo](#)
 - [MethodBase](#)
 - [MethodInfo](#)
 - [PropertyInfo](#)
- [TextReader](#)
- [TextWriter](#)
- [abstract keyword](#)
- [abstract members](#)
- [access members](#)
- [access modifiers](#)
 - [constructors](#)
 - [internal](#)
 - [nested types](#)
 - [private](#)
 - [protected](#)
 - [restrictions](#)
- [accessors, events](#)
- [Activator class, System namespace](#)
- [AddressFamily enumeration, System.Net.Sockets namespace](#)
- [ADepends.exe](#)
- [AI.exe](#)
- [aliasing](#)
 - [namespaces](#)
 - [types](#)
- [all caps naming convention style](#)
- [alternation, regular expressions](#)
- [AmbiguousException sealed class, System.Reflection API](#)
- [ApartmentState enumeration, System.Threading](#)
- [AppDomain class, System namespace](#)
- [AppDomains, reflection and](#)
- [AppDomainSetup class, System namespace](#)
- [AppDomainUnloadedException class, System namespace](#)
- [application exceptions](#)
- [ApplicationException class, System namespace](#)
- [applications](#)
 - [multithreaded](#)
 - [web-based, FCL and](#)
- [ArgumentException](#)
- [ArgumentException class, System namespace](#)

[ArgumentNullException class, System namespace](#)
[ArgumentOutOfRangeException class, System namespace](#)
[arguments, passing by value](#)
[arithmetic overflow check operators](#)
[ArithmeticException class, System namespace](#)
[Array abstract class, System namespace](#)
[Array class, collections and](#)
[array covariance](#)
[ArrayList class, System.Collections](#)
[collections and](#)
[arrays](#) [2nd](#)
[bounds checking](#)
[brackets](#)
[conversions](#)
[declarations, local](#)
[jagged](#)
[length](#)
[multidimensional](#)
[rank](#)
[rectangular](#) [2nd](#)
[ArrayTypeMismatchException class, System namespace](#)
[ArrayWithOffset struct, System.Runtime.InteropServices](#)
[ArtIterator struct, System namespace](#)
[as operator](#)
[ASCIIEncoding class, System.Text](#)
[ASP.NET, Wsdl.exe and](#)
[assemblies](#)
[ADepends.exe](#)
[Al.exe](#)
[COM+ registry](#)
[Cordbg.exe](#)
[deployment and](#)
[FCL and](#)
[GacUtil.exe](#)
[ILasm.exe](#)
[ILDasm.exe](#)
[InstallUtil.exe](#)
[loading](#)
[manifest, metadata included](#)
[modules](#) [2nd](#)
[reflection and](#)
[namespaces and](#)
[naming](#)
[Ngen.exe](#)
[quick reference entries](#)
[RegAsm.exe and](#)
[RegSvcs.exe](#)
[resolving](#)
[resources](#)
[security permissions](#)
[signing](#)
[Sn.exe](#)

[type references](#)

[types](#)

[version number](#)

[WinCV.exe](#)

[Assembly class, System.Reflection API](#)

[AssemblyAlgorithmIdAttribute sealed class, System.Reflection API](#)

[AssemblyBuilder sealed class, System.Reflection.Emit](#)

[AssemblyBuilderAccess enumeration, System.Reflection.Emit](#)

[AssemblyCompanyAttribute sealed class, System.Reflection API](#)

[AssemblyConfigurationAttribute sealed class, System.Reflection API](#)

[AssemblyCopyrightAttribute sealed class, System.Reflection API](#)

[AssemblyCultureAttribute sealed class, System.Reflection API](#)

[AssemblyDefaultAliasAttribute sealed class, System.Reflection API](#)

[AssemblyDelaySignAttribute sealed class, System.Reflection API](#)

[AssemblyDescriptionAttribute sealed class, System.Reflection API](#)

[AssemblyFileVersionAttribute sealed class, System.Reflection API](#)

[AssemblyFlagsAttribute sealed class, System.Reflection API](#)

[AssemblyInformationalVersionAttribute sealed class, System.Reflection API](#)

[AssemblyKeyFileAttribute sealed class, System.Reflection API](#)

[AssemblyKeyNameAttribute sealed class, System.Reflection API](#)

[AssemblyLoadEventArgs class, System namespace](#)

[AssemblyLoadEventHandler delegate, System namespace](#)

[AssemblyName sealed class, System.Reflection API](#)

[AssemblyNameFlags enumerations, System.Reflection API](#)

[AssemblyNameProxy classes, System.Reflection API](#)

[AssemblyProductAttribute sealed classes, System.Reflection API](#)

[AssemblyRegistrationFlags enumeration, System.Runtime.InteropServices](#)

[AssemblyTitleAttribute sealed classes, System.Reflection API](#)

[AssemblyTrademarkAttribute sealed classes, System.Reflection API](#)

[AssemblyVersionAttribute sealed classes, System.Reflection API](#)

[assertion, diagnostics and](#)

[AsyncCallback delegate, System namespace](#) [2nd](#)

[asynchronous delegates, threading and](#)

[asynchronous I/O](#)

[atomic operations, thread synchronization](#)

[Attribute abstract class, System namespace](#)

[attribute classes](#)

[attributes](#)

[\[AttributeUsage\]](#)

[brackets \(\[\]\) and](#)

[\[CLSCompliant\]](#)

[COM interop](#)

[\[Conditional\]](#)

[custom](#)

[compilers](#)

[creating](#)

[language](#)

[predefined attributes](#)

[retrieving at runtime](#)

[runtime support](#)

[DllImport](#)

[FieldOffset](#)

[In](#)
[MarshalAs](#)
[multiple](#)
[\[NonSerialized\]](#)
[\[Obsolete\]](#)
[Out](#)
[predefined](#)
[interoperable](#)
[\[Serializable\]](#)
[StructLayout](#) [2nd](#)
[targets](#)

[AttributeTargets enumeration, System namespace](#)
[\[AttributeUsage\] attribute](#)
[AttributeUsageAttribute sealed class, System namespace](#)
[AuthenticationManager class, System.Net](#)
[Authorization class, System.Net](#)
[AutoResetEvent sealed class, System.Threading](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[back references, regular expressions](#)
[BadImageFormatException class, System namespace](#)
[base keyword](#) [2nd](#)
[Berkeley sockets](#)
[BestFitMappingAttribute sealed class, System.Runtime.InteropServices](#)
[binary format, mapping structs to](#)
[BinaryFormatter sealed class, System.Runtime.Serialization.Formatter](#)
[BinaryReader class, System.I/O](#)
[BinaryReader class, System.IO](#)
[BinaryWriter class, System.I/O](#)
[BinaryWriter class, System.IO](#)
[Binder abstract class, System.Reflection API](#)
[binding](#)
 [COM and C# objects](#)
 [late binding, reflection and](#)
[BindingFlags enumerations, System.Reflection API](#)
[BitArray sealed class, System.Collections](#)
 [collections and](#)
[BitConverter sealed class, System namespace](#)
[BitVector32 struct, System.Collections.Specialized](#)
[BitVector32.Section struct, System.Collections.Specialized](#)
[blocks](#)
 [catch blocks](#)
 [finally block](#)
 [try blocks](#)
[bool keyword](#)
[bool types](#)
[Boolean struct, System namespace](#)
[BooleanSwitch class, System.Diagnostics](#)
[bounds checking, arrays](#)
[boxing value types](#)
[brackets \(\[\]\)](#)
 [in arrays](#)
 [in attributes](#)
[break keyword](#)
[break statement](#)
[Buffer sealed class, System namespace](#)
[BufferedStream sealed class, System.IO](#)
[builder classes, System.Reflection.Emit namespace](#)
[byte keyword](#)
[Byte struct, System namespace](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

C#

- [COM mapping](#)
- [COM object exposure](#)
- [language overview](#)
- [managed language description](#)
- objects
 - [binding COM objects](#)
 - [COM exposure](#)
 - [online resources for further information](#)
 - [syntax table](#)
- [C/C++ comments](#)
- [Calendar class, System.Globalization](#)
- [CalendarWeekRule enumeration, System.Globalization](#)
- [callbacks, P/Invoke layer and](#)
- [calling into DLLs](#)
- [CallingConvention enumeration, System.Runtime.InteropServices](#)
- [CallingConventions enumerations, System.Reflection API](#)
- [Camel, naming convention case and](#)
- [CannotUploadAppDomainException class, System namespace](#)
- [CanRead method, Stream class](#)
- [CanSeek method, Stream class](#)
- [CanWrite method, Stream class](#)
- [Capture class, System.Text.RegularExpressions](#)
- [CaptureCollection class, System.Text.RegularExpressions](#)
 - [strings and](#)
- [case keyword](#)
- [case, naming conventions](#)
- [CaseInsensitiveComparer class, System.Collections](#)
- [CaseInsensitiveHashCodeProvider class, System.Collections](#)
- [catch blocks](#)
- [catch clause](#)
 - [catch expression](#)
 - [exception variable](#)
 - [multiple](#)
- [catch keyword](#)
- [CCW \(COM Callable Wrapper\)](#)
- [char keyword](#)
- [Char struct, System namespace](#)
- [char types](#)
- [character sets, regular expressions](#)
- [CharEnumerator sealed class, System namespace](#)
- [CharSet enumeration, System.Runtime.InteropServices](#)
- [checked keyword](#)
- [checked operators, arithmetic overflow](#)
- [CIL \(Common Intermediate Language\)](#)
- [class keyword](#)
- [classes](#) [See also sealed classes][2nd](#) [See also abstract classes]

- [stream-derived](#)
- [StreamReader](#)
- [StreamWriter](#)
- [string class](#)
 - [types and](#)
- [StringBuilder](#)
- [StringCollection, collections and](#)
- [StringDictionary, collections and](#)
- [StringReader](#)
- [StringWriter](#)
- [struct comparison](#)
- System namespace
 - [AppDomainUnloadedException](#)
 - [ApplicationException](#)
 - [ArgumentException](#)
 - [ArgumentNullException](#)
 - [ArgumentOutOfRangeException](#)
 - [ArithmeticException](#)
 - [ArrayTypeMismatchException](#)
 - [AssemblyLoadEventArgs](#)
 - [BadImageFormatException](#)
 - [CannotUploadAppDomainException](#)
 - [ContextMarshalException](#)
 - [ContextStaticAttribute](#)
 - [DivideByZeroException](#)
 - [DllNotFoundException](#)
 - [DuplicateWaitObjectException](#)
 - [EntryPointNotFoundException](#)
 - [EventArgs](#)
 - [Exception](#)
 - [FieldAccessException](#)
 - [FlagsAttribute](#)
 - [FormatException](#)
 - [InvalidCastException](#)
 - [InvalidOperationException](#)
 - [MemberAccessException](#)
 - [MethodAccessException](#)
 - [MissingFieldException](#)
 - [MissingMemberException](#)
 - [MissingMethodException](#)
 - [NotFiniteNumberException](#)
 - [NotImplementedException](#)
 - [NotSupportedException](#)
 - [NullReferenceException](#)
 - [Object](#)
 - [ObjectDisposedException](#)
 - [OutOfMemoryException](#)
 - [OverflowException](#)
 - [PlatformNotSupportedException](#)
 - [Random](#)
 - [RankException](#)
 - [ResolveEventArgs](#)

[SystemException](#)
[ThreadStaticAttribute](#)
[TypeLoadException](#)
[TypeUnloadedException](#)
[UnauthorizedAccessException](#)
[UnhandledExceptionEventArgs](#)
[UnhandledExceptionHandler](#)
[Uri](#)
[UriBuilder](#)
[UriException](#)
[WeakReference](#)

[System.Activator](#)

System.Diagnostics namespace

[BooleanSwitch](#)
[CounterCreationData](#)
[CounterCreationDataCollection](#)
[DefaultTraceListener](#)
[EntryWrittenEventArgs](#)
[EventLog](#)
[EventLogEntryCollection](#)
[EventLogInstaller](#)
[EventLogPermissionAttribute](#)
[EventLogPermissionEntry](#)
[EventLogPermissionEntryCollection](#)
[InstanceData](#)
[InstanceDataCollection](#)
[InstanceDataCollectionCollection](#)
[MonitoringDescriptionAttribute](#)
[PerformanceCounterInstaller](#)
[PerformanceCounterPermissionAttribute](#)
[PerformanceCounterPermissionEntry](#)
[PerformanceCounterPermissionEntryCollection](#)
[Process](#)
[ProcessModule](#)
[ProcessModuleCollection](#)
[ProcessThread](#)
[ProcessThreadCollection](#)
[StackFrame](#)
[StackTrace](#)
[TextWriterTraceListener](#)
[TraceListenerCollection](#)
[TraceSwitch](#)

System.Globalization namespace

[CompareInfo](#)
[CultureInfo](#)
[DaylightTime](#)
[GregorianCalendar](#)
[HebrewCalendar](#)
[HijriCalendar](#)
[JapaneseCalendar](#)
[JulianCalendar](#)
[KoreanCalendar](#)

[RegionInfo](#)

System.IO namespace

[BinaryReader](#)

[BinaryWriter](#)

[DirectoryNotFoundException](#)

[EndOfStreamException](#)

[ErrorEventArgs](#)

[FileLoadException](#)

[FileNotFoundException](#)

[FileStream](#)

[FileSystemEventArgs](#)

[FileSystemWatcher](#)

[InternalBufferOverflowException](#)

[IODescriptionAttribute](#)

[IOException](#)

[MemoryStream](#)

[PathTooLongException](#)

[RenamedEventArgs](#)

[StreamReader](#)

[StreamWriter](#)

[StringReader](#)

[StringWriter](#)

System.IO.IsolatedStorage namespace

[IsolatedStorageException](#)

[IsolatedStorageFileStream](#)

System.Net namespace

[AuthenticationManager](#)

[Authorization](#)

[CookieCollection](#)

[CookieContainer](#)

[CookieException](#)

[CredentialCache](#)

[Dns](#)

[EndPointPermission](#)

[FileWebRequest](#)

[FileWebResponse](#)

[GlobalProxySelection](#)

[HttpVersion](#)

[HttpWebRequest](#)

[HttpWebResponse](#)

[IPAddress](#)

[IPEndPoint](#)

[IPHostEntry](#)

[NetworkCredential](#)

[ProtocolViolationException](#)

[ServicePoint](#)

[ServicePointManager](#)

[SocketAddress](#)

[WebException](#)

[WebHeaderCollection](#)

[WebProxy](#)

System.Net.Sockets namespace

[IPv6MulticastOption](#)

[LingerOption](#)

[MulticastOption](#)

[NetworkStream](#)

[Socket](#)

[SocketException](#)

[TcpClient](#)

[TcpListener](#)

[UdpClient](#)

System.Reflection.Emit namespace

[CustomAttributeBuilder](#)

[ILGenerator](#)

[ModuleBuilder](#)

[OpCodes](#)

[ParameterBuilder](#)

System.Runtime.InteropServices namespace

[COMException](#)

[ExternalException](#)

[InvalidComObjectException](#)

[InvalidOleVariantTypeException](#)

[MarshalDirectiveException](#)

[RegistrationServices](#)

[RuntimeEnvironment](#)

[SaveArrayRankMismatchException](#)

[SaveArrayTypeMismatchException](#)

[SEHException](#)

System.Runtime.Serialization namespace

[FormatterConverter](#)

[ObjectIDGenerator](#)

[ObjectManager](#)

[SerializationException](#)

[SurrogateSelector](#)

System.Runtime.Serialization.Formatters namespace

[SoapMessage](#)

System.Text namespace

[ASCIIEncoding](#)

[UnicodeEncoding](#)

[UTF7Encoding](#)

System.Text.RegularExpressions namespace

[Capture](#)

[CaptureCollection](#)

[Group](#)

[GroupCollection](#)

[Match](#)

[MatchCollection](#)

[Regex](#)

[RegexCompilationInfo](#)

System.Threading namespace

[Overlapped](#)

[SynchronizationLockException](#)

[ThreadExceptionEventArgs](#)

[ThreadInterruptedException](#)

[ThreadStateException](#)

System.Timers namespace

[ElapsedEventArgs](#)

[Timer](#)

[TimersDescriptionAttribute](#)

System.Xml namespace

[NameTable](#)

[XmlAttribute](#)

[XmlAttributeCollection](#)

[XmlCDATASection](#)

[XmlComment](#)

[XmlConvert](#)

[XmlDataDocument](#)

[XmlDeclaration](#)

[XmlDocument](#)

[XmlDocumentFragment](#)

[XmlDocumentType](#)

[XmlElement](#)

[XmlEntity](#)

[XmlEntityReference](#)

[XmlException](#)

[XmlImplementation](#)

[XmlNamedNodeMap](#)

[XmlNamespaceManager](#)

[XmlNodeChangedEventArgs](#)

[XmlNodeReader](#)

[XmlNotation](#)

[XmlParserContext](#)

[XmlProcessingInstructor](#)

[XmlQualifiedName](#)

[XmlSecureResolver](#)

[XmlSignificantWhitespace](#)

[XmlText](#)

[XmlTextReader](#)

[XmlTextWriter](#)

[XmlUriResolver](#)

[XmlValidatingReader](#)

[XmlWhitespace](#)

System.Xml.XPath namespace

[XPathDocument](#)

[XPathException](#)

System.Xml.Xsl namespace

[XsltCompileException](#)

[XsltException](#)

System.Collections namespace

[ArrayList](#)

[CaseInsensitiveComparer](#)

[CaseInsensitiveHashCodeProvider](#)

[Hashtable](#)

[Queue](#)

[SortedList](#)

[Stack](#)

System.Collections.Specialized namespace

[CollectionsUtil](#)

[HybridDictionary](#)

[ListDictionary](#)

[NameObjectCollectionBase.KeysCollection](#)

[NameValueCollection](#)

[StringCollection](#)

[StringDictionary](#)

[StringEnumerator](#)

System.Reflection API

[Assembly](#)

[AssemblyNameProxy](#)

[CustomAttributeFormatException](#)

[InvalidFilterCriteriaException](#)

[ManifestResourceInfo](#)

[Module](#)

[ParameterInfo](#)

[StrongNameKeyPair](#)

[TargetException](#)

[TypeDelegator](#)

[TcpClient](#)

[TcpListener](#)

[Trace](#)

[Type, reflection and](#)

[UdpClient](#)

[XmlNodeReader](#)

[XmlReader](#)

[XmlValidatingReader](#)

[XmlWriter](#)

[classesXmlTextReader](#)

[ClassInterfaceAttribute](#) sealed class, System.Runtime.InteropServices

[ClassInterfaceType](#) enumeration, System.Runtime.InteropServices

[CLI \(Common Language Infrastructure\)](#)

[Close\(\)](#) method, memory management

[CLR \(Common Language Runtime\)](#) 2nd

[classes, COM+ and](#)

[data marshaling](#)

[managed execution and](#)

[strings, indexed](#)

[CLR marshaler](#)

[CLS \(Common Language Specification\)](#)

[CLS Consumers](#)

[CLS Extenders](#)

[CTS and](#)

[\[CLSCompliant\]](#) attribute

[CLSCompliantAttribute](#) sealed class, System namespace

[CoClassAttribute](#) sealed class, System.Runtime.InteropServices

code

[introductory program](#)

[unsafe](#)

[CollectionBase](#) abstract class, System.Collections

collections

[Array class](#)

[ArrayList class](#)

[Assembly API](#)

[BitArray class](#)

[FCL](#)

[hash code generation](#)

[Hashtable class](#)

[IComparable interface](#)

[IComparer interfaces](#)

[IEnumerable interface and](#)

[IEnumerator interface and](#)

[interfaces](#)

[ICollection](#)

[IDictionary](#)

[IList](#)

[iteration and](#)

[ordering and](#)

[predefined classes](#)

[Queue class](#)

[SortedList class](#)

[Stack class](#)

[StringCollection class](#)

[StringDictionary class](#)

[CollectionsUtil class, System.Collections.Specialized](#)

COM

[binding C# objects](#)

[component-based software and](#)

[interop support attributes](#)

[mapping in C#](#)

[objects, exposing to C#](#)

[typelib](#)

[TlbExp.exe](#)

[TlbImp.exe](#)

[COM Callable Wrapper](#) [See CCW]

COM+ services

[FCL and](#)

[COM+ support](#)

[COM+, CLR classes and](#)

[ComAliasNameAttribute sealed class, System.Runtime.InteropServices](#)

[ComCompatibleVersionAttribute sealed class, System.Runtime.InteropServices](#)

[ComConversionLossAttribute sealed class, System.Runtime.InteropServices](#)

[COMException class, System.Runtime.InteropServices](#)

[ComImportAttribute sealed class, System.Runtime.InteropServices](#)

[ComInterfaceType enumeration, System.Runtime.InteropServices](#)

commands

[Cordbg.exe](#)

[GacUtil.exe](#)

[ComMemberType enumeration, System.Runtime.InteropServices](#)

[comments in XML documentation](#)

[C/C++ style](#)

[Common Intermediate Language](#) [See CIL]

[Common Language Infrastructure](#) [See CLI]

[Common Language Runtime](#) [See CLR]
[Common Type System](#) [See CTS]
[CompareInfo](#) classes, [System.Globalization](#)
[CompareOptions](#) enumeration, [System.Globalization](#)
[Comparer](#) sealed class, [System.Collections](#)
[comparisons](#), [strings](#)
[compilers](#)
 [conditional compilation](#)
 [custom attributes](#)
 [FCL and](#)
 [System.Reflection.Emit](#) namespace and
[compiling](#), [Csc.exe](#) and
[component-based development](#), [enabling](#)
[components](#)
 [language support](#)
 [Nmake.exe](#)
[ComRegisterFunctionAttribute](#) sealed class, [System.Runtime.InteropServices](#)
[ComSourceInterfacesAttribute](#) sealed class, [System.Runtime.InteropServices](#)
[ComUnregisterFunctionAttribute](#) sealed class, [System.Runtime.InteropServices](#)
[ComVisibleAttribute](#) sealed class, [System.Runtime.InteropServices](#)
[\[Conditional\]](#) attribute
[ConditionalAttribute](#) sealed class, [System.Diagnostics](#)
[configuration](#), [FCL and](#)
[Console](#) class
[Console](#) sealed class, [System](#) namespace
[const](#) keyword
[constants](#)
[ConstructorBuilder](#) sealed class, [System.Reflection.Emit](#)
[ConstructorInfo](#) abstract class, [System.Reflection](#) API
[constructors](#)
 [access modifiers](#)
 [inheritance and, initialization](#)
 [instance constructors](#)
 [overloading](#)
 [static](#)
 [nondeterminism](#)
[ContextBoundObject](#) abstract class, [System](#) namespace
[ContextMarshalException](#) class, [System](#) namespace
[ContextStaticAttribute](#) class, [System](#) namespace
[continue](#) keyword
[continue](#) statement
[conversions](#)
 [arrays](#)
 [bool](#) types
 [char](#) types
 [classes](#)
 [decimal](#) types
 [enums](#)
 [explicit](#)
 [floating-point](#) types
 [implicit](#)
 [integral](#) types

[interfaces](#)

[types](#)

[user-defined](#)

[Convert sealed class, System namespace](#)

[Convert type](#)

[Cookie class, System.Net](#)

[CookieCollection class, System.Net](#)

[CookieContainer class, System.Net](#)

[CookieException class, System.Net](#)

[COOL language](#)

[CORBA, component-based software and](#)

[Cordbg.exe](#)

[CounterCreationData class, System.Diagnostics](#)

[CounterCreationDataCollection class, System.Diagnostics](#)

[CounterSample struct, System.Diagnostics](#)

[CounterSampleCalculator sealed class, System.Diagnostics](#)

[CredentialCache class, System.Net](#)

[cross-references in quick reference](#)

[cross-references, XML types](#)

[CrossAppDomainDelegate delegate, System namespace](#)

[Csc.exe](#)

[CSP \(Cryptographic Service Provider\), Sn.exe and](#)

[CTS \(Common Type System\)](#)

[CLS and](#)

[CultureInfo class, System.Globalization](#)

[CultureTypes enumeration, System.Globalization](#)

[CurrencyWrapper sealed class, System.Runtime.InteropServices](#)

[custom attributes](#)

[compilers](#)

[creation](#)

[language](#)

[predefined attributes](#)

[retrieving at runtime](#)

[runtime support](#)

[custom types](#)

[CustomAttributeBuilder class, System.Reflection.Emit](#)

[CustomAttributeFormatException class, System.Reflection API](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[data](#)

- [description](#)
- [types and](#)

[data access, FCL and](#)

[data marshaling](#)

[data members](#)

- [classes, definition](#)

[databases, FCL and](#)

[date and time format specifiers](#)

[DateTime format specifiers](#)

[DateTime struct, System namespace](#)

[DateTimeFormatInfo sealed class, System.Globalization](#)

[DateTimeStyles enumeration, System.Globalization](#)

[DaylightTime class, System.Globalization](#)

[DayOfWeek enumeration, System namespace](#)

[DbgCLR.exe](#)

[DBNull sealed class, System namespace](#)

[deadlocks, threading and 2nd](#)

[Debug class](#)

- [conditional compiling](#)

[Debug sealed class, System.Diagnostics](#)

[DebuggableAttribute sealed class, System.Diagnostics](#)

[Debugger sealed class, System.Diagnostics](#)

[DebuggerHiddenAttribute sealed class, System.Diagnostics](#)

[DebuggerStepThroughAttribute sealed class, System.Diagnostics](#)

[debugging](#)

- [Cordbg.exe utility](#)
- [DbgCRL.exe](#)
- [FCL and](#)
- [integration](#)

[decimal keyword](#)

[Decimal structs, System namespace](#)

[decimal types](#)

[declaration statements](#)

[declarations](#)

- [arrays](#)
- [field](#)
- [local](#)
- [field](#)

[Decoder abstract class, System.Text](#)

[default keyword](#)

[DefaultMemberAttribute sealed class, System.Reflection API](#)

[DefaultTraceListener class, System.Diagnostics](#)

[Delegate abstract class, System namespace](#)

[delegate keyword](#)

[delegates](#)

- [asynchronous, threading and](#)

[events and](#)

[function pointers comparison](#)

[interfaces comparison](#)

Microsoft.Win32 namespace

[PowerModeChangedEventHandler](#)

[SessionEndedEventHandler](#)

[SessionEndingEventHandler](#)

[TimerElapsedEventHandler](#)

[UserPreferenceChangedEventHandler](#)

[UserPreferenceChangingEventHandler](#)

[multicast](#)

[return types](#)

System

[AssemblyLoadEventHandler](#)

[AsyncCallback](#)

[CrossAppDomainDelegate](#)

[EventHandler](#)

[ResolveEventHandler](#)

[System.Diagnostics, EntryWrittenEventHandler](#)

System.IO

[ErrorEventHandler](#)

[FileSystemEventHandler](#)

[RenamedEventHandler](#)

[System.Net, HttpContinueDelegate](#)

[System.Runtime.InteropServices, ObjectCreationDelegate](#)

[System.Text.RegularExpressions, MatchEvaluator](#)

System.Threading

[IOCompletionCallback](#)

[ThreadExceptionEventHandler](#)

[ThreadStart](#)

[TimerCallback](#)

[WaitCallback](#)

[WaitOrTimerCallback](#)

[System.Timers, ElapsedEventHandler](#)

[System.Xml, XmlNodeChangedEventHandler](#)

System.Reflection API

[MemberFilter](#)

[ModuleResolveEventHandler](#)

[TypeFilter](#)

[deployment, assemblies and](#)

[deserialization](#)

[destructors](#)

[diagnostics 2nd](#) [See also [System.Diagnostics](#)]

[assertion and](#)

[FCL and](#)

[logging and](#)

[performance counters](#)

[DictionaryBase abstract class, System.Collections](#)

[DictionaryEntry struct, System.Collections](#)

directives

[#error symbol](#)

[#warning symbol](#)

[preprocessor directives](#)

[using](#)

[directories](#)

[DirectoryInfo class](#)

[FileInfo class](#)

[Directory class, FileStream and](#)

[Directory sealed class, System.IO](#)

[DirectoryInfo class](#)

[DirectoryInfo sealed class, System.IO](#)

[DirectoryNotFoundException class, System.IO](#)

[DispatchWrapper sealed class, System.Runtime.InteropServices](#)

[DispidAttribute sealed class, System.Runtime.InteropServices](#)

[Dispose\(\) method](#)

[DivideByZeroException class, System namespace](#)

[DllImport attribute](#)

[DllImportAttribute sealed class, System.Runtime.InteropServices](#)

[DllNotFoundException class, System namespace](#)

[DLLs, calling into](#)

[DNS \(Domain Name System\)](#)

[Dns class, System.Net](#)

[DnsPermission sealed class, System.Net](#)

[DnsPermissionAttribute sealed class, System.Net](#)

[do keyword](#)

[do-while loops](#)

[documentation, XML](#)

[comments](#)

[comments, C/C++ style](#)

[documentation files](#)

[generated](#)

[documents, XML](#)

[double floating-point types](#)

[double keyword](#)

[Double struct, System namespace](#)

[DuplicateWaitObjectException class, System namespace](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[ECMA \(European Computer Manufacturers Association\)](#)

[standardization](#)

[ElapsedEventArgs class, System.Timers](#)

[ElapsedEventHandler delegate, System.Timers](#)

[else keyword](#)

[encapsulation, raw streams](#)

[encoded strings](#)

[Encoder abstract class, System.Text](#)

[Encoding abstract class, System.Text](#)

[EndOfStreamException class, System.IO](#)

[EndPoint abstract class, System.Net](#)

[EndPointPermission class, System.Net](#)

[Enter\(\) method, threading and](#)

[EntityHandling enumeration, System.Xml](#)

[EntryPointNotFoundException class, System namespace](#)

[EntryWrittenEventArgs class, System.Diagnostics](#)

[EntryWrittenEventHandler delegate, System.Diagnostics](#)

[Enum abstract class, System namespace](#)

[enum keyword](#)

[Enum type](#)

[EnumBuilder sealed class, System.Reflection.Emit](#)

[enumeration](#)

[isolated storage contents](#)

[performance counters](#)

[enumerations](#)

[Microsoft.Win32 namespace](#)

[PowerModes](#)

[RegistryHive](#)

[SessionEndReasons](#)

[UserPreferenceCategory](#)

[System](#)

[AttributeTargets](#)

[DayOfWeek](#)

[Environment.SpecialFolder](#)

[LoaderOptimization](#)

[PlatformID](#)

[TypeCode](#)

[UriHostNameType](#)

[UriPartial](#)

[System.Diagnostics](#)

[EventLogEntryType](#)

[EventLogPermissionAccess](#)

[PerformanceCounterPermissionAccess](#)

[PerformanceCounterType](#)

[ProcessPriorityClass](#)

[ProcessWindowStyle](#)

[ThreadPriorityLevel](#)

[ThreadState](#)

[ThreadWaitReason](#)

[TraceLevel](#)

System.Globalization

[CalendarWeekRule](#)

[CompareOptions](#)

[CultureTypes](#)

[DateTimeStyles](#)

[GregorianCalendarTypes](#)

[NumberStyle](#)

System.IO

[FileAccess](#)

[FileAttributes](#)

[FileMode](#)

[FileShare](#)

[NotifyFilters](#)

[SeekOrigin](#)

[WatcherChangeTypes](#)

[System.IO.IsolatedStorage, IsolatedStorageScope](#)

System.Net

[HttpStatusCode](#)

[NetworkAccess](#)

[SecurityProtocolType](#)

[TransportType](#)

[WebExceptionStatus](#)

System.Net.Sockets

[AddressFamily](#)

[ProtocolFamily](#)

[ProtocolType](#)

[SelectMode](#)

[SocketFlags](#)

[SocketOptionLevel](#)

[SocketOptionName](#)

[SocketShutdown](#)

[SocketType](#)

System.Reflection.Emit

[AssemblyBuilderAccess](#)

[FlowControl](#)

[OpCodeType](#)

[OperandType](#)

[PackingSize](#)

[PEFileKinds](#)

[StackBehaviour](#)

System.Runtime.InteropServices

[AssemblyRegistrationFlags](#)

[CallingConvention](#)

[CharSet](#)

[ClassInterfaceType](#)

[ComInterfaceType](#)

[ComMemberType](#)

[GCHandleType](#)

[IDispatchImplType](#)

[LayoutKind](#)
[UnmanagedType](#)
[VarEnum](#)

[System.Runtime.Serialization, StreamingContextStates](#)

System.Runtime.Serialization.Formatter

[FormatterAssemblyStyle](#)
[FormatterTypeStyle](#)
[TypeFilterLevel](#)

[System.Text.RegularExpressions, RegexOptions](#)

System.Threading

[ApartmentState](#)
[ThreadPriority](#)
[ThreadState](#)

System.Xml

[EntityHandling](#)
[Formatting](#)
[ReadState](#)
[ValidationType](#)
[WhitespaceHandling](#)
[WriteState](#)
[XmlNodeChangedAction](#)
[XmlNodeOrder](#)
[XmlNodeType](#)
[XmlSpace](#)
[XmlTokenizedType](#)

System.Xml.XPath

[XmlCaseOrder](#)
[XmlDateType](#)
[XmlSortOrder](#)
[XPathNamespaceScope](#)
[XPathNodeType](#)
[XPathResultType](#)

System.Reflection API

[AssemblyNameFlags](#)
[BindingFlags](#)
[CallingConventions](#)
[EventAttributes](#)
[FieldAttributes](#)
[MemberTypes](#)
[MethodAttributes](#)
[MethodImplAttributes](#)
[ParameterAttributes](#)
[PropertyAttributes](#)
[ResourceAttributes](#)
[ResourceLocation](#)
[TypeAttributes](#)

[enums](#)

[conversions](#)
[operators](#)

[Environment sealed class, System namespace](#)

[Environment.SpecialFolder enumeration, System namespace](#)

[equality of values, operator overloading and](#)

[error reporting](#)

[ErrorEventArgs class, System.IO](#)

[ErrorEventHandler delegate, System.IO 2nd](#)

[ErrorWrapper sealed class, System.Runtime.InteropServices](#)

[escape characters, regular expressions](#)

[event handlers](#)

[event keyword](#)

[event logs](#)

[monitoring](#)

[reading](#)

[writing to](#)

[EventArgs classes, System namespace](#)

[EventArgs classes, System namespace](#)

[EventAttributes enumerations, System.Reflection API](#)

[EventBuilder sealed class, System.Reflection.Emit](#)

[EventHandler delegate, System namespace](#)

[EventInfo abstract class, System.Reflection API](#)

[EventLog class, System.Diagnostics](#)

[EventLogEntry sealed class, System.Diagnostics](#)

[EventLogEntryCollection class, System.Diagnostics](#)

[EventLogEntryType enumeration, System.Diagnostics](#)

[EventLogInstaller class, System.Diagnostics](#)

[EventLogPermission sealed class, System.Diagnostics](#)

[EventLogPermissionAccess enumeration, System.Diagnostics](#)

[EventLogPermissionAttribute class, System.Diagnostics](#)

[EventLogPermissionEntry class, System.Diagnostics](#)

[EventLogPermissionEntryCollection class, System.Diagnostics](#)

[EventLogTraceListener sealed class, System.Diagnostics](#)

[events](#)

[accessors](#)

[declaring](#)

[delegates and](#)

[EventArgs class](#)

[filesystem, catching](#)

[firing](#)

[index](#)

[EventToken struct, System.Reflection.Emit](#)

[Exception class, System namespace](#)

[exception handling](#)

[Exception type](#)

[exceptions](#)

[application exceptions](#)

[ArgumentException](#)

[system exceptions](#)

[System.Exception](#)

[try statements and](#)

[variables, omitting](#)

[ExecutionEngineException sealed class, System namespace](#)

[Exit\(\) method, threading and](#)

[explicit conversions 2nd](#)

[explicit keyword](#)

[expression statements](#)

[expression-based patterns](#)

[expressions](#)

[catch expression](#)

[regular expressions, strings and](#)

[ExtensibleClassFactory sealed class, System.Runtime.InteropServices](#)

[extern keyword](#)

[ExternalException class, System.Runtime.InteropServices](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[false keyword](#)

[three-state logic operators](#)

[FCL \(Framework Class Library\)](#) [2nd](#) [3rd](#)

[assemblies](#)

[collections](#)

[COM+ services and](#)

[compilers and](#)

[configuration](#)

[data access and](#)

[debugging and](#)

[diagnostics and](#)

[globalization and](#)

[graphics and](#)

[GUI applications](#)

[HTTP protocol and](#)

[I/O](#)

[metadata](#)

[MSMQ and](#)

[networking](#)

[OS facilities, native](#)

[reflection](#)

[remoting](#)

[runtime facilities](#)

[security](#)

[serialization](#)

[streams](#)

[text](#)

[threading](#)

[tools](#)

[types, core types](#)

[undocumented types](#)

[unmanaged code and](#)

[web services](#)

[web-based applications and](#)

[XML and](#)

[field declarations, arrays](#)

[FieldAccessException class, System namespace](#)

[FieldAttributes enumeration, System.Reflection API](#)

[FieldBuilder sealed class, System.Reflection.Emit](#)

[FieldInfo abstract class, System.Reflection API](#)

[FieldOffset attribute](#)

[FieldOffsetAttribute class, sealed System.Runtime.InteropServices](#)

[fields](#)

[constants](#)

[index](#)

[inheritance and, initialization](#)

[initialization order](#)

- [static fields](#)
- [introduction](#)
- [nonstatic](#)
- [properties](#)
- [readonly modifier](#)
- [FieldToken struct, System.Reflection.Emit](#)
- [File class, FileStream and](#)
- [File class, System.IO](#)
- [FileAccess enumeration, System.IO](#)
- [FileAttributes enumeration, System.IO](#)
- [FileInfo class sealed class, System.IO](#)
- [FileInfo sealed class, System.IO](#)
- [FileLoadException class, System.IO](#)
- [FileMode enumeration, System.IO](#)
- [FileNotFoundException class, System.IO](#)
- files
 - [namespaces](#)
 - [reading, I/O](#)
 - [writing, I/O](#)
 - [XML documentation](#)
 - [FileShare enumeration, System.IO](#)
 - [FileStream class, System.IO 2nd 3rd](#)
 - [filesystem events, catching](#)
 - [FileSystemEventArgs class, System.IO](#)
 - [FileSystemEventHandler delegate, System.IO 2nd](#)
 - [FileSystemInfo abstract class, System.IO](#)
 - [FileSystemWatcher class, System.IO 2nd](#)
 - [FileVersionInfo sealed class, System.Diagnostics](#)
 - [FileWebRequest class, System.Net](#)
 - [FileWebResponse class, System.Net](#)
 - [Finalize method](#)
- [finalizers](#)
 - [memory management](#)
- [finally block](#)
- [finally keyword](#)
- [fixed keyword](#)
- [fixed statement, pointers and](#)
- [flags, quick reference entries](#)
- [FlagsAttribute class, System namespace](#)
- [float keyword](#)
- [floating-point types](#)
 - [conversions](#)
- [FlowControl enumeration, System.Reflection.Emit](#)
- [for keyword](#)
- [for loops](#)
- [foreach keyword](#)
- [foreach loops](#)
- Format method
 - [date and time formats](#)
 - [numeric formats](#)
 - [picture formats](#)
- format specifiers

[date and time formats](#)

[DateTime](#)

[numeric](#)

[numeric formats](#)

[picture](#)

[picture formats](#)

[Format\(\) method, string formatting](#)

[format-specification string](#)

[FormatException class, System namespace](#)

[Formatter abstract class, System.Runtime.Serialization](#)

[FormatterAssemblyStyle enumeration, System.Runtime.Serialization.Formatter](#)

[FormatterConverter class, System.Runtime.Serialization](#)

[FormatterServices sealed class, System.Runtime.Serialization](#)

[FormatterTypeStyle enumeration, System.Runtime.Serialization.Formatter](#)

[Formatting enumeration, System.Xml](#)

[formatting strings](#)

[frames, stack frames](#)

[Framework Class Library](#) [See FCL]

function members

virtual

[sealed](#)

[versions](#)

[virtual function members](#)

[overriding](#)

[function pointers, delegates comparison](#)

[functionality, FCL and](#)

functions

[data and](#)

[description](#)

[members](#)

[standalone](#)

[types and](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

- [GAC \(Global Assembly Cache\)](#)
 - [GacUtil.exe and](#)
- [GacUtil.exe 2nd](#)
- [GC \(garbage collector\) 2nd](#)
 - [optimization and](#)
 - [tracing garbage collectors](#)
- [GC sealed class, System namespace](#)
- [GCHandle struct, System.Runtime.InteropServices](#)
- [GCHandleType enumeration, System.Runtime.InteropServices](#)
- [generated documentation, XML](#)
- [get keyword](#)
- [GetEnumerator\(\) method](#)
- [GetHashCode\(\) method](#)
- [GetLength method](#)
- [GetType\(\) method](#)
- [global namespaces](#)
- [globalization, FCL and](#)
- [GlobalProxySelection class, System.Net](#)
- [Golde, Peter](#)
- [goto keyword](#)
- [goto statement](#)
- [graphics, FCL and](#)
- [GregorianCalendar class, System.Globalization](#)
- [GregorianCalendarTypes enumeration, System.Globalization](#)
- [Group class, System.Text.RegularExpressions](#)
 - [strings and](#)
- [GroupCollection class, System.Text.RegularExpressions](#)
- [groups, regular expressions](#)
- [GUI \(graphical user interface\) applications, FCL and](#)
- [Guid struct, System namespace](#)
- [GuidAttribute sealed class, System.Runtime.InteropServices](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[HandleRef struct, System.Runtime.InteropServices](#)
[hash code generation, collections and](#)
[Hashtable class, collections and](#)
[Hashtable class, System.Collections](#)
[heap](#)
[HebrewCalendar class, System.Globalization](#)
[Hejlsberg, Anders](#)
hierarchies

- classes
 - [inheritance and](#)
 - [quick reference entries](#)
 - [types, reflection and 2nd](#)

[HijriCalendar class, System.Globalization](#)
[HTML links, regular expressions and](#)
[HTTP-specific support, networking and](#)
[HttpContinueDelegate delegate, System.Net](#)
[HttpStatusCode enumeration, System.Net](#)
[HttpVersion class, System.Net](#)
[HttpRequest class, System.Net](#)
[HttpWebResponse class, System.Net](#)
[HybridDictionary class, System.Collections.Specialized](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

I/O

- [asynchronous](#)
- [FCL and](#)
- [FileStream](#)
- [reading files](#)
- [writing files](#)
- [IAsyncResult interface, System namespace](#)
- [IAuthenticationModule interface, System.Net](#)
- [ICertificatePolicy interface, System.Net](#)
- [ICloneable interface, System namespace](#)
- [ICollection interface, System.Collections 2nd](#)
- [IComparable interface, System namespace 2nd](#)
- [IComparer interface, System.Collections 2nd](#)
- [IConvertible interface, System namespace](#)
- [ICredentials interface, System.Net](#)
- [ICustomAttributeProvider interface, System.Reflection API](#)
- [ICustomFormatter interface, System namespace](#)
- identifiers
 - [@ prefix](#)
 - [keywords and](#)
- [IDeserializationCallback interface, System.Runtime.Serialization](#)
- [IDictionary interface, System.Collections 2nd](#)
- [IDictionaryEnumerator interface, System.Collections](#)
- [IDispatchImplAttribute sealed class, System.Runtime.InteropServices](#)
- [IDispatchImplType enumeration, System.Runtime.InteropServices](#)
- [IDisposable interface, System namespace](#)
- [IEnumerable interface](#)
 - [collections and](#)
 - [implementation](#)
 - [optimization for](#)
- [IEnumerator interface](#)
 - [collections and](#)
 - [implementation](#)
 - [optimization for](#)
- [IExpando interface, System.Runtime.InteropServices](#)
- [if keyword](#)
- [if-else statements](#)
- [IFieldInfo interface, System.Runtime.Serialization.Formatters](#)
- [IFormatProvider interface, System namespace](#)
- [IFormattable interface, System namespace](#)
- [IFormatter interface, System.Runtime.Serialization](#)
- [IFormatterConverter interface, System.Runtime.Serialization](#)
- [IHashCodeProvider interface, System.Collections](#)
- [IHasXmlNode interface, System.Xml](#)
- ILasm.exe
 - [assemblies and](#)
 - [assembly and](#)

- ILDasm.exe
 - [assemblies and](#)
 - [disassembly and](#)
- [ILGenerator class, System.Reflection.Emit](#)
- [IList interface, System.Collections 2nd](#)
- [immutability of strings](#)
- implementation of interfaces
 - [explicit](#)
 - [reimplementation](#)
- [implicit conversions 2nd](#)
- [integral types](#)
- [implicit keyword](#)
- [In attribute](#)
- [in keyword](#)
- [in/out marshaling](#)
- [InAttribute sealed class, System.Runtime.InteropServices](#)
- [indexers](#)
- [indexes, strings](#)
- [IndexOutOfRangeException sealed class, System namespace](#)
- [indirectly overloadable operators](#)
- [inheritance](#)
 - [constructors, initialization](#)
 - [fields, initialization](#)
 - [finding members](#)
- initialization
 - constructors
 - [inheritance and](#)
 - fields
 - [inheritance and](#)
 - [order](#)
 - [static fields](#)
- [InnerException property, System.Exception](#)
- [INormalizeForIsolatedStorage interface, System.IO.IsolatedStorage](#)
- [InstallUtil.exe](#)
- [instance constructors](#)
- [instance data members, nonstatic fields](#)
- [instance variables, nonstatic fields](#)
- [InstanceData class, System.Diagnostics](#)
- [InstanceDataCollection class, System.Diagnostics](#)
- [InstanceDataCollectionCollection class, System.Diagnostics](#)
- [instances types](#)
- [int keyword](#)
- [int struct](#)
- [Int16 struct, System namespace](#)
- [Int32 struct, System namespace](#)
- [Int64 struct, System namespace](#)
- [interface keyword](#)
- [InterfaceMapping struct, System.Reflection API](#)
- interfaces
 - [C++ and](#)
 - [classes comparison](#)
 - [collections](#)

- [conversions](#)
- [defining](#)
- [delegates comparison](#)
- [extending](#)
- [ICollection](#)
- [IComparable](#)
- [IComparer](#)
- [IDictionary](#)
- [IEnumerable](#)
 - [implementation](#)
 - [optimization for](#)
- [IEnumerator](#)
 - [implementation](#)
 - [optimization for](#)
- [IList](#)
- [implementation](#)
 - [explicit](#)
 - [reimplementation](#)
- System
 - [IAsyncResult](#)
 - [ICloneable](#)
 - [IComparable](#)
 - [IConvertible](#)
 - [ICustomFormatter](#)
 - [IDisposable](#)
 - [IFormatProvider](#)
 - [IFormattable](#)
 - [IServiceProvider](#)
- System.IO.IsolatedStorage
 - [INormalizForIsolatedStorage](#)
- System.Net
 - [IAuthenticationModule](#)
 - [ICertificatePolicy](#)
 - [ICredentials](#)
 - [IWebProxy](#)
 - [IWebRequestCreate](#)
- System.Runtime.InteropServices
 - [IExpando](#)
 - [IRegistrationServices](#)
- System.Runtime.Serialization
 - [IDeserializationCallback](#)
 - [IFormatter](#)
 - [IFormatterConverter](#)
 - [IObjectReference](#)
 - [ISerializable](#)
 - [ISerializationSurrogate](#)
 - [ISurrogateSelector](#)
- System.Runtime.Serialization.Formatter
 - [IFieldInfo](#)
 - [ISoapMessage](#)
- System.Xml
 - [IHasXmlNode](#)

[IXmlLineInfo](#)

System.Xml.XPath

[IXPathNavigable](#)

System.Xml.Xsl

[IXsltContextFunction](#)

[IXsltContextVariable](#)

System.Collections

[ICollection](#)

[IComparer](#)

[IDictionary](#)

[IDictionaryEnumerator](#)

[IEnumerable](#)

[IEnumerator](#)

[IHashCodeProvider](#)

[IList](#)

System.Reflection API

[ICustomAttributeProvider](#)

[IReflect](#)

[uses](#)

[InterfaceTypeAttribute](#) sealed class, System.Runtime.InteropServices

[Interlocked](#) sealed class, System.Threading

[internal](#) access modifiers

[internal](#) keyword

[InternalBufferOverflowException](#) class, System.IO

[interning](#) strings

[interoperable](#) support attributes, predefined

[IntPtr](#) struct, System namespace

[introspection](#), reflection and

[InvalidCastException](#) class, System namespace

[InvalidComObjectException](#) class, System.Runtime.InteropServices

[InvalidFilterCriteriaException](#) class, System.Reflection API

[InvalidOleVariantTypeException](#) class, System.Runtime.InteropServices

[InvalidOperationException](#) class, System namespace

[InvalidProgramException](#) sealed class, System namespace

[ObjectReference](#) interface, System.Runtime.Serialization

[IOCompletionCallback](#) delegate, System.Threading

[IODescriptionAttribute](#) class, System.IO

[IOException](#) class, System.IO

[IP](#) addresses, detecting with regular expressions

[IPAddress](#) class, System.Net

[IPEndPoint](#) class, System.Net

[IHostEntry](#) class, System.Net

[IPv6MulticastOption](#) class, System.Net.Sockets namespace

[IReflect](#) interface, System.Reflection API

[IRegistrationServices](#) interface, System.Runtime.InteropServices

[is](#) keyword

[is](#) operator

[ISerializable](#) interface, System.Runtime.Serialization

[ISerializationSurrogate](#) interface, System.Runtime.Serialization

[IServiceProvider](#) interface, System namespace

[ISoapMessage](#) interface, System.Runtime.Serialization.Formatter

[isolated](#) storage

[content enumeration](#)

[reading](#)

[storadm.exe and](#)

[writing](#)

[IsolatedStorage abstract class, System.IO.IsolatedStorage](#)

[IsolatedStorageException class, System.IO.IsolatedStorage](#)

[IsolatedStorageFile sealed class, System.IO.IsolatedStorage](#)

[IsolatedStorageFileStream class, System.IO.IsolatedStorage 2nd](#)

[IsolatedStorageScope enumeration, System.IO.IsolatedStorage](#)

[ISurrogateSelector interface, System.Runtime.Serialization](#)

[iteration, collections and](#)

[IWebProxy interface, System.Net](#)

[IWebRequestCreate interface, System.Net](#)

[IXmlLineInfo interface, System.Xml](#)

[XPathNavigable interface, System.Xml.XPath](#)

[IXsltContextFunction interface, System.Xml.Xsl](#)

[IXsltContextVariable interface, System.Xml.Xsl](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[jagged arrays](#)
[JapaneseCalendar class, System.Globalization](#)
[joining strings, regular expressions and](#)
[JulianCalendar class, System.Globalization](#)
[jump statements](#)

[\[Team LiB \]](#)

[[Team LiB](#)]

[[SYMBOL](#)] [[A](#)] [[B](#)] [[C](#)] [[D](#)] [[E](#)] [[F](#)] [[G](#)] [[H](#)] [[I](#)] [[J](#)] [[K](#)] [[L](#)] [[M](#)] [[N](#)] [[O](#)] [[P](#)] [[Q](#)] [[R](#)] [[S](#)] [[T](#)] [[U](#)] [[V](#)] [[W](#)] [[X](#)]

- keywords
- [abstract](#)
 - [base](#) [2nd](#)
 - [bool](#)
 - [break](#)
 - [byte](#)
 - [case](#)
 - [catch](#)
 - [char](#)
 - [checked](#)
 - [class](#)
 - [const](#)
 - [continue](#)
 - [decimal](#)
 - [default](#)
 - [delegate](#)
 - [do](#)
 - [double](#)
 - [else](#)
 - [enum](#)
 - [event](#)
 - [explicit](#)
 - [extern](#)
 - [false](#)
 - [finally](#)
 - [fixed](#)
 - [float](#)
 - [for](#)
 - [foreach](#)
 - [get](#)
 - [goto](#)
 - [identifiers and](#)
 - [if](#)
 - [implicit](#)
 - [in](#)
 - [int](#)
 - [interface](#)
 - [internal](#)
 - [is](#)
 - [listing](#)
 - [lock](#)
 - [long](#)
 - [namespace](#)
 - [naming conventions and](#)
 - [new](#)
 - [null](#)
 - [object](#)

[operator](#) [2nd](#) [3rd](#)
[out](#)
[override](#)
[params](#)
[private](#)
[protected](#)
[public](#)
[readonly](#)
[ref](#)
[return](#)
[sbyte](#)
[sealed](#)
[set](#)
[short](#)
[sizeof](#)
[stackalloc](#) [2nd](#)
[static](#)
[string](#)
[struct](#)
[switch](#)
[this](#) [2nd](#)
[throw](#)
[true](#)
[try](#)
[typeof](#)
[uint](#)
[ulong](#)
[unchecked](#)
[unsafe](#) [2nd](#)
[ushort](#)
[using](#) [2nd](#)
[value](#)
[virtual](#)
[void](#)
[volatile](#)
[while](#)

[KoreanCalendar class, System.Globalization](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[Label struct, System.Reflection.Emit](#)
[language support components](#)
[languages](#)
 [custom attributes](#)
 [managed languages](#)
[late binding, reflection and](#)
[LayoutKind enumeration, System.Runtime.InteropServices](#)
[LCIDConversionAttribute sealed class, System.Runtime.InteropServices](#)
[libraries](#)
 [FCL 2nd](#)
 [runtime libraries](#)
 [serialization libraries](#)
[lightweight processes, threads and](#)
[LingerOption class, System.Net.Sockets namespace](#)
[ListDictionary class, System.Collections.Specialized](#)
[literals, floating-point](#)
[liveness, threading](#)
[LoaderOptimization enumeration, System namespace](#)
[LoaderOptimizationAttribute sealed class, System namespace](#)
[loading assemblies](#)
[local declarations, arrays](#)
[LocalBuilder sealed class, System.Reflection.Emit](#)
[LocalDataStoreSlot sealed class, System namespace](#)
[lock keyword](#)
[lock statement](#)
 [thread synchronization and](#)
[LockCookie struct, System.Threading](#)
[logging, diagnostics and](#)
[logic operators, three-state](#)
[logical pairs, operators](#)
[logs](#) [See event logs]
[long keyword](#)
[loop statements](#)
 [do-while loops](#)
 [for loops](#)
 [foreach loops](#)
 [while loops](#)
[loops](#)
 [do-while loops](#)
 [for loops](#)
 [foreach loops](#)
 [while loops](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[managed languages](#)
[manifest, assemblies](#)
[ManifestResourceInfo class, System.Reflection API](#)
[ManualResetEvent sealed class, System.Threading](#)
[mapping](#)
 [COM in C#](#)
 [structs to binary format](#)
[Marsh sealed class, System namespace](#)
[Marshal sealed class, System.Runtime.InteropServices](#)
[MarshalAs attribute](#)
[MarshalAsAttribute sealed class, System.Runtime.InteropServices](#)
[MarshalByRefObject abstract class, System namespace](#)
[MarshalDirectiveException class, System.Runtime.InteropServices](#)
[marshaling](#)
 [classes](#)
 [common types](#)
 [in/out](#)
 [structs](#)
[Match class](#)
 [regular expressions](#)
 [strings and](#)
[Match class, System.Text.RegularExpressions](#)
[MatchCollection class](#)
[MatchCollection class, System.Text.RegularExpressions](#)
[MatchEvaluator delegate, System.Text.RegularExpressions](#)
[mechanics, naming conventions](#)
[MemberAccessException class, System namespace](#)
[MemberFilter delegate, System.Reflection API](#)
[MemberInfo abstract class, System.Reflection API](#)
[members](#)
 [abstract members](#)
 [quick reference entries](#)
[MemberTypes enumeration, System.Reflection API](#)
[memory](#)
 [heap](#)
 [stack](#)
 [types and](#)
[memory management](#)
 [Close\(\) method](#)
 [Dispose\(\) method](#)
 [finalizers](#)
 [garbage collector](#)
 [GC \(garbage collector\)](#)
 [optimization](#)
[MemoryStream class, System.IO](#)
[Message property, System.Exception](#)
[metadata, FCL](#)

[MethodAccessException class, System namespace](#)
[MethodAttributes enumeration, System.Reflection API](#)
[MethodBase abstract class, System.Reflection API](#)
[MethodBuilder sealed class, System.Reflection.Emit](#)
[MethodImplAttributes enumeration, System.Reflection API](#)
[MethodInfo abstract class, System.Reflection API](#)
[MethodRental sealed class, System.Reflection.Emit](#)
[methods](#)

[Close\(\), memory management and](#)

[delegates](#)

[destructors](#)

[Dispose\(\)](#)

[Enter\(\)](#)

[Exit\(\)](#)

[Finalize method](#)

[finalizers](#)

[Format\(\)](#)

[GetEnumerator\(\)](#)

[GetHashCode\(\)](#)

[GetLength](#)

[GetType\(\)](#)

[identifiers](#)

[index](#)

[introduction](#)

[Object.GetHashCode\(\)](#)

[overloading](#)

[Pulse\(\)](#)

[threading and](#)

[PulseAll\(\)](#)

[Regex class](#)

[signatures](#)

[statements](#)

[String.Format\(\)](#)

[TryEnter\(\)](#)

[Wait\(\)](#)

[WebRerquest.Create\(\)](#)

[MethodToken struct, System.Reflection.Emit](#)

[Microsoft Transaction Server](#) [See MTS]

Microsoft.Win32

classes

[PowerModeChangedEventArgs](#)

[SessionEndedEventArgs](#)

[SessionEndingEventArgs](#)

[TimerElapsedEventArgs](#)

[UserPreferenceChangedEventArgs](#)

[UserPreferenceChangingEventArgs](#)

delegates

[PowerModeChangedEventHandler](#)

[SessionEndedEventHandler](#)

[SessionEndingEventHandler](#)

[TimerElapsedEventHandler](#)

[UserPreferenceChangedEventHandler](#)

[UserPreferenceChangingEventHandler](#)

enumerations

[PowerModes](#)

[RegistryHive](#)

[SessionEndReasons](#)

[UserPreferenceCategory](#)

sealed classes

[Registry](#)

[RegistryKey](#)

[SystemEvents](#)

[Missing sealed class, System.Reflection API](#)

[MissingFieldException class, System namespace](#)

[MissingMemberException class, System namespace](#)

[MissingMethodException class, System namespace](#)

[MMC \(Microsoft Management Console\), performance counters and](#)

modifiers

[out modifier](#)

[protected internal modifiers](#)

[Module class, System.Reflection API](#)

[ModuleBuilder class, System.Reflection.Emit](#)

[ModuleResolveEventHandler delegate, System.Reflection API](#)

[modules, assemblies 2nd](#)

[reflection and](#)

[Monitor sealed class, System.Threading](#)

[threads and](#)

[MonitoringDescriptionAttribute class, System.Diagnostics](#)

[MSIL \(Microsoft Intermediate Language\)](#)

[PEVerify.exe](#)

[MSMQ \(Message Queue infrastructure\), FCL and](#)

[MTA \(multithreaded apartments\)](#)

[MTAThreadAttribute sealed class, System namespace](#)

[MTS \(Microsoft Transaction Server\)](#)

[multicast delegates](#)

[MulticastDelegate abstract class, System namespace](#)

[MulticastNotSupportedException sealed class, System namespace](#)

[MulticastOption class, System.Net.Sockets namespace](#)

[multidimensional arrays](#)

[multithreaded applications](#)

[Mutex sealed class, System.Threading](#)

[\[Team LiB \]](#)

[[Team LiB](#)]

[[SYMBOL](#)] [[A](#)] [[B](#)] [[C](#)] [[D](#)] [[E](#)] [[F](#)] [[G](#)] [[H](#)] [[I](#)] [[J](#)] [[K](#)] [[L](#)] [[M](#)] [[N](#)] [[O](#)] [[P](#)] [[Q](#)] [[R](#)] [[S](#)] [[T](#)] [[U](#)] [[V](#)] [[W](#)] [[X](#)]

[named parameters](#)

[NameObjectCollectionBase class, System.Collections.Specialized](#)

[NameObjectCollectionBase.KeysCollection class, System.Collections.Specialized](#)

[namespace keyword](#)

[namespaces](#)

[aliasing](#)

[assemblies](#)

[description](#)

[DLLs and](#)

[files](#)

[global](#)

[naming conventions](#)

[nesting](#)

[quick reference entries](#)

[System 2nd](#)

[System.Collections.Specialized](#)

[System.Diagnostics](#)

[System.Globalization](#)

[System.IO](#)

[System.IO.IsolatedStorage](#)

[System.Net](#)

[System.Net.Sockets](#)

[System.Reflection](#)

[System.Reflection.Emit](#)

[System.Runtime.InteropServices](#)

[System.Runtime.Serialization](#)

[System.Runtime.Serialization.Formatters](#)

[System.Text](#)

[System.Text.RegularExpressions](#)

[System.Threading](#)

[System.Timers](#)

[System.Xml](#)

[System.Xml.XPath](#)

[System.Xml.Xsl](#)

[types and, fully qualified name](#)

[types from](#)

[using keyword and](#)

[NameTable class, System.Xml](#)

[NameValueCollection class, System.Collections.Specialized](#)

[naming conventions](#)

[assemblies](#)

[case](#)

[keywords to avoid](#)

[mechanics](#)

[namespaces](#)

[word choice](#)

[NativeOverlapped structs, System.Threading](#)

nesting

[namespaces](#)

[types](#)

[access modifiers and](#)

[.NET Framework SDK](#)

[DbgCLR.exe](#)

[NetworkAccess enumerations, System.Net](#)

[NetworkCredential class, System.Net](#)

networking

[DNS](#)

[FCL and](#)

[HTTP-specific support](#)

[network programming models](#)

[protocols, adding handlers](#)

[request/response architecture](#)

[sockets](#)

[TCP](#)

[UDP](#)

[WebClient](#)

[NetworkStream class](#)

[NetworkStream class, System.Net.Sockets namespace](#)

[new keyword](#)

[newline character, regular expressions and](#)

[Ngen.exe](#)

[Nmake.exe](#)

[nondeterminism of static constructors](#)

[\[NonSerialized\] attribute](#)

[NonSerializedAttribute sealed class, System namespace](#)

[nonstatic fields](#)

[NotFiniteNumberException class, System namespace](#)

[NotifyFilters enumeration, System.IO](#)

[NotImplementedException class, System namespace](#)

[NotSupportedException class, System namespace](#)

[null keyword](#)

[NullReferenceException class, System namespace](#)

[NumberFormatInfo class, System.Globalization](#)

numbers

[extracting, regular expressions and](#)

[pseudorandom](#)

[NumberStyle enumeration, System.Globalization](#)

[numeric format specifiers](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[Object class, System namespace](#)
[object keyword](#)
[object types](#)
[object-oriented languages](#)
[Object.GetHashCode\(\) method](#)
[ObjectCreationDelegate delegate, System.Runtime.InteropServices](#)
[ObjectDisposedException class, System namespace](#)
[ObjectIDGenerator class, System.Runtime.Serialization](#)
[ObjectManager class, System.Runtime.Serialization](#)
[\[Obsolete\] attribute](#)
[ObsoleteAttribute class, System namespace](#)
[OpCode struct, System.Reflection.Emit](#)
[OpCodes class, System.Reflection.Emit](#)
[OpCodeType enumeration, System.Reflection.Emit](#)
[OperandType enumeration, System.Reflection.Emit](#)
[OperatingSystem class, System namespace](#)
[operator keyword](#) [2nd](#) [3rd](#)
[operator overloading](#)
[operators](#)
 [as](#)
 [enums](#)
 [is](#)
 [logic operators, three-state](#)
 [logical pairs](#)
 [overloading](#)
 [indirectly](#)
 [value equality and](#)
 [pointer-to-member](#)
 [pointers](#)
 [precedence](#)
[optimization, memory management](#)
[OptionalAttribute sealed class, System.Runtime.InteropServices](#)
[ordering, collections and](#)
[OS facilities, FCL and](#)
[Out attribute](#)
[out keyword](#)
[out modifier, parameters](#)
[OutAttribute sealed class, System.Runtime.InteropServices](#)
[OutOfMemoryException class, System namespace](#)
[OverflowException class, System namespace](#)
[Overlapped class, System.Threading](#)
[overloading](#)
 [constructors](#)
 [methods](#)
 [operators](#) [2nd](#)
 [indirectly](#)
 [value equality and](#)

[override keyword](#)
[overriding virtual function members](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[P/Invoke layer, callbacks and](#)
[PackingSize enumeration, System.Reflection.Emit](#)
[ParamArrayAttribute sealed class, System namespace](#)
[ParameterAttributes enumeration, System.Reflection API](#)
[ParameterBuilder class, System.Reflection.Emit](#)
[ParameterInfo class, System.Reflection API](#)
[ParameterModifier struct, System.Reflection API](#)
[parameters](#)
 [arguments, passing by value](#)
 [named](#)
 [out modifier](#)
 [params modifier](#)
 [positional](#)
 [ref modifier](#)
[ParameterToken struct, System.Reflection.Emit](#)
[params keyword](#)
[params modifier](#)
[parsing XML streams](#)
[Pascal, naming convention case and](#)
[pass-by-reference semantics](#)
[Path sealed class, System.IO](#)
[PathTooLongException class, System.IO](#)
[patterns](#)
 [expression-based](#)
 [procedural-based](#)
[PDC \(Professional Developer's Conference\)](#)
[PE \(Portable Executable\) files, assemblies](#)
[PEFileKinds enumeration, System.Reflection.Emit](#)
[performance counters](#)
 [enumeration](#)
 [new](#)
 [reading data](#)
[PerformanceCounter class, System.Diagnostics](#)
[PerformanceCounterCategory sealed class, System.Diagnostics](#)
[PerformanceCounterInstaller class, System.Diagnostics](#)
[PerformanceCounterPermission sealed class, System.Diagnostics](#)
[PerformanceCounterPermissionAccess enumeration, System.Diagnostics](#)
[PerformanceCounterPermissionAttribute class, System.Diagnostics](#)
[PerformanceCounterPermissionEntry classes, System.Diagnostics](#)
[PerformanceCounterPermissionEntryCollection classes, System.Diagnostics](#)
[PerformanceCounterType enumeration, System.Diagnostics](#)
[permissions, assemblies](#)
[PEVerify.exe](#)
[picture format specifiers](#)
[PInvoke \(Platform Invocation Services\)](#)
[PlatformID enumeration, System namespace](#)
[PlatformNotSupportedException class, System namespace](#)

[Pointer sealed class, System.Reflection API](#)

[pointer-to-member operators](#)

[pointers](#)

[fixed statement](#)

[operators](#)

[stackalloc keyword](#)

[umanged code](#)

[unsafe](#)

[void*](#)

[polymorphism](#)

[positional parameters](#)

[PowerModeChangedEventArgs class, Microsoft.Win32](#)

[PowerModeChangedEventHandler delegate, Microsoft.Win32](#)

[PowerModes enumeration, Microsoft.Win32](#)

[precedence of operators](#)

[predefined attributes](#)

[custom attributes](#)

[interoperable](#)

[predefined collection classes](#)

[preprocessor directives](#)

[PreserveSigAttribute sealed class, System.Runtime.InteropServices](#)

[primitive types, values](#)

[private access modifiers](#)

[private keyword](#)

[procedural-based patterns](#)

[Process class, System.Diagnostics](#)

[processes](#)

[diagnostics and](#)

[launching, diagnostics and](#)

[running, examining](#)

[threads in](#)

[ProcessModule class, System.Diagnostics](#)

[ProcessModuleCollection class, System.Diagnostics](#)

[ProcessPriorityClass enumeration, System.Diagnostics](#)

[ProcessStartInfo sealed class, System.Diagnostics](#)

[ProcessThread class, System.Diagnostics](#)

[ProcessThread type](#)

[ProcessThreadCollection class, System.Diagnostics](#)

[ProcessWindowStyle enumeration, System.Diagnostics](#)

[Professional Developer's Conference \(PDC\)](#)

[ProgIdAttribute sealed class, System.Runtime.InteropServices](#)

[properties](#)

[index](#)

[introduction](#)

[System.Exception](#)

[PropertyAttributes enumeration, System.Reflection API](#)

[PropertyBuilder sealed class, System.Reflection.Emit](#)

[PropertyInfo abstract class, System.Reflection API](#)

[PropertyToken struct, System.Reflection.Emit](#)

[protected access modifiers](#)

[protected internal modifiers](#)

[protected keyword](#)

[protocol handlers, adding](#)

[ProtocolFamily enumeration, System.Net.Sockets namespace](#)

[ProtocolType enumeration, System.Net.Sockets namespace](#)

[ProtocolViolationException class, System.Net](#)

[pseudorandom numbers](#)

[public](#)

[public access modifiers](#)

[public keyword](#)

[Pulse\(\) method](#)

[threading and](#)

[PulseAll\(\) method](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[Queue class, System.Collections](#)

[collections and](#)

quick reference

[assemblies](#)

[class hierarchies](#)

[cross-references](#)

[description of entries](#)

[entries, locating](#)

[entry reading](#)

[namespaces](#)

[synopsis](#)

[type names](#)

types

[categories](#)

[names](#)

quick references

[flags](#)

[quotation marks, regular expressions and](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[Random class, System namespace](#)
[random numbers](#)
[RankException class, System namespace](#)
[raw streams, encapsulating](#)
[RCW \(Runtime Callable Wrapper\)](#)
[ReaderWriterLock sealed class, System.Threading](#)
[reading](#)

- [event logs](#)
- [files, I/O](#)
- [isolated storage](#)
- [performance counter data](#)

[readonly keyword](#)
[readonly modifier](#)
[ReadOnlyCollectionBase abstract class, System.Collections](#)
[ReadState enumeration, System.Xml](#)
[rectangular arrays 2nd](#)
[ref keyword](#)
[ref modifier, parameters](#)
[reference types](#)

- [value types and](#)

[reflection](#)

- [advanced uses](#)
- [AppDomains](#)
- [assemblies, modules](#)
- [FCL](#)
- [introspection and](#)
- [late binding and](#)
- [SQL and](#)
- [Type class and](#)
- [type hierarchy and 2nd](#)

[Reflection API \[See System.Reflection API\]](#)
[ReflectionTypeLoadException sealed class, System.Reflection API](#)
[RegAsm.exe](#)
[Regex class, System.Text.RegularExpressions](#)

- [regular expressions](#)
- [strings and](#)

[RegexCompilationInfo class, System.Text.RegularExpressions](#)
[RegexOptions delegates, System.Text.RegularExpressions](#)
[RegionInfo classes, System.Globalization](#)
[RegisterWaitHandle sealed class, System.Threading](#)
[RegistrationServices class, System.Runtime.InteropServices](#)
[Registry sealed class, Microsoft.Win32](#)
[RegistryHive enumeration, Microsoft.Win32](#)
[RegistryKey sealed class, Microsoft.Win32](#)
[RegSvcs.exe](#)
[regular expressions](#)

- [alternation](#)

- [back references](#)
- [C comments, deleting](#)
- [caps in words](#)
- [character sets](#)
- [directory changes](#)
- [escape codes](#)
- [expanding hex escapes](#)
- [extracting date/time values](#)
- [filename path removal](#)
- [grammar](#)
- [groups](#)
- [initial caps](#)
- [IP address detection](#)
- [joining multiline strings](#)
- [keyword-value matching](#)
- [links in HTML](#)
- [lowercase words](#)
- [Match class](#)
- [matching lines](#)
- [middle initials](#)
- [newline character](#)
- [number extraction from strings](#)
- [options](#)
- patterns
 - [expression-based](#)
 - [procedural-based](#)
- [positions](#)
- [quantifiers](#)
- [quotation marks](#)
- [Regex class](#)
- [roman numeral matching](#)
- [strings and](#)
 - [Match class](#)
 - [MatchCollection class](#)
- [substitutions](#)
- [swapping words](#)
- [syntax](#)
- [whitespace removal](#)
- [remoting, FCL and](#)
- [RenamedEventArgs class, System.IO](#)
- [RenamedEventHandler delegate, System.IO 2nd](#)
- [request/response architecture, networking](#)
- [ResolveEventArgs class, System namespace](#)
- [ResolveEventHandler delegate, System namespace](#)
- [resolving assemblies](#)
- [ResourceAttributes enumerations, System.Reflection API](#)
- [ResourceLocation enumerations, System.Reflection API](#)
- [resources, assemblies](#)
- [return keyword](#)
- [return statement](#)
- [return types, delegates](#)
- [Runtime Callable Wrapper \[See RCW\]](#)

[runtime environments, CLR](#)
[runtime libraries](#)
[runtime support, custom attributes](#)
[RuntimeEnvironment class, System.Runtime.InteropServices](#)
[RuntimeTypeHandle struct, System namespace](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[safety, threading](#)
[SaveArrayRankMismatchException class, System.Runtime.InteropServices](#)
[SaveArrayTypeMismatchException class, System.Runtime.InteropServices](#)
[sbyte keyword](#)
[SByte struct, System namespace](#)
[schemas, XML](#)
[SoapSuds.exe](#)
[Xsd.exe](#)
[script hosts, System.Reflection.Emit namespace and](#)
[sealed classes](#)

Microsoft.Win32 namespace

[Registry](#)
[Registrykey](#)
[SystemEvents](#)

System

[Activator](#)
[AppDomain](#)
[AppDomainSetup](#)
[AttributeUsageAttribute](#)
[BitConverter](#)
[Buffer](#)
[CharEnumerator](#)
[CLSCompliantAttribute](#)
[Console](#)
[Convert](#)
[DBNull](#)
[Environment](#)
[ExecutionEngineException](#)
[GC](#)
[IndexOutOfRangeException](#)
[InvalidProgramException](#)
[LoaderOptimizationAttribute](#)
[LocalDataStoreSlot](#)
[Marsh](#)
[MTAThreadAttribute](#)
[MulticastNotSupportedException](#)
[NonSerializedAttribute](#)
[ObsoleteAttribute](#)
[OperatingSystem](#)
[ParamArrayAttribute](#)
[SerializableAttribute](#)
[StackOverflowException](#)
[STAThreadAttribute](#)
[String](#)
[TypeInitializationException](#)
[Version](#)

System.Diagnostics

- [ConditionalAttribute](#)
- [CounterSampleCalculator](#)
- [Debug](#)
- [DebuggableAttribute](#)
- [Debugger](#)
- [DebuggerHiddenAttribute](#)
- [DebuggerStepThroughAttribute](#)
- [EventLogEntry](#)
- [EventLogPermission](#)
- [EventLogTraceListener](#)
- [FileVersionInfo](#)
- [PerformanceCounter](#)
- [PerformanceCounterCategory](#)
- [PerformanceCounterPermission](#)
- [ProcessStartInfo](#)
- [Trace](#)

System.Globalization

- [DateTimeFormatInfo](#)
- [NumberFormatInfo](#)

System.IO

- [BufferedStream](#)
- [Directory](#)
- [DirectoryInfo](#)
- [File](#)
- [FileInfo](#)
- [Path](#)

[System.IO.IsolatedStorage, IsolatedStorageFile](#)

System.Net

- [Cookie](#)
- [DnsPermission](#)
- [DnsPermissionAttribute](#)
- [SocketPermission](#)
- [SocketPermissionAttribute](#)
- [WebClient](#)
- [WebPermission](#)
- [WebPermissionAttribute](#)

System.Reflection.Emit

- [AssemblyBuilder](#)
- [ConstructorBuilder](#)
- [EnumBuilder](#)
- [EventBuilder](#)
- [FieldBuilder](#)
- [LocalBuilder](#)
- [MethodBuilder](#)
- [MethodRental](#)
- [PropertyBuilder](#)
- [SignatureHelper](#)
- [TypeBuilder](#)
- [UnmanagedMarshal](#)

System.Runtime.InteropServices

- [BestFitMappingAttribute](#)
- [ClassInterfaceAttribute](#)

[CoClassAttribute](#)
[ComAliasNameAttribute](#)
[ComCompatibleVersionAttribute](#)
[ComConversionLossAttribute](#)
[ComImportAttribute](#)
[ComRegisterFunctionAttribute](#)
[ComSourceInterfacesAttribute](#)
[ComUnregisterFunctionAttribute](#)
[ComVisibleAttribute](#)
[CurrencyWrapper](#)
[DispatchWrapper](#)
[DispIdAttribute](#)
[DllImportAttribute](#)
[ErrorWrapper](#)
[ExtensibleClassFactory](#)
[FieldOffsetAttribute](#)
[GuidAttribute](#)
[IDispatchImplAttribute](#)
[InAttribute](#)
[InterfaceTypeAttribute](#)
[LCIDConversionAttribute](#)
[Marshal](#)
[MarshalAsAttribute](#)
[OptionalAttribute](#)
[OutAttribute](#)
[PreserveSigAttribute](#)
[ProgIdAttribute](#)
[StructLayoutAttribute](#)
[TypeLibVersionAttribute](#)
[UnknownWrapper](#)

System.Runtime.Serialization

[FormatterServices](#)
[SerializationInfo](#)
[SerializationInfoEnumerator](#)

System.Runtime.Serialization.Formatter

[BinaryFormatter](#)
[ServerFault](#)
[SoapFault](#)
[SoapFormatter](#)

System.Text, StringBuilder

System.Threading

[AutoResetEvent](#)
[Interlocked](#)
[ManualResetEvent](#)
[Monitor](#)
[Mutex](#)
[ReaderWriterLock](#)
[RegisteredWaitHandle](#)
[Thread](#)
[ThreadAbortException](#)
[ThreadPool](#)
[Timeout](#)

[Timer](#)

[System.Xml.Xsl](#)

[XsltArgumentList](#)

[XsltTransform](#)

[System.Collections](#)

[BitArray](#)

[Comparer](#)

[System.Reflection API](#)

[AmbiguousMatchException](#)

[AssemblyAlgorithmIdAttribute](#)

[AssemblyCompanyAttribute](#)

[AssemblyConfigurationAttribute](#)

[AssemblyCopyrightAttribute](#)

[AssemblyCultureAttribute](#)

[AssemblyDefaultAliasAttribute](#)

[AssemblyDelaySignAttribute](#)

[AssemblyDescriptionAttribute](#)

[AssemblyFileVersionAttribute](#)

[AssemblyFlagsAttribute](#)

[AssemblyInformationalVersionAttribute](#)

[AssemblyKeyFileAttribute](#)

[AssemblyKeyNameAttribute](#)

[AssemblyName](#)

[AssemblyProductAttribute](#)

[AssemblyTitleAttribute](#)

[AssemblyTrademarkAttribute](#)

[AssemblyVersionAttribute](#)

[DefaultMemberAttribute](#)

[Missing](#)

[Pointer](#)

[ReflectionTypeLoadException](#)

[TargetInvocationException](#)

[TargetParameterCountException](#)

[sealed keyword](#)

[sealed virtual function members](#)

[security](#)

[FCL and](#)

[permissions, assemblies](#)

[SecurityProtocolType enumeration, System.Net](#)

[SeekOrigin enumeration, System.IO](#)

[SEHException class, System.Runtime.InteropServices](#)

[selection statements](#)

[SelectMode enumeration, System.Net.Sockets namespace](#)

[\[Serializable\] attribute](#)

[SerializableAttribute sealed class, System namespace](#)

[serialization](#)

[deserialization](#)

[FCL and](#)

[libraries](#)

[SerializationBinder abstract class, System.Runtime.Serialization](#)

[SerializationEntry struct, System.Runtime.Serialization](#)

[SerializationException class, System.Runtime.Serialization](#)

[SerializationInfo sealed class, System.Runtime.Serialization](#)
[SerializationInfoEnumerator sealed class, System.Runtime.Serialization](#)
[ServerFault sealed class, System.Runtime.Serialization.Formatter](#)
[ServicePoint class, System.Net](#)
[ServicePointManager class, System.Net](#)
[SessionEndedEventArgs class, Microsoft.Win32](#)
[SessionEndedEventHandler delegate, Microsoft.Win32](#)
[SessionEndingEventArgs class, Microsoft.Win32](#)
[SessionEndingEventHandler delegate, Microsoft.Win32](#)
[SessionEndReason enumerations, Microsoft.Win32](#)
[set keyword](#)
[Shared Source CLI](#) [See SSCLI]
[short keyword](#)
[SignatureHelper sealed class, System.Reflection.Emit](#)
[signatures, methods](#)
[SignatureToken struct, System.Reflection.Emit](#)
[signing assemblies](#)
[Single struct, System namespace](#)
[sizeof keyword](#)
[Sn.exe utility](#)
[signing assemblies](#)
[SOAP, FCL and](#)
[SoapFault sealed class, System.Runtime.Serialization.Formatter](#)
[SoapFormatter sealed class, System.Runtime.Serialization.Formatter](#)
[SoapMessage class, System.Runtime.Serialization.Formatter](#)
[SoapSuds.exe](#)
[Socket class, System.Net.Sockets namespace](#)
[SocketAddress class, System.Net](#)
[SocketException class, System.Net.Sockets namespace](#)
[SocketFlags enumeration, System.Net.Sockets namespace](#)
[SocketOptionLevel enumeration, System.Net.Sockets namespace](#)
[SocketOptionName enumeration, System.Net.Sockets namespace](#)
[SocketPermission class, System.Net](#)
[SocketPermissionAttribute sealed class, System.Net](#)
[sockets](#)
[Berkeley sockets APIs](#)
[SocketShutdown enumeration, System.Net.Sockets namespace](#)
[SocketType enumeration, System.Net.Sockets namespace](#)
[SortedList class, System.Collections](#)
[collections and](#)
[sorting, collections and](#)
[SortKey classes, System.Globalization](#)
[SQL \(Structured Query Language\), reflection and](#)
[SSCLI \(Shared Source CLI\)](#)
[STA \(single-threaded apartments\)](#)
[stack](#)
[Stack class, System.Collections](#)
[collections and](#)
[stack frames, threads in](#)
[stackalloc keyword](#) 2nd
[StackBehaviour enumeration, System.Reflection.Emit](#)
[StackFrame class, System.Diagnostics](#) 2nd

[StackOverflowException sealed classes, System namespace](#)

[stacks, diagnostics and](#)

[StackTrace class, System.Diagnostics 2nd](#)

[StackTrace property, System.Exception](#)

[standalone functions](#)

[statements](#)

[break statement](#)

[continue statement](#)

[declaration statements](#)

[expression statements](#)

[fixed statement, pointers and](#)

[goto statement](#)

[if-else statements](#)

[introduction](#)

[jump statements](#)

[lock statement](#)

[thread synchronization and](#)

[loop statements](#)

[return statement](#)

[selection statements](#)

[switch statements](#)

[throw statement](#)

[try statements](#)

[using statement](#)

[STAThreadAttribute sealed class, System namespace](#)

[static constructors](#)

[nondeterminisim](#)

[static fields, initialization order](#)

[static keyword](#)

[static methods, thread relative statics](#)

[storadm.exe utility, isolated storage and](#)

[Stream abstract class, System.IO](#)

[Stream class](#)

[methods](#)

[stream-derived classes](#)

[StreamingContext struct, System.Runtime.Serialization](#)

[StreamingContextStates enumeration, System.Runtime.Serialization](#)

[StreamReader class, System.IO 2nd](#)

[streams](#)

[abstract Stream class](#)

[FCL and](#)

[raw, encapsulating](#)

[stream-derived classes](#)

[StringReader class](#)

[StringWriter class](#)

[TextReader class](#)

[TextWriter class](#)

[XML, parsing](#)

[StreamWriter class, System.IO 2nd](#)

[string class](#)

[types and](#)

[string keyword](#)

[String sealed class, System namespace](#)

[string types](#)

[String.Format\(\) method](#)

[StringBuilder sealed class, System.Text 2nd](#)

[StringCollection class, System.Collections.Specialized
collections and](#)

[StringDictionary class, System.Collections
Specialized
collections and](#)

[StringDictionary class, System.Collections.Specialized](#)

[StringEnumerator class, System.Collections.Specialized](#)

[StringInfo classes, System.Globalization](#)

[StringReader class](#)

[StringReader class, System.IO](#)

strings

[CaptureCollection class](#)

[comparing](#)

[encoded](#)

[format-specification string](#)

[formatting](#)

[Group class](#)

[immutability](#)

[indexing](#)

[interning](#)

[numbers, regular expressions](#)

[Regex class and](#)

[regular expressions and](#)

[Match class](#)

[MatchCollection class](#)

[StringToken struct, System.Reflection.Emit](#)

[StringWriter class, System.IO 2nd](#)

[StrongNameKeyPair class, System.Reflection API](#)

[struct keyword](#)

[StructLayout attribute 2nd](#)

[StructLayoutAttribute sealed class, System.Runtime.InteropServices](#)

structs

[binary format, mapping to](#)

[classes comparison](#)

[marshaling](#)

System

[ArgIterator](#)

[Boolean](#)

[Byte](#)

[Char](#)

[DateTime](#)

[Decimal](#)

[Double](#)

[Guid](#)

[Int16](#)

[Int32](#)

[Int64](#)

[IntPtr](#)

[RuntimeTypeHandler](#)

[SByte](#)

[Single](#)

[TimeSpan](#)

[UInt16](#)

[UInt32](#)

[UInt64](#)

[UIntPtr](#)

[Void](#)

[System.Diagnostics, CounterSample](#)

[System.IO, WaitForChangedResult](#)

[System.Reflection.Emit](#)

[EventToken](#)

[FieldToken](#)

[Label](#)

[MethodToken](#)

[OpCode](#)

[ParameterToken](#)

[PropertyToken](#)

[SignatureToken](#)

[StringToken](#)

[TypeToken](#)

[System.Runtime.InteropServices](#)

[ArrayWithOffset](#)

[GCHandle](#)

[HandleRef](#)

[System.Runtime.Serialization](#)

[SerializationEntry](#)

[StreamingContext](#)

[System.Threading](#)

[LockCookie](#)

[NativeOverlapped](#)

[System.Collections, DictionaryEntry](#)

[System.Collections.Specialized](#)

[BitVector32](#)

[BitVector32.Section](#)

[System.Reflection API](#)

[InterfaceMapping](#)

[ParameterModifier](#)

[unions](#)

[SurrogateSelector class, System.Runtime.Serialization](#)

[Switch abstract class, System.Diagnostics](#)

[switch keyword](#)

[switch statements](#)

[synchronization](#)

[threads](#)

[atomic operations](#)

[deadlocks](#)

[lock statement](#)

[Pulse\(\) method](#)

[SynchronizationLockException class, System.Threading](#)

[synopsis, quick reference entries](#)

[system exceptions](#)

[System namespace](#) [2nd](#)

abstract classes

[Array](#)

[Attribute](#)

[ContextBoundObject](#)

[Delegate](#)

[Enum](#)

[MarshalByRefObject](#)

[MulticastDelegate](#)

[TimeZone](#)

[Type](#)

[ValueType](#)

[application exceptions](#)

[base types](#)

classes

[AppDomainUnloadedException](#)

[ApplicationException](#)

[ArgumentException](#)

[ArgumentNullException](#)

[ArgumentOutOfRangeException](#)

[ArithmeticException](#)

[ArrayTypeMismatchException](#)

[AssemblyLoadEventArgs](#)

[BadImageFormatException](#)

[CannotUploadAppDomainException](#)

[ContextMarshalException](#)

[ContextStaticAttribute](#)

[DivideByZeroException](#)

[DllNotFoundException](#)

[DuplicateWaitObjectException](#)

[EntryPointNotFoundException](#)

[EventArgs](#)

[Exception](#)

[FieldAccessException](#)

[FlagsAttribute](#)

[FormatException](#)

[InvalidCastException](#)

[InvalidOperationException](#)

[MemberAccessException](#)

[MethodAccessException](#)

[MissingFieldException](#)

[MissingMemberException](#)

[MissingMethodException](#)

[NotFiniteNumberException](#)

[NotImplementedException](#)

[NotSupportedException](#)

[NullReferenceException](#)

[Object](#)

[ObjectDisposedException](#)

[OutOfMemoryException](#)

[OverflowException](#)

- [PlatformNotSupportedException](#)
- [Random](#)
- [RankException](#)
- [ResolveEventArgs](#)
- [SystemException](#)
- [ThreadStaticAttribute](#)
- [TypeLoadException](#)
- [TypeUnloadedException](#)
- [UnauthorizedAccessException](#)
- [UnhandledExceptionEventArgs](#)
- [Uri](#)
- [UriBuilder](#)
- [UriFormatException](#)
- [WeakReference](#)

delegates

- [AssemblyLoadEventHandler](#)
- [AsyncCallback](#)
- [CrossAppDomainDelegate](#)
- [EventHandler](#)
- [ResolveEventHandler](#)
- [UnhandledExceptionHandler](#)

enumerations

- [AttributeTargets](#)
- [DayOfWeek](#)
- [Environment.SpecialFolder](#)
- [LoaderOptimization](#)
- [PlatformID](#)
- [TypeCode](#)
- [UriHostNameType](#)
- [UriPartial](#)

interfaces

- [IAsyncResult](#)
- [ICloneable](#)
- [IComparable](#)
- [IConvertible](#)
- [ICustomFormatter](#)
- [IDisposable](#)
- [IFormatProvider](#)
- [IFormattable](#)
- [IServiceProvider](#)

sealed classes

- [Activator](#)
- [AppDomain](#)
- [AppDomainSetup](#)
- [AttributeUsageAttribute](#)
- [BitConverter](#)
- [Buffer](#)
- [CharEnumerator](#)
- [CLSCompliantAttribute](#)
- [Console](#)
- [Convert](#)
- [DBNull](#)

- [Environment](#)
- [ExecutionEngineException](#)
- [GC](#)
- [IndexOutOfRangeException](#)
- [InvalidProgramException](#)
- [LoaderOptimizationAttribute](#)
- [LocalDataStoreSlot](#)
- [Math](#)
- [MTAThreadAttribute](#)
- [MulticastNotSupportedException](#)
- [NonSerializedAttribute](#)
- [ObsoleteAttribute](#)
- [OperatingSystem](#)
- [ParamArrayAttribute](#)
- [SerializableAttribute](#)
- [StackOverflowException](#)
- [STAThreadAttribute](#)
- [String](#)
- [TypeInitializationException](#)
- [Version](#)

structs

- [ArgIterator](#)
- [Boolean](#)
- [Byte](#)
- [Char](#)
- [DateTime](#)
- [Decimal](#)
- [Double](#)
- [Guid](#)
- [Int16](#)
- [Int32](#)
- [Int64](#)
- [IntPtr](#)
- [RuntimeTypeHandle](#)
- [SByte](#)
- [Single](#)
- [TimeSpan](#)
- [UInt16](#)
- [UInt32](#)
- [UInt64](#)
- [UIntPtr](#)
- [Void](#)

[system exceptions](#)

- [System.Activator class](#)
- [System.Array base type](#)
- [System.Attribute base type 2nd](#)
- [custom attributes](#)

System.Collections

abstract classes

- [CollectionBase](#)
- [DictionaryBase](#)
- [ReadOnlyCollectionBase](#)

classes

- [ArrayList](#)
- [CaseInsensitiveComparer](#)
- [CaseInsensitiveHashCodeProvider](#)
- [Hashtable](#)
- [Queue](#)
- [SortedList](#)
- [Stack](#)

interfaces

- [ICollection](#)
- [IComparer](#)
- [IDictionary](#)
- [IDictionaryEnumerator](#)
- [IEnumerable](#)
- [IEnumerator](#)
- [IHashCodeProvider](#)
- [IList](#)

sealed classes

- [BitArray](#)
- [Comparer](#)

[structs, DictionaryEntry](#)

System.Collections.Specialized

[abstract classes, NameObjectCollectionBase](#)

classes

- [CollectionsUtil](#)
- [HybridDictionary](#)
- [ListDictionary](#)
- [NameObjectCollectionBase.KeysCollection](#)
- [NameValueCollection](#)
- [StringCollection](#)
- [StringDictionary](#)
- [StringEnumerator](#)

structs

- [BitVector32](#)
- [BitVector32.Section](#)

[System.Delegate base type](#)

System.Diagnostics

abstract classes

- [Switch](#)
- [TraceListener](#)

classes

- [BooleanSwitch](#)
- [CounterCreationData](#)
- [CounterCreationDataCollection](#)
- [DefaultTraceListener](#)
- [EntryWrittenEventArgs](#)
- [EventLog](#)
- [EventLogEntryCollection](#)
- [EventLogInstaller](#)
- [EventLogPermissionAttribute](#)
- [EventLogPermissionEntry](#)
- [EventLogPermissionEntryCollection](#)

- [InstanceData](#)
- [InstanceDataCollection](#)
- [InstanceDataCollectionCollection](#)
- [MonitoringDescriptionAttribute](#)
- [PerformanceCounterInstaller](#)
- [PerformanceCounterPermissionAttribute](#)
- [PerformanceCounterPermissionEntry](#)
- [PerformanceCounterPermissionEntryCollection](#)
- [Process](#)
- [ProcessModule](#)
- [ProcessModuleCollection](#)
- [ProcessThread](#)
- [ProcessThreadCollection](#)
- [StackFrame](#)
- [StackTrace](#)
- [TextWriterTraceListener](#)
- [TraceListenerCollection](#)
- [TraceSwitch](#)

[delegates, EntryWrittenEventHandler](#)

enumerations

- [EventLogEntryType](#)
- [EventLogPermissionAccess](#)
- [PerformanceCounterPermissionAccess](#)
- [PerformanceCounterType](#)
- [ProcessPriorityClass](#)
- [ProcessWindowStyle](#)
- [ThreadPriorityLevel](#)
- [ThreadState](#)
- [ThreadWaitReason](#)
- [TraceLevel](#)

sealed classes

- [ConditionalAttribute](#)
- [CounterSampleCalculator](#)
- [Debug](#)
- [DebuggableAttribute](#)
- [Debugger](#)
- [DebuggerHiddenAttribute](#)
- [DebuggerStepThroughAttribute](#)
- [EventLogEntry](#)
- [EventLogPermission](#)
- [EventLogTraceListener](#)
- [FileVersionInfo](#)
- [PerformanceCounter](#)
- [PerformanceCounterCategory](#)
- [PerformanceCounterPermission](#)
- [ProcessStartInfo](#)
- [Trace](#)

[structs, CounterSample](#)

System.Globalization

[abstract classes, Calendar](#)

classes

[CompareInfo](#)

- [CultureInfo](#)
- [DaylightTime](#)
- [GregorianCalendar](#)
- [HebrewCalendar](#)
- [HijriCalendar](#)
- [JapaneseCalendar](#)
- [JulianCalendar](#)
- [KoreanCalendar](#)
- [RegionInfo](#)
- [SortKey 2nd](#)
- [StringInfo 2nd](#)
- [TaiwanCalendar 2nd](#)
- [TextElementEnumerator 2nd](#)
- [TextInfo 2nd](#)
- [ThaiBuddhistCalendar 2nd](#)
- [UnicodeCategory](#)

enumerations

- [CalendarWeekRule](#)
- [CompareOptions](#)
- [CultureTypes](#)
- [DateTimeStyles](#)
- [GregorianCalendarTypes](#)
- [NumberStyle](#)
- [UnicodeCategory](#)

sealed classes

- [DateTimeFormatInfo](#)
- [NumberFormatInfo](#)

System.IO

abstract classes

- [FileSystemInfo](#)
- [Stream](#)
- [TextReader](#)
- [TextWriter](#)

classes

- [BinaryReader](#)
- [BinaryWriter](#)
- [DirectoryNotFoundException](#)
- [EndOfStreamException](#)
- [ErrorEventArgs](#)
- [FileLoadException](#)
- [FileNotFoundException](#)
- [FileStream](#)
- [FileSystemEventArgs](#)
- [FileSystemWatcher](#)
- [InternalBufferOverflowException](#)
- [IODescriptionAttribute](#)
- [IOException](#)
- [MemoryStream](#)
- [PathTooLongException](#)
- [RenamedEventArgs](#)
- [StreamReader](#)
- [StreamWriter](#)

[StringReader](#)

[StringWriter](#)

delegates

[ErrorEventHandler](#)

[FileSystemEventHandler](#)

[RenamedEventHandler](#)

enumerations

[FileAccess](#)

[FileAttributes](#)

[FileMode](#)

[FileShare](#)

[NotifyFilters](#)

[SeekOrigin](#)

[WatcherChangeTypes](#)

sealed classes

[BufferedStream](#)

[Directory](#)

[DirectoryInfo](#)

[File](#)

[FileInfo](#)

[Path](#)

[stream-on-stream options](#)

[structs, WaitForChangedResult](#)

System.IO.IsolatedStorage

[abstract classes, IsolatedStorage](#)

classes

[IsolatedStorageException](#)

[IsolatedStorageFileStream](#)

[enumerations, IsolatedStorageScope](#)

[interfaces, INormalizeForIsolatedStorage](#)

[sealed classes, IsolatedStorageFile](#)

[System.MulticastDelegate base type](#)

System.Net

abstract classes

[EndPoint](#)

[WebRequest](#)

[WebResponse](#)

classes

[AuthenticationManager](#)

[Authorization](#)

[CookieCollection](#)

[CookieContainer](#)

[CookieException](#)

[CredentialCache](#)

[EndPointPermission](#)

[FileWebRequest](#)

[FileWebResponse](#)

[GlobalProxySelection](#)

[HttpVersion](#)

[HttpWebRequest](#)

[HttpWebResponse](#)

[IPAddress](#)

- [IPEndPoint](#)
- [IPEndPointEntry](#)
- [NetworkCredential](#)
- [ProtocolViolationException](#)
- [ServicePoint](#)
- [ServicePointManager](#)
- [SocketAddress](#)
- [WebException](#)
- [WebHeaderCollection](#)
- [WebProxy](#)

[delegates, HttpContinueDelegate](#)

enumerations

- [HttpStatusCode](#)
- [NetworkAccess](#)
- [SecurityProtocolType](#)
- [TransportType](#)
- [WebExceptionStatus](#)

interfaces

- [IAuthenticationModule](#)
- [ICertificatePolicy](#)
- [ICredentials](#)
- [IWebProxy](#)
- [IWebRequestCreate](#)

sealed classes

- [Cookie](#)
- [Dns](#)
- [DnsPermission](#)
- [DnsPermissionAttribute](#)
- [SocketPermission](#)
- [SocketPermissionAttribute](#)
- [WebClient](#)
- [WebPermission](#)
- [WebPermissionAttribute](#)

System.Net.Sockets

classes

- [IPv6MulticastOption](#)
- [LingerOption](#)
- [MulticastOption](#)
- [NetworkStream](#)
- [Socket](#)
- [SocketException](#)
- [TcpClient](#)
- [TcpListener](#)
- [UdpClient](#)

enumerations

- [AddressFamily](#)
- [ProtocolFamily](#)
- [ProtocolType](#)
- [SelectMode](#)
- [SocketFlags](#)
- [SocketOptionLevel](#)
- [SocketOptionName](#)

[SocketShutdown](#)

[SocketType](#)

System.Reflection API

abstract classes

[Binder](#)

[ConstructorInfo](#)

[EventInfo](#)

[FieldInfo](#)

[MemberInfo](#)

[MethodBase](#)

[MethodInfo](#)

[PropertyInfo](#)

classes

[Assembly](#)

[AssemblyNameProxy](#)

[CustomAttributeFormatException](#)

[InvalidFilterCriteriaException](#)

[ManifestResourceInfo](#)

[Module](#)

[ParameterInfo](#)

[StrongNameKeyPair](#)

[TargetException](#)

[TypeDelegator](#)

delegates

[MemberFilter](#)

[ModuleResolveEventHandler](#)

[TypeFilter](#)

enumerations

[AssemblyNameFlags](#)

[BindingFlags](#)

[CallingConventions](#)

[EventAttributes](#)

[FieldAttributes](#)

[MemberTypes](#)

[MethodAttributes](#)

[MethodImplAttributes](#)

[ParameterAttributes](#)

[PropertyAttributes](#)

[ResourceAttributes](#)

[ResourceLocation](#)

[TypeAttributes](#)

interfaces

[ICustomAttributeProvider](#)

[IReflect](#)

sealed classes

[AmbiguousMatchException](#)

[AssemblyAlgorithmIdAttribute](#)

[AssemblyCompanyAttribute](#)

[AssemblyConfigurationAttribute](#)

[AssemblyCopyrightAttribute](#)

[AssemblyCultureAttribute](#)

[AssemblyDefaultAliasAttribute](#)

[AssemblyDelaySignAttribute](#)
[AssemblyDescriptionAttribute](#)
[AssemblyFileVersionAttribute](#)
[AssemblyFlagsAttribute](#)
[AssemblyInformationalVersionAttribute](#)
[AssemblyKeyFileAttribute](#)
[AssemblyKeyNameAttribute](#)
[AssemblyName](#)
[AssemblyProductAttribute](#)
[AssemblyTitleAttribute](#)
[AssemblyTrademarkAttribute](#)
[AssemblyVersionAttribute](#)
[DefaultMemberAttribute](#)
[Missing](#)
[Pointer](#)
[ReflectionTypeLoadException](#)
[TargetInvocationException](#)
[TargetParameterCountException](#)

structs

[InterfaceMapping](#)
[ParameterModifier](#)

[System.Reflection namespace](#)

System.Reflection.Emit

classes

[CustomAttributeBuilder](#)
[ILGenerator](#)
[ModuleBuilder](#)
[OpCodes](#)
[ParameterBuilder](#)

enumerations

[AssemblyBuilderAccess](#)
[FlowControl](#)
[OpCodeType](#)
[OperandType](#)
[PackingSize](#)
[PEFileKinds](#)
[StackBehaviour](#)

sealed classes

[AssemblyBuilder](#)
[ConstructorBuilder](#)
[EnumBuilder](#)
[EventBuilder](#)
[FieldBuilder](#)
[LocalBuilder](#)
[MethodBuilder](#)
[MethodRental](#)
[PropertyBuilder](#)
[SignatureHelper](#)
[TypeBuilder](#)
[UnmanagedMarshal](#)

structs

[EventToken](#)

[FieldToken](#)
[Label](#)
[MethodToken](#)
[OpCode](#)
[ParameterToken](#)
[PropertyToken](#)
[SignatureToken](#)
[StringToken](#)
[TypeToken](#)

System.Runtime.InteropServices

classes

[COMException](#)
[ExternalException](#)
[InvalidComObjectException](#)
[InvalidOleVariantTypeException](#)
[MarshalDirectiveException](#)
[RegistrationServices](#)
[RuntimeEnvironment](#)
[SaveArrayRankMismatchException](#)
[SaveArrayTypeMismatchException](#)
[SEHException](#)

[delegates, ObjectCreationDelegate](#)

enumerations

[AssemblyRegistrationFlags](#)
[CallingConvention](#)
[CharSet](#)
[ClassInterfaceType](#)
[ComInterfaceType](#)
[ComMemberType](#)
[GCHandleType](#)
[IDispatchImplType](#)
[LayoutKind](#)
[UnmanagedType](#)
[VarEnum](#)

interfaces

[IExpando](#)
[IRegistrationServices](#)

sealed classes

[BestFitMappingAttribute](#)
[ClassInterfaceAttribute](#)
[CoClassAttribute](#)
[ComAliasNameAttribute](#)
[ComCompatibleVersionAttribute](#)
[ComConversionLossAttribute](#)
[ComImportAttribute](#)
[ComRegisterFunctionAttribute](#)
[ComSourceInterfacesAttribute](#)
[ComUnregisterFunctionAttribute](#)
[ComVisibleAttribute](#)
[CurrencyWrapper](#)
[DispatchWrapper](#)
[DispIdAttribute](#)

- [DllImportAttribute](#)
- [ErrorWrapper](#)
- [ExtensibleClassFactory](#)
- [FieldOffsetAttribute](#)
- [GuidAttribute](#)
- [IDispatchImplAttribute](#)
- [InAttribute](#)
- [InterfaceTypeAttribute](#)
- [LCIDConversionAttribute](#)
- [Marshal](#)
- [MarshalAsAttribute](#)
- [OptionalAttribute](#)
- [OutAttribute](#)
- [PreserveSigAttribute](#)
- [ProgIdAttribute](#)
- [StructLayoutAttribute](#)
- [TypeLibVersionAttribute](#)
- [UnknownWrapper](#)

structs

- [ArrayWithOffset](#)
- [GCHandle](#)
- [HandleRef](#)

System.Runtime.Serialization

abstract classes

- [Formatter](#)
- [SerializationBinder](#)

[child namespaces](#)

classes

- [FormatterConverter](#)
- [ObjectIDGenerator](#)
- [ObjectManager](#)
- [SerializationException](#)
- [SurrogateSelector](#)

[enumeration, StreamingContextStates](#)

interfaces

- [IDeserializationCallback](#)
- [IFormatter](#)
- [IFormatterConverter](#)
- [IObjectReference](#)
- [ISerializable](#)
- [ISerializationSurrogate](#)
- [ISurrogateSelector](#)

sealed classes

- [FormatterServices](#)
- [SerializationInfo](#)
- [SerializationInfoEnumerator](#)

structs

- [SerializationEntry](#)
- [StreamingContext](#)

System.Runtime.Serialization.Formatter

[classes, SoapMessage](#)

enumerations

- [FormatterAssemblySstyle](#)
- [FormatterTypeSstyle](#)
- [TypeFilterLevel](#)

interfaces

- [IFieldInfo](#)
- [ISoapMessage](#)

sealed classes

- [BinaryFormatter](#)
- [ServerFault](#)
- [SoapFault](#)
- [SoapFormatter](#)

[System.SerializableAttribute](#)

System.Text

abstract classes

- [Decoder](#)
- [Encoder](#)
- [Encoding](#)

classes

- [ASCIIEncoding](#)
- [UnicodeEncoding](#)
- [UTF7Encoding](#)

[sealed classes, StringBuilder](#)

System.Text.RegularExpressions

classes

- [Capture](#)
- [CaptureCollection](#)
- [Group](#)
- [GroupCollection](#)
- [Match](#)
- [MatchCollection](#)
- [Regex](#)
- [RegexCompilationInfo](#)

[delegates, MatchEvaluator](#)

[enumerations, RegexOptions](#)

System.Threading

[abstract classes, WaitHandle](#)

classes

- [Overlapped](#)
- [SynchronizedLockException](#)
- [ThreadExceptionEventArgs](#)
- [ThreadInterruptedException](#)
- [ThreadStateException](#)

delegates

- [IOCompletionCallback](#)
- [ThreadExceptionHandler](#)
- [ThreadStart](#)
- [TimerCallback](#)
- [WaitCallback](#)
- [WaitOrTimerCallback](#)

enumerations

- [ApartmentState](#)
- [ThreadPriority](#)

[ThreadState](#)

sealed classes

[AutoResetEvent](#)

[Interlocked](#)

[ManualResetEvent](#)

[Monitor](#)

[Mutex](#)

[ReaderWriterLock](#)

[RegisteredWaitHandle](#)

[Thread](#)

[ThreadAbortException](#)

[ThreadPool](#)

[Timeout](#)

[Timer](#)

structs

[LockCookie](#)

[NativeOverlapped](#)

System.Timers

classes

[ElapsedEventArgs](#)

[Timer](#)

[TimersDescriptionAttribute](#)

[delegates, ElapsedEventHandler](#)

System.Xml

abstract classes

[XmlCharacterData](#)

[XmlLinkedNode](#)

[XmlNameTable](#)

[XmlNode](#)

[XmlNodeList](#)

[XmlReader](#)

[XmlResolver](#)

[XmlWriter](#)

classes

[NameTable](#)

[XmlAttribute](#)

[XmlAttributeCollection](#)

[XmlCDATASection](#)

[XmlComment](#)

[XmlConvert](#)

[XmlDataDocument](#)

[XmlDeclaration](#)

[XmlDocument](#)

[XmlDocumentFragment](#)

[XmlDocumentType](#)

[XmlElement](#)

[XmlEntity](#)

[XmlEntityReference](#)

[XmlException](#)

[XmlImplementation](#)

[XmlNameNodeMap](#)

[XmlNamespaceManager](#)

- [XmlNodeChangedEventArgs](#)
- [XmlNodeReader](#)
- [XmlNotation](#)
- [XmlParserContext](#)
- [XmlProcessingInstruction](#)
- [XmlQualifiedName](#)
- [XmlSecureResolver](#)
- [XmlSignificantWhitespace](#)
- [XmlText](#)
- [XmlTextReader](#)
- [XmlTextWriter](#)
- [XmlUriResolver](#)
- [XmlValidatingReader](#)
- [XmlWhitespace](#)

[delegates, XmlNodeChangedEventHandlers](#)

enumerations

- [EntityHandling](#)
- [Formatting](#)
- [ReadState](#)
- [ValidationType](#)
- [WhitespaceHandling](#)
- [WriteState](#)
- [XmlNodeChangedAction](#)
- [XmlNodeOrder](#)
- [XmlNodeType](#)
- [XmlSpace](#)
- [XmlTokenizedType](#)

interfaces

- [IHasXmlNode](#)
- [IXmlLineInfo](#)

[System.Xml.XPath](#)

abstract classes

- [XPathExpression](#)
- [XPathNavigator](#)
- [XPathNodeIterator](#)

classes

- [XPathDocument](#)
- [XPathException](#)

enumerations

- [XmlCaseOrder](#)
- [XmlDataType](#)
- [XmlSortOrder](#)
- [XPathNamespaceScope](#)
- [XPathNodeType](#)
- [XPathResultType](#)

[interfaces, XPathNavigable](#)

[System.Xml.Xsl](#)

[abstract classes, XsltContext](#)

classes

- [XsltCompileException](#)
- [XsltException](#)

interfaces

[IXsltContextFunction](#)

[IXsltContextVariable](#)

sealed classes

[XsltArgumentList](#)

[XsltTransform](#)

[SystemEvents sealed class, Microsoft.Win32](#)

[SystemException class, System namespace](#) [2nd](#)
[properties](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

tags, XML

- [predefined 2nd](#)
- [user-defined](#)

[TaiwanCalendar classes, System.Globalization](#)

[TargetException class, System.Reflection API](#)

[TargetInvocationException sealed class, System.Reflection API](#)

[TargetParameterCountException sealed class, System.Reflection API](#)

[targets, attributes](#)

[TCP \(Transmission Control Protocol\) 2nd](#)

[TcpClient class, System.Net.Sockets namespace 2nd](#)

[TcpListener class, System.Net.Sockets namespace 2nd](#)

[text, FCL](#)

[TextElementEnumerator classes, System.Globalization](#)

[TextInfo classes, System.Globalization](#)

[TextReader abstract class, System.IO 2nd](#)

[TextWriter abstract class, System.IO 2nd](#)

[TextWriterTraceListener class, System.Diagnostics](#)

[ThaiBuddhistCalendar classes, System.Globalization](#)

[thick clients, FCL and](#)

[thin clients, FCL and](#)

[this keyword 2nd](#)

[thread local storage](#)

[thread relative statics](#)

[Thread sealed class, System.Threading](#)

[ThreadAbortException sealed class, System.Threading](#)

[ThreadExceptionEventArgs class, System.Threading](#)

[ThreadExceptionHandler delegate, System.Threading](#)

[threading 2nd](#)

- [apartments](#)
- [asynchronous delegates](#)
- [deadlock](#)
- [Enter\(\) method](#)
- [Exit\(\) method](#)
- [FCL and](#)
- [liveness](#)
- [Monitor class and](#)
- [ProcessThread type](#)
- [Pulse\(\) method](#)
- [PulseAll\(\) method](#)
- [safety](#)
- [synchronization](#)
 - [atomic operations](#)
 - [deadlocks](#)
 - [lock statement](#)
 - [Pulse\(\) method](#)
- [TryEnter\(\) method](#)
- [Wait\(\) methods](#)

[ThreadInterruptedException class, System.Threading](#)
[ThreadPool sealed class, System.Threading](#)
[ThreadPriority enumerations, System.Threading](#)
[ThreadPriorityLevel enumeration, System.Diagnostics](#)
[threads](#)
 [diagnostics and](#)
 [in processes](#)
 [stack frames and](#)
[ThreadStart delegate, System.Threading](#)
[ThreadState enumeration, System.Diagnostics](#)
[ThreadState enumeration, System.Threading](#)
[ThreadStateException class, System.Threading](#)
[ThreadStaticAttribute class, System namespace](#)
[ThreadWaitReason enumeration, System.Diagnostics](#)
[three-state logic operators](#)
[throw keyword](#)
[throw statement](#)
[Timeout sealed class, System.Threading](#)
[Timer class, System.Timers](#)
[Timer sealed class, System.Threading](#)
[TimerCallback delegate, System.Threading](#)
[TimerElapsedEventArgs class, Microsoft.Win32](#)
[TimerElapsedEventHandler delegate, Microsoft.Win32](#)
[TimersDescriptionAttribute class, System.Timers](#)
[TimeSpan struct, System namespace](#)
[TimeZone abstract class, System namespace](#)
[TlbExp.exe](#)
[TlbImp.exe](#)
[Trace class](#)
 [conditional compiling and](#)
[Trace sealed classes, System.Diagnostics](#)
[TraceLevel enumerations, System.Diagnostics](#)
[TraceListener abstract class, System.Diagnostics](#)
[TraceListenerCollection class, System.Diagnostics](#)
[TraceSwitch class, System.Diagnostics](#)
[tracing garbage collectors](#)
[TransportType enumeration, System.Net](#)
[true keyword](#)
 [three-state logic operators](#)
[try blocks](#)
[try keyword](#)
[try statements](#)
[TryEnter\(\) method](#)
[Type abstract class, System namespace](#)
[Type class, reflection and](#)
 [GetType\(\) method](#)
[type references in assemblies](#)
[type-safe MSIL, PEVerify.exe and](#)
[TypeAttributes enumeration, System.Reflection API](#)
[TypeBuilder sealed class, System.Reflection.Emit](#)
[TypeCode enumeration, System namespace](#)
[TypeDelegator class, System.Reflection API](#)

[TypeFilter delegate, System.Reflection API](#)
[TypeFilterLevel enumeration, System.Runtime.Serialization.Formatters](#)
[TypeInitializationException sealed class, System namespace](#)
[TypeLibVersionAttribute sealed class, System.Runtime.InteropServices](#)
[TypeLoadException class, System namespace](#)
[typeof keyword](#)
[types](#) [2nd](#) [See also CTS][3rd](#)
 [aliasing](#)
 [assemblies](#)
 [bool types](#)
 [categories, quick reference entries](#)
 [char types](#)
 [CLR marshaler and](#)
 [COM type mapping](#)
 [conversions](#)
 [Convert](#)
 [creating at runtime](#)
 [custom](#)
 [decimal types](#)
 [description](#)
 [Enum](#)
 [Exception](#)
 [FCL core types](#)
 [floating-point](#)
 [conversions](#)
 [from another namespace](#)
 [hierarchies, reflection and](#) [2nd](#)
 [ID prefixes, XML](#)
 [identifiers](#)
 [index](#)
 [instances](#)
 [int struct](#)
 [memory and](#)
 [names, quick reference entries](#) [2nd](#)
 [namespaces and, fully qualified name](#)
 [nested](#)
 [access modifiers and](#)
 [object types](#)
 [primitive, values](#)
 [ProcessThread](#)
 [reference types](#)
 [value types and](#)
 [string class](#)
 [string types](#)
 [system unification](#)
 [TlbExp.exe](#)
 [TlbImp.exe](#)
 [undocumented, FCL and](#)
 [value types](#)
 [boxing](#)
 [reference types and](#)
 [simple types and](#)

[ValueType](#)

[variant types](#)

[XML, cross-references](#)

[TypeToken struct, System.Reflection.Emit](#)

[TypeUnloadedException class, System namespace](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[UDP \(User Datagram Protocol\) 2nd](#)
[UdpClient class, System.Net.Sockets namespace 2nd](#)
[uint keyword](#)
[UInt16 struct, System namespace](#)
[UInt32 struct, System namespace](#)
[UInt64 struct, System namespace](#)
[UIntPtr struct, System namespace](#)
[ulong keyword](#)
[UnauthorizedAccessException class, System namespace](#)
[unchecked keyword](#)
[underscore-separation naming convention style](#)
[undocumented types, FCL and](#)
[UnhandledExceptionEventArgs class, System namespace](#)
[UnhandledExceptionHandler class, System namespace](#)
[Unicode char types](#)
[UnicodeCategory classes, System.Globalization](#)
[UnicodeEncoding class, System.Text](#)
[unions, structs](#)
[UnknownWrapper sealed class, System.Runtime.InteropServices](#)
[unmanaged code](#)
 [FCL and](#)
 [pointers to](#)
[UnmanagedMarshal sealed class, System.Reflection.Emit](#)
[UnmanagedType enumeration, System.Runtime.InteropServices](#)
[unsafe code, pointers](#)
[unsafe keyword 2nd](#)
[URI \(Uniform Resource Indicator\)](#)
[Uri class, System namespace](#)
[UriBuilder class, System namespace](#)
[UriException class, System namespace](#)
[UriHostNameType enumeration, System namespace](#)
[UriPartial enumeration, System namespace](#)
[user-defined conversions](#)
[user-defined tags, XML](#)
[UserPreferenceCategory enumeration, Microsoft.Win32](#)
[UserPreferenceChangedEventArgs class, Microsoft.Win32](#)
[UserPreferenceChangedEventHandler delegate, Microsoft.Win32](#)
[UserPreferenceChangingEventArgs class, Microsoft.Win32](#)
[UserPreferenceChangingEventHandler delegate, Microsoft.Win32](#)
[ushort keyword](#)
[using directive](#)
[using keyword 2nd](#)
[using statement](#)
[UTF7Encoding class, System.Text](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[ValidationType enumeration, System.Xml](#)

[value equality](#)

[value keyword](#)

[value types](#)

[boxing](#)

[reference types and](#)

[simple types and](#)

[values](#)

[passing by](#)

[primitive types](#)

[variables, assignment](#)

[ValueType abstract class, System namespace](#)

[ValueType type](#)

[VarEnum enumeration, System.Runtime.InteropServices](#)

[variables](#)

[associated types](#)

[exception variable, omitting](#)

[identifiers](#)

[values](#)

[assignment](#)

[primitive types](#)

[variant types](#)

[version number, assemblies](#)

[Version sealed class, System namespace](#)

[virtual function members](#)

[overriding](#)

[sealed](#)

[versions](#)

[virtual keyword](#)

[Visual C# 2003](#)

[Visual Studio](#)

[Visual Studio .NET](#)

[editions](#)

[void keyword](#)

[Void struct, System namespace](#)

[void*](#)

[volatile keyword](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

[Wait\(\) method](#)
[WaitCallback delegate, System.Threading](#)
[WaitForChangedResult struct, System.IO](#)
[WaitHandle abstract class, System.Threading](#)
[WaitOrTimerCallback delegate, System.Threading](#)
[WatcherChangeTypes enumeration, System.IO](#)
[WeakReference class, System namespace](#)
web services
 [FCL and](#)
 [WSDL.exe](#)
web-based applications, [FCL and](#)
[WebClient](#)
[WebClient sealed class, System.Net](#)
[WebException class, System.Net](#)
[WebExceptionStatus enumeration, System.Net](#)
[WebHeaderCollection class, System.Net](#)
[WebPermission sealed class, System.Net](#)
[WebPermissionAttribute sealed class, System.Net](#)
[WebProxy class, System.Net](#)
[WebRequest abstract class, System.Net](#)
[WebRequest.Create\(\) method](#)
[WebResponse abstract class, System.Net](#)
while keyword
while loops
whitespace, [regular expressions and](#)
[WhitespaceHandling enumeration, System.Xml](#)
[Wiltamuth, Scott](#)
[WinCV.exe](#)
word choice, [naming conventions](#)
[WriteState enumeration, System.Xml](#)
writing
 [to event logs](#)
 [files, I/O](#)
 [isolated storage](#)
[WSDL.exe](#)

[\[Team LiB \]](#)

[\[Team LiB \]](#)

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#)

XML (eXtensible Markup Language)

[documentation](#)

[comments](#)

[comments, C/C++ style](#)

[files](#)

[generated](#)

documents

[access](#)

[XSLT and](#)

[FCL and 2nd](#)

[nodes, XPath and](#)

[streams, parsing](#)

tags

[predefined 2nd](#)

[user-defined](#)

[type ID prefixes](#)

[types, cross-references](#)

XML schemas

[SoapSuds.exe](#)

[Xsd.exe](#)

[XmlAttribute class, System.Xml](#)

[XmlAttributeCollection class, System.Xml](#)

[XmlCaseOrder enumeration, System.Xml.XPath](#)

[XmlCDATASection class, System.Xml](#)

[XmlCharacterData abstract class, System.Xml](#)

[XmlComment class, System.Xml](#)

[XmlConvert class, System.Xml](#)

[XmlDataDocument class, System.Xml](#)

[XmlDataType enumeration, System.Xml.XPath](#)

[XmlDeclaration class, System.Xml](#)

[XmlDocument class, System.Xml](#)

[XmlDocumentFragment class, System.Xml](#)

[XmlDocumentType class, System.Xml](#)

[XmlElement class, System.Xml](#)

[XmlEntity class, System.Xml](#)

[XmlEntityReference class, System.Xml](#)

[XmlException class, System.Xml](#)

[XmlImplementation class, System.Xml](#)

[XmlLinkedNode abstract class, System.Xml](#)

[XmlNamedNodeMap class, System.Xml](#)

[XmlNamespaceManager class, System.Xml](#)

[XmlNameTable abstract class, System.Xml](#)

[XmlNode abstract class, System.Xml](#)

[XmlNodeChangedAction enumeration, System.Xml](#)

[XmlNodeEventArgs classes, System.Xml](#)

[XmlNodeEventHandler delegates, System.Xml](#)

[XmlNodeList abstract class, System.Xml](#)

[XmlNodeOrder enumeration, System.Xml](#)
[XmlNodeReader class](#)
[XmlNodeReader class, System.Xml](#)
[XmlNodeType enumeration, System.Xml](#)
[XmlNotation class, System.Xml](#)
[XmlParserContext class, System.Xml](#)
[XmlProcessingInstruction class, System.Xml](#)
[XmlQualifiedName class, System.Xml](#)
[XmlReader class](#)
[XmlReader class, System.Xml](#)
[XmlResolver class, System.Xml](#)
[XmlSecureResolver class, System.Xml](#)
[XmlSignificant Whitespace class, System.Xml](#)
[XmlSortOrder enumeration, System.Xml.XPath](#)
[XmlSpace enumeration, System.Xml](#)
[XmlText class, System.Xml](#)
[XmlTextReader class](#)
[XmlTextReader class, System.Xml](#)
[XmlTextWriter class, System.Xml](#)
[XmlTokenizedWriter enumeration, System.Xml](#)
[XmlUrlResolver class, System.Xml](#)
[XmlValidatingReader class](#)
[XmlValidatingReader class, System.Xml](#)
[XmlWhitespace class, System.Xml](#)
[XmlWriter abstract class, System.Xml](#)
[XmlWriter class](#)
[XPath](#)
[XPathDocument class, System.Xml.XPath](#)
[XPathException class, System.Xml.XPath](#)
[XPathExpression abstract class, System.Xml.XPath](#)
[XPathNamespaceScope enumeration, System.Xml.XPath](#)
[XPathNavigator abstract class, System.Xml.XPath](#)
[XPathNodeIterator abstract class, System.Xml.XPath](#)
[XPathNodeType enumeration, System.Xml.XPath](#)
[XPathResultType enumeration, System.Xml.XPath](#)
[Xsd.exe](#)
[XSLT \(eXtensible Stylesheet Language Transformation\) 2nd](#)
[XSLT stylesheets, generated documentation](#)
[XsltArgumentList sealed class, System.Xml.Xsl](#)
[XsltCompileException classes, System.Xml.Xsl](#)
[XsltContext classes, System.Xml.Xsl](#)
[XsltException class, System.Xml.Xsl](#)
[XsltTransform sealed class, System.Xml.Xsl](#)

[\[Team LiB \]](#)