



Jakarta Commons Cookbook

By Timothy M. O'Brien

Publisher: O'Reilly

Pub Date: November 2004

ISBN: 0-596-00706-X

Pages: 400

- [Table of Contents](#)
- [Index](#)
- [Reviews](#)
- [Reader](#)
- [Reviews](#)
- [Errata](#)
- [Academic](#)

This collection provides expert tips for using the utilities of the Java-based Jakarta Commons open source project. You don't have to be an expert, the book's solution-based format contains code examples for a wide variety of web, XML, network, testing, and application projects. If you want to learn how to use Jakarta Commons utilities to create powerful Java applications and tools, the *Jakarta Commons Cookbook* is for you.



Jakarta Commons Cookbook
By Timothy M. O'Brien

Publisher: O'Reilly
Pub Date: November 2004
ISBN: 0-596-00706-X
Pages: 400

- [Table of Contents](#)
- [Index](#)
- [Reviews](#)
- [Reader Reviews](#)
- [Errata](#)
- [Academic](#)

[Copyright](#)

[Preface](#)

[What's Inside](#)

[Conventions Used in This Book](#)

[What You'll Need](#)

[The Jakarta Commons Community](#)

[The Apache Software License](#)

[Using Code Examples](#)

[We'd Like to Hear from You](#)

[Acknowledgments](#)

[Chapter 1. Supplements to the Java 2 Platform](#)

[Introduction](#)

[Recipe 1.1. Obtaining Commons Lang](#)

[Recipe 1.2. Joining the Commons-User Mailing List](#)

[Recipe 1.3. Getting the Commons Lang Source Code](#)

[Recipe 1.4. Automating the Generation of toString\(\) Content](#)

[Recipe 1.5. Customizing Generated toString\(\) Content](#)

[Recipe 1.6. Automating hashCode\(\) and equals\(\)](#)

[Recipe 1.7. Automating compareTo\(\)](#)

[Recipe 1.8. Printing an Array](#)

[Recipe 1.9. Cloning and Reversing Arrays](#)

[Recipe 1.10. Transforming Between Object Arrays and Primitive Arrays](#)

[Recipe 1.11. Finding Items in an Array](#)

[Recipe 1.12. Creating a Map from a Multidimensional Array](#)

[Recipe 1.13. Formatting Dates](#)

[Recipe 1.14. Rounding Date Objects](#)

[Recipe 1.15. Truncating Date Objects](#)

[Recipe 1.16. Creating an Enum](#)

[Recipe 1.17. Generating Unique Numeric Identifiers](#)

[Recipe 1.18. Validation of Method Parameters](#)

[Recipe 1.19. Measuring Time](#)

[Chapter 2. Manipulating Text](#)

[Introduction](#)

[Recipe 2.1. Setting Up StringUtils and WordUtils](#)

[Recipe 2.2. Checking for an Empty String](#)

[Recipe 2.3. Abbreviating Strings](#)

[Recipe 2.4. Splitting a String](#)

[Recipe 2.5. Finding Nested Strings](#)

[Recipe 2.6. Stripping and Trimming a String](#)

[Recipe 2.7. Chomping a String](#)

[Recipe 2.8. Creating an Emphasized Header](#)

[Recipe 2.9. Reversing a String](#)

[Recipe 2.10. Wrapping Words](#)

[Recipe 2.11. Testing the Contents of a String](#)

[Recipe 2.12. Measuring the Frequency of a String](#)

[Recipe 2.13. Parsing Formatted Strings](#)

[Recipe 2.14. Calculating String Difference](#)

[Recipe 2.15. Using Commons Codec](#)

[Recipe 2.16. Getting the Commons Codec Source Code](#)

[Recipe 2.17. Calculating Soundex](#)

[Chapter 3. JavaBeans](#)

[Introduction](#)

[Recipe 3.1. Representing Beans Graphically](#)

[Recipe 3.2. Obtaining Commons BeanUtils](#)

[Recipe 3.3. Getting the Commons BeanUtils Source Code](#)

[Recipe 3.4. Accessing Simple Bean Properties](#)

[Recipe 3.5. Accessing Nested Bean Properties](#)

[Recipe 3.6. Accessing Indexed Bean Properties](#)

[Recipe 3.7. Accessing Mapped Bean Properties](#)

[Recipe 3.8. Accessing a Simple, Nested, Indexed, and Mapped Bean Property](#)

[Recipe 3.9. Determining the Type of a Bean Property](#)

[Recipe 3.10. Comparing Beans](#)

[Recipe 3.11. Copying Bean Properties](#)

[Recipe 3.12. Cloning a Bean](#)

[Recipe 3.13. Setting a Bean Property](#)

[Recipe 3.14. Testing Property Access](#)

[Recipe 3.15. Validating Beans with Predicates](#)

[Recipe 3.16. Creating a Map of Bean Properties](#)

[Recipe 3.17. Wrapping a Bean with a Map](#)

[Recipe 3.18. Creating a Dynamic Bean](#)

[Recipe 3.19. Getting and Setting Properties as Strings](#)

[Chapter 4. Functors](#)

[Introduction](#)

[Recipe 4.1. Obtaining Commons Collections](#)

[Recipe 4.2. Getting the Commons Collections Source Code](#)

[Recipe 4.3. Reversing a Comparator](#)

[Recipe 4.4. Chaining Comparators](#)

[Recipe 4.5. Comparing Nulls](#)

[Recipe 4.6. Fixed-Order Comparison](#)

[Recipe 4.7. Using Simple Predicates](#)

[Recipe 4.8. Writing a Custom Predicate](#)

[Recipe 4.9. Creating Composite Predicates](#)

[Recipe 4.10. Transforming Objects](#)

[Recipe 4.11. Creating a Chain of Transformations](#)

[Recipe 4.12. Applying Conditional Transformations](#)

[Recipe 4.13. Writing a Closure](#)

[Recipe 4.14. Chaining Closures](#)

[Recipe 4.15. Modeling Conditional Statements with Closures](#)

[Recipe 4.16. Modeling Loops with Closures](#)

[Chapter 5. Collections](#)

[Introduction](#)

[Recipe 5.1. Obtaining Commons Collections](#)

[Recipe 5.2. Using a Looping Iterator](#)

[Recipe 5.3. Iterating Over an ArrayList](#)

[Recipe 5.4. Filtering a Collection with a Predicate](#)

[Recipe 5.5. Iterating Through Distinct Elements](#)

[Recipe 5.6. Using a Bag](#)

[Recipe 5.7. Using a Buffer](#)

[Recipe 5.8. Creating a Priority Queue](#)

[Recipe 5.9. Using a Blocking Buffer](#)

[Recipe 5.10. Storing Multiple Values in a Map](#)

[Recipe 5.11. Retrieving a Key by a Value](#)

[Recipe 5.12. Using a Case-Insensitive Map](#)

[Recipe 5.13. Creating Typed Collections and Maps](#)

[Recipe 5.14. Constraining Map Values](#)

[Recipe 5.15. Constraining List Contents](#)

[Recipe 5.16. Transforming Collections](#)

[Recipe 5.17. Creating a Least Recently Used Cache](#)

[Recipe 5.18. Using a Lazy Map](#)

[Recipe 5.19. Counting Objects in a Collection](#)

[Recipe 5.20. Performing Set Operations](#)

[Recipe 5.21. Retrieving Map Values Without Casting](#)

[Chapter 6. XML](#)

[Introduction](#)

[Recipe 6.1. Obtaining Jakarta Commons Digester](#)

[Recipe 6.2. Turning XML Documents into Objects](#)

[Recipe 6.3. Namespace-Aware Parsing](#)

[Recipe 6.4. Creating a Simple XML Command Language](#)

[Recipe 6.5. Variable Substitution and XML Parsing](#)

[Recipe 6.6. Obtaining Jakarta Commons Betwixt](#)

[Recipe 6.7. Turning Beans into XML Documents](#)

[Recipe 6.8. Customizing XML Generated from an Object](#)

[Recipe 6.9. Turning XML Documents into Beans](#)

[Chapter 7. Application Infrastructure](#)

[Introduction](#)

[Recipe 7.1. Obtaining Commons CLI](#)

[Recipe 7.2. Parsing a Simple Command Line](#)

[Recipe 7.3. Parsing a Complex Command Line](#)

[Recipe 7.4. Printing Usage Information](#)

[Recipe 7.5. Obtaining Commons Configuration](#)

[Recipe 7.6. Configuring Applications with Properties Files](#)

[Recipe 7.7. Configuring Applications with XML](#)

[Recipe 7.8. Using Composite Configuration](#)

[Recipe 7.9. Obtaining Commons Logging](#)

[Recipe 7.10. Using an Abstract Logging Interface](#)

[Recipe 7.11. Specifying a Logging Implementation](#)

[Recipe 7.12. Obtaining Apache Log4J](#)

[Recipe 7.13. Configuring Log4J with a Properties File](#)

[Recipe 7.14. Configuring Log4J with XML](#)

[Chapter 8. Math](#)

[Introduction](#)

[Recipe 8.1. Using Fractions](#)

[Recipe 8.2. Finding the Maximum and Minimum in an Array](#)

[Recipe 8.3. Using Number Ranges](#)

[Recipe 8.4. Generating Random Variables](#)

[Recipe 8.5. Obtaining Commons Math](#)

[Recipe 8.6. Calculating Simple Univariate Statistics](#)

[Recipe 8.7. Solving a System of Linear Equations](#)

[Recipe 8.8. Arithmetic with Complex Numbers](#)

[Recipe 8.9. Establishing Relationships Between Variables](#)

[Recipe 8.10. Estimating the Amount of Time Left in a Process](#)

[Chapter 9. Templating](#)

[Introduction](#)

[Recipe 9.1. Obtaining Commons JEXL](#)

[Recipe 9.2. Using an Expression Language](#)

[Recipe 9.3. Invoking Methods in an Expression](#)

[Recipe 9.4. Externalizing Logic with an Expression Language](#)

[Recipe 9.5. Obtaining Jakarta Velocity](#)

[Recipe 9.6. Using a Simple Templating Language](#)

[Recipe 9.7. Writing Templates with Conditionals and Loops](#)

[Recipe 9.8. Using Macros in a Templating Engine](#)

[Recipe 9.9. Invoking Methods in a Template](#)

[Recipe 9.10. Obtaining FreeMarker](#)

[Recipe 9.11. Using a Complex Scripting Engine](#)

[Recipe 9.12. Accessing XML Documents from a Templating Engine](#)

[Recipe 9.13. Using Velocity in a Web Application](#)

[Recipe 9.14. Using FreeMarker in a Web Application](#)

[Recipe 9.15. Writing Templates in Eclipse](#)

[Chapter 10. I/O and Networking](#)

[Introduction](#)

[Recipe 10.1. Obtaining Commons IO](#)

[Recipe 10.2. Copying Streams, byte\[\], Readers, and Writers](#)

[Recipe 10.3. Closing Streams, Readers, and Writers](#)

[Recipe 10.4. Printing a Human-Readable File Size](#)

[Recipe 10.5. Copying Files, Strings, and URLs](#)

[Recipe 10.6. Deleting Directories Recursively](#)

[Recipe 10.7. Obtaining the Size of a Directory](#)

[Recipe 10.8. Touching a File](#)

[Recipe 10.9. Filtering Files](#)

[Recipe 10.10. Measuring Stream Traffic](#)

[Recipe 10.11. Splitting an OutputStream](#)

[Recipe 10.12. Obtaining Jakarta ORO](#)

[Recipe 10.13. Using Globs and Perl5 Regular Expressions to List Files](#)

[Recipe 10.14. Obtaining Commons Net](#)

[Recipe 10.15. Writing an FTP Client](#)

[Recipe 10.16. Sending Mail with SMTP](#)

[Recipe 10.17. Checking a POP3 Mailbox](#)

[Chapter 11. HTTP and WebDAV](#)

[Introduction](#)

[Recipe 11.1. Obtaining Jakarta HttpClient](#)

[Recipe 11.2. Getting Jakarta HttpClient Source Code](#)

[Recipe 11.3. Performing an HTTP GET](#)

[Recipe 11.4. Sending Parameters in a Query String](#)

[Recipe 11.5. Retrieving Content with a Conditional GET](#)

[Recipe 11.6. Debugging HTTP Communications](#)

[Recipe 11.7. Making an HTTP POST Request](#)

[Recipe 11.8. Sending POST Data from a File](#)

[Recipe 11.9. Uploading Files with a Multipart POST](#)

[Recipe 11.10. Basic Authentication](#)

[Recipe 11.11. NTLM Authentication](#)

[Recipe 11.12. Working with Cookies](#)

[Recipe 11.13. Handling Redirects](#)

[Recipe 11.14. SSL](#)

[Recipe 11.15. Accepting a Self-Signed Certificate](#)

[Recipe 11.16. Obtaining Jakarta Slide](#)

[Recipe 11.17. Connecting to WebDAV Resources](#)

[Recipe 11.18. Modifying a WebDAV Resource](#)

[Chapter 12. Searching and Filtering](#)

[Introduction](#)

- [Recipe 12.1. Obtaining Commons JXPath](#)
- [Recipe 12.2. Querying an Object Graph with XPath](#)
- [Recipe 12.3. Search a Collection of Simple Objects](#)
- [Recipe 12.4. Applying XPath Queries to Complex Object Graphs](#)
- [Recipe 12.5. Obtaining Jakarta Lucene](#)
- [Recipe 12.6. Creating an Index of XML Documents](#)
- [Recipe 12.7. Searching for a Specific Term in a Document Index](#)
- [Recipe 12.8. Finding the Frequency of Terms in an Index](#)

[Colophon](#)

[Index](#)



Copyright © 2005 O'Reilly Media, Inc. All rights reserved.

Printed in the United States of America.

Published by O'Reilly Media, Inc., 1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (<http://safari.oreilly.com>). For more information, contact our corporate/institutional sales department: (800) 998-9938 or corporate@oreilly.com.

Nutshell Handbook, the Nutshell Handbook logo, and the O'Reilly logo are registered trademarks of O'Reilly Media, Inc. The Cookbook series designations, Jakarta Commons Cookbook, the image of an aardvark, and related trade dress are trademarks of O'Reilly Media, Inc.

Java and all Java-based trademarks and logos are trademarks or registered trademarks of Sun Microsystems, Inc., in the United States and other countries. O'Reilly Media, Inc. is independent of Sun Microsystems, Inc.

Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media, Inc. was aware of a trademark claim, the designations have been printed in caps or initial caps.

While every precaution has been taken in the preparation of this book, the publisher and authors assume no responsibility for errors or omissions, or for damages resulting from the use of the information contained herein.

Preface

In this book, you'll find information about a set of libraries developed within the Jakarta Commons (also referred to as "Commons"). Commons (<http://jakarta.apache.org/commons>) is a set of small, popular components from the Apache Software Foundation's Jakarta project. Ranging from the elementary to the complex, many would consider some of these libraries indispensable to any Java® project. These components are so widespread, they may already be on your classpath. If you develop an application using Jakarta Struts, Apache Tomcat, or Hibernate, you have Commons BeanUtils and Commons Logging in your classpath. If you just installed Red Hat Enterprise Linux with the default configuration, you've got Commons libraries somewhere in */usr*. If you downloaded Sun's J2EE 1.4 SDK, you will have also downloaded Commons Logging and Commons Launcher. While Jakarta Commons may be everywhere, many are still unaware of the capabilities these components provide.

This book uses Jakarta Commons to focus on tactical implementation details, answering such questions as: How do we parse XML? How do we serialize beans? Is there an easier way to work with Collections? How do we work with HTTP and keep track of cookies? The tactical is often sacrificed for the strategic. Consider a complex J2EE system with a solid, well-conceived architecture. The strategic (or high-level) design appears reasonable from 40,000 feet, but as soon as you drill into the details, you notice that every Servlet or JSP contains pages upon pages of unmaintainable and unnecessary code because the developers were not aware of some valuable time-saver like BeanUtils, Collections, or the Digester. Or, worse, the developer may have spent a week reimplementing most of the capabilities of Commons BeanUtils even though BeanUtils was already in the classpath. Knowing what Jakarta Commons has to offer often helps to inform decisions made at the lowest level.

Few application developers would consider writing a custom XML parser, but developers will frequently write custom components that duplicate freely available libraries. Take, as an example, a set of static utility methods that seems to pop up in almost every complex project. A common process such as reading a file to a `String` may be refactored into a `CommonFileUtils` class, or turning a DOM `Document` into a set of beans may be accomplished with a set of classes in some custom code. Jakarta Commons provides solutions to both of these problems and many more, and reading this book may help you to avoid unnecessary wheel reinvention.

Many people know of these components in a general sense, but few have the months or weeks necessary to sit down and read the relevant tutorials, FAQs, blogs, and archived mailing lists associated with each component. The amount of work involved in keeping up-to-date with an array of open source communities is not trivial. This is why I've tried to compact much of this information into easily accessible recipes. These recipes were written to provide the information you need to start using Commons in a few minutes, but the Discussion and See Also sections give you an opportunity to dig deeper into the motivation behind each Commons component if you need more information.

The tools introduced herein save you serious time and provide you with a set of alternatives you may not currently be aware of. I wish I had read a book like this five years ago; it would have accelerated my learning and helped me to avoid some costly design decisions. Use this text as you will; if you are only interested in Commons Collections, you should be able to quickly familiarize yourself with Collections by browsing [Chapter 5](#). On the other hand, if you are looking for a survey of some of the major projects in Jakarta Commons, read this book from start to finish. Part structured reference,

part prose, the cookbook format lets you customize your reading experience, and I hope this book is as interesting to read as it was to write.

What's Inside

This book covers components from Jakarta Commons, a few projects from Jakarta, and one project outside of the Apache Software Foundation. This book covers the following components:

- Jakarta Commons BeanUtils
- Jakarta Commons Betwixt
- Jakarta Commons CLI
- Jakarta Commons Codec
- Jakarta Commons Collections
- Jakarta Commons Configuration
- Jakarta Commons Digester
- Jakarta Commons HttpClient
- Jakarta Commons ID
- Jakarta Commons IO
- Jakarta Commons JEXL
- Jakarta Commons XPath
- Jakarta Commons Lang
- Jakarta Commons Logging
- Jakarta Commons Math
- Jakarta Commons Net
- Apache Log4J
- Jakarta Velocity
- FreeMarker
- Jakarta Lucene
- Jakarta Slide

All of these projects are covered in detail in the following chapters. Here's what's in each chapter:

[Chapter 1](#), *Supplements to the Java 2 Platform*

This chapter introduces Commons Lang. Automation of `toString()`, working with arrays, formatting and rounding dates, working with enumerations, generating identifiers, and measuring time are some of the topics discussed in this chapter. This chapter also covers the generation of unique identifiers with Commons ID.

[Chapter 2](#), *Manipulating Text*

While Java does not have the extensive text manipulation capabilities of a scripting language like Perl, Commons Lang's `StringUtils` has a number of utility methods that can be used to manipulate text. This chapter deals with `StringUtils`, `WordUtils`, and Commons Codec.

[Chapter 3](#), *JavaBeans*

Beans appear throughout Java; from Jakarta Struts to Hibernate, beans are a unit of information in an object model. This chapter introduces Commons BeanUtils, one of the most widely used components from Jakarta Commons.

[Chapter 4](#), *Functors*

Functors are a fundamental way of thinking about programming as a set of functional objects. Commons Collections introduced predicates, transformers, and closures, and functors, which can be used to model control structures and loops. This chapter demonstrates how one would apply functors to any program.

[Chapter 5](#), *Collections*

Iterators, filtering with predicates, buffers, queues, bidirectional maps, type-safe collections, constraining collections, lazy maps, and set operations are a few of the topics introduced in this chapter. This chapter deals with Commons Collections, new collection types introduced, and the application of functors to various collections.

[Chapter 6](#), *XML*

If you are constantly parsing or creating XML documents, this chapter introduces some alternatives to the standard parser APIs (SAX, DOM, and JDOM). This chapter introduces Commons Digester, Commons Betwixt, and Commons XPath.

[Chapter 7](#), *Application Infrastructure*

Commons Configuration is introduced as a way to parse properties files and XML configuration files. Other recipes in this chapter show how Commons CLI can be used to parse a complex set of required and optional command-line options. This chapter also details the configuration and use of Commons Logging and Apache Log4J.

[Chapter 8](#), *Math*

This chapter focuses on simple mathematical capabilities in both Commons Lang and Commons Math. This chapter introduces classes to work with fractions, complex numbers, matrices, and simple univariate statistics.

[Chapter 9](#), *Templating*

This chapter deals with simple expression languages such as Commons JEXL to more complex templating engines such as Jakarta Velocity and FreeMarker. This chapter also demonstrates the integration of both Velocity and FreeMarker with a J2EE servlet container such as Jakarta Tomcat.

[Chapter 10](#), *I/O and Networking*

This chapter introduces Commons IO, which contains a number of utilities for working with streams and files, and Commons Net, which contains simple clients for the FTP, POP, and SMTP protocols.

[Chapter 11](#), *HTTP and WebDAV*

If you need to communicate with anything over HTTP, read this chapter, which deals with Jakarta HttpClient and the WebDAV client library from Jakarta Slide.

[Chapter 12](#), *Searching and Filtering*

Commons XPath can be used to apply XPath expressions to collections and object graphs. Jakarta Lucene is a fully functional search engine that can index any structured document. This chapter demonstrates the use of Lucene with Commons Digester.

Limited time and resources forced me to make some decisions about which projects to include in this text. Projects like Velocity, FreeMarker, and Log4J, while not Commons components, were included because they fit the mold of a small, easily reusable component. Other Commons components were not included in this book because they were still being developed at the time of writing, or because a short recipe would have been impossible without a detailed 30-page introduction. Commons DbUtils, DBCP, Discovery, Jelly, Launcher, Modeler, Pool, Primitives, Chain, and promising sandbox components could fill another entire volume. Some projects, such as Jakarta HiveMind, started as

components in the Commons Sandbox only to be promoted directly to subproject status of the Jakarta project. Classification of projects and components in Jakarta can also be somewhat arbitrary; Jakarta ORO and Jakarta RegExp would both seem to be prime candidates for the Jakarta Commons, but they are both subprojects of Jakarta. Other projects, such as Jakarta Commons HttpClient, have recently been promoted to be subprojects of Jakarta, leaving the Commons entirely. Think of this book as focusing on Jakarta Commons with some other projects thrown in to liven up the discussion. I apologize in advance if I left your favorite project out.

Writing a book about a series of frequently released components is reminiscent of a game called whack-a-mole. Just when you finish updating a chapter for a new release, another component has a release. On average, one commons component is released every one or two weeks; therefore, a few of the versions in this book may be obsolete as soon as this book hits the shelves. In general, Jakarta Commons makes a concerted effort to preserve backward compatibility and keep a stable public interface. Lessons learned on Commons BeanUtils 1.6 should remain applicable to Commons BeanUtils 1.7. If you find that a more recent version of a component has been released, you should download that more recent version and check the O'Reilly site for updates related to this book.

Conventions Used in This Book

I'll use a number of conventions you should know about in this book. For example, menu items are separated with an **→** like this: File**→**New Project. To make them stand out, new lines of code will be displayed highlighted when they're added. Example code is often presented out of context; instead of developing an entire class, only the relevant block of code is presented. Most examples will include the necessary import statements for Commons-relevant classes, and other `import` statements will be implied. When code is omitted or implied, it will be represented by ellipses:

```
import org.apache.commons.digester.Digester;
```

```
...
```

```
Digester digester = new Digester( );
```

```
digester.doSomething( );
```

In addition, the following typographical conventions are also used in this book:

Italic

Indicates new terms, URLs, email addresses, filenames, file extensions, pathnames, directories and Unix utilities.

`Constant width`

Indicates commands, options, switches, variables, types, classes, namespaces, methods, modules, properties, parameters, values, objects, events, event handlers, and XML tags.

`Constant width italic`


Shows text that should be replaced with user-supplied values.

Constant width bold

Highlights important text within code examples.



This icon signifies a tip, suggestion, or general note.



This icon indicates a warning or caution.



What You'll Need

To experiment with the various libraries introduced in this book, you will need the J2SE 1.4 SDK, which can be obtained from <http://www.javasoft.com>. The examples in this book were developed in an IDE named Eclipse, which can be downloaded from the Eclipse project site at <http://www.eclipse.org>. Each chapter contains instructions for downloading the various Jakarta Commons components; to download any component from Jakarta Commons, go to the Jakarta Commons page at <http://jakarta.apache.org/commons> and click on "Binaries" under "Download" in the left menu.

The Jakarta Commons Community

The Jakarta community and the larger community of the Apache Software Foundation is committed to developing open source software. The Apache Software Foundation is a nonprofit corporation registered in Delaware that supports ongoing collaborative software development according to a set of simple ideals: transparency, meritocracy, consensus, and mutual respect. To learn more about the foundation, start at the Frequently Asked Questions page on www.apache.org (<http://www.apache.org/foundation/faq.html>). Jakarta is a project under the Apache Software Foundation, and it is managed by what is known as a Project Management Committee (PMC). This committee manages a number of Jakarta subprojects including the Jakarta Commons.

The Jakarta community and Apache XML community both had tremendous growth spurts from 1999 to 2003, with both projects becoming dominant forces in open source Java. Tomcat, Struts, Xerces, Xalan, Ant, Cocoon, and other projects were embraced by the larger community and Java developed a very strong association with open source because of the influence of Jakarta. Toward the end of this growth spurt, the corporate structure of Apache required a certain level of oversight and accountability, which could not be achieved in an umbrella project like Jakarta with hundreds of committers. A decision was made to encourage Jakarta subprojects to move toward smaller, more focused PMCs. One of the first projects to leave Jakarta was Apache Ant, and other projects such as Maven, Struts, and Log4j followed suit. This new, more nimble approach to the structure of collaborative software development avoids the creation of a management layer between project participants and the PMC. Apache is making way for a new generation of projects that will set the standard for open source Java, including Geronimo, Pluto, Directory, Derby, and Axion. Be aware that the structure of projects and subprojects in Jakarta is somewhat fluid at the moment, and, as the situation evolves, certain components could be split off into separate Apache projects.

If you find the components in this book helpful, I encourage you to take some time to observe the commons-dev developer mailing list. The ASF is (mostly) transparent, and this means that the general public has a window into the collaborative development process that is used to create a large body of great software. I would encourage any developer to take an interest in a piece of software and watch the development process. Follow the decisions, releases, arguments, flame-wars, and evolution of something like Jakarta Commons and you can see for yourself what works and what doesn't work. This is also a great way to keep yourself informed of the changes and direction of certain projects.

I don't intend to speak for this community, and, honestly, no one can speak for a group as diverse as the one that has formed around Jakarta Commons. I wanted to write this book to help attract more people to the concept of Jakarta Commons and to take some time to encourage people to think about how they could contribute to that effort. If there are more people paying attention to the software, Commons components will have higher quality, more bug reports will be filed, and more people might take some time to submit documentation patches. If you find Jakarta Commons (or any other Apache software) useful, you should consider taking a little bit of time to help a fellow user on the user mailing list or submit documentation patches. If you find a typo or a bug, file a report on Apache's Bugzilla installation (<http://issues.apache.org/bugzilla>) or Jira installation (<http://issues.apache.org/jira>).

There is always a need for greater unit test coverage, and any time you find an inconsistency in code

you should file a bug. Contributions can come in many forms - answering user questions, writing documentation, writing unit tests, submitting patches, or providing feedback. All of these contributions help sustain a living community. If you find yourself unable to participate in the community, you can make a small (possibly tax-deductible) donation to the Apache Software Foundation to help offset the cost of infrastructure and bandwidth (<http://www.apache.org/foundation/contributing.html>).



The Apache Software License

Everything in this book is covered by the Apache Software License 2.0 (except FreeMarker, which is covered by a similar BSD-style license). All developers who touch open source should be familiar with the various licenses and come to their own conclusions; most importantly, you should become familiar with the Apache license (and other BSD-style licenses) and how it differs from the GNU General Public License (GPL) and GNU Lesser General Public License (LGPL). Read the Apache Software License 2.0 at <http://www.apache.org/licenses/>.

I am not a lawyer (IANAL), but I would urge you to learn as much as you can about these licenses before you start to use them. For more information about open source, and for a comprehensive list of licenses, see the Open Source Initiative (OSI) at <http://www.opensource.org>. The Apache license does not place restrictions on people or organizations that wish to redistribute the software it covers, and, in general, the Apache license creates fewer licensing headaches for individuals and organizations that want to incorporate open source software into a commercial product.



Using Code Examples

This book is here to help you get your job done. In general, you may use the code in this book in your programs and documentation. You do not need to contact us for permission unless you're reproducing a significant portion of the code. For example, writing a program that uses several chunks of code from this book does not require permission. Selling or distributing a CD-ROM of examples from O'Reilly books *does* require permission. Answering a question by citing this book and quoting example code does not require permission. Incorporating a significant amount of example code from this book into your product's documentation *does* require permission.

We appreciate, but do not require, attribution. An attribution usually includes the title, author, publisher, and ISBN. For example: "*Jakarta Commons Cookbook*, by Timothy M. O'Brien. Copyright 2005 O'Reilly Media, Inc., 0-596-00706-X."

If you feel your use of code examples falls outside fair use or the permission given above, feel free to contact us at permissions@oreilly.com.



We'd Like to Hear from You

Please address comments and questions concerning this book to the publisher:

O'Reilly Media, Inc.
1005 Gravenstein Highway North
Sebastopol, CA 95472
(800) 998-9938 (in the United States or Canada)
(707) 829-0515 (international or local)
(707) 829-0104 (fax)

O'Reilly maintains a web page for this book, where errata, examples, and any additional information are listed. You can access this page at:

<http://www.oreilly.com/catalog/jakartackbk>

To comment or ask technical questions about this book, send email to:

bookquestions@oreilly.com

For more information about O'Reilly books, conferences, Resource Centers, and the O'Reilly Network, see the web site:

<http://www.oreilly.com>

Acknowledgments

This book would have been impossible to write were it not for the support and inspiration of a number of colleagues, friends, and family.

Thanks to Brett McLaughlin, my editor, who had a huge impact on the quality, structure, and content of the book. His feedback and advice over the course of the past year has been immeasurably valuable. Thanks also to Karen Tegtmeyer for reviewing this book.

Primary credit should first go to the Jakarta community and the various individuals who give hours upon hours of time to cut releases and maintain infrastructure. In the face of constant challenge, Jakarta has remained a well spring of innovation.

Thanks to Michael Podrazik, Stefan Winz, Bob Hartlaub, Gautam Guliani, Jarret Rackoff, Robert Sorkin, and Federico Hatoum, and Grassroots Technologies in New York, NY. Stefan originally introduced me to the Commons in the form of the Digester.

Thanks to various colleagues: Tim Beynart, Mike Smith, Felix Sheng, Julian Bleecker, Jim Buswell, Peter Costa, Rich Angeletti, David Winterfeldt, Ray Krueger, Chris Bobbitt, Tom Bergerson, Alex Wolfe, David Navin, Mark Snell, Bill Martens, Sultan Meghji, Daniel Summers, Greg Sandell, Dan Waite, and Benjamin Burton.

Mad props to Dave and Nicola, Rock, Patrick, Kat and Jay, Mike, Kelcey, John, Heather, Nick, Jessica, Marc, Krys, Joan, Jim, Zach, Sarah, and Mickey. Much respect to John Bicknell, Karen Brunssen, Kit Bridges and the Trinity Episcopal Church Choir. Endless thanks to Andrea and Klaus.

Thanks to my family, Chris, Kriste, Charlotte, Lily, Sean, Amy, Lucy, Kathy, Toby, Julie, Taylor, the Gilmores, Janey, all the O'Briens, and my parents Margaret and Michael. Thanks to the Paynes: Becky, James, Heather, Chris, Jeannette, Matt, Susette and Tom, Grandma Barbee and James Sr.

Most of all, I would like to thank my wife, Susan O'Brien, for being perfect. Happy Halloween.

Chapter 1. Supplements to the Java 2 Platform

[Introduction](#)

[Recipe 1.1. Obtaining Commons Lang](#)

[Recipe 1.2. Joining the Commons-User Mailing List](#)

[Recipe 1.3. Getting the Commons Lang Source Code](#)

[Recipe 1.4. Automating the Generation of toString\(\) Content](#)

[Recipe 1.5. Customizing Generated toString\(\) Content](#)

[Recipe 1.6. Automating hashCode\(\) and equals\(\)](#)

[Recipe 1.7. Automating compareTo\(\)](#)

[Recipe 1.8. Printing an Array](#)

[Recipe 1.9. Cloning and Reversing Arrays](#)

[Recipe 1.10. Transforming Between Object Arrays and Primitive Arrays](#)

[Recipe 1.11. Finding Items in an Array](#)

[Recipe 1.12. Creating a Map from a Multidimensional Array](#)

[Recipe 1.13. Formatting Dates](#)

[Recipe 1.14. Rounding Date Objects](#)

[Recipe 1.15. Truncating Date Objects](#)

[Recipe 1.16. Creating an Enum](#)

[Recipe 1.17. Generating Unique Numeric Identifiers](#)

[Recipe 1.18. Validation of Method Parameters](#)

[Recipe 1.19. Measuring Time](#)

Introduction

This chapter introduces utilities that augment the Java 2 Standard Edition (J2SE), providing classes and utilities that make some of the more mundane programming tasks more straightforward. Jakarta Commons Lang is a collection of useful supplements to the J2SE. This package fills gaps present in the standard Java API and provides a number of simple, time-saving utility classes. Sun's Javadoc for the `java.lang` package in the J2SE states that the package "provides classes that are fundamental to the design of the Java programming language." In the same vein, Jakarta Commons Lang provides classes that augment the fundamental design of the Java programming language.

You may be tempted to skip the simple recipes presented in this chapter and continue on to more advanced topics in this text. String manipulation, date truncation, and `toString()` methods do not inspire the sense of mystery and genius one feels when working with Extensible Markup Language (XML) or an open source text-to-speech engine. But, even if you are the most fluent speaker of Java, there are lessons to be learned from the utilities introduced in this chapter; a simple trick learned here may save you a few minutes every single day. Don't waste your time rewriting and maintaining utilities that already exist in Commons Lang; there are more interesting problems to be solved, and building `hashCode()` functions is not one of them.

The Advent of Tiger

With the release of Tiger (the codename for Java 1.5), some of these utilities are duplicated or superseded. Those of you who are stuck with 1.4 for a few more months will find some of the supplements in this chapter helpful, regardless of the availability of a new Java Virtual Machine (JVM). Even if you are using Java 1.5, the recipes in this chapter will still be relevant. A few classes in many Jakarta Commons projects have been made obsolete by the release of 1.4, but there are still many vocal users who are using an application that only runs in 1.3 (or even 1.2). The bar for backward compatibility will eventually shift, but for now, most Commons components work with 1.3 or 1.4 at a minimum.



Recipe 1.1 Obtaining Commons Lang

Problem

You want to use Commons Lang because your program needs to use some of the simple utilities this component provides, such as array manipulation, date manipulation, and enums.

Solution

To download the latest version of Commons Lang, follow these steps:

1. In a web browser, open the URL <http://jakarta.apache.org/site/binindex.cgi>. This URL will select a mirror, and generate a page with links to download binary distributions from an Apache mirror.
2. Find the Commons Lang project section. If you search for the term "Commons Lang," you will find a section that provides a link to download the latest binary release of Commons Lang.
3. Click on either the *2.0 zip* or *2.0 tar.gz* (depending on your platform) to download Commons Lang 2.0.
4. Unzip or untar the binary distribution. This will create a directory named *commons-lang-2.0*. The *commons-lang-2.0* directory should now contain a Java Archive (JAR) file, *commons-lang-2.0.jar*.
5. Copy or add *commons-lang-2.0.jar* to your classpath.

Discussion

Step #5 varies based on your development environment. If you are working with Apache Ant as a build tool, you will need to make sure that your classpath includes the Commons Lang JAR. If you are using an Integrated Development Environment (IDE) like Eclipse, you will need to copy this JAR to a directory in your project, and alter your project's preferences to add Commons Lang 2.0 to the "Java Build Path." If you are using Maven as a build tool, add the following dependency to the dependencies section of your *project.xml*.

<dependencies>

<dependency>

```
<id>commons-lang</id>

<version>2.0</version>

</dependency>

...other dependencies...

</dependencies>
```

The Commons Lang library includes utilities for working with dates, exceptions, arrays, enums, and more. It is one of the most widely used libraries in open source Java. To learn more about Commons Lang, visit the Jakarta Commons Lang web site at <http://jakarta.apache.org/commons/lang/>.



At the time of writing, the most recent version of the Commons Lang component was Version 2.0. If there is a more recent version of Commons Lang available, use the latest version. Although not a guarantee or a promise, most Jakarta Commons components strive for backward compatibility. If an interface has been altered or functionality removed, it will be noted in the release notes for a newer version. If you are going to use a different version of the Commons Lang component with the recipes in this chapter, make sure to read the release notes, which are stored in the file *RELEASE-NOTES.txt*.

See Also

If you are having an issue with one of the utilities in Commons Lang, see [Recipe 1.2](#) on joining the Commons-user mailing list. If you are looking for the source code, see [Recipe 1.3](#) on obtaining the source code for Commons Lang. You can also visit the Commons Lang web site at <http://jakarta.apache.org/commons/lang>.



Recipe 1.2 Joining the Commons-User Mailing List

Problem

You want to ask a question about a component in Jakarta Commons.

Solution

Join the commons-user@jakarta.apache.org mailing list, and ask your question. This mailing list is full of Commons users, and it is a good place to discuss any problems you've had with a particular utility in the Jakarta Commons.

Discussion

Before you join this mailing list, take a moment to familiarize yourself with the mailing list guidelines available at <http://jakarta.apache.org/site/mail.html>. Once you have read these guidelines, you can find information about joining this mailing list at <http://jakarta.apache.org/site/mail2.html#Commons>.

The Jakarta Commons-user mailing list is a place for users of all Commons components to ask questions of other users and Commons developers. This mailing list has a high volume of messages, and subscribers should prefix all subjects with the component you are discussing. In the case of Commons Lang, make sure your email subject starts with `[lang]` before sending a message to the Commons-user mailing list; otherwise, your email may be ignored.

If you have a question or a comment, you will save yourself time and trouble if you search the archives of the Commons-user mailing list (<http://www.mail-archive.com/commons-user@jakarta.apache.org/>) for related discussions. The archives of this mailing list are a great place to look if you are having problems with a particular Commons component. Try not to ask a question that has already been asked and answered in a previous discussion, and remember that the Apache Software Foundation (ASF) is a volunteer organization-members of the community will gladly assist you if you provide enough information. And, don't be shy. If you know the answer to someone's question, you don't have to ask for anyone's permission to actively participate.

See Also

The Commons-user mailing list archive is also available from the Eyebrowse list archive at <http://nagoya.apache.org/eyebrowse/SummarizeList?listId=15>.



Recipe 1.3 Getting the Commons Lang Source Code

Problem

You want to view the source code for the Commons Lang project.

Solution

Download the source code from <http://jakarta.apache.org/site/sourceindex.cgi>. Following the same procedure as outlined in [Recipe 1.1](#), you can download a file named *commons-lang-2.0-src.zip* (or *commons-lang-2.0-src.tar.gz*). Once you unzip this file, you will have the source to Commons Lang in *./commons-lang-2.0-src*.

Discussion

The *commons-lang-2.0-src* directory will contain the following:

build.xml

An Apache Ant build file, which you can use to compile the source. If Ant is installed, you can compile or test by running `ant compile` or `ant test`.

src/java

This subdirectory contains the source for the classes in Commons Lang.

src/test

This subdirectory contains unit tests for the Commons Lang project. Each **Test.java* file is an extension of JUnit `TestCase` class.

See Also

For more information about Apache Ant, see the Ant project page at<http://ant.apache.org>. Also see Chapter 3 in the *Java Extreme Programming Cookbook* by Eric M. Burke and Brian M. Coyner (O'Reilly).

The unit tests in this source distribution use the JUnit testing framework. For more information about JUnit, see the JUnit project page at <http://www.junit.org>. Also see Chapter 4 in the *Java Extreme Programming Cookbook* by Burke and Coyner.

See [Recipe 1.1](#) for information about obtaining the binary distribution for Commons Lang, and see the Commons Lang web site at <http://jakarta.apache.org/commons/lang>.



Recipe 1.4 Automating the Generation of toString() Content

Problem

You want to automate the creation of `toString()` methods.

Solution

Use the Commons Lang `ReflectionToStringBuilder` or `ToStringBuilder` and `ToStringBuilder` to create `toString()` methods. The following code is an example of a `toString()` method, which uses a reflection builder:

```
import org.apache.commons.lang.builder.ToStringBuilder;

public void toString( ) {

    ReflectionToStringBuilder.toString( this );

}
```

Discussion

Assume that you have an object named `PoliticalCandidate`-a bean that represents some information about a presidential candidate. This bean has a set of properties: `firstName`, `lastName`, `dateOfBirth`, `moneyRaised`, and `homeState`. [Example 1-1](#) shows the `PoliticalCandidate` class using a `ReflectionToStringBuilder`; the getter and setter methods have been omitted for brevity.

Example 1-1. The PoliticalCandidate class using ReflectionToStringBuilder

```
import java.math.*;

import java.util.*;

import org.apache.commons.lang.builder.ReflectionToStringBuilder;
```



```
public class PoliticalCandidate {

    private String lastName;

    private String firstName;

    private Date dateOfBirth;

    private BigDecimal moneyRaised;

    private State homeState;

    // get/set methods are omitted for brevity...

    public void toString( ) {

        ReflectionToStringBuilder.toString( this );

    }

}
```

The process of keeping the contents of a `toString()` method synchronized with a changing object model becomes a chore (usually a forgotten one). Commons Lang includes a fairly simple utility designed to automate this chore using reflection. The `ToStringBuilder` class and its extension, `ReflectionToStringBuilder`, can condense a large `toString()` method body into one line of code. Most importantly, the `ReflectionToStringBuilder` reflects any future changes that are made to the object model. The following code demonstrates the output of a string built via reflection:

```
// Create a State

State va = new State( "VA", "Virginia");

// Create a Birth Date

Calendar calendar = new GregorianCalendar( );

calendar.set( Calendar.YEAR, 1743 );

calendar.set( Calendar.MONTH, Calendar.APRIL );
```

```

calendar.set( Calendar.DAY_OF_MONTH, 13 );

Date dob = calendar.getTime( );

BigDecimal moneyRaised = new BigDecimal( 293829292.93 );

// Create a Political Candidate

PoliticalCandidate candidate =

    new PoliticalCandidate( "Jefferson", "Thomas", dob, moneyRaised, va );

System.out.println( candidate );

```

Assume that the `State` object is another bean using the same `ReflectionToStringBuilder`. The code above sets the properties of a bean and produces the following output:

```

com.discursive.jccook.lang.builders.PoliticalCandidate@187aeca

[lastName=Jefferson,\firstName=Thomas,

dateOfBirth=Sat Apr 13 22:38:42 CST 1743,

moneyRaised=\293829292.930000007152557373046875,


state=\com.discursive.jccook.lang.builders.State@87816d

[abbreviation=VA,name=Virginia]]

```

As in other cases in this book, I've applied a minimal amount of formatting to the output so that it fits on the printed page. Your results will be the same in terms of content but will be all on one long line.

This is not the most readable piece of information in the world, but it *was* automatically generated. Keeping a `toString()` method up-to-date in an object model that contains one hundred entities is next to impossible under the constraints of a deadline and a budget. If your objects have meaningful `toString()` methods, it will be much easier to diagnose problems in your application. If you use the `ReflectionToStringBuilder`, you are assured that the message printed out will be accurate; the alternative is to have a message that may or may not be relevant-trusting developers to keep `toString()` methods updated manually.



This utility uses the class `AccessibleObject` in the J2SE reflection package to bypass access modifiers and access private member variables of an object directly. If your system is running under a restrictive `SecurityManager`, you may need to alter your configuration to allow Commons Lang to bypass these security restrictions. Only use this reflection builder if you are certain that your code will run in an environment without a restrictive security policy. I use this utility in a system that runs on a few servers in a known location, but if I were writing a reusable library, a reflection builder would not be feasible; if someone were to use my library in an environment with a different security policy, calling a `toString()` may cause problems. The relevant permission is the `suppressAccessChecks` permission target of the `java.lang.reflect.ReflectPermission` class.

Recipe 1.5 Customizing Generated toString() Content

Problem

You need to automate `toString()` while retaining control over the output, contents, and formatting.

Solution

In addition to the `ReflectionToStringBuilder`, Commons Lang provides for customization via the `ToStringBuilder` and `ToStringStyle` class. From the previous recipe, if you only want the `PoliticalCandidate` `toString()` method to print `lastName` and `firstName`, use the `ToStringBuilder` class and pass in a `ToStringStyle` object. The following example demonstrates a `toString()` method implementation that customizes both style and content:

```
import org.apache.commons.lang.builder.ToStringBuilder;

import org.apache.commons.lang.builder.ToStringStyle;

public String toString( ) {

    return new ToStringBuilder(this, ToStringStyle.MULTI_LINE_STYLE)

        .append("lastName", lastName)

        .append("firstName", firstName)

        .toString( );

}
```


Calling `toString()` on this object will produce the following output containing only the two properties specified as parameters to `append()`:

```
com.discursive.jccook.lang.builders.PoliticalCandidate@1cd2e5f[

    lastName=Jefferson

    firstName=Thomas
```


]



Unlike the output shown in [Recipe 1.4](#), this output is shown *exactly* as it appears on your screen.

Discussion

Generating `toString()` content using reflection saves time, but the trade-off is that the code using reflection prints out every member variable of a given class. What do you do when the desired behavior is to print out only a few selected variables from a given class? What if your objects are very *wide*, in that they have many properties that you don't want to print out in a `toString()` method? There are situations where an object could have a large number of properties or when a particular property of an object might contain a large amount of textual content. In these situations, it would be counterproductive to use `ReflectionToStringBuilder` to print out every member variable in a class.

Use a `ToStringBuilder` and customize the contents of the output with a static member of a `ToStringStyle`. The constructor of a `ToStringBuilder` takes an object instance and a `ToStringStyle`, returning an instance of a `ToStringBuilder`. This builder is then customized by calling `append()`, which lets you specify the properties you want included in the output. To customize the contents of a `ToStringBuilder`, you must manually add each property to an instance of a builder. The `append()` method accepts all primitives, objects, and arrays. [Table 1-1](#) summarizes the variations of `append()` for integer primitives and objects.

Table 1-1. Variations of ToStringBuilder append()

ToStringBuilder method	Description
<code>append(int value)</code>	Appends the value of the integer.
<code>append(String n, int value)</code>	Appends the value of the integer and the name of the property.
<code>append(Object value)</code>	Appends the <code>toString()</code> of an Object.
<code>append(String n, Object value)</code>	Appends the <code>toString()</code> of an Object and the name of the property.
<code>append(int[] array)</code> <code>append(Object[] array)</code>	Appends the formatted contents of array.
<code>append(String n int[] array)</code> <code>append(String n, Object[] array)</code>	Appends the property name and the size of an array
<code>append(String n, int[] array, boolean detail)</code>	Appends the property name and the full contents of an array.

The `ToStringStyle` class provides a mechanism to customize the output of a `ToStringBuilder`, and this class contains a few built-in styles. One example is the `ToStringStyle.MULTI_LINE_STYLE`, which puts a newline character between every property. Another example is the `ToStringStyle.SIMPLE_STYLE`, which simply prints the value of every member variable. The following list provides an example of each of these preset styles:

```
ToStringStyle.DEFAULT_STYLE
```

```
com.discursive.jccook.lang.builders.
```

```
PoliticalCandidate@1cd2e5f[lastName=Jefferson,firstName=Thomas]
```

```
ToStringStyle.MULTI_LINE_STYLE
```

```
com.discursive.jccook.lang.builders.PoliticalCandidate@1cd2e5f[
```

```
    lastName=Jefferson
```

```
    firstName=Thomas
```

```
]
```

```
ToStringStyle.NO_FIELD_NAMES_STYLE
```

```
com.discursive.jccook.lang.builders.PoliticalCandidate@1cd2e5f[Jefferson,Thomas]
```

```
ToStringStyle.SIMPLE_STYLE
```

```
Jefferson,Thomas
```

What's the big deal about `toString()` methods? This is about accuracy and keeping messages relevant in an evolving system. All useful error messages include a string representation of the object involved in the error. If you get an exception, and you print the value of an object, it is usually clear what is causing that exception. In the absence of sensible logging, it is next to impossible to debug a system without diving directly into a debugger. This is especially true if you are trying to diagnose the cause of an infrequent problem that only affects a tiny percentage of users who only encounter a problem if they perform a very specific action in a specific context. In these cases, it is helpful to know the internal state of every object involved in the error, and `toString()` is the easiest way to print this out to a log. Automate your `toString()` method, and your error messages will be more meaningful.

Recipe 1.6 Automating hashCode() and equals()

Problem

You need a way to automatically implement `equals()` and `hashCode()` methods.

Solution

Commons Lang `EqualsBuilder` and `HashCodeBuilder` provide methods to automate both the `equals()` and `hashCode()`. [Example 1-2](#) briefly demonstrates these two builders using the `PoliticalCandidate` bean from the previous two recipes.

Example 1-2. Automating hashCode() and equals()

```
import org.apache.commons.lang.builder.HashCodeBuilder;

import org.apache.commons.lang.builder.EqualsBuilder;

public class PoliticalCandidate {

    // Member variables - omitted for brevity

    // Constructors - omitted for brevity

    // get/set methods - omitted for brevity

    // A hashCode which creates a hash from the two unique identifiers

    public int hashCode( ) {

        return new HashCodeBuilder(17, 37)
```



```
        .append(firstName)

        .append(lastName).hashCode( );

    }

    // An equals which compares two unique identifiers

    public boolean equals(Object o) {

        boolean equals = false;

        if ( o != null &&

            PoliticalCandidate.class.isAssignableFrom(o) ) {

            PoliticalCandidate pc = (PoliticalCandidate) o;

            equals = (new EqualsBuilder( )

                .append(firstName, ps.firstName)

                .append(lastName, ps.lastName)).isEquals( );

        }

        return equals;

    }

}
```

Discussion

`HashCodeBuilder` has a constructor that takes two integer primitives. These primitives are used as an offset when creating a hash code; both numbers should be odd, nonzero, and prime. The `HashCodeBuilder` in [Example 1-2](#) is configured to use the `firstName` and the `lastName` of the `PoliticalCandidate` object; therefore, two `PoliticalCandidate` objects with the same first and last name will have identical hash codes. If a hash code depends on every field in a class, you may use reflection to generate a hash code:

```
public int hashCode( ) {

    return HashCodeBuilder.reflectionHashCode(this);

}
```

Like `ToStringBuilder` and `HashCodeBuilder`, the `EqualsBuilder` is also configured via an `append()` method, which takes two arguments to compare. `EqualsBuilder`'s `append()` method accepts all primitives, objects, and arrays, and one advantage of `EqualsBuilder` is the ability to compare two arrays by simply passing them to `append()`. When this happens, `EqualsBuilder` compares every element of an array:

```
int[] array1 = new int[] { 1, 3, 4, 2, 5, 3, 4, 5, 3, 4 };

int[] array2 = new int[] { 1, 3, 4, 2, 5, 3, 4, 5, 3, 4 };

int[] array3 = new int[] { 3, 3, 3, 3, 3, 3, 3, 3, 3, 3 };

EqualsBuilder builder = new EqualsBuilder( );

builder.append( array1, array2 );

boolean firstTwoEqual = builder.isEquals( );

System.out.println( "Is array1 equal to array2? " + firstTwoEqual );

EqualsBuilder builder = new EqualsBuilder( );

builder.append( array2, array3 );

boolean lastTwoEqual = builder.isEquals( );

System.out.println( "Is array2 equal to array3? " + lastTwoEqual );
```

The `EqualsBuilder` compares the contents of two arrays, checking to see that the corresponding element is equal. The following output is produced:

```
Is array1 equal to array2? true

Is array2 equal to array3? false
```

If two classes are equal only if every field is equal, the `EqualsBuilder` can compare two objects using reflection as in the following code:

```
public boolean equals(Object o) {

    return EqualsBuilder.reflectionEquals(this, o);

}
```



Be careful when using reflection to automate `hashCode()` and `equals()`, you may get more than you bargained for. In [Example 1-2](#), a candidate is uniquely identified by first and last name; if this bean were mapped to a table in a relational database, `firstName` and `lastName` would be a composite key identifying each unique row. A `HashMap` or `HashSet` is similar to a database table in that the identifier is defined by the fields used by `hashCode()` and `equals()`; putting an equal object with the same hash code into a `HashMap` replaces the previous entry. A poorly implemented `hashCode()` or `equals()` can have unintended consequences when storing objects in such a data structure. In other words, `equals()` and `hashCode()` should be based off of the properties that uniquely identify a class. This being the case, the `equals()` function should return true if two `PoliticalCandidate` objects have identical first and last names, and the hash code for two equal objects should be identical. The `hashCode()` and `equals()` in [Example 1-2](#) are written to only take into account the `firstName` and `lastName` properties.

Recipe 1.7 Automating compareTo()

Problem

You need a quick way to implement `compareTo()` methods.

Solution

Commons Lang `CompareToBuilder` provides a builder for `compareTo()` methods. `CompareToBuilder` can perform a comparison via reflection, or a comparison can be customized by passing parameters to an instance of `CompareToBuilder`. The following example demonstrates the use of the reflection builder to implement a `compareTo()` method. This implementation compares all nonstatic and nontransient member variables in both classes.

```
import org.apache.commons.lang.builder.CompareToBuilder;

// Build a compareTo function from reflection

public int compareTo(Object o) {

    return CompareToBuilder.reflectionCompare(this, obj);

}
```

Discussion

`CompareToBuilder.reflectionCompare()` takes two objects and compares the non-static, nontransient member variables of these objects. In [Example 1-2](#), the comparison involves the name properties of two `PoliticalCandidate` objects from [Example 1-3](#), which are considered equal if both `firstName` and `lastName` are equal. `reflectionCompare()` ignores static fields and transients; therefore, in [Example 1-3](#), `averageAge` and `fullName` do not contribute to the automated comparison.

Example 1-3. Implementing compareTo() using a reflection builder

```
public class PoliticalCandidate {
```



```

        // Static variable

        private static String averageAge;

        // Member variables

        private String firstName;

        private String lastName;

        private transient String fullName;

        // Constructors

        // get/set methods

        // Build a compareTo function from reflection

        public int compareTo(Object o) {

            return CompareToBuilder.reflectionCompare(this, obj);

        }

    }

```

In addition to a comparison by reflection, the `CompareToBuilder` can be configured to compare two objects by a set of variables in a particular order. The order of comparisons plays a key role when a comparison involves multiple member variables; this order is not specified when using the `reflectionCompare()` method. Assume that the default sorting behavior for `PoliticalCandidate` objects should be `lastName` and then `firstName`; if two objects have the same `lastName`, then sort by the `firstName`. The following example demonstrates a customization of the `compareTo()` method.

Calling `append()` specifies what variables will be compared and in what order they will be compared. The order of the calls to `append()` are backward-similar to pushing an object onto the top of a stack. The last property "pushed" onto the `CompareToBuilder` is the first property to be compared. Objects are compared by last name, and first name is used as a "tiebreaker." [Example 1-4](#) will compare two `PoliticalCandidate` objects by `lastName`, falling back to `firstName` only if the `lastName` values were equal.

Example 1-4. Customizing a `compareTo()` method with `CompareToBuilder`

```
// A compare to that mimics the behavior of equals( )

public int compareTo(Object o) {

    int compare = -1; // By default return less-than

    if( o != null &&

        PoliticalCandidate.class.isAssignableFrom( o.getClass( ) ) ) {

        PoliticalCandidate pc = (PoliticalCandidate) o;

        compare = (new CompareToBuilder( )

            .append(firstName, pc.firstName)

            .append(lastName, pc.lastName)).toComparison( );

    }

    return compare;

}
```

Remember to keep the behavior of `equals()` and `compareTo()` consistent to avoid problems when sorting collections. Automating the `compareTo()` method via reflection may not compare objects in a way that is consistent with `equals()`.

See Also

`compareTo()` methods provide the natural sorting order for a set of objects, and they are frequently used when sorting a collection of JavaBeans®. If you are trying to sort a collection of beans, you are better off using the `BeanComparator`, which is described in [Recipe 3.10](#).

Instead of capturing comparison logic in a `compareTo()` method, consider using a `Comparator` object. The Jakarta Commons Collections project contains a number of supplements to the `Comparator` interface, such as utilities to reverse and chain comparators. `Comparator` utilities are discussed in [Chapter 4](#).



Recipe 1.8 Printing an Array

Problem

You need to print the contents of an array.

Solution

Use `ArrayUtils.toString()` to print the contents of an array. This method takes any array as an argument and prints out the contents delimited by commas and surrounded by brackets:

```
int[] intArray = new int[] { 2, 3, 4, 5, 6 };
```

```
int[] multiDimension = new int[][] { { 1, 2, 3 }, { 2, 3 }, {5, 6, 7} };
```

```
System.out.println( "intArray: " + ArrayUtils.toString( intArray ) );
```

```
System.out.println( "multiDimension: " + ArrayUtils.  
toString( multiDimension ) );
```

This example takes two arrays and prints them out using `ArrayUtils.toString()`:

```
intArray: {2,3,4,5,6}
```

```
multiDimension: {{1,2,3},{2,3},{5,6,7}}
```

Discussion

This simple utility can be used to print the contents of an `Object[]`, substituting an object for a `null` element:

```
String[] strings = new String[] { "Blue", "Green", null, "Yellow" };
```

```
System.out.println( "Strings: " + ArrayUtils.toString( strings, "Unknown" ) );
```

This example prints the `strings` array, and when `ArrayUtils` encounters a `null` element, it will print out "Unknown":

```
Strings: {Blue,Green,Unknown,Yellow}
```

This utility comes in handy when you need to print the contents of a `Collection` for debugging purposes. If you need to print out the contents of a `Collection`, convert it to an array, and pass that array to `ArrayUtils.toString()`:

```
List list = new ArrayList( );
```

```
list.add( "Foo" );
```

```
list.add( "Blah" );
```

```
System.out.println( ArrayUtils.toString( list.toArray( ) ) );
```




Recipe 1.9 Cloning and Reversing Arrays

Problem

You need to reverse and clone the contents of an array.

Solution

Use `ArrayUtils.clone()` and `ArrayUtils.reverse()` methods from Commons Lang. [Example 1-5](#) demonstrates the reversal and cloning of a primitive array full of `long` primitives.

Example 1-5. Cloning and reversing a primitive array with ArrayUtils

```
import org.apache.commons.lang.ArrayUtils;

long[] array = { 1, 3, 2, 3, 5, 6 };

long[] reversed = ArrayUtils.clone( array );

ArrayUtils.reverse( reversed );

System.out.println( "Original: " + ArrayUtils.toString( array ) );

System.out.println( "Reversed: " + ArrayUtils.toString( reversed ) );
```

The `array` is cloned and reversed, and the contents of the original and the reversed array are displayed as output using `ArrayUtils.toString()`:

```
Original: { 1, 3, 2, 3, 5, 6 }

Reversed: { 6, 5, 3, 2, 3, 1 }
```

Discussion

In [Example 1-5](#), `clone()` returns a reference to a new array, and `reverse()` operates on the array reference supplied as a parameter. It is important to realize that while `clone()` leaves the original array alone, `reverse()` operates directly on the supplied array. In addition to supporting all primitive arrays, `ArrayUtils.clone()` and `ArrayUtils.reverse()` work with object arrays. If `array` had been an array of `Long` objects, the code would bear a striking resemblance to the previous example.

The only difference between Examples [Example 1-6](#) and [Example 1-5](#) is the type of array being cloned and reversed. Again, `ArrayUtils.toString()` is used to print out the contents of both the original and the reverse array:

```
Original: { 3, 56, 233 }
```

```
Reversed: { 233, 56, 3 }
```

Example 1-6. Cloning and reversing an `Object[]` with `ArrayUtils`

```
Long[] array = new Long[] { new Long(3), new Long(56), new Long(233) };
```

```
Long[] reversed = ArrayUtils.clone( array );
```

```
ArrayUtils.reverse( reversed );
```

```
System.out.println( "Original: " + ArrayUtils.toString( array ) );
```

```
System.out.println( "Reversed: " + ArrayUtils.toString( reversed ) );
```

Without the aid of `ArrayUtils.clone()` and `ArrayUtils.reverse()`, this task would have involved writing a loop to populate a reversed array. The following code completes the same task, but, in order to reverse an array, this example assigns the values from the original array in reverse; elements are inserted starting at `reversed[reversed.length - 1]` and ending at `reversed[0]`:

```
// readTemps returns a 1000 member double[]
```

```
double[] temperature = readTemps( );
```

```
double[] reversed = new double[temperature.length];
```

```
for( int i = 0; i < temperature.length; i++ ) {
```

```
    reversed[reversed.length - (i+1)] = temperature[i];
```

```
}
```

Another option is the use of the `Collections.reverse()` method. J2SE contains a `Collections`

object with a static `reverse()` method, but this only operates on a `List` object. If you had an array of `double` primitives, and you wanted to take advantage of the `Collections` class, you would need to convert your double array to a list. Without Java 1.5's autoboxing feature, a `double[]` will need to be translated into a `Double[]` before elements can be used to populate a list:

```
double[] temps = readTemps( );

List tempList = new ArrayList( );

for( int i = 0; i < temps.length; i++ ) {

    tempList.add( new Double[temps[i]] );

}

Collections.reverse( tempList );

double[] reversed = new double( tempList.size( ) );

Iterator i = tempList.iterator( );

int index = 0;

while( i.hasNext( ) ) {

    reversed[index] = ((Double) i.next( )).doubleValue( );

    index++;

}
```

That nasty translation between a `double` array and a list of `Double` objects complicates your code. The next recipe will touch upon an easier method for performing this translation.

Is `ArrayUtils.clone()` really necessary? All arrays have a `clone()` method, and all Java arrays implement `Cloneable` and `Serializable`, but I would be surprised if many Java developers have read the relevant section of the Java Language Specification (JLS), which discusses Array Members (section 10.7). All arrays can be cloned by calling the `clone()` method:

```
long[] temps = readTemps( );

long[] cloned = (long[]) temps.clone( );
```

`ArrayUtils.clone()` doesn't provide you with any performance benefits, it doesn't necessarily

improve your code, and one could debate the assertion that it makes for more readable code. But, mainly, it exists as a safe way to handle `null` array references. If you attempt to clone a `null` reference, this utility will return a `null` instead of throwing a runtime exception.



Recipe 1.10 Transforming Between Object Arrays and Primitive Arrays

Problem

You need a way to convert an object array to a primitive array.

Solution

Use `ArrayUtils.toObject()` and `ArrayUtils.toPrimitive()` to translate between primitive arrays and object arrays. The following example demonstrates the translation from a primitive array to an object array and vice versa:

```
import org.apache.commons.lang.ArrayUtils;

long[] primitiveArray = new long[] { 12, 100, 2929, 3323 };

Long[] objectArray = ArrayUtils.toObject( primitiveArray );

Double[] doubleObjects = new Double[] { new Double( 3.22, 5.222, 3.221 ) };

double[] doublePrimitives = ArrayUtils.toPrimitive( doubleObject );
```

The result from both translations is an array of equal length and equal contents. The first translation takes a `long[]` and translates the array to a `Long[]`, and the second translation takes a `Double[]` and turns it into a `double[]`.

Discussion

Assume that the following example uses an external library that expects a list of `Double` objects. The existing system uses an array of double primitives, and you need to "step up" from a primitive array to an object array in order to pass a parameter to the `complexCalculation()` method:

```
// Assume that temps is a 4000 element double[]
```

```
double[] temps = readTemps( );

// Turn the double[] into an array of Double objects
Double[] objectArray = ArrayUtils.toObject( temps );

List inputList = Arrays.asList( objectArray );

// Assume that some process returns results as a List of Double
// objects
List outputList = externalLib.complexCalculation( inputList );

// Transform this List of doubles to an array of double primitives
Double[] resultObjArray =

    (Double[]) outputList.toArray( new Double[0] );

double[] result =

    ArrayUtils.toPrimitive( resultObjArray, Double.NaN );
```

The primitive array, `temps`, is transformed to an object array using `ArrayUtils.toObject()`, and the results of our calculation are translated from a list to an array of primitives using `ArrayUtils.toPrimitive()`. While an object array can contain a `null` element, a primitive array cannot; the second argument to `ArrayUtils.toPrimitive()` specifies a double value to be used if there is a `null` in the object array. In this example, `null` values in the object array are stored as `Double.NaN` in our primitive array. The second argument to `ArrayUtils.toPrimitive()` is optional; if it is not present and a `null` value is present in the object array, a `NullPointerException` is thrown.

`ArrayUtils` offers various static methods to transform between primitive and object arrays. Tables [Table 1-2](#) and [Table 1-3](#) summarize both the `toObject()` and `toPrimitive()` methods.

Table 1-2. The various flavors of `ArrayUtils.toObject()`

Return type	Method signature
Boolean[]	ArrayUtils.toObject(boolean[] array)
Byte[]	ArrayUtils.toObject(byte[] array)
Double[]	ArrayUtils.toObject(double[] array)
Float[]	ArrayUtils.toObject(float[] array)
Integer[]	ArrayUtils.toObject(int[] array)
Short[]	ArrayUtils.toObject(short[] array)
Long[]	ArrayUtils.toObject(long[] array)

Table 1-3. The various flavors of ArrayUtils.toPrimitive()

Return type	Method signature
Boolean[]	ArrayUtils.toPrimitive(boolean[] array)
Byte[]	ArrayUtils.toPrimitive(byte[] array)
Double[]	ArrayUtils.toPrimitive(double[] array)
Float[]	ArrayUtils.toPrimitive(float[] array)
Integer[]	ArrayUtils.toPrimitive(integer[] array)
Short[]	ArrayUtils.toPrimitive(short[] array)
Long[]	ArrayUtils.toPrimitive(long[] array)

See Also

Java 1.5 has added a feature called autoboxing, which provides for automatic conversions between primitives and objects. For more information about autoboxing, see <http://www.jcp.org/aboutJava/communityprocess/jsr/tiger/autoboxing.html>.



Recipe 1.11 Finding Items in an Array

Problem

You need to test an array to see if it contains an element. If the array contains the element, you need the index of the matching element.

Solution

Use `ArrayUtils.contains()` to see if an array contains a specified element, and use `ArrayUtils.indexOf()` or `ArrayUtils.lastIndexOf()` to find the position of a matching element. The following example demonstrates the use of these three methods:

```
import org.apache.commons.lang.ArrayUtils;

String[] stringArray = { "Red", "Orange", "Blue", "Brown", "Red" };

boolean containsBlue = ArrayUtils.contains( stringArray, "Blue" );

int indexOfRed = ArrayUtils.indexOf( stringArray, "Red");

int lastIndexOfRed = ArrayUtils.lastIndexOf( string, "Red" );

System.out.println( "Array contains 'Blue'? " + containsBlue );

System.out.println( "Index of 'Red'? " + indexOfRed );

System.out.println( "Last Index of 'Red'? " + lastIndexOfRed );
```

This example locates strings in a string array and produces the following output:

```
Array contains 'Blue'? true

Index of 'Red'? 0

Last Index of 'Red'? 4
```


Discussion

All three methods work with an object array or any primitive array; in fact, almost every method defined in `ArrayUtils` can be applied to every possible array type- `boolean[]`, `byte[]`, `char[]`, `double[]`, `float[]`, `long[]`, `short[]`, and `Object[]`. When using a primitive array, `ArrayUtils` compares the value in question to each element of an array until a match is found. When using an object array, `ArrayUtils` calls the `equals()` method to check for a matching array element.

`ArrayUtils.indexOf()` and `ArrayUtils.lastIndexOf()` take an optional third parameter that controls where an element search begins. In the next example, you are searching an array of double primitives for the value -9999. [Example 1-7](#) demonstrates how to establish that the value is contained within an array and how to locate the index for each matching element.

Example 1-7. Searching an array using `ArrayUtils.contains()` and `ArrayUtils.indexOf()`

```
// temps is a 1000 element long[]

long[] temps = readTemps( );

// Check to see if the array contains -9999

boolean hasErrorFlag = ArrayUtils.contains( temperature, -9999 );

// Print out the index of every errored reading

int start = 0;

while( hasErrorFlag &&
        (ArrayUtils.indexOf(temperature, -9999, start) != -1) ) {
    int errorIdx = ArrayUtils.indexOf(temperature, -9999, start);
    System.out.println( "Error reading at index: " + errorIdx );
    start = errorIdx + 1;
}
```

You could easily implement this method yourself; `ArrayUtils.contains()` and `ArrayUtils.indexOf()` are simply methods that iterate through every element of an array and test for equality. The simple savings you gain from `ArrayUtils` is one less `for` loop you have to test and

maintain:

```
long testValue = -9999;

boolean hasErrors = false;

for( int i = 0; i < temps.length; i++ ) {

    if( temps[i] == testValue ) {

        hasErrors = true;

    }

}
```

The benefits are small, but maintaining your own custom utility classes is a pain-it is just another thing to test and maintain. `ArrayUtils` isn't going to change your application's architecture, but it will ultimately reduce the amount of trivial code you have to write, and you will not have to expend energy maintaining or testing trivial code.

See Also

[Chapter 4](#) contains a number of recipes dealing with `Predicate` objects and filtering collections. Instead of using the three methods defined in this recipe, you can put objects into a collection and count or select the elements that match an `EqualPredicate`. See [Chapter 4](#) for more information about querying collections with predicates.



Recipe 1.12 Creating a Map from a Multidimensional Array

Problem

You need to create a `Map` from a multidimensional array.

Solution

Use `ArrayUtils.toMap()` to create a `Map` from a two-dimensional array (`Object[][]`). [Example 1-8](#) demonstrates the creation of such a `Map`. [Example 1-8](#) takes an `Object[][]` representing atomic symbols and atomic weights and turns it into a `Map` retrieving the atomic weight for hydrogen.

Example 1-8. Creating a Map from an `Object[][]`

```
import org.apache.commons.lang.ArrayUtils;

Object[] weightArray =

    new Object[][] { { "H" , new Double( 1.007)},
                     { "He", new Double( 4.002)},
                     { "Li", new Double( 6.941)},
                     { "Be", new Double( 9.012)},
                     { "B" , new Double(10.811)},
                     { "C" , new Double(12.010)},
                     { "N" , new Double(14.007)},
                     { "O" , new Double(15.999)},
                     { "F" , new Double(18.998)},
                     { "Ne", new Double(20.180)} };
```

```
// Create a Map mapping colors.  
  
Map weights = ArrayUtils.toMap( weightArray );  
  
  
Double hydrogenWeight = map.get( "H" );
```

Discussion

Instead of calling `weights.put()` for each entry in the `Map`, an `Object[][]` is created and then passed to `ArrayUtils.toMap()`. The `toMap()` method then extracts the first item in each array as the key and the second item as the value. This is a simple way to quickly create a `Map` in a piece of code; the alternative to using `ArrayUtils.toMap()` is to simply create a `Map` and repeatedly call the `put()` method.

See Also

In the previous example, `Double` objects are added to a `Map`, and values are retrieved from the `Map` using `get()`. Commons Collections contains utility methods for retrieving `Double` objects as `double` primitives; `MapUtils.getDouble()` retrieves an object from a `Map`, casts it to a `Number`, and calls `doubleValue()` using the default value supplied if there is no corresponding key in the `Map`. See [Recipe 5.21](#) for more information about `MapUtils.getDouble()`.

Recipe 1.13 Formatting Dates

Problem

You need to format a date, and `SimpleDateFormat` is not thread-safe. You are also looking for standard International Organization of Standards (ISO) date formats.

Solution

Use `FastDateFormat`, a thread-safe formatter for Java `Date` objects, and use public static instances of `FastDateFormat` on `DateFormatUtils`, which correspond to ISO date and time formatting standards defined in ISO 8601. The following example outputs the international standard for representing a date and time in a given time zone:

```
Date now = new Date( );

String isoDT = DateFormatUtils.ISO_DATETIME_TIME_ZONE_FORMAT.format( now );

System.out.println( "It is currently: " + isoDT );
```

This produces the following output displaying the current time with time-zone information:

```
It is currently: 2004-03-26T16:20:00-07:00
```

If you need to use a custom date format, use `FastDateFormat` as a substitute for `SimpleDateFormat`:

```
// create a formatter that simply prints the year and month

FastDateFormat formatter =

    new FastDateFormat( "yyyy-mm",

        TimeZone.getDefault( ),

        Locale.getDefault( ) );
```

```
String output = formatter.format( new Date( ) );

// output equals "2003-10"
```

Discussion

The problem for this recipe is two-fold; your multithreaded application needs to print out standard date/time formats. Printing a standard format is a problem easily solved by static instances of `FastDateFormat` on `DateFormatUtils`. Ideally, every program that needs to deal with dates knows how to recognize an ISO 8601 date when parsing input. The world is getting smaller by the day; use international standards when presenting dates, times, measures, and country codes.

`SimpleDateFormat` is incapable of producing an ISO-8601-compliant time zone that matches the pattern: `+11:30`. Sun's `SimpleDateFormat` class can generate time zones without the colon separator, but these are incompatible with systems that need to be able to parse a standard format. `FastDateFormat` has achieved compliance with the ISO 8601 standard by adding a "ZZ" date format symbol, which is translated into the appropriate time-zone representation. In addition to the format demonstrated in the previous example, the `DateFormatUtils` class maintains a number of variations on the full ISO 8601 date format; there is a format to show only the time, a format to show only the date, and others, as well as the standard format for displaying dates in Simple Mail Transfer Protocol (SMTP). (See [Table 1-4](#).)

Table 1-4. Static date/time formats in `DateFormatUtils`

Name	Format
ISO_DATE_FORMAT	yyyy-MM-dd"2004-01-02"
ISO_DATE_TIME_ZONE_FORMAT	yyyy-MM-ddZZ"2004-01-02-07:00"
ISO_DATETIME_FORMAT	yyyy-MM-dd'T'HH:mm:ss"2004-01-02T23:22:12"
ISO_DATETIME_TIME_ZONE_FORMAT	yyyy-MM-dd'T'HH:mm:ssZZ"2004-01-02T21:13:45-07:00"
ISO_TIME_FORMAT	'T'HH:mm:ss"T04:23:22"
ISO_TIME_NO_T_FORMAT	HH:mm:ss"05:12:34"
ISO_TIME_NO_T_TIME_ZONE_FORMAT	HH:mm:ssZZ"12:32:22-07:00"
ISO_TIME_TIME_ZONE_FORMAT	'T'HH:mm:ssZZ"T18:23:22-07:00"
SMTP_DATETIME_FORMAT	EEE, dd MMM yyyy HH:mm:ss Z"Wed, 01 Feb 2004 20:03:01 CST"

Why would you want to use `FastDateFormat` in the same way `SimpleDateFormat` is used? Isn't `SimpleDateFormat` enough? The simple answer is no; `SimpleDateFormat` is *not* thread-safe and `FastDateFormat` is. In fact, you should be aware that none of the Sun formatting classes are thread-safe. If multiple threads are using any Java formatting object there is a possibility of deadlock,

`RuntimeException`, or inconsistent behavior. If your systems use a shared instance `SimpleDateFormat` across multiple threads, you should migrate to `FastDateFormat` immediately.

See Also

Java date and time classes have a number of issues-concurrency issues with date formatting being "only the tip of the iceberg." An active member of the Jakarta Commons Community, Stephen Colebourne, has taken time to create a clean room reimplementation of a date and time API. For more information about Joda, take a look at the Joda project page (<http://www.joda.org/>).

For more information about the ISO date and time standards, see <http://www.cl.cam.ac.uk/~mgk25/iso-time.html>.

For more information about nonthread-safe implementations of `SimpleDateFormat`, see Sun's Bug Database, and look for Bug #4264153. Sun specifically states that all of the format classes `Format`, `MessageFormat`, `NumberFormat`, `DecimalFormat`, `ChoiceFormat`, `DateFormat`, and `SimpleDateFormat` are not thread-safe. It is unclear if Sun has addressed this issue in Java 1.4, but if you are writing critical multithreaded applications, you should avoid Sun's formatting classes or synchronize access to them.

Recipe 1.14 Rounding Date Objects

Problem

You need to round a date to the nearest second, minute, hour, day, month, or year.

Solution

Use `DateUtils` to round `Date` objects to the nearest `Calendar` field. `DateUtils.round()` can round to almost every `Calendar` field, including `Calendar.SECOND`, `Calendar.MINUTE`, `Calendar.HOUR`, `Calendar.DAY_OF_MONTH`, `Calendar.MONTH`, and `Calendar.YEAR`. The following example demonstrates the use of `DateUtils.round()`:

```
import org.apache.commons.lang.time.FastDateFormat;

import org.apache.commons.lang.time.DateFormatUtils;

import org.apache.commons.lang.time.DateUtils;

FastDateFormat dtFormat = DateFormatUtils.ISO_DATETIME_FORMAT;

Date now = new Date( );

Date nearestHour = DateUtils.round( now, Calendar.HOUR );

Date nearestDay = DateUtils.round( now, Calendar.DAY_OF_MONTH );

Date nearestYear = DateUtils.round( now, Calendar.YEAR );

System.out.println( "Now: " + dtFormat.format( now ) );

System.out.println( "Nearest Hour: " + dtFormat.format( nearestHour ) );

System.out.println( "Nearest Day: " + dtFormat.format( nearestDay ) );

System.out.println( "Nearest Year: " + dtFormat.format( nearestYear ) );
```


This example creates an object representing the current time and rounds this date to the nearest hour, day, and year. Assuming that the current date is March 28, 2004, and the current time is 1:48 P.M., this program creates the following output using the `FastDateFormat` class from the previous recipe:

```
Now: 2004-03-28T13:48:12

Nearest Hour: 2004-03-28T14:00:00

Nearest Day: 2004-03-29T00:00:00

Nearest Year: 2004-01-01T00:00:00
```

Discussion

If you are creating a system to record the time of an event, and you are not certain exactly when that event happened, it is appropriate to round that date and time to an approximate value. Are you certain that you woke up at 9:02 A.M., 23 seconds, and 879 milliseconds? Or, is it more likely that you remember that you woke up around 9 A.M.? It would be appropriate to round this time to the `Calendar.MINUTE` or `Calendar.HOUR` field at the very least—recording a general time, such as "around 9 A.M." In the following example, `DateUtils.round()` calculates an approximate time:

```
// Rounding to the nearest hour

Date wokeUp = new Date( );

Date wokeUpAround = DateUtils.round( now, Calendar.HOUR );
```

If your `wokeUp Date` object is 1:31 P.M., then `wokeUpAround` will be equal to 2:00 P.M. But, if you woke up at 1:15 P.M., your `wokeUpAround` object would then be rounded down to 1:00 P.M. When you round or truncate to a field, all of the date fields less significant than the specified field are set to zero. In this example, rounding to an hour causes the minutes, seconds, and milliseconds to be set to zero. Rounding a `Date` to a `Calendar.YEAR` sets the day of the year to one and the time to the first instance of the nearest year:

```
Date now = new Date( );

Date nearestYear = DateUtils.round( now, Calendar.YEAR );
```

This previous code rounds to the nearest year, and if `now` is 15 May 2004, the resulting `Date` will correspond to the first instance of 2004. Alternatively, if `now` is 15 July 2004, the resulting `Date` will be the first instance of 2005.

`DateUtils.round()` works with the following field values, listed in order of significance:

- `Calendar.MILLISECOND`

- `Calendar.SECOND`
- `Calendar.MINUTE`
- `Calendar.HOUR_OF_DAY` and `Calendar.HOUR`
- `Calendar.DATE`, `Calendar.DAY_OF_MONTH`, and `Calendar.AM_PM`
- `Calendar.MONTH`
- `DateUtils.SEMI_MONTH`
- `Calendar.YEAR`
- `Calendar.ERA`

`DateUtils` introduces a `DateUtils.SEMI_MONTH` field, which will cause dates to be rounded to the middle or beginning of a month. In `DateUtils`, the middle of the month is defined as the 15th day of the month with the second half of the month starting at midnight on the 16th day of the month:

```
Calendar cal = Calendar.getInstance( );

cal.set( 2004, Calendar.MARCH, 5, 10, 2, 2 );

System.out.println( DateUtils.round( cal.getTime( ) ,

DateUtils.SEMI_MONTH ) );
```

This code will print out *Mon Mar 01 00:00:00 CST 2004* as the 5th of March and is closer to the beginning of the month than it is to the middle of the month. If the `Calendar` object was March, 14th, 2004, and it had been rounded to a `DateUtils.SEMI_MONTH`, the rounded date would have been set to midnight on March 16th. One would think that the middle of March is the 15th? Isn't that date the famous Ides of March-the date on which Brutus betrayed Caesar? According to `DateUtils`, the first half of the month ends at 11:59 P.M. on the 15th of the month; the `DateUtils.round()` method returns the first instant of the beginning of the second half of March: *March 16 12:00:00.000 A.M.*

See Also

The more you work with Java's `Date` and `Calendar` object, the more you will curse the J2SE. If your frustration is boiling over, take a look at Joda. Joda contains an entire package devoted to date, time, and duration formatting, and it is not based on the `Date` or `Calendar` classes. For more information about Joda, take a look at the Joda project page at: <http://www.joda.org/>.

Recipe 1.15 Truncating Date Objects

Problem

You need to truncate a date to a calendar field.

Solution

Use `DateUtils.truncate()` to throw out all fields less significant than the specified field. When a `Date` is truncated to the `Calendar.MONTH` field, `DateUtils.truncate()` will return a `Date` object set to the first instance of the month. The day, hour, minute, second, and millisecond field will each contain the minimum possible value for that field. [Example 1-9](#) truncates a date at the month field and the hour field.

Example 1-9. Truncating a Date object at Calendar.MONTH

```
import org.apache.commons.lang.time.DateUtils;

import org.apache.commons.lang.time.FastDateFormat;

import org.apache.commons.lang.time.DateFormatUtils;

FastDateFormat dtFormat = DateFormatUtils.ISO_DATETIME_FORMAT;

Date now = new Date( );

Date truncatedMonth = DateUtils.truncate( now, Calendar.MONTH );

Date truncatedHour = DateUtils.truncate( now, Calendar.HOUR );

System.out.println( "Now: " + dtFormat.format( now ) );

System.out.println( "Truncated Month: "

                    + dtFormat.format( truncatedMonth ) );
```



```
System.out.println( "Truncated Hour: "
                    + dtFormat.format( truncatedHour ) );
```

Assuming that the current date is March 28, 2004, and the current time is 1:48 P.M., this example produces the following output:

```
Now: 2004-03-28T13:48:12
```

```
Truncated Month: 2004-03-01T00:00:00
```

```
Truncated Hour: 2004-03-28T13:00:00
```

Discussion

If you want to associate every event that happened between 2 P.M. and 3 P.M. with the 2 P.M. hour, or every event that happened in a particular year with the first instant of that year, you need to truncate a `Date` at a specified `Calendar` field. When a `Date` is truncated, it is rounded down; `DateUtils.truncate()` is the equivalent of `Math.floor()` for the `Date` class. If it is 4:02 P.M. on October 31, 1975, a `Date` object truncated at the `Calendar.HOUR` field will point to 4:00 P.M., and a `Date` truncated at the `Calendar.YEAR` field will point to the first millisecond of the first minute, of the first hour, of the first day of year 2005: *January 01 2005: 12:00:00.000 A.M.*

See Also

`DateUtils.truncate()` can also be used to truncate a date to the nearest `DateUtils.SEMI_MONTH`. [Recipe 1.14](#) discusses `DateUtils.SEMI_MONTH` in more detail.

Recipe 1.16 Creating an Enum

Problem

You need an Enum, but you are not using the new Java 1.5 release.

Solution

If you are stuck with Java 1.4 or lower, you can use Commons Lang `Enum`, `ValuedEnum`, and `EnumUtils` to create an enum "type," which approximates the new language feature. [Example 1-10](#) extends `Enum`, providing three flavors: `Flavor.CHOCOLATE`, `Flavor.VANILLA`, and `Flavor.STRAWBERRY`.

Example 1-10. Defining a Flavor enumeration by extending Enum

```
import java.util.*;

import org.apache.commons.lang.enum.Enum;

public final class Flavor extends Enum {

    public static Flavor CHOCOLATE = new Flavor( "Chocolate" );

    public static Flavor VANILLA = new Flavor( "Vanilla" );

    public static Flavor STRAWBERRY = new Flavor( "Strawberry" );

    private Flavor(String name, int value) { super( name, value ); }

    public static Flavor getEnum(String flavor) {

        return (Flavor) getEnum(Flavor.class, flavor);

    }

}
```

```
public static Map getEnumMap( ) {  
    return getEnumMap(Flavor.class);  
}  
  
public static List getEnumList( ) {  
    return getEnumList(Flavor.class);  
}  
  
public static Iterator iterator( ) {  
    return iterator(Flavor.class);  
}  
}
```

The key to an `Enum` is the private constructor; this guarantees that there are only three instances of `Flavor` in any virtual machine. This extension of `Enum` provides a number of useful utilities to get a `List` or `Map` of available `Flavor` instances:

```
// Using Flavor to create an ice cream cone  
  
IceCreamCone cone = new IceCreamCone( );  
  
cone.setScoops( 5 );  
  
cone.setFlavor( Flavor.VANILLA );  
  
cone.addTopping( "sprinkles" );  
  
  
List flavors = Flavor.getEnumList( );  
  
System.out.println( ArrayUtils.toString( flavors.toString( ) ) );  
  
// prints "{ Chocolate, Vanilla, Strawberry }"
```

Discussion

Assume that you are writing a system to classify choral singers by voice type: soprano, alto, tenor, and bass. Your database has a table `dbo.lu_VoicePart`, which contains a part name and a numeric part code. This voice part is a coded type; it needs both a name and a code, and a straightforward design is achieved by extending `ValuedEnum`. `ValuedEnum` is an `Enum` that keeps track of a numeric code for each instance of the enumeration. `PartEnum` extends `ValuedEnum` to store static instances of the four possible voice parts: soprano, alto, tenor, and bass. (See [Example 1-11](#).)

Example 1-11. Extending ValuedEnum to create an enum

```
import java.util.*;

import org.apache.commons.lang.enum.ValuedEnum;

public final class PartEnum extends ValuedEnum {

    public static int    SOPRANO_VAL = 1;

    public static int    ALTO_VAL = 2;

    public static int    TENOR_VAL = 3;

    public static int    BASS_VAL = 4;

    public static PartEnum SOPRANO = new PartsEnum( "Soprano", SOPRANO_VAL );

    public static PartEnum ALTO = new PartsEnum( "Alto", ALTO_VAL );

    public static PartEnum TENOR = new PartsEnum( "Tenor", TENOR_VAL );

    public static PartEnum BASS = new PartsEnum( "Bass", BASS_VAL );

    private PartsEnum(String name, int value) { super( name, value ); }

    public static PartEnum getEnum(String part) {

        return (PartEnum) getEnum(PartEnum.class, part);

    }

    public static PartEnum getEnum(int part) {
```

```
        return (PartEnum) getEnum(PartEnum.class, part);
    }

    public static Map getEnumMap( ) {
        return getEnumMap(PartEnum.class);
    }

    public static List getEnumList( ) {
        return getEnumList(PartEnum.class);
    }

    public static Iterator iterator( ) {
        return iterator(PartEnum.class);
    }
}
```

This class extends `ValuedEnum` and has a private constructor. This guarantees that the only instances of this enumeration will be defined in `PartEnum`; four instances of `PartEnum` are created as public static final constants, and a name is assigned to every part. (See [Example 1-12](#).)

Example 1-12. Vocalist bean with a PartEnum

```
public class Vocalist {

    private String name;

    private PartEnum part;

    public String getName( ) { return name; }

    public void setName(String name) { this.name = name; }
```



```

    public PartEnum getPart( ) { return part; }

    public void setPart(PartEnum part) { this.part = part; }

}

```

Checking for every voice part involves a call to `PartEnum.iterator()`, which obviates the need for an `if/else if` control statement to catch every single voice part:

```

Iterator parts = PartEnum.iterator( );

while( parts.hasNext( ) ) {

    PartEnum part = (PartEnum) parts.next( );

    if( part.equals( vocalist.getPart( ) ) ) {

        System.out.println( "Vocalist is a " + part.getValue( ) );

    }

}

```

This example did not include any reference to a specific voice part, but, if your code needs to reference a specific voice type, it can use the static constants in `PartEnum`- `PartEnum.SOPRANO`, `PartEnum.ALTO`, `PartEnum.TENOR`, and `PartEnum.BASS`. And, lastly, it is impossible to create a `Vocalist` object with an invalid voice part, as the part property must be one of the four static instances of `PartEnum` defined in a `PartEnum` or `null`.

Using Enum types becomes especially important if an object has multiple classifications. If you were creating an object to track a person, you could easily end up with two overlapping classifications. In [Example 1-13](#), both `jobStatus` and `gender` can be `UNKNOWN`, and the valid options for both `jobStatus` and `gender` are defined as public static `int` variables.

Example 1-13. Using public static final constants for category information

```

public class Person {

    public static final int STUDENT = -1;

    public static final int EMPLOYED = 0;

    public static final int UNEMPLOYED = 1;

    public static final int RETIRED = 2;

    public static final int UNKNOWN = 3;
}

```

```

    public static final int MALE = 0;

    public static final int FEMALE = 1;

    private int jobStatus;

    private int gender;

    public int getJobStatus( ) { return jobStatus; }

    public void setJobStatus(int jobStatus) { this.jobStatus = jobStatus; }

    public int getGender( ) { return gender; }

    public void setGender(int gender) { this.gender = gender; }

}

```

This class defines two properties-`jobStatus` and `gender`-and both correspond to codes stored in the database. This system needs to know; that `MALE`, `FEMALE`, and `UNKNOWN` are the valid values for the `gender` property; and `STUDENT`, `EMPLOYED`, `UNEMPLOYED`, `UNKNOWN`, and `RETIRED` all correspond to the `jobStatus` property. This class does not define which constants are related to which property. Is `UNKNOWN` a `gender` or a `jobStatus`? Some systems rename these static variables to reflect which properties they correspond to-`GENDER_MALE`, `GENDER_FEMALE`, and `GENDER_UNKNOWN` would clearly correspond to the `gender` property; and `JOB_STUDENT`, `JOB_EMPLOYED`, `JOB_UNEMPLOYED`, `JOB_UNKNOWN`, and `JOB_RETIRED` would correspond to the `jobStatus` property. This solution only draws a conceptual boundary in the mind of the programmer; no logical separation is achieved, and there is still no way to guarantee that a bean property will have a valid value. (See [Example 1-14](#).)

Example 1-14. Simplifying with ValueEnum

```

public class Person {

    private JobStatusEnum jobStatus;

    private GenderEnum gender;

    public JobStatusEnum getJobStatus( ) { return jobStatus; }

    public void setJobStatus(JobStatusEnum jobStatus) {

```

```
        this.jobStatus = jobStatus;
    }
}
```

```
public GenderEnum getGender( ) { return gender; }

public void setGender(GenderEnum gender) { this.gender = gender; }

}
```

The solution to this problem can be solved by extending `ValuedEnum` and getting rid of the confusing mish-mash of public static constants. If you find yourself frequently creating static variables to reflect categories or types, enums are the solution. And, if you haven't upgraded to Java 1.5, use Commons Lang `Enum` and `ValuedEnum`.

See Also

As mentioned previously, Java 1.5 (or Tiger) has a new language feature: enums. If you are using Java 1.5, see the "Java 1.5 in a Nutshell" article from Sun Microsystems at <http://java.sun.com/developer/technicalArticles/releases/j2se15/>.

Recipe 1.17 Generating Unique Numeric Identifiers

Problem

You need to generate numeric and alphanumeric identifiers.

Solution

Use `IdentifierUtils` to create an `IdentifierFactory` with both numeric and alphanumeric identifiers. [Example 1-15](#) demonstrates the use of a `LongIdentifierFactory` to create unique numeric identifiers.

Example 1-15. Using a `LongIdentifierFactory` to create unique numeric identifiers

```
import org.apache.commons.lang.util.IdentifierUtils;

import org.apache.commons.lang.util.LongIdentifierFactory;

LongIdentifierFactory idFactory = factory.longGenerator(false, 0);

System.out.print( "Identifiers: " );

for( int i = 0; i < 10; i++ ) {

    System.out.println( idFactory.nextLongIdentifier( ) + " " );

}
```

This code will create 10 unique numeric identifiers and print them out on one line, producing the following output:

```
Identifiers: 0 1 2 3 4 5 6 7 8 9
```


Discussion

If you need a unique alphanumeric identifier, create a `StringIdentifierFactory`. This factory is created by calling the `stringAlphanumericIdentifierFactory()` method, passing true if you want the factory to wrap when it reaches a maximum value. The second parameter to this method specifies the length of the alphanumeric identifier; in this case, a length of four is specified. (See [Example 1-16](#).)

Example 1-16. Using an IdentifierGenerator to create unique alphanumeric identifiers

```
import org.apache.commons.lang.util.IdentifierUtils;

import org.apache.commons.lang.util.StringIdentifierFactory;

StringIdentifierFactory idFactory =

    IdentifierUtils.stringAlphanumericIdentifierFactory(true, 4);

System.out.print( "Identifiers: " );

for( int i = 0; i < 10; i++ ) {

    System.out.println( idFactory.nextStringIdentifier( ) + " " );

}
```

This factory will create strings with four characters, which contain a base-36 representation of an integer that is incremented every time `nextStringIdentifier()` is called. The progression of alphanumeric identifiers follows this pattern:

```
0000, 0001, 0002, ... 000a, 000b, 000c, ... 000z, 0010, 0011, 0012,

... 001a, etc.
```

Once the identifier reaches the maximum value of "1111," it will wrap around to the start of the sequence. A factory that was not configured to wrap will throw an `IllegalStateException` when the maximum ID value has been reached.

If you do not feel like instantiating your own instance of a generator, `IdentifierUtils` contains static methods to access three static identifier factories: `LONG_IDENTIFIER_FACTORY`, `STRING_NUMERIC_IDENTIFIER_FACTORY`, and `STRING_ALPHANUMERIC_IDENTIFIER_FACTORY`. (See [Example 1-17](#).)

Example 1-17. Static generators on IdentifierUtils

```
import org.apache.commons.lang.util.IdentifierUtils;

// Returns a Long identifier.

Long longId = IdentifierUtils.nextLongIdentifier( );

// Returns a String numeric id.

String idNumber = IdentifierUtils.nextStringNumericIdentifier( );

// Returns a String alphanumeric id.

String idAlpha = IdentifierUtils.nextStringAlphanumericIdentifier( );
```

The `nextStringNumericIdentifier()` method returns a string that contains a number: "1," "2," "3," and so on. This static `STRING_ALPHANUMERIC_IDENTIFIER_FACTORY` is a wrapping alphanumeric generator that creates strings of length 15.

This recipe demonstrates the use of the identifier generation utilities available in Commons Lang. Ongoing development of `IdentifierUtils` and `IdentifierFactory` has moved to the Commons Id project in the Jakarta Commons Sandbox.

See Also

The examples in this recipe provide a simple mechanism to create unique identifiers within a single JVM; the problem of generating truly unique identifiers across multiple systems is a job for the Universal Unique Identifier (UUID). The nascent Commons Id project contains a few utilities for working with UUID values, but, at the time of writing, these utilities are not yet ready for a final release. If you would like to either generate or use a UUID in a Java program, you are encouraged to follow the development of Commons Id UUID utilities at <http://jakarta.apache.org/commons/sandbox/id>.

The J2SE contains a class that can create a unique identifier across every JVM: aVirtual Machine Identifier (VMID). For more information about this class, which is associated with remote method invocation (RMI), see the Javadoc at <http://java.sun.com/j2se/1.4.2/docs/api/java/rmi/dgc/VMID.html>.

Recipe 1.18 Validation of Method Parameters

Problem

You need to validate parameters passed to a method. You would prefer one line of code to test that a method parameter is valid.

Solution

Use `Validate` to check method parameters. `Validate` can check for empty or `null` parameters, as well as evaluate any logical conditions. [Example 1-18](#) demonstrates the use of `Validate` to perform a few simple validations.

Example 1-18. Using Validate to perform simple validations

```
import org.apache.commons.lang.Validate;

public doSomething( int param1, Object[] param2, Collection param3 ) {

    Validate.isTrue( param1 > 0, "param must be greater than zero" );

    Validate.notEmpty( param2, "param2 must not be empty" );

    Validate.notEmpty( param3, "param3 must not be empty" );

    Validate.noNullElements( param3, "param3 cannot contain null elements" );

    // do something complex and interesting

}
```

Discussion

Write finicky methods. Don't just work with any input, have some standards. Don't hang around with garbage or `nulls`-clean up your act, and use `Validate`. Methods in `Validate` throw an `IllegalArgumentException` if invalid parameters are encountered. `Validate.notEmpty()` will throw an exception if the parameter is `null` or empty, and `Validate.isTrue()` takes a logical expression that must evaluate to true. [Table 1-5](#) lists a number of static methods of `Validate`.

Table 1-5. Available static methods on `Validate`

Validate method	Description
<code>isTrue(boolean expr)</code>	Fails if expression evaluates to false
<code>isTrue(boolean expr, String msg)</code>	Same as above; constructs exception with a message
<code>noNullElements(Collection col)</code>	Fails if collection contains a null
<code>noNullElements(Object[] array)</code>	Fails if array contains a null
<code>notEmpty(Collection col)</code>	Fails if collection is empty
<code>notEmpty(Map map)</code>	Fails if map is empty
<code>notEmpty(Object[] array)</code>	Fails if array is empty
<code>notNull(Object obj)</code>	Fails if object is null

Well-written code tests input and parameters. Is the number within a given range? Has the user supplied an index that is out of bounds for this array? Unless you want your applications to break down and throw exceptions, make sure that you are not trying to access the 15th element of a 10-element array; your code should be skeptical of parameters and refuse to run if it doesn't get its way. In fragile systems, parameter validation is not a top priority; errors are dealt with as different application layers throw a potpourri of exceptions. Other, more unstable, systems will pass `null` all the way down the call stack until the lowest level blows up and spits back a `NullPointerException`-with a long-winded stack trace. Don't play around with `null`-avoid it, test your system exhaustively, and throw an `IllegalArgumentException`.

Consider the following method, which takes a latitude, longitude, and mode parameter. Both the latitude and longitude must fall within a valid range, and this method should throw an `IllegalArgumentException` if it encounters an unrealistic latitude, an unrealistic longitude, or an empty mode parameter. The `Validate` utility used in conjunction with a `DoubleRange` object can reduce the amount of code dedicated to range checking and method parameter validation. To test the validity of the coordinates, two constant `DoubleRange` objects are created outside of the method. `DoubleRange.includesDouble(double d)` returns true if the number falls within the defined range-if `x <= rangeMax && x >= rangeMin`. (See [Example 1-19](#).)

Example 1-19. Using the Validator and the DoubleRange to validate method parameters

```
public static final DoubleRange LAT_RANGE = new DoubleRange( -90.0, 90.0 );
```



```

public static final DoubleRange LON_RANGE = new DoubleRange( -180.0, 180.0 );

public double elevation( double latitude,

                        double longitude,

                        String mode ) {

    Validate.notEmpty( mode, "Mode cannot be empty or null" );

    Validate.isTrue( LAT_RANGE.includesDouble( latitude ),

                    "Lat not in range " + latRange, latitude );

    Validate.isTrue( LON_RANGE.includesDouble( longitude ),

                    "Lon not in range " + lonRange, longitude );

    double elevation = 0.0;

    // code to implement the elevation method

    return elevation;

}

```

It takes a fair amount of institutional discipline to make sure that a code base has a sufficient amount of validation, and it is surprising how often systems scale to thousands of lines without it. Systems without good internal validation and sanity checks are characterized by frequent occurrences of `NullPointerException` and `RuntimeException`. Throwing `RuntimeException` in the form of `IllegalArgumentException` might seem like an odd recipe for increasing overall stability. But, if you actively throw exceptions and test exhaustively, it will be less toil and trouble to identify and fix defects-your application will fail sooner, and you will have short stack traces and well-defined problems. Performing rigorous parameter validation alone will not create a stable system, but it is part of a larger equation, which involves unit testing and validation.

In addition to parameter validation, you should be writing unit tests that test this validation. If you write good unit tests using JUnit and then measure your test coverage with a tool like Clover or JCoverage, you can save yourself an amazing amount of grief fixing unanticipated defects. Your unit tests should be covering close to 100% of your code, and they should throw curveballs. Don't just test the expected situation-if your method takes a double, see what it does with `Double.POSITIVE_INFINITY`; and if your method takes an array, pass it a `null`. Test the unexpected; if you find that your method melts down with a `null`, check the parameter with `Validate`. 100% test coverage is not an unrealistic ideal; it will drive your validation code. More test coverage always leads to a higher level of system quality.

See Also

[Chapter 8](#) discusses `DoubleRange` and other utilities for capturing a range of numbers.

Chapters 4 to Chapter 7 of the *Java Extreme Programming Cookbook* by Eric Burke and Brian Coyner (O'Reilly) are great introductions to unit testing tools and concepts. Read this book for an introduction to JUnit, HttpUnit, mock objects, and the idea of unit testing. Think of `Validate` as a runtime test for a method; the methods on `Validate` are analogous to the `assert()` methods in JUnit's `TestCase` class.

If you are interested in measuring code coverage of unit tests, take some time to look at Clover from Cortex eBusiness. Cortex eBusiness offers a free license to Open Source projects, but if you are using the product in a commercial environment, it is around \$250. More information about Clover is available at <http://www.thecortex.net/clover/>. Other than Clover, there is another tool named JCoverage, which can also be used to measure test coverage. More information about JCoverage is available at <http://www.jcoverage.com/>. For more information about JUnit, go to <http://www.junit.org/>.

Recipe 1.19 Measuring Time

Problem

You need to determine how much time has elapsed during the execution of a block of code.

Solution

Use `StopWatch` to measure the time it

Chapter 2. Manipulating Text

[Introduction](#)

[Recipe 2.1. Setting Up StringUtils and WordUtils](#)

[Recipe 2.2. Checking for an Empty String](#)

[Recipe 2.3. Abbreviating Strings](#)

[Recipe 2.4. Splitting a String](#)

[Recipe 2.5. Finding Nested Strings](#)

[Recipe 2.6. Stripping and Trimming a String](#)

[Recipe 2.7. Chomping a String](#)

[Recipe 2.8. Creating an Emphasized Header](#)

[Recipe 2.9. Reversing a String](#)

[Recipe 2.10. Wrapping Words](#)

[Recipe 2.11. Testing the Contents of a String](#)

[Recipe 2.12. Measuring the Frequency of a String](#)

[Recipe 2.13. Parsing Formatted Strings](#)

[Recipe 2.14. Calculating String Difference](#)

[Recipe 2.15. Using Commons Codec](#)

[Recipe 2.16. Getting the Commons Codec Source Code](#)

[Recipe 2.17. Calculating Soundex](#)

Introduction

Parsing text fell out of fashion when Extensible Markup Language (XML) came to town. Java's text manipulation capabilities have only recently received some badly overdue attention, with the addition of regular expressions and numerous improvements in Java 1.5. Despite the improvements, using Java to manipulate plain text can inspire frustration. Hand a developer a fixed-length text file format to parse, and you will hear the groans-"Why can't we use something `modern' like XML? I don't want to parse text." And while parsing and manipulating text may not build you a sexy resume, there is still a need to work with text in any program. For every snazzy XML file format, there is a widely accepted text file format with fixed-length fields; and for every XML web service, a vendor sends a proprietary feed that must be parsed character by character. Text manipulation is a must, but the Java 2 Standard Edition (J2SE) leaves developers wanting for more convenient ways to slice, dice, chomp, and manipulate text. This chapter introduces some simple utilities, which fill a few of Java's many gaps.

The recipes in this chapter deal with a collection of static methods on two classes in Jakarta Commons Lang-`StringUtils` and `WordUtils`. Some of the methods on `StringUtils` have been made obsolete by changes introduced in Java 1.4 and Java 1.5, but, regardless, there are times when you will want to split a string without regular expressions. Using `StringUtils.chomp()` achieves more readable logic than writing the equivalent logic using the `String.indexOf()` and `String.substring()` methods. These recipes will not change the basic architecture of a system with new, groundbreaking technology, but they are valuable "shortcuts" whose benefits will add up over time. Simple solutions to common tasks will save minutes of coding and hours of maintenance in the long run. Over time, many grow so accustomed to the efficiencies gained with Commons Lang, they consider it an indispensable supplement to the Java language.

Read the recipes in this chapter, and take some time to read the Javadoc for `StringUtils` and `WordUtils`. These utility classes provide some common string operations missing in Java, and they are simple and well-documented. These utilities are so simple that, throughout this chapter, you will notice recipes without a Discussion or See Also section-it's just not needed! These simple recipes have relevance to all skill levels; even if you are an experienced developer, you may be surprised at what Commons Lang string manipulation has to offer.



Recipe 2.1 Setting Up StringUtils and WordUtils

Problem

You want the ability to use `StringUtils` and `WordUtils` to manipulate text.

Solution

To download the latest version of Commons Lang, refer to the steps outlined in [Recipe 1.1](#).

Discussion

This chapter focuses on a very small subset of the Commons Lang project- `StringUtils` and `WordUtils`. To use either `StringUtils` or `WordUtils` in a Java class, add the following lines to your import statements:

```
import org.apache.commons.lang.StringUtils;

import org.apache.commons.lang.WordUtils;
```

Recipes that use `StringUtils` and `WordUtils` in this chapter will omit these import statements in code fragments. When `StringUtils` or `WordUtils` appears in an example, assume that it has already been imported.

See Also

If you have questions about these utilities, join the Jakarta Commons User mailing list; see [Recipe 1.2](#). To download the source for Commons Lang, see [Recipe 1.3](#).



Recipe 2.2 Checking for an Empty String

Problem

You need to test for an empty or `null` string.

Solution

Use `StringUtils.isBlank()`. This method will return true if it is supplied with an empty, zero length, or whitespace-only string. This method gracefully handles a `null` input by returning true. The following example demonstrates `isBlank()` with four strings:

```
String test = "";

String test2 = "\n\n\t";

String test3 = null;

String test4 = "Test";


System.out.println( "test blank? " + StringUtils.isBlank( test ) );

System.out.println( "test2 blank? " + StringUtils.isBlank( test2 ) );

System.out.println( "test3 blank? " + StringUtils.isBlank( test3 ) );

System.out.println( "test4 blank? " + StringUtils.isBlank( test4 ) );
```

All four strings are tested, and the following output is produced:

```
test blank? true

test2 blank? true

test3 blank? true

test4 blank? false
```


Discussion

Checking for nonblank strings is just as easy; `StringUtils.isNotBlank()` will return the compliment of `isBlank()`. If a string is empty, contains only whitespace, or is `null`, the `StringUtils.isNotBlank()` method will return false. This method comes in handy when a process expects a certain string to have content, and it gracefully handles a `null` input by returning false:

```
String test = "\t\t";

String test2 = "Test";

System.out.println( "test is not blank? " + StringUtils.isNotBlank( test ) );

System.out.println( "test2 is not blank? " + StringUtils.isNotBlank( test2 ) );
```

This produces the following output, which shows that a string containing only whitespace is considered blank:

```
test is not blank? false

test2 is not blank? true
```

Another method to test for an empty string is to "trim" a string to `null` if it contains only whitespace, and then test to see if the trimmed result is `null`. Use `StringUtils.trimToNull()` to transform empty strings to `null`. This method handles a `null` parameter value by returning `null`.

```
String test1 = "\t";

String test2 = "Test";

String test3 = null;

System.out.println( "test1 trimToNull: " + StringUtils.trimToNull( test1 ) );

System.out.println( "test2 trimToNull: " + StringUtils.trimToNull( test2 ) );

System.out.println( "test3 trimToNull: " + StringUtils.trimToNull( test3 ) );
```

This produces the following output, which shows that a string containing only whitespace is trimmed to `null`:

```
test1 trimToNull: null

test2 trimToNull: Test
```



```
test3 trimToNull: null
```

These three methods are laughably simple, but they will serve to reduce the amount of complexity in a system that needs to test strings. Use the methods from this recipe to avoid writing code to test for a `null`, and check the length of a string:

```
if( variable != null &&
    variable.length( ) > 0 &&
    !variable.trim( ).equals("") ) {
    // Do something
}
```

The code above can be rewritten with one call to `StringUtils.isNotBlank()`:

```
if( StringUtils.isNotBlank( variable ) ) {
    // Do something
}
```

It is good practice to avoid using `null` whenever possible; code that uses `null` to signify emptiness or an error condition is harder to maintain and more likely to throw a nasty `NullPointerException`. Worse yet are methods that return a `null` whenever a problem occurs or an exception is thrown. While `trimToNull()` can accomplish the goal, it does increase the occurrence of `nulls` in code; use `isBlank()` and `isNotBlank()` to excise dangerous `nulls` from your code.



Recipe 2.3 Abbreviating Strings

Problem

You want to abbreviate a string.

Solution

Use `StringUtils.abbreviate()` . Supply the string to abbreviate, and the maximum allowed length for the abbreviation. The following example will abbreviate the supplied text messages to 10 characters:

```
String test = "This is a test of the abbreviation."
```

```
String test2 = "Test"
```

```
System.out.println( StringUtils.abbreviate( test, 10 ) );
```

```
System.out.println( StringUtils.abbreviate( test2, 10 ) );
```

Here is the output of two string abbreviations:

```
This is...
```

```
Test
```

Discussion

`StringUtils.abbreviate()` takes a string and abbreviates it, if necessary. When abbreviating to 20 characters, if the text is less than 20 characters, the method simply returns the original text. If the text is greater than 20 characters, the method displays 17 characters followed by three ellipses. Abbreviating a piece of text to 20 characters guarantees that the text will occupy 20 characters or less:

```
String message = "Who do you think you are?";
```

```
String abbrev = StringUtils.abbreviate( message, 20 );
```

```
String message2 = "Testing";

String abbrev2 = StringUtils.abbreviate( message, 40 );

System.out.println( "Subject: " + message );

System.out.println( "Subject2: " + messages2);
```

This simple example abbreviates the first message variable, `message`, to "Who do you think...?" The second message variable, `message2`, is not affected by the abbreviation because it is less than 40 characters long; `abbrev2` will equal the contents of `message2`.

`StringUtils.abbreviate()` can also abbreviate text at an offset within a string. If you are writing an application that searches for a given word and prints that word out in context, you can use the `StringUtils.abbreviate()` method to print the context in which a word appears:

```
String message = "There was a palpable sense that the rest of the world " +
    "might, one day, cease to exist. In the midst of the " +
    "confusion - the absence of firm ground - something would " +
    "fail to recover. The whole city is still, in a way, " +
    "holding it's breath, hoping the the worst has come and " +
    "gone.";

int index = message.indexOf( "ground" );

int offset = index - 20;

int width = 20 + message.length( );

String context = StringUtils.abbreviate(message, offset, width);

System.out.println( "The word 'ground' in context: " + context );
```

The output of this example is:

```
The word 'ground' in context: ... absence of firm ground, something would...
```

This code attempts to locate "ground." Once the index of the word has been located, an offset abbreviation is used to show the context of the word. The `offset` parameter tells `StringUtils.abbreviate()` to start at a specific index in the string. Once the index of "ground" has been found, an offset and a width are computed to print 20 characters before and after the word "ground."

If an offset is less than four, output will start from the beginning of a string. If the offset is greater than four, the first three characters will be ellipses.



If a width less than four is specified, `abbreviate()` will throw an `IllegalArgumentException`. A width less than four does not give the `abbreviate()` method enough room to print ellipses and content.



Recipe 2.4 Splitting a String

Problem

You want to split a string on a number of different character delimiters.

Solution

Use `StringUtils.split()`, and supply a series of characters to split upon. The following example demonstrates splitting strings of a comma and a space:

```
import org.apache.commons.lang.ArrayUtils;

String input = "Frantically oblong";

String input2 = "Pharmacy, basketball,funky";

String[] array1 = StringUtils.split( input, " ,", 2 );

String[] array2 = StringUtils.split( input2, " ,", 2 );

System.out.println( ArrayUtils.toString( array1 ) );

System.out.println( ArrayUtils.toString( array2 ) );
```

This produces the output:

```
{ "Frantically", "oblong" }

{ "Pharmacy", "basketball" }
```

Discussion

The `StringUtils.split()` function does not return empty strings for adjacent delimiters. A

number of different delimiters can be specified by passing in a string with a space and a comma. This last example limited the number of tokens returned by `split` with a third parameter to `StringUtils.split()`. The `input2` variable contains three possible tokens, but the `split` function only returns an array of two elements.

The most recent version of J2SE 1.4 has a `String.split()` method, but the lack of `split()` in previous versions was an annoyance. To split a string in the old days, one had to instantiate a `StringTokenizer`, and iterate through an `Enumeration` to get the components of a delimited string. Anyone who has programmed in Perl and then had to use the `StringTokenizer` class will tell you that programming without `split()` is time consuming and frustrating. If you are stuck with an older Java Development Kit (JDK), `StringUtils` adds a `split` function that returns an `Object` array. Keep this in mind when you question the need for `StringUtils.split()`; there are still applications and platforms that do not have a stable 1.4 virtual machine.

The J2SE 1.4 `String` class has a `split()` method, but it takes a regular expression. Regular expressions are exceedingly powerful tools, but, for some tasks, regular expressions are needlessly complex. One regular expression to match either a space character or a comma character is `[' ', ',']`. I'm sure there are a thousand other ways to match a space or a comma in a regular expression, but, in this example, you simply want to split a string on one of two characters:

```
String test = "One, Two Three, Four Five";

String[] tokens = test.split( "[ ' ', ',']" );

System.out.println( ArrayUtils.toString( tokens ) );
```

This example prints out the tokens array:

```
{ "One", "", "Two", "Three", "", "Four", "Five" }
```

The array the previous example returns has blanks; the `String.split()` method returns empty strings for adjacent delimiters. This example also uses a rather ugly regular expression involving brackets and single quotes. Don't get me wrong, regular expressions are a welcome addition in Java 1.4, but the same requirements can be satisfied using `StringUtils.split(" .")`-a simpler way to split a piece of text.

See Also

Note the use of `ArrayUtils.toString()` in the solution section. See [Chapter 1](#) for more information about `ArrayUtils` in Commons Lang.

Recipe 2.5 Finding Nested Strings

Problem

You want to locate strings nested within other strings.

Solution

Use `StringUtils.substringBetween()`. This method will return a string surrounded by two strings which are supplied as parameters. The following example demonstrates the use of this method to extract content from HTML:

```
String htmlContent = "<html>\n" +  
    "  
    <head>\n" +  
    "  
    <title>Test Page</title>\n" +  
    "  
    </head>\n" +  
    "  
    <body>\n" +  
    "  
    <p>This is a TEST!</p>\n" +  
    "  
    </body>\n" +  
    "</html>";  
  
// Extract the title from this XHTML content  
  
String title = StringUtils.substringBetween(htmlContent, "<title>",  
    "</title>");  
  
System.out.println( "Title: " + title );
```

This code extracts the title from this HTML document and prints the following:

Title: Test Page

Discussion

In the Solution section, the `substringBetween()` method returns the first string between the `open` and `close` strings-the title of an HTML document. The previous example only contained one nested element, but what happens when a string contains multiple elements nested in the same two strings? In the following example, three variables are extracted from a string using `substringBetween()`:

```
String variables = "{45}, {35}, {120}" ;

List numbers = new ArrayList( );

String variablesTemp = variables;

while( StringUtils.substringBetween( variablesTemp, "{" , "}" ) != null ) {

    String numberStr = StringUtils.substringBetween( variables, "{" , "}" );

    Double number = new Double( numberStr );

    numbers.add( number );

    variablesTemp = variablesTemp.substring( variablesTemp.indexOf(",") );

}

double sum = StatUtil.sum( ArrayUtils.toPrimitive( numbers.toArray( ) ) );

System.out.println( "Variables: " + variables + ", Sum: " + sum );
```

The output of this example is:

```
Variable: {45}, {35}, {120}, Sum: 200
```

After each number is extracted from the curly braces, the system finds the index of the next comma and reduces the size of the string to search for the next call to `StringUtils`.

`StringUtils.substringBetween()` can also find text that is delimited by the same character:

```
String message = "|TESTING| BOUNDARYExampleBOUNDARY";

String first = StringUtils.substringBetween( message, "|" );
```



```
String second = StringUtils.substringBetween( message, "BOUNDARY" );
```

The first string would return "TESTING" as it is between the | characters, and the second string would contain "Example."

Recipe 2.6 Stripping and Trimming a String

Problem

You need to strip or trim a string of extraneous whitespace, control characters, or other specified characters.

Solution

`StringUtils.trim()` takes a string and removes every whitespace and control character from the beginning and the end:

```
String test1 = " \a\r Testing 1 2 3 ";
```

```
String test2 = " \r\n ";
```

```
String trimTest1 = StringUtils.trim( test1 );
```

```
String trimTest2 = StringUtils.trimOrNull( test2 );
```

```
System.out.println( trimTest1 );
```

```
System.out.println( trimTest2 );
```

This code produces the following result. The `test1` variable is trimmed of leading and trailing whitespace, and the `test2` variable is trimmed to `null`:

```
Testing 1 2 3
```

```
null
```

Discussion

A *control character* is defined as all characters below 32 on the ASCII table-everything from `0 (NUL)` to `31 (unit separator)`. `StringUtils.trim()` delegates to the `trim()` function on `String` and gracefully handles `null`. When you pass a `null` to `StringUtils.trim()`, it returns a `null`.

Stripping a string

If a string contains leading and trailing characters to be removed, you can remove them with `StringUtils.strip()`. The `strip()` method differs from `trim()` in that you can specify a set of characters to strip from the beginning and end of a string. In this example, dashes and asterisks are stripped from the start and end of a string:

```
String original = "-----***---SHAZAM!---***-----";

String stripped = StringUtils.strip( original, "-*" );

System.out.println( "Stripped: " + stripped );
```

This produces the following output:

```
Stripped: SHAZAM!
```

Trimming to null

Use `trimToNull()` to test if a given parameter is present. Take the following servlet code as an example:

```
public void doGet(HttpServletRequest request, HttpServletResponse response)

    throws IOException, ServletException {

    String companyName =

        StringUtils.trimToNull( request.getParameter("companyName") );

    if( companyName != null ) {

        response.getWriter( ).write( "You supplied a company name!" );

    }

}
```

Using `StringUtils` reduces code complexity incrementally-four or five lines of code at a time. Testing for the absence or emptiness of a string usually entails checking to see if a string is empty or of zero length, and because a string could be `null`, you always need to check for `null` to avoid throwing a `NullPointerException`. In this last example, empty has the same meaning as `null`-the

`StringUtils.trimToNull()` method takes a string as a parameter, and if it is `null` or empty, the method returns a `null`.



Recipe 2.7 Chomping a String

Problem

You need to remove a trailing newline or carriage return from a string.

Solution

Use `StringUtils.chomp()` to remove the last line termination sequence from a string:

```
String input = "Hello\n";

String chomped = StringUtils.chomp( input );

// chomped equals "Hello"


String input2 = "Another test\r\n";

String chomped2 = StringUtils.chomp( input2 );

// chomped2 equals "Another test";
```

Recipe 2.8 Creating an Emphasized Header

Problem

You would like to print an attention-grabbing header.

Solution

Combine the powers of `StringUtils.repeat()`, `StringUtils.center()`, and `StringUtils.join()` to create a textual header. The following example demonstrates the use of these three methods to create a header:

```
public String createHeader( String title ) {  
  
    int width = 30;  
  
    // Construct heading using StringUtils: repeat(), center(), and join()  
  
    String stars = StringUtils.repeat( "*", width);  
  
    String centered = StringUtils.center( title, width, "*" );  
  
    String heading =  
  
        StringUtils.join(new Object[]{stars, centered, stars}, "\n");  
  
    return heading;  
  
}
```

Here's the output of `createHeader("TEST")`:

```
*****  
  
*****  TEST  *****  
  
*****
```

Discussion

In the example, `StringUtils.repeat()` creates the top and bottom rows with `StringUtils.repeat("*", 30)`, creating a string with 30 consecutive `*` characters. Calling `StringUtils.center(title, width, "*")` creates a middle line with the header title centered and surrounded by `*` characters. `StringUtils.join()` joins the lines together with the newline characters, and out pops a header.





Recipe 2.9 Reversing a String

Problem

You need to reverse a string.

Solution

Use `StringUtils.reverse()`. Supply a string parameter to this method, and it will return a reversed copy. The following example reverses two strings:

```
String original = "In time, I grew tired of his babbling nonsense.";

String reverse = StringUtils.reverse( original );

String originalGenes = "AACGTCCCTTGGTTTCCCAAAGTTTCCCTTTGAAATATATGCCCGCG";

String reverseGenes = StringUtils.reverse( originalGenes );


System.out.println( "Original: " + original );

System.out.println( "Reverse: " + reverse );

System.out.println( "\n\nOriginal: " + originalGenes );

System.out.println( "Reverse: " + reverseGenes );
```

The output contains a reversed string along with an original string:

```
Original: In time, I grew tired of his babbling nonsense.

Reverse: .esnesnon gnilbbab sih fo derit werg I ,emit nI


Original: AACGTCCCTTGGTTTCCCAAAGTTTCCCTTTGAAATATATGCCCGCG

Reverse: GCGCCCGTATATAAAGTTTCCCTTTGAAACCCTTTGGTTCCCTGCAA
```


Discussion

Reversing a `String` is easy, but how would you rearrange the words in a sentence? `StringUtils.reverseDelimited()` can reverse a string of tokens delimited by a character, and a sentence is nothing more than a series of tokens separated by whitespace and punctuation. To reverse a simple sentence, chop off the final punctuation mark, and then reverse the order of words delimited by spaces. The following example reverses an unrealistically simple English sentence:

```
public Sentence reverseSentence(String sentence) {  
  
    String reversed = StringUtils.chomp( sentence, "." );  
  
    reversed = StringUtils.reverseDelimited( reversed, ' ' );  
  
    reversed = reversed + ".";  
  
    return reversed;  
  
}
```

....

```
String sentence = "I am Susan."  
  
String reversed = reverseSentence( sentence );  
  
System.out.println( sentence );  
  
System.out.println( reversed );
```

The sentence is reversed and printed alongside the original:

```
I am Susan.  
  
Susan am I.
```

Here, the order of the characters within each delimited token is preserved. Notice that this example includes `StringUtils.chomp()` with two parameters, the last specifying the character to chomp from the string. Instead of chomping a newline, in this example, the period is chomped off of the sentence before performing the delimited reversal.

Recipe 2.10 Wrapping Words

Problem

You want to wrap lines of text using different line widths and various line termination sequences.

Solution

Use `WordUtils` to wrap words. Supply the number of columns and a line termination string, and `WordUtils` will wrap text. The following example wraps a small string to 20 columns:

```
// Define original String

String message = "One Two Three Four Five";


// Wrap the text.

String wrappedString =

    WordUtils.wrapText( message, 20, "\n", false );


System.out.println( "Wrapped Message:\n\n" + wrappedString );
```

This produces the following output:

Wrapped Message:

One Two Three Four

Five

Discussion

When `WordUtils` wraps a string, it takes a user-supplied line termination sequence like `\n` or `\r\n`

and inserts this line termination sequence after a specified number of characters, without splitting a word. In the next example, if the user is using a hand-held device, the number of columns in the display is 40, and a new line is represented by the sequence `\r\n`. On a workstation, the number of available columns is 80, and a new line is a single `\n` character. The platform is available as the System property `application.platform`:

```
String message = "Four score and seven years ago, our fathers " +  
    "brought forth upon this continent a new nation: " +  
    "conceived in liberty, and dedicated to the proposition " +  
    "that all men are created equal. ";  
  
// Define variables to hold two parameters to word wrapping  
  
int cols;  
  
String lineSeparator = "";  
  
// Retrieve the platform property from System  
  
String platform = System.getProperty("application.platform");  
  
if( platform.equals( "Handheld" ) ) {  
    cols = 40;  
    lineSeparator = "\r\n";  
} else if( platform.equals( "Workstation" ) ) {  
    cols = 80;  
    lineSeparator = "\n";  
}  
  
// Wrap the text.  
  
String wrappedString =  
    WordUtils.wrapText( message, cols, lineSeparator, true );
```

Depending on the platform, the `wrappedString` variable now holds the initial paragraph of the

Gettysburg Address wrapped to fit either a 40-column handheld device or an application running on a workstation with an 80-column display.

To wrap text for presentation on the Web, use the line termination sequence `
` to add an HTML line break. The following example wraps text with `
`, and introduces an option to prevent `WordUtils` from wrapping larger words:

```
String message = "Four score and seven years ago, our fathers " +  
    "brought forth upon this continent a new nation: conceived " +  
    "in liberty, and dedicated to the proposition that all men " +  
    "are created equal. http://www.oreilly.com/Gettysburg ";  
  
// Wrap the text.  
  
String wrappedString = WordUtils.wrap( message, 40, "<br/>", false );
```

In this example, the Gettysburg Address is formatted to fit into 40 columns in an HTML document. The final parameter to the `WordUtils.wrap()` method tells the wrapping algorithm not to bother wrapping large words, such as the long URL at the end of the text. Wrapping a long word would prevent people from being able to copy this URL correctly.

Recipe 2.11 Testing the Contents of a String

Problem

You need to make sure a string contains only numbers, letters, or a combination of both.

Solution

Use the various `StringUtils` methods to validate user input; `isNumeric()`, `isAlpha()`, `isAlphanumeric()`, and `isAlphaSpace()` verify that a string does not contain any undesired characters:

```
String state = "Virginia"

System.out.println( "Is state number? " +
                    StringUtils.isNumeric( state ) );

System.out.println( "Is state alpha? " +
                    StringUtils.isAlpha( state ) );

System.out.println( "Is state alphanumeric? " +
                    StringUtils.isAlphanumeric( state ) );

System.out.println( "Is state alphaspace? " +
                    StringUtils.isAlphaspace( state ) );
```

This code tests the string "Virginia" against four validation methods, producing the following output:

```
Is state a number? false

Is state alpha? true

Is state alphanumeric? true

Is state alphaspace? true
```

Discussion

`StringUtils.isNumeric()` returns true if the string being tested contains only digits from 0 to 9. If you are asking a user to input a numerical value, such as year or age, you need to have a way to ensure that the input supplied is, in fact, a numeric value:

```
String test1 = "1976";

String test2 = "Mozart";

boolean t1val = StringUtils.isNumeric( test1 );

boolean t2val = StringUtils.isNumeric( test2 );

System.out.println( "Is " + test1 + " a number? " + t1val );

System.out.println( "Is " + test2 + " a number? " + t2val );
```

This code tests two strings and produces the following output:

```
Is 1976 a number? true

Is Mozart a number? false
```

You can use the following code to see if a string contains only letters or a combination of letters and numbers:

```
String test1 = "ORANGE";

String test2 = "ICE9";

String test3 = "ICE CREAM";

String test4 = "820B Judson Avenue";

boolean t1val = StringUtils.isAlpha( test1 ); // returns true

boolean t2val = StringUtils.isAlphanumeric( test2 ); // returns true

boolean t3val = StringUtils.isAlphaSpace( test3 ); // returns true

boolean t4val =
```

```
StringUtils.isAlphanumericSpace( test4 ); // returns true
```

User supplied input can rarely be trusted. If you have asked the user to supply an age, a year, or a day of the week, you will need to then validate that input. Or, if you have asked the user to type in a name, you will want to make sure that the supplied name contains only letters and acceptable punctuation. An application with inadequate input validation will frequently fail, and produce unsightly stack traces caused by either `NumberFormatException`s or `NullPointerException`s. An application should be able to gracefully handle the most nonsensical input without missing a beat, and prompt the user for a valid input. Tools such as Jakarta Commons Validator provide a framework to validate the contents of a JavaBean, but at a much lower level, the `StringUtils` class in Commons Lang provides some useful utilities for examining the contents of a string.

Input forms frequently need to validate a user's name. In this case, it is important to remember that certain names have apostrophes and dashes. If you are validating a name, always make sure that you allow for names with punctuation. Here is an example that validates a name with a dash, an apostrophe, and a period:

```
String name1 = "Tim O'Reilly";
```

```
String name2 = "Mr. Mason-Dixon!";
```

```
String punctuation = ".-!";
```

```
String name1Temp = StringUtils.replaceChars( name1, punctuation, "");
```

```
String name2Temp = StringUtils.replaceChars( name1, punctuation, "");
```

```
boolean t1val = StringUtils.isAlpha( name1Temp ); // returns true
```

```
boolean t2val = StringUtils.isAlpha( name2Temp ); // returns false
```

"Tim O'Reilly" is a valid name, but you need to use the `StringUtils.replaceChars()` method to throw out punctuation before you can pass both of the names to the `StringUtils.isAlpha()` method. "Mr. Mason-Dixon!" is not a valid name, because an exclamation point is not on the list of valid name punctuation. As an Irishman, I encourage you to always check your name validation with names like "O'Toole" or "O'Brien," and, as the world continues to shrink, more exceptions to the rule, like "Al-Sa'ud," will become more prevalent; your system should not force someone to change their name. Speaking from personal experience, it is insulting when a web site or an application forces you to change your name, and it is a quick way to alienate your customers. I cannot begin to tell you how many web sites have shown me a nasty Open Database Connectivity (ODBC) error page or stack trace after I've told them my last name-it is frustrating.

Recipe 2.12 Measuring the Frequency of a String

Problem

You need to find out how many times a certain word or piece of text occurs in a string.

Solution

`StringUtils.countMatches()` returns the frequency of a piece of text within another string:

```
File manuscriptFile = new File("manuscript.txt");

Reader reader = new FileReader( manuscriptFile );

StringWriter stringWriter = new StringWriter( );

while( reader.ready( ) ) { writer.write( reader.read( ) ); }

String manuscript = stringWriter.toString( );

// Convert string to lowercase

manuscript = StringUtils.lowerCase(manuscript);

// count the occurrences of "futility"

int numFutility = StringUtils.countMatches( manuscript, "futility" );
```

Converting the entire string to lowercase ensures that all occurrences of the word "futility" are counted, regardless of capitalization. This code executes and `numFutility` will contain the number of occurrences of the word "futility."

Discussion

If the *manuscript.txt* file is large, it makes more sense to search this file one line at a time, and sum the number of matches as each line is read. A more efficient implementation of the previous example

would look like this:

```
File manuscriptFile = new File("manuscript.txt");

Reader reader = new FileReader( manuscriptFile );

LineNumberReader lineReader = new LineNumberReader( reader );

int numOccurences = 0;

while( lineReader.ready( ) ) {

    String line = StringUtils.toLowerCase( lineReader.readLine( ) );

    numOccurences += StringUtils.countMatches( , "futility" );

}
```

Your random access memory will thank you for this implementation. Java programmers are often lulled into a sense of false security knowing that they do not have to worry about memory management. Poor design decisions and inefficient implementation often lead to slow running or hard-to-scale applications. Just because you don't have to allocate and deallocate memory does not mean that you should stop thinking about efficient memory use. If you are trying to search for the frequency of a word in a 20 megabyte file, please try not to read the entire file into memory before searching. Performing a linear search on a large string is an inappropriate way to search a large database of documents. When searching large amounts of text, it is more efficient to create an index of terms than to perform a linear search over a large string. A method for indexing and searching documents using Jakarta Lucene and Jakarta Commons Digester will be discussed in a later chapter.

See Also

[Chapter 12](#) contains a number of recipes devoted to searching and filtering content. If you are creating a system that needs to search a large collection of documents, consider using Jakarta Lucene (<http://jakarta.apache.org/lucene>) to index your content.

Recipe 2.13 Parsing Formatted Strings

Problem

You need to parse a string containing control characters and the delimiters `(`, `[`, `)`, `]`, and `|`.

Solution

Use variations of `substring()` from `StringUtils`. This next example parses a string that contains five numbers delimited by parentheses, brackets, and a pipe symbol (`N0 * (N1,N2) [N3,N4] | N5`):

```
String formatted = " 25 * (30,40) [50,60] | 30"
```

```
PrintWriter out = System.out;

out.print("N0: " + StringUtils.substringBeforeLast( formatted, "*" ) );

out.print(", N1: " + StringUtils.substringBetween( formatted, "(", "," ) );

out.print(", N2: " + StringUtils.substringBetween( formatted, ",", ")" ) );

out.print(", N3: " + StringUtils.substringBetween( formatted, "[", "," ) );

out.print(", N4: " + StringUtils.substringBetween( formatted, ",", "]" ) );

out.print(", N5: " + StringUtils.substringAfterLast( formatted, "|" ) );
```

This parses the formatted text and prints the following output:

```
N0: 25, N1: 30, N2: 40, N3: 50, N4: 60, N5: 30
```

Discussion

The following public static methods come in handy when trying to extract information from a formatted string:

```
StringUtils.substringBetween( )
```

Captures content between two strings

```
StringUtils.substringAfter( )
```

Captures content that occurs after the specified string

```
StringUtils.substringBefore( )
```

Captures content that occurs before a specified string

```
StringUtils.substringBeforeLast( )
```

Captures content after the last occurrence of a specified string

```
StringUtils.substringAfterLast( )
```

Captures content before the last occurrence of a specified string

To illustrate the use of these methods, here is an example of a feed of sports scores. Each record in the feed has a defined format, which resembles this feed description:

```
\(SOT)<sport>[<team1>,<team2>] (<score1>,<score2>)\(ETX)
```

Notes:

```
\(SOT) is ASCII character 2 "Start of Text",
```

```
\(ETX) is ASCII character 4 "End of Transmission".
```

Example:

```
\(SOT)Baseball[BOS,SEA] (24,22)\(ETX)
```

```
\(SOT)Basketball[CHI,NYC] (29,5)\(ETX)
```

The following example parses this feed using `StringUtils` methods `trim()`, `substringBetween()`, and `substringBefore()`. The `boxScore` variable holds a test string to parse, and, once parsed, this code prints out the game score:

```
// Create a formatted string to parse - get this from a feed

char SOT = '\u0002';

char ETX = '\u0004';

String boxScore = SOT + "Basketball[CHI,BOS](69,75)\r\n" + ETX;


// Get rid of the archaic control characters

boxScore = StringUtils.trim( boxScore );


// Parse the score into component parts

String sport = StringUtils.substringBefore( boxScore, "[" );

String team1 = StringUtils.substringBetween( boxScore, "[", "," );

String team2 = StringUtils.substringBetween( boxScore, ",", "]" );

String score1 = StringUtils.substringBetween( boxScore, "(", "," );

String score2 = StringUtils.substringBetween( boxScore, ",", ")" );


PrintWriter out = System.out

out.println( "**** " + sport + " Score" );

out.println( "\t" + team1 + "\t" + score1 );

out.println( "\t" + team2 + "\t" + score2 );
```

This code parses a score, and prints the following output:

```
**** Basketball

CHI 69

BOS 75
```

In the previous example, `StringUtils.trim()` rids the text of the `SOT` and `ETX` control characters. `StringUtils.substringBefore()` then reads the sport name-"Basketball"-and `substringBetween()` is used to retrieve the teams and scores.

At first glance, the value of these `substring()` variations is not obvious. The previous example parsed this simple formatted string using three static methods on `StringUtils`, but how difficult would it have been to implement this parsing without the aid of Commons Lang? The following example parses the same string using only methods available in the Java 1.4 J2SE:

```
// Find the sport name without using StringUtils

boxScore = boxScore.trim( );

int firstBracket = boxScore.indexOf( "[" );

String sport = boxScore.substring( 0, firstBracket );

int firstComma = boxScore.indexOf( "," );

String team1 = boxScore.substring( firstBracket + 1, firstComma );

int secondBracket = boxScore.indexOf( "]" );

String team2 = boxScore.substring( firstComma + 1, secondBracket );

int firstParen = boxScore.indexOf( "(" );

int secondComma = boxScore.indexOf( ",", firstParen );

String score1 = boxScore.substring( firstParen + 1, secondComma );

int secondParen = boxScore.indexOf( ")" );

String score2 = boxScore.substring( secondComma + 1, secondParen );
```

This parses the string in a similar number of lines, but the code is less straightforward and much more difficult to maintain. Instead of simply calling a `substringBetween()` method, the previous example calls `String.indexOf()` and performs arithmetic with an index while calling `String.substring()`. Additionally, the `substring()` methods on `StringUtils` are `null`-safe; the Java 1.4 example could throw a `NullPointerException` if `boxScore` was `null`.

`String.trim()` has the same behavior as `StringUtils.trim()`, stripping the string of all whitespace and ASCII control characters. `StringUtils.trim()` is simply a wrapper for the `String.trim()` method, but the `StringUtils.trim()` method can gracefully handle a `null` input. If a `null` value is passed to `StringUtils.trim()`, a `null` value is returned.

Recipe 2.14 Calculating String Difference

Problem

Your application needs to compare two strings and print out the difference.

Solution

Use `StringUtils.difference()`, `StringUtils.indexOfDifference()`, and `StringUtils.getLevenshteinDistance()`. `StringUtils.difference()` prints out the difference between two strings, `StringUtils.indexOfDifference()` returns the index at which two strings begin to differ, and `StringUtils.getLevenshteinDistance()` returns the "edit distance" between two strings. The following example demonstrates all three of these methods:

```
int dist = StringUtils.getLevenshteinDistance( "Word", "World" );

String diff = StringUtils.difference( "Word", "World" );

int index = StringUtils.indexOfDifference( "Word", "World" );

System.out.println( "Edit Distance: " + dist );

System.out.println( "Difference: " + diff );

System.out.println( "Diff Index: " + index );
```

This code compares the strings "Word" and "World," producing the following output:

```
Edit Distance: 2

Difference: ld

Diff Index: 3
```

Discussion

`StringUtils.difference()` returns the difference between two strings, returning the portion of the second string, which starts to differ from the first. `StringUtils.indexOfDifference()` returns the

index at which the second string starts to diverge from the first. The difference between "ABC" and "ABE" is "E," and the index of the difference is 2. Here's a more complex example:

```
String a = "Strategy";

String b = "Strategic";


String difference = StringUtils.difference( a, b );

int differenceIndex = StringUtils.indexOfDifference( a, b );


System.out.println( "difference(Strategy, Strategic) = " +
                    difference );

System.out.println( "index(Strategy, Strategic) = " +
                    differenceIndex );


a = "The Secretary of the UN is Kofi Annan."
b = "The Secretary of State is Colin Powell."


difference = StringUtils.difference( a, b );

differenceIndex = StringUtils.indexOfDifference( a, b );


System.out.println( "difference(..., ...) = " +
                    difference );

System.out.println( "index(..., ...) = " +
                    differenceIndex );
```

This produces the following output, showing the differences between two strings:

```
difference(Strategy, Strategic) = ic

index(Strategy, Strategic) = 7
```



```
difference(...,...) = State is Colin Powell.  
  
index(...,...) = 17
```

The Levenshtein distance is calculated as the number of insertions, deletions, and replacements it takes to get from one string to another. The distance between "Boat" and "Coat" is a one letter replacement, and the distance between "Remember" and "Alamo" is 8-five letter replacements and three deletions. Levenshtein distance is also known as the *edit distance*, which is the number of changes one needs to make to a string to get from string A to string B. The following example demonstrates the `getLevenshteinDistance()` method:

```
int distance1 =  
  
    StringUtils.getLevenshteinDistance( "Boat", "Coat" );  
  
int distance2 =  
  
    StringUtils.getLevenshteinDistance( "Remember", "Alamo" );  
  
int distance3 =  
  
    StringUtils.getLevenshteinDistance( "Steve", "Stereo" );  
  
  
  
System.out.println( "distance(Boat, Coat): " + distance1 );  
  
System.out.println( "distance(Remember, Alamo): " + distance2 );  
  
System.out.println( "distance(Steve, Stereo): " + distance3 );
```

This produces the following output, showing the Levenshtein (or edit) distance between various strings:

```
distance(Boat, Coat): 1  
  
distance(Remember, Alamo): 8  
  
distance(Steve, Stereo): 3
```

See Also

The Levenshtein distance has a number of different applications, including pattern recognition and correcting spelling mistakes. For more information about the Levenshtein distance, see <http://www.merriampark.com/ld.htm>, which explains the algorithm and provides links to implementations of this algorithm in 15 different languages.

Recipe 2.15 Using Commons Codec

Problem

You want to use Commons Codec.

Solution

You must download the latest version of Jakarta Commons Codec, and place the Commons Codec JAR in your project's classpath. Follow the steps outlined in [Recipe 1.1](#), downloading Commons Codec 1.2 instead of Commons Lang.

Discussion

The Commons Codec library is a small library, which includes encoders and decoders for common encoding algorithms, such as `Hex`, `Base64`; and phonetic encoders, such as `Metaphone`, `DoubleMetaphone`, and `Soundex`. This tiny component was created to provide a definitive implementation of `Base64` and `Hex`, encouraging reuse and reducing the amount of code duplication between various Apache projects.

If you have a Maven project that needs to use Commons Codec, add a dependency on Commons Codec 1.2 with the following section in *project.xml*:

```
<dependencies>

  <dependency>

    <id>commons-codec</id>

    <version>1.2</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For information on obtaining the source code for Commons Codec, see[Recipe 2.16](#). To learn more about Commons Codec, visit the Jakarta Commons Codec web site at <http://jakarta.apache.org/commons/codec/>.



Recipe 2.16 Getting the Commons Codec Source Code

Problem

You want the source code for the Commons Codec project.

Solution

Download the source from <http://jakarta.apache.org/site/sourceindex.cgi>. Follow the same procedure as outlined in [Recipe 1.1](#). Download a file named *commons-codec-1.2-src.zip* (or *commons-lang-1.2-src.tar.gz*), and once you unzip this file, you will have the source to Commons Codec in *./commons-codec-1.2-src/src*.

See Also

Most Commons components follow a similar convention for the layout of binary and source distributions. For more information about the contents layout of the Codec source distribution, see [Recipe 1.3](#).

For information on obtaining the binary distribution for Commons Codec, see [Recipe 2.15](#).



Recipe 2.17 Calculating Soundex

Problem

You need the **Soundex** code of a word or a name.

Solution

Use Jakarta Commons Codec's **Soundex**. Supply a surname or a word, and **Soundex** will produce a phonetic encoding:

```
// Required import declaration

import org.apache.commons.codec.language.Soundex;

// Code body

Soundex soundex = new Soundex( );

String obrienSoundex = soundex.soundex( "O'Brien" );

String obrianSoundex = soundex.soundex( "O'Brian" );

String obryanSoundex = soundex.soundex( "O'Bryan" );

System.out.println( "O'Brien soundex: " + obrienSoundex );

System.out.println( "O'Brian soundex: " + obrianSoundex );

System.out.println( "O'Bryan soundex: " + obryanSoundex );
```

This will produce the following output for three similar surnames:

```
O'Brien soundex: 0165

O'Brian soundex: 0165

O'Bryan soundex: 0165
```

Discussion

`Soundex.soundex()` takes a string, preserves the first letter as a letter code, and proceeds to calculate a code based on consonants contained in a string. So, names such as "O'Bryan," "O'Brien," and "O'Brian," all being common variants of the Irish surname, are given the same encoding: "O165." The 1 corresponds to the B, the 6 corresponds to the R, and the 5 corresponds to the N; vowels are discarded from a string before the `Soundex` code is generated.

The `Soundex` algorithm can be used in a number of situations, but `Soundex` is usually associated with surnames, as the United States historical census records are indexed using `Soundex`. In addition to the role `Soundex` plays in the census, `Soundex` is also used in the health care industry to index medical records and report statistics to the government. A system to access individual records should allow a user to search for a person by the `Soundex` code of a surname. If a user types in the name "Boswell" to search for a patient in a hospital, the search result should include patients named "Buswell" and "Baswol;" you can use `Soundex` to provide this capability if an application needs to locate individuals by the sound of a surname.

The `Soundex` of a word or name can also be used as a primitive method to find out if two small words rhyme. Commons Codec contains other phonetic encodings, such as `RefinedSoundex`, `Metaphone`, and `DoubleMetaphone`. All of these alternatives solve similar problems-capturing the *phonemes* or sounds contained in a word.

See Also

For more information on the `Soundex` encoding, take a look at the Dictionary of Algorithms and Data Structures at the National Institute of Standards and Technology (NIST), <http://www.nist.gov/dads/HTML/soundex.html>. There you will find links to a C implementation of the `Soundex` algorithm.

For more information about alternatives to `Soundex` encoding, read "The Double Metaphone Search Algorithm" by Lawrence Philips (<http://www.cuj.com/documents/s=8038/cuj0006philips/>). Or take a look at one of Lawrence Philips's original Metaphone algorithm implementations at <http://aspell.sourceforge.net/metaphone/>. Both the Metaphone and Double Metaphone algorithms capture the sound of an English word; implementations of these algorithms are available in Commons Codec as `Metaphone` and `DoubleMetaphone`.

Chapter 3. JavaBeans

[Introduction](#)

[Recipe 3.1. Representing Beans Graphically](#)

[Recipe 3.2. Obtaining Commons BeanUtils](#)

[Recipe 3.3. Getting the Commons BeanUtils Source Code](#)

[Recipe 3.4. Accessing Simple Bean Properties](#)

[Recipe 3.5. Accessing Nested Bean Properties](#)

[Recipe 3.6. Accessing Indexed Bean Properties](#)

[Recipe 3.7. Accessing Mapped Bean Properties](#)

[Recipe 3.8. Accessing a Simple, Nested, Indexed, and Mapped Bean Property](#)

[Recipe 3.9. Determining the Type of a Bean Property](#)

[Recipe 3.10. Comparing Beans](#)

[Recipe 3.11. Copying Bean Properties](#)

[Recipe 3.12. Cloning a Bean](#)

[Recipe 3.13. Setting a Bean Property](#)

[Recipe 3.14. Testing Property Access](#)

[Recipe 3.15. Validating Beans with Predicates](#)

[Recipe 3.16. Creating a Map of Bean Properties](#)

[Recipe 3.17. Wrapping a Bean with a Map](#)

[Recipe 3.18. Creating a Dynamic Bean](#)

[Recipe 3.19. Getting and Setting Properties as Strings](#)

Introduction

Beans are everywhere, popping up in web-application frameworks, enterprise applications, Swing Graphical User Interface (GUIs), templating engines, and object-relational mapping (ORM) tools. Most systems have some sort of object model; for example, an electronic commerce application would have an object model involving an *Invoice*, which relates to a *Customer*; or a sports news web site would have related *Athlete*, *Sport*, and *Team* objects. Frequently, objects in these object models are beans-simple objects with properties, encapsulating access to these properties via public getter and setter methods.

In 1997, Sun Microsystems published Version 1.01 of the JavaBeans® specification. Initially, Sun offered beans as visual components for graphical user interfaces; JavaBeans were to be the equivalent of Microsoft's ActiveX controls-a framework and set of interfaces for creating reusable and pluggable GUI components. Used as components, which exposed states through a series of accessor and mutator (*getX()* and *setX()*) methods, a developer would develop a GUI Java application by creating a visual layout using an IDE like Visual Cafe or JBuilder. If you've ever developed with Microsoft tools, you'll know exactly what this means-Java was going to unseat Visual Basic, and GUI development was going to be easier than easy. According to the JavaBeans Specification Version 1.01 from 1997:

A Java Bean is a reusable software component that can be manipulated visually in a builder tool.

Don't be misled; 1997 was ages ago, and the concept of the bean has evolved. In the last seven years, Java has become a dominant technology for server-side applications; impressive Swing applications do exist, but Java has not been an attractive platform for desktop application development due to reasons technical, economic, and judicial.

Don't be confused by the 1997 JavaBeans specification, either; it is still relevant, but, when used in the context of this book, the term *bean* is any object with a no-argument constructor, which encapsulates access to private member variables via getter and setter methods. [Example 3-1](#) defines a bean, *SimpleBean*, which contains two bean properties-*name1* and *name2*.

Example 3-1. Sample bean

```
package org.test.bean;

public class SimpleBean {

    private String name1;

    private String name2;
```



```
public SimpleBean( ) {}

public String getName1( ) { return name1; }

public void setName1(String name1) { this.name1 = name1; }

public String getName2( ) { return name2; }

public void setName2(String name2) { this.name2 = name2; }

}
```

The presence of the public methods `getName1()` and `getName2()` make the bean properties `name1` and `name2` readable, and the public methods `setName1()` and `setName2()` make these properties writable. A bean should also have a public no-argument constructor; other constructors are not prohibited, but, since many tools need to dynamically create and populate beans, a no-argument constructor is required.

The original JavaBeans specification is available at <http://java.sun.com/products/javabeans/docs/spec.html>. The JavaBeans specification still exists and features have been added to the Java 1.4 release to support reading and writing JavaBeans to Extensible Markup Language (XML) documents. More information about more modern additions to the JavaBeans specification can be found at <http://java.sun.com/j2se/1.4.2/docs/guide/beans/changes14.html>.

Recipe 3.1 Representing Beans Graphically

Problem

You need to draw a diagram of a simple bean that shows the relationships between different objects.

Solution

Use a simplified variant of a Unified Modeling Language (UML) class diagram that contains only class names, attribute names, and attribute types. [Figure 3-1](#) describes two related beans-**Person** and **Job**.

Figure 3-1. Structure of Person and Job beans

Discussion

Many of the recipes in this book deal with an object model consisting of JavaBeans, and, to save paper, I've devised this simple shorthand for describing a collection of related beans. Every time you see a diagram like [Figure 3-1](#), mentally translate it to a set of classes, one for each box; each class attribute in that box is a private member variable, with a getter method and a setter method. The beans represented by these diagrams are simply objects with attributes, and the only operations on a bean are getter and setter methods and no-argument constructors. To help you get used to translating these diagrams into code, the **Person** and **Job** classes are defined in Examples [Example 3-2](#) and [Example 3-3](#).

Example 3-2. The Person bean

```
public class Person {  
  
    private String name;  
  
    private Integer age;  
  
}
```

```
private Job job;

public String getName( ) { return name; }

public void setName(String name) { this.name = name; }

public Integer getAge( ) { return age; }

public void setAge(Integer age) { this.age = age; }

public Job getJob( ) { return job; }

public void setJob(Job job) { this.job = job; }

}
```

Example 3-3. The Job bean

```
public class Job {

    private String title;

    private BigDecimal salary;

    public String getTitle( ) { return title; }

    public void setTitle(String title) { this.title = title; }

    public BigDecimal getSalary( ) { return salary; }


    public void setSalary(BigDecimal salary) { this.salary = salary; }

}
```

When an object contains an attribute of type `List`, it is helpful to know the type of object that `List` contains. To convey the type of object contained in a `List`, every list attribute will be followed by the type it is intended to contain surrounded by brackets: *List<Integer>*. Similarly, if an object contains a `Map`, the type of the key and value will be separated by a comma and surrounded by brackets: *Map<String,Integer>*. If the `Person` object had contained a list of `Job` objects instead of a single `Job`

object, the attribute type would be written *List<Job>*, as in [Figure 3-2](#).

Figure 3-2. Representing a list of Job objects



The angle bracket syntax is actually the standard means of representing these objects in the newest version of Java, JDK 1.5. For more on JDK 1.5, check out *Java 1.5 Tiger: A Developer's Notebook*, by David Flanagan and Brett McLaughlin(O'Reilly).

See Also

Don't confuse UML with object-oriented design, as this is a mistake all too often made; UML captures the form and function of a system, but it is no substitute for a good design. All the drawings in the world won't make a bad design good, and spending a day drawing a big UML diagram is simply a creative form of procrastination. That said, if you insist on drawing UML diagrams, check out some of the following tools:

ArgoUML

ArgoUML is a UML editor from Tigris.org, an open source community hosted by CollabNet (<http://www.collabnet.com>). ArgoUML supports reverse engineering and code generation to Java, C++, C#, and PHP. For more information about ArgoUML, see the project page at <http://argouml.tigris.org/>. To launch ArgoUML via Java Web Start, click on <http://argouml.tigris.org/files/documents/4/383/ArgoUML-stable.jnlp>.

Poseidon for UML

Gentleware AG has taken ArgoUML and extended it, providing additional features, such as language export options and improved usability. A community edition is free to download and use. For more information about this product, see the Gentleware AG site at <http://www.gentleware.com>. If you have Java Web Start installed, you can launch the community edition of Poseidon through a browser by clicking on <http://www.gentleware.com/products/webstart.php4>.

SmartDraw

SmartDraw, from SmartDraw.com, offers a very usable general purpose tool for creating diagrams. This tool stands out from the rest because it is simple, and, unlike other tools, it is solely concerned with the creation of diagrams; it makes no attempt to get involved with your application, and it has an attractive price of around \$129. Details are at <http://www.smartdraw.com>.

Other Tools

It seem that almost every software company has attempted to create a UML modeling tool, some of the well-known commercial products are IBM's Rational Rose, Microsoft's Visio, and Borland's Together. The URL http://www.objectsbydesign.com/tools/umltools_byCompany.html contains an exhaustive list of other UML tools.





Recipe 3.2 Obtaining Commons BeanUtils

Problem

You want to use Jakarta Commons BeanUtils to manipulate and access simple, indexed, and nested bean properties.

Solution

You must download the latest version of Commons BeanUtils, and place the Commons BeanUtils JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons BeanUtils 1.7 instead of Commons Lang.

Commons BeanUtils depends on Commons Logging 1.0.3 and Commons Collections 3.0; both of these can be downloaded from the same location as Commons BeanUtils.

Discussion

Commons BeanUtils is a collection of utilities that makes working with beans and bean properties much easier. This project contains utilities that allow one to retrieve a bean property by name, sort beans by a property, translate beans to maps, and more. BeanUtils is simple and straightforward, and, as such, you will find that it is one of the most widely used and distributed libraries in open source Java. Along with Commons Lang and Commons Collections, Commons BeanUtils is part of the core of Jakarta Commons. Unless specified otherwise, every utility mentioned in this chapter is from Commons BeanUtils.

If you have a Maven project that needs to use Commons BeanUtils, add a dependency on Commons BeanUtils 1.7 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-beanutils</id>

    <version>1.7</version>

  </dependency>
```

```
.....other dependencies...  
</dependencies>
```

The rest of this chapter focuses on Commons BeanUtils.

In the Beginning...

BeanUtils was originally a part of Jakarta Struts, a widely used Model-View-Controller (MVC) framework for web applications, which originated in the Jakarta project. The Struts framework hinges upon *form beans*, which are used to present and communicate user input to and from a Struts action. The Struts `ActionServlet` and the bean JavaServer Pages (JSP) tag libraries use the `BeanUtils`, `PropertyUtils`, and `ConvertUtils` classes to populate and manipulate beans. Refactoring BeanUtils from Struts has created new possibilities of reuse throughout the Jakarta project and the larger open source Java community.

See Also

For more information about downloading Commons Logging 1.0.3, see [Recipe 7.9](#). For more information about downloading Commons Collections, see [Recipe 4.1](#). For information on obtaining the source code for Commons BeanUtils, see [Recipe 3.3](#).

To learn more about Commons BeanUtils, visit the Commons BeanUtils web site: <http://jakarta.apache.org/commons/beanutils/>.

If you have questions about how to use Commons BeanUtils, you can join the commons-user@jakarta.apache.org mailing list. Refer to [Recipe 1.2](#) for instructions on joining the Commons-user mailing list.



Recipe 3.3 Getting the Commons BeanUtils Source Code

Problem

You need the source code for the Commons BeanUtils project.

Solution

Download the source from <http://jakarta.apache.org/site/sourceindex.cgi>, following the same procedure as outlined in [Recipe 1.1](#). Download a file named *commons-beanutils-1.7-src.zip* (or *commons-beanutils-1.7-src.tar.gz*); once you unzip this archive, you will have the source to Commons BeanUtils in *./commons-beanutils-1.7-src/src*.

See Also

Most Commons components follow a similar convention for the layout of binary and source distributions. For more information about the layout of the BeanUtils source distribution, see [Recipe 1.3](#).

For information on obtaining the binary distribution for Commons BeanUtils, see [Recipe 3.2](#).

Recipe 3.4 Accessing Simple Bean Properties

Problem

You need to access a simple bean property by name.

Solution

Use `PropertyUtils.getSimpleProperty()` to access a bean property by name; this method takes the name of a property and returns the value of that property. The following example uses this method to retrieve the `name` property from a `Person` bean:

```
import org.apache.commons.beanutils.PropertyUtils;

Person person = new Person( );

person.setName( "Alex" );

String name = (String) PropertyUtils.getSimpleProperty( person, "name" );

System.out.println( name );
```

`PropertyUtils.getSimpleProperty()` invokes the public method `getName()` on an instance of `Person`, returning the value of the `name` property. The previous example executes and prints out the name "Alex."

Discussion

A simple bean property is a private member variable that can be accessed with a getter method. If a property can be read via a getter method, that getter method is said to be the *read method* for the named property. If the property can be modified with a setter method, that setter method is said to be the *write method* for the named property. The `Person` bean in [Example 3-4](#) defines two simple bean properties, `name` and `favoriteColor`.

Example 3-4. A Person bean with two simple properties

```
package com.discursive.jccook.bean;

public class Person {

    private String name;

    private String favoriteColor;

    public Person( ) {}

    public String getName( ) { return name; }

    public void setName(String name) {

        this.name = name;

    }

    public String getFavoriteColor( ) { return favoriteColor; }

    public void setFavoriteColor(String favoriteColor) {

        this.favoriteColor = favoriteColor;

    }

}
```

The class defined in [Example 3-4](#) is used in the following sample code, which creates a `Person` object, sets the `name` and `favoriteColor` properties, and demonstrates the use of `Property.getSimpleProperty()` to retrieve both properties by name:

```
import org.apache.commons.beanutils.PropertyUtils;

// Create a person

Person person = new Person( );

person.setName( "Alex Wolfe" );
```

```

person.setFavoriteColor( "Green" );

try {

    String name = (String) PropertyUtils.getSimpleProperty( person, "name" );

    String favoriteColor =

        (String) PropertyUtils.getSimpleProperty( person, "favoriteColor" );

    System.out.println( "The Person: " + name + " likes " + favoriteColor );

} catch (IllegalAccessException e) {

    System.out.println( "You are not allowed to access a property!" );

} catch (InvocationTargetException e) {

    System.out.println( "There was a problem invoking the method." );

} catch (NoSuchMethodException e) {

    System.out.println( "There is no method to get a property." );

}

```

Take note of the extensive exception handling required to retrieve two bean properties; three separate exceptions can be thrown by `getSimpleProperty()`. The first, `IllegalAccessException`, is thrown if the getter method is not accessible (not public). `InvocationTargetException` is thrown if the getter method throws an exception, and `NoSuchMethodException` is thrown if you specify a bean property that does not exist on an object; for example, attempting to retrieve the `numberOfDoors` property from the `person` object above would throw a `NoSuchMethodException` because there is no `getNumberOfDoors()` method.

To simplify the examples in this chapter, most examples will omit the `try/catch` or catch the general `Exception`-to do otherwise would be a needless waste of paper. As a general programming practice, catching the general `Exception` should be avoided; well-written code usually catches individual, specific exceptions. But, in this case, catching the general `Exception` may save you a great deal of hassle.

Using `PropertyUtils.getSimpleProperty()` when you could simply call a get method might seem like an unwieldy solution to a very simple problem, but the alternative-calling a getter method-locks you into a specific bean property at compile time. This may be unacceptable if you are designing something generic like a templating system or an expression language interpreter; you may need to access an arbitrary property of an arbitrary object known only at runtime. The ability to retrieve the value of a bean property by name lies at the heart of a number of important tools, such

as Struts, Jakarta Velocity, Jakarta Commons JEXL, and utilities from Jakarta Commons Collections. Accessing bean properties by name is an appropriate solution for a system that needs a high level of flexibility.

See Also

The next three recipes focus on accessing different types of bean properties: nested, indexed, and mapped. Simple properties may also be retrieved with `PropertyUtils.getProperty()`; this method is described in [Recipe 3.8](#).

This recipe mentions Struts, a web application MVC framework. For more information about the Struts project, see <http://jakarta.apache.org/struts>. Jakarta Velocity and Jakarta Commons JEXL are discussed in [Chapter 9](#), and Commons Collections is discussed in [Chapter 5](#).

PREV

< Day Day Up >

Recipe 3.5 Accessing Nested Bean Properties

Problem

You need to access a nested bean property.

Solution

Use `PropertyUtils.getNestedProperty()` to retrieve a nested bean property. Use a period as a delimiter to identify nested bean properties; *one.two.three.four* refers to a property nested three levels deep-the `four` property of the `three` property of the `two` property of the `one` property. The following example accesses a nested bean property on a `Person` bean, *author.name*.

```
import org.apache.commons.beanutils.PropertyUtils;

Book book = new Book( );

book.setName( "Emerson's Essays" );

Person author = new Person( );

author.setName( "Ralph Waldo Emerson" );

book.setAuthor( author );

String authorName = (String) PropertyUtils.getNestedProperty(book,


"author.name");

System.out.println( "authorName" );This example retrieves the name
property of the author property on the Book object, printing "Ralph
Waldo Emerson".
```

Discussion

The `author` property of `Book` is a `Person` bean with a `name` property; calling `getNestedProperty()` with `author.name` retrieves the simple property `author` from `Book` and the property `name`, which is nested in the `author` property. [Figure 3-3](#) shows the `Book` and `Person` beans that were used in the previous example.

Figure 3-3. Structure of two simple beans: Book and Person



The following example demonstrates a combination of `getSimpleProperty()` and `getNestedProperty()`, retrieving a book name and an author name:

General Exception is caught.

```
import org.apache.commons.beanutils.PropertyUtils;

// Create an author

Person author = new Person( );

author.setName( "Chaucer" );

Book book = new Book( );

book.setName( "The Canterbury Tales" );

book.setAuthor( author );

try {

    String bookName = (String) PropertyUtils.getSimpleProperty( book, "name" );

    String authorName =

        (String) PropertyUtils.getNestedProperty( book, "author.name" );
```

```
        System.out.println( "The book is " + bookName );

        System.out.println( "The author is " + authorName );

    } catch (Exception e) {

        System.out.println( "There was a problem getting a bean property." );

        e.printStackTrace( );

    }
```



To reduce the size of the example code, only the general `Exception` is caught.

When using `getNestedProperty()`, there is no limit to the number of nesting levels for a property; demonstrating the retrieval of a deeply nested property, the following example retrieves the `name` property from the `state` property of the `address` property of a `Person` object:

```
String propertyName = "address.state.name";

String stateName =

    (String) PropertyUtils.getNestedProperty( person,  propertyName );
```

This example assumes that the `Person` class has a `getAddress()` method that returns an `Address` object with a `getState()` method and returns a `State` object with a `getName()` method. The emphasized code in the previous example is the equivalent of the following three lines of code:

```
Address address = person.getAddress( );

State state = address.getState( );

String stateName = state.getName( );
```



Recipe 3.6 Accessing Indexed Bean Properties

Problem

You need to access the nth element of a bean property, which is an array or a `List`.

Solution

Use `PropertyUtils.getIndex()` to retrieve an element at a specific index of an array or a `List` property. Assuming that the `chapters` property of the `Book` object is an instance of `List`, the following demonstrates the use of `getIndexProperty()` to access the first element of the list of chapters.

```
import org.apache.commons.beanutils.PropertyUtils;

// Create a new Book

Book book = new Book( );

// Create a list of Chapters

Chapter chapter1 = new Chapter( );

Chapter chapter2 = new Chapter( );

book.getChapters( ).add( chapter1 );

book.getChapters( ).add( chapter2 );

// Retrieve the first Chapter via a property name and an index.

Chapter chapter =

    (Chapter) PropertyUtils.getIndexProperty(book, "chapters[0]");
```


Discussion

There are two ways of accessing an indexed property via `PropertyUtils`: the index can be specified in the name, or it can be specified as a third parameter. The following code uses both versions of `getIndexedProperty()` to retrieve the first chapter from the list of chapters:

```
import org.apache.commons.beanutils.PropertyUtils;

Book book = new Book( );

Chapter chapter1 = new Chapter( );
Chapter chapter2 = new Chapter( );

List chapters = new ArrayList( );

chapters.add( chapter1 );
chapters.add( chapter2 );

book.setChapters( chapters );

// You can retrieve the first chapters like this...

Chapter chapterOne =
    (Chapter) PropertyUtils.getIndexedProperty( book, "chapters[0]" );

// Or... you can retrieve the first chapter like this...

chapterOne =
    (Chapter) PropertyUtils.getIndexedProperty( book, "chapters", 0 );
```

In the previous example, the first version of `getIndexedProperty()` accepts a string specifying an indexed bean property-`chapters[0]`. If this string is not well-formed, `PropertyUtils` will throw an `IllegalArgumentException`; `chapters[zero]` and `chapters['zero']` will cause an exception because neither index is an integer value, and `chapters]0[` will cause an exception because the brackets are transposed. The second call to `getIndexedProperty()` is preferred because there is less risk that a parsing error will throw an `IllegalArgumentException`.





Recipe 3.7 Accessing Mapped Bean Properties

Problem

You need to retrieve values from a bean property of type `Map`.

Solution

Use `PropertyUtils.getMappedProperty()` to obtain values from a map property. The code here retrieves the value corresponding to the key "Dining Room" from the `room map` property of the `Apartment` bean:

```
import org.apache.commons.beanutils.PropertyUtils;

Room dining = new Room( );

dining.setArea( 20 );

dining.setCarpeted( true );

dining.setFurnished( true );

Map rooms = new HashMap( );

rooms.put( "Dining Room", dining );

Apartment apartment = new Apartment( );

apartment.setRooms( rooms );

// Retrieve the Dining Room object


Room room =

    PropertyUtils.getMappedProperty( apartment, "rooms(Dining Room)" );
```

Discussion

The code shown in the Solution section retrieves the value from the `rooms` map corresponding to the key "Dining Room"-`rooms(Dining Room)`. The call to `getMappedProperty()` is the equivalent of calling `apartment.getRooms().get("Dining Room")`. [Figure 3-4](#) illustrates the structure and relationship of these two beans used, `Apartment` and `Room`.

Figure 3-4. Diagram of the Apartment and Room beans



`getMappedProperty()` works only if the specified `Map` has `String` keys. `getMappedProperty()` takes the string between (and) and retrieves the value corresponding to this string.

There is another version of `PropertyUtils.getMappedProperty()` that takes a third argument, allowing you to specify the map property in the second argument and the key in the third argument. The code here uses two different versions of `getMappedProperty()` to retrieve the same value from the `rooms` map property:

```
import java.util.Map;

import java.util.HashMap;

import org.apache.commons.beanutils.PropertyUtils;
```

```
Room dining = new Room( );

dining.setArea( 20 );

dining.setCarpeted( true );

dining.setFurnished( true );


Map rooms = new HashMap( );

rooms.put( "Dining Room", dining );
```



```
Apartment apartment = new Apartment( );

apartment.setRooms( rooms );


// Retrieve the livingRoom key

Room room =

    (Room) PropertyUtils.getMappedProperty( apartment,

        "rooms(Dining Room)" );


// Or.. retrieve the livingRoom key with 3 parameters -

// equivalent to previous

room =

    (Room) PropertyUtils.getMappedProperty( apartment, "rooms",

        "Dining Room" );
```

What was true for `getIndexedProperty()` is also true for `getMappedProperty()`. In the previous example, the first call to `getMappedProperty()` specifies a key with a string-`rooms(Dining Room)`. If `getMappedProperty()` is unable to parse this string, an `IllegalArgumentException` will be thrown; `rooms[DiningRoom]` and `rooms((DiningRoom))` will both throw `IllegalArgumentException` because the property string is not well-formed. The second call to `getMappedProperty()` reduces the risk of a property string parsing error because the key is specified in a third parameter.

Recipe 3.8 Accessing a Simple, Nested, Indexed, and Mapped Bean Property

Problem

You need to access a nested, indexed, and mapped bean property by name.

Solution

Use `PropertyUtils.getProperty()` to access any bean property. This single utility can be used to access any bean property be it simple, nested, indexed, mapped, or any combination thereof. The following example accesses a simple property, `population`, of a nested mapped property, `cities`, on an indexed property, `regions`:

```
import java.util.*;

import org.apache.commons.beanutils.PropertyUtils;

// Create a series of nested beans

City richmond = new City( );

richmond.setName( "Richmond" );

richmond.setPopulation( new Long(500000) );

Map cities = new HashMap( );

cities.put( "richmond", richmond );

Region midAtlantic = new Region( );

midAtlantic.setName( "Mid-Atlantic" );

midAtlantic.setCities( cities );
```

```
List regions = new ArrayList( );

regions.add( midAtlantic );

Country country = new Country( );

country.setName( "United States" );

country.setRegions( regions );

// Retrieve the population of Richmond

Long population =

    (Long) PropertyUtils.getProperty( country,

                                     "regions[0].cities(richmond).population" );
```

Most of this code sets up a complex nested object hierarchy to be queried by `PropertyUtils.getProperty()`. Retrieving the `regions[0].cities(richmond).population` property is the equivalent of traversing down a tree of objects and retrieving the bottom-most element-`population`.

Discussion

The emphasized code retrieves the `population` of the `City` object `richmond`; it is equivalent to the following code excerpt:

```
Region region = (Region) country.getRegions( ).get(0);

City city = (City) region.getCities( ).get("Richmond");

Long population = city.getPopulation( );
```

[Figure 3-5](#) displays the structure of these three beans: `Country`, `Region`, and `City`.

Figure 3-5. The Country, Region, and City beans



When accessing a bean property, you can use `PropertyUtils.getProperty()` in lieu of the methods introduced in the previous four recipes. The `getProperty()` method parses the supplied property name, splitting the name as the period character. Once this property has been split, this utility parses each token and passes the string to the appropriate method- `getSimpleProperty()`, `getNestedProperty()`, `getIndexedProperty()`, or `getMappedProperty()`.

See Also

Bean properties may also be retrieved using a simple expression language, such as Expression Language (EL) or Java Expression Language (JEXL). For more information about retrieving bean properties using an expression language, see [Recipe 12.1](#).

Bean properties may also be retrieved using an XPath expression. For more information, see [Recipe 12.1](#).



Recipe 3.9 Determining the Type of a Bean Property

Problem

You need to determine the type of a bean property.

Solution

Use `PropertyUtils.getPropertyType()` to determine the type of a bean property. This utility will return a `Class` object that represents the return type of the property's getter method. The following example uses this method to obtain the return type for the `author` property on the `Book` bean:

```
import org.apache.commons.beanutils.PropertyUtils

Book book = new Book( );

Class type = PropertyUtils.getPropertyType( book, "author" );

System.out.println( "book.author type: " + type.getName( ) );
```

This example retrieves and displays the type of the `author` property on `Book`, which happens to be a `Person` object. The type of the property is returned and printed to the console:

```
book.author type: org.test.Person
```

Discussion

`PropertyUtils.getPropertyType()` also works for a complex bean property. Passing a nested, indexed, or mapped bean property to this utility will return the type of the last property specified. The following code retrieves the type of a nested, indexed property- `chapters[0].name`:

```
import org.apache.commons.beanutils.PropertyUtils;
```

```
Chapter chapter = new Chapter( );

chapter.setName( "Chapter 3 BeanUtils" );

chapter.setLength( new Integer(40) );


List chapters = new ArrayList( );

chapters.add( chapter );


Book book = new Book( );

book.setName( "Jakarta Commons Cookbook" );

book.setAuthor( "Dude" );

book.setChapters( chapters );


String property = "chapters[0].name";

Class propertyType = PropertyUtils.getPropertyType(book, property);


System.out.println( property + " type: " + propertyType.getName( ) );
```

This code retrieves the type of the `name` property from an instance of the `Chapter` retrieved as an indexed property, and it prints the following output:

```
chapters[0].name type: java.lang.String
```

`PropertyUtils` contains another method to retrieve a `PropertyDescriptor`--
`PropertyUtils.getPropertyDescriptor()`. This method takes a reference to any bean property, simple or complex, and returns an object describing the type of a property and providing access to the read and write methods of a property. The following code excerpt obtains the `PropertyDescriptor` of a nested, indexed property-`chapters[0].name`:

```
String property = "chapters[0].name";


PropertyDescriptor descriptor =

    PropertyUtils.getPropertyDescriptor(book, property);
```

```
Class propertyType = descriptor.getPropertyType( );  
  
Method writeMethod = descriptor.getWriteMethod( );  
  
Method readMethod = descriptor.getReadMethod( );
```

Recipe 3.10 Comparing Beans

Problem

You need to sort or compare beans by a bean property.

Solution

Use `BeanComparator` to compare two beans using a bean property, which can be simple, nested, indexed, or mapped. `BeanComparator` obtains the value of the same bean property from two objects and, by default, compares the properties with a `ComparableComparator`. The following example sorts a list of `Country` objects using a `BeanComparator` and the default `ComparableComparator`:

```
import java.util.*;

import org.apache.commons.beanutils.BeanComparator;

Country country1 = new Country( );

country1.setName( "India" );

Country country2 = new Country( );

country2.setName( "Pakistan" );

Country country3 = new Country( );

country3.setName( "Afghanistan" );

// Create a List of Country objects

Country[] countryArray = new Country[] { country1, country2, country3 };

List countryList = Arrays.asList( countryArray );
```



```
// Sort countries by name

Comparator nameCompare = new BeanComparator( "name" );

Collections.sort( countryList, nameCompare );

System.out.println( "Sorted Countries:" );

Iterator countryIterator = countryList.iterator( );

while( countryIterator.hasNext( ) ) {

    Country country = (Country) countryIterator.next( );

    System.out.println( "\tCountry: " + country.getName( ) );

}
```

This code creates three `Country` objects with different names, places the `Country` objects into a list, and sorts this list with a `BeanComparator` configured to compare by the bean property `name`. This code executes and prints the sorted list of countries:

```
Sorted Countries:

    Country: Afghanistan


    Country: India

    Country: Pakistan
```

Discussion

The previous example demonstrated the default behavior of `BeanComparator`; when a `BeanComparator` is constructed with only one parameter, it uses a `ComparableComparator` to compare the values of the properties it retrieves. You can also construct a `BeanComparator` with an instance of `Comparator`; in this case, `BeanComparator` decorates another `Comparator`, retrieving the values of a property and passing these values on to an instance of `Comparator`. The following example demonstrates the use of `BeanComparator` with a custom `Comparator` implementation. This example involves two objects shown in [Figure 3-6](#): `ElectricVehicle` and `Engine`.

Figure 3-6. Objects involved in a sorting example



An application needs to sort `ElectricVehicle` objects by efficiency, and, in this contrived example, efficiency is defined as the number of miles per gallon times the percentage of electric operation; an 80% electric hybrid vehicle is more efficient than a 25% electric hybrid vehicle with the same mileage because of reduced emissions. The code fragments shown in [Example 3-5](#) sort a collection of beans by wrapping a custom `Comparator` with a `BeanComparator`.

Example 3-5. Decorating a Comparator with a BeanComparator

```
import java.util.*;

import org.apache.commons.beanutils.BeanComparator;

// Create Engines

Engine engine1 = new Engine( );

engine1.setMilesGallon( new Integer(60) );

engine1.setPercentElectric( new Integer(50) );

Engine engine2 = new Engine( );

engine2.setMilesGallon( new Integer(90) );

engine2.setPercentElectric( new Integer(50) );

Engine engine3 = new Engine( );

engine3.setMilesGallon( new Integer(65) );

engine3.setPercentElectric( new Integer(45) );

// Create Vehicles

ElectricVehicle vehicle1 = new ElectricVehicle( );
```

```
vehicle1.setMake( "Toy Yoda" );

vehicle1.setModel( "Electro" );

vehicle1.setYear( 2005 );

vehicle1.setEngine( engine1 );


ElectricVehicle vehicle2 = new ElectricVehicle( );

vehicle2.setMake( "Fjord" );

vehicle2.setModel( "Photon" );

vehicle2.setYear( 2004 );

vehicle2.setEngine( engine2 );


ElectricVehicle vehicle3 = new ElectricVehicle( );

vehicle3.setMake( "Ford" );

vehicle3.setModel( "Electric Pinto" );

vehicle3.setYear( 2005 );

vehicle3.setEngine( engine3 );


// Create List of Vehicles

List vehicles = new ArrayList( );

vehicle.add( vehicle1 );

vehicle.add( vehicle2 );

vehicle.add( vehicle3 );


// Define Engine Comparison Logic in an Anonymous inner class

// which implements the Comparator interface

Comparator engineCompare = new Comparator( ) {
```

```
public int compare(Object o1, Object o2) {

    Engine engine1 = (Engine) o1;

    Engine engine2 = (Engine) o2;

    int engine1Temp = engine1.getMilesGallon( ).intValue( ) *
        engine1.getPercentElectric( ).intValue( );

    int engine2Temp = engine2.getMilesGallon( ).intValue( ) *
        engine2.getPercentElectric( ).intValue( );

    Integer engine1Factor = new Integer( engine1Temp );

    Integer engine2Factor = new Integer( engine2Temp );

    return engine1Factor.compareTo( engine2Factor );

}

}

Comparator vehicleCompare = new BeanComparator( "engine", engineCompare );

Collections.sort( vehicles, vehicleCompare );

// Print Sorted Results

System.out.println( "Vehicles Sorted by Efficiency:" );

Iterator vehicleIter = vehicles.iterator( );

while( vehicleIter.hasNext( ) ) {

    ElectricVehicle vehicle = (ElectricVehicle) vehicleIter.next( );

    System.out.println( "\tVehicle: " + vehicle.getModel( ) + ", " +
        vehicle.getEngine( ).getMilesGallon( ) + " MPG, " +
```



```
        vehicle.getEngine( ).getPercentElectric( ) + "% Electric" );  
    }  
}
```

`engineCompare` contains the logic used to sort vehicles by efficiency, and `BeanComparator` supplies the `engine` properties to this `Comparator` implementation. This previous example creates three vehicles and sorts the vehicles in order of efficiency; the following results are printed:

Vehicles Sorted by Efficiency:

Vehicle: Photon, 90 MPG, 50% Electric

Vehicle: Electro, 60 MPG, 50% Electric

Vehicle: Electric Pinto, 65 MPG, 45% Electric

See Also

[Chapter 4](#) provides examples of various `Comparator` implementations, which can be used to decorate other comparators. One `Comparator` in particular is important if you plan to sort beans on a bean property, which could be `null`. If a bean property could be `null`, make sure to pass a `NullComparator` to `BeanComparator`; otherwise, `ComparableComparator` will throw a `NullPointerException` if a property value is `null`. [Recipe 4.5](#) discusses techniques for decorating a `Comparator` with `NullComparator`.

[Recipe 3.15](#) discusses a `BeanPredicate` object that can be used to validate beans. The `BeanPredicate` is similar to the `BeanComparator` as it decorates another instance of `Predicate`, providing access to a bean property.



Recipe 3.11 Copying Bean Properties

Problem

You have two instances of a bean, and you need to copy the properties of one bean to another instance of the same class.

Solution

Use `PropertyUtils.copyProperties()` to copy the properties from one bean to another. The first parameter is the destination bean, and the second parameter is the bean to copy properties from:

```
import org.apache.commons.beanutils.PropertyUtils;

Book book = new Book( );

book.setName( "Prelude to Foundation" );

book.setAuthorName( "Asimov" );

Book destinationBook = new Book( );

PropertyUtils.copyProperties( destinationBook, book );
```

After executing this code, `destinationBook.getName()` should return "Prelude to Foundation," and `destinationBook.getAuthorName()` should return "Asimov"; the `name` and `authorName` properties of `book` were both copied to `destinationBook`.

Discussion

`PropertyUtils.copyProperties()` retrieves the values of all properties from a source instance of a bean, assigning the retrieved values to a matching property on a destination instance. If the `Book` bean in the previous example had an `author` property of type `Author`, `copyProperties()` would have assigned the same reference object to the `destinationBook`. In other words,

`copyProperties()` does *not* clone the values of the bean properties. The following example demonstrates this explicitly:

```
Author author = new Author( );
```

```
author.setName( "Zinsser" );
```

```
Book book = new Book( );
```

```
book.setName( "On Writing Well" );
```

```
book.setAuthor( author );
```

```
Book destinationBook = new Book( );
```

```
PropertyUtils.copyProperties( destinationBook, book );
```

```
// At this point book and destinationBook have the same author object
```

```
if( book.getAuthor( ) == destinationBook.getAuthor( ) ) {  
    system.out.println( "Author objects identical" );  
}
```

The `author` properties of these two objects are now identical references to the same instance of the `Author` class. `copyProperties()` does not clone the values of bean properties.

`copyProperties()` can also copy the contents of a `Map` to a bean if the keys of a `Map` correspond to names of simple bean properties on the destination bean:

```
Map mapProps = new HashMap( );
```

```
mapProps.put( "name", "The Art of Computer Programming" );
```

```
mapProps.put( "author", "Knuth" );
```

```
Book destinationBook = new Book( );
```

```
PropertyUtils.copyProperties( destinationBook, mapProps );
```

See Also

If you need to clone a bean, take a look at [Recipe 3.12](#)

Recipe 3.12 Cloning a Bean

Problem

You need to clone a bean.

Solution

Use `BeanUtils.cloneBean()`. This method creates a new instance of a bean with the default constructor, and it copies every property to the new bean instance. The following instance creates a cloned instance of a `Book` object:

```
import org.apache.commons.beanutils.BeanUtils;

Book book1 = new Book( );

book1.setName( "Count of Monte Cristo" );

Book book2 = (Book) BeanUtils.cloneBean( book1 );
```

Discussion

`cloneBean()` instantiates a new instance of the bean to be cloned and calls `BeanUtils.copyProperties()` to transfer all readable bean properties to the newly instantiated bean. The following code demonstrates the steps that `cloneBean()` is taking to clone an instance of a bean:

```
Book book1 = new Book( );

book1.setName( "Practical C Programming" );

Book book2 = book1.getClass( ).newInstance( );

PropertyUtils.copyProperties( book2, book1 );
```



Recipe 3.13 Setting a Bean Property

Problem

You need to set a simple, indexed, nested, or mapped bean property by name.

Solution

Use `PropertyUtils.setProperty()` to set any bean property: simple, nested, indexed, or mapped. Pass the bean object to be modified, the name of the property, and the value to `setProperty()`; this method will call the appropriate setter method on the supplied object. The following example demonstrates the use of this method to set two properties on a `Book` bean:

```
import org.apache.commons.beanutils.PropertyUtils;

Person person1 = new Person( );

person1.setName( "Blah" );

Book book1 = new Book( );

book1.setName( "Blah" );

book1.setAuthor( "Blah" );

PropertyUtils.setProperty( book1, "name", "Some Apache Book" );

PropertyUtils.setProperty( book1, "author", new Person( ) );

PropertyUtils.setProperty( book1, "author.name", "Ken Coar" );
```

This code created an instance of the `Book` bean and the `Person` bean, and `PropertyUtils.setProperty()` set both a simple and a nested bean property.

Discussion

In addition to simple and nested bean properties, this utility can populate indexed and mapped properties. The following example demonstrates the setting of mapped and indexed bean properties on a `Book` object:

```
Book book1 = new Book( );

book1.getChapters( ).add( new Chapter( ) );

book1.getChapters( ).add( new Chapter( ) );


PropertyUtils.setProperty( book1, "name", "Apache: The Definitive Guide" );

PropertyUtils.setProperty( book1, "author", new Person( ) );

PropertyUtils.setProperty( book1, "author.name", "Laurie" );

PropertyUtils.setProperty( book1, "chapters[0].name", "Introduction" );


Apartment apartment = new Apartment( );

apartment.getRooms( ).put( "livingRoom", new Room( ) );


PropertyUtils.setProperty( apartment, "rooms(livingRoom).length",

                           new Integer(12) );
```

Assume that the `Book` bean is associated with a series of `Chapter` objects each of which have a name property. The `Book` bean has a `chapters` property, which is a list. The name of the first chapter is set by referencing the `chapters[0].name` property.



Recipe 3.14 Testing Property Access

Problem

You need to test a bean property to see if it can be read from or written to.

Solution

Use `PropertyUtils.isReadable()` and `PropertyUtils.isWritable()` to see if a bean property is readable or writable. The following code tests the `name` property of the `Book` bean to see if it is readable and writable:

```
import org.apache.commons.beanutils.PropertyUtils;

// Create a Book demonstrating the getter and setter for "name"

Book book1 = new Book();

book1.setName( "Blah" );

String name = book1.getName();

// Can we read and write "name"

boolean nameReadable = PropertyUtils.isReadable( book, "name" );

boolean nameWritable = PropertyUtils.isWritable( book, "name" );

System.out.println( "Is name readable? " + nameReadable );

System.out.println( "Is name writable? " + nameWritable );
```

The `name` property is both readable and writable, so the `nameReadable` and `nameWritable` variables will both be true. The output of this example is as follows:

```
Is name readable? true
```

```
Is name writable? true
```

Discussion

In addition to working with simple properties, `isReadable()` and `isWritable()` also work on nested, indexed, and mapped properties. The following example demonstrates the use of these methods to check access to the indexed, quadruple-nested, mapped bean property `length`:

```
Book book1 = new Book( );

book1.getChapters( ).add( new Chapter( ) );

boolean isReadable =
    PropertyUtils.isReadable( book,
        "chapters[0].author.apartment.rooms(livingRoom).length" );

boolean isWritable =
    PropertyUtils.isWritable( book,
        "chapters[0].author.apartment.rooms(livingRoom).length" );
```

`PropertyUtils.isReadable()` returns true if a specified bean property can be obtained via a public getter method, and `PropertyUtils.isWritable()` returns true if a specified bean property corresponds to a public setter method. This is an overly complex example, but it demonstrates the versatility of `PropertyUtils.isReadable()` and of `PropertyUtils.isWritable()`.



Recipe 3.15 Validating Beans with Predicates

Problem

You need to test the state of a bean, testing for the presence or absence of simple and nested bean properties.

Solution

Use a `BeanPredicate` from Commons BeanUtils. A `BeanPredicate` is an implementation of the `Predicate` interface defined in Commons Collections. As described in [Chapter 4](#), a `Predicate`'s `evaluate()` method takes an object and returns a `boolean`; `BeanPredicate` decorates another `Predicate`, allowing that `Predicate` to evaluate a bean property: simple, nested, indexed, or mapped. The following code demonstrates the use of `BeanPredicate` to validate the condition of a bean:

```
import org.apache.commons.beanutils.*;

import org.apache.commons.collections.*;

// A Predicate that returns true if the "name" property is not null

Predicate teamNotNull = new BeanPredicate( "name", new NotNullPredicate( ) );

// A Predicate that returns true if the "coach.firstName" property
// is "Tom"

Predicate coachFirstName = new BeanPredicate( "coach.firstName",

                                              new EqualsPredicate("Tom") );

// Tie two Predicates together into an AndPredicate

Predicate validateTeam = new AllPredicate( predicateArray );
```

```
// Create Team Objects

Team fish = new Team( "Swordfish", new Coach( "Tom", "O'Connell" ) );

Team hens = new Team( "Hens", new Coach( "Bob", "McGarry" ) );


boolean fishValid = validateTeam.evaluate( fish );

boolean henValid = validateTeam.evaluate( hens );


System.out.println( "Is Swordfish team valid? " + fishValid );

System.out.println( "Is Hens team valid? " + henValid );
```

Assume that the two `Team` objects contain two properties: `name` and `coach`. The `coach` property on `Team` is a `Coach` object with two properties: `firstName` and `lastName`. The first `BeanPredicate`, `teamNotNull`, uses a `NotNullPredicate` to test the simple property `name`. The second `BeanPredicate` uses an `EqualPredicate` to test the nested property `coach.firstName`. In the previous example, a `Team` object is only valid if it has a name, and the first name of the coach is "Tom." Two teams are created and the following output is printed:

```
Is Swordfish team valid? true

Is Hens team valid? false
```

Discussion

A `BeanPredicate` obtains the value of the specified bean property using `PropertyUtils` and passes the resulting property value to the `Predicate` it was constructed with; `BeanPredicate` decorates another `Predicate`. The following example demonstrates the use of `BeanPredicate`, wrapping an `EqualPredicate`, `InstanceofPredicate`, and a composite `AnyPredicate`:

```
import org.apache.commons.collections.Predicate;

import org.apache.commons.beanutils.BeanPredicate;

import org.apache.commons.collections.functors.AnyPredicate;

import org.apache.commons.collections.functors.EqualPredicate;

import org.apache.commons.collections.functors.InstanceofPredicate;

import org.apache.commons.collections.functors.OrPredicate;
```



```
// A predicate to validate the value of the age property

Predicate example1 = new BeanPredicate( "age",

    new EqualPredicate( new Integer( 10 ) );

// A predicate to validate the type of the title property

Predicate example2 = new BeanPredicate( "book[4].title",

    new InstanceofPredicate( String.class ) );

// A composite predicate definition

Predicate equalA = new EqualsPredicate("A");

Predicate equalB = new EqualsPredicate("B");

Predicate equalC = new EqualsPredicate("C");

Predicate eitherABC =

    new AnyPredicate( new Predicate[] { equalA, equalB, equalC } );

// A predicate to validate the type of the title property

Predicate example3 = new BeanPredicate( "mode", eitherABC );
```

Predicate `example1` tests the `age` property of a bean, passing the property value to an `EqualPredicate`, which returns true if age is 10. Predicate `example2` tests the property `title` from the fifth element in the `book` property; if the book's title property value is of type `String`, `example2` returns true. Predicate `example3` tests the value of the `mode` property of a bean, it evaluates to true if `mode` equals "A," "B," or "C." These three examples demonstrate that a `BeanPredicate` is a simple decorator, which allows one to apply any `Predicate` to a bean property.

See Also

[Chapter 4](#) contains more recipes focused on using `Predicate` implementations to perform complex validation and to create intelligent, self-validating collections. This recipe introduces two simple predicates; `EqualPredicate` and `NotNullPredicate` are discussed in [Recipe 4.7](#). For more information about using predicates, see [Chapter 4](#) and the Commons Collections project site at <http://jakarta.apache.org/commons/collections>.

Recipe 3.16 Creating a Map of Bean Properties

Problem

You need to create a `Map` that contains every property in a bean.

Solution

Use `PropertyUtils.describe()` to generate a `Map` containing all of the readable bean properties from a bean instance. Supply an instance of a bean and this method will return a `Map` containing all readable bean properties. The code shown here demonstrates the use of `PropertyUtils.describe()` to describe a `Person` bean:

```
import java.util.*;

import org.apache.commons.beanutils.PropertyUtils;

// Create a Person and a Book bean instance

Person person = new Person( );

person.setName( "Some Dude" );


Book book = new Book( );

book.setName( "Some Silly Computer Book" );

book.setAuthor( person );


// Describe both beans with a Map

Map bookMap = PropertyUtils.describe( book );

Map authorMap = PropertyUtils.describe( bookMap.get("book") );
```

```
System.out.println( "Book Name: " + bookMap.get( "name" ) );

System.out.println( "Author Name: " + authorMap.get( "name" ) );
```

Discussion

The previous example involves a `Book` bean with a `name` and `author` property; the `author` property is a `Person` bean with one property: `name`. The two maps, `bookMap` and `authorMap`, contain keys for every defined bean property, and two of those properties are printed out:

```
Book Name: Some Silly Computer Book

Author Name: Some Dude
```

The map returned from `PropertyUtils.describe()` is a `HashMap` that contains every property from the bean to be described. Internally, `PropertyUtils.describe()` uses `PropertyUtils.getPropertyDescriptors()` to obtain the list of properties to put into this map.

See Also

[Recipe 3.17](#) demonstrates the use of the `BeanMap` to wrap a bean and expose a bean's properties via the `Map` interface.



Recipe 3.17 Wrapping a Bean with a Map

Problem

You need to expose a bean's properties as a `Map`, and operate on the bean properties as if they were entries in a `Map`.

Solution

Wrap any bean in a `BeanMap`. This `Map` implementation uses introspection to provide access to bean properties as if they were key/value pairs in a map. This code wraps a `Person` bean with `BeanMap`, iterating through every key and accessing bean properties with `get()`:

```
import java.util.*;

import org.apache.commons.collections.BeanMap;

Person person = new Person( );

person.setName( "Jim" );

person.setAge( new Integer( 28 ) );

person.setOccupation( "Developer" );

Map beanMap = new BeanMap( person );

Set keys = beanMap.keySet( );

Iterator keyIterator = keys.iterator( );

while( keyIterator.hasNext( ) ) {

    String propertyName = (String) keyIterator.next( );
```

```
        System.out.println( "Property: " + propertyName +
                               ", Value: " + beanMap.get( propertyName ) +
                               ", Type: " + beanMap.getType( propertyName ).
                               toString( ) );
    }
}
```

The `Person` bean has the following properties: `age`, `name`, and `occupation`; an instance of this bean is created and passed to the constructor of `BeanMap`. The following output is created by iterating over the key set of `beanMap`:

```
Property: Age, Value: 28, Type: java.lang.String

Property: Name, Value: Jim, Type: java.lang.Integer

Property: Occupation, Value: Developer, Type: java.lang.String
```

Discussion

The previous example demonstrates the use of `PropertyUtils.describe()` to create a `Map` containing bean properties. `BeanMap` not only exposes bean properties with a `Map` interface, it wraps a bean instance, allowing you to alter the contents of the underlying bean via `put()`. In addition to implementing the `Map` interface, `BeanMap` provides a number of additional methods for obtaining `Method` objects and the types of bean properties. [Table 3-1](#) describes a few of these methods.

Table 3-1. Methods provided by BeanMap

Method	Description
<code>clear()</code>	Constructs a new instance of a bean using the no-argument constructor of the class that corresponds to <code>getBean().getClass()</code>
<code>clone()</code>	If possible, creates another instance of <code>BeanMap</code> , wrapping a copy of the wrapped bean
<code>getBean()</code>	Returns the bean wrapped by this <code>BeanMap</code>
<code>setBean(Object bean)</code>	Causes an instance of <code>BeanMap</code> to wrap the supplied bean
<code>getType(String name)</code>	Retrieves the type of the specified bean property
<code>getReadMethod(String name)</code>	Retrieves a <code>Method</code> object for the read method (or getter) of the specified property
<code>getWriteMethod(String name)</code>	Retrieves a <code>Method</code> object for the write method (or setter) of the specified property

[Example 3-6](#) demonstrates the use of the methods listed above to manipulate and alter properties of a `Person` bean. Remember, when you alter a `BeanMap`, you are modifying the underlying bean.

Example 3-6. BeanMap methods `getBean()`, `setBean()`, `getType()`, `getReadMethod()`, and `getWriteMethod()`

```
package com.discursive.jccook.collections;

import java.lang.reflect.Method;

import org.apache.commons.collections.BeanMap;

public class BeanMapExample {

    public static void main(String[] args) throws Exception {

        BeanMapExample example = new BeanMapExample( );

        example.start( );

    }

    public void start( ) throws Exception {

        // Create a Person bean

        Person person = new Person( );

        person.setName( "Todd" );

        person.setAge( new Integer( 45 ) );

        person.setOccupation( "Record Collector" );

        // Wrap person with a Map
```

```
BeanMap map = new BeanMap( person );

// Set the age to 24 using a Method from this map

Method method = map.getWriteMethod( "age" );

method.invoke( person, new Integer(24) );

// Set the name to "John" using map.put

map.put( "name", "John" );

// Create a Person bean

Person person2 = new Person( );

person2.setName( "Cindy" );

person2.setAge( new Integer( 39 ) );

person2.setOccupation( "Transcriptionist" );

// Make the BeanMap operate on another bean

map.setBean( person2 );

// Get the type of the Age property

Class type = map.getType( "age" );

}

}
```

See Also

`BeanMap` provides a convenient shortcut for accessing and manipulating beans, providing the same abilities that are provided by `PropertyUtils`. For more information about accessing and manipulating bean properties with `PropertyUtils`, see [Recipe 3.8](#) and [Recipe 3.13](#).



Recipe 3.18 Creating a Dynamic Bean

Problem

You need to be able to create a bean dynamically at runtime.

Solution

Use a `DynaBean`. You can create a `DynaBean` with an arbitrary set of properties at runtime, and the resulting `DynaBean` object will function properly with all Commons BeanUtils utilities, such as `PropertyUtils`. The following example demonstrates the use of a `BasicDynaBean` to model a politician:

```
import java.util.*;

import org.apache.commons.beanutils.*;

DynaProperty[] beanProperties = new DynaProperty[]{

    new DynaProperty("name", String.class),

    new DynaProperty("party", Party.class),

    new DynaProperty("votes", Long.class)

};

BasicDynaClass politicianClass =

    new BasicDynaClass("politician", BasicDynaBean.class, props);

DynaBean politician = politicianClass.newInstance( );

// Set the properties via DynaBean
```

```
politician.set( "name", "Tony Blair" );

politician.set( "party", Party.LABOUR );

politician.set( "votes", new Long( 50000000 ) );


// Set the properties with PropertyUtils

PropertyUtils.setProperty( politician, "name", "John Major" );

PropertyUtils.setProperty( politician, "party", Party.TORY );

PropertyUtils.setProperty( politician, "votes", new Long( 50000000 ) );
```

In this code, the properties of the `politician` bean are set using two different methods. The first method is to manipulate properties via the `DynaBean` interface, and the second method involves using `PropertyUtils.setProperty()`. Both regions of code accomplish the same goal, and `PropertyUtils` was included to emphasize the fact that most utilities in `BeanUtils` will understand how to work with `DynaBean` implementations.

Discussion

`DynaBean` objects come in handy when your system uses beans to represent a data model. Since a bean is just a collection of properties, you can avoid having to maintain a bean class by automatically generating a bean from a description of the objects and properties; for example, a complex data model could be described in an XML document, and a utility would parse such a document and create a number of `DynaClass` objects at runtime.

A `DynaBean` contains the methods listed in [Table 3-2](#). There are methods to get and set indexed and mapped properties, and two operations-`remove()` and `contains()`-allow you to manipulate the contents of a `Map` property.

Table 3-2. Methods available on a DynaBean

Method	Description
<code>get(String name)</code>	Retrieves a simple bean property
<code>get(String name, int i)</code>	Retrieves an indexed bean property
<code>get(String name, String key)</code>	Retrieves a mapped bean property
<code>set(String name, Object value)</code>	Sets a simple bean property
<code>set(String name, int i, Object value)</code>	Sets an indexed bean property

Method	Description
<code>set(String name, String key, Object value)</code>	Sets a mapped bean property
<code>remove(String name, String key)</code>	Removes a key from a mapped bean property
<code>contains(String name, String key)</code>	Tests a map property for the presence of a key

See Also

[Chapter 6](#) combines the power of Commons Digester and Commons BeanUtils to create a utility that reads in bean definitions from an XML document. A data model is described using an XML document, and it is realized into a set of `DynaClass` objects.

[Chapter 12](#) discusses the power of Commons BeanUtils as it relates to working with a database. A `ResultSetDynaClass` enables you to wrap a JDBC `ResultSet`.

Recipe 3.19 Getting and Setting Properties as Strings

Problem

You need to persist a bean to a text file, or populate a bean's properties from a `String`.

Solution

Use `BeanUtils` to get and set bean properties with strings. This utility contains many of the same functions as `PropertyUtils` with one major exception; instead of returning the `Object` value of the property, `BeanUtils` returns and expects a string representation of a value. The following code uses `BeanUtils` to populate a bean that is dependent on user input:

```
import java.util.*;

import org.apache.commons.beanutils.*;

Person person = new Person( );

person.setAge( new Integer( 45 ) );

person.setName( "Donald" );

person.setOccupation( "Salesman" );


// Get the Age as a String

String ageString = BeanUtils.getProperty( person, "age" );


// Set the Age from a String

BeanUtils.setProperty( person, "age", "50" );
```

Discussion

`BeanUtils` come in handy when a bean is populated from a user-supplied input like standard input or the parameters of an HTTP request. In fact, `BeanUtils` started as the mechanism used to populate a Struts `ActionForm` from the contents of an HTTP request. When the Struts `ActionServlet` receives a request that is mapped to an `Action`, the `ActionServlet` calls a method in `RequestUtils`, which examines the request and sets any properties on the relevant `ActionForm`. Because the inner workings of Struts are outside the scope of this book, [Example 3-7](#) takes a `String` input from `System.in` and sets the `age` property of `Person`.

Example 3-7. Using BeanUtils to populate a bean from user input

```
import java.io.*;

public class ReadAge {

    public static void main (String[] args) throw Exception {

        //  Prompt for an Age

        System.out.print("Enter Age: ");

        //  open up standard input

        BufferedReader br =

            new BufferedReader(new InputStreamReader(System.in));

        String ageString = null;

        ageString = br.readLine( );

        //  Set the Integer property with a String

        Person person = new Person( );

        BeanUtils.setProperty( person, "age", ageString );

    }

}
```

When `BeanUtils` sets the `age` property, it uses a set of registered `Converter` instances that are

available to translate between a `String` and an `Object`. Behind the scenes, `BeanUtils` used the `IntegerConverter` class to convert the user-supplied `String` to an `Integer` object. For a full list of converters, read the documentation for the `org.apache.commons.beanutils.converters` package.

See Also

The BeanUtils Javadoc is available at <http://jakarta.apache.org/commons/beanutils/api/index.html>.



Chapter 4. Functors

[Introduction](#)

[Recipe 4.1. Obtaining Commons Collections](#)

[Recipe 4.2. Getting the Commons Collections Source Code](#)

[Recipe 4.3. Reversing a Comparator](#)

[Recipe 4.4. Chaining Comparators](#)

[Recipe 4.5. Comparing Nulls](#)

[Recipe 4.6. Fixed-Order Comparison](#)

[Recipe 4.7. Using Simple Predicates](#)

[Recipe 4.8. Writing a Custom Predicate](#)

[Recipe 4.9. Creating Composite Predicates](#)

[Recipe 4.10. Transforming Objects](#)

[Recipe 4.11. Creating a Chain of Transformations](#)

[Recipe 4.12. Applying Conditional Transformations](#)

[Recipe 4.13. Writing a Closure](#)

[Recipe 4.14. Chaining Closures](#)

[Recipe 4.15. Modeling Conditional Statements with Closures](#)

[Recipe 4.16. Modeling Loops with Closures](#)

Introduction

The American Heritage Dictionary defines a *functor* as "one that performs an operation or a function," and, in the context of programming, a functor is an object that encapsulates "functional logic"-a functional object. So with a definition as abstract as "something that does stuff," you won't find a lot of satisfying, concise explanations of what a functor can do; in the abstract, anything that performs an operation or function could be considered a functor, and the process of drawing divisions between what should and should not be implemented with functors becomes a matter of personal preference. I'm not going to attempt to give a well-polished, textbook definition of a functor; this chapter simply demonstrates the set of basic functors from Commons Collections. Functors are less of an impressive new technology and are more of an approach to programming. Even if you are unfamiliar with the term, you've likely used functors without realizing it; two functors in common usage are `Comparator` and `Iterator`.

Both `Comparator` and `Iterator` serve to isolate an algorithm; `Comparator` encapsulates logic to compare two objects, and `Iterator` encapsulates logic used to iterate over a collection of objects. Functors often lead to more code reuse and a cleaner design because functional logic can be abstracted and extracted out of logic dealing with a specific data structure. For example, to compare two `Person` beans, you could make the `Person` class implement `Comparable` and provide a `compareTo()` method in the `Person` class, or you could write a `PersonComparator`, separating the comparison logic from the `Person` class. It is this separation of functional logic and the ability to combine functors together that make functors an interesting solution to a number of problems, from the creation of a `Closure` pipeline to a series of `Predicate` objects used to model a digital logic circuit.

Jakarta Commons Collections 3.0 introduces a set of functor interfaces in the `org.apache.commons.collections` package: `Predicate`, `Transformer`, `Factory`, and `Closure` objects. `Predicate` objects evaluate criteria or conditions, returning a `boolean` result. `Transformer` objects create a new object based on an input object, `Closure` objects act on an input object, and `Factory` objects create objects. The powerful part of functors isn't that Commons Collections has introduced a few new interfaces-the power is only evident once you realize how they can be used in concert with other Jakarta Commons utilities such as Commons BeanUtils and Commons Collections. [Chapter 5](#) makes heavy use of the functors introduced in this chapter, and [Chapter 3](#) discusses a `BeanComparator` and a `BeanPredicate`.

This chapter focuses on the functors introduced in Commons Collections 3.0 and also deals with improvements to the `Comparator` interface. Commons Collections introduces some improvements to the `Iterator` interface, but, since people usually use `Iterator` objects with `Collections`, recipes involving `Iterator` objects are in the next chapter, which covers Java Collections. Functors, part of Commons Collections, are somewhat misplaced, and, even as this chapter is written, a Commons Functor project is being finalized in the Jakarta Commons Sandbox. By the time you read this chapter, the Commons Functor project may have been released. This book assumes that you are using the functors available in the 3.0 release of Commons Collections. The Commons Functor release contains a number of changes and improvements to the set of functors introduced in Commons Collections 3.0, and, when possible, the See Also sections in each recipe discuss the relevant class or interface in the fast-developing Commons Functor project.

Recipe 4.1 Obtaining Commons Collections

Problem

You need to use Jakarta Commons Collections because your system could benefit from the various functor interfaces and implementations provided by this component.

Solution

You must download the latest version of Commons Collections and place the Commons Collections JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons Collections 3.0 instead of Commons Lang.

Discussion

Commons Collections was introduced as a series of utilities that augment the Java Collections API. Commons Collections contains functors such as `Predicate` and `Closure`, utilities for filtering and selecting elements in a collection, and some new collections: `Bag` and `Buffer`. Commons Collections is as widely used as Commons BeanUtils and Commons Lang, and with these two projects, it forms the core of the Jakarta Commons components.

If you have a Maven project that needs to use Commons Collections, add a dependency on Commons Collections 3.0 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-collections</id>

    <version>3.0</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information about the Commons Collections project, see the project page at <http://jakarta.apache.org/commons/collections>. If you have questions about using Commons Collections, feel free to join the commons-user@jakarta.apache.org mailing list. Instructions for joining the user mailing list can be found in [Recipe 1.2](#). For information on obtaining the source code for Commons Collections, see [Recipe 4.2](#).

PREV

< Day Day Up >



Recipe 4.2 Getting the Commons Collections Source Code

Problem

You need the source code for the Commons Collections project.

Solution

Download the source from <http://jakarta.apache.org/site/sourceindex.cgi>. Following the same procedure outlined in [Recipe 1.3](#), download a file named *commons-collections-3.0-src.zip* (or *commons-collections-3.0-src.tar.gz*); once you unzip this archive, you will have the source to Commons Collections in *./commons-collections-3.0-src/src*.

See Also

Most Commons components follow a similar convention for the layout of binary and source distributions. For more information about the layout of the Collections source distribution, see [Recipe 1.3](#). For information on obtaining the binary distribution for Commons Collections, see [Recipe 4.1](#).

Recipe 4.3 Reversing a Comparator

Problem

You need to reverse the effects of a `Comparator`. You need to return less than when this `Comparator` returns greater than, and greater than when it returns less than.

Solution

Use `ReverseComparator` to reverse the effects of a `Comparator`. Supply an existing `Comparator` to the constructor of `ReverseComparator`, and it reverses the effects of that `Comparator`. The following example demonstrates the use of `ReverseComparator` to reverse the result of a custom `MyComparator` instance:

```
Comparator myComparator = new MyComparator( );

Comparator reverseComparator = new ReverseComparator( myComparator );

Book book1 = new Book( );

Book book2 = new Book( );

int comparison = myComparator.compare( book1, book2 );

int reversedComparison = reverseComparator( book1, book2 );
```

The value of `reversedComparison` is simply the negative of `comparison`; if `MyComparator` decides that `book1` is less than `book2`, the `ReverseComparator` returns the opposite result-greater than. `ReverseComparator` simply wraps the original `Comparator` and multiplies the result by negative one.

Discussion

[Example 4-1](#) is an implementation of a `Comparator` that is reversed using the `ReverseComparator`. This `BookComparator` compares two `Book` objects by the `name` and `author` bean properties. Sorting a

list of books using this `Comparator` results in a list sorted alphabetically by book name and author name; if two books have the same name, they are sorted by author name.

Example 4-1. A Comparator that compares Book objects by name and author

```
package com.discursive.jccook.collections.compare;

import java.util.*;

import org.apache.commons.lang.StringUtils;

import org.apache.commons.collections.comparators.ReverseComparator;

public class BookComparator implements Comparator {

    public int compare(Object o1, Object o2) {

        int comparison = -1;

        if( o1 instanceof Book && o2 instanceof Book ) {

            Book b1 = (Book) o1;

            Book b2 = (Book) o2;

            String b1Name = b1.getName( );

            String b2Name = b2.getName( );

            String b1Author = b1.getAuthor( );

            String b2Author = b2.getAuthor( );

            if( StringUtils.isEmpty( b1Name ) &&
```

```
        StringUtils.isEmpty( b2Name ) ) {

            comparison = b1Name.compareTo( b2Name );

        }

        if( comparison == 0 &&

            StringUtils.isEmpty( b1Author ) &&

            StringUtils.isEmpty( b2Author ) ) {

            comparison = b1Author.compareTo( b2Author );

        }

    }

    return comparison;

}

}
```

[Example 4-2](#) sorts an array of `Book` objects in reverse order.

Example 4-2. Using ReverseComparator to sort Book objects

```
package com.discursive.jccook.collections.compare;

import java.util.*;

import org.apache.commons.collections.comparators.ReverseComparator;

public class ReverseExample {

    public static void main(String[] args) throws Exception {

        ReverseExample example = new ReverseExample( );

        example.start( );

    }

}
```



```
}
```

```
public void start( ) throws Exception {

    // Create a Reversed BookComparator

    Comparator bookCompare = new BookComparator( );

    Comparator reverseComparator = new ReverseComparator( bookComparator );

    // Create a List of Book objects

    List books = new ArrayList( );

    Book book1 = new Book( );

    book1.setName( "TitleA" );

    book1.setAuthor( "John" );

    books.add( book1 );

    Book book2 = new Book( );

    book2.setName( "TitleB" );

    book2.setAuthor( "Donald" );

    books.add( book2 );

    Book book3 = new Book( );

    book3.setName( "TitleA" );

    book3.setAuthor( "Doug" );

    books.add( book3 );
```

```
        // Sort the List of Book objects with the Reversed BookComparator

        Collections.sort( books, reverseComparator );

    }

}
```

After `Collections.sort()`, the `books` array is sorted in reverse alphabetical order by book name and author name: "TitleB by Donald" followed by "TitleA by John" followed by "TitleA by Doug."

See Also

If you were using a simple `Comparator` to sort an array, you could sort and reverse the resulting array with `Arrays.reverse()`, or you could reverse a `List` with `Collections.reverse()`. Wrapping a `Comparator` in `ReverseComparator` may help you avoid the call to `reverse()`, but the benefit is miniscule. `ReverseComparator` makes more sense when used in the context of a `ChainedComparator`; see [Recipe 4.4](#) for more information about the `ChainedComparator`.

Note that use of `StringUtils.isEmpty()` is used in `BookComparator` to check if either of the bean properties are null or blank. This utility, is from `StringUtils`, and it is introduced in [Recipe 2.2](#).



Recipe 4.4 Chaining Comparators

Problem

You need to sort a collection of objects by more than one property.

Solution

Use `ComparatorChain` to create a series of `Comparator` objects that appear as a single `Comparator`. A `ComparatorChain` compares two objects with each `Comparator` in the chain until a `Comparator` returns a nonzero value. If a `Comparator` returns equality (zero), the `ComparatorChain` then moves to the next `Comparator` to obtain another comparison. The following example demonstrates the use of chained `BeanComparators`; if two `Person` objects have the same `lastName`, the chain created in this example tries to compare the objects by `firstName`:

```
Person person1 = new Person( );

person1.setLastName( "Payne" );

person1.setFirstName( "James" );

person1.setAge( 21 );
```

```
Person person2 = new Person( );

person2.setLastName( "Payne" );

person2.setFirstName( "James" );

person2.setAge( 85 );
```

```
Person person3 = new Person( );

person3.setLastName( "Payne" );

person3.setFirstName( "Susan" );

person3.setAge( 29 );
```

```

Person[] persons = new Person[] { person1, person2, person3 };

ComparatorChain comparatorChain = new ComparatorChain( );

comparatorChain.addComparator( new BeanComparator( "lastName" ) );

comparatorChain.addComparator( new BeanComparator( "firstName" ) );

comparatorChain.addComparator( new BeanComparator( "age" ), true );

Arrays.sort( persons, comparatorChain );

```

This example sorts an array of `Person` objects: by `lastName` ascending, `firstName` ascending, and `age` descending. The sorted `persons` array will be in the following order: the older James Payne, the younger James Payne, followed by Susan Payne. The `ChainedComparator` successfully sorts two objects with the same first and last names-falling back to the age to provide the correct sort order.

Discussion

A `ComparatorChain` evaluates every `Comparator` in the chain as needed. If the current `Comparator` returns a zero, the next `Comparator` is invoked until there are no more `Comparator` objects left in the chain. If the final `Comparator` returns a zero value, the `ComparatorChain` returns a zero. The `ComparatorChain` implements the `Comparator` interface and is an aggregate of other `Comparator` objects; it can be used wherever a `Comparator` is used, including array sorting and as a `Comparator` for a tree-based `Collection` implementation.

The `ReverseComparator` (introduced in [Recipe 4.3](#)) makes more sense in light of the `ComparatorChain`. If you need to sort a collection of objects for display, you might want to reverse a particular `Comparator` in a `ComparatorChain`. In the previous example, there are two people named "James Payne": one is 21 and the other is 85. Your application respects age and you want to put the older James Payne in front of the younger James Payne in the sorted list. Sorting by `lastName` ascending, `firstName` ascending, and `age` descending calls for the last `Comparator` in the chain to be reversed; the following code calls `addComparator()` with a second parameter, `true`, causing the `BeanComparator` for `age` to be reversed with `ReverseComparator`:

```

comparatorChain.addComparator( new BeanComparator( "age" ), true );

```

The previous statement is equivalent to the following code:

```

comparaterChain.addComparator( new ReverseComparator

```



```
(new BeanComparator("age") );
```

Using a `ComparatorChain` may remind you of the way a result set is sorted in a SQL `SELECT` statement. This recipe's Solution implements the following SQL statement in a `ComparatorChain`:

```
SELECT * FROM person ORDER BY lastName ASC, firstName ASC, age DESC;
```

Where to Sort?

In many organizations, there is a debate over where to sort data in an application: should sorting be done in the database or in an application server? The answer depends on a number of factors, but, now that you have seen how a `ComparatorChain` works, you can implement *any* complex sort in Java. The use of a `ComparatorChain` is especially relevant if you are writing a web application that presents a sortable table and you have decided to implement sorting logic in your presentation layer. If you are sorting beans, load your data into a collection and use a `ComparatorChain` made up of `BeanComparators`.

See Also

The `BeanComparator` was introduced in the previous chapter; for more information, see [Recipe 3.10](#). The `ReverseComparator` was introduced in [Recipe 4.3](#).



Recipe 4.5 Comparing Nulls

Problem

You need to sort an object array that contains `null` elements, and you want to have control over whether the `null` values are at the beginning or end of a sorted array.

Solution

Wrap your `Comparator` in a `NullComparator` from Commons Collections. The `NullComparator` can sort `null` values higher or lower than non-`null` values, depending on options passed into the constructor. The following example shows a custom `BookComparator` wrapped with a `NullComparator`:

```
import org.apache.commons.collections.comparators.NullComparator;
```

```
import java.util.*;
```

```
Comparator bookComparator = new BookComparator( );
```

```
Comparator nullComparator = new NullComparator( BookComparator );
```

```
Book[] bookArray = new Book[] { new Book( ), null, new Book( ) };
```

```
Arrays.sort( bookArray, nullComparator );
```

This example sorts an array of `Book` objects, placing `null` at the end of the sorted array; after the sort, `bookArray` contains two `Book` objects at index zero and index one and a `null` reference at index two.

If a `Comparator` does not handle `null` values gracefully, wrap it in a `NullComparator` and avoid a `NullPointerException`.

Discussion

To configure `NullComparator` to sort `null` values as less than non-`null` values, pass `false` to the constructor of `NullComparator`; to sort `null` values as greater than non-`null` values, pass `true`. By default, `null` values are sorted higher:

```
// null is less than non-null

Comparator nullComparator = new NullComparator( bookComparator, false );
```

```
// null is greater than non-null (default)

Comparator nullComparator = new NullComparator( bookComparator, true );
```

While the `NullComparator` usually decorates another instance of `Comparator`, the `NullComparator` can also be used by itself to compare `null` and non-`null` objects, as in the following example:

```
Comparator nullHighComparator = new NullComparator( );

Comparator nullLowComparator = new NullComparator(false);
```

```
// Returns 1

nullHighComparator.compare( null, new Double(3.0) );
```

```
// Returns -1

nullLowComparator.compare( null, new Double(3.0) );
```

```
// Returns 0

nullLowComparator.compare( null, null );
```

See Also

Both `ReverseComparator` and `NullComparator` are objects that decorate an existing `Comparator`. Take note of the decorator pattern as it is a common pattern used throughout Commons Collections. For more information about the decorator design pattern, read *Design Patterns: Elements of Reusable Object-Oriented Software* (Addison Wesley).

Recipe 4.6 Fixed-Order Comparison

Problem

You need to sort a collection of objects that have a preestablished order, such as the days of the week or the order of planets in the solar system.

Solution

Use `FixedOrderComparator` in Jakarta Commons Collections. When using `FixedOrderComparator`, you supply an array of objects in a sorted order and the `Comparator` returns comparison results based on the order of the objects in this array. The following example uses a fixed string array to compare different Olympic medals:

```
import java.util.*;

import org.apache.commons.beanutils.BeanComparator;

import org.apache.commons.collections.comparators.FixedOrderComparator;

String[] medalOrder = {"tin", "bronze", "silver", "gold", "platinum"};

Comparator medalComparator = new FixedOrderComparator( medalOrder );

Comparator athleteComparator = new BeanComparator( "medal", medalComparator );

Athlete athlete1 = new Athlete( );

Athlete athlete2 = new Athlete( );

int compare = medalComparator.compare( athlete1.getMedal( ),
athlete2.getMedal( ) );
```

In this code, a `FixedOrderComparator` compares two `Athletes` by the value of the `medal` property. The `medal` property can be "tin," "bronze," "silver," "gold," or "platinum," and a `FixedOrderComparator` uses the order of the `medalOrder` array to compare these values. The `medalOrder` array establishes a fixed relationship between the three medal types; "bronze" is less than "silver," which is less than "gold."

Discussion

Use `FixedOrderComparator` when sorting an array or a collection that contains values that are ordered in a pre-determined fashion: days of the week, planets in the solar system, colors in the spectrum, or hands dealt in a poker game. One way to sort an array containing the days of the week would be to assign a numerical value to each day-"Monday" is one, "Tuesday" is two, "Wednesday" is three, etc. Then you could sort the array with a `Comparator` that takes each day's name, sorting elements based on the numerical value corresponding to a day's name. An alternative is the use of `FixedOrderComparator`, letting the comparator order objects based on the order of an array of day names.

If a bean contains a property to be sorted according to a fixed-order array, you can use the `BeanComparator` in conjunction with `FixedOrderComparator`. The following example sorts cards by value and suit using a `FixedOrderComparator` and a `BeanComparator`; A `PlayingCard` object, defined in [Example 4-3](#), is sorted according to the order of two arrays-one for the face value of the `PlayingCard` and one for the suit of the `PlayingCard`.

Example 4-3. A bean representing a playing card

```
package org.discursive.jccook.collections.compare;
```

```
public class PlayingCard( ) {

    public static String JOKER_VALUE = null;

    public static String JOKER_SUIT = null;

    private String value;

    private String suit;

    public PlayingCard( ) {}

    public PlayingCard(String value, String suit) {
```

```

        this.value = value;

        this.suit = suit;
    }

    public String getValue( ) { return value; }

    public void setValue(String value) { this.value = value; }

    public String getSuit( ) { return suit; }

    public void setSuit(String suit) { this.suit = suit; }

    public String toString( ) {

        String cardString = "JOKER";

        if( value != null && suit != null ) {

            cardString = value + suit;

        }

        return cardString;

    }
}

```

[Example 4-4](#) creates a `ComparatorChain` of `BeanComparators`, which compares the `value` and `suit` properties using a `FixedOrderComparator`. Each card's suit is compared first, and, if two cards have the same suit, they are compared by face value. Jokers do not have suits or a face value, and this example handles jokers with a `null`-valued `suit` and `value` property by wrapping each `FixedOrderComparator` with a `NullComparator`.

Example 4-4. Combining FixedOrderComparator with BeanComparator, NullComparator, and ComparatorChain

```
package com.discursive.jccook.collections.compare;
```

```
import java.util.ArrayList;

import java.util.Comparator;

import java.util.List;


import org.apache.commons.beanutils.BeanComparator;


import org.apache.commons.collections.comparators.NullComparator;

import org.apache.commons.collections.comparators.FixedOrderComparator;

import org.apache.commons.collections.comparators.ComparatorChain;


public class FixedOrderExample {


    // Suit order "Spades", "Clubs", "Diamonds", "Hearts"

    private String[] suitOrder = { "S", "C", "D", "H" };


    private String[] valueOrder = { "2", "3", "4", "5", "6", "7", "8",
                                     "9", "10", "J", "Q", "K", "A" };


    public static void main(String[] args) {

        FixedOrderExample example = new FixedOrderExample( );

        example.start( );

    }


    public void start( ) {


        List cards = new ArrayList( );
```



```
cards.add( PlayingCard( "J", "C" ) );

cards.add( PlayingCard( "2", "H" ) );

cards.add( PlayingCard( PlayingCard.JOKER_VALUE, PlayingCard.
JOKER_SUIT));

cards.add( PlayingCard( "2", "S" ) );

cards.add( PlayingCard( "Q", "S" ) );

cards.add( PlayingCard( "4", "C" ) );

cards.add( PlayingCard( "J", "D" ) );


    System.out.println( "Before sorting: " + printCards( cards ) );


// Create a null-safe suit order comparator that will compare the
// suit property of two Java beans

Comparator suitComparator = new FixedOrderComparator( suitOrder );

suitComparator = new NullComparator( suitComparator );

suitComparator = new BeanComparator( "suit", suitComparator );


// Create a null-safe value order comparator that will compare the
// value property of two Java beans

Comparator valueComparator = new FixedOrderComparator( valueOrder );

valueComparator = new NullComparator( valueComparator );

valueComparator = new BeanComparator( "value", valueComparator );


// Create a chain of comparators to sort a deck of cards

Comparator cardComparator = new ComparatorChain( );

cardComparator.addComparator( suitComparator );
```

```

        cardComparator.addComparator( valueComparator );

        Collections.sort( cards, cardComparator );

        System.out.println( "After sorting: " + printCards( cards ) );
    }

    private String printCards( List cards ) {

        StringBuffer resultBuffer = new StringBuffer( );

        Iterator cardIter = cards.iterator( );

        while( cardIter.hasNext( ) ) {

            PlayingCard card = (PlayingCard) cards.next( );

            resultBuffer.append( " " + card.toString( ) );

        }

        return resultBuffer.toString( );

    }

}

```

This example sorts the `PlayingCard` objects and produces the following output:

Before sorting: JC 2H JOKER 2S QS 4C JD

After sorting: 2S QS 4C JC JD 2H JOKER

The list is sorted such that all the cards of a similar suit are grouped together-spades are less than clubs, clubs are less than diamonds, and diamonds are less than hearts. A sorted collection of cards is grouped by suits, and, within each suit, cards are organized according to face value-2 is low and aces is high. The order used in the sorting is captured in two fixed-order arrays, `suitOrder` and `faceOrder`. If a shuffled deck were used in the example, it would end up as a perfectly sorted deck of cards.

[Example 4-4](#) ties a number of simple `Comparators` together to perform a fairly complex sort. A `FixedOrderComparator` is wrapped in a `NullComparator`, which is then wrapped with a `BeanComparator`. These `BeanComparator` instances are then combined in a `ComparatorChain`. The

use of `NullComparator` with a `BeanComparator` is recommended to avoid a `NullPointerException` from `BeanComparator`; `BeanComparator` is not designed to handle `null`-valued bean properties, and it throws an exception if you ask it to play nice with `nulls`.

See Also

`BeanComparator` is discussed in [Recipe 3.10](#). This helpful utility is indispensable if you are working with systems that need to sort JavaBeans.

For more information about the `ComparatorChain` object, see [Recipe 4.4](#). For more information on the `NullComparator`, see [Recipe 4.5](#).



Recipe 4.7 Using Simple Predicates

Problem

You need to perform logic that is predicated on a certain condition being satisfied, and you want to encapsulate this condition in an object.

Solution

Use a `Predicate` to evaluate a criteria or a condition. A `Predicate` is an object that evaluates another object and returns `true` or `false`; predicates are used throughout the Commons Collections packages for filtering, selecting, and validating the contents of collections. This code demonstrates the use of simple predicates to test the type and contents of an object:

```
import org.apache.commons.collection.Predicate;

import org.apache.commons.collection.functors.*;

String name = "Tim";

Predicate nameJohn = new EqualPredicate( "John" );

Predicate nameTim = new EqualPredicate( "Tim" );

Predicate instanceString = new InstanceofPredicate( String.class );

Predicate instanceDouble = new InstanceofPredicate( Double.class );

// Testing all predicates for "Tim"

System.out.println( "Is Name John?: " + nameJohn.evaluate( name ) );

System.out.println( "Is Name Tim?: " + nameTim.evaluate( name ) );

System.out.println( "Is this a String?: " + instanceString.evaluate( name ) );
```



```
System.out.println( "Is this a Double?: " + instanceDouble.evaluate( name ) );
```

The previous example tests the `name` object against a few `Predicate` implementations producing the following console output:

```
Is Name John?: false
```

```
Is Name Tim?: true
```

```
Is this a String?: true
```

```
Is this a Double?: false
```

The string "Tim" is subjected to various `Predicate` tests. The first two `EqualPredicate` objects test the contents of the string, returning `true` if the object being evaluated is equal to the object passed into the `EqualPredicate`'s constructor. The last two `Predicate` objects are `InstanceofPredicate` instances, which test the type of object being evaluated; if an `InstanceofPredicate` constructor is passed to the `String` class, it returns `true` if the object being evaluated is a `java.lang.String` type.

Discussion

The simple `Predicate` interface is central to a number of utilities introduced in this chapter. To implement `Predicate`, define an `evaluate()` method that returns a `boolean`; a `Predicate` is a function object (or functor) that captures a criteria in an object that can be created and altered at runtime. Creating and evaluating a `Predicate` is just as valid as writing an `if` statement; for example, the code in the Solution of this recipe could have been implemented as a series of `if` statements:

```
String name = "Tim";
```

```
if( name.equals( "John" ) ) {  
  
    System.out.println( "The name is John." );  
  
}
```

```
if( name.equals( "Tim" ) ) {  
  
    System.out.println( "The name is Tim." );  
  
}
```

```
if( name instanceof String ) ) {  
  
    System.out.println( "name is as String object" );  
  
}  
  
if( name instanceof Double ) ) {  
  
    System.out.println( "name is as Double object" );  
  
}
```

`Predicate` instances capture an `if` statement in an object, and if you are going to constantly change the behavior of your application, you might want to consider placing conditional expressions in `Predicate` instances. For example, if a system is designed to classify a storm as being a hurricane, you may want to capture all of your classification criteria in an XML file-parsing this file at runtime and creating a series of `Predicate` objects. A storm is a hurricane when the winds exceed a certain value, and the barometric pressure falls below a certain point. But, in a few years those criteria might change to involve a new, or more complex, set of measurements. If your decision logic is encapsulated in a `Predicate` object, it will be easier to upgrade the program to take new criteria into account; all of this logic will be encapsulated in an instance of `Predicate`.

Commons Collections provides a number of basic predicates for common situations, such as testing to see if an object equals another object (`EqualPredicate`), or that an object is of a certain type (`InstanceOfPredicate`). [Table 4-1](#) lists a number of simple `Predicate` implementations.

Table 4-1. Predicate implementations

Name	Description
<code>EqualPredicate</code>	Compares each object to an object passed via a constructor-returning true if the two are equal.
<code>IdentityPredicate</code>	Returns true if the object being evaluated is the same object reference as the object passed to its constructor. The <code>IdentityPredicate</code> uses the <code>==</code> operator to compare two object references.
<code>NotPredicate</code>	Wraps a <code>Predicate</code> and returns the opposite result.
<code>InstanceOfPredicate</code>	Returns <code>true</code> if the object being evaluated matches the type passed into its constructor.
<code>NullPredicate</code> <code>NullIsTruePredicate</code>	Returns true if the object being evaluated is <code>null</code> .
<code>NotNullPredicate</code> <code>NullIsFalsePredicate</code>	Returns true if the object being evaluated is not <code>null</code> .
<code>TruePredicate</code>	Always returns <code>true</code> .

Name	Description
FalsePredicate	Always returns <code>false</code> .
UniquePredicate	Returns <code>true</code> if it is the first time a particular object has been evaluated. The <code>UniquePredicate</code> maintains a <code>HashSet</code> of objects it has evaluated; if an object is already in that <code>HashSet</code> , this <code>Predicate</code> returns <code>false</code> . <code>UniquePredicate</code> can be used to select distinct objects from a collection.

The following example demonstrates simple `Predicate` objects with a test for equality, inequality, and equality by identity:

```
import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.*;

...

String testName = "Ben";

Predicate equals = new EqualPredicate( testName );

Predicate notEquals = new NotPredicate( equals );

Predicate identity = new IdentityPredicate( testName );

System.out.println( "Does name equal 'Ben'? " + equals.evaluate( "Ben" ) );

System.out.println( "Is object 'Ben'? " + identity.evaluate( testName ) );

System.out.println( "Does name equal 'Tim'? " + equals.evaluate( "Tim" ) );

System.out.println( "Does name not equal 'Tim'? " + notEquals.
evaluate( "Tim" ) );

System.out.println( "Is object 'Tim'? " + identity.evaluate( "Tim" ) );
```

This code demonstrates the use of `Predicate` objects to determine if objects are equal or if two object references reference the same instance. When executed, the following is output to the console:


```
Does name equal 'Ben'? true
```

```
Is object 'Ben'? true
```

```
Does name equal 'Tim'? false
```

```
Does name not equal 'Tim'? true
```

```
Is object 'Tim'? false
```

The following code demonstrates simple predicates that test for the presence or absence of `null` or if an object being evaluated is of a certain type. The example also demonstrates the use of a `UniquePredicate` that returns `true` when it encounters an object for the first time:

```
import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.*;

String nullString = null;

Double testDouble = new Double(3.4);

Predicate isString = new InstanceofPredicate( String.class );
Predicate isLong = new InstanceofPredicate( Long.class );
Predicate isNumber = new InstanceofPredicate( Number.class );

Predicate isNotNull = NotNullPredicate.INSTANCE;
Predicate isNull = NullPredicate.INSTANCE;

Predicate unique = new UniquePredicate( );

System.out.println("'nullString' not null?: " + isNotNull.
evaluate(nullString));

System.out.println("'nullString' null?: " + isNull.evaluate(nullString));
```



```
System.out.println("'testDouble' a String?: " + isString.  
evaluate(testDouble));  
  
System.out.println("'testDouble' a Long?: " + isLong.evaluate(testDouble));  
  
System.out.println("'testDouble' a Number?: " + isNumber.  
evaluate(testDouble));  
  
  
System.out.println("'A' Unique?: " + unique.evaluate("A"));  
  
System.out.println("'C' Unique?: " + unique.evaluate("C"));  
  
System.out.println("'A' Unique?: " + unique.evaluate("A"));  
  
System.out.println("'B' Unique?: " + unique.evaluate("B"));
```

The sample evaluates objects against the `InstanceOfPredicate`, the `NullPredicate`, the `NotNullPredicate`, and the `UniquePredicate`, and the following is output to the console:

```
'nullString' not null?: false  
  
'nullString' null?: true  
  
  
'testDouble' a String?: false  
  
'testDouble' a Long?: false  
  
'testDouble' a Number?: true  
  
  
'A' Unique?: true  
  
'C' Unique?: true  
  
'A' Unique?: false  
  
'B' Unique?: true
```

The `UniquePredicate` returns `false` the second time it encounters "A." The `Double` object `testDouble` is shown to be a `Number` object, and the `nullString` is evaluated as non-`null`.

See Also

This recipe mentions function pointers in C and C++. Function pointers are pointers to the address of a function, and they allow for some interesting logical acrobatics. For more information about function pointers in C and C++, see <http://www.function-pointer.org/>.

`Predicate`, `Closure`, and `Transformer` are all functor objects that are used throughout the Commons Collections component. You may be familiar with functors if you have used the Standard Template Library (STL) in C++. STL documentation contains rigorous definitions for function objects and predicates. For more information about functors in STL, see <http://www.sgi.com/tech/stl/functors.html>.

PREV

< Day Day Up >



Recipe 4.8 Writing a Custom Predicate

Problem

You need to evaluate an object to see if it meets criteria, and you want to capture these criteria in a custom `Predicate`.

Solution

Implement the `Predicate` interface and capture your logic in an `evaluate()` method. [Example 4-5](#) is a simple `Predicate` implementation that always returns `true`; it is intended as a basic example of how to implement the `Predicate` interface.

Example 4-5. A simple Predicate implementation

```
import org.apache.commons.collections.Predicate;

public class SimplePredicate implements Predicate {

    public boolean evaluate(Object object) {

        // do something.

        boolean result = true;

        return result;

    }

}
```

Discussion

`Predicates` can be used in any number of situations, such as validating user input, filtering a `Collection`, or just as a replacement for complex conditional logic. A `Predicate` can be as simple or as complex as you need it to be; the only contract it must satisfy is the production of a `boolean` result from an `evaluate()` method.

To demonstrate the process of writing a fairly complex implementation of the `Predicate` interface, a contrived example is developed in [Example 4-6](#). Your application evaluates the condition of the space shuttle and makes a determination for launch-go or no go. Some of the criteria include the temperature of the launch pad, the status of the crew, and the presence (or absence) of fuel. In the end, your boss is looking for thumbs up or thumbs down, and you decide to write a program that returns a `boolean` decision. This decision is implemented in the `LaunchPredicate` class.

Example 4-6. Implementing the Predicate interface

```
package com.discursive.jccook.collections.predicate;

import org.apache.commons.collections.Predicate;

public class LaunchPredicate implements Predicate {

    public LaunchPredicate( ) {}

    public boolean evaluate(Object object) {

        boolean launchGo = false;

        LaunchStats stats = (LaunchStats) object;

        boolean crewReady = stats.isCrewPresent( ) && stats.isCrewHealthy( );

        boolean fueled = stats.isShuttleFueled( ) && stats.
            isFuelIgnitionReady( );

        boolean withinLaunchWindow = stats.isLaunchWindowOpen( );

        boolean properWeather =
            ( stats.temperature( ) > 35 ) &&
            ( !stats.isLightningDangerPresent( ) );
```



```
        // Check the crew, fuel, and launch time

        if( crewReady && fueled && withinLaunchWindow ) {

            launchGo = true;

        }

        // Override a GO decision if the weather is bad

        if( !properWeather ) {

            launchGo = false;

        }

        return launchGo;

    }

}
```

A shuttle launch is predicated on the presence and health of the crew, the state of the fuel, and the time of the launch event. A final weather check is performed to ensure that the temperature of the shuttle is not below 35 degrees Fahrenheit. If this critical temperature limit is not met, the **Predicate** overrides the previous decision to launch. Using a **LaunchPredicate** encapsulates your decision logic in one object, making it easier to upgrade, maintain, and test this decision process. Your unit tests can pass a mock object to this predicate, testing every possible permutation of possible inputs. The following example demonstrates the use of the **LaunchPredicate**:

```
LaunchPredicate launchDecision = new LaunchPredicate( );
```

```
LaunchStats stats = measureLaunchStatistics( );
```

```
if( launchDecision.evaluate( stats ) ) {

    System.out.println( "We are Go for Ignition." );

} else {

    System.out.println( "Abort mission." );

}
```

```
}
```

See Also

The real Space Shuttle Launch Team has the outrageously complex job of monitoring and controlling every aspect of launching a spacecraft, and I'm sure that NASA doesn't implement the `Predicate` interface from Jakarta Commons Collections. While it isn't related to the topic of open source Java programming, it is a fascinatingly complex piece of software that maintains a shuttle launch. It is written in something called high-order assembly language/shuttle (HAL/S). If you are interested in learning more about one of the most complex pieces of software, take a look at NASA's Space Shuttle Launch Team website at <http://science.ksc.nasa.gov/shuttle/countdown/launch-team.html>. (Besides, I'm sure you are amused that NASA controls spacecraft with an assembly language known as HAL.)

This recipe mentions the use of a mock object to test a `Predicate`. One of the attractions of using a `Predicate` to encapsulate any complex condition is the ability to write a test for this condition logic; *mock objects* are a method of unit testing that involves passing a mock implementation of an object to a class in a test. For more information about mock objects, see <http://www.mockobjects.com/>.

Recipe 4.9 Creating Composite Predicates

Problem

You need to perform complex conditional logic using multiple `Predicate` objects, and you need to combine and expose multiple criteria as one `Predicate`.

Solution

To combine several `Predicate` instances, create a `Predicate` to capture each portion of a compound condition, and combine each condition with `AndPredicate`, `OrPredicate`, `AllPredicate`, `OnePredicate`, `AnyPredicate`, or `NonePredicate`. All of these predicate implementations are used to combine the results of multiple predicates-creating a compound predicate. The following code demonstrates the use of the `AndPredicate`, `OrPredicate`, `AllPredicate`, and `OnePredicate`:

```
import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.*;

// Create Base Predicates

Predicate isTim = new EqualsPredicate("Tim");

Predicate isDouble = new InstanceOfPredicate( Double.class );

Predicate isNotNull = NotNullPredicate.INSTANCE;

Predicate[] predicates = new Predicate[] { isTim, isDouble, isNotNull };

// Create 2 argument logical predicate composites

Predicate andPredicate = new AndPredicate( isTim, isNotNull );

Predicate orPredicate = new OrPredicate( isTim, isNotNull );
```

```
// Create n-argument logical predicate composites

Predicate allPredicate = new AllPredicate( predicates );

Predicate onePredicate = new OnePredicate( predicates );

System.out.println( "'Tim' and not null?: " + andPredicate.
    evaluate( "Tim" ) );

System.out.println( "'Tim' or not null?: " + andPredicate.
    evaluate(new Long(3)) );

System.out.println( "'Tim', not null, and Double?: "
    + allPredicate.evaluate( "Impossible" ) );

System.out.println( "XOR ('Tim', not null, or Double?): "
    + allPredicate.evaluate( "Impossible" ) );
```

This example creates the following output:

```
'Tim' and not null?: true

'Tim' or not null?: true


'Tim', not null, and Double?: false

XOR('Tim', not null, or Double?): true
```

Discussion

An `AndPredicate` returns `true` if both predicates supplied to its constructor return `true`, and an `OrPredicate` returns `true` if at least one of the two predicates passed to its constructor returns `true`. An `AllPredicate` takes an array of predicates, only returning `true` if every predicate evaluates to `true`. The `OnePredicate` also takes an array of predicates, only returning `true` if exactly one predicate evaluates to `true`.

In the code sample, the use of the second to last predicate, `AllPredicate`, is impossible to satisfy; an object can never be a `String` and a `Double` at the same time. This example fails to demonstrate `AnyPredicate` and `NonePredicate`-both take an array of predicates. `AnyPredicate` returns `true` if

any of the predicates evaluate to `true`, and `NonePredicate` returns `true` only if none of the predicates evaluate to `true`. The behavior of these objects is easily inferred from the names: `And`, `Or`, `All`, `One`, `Any`, or `None`.

Any logical expression can be modeled by connecting `Predicate` objects together- similar to the way that simple logic gates are connected to create complex digital logic. Logical inputs (1 and 0) are routed to logic gates (`AND`, `OR`, `NOR`, `NAND`, `XOR`, etc.), and the outputs of a logic circuit are a result of stages that perform the same function as the `Predicate` objects introduced in this recipe. In the next example, a logic circuit will be used to demonstrate a complex hierarchy of `Predicate` objects; a circuit diagram is drawn, and a series of predicates are developed to model this circuit. [Figure 4-1](#) contains a logical expression that is implemented with digital logic and `Predicate` objects.

Figure 4-1. Logical expression to be modeled with Predicate

Assuming that every letter corresponds to a `boolean` variable, this expression corresponds to the circuit diagram in [Figure 4-2](#). Each gate can be modeled as a composite `Predicate`, and from [Figure 4-2](#) it is clear that this example will include two `AndPredicates`, an `OrPredicate`, and a `NotPredicate`. The "AND" gate is modeled with an `AndPredicate`, and an "OR" gate with an `OrPredicate`. The "NAND" gate is transformed into a three-input "AND" gate followed by an inverter that is modeled with an `AllPredicate` wrapped in a `NotPredicate`.

Figure 4-2. Circuit representing logical expression

The system has five inputs, which will be stored in a `Map` with five keys: `A`, `B`, `C`, `D`, and `E`. A simple `InputPredicate` is developed to handle the inputs to the system-a map of `Boolean` input objects is passed to the top-level `Predicate`. An `InputPredicate` is configured to evaluate the input `Map` and return the `boolean` value of one of the inputs; in other words, an `InputPredicate` selects a `boolean` value from a `Map`, always returning the value of that input from the `Map` it evaluates. (See [Example 4-7](#).)

Example 4-7. `InputPredicate`: a predicate that selects an input from a `Map`

```
package com.discursive.jccook.collections.predicate;
```

```
import org.apache.commons.collections.Predicate;

public class InputPredicate implements Predicate {

    private String inputKey;

    public BooleanPredicate(String inputKey) {

        this.inputKey = inputKey;

    }

    public boolean evaluate(Object object) {

        boolean satisfies = false;

        Map inputMap = (Map) object;

        Boolean input = (Boolean) inputMap.get( inputKey );

        if( input != null ) {

            satisfies = input.booleanValue( );

        }

        return satisfies;

    }

}
```

The entire circuit is modeled by one top-level `Predicate` and a `Map` of `Boolean` input signals is passed down a hierarchy of predicates as needed. Unlike a real circuit, where inputs would cause gates to fire sequentially, the predicate hierarchy is evaluated from the final stage backward-the example evaluates the `Predicate` variable `circuit`. The input map is passed to the top-most `Predicate`, which, in turn, passes this same map to the `Predicate` that precedes it in the circuit.

[Example 4-8](#) ties everything together, and the logic to create our circuit-modeling predicate has been confined to the `createPredicate()` method.

Example 4-8. Implementing a multilevel composite Predicate

```
package com.discursive.jccook.collections.predicate;

import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.*;

public class CompoundPredicateExample {

    public static void main(String[] args) {

        CompoundPredicateExample example = new CompoundPredicateExample( );

        example.start( );

    }

    public void start( ) {

        Predicate circuit = createPredicate( );

        Object[] inputsArray =

            new Object[][] { {"A", Boolean.TRUE},

                            {"B", Boolean.FALSE},

                            {"C", Boolean.TRUE},

                            {"D", Boolean.FALSE},

                            {"E", Boolean.FALSE} };

        Map inputs = ArrayUtils.toMap( inputsArray );

        boolean result = circuit.evaluate( inputs );
```

```
        System.out.println( "The circuit fired?: " + result );
    }

    public Predicate createPredicate( ) {

        Predicate aPredicate = new InputPredicate("A");

        Predicate bPredicate = new InputPredicate("B");

        Predicate cPredicate = new InputPredicate("C");

        Predicate dPredicate = new InputPredicate("D");

        Predicate ePredicate = new InputPredicate("E");

        Predicate expression1 = new AndPredicate( aPredicate, bPredicate );

        Predicate expression2 = new OrPredicate( cPredicate, dPredicate );

        Predicate[] secondLevel =

            new Predicate( ) { expression1, expression2, ePredicate };

        Predicate topLevel = new NotPredicate( secondLevel );

        return topLevel;
    }
}
```

This code prints `The circuit fired?: true`. This complex example has demonstrated the process of modeling composite, multistage logic with a hierarchy of predicates. `APredicate` is the most basic functor and when combined with other `Predicate` instances, there is no limit to the level of complexity that can be achieved. Logic circuits were used in this example because a logic gate is a great analogy for a `Predicate`. Think of a `Predicate` as a component-a gate in a logic circuit.

Recipe 4.10 Transforming Objects

Problem

You need to perform a transformation, taking an object and creating a new object.

Solution

Implement the `Transformer` interface. A `Transformer` takes an object and returns a new object instance. The following example demonstrates the `joinArmyTransformer`; the `transform()` method takes a `Recruit` object instance and returns a `Soldier` object:

```
import org.apache.commons.collections.Transformer;

Transformer joinArmy = new Transformer( ) {

    public Object transform(Object input) {

        Recruit recruit = (Recruit) input;

        BootCamp.obstacleCourse( recruit );

        Soldier soldier = BootCamp.graduate( recruit );

    }

}

Recruit recruit1 = new Recruit("Pat T.");

System.out.println( "Status before transformation: " + recruit );

Soldier soldier1 = (Soldier) joinArmy.transform( recruit1 );

System.out.println( "Status after transformation: " + soldier );
```

A `Recruit` object is passed to the `joinArmy.transform()` method, and a `Soldier` object is returned. The state of the `recruit` and `soldier` instances are printed before and after the transformation:

```
Status before transformation: Pat T., Recruit
```

```
Status after transformation: Pat T., Soldier
```

Discussion

This object isolates and encapsulates a transition; a system that needs to translate between two domain models or two object types should encapsulate such a transition in a `Transformer`. `Transformer` may be something of a misnomer. When an object undergoes a transformation, it is common to think of an object being modified or acted upon, but this is contrary to the design of the `Transformer` interface. The Javadoc for `Transformer` expressly states, "The original object is left unchanged." [Figure 4-3](#) illustrates the simple `joinArmy Transformer`.

Figure 4-3. Diagram of the joinArmy Transformer

See Also

Jakarta Commons Functor in the Commons Sandbox expands on the initial functors introduced in Commons Collections, introducing a `UnaryFunction` object that provides a simple interface equivalent to `Transformer`. For more information about `UnaryFunction`, see the Commons Functor page at <http://jakarta.apache.org/commons/sandbox/functor>.

Recipe 4.11 Creating a Chain of Transformations

Problem

You have a series of transformations and you need to chain them together, passing the output of one stage to the input of the next.

Solution

Create multiple implementations of `Transformer`, and chain them together with `ChainedTransformer`. A `ChainedTransformer` takes an array of `Transformer` objects, passing the output of each `Transformer` to the next `Transformer` in the chain. The following example demonstrates a `ChainedTransformer` with two `Transformer` stages. The first stage, `multiply`, multiplies a number by 100, and the second stage, `increment`, adds one to the result from the first stage:

```
import org.apache.commons.collections.Transformer;

import org.apache.commons.collections.functors.ChainedTransformer;

Transformer multiply = new Transformer( ) {

    public Object transform(Object input) {

        Long number = (Long) input;

        return( new Long( number.longValue( ) * 100 ) );

    }

}

Transformer increment = new Transformer( ) {

    public Object transform(Object input) {

        Long number = (Long) input;

        return( new Long( number.longValue( ) + 1 ) );

    }

}
```

```
        }
    }

    Transformer[] chainElements = new Transformer[] { multiply, increment };

    Transformer chain = new ChainedTransformer( chainElements );

    Long original = new Long( 34 );

    Long result = chain.transform( original );

    System.out.println( "Original: " + original );

    System.out.println( "Result: " + result );
```

The `Transformer` chain takes the `Long` instance `original` and transforms it into a result:

Original: 34

Result: 3401

Discussion

Since a `Transformer` leaves the input parameter passed to `transform()` intact, this two-stage `ChainedTransformer` creates a new instance of `Long` for each stage in the `ChainedTransformer`. A `Long` is passed to the first stage, `multiply`, which transforms 34 to 3400. The result from the first stage, 3400, is then passed to the second stage, `increment`, which produces the final `Long` result, 3401. A real example would involve more complex implementations of `Transformer`, but this simple example demonstrates the mechanics of creating a simple pipeline of transformations, one leading to another. [Figure 4-4](#) illustrates the simple structure of this two-staged `ChainedTransformer`.

Figure 4-4. A ChainedTransformer with two Transformers

See Also

Jakarta Commons Functor in the Commons Sandbox introduces a `UnaryFunction` interface that provides an interface equivalent to `Transformer`, and multiple `UnaryFunction` instances can be chained together using the `CompositeUnaryFunction` class. For more information about `CompositeUnaryFunction`, see the Commons Functor page at <http://jakarta.apache.org/commons/sandbox/functor>.

Recipe 4.12 Applying Conditional Transformations

Problem

You need to perform a different transformation depending on a series of conditions or cases.

Solution

Use a `SwitchTransformer` to apply a `Transformer` that is dependent on a `Predicate`. A `SwitchTransformer` models a `switch` statement, and it takes three parameters: an array of `Predicate` instances, an array of `Transformer` instances, and a default `Transformer`. [Example 4-9](#) uses a `SwitchTransformer` to apply a different `Transformer` implementation to odd and even numbers.

Example 4-9. Using a SwitchTransformer

```
Transformer oddTransform = new Transformer( ) {  
  
    public Object transform(Object input) {  
  
        Integer number = new Integer( input );  
  
        return ( new Integer( number.intValue( ) * 2 ) );  
  
    }  
  
}
```

```
Transformer evenTransform = new Transformer( ) {  
  
    public Object transform(Object input) {  
  
        Integer number = new Integer( input );  
  
        return ( new Integer( number.intValue( ) * 3 ) );  
  
    }  
  
}
```

```
Predicate isEven = new Predicate( ) {

    public boolean evaluate(Object input) {

        Integer number = (Integer) input;

        return( number.intValue( ) % 2 == 0 );

    }

}

Predicate isOdd = new NotPredicate(isEven);

Predicate[] pArray = new Predicate[] { isOdd, isEven };

Transformer[] tArray = new Transformer[] { oddTransform, evenTransform };

Transform predicateTransform =

    new SwitchTransform( pArray, tArray, new NOPTransformer( ) );

Integer one = new Integer( 1 );

Integer two = new Integer( 2 );

Integer three = new Integer( 3 );

Integer four = new Integer( 4 );

System.out.println( "Transform of 1 = " + predicateTransform.
transform( one ) );

System.out.println( "Transform of 2 = " + predicateTransform.
transform( two ) );

System.out.println( "Transform of 3 = " + predicateTransform.
```

```
transform( three ) );

System.out.println( "Transform of 4 = " + predicateTransform.

transform( four ) );
```

If an object being transformed satisfies the `isOdd Predicate`, it is passed to the `oddTransform Transformer`. If an object being transformed satisfies the `isEven Predicate`, it is passed to the `evenTransform Predicate`. If the object satisfies neither `Predicate`, it is passed to an instance of `NOPTransformer`, which is a `Transformer` implementation that returns the object passed to `transform()`:

```
Transform of 1 = 2

Transform of 2 = 6

Transform of 3 = 6

Transform of 4 = 12
```

Discussion

The array of `Predicate` instances and the array of `Transformer` instances passed to the constructor of `SwitchTransformer` must be of equal length. The `SwitchTransformer` evaluates each of the `Predicate` instances in the array. If a `Predicate` evaluates to `true`, the `SwitchTransformer` retrieves the `Transformer` that corresponds to the matching `Predicate`. If no `Predicate` evaluates to `true`, the `SwitchTransformer` passes the object being transformed to the third parameter-the default `Transformer`. In [Example 4-9](#), the default `Transformer` was a `NOPTransformer`, which is a `Transformer` implementation that performs no transformation and returns the object passed to `transform()`. [Figure 4-5](#) illustrates the `SwitchTransformer` from the Solution; the two `Predicate` instances correspond to two `Transformer` instances.

Figure 4-5. A SwitchTransform with two Predicate instances, two Transformer instances, and a default Transformer

See Also

Jakarta Commons Functor in the Commons Sandbox introduces a `UnaryFunction` interface that provides an interface equivalent to `Transformer`. A `UnaryFunction` can be predicated with a `UnaryPredicate` object via the `ConditionalUnaryFunction` class. For more information about `UnaryPredicate` and `ConditionalUnaryFunction`, see the Commons Functor page at <http://jakarta.apache.org/commons/sandbox/functor>.

Recipe 4.13 Writing a Closure

Problem

You need a functor that operates on an object.

Solution

Use a `Closure` to encapsulate a block of code that acts on an object. In this example, a `discount Closure` operates on a `Product` object, reducing the price by 10 percent:

```
Closure discount = new Closure( ) {  
  
    int count = 0;  
  
    public int getCount( ) { return count; }  
  
    public void execute(Object input) {  
  
        count++;  
  
        (Product) product = (Product) input;  
  
        product.setPrice( product.getPrice( ) * 0.90 );  
  
    }  
}  
  
Product shoes = new Product( );  
  
shoes.setName( "Fancy Shoes" );  
  
shoes.setPrice( 120.00 );  
  
System.out.println( "Shoes before discount: " + shoes );
```

```
discount.execute( shoes );

System.out.println( "Shoes after discount: " + shoes );

discount.execute( shoes );

discount.execute( shoes );

System.out.println( "Shoes after " + discount.getcount( ) +

                    " discounts: " + shoes );
```

The example prints out the original cost of `shoes` (\$120) and then proceeds to discount `shoes` and print out the discounted price. The `Product` object, `shoes`, is modified by the `discount Closure` three separate times:

```
Shoes before discount: Fancy Shoes for $120.00
```

```
Shoes after discount: Fancy Shoes for $108.00
```

```
Shoes after 3 discounts: Fancy Shoes for $87.48
```

Discussion

A `Closure` operates on the input object passed to the `execute()` method, while a `Transformer` does not alter the object passed to `transform()`. Use `Closure` if your system needs to act on an object. Like the `Transformer` and `Predicate` interfaces, there are a number of `Closure` implementations that can be used to chain and combine `Closure` instances.

See Also

Jakarta Commons Functor in the Commons Sandbox expands on the initial functors introduced in Commons Collections, introducing a `UnaryProcedure` object that provides a simple interface equivalent to `Closure`. For more information about `UnaryProcedure`, see the Commons Functor page at <http://jakarta.apache.org/commons/sandbox/functor>.

Problem

An object needs to be acted on by a series of **Closure** instances.

Solution

Use `ChainedClosure` to create a chain of `Closure` instances that appears as a single `Closure`. A `ChainedClosure` takes an array of `Closure` objects and passes the same object sequentially to each `Closure` in the chain. This example sends an object through a `ChainedClosure` containing two stages that modify different properties on the object:

```
Closure fuel = new Closure( ) {

    public void execute(Object input) {

        Shuttle shuttle = (Shuttle) input;

        shuttle.setFuelPercent( 100.0 );

    }

}
```

```
Closure repairShielding = new Closure( ) {  
  
    public void execute(Object input) {  
  
        Shuttle shuttle = (Shuttle) input;  
  
        shuttle.setShieldingReady( true );  
  
    }  
  
}
```

```
Closure[] cArray = new Closure[] { repairShielding, fuel };
```



```
Closure preLaunch = new ChainedClosure( cArray );

Shuttle endeavour = new Shuttle( );

endeavour.setName( "Endeavour" );

System.out.println( "Shuttle before preLaunch: " + shuttle );

preLaunch.execute( endeavour );

System.out.println( "Shuttle after preLaunch: " + shuttle );
```

A `Shuttle` object is passed through a `ChainedClosure`, `preLaunch`, which consists of the stages `fuel` and `repairShielding`. These two `Closure` objects each modify the internal state of the `Shuttle` object, which is printed out both before and after the execution of the `preLaunch Closure`:

Shuttle before preLaunch: Shuttle Endeavour has no fuel and no shielding.

Shuttle before preLaunch: Shuttle Endeavour is fueled and is ready for reentry.

Discussion

This example should remind you of [Recipe 4.11](#). When chaining `Transformer` objects, the result of each transformation is passed between stages-the results of stage one are passed to stage two, the results of stage two are passed to stage three, and so on. A `ChainedClosure` is different; the same object is passed to each `Closure` in sequence like a car moving through a factory assembly line.

See Also

Jakarta Commons Functor in the Commons Sandbox introduces a `UnaryProcedure` interface that is equivalent to `Closure`. Two or more `UnaryProcedure` instances can be chained together using the `CompositeUnaryProcedure` class. For more information about `CompositeUnaryProcedure`, see the Commons Functor page at <http://jakarta.apache.org/commons/sandbox/functor>.



Recipe 4.15 Modeling Conditional Statements with Closures

Problem

You need to model a conditional statement with functors.

Solution

Use an `IfClosure`, supplying a `Predicate` and two `Closure` objects. If the `Predicate` evaluates to `true`, the first `Closure` is executed; if the `Predicate` evaluates to `false`, the second `Closure` is executed. The following closure deals with a financial decision; a `Predicate`, `isWinning`, evaluates a `Stock` object. If the purchase price is less than the current price, the stock is a winner, causing the `buy Closure` to be executed. If the purchase price is higher than the current price, the stock is a loser and it is sold by passing it to the `sell Closure`:

```
Closure sell = new Closure( ) {  
  
    public void execute(Object input) {  
  
        Stock stock = (Stock) input;  
  
        stock.sell( stock.getShares( ) );  
  
        System.out.println( "\tSold all shares" );  
  
    }  
  
}
```

```
Closure buy = new Closure( ) {  
  
    public void execute(Object input) {  
  
        Stock stock = (Stock) input;  
  
        int buyShares = stock.getShares( ) * 0.10;  
  
        stock.buy( buyShares );  
  
    }  
  
}
```

```
        System.out.println( "\tBought " + buyShares );
    }
}

Predicate isWinning = new Predicate( ) {
    public boolean evaluate(Object object) {
        Stock stock = (Stock) object;

        if( stock.getPurchasePrice( ) < stock.getCurrentPrice( ) ) {
            System.out.println( stock.getSymbol( ) + " is a winner";
            return true;
        } else {
            System.out.println( stock.getSymbol( ) + " is a loser";
            return false;
        }
    }
}
```

```
Closure stockAction = new IfClosure( isWinning, buy, sell );
```

```
Stock yahoo = new Stock("YHOO");
yahoo.setPurchasePrice( 10.0 );
yahoo.setCurrentPrice( 20.0 );
yahoo.setShares( 100 );
```

```
Stock tibco = new Stock("TIB");
tibco.setPurchasePrice( 50.0 );
```

```
tibco.setCurrentPrice( 30.0 );

tibco.setShares( 50 );

// Execute the IfClosure, take action on stocks based on performance

stockAction.execute( yahoo );

stockAction.execute( tibco );
```

The example evaluates two stocks, a winner and a loser. The following output is generated:

```
YHOO is a winner

    Bought 10 shares

TIB is a loser

    Sold All Shares
```

Discussion

Because an `IfClosure` is an implementation of a `Closure`, you can nest `IfClosures` within other `IfClosures`. The following code uses the `Closure` objects and the `Predicate` defined in the Solution, adding a third `Closure`, `isUnchanged`, to create a nested `IfClosure--sellOrHold`:

```
Predicate isUnchanged = new Predicate( ) {

    public boolean evaluate(Object object) {

        Stock stock = (Stock) object;

        if( stock.getPurchasePrice( ) == stock.getCurrentPrice( ) ) {

            System.out.println( stock.getSymbol( ) + " is unchanged";

            return true;

        }

        return false;

    }

}
```



```
Closure sellOrHold = new IfClosure( isUnchanged, new NOPClosure( ), sell );

Closure stockAction = new IfClosure( isWinning, buy, sellOrHold );


Stock tibco = new Stock("TIB");

tibco.setPurchasePrice( 50.0 );

tibco.setCurrentPrice( 30.0 );

tibco.setShares( 50 );


Stock lucent = new Stock("LU");

tibco.setPurchasePrice( 30.0 );

tibco.setCurrentPrice( 30.0 );

tibco.setShares( 150 );


stockAction.execute( tibco );

stockAction.execute( lucent );
```

When `stockAction` is executed, and a `Stock` does not satisfy the `isWinning Predicate`, it is passed to the `sellOrHold Closure`, which is another `IfClosure`. The `sellOrHold Closure` then evaluates the `Stock` to see if it is a loser or unchanged. If the stock price is unchanged, it is passed to a `NOPClosure`, which performs no operation on the `Stock` object. If the stock price is less than the purchase price, the `Stock` is passed to the `sell Closure`.

Recipe 4.16 Modeling Loops with Closures

Problem

You need to execute a `Closure` multiple times.

Solution

Use a `WhileClosure`, passing in a `Predicate` and a `Closure`. The `WhileClosure` will execute the `Closure` as long as a `Predicate` evaluates to `true`. The following example demonstrates a `Closure` named `drive`, which operates on a `Car` object and a `Predicate` named `hasFuel`, which evaluates the `Car` object. Each time a `Car` is passed to `drive`, a gallon of fuel is used, and `hasFuel` will evaluate to `true` if the amount of fuel in a car is greater than zero. The `WhileClosure`, `useAllFuel`, evaluates `drive` until `hasFuel` evaluates to `false`:

```
import org.apache.commons.collections.Closure;

import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.WhileClosure;
```

```
Closure drive = new Closure( ) {

    public void execute(Object input) {

        Car car = (Car) input;

        car.setFuel( car.getFuel( ) - 1 );

    }

}
```

```
Predicate hasFuel = new Predicate( ) {

    public boolean evaluate(Object object) {

        Car car = (Car) input;
```

```
        return car.getFuel( ) > 0;
    }
}

Closure useAllFuel = new WhileFuel( hasFuel, drive );

Car car = new Car( );

car.setMakeModel( "Ford Escort" );

car.setFuel( 20 );

System.out.println( "Car before while closure: " + car );

useAllFuel.execute( car );

System.out.println( "Car after while closure: " + car );
```

The `WhileClosure`, `useAllFuel`, takes a `Car` object, executing a `Closure` and evaluating a `Predicate` after every execution. The state of the car is printed both before and after it is passed to the `WhileClosure`:

Car before while closure: Ford Escort with 20 gallons of fuel.

Car after while closure: Ford Escort with no fuel.

Discussion

If you need to execute a `Closure` a set number of times, you can also use a `ForClosure`, passing in an `int` that specifies the number of times an object is passed to the `execute()` method of a `Closure`. This example uses the same `Closure` defined in the Solution, but, this time, the `drive Closure` is only executed five times:

```
Closure driveSome = new ForClosure( 5, drive );
```

```
Car car = new Car( );

car.setMakeModel( "Toyota Camry" );
```

```
car.setFuel( 20 );

System.out.println( "Car before for closure: " + car );

driveSome.execute( car );

System.out.println( "Car after for closure: " + car );
```

Since the `driveSome Closure` is called only five times, the Camry still has 15 gallons after the `ForClosure` is executed:

```
Car before for closure: Toyota Camry with 20 gallons of fuel.

Car after for closure: Toyota Camry with 15 gallons of fuel.
```


Chapter 5. Collections

[Introduction](#)

[Recipe 5.1. Obtaining Commons Collections](#)

[Recipe 5.2. Using a Looping Iterator](#)

[Recipe 5.3. Iterating Over an ArrayList](#)

[Recipe 5.4. Filtering a Collection with a Predicate](#)

[Recipe 5.5. Iterating Through Distinct Elements](#)

[Recipe 5.6. Using a Bag](#)

[Recipe 5.7. Using a Buffer](#)

[Recipe 5.8. Creating a Priority Queue](#)

[Recipe 5.9. Using a Blocking Buffer](#)

[Recipe 5.10. Storing Multiple Values in a Map](#)

[Recipe 5.11. Retrieving a Key by a Value](#)

[Recipe 5.12. Using a Case-Insensitive Map](#)

[Recipe 5.13. Creating Typed Collections and Maps](#)

[Recipe 5.14. Constraining Map Values](#)

[Recipe 5.15. Constraining List Contents](#)

[Recipe 5.16. Transforming Collections](#)

[Recipe 5.17. Creating a Least Recently Used Cache](#)

[Recipe 5.18. Using a Lazy Map](#)

[Recipe 5.19. Counting Objects in a Collection](#)

[Recipe 5.20. Performing Set Operations](#)

[Recipe 5.21. Retrieving Map Values Without Casting](#)



Introduction

Java 2 Standard Edition (J2SE) introduced the Collections API-a dramatic improvement over `Vector` and `Hashtable` in Java 1.1. This new API provides `Set`, `List`, `Map`, and `Iterator` interfaces with various implementations addressing different needs for different applications. Despite the additions and improvements, there are still gaps in the Java's Collections API-functionality that is addressed by a supplemental library, Jakarta Commons Collections. Most of the features introduced in Jakarta Commons Collections are easily anticipated extensions of the Java 2 platform: a reversible `Comparator` or a `Bag` interface, for example. Other concepts in Commons Collections are innovative additions to the J2SE-predicated collections, self-validating collections, set operations, and lazy collections using transformers. Commons Collections 3.0 also introduces the concept of functors (see [Chapter 4](#)).

Java 5.0 (a.k.a. Tiger) has introduced a number of new language features and improvements to the Collections API. A `Queue` class and type-safe generics are two major additions that will become available to most programmers with the production-ready release of 5.0. Some recipes in this chapter introduce utilities that overlap the functionality of 5.0, and, if a recipe introduces a utility with an analog in 5.0, an effort has been made to identify any opportunity to achieve the same result with new 5.0 classes and features.



Recipe 5.1 Obtaining Commons Collections

Problem

You need to use Jakarta Commons Collections because your application makes heavy use of `Collection` objects, and you wish to use some of the utilities provided by this component.

Solution

Commons Collections was introduced in [Chapter 4](#). For instructions on obtaining Collections, see [Recipe 4.1](#).

See Also

For more information about the Commons Collections project, see the project page at <http://jakarta.apache.org/commons/collections>. If you have questions about using Commons Collections, feel free to join the commons-user@jakarta.apache.org mailing list. Instructions for joining the user mailing list can be found in [Recipe 1.2](#). For information on obtaining the source code for Commons Collections, see [Recipe 4.2](#).

Recipe 5.2 Using a Looping Iterator

Problem

You need to loop through the contents of a `Collection`.

Solution

Use a `LoopingIterator` to repeatedly iterate through the contents of a `Collection`. Pass an existing `Collection` to the constructor of `LoopingIterator`, and call `iterator()`. The following code uses a `LoopingIterator` to retrieve five items from a `List` with three items:

```
List drivers = new ArrayList( );

drivers.add( "Chris" );
drivers.add( "Sean" );
drivers.add( "Kathy" );

LoopingIterator loopingIterator = new LoopingIterator( drivers );

for( int i = 1; i <= 5; i++ ) {

    String driver = (String) loopingIterator.next( );

    System.out.println( "Driver for Day " + i + ": " + driver );

}
```

The previous example simulates the selection of a driver in a car pool with three drivers. Five drivers are selected, and the `LoopingIterator` returns the first item in the `List` on the fourth day:

Driver for Day 1: Chris

Driver for Day 2: Sean

Driver for Day 3: Kathy

Driver for Day 4: Chris

Driver for Day 5: Sean

Discussion

Keep in mind that a `LoopingIterator` never stops iterating; `hasNext()` always returns `true` in a `LoopingIterator`. If you are using a `LoopingIterator` with a `while` loop, be sure to code an exit condition. A `LoopingIterator` is appropriate for a situation in which a series of values must be repeatedly evaluated, or a loop of commands must be repeatedly executed. An application, for example, may have a series of components that need to be continuously updated, or a series of queues or buffers that need to be continuously tested or monitored-an event loop, for example.

The `LoopingIterator` also implements the Commons Collections interface `ResettableIterator`; this extension of the `Iterator` interface can be reset to start at the beginning of a `Collection`. When using a `ResettableIterator`, call `reset()` to jump back to the beginning of a `Collection`:

```
List items = new ArrayList( );

items.add( "Item 1" );
items.add( "Item 2" );
items.add( "Item 3" );

LoopingIterator iterator = new LoopingIterator( items );

// Print out two elements from the LoopingIterator
System.out.println( iterator.next( ) );
System.out.println( iterator.next( ) );

// Reset iterator to start of List
System.out.println( "Reset" );

iterator.reset( );
```

```
// Print out two elements from the LoopingIterator

System.out.println( iterator.next( ) );

System.out.println( iterator.next( ) );
```

This example iterates over the first two elements in a `List` before calling `reset()`. After calling `reset()`, the code calls `next()` twice, printing out the first two elements, as shown below:

```
Item 1

Item 2

Reset

Item 1

Item 2
```

See Also

[Recipe 5.3](#) deals with another implementation of `ResettableIterator`, `ArrayListIterator`, which can be used to iterate over a subset of elements in an `ArrayList`.

Recipe 5.3 Iterating Over an ArrayList

Problem

You need to iterate over a portion of an `ArrayList`. For example, you have an `ArrayList` with 30 elements, and you need to iterate from index 0 to index 20.

Solution

Use an `ArrayListIterator` to iterate through a specified region of an `ArrayList`. This implementation of `Iterator` is constructed with a reference to an `ArrayList` and two optional parameters that specify the start and end of an iteration. This example demonstrates the use of `ArrayListIterator` to iterate over the 3rd, 4th, and 5th elements of an `ArrayList`:

```
String[] strings = new String[] { "A", "B", "C", "D", "E", "F" };

List list = new ArrayList( Arrays.asList( strings ) );

Iterator iterator = new ArrayListIterator( list, 3, 6 );

while( iterator.hasNext( ) ) {

    int index = iterator.nextIndex( );

    String element = (String) iterator.next( );

    System.out.println( "Element at " + index + ": " + element );

}
```

`ArrayListIterator` also allows you to obtain the index of an element during an iteration. In the previous example, `iterator.nextIndex()` returns the index of the element returned by the subsequent call to `iterator.next()`. The code above iterates through three elements of the `ArrayList`, producing the following output:

```
Element at 3: D

Element at 4: E

Element at 5: F
```

Discussion

You can construct an `ArrayListIterator` with up to three arguments. The first argument is the `ArrayList` to be iterated over. The second optional argument specifies the inclusive start index, and the third optional argument specifies the exclusive end index. If only two parameters are supplied to the constructor, the `ArrayListIterator` will iterate until the end of the `ArrayList` is reached. The following code demonstrates the three constructors of `ArrayListIterator`:

```
String[] strings = new String[] { "A", "B", "C", "D", "E", "F" };

List list = new ArrayList( Arrays.asList( strings ) );

// Iterate over all elements

Iterator iterator1 = new ArrayListIterator( list );

// Iterate over "C", "D", "E", "F"

Iterator iterator2 = new ArrayListIterator( list, 2 );

// Iterate over "B", "C", "D"

Iterator iterator3 = new ArrayListIterator( list, 1, 4 );
```

`ArrayListIterator` implements the `ResettableIterator` interface, which provides one function: `reset()`. The `reset()` method takes the iterator back to the beginning of an iteration. After a reset a call to `next()` returns the first element that an `ArrayListIterator` has been configured to return-the element at the index specified in the constructor's optional second parameter. An `ArrayListIterator` also provides a way to set the current element: the `set()` method takes an object parameter and changes the contents of the underlying `ArrayList`. The following example demonstrates both the `reset()` and `set()` methods on `ArrayListIterator`:

```
String[] strings = new String[] { "A", "B", "C", "D", "E", "F" };

List list = new ArrayList( Arrays.asList( strings ) );

System.out.println( "Original List: " + Arrays.toString( list.toArray( ) ) );
```



```
ResettableIterator iterator = new ArrayListIterator( list, 2 );

// Retrieve an Element from the List

int index = iterator.nextIndex( );

String element = (String) iterator.next( );

System.out.println( "Element at " + index + ": " + element );

// Set the Current Element

iterator.set( "G" );

System.out.println( "Modifying index: " + index + " to G");

// Retrieve the Next Element from the List

index = iterator.nextIndex( );

element = (String) iterator.next( );

System.out.println( "Element at " + index + ": " + element );

// Set the Current Element

iterator.set( "H" );

System.out.println( "Modifying index: " + index + " to H");

// Reset the Iterator (Go to beginning of iteration)

iterator.reset( );

System.out.println( "Reset" );

index = iterator.nextIndex( );

element = (String) iterator.next( );
```

```
System.out.println( "Element at " + index + ": " + element );

System.out.println( "Modified List: " + Arrays.toString( list.toArray( ) ) );
```

This example iterates through the `ArrayList`, modifying two elements before calling `reset()`. The following output shows that after a `reset()`, the first element returns the value, which was supplied to `set()`:

```
Original List: {A,B,C,D,E,F}

Element at 2: C

Modifying index: 2 to G

Element at 3: D

Modifying index: 3 to H

Reset

Element at 2: G

Modified List: {A,B,G,H,E,F}
```

See Also

If you need to iterate over an array or an object array, use two related implementations of `Iterator`: `ArrayIterator` and `ObjectArrayIterator`. See the Commons Collections project page at <http://jakarta.apache.org/commons/collections> for more information about these `Iterator` implementations.

Recipe 5.4 Filtering a Collection with a Predicate

Problem

You need to iterate through elements of a `Collection` that match a specified condition. Or, you have a `Collection` from which you need to remove elements not satisfying a condition.

Solution

Create a `FilterIterator` with a `Predicate`; if the `Predicate` returns `true` for an element, that element will be included in the `Iterator`. The `FilterIterator` decorates another `Iterator` and provides the ability to apply an arbitrary filter to a `Collection`. In the following example, `Earthquake` beans are kept in an `ArrayList` that is filtered using the `majorQuakePredicate` and a `FilterIterator`:

```
import org.apache.commons.collection.Predicate;

import org.apache.commons.collection.iterators.FilterIterator;

List quakes = new ArrayList( );

Earthquake quake1 = new Earthquake( );

quake1.setLocation( "Chicago, IL" );

quake1.setIntensity( new Float( 6.4f ) );

quake1.setIntensity( new Float( 634.23f ) );

quake1.setTime( new Date( ) );

quakes.add( quake1 );

Earthquake quake2 = new Earthquake( );

quake2.setLocation( "San Francisco, CA" );
```

```

quake2.setIntensity( new Float( 4.4f ) );

quake2.setIntensity( new Float( 63.23f ) );

quake2.setTime( new Date( ) );

quakes.add( quake2 );

Predicate majorQuakePredicate =

    new MajorQuakePredicate( new Float(5.0), new Float(1000.0) );

Iterator majorQuakes =

    new FilterIterator( quakes.iterator( ), majorQuakePredicate );

while( majorQuakes.hasMore( ) ) {

    EarthQuake quake = (EarthQuake) majorQuakes.next( );

    System.out.println( "ALERT! MAJOR QUAKE: "

        + quake.getLocation( ) + ": " + quake.getIntensity( ) );

}

```

An instance of `MajorQuakePredicate` is created, and it is passed to a `FilterIterator`. Quakes satisfying the criteria are returned by the `FilterIterator` and printed to the console:

```
ALERT! MAJOR QUAKE: Chicago, IL: 6.4
```

Discussion

The Solution uses a custom `Predicate` to select a subset of a `Collection`, filtering `EarthQuake` beans and alerting the user if a major earthquake is measured. An earthquake is classified by intensity on the Richter scale and the depth of the epicenter; this information is modeled by the `EarthQuake` bean defined in [Example 5-1](#).

Example 5-1. An EarthQuake bean

```
package com.discursive.jccook.collections.predicates;
```



```
public class EarthQuake {

    private String location;

    private Float intensity;

    private Float depth;

    private Date time;

    public class EarthQuake( ) {}

    public String getLocation( ) { return location; }

    public void setLocation(String location) { this.location = location; }

    public Float getIntensity( ) { return intensity; }

    public void setInsensity(Float intensity) { this.intensity = intensity; }

    public Float getDepth( ) { return depth; }

    public void setDepth(Float depth) { this.depth = depth; }

    public Date getTime( ) { return time; }

    public void setTime(Date time) { this.time = time; }

}
```

An earthquake is considered major if it is above a five on the Richter scale and above a depth of 1000 meters. To test each `EarthQuake` object, a custom `Predicate`, `MajorQuakePredicate`, evaluates `EarthQuake` objects, returning `true` if an earthquake satisfies the criteria for a major earthquake. The `Predicate` defined in [Example 5-2](#) encapsulates this decision logic.

Example 5-2. Major earthquake classification Predicate

```
package com.discursive.jccook.collections.predicates;
```

```
import org.apache.commons.collections.Predicate;

public class MajorQuakePredicate implements Predicate {

    private Float majorIntensity;

    private Float majorDepth;

    public MajorQuakePredicate(Float majorIntensity, Float majorDepth) {

        this.majorIntensity = majorIntensity;

        this.majorDepth = majorDepth;

    }

    public boolean evaluate(Object object) {

        private satisfies = false;

        if( object instanceof EarthQuake) {

            EarthQuake quake = (EarthQuake) object;

            if( quake.getIntensity( ).floatValue( ) > majorIntensity.

                floatValue( ) &&

                quake.getDepth( ).floatValue( ) < majorDepth.

                floatValue( ) ) {

                satisfies = true;

            }

        }

        return satisfies;

    }

}
```

```
}
```

If you want to create a `Collection` of elements that match a `Predicate`, you can remove elements from a `Collection` using `CollectionUtils.filter()`. `CollectionUtils.filter()` is destructive; it removes elements from a `Collection`. The following example demonstrates the use `CollectionUtils.filter()` to remove nonmatching elements from a `Collection`:

```
import org.apache.commons.collection.Predicate;

import org.apache.commons.collection.iterators.FilterIterator;

ArrayList quakes = createQuakes();

Predicate majorQuakePredicate =

    new MajorQuakePredicate( new Float(5.0), new Float(1000.0) );

CollectionUtils.filter( quakes, majorQuakePredicate );
```

After the execution of this code, `quakes` will only contain `EarthQuake` objects that satisfy the `MajorQuakePredicate`. If you don't want to alter or modify an existing `Collection`, use `CollectionUtils.select()` or `CollectionUtils.selectRejected()` to create a new `Collection` with matching or nonmatching elements. The following example demonstrates the use of `CollectionUtils.select()` and `CollectionUtils.selectRejected()` to select elements from a `Collection` leaving the original `Collection` unaffected:

```
import org.apache.commons.collection.Predicate;

import org.apache.commons.collection.iterators.FilterIterator;

ArrayList quakes = createQuakes();

Predicate majorQuakePredicate =

    new MajorQuakePredicate( new Float(5.0), new Float(1000.0) );

Collection majorQuakes = CollectionUtils.select( quakes, majorQuakePredicate );
```

```
Collection minorQuakes =  
  
    CollectionUtils.selectRejected( quakes, majorQuakePredicate );
```

The `majorQuakes` `Collection` contains `EarthQuake` objects satisfying the `majorQuakePredicate`, and the `minorQuakes` `Collection` contains `EarthQuake` objects not satisfying the `majorQuakePredicate`. The `quakes` `List` is not modified by `select()` or `selectRejected()`.

See Also

Collections can be filtered via a combination of `CollectionUtils` and `Predicate` objects, or you can also select elements from a `Collection` using an XPath expression. [Recipe 12.1](#) demonstrates the use on Commons JXPath to query a `Collection`.



Recipe 5.5 Iterating Through Distinct Elements

Problem

You need to iterate over the unique elements in a `Collection`.

Solution

Use a `UniqueFilterIterator` to iterate over distinct elements contained in a `Collection`. `UniqueFilterIterator` wraps another instance of `Iterator`, keeping track of all the objects returned by that `Iterator`. When calling `next()` on a `UniqueFilterIterator`, only objects not yet encountered are returned. The following example demonstrates the use of `UniqueFilterIterator` to find unique elements in a `List`:

```
import org.apache.commons.collections.iterators.UniqueFilterIterator;

String[] medals = new String[] { "gold", "silver", "silver", "gold", "bronze" };

List medalsList = Arrays.asList( medals );

Iterator uniqueIterator = new UniqueFilterIterator( medalsList.iterator( ) );

while( uniqueIterator.hasNext( ) ) {

    System.out.println( "Unique Medal: " + uniqueIterator.next( ) );

}
```

`UniqueFilterIterator` iterates over a `List` of strings, returning one copy of each distinct element; `UniqueFilterIterator` uses the `equals()` and `hashCode()` methods to compare objects in the `Collection` passed to the constructor. Equal objects with equal hash codes are removed. As shown by the output produced by the example, the `UniqueFilterIterator` prints out only the three distinct medals in the `medalsList`: "gold," "silver," and "bronze":

```
Unique Medal: gold
```

```
Unique Medal: silver
```

```
Unique Medal: bronze
```

Discussion

The building blocks for `UniqueFilterIterator` have already been introduced. `FilterIterator` was introduced in [Recipe 5.4](#), and `UniquePredicate` is a `Predicate` that keeps track of objects it has evaluated in a `HashSet`. A `UniqueFilterIterator` is the equivalent of a `FilterIterator` with a `UniquePredicate`. As the following code demonstrates, the example from the Solution can be implemented with a `FilterIterator` and a `Predicate`:

```
import org.apache.commons.collections.iterators.FilterIterator;

import org.apache.commons.collections.functors.UniquePredicate;

String[] medals = new String[] { "gold", "silver", "silver", "gold", "bronze" };

List medalsList = Arrays.asList( medals );

Iterator uniqueIterator =

    new FilterIterator( medalsList.iterator( ), new UniquePredicate( ) );

while( uniqueIterator.hasNext( ) ) {

    System.out.println( "Unique Medal: " + uniqueIterator.next( ) );

}
```

See Also

For more information about the `UniquePredicate` see [Recipe 4.7](#).

Recipe 5.6 Using a Bag

Problem

You need to find out how many times an object occurs within a `Collection`, and you need a `Collection` that lets you manipulate the cardinality of objects it contains.

Solution

Use a `Bag`. A `Bag` can store the same object multiple times while keeping track of how many copies it contains. For example, a `Bag` object can contain 20 copies of object "A" and 50 copies of object "B," and it can be queried to see how many copies of an object it contains. You can also add or remove multiple copies of an object-add 10 copies of "A" or remove 4 copies of "B." The following example creates a `Bag` and adds multiple copies of two `String` objects:

```
import org.apache.commons.collections.Bag;

import org.apache.commons.collections.bag.HashBag;

Bag bag = new HashBag( );

bag.add( "TEST1", 100 );

bag.add( "TEST2", 500 );

int test1Count = bag.getCount( "TEST1" );

int test2Count = bag.getCount( "TEST2" );

System.out.println( "Counts: TEST1: " + test1Count + ", TEST2: " + test2Count );

bag.remove( "TEST1", 1 );
```

```
bag.remove( "TEST2", 10 );

int test1Count = bag.getCount( "TEST1" );

int test2Count = bag.getCount( "TEST2" );

System.out.println( "Counts: TEST1: " + test1Count + ", TEST2: " + test2Count );
```

This example put 100 copies of the `String` "TEST1" and 500 copies of the `String` "TEST2" into a `HashBag`. The contents of the `Bag` are then printed, and 1 instance of "TEST1" and 10 instances of "TEST2" are removed from the `Bag`:

```
Counts: TEST1: 100, TEST2: 500

Counts: TEST1: 99, TEST2: 490
```

Discussion

`Bag` has two implementations-`HashBag` and `TreeBag`-which use a `HashMap` and a `TreeMap` to store the contents of a `Bag`. The same design considerations apply to `Bag` that apply to `Map`. Use `HashBag` for performance and `TreeBag` when it is important to maintain the order that each distinct object was added to a `Bag`. A `TreeBag` returns unique objects in the order they were introduced to the `Bag`.

To demonstrate the `Bag` object, a system to track inventory is created using a `Bag` as an underlying data structure. An inventory management system must find out how many copies of a product are in stock, and a `Bag` is appropriate because it allows you to keep track of the cardinality of an object in a `Collection`. In [Example 5-3](#), a record store tracks an inventory of albums, consisting of 200 Radiohead albums, 100 Kraftwerk albums, 500 Charlie Parker albums, and 900 ABBA albums.

Example 5-3. Using a Bag to track inventory

```
package com.discursive.jccook.collections.bag;

import java.text.NumberFormat;

import java.util.Collection;

import java.util.Iterator;

import java.util.Set;
```



```
import org.apache.commons.collections.Bag;

import org.apache.commons.collections.bag.HashBag;

import org.apache.commons.lang.StringUtils;

public class BagExample {

    Bag inventoryBag = new HashBag( );

    // Define 4 Albums

    Album album1 = new Album( "Radiohead", "OK Computer" );

    Album album2 = new Album( "Kraftwerk", "The Man-Machine" );

    Album album3 = new Album( "Charlie Parker", "Now's the Time" );

    Album album4 = new Album( "ABBA", "ABBA - Gold: Greatest Hits" );

    public static void main(String[] args) {

        BagExample example = new BagExample( );

        example.start( );

    }

    private void start( ) {

        // Read our inventory into a Bag

        populateInventory( );

        System.out.println( "Inventory before Transactions" );

        printAlbums( inventoryBag );

        printSeparator( );

    }

}
```

```
// A Customer wants to purchase 500 ABBA, 2 Radiohead, and 150 Parker
Bag shoppingCart1 = new HashBag( );

shoppingCart1.add( album4, 500 );

shoppingCart1.add( album3, 150 );

shoppingCart1.add( album1, 2 );

checkout( shoppingCart1, "Customer 1" );


// Another Customer wants to purchase 600 copies of ABBA
Bag shoppingCart2 = new HashBag( );

shoppingCart2.add( album4, 600 );

checkout( shoppingCart2, "Customer 2" );


// Another Customer wants to purchase 3 copies of Kraftwerk
Bag shoppingCart3 = new HashBag( );

shoppingCart3.add( album2, 3 );

checkout( shoppingCart3, "Customer 3" );


System.out.println( "Inventory after Transactions" );

printAlbums( inventoryBag );

}


private void populateInventory( ) {

    // Adds items to a Bag

    inventoryBag.add( album1, 200 );

    inventoryBag.add( album2, 100 );

}
```

```
        inventoryBag.add( album3, 500 );

        inventoryBag.add( album4, 900 );

    }

    private void printAlbums( Bag albumBag ) {

        Set albums = albumBag.uniqueSet( );

        Iterator albumIterator = albums.iterator( );

        while( albumIterator.hasNext( ) ) {

            Album album = (Album) albumIterator.next( );

            NumberFormat format = NumberFormat.getInstance( );

            format.setMinimumIntegerDigits( 3 );

            format.setMaximumFractionDigits( 0 );

            System.out.println( "\t" +

                format.format( albumBag.getCount( album ) ) +

                " - " + album.getBand( ) );

        }

    }

    private void checkout( Bag shoppingCart, String customer ) {

        // Check to see if we have the inventory to cover this purchase

        if( inventoryBag.containsAll( (Collection) shoppingCart ) ) {

            // Remove these items from our inventory

            inventoryBag.removeAll( (Collection) shoppingCart );

            System.out.println( customer + " purchased the following items:" );

            printAlbums( shoppingCart );

        } else {
```

```
        System.out.println( customer + ", I'm sorry " +
                               "but we are unable to fill your order." );
    }

    printSeparator( );
}

private void printSeparator( ) {
    System.out.println( StringUtils.repeat( "*", 65 ) );
}
}
```

Albums are stored in the `inventoryBag` variable, which is populated by a call to `populateInventory()` method. The `printAlbums()` method demonstrates how a `Bag`'s iterator will iterate through all of the distinct objects stored in a `Bag`, printing out the count for each album by calling `getCount()` on the `inventoryBag`. After populating and printing the store's inventory, the `start()` method models the behavior of three customers. Each customer creates a `Bag` instance, `shoppingBag`, which holds the `Album` objects she wishes to purchase.

When a customer checks out of the store, the `containsAll()` method is called to make sure that the `inventoryBag` contains adequate inventory to fulfill a customer's order. If a customer attempts to buy 40 copies of an album, we create a `Bag` with 40 instances of the `Album` object, and `containsAll()` will only return `true` if the `inventoryBag` contains at least 40 matching albums. Certain that the order can be fulfilled, `removeAll()` reduces the number of albums in the `inventoryBag` by 40 and the customer's transaction is considered complete.

Each customer transaction is modeled by a `Bag` that is subtracted from the `inventoryBag` using the `removeAll()` method. [Example 5-3](#) prints the inventory before and after the three customer transactions, summarizing the result of each:

Inventory before Transactions

```
200 - Radiohead
100 - Kraftwerk
900 - ABBA
500 - Charlie Parker
```

Customer 1 purchased the following items:

002 - Radiohead

500 - ABBA

150 - Charlie Parker

Customer 2, I'm sorry but we are unable to fill your order.

Customer 3 purchased the following items:

003 - Kraftwerk

Inventory after Transactions

198 - Radiohead

097 - Kraftwerk

400 - ABBA

350 - Charlie Parker

Technically speaking, `Bag` is not a real `Collection` implementation. The `removeAll()`, `containsAll()`, `add()`, `remove()`, and `retainAll()` methods do not strictly follow the contract defined by the `Collection` interface. Adhering to a strict interpretation of the `Collection` interface, `removeAll()` should remove all traces of an object from a collection, and `containsAll()` should not pay attention to the cardinality of an object in a collection. Calling `removeAll()` with a single `Album` object should clear the `Bag` of any references to the specified `Album` object, and `containsAll()` should return `true` if a collection contains even one instance of a specified object. In `Bag`, a call to `removeAll()` with three `Album` objects will remove only the specified number of each `Album` object. In [Example 5-3](#), the `checkout()` method uses `removeAll()` to remove albums from the inventory. A call to `containsAll()` will only return `true` if a `Bag` contains a number greater than or equal to the cardinality specified in the `Collection`. In [Example 5-3](#), the `checkout()` method uses `containsAll()` to see if there is sufficient inventory to satisfy an order. These violations should not keep you from using `Bag`, but keep these exceptions to the collection interface in mind if you are going to expose a `Bag` as a collection in a widely used API.

See Also

For more information about the bag data structure, look at a definition from the National Institute of Standards and Technology (NIST) at <http://www.nist.gov/dads/HTML/bag.html>.



Recipe 5.7 Using a Buffer

Problem

You need a data structure that can act as a temporary staging area, i.e., a buffer.

Solution

Use `Buffer` from Jakarta Commons Collections. A *buffer* is an object that is defined by the algorithm used for element removal. `Buffer` objects can be priority queues, staging areas, message queues, or buffers for I/O. One of the simplest `Buffer` implementations is the `UnboundedFifoBuffer`, a first-in, first-out data structure with no size limit. The following example demonstrates the use of an `UnboundedFifoBuffer`:

```
import org.apache.commons.collections.Buffer;

import org.apache.commons.collections.buffer.UnboundedFifoBuffer;

// Create an Unbounded FIFO

Buffer buffer = new UnboundedFifoBuffer( );

// Add elements to the Buffer

buffer.add("A");

buffer.add("B");

buffer.add("D");

// Remove element from the buffer

String value = (String) buffer.remove( );

buffer.add("E");
```

```
value = (String) buffer.remove( );
```

This example creates an `UnboundedFifoBuffer`, adding three elements: "A," "B," and "D." When `remove()` is invoked, the buffer selects the item that was placed into the buffer first-the first-in is the first-out. The first call to `remove()` returns "A," and the second call returns "B."

Discussion

A FIFO buffer can be viewed as a kind of stack; instead of `pop()` returning the last item to be placed on the stack, `remove()` returns the bottom of the stack-the first item added to the `Buffer`. A `Buffer` throws a `BufferUnderflowException` if you try to `remove()` or `get()` an element from an empty `Buffer`. This data structure is useful if you need a temporary holding area between stages in a pipeline-a queue to hold objects as they wait to be processed by the next stage. An unbounded FIFO buffer has no size limit, and, as such, it could grow to a limitless size. In fact, if an application continued to fill an unbounded buffer, it would exhaust available memory. [Figure 5-1](#) describes a FIFO buffer as a linear sequence of elements: items flow through this sequence from left to right.

Figure 5-1. A FIFO buffer

In addition to `UnboundedFifoBuffer`, there is a bounded counterpart-`BoundedFifoBuffer`. `BoundedFifoBuffer` has a maximum size that cannot be exceeded; adding an object to a `BoundedFifoBuffer` already at maximum size will cause a `BufferOverflowException`. [Example 5-4](#) demonstrates the use of a bounded buffer with a maximum size limit of two.

Example 5-4. Using a BoundedFifoBuffer

```
import org.apache.commons.collections.Buffer;

import org.apache.commons.collections.BufferOverflowException;

import org.apache.commons.collections.buffer.BoundedFifoBuffer;

...

// Create a Bounded FIFO with a max size of two

Buffer buffer = new BoundedFifoBuffer(2);
```



```
buffer.add( "One" );

buffer.add( "Two" );

// Adding a third element to this buffer will cause an exception
try {

    buffer.add( "Three" );

} catch( BufferOverflowException bue ) {

    System.out.println( "Buffer is Full!" );

}

// Remove an object... Buffer now contains one element.
Object removed = buffer.remove( );

// Add another object
buffer.add( "Three" );

Object remove1 = buffer.remove( );
Object remove2 = buffer.remove( );

// This next remove( ) should cause a BufferUnderflowException
try {

    Object remove3 = buffer.remove( );

} catch( BufferUnderflowException bue ) {

    System.out.println( "Buffer is Empty!" );

}
```



Later recipes will demonstrate the use of `Buffer` objects in processing pipelines where it is important to provide a limit on how much memory a `Buffer` is able to consume.

See Also

A `Buffer` in Jakarta Commons Collections is analogous to a `Queue` in Java 5.0. The `Queue` interface is accompanied by a number of interfaces that provide almost identical behavior to the `Buffer` interface as defined in Jakarta Commons Collections 3.0. `Queue` contains some new methods, `offer()` and `peek()`, which perform the same functions as `add()` and `remove()`, with one difference: these new methods return `false` if there is any problem adding an object to a `Queue`. More information about queues and other changes to the Collections framework in Java 5.0 are available at: <http://java.sun.com/j2se/1.5.0/docs/guide/collections/changes5.html>.

Recipe 5.8 Creating a Priority Queue

Problem

You need to prioritize objects: removing higher priority objects from a `Collection` before lower priority objects.

Solution

Use a `PriorityBuffer` to hold objects to be prioritized. Objects will be removed from this `Buffer` according to a priority generated with a `Comparator`. Whenever the `remove()` method is called on this `Buffer` implementation, a `PriorityBuffer` uses the `Comparator` to sort its contents, returning the element of greatest priority. Using a `PriorityBuffer` without a `Comparator` causes the buffer to prioritize objects by natural order, casting each object to `Comparable` and comparing objects with the `compareTo()` method; all objects must implement the `Comparable` interface if no `Comparator` is supplied. The following example demonstrates the use of a `PriorityBuffer` without supplying a `Comparator`:

```
import java.util.*;

import org.apache.commons.collections.Buffer;

import org.apache.commons.collections.buffer.PriorityBuffer;

// Create a PriorityBuffer with no Comparator

Buffer priority = new PriorityBuffer( );

priority.add( new Long( 2 ) );

priority.add( new Long( 1 ) );

priority.add( new Long( 20 ) );

priority.add( new Long( 7 ) );

priority.add( new Long( 18 ) );

priority.add( new Long( 1 ) );
```

```
// Print the results in priority order

Iterator priorityIterator = priority.iterator( );

while( priorityIterator.hasNext( ) ) {

    Long value = (Long) priority.next( );

    System.out.println( "Value: " + value );

}
```

The previous example removes values from the buffer based on a natural order, and the following output is produced:

Value: 20

Value: 18

Value: 7

Value: 2

Value: 1

Value: 1

Discussion

A `PriorityBuffer`, like all `Buffer` implementations, is defined by the logic to select which object to remove. If you've ever visited an emergency room, you are already familiar with the inner workings of the `PriorityBuffer`. When a patient enters the emergency room, his or her condition is evaluated by a nurse who then assigns a severity. When a doctor moves to the next patient, she chooses the next patient based on severity and how long each patient has been waiting. A patient with a critical, life-threatening condition will be treated before an individual with a headache-the critical patient has a higher priority in the `Buffer`.

The following example models an emergency waiting room with a `PriorityBuffer`. Assume that you have a `Patient` bean with `name`, `severity`, and `checkIn` properties, which is defined in [Example 5-5](#). A patient's severity is a number from 0 to 10, 0 being the lowest severity and 10 being the highest. A critical patient would be assigned a priority of 10, and a patient with a bad cold would be assigned a severity of 0. A patient also has a `checkIn` time: this is the time he is admitted to the waiting room, and it is used as a tie-breaker to determine priority when two patients have the same `severity`.

Example 5-5. A Patient object

```
package com.discursive.jccook.collections.buffers;
```



```
public class Patient {  
  
    private String name;  
  
    private Integer severity;  
  
    private Date checkIn;  
  
  
    public class Patient( ) {}  
  
  
    public String getName( ) { return name; }  
  
    public void setName(String name) { this.name = name; }  
  
  
    public Integer getSeverity( ) { return severity; }  
  
    public void setSeverity(Integer severity) { this.severity = severity; }  
  
  
    public Date getCheckIn( ) { return checkIn; }  
  
    public void setCheckIn(Date checkIn) { this.checkIn = checkIn; }  
  
}
```

The `PatientPriorityComparator` in [Example 5-6](#) prioritizes patients by severity of condition and time since check-in. A patient with a more severe condition takes priority over a patient with a less severe condition who has been waiting longer, and, if two patients have the same severity, the one who has been waiting longer gets a higher priority. If this `Comparator` is used to sort an array of `Patient` objects, the most critical patient would be at the last index, and the least critical would be at the first index.

Example 5-6. A Comparator to sort Patient objects by priority

```
package com.discursive.jccook.collections.buffers;  
  
  
import java.util.Comparator;
```

```
public PatientPriorityComparator implements Comparator {

    public int compare(Object o1, Object o2) {

        int comparison = -1;

        if( o1 instanceof Patient &&
            o2 instanceof Patient ) {

            Patient p1 = (Patient) o1;

            Patient p2 = (Patient) o2;

            comparison = p1.getSeverity( ).compareTo( p2.getSeverity( ) );

            if( comparison == 0 ) {

                comparison =

                p1.getCheckIn( ).compareTo( p2.getCheckIn( ) );

            }

        }

        return comparison;

    }

}
```

When using the `PriorityBuffer` with a `PatientPriorityComparator`, `Patient` objects are added to the `Buffer` and `remove()` returns the `Patient` with the highest priority. Using a `PriorityBuffer` means that you do not need to worry about constantly resorting a `Collection` by priority; this logic is completed automatically every time an object is removed from the `Buffer`. In other words, you are delegating responsibility to a `Buffer`; it takes care of the sorting and selecting on an as-needed basis.

[Example 5-7](#) adds three `Patient` objects to a `PriorityBuffer`: John Doe 1 has an ear ache, John Doe 2 has a broken back, and Jane Doe 3 has a concussion. Both John 2 and Jane 3 have serious conditions, and, since John 2 checked in before Jane 3, John 2 has a higher priority than Jane 3. John 1's condition is not nearly as critical; therefore, his priority is much lower, and he is treated last.

Example 5-7. Using a prioritizing buffer

```
package com.discursive.jccook.collections.buffers;

import java.util.Date;
import java.util.PriorityBuffer;
import java.util.PriorityComparator;
import java.util.concurrent.locks.Lock;
import java.util.concurrent.locks.ReentrantLock;

public class WaitingRoomApp {

    public static void main(String[] args) {

        WaitingRoomApp example = new WaitingRoomApp( );

        example.start( );

    }

    public void start( ) {

        Buffer patients =

            new PriorityBuffer( new PatientPriorityComparator( ) );

        Patient johnDoe1 = new Patient( );

        johnDoe1.setName( "John Doe 1" );

        johnDoe1.setSeverity( new Integer( 7 ) );

        johnDoe1.setCheckIn( new Date( ) );

        patients.add( johnDoe1 );

        Patient johnDoe2 = new Patient( );

        johnDoe2.setName( "John Doe 2" );

        johnDoe2.setSeverity( new Integer( 9 ) );
```

```
        johnDoe2.setCheckIn( new Date( ) );

        patients.add( johnDoe2 );

        Patient janeDoe3 = new Patient( );

        janeDoe3.setName( "Jane Doe 3" );

        janeDoe3.setSeverity( new Integer( 9 ) );

        janeDoe3.setCheckIn( new Date( ) );

        patients.add( janeDoe3 );

        while( patients.size( ) > 0 ) {

            Patient patient = (Patient) patients.remove( );

            System.out.println( "Patient: " + patient.getName( ) );

        }

    }

}
```

As each `Patient` is treated, the patient's name is printed to the console:

```
Patient: John Doe 2
```

```
Patient: Jane Doe 3
```

```
Patient: John Doe 1
```

See Also

A `PriorityBuffer` in Jakarta Commons Collections is analogous to a `PriorityQueue` in Java 5.0. For information about `PriorityQueue` and other important changes to the Collections framework in Java 5.0, see <http://java.sun.com/j2se/1.5.0/docs/api/index.html>.

Recipe 5.9 Using a Blocking Buffer

Problem

Your system needs to wait for input and act on an object the moment it is added to a `Buffer`. To achieve this, you need your application to block until input is received.

Solution

Use `BlockingBuffer` to decorate an instance of `Buffer`. When a process calls `get()` or `remove()` on a buffer decorated with `BlockingBuffer`, the decorated buffer does not return a value until it has an object to return. The following example creates a `BlockingBuffer` and a listener that calls `remove()`. A `BlockingBuffer` can only be demonstrated by an example that deals with multiple threads, and the following code uses a `Runnable` implementation, `BufferListener`, which is defined in [Example 5-8](#):

```
import java.util.*;

import org.apache.commons.collections.Buffer;

import org.apache.commons.collections.buffer.BlockingBuffer;

import org.apache.commons.collections.buffer.BoundedFifoBuffer;


// Create a Blocking Buffer

Buffer buffer = BlockingBuffer.decorate( new BoundedFifoBuffer( ) );


// Create Thread to continuously remove( ) from the previous Buffer

BufferListener listener = new BufferListener(buffer);

Thread listenerThread = new Thread( listener );

listenerThread.start( );


buffer.add( "Hello World!" );
```

```
buffer.add( "Goodbye, Y'all." );
```

The previous example creates an instance of `BufferListener`-a `Runnable` object that calls `remove()` on a `BoundedFifoBuffer` decorated with `BlockingBuffer`. The `listenerThread` will block on a call to `buffer.remove()` within the `run()` method of `BufferListener`, an object that runs in a separate thread and waits for objects to be added to a `BlockingBuffer`.

Example 5-8. A BufferListener constantly calling `remove()`

```
public class BufferListener implements Runnable {

    private Buffer buffer;

    public BufferListener(Buffer buffer) {

        this.buffer = buffer;

    }

    public void run( ) {

        while(true) {

            String message = (String) buffer.remove( );

            System.out.println( message );

        }

    }

}
```

The two calls to `buffer.add()` causes `BufferListener` to print the strings added:

```
Hello World!
```


```
Goodbye, Y'all.
```

Discussion

A `BlockingBuffer` is used in a system that needs to act on a piece a data as soon as it is available,

and this data structure comes in handy when there are a series of worker threads listening to buffers between components in a pipeline. `BlockingBuffer` allows you to build cascading pipelines, which automatically notify the next stage of available data. Think of this pattern as a stepped waterfall; water automatically flows down the steps, and each step is a `Buffer`. (See [Figure 5-2](#).)

Figure 5-2. Using a `BlockingBuffer` to create a pipeline



Assume that you need to write a workflow application for a news publisher; the workflow consists of a pipeline: news stories are published as XML files, which are passed to a search indexer and then processed with an XSLT stylesheet. A news story is simply passed as a `String` containing an XML document. The following example creates a pipeline consisting of two `BlockingBuffer` instances terminated by an `UnboundedFifoBuffer`:

```

import java.util.*;

import org.apache.commons.collections.Buffer;
import org.apache.commons.collections.buffer.BlockingBuffer;
import org.apache.commons.collections.buffer.UnboundedFifoBuffer;

// Create a Blocking Buffer for each stage, last stage not a blocking buffer
Buffer published = BlockingBuffer.decorate( new UnboundedFifoBuffer( ) );
Buffer indexed = BlockingBuffer.decorate( new UnboundedFifoBuffer( ) );
Buffer transformed = new UnboundedFifoBuffer( );

// Create a Thread that will watch the published Buffer and index a news story
Indexer indexer = new Indexer(published, indexed);
Thread indexerThread = new Thread( indexer );
indexerThread.start( );

// Create a Thread that will watch the indexed Buffer and style a news story

```

```
Styler styler = new Styler(index, transformed);

Thread stylerThread = new Thread( styler );

stylerThread.start( );

String newsStory = getNewsStory( );

published.add( newsStory );
```

The previous example creates three buffers to hold the results of the stages of a pipeline-`published`, `indexed`, and `transformed`. Three `Runnable` objects are created to perform the task of processing each news story; the `Indexer` object listens to the `published` buffer and places its results in the `indexed` buffer, and the `Styler` object listens to the `indexed` buffer and places its results in the `transformed` buffer. The `Indexer` object implements `Runnable` and is constructed with two `Buffer` objects, `inbound` and `outbound`. The `Indexer`, as shown in [Example 5-9](#), continuously calls `remove()` on a `BlockingBuffer` and waits until a story is available to process.

Example 5-9. An Indexer stage in a pipeline

```
public class Indexer implements Runnnable {

    private Buffer inbound;

    private Buffer outbound;

    public Indexer(Buffer inbound, Buffer outbound) {

        this.inbound = inbound;

        this.outbound = outbound;

    }

    public void run( ) {

        while(true) {

            String story = (String) inbound.remove( );

            String processedStory = processStory( story );
```



```
        outbound.add( processedStory );
    }
}

public String processedStory(String story) {

    // Run story through a search indexer

    return story;

}
}
```

The `Styler` is omitted because it follows the exact same pattern. Every stage in this pipeline is a `Runnable` implementation running in a thread and listening to an inbound buffer by calling (and blocking) on `inbound.remove()`. Using this mechanism allows your system to process information in parallel by running separate stages in separate threads, and there is no need for a controller to coordinate the actions of a complex system. A pipeline can be extended by simply adding another stage with an additional `BlockingBuffer`. This pattern is useful in a system that models a very complex workflow; instead of attempting to capture a complex symphony of coordination, break the system into autonomous stages that only know about inputs and outputs.

See Also

A `BlockingBuffer` in Jakarta Commons Collections is analogous to a `BlockingQueue` in Java 5.0. A `BlockingQueue` in Java 5.0 has an important feature that is missing in Commons Collections 3.0 implementation of `BlockingBuffer`: in Java 5.0's `BlockingQueue`, you can specify a timeout when adding and removing values from a queue.

Recipe 5.10 Storing Multiple Values in a Map

Problem

You need to store multiple values for a single key in a `Map`. Instead of a one-to-one relationship between keys and values, you need a `Map` that provides one-to-many relationships between keys and values.

Solution

Use a `MultiMap`. A `MultiMap` maintains a collection of values for a given key. When a new key/value pair is added to a `MultiMap`, the value is added to the collection of values for that key. The `MultiMap` also provides a way to remove a specific key/value pair. The following example demonstrates the use of `MultiMap`:

```
import org.apache.commons.collections.MultiMap;

import org.apache.commons.collections.MultiHashMap;

MultiMap map = new MultiHashMap( );

map.put( "ONE", "TEST" );

map.put( "TWO", "PICNIC" );

map.put( "ONE", "HELLO" );

map.put( "TWO", "TESTIMONY" );

Set keySet = map.keySet( );

Iterator keyIterator = keySet.iterator( );

while( keyIterator.hasNext( ) ) {
```

```

        Object key = keyIterator.next( );

        System.out.print( "Key: " + key + ", " );

        Collection values = (Collection) map.get( key );

        Iterator valuesIterator = values.iterator( );

        while( valuesIterator.hasNext( ) ) {

            System.out.print( "Value: " + valuesIterator.next( ) + ". " );

        }

        System.out.print( "\n" );

    }

```

Each key in a `MultiMap` corresponds to a collection of values. This example produces the following output while iterating through all values for each key:

```
Key: ONE, Value: TEST. Value: HELLO
```

```
Key: TWO, Value: PICNIC. Value: Testimony
```

Discussion

In a traditional `Map`, a key is removed with `map.remove()`; this method removes the specified key from the map. In a `MultiMap`, a specific key/value pair can be removed from a key's value collection. When removing a specific pair, the value is extracted from a key's value collection. [Example 5-10](#) demonstrates the use of a `MultiMap.remove()` method.

Example 5-10. Using `MultiMap.remove()`

```

package com.discursive.jccook.collections.map;

import org.apache.commons.collections.*;

import java.util.*;

```

```
public class MultiMapExample {

    public static void main(String[] args) {

        MultiMapExample example = new MultiMapExample( );

        example.start( );

    }

    public void start( ) {

        MultiMap map = new MultiHashMap( );

        map.put( "ONE", "TEST" );

        map.put( "ONE", "WAR" );

        map.put( "ONE", "CAR" );

        map.put( "ONE", "WEST" );

        map.put( "TWO", "SKY" );

        map.put( "TWO", "WEST" );

        map.put( "TWO", "SCHOOL" );

        // At this point "ONE" should correspond to "TEST", "WAR", "CAR", "WEST"

        map.remove( "ONE", "WAR" );

        map.remove( "ONE", "CAR" );

        // The size of this collection should be two "TEST", "WEST"

        Collection oneCollection = (Collection) map.get("ONE");
```



```
        // This collection should be "TEST", "WEST", "SKY", "WEST", "SCHOOL"

        Collection values = map.values( );

    }

}
```

The `MultiMap` is relevant when one object is associated with many different objects. A sensible example would be a `MultiMap` of people to the languages they speak fluently, and the following example demonstrates such a `Map`:

```
MultiMap languageAbility = new MultiHashMap( );

languageAbility.put( "Tom", "French" );

languageAbility.put( "Chris", "Spanish" );

languageAbility.put( "Chris", "German" );

languageAbility.put( "John", "Arabic" );

languageAbility.put( "Tom", "Pashto" );


// What languages does Tom speak?

Collection languages = (Collection) languageAbility.get("Tom");

Iterator languageIterator = languages.iterator( );

while( languageIterator.hasNext( ) ) {

    System.out.println( "Tom speaks " + languageIterator.next( ) );

}
```

If you had to locate people who were fluent in a given language, it would be equally as valid to use languages as keys and names as values. One could then query the `MultiMap` for a list of people who speak a certain language. If your system contains two collections of objects that have a many-to-many relationship, these relationships can be managed with two instances of `MultiMap`.

Recipe 5.11 Retrieving a Key by a Value

Problem

You need a `Map` that allows you to access a value by a key and a key by a value.

Solution

`BidiMap` in Commons Collections provides an implementation of `Map`, which can be reversed if both the keys and values are unique; you can use a `BidiMap` to retrieve a value for a key or a key for a value. The following example demonstrates the use of a `BidiMap` to access state names by state abbreviation and state abbreviations by state names:

```
BidiMap bidiMap = new DualHashBidiMap( );

bidiMap.put( "il", "Illinois" );

bidiMap.put( "az", "Arizona" );

bidiMap.put( "va", "Virginia" );

// Retrieve the key with a value via the inverse map

String vaAbbreviation = bidiMap.inverseBidiMap( ).get( "Virginia" );

// Retrieve the value from the key

String illinoisName = bidiMap.get( "il" );
```

`DualHashBidiMap` stores keys and values in two `HashMap` instances. One `HashMap` stores keys as keys and values as values, and the other `HashMap` stores the inverse-values as keys and keys as values.

Discussion

In [Example 5-11](#), a `BidiMap` is used to store country names and country codes; an application stores ISO country codes and translates between ISO country codes and country names to present intelligible output-"us" is translated to "United States." Alternatively, when a user types in a name of a country, the application needs to be able to produce the country code for that country name-"United States" must be translated back to "us."

Example 5-11. Storing ISO country codes in a BidiMap

```
package com.discursive.jccook.collections.bidi;

import org.apache.commons.collections.BidiMap;
import org.apache.commons.collections.bidimap.DualHashBidiMap;

public class BidiMapExample {

    private BidiMap countryCodes = new DualHashBidiMap( );

    public static void main(String[] args) {

        BidiMapExample example = new BidiMapExample( );

        example.start( );

    }

    private void start( ) {

        populateCountryCodes( );

        String countryName = (String) countryCodes.get( "tr" );

        System.out.println( "Country Name for code 'tr': " + countryName );

        String countryCode =
```

```
        (String) countryCodes.inverseBidiMap( ).get( "Uruguay" );

        System.out.println( "Country Code for name 'Uruguay': " + countryCode );

        countryCode = (String) countryCodes.getKey( "Ukraine" );

        System.out.println( "Country Code for name 'Ukraine': " + countryCode );

    }

    private void populateCountryCodes( ) {

        countryCodes.put( "to", "Tonga" );

        countryCodes.put( "tr", "Turkey" );

        countryCodes.put( "tv", "Tuvalu" );

        countryCodes.put( "tz", "Tanzania" );

        countryCodes.put( "ua", "Ukraine" );

        countryCodes.put( "ug", "Uganda" );

        countryCodes.put( "uk", "United Kingdom" );

        countryCodes.put( "um", "USA Minor Outlying Islands" );

        countryCodes.put( "us", "United States" );

        countryCodes.put( "uy", "Uruguay" );

    }

}
```

The previous example makes sense because country codes and country names are both unique; there is only one entry for "Djibouti," "dj," and no other country has an overlapping code because country codes are defined by an International Organization for Standardization (ISO) standard, ISO 3166. If you attempt to insert a duplicate key in a regular map, the existing entry with the same key would be replaced by the new value. In a **BidiMap**, if you insert a duplicate value, or a *duplicate key*, the entry holding this value is replaced by a new entry. The following example illustrates this concept:

```
private BidiMap bidiMap = new DualHashBidiMap( );
```



```
// Insert initial content { "one":"red", "two":"green", "three":"blue" }

bidiMap.put("one","red");

bidiMap.put("two","green");

bidiMap.put("three","blue");


// replace "one" key entry

bidiMap.put("one","black");


// replace "green" value entry

bidiMap.put("five","green");


// Contents are now { "one":"black", "three":"blue", "five":"green" }
```

Changing key "one," value "black" replaces the original key "one," value "red" because the key is duplicated; this behavior is consistent with a normal implementation of `Map`. The difference in a `BidiMap` is that when adding key "five," value "green" to a `BidiMap`, the previous key "two," value "green" is replaced with a new entry because "green" is a duplicate value. A regular `Map` simply adds another entry, and getting the value of either the "five," or "two," key would return the value "green." Because "green" already occurs as a key in the inverse map, the entry corresponding to the "two," key is removed and replaced by a new entry. Bidirectional access to keys by value is only possible if keys and values form two unique sets.

There are three implementations of the `BidiMap` interface: `DualHashBidiMap`, `DualTreeBidiMap`, and `TreeBidiMap`. A `DualHashBidiMap` is the simplest option, storing keys and values in two separate instances of `HashMap`. When a value is requested by key, one `HashMap` is consulted, and when a key is requested by value, the inverse `HashMap` is consulted. The `DualHashMap` is likely to be your implementation of choice if it is not important to keep track of the insertion order; it has a straightforward implementation using the familiar `HashMap`.

If you need to preserve the order of insertion, a `DualTreeBidiMap` uses two separate `TreeMap` instances to hold the regular and inverse mappings. This implementation implements the `SortedMap` interface that keeps track of the order of insertion and provides `subMap()`, `headMap()`, and `tailMap()` methods. A third implementation, `TreeBidiMap`, implements `BidiMap` without maintaining two internal storage maps. Instead, `TreeBidiMap` stores nodes in a red-black tree, identifying each node as both a key and a value; it costs twice as much to `put()` into a `TreeBidiMap`, but this implementation comes in handy if you are worried about memory consumption-it does not need to store each key and value twice in two maps.

See Also

This example used ISO 3166 country codes, a list of every country and corresponding two letter country code. If you are writing an application for a worldwide audience, you may find the following list helpful: <http://www.iso.ch/iso/en/prods-services/iso3166ma/02iso-3166-code-lists/list-en1.html>.

PREV

< Day Day Up >

Recipe 5.12 Using a Case-Insensitive Map

Problem

You need to use a `Map` with `String` keys that will ignore the capitalization of a key when retrieving a value.

Solution

Use a `CaseInsensitiveMap` from the Commons Collections. This implementation of `Map` takes `String` keys and provides case-insensitive access. An entry with a key "Test" can be retrieved with the strings "TEST," "test," and "tEST." Here is a small example demonstrating the case insensitivity:

```
import java.util.*;

import org.apache.commons.collection.map.CaseInsensitiveMap;

Map grades = new CaseInsensitiveMap( );

grades.put( "Fortney", "B-" );

grades.put( "Puckett", "D+" );

grades.put( "Flatt", "A-" );

String grade1 = (String) grades.get( "puckett" );

String grade2 = (String) grades.get( "FLATT" );
```

In this example, the grades are stored with a capitalized last name, and the results are retrieved with irregularly capitalized last names. This example returns the grades for "Puckett" and "Flatt" even though they were retrieved with "puckett" and "FLATT."

Discussion

[Example 5-12](#) demonstrates the use of `CaseInsensitiveMap` to access state names by state

abbreviations regardless of capitalization. This is useful when an application is requesting a state from a user in a form to capture an address. If a user enters "il," "IL," or "II," you need to be able to return "Illinois."

Example 5-12. Using a CaseInsensitiveMap for U.S. states

```
package com.discursive.jccook.collections.insensitive;

import java.util.Map;

import org.apache.commons.collections.map.CaseInsensitiveMap;

public class CaseInsensitiveExample {

    Map states = new CaseInsensitiveMap( );

    public static void main(String[] args) {

        CaseInsensitiveExample example = new CaseInsensitiveExample( );

        example.start( );

    }

    private void start( ) {

        states.put("IL", "Illinois");

        states.put("PA", "Pennsylvania");

        states.put("GA", "Georgia");

        states.put("AZ", "Arizona");

        String stateName = (String) states.get( "il" );

        System.out.println( "Value retrieved for 'il': " + stateName );

    }

}
```



```
        stateName = (String) states.get( "IL" );

        System.out.println( "Value retrieved for 'IL': " + stateName );

        stateName = (String) states.get( "iL" );

        System.out.println( "Value retrieved for 'iL': " + stateName );

    }

}
```

[Example 5-12](#) populates a `CaseInsensitiveMap` with state abbreviations and state names, and it retrieves the state name for three different capitalizations of "IL": "iL," "IL," and "il." For all three keys, the `CaseInsensitiveMap` returns the proper state name-"Illinois"-as illustrated by the output from the previous example:

```
Value retrieved for 'il': Illinois
```

```
Value retrieved for 'IL': Illinois
```

```
Value retrieved for 'iL': Illinois
```

See Also

If you are interested in how this class works, take a look at the source for `CaseInsensitiveMap`, and you will see that this implementation of `Map` extends the `AbstractHashMap` class in the `org.apache.commons.collections.map` package. It would be just as easy to decorate a `Map` with a `Transformer` object to provide case insensitivity. [Recipe 5.16](#) discusses the use of a `Transformer` to alter objects as they are stored in a `Collection`.

Recipe 5.13 Creating Typed Collections and Maps

Problem

You need to guarantee that a `Collection` or a `Map` only contains objects of a certain type.

Solution

Use `TypedCollection.decorate()` to create a `Collection` that only accepts objects of a specified type. Supply an existing `Collection` along with the `Class` that all elements should be constrained to. `TypedCollection` will decorate this existing `Collection`, validating elements as they are added to a `Collection`. The following example creates a `Collection` that will only accept strings:

```
List existingList = new ArrayList( );

Collection typedCollection = TypedCollection.decorate( existingList,
String.class );

// This will add a String
typedCollection.add( "STRING" );

// And, This will throw an IllegalArgumentException
typedCollection.add( new Long(28) );
```

Similarly, if you want to constrain keys and values to specified types, pass a `Map` to `TypedMap.decorate()` method, specifying a `Class` for both the key and the value. In the following example, `typedMap` only accepts `String` keys and `Number` values:

```
Map existingMap = new HashMap( );

Map typedMap = TypedMap.decorate( existingMap, String.class, Number.class );

// This will add a String key and a Double value
```

```
typedMap.put( "TEST", new Double( 3.40 ) );

// Both of these throw an IllegalArgumentException

typedMap.put( new Long(202), new Double( 3.40 ) );

typedMap.put( "BLAH", "BLAH" );
```

`TypedCollection` and `TypedMap` will decorate any existing `Collection` or `Map` and will throw an `IllegalArgumentException` if you try to add an incompatible type.

Discussion

A `Map` frequently contains keys and values with consistent types; for instance, an application that keeps track of `Person` objects by name most likely has a `personMap` with `Person` values and `String` keys. Rarely does a `Map` hold a wide diversity of types. `Collections` and `Maps` are not type-safe, and this lack of type safety means that unexpected objects may be cast to incompatible types, causing nasty `ClassCastException`s. It is unlikely that every time you call `get()` and cast the resulting object, you catch `ClassCastException`; and, in most systems, it is reasonable to assume that no one has put an incompatible type into a `Map`. But, if a `Map` plays a central role in a critical application, you may want an extra layer of validation; decorate your maps with `TypedMap` to ensure that a `Map` contains consistent types. There is little penalty for decorating a `Map` as such, and if someone writes code to insert invalid input, your application should fail immediately with an `IllegalArgumentException`.

If your application uses a `TypedMap`, it is easier to track down defects. If a `ClassCastException` is thrown when calling `get()`, you then need to work backward to find out where the offending object was put into a `Map`. An alternative is to validate each object as it is added to a `Map`. If the `put()` method throws `IllegalArgumentException`, it will be easier to identify the offending code.

Java 5.0 adds the idea of generics-compile-time type safety for any number of objects including `Collections` and `Maps`. But, if you are stuck with an older version of the JDK, you can use Commons Collections to create a `Collection` that only accepts input of a certain type. `TypedSet`, `TypedBag`, `TypedList`, `TypedMap`, `TypedBuffer`, `TypedSortedSet`, `TypedSortedBag`, `TypedSortedMap` all provide the same decoration as `TypedCollection`, but they return a specific interface; for example, `TypedList` decorates and returns a `List`, and `TypedSet` decorates and returns a `Set`. [Example 5-13](#) demonstrates the use of the `TypedList` decorator to return a `List` instead of a `Collection`.

Example 5-13. Using TypedList to decorate a list

```
package com.discursive.jccook.collections.typed;

import java.util.ArrayList;
```



```
import java.util.List;

import org.apache.commons.collections.list.TypedList;

public class TypedListExample {

    private List hostNames;

    public static void main(String[] args) {

        TypedListExample example = new TypedListExample( );

        example.start( );

    }

    public void start( ) {

        // Make sure that items added to this

        hostNames = TypedList.decorate( new ArrayList( ), String.class );

        // Add two String objects

        hostNames.add( "papp01.thestreet.com" );

        hostNames.add( "test.slashdot.org" );

        // Try to add an Integer

        try {

            hostNames.add( new Integer(43) );

        } catch( IllegalArgumentException iae ) {

            System.out.println( "Adding an Integer Failed as expected" );

        }

    }

}
```



```
    }

    // Now we can safely cast without the possibility of a
    // ClassCastException

    String hostName = (String) hostNames.get(0);

}

}
```

If a `List` decorated with `TypedList` encounters an invalid object, the `add()` method will throw an `IllegalArgumentException`.



A `Typed<X>` decorated `Collection` will not be able to provide the compile-time type safety of Java 5.0's generics, but it will enforce a restriction on what it can accept—it is up to you to catch the runtime exception.

`TypedMap` allows you to constrain both the keys and values of a map. `TypedMap.decorate()` takes three parameters: the `Map` to decorate, the key `Class`, and the value `Class`. To create a `Map` that only constrains key types, pass in a `null` value for the value type. To create a `Map` that only validates the type of the value, pass in a `null` for the key type. [Example 5-14](#) uses `TypedMap.decorate()` to create a `Map` that only accepts `String` keys and `Number` values.

Example 5-14. Decorating a map with TypedMap

```
package com.discursive.jccook.collections.typed;

import java.util.HashMap;

import java.util.Map;

import org.apache.commons.collections.map.TypedMap;

public class TypedMapExample {
```

```
private Map variables;

public static void main(String[] args) {

    TypedMapExample example = new TypedMapExample( );

    example.start( );

}

public void start( ) {

    // Make sure that items added to this

    variables =

        TypedMap.decorate( new HashMap( ), String.class, Number.class );

    // Add two String objects

    variables.put( "maxThreads", new Integer(200) );

    variables.put( "minThreads", new Integer(20) );

    variables.put( "lightSpeed", new Double( 2.99792458e8 ) );

    // Try to add a String value

    try {

        variables.put( "server", "test.oreilly.com" );

    } catch( IllegalArgumentException iae ) {

        System.out.println( "Adding an String value Failed as expected" );

    }

    // Try to add an Integer key
```

```
        try {

            variables.put( new Integer(30), "test.oreilly.com" );

        } catch( IllegalArgumentException iae ) {

            System.out.println( "Adding an Integer key Failed as expected" );

        }

        // Now we can safely cast without the possibility of a ClassCastException

        Number reading = (Number) variables.get("lightSpeed");

    }

}
```

See Also

Java 5.0 has added generics-a welcome addition. For more information about generics, look at the release notes for Java 5.0 at <http://java.sun.com/j2se/1.5.0/docs/relnotes/features.html#generics>.

For more information about the decorator design pattern, read the classic *Design Patterns: Elements of Reusable Object-Oriented Software* by Erich Gamma et al., or take a look at this onJava.com article by Budi Kurniawan: <http://www.onjava.com/pub/a/onjava/2003/02/05/decorator.html>, which deals with the decorator pattern as applied to Java Swing development, but this pattern also has relevance outside of a GUI development context.

This `TypedCollection` decorator is a specialized version of a `PredicatedCollection`. Type-safety is implemented through the use of an `InstanceofPredicate`, and the next recipe discusses the use of a `PredicatedMap`.

Recipe 5.14 Constraining Map Values

Problem

You need to ensure that all values added to a `Map` satisfy a set of arbitrary conditions.

Solution

Decorate an existing `Map` with `PredicatedMap` from Commons Collections. `Predicates` add an inbound validation to a `Map`, validating keys or values any time an entry is added to a `PredicatedMap`. If a `Predicate` assigned to a key or value returns `false`, `put()` throws an `IllegalArgumentException`. The following example decorates a `HashMap` with `PredicatedMap`-two `Predicates` are created to validate the keys and the values:

```
import java.util.*;

import org.apache.commons.collections.map.PredicatedMap;

import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.EqualPredicate;

import org.apache.commons.collections.functors.InstanceofPredicate;

import org.apache.commons.collections.functors.OrPredicate;

// Create a Predicate that only accepts Strings

Predicate onlyStrings = new InstanceofPredicate( String.class );

// Create a Predicate that only allows "green" or "red "

Predicate onlyGreen = new EqualPredicate( "green" );

Predicate onlyRed = new EqualPredicate( "red" );

Predicate greenOrRed = new OrPredicate( onlyGreen, onlyRed );
```



```
// Created a Decorated Map - accepting String keys and "green" or "red" values

Map map = PredicatedMap.decorate( new HashMap( ), onlyStrings, greenOrRed );

// All of these puts should work

map.put( "tony" , "green" );

map.put( "alice" , "red" );

map.put( "mike" , "red" );

map.put( "bobby" , "green" );

// All of these puts should throw an IllegalArgumentException

map.put( new Double(4.0) , "green" );

map.put( "alice" , "purple" );

map.put( new Long(32) , new Long(43) );
```

In the previous example, keys are validated by a simple `InstanceOfPredicate`, which ensures that each key is a `String`. The values are validated with an `OrPredicate`, which combines two `EqualPredicates`; values are accepted if they are equal to the strings "green" or "red."

Discussion

A `PredicatedMap` can work with any `Predicate` no matter how simple or complex. Passing in a `null` value for either the key or value `Predicate` instructs the `PredicatedMap` not to validate keys or values. In the following example, a `PredicatedMap` decorates a `HashMap` to ensure that a `Map` contains valid `Team` values:

```
import org.apache.commons.collections.functors.AndPredicate;

import org.apache.commons.collections.map.PredicatedMap;

// Create the Predicates

ValidTeamPredicate validTeam = new ValidTeamPredicate( );

ValidCoachPredicate validCoach = new ValidCoachPredicate( );
```

```
// Tie two Predicates together into an AndPredicate

AndPredicate valuePredicate = new AndPredicate( validTeam, validCoach );


// Decorate a HashMap with a predicate on the value

Map teamMap = PredicatedMap.decorate( new HashMap( ), null, valuePredicate);


// Manufacture some teams

Team redSox = new Team( "Red Sox", new Coach( "Patrick", "Moloney") );

Team yankees= new Team( "Yankees", new Coach( "David", "McGarry") );

Team dodgers = new Team( "Dodgers", new Coach( "Nick", "Taylor") );

Team twins = new Team( null, new Coach( "Patrick", "Moloney") );

Team braves = new Team( "Braves", null );


// The following put calls should work fine

teamMap.put( "RedSox", redSox );

teamMap.put( "Yankees", yankees );

teamMap.put( "Dodgers", dodgers );


// This put should fail because the team name is null

try {

    teamMap.put( "Twins", twins);

} catch( IllegalArgumentException iae ) {

    System.out.println( "Twins put failed, as expected" );

}
```

```
// This put should fail because the coach is null

try {

    teamMap.put( "Braves", braves);

} catch( IllegalArgumentException iae ) {

    System.out.println( "Braves put failed, as expected" );

}
```

An application can assume that every team in `teamMap` has met the following requirements:

- Every `Team` object must have a non-`null` `name` property.
- Every `Team` object must have a non-`null` `coach` property, and this `Coach` object must have a first and last name.

The previous example uses two `Predicate` objects to validate both the team and the coach. These two custom predicates (`ValidTeamPredicate` and `ValidCoachPredicate`) are defined in Examples [Example 5-15](#) and [Example 5-16](#). These `Predicate` objects are passed to the `PredicatedMap.decorate()` method to decorate a `Map` with these conditions. The first `Predicate`, `ValidTeamPredicate`, validates a `Team` object to see if it has a non-`null` `name` property.

Example 5-15. A Predicate to validate a Team's name property

```
import org.apache.commons.collections.Predicate;

public class ValidTeamPredicate implements Predicate {

    public boolean evaluate(Object object) {

        Team team = (Team) object;

        return team.getName( ) != null;

    }

}
```

Example 5-16. Predicate to validate a Team's coach property

```
import org.apache.commons.collections.Predicate;

public class ValidCoachPredicate implements Predicate {

    public boolean evaluate(Object object) {

        boolean validCoach = false;

        Team team = (Team) object;

        if( team.getCoach( ) != null &&

            team.getCoach( ).getFirstName( ) != null &&

            team.getCoach( ).getLastName( ) != null ) {

            validCoach = true;

        }

        return validCoach;

    }

}
```

The second `Predicate`, `ValidCoachPredicate`, validates a `Team` object, checking to see if the `coach` property is non-`null`, and that the coach has a first and last name.

In [Example 5-16](#), a `Predicate` is created by combining the `ValidTeamPredicate` and `ValidCoachPredicate` in an `AndPredicate`. A `HashMap` is then decorated with `PredicatedMap.decorate()`, passing the `AndPredicate` in as the predicate to validate `Map` values. A few `Team` objects are created, all of which are valid with the exception of the Twins and the Braves, and, as expected, the Twins and Braves cause `put()` to throw an `IllegalArgumentException`.

Recipe 5.15 Constraining List Contents

Problem

You need to constrain objects that can be added to a `List`.

Solution

Decorate a `List` using `PredicatedList`. The following example demonstrates the use of `PredicatedList` to create a `List` that only accepts even `Integer` objects:

```
import java.util.*;

import org.apache.commons.collections.list.PredicatedList;

import org.apache.commons.collections.Predicate;

import org.apache.commons.lang.ArrayUtils;

// Create a Predicate that only accepts even Integer objects
Predicate onlyEven = new Predicate( ) {

    public boolean evaluate(Object object) {

        Integer integer = (Integer) object;

        return( integer.intValue( ) % 2 == 0 );

    }

}

List list = PredicatedList.decorate( new ArrayList( ), onlyEven );

list.add( new Integer(1) ); // Will throw IllegalArgumentException
```

```
list.add( new Integer(2) );

list.add( new Integer(3) ); // Will throw IllegalArgumentException

list.add( new Integer(4) );
```

In this example, attempting to add an `Integer` with an odd value causes an `IllegalArgumentException`, but adding an even number does not cause an exception to be thrown.

Discussion

A `PredicatedList` is very similar to a `PredicatedMap`; this decorator works with an existing `List` and adds inbound validation to a `List`. There is no limit to the complexity of the `Predicate` that can be used to provide inbound validation to a `List`.

See Also

`PredicatedList` and `PredicatedMap` are not the only `Collection` decorators available in the Jakarta Commons Collections. Any `Collection` interface in the following list can be decorated with a `Predicate`.

- `PredicatedBag` decorates a `Bag`.
- `PredicatedBuffer` decorates a `Buffer`.
- `PredicatedCollection` decorates a `Collection`.
- `PredicatedList` decorates a `List`.
- `PredicatedMap` decorates a `Map`.
- `PredicatedSet` decorates a `Set`.
- `PredicatedSortedBag` decorates a `SortedBag`.
- `PredicatedSortedMap` decorates a `SortedMap`.
- `PredicatedSortedSet` decorates a `SortedSet`.

For more information about these utilities, see the Jakarta Commons Collections project page at <http://jakarta.apache.org/commons/collections>.

Recipe 5.16 Transforming Collections

Problem

You need to perform a transformation using each element in a `Collection`.

Solution

Use `CollectionUtils.transform()` . Supply a `Collection` and a `Transformer` to this method, and this utility will pass each element in the `Collection` to that `Transformer`, returning a new `Collection` containing the results of each transformation. The following example demonstrates the use of `transform()` with a custom `Transformer` object:

```
import java.util.*;

import org.apache.commons.collections.Transformer;

import org.apache.commons.collections.CollectionUtils;

import org.apache.commons.lang.ArrayUtils;

import org.apache.commons.lang.StringUtils;


// Create a transformer that reverses strings.

Transformer reversingTransformer = new Transformer() {

    public Object transform(Object object) {

        String string = (String) object;

        return StringUtils.reverse( string );

    }

}


String[] array = new String[] { "Aznar", "Blair", "Chirac", "Putin", "Bush" };
```

```
List<String> stringList = Arrays.asList( ArrayUtils.clone( array ) );

// Transform each element with a Transformer

CollectionUtils.transform( stringList, reversingTransformer );

System.out.println( "Original: " + ArrayUtils.toString( array ) );

System.out.println( "Transformed: " +

    ArrayUtils.toString( stringList.toArray( ) ) );
```

This example creates a `List` of strings, transforming each element with a `Transformer` that produces reversed strings. The `List` is transformed in-place, which means that the contents of the `List` are replaced with the output from the `transform()` method of the `Transformer`. As expected, the transformed `List` contains reversed strings:

Original: Aznar, Blair, Chirac, Putin, Bush

Transformed: ranzA, rialB, carihC, nituP, hsuB

`CollectionUtils.transform()` does not only apply to `Lists`; any object implementing the `Collection` interface can be used with this utility.

Discussion

`Transformers` are another form of functor that transforms one object into another, leaving the original object unchanged. `Transformer` is a very straightforward interface, simply requiring the presence of a `transform()` method. The `Transformer` interface, like `Predicate`, is augmented by a number of useful built-in implementations, which can combine the effects of multiple transformers. One of these `Transformer` implementations is the `ChainedTransformer`, which allows you to create a linear pipeline of transformations. The following example demonstrates the use of a `ChainedTransformer` to transform the contents of a `Collection`:

```
import java.util.*;

import org.apache.commons.collections.Transformer;

import org.apache.commons.collections.functors.ChainedTransformer;

import org.apache.commons.collections.CollectionUtils;

import org.apache.commons.lang.ArrayUtils;
```



```
import org.apache.commons.lang.StringUtils;

// Create a transformer that multiplies a number by 10
Transformer multiplyTransform = new Transformer( ) {

    public Object transform(Object object) {

        Integer integer = (Integer) object;

        return new Integer( integer.intValue( ) * 10 );

    }

}

// Create a transformer that subtracts 20 from a number
Transformer subtractTransform = new Transformer( ) {

    public Object transform(Object object) {

        Integer integer = (Integer) object;

        return new Integer( integer.intValue( ) - 20 );

    }

}

// Chain the transformers together
Transformer transformChain = new ChainedTransformer(

    new Transformer[] { multiplyTransform, subtractTransform } );

// Create a List of Integer objects
int[] array = new int[] { 1, 2, 3, 4, 5, 6, 7, 8 };

List intList = Arrays.asList( ArrayUtils.toObject( array ) );
```

```
CollectionUtils.transform( intList, transformChain );

System.out.println( "Original: " + ArrayUtils.toString( array ) );

System.out.println( "Transformed: " +
    ArrayUtils.toString( intList.toArray( ) ) );
```

Two transformers, `multiplyTransform` and `subtractTransform`, are defined as anonymous inner classes, which implement the `Transformer` interface. These two `Transformers` are combined in a `ChainedTransformer`. An array of `int` primitives is converted to an array of `Integer` objects using `ArrayUtils.toObject()`. This object array is then converted to a `List`, which is transformed using `CollectionUtils.transform()`. The transformation multiplies each element by 10 and subtracts 20, producing the following output:

```
Original: 1, 2, 3, 4, 5, 6, 7, 8

Transformed: -10, 0, 10, 20, 30, 40, 50, 60
```

See Also

In addition to the `ChainedTransformer`, there are a number of other useful `Transformer` implementations that ship with Commons Collections. The `ChainedTransformer` and other `Transformer` implementations are discussed in depth in [Chapter 4](#). For more information about the various implementations of `Transformer`, see the Commons Collections project (<http://jakarta.apache.org/commons/collections>).



Recipe 5.17 Creating a Least Recently Used Cache

Problem

You need to present common data to many clients, and you want to cache this common data in a data structure of limited size, evicting the least recently used entry when the maximum size limit has been reached.

Solution

Use `LRUMap`-a fixed size map that uses the least recently used algorithm to evict entries once the maximum size has been reached. The least recently used algorithm evicts the element that has not been used for the longest amount of time. The following example demonstrates the use of an `LRUMap` to store stock quotes:

```
import java.util.Map;

import org.apache.commons.collections.map.LRUMap;

cache = new LRUMap( 5 );

// Populate the cache with 5 stock prices

cache.put( "MSFT", new Float( 0.03 ) );

cache.put( "TSC", new Float( 0.001 ) );

cache.put( "LU", new Float( 23.30 ) );

cache.put( "CSCO", new Float( 242.20 ) );

cache.put( "P", new Float( 10.23 ) );

// Now use some of the entries in the cache

Float cscPrice = (Float) cache.get( "CSCO" );
```

```
Float msPrice = (Float) cache.get( "MSFT" );

Float tscPrice = (Float) cache.get( "TSC" );

Float luPrice = (Float) cache.get( "LU" );

Float pPrice = (Float) cache.get( "P" );

Float msPrice2 = (Float) cache.get( "MSFT" );


// Add another price to the Map, this should kick out the LRU item.

cache.put( "AA", new Float( 203.20 ) );


// CSCO was the first price requested, it is therefore the

// least recently used.

if( !cache.containsKey("CSCO") ) {

    System.out.println( "As expected CSCO was discarded" );

}
```

Since the `LRUMap` created in this example can only hold five elements, the "CSCO" quote is evicted when "AA" is added to the map because it is the "least recently used."

Discussion

An `LRUMap` is appropriate when a system presents common data to a number of clients. For example, if a web site displays breaking news stories, objects representing these stories can be stored in a size-limited cache with an LRU eviction policy, such as `LRUMap`. Demand for objects that represent breaking news stories can be very time sensitive; many customers read the same story at the same time. Your application server has a size-limited `LRUMap` that holds 100 news stories, and, when a new story is added, the `LRUMap` evicts the stalest story in the `Map`.

See Also

The `LRUMap` is an ideal solution for a cache, but, if your application needs to make heavy use of caching, take a look at the following open source cache implementations-OSCache or JCS. For more information about OSCache, see the OpenSymphony OSCache project page (<http://www.opensymphony.com/oscache/>). The Java Caching System (JCS) was an offshoot of the Jakarta Turbine project; for more information about JCS, see the JCS project page

(<http://jakarta.apache.org/turbine/jcs/>).

PREV

< Day Day Up >

Recipe 5.18 Using a Lazy Map

Problem

You need a `Map` that can populate a value when its corresponding key is requested.

Solution

Decorate a `Map` with `LazyMap`. Attempting to retrieve a value with a key that is not in a `Map` decorated with `LazyMap` will trigger the creation of a value by a `Transformer` associated with this `LazyMap`. The following example decorates a `HashMap` with a `Transformer` that reverses strings; when a key is requested, a value is created and put into the `Map` using this `Transformer`:

```
import java.util.*;

import org.apache.commons.collections.Transformer;

import org.apache.commons.collections.map.LazyMap;

import org.apache.commons.lang.StringUtils;

// Create a Transformer to reverse strings - defined below
Transformer reverseString = new Transformer( ) {

    public Object transform( Object object ) {

        String name = (String) object;

        String reverse = StringUtils.reverse( name );

        return reverse;

    }

}

// Create a LazyMap called lazyNames, which uses the above Transformer
```

```
Map names = new HashMap( );

Map lazyNames = LazyMap.decorate( names, reverseString );

// Get and print two names

String name = (String) lazyNames.get( "Thomas" );

System.out.println( "Key: Thomas, Value: " + name );

name = (String) lazyNames.get( "Susan" );

System.out.println( "Key: Susan, Value: " + name );
```

Whenever `get()` is called, the decorated `Map` passes the requested key to a `Transformer`, and, in this case, a reversed string is put into a `Map` as a value. The previous example requests two strings and prints the following output:

```
Key: Thomas, Value: samohT
```

```
Key: Susan, Value: nasuS
```

Discussion

`LazyMap` works best when a key is a symbol or an abbreviation for a more complex object. If you are working with a database, you could create a `LazyMap` that retrieves objects by a primary key value; in this case, the `Transformer` simply retrieves a record from a database table using the supplied key. Another example that springs to mind is a stock quote; in the stock exchange, a company is represented as a series of characters: "YHOO" represents the company Yahoo!, Inc., and "TSC" represents TheStreet.com. If your system deals with a quote feed, use a `LazyMap` to cache frequently used entries. [Example 5-17](#) uses a `LazyMap` to create a cache populated on demand, and it also demonstrates the `LRUMap`-a fixed-size implementation of the `Map` introduced in [Recipe 5.17](#).

Example 5-17. Example using a LazyMap

```
package com.discursive.jccook.collections.lazy;

import java.net.URL;

import java.util.Map;
```

```
import org.apache.commons.collections.map.LRUMap;

import org.apache.commons.collections.map.LazyMap;

public class LazyMapExample {

    Map stockQuotes;

    public static void main(String[] args) throws Exception {

        LazyMapExample example = new LazyMapExample( );

        example.start( );

    }

    public void start( ) throws Exception {

        StockQuoteTransformer sqTransformer = new StockQuoteTransformer( );

        sqTransformer.setQuoteURL( new URL("http://quotes.company.com") );

        sqTransformer.setTimeout( 500 );

        // Create a Least Recently Used Map with max size = 5

        stockQuotes = new LRUMap( 5 );

        // Decorate the LRUMap with the StockQuoteTransformer

        stockQuotes = LazyMap.decorate( stockQuotes, sqTransformer );

        // Now use some of the entries in the cache

        Float price = (Float) stockQuotes.get( "CSCO" );
```



```
        price = (Float) stockQuotes.get( "MSFT" );

        price = (Float) stockQuotes.get( "TSC" );

        price = (Float) stockQuotes.get( "TSC" );

        price = (Float) stockQuotes.get( "LU" );

        price = (Float) stockQuotes.get( "P" );

        price = (Float) stockQuotes.get( "P" );

        price = (Float) stockQuotes.get( "MSFT" );

        price = (Float) stockQuotes.get( "LU" );

        // Request another price to the Map, this should kick out the LRU item.

        price = (Float) stockQuotes.get( "AA" );

        // CSCO was the first price requested, it is therefore the

        // least recently used.

        if( !stockQuotes.containsKey( "CSCO" ) ) {

            System.out.println( "As expected CSCO was discarded" );

        }

    }

}
```

The **Transformer** in [Example 5-17](#) is an object that takes a string and hits a URL using Jakarta HttpClient-a utility introduced in [Chapter 11](#). Every time a new symbol is encountered, this **Transformer** creates another thread with a timeout and hits a "quote server" that is configured to return the latest price for that company's symbol. [Example 5-18](#) defines a **StockQuoteTransformer** that retrieves a quote by passing a stock symbol as a URL parameter.

Example 5-18. A StockQuoteTransformer

```
package com.discursive.jccook.collections.lazy;
```

```
import java.net.URL;

import org.apache.commons.collections.Transformer;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpURL;

import org.apache.commons.httpclient.methods.GetMethod;

public class StockQuoteTransformer implements Transformer {

    protected URL quoteURL;

    protected long timeout;

    public Object transform(Object symbol) {

        QuoteRetriever retriever = new QuoteRetriever( (String) symbol );

        try {

            Thread retrieveThread = new Thread( retriever );

            retrieveThread.start( );

            retrieveThread.join( timeout );

        } catch( InterruptedException ie ) {

            System.out.println( "Quote request timed out." );

        }

        return retriever.getResult( );

    }

}
```

```
public URL getQuoteURL( ) { return quoteURL; }

public void setQuoteURL(URL url) { quoteURL = url; }

public long getTimeout( ) { return timeout; }

public void setTimeout(long l) { timeout = l; }

public class QuoteRetriever implements Runnable {

    private String symbol;

    private Float result = new Float( Float.NaN );

    public QuoteRetriever(String symbol) {

        this.symbol = symbol;

    }

    public Float getResult( ) {

        return result;

    }

    public void run( ) {

        HttpClient client = new HttpClient( );

        try {

            HttpURL url = new HttpURL( quoteURL.toString( ) );

            url.setQuery( "symbol", symbol );

            GetMethod getMethod = new GetMethod( url.toString( ) );

            client.executeMethod( getMethod );
```

```
        String response = getMethod.getResponseBodyAsString( );

        result = new Float( response );

    } catch( Exception e ) {

        System.out.println( "Error retrieving quote" );

    }

}

}
```

The point of this example is to demonstrate the power of decorating an `LRUMap` with `LazyMap` and to write a `Transformer` that can fetch a piece of data from another server, not that the `StockQuoteTransformer` uses Jakarta `HttpClient`.

See Also

For more information about Jakarta `HttpClient`, see [Chapter 11](#). For more information about the `LRUMap`, see [Recipe 5.17](#).

Recipe 5.19 Counting Objects in a Collection

Problem

You need to count the number of times an object occurs in a `Collection`.

Solution

Use `CollectionUtils` methods `countMatches()` or `cardinality()`. `countMatches()` takes a `Collection` and a `Predicate`, returning the number of elements that satisfy that `Predicate`. `cardinality()` takes an `Object` and a `Collection`, returning the number of items equal to the supplied `Object`. The following example demonstrates the use of both methods to count the number of times an `Object` occurs in a `Collection`:

```
import java.util.*;

import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.EqualPredicate;

import org.apache.commons.collections.CollectionUtils;

import org.apache.commons.lang.ArrayUtils;

String[] array = new String[] { "A", "B", "C", "C", "B", "B" };

List<String> stringList = Arrays.asList( array );

Predicate equalPredicate = new EqualPredicate("C");

int numberCs = CollectionUtils.countMatches( stringList, equalPredicate );

int numberBs = CollectionUtils.cardinality( "B", stringList );

System.out.println( "List: " + ArrayUtils.toString( array ) );
```

```
System.out.println( "Number of Cs: " + numberCs );

System.out.println( "Number of Bs: " + numberBs );
```

When used with the `EqualPredicate`, `countMatches()` performs the same function as `cardinality()`. This example produces the following output.

```
List: A, B, C, C, B, B

Number of Cs: 2

Number of Bs: 3
```

Discussion

`countMatches()` is not limited to counting the number of elements in a `Collection` equal to an object; this method can also be used to count objects that meet any arbitrary `Predicate`. For example, you could count the number of elements in a list that match a composite predicate or a custom predicate. The following example demonstrates the use of `countMatches()` to count the number of objects that match a custom predicate:

```
import java.util.*;

import org.apache.commons.collections.Predicate;

import org.apache.commons.collections.functors.EqualPredicate;

import org.apache.commons.collections.CollectionUtils;

import org.apache.commons.lang.ArrayUtils;

int[] array = new int[] { 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 };

List<Integer> intList = Arrays.asList( ArrayUtils.toObject( array ) );

Predicate isEvenPredicate = new Predicate( ) {

    public boolean evaluate(Object object) {

        Integer value = (Integer) object;

        return ( (value.intValue( ) % 2) == 0 );

    }

}
```

```
}
```

```
int numberEven = CollectionUtils.countMatches( intList, isEvenPredicate );
```

```
System.out.println( "List: " + ArrayUtils.toString( array ) );
```

```
System.out.println( "Number of Even Numbers: " + numberEven );
```

This example counts the number of even numbers in a `Collection`; the `isEvenPredicate` is an anonymous inner class that implements the `Predicate` interface. This `Predicate` is passed to `CollectionUtils.countMatches()`, producing the following output:

```
List: 1, 2, 3, 4, 5, 6, 7, 8, 9, 10
```

```
Number of Even Numbers: 5
```

`CollectionUtils` can also return a frequency `Map` for every object in a `Collection`; calling `CollectionUtils.getCardinalityMap()` returns such a `Map`. The keys of this `Map` are the distinct objects in the `Collection`, and the values are `Integer` objects representing the number of times each object appears in the `Collection`. The following example demonstrates the creation of a frequency `Map` from a list of strings:

```
import java.util.*;
```

```
import org.apache.commons.collections.Predicate;
```

```
import org.apache.commons.collections.functors.EqualPredicate;
```

```
import org.apache.commons.collections.CollectionUtils;
```

```
import org.apache.commons.lang.ArrayUtils;
```

```
String[] array = new String[] { "Red", "Blue", "Blue", "Yellow", "Red",  
"Black" };
```

```
List stringList = Arrays.asList( arrays );
```

```
Map cardinalityMap = CollectionUtils.getCardinalityMap( stringList );
```

```
System.out.println( "List: " + ArrayUtils.toString( array ) );

System.out.println( "Cardinality Map:\n" + MapUtils.

debugPrint( cardinalityMap ) );
```

A `String` array is converted to a `List` of strings, and a frequency `Map` is created. This `Map` is printed using `MapUtils.debugPrint()`:

```
List: Red, Blue, Blue, Yellow, Red, Black
```

```
Cardinality Map:
```

```
{

    Red = 3

    Blue = 2

    Yellow = 1

    Black = 1

}
```

See Also

If you are interested in the cardinality of objects in a `Collection`, consider using a `Bag`. A `Bag` is a `Collection` that revolves around the cardinality of objects it contains. `Bag` objects are described in [Recipe 5.6](#).

Recipe 5.20 Performing Set Operations

Problem

You need to perform set operations to find the union, intersection, disjunction, and difference of two collections.

Solution

Use one of four `CollectionUtils` methods to perform set operations-`union()`, `intersection()`, `disjunction()`, and `subtract()`. [Example 5-19](#) demonstrates the use of these four methods with two `Collections`.

Example 5-19. Using `CollectionUtils` `union()`, `intersection()`, `disjunction()`, and `subtract()`

```
import java.util.*;

String[] arrayA = new String[] { "1", "2", "3", "3", "4", "5" };
String[] arrayB = new String[] { "3", "4", "4", "5", "6", "7" };

List a = Arrays.asList( arrayA );
List b = Arrays.asList( arrayB );

Collection union = CollectionUtils.union( a, b );
Collection intersection = CollectionUtils.intersection( a, b );
Collection disjunction = CollectionUtils.disjunction( a, b );
Collection subtract = CollectionUtils.subtract( a, b );
```

```
Collections.sort( union );

Collections.sort( intersection );

Collections.sort( disjunction );

Collections.sort( subtract );

System.out.println( "A: " + ArrayUtils.toString( a.toArray( ) ) );

System.out.println( "B: " + ArrayUtils.toString( b.toArray( ) ) );

System.out.println( "Union: " + ArrayUtils.toString( union.toArray( ) ) );

System.out.println( "Intersection: " +

    ArrayUtils.toString( intersection.toArray( ) ) );

System.out.println( "Disjunction: " +

    ArrayUtils.toString( disjunction.toArray( ) ) );

System.out.println( "Subtract: " + ArrayUtils.toString( subtract.toArray( ) ) );
```

The previous example performs these four operations on two `List` objects, `a` and `b`, printing the results with `ArrayUtils.toString()`:

```
A: {1,2,2,2,3,3,4,5}

B: {3,4,4,5,6,7}

Union: {1,2,2,2,3,3,4,4,5,6,7}

Intersection: {3,4,5}

Disjunction: {1,2,2,2,3,4,6,7}

Subtract: {1,2,2,2,3}
```


Discussion

Pay close attention to how these four functions deal with cardinality. These four set operations on `CollectionUtils`- `union()`, `intersection()`, `disjunction()`, and `subtraction()`- all respect the cardinality of objects in both `Collections`. Take, for example, the results of the union of `a` and `b` in the Solution; the union of `a` and `b` contains two "3" elements and two "4" elements. The cardinality of an element in a union is the maximum cardinality of the element in both `Collections`. On the other hand, the cardinality of an element in an intersection is the minimum cardinality of the

element in both `Collections`; there is only one "3" element and one "4" element in the intersection of `a` and `b`.

[Figure 5-3](#) illustrates each set operation with a Venn diagram. "A union B" is the combination of A and B, and "A intersection B" is the common overlap of A and B. "A subtract B" is all elements only in A, and "A disjunction B" is all elements in either A or B but not both.

Figure 5-3. Venn diagrams for four set operations in `CollectionUtils`



Recipe 5.21 Retrieving Map Values Without Casting

Problem

You need to retrieve a primitive `double` from a `Map`, but the value is stored as a `Double` object.

Solution

Use `MapUtils.getDoubleValue()` to retrieve a `Double` object from a `Map` as a `double` primitive. The following example demonstrates `getDoubleValue()`:

```
import java.util.*;

import org.apache.commons.lang.ArrayUtils;

import org.apache.commons.collections.MapUtils;

Object[] mapArray = new Object[][] {

    { "A", new Double( 2.0 ) },

    { "B", new Double( 0.223242 ) },

    { "C", new Double( 2828e4 ) },

    { "D", "GARBAGE" } };

Map numberMap = ArrayUtils.toMap( mapArray );

double a = MapUtils.getDoubleValue( numberMap, "A" );

double b = MapUtils.getDoubleValue( numberMap, "B" );

double c = MapUtils.getDoubleValue( numberMap, "C" );

double d = MapUtils.getDoubleValue( numberMap, "D", new Double( Double.NaN ) );
```



```
System.out.println( "A = " + a );

System.out.println( "B = " + b );

System.out.println( "C = " + c );

System.out.println( "D = " + d );
```

This simple utility retrieves four doubles from `numberMap`; the fourth call to `getDoubleValue()` supplies a default `double` to be returned if the value's type cannot be converted to a `double`. This example produces the following output:

```
A = 2.0

B = 0.223242

C = 28280.0

D = NaN
```

Discussion

This utility is laughably simple, but if you are working with numbers, this utility can help you avoid casting and calling `doubleValue()`. In addition to `MapUtils.getDoubleValue()`, `MapUtils` also contains the `MapUtils.getDouble()` method, which simply returns a `Double` object. The following example demonstrates the various utility methods for obtaining primitives and their corresponding object types from a `Map`:

```
import java.util.*;

import org.apache.commons.collections.MapUtils;

Map map = new HashMap( );

map.put( "A", new Long( 3.4 ) );

map.put( "B", new Short( 33 ) );

map.put( "C", "BLAH" );

Number aNumber = MapUtils.getNumber( map, "A" );

Long aLong = MapUtils.getLong( map, "A" );
```

```
long a = MapUtils.getLongValue( map, "A" );

short b = MapUtils.getShortValue( map, "B" );

Byte c = MapUtils.getBytes( map, "C", Byte.MAX_VALUE );
```

As shown in the previous example, `MapUtils` contains utility methods for working with `bytes`, `shorts`, and `long`, among other primitive types.

[Table 5-1](#) details several related methods for `Boolean`, `Double`, and `Number`, which can retrieve objects and primitive values from a `Map`. While [Table 5-1](#) deals with `Boolean` and `Double`, you should be aware that similar methods exist for all primitive types and corresponding objects.

Table 5-1. Methods on MapUtils

Return type	Signature
Boolean	<code>getBoolean(Map map, Object key)</code> <code>getBoolean(Map map, Object key, Boolean default)</code>
boolean	<code>getBooleanValue(Map map, Object key)</code> <code>getBooleanBalue(Map map, Object key, boolean default)</code>
Double	<code>getDouble(Map map, Object key)</code> <code>getDouble(Map map, Object key, Double default)</code>
double	<code>getDoubleValue(Map map, Object key)</code> <code>getDoubleValue(Map map, Object key, double default)</code>
Number	<code>getNumber(Map map, Object key)</code> <code>getNumber(Map map, Object key, Number default)</code>

Chapter 6. XML

[Introduction](#)

[Recipe 6.1. Obtaining Jakarta Commons Digester](#)

[Recipe 6.2. Turning XML Documents into Objects](#)

[Recipe 6.3. Namespace-Aware Parsing](#)

[Recipe 6.4. Creating a Simple XML Command Language](#)

[Recipe 6.5. Variable Substitution and XML Parsing](#)

[Recipe 6.6. Obtaining Jakarta Commons Betwixt](#)

[Recipe 6.7. Turning Beans into XML Documents](#)

[Recipe 6.8. Customizing XML Generated from an Object](#)

[Recipe 6.9. Turning XML Documents into Beans](#)

Introduction

Extensible Markup Language (XML) went from a risky buzzword to a ubiquitous data format in a few short years, bringing with it an overwhelming array of tools, standards, APIs, and technologies. World Wide Web Consortium's (W3C) publication of the initial XML recommendation in 1998 redefined the way information is represented, stored, and exchanged, and it seems that a new standard involving XML is created every month: XSL, XML Query, XPointer, XPath, XLink, XHTML, SVG, MathML, XForms, XML Encryption, SOAP, XML-RPC, WSDL, XML Schema, RelaxNG, TREX, and the list continues. Such standards are accompanied by an almost endless series of standard APIs, such as SAX and DOM. To further complicate matters, Sun Microsystems has created a number of Java APIs to handle most everything XML, including JAXP, TrAX, JAXB, JAXM, JAX-RPC, JAXR, and SAAJ. It would take years to become an expert in each of these standards, tools, and APIs, and, because of this, most programmers focus on the tip of the iceberg: SAX, DOM, a little XPath, DTD, and XML Schema. This chapter focuses on parsing and data binding; reading a XML document and creating an XML document from a set of objects.

More than a few developers have noted that parsing a simple XML document with SAX or DOM can be an unreasonably complex task, especially if one is simply attempting to create a prototype. With SAX you need to write a series of callback methods like `startElement()` and `endElement()`, and in DOM, you need to write a not-trivial amount of code to traverse a `Document` object. It isn't the case that you should never write a DOM or SAX parser; there are some systems that call for this level of control and complexity, and a thorough knowledge of SAX, DOM, and JDOM is essential knowledge for any developer. This chapter isn't looking to unseat the reigning standards; instead, this chapter simply introduces you to some tools that sit on top of standard parsers and do some parsing dirty work in specific situations. A very common task in any Java program is reading in an XML document and creating a set of objects, and Commons Digester and Commons Betwixt make this task as simple as it should be.

With almost a trillion different ways to parse or create a simple XML document, you can easily overlook a tool that might save days of programming time. Commons Digester, Commons Betwixt, Zeus, Quick, Apache XMLBeans, JAXB, XStream, JiBX, Exolab Castor, and others are all projects and products that deal with the simple task of serializing objects to XML and unmarshalling XML to objects. This field is crowded, and a number of these technologies have great promises and great flaws. Just as this chapter was not written to convince you to abandon SAX and DOM, this chapter was also not written to sell Digester or Betwixt over all other options. If you don't like what you see in this chapter, there are a variety of options, and while the abundance of choice is overwhelming, open source is about having options and choices. This chapter introduces you to two battle-tested options from Jakarta Commons-Jakarta Commons Digester and Jakarta Commons Betwixt.

Commons Digester makes the task of parsing XML exceedingly straightforward; with the Digester in hand, you can map an XML document to a series of objects using a simple set of rules and a small amount of Java code. If you use Digester with an XML rule set, it is possible to write a system that parses an XML document with three or four lines of compiled code and no hardcoded logic dealing with document structure. Commons Betwixt maps beans to XML documents and vice versa. The `BeanWriter` class can be used to serialize an object as an XML document, and the `BeanReader` can be used to read an XML document. The XML produced by Betwixt can be customized with an XML

document that controls such things as whether properties are to be serialized as attributes or elements, how Collections are handled, or how property names are converted to element or attribute names.

For more information about XML data binding, pick up a copy of Brett McLaughlin's *Java & XML Data Binding* (O'Reilly) or *Java & XML* (O'Reilly). For more information about XML, see the W3C at <http://www.w3c.org>. For a list of technologies, take a look at Ronald Bourret's *XML Data Binding Resources* (<http://www.rpbourret.com/xml/XMLDataBinding.htm>).

Recipe 6.1 Obtaining Jakarta Commons Digester

Problem

You need to use Jakarta Commons Digester to quickly parse an XML document into a set of objects.

Solution

You must download the latest version of Commons Digester and place the Commons Digester JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons Digester 1.5 instead of Commons Lang. Uncompress the distribution archive and place *commons-digester.jar* in your classpath. Commons Digester depends on Commons BeanUtils, Commons Logging, and Commons Collections. To download dependencies, see [Recipe 3.2](#), [Recipe 5.1](#), and [Recipe 7.9](#).

Discussion

Commons Digester started as a part of Jakarta Struts, and it was moved to the Jakarta Commons project by way of the Commons Sandbox in early 2001. Digester is the mechanism Struts uses to read XML configuration; *struts-config.xml* is the main configuration point for Jakarta Struts, and it is converted to a set of objects using the Digester. The Digester's most straightforward application is the mapping of an XML document to a set of Java objects, but, as shown in this chapter and [Chapter 12](#), Digester can also be used to create a simple XML command language and search index. Digester is a shortcut for creating a SAX parser. Almost anything you can do with a SAX parser can be done with Jakarta Commons Digester.

If you have a Maven project that needs to use Commons Digester, add a dependency on Commons Digester 1.5 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-digester</id>

    <version>1.5</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information about Commons Digester, see the Commons Digester project page at <http://jakarta.apache.org/commons/digester>. For information about using the Digester to create a Lucene index, see [Chapter 12](#).

PREV

< Day Day Up >

Recipe 6.2 Turning XML Documents into Objects

Problem

You need to parse an XML document into an object graph, and you would like to avoid using either the DOM or SAX APIs directly.

Solution

Use the Commons Digester to transform an XML document into an object graph. The Digester allows you to map an XML document structure to an object model in an external XML file containing a set of rules telling the Digester what to do when specific elements are encountered. In this recipe, the following XML document containing a description of a play will be parsed into an object graph:

```
<?xml version="1.0"?>

<plays>

  <play genre="tragedy" year="1603" language="english">

    <name>Hamlet</name>

    <author>William Shakespeare</author>

    <summary>

      Prince of Denmark freaks out, talks to ghost, gets into a

      crazy nihilistic funk, and dies in a duel.

    </summary>

    <characters>

      <character protagonist="false">

        <name>Claudius</name>

        <description>King of Denmark</description>

      </character>
```



```
<character protagonist="true">

  <name>Hamlet</name>

  <descr>

    Son to the late, and nephew of the present king

  </descr>

</character>

<character protagonist="false">

  <name>Horatio</name>

  <descr>

    friend to Hamlet

  </descr>

</character>

</characters>

</play>

</plays>
```

This XML document contains a list of `play` elements describing plays by William Shakespeare. One play element describes "Hamlet"; it includes a `name`, `author`, and `summary` element as well as a `characters` element containing `character` elements describing characters in the play. After parsing a document with Digester, each `play` element will be represented by a `Play` object with a set of properties and a `List` of `Character` objects:

```
public class Play {

  private String genre;

  private String year;

  private String language;

  private String name;

  private String author;

  private String summary;
```

```
private List characters = new ArrayList( );

// accessors omitted for brevity

// Add method to support adding elements to characters.
public void addCharacter(Character character) {
    characters.add( character );
}

}

public class Character {
    private String name;
    private String description;
    private boolean protagonist;

    // accessors omitted for brevity
}
```

The Digester maps XML to objects using a set of rules, which can be defined either in an XML file, or they can be constructed programmatically by creating instances of **Rule** and adding them to an instance of **Digester**. This recipe uses an XML file to create a set of rules that tell the Digester how to translate an XML document to a **List** of **Play** objects:

```
<?xml version="1.0"?>

<digester-rules>

    <pattern value="plays/play">

        <object-create-rule classname="xml.digester.Play"/>

        <set-next-rule methodname="add" paramtype="java.lang.Object"/>

    </pattern>
</digester-rules>
```

```
<set-properties-rule/>

<bean-property-setter-rule pattern="name"/>

<bean-property-setter-rule pattern="summary"/>

<bean-property-setter-rule pattern="author"/>


<!-- Nested Pattern for Characters -->

<pattern value="characters/character">

    <object-create-rule classname="xml.digester.Character"/>

    <set-next-rule methodname="addCharacter"

        paramtype="xml.digester.Character"/>

    <set-properties-rule/>

    <bean-property-setter-rule pattern="name"/>

    <bean-property-setter-rule pattern="descr"

        propertyname="description"/>

</pattern>


</pattern>

</digester-rules>
```

This mapping document (or rule sets) can be explained in very straightforward language. It is telling Digester how to deal with the document, "When you see an element matching the pattern *plays/play*, create an instance of `xml.digester.Play`, set some properties, and push it on to a `Stack` (`object-create-rule`). If you encounter an element within a `play` element that matches *characters/character*, create an instance of `xml.digester.Character`, set some properties, and add it to the `Play` object." The following code creates an instance of `Digester` from the XML rule sets shown previously, producing a `plays List`, which contains one `Play` object:

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.xmlrules.DigesterLoader;


List plays = new ArrayList( );
```

```
// Create an instance of the Digester from the XML rule set

URL rules = getClass( ).getResource("./play-rules.xml");

Digester digester = DigesterLoader.createDigester(rules);


// Push a reference to the plays List on to the Stack

digester.push(plays);


// Parse the XML document

InputStream input = getClass( ).getResourceAsStream("./plays.xml");

Object root = digester.parse(input);


// The XML document contained one play "Hamlet"

Play hamlet = (Play) plays.get(0);

List characters = (List) hamlet.getCharacters( );
```

Discussion

Digester is simple, but there is one concept you need to understand: Digester uses a **Stack** to relate objects to one another. In the previous example, **set-next-rule** tells the Digester to relate the top of the **Stack** to the next-to-top of the **Stack**. Before the XML document is parsed, a **List** is pushed onto the **Stack**. Every time the Digester encounters a **play** element, it will create an instance of **Play**, push it onto the top of the **Stack**, and call **add()** with **Play** as an argument on the object next to the top of the stack. Since the **List** is next to the top of the **Stack**, the Digester is simply adding the **Play** to the **playList**. Within the pattern element matching *plays/play*, there is another pattern element matching *characters/character*. When an element matching *characters/character* is encountered, a **Character** object is created, pushed onto the top of the **Stack**, and the **addCharacter()** method is called on the next to top of the **Stack**. When the **Character** object is pushed onto the top of the **Stack**, the **Play** object is next to the top of the **Stack**; therefore, the call to **addCharacter()** adds a **Character** to the **List** of **Character** objects in the **Play** object.

Digester can be summed up as follows: define patterns to be matched and a sequence of actions (rules) to take when these patterns are encountered. Digester is essentially short-hand for your own SAX parser, letting you accomplish the same task without having to deal with the complexity of the SAX API. If you look at the source for the **org.apache.commons.digester.Digester** class, you see

that it implements `org.xml.sax.helpers.DefaultHandler` and that a call to `parse()` causes `Digester` to register itself as a content handler on an instance of `org.xml.sax.XMLReader`. `Digester` is simply a lightweight shell around SAX, and, because of this, you can parse XML just as fast with the `Digester` as with a system written to the SAX API.

`Digester` rule sets can be defined in an external XML document, or programmatically in compiled Java code, but the general rules are the same. The following code recreates the rule set defined in the previous XML rule set:

```
import org.apache.commons.digester.BeanPropertySetterRule;

import org.apache.commons.digester.Digester;

import org.apache.commons.digester.ObjectCreateRule;

import org.apache.commons.digester.Rules;

import org.apache.commons.digester.SetNextRule;

import org.apache.commons.digester.SetPropertiesRule;


Digester digester = new Digester( );


Rules rules = digester.getRules( );


// Add Rules to parse a play element

rules.add( "plays/play", new ObjectCreateRule("xml.digester.Play") );

rules.add( "plays/play", new SetNextRule("add", "java.lang.Object") );

rules.add( "plays/play", new SetPropertiesRule( ) );

rules.add( "plays/play/name", new BeanPropertySetterRule("name") );

rules.add( "plays/play/summary", new BeanPropertySetterRule("summary") );

rules.add( "plays/play/author", new BeanPropertySetterRule("author") );


// Add Rules to parse a character element

rules.add( "plays/play/characters/character", new

    ObjectCreateRule("xml.digester.Character") );
```

```
rules.add( "plays/play/characters/character",  
  
    new SetNextRule("addCharacter", "xml.digester.Character"));  
  
rules.add( "plays/play/characters/character", new SetPropertyRule( ) );  
  
rules.add( "plays/play/characters/character/name",  
  
    new BeanPropertySetterRule("name") );  
  
rules.add( "plays/play/characters/character/description",  
  
    new BeanPropertySetterRule("description") );
```

While this is perfectly acceptable, think twice about defining Digester rule sets programmatically. Defining rule sets in an XML document provides a very clear separation between the framework used to parse XML and the configuration of the Digester. When your rule sets are separate from compiled code, it will be easier to update and maintain logic involved in parsing; a change in the XML document structure would not involve changing code that deals with parsing. Instead, you would change the model and the mapping document. Defining Digester rule sets in an XML document is a relatively new Digester feature, and, because of this, you may find that some of the more advanced capabilities of Digester demonstrated later in this chapter are not available when defining rule sets in XML.

See Also

More information about Digester XML rule sets can be found in the package document for `org.apache.commons.digester.xmlrules` (<http://jakarta.apache.org/commons/digester/apidocs/index.html>).

Recipe 6.3 Namespace-Aware Parsing

Problem

You need to parse an XML document with multiple namespaces.

Solution

Use Digester to parse XML with multiple namespaces, using `digester.setNamespaceAware(true)`, and supplying two `RuleSet` objects to parse elements in each namespace. Consider the following document, which contains elements from two namespaces: *http://discursive.com/page* and *http://discursive.com/person*.

```
<?xml version="1.0"?>

<pages xmlns="http://discursive.com/page"

    xmlns:person="http://discursive.com/person">

    <page type="standard">

        <person:person firstName="Al" lastName="Gore">

            <person:role>Co-author</person:role>

        </person:person>

        <person:person firstName="George" lastName="Bush">

            <person:role>Co-author</person:role>

        </person:person>

    </page>

</pages>
```

To parse this XML document with the Digester, you need to create two separate sets of rules for each namespace, adding each `RuleSet` object to `Digester` with `addRuleSet()`. A `RuleSet` adds `Rule` objects to an instance of `Digester`. By extending the `RuleSetBase` class, and setting the

`namespaceURI` in the default constructor, the following class, `PersonRuleSet`, defines rules to parse the *http://discursive.com/person* namespace:

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.RuleSetBase;

public class PersonRuleSet extends RuleSetBase {

    public PersonRuleSet( ) {

        this.namespaceURI = "http://discursive.com/person";

    }

    public void addRuleInstances(Digester digester) {

        digester.addObjectCreate("*/person", Person.class);

        digester.addSetNext("*/person", "addPerson");

        digester.addSetProperties("*/person");

        digester.addBeanPropertySetter("*/person/role", "role");

    }

}
```

`PersonRuleSet` extends `RuleSetBase`, which is an implementation of the `RuleSet` interface. `RuleSetBase` adds support for namespaces with a protected field `namespaceURI`. The constructor of `PersonRuleSet` sets the `namespaceURI` field to *http://discursive.com/person*, which tells the `Digester` to apply these rules only to elements and attributes in the *http://discursive.com/person* namespace. `PageRuleSet` extends `RuleSetBase` and provides a set of rules for the *http://discursive.com/page* namespace:

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.RuleSetBase;

public class PageRuleSet extends RuleSetBase {

    public PageRuleSet( ) {

        this.namespaceURI = "http://discursive.com/page";

    }

}
```



```

    }

    public void addRuleInstances(Digester digester) {

        digester.addObjectCreate("*/page", Page.class);

        digester.addSetNext("*/page", "addPage");

        digester.addSetProperties("*/page");

        digester.addBeanPropertySetter("*/page/summary", "summary");

    }

}

```

Both `RuleSet` implementations instruct the Digester to create a `Page` or a `Person` object whenever either element is encountered. The `PageRuleSet` instructs the Digester to create a `Page` object when a `page` element is encountered by using a wildcard pattern- `*/page`. Both `PageRuleSet` and `PersonRuleSet` use `digester.addSetNext()` to add the objects just created to the next object in the `Stack`. In the following code, an instance of `Pages` is pushed onto the Digester `Stack`, and both `RuleSet` implementations are added to a `Digester` using `addRuleSet()` :

```

import org.apache.commons.digester.Digester;

import org.apache.commons.digester.ObjectCreateRule;

import org.apache.commons.digester.RuleSetBase;

import org.apache.commons.digester.Rules;

import org.apache.commons.digester.SetNextRule;

```

```

Pages pages = new Pages( );

```

```

Digester digester = new Digester( );

digester.setNamespaceAware(true);

digester.addRuleSet( new PageRuleSet( ) );

digester.addRuleSet( new PersonRuleSet( ) );

```

```
digester.push(pages);

InputStream input = getClass().getResourceAsStream("./content.xml");

digester.parse(input);

Page page = (Page) pages.getPages().get(0);

System.out.println(page);
```

Because the `PageRuleSet` adds each `Page` object to the next object on the `Stack`, the `Pages` object has an `addPage()` method that accepts a `Page` object.

Discussion

Each of the `RuleSet` implementations defined a set of rules in compiled Java code. If you prefer to define each set of rules in an XML file, you may use the `FromXmlRuleSet` instead of the `RuleSetBase`, as follows:

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.xmlrules.FromXmlRuleSet;

Pages pages = new Pages();

Digester digester = new Digester();

digester.setNamespaceAware(true);

// Add page namespace

digester.setRuleNamespaceURI("http://discursive.com/page");

URL pageRules = getClass().getResource("./page-rules.xml");

digester.addRuleSet(new FromXmlRuleSet(pageRules));
```

```
// Add person namespace

digester.setRuleNamespaceURI("http://discursive.com/person");

URL personRules = getClass().getResource("./person-rules.xml");

digester.addRuleSet( new FromXmlRuleSet( personRules ) );


digester.push(pages);


InputStream input = getClass().getResourceAsStream("./content.xml");

digester.parse(input);


Page page = (Page) pages.getPages().get(0);

System.out.println(page);
```

Calling `digester.setRuleNamespaceURI()` associates the Rules contained in each `FromXmlRuleSet` with a specific namespace. In the Solution, the `RuleSetBase` protected field `namespaceURI` was used to associate `RuleSet` objects with namespaces. In the previous example, the namespace is specified by calling `setRuleNamespaceURI()` before each `FromXmlRuleSet` is added to the `digester` because there is no access to the protected member variable, `namespaceURI`, which `FromXmlRuleSet` inherits from `RuleSetBase`. *person-rules.xml* contains an XML rule set for parsing the *http://discursive.com/person* namespace:

```
<?xml version="1.0"?>


<!DOCTYPE digester-rules PUBLIC

    "-//Jakarta Apache //DTD digester-rules XML V1.0//EN"

    "http://jakarta.apache.org/commons/digester/dtds/digester-rules.dtd">


<digester-rules>

    <pattern value="*/page">

        <object-create-rule classname="com.discursive.jccook.xml.bean.Page"/>

        <set-next-rule methodname="addPage"/>
```

```
<set-properties-rule/>

<bean-property-setter-rule pattern="summary" name="summary" />

</pattern>

</digester-rules>
```

`page-rules.xml` contains an XML rule set for parsing the *`http://discursive.com/page`* namespace:

```
<?xml version="1.0"?>

<!DOCTYPE digester-rules PUBLIC

    "-//Jakarta Apache //DTD digester-rules XML V1.0//EN"

    "http://jakarta.apache.org/commons/digester/dtds/digester-rules.dtd">

<digester-rules>

    <pattern value="*/person">

        <object-create-rule classname="com.discursive.jccook.xml.bean.Person" />

        <set-next-rule methodname="addPerson" />

        <set-properties-rule/>

        <bean-property-setter-rule pattern="role" />

    </pattern>

</digester-rules>
```

See Also

For more information relating to the use of namespaces in the `Digester`, refer to the Javadoc for the `org.apache.commons.digester` package at <http://jakarta.apache.org/commons/digester/apidocs>.

Recipe 6.4 Creating a Simple XML Command Language

Problem

You would like to capture commands in an XML document, and create a framework to execute these commands.

Solution

Write a custom implementation of `Rule`, and create a rule set that instructs Commons Digester to invoke these rules when specific elements are parsed. Consider the example of a system that sends an encrypted email. The following XML document contains instructions for the primitive encryption of an email:

```
<?xml version="1.0"?>

<operations xmlns="http://discursive.com/textmanip">

  <email to="tobrien@discursive.com"

    from="root@discursive.com">

    <replace search="o" replace="q"/>

    <replace search="d" replace="z"/>

    <lower/>

    <reverse/>

  </email>

</operations>
```

The `email` tag surrounds three elements-`replace`, `lower`, and `reverse`. The system that executes these commands receives a message as a `String` and runs this `String` through three stages before sending an email to *tobrien@discursive.com*. When the parser encounters the `replace` element, it replaces all occurrences of the contents of the `search` attribute with the contents of the `replace` attribute. When the parser encounters a `lower` element, it translates all characters to lowercase; and when the parser encounters a `reverse` element, it reverses the `String`. When the parser encounters

the end of the `email` element, the result of these four operations is sent to the recipient specified in the `to` attribute of the `email` element.

```
import org.apache.commons.digester.Digester;

// Message object that holds text to manipulate
Message message = new Message( );

message.setText( "Hello World!" );

System.out.println( "Initial Message: " + message.getText( ) );

// XML Document with set of commands
InputStream encrypt = getClass( ).getResourceAsStream( "./encrypt.xml" );

// Create Custom Rules (or Commands)
Digester digester = new Digester( );

digester.addRule( "*/email", new EmailRule( ) );
digester.addRule( "*/lower", new LowerRule( ) );
digester.addRule( "*/reverse", new ReverseRule( ) );
digester.addRule( "*/replace", new ReplaceRule( ) );

digester.push( message );

// Parse the XML document - execute commands
digester.parse( encrypt );

System.out.println("Resulting Message: " + message.getText( ) );
```

The `Message` object is a bean with one `String` property: `text`. This `Message` object is pushed onto the `Digester`'s `Stack` and is acted upon by each of the commands in the XML document *encrypt.xml*,

shown previously. This code is executed, and the following output is produced showing that the original message has been passed through two replace commands, a lowercase command, and a reverse command:

Intial Message: Hello World!

Resulting Message: !zlrqw qlleh

This example defines three new extensions of `Rule`: `EmailRule`, `LowerRule`, `ReverseRule`, and `ReplaceRule`. Each of these rules will retrieve and operate upon the root object from the `Digester`; this "root" object is the bottom of the `Stack`, and, in this case, the `Message` object pushed onto the `Digester` before parsing. These rules are assigned to patterns; for example, the previous code associates the `EmailRule` with the `*/email` pattern and the `LowerRule` with the `*/lower` pattern. The `Rule` object defines a series of callback methods to handle different stages of parsing an element-`begin()`, `body()`, `end()`, and `finish()`. The `LowerRule` from the previous example overrides one method, and manipulates the `Message` that which is on the top of the `Digester Stack`:

```
package com.discursive.jccook.xml.bean;

import org.apache.commons.digester.Rule;

import org.apache.commons.lang.StringUtils;

public class LowerRule extends Rule {

    public LowerRule( ) { super( ); }

    public void body(String namespace, String name, String text)

        throws Exception {

        Message message = (Message) digester.getRoot( );

        String lower = StringUtils.lowerCase( message.getText( ) );

        message.setText( lower );

    }

}
```

`LowerRule` uses `StringUtils` from Commons Lang to translate the `text` property of the `Message`

object to lowercase. If you need to write a `Rule` that can access attributes, you would override the `begin()` method. The following class, `ReplaceRule`, extends `Rule` and overrides the `begin()` method:

```
package com.discursive.jccook.xml.bean;

import org.apache.commons.digester.Rule;

import org.apache.commons.lang.StringUtils;

import org.xml.sax.Attributes;

public class ReplaceRule extends Rule {

    public ReplaceRule( ) { super( ); }

    public void begin(Attributes attributes) throws Exception {

        Message message = (Message) digester.getRoot( );

        String repl = attributes.getValue("search");

        String with = attributes.getValue("replace");

        String text = message.getText( );

        String translated =

            StringUtils.replace( text, repl, with );

        message.setText( translated );

    }

}
```

`ReplaceRule` reads the `search` and `replace` attributes, using `StringUtils` to replace all occurrences of the search `String` in the `text` property of `Message` with the replace `String`. The `EmailRule` demonstrates a more complex extension of the `Rule` object by overriding `begin()` and `end()`:

```
import org.apache.commons.digester.Rule;
```



```
import org.apache.commons.net.smtp.SMTPClient;

import org.xml.sax.Attributes;

public class EmailRule extends Rule {

    private String to;

    private String from;

    public EmailRule( ) { super( ); }

    public void begin(Attributes attributes) throws Exception {

        to = attributes.getValue( "to" );

        from = attributes.getValue( "from" );

    }

    public void end( ) throws Exception {

        Message message = (Message) digester.getRoot( );

        SMTPClient client = new SMTPClient( );

        client.connect("www.discursive.com");

        client.sendMessage(from, to, message.getText( ) );

    }

}
```

The `email` element encloses the four elements that control the primitive message encryption, and the end of this element tells this rule to send an email to the address specified in the `to` attribute recorded in `begin()`. `EmailRule` uses the `SMTPClient` from Commons Net to send a simple email in `end()`.

Discussion

The `Rule` class defines four methods that you can override to execute code when XML is parsed-`begin()`, `body()`, `end()`, and `finish()`. `begin()` provides access to an element's attributes; `body()` provides access to the element's namespace, local name, and body text; `end()` is called when the end of an element is encountered; and `finish()` is called after `end()` and can be used to clean up data or release resources, such as open network connections or files. When using the Digester in this manner, you are using a technique much closer to writing a SAX parser; instead of dealing with a single `startElement`, `Digester` registers itself as a content handler with an `XMLReader` and delegates to `Rule` objects associated with a given pattern. If you are simply dealing with attributes, elements, and text nodes, Commons Digester can be a very straightforward alternative to writing a SAX parser.

See Also

This recipe uses `StringUtils` to manipulate text. For more information about `StringUtils`, see [Chapter 2](#). An email message is sent from the `EmailRule` using the `SMTPClient` from Commons Net. For more information about Commons Net, see [Chapter 10](#).

Recipe 6.5 Variable Substitution and XML Parsing

Problem

You need to parse XML that contains references to variables, and you need to replace these references with variable values at parse time.

Solution

Use Commons Digester's `MultiVariableExpander` and the `VariableSubstitutor` to expand variable references in an XML document during a parse.

This recipe explores a feature of Commons Digester-variable substitution-which is available only with a prerelease version of Digester, 1.6-dev. To follow the example in this recipe, you must download a nightly snapshot distribution from <http://cvs.apache.org/builds/jakarta-commons/nightly/>. Use nightly distributions of Commons components at your own risk; these distributions may contain unresolved bugs.

The following XML document contains four variable references- `${email.to}`, `${order.id}`, `${user.name}`, and `${product.name}`-all of which need to be replaced with values before the XML is parsed by the `Digester`:

```
<?xml version="1.0"?>

<email to="${email.to}" from="ceo@xyzblah.com">

  <subject>Purchase Confirmation: ${order.id}</subject>

  <priority>High</priority>

  <message>

    Dear ${user.name}, we appreciate your business. As CEO

    of Big Software Company, Inc., I would like to

    personally thank you for helping us become filthy rich.
```

```
        Your purchase of ${product.name} helped me purchase an  
        even larger boat for myself.  Thanks again.  
    </message>  
</email>
```

This document represents a purchase confirmation message, and your system needs to unmarshall the above message to the following class, `Email`:

```
public class Email {  
  
    private String to;  
  
    private String from;  
  
    private String subject;  
  
    private String priority;  
  
    // accessors omitted for brevity.  
  
}
```

The following XML rule set is similar to the rule set defined in [Recipe 6.2](#). When the parser hits an `email` element, an instance of `Email` is created and properties are populated:

```
<?xml version="1.0"?>  
  
<digester-rules>  
  
    <pattern value="email">  
  
        <object-create-rule classname="com.discursive.jccook.xml.bean.Email"/>  
  
        <set-next-rule methodname="add" paramtype="java.lang.Object"/>  
  
        <set-properties-rule/>  
  
        <bean-property-setter-rule pattern="subject"/>  
  
        <bean-property-setter-rule pattern="priority"/>  
  
        <bean-property-setter-rule pattern="message"/>  
  
    </pattern>  
  
</digester-rules>
```



```
</pattern>

</digester-rules>
```

This difference between this recipe and [Recipe 6.2](#) is that our XML document contains variables to be replaced at parse time. The following code creates a `Map` that contains variables referenced in the XML document being parsed. This code creates the variable `Map`, reads the XML rule set from *email-rules.xml*, and parses the XML document *email.xml*.

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.Substitutor;

import org.apache.commons.digester.substitution.MultiVariableExpander;

import org.apache.commons.digester.substitution.VariableSubstitutor;

import org.apache.commons.digester.xmlrules.DigesterLoader;

// Read the Digester XML rule set and create Digester
URL rules = getClass().getResource("./email-rules.xml");

Digester digester = DigesterLoader.createDigester(rules);

// Create object to push onto Digester Stack
List emails = new ArrayList();

digester.push( emails );

// Create Map of variables
Map vars = new HashMap();

vars.put("email.to", "ldavid@hbo.com");

vars.put("user.name", "Tim");

vars.put("order.id", "1RR2E223WVVS" );

vars.put("product.name", "Foundation" );
```

```
// Create an expander with the Map that matches ${var}

MultiVariableExpander expander = new MultiVariableExpander( );

expander.addSource("$", vars);

// Create a substitutor with the expander

Substitutor substitutor = new VariableSubstitutor(expander);

digester.setSubstitutor(substitutor);

// Parse XML document

InputStream input = getClass( ).getResourceAsStream("./email.xml");

digester.parse( input );

// Retrieve Email object

Email email = (Email) emails.get(0);

System.out.println( "Email Subject: " + email.getSubject( ) );

System.out.println( "Email To: " + email.getTo( ) );
```

Variable substitution is performed by a `VariableSubstitutor` that has been configured with a `MultiVariableExpander`. The `MultiVariableExpander` retrieves variables from a `Map`, and, in this example, the `addSource()` method is called with a `$` marker. This means that variables are referenced by surrounding a variable name with `${` and `}--${variable}`. The previous example produces the following output, which demonstrates the substitution of variables:

```
Email Subject: Purchase Confirmation: 1RR2E223WVVS
```

```
Email To: ldavid@hbo.com
```

Discussion

Variable substitution is part parsing, part templating, and can be valuable when you need to specify a set of default properties on a bean that need to be parameterized for different situations. The example in this recipe was an email message confirming a purchase from an e-commerce system, but there are other situations where an object may need to be personalized with a user identifier or a username.

See Also

For more information about other new features planned for Digester 1.6, see the current development Javadoc for the Digester at <http://jakarta.apache.org/commons/digester/apidocs/index.html>.

PREV

< Day Day Up >

Recipe 6.6 Obtaining Jakarta Commons Betwixt

Problem

You need to use Jakarta Commons Betwixt to serialize and deserialize beans to and from XML documents.

Solution

You must download the latest version of Commons Betwixt, and place the Commons Betwixt JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons Betwixt 0.5 instead of Commons Lang. Uncompress the distribution archive and place *commons-betwixt.jar* in your classpath. Commons Betwixt depends on Commons Digester, Commons BeanUtils, Commons Logging, and Commons Collections. To download dependencies, see [Recipe 3.2](#), [Recipe 5.1](#), [Recipe 6.1](#), and [Recipe 7.9](#).

Discussion

Betwixt allows you to translate from beans to XML and vice versa. Beans are serialized to XML documents using a **BeanWriter**, and they are read from XML using a **BeanReader**. The structure of the XML can be automatically generated or customized using an XML document to bind properties to elements or attributes.

If you have a Maven project that needs to use Commons Betwixt, add a dependency on Commons Betwixt 0.5 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-betwixt</id>

    <version>0.5</version>

  </dependency>

  ....other dependencies...

</dependencies>
```


See Also

For more information about Commons Betwixt, see the Commons Betwixt project page at <http://jakarta.apache.org/commons/betwixt>.

PREV

< Day Day Up >

Recipe 6.7 Turning Beans into XML Documents

Problem

You need to create an XML document from a bean.

Solution

Use Commons Betwixt `BeanWriter` to transform a bean to an XML document. The following code turns an instance of the `Play` object from [Recipe 6.2](#) into an XML document:

```
import org.apache.commons.betwixt.io.BeanWriter;

Play play = new Play( );

// populatePlay populates all properties and nested Character objects
populatePlay( play );

// Write XML document

BeanWriter beanWriter = new BeanWriter( );

beanWriter.enablePrettyPrint( );

beanWriter.write( play );

System.out.println( beanWriter.toString( ) );
```

A `BeanWriter` instance is created, indentation is enabled with a call to `enablePrettyPrint()`, and the `Play` object is written to an XML document with `beanWriter.write()`. The previous example prints an XML document with structure similar to the XML document parsed in [Recipe 6.2](#) with the exception of the `genre`, `year`, and `language` elements. The following XML document is produced by the call to `beanWriter.write()`:

```
<Play>

<author>William Shakespeare</author>

<characters>

  <character>

    <description>King of Denmark</description>

    <name>Claudius</name>

    <protagonist>false</protagonist>

  </character>

  <character>

    <description>

      Son to the late, and nephew of the present

      king

    </description>

    <name>Hamlet</name>

    <protagonist>true</protagonist>

  </character>

  <character>

    <description>friend to Hamlet</description>

    <name>Horatio</name>

    <protagonist>false</protagonist>

  </character>

</characters>

<genre>tragedy</genre>

<language>english</language>

<name>Hamlet</name>

<summary>
```

```
// Pass FileWriter to BeanWriter
```



```
BeanWriter beanWriter = new BeanWriter( outputWriter );

beanWriter.setEndOfLine( "\r\n" );

beanWriter.setIndent( "\t" );

beanWriter.enablePrettyPrint( );

beanWriter.write( play );


// Close FileWriter

outputWriter.close( );
```

Since the previous example contains a call to `setEndOfLine()`, `enablePrettyPrint()`, and `setIndent()`, *test.dat* will have DOS-style line termination and Betwixt will use the tab character for indentation.

See Also

By default, `BeanWriter` writes every bean property of `Play` as an element. [Recipe 6.8](#) shows you how to customize the XML generated by Betwixt.

Recipe 6.8 Customizing XML Generated from an Object

Problem

You are trying to create an XML document from a Java object, and you want to customize the layout and structure of the generated XML document.

Solution

Use a Betwixt mapping file to customize the output of the `BeanWriter`. Below is an example of a mapping file for the `Play` class, which was introduced in [Recipe 6.2](#). When Betwixt serializes or deserializes an object to or from XML, it will search for a resource, `<classname>.betwixt`, in the same package as the class to be written or read. The following XML document- `Play.betwixt`-is stored in the same package as the `Play` class, and it customizes the XML output from Betwixt:

```
<info primitiveTypes="element">

  <element name="play">

    <attribute name="genre" property="genre"/>

    <attribute name="year" property="year"/>

    <attribute name="language" property="language"/>

    <addDefaults/>

  </element>

</info>
```

This file tells Betwixt that `genre`, `year`, and `language` shall be stored as XML attributes, and that the remaining bean properties are to be written as XML elements. The following code is used to create a customized XML document from an instance of `Play`:

```
import org.apache.commons.betwixt.io;

Play play = (Play) plays.get(0);
```

```
BeanWriter beanWriter = new BeanWriter( );

beanWriter.enablePrettyPrint( );

beanWriter.write( play );

logger.debug( beanWriter.toString( ) );
```

Betwixt creates the following XML document, which stores the `genre`, `year`, and `language` properties as attributes of the `play` element. The differences between this XML document and the XML document in [Recipe 6.7](#) are emphasized:

```
<play genre="tragedy" year="1603" language="english">

  <author>William Shakespeare</author>

  <characters>

    <character protagonist="false">

      <description>King of Denmark</description>

      <name>Claudius</name>

    </character>

    <character protagonist="true">

      <description>Son to the late, and nephew of the present king</description>

      <name>Hamlet</name>

    </character>

    <character protagonist="false">

      <description>friend to Hamlet</description>

      <name>Horatio</name>

    </character>

  </characters>

  <name>Hamlet</name>

  <summary>Prince of Denmark (Hamlet) freaks out, talks to father's ghost, and
```

```
        finally dies in a duel.</summary>
</play>
```

Discussion

The previous example wrote the `protagonist` property of the `Character` class as an attribute of the `character` element. This customization was accomplished by putting a *Character.betwixt* resource in the same package as the `Character` class. *Character.betwixt* is shown here:

```
<info primitiveTypes="element">

  <element name="character">

    <attribute name="protagonist" property="protagonist"/>

    <addDefaults/>

  </element>

</info>
```

In addition to customizing the structure on an XML document, a Betwixt mapping file can also be used to change the names of elements and attributes in an XML document. The following mapping file-another version of *Character.betwixt*-writes the `description` property of `Character` as a `bio` element:

```
<info primitiveTypes="element">

  <element name="character">

    <attribute name="protagonist" property="protagonist"/>

    <element name="bio" property="description"/>

    <addDefaults/>

  </element>

</info>
```

In this recipe, Betwixt has wrapped all `character` elements in a `characters` element. If you prefer `character` elements to be child elements of `play`, you can tell the `XMLIntrospector` used by `BeanWriter` to omit elements wrapping collections with the following code:

```
import org.apache.commons.betwixt.io.BeanWriter;

import org.apache.commons.betwixt.XMLIntrospector;
```



```
Play play = (Play) plays.get(0);

BeanWriter beanWriter = new BeanWriter( );

beanWriter.enablePrettyPrint( );

// Configure XML Introspector to omit collection elements

XMLIntrospector introspector = beanWriter.getXMLIntrospector( );

introspector.setWrapCollectionsInElement(false);

beanWriter.write( play );

logger.debug( beanWriter.toString( ) );
```

The previous code creates an XML document without the `characters` element:

```
<play genre="tragedy" year="1603" language="english">

  <author>William Shakespeare</author>

  <character protagonist="false">

    <description>King of Denmark</description>

    <name>Claudius</name>

  </character>

  <character protagonist="true">

    <description>Son to the late, and nephew of the present king</description>

    <name>Hamlet</name>

  </character>

  <character protagonist="false">

    <description>friend to Hamlet</description>
```

```
<name>Horatio</name>

</character>

<name>Hamlet</name>

<summary>Prince of Denmark (Hamlet) freaks out, talks to father's ghost, and
    finally dies in a duel.</summary>

</play>
```

Betwixt also allows for the customization of element and attribute names; for example, if your class contains the property `maximumSpeed`, it can be written as an attribute named `maximum-speed` or `MAXIMUM_SPEED`, using the `HyphenatedNameMapper` strategy. The same property could also be written as an element named `MaximumSpeed`, using the `CapitalizeNameMapper` strategy. Different naming strategies can be used for elements and attributes by passing instances of `NameMapper` to `setElementNameMapper()` and `setAttributeNameMapper()` on an `XMLIntrospector`. The following code demonstrates the setting of both the attribute and element `NameMapper` on a `BeanWriter`'s `XMLIntrospector`:

```
import org.apache.commons.betwixt.io.BeanWriter;

import org.apache.commons.betwixt.XMLIntrospector;

import org.apache.commons.betwixt.strategy.CapitalizeNameMapper;

import org.apache.commons.betwixt.strategy.HyphenatedNameMapper;

BeanWriter beanWriter = new BeanWriter( );

// Set NameMappers on XMLIntrospector

XMLIntrospector introspector = beanWriter.getXMLIntrospector( );

introspector.setElementNameMapper( new CapitalizeNameMapper( ) );

introspector.setAttributeNameMapper( new HyphenatedNameMapper( ) );

beanWriter.write( object );
```

See Also

For more information about possible customizations in Betwixt, see the "Binding Beans" section of the user guide at <http://jakarta.apache.org/commons/betwixt/guide/binding.html>.



Recipe 6.9 Turning XML Documents into Beans

Problem

You need to convert an XML document into a Bean.

Solution

Use Betwixt's `BeanReader` to parse an XML document and create an instance of the appropriate bean. Register bean classes with the `BeanReader`, and parse an XML document loaded from an `InputStream`, `InputStream`, or `Reader`. The following XML document will be parsed into the `Play` and `Character` beans introduced in [Recipe 6.2](#):

```
<play genre="tragedy" year="1603" language="english">

  <author>William Shakespeare</author>

  <character protagonist="false">

    <description>King of Denmark</description>

    <name>Claudius</name>

  </character>

  <character protagonist="true">

    <description>Son to the late, and nephew of the present king</description>

    <name>Hamlet</name>

  </character>

  <character protagonist="false">

    <description>friend to Hamlet</description>

    <name>Horatio</name>

  </character>

  <name>Hamlet</name>
```



```
<summary>Prince of Denmark (Hamlet) freaks out, talks to father's ghost, and
    finally dies in a duel.</summary>

</play>
```

This XML document was created with `BeanWriter`, using the customized format from [Recipe 6.8](#). To read this XML document with `BeanReader`, the `Play` class will need to be registered with `BeanReader` and the `XMLIntrospector` must have the same settings as the `XMLIntrospector` used when writing the document with `BeanWriter`. The following code instantiates and configures a `BeanReader` to read this customized XML for the `Play` object:

```
import org.apache.commons.betwixt.io.BeanReader;

InputStream customPlay =

    getClass().getResourceAsStream("./customized-play.xml");

BeanReader beanReader = new BeanReader( );

beanReader.getXMLIntrospector( ).setWrapCollectionsInElement(false);

beanReader.registerBeanClass(Play.class);

Play play = (Play) beanReader.parse( customPlay );
```

Discussion

Betwixt uses Commons Digester to parse XML, and the `BeanReader` object is an extension of the `Digester`. `BeanReader` creates a Digester rule set using introspection and the Betwixt mapping files available on the classpath. Digester, as introduced in the first half of this chapter, is a quick way to parse an XML document; all that is required to parse XML with the Digester is a rule set and a little bit of code. Betwixt is built-upon Digester, and the `BeanReader` further reduces the amount of work required to parse XML to a bean. Instead of completing the process demonstrated in [Recipe 6.2](#), you can simply write a few, very manageable, *.betwixt* files using `BeanReader` to read the XML documents and `BeanWriter` to write the XML documents.

When Betwixt is adding `Character` objects to the characters `List` on a `Play` object, it's calling the `addCharacter()` method on the `Play` object. Without this `addCharacter()` object, Betwixt would not be able to populate this `List`. Betwixt automatically recognizes a plural property name such as `characters`, `characterList`, or `characterSet`, and it attempts to call the corresponding `addCharacter()` method. For more information about the algorithm Betwixt uses to recognize composite properties, see "Using Adder Methods for Composite Properties" in the Betwixt user guide (<http://jakarta.apache.org/commons/betwixt/guide/binding.html>).

See Also

For more information about reading beans with Betwixt, see "Reading Beans" in the Betwixt user guide (<http://jakarta.apache.org/commons/betwixt/guide/reading.html>).

PREV

< Day Day Up >

Chapter 7. Application Infrastructure

[Introduction](#)

[Recipe 7.1. Obtaining Commons CLI](#)

[Recipe 7.2. Parsing a Simple Command Line](#)

[Recipe 7.3. Parsing a Complex Command Line](#)

[Recipe 7.4. Printing Usage Information](#)

[Recipe 7.5. Obtaining Commons Configuration](#)

[Recipe 7.6. Configuring Applications with Properties Files](#)

[Recipe 7.7. Configuring Applications with XML](#)

[Recipe 7.8. Using Composite Configuration](#)

[Recipe 7.9. Obtaining Commons Logging](#)

[Recipe 7.10. Using an Abstract Logging Interface](#)

[Recipe 7.11. Specifying a Logging Implementation](#)

[Recipe 7.12. Obtaining Apache Log4J](#)

[Recipe 7.13. Configuring Log4J with a Properties File](#)

[Recipe 7.14. Configuring Log4J with XML](#)

Introduction

The plumbing of an application-command-line parsing, configuration, and logging-can be viewed as application infrastructure. This chapter introduces a few tools to help applications work with configuration, arguments, and log files: Commons CLI for command-line parsing, Commons Configuration for reading application configuration from properties files and XML documents, Commons Logging, and Log4J.



Recipe 7.1 Obtaining Commons CLI

Problem

You need to use Commons CLI (Command-Line Interface) to parse an application's command-line arguments.

Solution

Download Commons CLI 1.0. Following the steps outlined in [Recipt 1.1](#), download "Commons CLI 1.0" instead of Commons Lang. The Commons CLI archive- *cli-1.0.zip*-contains a file named *commons-cli-1.0.jar*; place this JAR file in your classpath, and you are ready to use Commons CLI in your application.

Discussion

Commons CLI provides a standard mechanism for parsing command-line arguments. Contained in the `org.apache.commons.cli` package, CLI provides a set of classes that can parse command-line arguments containing optional arguments, arguments with parameters, and short and long arguments. As shown in this chapter, CLI also provides a mechanism for printing out usage information.

See Also

For more information about Commons CLI, see the Commons CLI project page (<http://jakarta.apache.org/commons/cli>).

For C developers, see the getopt and argp in the GNU C Library. For more information, see the section "Parsing Program Arguments" in the GNU C Library manual (http://www.gnu.org/software/libc/manual/html_node/index.html).

Recipe 7.2 Parsing a Simple Command Line

Problem

You need to parse a simple command line containing optional and required arguments.

Solution

Use the Jakarta Commons CLI to parse program arguments. Populate an `Options` object to configure command-line parsing. Pass the `Options` class and a `String[]` of arguments to a `CommandLineParser`, which parses and returns a `CommandLine` object capturing the supplied options and parameters.

For the purposes of this recipe, assume that you are attempting to parse a command line with three optional arguments: `-h`, `-v`, and `-f <filename>`. `-h` prints out a simple help message with usage information and available command-line options, `-v` runs the program with verbose logging, and `-f` sends the output of the application to a file. To parse this command line, your `main()` method would resemble the following code:

```
import org.apache.commons.cli.CommandLineParser;

import org.apache.commons.cli.BasicParser;

import org.apache.commons.cli.Options;

import org.apache.commons.cli.CommandLine;

public static void main(String[] args) throws Exception {

    // Create a Parser

    CommandLineParser parser = new BasicParser( );

    Options options = new Options( );

    options.addOption("h", "help", false, "Print this usage information");

    options.addOption("v", "verbose", false, "Print out VERBOSE information" );
```

```
options.addOption("f", "file", true, "File to save program output to");

// Parse the program arguments

CommandLine commandLine = parser.parse( options, args );

// Set the appropriate variables based on supplied options

boolean verbose = false;

String file = "";

if( commandLine.hasOption('h') ) {

    System.out.println( "Help Message" )

    System.exit(0);

}

if( commandLine.hasOption('v') ) {

    verbose = true;

}

if( commandLine.hasOption('f') ) {

    file = commandLine.getOptionValue('f');

}

}
```

Discussion

The `Options` object tells the `CommandLineParser` to expect three arguments: `-h`, `-v`, and `-f`. The first argument to `options.addOption()` is the short name or abbreviation of the option, and the second argument is the long name of the argument. When the long name of an option is specified, either may be used as program arguments. For example, a command line specifying short-name

arguments, `-h -v -f test.xml`, is equivalent to a command line specifying long-name arguments, `--help --version --file test.xml`, and both short- and long-name arguments may be mixed in the same command line. The third argument to `options.addOption()` specifies whether the option takes a parameter; in the previous example, only the file option expects a parameter. The fourth parameter is a `String` containing a description of the option for a user.

An `Options` object may be configured using the `options.addOption()`, or an `Option` object can be created and added to the `Options` object. The following code is equivalent to the call to `options.addOption()` in the previous example, which adds the help option:

```
Option helpOption = new Option("h", "Prints this usage information");

helpOption.setLongOpt( "help" );

options.addOption( helpOption );
```

Both the `Options` object and the `args String[]` are passed to `parser.parse()`, which returns a `CommandLine` object. `CommandLine` captures the supplied program arguments, and provides access to the supplied options and arguments. `commandLine.hasOption('h')` checks for the presence of the optional help choice, and `commandLine.getOptionValue('f')` retrieves the filename argument for the file option.

See Also

In this recipe, `BasicParser`, an implementation of `CommandLineParser`, is used to parse command lines. This implementation allows for mixed short- and long-name options: `-f test.xml --help`. If you are developing an application that needs to parse arguments using POSIX Conventions, use `org.apache.commons.cli.PosixParser` instead of `BasicParser`. If you need to parse arguments using the less strict GNU conventions, use the `org.apache.commons.cli.GNUParser`.

For background about the differences between POSIX and GNU standards, see Section 4.6 of the "GNU Coding Standards" (http://www.gnu.org/prep/standards_18.html). For information about POSIX syntax guidelines, see Section 12.2, "Utility Syntax Guidelines" of "The Single UNIX Specification Version 3" (<http://www.unix-systems.org/online.html>), also known as IEEE Standard 1003.1 and ISO/IEC 9945.



Recipe 7.3 Parsing a Complex Command Line

Problem

You need to parse a command line with two exclusive options.

Solution

Store mutually exclusive `Option` objects in an `OptionGroup`, and add this `OptionGroup` to an `Options` object using the `addOptionGroup()` method. Assume you are working with the following program argument specification: `-h`, `-v`, and `-f <filename> | -m <email>`. `-h` and `-v` are both optional and only one of `-f` or `-m` can be specified. If both `-m` and `-f` are supplied as program arguments, an exception is thrown. In the following example, the `-f` and `-m` options are added to an `OptionGroup`, which is then added to the `Options` object used to parse the program arguments:

```
import org.apache.commons.cli.CommandLineParser;

import org.apache.commons.cli.BasicParser;

import org.apache.commons.cli.Options;

import org.apache.commons.cli.OptionBuilder;

import org.apache.commons.cli.OptionGroup;

import org.apache.commons.cli.CommandLine;

public static void main(String[] args) throws Exception {

    // Create a Parser

    CommandLineParser parser = new BasicParser( );

    Options options = new Options( );

    options.addOption("h", "help", false, "Print this usage information");

    options.addOption("v", "verbose", false, "Print out VERBOSE information" );
```

```
OptionGroup optionGroup = new OptionGroup( );

optionGroup.addOption( OptionBuilder.hasArg( true ).create( 'f' ) );

optionGroup.addOption( OptionBuilder.hasArg( true ).create( 'm' ) );

options.addOptionGroup( optionGroup );


// Parse the program arguments

CommandLine commandLine = parser.parse( options, args );


// ... do important stuff ...

}
```

If the user supplies both `-f` and `-m` at the same time, the `CommandLineParser` will throw an `AlreadySelectedException`.

Discussion

In the Solution, the `-f` and `-m` options were created using the `OptionBuilder` class. This utility lets you build an `Option` object by chaining a series of method calls. For example, the following code creates a required option, "b," which takes an argument:

```
Option option = OptionBuilder.hasArgs( true ).isRequired( true ).create( 'b' );
```

`OptionGroup` objects are a good way to enforce the structure of command-line options. If you were parsing the command line with a `StringTokenizer` and keeping track of all of the specified options that may or may not have parameters, this could involve 30 or 40 lines of code just to manage this validation process. By using the Jakarta Commons CLI, you delegate this complexity and cut down on the amount of code you need to maintain.

See Also

What happens if a user specifies two options from an `OptionGroup`? Does the application just fail catastrophically from a `RuntimeException`? Usually, if a program has a problem parsing command-line arguments, it will print out a helpful usage message. "Printing Usage Information" demonstrates the use of CLI to automatically create a usage message.

Recipe 7.4 Printing Usage Information

Problem

You need to provide the user with a formatted list of available options.

Solution

Pass an `Options` object to a `HelpFormatter` and print a usage message. Example 7-1 creates the same `Options` object from Recipe 7.3 . If the help option is specified, or if there is a problem parsing the program arguments, the `printUsage()` method is called to print usage information to `System.out` .

Example 7-1. Printing usage information with HelpFormatter

```
import org.apache.commons.cli.CommandLineParser;

import org.apache.commons.cli.BasicParser;

import org.apache.commons.cli.Options;

import org.apache.commons.cli.OptionBuilder;

import org.apache.commons.cli.OptionGroup;

import org.apache.commons.cli.CommandLine;

import org.apache.commons.cli.HelpFormatter;

public class SomeApp {

    private static final String USAGE = "[-h] [-v] [-f <file> | -m <email>]";

    private static final String HEADER =

        "SomeApp - A fancy and expensive program, Copyright 2010 Blah.";

    private static final String FOOTER =

        "For more instructions, see our website at: http://www.blah123.org";
```



```
public static void main(String[] args) throws Exception {

    // Create a Parser

    CommandLineParser parser = new BasicParser( );

    Options options = new Options( );

    options.addOption("h", "help", false, "Print this usage
                                                                    information");

    options.addOption("v", "verbose", false, "Print out VERBOSE
                                                                    information" );

    OptionGroup optionGroup = new OptionGroup( );

    optionGroup.addOption( OptionBuilder.hasArg(true).withArgName("file")
                                                                    .withLongOpt("file").create('f') );

    optionGroup.addOption( OptionBuilder.hasArg(true).withArgName("email")
                                                                    .withLongOpt("email").create('m') );

    options.addOptionGroup( optionGroup );

    // Parse the program arguments

    try {

        CommandLine commandLine = parser.parse( options, args );

        if( commandLine.hasOption('h') ) {

            printUsage( options );

            System.exit(0);

        }

        // ... do important stuff ...

    }
```

```
        } catch( Exception e ) {

            System.out.println( "You provided bad program arguments!" );

            printUsage( options );

            System.exit(1);

        }

    }

    private static void printUsage(Options options) {

        HelpFormatter helpFormatter = new HelpFormatter( );

        helpFormatter.setWidth( 80 );

        helpFormatter.printHelp( USAGE, HEADER, options, FOOTER );

    }

}
```

When this application is executed and the parser encounters an unexpected program argument, the following output is produced:

```
You provided bad program arguments!
```

```
usage: [-h] [-v] [-f <file> | -m <email>]
```

```
SomeApp - A fancy and expensive program, Copyright 2010 Blah.
```

```
-f,--file <file>
```

```
-h,--help          Print this usage information
```

```
-m,--email <email>
```

```
-v,--verbose       Print out VERBOSE information
```

```
For more instructions, see our website at: http://www.blah123.org
```

Discussion

If an exception is thrown during `parser.parse()`, the application will print an error message and call `printUsage()`, which creates a `HelpFormatter` object and sets the display width to 80 characters.

`helpFormatter.printHelp()` prints to standard out and takes five parameters, including the `Options` object, which contains configuration for the `CommandLineParser` . The first parameter specified a usage string, which is an abbreviated specification of the program arguments: `-h , -v , and -f <file> | -m <email>` . The second argument is a header to print before the list of available options. The third parameter is the same `Options` object passed to the `CommandLineParser` . `HelpFormatter` will use this `Options` object to print out the short name, long name, and description of each option. The fourth parameter is a footer to display after the list of options.





Recipe 7.5 Obtaining Commons Configuration

Problem

You need to use Commons Configuration to access configuration stored in properties files and XML documents.

Solution

Commons Configuration 1.0 is not yet released, but you may download a nightly build from <http://cvs.apache.org/builds/jakarta-commons/nightly/commons-configuration/>. As Commons Configuration approaches a 1.0 release, a full binary release may also be available. Once Commons Configuration is released, you should be able to download a JAR by following the steps outlined in [Recipe 1.1](#) and downloading "Commons Configuration 1.0" instead of Commons Lang. The Commons Configuration archive contains a JAR file named *commons-configuration-1.0-rc1.jar*, which should be placed in your classpath.

Discussion

Commons Configuration is designed to provide access to application configuration in the form of properties files, XML documents, JNDI resources, or data from a JDBC **DataSource**. Commons Configuration also allows you to create a hierarchical or multileveled configuration allowing for default settings to be selectively overridden by local configuration. Commons Configuration also provides typed access to single- and multivalued configuration parameters.

See Also

For more information about the Commons Configuration project, see the Commons Configuration project page at <http://jakarta.apache.org/commons/configuration>.



Recipe 7.6 Configuring Applications with Properties Files

Problem

You need to access configuration parameters as typed objects. In other words, you have configuration parameters that may be numbers or lists of strings, and you want to access them as typed objects instead of first retrieving them as `String` objects from a `Properties` object.

Solution

Use the `PropertiesConfiguration` from Commons Configuration in the `org.apache.commons.configuration` package. This class loads a properties file and provides access to numbers, arrays, and lists. The following properties file contains three properties: `speed` is a floating-point number, `names` is a comma-separated list of strings, and `correct` is a boolean value:

```
speed=23.332
```

```
names=Bob,Gautam,Jarret,Stefan
```

```
correct=false
```

This properties file is stored in `test.properties` in the working directory of an application, which needs access to all three properties as a `float`, `List`, and `boolean`. The following code creates a `PropertiesConfiguration` and accesses each property:

```
import org.apache.commons.configuration.Configuration;
```

```
import org.apache.commons.configuration.PropertiesConfiguration;
```

```
Configuration config = new PropertiesConfiguration( "test.properties" );
```

```
float speed = config.getFloat("speed");
```

```
List names = config.getList("names");
```

```
boolean correct = config.getBoolean("correct");
```

Discussion

Passing a `String` to the constructor of `PropertiesConfiguration` will load configuration properties from a file named *test.properties*. Properties are then referenced by the key of the property in the properties file. This recipe demonstrates a modest improvement upon the existing `Properties` class that ships with the J2SE. The methods provided by the `Configuration` interface enable you to retrieve properties with a specific type, throwing a `NumberFormatException`, `ClassCastException`, and `NoSuchElementException` if there is a problem finding or parsing a property value.

See Also

For a full list of the methods provided by the `Configuration` interface, see the Commons Configuration JavaDoc at <http://jakarta.apache.org/commons/configuration/apidocs>.

PREV

< Day Day Up >



Recipe 7.7 Configuring Applications with XML

Problem

You need to configure an application with an XML document.

Solution

Use an implementation of `XMLConfiguration` to load configuration parameters from an XML document. The following XML document contains configuration information that is loaded with a `DOMConfiguration` object:

```
<?xml version="1.0" encoding="ISO-8859-1" ?>
```

```
<engine-config>
```

```
  <start-criteria>
```

```
    <criteria type="critical">
```

```
      Temperature Above -10 Celsius
```

```
    </criteria>
```

```
    <criteria>
```

```
      Fuel tank is not empty
```

```
    </criteria>
```

```
  </start-criteria>
```

```
  <name>
```

```
    <first>Tom</first>
```

```
    <last>Payne</last>
```

```
  </name>
```

```
  <horsepower>42</horsepower>
```

```
</engine-config>
```

A `DOMConfiguration` object uses the Xerces XML parser to parse an entire XML document into a `DOM Document` object. Subsequent calls to methods on the `Configuration` interface cause the `DOMConfiguration` object to traverse nodes in the `Document`. The code to read in this XML configuration with `DOMConfiguration` follows:

```
import org.apache.commons.configuration.Configuration;

import org.apache.commons.configuration.DOMConfiguration;

String resource = "com/discursive/jccook/configuration/global.xml";

Configuration config = new DOMConfiguration(resource);

// Retrieve a list of all Criteria elements

List startCriteria = config.getList("start-criteria.criteria");

// Retrieve the value of the first criteria element

String firstCriteria = config.getString("start-criteria.criteria(0)");

// Retrieve the type attribute of the first criteria element

String firstCriteriaType = config.getString("start-criteria.criteria(0)[@type]");

// Retrieve the horsepower as an int

int horsepower = config.getInt("horsepower");
```

Discussion

Passing a `String` to the constructor of `DOMConfiguration` loads an XML document from the classpath as a resource. If you need to load XML configuration from a file, pass a `File` object to the `DOMConfiguration` constructor. Configuration parameters are retrieved using methods from the `Configuration` interface, and parameters are referenced using a syntax that resembles XPath. Subelements are referenced by appending a period and the subelement name to the name of an

element; in this example, `name.first` references the subelement `first` of the element `name`. Attributes are referenced by prefixing an attribute name with an `@` and surrounding the reference with brackets; in this example, `start-criteria.criteria(0)[@type]` references the `type` attribute of the `criteria` element. Specific elements in a list of elements are referenced by surrounding the index with parentheses; `start-criteria.criteria(0)` references the first `criteria` element.

`DOMConfiguration` will only work if the Xerces XML parser is available in your classpath. If Xerces is not available, you may use another implementation of `XMLConfiguration`, `DOM4JConfiguration`, which is written to parse an XML document using DOM4J. To use the `DOM4JConfiguration`, make sure that DOM4J is in your classpath, and interchange `DOM4JConfiguration` with `DOMConfiguration` from the previous example.

See Also

For more information about downloading the Xerces XML parser, see the Xerces project page at <http://xml.apache.org/xerces>.

For more information about downloading DOM4J, see the DOM4J project page at <http://www.dom4j.org>.

Recipe 7.8 Using Composite Configuration

Problem

Your application calls for a multilayered configuration where a set of default properties can be selectively overridden by local or user configuration preferences.

Solution

Create a *configuration.xml* file that contains references to multiple properties files, and pass this file to a `ConfigurationFactory`. A `ConfigurationFactory` will then return a `Configuration` implementation that obtains configuration parameters from multiple properties file.

[Table 7-1](#) lists configuration properties for an application. A global configuration layer defines default values for configuration parameters. A local configuration layer allows you to customize the behavior of a system at a particular site, and the user configuration layer refines configuration parameters for a specific user. When an application retrieves the value of "name," the user layer's value of "Sean" overrides the global layer's value of "Default User."

Table 7-1. Three layers of configuration

Property	Global	Local	User
threads.max	50	30	
threads.min	20		1
timeout	15.52		
interactive	TRUE		
color	red		black
speed	50	55	75
name	Default User		Sean

Properties are stored in three separate files shown in Examples[Example 7-2](#) (*global.properties*), [Example 7-3](#) (*local.properties*), and [Example 7-4](#) (*user.properties*).

Example 7-2. global. properties

```
threads.max=50

threads.min=2

timeout=15.52

interactive=true

color=red

speed=50

name=Default User
```

Example 7-3. local .properties

```
# Overrides Global Props

threads.max=30

speed=55
```

Example 7-4. user. properties

```
# Overrides Local Props

threads.min=1

color=black

speed=5000

name=Sean
```

A *configuration.xml* file provides a configuration for the `ConfigurationFactory`. This file is stored as a resource in the classpath, and the URL for this resource is passed to the `setConfigurationURL()` method of `ConfigurationFactory`. The following *configuration.xml* will create a `Configuration` object, which locates properties from properties files using the override order defined in the XML document. *user.properties* overrides *local.properties*, which overrides *global.properties*.

```
<?xml version="1.0" encoding="ISO-8859-1" ?>

<configuration>
```

```

        <properties fileName="user.properties"/>

        <properties fileName="local.properties"/>

        <properties fileName="global.properties"/>

</configuration>

```

The following code passes the URL of the *configuration.xml* resource to a `ConfigurationFactory`, and a `Configuration` instance is returned, which resolves application configuration parameters according to the rules outlined above:

```

import org.apache.commons.configuration.Configuration;

import org.apache.commons.configuration.ConfigurationFactory;

// Configure Factory

ConfigurationFactory factory = new ConfigurationFactory( );

URL configURL = this.getClass( ).getResource("configuration.xml");

factory.setConfigurationURL( configURL );

Configuration config = factory.getConfiguration( );

// Print out properties

System.out.println( "Timeout: " + config.getFloat("timeout"));

System.out.println( "Max Threads: " + config.getString("threads.max"));

System.out.println( "Name: " + config.getString("name"));

System.out.println( "Speed: " + config.getInt("speed"));

```

This code executes and prints the value of four properties to the console. The `timeout` property is retrieved from *global.properties*, the `threads.max` property is retrieved from *local.properties*, and both `speed` and `name` are retrieved from *user.properties*.

```
Timeout: 15.52
```

```
Max Threads: 30
```


Name: Sean

Speed: 75

Discussion

The *configuration.xml* file instructs the `ConfigurationFactory` to create a `Configuration` implementation based on multiple properties files. In the previous example, when the application retrieves a property, there is no parameter signifying the source of the property. There is no mechanism for obtaining the source of a configuration property; in other words, there is no way for our application to see which properties file a particular value was obtained from, and there is no mechanism for enumerating the properties in a single properties file. The *configuration.xml* file "configures" the `ConfigurationFactory` to create a `Configuration`-complexity is hidden from the application and the source of configuration can be changed with no effect to this example.

A *configuration.xml* file can also instruct a `ConfigurationFactory` to use a mixture of properties files and XML documents. The following *configuration.xml* instructs the `ConfigurationFactory` to create a `Configuration` instance that looks for properties from a properties file and an XML document:

```
<?xml version="1.0" encoding="ISO-8859-1" ?>

<configuration>

    <properties fileName="test.properties"/>

    <dom4j fileName="test.xml"/>

</configuration>
```

With this configuration, a `Configuration` instance will attempt to locate a property with a matching key in *test.properties* before it attempts to locate the matching property in *test.xml*. See [Recipe 7.7](#) for more information about retrieving configuration from XML documents.

See Also

In addition to properties files and XML documents, Commons Configuration can also be instructed to resolve configuration properties from a JNDI tree using `org.apache.commons.configuration.JNDIConfiguration`. For more information on accessing properties in a JNDI tree using Commons Configuration, see the "Configuration Overview" page on the Commons Configuration project site (<http://jakarta.apache.org/commons/configuration/overview.html>).

Recipe 7.9 Obtaining Commons Logging

Problem

You need to use Commons Logging to develop a system that works under various logging frameworks, including Sun's logging framework and Apache Log4J.

Solution

Download Commons Logging 1.0.3. Following the steps outlined in [Recipe 1.1](#), download "Commons Logging 1.0.3" instead of Commons Lang. The Commons Logging archive- *commons-logging-1.0.3.zip*-will contain a file named *commons-logging.jar*. Place this JAR file in your classpath, and you will be ready to use Commons Logging.

Discussion

Commons Logging was created for developers who need to create components or libraries that may need to operate in environments with different logging frameworks, including Apache Log4J and the built-in logging framework introduced in Java 1.4. Using Commons Logging, a component like Commons BeanUtils or Commons Digester can write log messages to an abstracted **Log** interface, and Commons Logging can deal with passing these log messages to whichever logging framework is available. Commons Logging is used in almost every Jakarta Commons component.

If you have a Maven project that needs to use Commons Logging, add a dependency on Commons Logging 1.0.3 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-logging</id>

    <version>1.0.3</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information about Commons Logging, see the Commons Logging project site (<http://jakarta.apache.org/commons/logging>).



Recipe 7.10 Using an Abstract Logging Interface

Problem

You are writing a reusable library, and you do not know where or how your code will execute. You need to write log messages to an abstracted logging interface because you cannot count on the presence of Log4J or JDK 1.4 logging.

Solution

Write messages to the Jakarta Commons Logging `Log` interface, and rely on Commons Logging to decide which concrete logging framework to use at runtime. The following code uses the `Log` interface to log trace, debug, info, warning, error, and fatal messages:

```
import org.apache.commons.logging.LogFactory;
```

```
import org.apache.commons.logging.Log
```

```
Log log = LogFactory.getLog( "com.discursive.jccook.SomeApp" );
```

```
if( log.isTraceEnabled( ) ) {
```

```
    log.trace( "This is a trace message" );
```

```
}
```

```
if( log.isDebugEnabled( ) ) {
```

```
    log.debug( "This is a debug message" );
```

```
}
```

```
log.info( "This is an informational message" );
```



```
log.warn( "This is a warning" );
```

```
log.error( "This is an error" );
```

```
log.fatal( "This is fatal" );
```

`LogFactory.getInstance()` returns an implementation of the `Log` interface, which corresponds to an underlying concrete logging framework. For example, if your system is configured to use Apache Log4J, a `Log4JLogger` is returned, which corresponds to the Log4J category *com.discursive.jccook.SomeApp*.

Discussion

The developers of a reusable library can rarely predict where and when such a library will be used, and since there are a number of logging frameworks currently available, it makes sense to use Commons Logging when developing reusable components such as Jakarta Commons components. When `LogFactory.getInstance()` is called, Commons Logging takes care of locating and managing the appropriate logging framework by testing a number of system properties and libraries available on the classpath. For the developer of a small reusable component, the complexity ends at the calls to the `Log` interface; the burden of configuring the underlying logging framework is shifted to the developer integrating this library into a larger system.

See Also

[Recipe 7.11](#) details the algorithm Commons Logging uses to identify the appropriate concrete logging framework to use at runtime.



Recipe 7.11 Specifying a Logging Implementation

Problem

You are using a component that writes log messages with Commons Logging, and you need to configure the underlying logging implementation.

Solution

If the system property *org.apache.commons.logging.Log* is not set, Commons Logging will use Apache Log4J if it is available in the classpath. To explicitly configure Commons Logging to use Log4J set the *org.apache.commons.logging.Log* property to `org.apache.commons.logging.impl.Log4JLogger` with the following statement:

```
System.setProperty( "org.apache.commons.logging.Log" ,  
                    "org.apache.commons.logging.impl.Log4JLogger" );
```

If the system property *org.apache.commons.logging.Log* is not set and Apache Log4J is not available on the classpath, Commons Logging will then use the built-in JDK 1.4 logging framework. To explicitly configure Commons Logging to use the JDK 1.4 logging framework, set the *org.apache.commons.logging.Log* property to `org.apache.commons.logging.impl.Jdk14Logger`.

If neither Apache Log4J nor the JDK 1.4 logging framework is available on the classpath and the *org.apache.commons.logging.Log* system property is not set, Commons Logging uses a basic logging implementation named `SimpleLog`. To explicitly configure Commons Logging to use `SimpleLog`, set the *org.apache.commons.logging.Log* property to `org.apache.commons.logging.impl.SimpleLog`.

Discussion

To summarize, Commons Logging performs the following steps when choosing an underlying logging implementation:

1. Checks the *org.apache.commons.logging.Log* system property. If this property is set, use the class specified in this property.
2. Checks for the presence of Log4J in the classpath. If Log4J is present, use a `Log4JLogger` instance.

3. Checks for the presence of the JDK 1.4 logging framework. If JDK 1.4 is present, use a `JDK14Logger` instance.

If neither Log4J nor JDK 1.4 is available, use `SimpleLog`.

See Also

For more information about the configuration of Apache Log4J, see [Recipe 7.13](#) and [Recipe 7.14](#). For more information about the configuration of the JDK 1.4 logging framework, see Sun's documentation of this framework at <http://java.sun.com/j2se/1.4.2/docs/guide/util/logging/>.

`SimpleLog` is a very simple logger that can be used when an application does not need a complex logging framework. For more information about configuring `SimpleLog` via system properties, read the Commons Logging JavaDoc at <http://jakarta.apache.org/commons/logging/api/index.html>.

 PREV

< Day Day Up >



Recipe 7.12 Obtaining Apache Log4J

Problem

You need to use Apache Log4J to print statements to a log file for informational or debugging purposes.

Solution

Download Apache Log4J 1.2.8 from the Binary Downloads page (<http://logging.apache.org/site/binindex.cgi>) of the Apache Logging Services project. On this page you will find two links to *Jakarta-log4j-1.2.8.tar.gz* and *Jakarta-log4j-1.2.8.zip*. Once this archive is uncompressed, you will find a *log4j-1.2.8.jar* file in the *dist/lib* directory. Put this JAR file in your classpath and you will be ready to use Log4J in your application.

Discussion

Log4J (formerly known as Jakarta Log4J) is a highly configurable logging framework providing hierarchical loggers, various log destinations, and log formats. Messages are written to Log4J **Logger** objects, which represent a specific category in a hierarchy of log categories; for example, the *com.discursive.Blah* category is a child of the *com.discursive* category. All messages sent to a child category are sent to each ancestor in a tree of **Logger** categories. A category can be assigned an **Appender** and a **Layout**; an **Appender** controls where a message is sent, and a **Layout** defines the formatting and contents of a message. Log4J ships with a number of **Appender** implementations, including **SMTPAppender**, **RollingFileAppender**, **SocketAppender**, **SyslogAppender**, and **NTEventLogAppender**. Log4J also ships with a number of **Layout** implementations, including **XMLLayout**, **PatternLayout**, **HTMLLayout**, and **DateLayout**.

See Also

For more information about the Apache Logging Services project, see the Logging Services project page at <http://logging.apache.org>. For more information about the Apache Log4J project, see the Log4J project page at <http://logging.apache.org/log4j/docs/>.

Recipe 7.13 Configuring Log4J with a Properties File

Problem

You need to use Log4J, and you would like to configure it with a properties file.

Solution

Use the `BasicConfigurator` to read a *log4j.properties* file resource from the classpath. The following code configures Log4J from a resource named *log4j.properties*, and logs two messages:

```
import org.apache.log4j.PropertyConfigurator;

import org.apache.log4j.Logger;

URL log4Jresource = this.getClass( ).getResource("log4j.properties");

PropertyConfigurator.configure( log4Jresource );

Logger log = Logger.getLogger( "com.discursive.SomeApp" );

log.info( "This is a log message" );

log.error( "This is an error message" );
```

The *log4j.properties* file contains a basic Log4J configuration that sets the root category logging level to `WARN` and the application's logging level to `DEBUG`:

```
# All logging output sent to standard out and a file

# WARN is default logging level

log4j.rootCategory=WARN, STDOUT, FILE

# Application logging level is DEBUG
```

```
log4j.logger.com.discursive=DEBUG

# Configure the Standard Out Appender

log4j.appender.STDOUT=org.apache.log4j.ConsoleAppender

log4j.appender.STDOUT.layout=org.apache.log4j.PatternLayout

log4j.appender.STDOUT.layout.ConversionPattern=%5p (%F:%L) %m%n


# Configure a rolling file appender

log4j.appender.FILE=org.apache.log4j.RollingFileAppender

log4j.appender.FILE.File=output.log

log4j.appender.FILE.MaxFileSize=2000KB

log4j.appender.FILE.MaxBackupIndex=5

log4j.appender.FILE.layout=org.apache.log4j.PatternLayout

log4j.appender.FILE.layout.ConversionPattern=%d %-5p %c - %m%n
```

This example prints a single info message to the console with the following format:

```
INFO (Sample.java:24) This is a log message

ERROR (Sample.java:25) This is an error message
```

The `rootCategory` is configured to send all log messages to the console and a `RollingFileAppender`. A file named *output.log* contains the following content after this code has been executed:

```
2004-06-14 00:12:22,324 INFO Sample - This is a log message

2004-06-14 00:12:22,326 ERROR Sample - This is an error message
```

Discussion

`PropertyConfigurator.configure()` takes a URL referencing a resource to be loaded from the classpath. This properties file is read and Log4J is configured to send all messages to both the console and a file. Content is written to a file using a `RollingFileAppender`, which writes to a file until it reaches a configurable maximum size (2 MB). Once this size has been reached, a

`RollingFileAppender` will move the existing *output.log* file to a file named *output.log.1* and create a new *output.log* file. As configured in the previous example, the `RollingFileAppender` will keep five backup log files, moving *output.log.1* to *output.log.2* and *output.log* to *output.log.1* the next time a log file's maximum size has been reached.

The Solution configures the default logging level to be `WARN`, meaning that all log messages lower on the level hierarchy will not be sent to appenders. Log4J has five default levels, and they are listed in order of importance: `DEBUG`, `INFO`, `WARN`, `ERROR`, and `FATAL`. If a category is configured with a logging level of `ERROR`, only `ERROR` and `FATAL` messages are sent to appenders, and if a category is configured with a logging level of `DEBUG`, all logging messages are sent to appenders. If you are only interested in the debugging output from your own program, set the `rootCategory` to a high logging level, and override that level for your application's classes. `log4j.logger.com.discursive=DEBUG` overrides the `rootCategory`'s logging level for every topic at or below the `com.discursive` logging category.

See Also

The properties file shown in the Solution should be used as a starting point for Log4J configuration. For more information about various implementations of `Appender` or syntax for `ConversionPattern`, see the Log4J API documentation at <http://logging.apache.org/log4j/docs/api/index.html>.

Recipe 7.14 Configuring Log4J with XML

Problem

You need to configure Log4J with an XML document.

Solution

Use the `DOMConfigurator` to configure Log4J with an XML document. The following code configures Log4J from a resource named *log4j.xml*, and logs two messages:

```
import org.apache.log4j.DOMConfigurator;

import org.apache.log4j.Logger;

URL log4Jresource = this.getClass( ).getResource("log4j.xml");

DOMConfigurator.configure( log4Jresource );

Logger log = Logger.getLogger( "com.discursive.SomeApp" );

log.info( "This is a log message" );

log.error( "This is an error message" );
```

The *log4j.xml* file contains a basic Log4J configuration, which sets the root category logging level to `WARN`, and the application's logging level to `DEBUG`. This XML document configures Log4J exactly the way that Log4J was configured by the previous example; log messages are sent to both the console and a `RollingFileAppender`:

```
<?xml version="1.0" encoding="UTF-8" ?>

<configuration configDebug="true">

    <appender name="STDOUT" class="org.apache.log4j.ConsoleAppender">
```



```
<layout class="org.apache.log4j.PatternLayout">

    <param name="ConversionPattern" value="%5p (%F:%L) %m%n"/>

</layout>

</appender>

<appender name="FILE" class="org.apache.log4j.RollingFileAppender">

    <param name="File" value="output.log" />

    <param name="MaxFileSize" value="2000KB" />

    <param name="MaxBackupIndex" value="5" />

    <layout class="org.apache.log4j.PatternLayout">

        <param name="ConversionPattern" value="%d %-5p %c - %m%n"/>

    </layout>

</appender>

<category name="com.discursive">

    <priority value="DEBUG" />

</category>

<root>

    <priority value="WARN"/>

    <appender-ref ref="STDOUT" />

    <appender-ref ref="FILE" />

</root>

</configuration>
```

This configuration will produce the same output as the previous recipe. The only difference between

this recipe and the last is that XML is used to configure Log4J.

See Also

For more information about Log4J, see the Log4J project page at <http://logging.apache.org/log4>.

PREV

< Day Day Up >



Chapter 8. Math

[Introduction](#)

[Recipe 8.1. Using Fractions](#)

[Recipe 8.2. Finding the Maximum and Minimum in an Array](#)

[Recipe 8.3. Using Number Ranges](#)

[Recipe 8.4. Generating Random Variables](#)

[Recipe 8.5. Obtaining Commons Math](#)

[Recipe 8.6. Calculating Simple Univariate Statistics](#)

[Recipe 8.7. Solving a System of Linear Equations](#)

[Recipe 8.8. Arithmetic with Complex Numbers](#)

[Recipe 8.9. Establishing Relationships Between Variables](#)

[Recipe 8.10. Estimating the Amount of Time Left in a Process](#)



Introduction

In recent years, Java has lost its reputation as a language suffering from serious performance problems. Although the debate still rages on and various benchmarks show conflicting results, improvements to the JVM, the compiler, and a more intelligent garbage collector have boosted performance to levels on par with C++ . Java has never been the traditional language-of-choice for scientific computing, numerical methods, or high-performance computing, but, as performance improves, there are fewer reasons to avoid using Java for numerical computing. It is no longer inconceivable to consider Java when implementing systems involving complex mathematics, and Jakarta Commons contains two projects that provide some very basic math capabilities: Commons Lang and Commons Math.

The first four recipes in this chapter deal with math utilities found in Commons Lang. This includes a class that represents fractions, finding the minimum and maximum values in an array, representing a range of numbers, and convenient ways to retrieve different random variables. Commons Lang was introduced in [Chapter 1](#), and instructions for downloading and installing Commons Lang can be found in [Recipe 1.1](#). The remainder of this chapter deals with Jakarta Commons Math. Recipes involving Commons Math deal with complex numbers, the calculation of univariate statistics, solving a system of linear equations, and establishing a relationship between two independent variables. Instructions for downloading and installing Commons Math can be found in [Recipe 8.5](#).

Recipe 8.1 Using Fractions

Problem

You need to work with fractions supplied by the user, such as 3 4/5 and 134/21. Your application needs to parse, multiply, and reduce fractions.

Solution

Use Jakarta Commons Lang's `Fraction` class to parse and manipulate fractions. The following code demonstrates the parsing of a `String` containing a fraction:

```
import org.apache.commons.lang.math.Fraction;

String userInput = "23 31/37";

Fraction fraction = Fraction.getFraction( userInput );

double value = fraction.doubleValue( );
```

The `String` "23 31/37" is converted to a `double` value of 23.837837. A `Fraction` object is created by calling the `Fraction.getFraction()` method, and `double` value of the `Fraction` object is obtained with `fraction.doubleValue()`.

Discussion

The `Fraction` class provides a number of operations that can be used to simplify the following expression to an improper fraction. The following code evaluates the expression in [Figure 8-1](#) using `Fraction`:

```
import org.apache.commons.lang.math.Fraction;

Fraction numer1 = Fraction.getFraction( 3, 4 );

Fraction numer2 = Fraction.getFraction( 51, 3509 );
```

```

Fraction numerator = numer1.multiplyBy( numer2 );

Fraction denominator = Fraction.getFraction( 41, 59 );

Fraction fraction = numerator.divideBy( denominator );

Fraction result = fraction.reduce( );

System.out.println( "as Fraction: " + result.reduce( ).toString( ) );

System.out.println( "as double: " + result.doubleValue( ) );

```

Figure 8-1. Expression to be evaluated with Fraction

The previous example creates an instance of `Fraction` by calling the static `getFraction(int numerator, int denominator)` method. Fraction objects are then multiplied and divided with the `multiplyBy()` and `divideBy()` methods of `Fraction`. And, the final call to `reduce()` reduces the `Fraction` to the smallest possible denominator. This example executes and prints the following output to the console:

```

Expression as Fraction: 9027/575476

Expression as double: 0.015686145034719084

```

An improper fraction is a fraction such that $X/Y > 1$ (i.e., "135/23" or "3/2"). `Fraction` provides the ability to convert improper fractions to proper fractions as demonstrated in the following example:

```

import org.apache.commons.lang.math.Fraction;

String userInput = "101/99";

String properString = Fraction.getFraction(userInput).toProperString( );

```

```
// properString is now "1 2/99"
```



`Fraction` does not automatically reduce contents, and it is important to call `reduce()` before performing any arithmetic with the `Fraction` class to reduce the risk of overflow. For example, `Fraction.getFraction(10000, 100000).pow(6)` should equal `1.0E-6`, but, because `Fraction` simply multiplies each numerator and denominator without reducing the fraction, the result of this statement will be `1.0`. When raised to the power of `6`, the `Fraction` object quickly becomes `Fraction.getFraction(Integer.MAX_VALUE, Integer.MAX_VALUE)` or `1.0`. Call `reduce()` liberally or you may have occasion to curse this `Fraction` class.

[Table 8-1](#) lists a sampling of methods available on the `Fraction` class.

Table 8-1. Methods on Commons Lang Fraction

Method	Description
<code>abs()</code>	Returns the absolute value of a <code>Fraction</code>
<code>add(Fraction fraction)</code>	Adds two <code>Fraction</code> objects together
<code>subtract(Fraction fraction)</code>	Subtracts the parameter from the current <code>Fraction</code>
<code>multiplyBy(Fraction fraction)</code>	Multiplies the parameter by the current <code>Fraction</code>
<code>divideBy(Fraction fraction)</code>	Divides the current <code>Fraction</code> by the parameter
<code>reduce()</code>	Reduces the <code>Fraction</code> to the smallest denominator
<code>negate()</code>	Returns <code>-1 * Fraction</code>
<code>invert()</code>	Swaps the numerator and denominator
<code>getNumerator()</code>	Returns the numerator
<code>getDenominator()</code>	Returns the denominator
<code>getProperNumerator()</code>	Returns the proper numerator
<code>getProperWhole()</code>	Returns the proper whole number
<code>pow()</code>	Raises a <code>Fraction</code> to the specified power

See Also

For more information about downloading Commons Lang, see [Recipe 1.1](#).



Recipe 8.2 Finding the Maximum and Minimum in an Array

Problem

You need to retrieve the maximum and minimum values from a `double[]`, `float[]`, `long[]`, `int[]`, `short[]`, or `byte[]`.

Solution

Use Commons Lang `NumberUtils.max()` and `NumberUtils.min()` to retrieve the minimum or maximum values from an array of primitives. The following code retrieves the minimum and maximum values from a `double[]`:

```
import org.apache.commons.lang.math.NumberUtils;

double[] array = {0.2, 0.4, 0.5, -3.0, 4.223, 4.226};

double max = NumberUtils.max( array ); // returns 4.226

double min = NumberUtils.min( array ); // returns -3.0
```

Discussion

`NumberUtils.min()` and `NumberUtils.max()` both accept `double[]`, `float[]`, `long[]`, `int[]`, `short[]`, and `byte[]`. If the array is empty or `null`, both `NumberUtils.min()` and `NumberUtils.max()` will return an `IllegalArgumentException`.

Jakarta Commons Math also contains a class that can find the minimum and maximum value in a `double[]`. The following example uses the `Max` and `Min` classes from Commons Math to evaluate a `double[]`:

```
import
```

```
org.apache.commons.math.stat.univariate.rank.Max;

import org.apache.commons.math.stat.univariate.rank.Min;

double[] array = {0.2, 0.4, 0.5, -3.0, 4.223, 4.226};

Max maximum = new Max( );

Min minimum = new Min( );

double max = maximum.evaluate( array, 0, array.length );

double min = minimum.evaluate( array, 0, array.length );
```

Recipe 8.3 Using Number Ranges

Problem

You need to define a range of acceptable values for a variable, and test to see if that variable is within those boundaries.

Solution

Use an implementation of `Range`, an interface that defines a simple numerical range. There are a number of different implementations for different types: `NumberRange`, `DoubleRange`, `FloatRange`, `IntRange`, and `LongRange`. The following example demonstrates the use of `DoubleRange` to verify that a variable is within a valid range. A `DoubleRange` is created with minimum and maximum values, and a value is tested by `DoubleRange` using a method named `containsDouble()`:

```
import org.apache.commons.lang.math.DoubleRange;

import org.apache.commons.lang.math.Range;

Range safeSpeed = new DoubleRange( 0.0, 65.0 );

double currentSpeed = getCurrentSpeed( );

if( !safeSpeed.containsDouble( currentSpeed ) ) {

    System.out.println( "Warning, current speed is unsafe." );

}
```

Discussion

Additionally, one can also test to see if another `Range` is contained within a `Range`, or if a `Range` overlaps another `Range`. The following example demonstrates the use of `containsRange()` to determine if a `Range` is entirely contained within another `Range`:

```
import org.apache.commons.lang.math.Range;
```

```
import org.apache.commons.lang.math.IntRange;

import org.apache.commons.lang.math.NumberUtils;

double recordHigh = getRecordHigh( );

double recordLow = getRecordLow( );

IntRange recordRange = new IntRange( recordLow, recordHigh );

int todayTemp = getTodayMaxTemp( );

IntRange daysRange = new IntRange( NumberUtils.min( todayTemp ),
                                   NumberUtils.max( todayTemp ) );

if( !recordRange.containsRange( todayTemp ) ) {
    System.out.println( "Today is a record temperature day!" );
}
```

The previous code creates a `Range`, `recordRange`, from the record high and low temperatures. It then creates `daysRange`, which is a `Range` of the current day's high and low temperatures. If `dayRange` is not entirely contained within the `recordRange`, then the current day contains a record temperature and `recordRange.containsRange(daysRange)` will return `false`. `containsRange()` returns `true` if every value in the containing range occurs in the contained range, and `overlapsRange()` returns `true` if two `Range` objects share any common value. `NumberUtils` is used to retrieve the maximum and minimum values from the `todayTemp` array.

In another example, a `Range` object is used to ascertain the state of an element from a temperature measurement. Elemental Gold (Au) melts at 1337.33 Kelvin and boils at 3129.15 Kelvin. The following code is used to read the temperature from a thermometer and print the current state of the element:

```
import org.apache.commons.lang.math.Range;

import org.apache.commons.lang.math.DoubleRange;

double melting = 1337.33;
```



```
double boiling = 3129.15

// State ranges for element Au

Object[] stateRanges =

    new Object[][]{{"solid" , new DoubleRange( 0.0, melting )},

                    {"liquid", new DoubleRange( melting, boiling )},

                    {"gas", new DoubleRange( boiling,Double.INFINITY) }};

// Read measurement from thermometer

double temp = thermometer.getReading( );

String state = "unknown";

// Test the state

for( int i = 0; i < stateRanges.length; i++ ) {

    DoubleRange stateRange = (DoubleRange) stateRanges[i][1];

    if( stateRange.contains( temp ) ) {

        state = (String) stateRanges[i][0];

    }

}

System.out.println( "The substance is in a " + state + " state." );

// If the temperature is a temperate 293 K, this line would print

// "The Gold is in a solid state."
```

The ranges in this example overlap; the `solid` range ends at `melting`, and the `liquid` range begins at `melting`. Because each `Range` is tested in a defined order, each `Range` object in this example is lower- and upper-bound inclusive. If the `temp` variable has the same value as `melting`, the program

will indicate solid state, and if the `temp` variable has the same value as `boiling`, this program will signify the `liquid` state.

See Also

For more information about downloading Commons Lang, see [Recipe 1.1](#).



Recipe 8.4 Generating Random Variables

Problem

J2SE 1.4 includes a `java.lang.Math` class that provides a mechanism to get a random `double` value between `0.0` and `1.0`, but you need to create random `boolean` values, or random `int` variables between zero and a specified number.

Solution

Generate random variables with Commons Lang `RandomUtils`, which provides a mechanism to generate random `int`, `long`, `float`, `double`, and `boolean` variables. The following code generates a random integer between zero and the value specified in the parameter to `nextInt()`:

```
import org.apache.commons.lang.math.RandomUtils;

// Create a random integer between 0 and 30

int maxVal = 30;

int randomInt = RandomUtils.nextInt( maxVal );
```

Or, if your application needs a random `boolean` variable, create one with a call to the static method `nextBoolean()`:

```
import org.apache.commons.lang.math.RandomUtils;

boolean randomBool = RandomUtils.nextBoolean( );
```

Discussion

A frequent argument for not using a utility like `RandomUtils` is that the same task can be achieved with only one line of code. For example, if you need to retrieve a random integer between 0 and 32, you could write the following code:

```
int randomInt = (int) Math.floor( (Math.random( ) * (double) maxVal) );
```

While this statement may seem straightforward, it does contain a conceptual complexity not present in `RandomUtils.nextInt(maxVal)`. `RandomUtils.nextInt(maxVal)` is a simple statement: "I need a random integer between 0 and `maxVal`"; the statement without `RandomUtils` is translated to a more complex statement:

I'm going to take a random `double` between 0.0 and 1.0, and multiply this number by `maxVal`, which has been cast to a `double`. This result should be a random `double` between 0.0 and `maxVal`, which I will then pass to `Math.floor()` and cast to an `int`.

While the previous statement does achieve the same task as `RandomUtils`, it does so by rolling-up multiple statements into a single line of code: two casts, a call to `floor()`, a call to `random()`, and a multiplication. You may be able to instantly recognize this pattern as code that retrieves a random integer, but someone else may have a completely different approach. When you start to use some of the smaller utilities from Jakarta Commons systemwide, an application will tend toward greater readability; these small reductions in conceptual complexity quickly add up.

Recipe 8.5 Obtaining Commons Math

Problem

You need to use Jakarta Commons Math to work with complex numbers, matrices, statistics, or linear equations.

Solution

Download Jakarta Commons Math and put the necessary JAR files in your classpath. Because Commons Math has not yet been released, you will need to download the latest nightly snapshot of Commons Math from <http://cvs.apache.org/builds/jakarta-commons/nightly/commons-math/>. Once you have downloaded the latest nightly build, uncompress the distribution, and place the *commons-math-1.0-RC1.jar* file in your classpath.

Discussion

Jakarta Commons Math was created to provide some more advanced mathematical capabilities under an Apache-style license. Commons Math provides classes to work with complex numbers, utilities to calculate statistics, a matrix implementation, special functions, continued fractions, root-finding, interpolation, and bivariate regression. Commons Math depends on Commons Collections 3.0, Commons Lang 2.0, and Commons Logging 1.0.3. To obtain these dependencies, see [Recipe 1.1](#), [Recipe 5.1](#), and [Recipe 7.9](#).

By the time this book is published, Commons Math 1.0 may be released. Make sure you look at the Commons Math project page (<http://jakarta.apache.org/commons/math>) and check for a release before downloading.

While the previous four recipes demonstrated classes and utilities available in Jakarta Commons Lang, the next five recipes demonstrate classes and utilities from Jakarta Commons Math. Simpler math utilities, which have wide application, will frequently be included in Commons Lang, and more complex utilities will be added to Commons Math. As both components continue to evolve, you may notice some overlap between the feature-set of Commons Lang and Commons Math.

See Also

Commons Math is a relatively new math library primarily motivated by licensing and community issues; all established math libraries were covered under a GPL or LGPL license. The Jakarta Commons community saw an opportunity to create a library, and through the hard work of a few dedicated developers in Commons, a very useful math library will soon be released. That being said, if you need a more mature math library, and your project can use LGPL components, look at the Colt Distribution from CERN (<http://hoschek.home.cern.ch/hoschek/colt/>).

For the authoritative cookbook of mathematics, pick up a copy of *Numerical Recipes in C++* or *Numerical Recipes in C* (Cambridge University Press). These classic tomes contain a huge library of code and examples, but be forewarned, the mathematics will quickly intimidate the faint of math. More information about this indispensable text can be found at the Numerical Recipes website (<http://www.nr.com/>). Unlike all the components described throughout this book, the code and examples from both of these books is covered under a very restrictive license described at <http://www.numerical-recipes.com/infotop.html#distinfo>.



Recipe 8.6 Calculating Simple Univariate Statistics

Problem

You need to calculate univariate statistics such as mean, median, variance, minimum and maximum.

Solution

Use Commons Math's `StatUtils` to calculate simple univariate statistics. The following example uses `StatUtils` to calculate simple statistics for a `double[]`:

```
import org.apache.commons.math.stat.StatUtils;

double[] values = new double[] { 2.3, 5.4, 6.2, 7.3, 23.3 };

System.out.println( "min: " + StatUtils.min( values ) );
System.out.println( "max: " + StatUtils.max( values ) );
System.out.println( "mean: " + StatUtils.mean( values ) );
System.out.println( "product: " + StatUtils.product( values ) );
System.out.println( "sum: " + StatUtils.sum( values ) );
System.out.println( "variance: " + StatUtils.variance( values ) );
```

This code executes and prints a few simple statistics to the console, as follows:

```
min: 2.3
max: 23.3
mean: 8.9
product: 13097.61036
sum: 44.5
```

```
variance: 68.25500000000001
```

Discussion

`StatUtils` delegates these calculations to functors in the `org.apache.commons.math.stat.univariate.moment`, `org.apache.commons.math.stat.univariate.rank`, and `org.apache.commons.math.stat.univariate.summary` packages. The following example uses the individual classes from these packages to recreate the previous example, and it adds some measures not available in `StatUtil`:

```
import org.apache.commons.math.stat.univariate.moment.*;

import org.apache.commons.math.stat.univariate.rank.*;

import org.apache.commons.math.stat.univariate.summary.*;

// Measures from previous example

Min min = new Min( );

Max max = new Max( );

Mean mean = new Mean( );

Product product = new Product( );

Sum sum = new Sum( );

Variance variance = new Variance( );

System.out.println( "min: " + min.evaluate( values ) );

System.out.println( "max: " + max.evaluate( values ) );

System.out.println( "mean: " + mean.evaluate( values ) );

System.out.println( "product: " + product.evaluate( values ) );

System.out.println( "sum: " + sum.evaluate( values ) );

System.out.println( "variance: " + variance.evaluate( values ) );
```



```
// New measures

Percentile percentile = new Percentile( );

GeometricMean geoMean = new GeometricMean( );

Skewness skewness = new Skewness( );

Kurtosis kurtosis = new Kurtosis( );


System.out.println( "80 percentile value: " +
                    percentile.evaluate( values, 80.0 ) );

System.out.println( "geometric mean: " + geoMean.evaluate( values ) );

System.out.println( "skewness: " + skewness.evaluate( values ) );

System.out.println( "kurtosis: " + kurtosis.evaluate( values ) );
```

The previous example adds percentile, geometric mean, standard deviation, skewness, and kurtosis to the available univariate statistics. The previous example produces the following output:

```
min: 2.3

max: 23.3

mean: 8.9

product: 13097.61036

sum: 44.5

variance: 68.25500000000001

80 percentile value: 20.099999999999998

geometric mean: 6.659450778469037

standard dev: 8.261658429153314

skewness: 1.9446683453691376

kurtosis: 4.102348153299074
```

See Also

If you need a formal definition of a specific moment, rank, or summary, see MathWorld (<http://mathworld.wolfram.com>), an invaluable mathematical reference site from Wolfram, the makers of Mathematica.

Recipe 8.7 Solving a System of Linear Equations

Problem

You need to find the values of x , y , and z that satisfy the system of linear equations shown in [Figure 8-2](#).

Figure 8-2. A system of linear equations

Solution

Use the `RealMatrix` and `RealMatrixImpl` from Commons Math. Represent this system of linear equations as matrices in the $Ax=B$ form, as shown in [Figure 8-3](#). Place the coefficients of A in a `RealMatrix`, and put B in a `double[]`. Call the `solve()` method on `RealMatrix` to retrieve a `double[]` of values for x , y , and z that satisfy this system of equations.

Figure 8-3. System of linear equations in $Ax=B$ form

The following example takes the coefficients and constants from [Figure 8-3](#) and uses a `RealMatrix` to solve this system:

```
import org.apache.commons.math.linear.RealMatrix;

import org.apache.commons.math.linear.RealMatrixImpl;

import org.apache.commons.lang.ArrayUtils;
```

```
double[][] coefficients = { { 3.0, 20.0, 89.0 },
                             { 4.0, 40.0, 298.0 },
                             { 7.0, 21.0, 0.42 } };

double[] values = { 1324, 2999, 2039 };

RealMatrix matrix = new RealMatrixImpl( );

matrix.setData( coefficients );

double[] answers = matrix.solve( values );

System.out.println( "Answers: " + ArrayUtils.toString( answers ) );
```

This example solves this system of equations and prints out the values of x, y, and z using Commons Lang `ArrayUtils` to print a `double[]`:

```
Answers: {400.4839095455532,-36.59139305646149,9.599731825759218}
```

Using Commons Math, we find that the following values satisfy this system of equations: $x = 400$, $y = -36$, and $z = 9.6$.

Discussion

To solve these equations, a `double[][]` of coefficients is created to represent a 3 3 matrix, and a `double[]` of constants is created. The `RealMatrix` interface is implemented by `RealMatrixImpl`, which stores a matrix as a `double[][]`; to populate this `double[][]`, pass the `double[][]`, `coefficients`, to the `setData()` method of `RealMatrixImpl`. To solve the system, the `values` `double[]` is passed to `matrix.solve()`, and a `double[]` containing x, y, and z is returned.

This method will not work for every matrix; there are systems of linear equations that are unsolvable. For example, if one attempts to find values for the system of equations from [Figure 8-4](#), an `InvalidMatrixException` will be thrown stating that the matrix is singular. Additionally, if the number of rows in B does not equal the number of columns in A , `solve()` will throw an `InvalidMatrixException`.

Figure 8-4. An unsolvable system of equations

See Also

For more information about solving systems of linear equations (or, for that matter, information about anything), see Wikipedia (http://en.wikipedia.org/wiki/System_of_linear_equations).

`RealMatixImpl` uses a process known as LU decomposition to solve this system of equations. For more information about LU decomposition, see the JavaDoc for the `org.apache.commons.math.linear` package (<http://jakarta.apache.org/commons/math/apidocs/index.html>).

◀ PREV

< Day Day Up >

Recipe 8.8 Arithmetic with Complex Numbers

Problem

You need to perform arithmetic with complex numbers. For example, given the complex numbers A , B , C , and E and two equations shown in [Figure 8-5](#), you need to find the real part of F and the imaginary part of D .

Figure 8-5. Expressions evaluated with the Complex object

Solution

Use Commons Math `Complex` and `ComplexMath` classes to represent complex numbers and perform arithmetic using complex numbers. Use the `ComplexFormat` class to print the real and imaginary parts of a complex number. The following example demonstrates the use of the `Complex` class to calculate D and F from [Figure 8-5](#) using arbitrary values for A , B , C , and E :

```
import org.apache.commons.math.complex.Complex;

import org.apache.commons.math.complex.ComplexFormat;

Complex a = new Complex(2, 3);

Complex b = new Complex(4, 5);

Complex c = new Complex(0.3, 2);

Complex e = new Complex(4, 4);

Complex sum = a.add( b );

Complex d = c.divide( sum );
```

```

Complex f = e.multiply( d.conjugate( ) );

System.out.println( "D is: " + ComplexFormat.formatComplex( d ) );

System.out.println( "F is: " + ComplexFormat.formatComplex( f ) );

double realF = f.getReal( );

double imD = d.getImaginary( );

double answer = realF / imD;

System.out.println( "Answer Re(F)/Im(D): " +

    NumberFormat.getInstance( ).format( answer ) );

```

The variables `a`, `b`, `c`, and `e` are created using arbitrary values, and an intermediate `Complex` object `sum` is calculated by adding `b` to `a`--`a.add(b)`. `d` is calculated by dividing this intermediate `sum` by `c`: `c.divide(sum)`. `f` is calculated by multiplying `e` times the complex conjugate of `d`: `e.multiply(d.conjugate())`. The final answer is calculated by taking the real part of `f` (`f.getReal()`) and dividing that by the imaginary part of `d`: `d.getImaginary()`. The previous example performs complex arithmetic and prints the following to the console:

```

D is: 0.18 + 0.1i

F is: 1.1 + 0.33i

Answer Re(F)/Im(D): 11.417

```

Discussion

The previous example used the `ComplexFormat` class to create a `String` representation of a `Complex` object. This class allows you to print out the complex number N in the format $Re(N) + Im(N)i$. This class also has a constructor that takes a `String` to use instead of "i." In electrical engineering, where "i" is frequently used to refer to current, complex impedance is represented using a "j" instead of an "i." To print a complex number using a "j", write the following code:

```

Complex impedance = new Complex( 1.0, 2.0 );

ComplexFormat format = new ComplexFormat("j");

System.out.println( "Impedance: " + format.format( impedance ) );

```

The previous code prints the following output to the console:

```
Impedance: 1.0 + 2.0j
```

The `Complex` object contains simple arithmetic methods such as `add()`, `subtract()`, `multiply()`, `divide()`, `conjugate()`, and `negate()`. More advanced methods are available as static methods on the `ComplexMath` class. `ComplexMath` includes trigonometric methods such as `sin()`, `sinh()`, `cos()`, and `tan()`, as well as methods to calculate logarithms and to take the square root of a `Complex` object.

See also

For more information about the `ComplexMath` utility, see the Commons Math JavaDoc at <http://jakarta.apache.org/commons/math/apidocs/index.html>.

Recipe 8.9 Establishing Relationships Between Variables

Problem

You need to establish a relationship between two independent variables. These variables could be temperature versus energy use or the number of news channels versus stress-related ailments; you need to measure the correlation between two variables.

Solution

Add data points to an instance of Commons Math `SimpleRegression`. This class will calculate the slope, slope confidence, and a measure of relatedness known as R-square. The `SimpleRegression` class performs a least squares regression with one independent variable; adding data points to this model refines parameters to the equation $y = ax + b$. The following code uses `SimpleRegression` to find a relationship between two series of values `[0, 1, 2, 3, 4, 5]` and `[0, 1.2, 2.6, 3.2, 4, 5]`.

```
import org.apache.commons.math.stat.multivariate.SimpleRegression;
```

```
SimpleRegression sr = new SimpleRegression( );
```

```
// Add data points
```

```
sr.addData( 0, 0 );
```

```
sr.addData( 1, 1.2 );
```

```
sr.addData( 2, 2.6 );
```

```
sr.addData( 3, 3.2 );
```

```
sr.addData( 4, 4 );
```

```
sr.addData( 5, 5 );
```

```
// Print the value of y when line intersects the y axis
```

```
System.out.println( "Intercept: " + sr.getIntercept( ) );
```

```
// Print the number of data points

System.out.println( "N: " + sr.getN( ) );


// Print the Slope and the Slop Confidence

System.out.println( "Slope: " + sr.getSlope( ) );

System.out.println( "Slope Confidence: " + sr.getSlopeConfidenceInterval( ) );


// Print RSquare a measure of relatedness

System.out.println( "RSquare: " + sr.getRSquare( ) );
```

This example passes six data points to `SimpleRegression` and prints the slope, number of data points, and R-square from `SimpleRegression`:

```
Intercept: 0.238

N: 6

Slope: 0.971

Slope Confidence: 0.169

RSquare: 0.985
```

Discussion

R-square is the square of something called the Pearson's product moment correlation coefficient, which can be obtained by calling `getR()` on `SimpleRegression`. R-square is a determination of correlation between two series of numbers. The parameters to the `addData()` method of `SimpleRegression` are a corresponding x and y value in two sets of data. If R-square is 1.0, the model shows that as x increases linearly, y increases linearly. In the previous example, R-square is 0.98, and this demonstrates that the (x,y) data points added to `SimpleRegression` have a strong linear relationship.

If R-square is -1.0, x increases linearly as y decreases linearly. A value of 0.0 shows that the relationship between x and y is not linear. The following example demonstrates two series of numbers with no relationship:

```
import org.apache.commons.math.stat.multivariate.SimpleRegression;
```

```
SimpleRegression sr = new SimpleRegression( );

sr.addData( 400, 100 );

sr.addData( 300, 105 );

sr.addData( 350, 70 );

sr.addData( 200, 50 );

sr.addData( 150, 300 );

sr.addData( 50, 500 );


// Print RSquare a measure of relatedness

System.out.println( "RSquare: " + sr.getRSquare( ) );
```

The data points added to this `SimpleRegression` are all over the map; x and y are unrelated, and the R-square value for this set of data points is very close to zero:

Intercept: 77.736

N: 12

Slope: 0.142

Slope Confidence: 0.699

RSquare: 0.02

The (x,y) data points supplied to the previous example have no linear correlation. This doesn't prove that there is no relationship between x and y, but it does prove that the relationship is not linear.

See Also

For more information about least squares, the technique used by `SimpleRegression`, see Wikipedia (http://en.wikipedia.org/wiki/Least_squares). More information about R and R-square can also be found on Wikipedia (http://en.wikipedia.org/wiki/Pearson_product-moment_correlation_coefficient).



Recipe 8.10 Estimating the Amount of Time Left in a Process

Problem

You are running a program that takes a long time to execute, and you need to present the user with an estimated time until completion.

Solution

Use Commons Math's `SimpleRegression` and Commons Lang's `StopWatch` to create a `ProcessEstimator` class that can be used to predict when a particular program will be finished. Your program needs to process a number of records, and this program could take a few hours to finish. You would like to provide some feedback, and, if you are confident that each record will take roughly the same amount of time, you can use `SimpleRegression`'s slope and intercept to estimate the time when all records will be processed. [Example 8-1](#) defines the `ProcessEstimator` class that combines the power of `StopWatch` and `ProcessEstimator` to estimate the time remaining in a process.

Example 8-1. ProcessEstimator to estimate time of program execution

```
package com.discursive.jccook.math.timeestimate;

import org.apache.commons.lang.time.StopWatch;

import org.apache.commons.math.stat.multivariate.SimpleRegression;

public class ProcessEstimator {

    private SimpleRegression regression = new SimpleRegression( );

    private StopWatch stopWatch = new StopWatch( );
```



```
// Total number of units

private int units = 0;

// Number of units completed

private int completed = 0;

// Sample rate for regression

private int sampleRate = 1;

public ProcessEstimator( int numUnits, int sampleRate ) {

    this.units = numUnits;

    this.sampleRate = sampleRate;

}

public void start( ) {

    stopWatch.start( );

}

public void stop( ) {

    stopWatch.stop( );

}

public void unitCompleted( ) {

    completed++;

    if( completed % sampleRate == 0 ) {
```

```
        long now = System.currentTimeMillis( );

        regression.addData( units - completed, stopWatch.getTime( ) );

    }

}

public long projectedFinish( ) {

    return (long) regression.getIntercept( );

}

public long getTimeSpent( ) {

    return stopWatch.getTime( );

}

public long projectedTimeRemaining( ) {

    long timeRemaining = projectedFinish( ) - getTimeSpent( );

    return timeRemaining;

}

public int getUnits( ) {

    return units;

}

public int getCompleted( ) {

    return completed;

}
```

```
}
```

`ProcessEstimator` has a constructor that takes the number of records to process and the sample rate to measure progress. With 10,000 records to process and a sample of 100, the `SimpleRegression` will add a data point of units remaining versus time elapsed after every 100 records. As the program continues to execute, `projectedTimeRemaining()` will return an updated estimation of time remaining by retrieving the y-intercept from `SimpleRegression` and subtracting the time already spent in execution. The y-intercept from `SimpleRegression` represents the y value when x equals zero, where x is the number of records remaining; as x decreases, y increases, and y represents the total time elapsed to process all records.

The `ProcessEstimationExample` in [Example 8-2](#) uses the `ProcessEstimator` to estimate the time remaining while calling the `performLengthyProcess()` method 10,000 times.

Example 8-2. An example using the ProcessEstimator

```
package com.discursive.jccook.math.timeestimate;

import org.apache.commons.lang.math.RandomUtils;

public class ProcessEstimationExample {

    private ProcessEstimator estimate;

    public static void main(String[] args) {

        ProcessEstimationExample example = new ProcessEstimationExample();

        example.begin();

    }

    public void begin() {

        estimate = new ProcessEstimator( 10000, 100 );

        estimate.start();

    }

}
```

```
        for( int i = 0; i < 10000; i++ ) {

            // Print status every 1000 items

            printStatus(i);

            performLengthyProcess( );

            estimate.unitCompleted( );

        }

        estimate.stop( );

        System.out.println( "Completed " + estimate.getUnits( ) + " in " +

            Math.round( estimate.getTimeSpent( ) / 1000 ) + " seconds." );

    }

    private void printStatus(int i) {

        if( i % 1000 == 0 ) {

            System.out.println( "Completed: " + estimate.getCompleted( ) +

                " of " + estimate.getUnits( ) );

            System.out.println( "\tTime Spent: " +

                Math.round( estimate.getTimeSpent( ) / 1000 ) +

                " sec" + ", Time Remaining: " +

                Math.round( estimate.projectedTimeRemaining( ) / 1000 ) +

                " sec" );

        }

    }

}
```



```
private void performLengthyProcess( ) {  
  
    try {  
  
        Thread.sleep(RandomUtils.nextInt(10));  
  
    } catch( Exception e ) {}  
  
}  
  
}
```

After each call to `performLengthyProcess()`, the `unitCompleted()` method on `ProcessEstimator` is invoked. Every 100th call to `unitComplete()` causes `ProcessEstimator` to update `SimpleRegression` with the number of records remaining and the amount of time spent so far. After every 1000th call to `performLengthyProcess()`, a status message is printed to the console as follows:

Completed: 0 of 10000

Time Spent: 0 sec, Time Remaining: 0 sec

Completed: 1000 of 10000

Time Spent: 4 sec, Time Remaining: 42 sec

Completed: 2000 of 10000

Time Spent: 9 sec, Time Remaining: 38 sec

Completed: 3000 of 10000

Time Spent: 14 sec, Time Remaining: 33 sec

Completed: 4000 of 10000

Time Spent: 18 sec, Time Remaining: 28 sec

Completed: 5000 of 10000

Time Spent: 24 sec, Time Remaining: 23 sec

Completed: 6000 of 10000

Time Spent: 28 sec, Time Remaining: 19 sec

Completed: 7000 of 10000

Time Spent: 33 sec, Time Remaining: 14 sec

Completed: 8000 of 10000

```
Time Spent: 38 sec, Time Remaining: 9 sec
```

```
Completed: 9000 of 10000
```

```
Time Spent: 43 sec, Time Remaining: 4 sec
```

```
Completed 10000 in 47 seconds.
```

As shown above, the output periodically displays the amount of time you can expect the program to continue executing. Initially, there is no data to make a prediction with, so the `ProcessEstimator` returns zero seconds, but, as the program executes the `performLengthyProcess()` method 10,000 times, a meaningful time remaining is produced.

Discussion

The previous example used a method that sleeps for a random number of milliseconds between 1 and 10, and this value is selected using the `RandomUtils` class described in [Recipe 8.4](#). It is easy to predict how long this process is going to take because, on average, each method call is going to sleep for five milliseconds. The `ProcessEstimator` is inaccurate when the amount of time to process each record takes a steadily increasing or decreasing amount of time, or if there is a block of records that takes substantially more or less time to process. If the amount of time to process each record does not remain constant, then the relationship between records processed and time elapsed is not linear. Because the `ProcessEstimator` uses a linear model, `SimpleRegression`, a nonconstant execution time will produce inaccurate predictions for time remaining. If you are using the `ProcessEstimator`, make sure that it takes roughly the same amount of time to process each record.

See Also

This recipe refers to the `StopWatch` class from Commons Lang. For more information about the `StopWatch` class, see [Recipe 1.19](#).

Chapter 9. Templating

[Introduction](#)

[Recipe 9.1. Obtaining Commons JEXL](#)

[Recipe 9.2. Using an Expression Language](#)

[Recipe 9.3. Invoking Methods in an Expression](#)

[Recipe 9.4. Externalizing Logic with an Expression Language](#)

[Recipe 9.5. Obtaining Jakarta Velocity](#)

[Recipe 9.6. Using a Simple Templating Language](#)

[Recipe 9.7. Writing Templates with Conditionals and Loops](#)

[Recipe 9.8. Using Macros in a Templating Engine](#)

[Recipe 9.9. Invoking Methods in a Template](#)

[Recipe 9.10. Obtaining FreeMarker](#)

[Recipe 9.11. Using a Complex Scripting Engine](#)

[Recipe 9.12. Accessing XML Documents from a Templating Engine](#)

[Recipe 9.13. Using Velocity in a Web Application](#)

[Recipe 9.14. Using FreeMarker in a Web Application](#)

[Recipe 9.15. Writing Templates in Eclipse](#)

Introduction

Systems designed without clear separation between presentation and application logic quickly become chores to maintain. Trivial look-and-feel updates in such applications take days or weeks, and trying to extend such a coupled architecture can introduce unmanageable risks and code that is impossible to unit test. To minimize the possibility of creating such disasters, avoid coupling presentation and application logic through the use of a good templating engine. Maintain clear separation between presentation and application logic from the beginning-be orthogonal. Don't print out HTML, XML, or SQL from Java code, use a templating engine.

The simplest example of templating is Java's `MessageFormat`. A simple message, such as `Hello {0}, I speak {1}`, can be parameterized using the `MessageFormat` class. A more complex templating example is found in applications that use Jakarta Velocity or FreeMarker to avoid mixing Java with HTML or textual output. Throughout this spectrum of complexity, the concept of templating remains the same; a template with references to variables is merged with a context containing these variables. There are many ways to decouple the rigors of logic from the prettiness of presentation, and after reading this chapter, you will have a range of options for different situations.

This chapter touches upon Jakarta Velocity, Jakarta Commons JEXL, and a technology outside of the Apache Software Foundation named FreeMarker. Templating engines are frequently used in web application, and this chapter ends with instructions for integrating these engines into a J2EE web application. Separating HTML or textual content into a separate file allows you to give graphic designers and business users a larger role in customizing and creating content for the enduser. With a templating engine, you can dramatically reduce the time and effort it takes to make simple changes. But, by far, the largest benefit of a templating engine is that it allows programmers to do more programming and graphic designers to do more designing by reducing needless coupling of presentation markup and compiled application logic.

Common Templating Problems in Applications

Server-side Java has won a fair amount of attention over the past five years, but developers seldom consider using templating engines when writing a standalone Java application. Consider the following code, which prints a formatted report for a bank customer:

```
System.out.println( "*****" );

System.out.println( "***** BANK STATEMENT *****" );

System.out.println( "*****" );

Account[] accounts = AccountUtil.getAccounts("1232");

double total = 0.0;

for( int i = 0; i < accounts.length; i++ ) {
```



```

        System.out.println( "Account: " +
            accounts[i].getBalance( ) );

        total += accounts[i].getBalance( );
    }

    System.out.println( "Total: " + total );

    System.out.println( "*****" );

```

In this example, textual content is mixed with Java code, and a programmer must be involved in any change to the look and feel of the report. If this report were generated using an external template, a nonprogrammer could be trained to change the report, or the customers could customize the output of this program by modifying a template with straightforward syntax.

Consider another common problem: generating an XML document. There are seemingly thousands of ways to create an XML document: using DOM or JDOM to create a `Document` object, serializing an object with Jakarta Commons Betwixt, and using Exolab's Castor are a few of these possibilities. Some of these techniques are explained in [Chapter 6](#), but here is an example of how not to generate an XML document:

```

System.out.println("<?xml version=\"1.0\"?>");

System.out.println("<Config>");

System.out.println("<Property name=\"" + name + "\"\n" +
    "value=\"" + value + "\"/>");

System.out.println("</Config>");

```

Avoid this practice at all costs. Here are a few red flags from the previous two examples:

Mixed languages

Nesting an XML document into a Java class by way of printing out `String` literals is unreadable. When you need to mentally decode heavily escaped XML nested in Java, you are asking yourself to do too much at once. You will also end up with mixed context, an XML element starting within a pair of parentheses, and ending in another. In this fugue of forward and back slashes, one misplaced slash produces an invalid XML document, or one overlooked `NullPointerException` causes a catastrophe. You are asking your brain to compile two strands of code with intertwined and overlapping syntax. While your compiler might not complain, your system will be difficult to maintain. Code that is difficult to comprehend is even more difficult to maintain.

Escaped characters in compiled code

Escaping characters in `String` literals quickly becomes an annoyance, especially if the strings to be encoded contain back slashes and double quotes. I accept that the `String c: Itemp\blah.txt`, must be written as `c:\\temp\\blah.txt`, but I don't enjoy doing it. How confusing is a literal `"c:\\temp\\"`? Avoid this entirely by using a templating engine or externalizing strings in properties files.

Mixing presentation with conditional or iterative logic

A previous example printed each account balance in a `for` loop. A common trick in JSP is to create a `while` loop with JSP scriptlets, surrounding the code to be executed with `<% while(i < 4) { %>` and `<% } %>`. Templating languages such as Velocity or even JSP 2.0 with JSTL support conditional and iterative operations without asking you to mix languages.

There are other opportunities for using a template in an application. These include code generation, creating SQL scripts, and interacting with an interpreted language via generated scripts. The list continues, and it proves that templating isn't just for making web pages.

Templating in Web Applications

Examine the JSP code below (the variable names have been changed to protect the innocent). Take this code and multiply it by 100 or 200 pages. Now, what happens when you want to move from PostgreSQL to Oracle? Do you do a global search and replace on the driver class name and the JDBC URL? Or, even worse, what happens when someone asks you to translate the entire site to Chinese in two weeks? It would be easier to learn Chinese in two weeks than it would be to internationalize this code. The offending JSP is:

```
<% ResultSet rs;

try {

    Class.forName( "org.postgresql.Driver" );

    String dbURL = "jdbc:postgresql://192.168.0.1/dbname";

    Connection dbCon =

        DriverManager.getConnection( dbURL, "system", "" );

    PreparedStatement ps =

        dbCon.prepareStatement( "select * from Offer " +

                                "where id = ?" );
```

```
        ps.setString( 1, request.getAttribute("id") );

        rs = ps.executeQuery( );

        rs.next( );

    } catch( Exception e ) {

        %><%= Something bad happened, Call Jack (800) 232-2233 %>

<% } %>

<jsp:include page="header.html" />

Hello <%= rs.getString("name") %>,

I would like to inform you of a good offer.

<%= rs.getString("offerText") %>

There are a few things I would like to tell you.

<ul>

    <% Thing[] things = OfferUtil.getThings( rs.getString("id") );

        for( int i = 0; i < things.length; i++ ) { %>

        <li><%= things[i].getText( )%></li>

    <% } %>

</ul>

<jsp:include page="footer.html" />
```




This is real code from a real system, and it was written by a whole team of programmers who didn't find anything terribly wrong with this style. If you were raised on JSP like this, you might not recognize some of the problems. What is wrong with the previous example? Four different "languages" are combined in one file (Java, SQL, HTML, and JSP); the page starts off with JSP scriptlets, then the example contains Java code that prints out HTML and generates SQL statements. Lastly, this particular JSP page forgets to close the connection it created to the database-something that could easily create a resource leak under a heavy load. Make it simpler, use a templating engine (or upgrade to JSP 2.0) and never write a line of Java in a JSP again.

Velocity, JEXL, and FreeMarker are remedies for the coupling issues demonstrated in the previous examples. Each of these tools can be integrated into any application in a matter of minutes. In this chapter, you will learn techniques for separating presentation logic from behavioral (or business) logic. At the end of the chapter, I will briefly explain how you can integrate all of these utilities into a J2EE web application.



Recipe 9.1 Obtaining Commons JEXL

Problem

You need to use Jakarta Commons JEXL to evaluate a simple expression that contains references to variables and object properties.

Solution

You must download the latest version of Commons JEXL, and place the Commons JEXL JAR in your project's classpath. Follow the steps outlined in [Recipe 1.1](#), downloading Commons JEXL 1.0 instead of Commons Lang.

Commons JEXL depends on Commons Logging 1.0.3, which can be downloaded from the same location as Commons JEXL.

Discussion

Commons JEXL is an expression language interpreter influenced by the expression language features of JSP 2.0; JEXL is an extended version of JSP 2.0 EL that does not depend on the Servlet API. This means that it can be integrated into any application that needs to use an expression language.

JEXL is similar to EL with one major difference. The JSP 2.0 EL implementation project in Jakarta Commons, Commons EL, is covered by a Java Specification Request (JSR), which was developed under the Java Community Process (JCP). Because of this, EL is bound to implement the JSP specification-no more and no less. On the other hand, JEXL is free to extend and improve upon the standard.

If you have a Maven project, which needs to use Commons JEXL, add a dependency on Commons JEXL 1.0 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-jexl</id>

    <version>1.0</version>
```

</dependency>

....other dependencies...

</dependencies>

See Also

For more information about downloading Commons Logging 1.0.3, see [Recipe 7.9](#).

To learn more about Commons JEXL, visit the Jakarta Commons JEXL web site (<http://jakarta.apache.org/commons/jexl/>).

If you have questions about how to use Jakarta Commons JEXL, you can join the commons-user@jakarta.apache.org mailing list. Refer to [Recipe 1.2](#) for instructions on joining the Commons User mailing list.

For more information about the Java Community Process, see the JCP home at <http://www.jcp.org/en/home/index>.



Recipe 9.2 Using an Expression Language

Problem

You need to parameterize text messages with variables and bean properties.

Solution

Use Commons JEXL to evaluate an expression containing references to bean properties. To reference properties of an object, create an expression using the bean property syntax introduced in [Chapter 3](#). Surround each property reference with curly braces and a leading \$, as in the following example:

```
${opera.name} was composed by ${opera.composer} in ${opera.year}.
```

Use the following code to "merge" an instance of the `Opera` bean with the above expression:

```
import org.apache.commons.jexl.Expression;

import org.apache.commons.jexl.ExpressionFactory;

import org.apache.commons.jexl.JexlContext;

import org.apache.commons.jexl.JexlHelper;

Opera opera = new Opera( );

opera.setName("The Magic Flute");

opera.setComposer("Mozart");

opera.setYear(1791);

String expr =

    "${opera.name} was composed by ${opera.composer} in " +

    "${opera.year}.";
```

```
Expression e = ExpressionFactory.createExpression( expr );

JexlContext jc = JexlHelper.createContext( );

jc.getVars( ).put("opera", opera);

String message = (String) e.evaluate(jc);


System.out.println( message );
```

This code puts an instance of the `Opera` bean in a `JexlContext` and evaluates the expression, producing the following output:

```
The Magic Flute was composed by Mozart in 1791.
```

Discussion

The previous example creates and populates an instance of the `Opera` bean: `opera`. An `Expression` object is then created by passing a `String` containing a JEXL expression to `ExpressionFactory.createExpression()`. A `JexlContext` is created with a call to `JexlHelper.createContext()`. This context contains a map-like structure that holds named variables, and the `Opera` object is added to the `JexlContext` under the name `opera`. Once an `Expression` and a `JexlContext` are created and populated, `expression.evaluate()` merges the expression with the context, and a message is generated. A JEXL expression evaluates to an `Object`, but, in this case, the expression evaluates to a `String` object, and the results of the evaluation are cast to a `String`.

This simple example sets the stage for a majority of recipes in this chapter; most templating engines involve the pattern established by the previous example. First, there is a template—in this case, a `String` that contains expressions that are to be replaced by bean properties. Second, a collection of named variables are put into a context. Lastly, the template is merged with the variables in the context.

This chapter makes heavy use of expressions in templating engines, and this is a logical time to introduce the concept of the syntax used to create expressions. If you are familiar with JavaServer Pages (JSPs) you may know about a tag library called the JavaServer Pages Standard Tag Library (JSTL), which is a set of standard JSP tag libraries that make creating JSP pages much easier. Along with JSTL came something called EL, which is an expression language you can use in JSTL tags and in JSP 2.0. In general, JEXL can do everything that JSP EL can do, and more. [Table 9-1](#) lists expressions that are valid in both JSP 2.0 EL and Jakarta Commons JEXL.

Table 9-1. Simple Commons JEXL and JSP 2.0 EL expressions

EL expression	Evaluates to
<code>\${true}</code>	<code>true</code>
<code>\${1}</code>	The integer <code>1</code>
<code>\${'Hello'}</code>	The <code>String</code> <code>"Hello"</code>
<code>\${'blah' == 'blah'}</code>	<code>true</code>
<code>\${var == true}</code>	<code>true</code> if the variable named <code>var</code> is a Boolean <code>true</code>
<code>\${x.a < 352}</code>	<code>true</code> if <code>x.getA()</code> is a number less than 352
<code>\${ball.color == 'Green'}</code>	<code>true</code> if <code>ball.getColor()</code> equals <code>"Green"</code>
<code>\${x == 2 y == 4}</code>	<code>true</code> if <code>x</code> equals 2 or if <code>y</code> equals 4
<code>\${thing.color.name}</code>	Retrieves the value of <code>thing.getColor().getName()</code>
<code>\${thing.shapes["circle"]}</code>	Retrieves the object stored under the key <code>"circle"</code> on the <code>Map</code> <code>shapes</code> , which is a bean property of <code>thing</code>
<code>\${thing.someList[55]}</code>	Retrieves the object at index 54 of a <code>List</code> , <code>someList</code> , which is a bean property of <code>thing</code>
<code>\${empty var}</code>	Evaluates to <code>true</code> if <code>var</code> is <code>null</code> or empty
<code>\${!(y < 4)}</code>	<code>true</code> if <code>y</code> is not less than 4

See Also

For more information about JSP 2.0 Expression Language, see Hans Bergsten's article on [onJava.com](http://www.onjava.com/pub/a/onjava/2003/11/05/jsp.html) called "JSP 2.0: The New Deal, Part 1" (<http://www.onjava.com/pub/a/onjava/2003/11/05/jsp.html>) or his book *JavaServer Pages* (O'Reilly).



Recipe 9.3 Invoking Methods in an Expression

Problem

You are trying to print out a message that contains data returned by a method.

Solution

Commons JEXL can evaluate any method that is made available to the interpreter. The following expression invokes the `language()` method on an `Opera` bean. The `acts` property of `Opera` is a `List`, and this expression invokes the `size()` method on this `List` to obtain the number of acts in the `Opera`:

```
${opera.name} was composed by ${opera.composer} in ${opera.year}.
```

```
This opera has ${opera.acts.size()}, and it is performed in ${opera.
```

```
language() }
```

The following code creates and populates an expression and a context, merging the two to create a message:

```
import org.apache.commons.jexl.Expression;

import org.apache.commons.jexl.ExpressionFactory;

import org.apache.commons.jexl.JexlContext;

import org.apache.commons.jexl.JexlHelper;

Opera opera = new Opera();

opera.setName("The Magic Flute");

opera.setComposer("Mozart");

opera.setYear(1791);

opera.acts( new ArrayList(2) );
```

```
String expr =

    "${opera.name} was composed by ${opera.composer} in ${opera.year}.";

    "This opera has ${opera.acts.size( )} acts, and it is performed in " +

    "${opera.language( )}";

Expression e = ExpressionFactory.createExpression( expr );

JexlContext jc = JexlHelper.createContext( );

jc.getVars( ).put("opera", opera);

String message = (String) e.evaluate(jc);

System.out.println( message );
```

The following message is printed to the console:

```
The Magic Flute was composed by Mozart in 1791.  This opera has

2 acts, and it is performed in German.
```

Discussion

This code is almost the same as the previous recipe, but you will notice that the expression contains a direct call to the `opera.language()` method and a call to the `size()` method on the `acts` property of `opera`.

Because JEXL is not governed by the Java Community Process (JCP), JEXL is free to extend the feature set of EL. [Table 9-2](#) presents valid JEXL expressions that are actually *invalid* JSP 2.0 EL expressions.

Table 9-2. Extended capabilities of JEXL expression language

JEXL expression	Evaluates to
<code>\${object.function()}</code>	Accessing any function on an object, this evaluates to the return value from this function.

JEXL expression	Evaluates to
<code>\${"Wolfgang" + " " + "Mozart"}</code>	JEXL supports string concatenation. This expression evaluates to "Wolfgang Mozart."
<code>\${"Cow".size()}</code>	In JEXL you can get the size of a string like this. This expression evaluates to 3.
<code>\${hashMap.size()}</code>	On a map, JEXL will return the number of keys.
<code>\${arrayList.size()}</code>	Returns the size of a list.

See Also

For more information about Commons JEXL's improvements on JSP 2.0 EL, see the Commons JEXL page (<http://jakarta.apache.org/commons/jexl/>).

Recipe 9.4 Externalizing Logic with an Expression Language

Problem

You need to capture application logic in an external file.

Solution

Use an external properties file to store expressions used in an application. For this recipe, imagine yourself creating a system to sort `Ball` objects based on a set of arbitrary criteria. Instead of hard-coding criteria in a series of Java `if-else` clauses, create a framework with loads sorting criteria from a properties file containing `boolean` JEXL expressions. For instance, the first line in this properties file would be:

```
Hvy-Green-Basket = ball.color == 'Green' && (ball.weight > 1000)
```

This translates to "If the ball's color is Green and the weight is over 1000, put this ball into the Heavy Green basket." The name of each property is the name of the basket into which a `Ball` matching the criteria is placed. The contents of the criteria file are:

```
Hvy-Green-Basket = ball.color == 'Green' && (ball.weight > 1000)
```

```
Sm-Yellow-bin = ball.color == 'Yellow' && (ball.weight < 100)
```

```
Transparent-Bin = ball.isTransparent( )
```

```
Lrg-Yellow-Basket = ball.color == 'Yellow' &&(ball.weight >= 100)
```

```
Misc-Bin = true
```

Each criterion is applied to each `Ball` object in the order it appears in the criteria file. The heavy green sorting criteria is applied first, and each criterion is evaluated until the last criterion is reached. The last criteria always evaluates to `true`-similar to a `switch-case` control statement, the "Misc-bin" is the default. The following code reads this criteria file and evaluates each JEXL expression in order to sort a collection of `Ball` objects:

```
import org.apache.commons.jexl.Expression;
```

```
import org.apache.commons.jexl.ExpressionFactory;
```

```
import org.apache.commons.jexl.JexlContext;

import org.apache.commons.jexl.JexlHelper;

// Load in our criteria properties

Properties criteria = new Properties( );

criteria.load( getClass( ).getResourceAsStream("criteria.txt") );

Set binNames = criteria.getKeys( );

// Load our ball objects into a List

List balls = getBalls( );

Iterator ballsIter = balls.iterator( );

while( ballsIter.hasNext( ) ) {

    Ball ball = (Ball) ballsIter.next( );

    // Iterate through every rule, until you find a match...

    Iterator binIter = binName.iterator( );

    while( ruleIter.hasNext( ) ) {

        // Get the name of the basket

        String basket = (String) binIter.next( );

        // Get the expression corresponding to this bin.

        String expr = conditions.get( bin );

        Expression e = ExpressionFactory.createExpression( expr );
```

```

        // Populate the context with the current Ball object

        JexlContext jc = JexlHelper.createContext( );

        jc.getVars( ).put("ball", ball);

        // Evaluate the Expression.

        Boolean result = (Boolean) e.evaluate(jc);

        // If the expression evaluated to true, add this Ball to the bin.

        if( result.booleanValue( ) == true ) {

            sendBall( ball, basket );

        }

    }

}

```

The result of the **Expression** evaluation is a **Boolean** value, and, if the **Boolean** result is **true**, the matching **Ball** is sent to the specified basket.

Discussion

Using this technique, as the number of criteria increases, the code to implement this sorting algorithm remains unchanged. The behavior of the system can be altered by changing the criteria file; compiled code is left untouched. The code in this Solution section is longer than a series of **if-else** clauses to implement these criteria in code, but, as the number of sorting criteria increases, you will be glad you took the extra time to create a general solution without hard coding system behavior in Java code.

This was the first example that involved something more than printing out a pretty message for human consumption. JEXL has been used to create a "language" for sorting criteria; if a client wants to change the rules, you can now train someone familiar with simple logic statements to change a system to meet changing requirements.

See Also

This recipe demonstrated a system that uses a simple set of rules to categorize balls. For more information about a serious open source Rule Engine for Java named JESS, take a look at

<http://herzberg.ca.sandia.gov/jess/index.shtml>. If you are interested in Rule Engines, take a look at JSR 94: Java Rule Engine API (<http://jcp.org/en/jsr/detail?id=94>) or Ernest Friedman-Hill's "Jess in Action" (Manning).



Recipe 9.5 Obtaining Jakarta Velocity

Problem

You need to use Jakarta Velocity to create templates that can reference variables and object properties and contain limited conditional and iterative control structures.

Solution

You must download the latest version of Jakarta Velocity, and place the Velocity JAR in your project's classpath. Follow the steps outlined in [Recipe 1.1](#), downloading Jakarta Velocity 1.4 instead of Commons Lang.

Discussion

After downloading the Velocity 1.4 binary release, unzip or untar the archive, and put both the *velocity-1.4.jar* and *velocity-dep-1.4.jar* into your project's classpath. If you have a Maven project that needs to use Jakarta Velocity, add a dependency on Jakarta Velocity with the following section in *project.xml*:

```
<dependencies>

  <dependency>

    <id>velocity</id>

    <version>1.4</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

To learn more about Velocity, visit the Jakarta Velocity web site

(<http://jakarta.apache.org/velocity/>).

If you have questions about how to use Jakarta Velocity, you can join the velocity-user@jakarta.apache.org mailing list. Refer to [Recipe 1.2](#) for instructions on joining a user mailing list. To join the Velocity user mailing list, see the Velocity section of the Jakarta mailing lists page (<http://jakarta.apache.org/site/mail2.html#Velocity>).



Recipe 9.6 Using a Simple Templating Language

Problem

You need to produce a parameterized message using a template stored in a file.

Solution

Use Jakarta Velocity and store your template in the filesystem. Jakarta Velocity is a straightforward templating engine with a lightweight syntax similar to the expression language introduced in [Recipe 9.2](#). The following Velocity template is used to create an email:

```
#set( $customer = $subscription.customer )
```

```
#set( $magazine = $subscription.magazine )
```

```
$customer.firstName,
```

```
Your subscription to ${magazine.title} on
```

```
$subscription.endDate. If you are interested in renewing your subscription,
```

```
please click on the following URL, and enter your password:
```

```
${magazine.baseUrl}/renew?cust=${customer.id}
```

This template references a `Subscription` bean bound to the name `subscription`. This `Subscription` object has a `customer` property and a `magazine` property, and both of these properties are assigned to a local template variable using the `#set` directive. To render a Velocity template, the engine is initialized using `Velocity.init()`, a `VelocityContext` is created and populated, and the template is read with a `FileReader`. The following code renders this template:

```
import org.apache.velocity.VelocityContext;
```

```
import org.apache.velocity.app.Velocity;
```

```
// Initialize Velocity

Velocity.init( );

// Create a context and put our subscription object into the context

VelocityContext context = new VelocityContext( );

context.put("subscription", testSubscription( ));

// Create a Reader to read our velocity template.

Reader reader = new FileReader( new File("renew.vm") );

// Evaluate our template and write the result to a StringWriter

StringWriter writer = new StringWriter( );

Velocity.evaluate(context, writer, "test", reader);

System.out.println( writer.toString( ) );
```

The template is loaded from the filesystem in a file named *renew.vm*, and the following output is printed to the console:

```
Tim,

Your subscription to Science World expires on July 20, 2003.  If
you are interested in renewing your subscription, please click on the following
URL, and enter in your password.

http://www.scienceworld.com/renew?cust=22324
```


Discussion

In the previous example, `Velocity` is used as a singleton-a single instance of the `VelocityEngine` in one Java Virtual Machine. The Velocity engine has a number of configuration options, but, in this example, the Velocity engine is configured with a default set of properties through a call to `Velocity.init()`. The template is stored on the filesystem, and the template is read using a `FileReader`. The output of the template evaluation is written to a `StringWriter`. To merge a template with a context, `Velocity.evaluate()` is passed the following parameters: a `VelocityContext`, a `Writer` to hold the output, a name for logging purposes, and a `Reader` to read the template.

Velocity syntax is very simple, and it is similar to the expression language used in JSP 2.0 EL and Commons JEXL. If you want to print out the value of a bean property, use `${bean.property}` or `${bean.getProperty()}`; Velocity can handle both bean properties and methods. In addition to the basic expression syntax, Velocity also supports a number of directives and control loops, which are explored in [Recipe 9.7](#).

The one directive used in the previous example is `#set`, which assigns a variable for use later in the script; `#set($customer = $subscription.customer)` assigns the `customer` property of the `subscription` object to the variable `$customer`. [Table 9-3](#) lists some sample Velocity references that demonstrate referencing bean properties and invoking methods.

Table 9-3. Sample Velocity references

Velocity reference	Evaluates to
<code>\${sub}</code>	The value of "sub" in the <code>VelocityContext</code> .
<code>\${sub.endDate}</code>	The value of <code>sub.getEndDate()</code> .
<code>\${sub.setProp("Val")}</code>	The return type of <code>setProp()</code> is void, this reference does not evaluate to a value, but it does invoke the setter with one argument.
<code>!\${customer.firstName}</code>	If <code>customer.getFirstName()</code> returns a <code>null</code> reference, this evaluates to an empty <code>String</code> . This is called a quiet reference.
<code>\${customer.firstName}</code>	If <code>customer.getFirstName()</code> returns a <code>null</code> , this evaluates to the <code>String</code> "null."

See Also

Velocity has a number of configuration options that allow you to configure logging, character encoding, and the behavior of directives. For more information about configuring Velocity, see "Velocity Configuration Key and Values" in the Velocity Developer's Guide (<http://jakarta.apache.org/velocity/developer-guide.html>).

Recipe 9.7 Writing Templates with Conditionals and Loops

Problem

Your template needs to iterate over a list of objects and highlight objects if a specific property meets a certain criteria.

Solution

Use a Velocity template with the `#foreach` and `#if` directives. The following Velocity template uses a `#foreach` to loop through a `List` of `Airport` beans and an `#if` to check for the location of an airport relative to the supplied `$countryCode`:

The World's Busiest Airports

```
<table>

  <tr>

    <td>Rank</td><td>Code</td><td>Name</td><td>Passengers</td>

    <td>${countryCode} Domestic</td>

  </tr>

  #foreach( $airport in $airports )

    <tr>

      <td>$velocityCount</td>

      <td>$airport.code</td>

      <td>$airport.name</td>

      <td>$airport.passengers</td>

      #if( $airport.countryCode == $countryCode )
```

```
        <td>Y</td>

    #else

        <td>N</td>

    #end

</tr>

#end

</table>
```

To render this template, a `List` of `Airport` objects and a `countryCode` `String` is created and put into a `VelocityContext`. The `$countryCode` reference is used to test the `countryCode` property of every `Airport` object in the `List`; if the `countryCode` property matches, a `Y` is placed in the last column. The following code initializes the Velocity engine, creates a `VelocityContext`, and renders the template:

```
import org.apache.velocity.Velocity;

import org.apache.velocity.app.VelocityContext;

// Initialize Velocity with default properties
Velocity.init( );

// Create a List to hold our Airport objects
List airports = new ArrayList( );

airports.add( new Airport(1, "ATL", "Hartsfield Atlanta", 76876128, "US" ) );
airports.add( new Airport(2, "ORD", "Chicago O'Hare", 66501496, "US" ) );
airports.add( new Airport(3, "LHR", "London Heathrow", 63338649, "UK" ) );
airports.add( new Airport(4, "HND", "Tokyo-Haneda", 61079478, "JP" ) );
airports.add( new Airport(5, "LAX", "Los Angeles", 56198447, "US" ) );
airports.add( new Airport(6, "DFW", "Dallas/Fort Worth", 52826304, "US" ) );

// Create a context and put a List into the context, and a country code
```

```
VelocityContext context = new VelocityContext( );

context.put( "airports", airports );

context.put( "countryCode", "US" );


// Create a Reader to read our velocity template.

Reader reader = new FileReader( new File("renew.vm") );


// Evaluate our template and write the result to a StringWriter

StringWriter writer = new StringWriter( );

Velocity.evaluate(context, writer, "test", reader);


System.out.println( writer.toString( ) );
```

This code produces the following output after merging the Velocity template with a VelocityContext:

The World's Busiest Airports

Rank	Code	Name	Passengers	US Domestic
1	ATL	Hartsfield Atlanta	76876128	Y
2	ORD	Chicago O'Hare	66501496	Y
3	LHR	Heathrow	63338649	N
4	HND	Tokyo-Haneda	61079478	N
5	LAX	Los Angeles	56198447	Y
6	DFW	Dallas/Fort Worth	52826304	Y

Discussion

The `#foreach` directive can iterate over arrays, `Enumerations`, `Lists`, and `Sets`; each element is

exposed as a local reference specified in the parameter to `#foreach`. A `#foreach` block is terminated by `#end`. The `#foreach` directive also exposes a local reference `$velocityCount`, which holds the index of the current row, and, if you need to create a table with alternating row colors, use the `velocityCount` variable with the `#if` directive:

```
#foreach( $widgets in $theToolbox )

    #if( $velocityCount % 2 == 0 )

        #set( $bgColor = '#DDD' )

    #else

        #set( $bgColor = '#CCC' )

    #end

    <tr color="{bgColor}">

        <td>Some Data</td>

    </tr>

#end
```

The `#if` directive takes a `boolean` expression, and renders the content contained in the `#if` block if this expression evaluates to `true`. Like `#foreach`, an `#if` block is also terminated by `#end`. The `#if` directive can also be followed by an `#elseif` block or an `#else` block, as shown in the following example:

```
#if( $variable == "TEST" )

    This is a test.

#elseif( $variable == "SERIOUS" )

    The condition is Serious.

#elseif( $variable == "MAJOR" )

    The condition is Major.

#else

    The condition is Nominal

#end
```

The `#foreach` directive can be used to iterate over a `Set` of keys from a `Map`. To access each element in a `Map`, use the bracket notation shown in the following example:

```
#set( $keys = someMap.keySet( ) )

#foreach( $key in $keys )

    $key: $someMap[$key]

#end
```

See Also

For information about the relational and logical operators supports by Velocity, see the Velocity Template Language (VTL) Reference Guide (<http://jakarta.apache.org/velocity/vtl-reference-guide.html>).



Recipe 9.8 Using Macros in a Templating Engine

Problem

You need to reuse portions of a template to standardize the display of common elements such as an address or a name.

Solution

Use Velocity Macro definitions to reuse logic to print out bothnames and addresses. Velocity macros are like subroutines that take a set of parameters and perform common tasks. In the following Velocity template, two macros, `#name` and `#address`, handle the printing of names and addresses:

```
#set( $volunteer = $appointment.volunteer )

#set( $location = $appointment.location )

#set( $org = $appointment.organization )


## Define the "name" macro

#macro( name $object )$!object.firstName $!object.lastName#end


## Define the "address" macro

#macro( address $object )

$!object.address.street1

$!object.address.street2

$!object.address.city, $!object.address.state $!object.address.zipcode

#end


#name( $volunteer ),
```

Thank you for volunteering to help serve food at the `$location.name` next week. This email is a reminder that you are scheduled to help out from `$appointment.startTime` to `$appointment.endTime` on `$appointment.date`.

The address of the shelter is:

`#address($location)`

If you need directions to the shelter click the following URL:

`${org.baseUrl}directions?location=${location.id}`

Also, if you are unable to help out on `$appointment.date`, please let us know by sending an email to `${org.email}` or by filling out the form at this URL:

`${org.baseUrl}planschange?appointment=${appointment.id}`

Thanks again,

`#name($org.president)`

`#address($org)`

In the following code, the template shown previously is loaded from a classpath resource `organize.vm`, and an `Appointment` object is placed in a `VelocityContext`:

```
import org.apache.velocity.VelocityContext;

import org.apache.velocity.app.VelocityEngine;
```



```
import org.apache.velocity.runtime.RuntimeConstants;

// Create and initialize a VelocityEngine setting a configuration property
VelocityEngine vEngine = new VelocityEngine( );

vEnging.setProperty( RuntimeConstants.VM_CONTEXT_LOCALSCOPE, Boolean.TRUE );

vEngine.init( );

// Create a test Appointment
Appointment appointment = testAppointment( );

// Create a Velocity Context and give it the appointment
VelocityContext context = new VelocityContext( );

context.put("appointment", appointment);

// Prepare a StringWriter that will hold the contents of
// our template merge
StringWriter writer = new StringWriter( );

// Get a stream to read in our velocity template. The
// organize.vm file is loaded from the classpath and is stored
// in the same package as the current class.
InputStream templateStream = getClass( ).getResourceAsStream("organize.vm");

Reader reader = new InputStreamReader( templateStream );

// Evaluate the template
vEngine.evaluate(context, writer, "test", reader);
```

```
// Print out the results of the template evaluation

System.out.println( "organize: " + writer.toString( ) );
```

The template is merged with a `VelocityContext`, and the following output is produced:

John S. ,

Thank you for volunteering to help serve food at the Boston Homeless Veterans Shelter next week. This email is a reminder that you are scheduled to help out from 9:00 AM to 2:00 PM on Monday, September 12, 2003. The address of the shelter is:

17 Court Street

Boston, MA 01260

If you need directions to the shelter click the following URL:

<http://www.organize.com/directions?location=2342>

Also, if you are unable to help out on September 12th, please let us know by sending an email to *organize@helpout.com* or by filling out the form at this URL:

<http://www.organize.com/planschange?appointment=29932422>

Thanks again,

Brishen R.

201 N. 2nd Street

Jersey City, NJ 20213

Discussion

A macro definition is started with the `#macro` directive and ended with `#end`; the same macro is invoked by calling `#<macro_name>(<parameters>)`. Velocity macros must be defined before they are referenced, using the following syntax:

```
#macro(<name> <arguments>)
```

```
    <Macro Body>
```

```
#end
```

Macro parameters are not typed as are method parameters in Java; there is no mechanism to check that an `Address` object is passed to the `#address` macro, throwing an exception if an inappropriate object is encountered. To successfully render this Velocity template, verify that an `Address` is sent to the `#address` macro and a `Person` is sent to the `#name` macro.

In the previous example, an instance of `VelocityEngine` is created and the `RuntimeConstants.VM_CONTEXT_LOCALSCOPE` property is set to `true`. This property corresponds to the `velocimacro.context.localscope`, which controls the scope of references created by `#set` directives within macros. When this configuration property is set to `true`, references created in the body of a macro are local to that macro.

The Velocity template in the Solution expects a single reference `$appointment` to an `Appointment` bean. Each `Appointment` has a `volunteer` property of type `Person`, and every `Organization` has a `president` property of type `Person`. These `Person` objects, `${appointment.volunteer}` and `${appointment.organization.president}`, are passed to the `#name` macro that prints out the first and last name. Two `Address` objects, `${appointment.location.address}` and `${appointment.organization.address}`, are passed to the `#address` macro that prints a standard U.S. mailing address.

A macro can contain any directive used in Velocity; the following macro uses nested directives to print out a list of numbers in HTML. `#numberList` allows you to specify a range with `$low` and `$high`; values in `$numbers` within this range will be printed bold:

```
#macro( numberList $numbers $low $high )
```

```
    <ul>
```

```
        #foreach( $number in $numbers )
```

```
            #if( ($number > $low) && ($number < $high) )
```

```
        <li><b>$number</b> - In Range!</li>

    #else

        <li>$number</li> - Out of Range!</li>

    #end

#end

</ul>

#end
```

The macro defined above would be called by the following Velocity template. Note the presence of comments, which are preceded by two hashes (##):

```
#set( $squares = [1, 4, 9, 16, 25, 36, 49, 64, 81, 100] )

## Print out a list of numbers highlighting numbers
## between 25 and 75

#numberList( $squares, 25, 75 )
```

See Also

If your system has a large number of Velocity templates, you can create a set of files to hold common macros, which will be made available to every Velocity template using the `velocimacro.library` property. For more information, see the Velocity User Guide (<http://jakarta.apache.org/velocity/user-guide.html#Velocimacros>).



Recipe 9.9 Invoking Methods in a Template

Problem

You need to invoke methods from a Velocity template.

Solution

Use Velocity to access public methods on an object in the `VelocityContext`. Bind an object to the `VelocityContext` and reference methods on these objects in a Velocity template. The following template, available on the classpath at *scripting/velocity/results.vm*, invokes the `average()`, `min()`, and `max()` methods on a `StatUtil` object bound to the reference `$stat`:

```
** Aggregate Statistics
```

```
Average: $stat.average( $results.scores )%
```

```
Lowest: $stat.min( $results.scores )%
```

```
Highest: $stat.max( $results.scores )%
```

```
** Scores:
```

```
#foreach( $student in $results.students )
```

```
    #score( $student 50 )
```

```
#end
```

```
More results are available here:
```

```
http://www.test.com/detail?test={results.id}
```

The `StatUtil` object, which is bound to `$stat`, computes basic statistics on integer arrays. This class definition is:

```
public class StatUtil {

    public int average(int[] array) {

        int sum = 0.0;

        for( int i = 0; i < array.length; i++ ) {

            sum += array[i];

        }

        return( sum / array.length );

    }


    public int min(int[] array) {

        int min = Integer.MAX_VALUE;

        for( int i = 0; i < array.length; i++) {

            if( array[i] < min) { min = array[i]; }

        }

        return( min );

    }


    public int max(int[] array) {

        int max = Integer.MIN_VALUE;

        for( int i = 0; i < array.length; i++) {

            if( array[i] > max) { max = array[i]; }

        }

        return( max );

    }

}
```

The template shown above is loaded from the classpath, and a `StatUtil` object is added to the

VelocityContext. The VelocityEngine is configured to load templates from the classpath, and the template is merged with a call to `mergeTemplate()`:

```
import org.apache.velocity.VelocityContext;

import org.apache.velocity.app.VelocityEngine;

// The following lines of code tell the Velocity Engine
// where to find our shared Macros, 2. Load everything from
// Classpath.

VelocityEngine vEngine = new VelocityEngine( );

vEngine.setProperty("velocimacro.library", "scripting/velocity/macros.vm");

vEngine.setProperty("resource.loader", "class");

vEngine.setProperty("class.resource.loader.description", "Classpath Loader");

vEngine.setProperty("class.resource.loader.class",

    "org.apache.velocity.runtime.resource.loader.ClasspathResourceLoader");

vEngine.init( );

// Put the test results and the StatUtil object into the context

VelocityContext context = new VelocityContext( );

context.put("results", testResults( ));

context.put("stat", new StatUtil( ));

// Since we've configured our VelocityEngine to load our
// templates from the classpath, we can call mergeTemplate and
// let the VelocityEngine take care of reading our template.

StringWriter writer = new StringWriter( );

vEngine.mergeTemplate("scripting/velocity/results.vm", context, writer);
```

```
// Print out the results

System.out.println( "results: " + writer.toString( ) );
```

When the template is merged with a `VelocityContext` containing student results and a `StatUtil` object, the following output is produced:

Here is the student performance on Test #3: The Geography of Upper Mongolia.

**** Aggregate Statistics**

Average: 84.3%

**** Scores:**

Tim O.	40.2%	FAIL
Susan P.	90.6%	PASS
Steven R.	80.4%	PASS
Kofi A.	78.0%	PASS
Rock P.	85.1%	PASS

More results are available here:
<http://www.tests.com/detail?testId=2324223>

Discussion

Note that the `#score` macro is absent from this template. The `#score` macro encapsulates presentation logic to translate a number grade to a printed letter grade. This macro is stored in a separate file made available as a classpath resource stored in *scripting/velocity/macros.vm*.

```
#macro( score $student $passingGrade )

    #if( $student.score >= $passingGrade )

        Student: ${student.name} Score: ${student.score}% PASS
```



```
#else

    Student: ${student.name} Score: ${student.score}% FAIL

#end

#end
```

The `VelocityEngine` is configured to load both the `#score` macro and the template from the classpath by setting the `resource.loader`, `class.resource.loader.description`, and `class.resource.loader.class`. The `#score` macro is loaded from a macro library, and the location of this library is specified in the `velocimacro.library` configuration property. Velocity has built-in resource loaders to load resources from the filesystem, the classpath, a database, or a JAR file. The following configuration configures two resource loaders for a `VelocityEngine`-a filesystem resource loader and a classpath resource loader. When a resource is loaded, the `VelocityEngine` attempts to locate the resource in the filesystem, and, if the resource is not found, it searches the classpath. Using this configuration, you can create an application with default templates in the classpath, which can be overridden by customized templates on the filesystem. The file resource loader is also configured to cache file resources in memory, checking for a modification every 600 seconds:

```
resource.loader = file, class

file.resource.loader.description = Customized Templates

file.resource.loader.class = \ org.apache.velocity.runtime.resource.loader.
FileResourceLoader

file.resource.loader.path = custom/templates

file.resource.loader.cache = true

file.resource.loader.modificationCheckInterval = 600

class.resource.loader.description = Default Templates

class.resource.loader.class = \ org.apache.velocity.runtime.resource.loader.
ClasspathResourceLoader
```

Instead of configuring a `VelocityEngine` in Java code, the name of this properties file can be passed to the `init()` method:

```
VelocityEngine engine = new VelocityEngine( );

engine.init( "conf/velocity.properties" );
```

See Also

If you need to format dates and numbers, take a look at the `VelocityTools` project, which provides a few ready-made utilities, such as `DateTool`, `NumberTool`, and `MathTool` (<http://jakarta.apache.org/velocity/tools/index.html>).

Velocity's simplicity can be both a blessing and a curse. In this last example, note that the student scores were all stored as integer values. Velocity's numeric comparisons only work with integers values. Try to evaluate `${var < 37.4}` in a Velocity template and you will have inconsistent results. Velocity is simple is by design. If you are looking for a more complex templating engine, the next few recipes introduce another templating engine named FreeMarker.





Recipe 9.10 Obtaining FreeMarker

Problem

You need to use FreeMarker to write templates that can reference variables, object properties, and DOM `Node` objects.

Solution

You must download the latest version of FreeMarker, and place the FreeMarker JAR in your project's classpath. Go to the FreeMarker download page at <http://www.freemarker.org/freemarkerdownload.html>, and download the FreeMarker 2.3 distribution. After you untar and unzip the distribution, you will find a *freemarker.jar* file in the *lib* directory; place this file in your project's classpath.

Discussion

If you have a Maven project that needs to use FreeMarker, add a dependency on FreeMarker with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>freemarker</id>

    <version>2.3</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

To learn more about FreeMarker, visit the FreeMarker web site (<http://www.freemarker.org/>).

To participate in the FreeMarker community, join the FreeMarker users or developers list (http://sourceforge.net/mail/?group_id=794).



Recipe 9.11 Using a Complex Scripting Engine

Problem

You need to find a templating engine that supports number formatting, date formatting, and comparison of double values. In addition, you are looking for a templating engine that gives you more control over whitespace and line breaks.

Solution

Use FreeMarker, a templating engine with a large built-in feature set that includes support for date and number formatting and intelligent handling of whitespace. The following FreeMarker template creates a summary report for a college course:

```
<#assign student = enrollment.student >

<#assign course = enrollment.course >

<#assign exams = enrollment.exams >

<#-- This macro assigns a variable named final -->

<@final exams=exams/>
```

```
${student.firstName} ${student.lastName},
```

```
Here is a summary of your performance in ${course.dept} ${course.num}
${course.name}.
```

```
Class:           ${course.name}

Professor:       ${course.professor}

Section:        ${enrollment.section?string("000")}
```

Exam, Date, Score, Weight, Grade

<#list exams as exam>

 <@compress single_line=true>

 <#assign score = exam.score >

 \${exam.name},

 \${exam.date?date?string.short},

 #{exam.score; m1M1},

 \${exam.weight},

 <@letter score=score/>

 </@compress>

</#list>

Final Grade: \${final; m1M1} <@letter score=final/>

Your final grade has been submitted to the Registrar.

<#macro final exams>

 <#local num = 0>

 <#local dem = 0>

 <#list exams as exam>

 <#local num = num + (exam.score * exam.weight)/>

 <#local dem = dem + exam.weight>

 </#list>

 <#assign final = num / dem>

</#macro>

```
<#macro letter score>

    <#if (score >= 90)> A

    <#elseif (score >= 80)> B

    <#elseif (score >= 70)> C

    <#elseif (score >= 60)> D

    <#else> F

</#if>

</#macro>
```

To merge this template with data, populate a `Map` with named attributes and pass this `Map` to the `template.process()` method. The following code creates a `Configuration` object that loads a FreeMarker template, *template.ftl*, from the classpath. An `Enrollment` object is added to the root `Map`, and the output of the template merge is written to a `StringWriter`:

```
import freemarker.template.Configuration;

import freemarker.cache.ClassTemplateLoader;

import freemarker.template.ObjectWrapper;

import freemarker.template.Template;

StringWriter writer = new StringWriter( );

// Create a Configuration object for FreeMarker

Configuration cfg = Configuration.getDefaultConfiguration( );

cfg.setTemplateLoader(new ClassTemplateLoader(getClass( )));

cfg.setObjectWrapper(ObjectWrapper.BEANS_WRAPPER);

// The root Map serves as a Context for our template engine

Map root = new HashMap( );
```

```
root.put("enrollment", testEnrollment( ));

// A template is processed with a Map and output is sent to a Writer.
Template template = cfg.getTemplate("template.ftl");
template.process(root, writer);

System.out.println("output: \n" + writer.toString( ));
```

The template is rendered, and the following output is printed to the console:

Stefan Winz,

Here is a summary of your performance in ECON 201 Macroeconomics.

Class: Macroeconomics

Professor: Dr. Stephen H. Jones

Section: 002

Exam, Date, Score, Weight, Grade

T01, 01/10/03, 93.4, 1.00, A
T02, 01/27/03, 85.5, 1.50, B
Mid, 02/15/03, 98.0, 2.00, A+
T03, 03/31/03, 71.5, 1.00, C-
T04, 04/10/03, 88.5, 1.50, B+
Fin, 05/05/03, 95.0, 4.00, A
Final Grade: 91 A-

Your final grade has been submitted to the Registrar. Have a great Summer!

Discussion

In the template for this recipe, three objects are retrieved from an `Enrollment` object: a `course` property, a `student` property, and a `List` of `Exam` objects. Three variables-`course`, `student`, and `exam`-are created with the `<#assign>` directive, `<#assign variable = expression >`. Properties are referenced as they were referenced in JEXL and Velocity; `${enrollment.student}` is used to access the `student` property on the `enrollment`. A student's final course grade is calculated in a macro by calling `<@final exams=exams/>`. This macro assigns a global template variable, `final`, which is formatted to one decimal place with the expression `${final; m1M1}`.

At first glance, a FreeMarker template looks very similar to a Velocity template, but there are several interesting features not available in Velocity:

Formatting dates and numbers

Our date object was formatted with the expression `${exam.date?date?string.short}. ?date` instructs the engine to take only the day, month, and year portion of the date, and `?string.short` tells FreeMarker to use the locale's short-date format (12/31/04). You can also specify your own date format using the same syntax you would use in `SimpleDateFormat`. The expression `${exam.date?string("MM-dd-yyyy hh:mm:ss")}` would output a string similar to "12-31-2004 04:23:22."

Comparing dates and numbers

FreeMarker can compare dates and numbers, both integer and floating point.

Macros with named parameters

Macros can be invoked with named parameters. For example, the `@letter` macro can be invoked with named parameters: `<@letter team="Boston Celtics" score="34"></@letter>`.

Here are some other interesting FreeMarker features not available in Velocity:

- Namespaces for variables and macros
- "Built-in" functions for basic types
- Access to XML document objects
- Improved looping
- Local macro variables

- Built-in XML and HTML escaping



Velocity has a very large user base, and it is the right tool for a simple job. FreeMarker has some very useful features "out of the box," while Velocity requires developers to install supporting utilities or write these "extensions" from scratch. Some developers will prefer a templating language that is simple by design, and others need a tool that is substantially more complex. There is a case to be made for simplicity. If you working on a large team, where you have content authors who need to create and maintain your templates, you may want to use a technology like Velocity that embraces simplicity. Open source communities benefit from healthy cross-pollination of ideas and competition, and FreeMarker was developed as an alternative to Jakarta Velocity; they even have a feature comparison page (<http://www.freemarker.org/fmVsVel.html>).

See Also

It is beyond the scope of this book to drill into the details of every FreeMarker feature listed in this recipe. If you are interested in learning more about FreeMarker, take a look at the online documentation (<http://www.freemarker.org/docs/index.html>).

If you are using Jakarta Velocity and wish to migrate your templates to FreeMarker, the FreeMarker team has written a utility, code named "US Cavalry," which will automatically translate your VTL templates to FTL templates. To obtain "US Cavalry," see <http://www.freemarker.org/usCavalry.html>.

Recipe 9.12 Accessing XML Documents from a Templating Engine

Problem

You need to reference XML nodes from a template.

Solution

Use FreeMarker and parse an XML document with the `NodeModel` class. A `NodeModel` is an object that allows access to an XML document as a hierarchy of named elements and attributes from a FreeMarker template. `NodeModel` has a `public static` method `parse()`, which parses an XML document and returns a `NodeModel` to be added to your context `Map`. The following code parses an XML document and passes a `NodeModel` to a template:

```
import freemarker.template.Configuration;

import freemarker.cache.ClassTemplateLoader;

import freemarker.template.ObjectWrapper;

import freemarker.template.Template;

import freemarker.ext.dom.NodeModel;

// Create a File Object for our XML data

File composers = new File("composers.xml");

NodeModel nodeModel = NodeModel.parse( composers );

Map root = new HashMap( );

root.put("doc", nodeModel);

// A template is processed with a Map and output is sent to a Writer.
```



```
Template template = cfg.getTemplate("composerTable.ftl");

template.process(root, writer);

System.out.println("output: \n" + writer.toString( ));
```

A `File` object refers to an XML document, and `NodeModel.parse()` is used to parse this document to a `NodeModel` object, which is then placed in the `root Map`-the context with which the FreeMarker template will be merged. The XML document contains information about the lives of great classical composers, and the structure of this document is shown here:

```
<?xml version="1.0"?>

<composers>

    <composer>

        <name>Bach, Johann Sebastian</name>

        <born date="3/21/1685">

            <location>Eisenbach</location>

        </born>

        <notes>Bach wrote intense and complex fugues.</notes>

        <link>http://www.bachfaq.org/</link>

    </composer>

    <composer>

        <name>Mozart, Wolfgang Amadeus</name>

        <born date="1/27/1756">

            <location>Salzburg</location>

        </born>

        <notes>Wrote first symphony at age 8.</notes>

        <link>http://www.mozartproject.org/</link>

    </composer>

    <composer>
```



```
<name>Hendrix, Jimi</name>

<born date="11/27/1942">

    <location>Seattle</location>

</born>

<notes>Hendrix set his guitar on fire in Monterey</notes>

<link>http://www.jimihendrix.com/</link>

</composer>

</composers>
```

The `NodeModel` object is exposed to the template as `doc`, and the `#list` directive is used to iterate through each `composer` element. A reference to a child element `link` of the `composer` element is `${composer.link}`, and a reference to the date attribute of the born element is preceded by `@--` `${composer.born.@date}`. The FreeMarker template, which references elements and attributes through a `NodeModel`, is:

```
<#list doc.composers.composer as composer>

    <p>

        <a href="${composer.link}">${composer.name}</a><br/>

        Born on ${composer.born.@date} in ${composer.born.location}<br/>

        Notes: ${composer.notes}

    </p>

</#list>
```

Discussion

In addition to simple access to elements and attributes, FreeMarker also allows you to use XPath expressions if Apache Xalan is available on the classpath. If you have Xalan, you can use XPath with the same syntax you would use if you were trying to access a map. Instead of `someMap["key"]`, you would use `someElement["<XPath>"]`. Here is a quick example, which uses an XPath expression to iterate through every composer's "born" element:

```
<#list doc["composers/composer/born"] as birth>

    <p>Born: ${birth.date}, ${birth.location}    ${birth?parent.name}</p>

</#list>
```

FreeMarker also includes a number of built-ins for `NodeModel` objects; in the previous template, `?parent` returns the parent element of the element represented by the `birth` node. [Table 9-4](#) lists a number of built-ins for XML nodes; `?children` returns all of the child nodes of a given node, and `?ancestors` gives every node above this node in an XML document.

Table 9-4. FreeMarker built-ins for `NodeModel` objects

Expression	Evaluates to
<code>\${composers?children}</code>	A sequence of all child nodes. This example would return 3 <code>composer</code> nodes.
<code>\${composer?parent}</code>	If called on a <code>composer</code> node, this would return the <code>composers</code> node.
<code>\${composer?root}</code>	This would return the <code>doc</code> node, which is the topmost node in this document.
<code>\${link?ancestors}</code>	If this corresponded to the link element for Jimi Hendrix, this would return a sequence of <code>[\${composers.composer[3]}, \${composers}]</code> . This returns an array of all ancestors starting with <code>\${link?parent}</code> and ending at <code>\${link.root}</code> .
<code>\${link?node_name}</code>	This would return "link." This returns the name of the element or attribute in question.
<code>\${link?node_type}</code>	This would return "element." It could return "attribute," "element," "text," "comment," "entity," and a few other types corresponding to <code>Node</code> types in the DOM API.

See Also

For more detail about referencing XML elements through `NodeModel` and the use of XPath expressions in FreeMarker, see the "Learning by Example" section of Imperative XML Processing (http://www.freemarker.org/docs/xgui_imperative_learn.html).

FreeMarker also offers syntax for declarative processing of XML-assigning macros to handle elements in an XML document. For more information about FreeMarker declarative XML processing, see the FreeMarker online documentation (http://www.freemarker.org/docs/xgui_declarative_basics.html).

Recipe 9.13 Using Velocity in a Web Application

Problem

You are sick of writing JSP and having to wait for pages to compile. You would like to find a way to use Velocity instead of JSP.

Solution

Configure your web application to use the `VelocityViewServlet` to render your Velocity templates. Download the latest version of the `VelocityView` project from <http://jakarta.apache.org/site/binindex.cgi>; it is listed under "Velocity Tools 1.1." Put the velocity and velocity-tools jars in the `WEB-INF/lib` directory, and configure your web application to render templates ending in `*.vm` with the `VelocityViewServlet`. Add the following `servlet` and `servlet-mapping` elements to your `web.xml` file as follows:

```
<!-- Define Velocity template compiler -->

<servlet>

    <servlet-name>velocity</servlet-name>

    <servlet-class>

        org.apache.velocity.tools.view.servlet.VelocityViewServlet

    </servlet-class>

    <load-on-startup>10</load-on-startup>

</servlet>

.....other servlets.....

<!-- Map *.vm files to Velocity -->

<servlet-mapping>

    <servlet-name>velocity</servlet-name>
```



```
<url-pattern>*.vm</url-pattern>

</servlet-mapping>
```

All requests ending in **.vm* are processed by the `VelocityViewServlet`, which locates the appropriate Velocity template in the document root of your web application. Attributes from the request, session, and application scope will be available as variables in the `VelocityContext`.

To test this configuration, create a simple Velocity template in the document root of your web application named *index.vm*, start your servlet container, and attempt to render the template by loading <http://<server>/<web-app>/index.vm> in a browser. If everything is set up correctly, you should see the rendered template. If the configuration is not correct, you will see the source for your Velocity template.

Discussion

JSP compilation is an annoyance, especially if you are constantly altering and debugging JSP—all that waiting around adds up over the course of a long project. Using Velocity can help improve performance; the simplicity and elegance of Velocity makes parsing and executing a template fast and efficient. If you are looking for a viable alternative to JSP, try Velocity as your view layer, and you might be surprised.

Velocity can be a refreshing break from JSP, and almost any web application framework will work with Velocity. If you are working with an existing web application, there is no need to stop using JSP in lieu of Velocity; you can use both technologies in the same web application. Templates ending in **.jsp* will be rendered by the existing JSP servlet, and templates ending in **.vm* will be rendered by the `VelocityViewServlet`.

See Also

VelocityTools also contains a project named VelocityStruts, which provides tools to integrate Velocity with Jakarta Struts. The VelocityStruts project has tools that duplicate the functionality of the Struts JSP tag libraries—a `FormTool` corresponds to the `html` tag library, a `MessageTool` duplicates the `bean:message` tag, a `TilesTool` provides access to the Struts tiles plug-in. It is possible to introduce Velocity into an existing Struts application by simply adding the `servlet` and `servlet-mapping` to *web.xml*, as shown above. Configure the `VelocityViewServlet`, and configure an `Action` to forward to a velocity template; configure the struts tools by following the directions on the VelocityStruts use guide (<http://jakarta.apache.org/velocity/tools/struts/userguide.html>).

Recipe 9.14 Using FreeMarker in a Web Application

Problem

You would like to use FreeMarker templates in a web application.

Solution

FreeMarker ships with a `FreemarkerServlet`, which can be configured to render your FreeMarker templates. To configure this servlet, add the following `servlet` and `servlet-mapping` elements to your *web.xml*/file:

```
<servlet>

    <servlet-name>freemarker</servlet-name>

    <servlet-class>freemarker.ext.servlet.FreemarkerServlet</servlet-class>

    <init-param>

        <param-name>TemplatePath</param-name>

        <param-value>/</param-value>

    </init-param>

    <init-param>

        <param-name>NoCache</param-name>

        <param-value>true</param-value>

    </init-param>

    <init-param>

        <param-name>ContentType</param-name>

        <param-value>text/html</param-value>

    </init-param>

    <load-on-startup>1</load-on-startup>

</servlet>
```

```
</servlet>

<servlet-mapping>

    <servlet-name>freemarker</servlet-name>

    <url-pattern>*.ftl</url-pattern>

</servlet-mapping>
```

Discussion

If your application contains custom JSP tag libraries, these tag libraries can be used from a FreeMarker template. To see how a JSP tag library can be used in FreeMarker, take a look at the following JSP page, which references an `app` tag library with a TLD file in */WEB-INF/app-taglib.tld*.

```
<%@page language="java"%>

<%@taglib uri="/WEB-INF/app-taglib.tld" prefix="app"%>


<p>

    This is an HTML page with a taglib in it.

</p>


<app:printStuff var="test" mode="fast"/>
```

The `app` tag library has a `printStuff` tag, which takes the parameters `var` and `mode`. The same tag can be used in a FreeMarker template by assigning a reference to *JspTaglibs["/WEB-INF/app-taglib.tld"]* in an `<#assign>` directive. The tag can then be used with a call to `<@app.printStuff/>`:

```
<#assign app=JspTaglibs["/WEB-INF/app-taglib.tld"]>


<p>

    This is an HTML page with a taglib in it.

</p>
```

```
<@app.printStuff var="test" mode="fast"/>
```

That couldn't be much simpler.

See Also

This is a valuable piece of functionality if you are using a framework like Struts, which depends on JSP tag libraries. For more details about using FreeMarker with Struts, see "Using FreeMarker with Servlets" (http://fmpp.sourceforge.net/freemarker/pgui_misc_servlet.html).





Recipe 9.15 Writing Templates in Eclipse

Problem

You are writing a fair amount of Velocity and FreeMarker templates, and you are looking for a tool that can do some syntax highlighting, validation, and code completion.

Solution

If you are writing Velocity templates, use the Velocity UI for Eclipse. To get this plug-in, point your Eclipse Update Manager at <http://veloedit.sourceforge.net/updates/>.

If you are writing FreeMarker templates, use the FreeMarker Eclipse plug-in. To get this plug-in, point your Eclipse Update Manager at <http://www.freemarker.org/eclipse/update>.

See Also

The FreeMarker project maintains templates, plug-ins, and modes for Eclipse, Emacs, jEdit, KWrite, TextPad 4, and Vim. These tools are described on the FreeMarker site at <http://freemarker.org/editors.html>.

The Velocity project has pointers to templates, plug-ins, and modes for IntelliJ IDEA, Eclipse, UltraEdit, JEdit, TextPad, and Emacs. These tools are described on the Velocity site at <http://jakarta.apache.org/velocity/devtools.html>.

For more information about Eclipse, see Steve Holzner's *Eclipse* (O'Reilly) and *Eclipse Cookbook* (O'Reilly).

Chapter 10. I/O and Networking

[Introduction](#)

[Recipe 10.1. Obtaining Commons IO](#)

[Recipe 10.2. Copying Streams, byte\[\], Readers, and Writers](#)

[Recipe 10.3. Closing Streams, Readers, and Writers](#)

[Recipe 10.4. Printing a Human-Readable File Size](#)

[Recipe 10.5. Copying Files, Strings, and URLs](#)

[Recipe 10.6. Deleting Directories Recursively](#)

[Recipe 10.7. Obtaining the Size of a Directory](#)

[Recipe 10.8. Touching a File](#)

[Recipe 10.9. Filtering Files](#)

[Recipe 10.10. Measuring Stream Traffic](#)

[Recipe 10.11. Splitting an OutputStream](#)

[Recipe 10.12. Obtaining Jakarta ORO](#)

[Recipe 10.13. Using Globbs and Perl5 Regular Expressions to List Files](#)

[Recipe 10.14. Obtaining Commons Net](#)

[Recipe 10.15. Writing an FTP Client](#)

[Recipe 10.16. Sending Mail with SMTP](#)

[Recipe 10.17. Checking a POP3 Mailbox](#)

Introduction

If you've ever had to copy a `File` or copy the contents of an `InputStream` to an `OutputStream`, you've probably wondered why Java goes out of its way to make things difficult. Java I/O is not a terribly complex subject, but it does have a knack for turning simpler tasks into complex nests of heavily wrapped `Readers` and streams. Jakarta Commons IO fills a few gaps in Java's I/O and networking capabilities by providing utilities and methods to copy streams, copy files, touch files, recursively delete directories, and safely close `Readers` and streams. If you are working with `Reader`, `Writer`, `InputStream`, or `OutputStream`, you should take a look at `IOUtils` and `CopyUtils`; they may save you a few lines of tedious code.

Commons IO also provides a set of simple `FilenameFilter` implementations, which can be used to selectively list files or directories. In addition to Commons IO's `FilenameFilter` implementations, Jakarta ORO's `GlobFilenameFilter` and `Perl5FilenameFilter` are presented to introduce you to more complex filters involving expressions. ORO is a subproject of Jakarta that provides support for Perl 5 regular expressions and glob expressions. A glob expression is commonly used when listing files in a directory; for example, the expression, `*.xml`, is a glob expression that matches every file that ends in `.xml`. While Java 1.4 provides support for regular expressions, there are subtle differences between the regular expression syntax supported by Java 1.4 and the regular expression syntax supported in Perl 5. You can learn more about the differences between Perl5 regular expressions supported by ORO and regular expressions supported by Java 1.4 by reading the ORO project page at <http://jakarta.apache.org/oro>. Take a look at Jakarta ORO if your application needs to work with globs and complex regular expressions.

Commons Net contains simple clients for common protocols, such as FTP, POP3, and SMTP. Using Commons Net, you can retrieve or transfer files to an FTP server with a very small amount of code. Sun provides a very capable set of classes to send and retrieve mail using POP and SMTP, but the `javax.mail` API brings a certain amount of complexity and overhead that might not make sense for an application sending a simple email message. Commons Net provides a lightweight SMTP client, which can be used to send a simple email message in a few lines of code without introducing the complexity of `javax.mail`. Commons Net also contains a very straightforward POP3 client, which can be used to check a POP mailbox for incoming messages. In addition to FTP, POP, and SMTP, Commons Net contains simple clients for Trivial File Transfer Protocol (TFTP), Telnet, Finger, and NNTP.

Recipe 10.1 Obtaining Commons IO

Problem

You need to use Jakarta Commons IO.

Solution

You must download the latest version of Commons IO, and place the Commons IO JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons IO 1.0 instead of Commons Lang.

Discussion

Commons IO contains a few utilities for simplifying a number of common I/O tasks. `CopyUtils` and `IOUtils` in the `org.apache.commons.io` package provide a suite of static utility methods for working with streams and readers. `org.apache.commons.io.FileUtils` provides static utility methods to help with common `File` operations, such as touching a file, recursive deletion of directories, and reading files. The `org.apache.commons.io.filefilter` package contains implementations of `FilenameFilter`, such as `SuffixFileFilter`, which accepts files with a specified name suffix.

If you have a Maven project, which needs to use Commons IO, add a dependency on Commons IO 1.0 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>commons-io</id>

    <version>1.0</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information about the Commons IO project, see the project page at <http://jakarta.apache.org/commons/io>. If you have questions about using Commons IO, please feel free to join the commons-user@jakarta.apache.org mailing list. Instructions for joining the user mailing list can be found in [Recipe 1.2](#).

Recipe 10.2 Copying Streams, byte[], Readers, and Writers

Problem

You need to copy a stream, `byte[]`, `Reader`, or `Writer`. For example, you need to copy the content from an `InputStream` or `Reader` to a `Writer`, or you need to copy a `String` to an `OutputStream`.

Solution

Use `CopyUtils` from Commons IO to copy the contents of an `InputStream`, `Reader`, `byte[]`, or `String` to an `OutputStream` or a `Writer`. The following code demonstrates the use of `CopyUtils` to copy between an `InputStream` and a `Writer`:

```
import org.apache.commons.io.CopyUtils;

try {

    Writer writer = new FileWriter( "test.dat" );

    InputStream inputStream =

        getClass( ).getResourceAsStream( "./test.resource" );

    CopyUtils.copy( inputStream, writer );

    writer.close( );

    inputStream.close( );

} catch (IOException e) {

    System.out.println( "Error copying data" );

}
```

The previous example reads *test.resource* using an `InputStream`, which is copied to a `FileWriter` using `CopyUtils.copy()`.

Discussion

If you need to copy information from a `Reader` or `InputStream` to a `String`, use `IOUtils.toString()`. The following example opens an `InputStream` from a `URL` and copies the contents to a `String`:

```
import org.apache.commons.io.IOUtils;

URL url = new URL( "http://www.slashdot.org" );

try {

    InputStream inStream = url.openStream( );

    String contents = IOUtils.toString( inStream );

    System.out.println( "Slashdot: " + contents );

} catch ( IOException ioe ) {

    // handle this exception

}
```

Because `CopyUtils` uses a 4 KB buffer to copy between the source and the destination, you do *not* need to supply buffered streams or readers to the `copy()` method. When using `CopyUtils.copy()`, make sure to `flush()` and `close()` any streams, `Readers`, or `Writers` passed to `copy()`.



Recipe 10.3 Closing Streams, Readers, and Writers

Problem

You need to close an `InputStream`, `OutputStream`, `Reader`, or `Writer`, and you want to avoid catching an `IOException` in a `finally` block.

Solution

Use `IOUtils.closeQuietly()` to close an `InputStream`, `OutputStream`, `Reader`, or `Writer` without having to test for `null` or deal with an `IOException`. The following code demonstrates the use of `closeQuietly()` to avoid a nasty `try/catch` within a `finally` block:

```
import org.apache.commons.io.IOUtils

import org.apache.commons.io.CopyUtils

Reader reader = null;

String result = "";

try {

    File file = new File( "test.dat" );

    reader = new FileReader( file );

    result = CopyUtils.toString( reader );


} catch( IOException ioe ) {

    System.out.println( "Unable to copy file test.dat to a String." );

} finally {

    IOUtils.closeQuietly( reader );
```

}



Recipe 10.4 Printing a Human-Readable File Size

Problem

You need to display the size of a file in kilobytes, megabytes, or gigabytes. Instead of displaying file sizes as 1,073,741,824 bytes, you want an approximate, human-readable size, such as 1 GB.

Solution

Use `FileUtils.byteCountToDisplaySize()` to produce a `String` containing an approximate, human-readable size. The following code passes the number of bytes in the file *project.xml* to `FileUtils.byteCountToDisplaySize()`:

```
import org.apache.commons.io.FileUtils;

try {

    File file = new File("project.xml");

    long bytes = file.length();

    String display = FileUtils.byteCountToDisplaySize( bytes );

    System.out.println("File: project.xml");

    System.out.println("  bytes: " + bytes );

    System.out.println("  size: " + display );

} catch( IOException ioe ) {

    System.out.println( "Error reading file length." );

}
```

This code prints out the number of bytes in the *project.xml*/file, and the human-readable size "2 KB":


```
File: project.xml

    bytes: 2132
```

size: 2 KB

Discussion

`FileUtils` contains three static variables-`FileUtils.ONE_KB`, `FileUtils.ONE_MB`, and `FileUtils.ONE_GB`-which represent the number of bytes in a kilobyte, megabyte, and gigabyte. `FileUtils.byteCountToDisplaySize()` divides the number of bytes by each constant until it finds a constant that can divide the number of bytes, discarding the remainder to create a human-readable value. For example, the value 2,123,022 is divided by `FileUtils.ONE_GB`, which returns a value of less than 1.0. The value is then divided by `FileUtils.ONE_MB`, which returns 2-the value used in the human-readable size "2 MB."



`FileUtils.byteCountToDisplaySize()` will not round the size of a file; a 2.9 MB file will have a display size of 2 MB. The byte count is divided by `ONE_KB`, `ONE_MB`, or `ONE_GB`, and the remainder is discarded.

Recipe 10.5 Copying Files, Strings, and URLs

Problem

You need to copy a file to another file, or you need to copy a file to a directory.

Solution

Use `FileUtils.copyFile()` and `FileUtils.copyFileToDirectory()` . The following code copies the file *test.dat* to *test.dat.bak*:

```
import org.apache.commons.io.FileUtils;

try {

    File src = new File( "test.dat" );

    File dest = new File( "test.dat.bak" );

    FileUtils.copyFile( src, dest ) {

} catch( IOException ioe ) {

    System.out.println( "Problem copying file." );

}
```

You may also use `FileUtils.copyFileToDirectory()` to copy a file to a directory. The following code copies the file *test.dat* to the directory *./temp*.

```
try {

    File src = new File( "test.dat" );

    File dir = new File( "./temp" );
```

```
        FileUtils.copyFileToDirectory( src, dir );
    } catch( IOException ioe ) {

        System.out.println( "Problem copying file to dir." );
    }
}
```

Discussion

Quite often you need to write the contents of a `String` to a file. `FileUtils.writeStringToFile()` provides a quick way to write textual content stored in a `String` to a `File`, without opening a `Writer`. The following code writes the contents of the `data String` to the file *temp.tmp*.

```
try {

    String string = "Blah blah blah";

    File dest = new File( "test.tmp" );

    FileUtils.writeStringToFile( dest, string, ? );

}
```

Another common task is storing the contents of a `URL` in a `File`. `FileUtils.copyURLToFile()` takes a `URL` object and stores the contents in a file. The following code stores the contents of the *New York Times* front page in a file *times.html*.

```
try {

    URL src = new URL( "http://www.nytimes.com" );

    File dest = new File( "times.html" );

    FileUtils.copyURLToFile( src, dest );

} catch( IOException ioe ) {

    System.out.println( "Error copying contents of a URL to a File." );

}
```


Recipe 10.6 Deleting Directories Recursively

Problem

You need to delete a directory and everything it contains. You need a recursive delete-the equivalent of a Unix `rm -r`.

Solution

Use `FileUtils.deleteDirectory()` to remove a directory and everything below it. The following example deletes the *temp* directory:

```
import org.apache.commons.io.FileUtils;

try {

    File dir = new File( "temp" );

    FileUtils.deleteDirectory( dir );

} catch( IOException ioe ) {

    System.out.println( "Error deleting directory." );

}
```

This code will delete every file and directory in the *temp* directory and, once the directory is empty, `deleteDirectory()` will remove the *temp* directory itself.

Discussion

You can also "clean" a directory with the `cleanDirectory()` method. When cleaning a directory, the contents of the directory are erased, but the directory itself is not deleted. The following example cleans the *temp* directory, emptying it of all files and subdirectories:

```
import org.apache.commons.io.FileUtils;
```

```
try {  
  
    File dir = new File( "temp" );  
  
    FileUtils.cleanDirectory( dir );  
  
} catch( IOException ioe ) {  
  
    System.out.println( "Problem cleaning a directory" );  
  
}
```

Recipe 10.7 Obtaining the Size of a Directory

Problem

You need to know the size of everything contained within a directory.

Solution

Use the `sizeOfDirectory()` method on `FileUtils`. The following example returns the size of the *temp* directory:

```
File dir = new File( "temp" );

long dirSize = FileUtils.sizeOfDirectory( );
```

If *temp* contains a number files, `FileUtils.sizeOfDirectory()` will return the sum of the size of every file in *temp*. If *temp* contains subdirectories, this method will recursively call `sizeOfDirectory()` on each subdirectory to obtain the size of each subdirectory, and it will return the sum of these sizes.

Recipe 10.8 Touching a File

Problem

You need to perform the equivalent of the Unix `touch` command; you want to create a file or update a file's modified timestamp.

Solution

Use the `touch()` method from `FileUtils`. To use `touch()`, pass it a `File` object; if the `File` does not exist, `touch()` will create a new file. If the file exists, the timestamp of the file will be updated to the current time. The following code demonstrates the `touch()` method on the file *testFile.txt*.

```
import org.apache.commons.io.FileUtils;

try {

    File testFile = new File( "testFile.txt" );

    // If testFile didn't already exists, create it

    // If testFile already exists, update the modified timestamp

    FileUtils.touch( testFile );

} catch( IOException ioe ) {

    System.out.println( "Error touching testFile" );

}
```

If *testFile.txt* does not exist, the file will be created by the call to `touch()`. If *testFile.txt* does exist, the last modified timestamp will be updated to the current time after the call to `touch()`.



Recipe 10.9 Filtering Files

Problem

You need to select all the files in a directory ending in *.xml*, or you need to select only files (not subdirectories) contained in a directory. In other words, you need to filter a list of files.

Solution

Use one of the many implementations of `IOFileFilter` in the `org.apache.commons.io.filefilter` package. This package contains various implementations of `FileFilter` and `FilenameFilter`, which can be used to filter the contents of a directory. The following example uses `SuffixFileFilter` to return an array of filenames that end in *.xml*:

```
import java.io.FilenameFilter;

import org.apache.commons.io.filefilter.SuffixFileFilter;

import org.apache.commons.lang.ArrayUtils;

File rootDir = new File(".");

FilenameFilter fileFilter = new SuffixFileFilter(".xml");

String[] xmlFiles = rootDir.list( fileFilter );

System.out.println( "*** XML Files" );

System.out.println( ArrayUtils.toString( xmlFiles ) );
```

This code searches for all files ending in *.xml* in the current directory. Running this in the root of the example project matches one file, *project.xml*, producing the following output:

```
*** XML Files

{project.xml}
```

Discussion

The `org.apache.commons.io.filefilter` package contains a number of implementations of `FilenameFilter` and `FileFilter`. `PrefixFileFilter` and `SuffixFileFilter` let you match files and directories by a prefix or suffix. `NameFileFilter` matches a file or a directory to a specific name. `DirectoryFileFilter` accepts only directories. `AndFileFilter`, `OrFileFilter`, and `NotFileFilter` allow for the logical combination of filters. The following example uses a combination of the file filters in this package to list `.htm` or `.htm/` files in a directory:

```
import org.apache.commons.io.filefilter.AndFileFilter;

import org.apache.commons.io.filefilter.DirectoryFileFilter;

import org.apache.commons.io.filefilter.IOFileFilter;

import org.apache.commons.io.filefilter.NotFileFilter;

import org.apache.commons.io.filefilter.OrFileFilter;

import org.apache.commons.io.filefilter.SuffixFileFilter;

import org.apache.commons.lang.ArrayUtils;

IOFileFilter htmlFilter =

    new OrFileFilter( new SuffixFileFilter("htm"),

                     new SuffixFileFilter("html") );

IOFileFilter notDirectory = new NotFileFilter( DirectoryFileFilter.INSTANCE );

FilenameFilter fileFilter = new AndFileFilter( htmlFilter, notDirectory );

String[] htmlFiles = rootDir.list(fileFilter);

System.out.println( "*** HTML Files" );

System.out.println( ArrayUtils.toString( htmlFiles ) );
```

This example combines two `SuffixFileFilter` instances in an `OrFileFilter` to match `.htm` or `.html/` files. Wrapping a `DirectoryFileFilter` with a `NotFileFilter` creates a filter that will accept files and reject directories. Combining these two filters in an `AndFileFilter` creates a filter to list files with either suffix. Every filter defined in the `org.apache.commons.io.filefilter` package is an implementation of the `IOFileFilter`, which implements both the `java.io.FileFilter` and `java.io.FilenameFilter` interfaces.

Recipe 10.10 Measuring Stream Traffic

Problem

You need to keep track of the number of bytes read from an `InputStream` or written to an `OutputStream`.

Solution

Use a `CountingInputStream` or `CountingOutputStream` to keep track of the number of bytes written to a stream. The following example uses a `CountingOutputStream` to keep track of the number of bytes written to a `FileOutputStream`:

```
import org.apache.commons.io.IOUtils;

import org.apache.commons.io.output.CountingOutputStream;

import java.io.*;

File test = new File( "test.dat" );

CountingOutputStream countStream = null;

try {

    FileOutputStream fos = new FileOutputStream( test );

    countStream = new CountingOutputStream( fos );

    countStream.write( "Hello".getBytes( ) );

} catch( IOException ioe ) {

    System.out.println( "Error writing bytes to file." );

} finally {

    IOUtils.closeQuietly( countStream );

}
```

```
}

if( countStream != null ) {

    int bytesWritten = countStream.getCount( );

    System.out.println( "Wrote " + bytesWritten + " bytes to test.dat" );

}
```

This previous example wrapped a `FileOutputStream` with a `CountingOutputStream`, producing the following console output:

```
Wrote 5 bytes to test.dat
```

Discussion

`CountingInputStream` wraps an `InputStream` and `getCount()` provides a running tally of total bytes read. The following example demonstrates `CountingInputStream`:

```
import org.apache.commons.io.IOUtils;

import org.apache.commons.io.output.CountingOutputStream;

import java.io.*;

File test = new File( "test.dat" );

CountingInputStream countStream = null;

try {

    FileInputStream fis = new FileInputStream( test );

    countStream = new CountingOutputStream( fis );

    String contents = IOUtils.toString( countStream );

} catch( IOException ioe ) {

    System.out.println( "Error reading bytes from file." );

} finally {
```



```
        IOUtils.closeQuietly( countStream );
    }

    if( countStream != null ) {
        int bytesRead = countStream.getCount( );

        System.out.println( "Read " + bytesRead + " bytes from test.dat" );
    }
}
```



Recipe 10.11 Splitting an OutputStream

Problem

You need to send the same output to two `OutputStream`s.

Solution

Use Commons IO `TeeOutputStream` to send the same data to two instances of `OutputStream`. When data is written to a `TeeOutputStream`, that data is sent to the two instances of `OutputStream` passed to its constructor. The following example demonstrates the use of `TeeOutputStream` to write the same `String` to two instances of `FileOutputStream`:

```
import org.apache.commons.io.IOUtils;

import org.apache.commons.io.output.TeeOutputStream;

File test1 = new File("split1.txt");

File test2 = new File("split2.txt");

OutputStream outputStream = null;

try {

    FileOutputStream fos1 = new FileOutputStream( test1 );

    FileOutputStream fos2 = new FileOutputStream( test2 );

    outputStream = new TeeOutputStream( fos1, fos2 );

    outputStream.write( "One Two Three, Test".getBytes( ) );

    outputStream.flush( );

} catch( IOException ioe ) {
```

```
        System.out.println( "Error writing to split output stream" );
    } finally {
        IOUtils.closeQuietly( outputStream );
    }
}
```

Flushing or closing a `TeeOutputStream` will flush or close both of the `OutputStream` instances it contains. After this example is executed, two files, *split1.txt* and *split2.txt*, will contain the same text.

Recipe 10.12 Obtaining Jakarta ORO

Problem

You need to use Jakarta ORO to finds files by a glob or regular expression.

Solution

Download Jakarta ORO 2.0.8 from <http://jakarta.apache.org/site/binindex.cgi>. Once you have downloaded and uncompressed the archive distribution, place the *jakarta-oro-2.0.8.jar* in your classpath.

Discussion

Jakarta ORO provides support for Perl regular expressions, AWK expressions, and glob expressions. Before Java 1.4 introduced the `java.util.regex` package and regular expression support in the `String` class, Jakarta ORO and Jakarta RegExp gave developers a way to use regular expressions in Java. Now that Java 1.4 supports regular expressions, ORO still remains relevant for developers who need specific support for Perl5 extended regular expressions.

If you have a Maven project that needs to use Jakarta ORO, add a dependency on Jakarta ORO 2.0.8 with the following section in *project.xml*.

```
<dependencies>
  <dependency>
    <id>oro</id>
    <version>2.0.8</version>
  </dependency>
  ....other dependencies...
</dependencies>
```

See Also

For more information about ORO, see the Jakarta ORO project at <http://jakarta.apache.org/oro>. For more information about the regular expression syntax supported by Jakarta ORO, see the package summary for the `org.apache.oro.test.regex` package at <http://jakarta.apache.org/oro/api/org/apache/oro/text/regex/package-summary.html>.

Recipe 10.13 Using Globs and Perl5 Regular Expressions to List Files

Problem

You need to get a list of files that match either a glob or regular expression.

Solution

Use `Perl5FilenameFilter` or `GlobFilenameFilter` from Jakarta ORO to select all files matching an expression. Both of these classes implement the `FileFilter` and `FilenameFilter` interface, and both can be passed to the `listFiles()` method on a `File` object. The following example uses `GlobFilenameFilter` to list XML files in the `./dataDir` directory:

```
import org.apache.oro.io.GlobFilenameFilter;

File dataDir = new File("./dataDir");

FilenameFilter xmlFilter = new GlobFilenameFilter( "*.xml" );

File[] xmlFiles = dataDir.listFiles( xmlFilter );
```

To find all files matching a Perl regular expression, use the `Perl5FilenameFilter`. The following example returns files starting with "dev" and ending with ".tld" by passing a regular expression to the constructor of `Perl5FilenameFilter`:

```
File dataDir = new File("./dataDir");

FilenameFilter regexFilter = new Perl5FilenameFilter( "^dev.*.tld$" );

File[] tldFiles = dataDir.listFiles( regexFilter );
```



Recipe 10.14 Obtaining Commons Net

Problem

You need to use Commons Net to write a simple FTP, SMTP, or POP3 client.

Solution

Download the latest version of Commons Net, and place the Commons Net JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons Net 1.2.2 instead of Commons Lang.

Discussion

Jakarta Commons Net contains some simple clients for commonly used network protocols, such as FTP, TFTP, Telnet, NNTP, POP3, and SMTP. Protocols are supported by collections of classes in packages dedicated to these protocols. For example, FTP is supported by a set of classes in the `org.apache.commons.net.ftp` package, including `FTPClient` and `FTPFile`; and SMTP is supported by classes in the `org.apache.commons.net.smtp` package, including `SMTPClient`.

If you have a Maven project that needs to use Commons Net, add a dependency on Commons Net 1.2.2 with the following section in *project.xml*:

```
<dependencies>

  <dependency>

    <id>commons-net</id>

    <version>1.2.2</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information about Commons Net, see the Commons Net project page at <http://jakarta.apache.org/commons/net>.

PREV

< Day Day Up >



Recipe 10.15 Writing an FTP Client

Problem

You need to write a program to interact with an FTP server.

Solution

Use Commons Net `FTPClient` to communicate with an FTP server. The following example retrieves the contents of the file *c64bus.gif* from *ftp.ibiblio.org*.

```
import org.apache.commons.io.IOUtils;

import org.apache.commons.net.ftp.FTPClient;

FTPClient client = new FTPClient( );

OutputStream outStream = null;

try {

    // Connect to the FTP server as anonymous

    client.connect( "ftp.ibiblio.org" );

    client.login( "anonymous", "" );

    String remoteFile = "/pub/micro/commodore/schematics/computers/c64/

        c64bus.gif";

    // Write the contents of the remote file to a FileOutputStream

    outStream = new FileOutputStream( "c64bus.gif" );
```



```

        client.retrieveFile( remoteFile, outputStream );
    } catch(IOException ioe) {

        System.out.println( "Error communicating with FTP server." );
    } finally {

        IOUtils.closeQuietly( outputStream );

        try {

            client.disconnect( );

        } catch (IOException e) {

            System.out.println( "Problem disconnecting from FTP server" );

        }

    }
}

```

In the previous example, an instance of `FTPClient` is created; the example then logs on to *ftp.ibiblio.org* as *anonymous*-with no password-using the `connect()` and `login()` method on `FTPClient`. The full path to the remote file *c64bus.gif* and an `OutputStream` are passed to `retrieveFile()`, which then transfers the contents of the *c64bus.gif* to a local file. Once the file has been retrieved, the `FTPClient` is disconnected from the server using the `disconnect()` method in a `finally` block.

Discussion

`FTPClient` can also be used to list the contents of a directory by passing a directory to the `listFiles()` method. The following example uses `FTPClient` to print the name and size of every file in the */pub/mirrors/apache/jakarta/ecs/binaries* directory on *ftp.ibiblio.org*.

```

import org.apache.commons.net.ftp.FTPClient;

import org.apache.commons.net.ftp.FTPFile;

FTPClient client = new FTPClient( );

// Connect to the FTP server as anonymous

client.connect( "ftp.ibiblio.org" );

```

```
client.login( "anonymous", "" );

String remoteDir = "/pub/mirrors/apache/jakarta/ecs/binaries";

// List the contents of the remote directory

FTPFile[] remoteFiles = client.listFiles( remoteDir );

System.out.println( "Files in " + remoteDir );

for (int i = 0; i < remoteFiles.length; i++) {

    String name = remoteFiles[i].getName( );

    long length = remoteFiles[i].getSize( );

    String readableLength = FileUtils.byteCountToDisplaySize( length );

    System.out.println( name + ":\t\t" + readableLength );

}

client.disconnect( );
```

After connecting to *ftp.ibiblio.org*, this example retrieves an array of `FTPFile` objects using `client.listFiles()`. Each `FTPFile` object contains information describing the remote file, and the name and size of each `FTPFile` is printed to the console as follows:

```
Files in /pub/mirrors/apache/jakarta/ecs/binaries

README.html:          1 KB

RELEASE_NOTES.txt:     2 KB

ecs-1.4.2.tar.gz:      1 MB

ecs-1.4.2.tar.gz.asc:   65 bytes

ecs-1.4.2.tar.gz.md5:   33 bytes

ecs-1.4.2.zip:         2 MB

ecs-1.4.2.zip.asc:     65 bytes
```

ecs-1.4.2.zip.md5: 33 bytes

See Also

Commons Net also contains a Trivial File Transfer Protocol (TFTP) client:
`org.apache.commons.net.tftp.TFTPClient`. For more information about TFTP client, see the Javadoc for `TFTPClient` at <http://jakarta.apache.org/commons/net/apidocs/org/apache/commons/net/tftp/TFTPClient.html>.

`FTPClient` contains a number of additional features, such as active and passive connection modes and the ability to append to remote files, make remote directories, and put files on a remote FTP server. For more information about `FTPClient`, see the `FTPClient` Javadoc at <http://jakarta.apache.org/commons/net/apidocs/org/apache/commons/net/ftp/FTPClient.html>.

Recipe 10.16 Sending Mail with SMTP

Problem

You need to send an email.

Solution

Use `SMTPClient` from Commons Net. The following example sends a simple email to *somedude@aol.org* from *tobrien@discursive.com* via the SMTP server on host *www.discursive.com* using port 25:

```
import org.apache.commons.net.smtp.SMTPClient;

SMTPClient client = new SMTPClient( );

client.connect("www.discursive.com");

client.sendMessage("tobrien@discursive.com",

                  "somedude@aol.com",

                  "Hey! Call me when you get a chance." );

client.disconnect( );
```

This example sends a very simple email message to one recipient by passing three arguments to `client.sendMessage()`: the sender's email address, the recipient's email address, and a message. If you are trying to send a simple email message to multiple recipients, pass a `String[]` containing each address as the second parameter to `sendMessage()`. The following example sends a simple email message to multiple recipients by passing a `String[]` to `sendMessage()`:

```
import org.apache.commons.net.smtp.SMTPClient;

SMTPClient client = new SMTPClient( );

client.connect("www.discursive.com");
```



```
String[] recipients = new String[2];

recipients[0] = "mission-control@nasa.gov";

recipients[1] = "announce@nasa.gov";


client.sendMessage("astronaut@nasa.gov",

                  recipients,

                  "The eagle has landed." );

client.disconnect( );
```

Discussion

Telnet to port 25 of a SMTP server, and you will see the server respond with a numeric code (220). `SMTPReply.isPositiveCompletion()` returns `true` if the response code of the previously executed command is between 200 and 299; the value of the initial response code, 220, is equal to the public static variable `SMTPReply.SERVICE_READY`. The following example uses `getReplyCode()` and `SMTPReply.isPositiveCompletion()` to test the connection to the SMTP server:

```
import org.apache.commons.net.smtp.SMTP;

import org.apache.commons.net.smtp.SMTPClient;

import org.apache.commons.net.smtp.SMTPReply;


SMTPClient client = new SMTPClient( );

client.connect("www.discursive.com");


int response = client.getReplyCode( );

if( SMTPReply.isPositiveCompletion( response ) ) {

    // Set the sender and the recipients

    client.setSender( "tobrien@discursive.com" );
```

```

        client.addRecipient( "president@whitehouse.gov" );

        client.addRecipient( "vicepresident@whitehouse.gov" );

        // Supply the message via a Writer

        Writer message = client.sendMessageData( );

        message.write( "Spend more money on energy research.  Thanks." );

        message.close( );

        // Send the message and print a confirmation

        boolean success = client.completePendingCommand( );

        if( success ) {

            System.out.println( "Message sent" );

        }

    } else {

        System.out.println( "Error communicating with SMTP server" );

    }

    client.disconnect( );

```

Instead of `sendSimpleMessage()`, the previous example sets a sender address and two recipient addresses using `setSender()` and `addRecipient()`. The message body is then written to a `Writer` returned by `sendMessageData()`. When the `Writer` is closed, the message is sent by calling `completePendingCommand()`. `completePendingCommand()` returns `true` if the message has been queued for delivery.

See Also

JavaMail is the set of utilities contained in the `javax.mail` package, and JavaMail is usually used in conjunction with the Java Activation Framework (JAF) to send email messages using SMTP. Common: Net does not aim to replace the JavaMail API, but it does provide a very straightforward alternative for sending email messages. For more information about JavaMail, see the JavaMail product page at <http://java.sun.com/products/javamail>. For more information about the JavaMail API, see Chapter 10, "JavaMail Best Practices," in *Java Enterprise Best Practices* (O'Reilly).

Recipe 10.17 Checking a POP3 Mailbox

Problem

You need to check a POP3 mailbox.

Solution

Use Commons Net `POP3Client` to check a POP3 mailbox for incoming mail. The following example connects to the POP3 server *www.discursive.com*, logs in as `tobrien@discursive.com`, and prints each message in the mailbox:

```
import org.apache.commons.io.CopyUtils;

import org.apache.commons.io.IOUtils;

import org.apache.commons.net.pop3.POP3Client;

import org.apache.commons.net.pop3.POP3MessageInfo;

POP3Client client = new POP3Client( );

client.connect("www.discursive.com");

client.login("tobrien@discursive.com", "secretpassword");

POP3MessageInfo[] messages = client.listMessages( );

for (int i = 0; i < messages.length; i++) {

    int messageNum = messages[i].number;

    System.out.println( "***** Message number: " + messageNum );

    Reader reader = client.retrieveMessage( messageNum );

    System.out.println( "Message:\n" + IOUtils.toString( reader ) );

    IOUtils.closeQuietly( reader );
}
```



```
}
```

```
client.logout( );
```

```
client.disconnect( );
```

This example calls `client.listMessage()` to get an array of `POP3MessageInfo` objects. Each message is retrieved using the message number contained in each `POP3MessageInfo`. To retrieve the contents of an individual message, the message number is passed to `retrieveMessage()`, which returns a `Reader` from which the message body is read. The previous example prints the contents of a POP3 mailbox, as shown below:

```
***** Message number: 1
```

```
Message:
```

```
Return-Path: <jerk@spamheaven.net>
```

```
X-Original-To: tobrien@discursive.com
```

```
Delivered-To: tobrien@discursive.com
```

```
Received: from jerk-net.co.jp (unknown [219.71.255.123])
```

```
    by pericles.symbiont.net (Postfix) with SMTP id 6FA54543FE
```

```
    for <tobrien@discursive.com>; Tue, 22 Jun 2004 02:19:13 -0400 (EDT)
```

```
Received: from 228.4.65.206 by smtp.cito.nl;
```

```
    Tue, 22 Jun 2004 06:09:26 +0000
```

```
Message-ID: <9b8001c4581f$2524e2e9$d8470c90@jerk-net.co.jp>
```

```
From: "Spammer" <jerk@spamheaven.net>
```

```
To: tobrien@discursive.com
```

```
Subject: Hey, I heard you need a mortgage
```

```
Date: Tue, 22 Jun 2004 02:09:21 -0400
```

```
MIME-Version: 1.0
```

```
Content-Type: text/plain;
```

```
    charset="iso-8859-1"
```

Content-Transfer-Encoding: 8bit

Hello,

I heard that you must be a sucker, so I thought I would send you some unsolicited email about a mortgage. Only 3%, and you can even wire the money directly to my friend from Nigeria. Did I mention that if you decide to take this mortgage I'll send you the secret for making millions by sending useless spam.

Mr. Jerk Spammer

"I ruin email for everyone!"

Discussion

This example did not venture into the topic of parsing an email message body. As shown above, the message read with `retrieveMessage()` is a raw message with SMTP headers containing the *Subject*, *Message-ID*, and other important pieces of data associated with a message. The body of a message is separated from a list of headers by a single blank, and if you are creating a mail client for a user, you will need to write a parser that can extract a relevant header-such as *Subject* and *From*-from the raw email message.

See Also

This recipe used `IOUtils.toString()` and `IOUtils.closeQuietly()` to copy and close a `Reader` for each email message. These methods are described in detail in [Recipe 10.2](#) and [Recipe 10.3](#).

For a good overview of SMTP and POP3 from the perspective of a FreeBSD administrator, take a look at Dru Lavigne's article "Understanding E-Mail" from OnLamp.com (http://www.onlamp.com/pub/a/bsd/2000/08/30/FreeBSD_Basics.html).

Chapter 11. HTTP and WebDAV

[Introduction](#)

[Recipe 11.1. Obtaining Jakarta HttpClient](#)

[Recipe 11.2. Getting Jakarta HttpClient Source Code](#)

[Recipe 11.3. Performing an HTTP GET](#)

[Recipe 11.4. Sending Parameters in a Query String](#)

[Recipe 11.5. Retrieving Content with a Conditional GET](#)

[Recipe 11.6. Debugging HTTP Communications](#)

[Recipe 11.7. Making an HTTP POST Request](#)

[Recipe 11.8. Sending POST Data from a File](#)

[Recipe 11.9. Uploading Files with a Multipart POST](#)

[Recipe 11.10. Basic Authentication](#)

[Recipe 11.11. NTLM Authentication](#)

[Recipe 11.12. Working with Cookies](#)

[Recipe 11.13. Handling Redirects](#)

[Recipe 11.14. SSL](#)

[Recipe 11.15. Accepting a Self-Signed Certificate](#)

[Recipe 11.16. Obtaining Jakarta Slide](#)

[Recipe 11.17. Connecting to WebDAV Resources](#)

[Recipe 11.18. Modifying a WebDAV Resource](#)



Introduction

The Hypertext Transfer Protocol (HTTP) is ubiquitous; this protocol is at the core of important technologies such as the World Wide Web (WWW), the Simple Object Access Protocol (SOAP), XML databases, content management systems, WebDAV, and, most importantly, iTunes. Much of the world's business is accomplished over HTTP in some form or another, and if this protocol were to suddenly vanish, a sizable portion of the world economy would vanish with it. Given this ubiquity, it is likely that you've had occasion to write a Java program that needed to fetch a web page or interact with a servlet or CGI script. While the J2SE contains some rudimentary tools to communicate via HTTP, the feature set of `URLConnection` is somewhat limited. This chapter introduces Jakarta HttpClient, a set of utilities that simplifies the task of retrieving and sending information over HTTP.

Jakarta HttpClient grew up in the Jakarta Commons, and until April 2004 it was a Commons project. It has only recently graduated to a full Jakarta project, and it is still visible as a part of the Jakarta Commons subproject. This chapter refers to HttpClient as Jakarta HttpClient, but you should be aware that most of the documentation and support still refer to the project as Jakarta Commons HttpClient until the project has successfully migrated out of the Jakarta Commons.

Recipe 11.1 Obtaining Jakarta HttpClient

Problem

You need to use Jakarta HttpClient to write a program to interact with a server over HTTP.

Solution

Download Jakarta HttpClient 3.0. Following the steps outlined in [Recipe 1.1](#), download "Commons HttpClient 3.0" instead of Commons Lang. The HttpClient archive- *commons-httpclient-3.0.zip*-will contain a file named *commons-httpclient-3.0.jar*, place this JAR file in your classpath, and you will be ready to use Jakarta HttpClient.

Jakarta HttpClient depends on Jakarta Commons Logging, which can be obtained from the same binary download page as HttpClient. To download Commons Logging, see [Recipe 7.9](#). Jakarta HttpClient also depends on Jakarta Commons Codec, which can also be obtained from the same binary download page as HttpClient. To download Commons Codec, see [Recipe 2.15](#).

Discussion

Jakarta HttpClient is a client library for the HTTP protocol. HttpClient is very feature-rich, supporting all HTTP methods defined in RFC 2616 (Hypertext Transfer Protocol, HTTP/1.1). Jakarta HttpClient supports GET, POST, PUT, OPTIONS, HEAD, and DELETE using the command pattern; `HttpMethod` objects are instantiated and executed by an `HttpClient` object that manages server interaction and state across multiple requests. HttpClient has support for various authentication mechanisms, including Basic, Digest, and NTLM authentication. HttpClient supports both HTTP and HTTPS, and the library can manage the complexity involved in using both schemes with an HTTP proxy. HttpClient can manage the state of a session, automatically keeping track of cookies across multiple requests.

If you have a Maven project that needs to use Jakarta HttpClient, add a dependency on Jakarta HttpClient 3.0 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>httpclient</id>

    <version>3.0</version>

  </dependency>
```

```
....other dependencies...
```

```
</dependencies>
```

See Also

For more information about the Jakarta HttpClient project, see the project page (<http://jakarta.apache.org/commons/httpclient>).



The Jakarta Commons HttpClient recently voted itself out of the Jakarta Commons and into Jakarta as a subproject. Be aware that the URLs specified in this recipe may not be accurate after HttpClient "graduates" from the Jakarta Commons.

If you have questions about using HttpClient, please feel free to join the commons-user@jakarta.apache.org mailing list. Instructions for joining the user mailing list can be found in [Recipe 1.2](#). Note that as Jakarta Commons HttpClient becomes Jakarta HttpClient, the commons-user mailing list may stop being the place to ask questions about Jakarta HttpClient. Investigate the current status of HttpClient before joining these mailing lists.

For information on obtaining the source code for Commons HttpClient, see [Recipe 11.2](#).



Recipe 11.2 Getting Jakarta HttpClient Source Code

Problem

You need the source code for the Jakarta HttpClient project.

Solution

Download the source distribution of Jakarta HttpClient 3.0. Following the steps outlined in [Recipe 1.3](#), download "Commons HttpClient 3.0" instead of Commons Lang. The HttpClient source archive-*commons-httpclient-3.0-src.zip*-contains a directory named *src*, which contains the source for HttpClient.

Discussion

The *commons-httpclient-3.0-src* directory will contain the following:

build.xml

An Apache Ant build file that you can use to compile the source. If Ant is installed, you can compile or test by running `ant compile` or `ant test`.

maven.xml, *project.xml*, and *project.properties*

These three files are Maven project files. If Maven is installed, you can compile or test by running `maven compile` or `maven test`.

src/java

This subdirectory contains the source for the classes in Jakarta HttpClient.

src/test

This subdirectory contains unit tests for the Jakarta HttpClient project. Each **Test.java* file is

an extension of JUnit `TestCase` class.

See Also

For information on obtaining the binary distribution for Jakarta HttpClient, see [Recipe 11.1](#).

PREV

< Day Day Up >



Recipe 11.3 Performing an HTTP GET

Problem

You need to retrieve information with the HTTP GET method.

Solution

Create an instance of `HttpClient` and use it to execute a `GetMethod` object. Once the method has been executed, the response body can be accessed as an `InputStream`, `byte[]`, or `String`. The following example gets the contents of <http://www.discursive.com/jccook/> and retrieves the response body as a string:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.methods.GetMethod;

HttpClient client = new HttpClient( );

String url = "http://www.discursive.com/jccook/";

HttpMethod method = new GetMethod( url );

try {

    client.executeMethod( method );

    if( method.getStatusCode( ) == HttpStatus.SC_OK ) {

        String response = method.getResponseBodyAsString( );

        System.out.println( response );

    }

}
```

```
    }

} catch( HttpException he ) {

    System.out.println( "HTTP Problem: " + he.getMessage( ) );

} catch( IOException ioe ) {

    System.out.println( "IO Exeception: " + ioe.getMessage( ) );

} finally {

    method.releaseConnection( );

    method.recycle( );

}
```

This code retrieves the content of <http://www.discursive.com/jccook> using the HTTP GET method. If the response code is `HttpStatus.SC_OK` or `200`, the response is printed to the console:

```
<html>

<head>

    <title>JCCook Example</title>

</head>

<body>

    <h1>Hello World!</h1>

</body>

</html>
```

Discussion

Note the exception handling involved in this example. Performing a simple HTTP GET called for two catch blocks: `HttpException` and `IOException`. An `HttpException` is thrown if there is a problem relating to the HTTP protocol, and an `IOException` is thrown if there is a problem with the network. Examples in this chapter omit the rigorous exception handling from the previous example; you can assume that every call to `execute()` is surrounded by the appropriate `try/catch` block.

`GetMethod` is an implementation of the `HttpMethod` interface, which is executed by `HttpClient`. The lifecycle of any `HttpMethod` implementation is straightforward; an `HttpMethod` is created, executed by an instance of `HttpClient`, and, once the response has been examined, the connection is released and the method is recycled. When an `HttpMethod` object is recycled by a call to `recycle()`

), it is a signal to the system that this specific `HttpMethod` instance can be used again. `releaseConnection()` instructs `HttpClient` to release the connection that is associated with an `HttpMethod` instance. No matter what happens during the execution of a method, the `releaseConnection()` must be called to free network resources.

Once a method has been executed, you can get the response status code from `method.getStatusCode()`. This method returns an `int`, which will correspond to one of the `public static final` variables on `HttpStatus`. Some of the more common status codes on `HttpStatus` are `SC_OK` (200), `SC_NOT_FOUND` (404), `SC_INTERNAL_SERVER_ERROR` (500), `SC_MOVED_TEMPORARILY` (302), and `SC_UNAUTHORIZED` (401). For a full list of HTTP status codes, see the Javadoc for `HttpStatus`. When a server sends back a bad HTTP status, it is sometimes accompanied by a short message. This message can be read by calling `method.getStatusText()`.

See Also

For a formal definition of the HTTP GET method, see Section 9.3 of RFC 2616 at <http://www.zvon.org/tmRFC/RFC2616/Output/index.html>.

For a full list of HTTP status codes, see the `HttpStatus` Javadoc at <http://jakarta.apache.org/commons/httpclient/apidocs/index.html>.

Recipe 11.4 Sending Parameters in a Query String

Problem

You need to send query parameters in a URL.

Solution

Set the query string using the `setQueryString()` method on an instance of `HttpMethod`. Use `URIUtil` to encode any text included in a URL. The following example puts two parameters on the query string:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.NameValuePair;

import org.apache.commons.httpclient.methods.GetMethod;

import org.apache.commons.httpclient.util.URIUtil;

HttpClient client = new HttpClient( );

String url = "http://www.discursive.com/cgi-bin/jccook/param_list.cgi";

HttpMethod method = new GetMethod( url );

// Set the Query String with setQueryString( )

method.setQueryString(URIUtil.encodeQuery("test1=O Reilly&blah=Whoop"));

System.out.println( "With Query String: " + method.getURI( ) );
```



```
client.executeMethod( method );
```

```
System.out.println( "Response:\n " + method.getResponseBodyAsString( ) );
```

```
method.releaseConnection( );
```

The *param_list.cgi* CGI script echoes all parameters received, and from the following output, you can see how `URIUtil` encodes the first parameter:

With Query String: `http://www.discursive.com/cgi-bin/jccook/param_list.`

```
cgi?test1=O%20Reilly&blah=Whoop
```

Response:

```
These are the parameters I received:
```

```
test1:
```

```
O Reilly
```

```
blah:
```

```
Whoop
```

The question mark is understood, and you do not need to supply a leading question mark to the `setQueryString()` method of `HttpMethod`, as it will be automatically added when the method is executed by an instance of `HttpClient`.

Discussion

In the previous example, `method.setQueryString()` is used to set the entire query string at once, but there is another alternative: setting the query string with an array of `NameValuePair` objects. When a `NameValuePair[]` is passed to `method.setQueryString()`, the `HttpMethod` then takes each pair and creates a series of parameters delimited by an ampersand. The approach encourages cleaner code because you are not concatenating strings to pass multiple parameters. The following example sets the same parameters used in the previous example, using `NameValuePair` objects:

```
// Set query string with name value pair objects
```

```
HttpMethod method = new GetMethod( url );

NameValuePair pair =

    new NameValuePair( "test1", URIUtil.encodeQuery( "O Reilly" ) );

NameValuePair pair2 =

    new NameValuePair( "blah", URIUtil.encodeQuery( "Whoop" ) );

NameValuePair[] pairs = new NameValuePair[] { pair, pair2 };

method.setQueryString( pairs );

System.out.println( "With NameValuePairs: " + method.getURI( ) );

client.executeMethod( method );

System.out.println( "Response:\n " + method.getResponseBodyAsString( ) );

method.releaseConnection( );
```

According to RFC 1738 (Uniform Resource Locators (URL) specification) URLs can only contain alphanumeric characters, `[0-9a-zA-Z]`, and a few other special characters. If you need to send a parameter with an unacceptable character in a URL, you will need to encode your string according to the standard defined in RFC 1738. `URIUtil` exposes a method `encodeQuery()` that can be used to encode the value "O Reilly" in the previous example. The following code demonstrates the use of `URIUtil` to encode strings for inclusion in a URL:

```
String encoded1 = URIUtil.encodeQuery( "<test>=O'Connell" );

String encoded2 = URIUtil.encodeQuery( "one:two=thr ee#" );


String decoded = URIUtil.decode( "Hello%20World%3F" );


System.out.println( "Encoded: " + encoded1 );

System.out.println( "Encoded: " + encoded2 );

System.out.println( "Decoded: " + decoded );
```

This simple example encodes two strings and decodes an encoded string using `URIUtil`. The output shows the result of each transformation:

```
Encoded: %3ctest%e3=O'Connell
```

Encoded: one%3atwo=thr%20ee#23

Decoded: Hello World?

See Also

In this example, `URLUtil` was used to encode content passed in on the query string. This `HttpClient` team has recently moved some of the URL encoding and decoding logic to the Jakarta Commons Codec project as a class named `URLCodec`. For more information about `URLCodec`, see the Jakarta Commons Codec project page (<http://jakarta.apache.org/codec>).

RFC 1738 discusses the legal characters for a URL and defines a process for encoding other characters. RFC 1738 can be found at <http://www.zvon.org/tmRFC/RFC2616/Output/index.html>.

Recipe 11.5 Retrieving Content with a Conditional GET

Problem

You need to retrieve the same content more than once, and you would like to have the server only send the content if it has changed since the last request.

Solution

Create a `GetMethod` and set the *If-None-Match* and *If-Modified-Since* headers; these two headers will instruct the server to refrain from sending content if the content has not been altered since the last request. [Example 11-1](#) makes three separate requests for the same URL (<http://www.apache.org>), and, because the content remains static, it is only sent in the response body of the first request.

Example 11-1. Requesting information with a conditional GET

```
import java.io.IOException;

import org.apache.commons.httpclient.Header;
import org.apache.commons.httpclient.HeaderElement;
import org.apache.commons.httpclient.HttpClient;
import org.apache.commons.httpclient.HttpException;
import org.apache.commons.httpclient.HttpMethod;
import org.apache.commons.httpclient.HttpStatus;
import org.apache.commons.httpclient.methods.GetMethod;

public class ConditionalGetExample {

    public static void main(String[] args) throws HttpException, IOException {
```



```
ConditionalGetExample example = new ConditionalGetExample( );

example.start( );

}

String entityTag = "";

String lastModified = "";

public void start( ) throws HttpException, IOException {

    HttpClient client = new HttpClient( );

    HttpMethod method = new GetMethod("http://www.apache.org");

    for( int i = 0; i < 3; i++ ) {

        setHeaders(method);

        client.executeMethod(method);

        processResults(method);

        method.releaseConnection( );

        method.recycle( );

    }

}

private void setHeaders(HttpMethod method) {

    method.setRequestHeader(new Header("If-None-Match", entityTag ) );

    method.setRequestHeader(new Header("If-Modified-Since",

                                         lastModified ) );

}
```

```

private void processResults(HttpMethod method) throws HttpException {

    if(method.getStatusCode( ) == HttpStatus.SC_NOT_MODIFIED ) {

        System.out.println( "Content not modified since last request" );

    } else {

        entityTag = retrieveHeader( method, "ETag" );

        lastModified = retrieveHeader( method, "Last-Modified" );

        System.out.println( "Get Method retrieved content." );

        System.out.println( "Entity Tag: " + entityTag );

        System.out.println( "Last Modified: " + lastModified );

    }

}

private String retrieveHeader( HttpMethod method, String name )

    throws HttpException {

    HeaderElement[] header = method.getResponseHeader("ETag").

        getElements( );

    String value = "";

    if(header.length > 0) {

        value = header[0].getName( );

    }

    return value;

}
}

```

[Example 11-1](#) requests the same page three times; the first request retrieves the content, and the second and third requests contain the headers for a conditional HTTP GET. Because the Apache homepage remains unchanged throughout this example, the content of <http://www.apache.org> is

retrieved only once. This example uses the headers in the first response to populate the *If-None-Match* and *If-Modified-Since* headers for the second and third requests:

Request 1. Get Method retrieved content.

Entity Tag: "2da794a-2d0d-998ebc80"

Last Modified: Wed, 14 Apr 2004 05:53:38 GMT

Request 2. Content not modified since last request

Request 3. Content not modified since last request

Discussion

This first request is similar to a regular HTTP GET, and if you examine the contents of the first request and response, you will see that the server's response contains two headers:

Last-Modified: Wed, 05 May 2004 02:51:59 GMT

ETag: "a06d2-76-829811c0"

[Example 11-1](#) takes the values of these two response headers and stores them in the `entityTag` and `lastModified` variables. When the next request is made, the values of these two variables are used to populate the conditional headers *If-None-Match* and *If-Modified-Since* in the `setHeaders()` method. These request headers are present in the second request for the same resource:

GET / HTTP/1.1

If-None-Match: "2da7807-31a8-e1eeb400"

If-Modified-Since: Tue, 11 May 2004 23:57:04 GMT

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: www.apache.org

When the server receives these conditional headers, it will check to see if the resource has been modified. If the resource has been modified, the resource will have a different modified date and different entity tag value. If the resource has not been modified, the server will respond to `HttpClient` with a `304 Not Modified` response code:

HTTP/1.1 304 Not Modified

Date: Sat, 15 May 2004 16:59:23 GMT

Server: Apache/2.0.49-dev (Unix)

ETag: "2da7807-31a8-e1eeb400"

Expires: Sun, 16 May 2004 16:59:23 GMT

Cache-Control: max-age=86400

The *ETag* header is known as an *entity tag*, and it is similar to a hash code for a resource served by a particular web server. Different servers have different algorithms for creating an *ETag* header; for example, the Apache HTTPD server has a configuration directive, which allows you to base an *ETag* on a configurable set of file attributes, such as size, i-node number, and modified time. Consider an *ETag* to be a unique identifier for a particular version of a resource; if this header changes, the corresponding resource has been altered.

See Also

Entity tags (the *ETag* header) are described in sections 3.11 and 14.19 of RFC 2616 (<http://www.zvon.org/tmRFC/RFC2616/Output/index.html>). The Apache HTTPD server can be configured to use different file attributes when creating an *ETag* header. For more information about configuring the Apache HTTPD server via the `FileETag` directive, see the documentation of Apache's core features (<http://httpd.apache.org/docs-2.0/mod/core.html#fileetag>).

Recipe 11.6 Debugging HTTP Communications

Problem

You need to see the low-level communications between the client and the server.

Solution

Set four `System` variables that control logging, and `HttpClient` will produce debugging statements dealing with environment information, SSL configuration information, and the raw data sent to and received from the server. The following example sets the four `System` properties that control `HttpClient` debugging output:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.methods.GetMethod;

String logging = "org.apache.commons.logging";

// Configure Logging

System.setProperty(logging + ".Log", logging + ".impl.SimpleLog");

System.setProperty(logging + ".logging.simplelog.showdatetime", "true");

System.setProperty(logging + ".simplelog.log.httpclient.wire", "debug");

System.setProperty(logging + ".simplelog.log.org.apache.commons.httpclient",

                    "debug");

HttpClient client = new HttpClient( );
```

```
String url = "http://www.discursive.com/jccook/";

HttpMethod method = new GetMethod( url );

client.executeMethod( method );

String response = method.getResponseBodyAsString( );

System.out.println( response );

method.releaseConnection( );

method.recycle( );
```

This code executes a simple `GetMethod` and produces the following debugging output, which contains environment information and a log of all data sent and received from the server:

```
HttpClient - -Java version: 1.4.2_04

HttpClient - -Java vendor: Sun Microsystems Inc.

HttpClient - -Java class path:

HttpClient - -Operating system name: Windows XP

HttpClient - -Operating system architecture: x86

HttpClient - -Operating system version: 5.1

HttpClient - -SUN 1.42: SUN (DSA key/parameter generation; DSA signing; SHA-1, \
    MD5 digests; SecureRandom; X.509 certificates; JKS keystore; \
    PKIX CertPathValidator; PKIX CertPathBuilder; LDAP, Collection \
    CertStores)

HttpClient - -SunJSSE 1.42: Sun JSSE provider(implements RSA Signatures, \
    PKCS12, SunX509 key/trust factories, SSLv3, TLSv1)

HttpClient - -SunRsaSign 1.42: SUN's provider for RSA signatures

HttpClient - -SunJCE 1.42: SunJCE Provider (implements DES, Triple DES, \
    AES, Blowfish, PBE, Diffie-Hellman, HMAC-MD5, HMAC-SHA1)

HttpClient - -SunJGSS 1.0: Sun (Kerberos v5)
```

```
HttpConnection - -HttpConnection.setSoTimeout(0)

HttpMethodBase - -Execute loop try 1

wire - ->> "GET /jccook/ HTTP/1.1[\r][\n]"

HttpMethodBase - -Adding Host request header

wire - ->> "User-Agent: Jakarta Commons-HttpClient/3.0final[\r][\n]"

wire - ->> "Host: www.discursive.com[\r][\n]"

wire - ->> "[\r][\n]"

wire - -<< "HTTP/1.1 200 OK[\r][\n]"

wire - -<< "Date: Thu, 06 May 2004 02:49:43 GMT[\r][\n]"

wire - -<< "Server: Apache/2.0.48 (Fedora)[\r][\n]"

wire - -<< "Last-Modified: Wed, 05 May 2004 02:51:37 GMT[\r][\n]"

wire - -<< "ETag: "a06d1-68-81486040"[\r][\n]"

wire - -<< "Accept-Ranges: bytes[\r][\n]"

wire - -<< "Content-Length: 104[\r][\n]"

wire - -<< "Content-Type: text/html; charset=UTF-8[\r][\n]"

HttpMethodBase - -Buffering response body

wire - -<< "<html>[\n]"

wire - -<< " <head>[\n]"

wire - -<< " <title>JCCook Example</title>[\n]"

wire - -<< " </head>[\n]"

wire - -<< " <body>[\n]"

wire - -<< " <h1>Hello World!</h1>[\n]"

wire - -<< " </body>[\n]"

wire - -<< "</html>"

HttpMethodBase - -Resorting to protocol version default close connection policy

HttpMethodBase - -Should NOT close connection, using HTTP/1.1.
```

```
<html>

<head>

  <title>JCCook Example</title>

</head>

<body>

  <h1>Hello World!</h1>

</body>

</html>
```

Discussion

The ability to see the communications between a browser and a server is a great diagnostic tool, and throughout this chapter, the wire protocol logging properties have been used to provide some insight into the inner workings of `HttpClient`. There were four `System` properties set in the previous example:

```
org.apache.commons.logging.simplelog.log.httpclient.wire
```

Setting this property to `debug` causes an `HttpClient` instance to print out all traffic sent to and received from a web server.

```
org.apache.commons.logging.simplelog.log.org.apache.commons.httpclient
```

Setting this property to `debug` configures `HttpClient` to print general debugging information. In the previous example, every line starting with `HttpClient` or `HttpMethodBase` is a debugging message configured by this setting.

```
org.apache.commons.logging.Log
```

Setting this property to `org.apache.commons.logging.impl.SimpleLog` configures `HttpClient` to log output to the console.

```
org.apache.commons.logging.simplelog.showdatetime
```

Setting this to `true` will cause the `SimpleLog` to print the date and time for every message.



Recipe 11.7 Making an HTTP POST Request

Problem

You need to supply parameters to a script or servlet using HTTP POST.

Discussion

Create a `PostMethod` and call `setParameter()` or `addParameter()` before you execute the method. The `PostMethod` will send a request with a *Content-Type* header of *application/x-www-form-urlencoded*, and the parameters will be sent in the request body. The following example demonstrates the use of `PostMethod` to send parameters:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.NameValuePair;

import org.apache.commons.httpclient.methods.PostMethod;

HttpClient client = new HttpClient( );

// Create POST method

String url = "http://www.discursive.com/cgi-bin/jccook/param_list.cgi";

PostMethod method = new PostMethod( url );

// Set parameters on POST

method.setParameter( "test1", "Hello World" );

method.addParameter( "test2", "This is a Form Submission" );

method.addParameter( "Blah", "Whoop" );
```

```
method.addParameter( new NameValuePair( "Blah", "Whoop2" ) );
```

```
// Execute and print response
```

```
client.executeMethod( method );
```

```
String response = method.getResponseBodyAsString( );
```

```
System.out.println( response );
```

```
method.releaseConnection( );
```

The *param_list.cgi* CGI script echoes all parameters received, and from the following output, you can see that three parameters were supplied to this script:

These are the parameters I received:

test1:

Hello World

test2:

This is a Form Submission

Blah:

Whoop

Whoop2

Discussion

The previous example sent the parameters in the request body. The request created by the previous example is shown below:

```
POST /cgi-bin/jccook/param_list.cgi HTTP/1.1[\r][\n]
```

```
User-Agent: Jakarta Commons-HttpClient/3.0final[\r][\n]
```

```
Host: www.discursive.com[\r][\n]
```

```
Content-Length: 72[\r][\n]
```

```
Content-Type: application/x-www-form-urlencoded[\r][\n]

[\r][\n]

test1=Hello+World&test2=This+is+a+Form+Submission&Blah=Whoop&Blah=Whoop2
```



This output was produced by turning on wire debugging for `HttpClient`, as described in Recipe 11.6.

The first line specifies the HTTP method, the request path, and the protocol. The second line identifies this client as `HttpClient Version 3.0`. The third line specifies the request host and is used by servers serving many different virtual hosts using one IP address. The fourth line states that the request body is exactly 72 bytes, and the *Content-Type* header defines the request body as being a series of URL-encoded parameters. The parameters are passed in one line as *name1=value1&name2=value&*, etc.

There are a few ways to specify parameters on a `PostMethod`. The most straightforward is to call `setParameter()` with two strings: the parameter name and parameter value. `setParameter()` will replace any existing parameter with the same name. If a parameter with the same name is already present in a `PostMethod`, `addParameter()` will add another value to an existing parameter; `addParameter()` also accepts two strings: the name and value. Alternatively, both methods can be called with a `NameValuePair` object that encapsulates the name and value of a parameter. The previous example sent two values for the parameter *Blah*, which were both added using `addParameter()`. The first was added with two string parameters, and the second was added using a `NameValuePair` object.

See Also

The POST method is defined in detail in Section 9.5 of RFC 2616 (<http://www.zvon.org/tmRFC/RFC2616/Output/index.html>).



Recipe 11.8 Sending POST Data from a File

Problem

You need to send the data from a file in an HTTP POST request.

Solution

Create a `PostMethod`, create a `File` object, and call `setRequestBody()` and `setRequestContentLength()` on the method before it is executed. The `PostMethod` will send a request with a *Content-Length* header, which reflects the size of the file sent in the request body. The following example demonstrates the use of `PostMethod` to send data from a file in a request body:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.methods.PostMethod;

HttpClient client = new HttpClient( );

// Create POST method

String weblintURL = "http://ats.nist.gov/cgi-bin/cgi.tcl/echo.cgi";

PostMethod method = new PostMethod( weblintURL );

File file = new File( "project.xml" );

method.setRequestBody( new FileInputStream( file ) );

method.setRequestContentLength( (int)file.length( ) );

// Execute and print response
```

```
client.executeMethod( method );

String response = method.getResponseBodyAsString( );

System.out.println( response );

method.releaseConnection( );
```

The previous example hits a CGI script, which echoes the contents of the request body. When this example is executed, the response body is printed with the contents of the file that was uploaded in an HTTP POST request.

Discussion

This recipe sets the request body of an HTTP POST directly by passing a `File` object to `method.setRequestBody()`. In addition to accepting a `File` object, `setRequestBody()` can accept an `InputStream` or a `String`. Any time a request body is populated, the *Content-Length* header must be set to reflect the size of the request body by calling `method.setRequestContentLength()`. The previous recipe sent parameters in an HTTP POST request body by calling `setParameter()` and `addParameter()`, and the *Content-Length* and *Content-Type* headers are automatically populated when the method is executed. In this example, the *Content-Type* header is not sent with the request as the content can be any arbitrary textual or binary data.

Recipe 11.9 Uploading Files with a Multipart POST

Problem

You need to upload a file or a set of files with an HTTP multipart POST.

Solution

Create a `MultipartPostMethod` and add `File` objects as parameters using `addParameter()` and `addPart()`. The `MultipartPostMethod` creates a request with a *Content-Type* header of *multipart/form-data*, and each part is separated by a boundary. The following example sends two files in an HTTP multipart POST:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.methods.MultipartPostMethod;

import org.apache.commons.httpclient.methods.multipart.FilePart;

HttpClient client = new HttpClient( );

// Create POST method

String weblintURL = "http://ats.nist.gov/cgi-bin/cgi.tcl/echo.cgi";

MultipartPostMethod method =

    new MultipartPostMethod( weblintURL );

File file = new File( "data", "test.txt" );

File file2 = new File( "data", "sample.txt" );

method.addParameter("test.txt", file );
```

```
method.addPart( new FilePart( "sample.txt", file2, "text/plain",  
"ISO-8859-1" ) );
```

```
// Execute and print response
```

```
client.executeMethod( method );
```

```
String response = method.getResponseBodyAsString( );
```

```
System.out.println( response );
```

```
method.releaseConnection( );
```

Two `File` objects are added to the `MultipartPostMethod` using two different methods. The first method, `addParameter()`, adds a `File` object and sets the file name to *test.txt*. The second method, `addPart()`, adds a `FilePart` object to the `MultipartPostMethod`. Both files are sent in the request separated by a part boundary, and the script echoes the location and type of both files on the server:

```
<h3>Form input</h3>
```

```
<pre>
```

```
sample.txt = /tmp/CGI14480.4 sample.txt {text/plain; charset=ISO-8859-1}
```

```
test.txt = /tmp/CGI14480.2 test.txt {application/octet-stream;
```

```
charset=ISO-8859-1}
```

```
</pre>
```

Discussion

Adding a part as a `FilePart` object allows you to specify the Multipurpose Internet Main Extensions (MIME) type and the character set of the part. In this example, the *sample.txt* file is added with a *text/plain* MIME type and an *ISO-8859-1* character set. If a `File` is added to the method using `addParameter()` or `setParameter()`, it is sent with the default *application/octet-stream* type and the default *ISO-8859-1* character set.

When `HttpClient` executes the `MultipartPostMethod` created in the previous example, the following request is sent to the server. The *Content-Type* header is *multipart/form-data*, and an arbitrary *boundary* is created to delineate multiple parts being sent in the request:


```
POST /cgi-bin/cgi.tcl/echo.cgi HTTP/1.1

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: ats.nist.gov

Content-Length: 498

Content-Type: multipart/form-data; boundary=-----31415926535

8979323846

-----314159265358979323846

Content-Disposition: form-data; name=test.txt; filename=test.txt

Content-Type: application/octet-stream; charset=ISO-8859-1

Content-Transfer-Encoding: binary


This is a test.

-----314159265358979323846

Content-Disposition: form-data; name=sample.txt; filename=sample.txt

Content-Type: text/plain; charset=ISO-8859-1

Content-Transfer-Encoding: binary


This is a sample

-----314159265358979323846--
```

Each part contains a *Content-Disposition* header to name the part and a *Content-Type* header to classify the part with a MIME type and character set.

See Also

RFC 1867 (form-based file upload in HTML defines a multipart POST) can be found at <http://www.zvon.org/tmRFC/RFC1867/Output/index.html>. Each part is sent using MIME, which is described in RFC 2045, Multipurpose Internet Mail Extensions (MIME) Part One: Format of Internet Message Bodies (<http://www.zvon.org/tmRFC/RF2045/Output/index.html>).



Recipe 11.10 Basic Authentication

Problem

You need to access information protected by HTTP Basic Authentication.

Solution

Create a `UsernamePasswordCredentials` object with a username and password. Add this `Credentials` object to the instance of `HttpState` associated with an `HttpClient` object. `HttpClient` will attempt to execute a message, and the server will respond with `401` response code; `HttpClient` will then retry the request with the appropriate *Authorization* header. The following example uses a `UsernamePasswordCredentials` object to access a protected resource:

```
import org.apache.commons.httpclient.Credentials;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.UsernamePasswordCredentials;

import org.apache.commons.httpclient.methods.GetMethod;


HttpClient client = new HttpClient( );

HttpState state = client.getState( );


// Set credentials on the client

Credentials credentials =

    new UsernamePasswordCredentials( "testuser", "crazypass" );

state.setCredentials( null, null, credentials );
```

```
String url = "http://www.discursive.com/jccook/auth/";

HttpMethod method = new GetMethod( url );

client.executeMethod( method );

String response = method.getResponseBodyAsString( );

System.out.println( response );

method.releaseConnection( );
```

This example executes a `GetMethod`, the server requests credentials, and the credentials are sent to the server. The final response is:

```
<html>

  <head>

    <title>Secure JCCook Example</title>

  </head>

  <body>

    <h1>Hello Secure World!</h1>

  </body>

</html>
```

Discussion

The previous example added a `UsernamePasswordCredentials` object to the `HttpState` with a `null` authentication realm and a `null` host; this makes the supplied `UsernamePasswordCredentials` object the default instance to use for all authentication realms and hosts. The requests and response created by this example demonstrate the inner-workings of `HttpClient`, which sent the following request when the `GetMethod` was executed:

```
GET /jccook/auth/ HTTP/1.1

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: www.discursive.com
```


The server then responds with a `401` response code, telling the client that authorization is required. The *WWW-Authenticate* header specifies that the server is expecting Basic authentication, and the authentication realm is *jccook realm*.

```
HTTP/1.1 401 Authorization Required

Date: Fri, 14 May 2004 20:40:59 GMT

Server: Apache/2.0.48 (Fedora)

WWW-Authenticate: Basic realm="jccook realm"

Content-Length: 487

Content-Type: text/html; charset=iso-8859-1

DOCTYPE HTML PUBLIC "-//IETF//DTD HTML 2.0//EN">

<html><head>

title>401 Authorization Required</title>

</head><body>

.... error message ....
```

The server did not return the information needed, and another request needs to be made, sending the credentials in an *Authorization* request header. Since the initial request was made with *HTTP/1.1*, the connection is not closed after the response, and a second request will be sent over the same connection. This second request is the same as the first request except for an *Authorization* header. `HttpClient` looked at the associated `HttpState` object and located the appropriate `Credentials` object to use to create the *Authorization* header:

```
GET /jccook/auth/ HTTP/1.1

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: www.discursive.com

Authorization: Basic dGVzdHVzZXI6Y3JhenlwYXNz
```

Finally, the server replies with a `200` response code and the content of the requested resource:

```
HTTP/1.1 200 OK

Date: Fri, 14 May 2004 20:40:59 GMT

Server: Apache/2.0.48 (Fedora)
```

Last-Modified: Wed, 05 May 2004 02:51:59 GMT

ETag: "a06d2-76-829811c0"

Accept-Ranges: bytes

Content-Length: 118

Content-Type: text/html; charset=UTF-8

```
<html>

  <head>

    <title>Secure JCCook Example</title>

  </head>

  <body>

    <h1>Hello Secure World!</h1>

  </body>

</html>
```

`HttpClient` waits for the server to send back a *401* response code before sending the appropriate credentials. If you are accessing a resource, which is known to be protected by authentication, you can configure the `HttpState` object to send credentials preemptively, obviating the need for the client to react to a *401* response code. In other words, the *Authorization* header is supplied in the initial request. To configure `HttpClient` to send credentials preemptively, retrieve an `HttpClientParams` object from `HttpClient` via the `getParams()` method, and call `setAuthenticationPreemptive(true)` as follows:

```
HttpClientParams params = client.getParams( );
```

```
params.setAuthenticationPreemptive( true );
```

Basic authentication involves sending an unencrypted password in the request. The value of the *Authorization* header in the request is simply `testuser:crazypass` sent through a `Base64` encoding utility. If you are working on a system that uses Basic authentication, make sure that any system that performs authentication does so over *SSL*; otherwise, your password will fall into the wrong hands.

See Also

If you want to convince someone that using Basic authentication without encryption is a bad idea, download the network protocol analyzer [Ethereal](http://www.ethereal.com/) (<http://www.ethereal.com/>), and capture some network traffic. Identify an *Authorize* header and run the value through a Base64 decoder (<http://www.securitystats.com/tools/base64.php>). Create a custom T-shirt or coffee mug with your friend's username and password, and present it to him as a gift.





Recipe 11.11 NTLM Authentication

Problem

You need to access a resource that is protected by Microsoft's NTLM authentication protocol.

Solution

Create an instance of `NTCredentials` with a username, password, host, and domain, and call `setCredentials()` on the `HttpState` associated with an instance of `HttpClient`. The following example demonstrates the use of `NTCredentials` to access a resource on host *test.windowsmachine.com*, which is on the domain *TESTDOM*.

```
import org.apache.commons.httpclient.Credentials;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpState;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.NTCredentials;

import org.apache.commons.httpclient.methods.GetMethod;

HttpClient client = new HttpClient( );

// Set credentials on the client

Credentials credentials =

    new NTCredentials( "testuser", "crazypass",

                      "homecomputer ", "TESTDOM" );

HttpState state = client.getState( );
```



```
state( ).setCredentials( null, null, credentials );
```

```
String url = "http://webmail.domain.biz/exchange/";
```

```
HttpMethod method = new GetMethod( url );
```

```
client.executeMethod( method );
```

```
String response = method.getResponseBodyAsString( );
```

```
System.out.println( response );
```

```
method.releaseConnection( );
```

Discussion

The parameters to the constructor of `NTCredentials` are the username, the password, a hostname, and a domain. The hostname is the name of the machine making the request, and, in this case, the third parameter is *homecomputer*. When this `Credential` object is set in the `HttpState` object, the first two parameters specify the authentication realm and the host to apply a `Credential` object to. The previous example sets both the authentication realm and the host to `null`; this makes the `NTCredentials` object the default `Credentials` to use if there is no realm or host specified. If we were using one instance of `HttpClient` to connect to two different hosts with two different `NTCredentials` objects, both `Credentials` objects could be added to `HttpState` with the following code:

```
HttpClient client = new HttpClient( );
```

```
Credentials credentials1 =
```

```
    new NTCredentials( "testuser", "crazypass",  
                      "homecomputer", "TESTDOM" );
```

```
Credentials credentials2 =
```

```
    new NTCredentials( "anotheruser", "password2",  
                      "homecomputer", "DIFFERENT_DOMAIN" );
```

```
HttpState state = client.getState( );

state( ).setCredentials( null, "webmail.domain.biz", credentials1 );

state( ).setCredentials( null, "silly-iis-server.lame.net", credentials2 );


// Execute a request which uses credentials1

String url = "http://webmail.domain.biz/exchange/";

HttpMethod method = new GetMethod( url );

client.executeMethod( method );


// Execute a request which uses credentials2

String url2 = "http://silly-iis-server.lame.net/test/";

HttpMethod method2 = new GetMethod( url2 );

client.executeMethod( method2 );
```

The host *webmail.domain.biz* tries to authenticate the first request against the *TESTDOM* domain, and the *silly-iis-server.lame.net* host tries to authenticate the second request against the *DIFFERENT_DOMAIN* domain. Since the `HttpState` is configured with two separate `Credentials` objects for different hosts, both requests are successfully authenticated.

See Also

No one will dispute the assertion that the HTTP protocol has dramatically changed the world we live in, and one of the reasons for this success is the openness of the protocol. Unfortunately, NTLM is proprietary and undocumented, and this is reason enough to avoid using it entirely. If you are stuck with NTLM and you want to learn more about the protocol, it is described in excruciating detail at <http://www.innovation.ch/java/ntlm.html> and <http://davenport.sourceforge.net/ntlm.html>.



Recipe 11.12 Working with Cookies

Problem

You need to work with a system that uses cookies to store state, and you need to be able to set cookies as well as keep track of cookies set by the server.

Solution

`HttpClient` handles cookies automatically. If you need to keep track of a cookie set by the server, simply use the same instance of `HttpClient` for each request in a session. If you need to set a cookie, create an instance of `Cookie`, and add it to `HttpState`. The following example sends a `Cookie` to the server:

```
import java.io.IOException;

import org.apache.commons.httpclient.Cookie;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.methods.GetMethod;

HttpClient client = new HttpClient( );

System.out.println( "Making Request without Cookie: " );

makeRequest(client);

System.out.println( "Making Request with Cookie: " );

Cookie cookie = new Cookie(".discursive.com", "test_cookie",

                           "hello", "/", null, false );
```

```
client.getState( ).addCookie( cookie );

makeRequest(client);

private static void makeRequest(HttpClient client)

    throws IOException, HttpException {

    String url = "http://www.discursive.com/cgi-bin/jccook/cookie_test.cgi";

    HttpMethod method = new GetMethod( url );

    client.executeMethod( method );

    String response = method.getResponseBodyAsString( );

    System.out.println( response );

    method.releaseConnection( );

    method.recycle( );

}
```

This example hits a CGI script that tests for the presence of a cookie named *test_cookie*. One request is made without the cookie and another request is made with the cookie. The following output is produced:

Making Request without Cookie:

```
<h1>test_cookie NOT PRESENT</h1>
```

Making Request with Cookie:

```
<h1>test_cookie PRESENT</h1 >
```

Discussion

Cookies are used by a number of application servers to manage user sessions; *JSESSIONID* cookies are used by most J2EE application servers and servlet containers to keep track of a session. Because `HttpClient` automatically handles cookies, if a server sets a cookie, it will be added to the `HttpState` instance associated with `HttpClient`. If you need to get a list of cookies associated with an `HttpState`, call `getCookies()` to obtain an array of `Cookie` objects. The following code retrieves an array of `Cookie` objects, printing the `domain`, `path`, `name`, and `value` of each `Cookie`:


```

HttpClient client = new HttpClient( );

// execute some methods...

Cookie[] cookies = client.getState( ).getCookies( );

for( int i = 0; i < cookies; i++ ) {

    Cookie cookie = cookies[i];

    String domain = cookie.getDomain( );

    String path = cookie.getPath( );

    String name = cookie.getName( );

    String value = cookie.getValue( );

    System.out.println( "Cookie: " + domain + ", " + path + ", " +

                        name + ", " + value );

}

```

There are two different approaches to cookies floating around the internet: Netscape Draft Specification and RFC 2109. Some servers use the Netscape Draft and others use RFC 2109; because of this, HttpClient offers a **COMPATIBILITY** mode that should work with most servers. The default cookie policy for HttpClient is the **RFC_2109** policy. If you are having problems with cookies, change the cookie policy to the **COMPATIBILITY** policy, which is a public static **int** in the **CookiePolicy** class. To change the cookie policy, call **setCookiePolicy()** on the **HttpState** associated with **HttpClient**, as follows:

```

HttpClient client = new HttpClient( );

// To use a Compatability policy

client.getState( ).setCookiePolicy(CookiePolicy.COMPATIBILITY);

// To use a Netscape Draft policy

client.getState( ).setCookiePolicy(CookiePolicy.NETSCAPE_DRAFT);

```

```
// To use a RFC 2109 policy - this is the default

client.getState( ).setCookiePolicy(CookiePolicy.RFC2109);
```

There is also a third approach-outlined in RFC 2965-which supercedes RFC 2109. However, there is no code-level support for this third approach in commons yet.

See Also

The original cookie specification was written by Netscape, and it can be found at http://wp.netscape.com/newsref/std/cookie_spec.html. RFC 2109 (HTTP State Management Mechanism) is available at <http://www.zvon.org/tmRFC/RFC2109/Output/>, and the newer RFC 2965 (HTTP State Management Mechanism) can be found at <http://www.zvon.org/tmRFC/RFC2965/Output/>. Currently, HttpClient does not support the RFC 2965 standard.



Recipe 11.13 Handling Redirects

Problem

You need to access a server that may send an arbitrary number of redirects.

Solution

Before executing an `HttpMethod` call, `setFollowRedirects(true)` on the method; `HttpClient` will take care of following any redirects a server may return in a response. The following example shows what happens when a method requests a CGI script that returns a `302` (moved temporarily) response code:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.methods.GetMethod;

HttpClient client = new HttpClient( );

String url = "http://www.discursive.com/cgi-bin/jccook/redirect.cgi";

System.out.println( "Executing Method not following redirects: " );

HttpMethod method = new GetMethod( url );

method.setFollowRedirects( false );

executeMethod(client, method);

System.out.println( "Executing Method following redirects: " );

method = new GetMethod( url );
```

```
method.setFollowRedirects( true );

executeMethod(client, method);

private static void executeMethod(HttpClient client, HttpMethod method)

    throws IOException, HttpException {

    client.executeMethod( method );

    System.out.println( "Response Code: " + method.getStatusCode( ) );

    String response = method.getResponseBodyAsString( );

    System.out.println( response );

    method.releaseConnection( );

    method.recycle( );

}
```

This example executes two `GetMethod` instances; the first method is configured not to follow redirects, and the second is configured to follow redirects. The first method is executed, and the server sends a `302` response code. Since this method is not configured to follow redirects, `HttpClient` does not make another request. When the second method is executed, `HttpClient` follows the initial redirect to a `redirect2.cgi` script, which sends another redirect to `/jccook/index.html`.

Executing Method not following redirects:

```
0      INFO  [main] org.apache.commons.httpclient.HttpMethodBase      - Redirect
requested but followRedirects is disabled

Response Code: 302
```

Executing Method following redirects:

```
Response Code: 200

<html>

  <head>

    <title>JCCook Example</title>
```



```
</head>

<body>

  <h1>Hello World!</h1>

</body>

</html>
```

Discussion

`HttpClient` can handle any of the following response codes specifying a redirect:

- Status Code 302: `HttpStatus.SC_MOVED_TEMPORARILY`
- Status Code 301: `HttpStatus.SC_MOVED_PERMANENTLY`
- Status Code 303: `HttpStatus.SC_SEE_OTHER`
- Status Code 307: `HttpStatus.SC_TEMPORARY_REDIRECT`

When a response code is retrieved, `HttpClient` sends another GET request for the resource specified in the *Location* header. The following code is the first request sent by a method configured to follow redirects:

```
GET /cgi-bin/jccook/redirect.cgi HTTP/1.1

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: www.discursive.com
```

The *redirect.cgi* script will then send a 302 *Moved* response, supplying a *Location* header that points to *redirect2.cgi*:

```
HTTP/1.1 302 Moved

Date: Sat, 15 May 2004 19:30:49 GMT

Server: Apache/2.0.48 (Fedora)

Location: /cgi-bin/jccook/redirect2.cgi

Content-Length: 0

Content-Type: text/plain; charset=UTF-8
```

`HttpClient` then sends another GET request for the resource specified in the previous response:

```
GET /cgi-bin/jccook/redirect2.cgi HTTP/1.1

User-Agent: Jakarta Commons-HttpClient/3.0final

Host: www.discursive.com
```

The *redirect2.cgi* is configured to send a redirect for */jccook/index.html*, and the response to the previous request does just that:

```
HTTP/1.1 302 Moved

Date: Sat, 15 May 2004 19:30:49 GMT

Server: Apache/2.0.48 (Fedora)

Location: /jccook/index.html

Content-Length: 0

Content-Type: text/plain; charset=UTF-8
```

How `HttpClient` handles redirect responses can be further customized by three configurable parameters on `HttpClient`. `REJECT_RELATIVE_REDIRECT` causes `HttpClient` to throw an exception if a server sends a *Location* header with a relative URL; for instance, if the *redirect.cgi* script returns a *Location* header of *../index.html*, the redirection causes an exception if `REJECT_RELATIVE_REDIRECT` is set to `true`. If `ALLOW_CIRCULAR_REDIRECTS` is set to `true`, `HttpClient` throws an exception if a series of redirects includes the same resources more than once. `MAX_REDIRECTS` allows you to specify a maximum number of redirects to follow. The following example sets all three parameters on an instance of `HttpClientParams` associated with an instance of `HttpClient`:

```
HttpClient client = new HttpClient( );

HttpClientParams params = client.getParams( );

params.setBooleanParameter( HttpClientParams.REJECT_RELATIVE_REDIRECT, false );

params.setBooleanParameter( HttpClientParams.ALLOW_CIRCULAR_REDIRECTS, false );

params.setIntParameter( HttpClientParams.MAX_REDIRECTS, 10 );
```

See Also

For more information on how `HttpClient` handles redirection, take a look at the source for the `HttpMethodDirector`. The `isRedirectNeeded()` and `processRedirectResponse()` methods handle redirection, and the source for this class can be viewed using ViewCVS

(<http://cvs.apache.org/viewcvs.cgi/jakarta-commons/httpclient/src/java/>). Navigate to the `org.apache.commons.httpclient` package and click on `HttpMethodDirector`.





Recipe 11.14 SSL

Problem

You need to execute a method using HTTP over Secure Sockets Layer (SSL).

Solution

If you are working with a server that has a certificate signed by a certificate authority included in the Java Secure Socket Extension (JSSE), `HttpClient` automatically handles HTTP over SSL; just use a URL that starts with *https*. The following example retrieves Amazon.com's sign-in page using HTTP over SSL:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.methods.GetMethod;

HttpClient client = new HttpClient( );

String url = "https://www.amazon.com/gp/flex/sign-in.html";

HttpMethod method = new GetMethod( url );

client.executeMethod( method );

String response = method.getResponseBodyAsString( );

System.out.println( response );

method.releaseConnection( );
```



```
method.recycle( );
```

This example executes a simple `GetMethod` constructed with a URL starting with *https*. The output of this example is:

```
0    WARN  [main] org.apache.commons.httpclient.HttpMethodBase    - Response
content length is not known

297  WARN  [main] org.apache.commons.httpclient.HttpMethodBase    - Response
content length is not known

<html>

<head><title>Amazon.com Sign In</title>

</head>

..... Content .....

</html>
```

Discussion

HttpClient handles SSL automatically, if it can verify the authenticity of a certificate against an authority; this is why this recipe is so similar to [Recipe 11.3](#). The example in this recipe only works if you are dealing with a site that has a certificate signed by a well-known authority. The Java Runtime Environment (JRE) keeps track of the signatures of all the known certificate authorities in a file named *cacerts*. *cacerts* can be found in *\${JAVA_HOME}/jre/lib/security/cacerts*, it is an archive that has a default password of `changeit`. For a list of certificate authorities in Java, execute the following command line and supply the default password:

```
keytool -list -keystore C:\j2sdk1.4.2_04\jre\lib\security\cacerts
```

The list will contain certificate fingerprints for Thawte, Entrust, Verisign, and other commercial certificate authorities. If you wish to use the JSSE without having to write your own `ProtocolSocketFactory`, you need to obtain a certificate signed by an authority.

See Also

If you need to work with a self-signed certificate, see the next recipe.



Recipe 11.15 Accepting a Self-Signed Certificate

Problem

You need to work with a server that is using a self-signed certificate.

Solution

Provide a custom `SSLProtocolSocketFactory` that is configured to trust your self-signed certificate. A sample implementation of `SSLProtocolSocketFactory` named `EasySSLProtocolSocketFactory` is available via HttpClient's CVS repository, and the following example uses it to trust a self-signed certificate:

```
import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.HttpMethod;

import org.apache.commons.httpclient.contrib.ssl.EasySSLProtocolSocketFactory;

import org.apache.commons.httpclient.methods.GetMethod;

import org.apache.commons.httpclient.protocol.Protocol;

HttpClient client = new HttpClient( );

String url = "https://pericles.symbiont.net/jccook";

ProtocolSocketFactory socketFactory =

    new EasySSLProtocolSocketFactory( );

Protocol https = new Protocol( "https", socketFactory, 443);

Protocol.registerProtocol( "https", https );
```

```
HttpMethod method = new GetMethod( url );

client.executeMethod( method );

String response = method.getResponseBodyAsString( );

System.out.println( response );

method.releaseConnection( );

method.recycle( );
```

This executes and accepts the self-signed certificate from *pericles.symbiont.net*.

Word up, this page was served using SSL!

Discussion

`EasySSLProtocolSocketFactory` and `EasyX509TrustManager` can be obtained from HttpClient's CVS in the *src/contrib* directory. If you do not want to checkout the source code from CVS, you can also obtain these two classes from ViewCVS on *cv.s.apache.org*. HttpClient's CVS repository can be accessed at <http://cv.s.apache.org/viewcvs.cgi/jakarta-commons/httpclient/>, and the two classes are in the *src/contrib/org/apache/commons/httpclient/contrib/ss* directory. To use these classes, you must integrate them into your own project, customizing the behavior of these classes as you see fit.

`EasySSLProtocolSocketFactory` uses the `EasyX509TrustManager` to validate a certificate. To customize the criteria for certificate acceptance and alter the implementation of `EasyX509TrustManager`. For example, if you only want to accept a certificate from a specific hostname, change the implementation of the `isServerTrusted()` method in `EasyX509TrustManager`.

See Also

In the same package as `EasySSLProtocolSocketFactory` and `EasyX509TrustManager` is an implementation of `SSLProtocolSocketFactory` named `StrictSSLProtocolSocketFactory`, which makes sure that the hostname of the SSL server matches the hostname of the SSL certificate. For more information, go to HttpClient's CVS repository (<http://cv.s.apache.org/viewcvs.cgi/jakarta-commons/httpclient/>) and download `StrictSSLProtocolSocketFactory` from this *src/contrib/org/apache/commons/httpclient/contrib/ss* directory.

Recipe 11.16 Obtaining Jakarta Slide

Problem

You need to use Jakarta Slide to access a Web-based Distributed Authoring and Versioning (WebDAV) resource.

Solution

Download the Jakarta Slide 2.0 WebDAV client, and place the appropriate JAR files in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Jakarta Slide 2.0-2.0 client *zip* instead of Commons Lang.

Jakarta Slide 2.0 WebDAV client depends on Jakarta Commons Logging and Jakarta HttpClient. These dependencies are included in the binary distribution, and once you unpack the archive, they should be available in the *lib* directory. The archive *jakarta-slide-webdavclient-bin-2.0.zip* will contain a JAR file named *jakarta-slide-webdavclient-2.0.jar*; add this JAR and the dependencies to your classpath, and you will be ready to use Jakarta Slide to access WebDAV resources.

Discussion

WebDAV, defined in RFC 2518, is an extension of HTTP/1.1, which supports distributed and collaborative authoring of content. Using a WebDAV client you can read, modify, copy, move, lock, and unlock resources, and you can read, enumerate, and modify properties associated with resources and collections of resources. Resources made available with WebDAV can be mounted as filesystems in Windows XP/2000, Mac OS X, and Linux, and the DAV protocol can be thought of as defining a filesystem built on top of HTTP/1.1. The WebDAV protocol is at the core of a number of distributed version control and content management systems.

Jakarta Slide extends Jakarta HttpClient implementing `HttpMethod` for the methods introduced by the WebDAV protocol. For example, the `LockMethod` in the `org.apache.webdav.lib.methods` package is an instance of `HttpMethod` from Jakarta HttpClient, and just as WebDAV is an extension of HTTP/1.1, Jakarta Slide is an extension of Jakarta HttpClient. When dealing with authentication, cookie management, or redirects, you can configure Jakarta Slide the same way you would configure Jakarta HttpClient; to use Slide, you must create an instance of `HttpClient`.

See Also

For more information about the Jakarta Slide project, see the project page at

<http://jakarta.apache.org/slide>.

It is far beyond the scope of this book to fully describe WebDAV, and attempting to do so in one or two recipes would not do it justice. WebDAV, like the protocol it extends, has the potential to transform the way people think about content creation, file sharing, and version control. To learn more about WebDAV, see the following resources:

- RFC 2518 (HTTP Extensions for Distributed Authoring-WEBDAV) at <http://www.zvon.org/tmRFC/RFC2518/Output/index.html>.
- <http://www.webdav.org> is a hub for the WebDAV community. If you are interested in learning about WebDAV and a number of related specifications, see <http://www.webdav.org/specs/>. For a list of software products that support WebDAV, see <http://www.webdav.org/projects/>.
- Subversion is a great replacement for CVS from the Tigris community. You can configure Apache 2.0 to expose a Subversion repository via the WebDAV/DeltaV protocol using mod_dav_svn. For more information about Subversion and mod_dav_svn, see <http://subversion.tigris.org> or *Version Control with Subversion* by Ben Collins-Sussman, Brian W. Fitzpatrick, and C. Michael Pilato (O'Reilly).

If you would like to set up your own WebDAV resource, I recommend installing the Apache HTTP Server with mod_dav. More information about installing "The Number One HTTP Server on the Internet" can be found at <http://httpd.apache.org/>. Information about configuring mod_dav can be found at http://httpd.apache.org/docs-2.0/mod/mod_dav.html. The Jakarta Tomcat 5.0 distribution is bundled with a web application that exposes a resource using a WebDAV servlet. To download and install Jakarta Tomcat 5.0, see <http://jakarta.apache.org/tomcat/>.

Recipe 11.17 Connecting to WebDAV Resources

Problem

You need to connect to a WebDAV resource and list the contents of a collection. As with most WebDAV resources, you need to supply authentication information.

Solution

Create an instance of `WebdavResource`, passing in a URL and a `UsernamePasswordCredential` object. List the contents of a WebDAV collection by calling the `listWebdavResources()` method. The following example demonstrates the use of `WebdavResource` to list the contents of a WebDAV collection:

```
import org.apache.commons.httpclient.Credentials;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.UsernamePasswordCredentials;

import org.apache.commons.lang.StringUtils;

import org.apache.commons.lang.time.FastDateFormat;

import org.apache.webdav.lib.WebdavResource;

HttpClient client = new HttpClient();

String url = "http://www.discursive.com/jccook/dav/";

Credentials credentials =

    new UsernamePasswordCredentials("davuser", "davpass");

// List resources in top directory
```

```
WebdavResource resource = new WebdavResource(url, credentials);

WebdavResource[] resources = resource.listWebdavResources( );

System.out.println( "type    name                size    type" +
                    "                modified");

System.out.println( "-----" +
                    "-----");

for( int i = 0; i < resources.length; i++ )    {

    WebdavResource item = resources[i];

    String type;

    if( item.isCollection( ) ) {

        type = "dir";

    } else {

        type = "file";

    }

    System.out.print( StringUtils.rightPad( type, 6 ) );

    System.out.print( StringUtils.rightPad( item.getName( ), 15 ) );

    System.out.print( StringUtils.rightPad( item.getGetContentLength( )
+ "", 8 ) );

    System.out.print( StringUtils.rightPad( item.getGetContentType( ),
23 ) );

    Date lastMod = new Date( item.getGetLastModified( ) );

    System.out.print(

        StringUtils.rightPad(

            FastDateFormat.getInstance( ).format( lastMod ), 25 ));

    System.out.print( "\n" );

}
```

The program connects to a WebDAV resource using the credentials supplied to the constructor of `WebdavResource`. It lists the contents of a collection and produces the following output:

type	name	size	type	modified

file	test.html	14	text/html	5/6/04 12:16 AM
file	index.html	14	text/html	5/5/04 11:59 PM
dir	test	0	httpd/unix-directory	5/6/04 12:01 AM

Discussion

Jakarta Slide is built on top of Jakarta HttpClient, but you will notice that this recipe did not involve the execution of an `HttpMethod`. This is because `WebdavResource` manages the complexity of working with an instance of `HttpClient` behind the scenes. The only trace of `HttpClient` is the `UsernamePasswordCredentials` object that is passed to the constructor of `WebdavResource`. Because Jakarta Slide is built on top of Jakarta HttpClient, almost any feature of Jakarta HttpClient translates directly to Jakarta Slide. If you need to access a WebDAV repository over SSL with a self-signed certificate, or if you need to alter the cookie policy, you can use the same facilities that are available to you when you are using `HttpClient` directly.

Recipe 11.18 Modifying a WebDAV Resource

Problem

You need to modify a WebDAV resource.

Solution

Use the `putMethod()` on `WebdavResource`, and be sure to lock and unlock the resource before and after modification. The following example demonstrates the use of `lockMethod()`, `putMethod()`, and `unlockMethod()` to modify a resource:

```
import org.apache.commons.httpclient.Credentials;

import org.apache.commons.httpclient.HttpClient;

import org.apache.commons.httpclient.HttpException;

import org.apache.commons.httpclient.UsernamePasswordCredentials;

import org.apache.webdav.lib.WebdavResource;

String url = "http://www.discursive.com/jccook/dav/test.html";

Credentials credentials =

    new UsernamePasswordCredentials("davuser", "davpass");

// List resources in top directory

WebdavResource resource = new WebdavResource(url, credentials);

// Lock the Resource for 100 seconds

boolean locked = resource.lockMethod( "tobrien", 100 );
```

```
if( locked ) {

    try {

        // Read content as a String

        String resourceData = resource.getMethodDataAsString( );

        // Modify a resource

        System.out.println( "*** Modifying Resource" );

        resourceData = resourceData.replaceAll( "test", "modified test" );

        resource.putMethod( resourceData );

    } finally {

        // Unlock the resource

        resource.unlockMethod( );

    }

}

// Close the resource

resource.close( );
```

Discussion

`lockMethod()` accepts an owner and a timeout; the owner is the owner of the lock, and the timeout is the timeout of the lock in number of seconds. When locking a resource, the `lockMethod()` will return a `boolean` value: `true` if the lock was granted and `false` if the lock was not granted. The `resource.putMethod()` was called with a `String` object, but it can also be invoked when a `byte[]`, `InputStream`, or `File`. `putMethod()` returns a `boolean` value: `true` if the put was successful; otherwise, `false`. The `unlockMethod()` unlocks the resource and makes it available for other clients to lock, modify, and unlock.

See Also

Section 7 of RFC 2518 (HTTP Extensions for Distributed Authoring-WEBDAV) discusses the various

types of write locks available in WebDAV. This RFC is available at <http://www.zvon.org/tmRFC/RFC2518/Output/chapter7.html>.

The Slide recipes in this chapter are only meant as a brief introduction to WebDAV. If you would like to learn more about how to work with properties, create collections, and search a WebDAV repository, please see the Jakarta Slide project page at <http://jakarta.apache.org/slide>.

PREV

< Day Day Up >



Chapter 12. Searching and Filtering

[Introduction](#)

[Recipe 12.1. Obtaining Commons JXPath](#)

[Recipe 12.2. Querying an Object Graph with XPath](#)

[Recipe 12.3. Search a Collection of Simple Objects](#)

[Recipe 12.4. Applying XPath Queries to Complex Object Graphs](#)

[Recipe 12.5. Obtaining Jakarta Lucene](#)

[Recipe 12.6. Creating an Index of XML Documents](#)

[Recipe 12.7. Searching for a Specific Term in a Document Index](#)

[Recipe 12.8. Finding the Frequency of Terms in an Index](#)



Introduction

XPath is a popular way to select nodes from an XML document. If you are working with a single XML document or a series of XML documents in an XML Database- such as Apache Xindice-XPath is used to query, address, and filter XML content. Jakarta Commons XPath allows you to use an XPath query to address objects in a collection or properties of a bean. XPath is an unconventional application of an XML standard to Java objects, which allows you to quickly select objects from a `Collection` without the need for an `Iterator` and a comparison. For example, if you had a `List` of `Person` objects with an `age` property, you could select all of the people older than 10 by passing the expression `/person[@age > 10]` to a `JXPathContext`. XPath implements a large subset of the XPath specification, and XPath expressions can be applied to a wide array of objects, beans, Document Object Model (DOM) Documents, collections, and maps. This chapter shows you how to use Commons XPath to search and filter objects in a collection.

A system will frequently need to search for and identify occurrences of text in a large set of documents. To accomplish this, you will use a tool, such as Jakarta Lucene, to create a searchable index of terms. For example, if you've used an IDE, such as Eclipse, you may find yourself searching for all of the occurrences of the text "testVariable" in your workspace. Eclipse can quickly perform any number of complex searches, and when it does, it is using Jakarta Lucene to index and search every file. Jakarta Lucene is a very efficient search engine that can be used to search a set of documents for terms and phrases and analyze the frequency of terms within a set of documents. Lucene offers a complex query syntax, which allows for compound queries and term matching using proximity and wildcards. This chapter combines Lucene with Commons Digester to create a tool to search a set of XML documents.

Recipe 12.1 Obtaining Commons XPath

Problem

You need to use Jakarta Commons XPath to select objects from a `Collection` using XPath syntax.

Solution

You must download the latest version of Commons XPath, and place the Commons XPath JAR in your project's classpath. Following the steps outlined in [Recipe 1.1](#), download Commons XPath 1.2 instead of Commons Lang.

Discussion

Commons XPath provides a mechanism for evaluating XML Path Language (XPath) expressions against objects and various data structures in Java. This unconventional application of XPath to objects enables a developer to traverse, address, and filter specific nodes or locations in a complex object graph. This chapter details a few of the ways in which XPath can be used to search, select, and filter objects.

If you have a Maven project that needs to use Commons XPath, add a dependency on Commons XPath 1.2 with the following section in *project.xml*:

```
<dependencies>

    <dependency>

        <id>commons-jxpath</id>

        <version>1.2</version>

    </dependency>

    ....other dependencies...

</dependencies>
```

See Also

For more information about Commons XPath, see the Commons XPath project page at <http://jakarta.apache.org/commons/jxpath>. For more information about XPath, see the official W3C XPath recommendation at <http://www.w3.org/TR/xpath>.

Recipe 12.2 Querying an Object Graph with XPath

Problem

You need to retrieve nested bean properties using an XPath expression. You need to perform an XPath query on an object graph.

Solution

Use Commons JXPath to evaluate an XPath expression against an object graph. JXPath treats nested bean properties as if they were nested elements in an XML document; using JXPath, the expression *a/b/c* is the equivalent of `getA().getB().getC()`. Create a `JXPathContext` by passing an object to `JXPathContext.newContext()`, and retrieve the value of a nested property by passing an XPath expression to the `getValue()` method on `JXPathContext`. The following example creates an object graph rooted on a `League` object and retrieves nested properties using two XPath expressions:

```
import org.apache.commons.jxpath.JXPathContext;

// Create an Object graph

League league = new League();

Team team = new Team();

league.getTeams().add( team );

team.setCoach( new Person( "Coach Bob" ) );

team.getPlayers().add( new Person( "Player Charlie" ) );

team.getPlayers().add( new Person( "Player Ted" ) );

team.getPlayers().add( new Person( "Player Bart" ) );

Team team2 = new Team();
```



```

league.getTeams( ).add( team2 );

team2.setCoach( new Person( "Coach Susan" ) );

team2.getPlayers( ).add( new Person( "Player Jim" ) );

// Query for the coach of a specific player.

XPathContext context = XPathContext.newContext( league );

System.out.println( "** Retrieve the first name of Ted's coach" );

String xpath = "teams/players[firstName = 'Player Ted']/../coach/firstName";

Object value = context.getValue( xpath );

System.out.println( value );

// Query for the players of a specific coach

context = XPathContext.newContext( league );

System.out.println( "** Retrieve the players on Coach Susan's team" );

value = context.getValue( "teams/coach[firstName = 'Coach Susan']/../players" );

System.out.println( value );

```

This example creates a `League` with two `Team` objects stored in a `List`. Each `Team` object has a `coach` property of type `Person`, and a `players` property, which is a `List` of `Person` objects. A `XPathContext` is created by passing `league` to `XPathContext.newContext()`, and two XPath queries are executed by passing query strings to `getValue()`. The first XPath query returns the `firstName` of Ted's coach, and the second XPath query returns the `players List` of the team Susan coaches. This example produces the following output:

```
Retrieve the first name of Ted's coach
```

```
Coach Bob
```

```
Retrieve the players on Coach Susan's team
```

```
[com.discursive.jccook.xml.jxpath.Person@173831b]
```

Discussion

XPath is generally used by select nodes in an XML document, and you may have used it to transform XML with Extensible Stylesheet Language Transformations (XSLT). In this example, XPath is used in a somewhat unconventional manner as a query to filter and select objects based on the values of deeply nested properties. The first query-*teams/players[firstname = `Player Ted`]/../coach/firstName*- is evaluated using the `League` object as the current node, and if one were to evaluate the XPath expressions *self()* or *.*, you would retrieve the `League` object passed to `newContext()`. When the previous example retrieved the first name of Ted's coach, JXPath iterated through the `teamList`, and located the matching `Player` and `Coach` object. The execution of the first XPath expression in the previous example is equivalent to the following code, which iterates through the `Team` and `Player` lists:

```
String firstName = null;

// ...

Iterator teamIterator = league.getTeams().iterator();

while( teamIterator.hasNext() ) {

    Team team = (Team) teamIterator.next();

    Iterator playerIterator = team.getPlayers().iterator();

    while( playerIterator.hasNext() ) {

        Player player = (Player) playerIterator.next();

        if( player.getFirstName().equals( "Player Ted" ) ) {

            firstName = team.getCoach().getFirstName();

        }

    }

}
```

The ability to filter a complex object graph with a simple expression can help you avoid writing tedious code to iterate through doubly nested collections to compare property values.

See Also

Commons JXPath can also be used to reference objects at a specific index in a `List` or an array, or objects by a known key in a `Map`. [Recipe 12.4](#) demonstrates how to use JXPath to reference items in a `Map`, and [Recipe 12.3](#) demonstrates the use of JXPath to reference an item at a specific index in a `List`.

Recipe 12.3 Search a Collection of Simple Objects

Problem

You need to select objects from a `Collection` using XPath predicates.

Solution

Use Jakarta Commons JXPath to select objects from a `Collection` using predicates in XPath expressions. The `iterate()` method on `JXPathContext` takes an XPath expression and returns an `Iterator` that contains each node satisfying that expression. The following example uses simple XPath predicates to select `Person` objects from a `List` by age, first name, and position:

```
import org.apache.commons.jxpath.JXPathContext;

// Create a List of Person objects

List people = new ArrayList( );

people.add(new Person("Ahmad", "Russell", 28 ));

people.add(new Person("Tom", "Russell", 35 ));

people.add(new Person("Ahmad", "Abuzayedeh", 33 ));

// Select all people older than 30

System.out.println( "** People older than 30" );

JXPathContext context = JXPathContext.newContext( people );

Iterator iterator = context.iterate(".[@age > 30]");

printPeople(iterator);

// Select all people with a first name of 'Ahmad'
```



```

context = XPathContext.newContext( people );

System.out.println( "** People with first name 'Ahmad'" );

iterator = context.iterate(".[@firstName = 'Ahmad']");

printPeople(iterator);

// Select the second person from the List

context = XPathContext.newContext( people );

System.out.println( "** Third Person in List" );

Person p = (Person) context.getValue(".[2]");

System.out.println( "Person: " + p.getFirstName( ) + " " + p.getLastName( ) +
                    ", age: " + p.getAge( ) );

// A method to print out the result of each iteration.

private void printPeople(Iterator iterator) {

    while( iterator.hasNext( ) ) {

        Person p = (Person) iterator.next( );

        System.out.println( "Person: " + p.getFirstName( ) +
                            " " + p.getLastName( ) + ", age: " + p.getAge( ) );

    }

}

```

A `XPathContext` is created by passing a `List` to `newContext()`, and each expression is evaluated through a call to `context.iterate()`. Three expressions are evaluated, and the results of each expression are printed in the `printPeople()` method:

```

** People older than 30

Person: Tom Russell, age: 35

Person: Ahmad Abuzayedeh, age: 33

```

```
** People with first name 'Ahmad'
```

```
Person: Ahmad Russell, age: 28
```

```
Person: Ahmad Abuzayedeh, age: 33
```

```
** Second Person in List
```

```
Person: Tom Russell, age: 35
```

Discussion

The final expression in the previous example is a reference to a specific index in a `List`; `./[2]` selected the second element in the `List` supplied to the `JXPathContext`. Whenever an XPath expression deals with a property, which is a `List` or an array, a one-based index can be supplied in brackets after the name of the property. If a `League` object contains a `List` of `Team` objects, and a `Team` object contains a `List` of `Player` objects, the third `Player` object of the fourteenth `Team` can be selected by using the XPath expression `/league/teams[14]/players[3]`.

In the previous example, which filtered a `List` of `Person` objects, you might have noticed that the properties `age` and `firstName` are referenced as attributes in the XPath predicate expression. A property can be referenced either as an element or an attribute. In XPath terms, when JXPath resolves properties on an object, the *child* and *attribute* axis both reference properties. This means that the expressions `./[@age > 30]` and `./[age > 30]` would return the same results, as `age` can be addressed as a child element or attribute of the current node.

`iterate()` returns an `Iterator` that lets you iterate over all nodes that satisfy the given XPath query. `getValue()` returns the first matching result. In the previous example, `iterate()` retrieves two `Person` objects with an `age` property greater than 30. If the same expression were evaluated with `getValue()`, only one `Person` object would have been returned: Tom Russell. Use `iterate()` when multiple nodes may match an XPath expression.

See Also

[Chapter 5](#) demonstrates the use of Commons Collections' `CollectionUtils` to select items in a `Collection` that satisfy a `Predicate`. For more information about using `Predicate` objects to filter collections, refer to [Recipe 5.4](#).



Recipe 12.4 Applying XPath Queries to Complex Object Graphs

Problem

You need to use XPath expressions to select objects from a complex object graph referencing the contents of a `Map` and using expressions with variable references.

Solution

Use Jakarta Commons JXPath to select objects from a collection using XPath queries. The following example uses Commons Digester to parse an XML file into an object graph, and selects `Planet` objects with a radius greater than 5000:

```
import org.apache.commons.digester.Digester;

import org.apache.commons.digester.xmlrules.DigesterLoader;

import org.apache.commons.jxpath.JXPathContext;

List planets = new ArrayList( );

// Parse Planet XML into a List of Planet objects

InputStream input = getClass( ).getResourceAsStream("./planets.xml");

URL rules = getClass( ).getResource("./planet-digester-rules.xml");

Digester digester = DigesterLoader.createDigester(rules);

digester.push(planets);

digester.parse( input );

// Select all planets with a radius greater than 5000
```

```
System.out.println( "Planet Name where radius > 5000");

XPathContext context = XPathContext.newContext( planets );

Iterator iterator = context.iterate(".[@radius > 5000]/name");

while( iterator.hasNext( ) ) {

    Object o  = (Object) iterator.next( );

    System.out.println( "Object: " + o);

}
```

The `Planet` objects are filtered and the names of planets with sufficient radii are printed to the console:

```
Planet Name where radius > 5000
```

```
Object: Venus
```

```
Object: Saturn
```

This object graph was created from an XML document that contains a list of planets and their physical properties including mass, radius, atmospheric composition, lunar population, and orbital distance and period. Commons Digester (from [Chapter 6](#)) is used to parse this XML document to a list of `Planet` objects. The following XML document, *planets.xml*, was parsed in the previous example:

```
<planets>

    <planet name="Venus" mass="4.869e+24" radius="6051.8">

        <orbit distance="108200000" period="224.701"/>

        <atmosphere meanTemp="482" pressure="92">

            <component symbol="CO2" percentage="96"/>

            <component symbol="N" percentage="3"/>

            <component symbol="Other" percentage="1"/>

        </atmosphere>

    </planet>

    <planet name="Mars" mass="6.421e+23" radius="3397.2">

        <orbit distance="227940000" period="686.98"/>
```



```
<atmosphere meanTemp="-63" pressure="0.007">

    <component symbol="CO2" percentage="95.32"/>

    <component symbol="N2" percentage="2.7"/>

    <component symbol="Ar" percentage="1.6"/>

</atmosphere>

<moon>Phobos</moon>

<moon>Deimos</moon>

</planet>

<planet name="Saturn" mass="5.688e+26" radius="60268">

    <orbit distance="1429400000" period="29.458"/>

    <atmosphere meanTemp="-125" pressure="1.4">

        <component symbol="H" percentage="97"/>

        <component symbol="He" percentage="3"/>

    </atmosphere>

    <moon>Pan</moon>

    <moon>Atlas</moon>

    <moon>Prometheus</moon>

    <moon>Pandora</moon>

    <moon>Epimetheus</moon>

    <moon>Janus</moon>

    <moon>Mimas</moon>

</planet>

</planets>
```

To parse this XML document, the following Digester rules are passed to `DigesterLoader.createDigester()`. This digester rule-set creates a `Planet`, `Orbit`, and `Atmosphere` object for each planet. `Moon` objects are created and added to `Planet` objects using the `addMoon()` method on `Planet`. Individual compounds in an atmosphere are added to an `Atmosphere`'s `component Map` using `addComponent()`. The following XML document contains the

contents of the *planet-digester-rules.xml*/file used in the previous example:

```
<digester-rules>

  <pattern value="planets/planet">

    <object-create-rule classname="Planet"/>

    <set-properties-rule/>

    <pattern value="orbit">

      <object-create-rule classname=" Orbit"/>

      <set-properties-rule/>

      <set-next-rule methodname="setOrbit" paramtype=" Orbit"/>

    </pattern>

    <pattern value="atmosphere">

      <object-create-rule classname="Atmosphere"/>

      <set-properties-rule/>

      <pattern value="component">

        <call-method-rule methodname="addComponent" paramcount="2"

          paramtypes="java.lang.String,java.lang.Double"/>

        <call-param-rule attrname="symbol" paramnumber="0"/>

        <call-param-rule attrname="percentage" paramnumber="1"/>

      </pattern>

      <set-next-rule methodname="setAtmosphere"

        paramtype=" Atmosphere"/>

    </pattern>

    <call-method-rule pattern="moon" methodname="addMoon"

      paramtypes="java.lang.String" paramcount="0"/>

    <set-next-rule methodname="add" paramtype="java.lang.Object"/>

  </pattern>
```

```
</digester-rules>
```

Discussion

XPath expressions can be parameterized by referencing a variable name: *\$variable*. The following example references a variable *\$moonName*, which is populated by calling `declareVariable()` on `context.getVariables()`:

```
System.out.println( "Planet Name where a moon is named Deimos");

context.getVariables( ).declareVariable("moonName", "Deimos");

iterator = context.iterate("./moons[. = $moonName]/../name");

while( iterator.hasNext( ) ) {

    String name = (String) iterator.next( );

    System.out.println( "Planet Name: " + name);

}
```

This example selects the name of a planet with a moon named "Deimos." The results of the previous example are printed below:

```
Planet Name where a moon is named Deimos
```

```
Planet Name: Mars
```

`Planet.getAtmosphere().getComponents()` returns a `Map` with element symbols as keys. The following example selects every planet with more than a 2% Helium atmosphere:

```
System.out.println( "Planet where Helium percentage greater than 2");

iterator = context.iterate("./atmosphere/components/He[.>2]/../..");

while( iterator.hasNext( ) ) {

    Planet p = (Planet) iterator.next( );

    System.out.println( "Planet: " + p.getName( ));

}
```

To select every planet with more than a 2% Helium atmosphere, the XPath expression in the previous example references a specific key in the components `Map` as if it were a nested element. *components/He[.>2]* will evaluate to `true` if `getComponents().get("He")` is a number larger than

2. The previous code determines that Saturn is the only one of these three planets with more than 2% Helium:

```
Planet where Helium percentage greater than 2

Planet: Saturn
```

The following example prints a list of each moon and the corresponding planet using a reference to a variable in an XPath expression:

```
System.out.println( "All of the Moon Names" );

iterator = context.iterate("./moons");

while( iterator.hasNext( ) ) {

    String moon = (String) iterator.next( );

    context.getVariables( ).declareVariable("moonName", moon);

    String planet =

        (String) context.getValue("./moons[. = $moonName]/../name");

    System.out.println( "Moon: " + moon + ", \t\tPlanet: " + planet);

}
```

The previous example shows that a `JXPathContext` can be reused. This example iterates through each moon and finds the name of the planet corresponding to each moon using the results of the first expression to populate a variable in the second expression. The XPath expression, `./moons[. = $moonName]/../name`, contains a reference to the variable `$moonName`, which is set by passing a variable name and value to the `declareVariable()` method on `JXPathContext`. This example prints each moon and planet to the console as follows:

```
All of the Moon Names

Moon: Phobos,          Planet: Mars
Moon: Deimos,          Planet: Mars
Moon: Pan,             Planet: Saturn
Moon: Atlas,           Planet: Saturn
Moon: Prometheus,      Planet: Saturn
Moon: Pandora,         Planet: Saturn
Moon: Epimetheus,      Planet: Saturn
```


Moon: Janus, Planet: Saturn

Moon: Mimas, Planet: Saturn

See Also

There is much more to XPath including object creation and the ability to set properties using XPath expressions; for more information about using XPath to access maps, collections, servlet contexts, and DOM/JDOM Documents, see the XPath User's Guide (<http://jakarta.apache.org/commons/jxpath/users-guide.html>).

Recipe 12.5 Obtaining Jakarta Lucene

Problem

You need to use Jakarta Lucene to create a searchable index of documents.

Solution

Download Jakarta Lucene 1.4 from <http://jakarta.apache.org/site/binindex.cgi>, and uncompress the distribution archive. Place the [lucene-1.4-final.jar](#) file in your classpath.

Discussion

Jakarta Lucene is a full-text search engine that can be used to index any information. Lucene maintains an index of **Document** objects that can contain any number of fields, and this index can be searched using a highly developed query language.

If you have a Maven project that needs to use Jakarta Lucene, add a dependency on Jakarta Lucene 1.4 with the following section in *project.xml*.

```
<dependencies>

  <dependency>

    <id>lucene</id>

    <version>1.4</version>

  </dependency>

  ....other dependencies...

</dependencies>
```

See Also

For more information on the Jakarta Lucene project, see the Jakarta Lucene project page at <http://jakarta.apache.org/lucene>.



Recipe 12.6 Creating an Index of XML Documents

Problem

You need to quickly search a collection of XML documents, and, to do this, you need to create an index of terms keeping track of the context in which these terms appear.

Solution

Use Jakarta Lucene and Jakarta Digester and create an index of Lucene `Document` objects for the lowest level of granularity you wish to search. For example, if you are attempting to search for speeches in a Shakespeare play that contain specific terms, create a Lucene `Document` object for each speech. For the purposes of this recipe, assume that you are attempting to index Shakespeare plays stored in the following XML format:

```
<?xml version="1.0"?>

<PLAY>

  <TITLE>All's Well That Ends Well</TITLE>

  <ACT>

    <TITLE>ACT I</TITLE>

    <SCENE>

      <TITLE>SCENE I.  Rousillon. The COUNT's palace.</TITLE>

      <SPEECH>
```



```
<SPEAKER>COUNTRESS</SPEAKER>

<LINE>In delivering my son from me, I bury a second husband.</LINE>

</SPEECH>

<SPEECH>

<SPEAKER>BERTRAM</SPEAKER>

<LINE>And I in going, madam, weep o'er my father's death</LINE>

<LINE>anew: but I must attend his majesty's command, to</LINE>

<LINE>whom I am now in ward, evermore in subjection.</LINE>

</SPEECH>

</SCENE>

</ACT>

</PLAY>
```

The following class creates a Lucene index of Shakespeare speeches, reading XML files for each play in the *./data/Shakespeare* directory, and calling the `PlayIndexer` to create Lucene `Document` objects for every speech. These `Document` objects are then written to a Lucene index using an `IndexWriter`:

```
import java.io.File;

import java.io FilenameFilter;

import org.apache.log4j.Logger;

import org.apache.lucene.analysis.standard.StandardAnalyzer;

import org.apache.lucene.index.IndexWriter;

import org.apache.oro.io.GlobFilenameFilter;

File dataDir = new File("./data/shakespeare");

logger.info( "Looking for XML files in "
```

```

FilenameFilter xmlFilter = new GlobFilenameFilter( "*.xml" );

File[] xmlFiles = dataDir.listFiles( xmlFilter );

logger.info( "Creating Index" );

IndexWriter writer = new IndexWriter("index",

                                     new SimpleAnalyzer( ), true);

PlayIndexer playIndexer = new PlayIndexer( writer );

playIndexer.init( );

for (int i = 0; i < xmlFiles.length; i++) {

    playIndexer.index(xmlFiles[i]);

}

writer.optimize( );

writer.close( );

logger.info( "Parsing Complete, Index Created" );

```

The `PlayIndexer` class, shown in [Example 12-1](#), parses each XML file and creates `Document` objects that are written to an `IndexWriter`. The `PlayIndexer` uses Commons Digester to create a Lucene `Document` object for every speech. The `init()` method creates a `Digester` instance designed to interact with an inner class, `DigestContext`, which keeps track of the current context of a speech-`play`, `act`, `scene`, `speaker`-and the textual contents of a `speech`. At the end of every speech element, the `DigestContext` invokes the `processSpeech()` method that creates a Lucene `Document` for each speech and writes this `Document` to the Lucene `IndexWriter`. Because each `Document` is associated with the specific context of a speech, it will be possible to obtain a specific location for each term or phrase.

Example 12-1. PlayIndexer using Commons Digester and Jakarta Lucene

```
package com.discursive.jccook.xml.bardsearch;
```

```
import java.io.File;

import java.io.IOException;

import java.net.URL;


import org.apache.commons.digester.Digester;

import org.apache.commons.digester.xmlrules.DigesterLoader;

import org.apache.log4j.Logger;

import org.apache.lucene.document.Document;

import org.apache.lucene.document.Field;

import org.apache.lucene.index.IndexWriter;

import org.xml.sax.SAXException;


import com.discursive.jccook.util.LogInit;


public class PlayIndexer {

    private static Logger logger =

        Logger.getLogger( PlayIndexer.class );

    static { LogInit.init( ); }


    private IndexWriter indexWriter;

    private Digester digester;

    private DigestContext context;


    public PlayIndexer(IndexWriter pIndexWriter) {

        indexWriter = pIndexWriter;

    }

}
```

```
}
```

```
public void init( ) {  
  
    URL playRules =  
  
        PlayIndexer.class.getResource("play-digester-rules.xml");  
  
    digester = DigesterLoader.createDigester( playRules );  
  
}
```

```
public void index(File playXml) throws IOException, SAXException {  
  
    context = new DigestContext( );  
  
    digester.push( context );  
  
    digester.parse( playXml );  
  
    logger.info( "Parsed: " + playXml.getAbsolutePath( ) );  
  
}
```

```
public void processSpeech( ) {  
  
    Document doc = new Document( );  
  
    doc.add(Field.Text("play", context.playTitle));  
  
    doc.add(Field.Text("act", context.actTitle));  
  
    doc.add(Field.Text("scene", context.sceneTitle));  
  
    doc.add(Field.Text("speaker", context.speaker));  
  
    doc.add(Field.Text("speech",  
  
                        new StringReader( context.speech.toString( ) )));  
  
    try {  
  
        indexWriter.addDocument( doc );  
  
    } catch( IOException ioe ) {
```



```

        logger.error( "Unable to add document to index", ioe);
    }
}

public class DigestContext {

    File playXmlFile;

    String playTitle, actTitle, sceneTitle, speaker;

    StringBuffer speech = new StringBuffer( );

    public void setActTitle(String string) { actTitle = string; }

    public void setPlayTitle(String string) { playTitle = string; }

    public void setSceneTitle(String string){ sceneTitle = string;}

    public void setSpeaker(String string) { speaker = string; }

    public void appendLine(String pLine) { speech.append( pLine ); }

    public void speechEnd( ) {

        processSpeech( );

        speech.delete( 0, speech.length( ) );

        speaker = "";

    }

}

```

[Example 12-1](#) used a Digester rule set defined in [Example 12-2](#). This set of rules is designed to invoke a series of methods in a set sequence to populate the context variables for each speech. The Digester rules in [Example 12-2](#) never push or pop objects onto the digester stack; instead, the Digester is being used to populate variables and invoke methods on an object that creates Lucene **Document** objects based on a set of context variables. This example uses the Digester as a shorthand Simple API for XML (SAX) parser; the **PlayIndexer** contains a series of callback methods, and the Digester rule set simplifies the interaction between the underlying SAX parser and the

DigestContext.

Example 12-2. Digester rules for PlayIndexer

```
<?xml version="1.0"?>

<digester-rules>

  <pattern value="PLAY">

    <bean-property-setter-rule pattern="TITLE"

      propertyname="playTitle"/>

  <pattern value="ACT">

    <bean-property-setter-rule pattern="TITLE"

      propertyname="actTitle"/>

  <pattern value="PROLOGUE">

    <bean-property-setter-rule pattern="TITLE"

      propertyname="sceneTitle"/>

  <pattern value="SPEECH">

    <bean-property-setter-rule pattern="SPEAKER"

      propertyname="speaker"/>

    <call-method-rule pattern="LINE"

      methodname="appendLine"

      paramtype="java.lang.String"

      paramcount="0"/>

    <call-method-rule methodname="speechEnd"

      paramtype="java.lang.Object"/>

  </pattern>

</pattern>
```

```
<pattern value="SCENE">

    <bean-property-setter-rule pattern="TITLE"

                                propertyname="sceneTitle"/>

<pattern value="SPEECH">

    <bean-property-setter-rule pattern="SPEAKER"

                                propertyname="speaker"/>

    <call-method-rule pattern="LINE"

                        methodname="appendLine"

                        paramtype="java.lang.String"

                        paramcount="0"/>

    <call-method-rule methodname="speechEnd"

                        paramtype="java.lang.Object"/>

</pattern>

</pattern>

</pattern>

</pattern>

</digester-rules>
```

Discussion

In this recipe, an `IndexWriter` was created with a `SimpleAnalyzer`. An `Analyzer` takes a series of terms or tokens and creates the terms to be indexed; different `Analyzer` implementations are appropriate for different applications. A `SimpleAnalyzer` will keep every term in a piece of text, discarding nothing. A `StandardAnalyzer` is an `Analyzer` that discards common English words with little semantic value, such as "the," "a," "an," and "for." The `StandardAnalyzer` maintains a list of terms to discard—a *stop list*. Cutting down on the number of terms indexed can save time and space in an index, but it can also limit accuracy. For example, if one were to use the `StandardAnalyzer` to index the play *Hamlet*, a search for "to be or not to be" would return zero results, because every term in that phrase is a common English word on `StandardAnalyzer`'s stop list. In this recipe, a `SimpleAnalyzer` is used because it keeps track of the occurrence of every term in a document.

What you end up with after running this example is a directory named *index*, which contains files used by Lucene to associate terms with documents. In this example, a Lucene `Document` consists of the contextual information fully describing each speech—"play," "act," "scene," "speaker," and

"speech." `Field` objects are added to `Document` objects using `Document`'s `addDoc()` method. The `processSpeech()` method in `PlayIndexer` creates Lucene `Document` objects that contain `Fields`; `Field` objects are created by calling `Text()`, a static method on `Field`. The first parameter to `Text()` is the name of the field, and the second parameter is the content to be indexed. Passing a `String` as the second parameter to `Text()` instructs the `IndexWriter` to store the content of a field in a Lucene index; a `Field` created with a `String` can be displayed in a search result. Passing a `Reader` as the second parameter to `Text()` instructs the `IndexWriter` not to store the contents of a field, and the contents of a field created with a `Reader` cannot be returned in a search result. In the previous example, the "speech" field is created with a `Reader` to reduce the size of the Lucene index, and every other `Field` is created with a `String` so that our search results can provide a speech's contextual coordinates.

See Also

Sure, you've created a Lucene index, but how would you search it? The index created in this recipe can be searched with Lucene using techniques described in [Recipe 12.7](#) and [Recipe 12.8](#).

If you are indexing a huge database of English documents, consider using the `StandardAnalyzer` to discard common English words. If you are indexing documents written in German or Russian, Lucene ships with `GermanAnalyzer` and `RussianAnalyzer`, which both contain stop word lists for these languages. For more information about these two implementations of `Analyzer`, see the Lucene JavaDoc at <http://jakarta.apache.org/lucene/docs/api/index.html>. Analyzer implementations for French, Dutch, Chinese, and Czech can be found in the Lucene Sandbox (<http://cvs.apache.org/viewcvs/jakarta-lucene-sandbox/contributions/analyzers/>).

For more information about Jakarta Lucene, see the Lucene project web site at <http://jakarta.apache.org/lucene>.

This recipe uses the *The Plays of Shakespeare*, compiled by Jon Bosak. To download the complete works of Shakespeare in XML format, see <http://www.ibiblio.org/bosak/>.

Recipe 12.8 Finding the Frequency of Terms in an Index

Problem

You need to find the most frequently used terms in a Lucene index.

Solution

Use Jakarta Lucene to index your documents and obtain a `TermEnum` using an `IndexReader`. The frequency of a term is defined as the number of documents in which a specific term appears, and a `TermEnum` object contains the frequency of every term in a set of documents. [Example 12-3](#) iterates over the terms contained in `TermEnum` returning every term that appears in more than 1,100 speeches.

Example 12-3. TermFreq finding the most frequent terms in an index

```
package com.discursive.jccook.xml.bardsearch;

import java.util.ArrayList;

import java.util.Collections;

import java.util.Iterator;

import java.util.List;

import org.apache.commons.lang.builder.CompareToBuilder;

import org.apache.log4j.Logger;

import org.apache.lucene.index.IndexReader;

import org.apache.lucene.index.TermEnum;

import com.discursive.jccook.util.LogInit;
```

```
public class TermFreq {

    private static Logger logger = Logger.getLogger(TermFreq.class);

    static { LogInit.init( ); }

    public static void main(String[] pArgs) throws Exception {

        logger.info("Threshold is 1100" );

        Integer threshold = new Integer( 1100 );

        IndexReader reader = IndexReader.open( "index" );

        TermEnum enum = reader.terms( );

        List termList = new ArrayList( );

        while( enum.next( ) ) {

            if( enum.docFreq( ) >= threshold.intValue( ) &&

                enum.term( ).field( ).equals( "speech" ) ) {

                Freq freq = new Freq( enum.term( ).text( ), enum.docFreq( ) );

                termList.add( freq );

            }

        }

        Collections.sort( termList );

        Collections.reverse( termList );

        System.out.println( "Frequency | Term" );

        Iterator iterator = termList.iterator( );

        while( iterator.hasNext( ) ) {

            Freq freq = (Freq) iterator.next( );
```

```
        System.out.print( freq.frequency );

        System.out.println( " | " + freq.term );

    }

}

public static class Freq implements Comparable {

    String term;

    int frequency;

    public Freq( String term, int frequency ) {

        this.term = term;

        this.frequency = frequency;

    }

    public int compareTo(Object o) {

        if( o instanceof Freq ) {

            Freq oFreq = (Freq) o;

            return new CompareToBuilder( )

                .append( frequency, oFreq.frequency )

                .append( term, oFreq.term )

                .toComparison( );

        } else {

            return 0;

        }

    }

}
```

```
}
```

A Lucene index is opened by passing the name of the *index* directory to `IndexReader.open()`, and a `TermEnum` is retrieved from the `IndexReader` with a call to `reader.terms()`. The previous example iterates through every term contained in `TermEnum`, creating and populating an instance of the inner class `Freq`, if a term appears in more than 1,100 documents and the term occurs in the "speech" field. `TermEnum` contains three methods of interest: `next()`, `docFreq()`, and `term()`. `next()` moves to the next term in the `TermEnum`, returning `false` if no more terms are available. `docFreq()` returns the number of documents a term appears in, and `term()` returns a `Term` object containing the text of the term and the field the term occurs in. The `List` of `Freq` objects is sorted by frequency and reversed, and the most frequent terms in a set of Shakespeare plays is printed to the console:

```
0      INFO  [main] TermFreq      - Threshold is 4500
```

```
Frequency | Term
```

```
2907 | i
2823 | the
2647 | and
2362 | to
2186 | you
1950 | of
1885 | a
1870 | my
1680 | is
1678 | that
1564 | in
1562 | not
1410 | it
1262 | s
1247 | me
1200 | for
1168 | be
1124 | this
```


1109 | but

Discussion

From this list, it appears that the most frequent terms in Shakespeare plays are inconsequential words, such as "the," "a," "of," and "be." The index this example was executed against was created with a `SimpleAnalyzer` that does not discard any terms. If this index is created with `StandardAnalyzer`, common articles and pronouns will not be stored as terms in the index, and they will not show up on the most frequent terms list. Running this example against an index created with a `StandardAnalyzer` and reducing the frequency threshold to 600 documents returns the following results:

Frequency | Term

2727 | i

2153 | you

1862 | my

1234 | me

1091 | your

1057 | have

1027 | he

973 | what

921 | so

893 | his

824 | do

814 | him

693 | all

647 | thou

632 | shall

614 | lord

See Also

There is an example of enumerating term frequency in the Jakarta Lucene Sandbox. To see this frequency analysis example, see the "High Frequency Terms" example (<http://jakarta.apache.org/lucene/docs/lucene-sandbox/>).

PREV

< Day Day Up >

Recipe 12.7 Searching for a Specific Term in a Document Index

Problem

You need to identify which documents in a Lucene index contain specific terms or phrases.

Solution

Use an `IndexSearcher` to search a Lucene index created with `IndexWriter`. This recipe assumes that you have created a Lucene index using the techniques shown in the previous recipe. The constructor of `IndexSearcher` takes the name of a directory that contains a Lucene index. A `Query` object can be created by passing a `String` query, a default search field, and an `Analyzer` to `QueryParser.parse()`. The following example searches the `Lucene` index created in the previous recipe for all speeches containing the term "Ophelia":

```
import org.apache.lucene.analysis.Analyzer;

import org.apache.lucene.analysis.SimpleAnalyzer;

import org.apache.lucene.document.Document;

import org.apache.lucene.queryParser.QueryParser;

import org.apache.lucene.search.Hits;

import org.apache.lucene.search.IndexSearcher;

import org.apache.lucene.search.Query;

import org.apache.lucene.search.Searcher;

logger.info("Searching for Ophelia");

Searcher searcher = new IndexSearcher("index");

Analyzer analyzer = new SimpleAnalyzer();

Query query = QueryParser.parse("Ophelia", "speech", analyzer);
```

```

Hits hits = searcher.search(query);

logger.info( "Searching Done, hit: " + hits.length( ) );

System.out.println( "Score | Play | Act | Scene | Speaker" );

for( int i = 0; i < hits.length( ); i++ ) {

    Document doc = hits.doc(i);

    System.out.print( (int) (hits.score(i) * 100 ) );

    System.out.print( " | " + doc.get("play") );

    System.out.print( " | " + doc.get("act") );

    System.out.print( " | " + doc.get("scene") );

    System.out.print( " | " + doc.get("speaker") + "\n" );

}

```

An `IndexSearcher` is created by passing in the name of the directory containing the Lucene index to its constructor. Next, an `Analyzer` is created that will analyze the query `String`.

It is important at this stage to use the same `Anaylzer` implementation that was used to create the Lucene index to be searched, and, in this case, a `SimpleAnalyzer` is used. If you use an `Analyzer`, which discards the words "to," "be," "or," and "not," and then try to create a `Query` for "to be or not to be," you are not going to find the appropriate speech in *Hamlet* because the `Analyzer` you used to parse your query dropped every term.

`QueryParser` parses the query string and creates a `Query` object that will search the "speech" field of each `Document` in the index. The example then calls `searcher.search()` and iterates through `Document` objects contained in an instance of `Hits`. `Hits` contains a `List` of `Document` objects and a relevance score for each result; a relevance score is a number between 1.00 and 0.00 that tells you how strongly a particular `Document` matches a particular query. The more a term occurs in a speech, the more relevant the speech is, and the closer the relevance score is to 1. The previous example returns every occurrence of the term "Ophelia" in every Shakespeare play, and, from the results, it is clear that Ophelia is a character in *Hamlet*. Every occurrence of Ophelia is listed with the relevance, play, act, scene, and speaker:

```

1   INFO [main] TermSearch      - Searching for Ophelia

321 INFO [main] TermSearch      - Searching Done, hit: 19

```


Score	Play	Act	Scene	Speaker
100	Hamlet	ACT IV	SCENE V	QUEEN GERTRUDE
100	Hamlet	ACT IV	SCENE V	KING CLAUDIUS
81	Hamlet	ACT IV	SCENE V	QUEEN GERTRUDE
81	Hamlet	ACT V	SCENE I	HAMLET
58	Hamlet	ACT I	SCENE III	LORD POLONIUS
58	Hamlet	ACT II	SCENE I	LORD POLONIUS
50	Hamlet	ACT I	SCENE III	LAERTES
33	Hamlet	ACT V	SCENE I	HAMLET
25	Hamlet	ACT III	SCENE I	QUEEN GERTRUDE
24	Hamlet	ACT III	SCENE I	LORD POLONIUS
22	Hamlet	ACT IV	SCENE VII	LAERTES
21	Hamlet	ACT III	SCENE I	KING CLAUDIUS
17	Hamlet	ACT IV	SCENE V	LAERTES
17	Hamlet	ACT II	SCENE II	LORD POLONIUS
16	Hamlet	ACT III	SCENE I	LORD POLONIUS
14	Hamlet	ACT II	SCENE II	LORD POLONIUS
13	Hamlet	ACT I	SCENE III	LORD POLONIUS
11	Hamlet	ACT I	SCENE III	LAERTES
11	Hamlet	ACT III	SCENE I	HAMLET

A **Query** can also search for multiple terms in a specific order because a Lucene index keeps track of the order relationships between terms within a **Document**. Searching for the famous "to be or not to be" returns a single match from Act III, Scene I of *Hamlet*.

```
0 [main] INFO TermSearch - Searching for 'speech:"to be or not to be"'
```

```
354 [main] INFO TermSearch - Searching Done, hit: 1
```

Score | Play | Act | Scene | Speaker

100 | Hamlet | ACT III | SCENE I | HAMLET

This search was only possible because the `SimpleAnalyzer` is used during index creation and query parsing. If a different `Analyzer` had been used to create the index, the Lucene index would not be storing information about such common words as "to," "be," "or," and "not." It is a common practice for general search engines to discard very common terms such as "the," "a," "an," or "when." Discarding unimportant terms can reduce the size of an index remarkably, but if you need to search for "to be or not to be," you will need to preserve all terms.

Discussion

Both of the previous examples executed queries in about 300 milliseconds on a very cheap 2.0 GHz Celeron eMachine. This search would have taken orders of magnitude longer to execute if every document had to be parsed and searched in response to a query. The only reason a full-text search can be completed in a few hundred milliseconds is the presence of a Lucene index. The Lucene index provides a database of Documents indexed by term, and an `IndexSearcher` is essentially retrieving objects from this database.

A Lucene query can combine multiple criteria, search for terms matching wildcards, and find documents by multiple fields. A specific field can be searched by prefixing a term with the field name and a colon; for example, to search for documents in a certain play, one would use the query `play: "Hamlet"`. The second parameter to `QueryParser.parse()` is the default field for a query, and, in the previous example, the default field is "speech." This means that a term without a field qualifier will match the "speech" field. [Table 12-1](#) lists some possible Lucene queries and describes the results they would return.

Table 12-1. A survey of Lucene queries

Query	Description
play: "Hamlet"	Returns all documents with a "play" field matching the string "Hamlet"
"to be" AND "not to be"	Returns a document with a "speech" field containing the strings "to be" and "not to be"
play: "Hamlet" AND ("Polonius" OR "Hamlet")	Returns all documents with a "play" field matching "Hamlet" with a "speech" field that contains the terms "Polonius" or "Hamlet"
s*ings	Returns all documents with a "speech" field containing a term that starts with "s" and ends in "ings"; includes terms such as "strings" and "slings"
L?ve	Returns all documents with a "speech" field containing terms such as "Love" or "Live"

Query	Description
"slings" NOT "arrows"	Returns documents with a "speech" field that contains "slings" but not "arrows"

The following Lucene query finds documents containing "Saint Crispin" and "England" or "to be or not to be" and "slings and arrows":

```
("Saint Crispin" AND "England") OR  
("to be or not to be" AND ("slings and arrows"))
```

When this query is executed against the Lucene index used in the previous two recipes, two speeches are returned-a rousing battle speech from [Henry V](#) and Hamlet's existential rant. Running this query would produce the following output:

```
0 [main] INFO TermSearch - Searching for ("Saint Crispin" AND "England") OR  
("to be or not to be" AND ("slings and arrows"))  
  
406 [main] INFO TermSearch - Searching Done, hit: 2  
  
Score | Play      | Act      | Scene                               | Speaker  
31     | Hamlet    | ACT III  | SCENE I.  A room in the castle.    | HAMLET  
11     | Henry V   | ACT IV   | SCENE III.  The English camp.      | KING HENRY V
```

See Also

Lucene is a capable search engine with very rich query syntax supporting fuzzy term matching and searching for terms based on proximity. For more details on Lucene query syntax, see <http://jakarta.apache.org/lucene/docs/queryparsersyntax.html>.



Colophon

Our look is the result of reader comments, our own experimentation, and feedback from distribution channels. Distinctive covers complement our distinctive approach to technical topics, breathing personality and life into potentially dry subjects.

The animal on the cover of Jakarta Commons Cookbook is an aardvark. Native to the grasslands and woodlands of sub-Saharan Africa, the aardvark is the only surviving species in the Orycteropodidae family of mammals. Despite being named for its resemblance to the pig (the word aardvark derives from the Dutch for "earth pig"), the aardvark's appearance is far more similar to that of marsupials, such as the bilby and the bandicoot.

Aardvarks are distinguished by their pig-like torso, arched back, oversized ears, and lengthy snout. They are typically yellow-gray in color, although their tough skin may appear reddish-brown when coated in soil. On average, the adult aardvark is slightly more than three feet long and weighs approximately 90 to 140 pounds. Aardvarks dine almost exclusively on ants and termites, for which their tiny, tubular mouth and long, slender tongue are ideally suited. Upon locating a cache of ants with their keen sense of smell, aardvarks use their strong front legs to dig into the nest and rapidly lap up the insects with their sticky tongue. Scientists have observed aardvarks devouring as many as 50,000 insects in a single night!

By nature, aardvarks tend to be reclusive. They are nocturnal creatures that build elaborate individual burrows of up to 40 feet in length in their home terrain, used to search for food and provide temporary shelter. Mothers make use of burrows as a more permanent home when giving birth to their young.

Currently, aardvarks are not considered an endangered species. However, they are still targeted by hunters for their exquisite cylindrical teeth, which are often used for decorative purposes.

Matt Hutchinson was the production editor for Jakarta Commons Cookbook . Octal Publishing, Inc. provided production services. Marlowe Shaeffer, Sarah Sherman, and Darren Kelly provided quality control.

Emma Colby designed the cover of this book, based on a series design by Edie Freedman. The cover image is a 19th-century engraving from Illustrated Natural History. Clay Fernald produced the cover layout with QuarkXPress 4.1 using Adobe's ITC Garamond font.

David Futato designed the interior layout. This book was converted by Julie Hawks to FrameMaker 5.5.6 with a format conversion tool created by Erik Ray, Jason McIntosh, Neil Walls, and Mike Sierra that uses Perl and XML technologies. The text font is Linotype Birka; the heading font is Adobe Myriad Condensed; and the code font is LucasFont's TheSans Mono Condensed. The illustrations that appear in the book were produced by Lesley Borash using Macromedia FreeHand MX and Adobe Photoshop CS. The tip and warning icons were drawn by Christopher Bing. This colophon was written by Sander Kleinfeld.

The online edition of this book was created by the Safari production group (John Chodacki, Ken Douglass, and Ellie Cutler) using a set of Frame-to-XML conversion and cleanup tools written and maintained by Erik Ray, Benn Salter, John Chodacki, Ellie Cutler, and Jeff Liggett.

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[abbreviating strings](#)

[access](#)

[beans](#)

[BidiMap](#)

[properties](#)

[beans 2nd](#)

[indexed beans](#)

[mapped beans](#)

[nested beans](#)

[addComponent\(\) method](#)

[addData\(\) method](#)

[addDoc\(\) method](#)

[adding](#)

[parts](#)

[properties](#)

[addParameter\(\) method](#)

[addRuleSet\(\) method](#)

[alphanumeric identifiers](#)

[Analyzers](#)

[creating](#)

[StandardAnalyzer](#)

[Apache Log4J](#)

[configuration](#)

[downloading](#)

[Apache Xalan](#)

[app tag library](#)

[append\(\) method](#)

[applications](#)

[Apache Log4J](#)

[Commons CLI](#)

[downloading](#)

[printing usage information](#)

[Commons Configuration](#)

[downloading](#)

[XML documents](#)

[Commons Logging, downloading](#)

[Log4J](#)

[logic](#)

[math](#)

[complex numbers](#)

[fractions](#)

[linear equations](#)

[number ranges](#)

[random variables](#)

[univariate statistic calculations](#)

[Web, templating](#)

[applying XPath to object graphs](#)

[ArgoUML](#)

[ArrayListIterator](#)

[ArrayLists, collections](#)

arrays

[_cloning](#)

[_conversion](#)

[_mapping multidimensional](#)

[_printing](#)

[_reversing](#)

[_searching](#)

[_testing](#)

[ArrayUtils.clone\(\) method](#)

[ArrayUtils.contains\(\) method](#)

[ArrayUtils.lastIndexOf\(\) method](#)

[ArrayUtils.reverse\(\) method](#)

[ArrayUtils.toMap\(\) method 2nd](#)

[ArrayUtils.toObject\(\) method](#)

[ArrayUtils.toPrimitive\(\) method](#)

[ArrayUtils.toString\(\) method](#)

authentication

[_Jakarta HttpClient](#)

[_WebDav](#)

[authorization, headers](#)

[autoboxing 2nd](#)

[automation 2nd](#)

[_compareTo\(\) method](#)

[_equals\(\) method](#)

[_hashCode\(\) method](#)

[_toString\(\) methods](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[bags](#)

[_collections](#)

[BasicParser](#)

[BeanComparator](#)

[BeanMap](#)

[BeanPredicate](#)

[BeanPredicate object](#)

[beans](#)

[Commons BeanUtils](#)

[_downloading](#)

[_source code](#)

[_Commons Betwixt](#)

[_dynamic](#)

[_EarthQuake](#)

[_expression language](#)

[_form](#)

[_populating](#)

[properties](#)

[_accessing 2nd](#)

[_cloning](#)

[_comparing](#)

[_copying](#)

[_indexed access](#)

[_mapped access](#)

[_mapping](#)

[_nested access](#)

[_setting](#)

[_strings](#)

[_testing](#)

[_types of](#)

[_validation](#)

[_wrapping maps](#)

[_relationships, diagramming](#)

[_XML 2nd 3rd](#)

[BeanUtils.cloneBean\(\) method](#)

[BeanWriter, customization](#)

[beanWriter.write\(\) method](#)

[begin\(\) method](#)

[BidiMap](#)

[blocking buffers, collections](#)

[blocks, finally](#)

[Boolean values](#)

[Boolean variables](#)

[BoundedFifoBuffer](#)

[buffer.remove\(\) method](#)

[BufferListener](#)

[BufferOverflowException](#)
[buffers](#)
[blocking](#)
[collections](#)
[indexes](#)
[build.xml](#)
[built-in styles](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[caches](#)

[calculations](#)

[\[Soundex\]\(#\)](#)

[\[univariate statistics\]\(#\)](#)

[capitalization, case-insensitive maps](#)

[capturing](#)

[\[application logic\]\(#\)](#)

[\[XML commands\]\(#\)](#)

[cardinality\(\) method](#)

[carriage returns, deleting](#)

[case-insensitive maps](#)

[CaseInsensitiveMap](#)

[casting](#)

[certificates, self-signed](#)

[ChainedClosure](#)

[ChainedTransformer 2nd](#)

[chaining](#)

[\[closures\]\(#\)](#)

[\[Comparators\]\(#\)](#)

[\[transformations\]\(#\)](#)

[characters](#)

[\[abbreviating\]\(#\)](#)

[\[control\]\(#\)](#)

[\[splitting\]\(#\)](#)

[\[stripping\]\(#\)](#)

[\[trimming\]\(#\)](#)

[chomping strings](#)

[classes](#)

[\[CompareToBuilder\]\(#\)](#)

[\[ComplexFormat\]\(#\)](#)

[\[CompositeUnaryFunction\]\(#\)](#)

[\[EqualsBuilder\]\(#\)](#)

[\[HashCodeBuilder\]\(#\)](#)

[\[java.lang.Math\]\(#\)](#)

[\[processEstimator\]\(#\)](#)

[\[ReflectionToStringBuilder\]\(#\)](#)

[\[SimpleDateFormat\]\(#\)](#)

[\[StringUtils\]\(#\)](#)

[\[ToStringBuilder\]\(#\)](#)

[\[customization\]\(#\)](#)

[\[styles\]\(#\)](#)

[\[ToStringStyle\]\(#\)](#)

[\[WordUtils\]\(#\)](#)

[cleanDirectory\(\) method](#)

[client.listMessage\(\) method](#)

[client.sendSimpleMessage\(\) method](#)

clients

Commons Net

[_downloading](#)

[_FTP](#)

[_HTTP POST requests](#)

Jakarta HttpClient

[_authentication](#)

[_cookies](#)

[_debugging](#)

[_downloading](#)

[_GET method 2nd](#)

[_redirects](#)

[_self-signed certificates](#)

[_sending query parameters](#)

[_source code](#)

[_SSL](#)

[_POP3](#)

[_SMTP](#)

[_TFTP](#)

[_WebDav](#)

[clock.getTime\(\) method](#)

cloning

[_arrays](#)

[_properties](#)

[close\(\) method](#)

[closing, Commons IO](#)

[closures](#)

[_chaining](#)

[_conditional statements with](#)

[_loops with](#)

code

[_Commons BeanUtils](#)

[_Commons Codec](#)

[_Commons Collections](#)

[_Commons Lang](#)

[_Jakarta HttpClient](#)

[_Soundex](#)

[coefficients](#)

collections

[_ArrayLists](#)

[_bags](#)

[_blocking buffers](#)

[_buffers](#)

[_caches](#)

[_case-insensitive maps](#)

[_casting](#)

Commons XPath

[_applying object graphs](#)

[_downloading](#)

[_querying object graphs](#)

[_searching](#)

[_counting](#)

- [_downloading](#)
- [_element iteration](#)
- [_key by value retrieval](#)
- [_lazy maps](#)
- [_list constraints](#)
- [_loops](#)
- [_map value constraints](#)
- [_multiple value storage](#)
- [_predicates, filtering with](#)
- [_priority queues](#)
- [_set operations](#)
- [_transformation](#)
- [_typed](#)

- [Collections.reverse\(\) method](#)
- [CollectionUtils.select\(\) method](#)
- [CollectionUtils.selectRejected\(\) method](#)
- [CollectionUtils.transform\(\) method](#)
- [combining predicates](#)
- [CommandLineParser](#)
- [commands, XML](#)

- Commons BeanUtils
 - [_downloading](#)
 - [_source code](#)
- [Commons Betwixt, downloading](#)

- Commons CLI
 - [_downloading](#)
 - [_printing usage information](#)

- [Commons Codec](#)
 - [_Soundex](#)
 - [_source code](#)

- Commons Collections
 - [_ArrayLists](#)
 - [_bags](#)
 - [_blocking buffers](#)
 - [_buffers](#)
 - [_caches](#)
 - [_case-insensitive maps](#)
 - [_casting](#)
 - [_counting](#)
 - [_downloading 2nd](#)
 - [_element iteration](#)
 - [_FixedOrderComparator](#)
 - [_key by value retrieval](#)
 - [_lazy maps](#)
 - [_list constraints](#)
 - [_loops](#)
 - [_map value constraints](#)
 - [_multiple value storage](#)
 - [_predicates](#)
 - [_combining](#)
 - [_customization](#)
 - [_filtering with](#)

- [_priority queues](#)
- [_set operations](#)
- [_source code](#)
- [_transformation](#)
- [_typed collections](#)

Commons Configuration

- [_downloading](#)
- [_XML documents](#)

Commons Digester

- [_downloading](#)
- [_Stack](#)

Commons IO

- [_closing](#)
- [_copying files](#)
- [_CopyUtils](#)
- [_deleting directories](#)
- [_downloading](#)
- [_filtering files](#)
- [_printing](#)
- [_sizing directories](#)
- [_splitting OutputStreams](#)
- [_timestamps](#)
- [_tracking traffic](#)

[Commons IO TeeOutputStream](#)

[Commons JEXL](#)

Commons XPath

- [_applying object graphs](#)
- [_downloading](#)
- [_querying object graphs](#)
- [_searching](#)

Commons Lang

- [_compareTo\(\) method](#)
- [_downloading](#)
- [_equals\(\) method](#)
- [_fractions](#)
- [_hashCode\(\) method](#)
- [_library](#)
- [_mailing lists](#)
- [_source code](#)

toString() methods

- [_automation](#)
- [_customization](#)

[Commons Logging, downloading](#)

Commons Math

- [_complex numbers](#)
- [_fractions](#)
- [_linear equations](#)
- [_number ranges](#)
- [_random variables](#)
- [_univariate statistic calculations](#)

Commons Net

- [_downloading](#)

[FTP](#)

[POP3](#)

[SMTP](#)

[commons-lang-2.0-src directory](#)

[ComparatorChain](#)

Comparators

[chaining](#)

[FixedOrderComparator](#)

[NullComparator](#)

[PatientPriorityComparator](#)

[PriorityBuffer](#)

[reversing](#)

[compareTo\(\) method, automation](#)

[CompareToBuilder class](#)

comparing

[beans](#)

[fixed order comparisons](#)

[nulls](#)

[strings](#)

[COMPATIBILITY mode](#)

[complex numbers](#)

[complexCalculation\(\) method](#)

[ComplexFormat class](#)

[CompositeUnaryFunction class](#)

[conditional transformations](#)

[conditions, combining predicates](#)

configuration

[Apache Log4J](#)

[bean properties](#)

Commons Configuration

[downloading](#)

[XML documents](#)

[NullComparator](#)

[redirects](#)

[StringUtils class](#)

[WordUtils class](#)

[configuration.xml file](#)

[ConfigurationFactory](#)

[connect\(\) method](#)

[connections](#) [See also Jakarta HttpClient]

[testing](#)

[WebDav](#)

constants

[public static final](#)

constraints

[lists](#)

[map values](#)

[containsDouble\(\) method](#)

[containsRange\(\) method](#)

[control characters](#)

[conversion 2nd 3rd](#)

[object arrays to primitive arrays](#)

XML

[beans 2nd](#)

[documents to objects](#)

[cookies, Jakarta HttpClient](#)

copying

[bean properties](#)

[files](#)

[CopyUtils](#)

[counting objects in collections](#)

[CountingInputStream](#)

[CountingOutputStream](#)

[countMatches\(\) method](#)

[country codes](#)

[countryCode string](#)

[createDigester\(\) method](#)

[createPredicate\(\) method](#)

[credentials](#)

[customization](#)

[compareTo\(\) method](#)

[objects](#)

[predicates](#)

[toString\(\) methods](#)

[ToStringBuilder class](#)

[ToStringStyle class](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

dates

- [_formatting](#)
- [_rounding](#)
- [_truncating](#)

[DateUtils.round\(\) method](#)

[DateUtils.truncate\(\) method](#)

days

- [_rounding](#)
- [_truncating](#)

debugging

- [_Apache Log4J](#)
- [_Jakarta HttpClient](#)

[declareVariable\(\) method](#)

deleting

- [_carriage returns](#)
- [_directories](#)
- [_newlines](#)

[diagramming relationships](#)

directories

- [_commons-lang-2.0-src](#)
- [_deleting](#)
- [_filtering](#)
- [_sizing](#)

[disconnect\(\) method](#)

[disjunctions, collections](#)

[Document objects](#)

documents

- [_Jakarta Lucene](#)
- [_specific searches](#)
- [_term frequency](#)

math

- [_complex numbers](#)
- [_fractions](#)
- [_linear equations](#)
- [_number ranges](#)
- [_random variables](#)
- [_univariate statistic calculations](#)

XML

- [_bean conversion 2nd](#)
- [_commands](#)
- [_Common Configuration](#)
- [_Commons Betwixt](#)
- [_converting to objects](#)
- [_Jakarta Lucene](#)
- [_Log4J](#)
- [_namespace-aware parsing](#)

[_object customization](#)

[_parsing](#)

[DoubleRange](#)

[downloading](#)

[_Apache Log4J](#)

[collections](#)

[Commons BeanUtils](#)

[Commons Betwixt](#)

[Commons CLI](#)

[Commons Collections](#)

[Commons Configuration](#)

[Commons Digester](#)

[Commons IO](#)

[Commons JXPath](#)

[Commons Lang 2nd](#)

[Commons Logging](#)

[Commons Net](#)

[FreeMarker 2nd](#)

[Jakarta HttpClient](#)

[Jakarta Lucene](#)

[Jakarta ORO](#)

[Jakarta Slide](#)

[Jakarta Velocity](#)

[DynaBean interface](#)

[dynamic beans](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

- [EarthQuake bean](#)
- [Eclipse](#)
- [editors, UML](#)
- [EL \(Expression Language\)](#)
- [elements, collection iteration](#)
- [email
 - \[_mailboxes\]\(#\)
 - \[_sending\]\(#\)
 - \[_tags\]\(#\)](#)
- [emphasized headers, creating](#)
- [empty strings, testing](#)
- [entity tags](#)
- [enums, creating](#)
- [equals\(\) method automation](#)
- [EqualsBuilder class](#)
- [ETag headers](#)
- [evaluate\(\) method](#)
- [exceptions, finally block](#)
- [execution, ProcessEstimator class](#)
- [Expression Language \(EL\)](#)
- [expressions
 - \[_Commons JEXL\]\(#\)
 - \[_files, listing\]\(#\)
 - \[_language\]\(#\)
 - \[_predicates\]\(#\)](#)
- [Extensible Markup Language \[See XML\]](#)
- [external files, capturing application logic](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[fields, truncating date objects](#)

[FIFO buffers](#)

[File Transfer Protocol](#) [\[See FTP\]](#)

[FileOutputStream 2nd](#)

[FilePart](#)

[FileReader](#)

[files](#)

[_capturing application logic](#)

[_configuration.xml](#)

[_copying](#)

[_filtering](#)

[_HTTP POST requests](#)

[Jakarta ORO](#)

[_downloading](#)

[_listing](#)

[_uploading](#)

[FileUtils.byteCountToDisplaySize\(\) method](#)

[FileUtils.copyFile\(\) method](#)

[FileUtils.copyFileToDirectory\(\) method](#)

[FileUtils.deleteDirectory\(\) method](#)

[FileUtils.sizeOfDirectory\(\) method](#)

[FileUtils.touch\(\) method](#)

[filtering](#)

[_collections](#)

[_files](#)

[FilterIterator](#)

[finally block](#)

[fixed order comparisons](#)

[FloatRange](#)

[form beans](#)

[formatting](#)

[_dates](#)

[_enums](#)

[_HelpFormatter](#)

[_lines](#)

[_strings, parsing](#)

[fractions](#)

[frameworks, Commons Logging](#)

[FreeMarker, downloading 2nd](#)

[frequency, measuring strings](#)

[FTP \(File Transfer Protocol\)](#)

[functors](#)

[Commons Collections](#)

[_downloading](#)

[_source code](#)

[Comparators](#)

- [_chaining](#)
- [_reversing](#)
- [fixed order comparisons](#)
- [nulls, comparing](#)
- objects
 - [_chaining closures](#)
 - [_chaining transformations](#)
 - [_closures](#)
 - [_conditional statements with closures](#)
 - [_conditional transformations](#)
 - [_loops with closures](#)
 - [_transformation](#)
- [_predicates](#)
 - [_combining](#)
 - [_customization](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

- [Gentleware AG](#)
- [GET method 2nd](#)
- [getAddress\(\) method](#)
- [getName\(\) method 2nd](#)
- [getR\(\) method](#)
- [getReplyCode\(\) method](#)
- [getState\(\) method](#)
- [getTime\(\) method](#)
- [global.properties](#)
- [GlobFilenameFilter](#)
- [globs](#)
- [graphs, objects 2nd](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[hashCode\(\) method automation](#)

[HashCodeBuilder class](#)

[HashMap](#)

[hasNext\(\) method](#)

headers

[_authorization](#)

[_ETag](#)

[_Location](#)

[_printing](#)

[_WWW-Authenticate](#)

[HelpFormatter](#)

hours

[_rounding](#)

[_truncating](#)

[HTTP \(Hypertext Transfer Protocol\) 2nd](#) [See also Jakarta HttpClient]

[HTTP POST requests](#)

[HttpMethodDirector](#)

[human-readable file size, printing](#)

[Hypertext Transfer Protocol](#) [See HTTP]

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

I/O

Commons IO

- [_closing](#)
- [_copying files](#)
- [_deleting directories](#)
- [_downloading](#)
- [_filtering files](#)
- [_printing](#)
- [_sizing directories](#)
- [_splitting OutputStreams](#)
- [_timestamps](#)
- [_tracking traffic](#)
- [_CopyUtils](#)

[IdentifierGenerator](#)

identifiers

- [_generating](#)
- [_UUID](#)

[IdentifierUtils](#)

[implementation](#) [See also configuration]

- [_multilevel composite predicates](#)
- [_Predicate interface](#)
- [_predicates](#)

indexes

- [_arrays](#)
- [_bean properties](#)
- [_buffer](#)
- [_comparing](#)

Jakarta Lucene

- [_downloading](#)
- [_specific searches](#)
- [_term frequency](#)
- [_XML documents](#)

[IndexSearcher](#)

[IndexWriter](#)

infrastructure (Commons CLI)

- [_downloading](#)
- [_printing usage information](#)

[InputPredicate](#)

[InputStream](#)

instances

beans

- [_cloning properties](#)
- [_copying properties](#)
- [_FileOutputStream](#)
- [_HttpClient](#)
- [_properties, adding](#)

[_SuffixFileFilter](#)

interfaces

[_BeanPredicate](#)

[_Commons CLI, downloading](#)

[_Commons Configuration](#)

[_DynaBean](#)

[_Log](#)

[_Predicate](#)

[_RuleSet](#)

[intersections, collections](#)

[IntRange](#)

[inventoryBag variable](#)

[IOException, finally blocks](#)

[IOFileFilter](#)

[IOUtils.closeQuietly\(\) methods](#)

[isAlpha\(\) method](#)

[isAlphanumeric\(\) method](#)

[isAlphaSpace\(\) method](#)

[isNumeric\(\) method](#)

[isRedirectNeeded\(\) method](#)

[iterate\(\) method](#)

iteration

[_ArrayLists](#)

[_elements](#)

[_looping](#)

[iterator\(\) method](#)

[iterator.next\(\) method](#)

[iterator.nextIndex\(\) method](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[J2SE \(Java 2 Standard Edition\)](#)

Jakarta [HttpClient](#)

- [authentication](#)
- [cookies](#)
- [debugging](#)
- [downloading](#)
- [GET method 2nd](#)
- [HTTP POST requests](#)
- [redirects](#)
- [self-signed certificates](#)
- [source code](#)
- [SSL](#)
- [URLs, sending query parameters](#)

Jakarta [Lucene](#)

- [downloading](#)
- [specific searches](#)
- [term frequency](#)
- [XML documents](#)

Jakarta [ORO](#)

- [downloading](#)
- [listing files](#)

[Jakarta Slide, downloading](#)

[Jakarta Velocity, downloading](#)

[Java 2 Standard Edition](#) [\[See J2SE\]](#)

[Java Community Process](#) [\[See JCP\]](#)

[Java Expression Language \(JEXL\)](#)

[Java Virtual Machine](#) [\[See JVM\]](#)

[java.lang.Math class](#)

[JavaBeans](#)

Commons [BeanUtils](#)

- [downloading](#)
- [source code](#)
- [dynamic beans](#)
- [populating](#)

properties

- [accessing 2nd](#)
- [cloning](#)
- [comparing](#)
- [copying](#)
- [indexed bean access](#)
- [mapped bean access](#)
- [mapping](#)
- [nested bean access](#)
- [setting](#)
- [strings](#)
- [testing](#)

- [_types of](#)
- [_validation](#)
- [_wrapping maps](#)
- [_relationships, diagramming](#)

[JavaServer Pages](#) [See JSPs]
[JavaServer Pages Standard Tag Library](#) [See JSTL]
[JCP \(Java Community Process\)](#)
[JEXL \(Java Expression Language\)](#)
[Joda](#)
[joining mailing lists](#)
[JSPs \(JavaServer Pages\)](#)
[JSTL \(JavaServer Page Tag Library\)](#)
[JVM \(Java Virtual Machine\)](#)
[XPathContext](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

keys

[_case-insensitive_maps](#)

[_value_retrieval](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[lazy maps](#)

libraries

[_app tag](#)

[_Commons Codec](#)

[_Commons Lang](#)

[_JSTL](#)

[linear equations 2nd](#)

[lines, formatting](#)

lists

[_constraints](#)

[_files](#)

[_mailing](#)

[listWebdavResources\(\) method](#)

[local.properties](#)

[Location headers](#)

[lockMethod\(\) method](#)

[Log interface](#)

[LogFactory.getInstance\(\) method](#)

logging

[_Commons Logging, downloading](#)

[_HttpClient](#)

[logic, applications](#)

[logical expressions, predicates](#)

[login\(\) method](#)

[LongIdentifierFactory](#)

[LongRange](#)

[LoopingIterator](#)

loops

[_with closures](#)

[_collections](#)

[Lucene](#) [See Jakarta Lucene]

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

macros

[_parameters](#)

[_templating](#)

[mailboxes, POP3](#)

[mailing lists](#)

[MajorQuakePredicate 2nd](#)

[map.remove\(\) method](#)

mapping

[bean property access](#)

[beans properties](#)

[BidiMap](#)

[case-insensitive maps](#)

[casting](#)

[InputPredicate](#)

[lazy maps](#)

[multidimensional arrays](#)

[multiple value storage](#)

[typed collections](#)

[value constraints](#)

[MapUtils.debugPrint\(\) method](#)

[MapUtils.getDoubleValue\(\) method](#)

math

[complex numbers](#)

[fractions](#)

[linear equations](#)

[number ranges](#)

[random variables](#)

[univariate statistic calculations](#)

measuring

[frequency of strings](#)

[stream traffic](#)

[time](#)

[mergeTemplate\(\) method](#)

[merging templates](#)

[method.setQueryString\(\) method](#)

methods

[addComponent\(\)](#)

[addData\(\)](#)

[addDoc\(\)](#)

[addParameter\(\)](#)

[addRuleSet\(\)](#)

[append\(\)](#)

[ArraysUtils.toMap\(\)](#)

[ArrayUtils.clone](#)

[ArrayUtils.contains\(\)](#)

[ArrayUtils.lastIndexOf\(\)](#)

- [ArrayUtils.reverse\(\)](#)
- [ArrayUtils.toMap\(\)](#)
- [ArrayUtils.toObject\(\)](#)
- [ArrayUtils.toPrimitive\(\)](#)
- [ArrayUtils.toString\(\)](#)
- [BeanMap](#)
- [BeanUtils.cloneBean\(\)](#)
- [beanWriter.write\(\)](#)
- [begin\(\)](#)
- [buffer.remove\(\)](#)
- [cardinality\(\)](#)
- [cleanDirectory\(\)](#)
- [client.listMessage\(\)](#)
- [client.sendSimpleMessage\(\)](#)
- [clockgetTime\(\)](#)
- [close\(\)](#)
- [Collections.reverse\(\)](#)
- [CollectionUtils.select\(\)](#)
- [CollectionUtils.selectRejected\(\)](#)
- [CollectionUtils.tranform\(\)](#)
- [compareTo\(\) automation](#)
- [complexCalculation\(\)](#)
- [connect\(\)](#)
- [containsDouble\(\)](#)
- [containsRange\(\)](#)
- [countMatches\(\)](#)
- [createDigester\(\)](#)
- [createPredicate\(\)](#)
- [DateUtils.round\(\)](#)
- [DateUtils.truncate\(\)](#)
- [declareVariable\(\)](#)
- [disconnect\(\)](#)
- [DynaBean](#)
- [equals\(\) automation](#)
- [evaluate\(\)](#)
- [FileUtils.byteCountToDisplaySize\(\)](#)
- [FileUtils.copyFile\(\)](#)
- [FileUtils.copyFileToDirectory\(\)](#)
- [FileUtils.deleteDirectory\(\)](#)
- [FileUtils.sizeOfDirectory\(\)](#)
- [FileUtils.touch\(\)](#)
- [GET 2nd](#)
- [getAddress\(\)](#)
- [getName\(\) 2nd](#)
- [getR\(\)](#)
- [getReplyCode\(\)](#)
- [getState\(\)](#)
- [getTime\(\)](#)
- [hashCode\(\) automation](#)
- [hasNext\(\)](#)
- [IOUtils.closeQuietly\(\)](#)
- [isAlpha\(\)](#)

[isAlphanumeric\(\)](#)
[isAlphaSpace\(\)](#)
[isNumeric\(\)](#)
[isRedirectNeeded\(\)](#)
[iterate\(\)](#)
[iterator\(\)](#)
[iterator.next\(\)](#)
[iterator.nextIndex\(\)](#)
[listWebdavResources\(\)](#)
[lockMethod\(\)](#)
[logFactory.getInstance\(\)](#)
[login\(\)](#)
[map.remove\(\)](#)
[MapUtils.debugPrint\(\)](#)
[mapUtils.getDoubleValue\(\)](#)
[mergeTemplate\(\)](#)
[method.setQueryString\(\)](#)
[MultiMap.remove\(\)](#)
[next\(\)](#)
[nextInt\(\)](#)
[nextStringNumericIdentifier\(\)](#)
[options.addOption\(\)](#)
[populateInventory\(\)](#)
[printAlbums\(\)](#)
[printUsage\(\)](#)
[processRedirectResponse\(\)](#)
[processSpeech\(\)](#)
[PropertyConfigurator.configure\(\)](#)
[PropertyUtils.copyProperties\(\)](#)
[PropertyUtils.describe\(\)](#)
[PropertyUtils.getIndex\(\)](#)
[PropertyUtils.getMappedProperty\(\)](#)
[PropertyUtils.getNestedProperty\(\)](#)
[PropertyUtils.getProperty\(\) 2nd](#)
[PropertyUtils.getSimpleProperty\(\)](#)
[PropertyUtils.isReadable\(\)](#)
[PropertyUtils.isWritable\(\)](#)
[PropertyUtils.setProperty\(\)](#)
[put](#)
[putMethod\(\)](#)
[QueryParser.parse\(\)](#)
[random\(\)](#)
[reduce\(\)](#)
[reflectionCompare\(\)](#)
[remove\(\)](#)
[removeAll\(\)](#)
[reset\(\)](#)
[retrieveFile\(\)](#)
[retrieveMessage\(\)](#)
[set\(\)](#)
[setCookiePolicy\(\)](#)
[setCredentials\(\)](#)

- [_setFollowRedirects\(\)](#)
- [_setParameter\(\)](#)
- [_setRequestBody\(\)](#)
- [_setRequestContentLength\(\)](#)
- [_SMTPReply.isPositiveCompletion\(\)](#)
- [_solve\(\)](#)
- [_split\(\)](#)
- [_start\(\)](#)
- [_StopWatch.getTime\(\)](#)
- [_StopWatch.unsplit\(\)](#)
- [_stringAlphanumericIdentifierFactory\(\)](#)
- [_StringUtils.abbreviate\(\)](#)
- [_StringUtils.center\(\)](#)
- [_StringUtils.chomp\(\)](#)
- [_StringUtils.countMatches\(\)](#)
- [_StringUtils.difference\(\)](#)
- [_StringUtils.indexOfDifference\(\)](#)
- [_StringUtils.isBlank\(\)](#)
- [_StringUtils.join\(\)](#)
- [_StringUtils.repeat\(\)](#)
- [_StringUtils.reverse\(\)](#)
- [_StringUtils.split\(\)](#)
- [_StringUtils.trim\(\)](#)
- [_substring\(\)](#)
- [_substringBetween\(\)](#)
- [_subtract\(\)](#)
- [_System.currentTimeMillis\(\)](#)
- [_template.process\(\)](#)
- [_Text\(\)](#)
- [_toMap\(\)](#)
- [_toString\(\)](#)
- [_automation](#)
- [_customization](#)
- [_transform\(\)](#)
- [_trimToNull\(\)](#)
- [_TypedCollection.decorate\(\)](#)
- [_unlockMethod\(\)](#)
- [_Velocity.init\(\)](#)
- [_milliseconds, truncating](#)
- [_MIME \(Multipurpose Internet Main Extensions\)](#)
- [_minutes](#)
- [_rounding](#)
- [_truncating](#)
- [_Model-View-Controller \(MVC\)](#)
- [_modifying WebDav](#)
- [_months](#)
- [_rounding](#)
- [_truncating](#)
- [_multidimensional arrays, mapping](#)
- [_multilevel composite predicate implementation](#)
- [_MultiMap 2nd](#)
- [_MultiMap.remove\(\) method](#)

- [MultipartPostMethod](#)
- [multiple predicates, combining](#)
- [multiple value storage](#)
- [Multipurpose Internet Main Extensions \(MIME\)](#)
- [MultiVariableExpander](#)
- [MVC \(Model-View-Controller\)](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

names

[_bean properties](#)

[_Soundex](#)

[namespace-aware parsing](#)

[NameValuePair](#)

[National Institute of Standards and Technology \(NIST\)](#)

[nested beans](#)

[nested strings, searching](#)

[Netscape Draft Specification](#)

[newlines, deleting](#)

[next\(\) method](#)

[nextInt\(\) method](#)

[nextStringNumericIdentifier\(\) method](#)

[NIST \(National Institute of Standards and Technology\)](#)

[NodeModel object](#)

[NTCredentials object](#)

[null strings, testing](#)

[NullComparator](#)

[_configuration](#)

[NullPointerException](#)

nulls

[_comparing](#)

[_trimming to](#)

[number ranges](#)

[NumberRange](#)

[numeric identifiers](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

objects

- [BeanPredicate](#)
- [closures](#)
 - [chaining](#)
 - [conditional statements with](#)
 - [loops with](#)

Collections

- [ArrayLists](#)
- [bags](#)
- [blocking buffers](#)
- [buffers](#)
- [caches](#)
- [case-insensitive maps](#)
- [casting](#)
- [counting](#)
- [downloading](#)
- [filtering with predicates](#)
- [iteration](#)
- [key by value retrieval](#)
- [lazy maps](#)
- [list constraints](#)
- [loops](#)
- [map value constraints](#)
- [multiple value storage](#)
- [priority queues](#)
- [set operations](#)
- [transformation](#)
- [typed collections](#)

Commons JXPath

- [applying object graphs](#)
- [downloading](#)
- [querying object graphs](#)
- [searching](#)
- [complex numbers](#)
- [conversion](#)
- [customization](#)
- [Documents](#)
- [DynaBean](#)
- [GetMethod](#)
- [JavaBeans, diagramming](#)
- [NodeModel](#)
- [NTCredentials](#)
- [predicates](#)
- [StatUtil](#)
- [TermEnum](#)
- [transformation](#)

[_chaining](#)

[_conditional](#)

[_UsernamePasswordCredentials](#)

[XML](#)

[_converting to](#)

[_customization](#)

[options.addOption\(\) method](#)

[org.apache.commons.io.filefilter package](#)

[ORO](#) [See Jakarta ORO]

[OutputStreams, splitting](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

parameters

[_HTTP POST requests](#)

[_macros](#)

[_queries, sending](#)

[_validation](#)

[parsing](#) [See also [Commons CLI](#)]

[_BasicParser](#)

[_namespace-aware](#)

[_SAX](#)

[_strings](#)

[_XML, variable substitutions](#)

[parts, adding](#)

[PatientPriorityComparator](#)

[Perl5FilenameFilter](#)

[PersonRuleSet](#)

[plain text 2nd](#) [See also [text](#)]

[PlayIndexer](#)

[POP3 \(Post Office Protocol 3\)](#)

[populateInventory\(\) method](#)

populating

[_beans](#)

[_values](#)

[Poseidon](#)

[PostMethod](#)

[PredicatedList](#)

[PredicatedMap](#)

predicates

[_bean validation](#)

[_collections, filtering with](#)

[_Commons Collections](#)

[_combining](#)

[_customization](#)

[_logical expressions](#)

[_searching](#)

[_validation](#)

[primitive array conversion](#)

[printAlbums\(\) method](#)

printing

[_Apache Log4J](#)

[_arrays](#)

[_Commons IO](#)

[_headers](#)

[_Jakarta Velocity](#)

[_strings](#)

[_usage information](#)

[printStuff tag](#)

- [printUsage\(\) method](#)
- [priority queues](#)
- [PriorityBuffer](#)
- [ProcessEstimator class](#)
- [processRedirectResponse\(\) method](#)
- [processSpeech\(\) method](#)
- programming
 - [Commons BeanUtils](#)
 - [Commons Codec](#)
 - [Commons Collections](#)
 - [Jakarta HttpClient](#)
 - [Soundex](#)
- properties
 - [adding](#)
- beans
 - [accessing 2nd](#)
 - [cloning](#)
 - [comparing](#)
 - [copying](#)
 - [indexed access](#)
 - [mapped access](#)
 - [mapping](#)
 - [nested access](#)
 - [setting](#)
 - [strings](#)
 - [testing](#)
 - [types of](#)
 - [validation](#)
 - [wrapping maps](#)
- [configuration](#)
- [expression language](#)
- [global.properties](#)
- [local.properties](#)
- [user.properties](#)
- [PropertyConfigurator.configure\(\) method](#)
- [PropertyUtils.copyProperties\(\) method](#)
- [PropertyUtils.describe\(\) method](#)
- [PropertyUtils.getIndex\(\) method](#)
- [PropertyUtils.getMappedProperty\(\) method](#)
- [PropertyUtils.getNestedProperty\(\) method](#)
- [PropertyUtils.getProperty\(\) method](#)
- [PropertyUtils.getPropertyType\(\) method](#)
- [PropertyUtils.getSimpleProperty\(\) method](#)
- [PropertyUtils.isReadable\(\) method](#)
- [PropertyUtils.isWritable\(\) method](#)
- [PropertyUtils.setProperty\(\) method](#)
- [public static final constants](#)
- [put\(\) method](#)
- [putMethod\(\) method](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

queries

[_Jakarta Lucene](#)

[_object graphs](#)

[QueryParser.parse\(\) method](#)

[queues, priority](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

- [random variables](#)
- [random\(\) method](#)
- [RandomUtils](#)
- [ranges, number](#)
- [read methods](#)
- readers
 - [_closing](#)
 - [_copying](#)
- [RealMatrix](#)
- [recursive deletes, directories](#)
- [redirects, Jakarta HttpClient](#)
- [reduce\(\) method](#)
- [references, variable substitution \(XML\)](#)
- [reflection builders](#)
 - [_compareTo\(\) method](#)
- [reflectionCompare\(\) method](#)
- [ReflectionToStringBuilder class](#)
- [regular expressions](#)
- relationships
 - [_diagramming](#)
 - [_MultiMap](#)
- [remote method invocation \(RMI\)](#)
- [remove\(\) method](#)
- [removeAll\(\) method](#)
- [reset\(\) method](#)
- resources
 - [_mailing lists](#)
 - WebDav
 - [_connections](#)
 - [_modifying](#)
- [response codes, redirects](#)
- [retrieveFile\(\) method](#)
- [retrieveMessage\(\) method](#)
- [retrieving content \(conditional GET method\)](#)
- [ReverseComparator](#)
- reversing
 - [_arrays](#)
 - [_Comparators](#)
 - [_strings](#)
- [RFC 2109](#)
- [RMI \(remote method invocation\)](#)
- [rounding dates](#)
- [rules, XML](#)
- [RuleSetBase](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[SAX parsers](#)

[scripts](#)

[_HTTP POST requests](#)

[_redirect.cgi](#)

[searching](#) [\[See also Jakarta Lucene\]](#)

[_arrays](#)

[Jakarta ORO](#)

[_downloading](#)

[_listing files](#)

[_objects](#)

[_strings](#)

[seconds, rounding](#)

[seconds, truncating](#)

[Secure Sockets Layer](#) [\[See SSL\]](#)

[self-signed certificates](#)

[sending](#)

[_email](#)

[_HTTP POST request files](#)

[_parameters](#)

[_query parameters](#)

[_redirects](#)

[servers](#)

[_authentication](#)

[_cookies](#)

[_FTP](#)

[_HTTP, debugging](#)

[_POP3](#)

[_SMTP](#)

[servlets, HTTP POST requests](#)

[set_operations](#)

[set\(\) method](#)

[setCookiePolicy\(\) method](#)

[setCredentials\(\) method](#)

[setFollowRedirects\(\) method](#)

[setParameter\(\) method](#)

[setRequestBody\(\) method](#)

[setRequestContentLength\(\) method](#)

[setting bean properties](#)

[Simple Mail Transfer Protocol](#) [\[See SMTP\]](#)

[Simple Object Access Protocol](#) [\[See SOAP\]](#)

[SimpleBean](#)

[SimpleDateFormat class](#)

[SimpleRegression 2nd](#)

[sizing](#)

[_directories](#)

[_print files](#)

- [Slide](#) [See Jakarta Slide]
- [SmartDraw](#)
- [SMTP \(Simple Mail Transfer Protocol\)](#)
- [SMTPReply.isPositiveCompletion\(\) method](#)
- [SOAP \(Simple Object Access Protocol\)](#)
- [solve\(\) method](#)
- sorting
 - [_bean properties](#)
 - [_Comparators](#)
- [Soundex](#)
- source code
 - [_Commons BeanUtils](#)
 - [_Commons Codec](#)
 - [_Commons Collections](#)
 - [_Commons Lang](#)
 - [_Jakarta HttpClient](#)
 - [_Soundex](#)
- [specific searches, Jakarta Lucene](#)
- [split\(\) method](#)
- splitting
 - [_OutputStreamsCommons IO](#)
 - [_strings](#)
- [src/java subdirectory](#)
- [src/test subdirectory](#)
- [SSL \(Secure Sockets Layer\)](#)
- [SSLProtocolSocketFactory](#)
- [StandardAnalyzer](#)
- [start\(\) method](#)
- [StatUtil object](#)
- [StatUtils](#)
- [StockQuoteTransformer](#)
- [StopWatch](#)
- [StopWatch.getTime\(\) method](#)
- [StopWatch.unsplit\(\) method](#)
- [storage, expressions](#)
- streams
 - [_closing](#)
 - [_copying](#)
 - [_tracking](#)
- [stringAlphanumericIdentifierFactory\(\) method](#)
- strings
 - [_abbreviating](#)
 - [_beans properties](#)
 - [_built via reflection](#)
 - [_chomping](#)
 - [_closing](#)
 - [_comparing](#)
 - [_copying 2nd](#)
 - [_countryCode](#)
 - [_empty, testing](#)
 - [_measuring frequency](#)
 - [_parsing](#)

- [reversing](#)
- [searching](#)
- [splitting](#)
- [stripping](#)
- [testing](#)
- [trimming](#)

StringUtils class

- [configuration](#)

text

- [abbreviating strings](#)
- [chomping strings](#)
- [comparing strings](#)
- [measuring string frequency](#)
- [parsing strings](#)
- [printing headers](#)
- [reversing strings](#)
- [searching nested strings](#)
- [splitting strings](#)
- [stripping strings](#)
- [testing empty strings](#)
- [testing strings](#)
- [trimming strings](#)

[StringUtils.abbreviate\(\) method](#)

[StringUtils.center\(\) method](#)

[StringUtils.chomp\(\) method](#)

[StringUtils.countMatches\(\) method](#)

[StringUtils.difference\(\) method](#)

[StringUtils.indexOfDifference\(\) method](#)

[StringUtils.isBlank\(\) method](#)

[StringUtils.join\(\) method](#)

[StringUtils.repeat\(\) method](#)

[StringUtils.reverse\(\) method](#)

[StringUtils.split\(\) method](#)

[StringUtils.trim\(\) method](#)

[stripping strings](#)

[Struts JSP tag libraries](#)

[styles](#)

[subdirectories](#) [See also [directories](#)]

- [cleaning](#)

- [src/java](#)

- [src/test](#)

[substring\(\) method](#)

[substringBetween\(\) method](#)

[subtract\(\) method](#)

[SuffixFileFilter instances](#)

[SwitchTransformer](#)

[syntax](#) [See also [code](#)]

- [Jakarta Velocity](#)

[System.currentTimeMillis\(\) method](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

tags

- [_app tag library](#)
- [_email](#)
- [_entity](#)
- [_JSTL](#)
- [_printStuff](#)

[TeeOutputStream](#)

[Telnet](#)

[template.process\(\) method](#)

templating

- [_Eclipse](#)
- [_expression languages](#)
- [_FreeMaker, downloading 2nd](#)
- [_Jakarta Velocity, downloading](#)
- [_macros](#)
- [_Web applications](#)

[term frequency, Jakarta Lucene](#)

[TermEnum object](#)

testing

- [_arrays](#)
- [_bean properties](#)
- [_connections](#)
- [_empty strings](#)
- [_parameters](#)
- [_strings](#)

text

- [_StringUtils class](#)
- [_abbreviating strings](#)
- [_chomping strings](#)
- [_comparing strings](#)
- [_measuring string frequency](#)
- [_parsing strings](#)
- [_printing headers](#)
- [_reversing strings](#)
- [_searching nested strings](#)
- [_splitting strings](#)
- [_stripping strings](#)
- [_testing empty strings](#)
- [_testing strings](#)
- [_trimming strings](#)
- [_WordUtils class](#)
- [_wrapping](#)

[Text\(\) method](#)

[TFTP \(Trivial File Transfer Protocol\)](#)

[Tiger](#)

[time, measuring](#)

- timestamps
 - [_Commons IO](#)
 - [_updating](#)
- [toMap\(\) method](#)
- tools
 - [_Eclipse](#)
 - [_randomUtils](#)
 - [_StatUtils](#)
 - [_UML editors](#)
 - [_VelocityTools](#)
- toString() methods
 - [_automation](#)
 - [_customization](#)
- [ToStringBuilder class 2nd 3rd](#)
- [ToStringStyle class customization](#)
- tracking
 - [_cookies](#)
- traffic
 - [_Commons IO](#)
 - [_tracking](#)
- [trailing newlines, deleting](#)
- [transform\(\) method](#)
- transformation
 - [_beans](#)
 - [_collections](#)
 - [_objects](#)
 - [_chaining](#)
 - [_conditional](#)
- [translation, arrays](#)
- [trimming strings](#)
- [trimToNull\(\) method](#)
- [Trivial File Transfer Protocol](#) [See TFTP]
- [troubleshooting mailing lists](#)
- [truncating dates](#)
- [typed collections](#)
- [TypedCollection.decorate\(\) method](#)
- [types of bean properties](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

UML (Unified Modeling Language)

[_diagrams](#)

[_editors](#)

[UnboundedFifoBuffer](#)

[Unified Modeling Language](#) [See UML]

[uniform resource locators](#) [See URLs]

[unions, collections](#)

[unique alphanumeric identifiers](#)

[unique numeric identifiers](#)

[UniqueFilterIterator](#)

[univariate statistic calculations](#)

[Universal Unique Identifier](#) [See UUID]

[unlockMethod\(\) method](#)

[updating timestamps](#)

[uploading files](#)

URLs (uniform resource locators)

[_copying](#)

[_Jakarta HttpClient](#)

[_SSL](#)

[user.properties](#)

[UsernamePasswordCredentials object](#)

utilities

[_Eclipse](#)

[_RandomUtils](#)

[_StatUtils](#)

[_VelocityTools](#)

[UUID \(Universal Unique Identifier\)](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

validation

[_bean properties](#)

[_parameters](#)

[_predicates](#)

[ValuedEnum, extending](#)

values

[_Boolean](#)

[_case-insensitive maps](#)

[_casting](#)

[_key by value retrieval](#)

[_map constraints](#)

[_multiple value storage](#)

[_populating](#)

[_UUID](#)

variables

[_Boolean](#)

[_expression language](#)

[_inventoryBag](#)

[_random](#)

[_substitution \(XML\)](#)

[VariableSubstitutor](#)

[Velocity](#) [See Jakarta Velocity]

[Velocity.init\(\) method](#)

[VelocityContext 2nd](#)

[VelocityEngine 2nd](#)

[VelocityStruts](#)

[VelocityTools](#)

[viewing source code](#)

[Virtual Machine Identifier](#) [See VMID]

[VMID \(Virtual Machine Identifier\)](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[Web applications, templating](#)

WebDav

[_connections](#)

[_Jakarta Slide, downloading](#)

[_modifying](#)

whitespace

[_stripping](#)

[_trimming](#)

[words](#) [See also [text](#)]

[_Soundex](#)

[_wrapping](#)

WordUtils class

[_configuration](#)

[_text, wrapping](#)

[World Wide Web \(WWW\)](#)

wrapping

[_bean properties](#)

[_words](#)

[write methods](#)

writers

[_closing](#)

[_copying](#)

[WWW-Authenticate header](#)

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[Xalan](#)

[XML \(Extensible Markup Language\)](#)

[beans 2nd](#)

[Commons Betwixt](#)

[Commons Configuration](#)

[Commons Digester, downloading](#)

[documents](#)

[_commands](#)

[_converting to objects](#)

[_namespace-aware parsing](#)

[Jakarta Lucene](#)

[Log4J](#)

[object customization](#)

[parsing](#)

[rules](#)

[XML Path Language](#) [See XPath]

[XPath \(XML Path Language\) 2nd](#) [See also Commons JXPath]

[\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[X\]](#) [\[Y\]](#)

[years, rounding](#)