

## Swing Hacks

By Chris Adamson, Joshua Marinacci

.....  
Publisher: O'Reilly

Pub Date: June 2005

ISBN: 0-596-00907-0

Pages: 542

[Table of Contents](#) | [Index](#)

## Overview

*Swing Hacks* helps Java developers move beyond the basics of Swing, the graphical user interface (GUI) standard since Java 2. If you're a Java developer looking to build enterprise applications with a first-class look and feel, Swing is definitely one skill you need to master. This latest title from O'Reilly is a reference to the cool stuff in Swing. It's about the interesting things you learn over the years--creative, original, even weird hacks--the things that make you say, "I didn't know you could even do that with Swing!"


*Swing Hacks* will show you how to extend Swing's rich component set in advanced and sometimes non-obvious ways. The book touches upon the entire Swing gamut--tables, trees, sliders, spinners, progress bars, internal frames, and text components. Detail is also provided on JTable/JTree, threaded component models, and translucent windows. You'll learn how to filter lists, power-up trees and tables, and add drag-and-drop support.

*Swing Hacks* will show you how to do fun things that will directly enhance your own applications. Some are visual enhancements to make your software look better. Some are functional improvements to make your software do something it couldn't do before. Some are even just plain silly, in print only to prove it could be done. The book will also give you a small glimpse of the applications coming in the future. New technology is streaming into the Java community at a blistering rate, and it gives application developers a whole new set of blocks to play with.

With its profusion of tips and tricks, *Swing Hacks* isn't just for the developer who wants to build a better user interface. It's also ideally suited for client-side Java developers who want to deliver polished applications, enthusiasts who want to push Java client application boundaries, and coders who want to bring powerful techniques to their own applications.

Whatever your programming needs, *Swing Hacks* is packed with programming lessons that increase your competency with interface-building tools.

← PREV



## Swing Hacks

By Chris Adamson, Joshua Marinacci

.....  
Publisher: O'Reilly

Pub Date: June 2005

ISBN: 0-596-00907-0

Pages: 542

[Table of Contents](#) | [Index](#)

— [Credits](#)

— [About the Authors](#)

— [Contributors](#)

— [Acknowledgments](#)

— [Preface](#)

— [Why Swing Hacks?](#)

— [How to Use This Book](#)

— [How This Book Is Organized](#)

— [Conventions Used in This Book](#)

— [Using Code Examples](#)

— [How to Contact Us](#)

— [Got a Hack?](#)

— [Safari Enabled](#)

— [Chapter 1. Basic JComponents](#)

— [Section 1.1. Hacks 112: Introduction](#)

— [Hack 1. Create Image-Themed Components](#)

— [Hack 2. Don't Settle for Boring Text Labels](#)

— [Hack 3. Fill Your Borders with Pretty Pictures](#)

— [Hack 4. Display Dates in a Custom Calendar](#)

— [Hack 5. Add a Watermark to a Text Component](#)

— [Hack 6. Watermark Your Scroll Panes](#)

— [Hack 7. Put a NASA Photo into the Background of a Text Area](#)

— [Hack 8. Animate Transitions Between Tabs](#)

— [Hack 9. Blur Disabled Components](#)

— [Hack 10. Building a Drop-Down Menu Button](#)

— [Hack 11. Create Menus with Drop Shadows](#)

— [Hack 12. Add Translucence to Menus](#)

— [Chapter 2. Lists and Combos](#)

— [Section 2.1. Hacks 1320: Introduction](#)

— [Hack 13. Filter JLists](#)

— [Hack 14. Add a Filter History](#)

— [Hack 15. Make JLists Checkable](#)

— [Hack 16. Make Different List Items Look Different](#)

- [Hack 17. Reorder a JList with Drag-and-Drop](#)
- [Hack 18. Animate Your JList Selections](#)
- [Hack 19. Turn Methods into List Renderers](#)
- [Hack 20. Create a Collections-Aware JComboBox](#)
- [Chapter 3. Tables and Trees](#)
  - [Section 3.1. Hacks 2127: Introduction](#)
  - [Hack 21. Size Your Columns to Suit Your JTable's Contents](#)
  - [Hack 22. Add Column Selection to JTables](#)
  - [Hack 23. Let Your JTables Do the Sorting](#)
  - [Hack 24. Create a JDBC Table Model](#)
  - [Hack 25. Export Table Data to an Excel Spreadsheet](#)
  - [Hack 26. Search Through JTables Easily](#)
  - [Hack 27. Animate JTree Drops](#)
- [Chapter 4. File Choosers](#)
  - [Section 4.1. Hacks 2832: Introduction](#)
  - [Hack 28. Add a Right-Click Context Menu to the JFileChooser](#)
  - [Hack 29. Display Shortcuts in the JFileChooser](#)
  - [Hack 30. Real Windows Shortcut Support](#)
  - [Hack 31. Add Image Preview to File Choosers](#)
  - [Hack 32. Preview ZIP and JAR Files](#)
- [Chapter 5. Windows, Dialogs, and Frames](#)
  - [Section 5.1. Hacks 3340: Introduction](#)
  - [Hack 33. Window Snapping](#)
  - [Hack 34. Make a Draggable Window](#)
  - [Hack 35. Add Windows Resize Icons](#)
  - [Hack 36. Add Status Bars to Windows](#)
  - [Hack 37. Save Window Settings](#)
  - [Hack 38. Earthquake Dialog](#)
  - [Hack 39. Spin Open a Detail Pane](#)
  - [Hack 40. Minimize to a Mini-Frame](#)
- [Chapter 6. Transparent and Animated Windows](#)
  - [Section 6.1. Hacks 4147: Introduction](#)
  - [Hack 41. Transparent Windows](#)
  - [Hack 42. Make Your Frame Dissolve](#)
  - [Hack 43. Create Custom Tool Tips](#)
  - [Hack 44. Turn Dialogs into Frame-Anchored Sheets](#)
  - [Hack 45. Animating a Sheet Dialog](#)
  - [Hack 46. Slide Notes Out from the Taskbar](#)
  - [Hack 47. Indefinite Progress Indicator](#)
- [Chapter 7. Text](#)
  - [Section 7.1. Hacks 4855: Introduction](#)
  - [Hack 48. Make Text Components Searchable](#)
  - [Hack 49. Force Text Input into Specific Formats](#)
  - [Hack 50. Auto-Completing Text Fields](#)
  - [Hack 51. Write Backward Text](#)
  - [Hack 52. Use HTML and CSS in Text Components](#)

- [Hack 53. Use Global Anti-Aliased Fonts](#)
- [Hack 54. Anti-Aliased Text Without Code](#)
- [Hack 55. Anti-Aliased Text with a Custom Look and Feel](#)
- [Chapter 8. Rendering](#)
  - [Section 8.1. Hacks 5664: Introduction](#)
  - [Hack 56. Create a Magnifying Glass Component](#)
  - [Hack 57. Create a Global Right-Click](#)
  - [Hack 58. Block a Window Without a Modal Dialog](#)
  - [Hack 59. Create a Color Eyedropper](#)
  - [Hack 60. Changing Fonts Throughout Your Application](#)
  - [Hack 61. Load New Fonts at Runtime](#)
  - [Hack 62. Build a Colorful Vector-Based Button](#)
  - [Hack 63. Add a Third Dimension to Swing](#)
  - [Hack 64. Turn the Spotlight on Swing](#)
- [Chapter 9. Drag-and-Drop](#)
  - [Section 9.1. Hacks 6569: Introduction](#)
  - [Hack 65. Drag-and-Drop with Files](#)
  - [Hack 66. Handle Dropped URLs](#)
  - [Hack 67. Handle Dropped Images](#)
  - [Hack 68. Handling Dropped Picts on Mac OS X](#)
  - [Hack 69. Translucent Drag-and-Drop](#)
- [Chapter 10. Audio](#)
  - [Section 10.1. Hacks 7078: Introduction](#)
  - [Hack 70. Play a Sound in an Applet](#)
  - [Hack 71. Play a Sound with JavaSound](#)
  - [Hack 72. Play a Sound with Java Media Framework](#)
  - [Hack 73. Play a Sound with QuickTime for Java](#)
  - [Hack 74. Add MP3 Support to JMF](#)
  - [Hack 75. Build an Audio Waveform Display](#)
  - [Hack 76. Play Non-Trivial Audio](#)
  - [Hack 77. Show Audio Information While Playing SoundHack](#)
  - [Hack 78. Provide Audio Controls During Playback](#)
- [Chapter 11. Native Integration and Packaging](#)
  - [Section 11.1. Hacks 7987: Introduction](#)
  - [Hack 79. Launch External Programs on Windows](#)
  - [Hack 80. Open Files, Directories, and URLs on Mac OS X](#)
  - [Hack 81. Make Mac Applications Behave Normally](#)
  - [Hack 82. Control iTunes on Mac OS X](#)
  - [Hack 83. Control iTunes Under Windows](#)
  - [Hack 84. Construct Single-Launch Applications](#)
  - [Hack 85. Stuff Stuff in JARs](#)
  - [Hack 86. Make Quick Look and Feel Changes](#)
  - [Hack 87. Create an Inverse Black-and-White Theme](#)
- [Chapter 12. Miscellany](#)
  - [Section 12.1. Hacks 88100: Introduction](#)
  - [Hack 88. Display a Busy Cursor](#)

- [Hack 89. Fun with Keyboard Lights](#)
- [Hack 90. Create Demonstrations with the Robot Class](#)
- [Hack 91. Check Your Mail with Swing](#)
- [Hack 92. Don't Block the GUI](#)
- [Hack 93. Code Models That Don't Block](#)
- [Hack 94. Fire Events and Stay Bug Free](#)
- [Hack 95. Debug Your GUI](#)
- [Hack 96. Debug Components with a Custom Glass Pane](#)
- [Hack 97. Mirror an Application](#)
- [Hack 98. Add Velocity for Dynamic HTML](#)
- [Hack 99. Get Large File Icons](#)
- [Hack 100. Make Frames Resize Dynamically](#)
- [Colophon](#)
- [Index](#)

[← PREV](#)

[← PREV](#)

# Credits

[About the Authors](#)

[Contributors](#)

[Acknowledgments](#)

[← PREV](#)

## About the Authors

Joshua Marinacci started playing with Java in the summer of '95 at the request of his favorite TA and has never looked back. Since then he has built all manner of Java software for clients ranging from large Fortune 500 companies to small Internet startups. He quickly discovered his passion for user interfaces and client software, building a reputation in the desktop Java world and finally joining the Swing Team at Sun in the spring of 2005. In his spare time, Joshua writes articles and weblogs for Java.net while contributing to the JDIC, JDNC, and WinLAF open source projects. He also heads up Flying Saucer, an open source, all-Java XHTML renderer. This is his first book, but hopefully not his last. He lives in historic East Atlanta with his girlfriend Kim and their yellow labrador Eliza.

Chris Adamson is the Editor of O'Reilly's ONJava site and the Associate Online Editor for Java.net, a collaboration of O'Reilly, Sun Microsystems, and CollabNet. He also writes about Java and Mac topics online and speaks at conferences such as ADHOC/MacHack and the O'Reilly Mac OS X Conference. He develops media applications under the guise of his consulting company, Subsequently & Furthermore Inc. He has an M.A. in Telecommunications from Michigan State University and a B.A. in English and B.S. in Symbolic Systems from Stanford University. He lives in Atlanta with his wife, Kelly, and their children, Keagan and Quinn, and he has thus far managed to own seven and a half Macs.

## Contributors

Swing is big enough that surely everyone who works with it takes away some new ideas for how to hack it. Our contributors helped flesh this book out with hacks that blew us away and that we're sure you'll like, too.

- Romain Guy is a French student currently working as an intern with the Swing Team at Sun Microsystems in California. He discovered Java in 1998 and contributed to the Open Source/Freeware Software community with Jext, a Java source code editor he developed over five years. He is also a freelance journalist for *Login*, a French computing magazine. Never short for ideas, he also wrote for *Javalobby*, the Java developer's journal, and a couple of French magazines. Romain seeks for other experiences whenever he can: he works as a translator for O'Reilly France, he taught Java in a French university, he fulfilled several missions as a freelance Java developer, and he even worked as a video game programmer. Today, Romain focuses on UI design and humane interaction. He shares his work on his weblog: [www.jroller.com/page/gfx](http://www.jroller.com/page/gfx).
- Jonathan Simon is a comprehensive client-side expert, designing and developing mission-critical financial trading clients for Wall Street investment banks. This requires a fluid combination of business and task analysis and interaction design with the intricacies of Java rich-client development to create content rich, ergonomic trading applications. He has written extensively about his experiences for Java.net, IBM DeveloperWorks, JavaWorld, and Addison Wesley. An avid percussionist, composer, and electronic musician, Jonathan also develops music software in Java. He is especially interested in interaction design and data visualization.



# Acknowledgments

## Joshua

This book has gone faster than I ever imagined, from original concept to final draft in less than a year. Writing *Swing Hacks* was harder than I ever thought, giving me great respect for those who write complete novels. I have had the utmost fun, however, and wouldn't trade the experience for the world.

I would first like to thank Kimi, my loving partner who convinced me to pursue writing as a serious endeavor. She has always believed that I could be more than just a contract coder. I couldn't have done it without you, Sweetie.

Many thanks to my family and friends who always said that I was never living up to my potential. Thank you for raising, loving, and teaching me. I promise to live up to my potential now, starting next week.

Thanks to the great team at O'Reilly, especially Brett, who tirelessly read through my drafts, dotted the *z*s, crossed the *s*s, and made my prose readable.

Thanks go out to the readers of Java.net and Daniel Steinberg, my Java.net editor, who have always provided encouragement, feedback, and constructive criticism. Without the Java community's ecology of code and fresh ideas, this book wouldn't have been possible.

Special thanks to Jonathan and Romain who gave us the boost we needed to get the book finished. They've put in some great stuff. *I've* even learned a few things.

Extra special thanks to Chris who believed from the start that this was a great idea for a book. He guided me through the proposal process, shaped our draft, and always kept the book on track. Maybe we can finally get that Okama GameSphere.

And, finally, my unending thanks to all of the Swing Team developers who put in 10 years of blood and sweat, making Swing the powerful toolkit it is today. I hope we can keep pushing it forward.

## Chris

Credit for this book needs to begin with Joshua! I'm still tempted to type "Joshy" because that's his username everywhere who started this book as an informal series on his popular Java.net weblog and had the wherewithal to push through a book proposal.

Also, all the really cool hacks are his. But I think that's what everyone involved with this book has been saying when they read what the others have contributed.

And speaking of them, thanks also to our contributors, Romain and Jonathan, who came in at just

the right time to get this book over the hump and make it real. Their inventiveness and responsiveness helped us pull through.

Thanks to Brett McLaughlin, who was on the receiving end of a pretty wild brain-dump, with two authors and two contributors going on wildly different tangents. He helped shape this book into something readable and fun.

Lots of other people in O'Reilly production will handle this book after I finish writing this acknowledgment, and I thank them in advance for everything they do.

And, of course, thanks to Kelly and Keagan for holding down the fort at home while daddy was in the office working on this book. Quinn also contributed, sleeping on my lap while I banged out parts of [Chapters 10](#) and [11](#).

Obligatory O'Reilly tune check: this time it was Delgados, The Tubes, Green Day, L'Arc~en~Ciel, David Bowie, Frank Zappa, Puffy AmiYumi, Little Feat, the *Gundam Wing Endless Waltz* soundtrack and the *Armitage's Dimension* stream.

 PREVIOUS

# Preface

Hi, welcome to *Swing Hacks*! This book is a reference, but not a complete reference of the Swing API. We already have that. It's called *Java Swing*, is published by O'Reilly, and weighs in at over 1,200 pages. It's available for purchase at fine bookstores and Russian black market web sites everywhere. We're not saying that it isn't a great book. It's fantastic! We've owned many weathered copies over the years. The problem is...it's huge! This isn't really the book's fault: Swing *itself* is huge. I once saw an API diagram that took an entire 30-inch poster. Swing is powerful, but it takes a long time to explore fully, simply because it *is* so big. That's not what this book is about.

This book is a reference to the cool stuff. It's about the interesting things you learn over the years. The weird hacks that make you say, "I didn't know you could even *do* that!" After years of working with Swing, you start to learn what the API is good at and what it lacks. Some days you learn something that makes your life as a developer easier, a way to do something quicker than the standard route. That's what we put into this book. Some days you learn a workaround for a long-standing bug or a missing feature that you've been dying to have. We put that stuff in the book, too. Sometimes it's something fun and interesting API that makes us think, "Well, if we were *evil* what could we do with it?" This is usually followed by the pinkie up to the mouth and cackling that can be heard outside our underground lair. After much consultation with lawyers and gods, we slipped some of these into the book, too.

## Why Swing Hacks?

The term *hacking* has a bad reputation in the press. They use it to refer to people who break into systems or wreak havoc with computers as their weapon. Among people who write code, though, the term *hack* refers to a quick-and-dirty solution to a problem, or a clever way to get something done. And the term *hacker* is taken very much as a compliment, referring to someone as being *creative*, having the technical chops to get things done. The Hacks series is an attempt to reclaim the word, document the good ways people are hacking, and pass the hacker ethic of creative participation on to the uninitiated. Seeing how others approach systems and problems is often the quickest way to learn about a new technology.

In the short term, we hope this book will show you how to do fun things that will enhance your own applications directly. Some are visual enhancements to make your software look better. Some are functional improvements to make your software do something it couldn't do before. Some are even just plain silly, in print only to prove it could be done. Whatever your interest, we hope you will find both better ways of doing old things and learn something new about techniques you never even thought of.

In the long term, we hope this book will give you a small glimpse of the applications coming in the future. This year (2005) we hope will be a watershed year for Java on the desktop. Users are demanding more advanced user interfaces than the Web can provide, and Java is poised to provide them. New technology is streaming into the Java community at a blistering rate, and it gives application developers a whole new set of blocks to play with. This is important because we are going to need these new technologies.

New desktop software promises greater integration between the Web, external devices, and software sitting right on your desktop. RSS readers and iPods. iTunes and photo collaboration. Gaming on desktops, servers, and cell phones; *all at the same time*. This is the future of desktop software. Swing is just a small part of desktop Java, but we feel it is the focal point the place where desktop technology (AWT, Java2D, JavaSound), network technology (web services, XML, JXTA), and device technology (iPods, cell phones, TVs) all converge upon Java. Many of the hacks in this book are not strictly about Swing, but about using Swing to do cool things with the rest of the world. And it's more than just "cool" animation is a powerful way to show a change in content or context, and sound can get the user's attention when he or she is away from the keyboard. These features are important parts of delivering user-centric, quality desktop applications.

## How to Use This Book

You can read this book from cover to cover if you like, but each hack stands on its own, so feel free to browse and jump to the different sections that interest you most. If there's a prerequisite you need to know about, a crossreference will guide you to the right hack. The code all works (we tried it but in case you can't get a hack to work, let us know at the book's web site:

<http://www.oreilly.com/catalog/swinghks>. You can also download the book's code online, or contribute your own tips and tricks. If we collect enough new material, and this book sells more than 10 copies, then the publishers might let us make *Swing Hacks 2: The Endless Repaint*.

With few exceptions, the hacks in this book were written for Java 2 Standard Edition (J2SE), version 1.4, which you can get from <http://java.sun.com/j2se/>. A few hacks depend on open source packages, which are freely downloadable from their home pages, as described in the hack itself. The only exceptions are two hacks that use QuickTime for Java, which is freely available from Apple (and installed by default on Mac OS X), but it is proprietary and available for Mac and Windows only.

Because this is a book about Swing, the program listings will be using the classes from the Swing and AWT packages, so we've skipped `import javax.swing.*` and `import java.awt.*` statements for space. You can also assume that any listing involving event handling will `import java.awt.event.*` and probably `import javax.swing.event.*` as well. Java2D hacks implicitly `import java.awt.image.*`. In short, we'll include import statements only when a hack involves non-core, and/or non-obvious imports, like the hacks that use JDBC, Lucene, Velocity, QuickTime for Java, etc.

## How This Book Is Organized

The book is divided into several chapters, organized by subject:

### [Chapter 1](#), *Basic JComponents*

Here you'll find simple hacks for the basic components like labels, buttons, and text fields. This chapter contains a lot of bang for the buck, and it illustrates some of the techniques that we will explore more fully later on. From fancy JLabels to translucent menus, this is a great place to start.

### [Chapter 2](#), *Lists and Combos*

This chapter features complicated Swing components that are used everywhere. Bend them to your will! Make them look good with polymorphic renderers and animated selections. Make them perform well with filtering and Collections support.

### [Chapter 3](#), *Tables and Trees*

This chapter reveals the secrets of these mystic components from Excel exporting to proper JTree drop targets. Make the JTree and JTable dance.

### [Chapter 4](#), *File Choosers*

One of Swing's most maligned components, the JFileChooser, actually has a lot of power hiding inside some murky APIs. This chapter will let you use custom icons, detect Windows shortcuts, and even navigate ZIP files.

### [Chapter 5](#), *Windows, Dialogs, and Frames*

This is where the fun begins. Every application needs a container, so why not make it pretty and powerful? Make your windows drag and snap. Build custom windows like the earthquake login and spin open dialog. You can even save your window settings automatically with almost no code changes.

### [Chapter 6](#), *Transparent and Animated Windows*

If you went through the previous chapter and still want more, then this chapter is for you. We push windows to the limit with transparency, animations, slide-in OS X stylesheets, and some of the coolest special effects you've ever seen.

### [Chapter 7](#), *Text*

Text components seem boring, but there's a lot of power hiding in there. This chapter will show you how to do regular expression searching, dot completion, backward text, and even three different ways to give your application the bright sheen of anti-aliasing.

### [Chapter 8](#), *Rendering*

This chapter has the meat of the graphics hacks. Custom fonts, a magnifying glass, vector buttons, and even some work with Java3D. We've got some great things to make your application pop.

### [Chapter 9](#), *Drag-and-Drop*

When your users want two pieces of software to work together the first thing they want to do is drag-and-drop data from their other programs to yours. This chapter covers how to do robust and attractive drag-and-drop entirely within Java.

### [Chapter 10](#), *Audio*

What would be a cool modern application without some media support? This chapter covers four different ways to play sound, how to display waveforms, and how to embed MP3 support in your own programs.

### [Chapter 11](#), *Native Integration and Packaging*

The best software works well with the native operating system. Here you'll learn how to launch web browsers, hack the Windows registry, customize your program for specific platforms, and even control iTunes.

### [Chapter 12](#), *Miscellany*

This chapter offers a grab bag of things that didn't fit anywhere else, but were too cool not to include. Animated cursors, better threading, flashing the keyboard lights, and a bunch of quick one-liners to let you make the most of your busy day.

## Conventions Used in This Book

The following is a list of the typographical conventions used in this book:

### *Italics*

Used to indicate URLs, filenames, filename extensions, and directory/ folder names. A path in the filesystem will appear as */Developer/Applications*, for example.

### Constant width

Used to show code examples, the contents of files, and console output, as well as the names of variables, commands, and other code excerpts.

### Constant width bold

Used to highlight portions of code, typically new additions to old code.

### Constant width italic

Used in code examples and tables to show sample text to be replaced with your own values.

### color

The second color is used to indicate a cross-reference within the text.


You should pay special attention to notes set apart from the text with the following icons:

This is a tip, suggestion, or general note. It contains useful supplementary information about the topic at hand.


This is a warning or note of caution, often indicating that your money or your privacy might be at risk.

The thermometer icons, found next to each hack, indicate the relative complexity of the hack:






beginner



moderate



expert

← PREV

← PREV

## Using Code Examples

This book is here to help you get your job done. In general, you may use the code in this book in your programs and documentation. You do not need to contact us for permission unless you're reproducing a significant portion of the code. For example, writing a program that uses several chunks of code from this book does not require permission. Selling or distributing a CD-ROM of examples from O'Reilly books *does* require permission. Answering a question by citing this book and quoting example code does not require permission. Incorporating a significant amount of example code from this book into your product's documentation *does* require permission.

We appreciate, but do not require, attribution. An attribution usually includes the title, author, publisher, and ISBN. For example: "*Swing Hacks* by Joshua Marinacci and Chris Adamson. Copyright 2005 O'Reilly Media, Inc., 0-596-00907-0."

If you feel your use of code examples falls outside fair use or the permission given above, feel free to contact us at [permissions@oreilly.com](mailto:permissions@oreilly.com).

← PREV

## How to Contact Us

We have tested and verified the information in this book to the best of our ability, but you may find that features have changed (or even that we have made mistakes!). As a reader of this book, you can help us to improve future editions by sending us your feedback. Please let us know about any errors, inaccuracies, bugs, misleading or confusing statements, and typos that you find anywhere in this book.

Please also let us know what we can do to make this book more useful to you. We take your comments seriously and will try to incorporate reasonable suggestions into future editions. You can write to us at:

O'Reilly Media, Inc.  
1005 Gravenstein Highway North  
Sebastopol, CA 95472  
(800) 998-9938 (in the U.S. or Canada)  
(707) 829-0515 (international/local)  
(707) 829-0104 (fax)

To ask technical questions or to comment on the book, send email to:

[bookquestions@oreilly.com](mailto:bookquestions@oreilly.com)

The web site for *Swing Hacks* lists examples, errata, and plans for future editions. You can find this page at:

<http://www.oreilly.com/catalog/swinghks>

For more information about this book and others, see the O'Reilly web site:

<http://www.oreilly.com>



## Got a Hack?

To explore Hacks books online or to contribute a hack for future titles, visit:

<http://hacks.oreilly.com>



← PREY

## Safari Enabled



When you see a Safari® Enabled icon on the cover of your favorite technology book, that means the book is available online through the O'Reilly Network Safari Bookshelf.

Safari offers a solution that's better than e-books. It's a virtual library that lets you easily search thousands of top tech books, cut and paste code samples, download chapters, and find quick answer: when you need the most accurate, current information. Try it for free at <http://safari.oreilly.com>.

← PREY

# Chapter 1. Basic JComponents

[Section 1.1. Hacks 112: Introduction](#)

[Hack 1. Create Image-Themed Components](#)

[Hack 2. Don't Settle for Boring Text Labels](#)

[Hack 3. Fill Your Borders with Pretty Pictures](#)

[Hack 4. Display Dates in a Custom Calendar](#)

[Hack 5. Add a Watermark to a Text Component](#)

[Hack 6. Watermark Your Scroll Panes](#)

[Hack 7. Put a NASA Photo into the Background of a Text Area](#)

[Hack 8. Animate Transitions Between Tabs](#)

[Hack 9. Blur Disabled Components](#)

[Hack 10. Building a Drop-Down Menu Button](#)

[Hack 11. Create Menus with Drop Shadows](#)

[Hack 12. Add Translucence to Menus](#)



## 1.1. Hacks 112: Introduction

Swing is a powerful toolkit, filled to the brim with complicated components, extension APIs, and large Model-View-Controller (MVC) systems. It can be quite daunting. The current edition of O'Reilly's *Java Swing* book now stretches over 1,200 pages! Swing now extends from the simplest `JButton` to the full Look and Feel API. I am still amazed at the power and flexibility of Swing, and quite aware of its complexity. Some of the more esoteric parts can take years to master. However, you don't need to go straight into the `JTree` or Look and Feel APIs just to do something cool. There are still a lot of fun things waiting in the standard components we don't always think about.

This chapter covers some of the basic components that every Swing developer uses: buttons, labels, menus, and the occasional scroll pane. From this base you will learn how to create image buttons, put watermarks into your text areas, and even build a new component or two. These are the components that seem boring, but with a little imagination, they can do a whole lot, and the techniques here lay the foundation for even more exciting hacks later in the book.

## Hack 1. Create Image-Themed Components



This hack shows how to use Swing's built-in image support to create a completely custom image-based user interface.

Most Swing applications get their look from a Look and Feel (L&F) either a standard one provided by the VM or a custom one. L&Fs are a whole lot of work to build and still aren't completely custom. You can redefine a button to look like red stoplights, but then all buttons throughout your application will look like red stoplights. Sometimes all you really want is a look built entirely out of images, much like image-based web navigation.

To give you an idea of where this hack is going, [Figure 1-1](#) shows our target: a frame with a panel containing a label, a button, and a checkbox. The panel, label, and button will be completely drawn with images, using none of the standard L&F. The checkbox will be a standard checkbox, but it should be transparent to fit in with the image background.

Figure 1-1. A component rendered with images

The first step toward image nirvana is the background. Because this type of component is quite reusable, I built a subclass of `JPanel` called `ImagePanel`, shown in [Example 1-1](#).

### Example 1-1. A Custom subclass of JPanel

```
public class ImagePanel extends JPanel {  
    private Image img;
```




```

public ImagePanel(Image img) {
    this.img = img;
    Dimension size = new Dimension(img.getWidth(null),
        img.getHeight(null));
    setSize(size);
    setPreferredSize(size);
    setMinimumSize(size);
    setMaximumSize(size);
    setLayout(null);
}
}

```

The constructor takes the image to draw and saves it for later use in the `img` variable. Then it calls `setSize()` and `setPreferredSize()` with the size of the image. This ensures that the panel will be the size of the image exactly. I had to set the preferred, maximum, and minimum sizes as well this is because the panel's parent and children may not be using absolute layouts.



*Absolute layout* means that there is no layout manager to position the components appropriately (which can be set by calling `setLayout(null)`).

In this case, the explicit size and position will be used (via `setSize()` and `setLocation()`). When a layout manager is set, the preferred, minimum, and maximum sizes may be used. To cover all of the bases, simply set all four values to the image size.

Now that the panel is sized appropriately, you can paint the image by overriding `paintComponent()`:

```

public void paintComponent(Graphics g) {
    g.drawImage(img, 0, 0, null);
}

```

It's important to override `paintComponent()` instead of `paint()`, or else the child components won't get drawn.

To test it, [Example 1-2](#) uses an `ImagePanel` and the usual `JFrame`.

## Example 1-2. Testing out image-based panels

```
public class ImageTest {  
  
    public static void main(String[] args) {  
        ImagePanel panel = new ImagePanel(new  
            ImageIcon("images/background.png").getImage());  
  
        JFrame frame = new JFrame("Hack #1: Create Image-Themed Components");  
        frame.getContentPane().add(panel);  
        frame.pack();  
        frame.setVisible(true);  
  
    }  
}
```

When run, the ImageTest program looks like [Figure 1-2](#).

Now that the background is done, it's time to focus on the label, Activate Reactor. This is just a static image that sits at a certain position on the background. You could use another `ImagePanel`, but since the Activate Reactor text is logically a `JLabel`, you can just create an `ImageLabel` subclass, as shown in [Example 1-3](#).

Figure 1-2. Background only

### Example 1-3. An image-based label

```
public class ImageLabel extends JLabel {  
  
    public ImageLabel(ImageIcon icon) {  
        setSize(icon.getImage().getWidth(null),  
            icon.getImage().getHeight(null));  
        setIcon(icon);  
        setIconTextGap(0);  
        setBorder(null);  
    }  
}
```

```
        setText(null);  
        setOpaque(false);  
    }  
  
}
```

As with the `ImagePanel`, set the size of the label to match the size of the image. The rest of the sizing isn't needed because the `JLabel` will take care of that itself. Next, set the icon to your image, which lets the `JLabel` take care of the image drawing. Setting the icon text gap to zero and the border and text to `null` will remove any extra space around my image, resulting in a perfect mesh with the background. The final `setOpaque(false)` tells the label not to draw its own background. If your image fills the label then this won't matter, but if the image has transparent areas (as PNG files often do), then this will let the background shine through the transparent parts.

Add this code to `ImageTest`'s `main()` method:

```
ImageLabel label = new ImageLabel(new ImageIcon("images/reactor.png"));  
label.setLocation(29,37);  
panel.add(label);
```

The result is shown in [Figure 1-3](#).

Figure 1-3. A custom JLabel

Next comes the button. Because buttons have rollovers and states, they are a bit trickier. Again, start with a `JButton` subclass, as in [Example 1-4](#).

Example 1-4. Creating an image-based button

```
public class ImageButton extends JButton {
    public ImageButton(ImageIcon icon) {
        setSize(icon.getImage().getWidth(null),
            icon.getImage().getHeight(null));
        setIcon(icon);
        setMargin(new Insets(0,0,0,0));
        setIconTextGap(0);
        setBorderPainted(false);
        setBorder(null);
        setText(null);
    }
}
```

The code is almost the same as `JLabel`. The only difference is the addition of the `setMargin()` and `setBorder()` calls. Most Look and Feels use a border and margin to indicate when the button has been selected. Labels aren't selectable so they don't have those methods. In any case, these are two more properties you can simply turn off.

Add this code to `ImageTest`'s `main()` method:

```
final ImageButton button = new ImageButton("images/button.png");
button.setLocation(60,74);
panel.add(button);
```

The result is shown in [Figure 1-4](#).

Figure 1-4. Image button

Now that the button is visible, you only have to add the rollovers and other states. Fortunately, this doesn't require any new coding in the subclass `JButton` already provides support for images

representing the rollover, pressed, selected, disabled, and disabled selected states. You can add various states by using normal set methods:

```
button.setPressedIcon(new ImageIcon("images/button-down.png"));
button.setRolloverIcon(new ImageIcon("images/button-over.png"));
button.setSelectedIcon(new ImageIcon("images/button-sel.png"));
button.setRolloverSelectedIcon(new ImageIcon("images/button-sel-over.png"));
button.setDisabledIcon(new ImageIcon("images/button-disabled.png"));
button.setDisabledSelectedIcon(
    new ImageIcon("images/button-disabled-selected.png"));
```

[Figures 1-5](#) and [1-6](#) are the images I used to represent each state. The rollover effect is done with an outer glow, and I used a blur for the disabled state. The red rectangle in the middle represents the selected state, and it includes its own color change and red glow mimicking a real glowing lightbulb.

Figure 1-5. Unselected button with rollover

Figure 1-6. Selected button

## On Image Creation

I created these images by drawing everything in a separate layer in Photoshop. Keeping it all separate means I could save any section of the image as its own file, with or without effects and backgrounds. Photoshop has a great feature called *slices* that lets you divide the image up into malleable sections. Photoshop's companion program, ImageReady, takes slices a step further by managing slice states for you. This lets you create rollovers, in and out images, and disabled states. When you Save Optimized, ImageReady automatically saves each slice state to a different file with the appropriate name (e.g., *buttondisabled-selected.png*). Slices were originally created for web design, but they can be put to great use in Swing applications as well.

To fully demonstrate all of the states, I have added a standard `JCheckBox`. Normally, it would draw a gray background (or striped on the Mac) but a simple `setOpaque(false)` fixes that. The call to `checkbox.setSize(checkbox.getPreferredSize())` is needed to make the checkbox size itself properly when there is no layout manager in the parent, which is the case for this panel:

```
final JCheckBox checkbox = new JCheckBox("Disable");
checkbox.setLocation(70,150);
checkbox.setOpaque(false);
checkbox.setSize(checkbox.getPreferredSize());
panel.add(checkbox);
checkbox.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent evt) {
        button.setEnabled(!checkbox.isSelected());
    }
});
```

With the addition of this code to `ImageTest`'s `main()` method, the imagebased showcase program is complete. [Figure 1-7](#) shows what the running program looks like in the selected but disabled state.

Figure 1-7. 1-7. Selected and disabled



## Hack 2. Don't Settle for Boring Text Labels



JLabel is a Swing staple; but it's easy to spruce up boring labels with drop shadows, outlines, and even 3D text.

When you want to draw non-editable text, Swing provides only the `JLabel`. You can change the font, size, color, and even add an icon. By using HTML in your components [[Hack #52](#)], you can even add things like underline and bullets. This is fine for most jobs, but sometimes you need more. What if you want a drop shadow or an embossed effect? The `JLabel` is simply inadequate for richer interfaces. Fortunately, the Swing Team made it very easy to extend the `JLabel` and add these features yourself.

A great many text effects can be achieved with two simple features. First, you can draw text multiple times, with each iteration slightly offset or in a different color, to create effects like drop shadows and embossing. Second, you can adjust the spacing between letters in a word (a feature known as *tracking* in text-processing circles). Tracking is always specified *in addition* to the default tracking specified by a font. Thus, a tracking of +1 would be drawn as one extra pixel between each letter. A tracking of 0 would have the same spacing as no extra tracking at all.

To implement all of this, you must override both the sizing and the painting code in `JLabel`, which of course calls for a subclass; see [Example 1-5](#) for details.

### Example 1-5. Defining a richer JLabel

```
public class RichJLabel extends JLabel {

    private int tracking;
    public RichJLabel(String text, int tracking) {
        super(text);
        this.tracking = tracking;
    }

    private int left_x, left_y, right_x, right_y;
    private Color left_color, right_color;
    public void setLeftShadow(int x, int y, Color color) {
        left_x = x;
        left_y = y;
        left_color = color;
    }
    public void setRightShadow(int x, int y, Color color) {
        right_x = x;
    }
}
```



```

    right_y = y;
    right_color = color;
}

```

`RichJLabel` extends the standard `javax.swing.JLabel` and adds a tracking argument to the constructor. Next, it adds two methods for the right and left shadow. These are called shadows because they will be drawn below the main text, but whether they actually look like shadows depend on the color, as well as the x- and y-offsets passed into each method.

With the boilerplate out of the way, you need to handle sizing issues. The `JLabel` automatically tells layout managers its preferred size based on the font size. When you add custom tracking, this sizing would be incorrect, resulting in labels too small for the text they contain. For small font sizes it won't be noticeable, but with large fancy text and cool effects and we all want cool effects it could chop off half of a letter or more.

Every Swing component returns its desired size using the `getPreferredSize()` method. By adjusting the returned size to be a bit bigger, layout controls using this component will give the label the extra room it needs:

```

public Dimension getPreferredSize() {
    String text = getText();
    FontMetrics fm = this.getFontMetrics(getFont());

    int w = fm.stringWidth(text);
    w += (text.length()-1)*tracking;
    w += left_x + right_x;
    int h = fm.getHeight();
    h += left_y + right_y;

    return new Dimension(w,h);
}

```

This implementation of `getPreferredSize()` calculates the size based on the font metrics of the currently set text. The `FontMetrics` object contains methods to get the width and height of the font for the current text. Because the tracking variable adds to the existing tracking of the font, you can expand the width by adding a tracking width between each letter one per letter, except the last letter. The line `w += (text.length()-1)*tracking` does just that. The shadows will be drawn the same size as the base text, but they will be offset by the `left_x` and `right_x` values, so you need to add those in as well. Tracking only affects the horizontal space between letters, so height can be calculated normally via the `fontmetrics.getHeight()` method.

Don't forget to account for those shadow offsets!

With the sizing handled, the only thing left is actually drawing the text on screen. As with all Swing components, override the `paintComponent()` method (and not `paint()`) so that the child components will be handled properly.

Here's the first bit of the `paintComponent()` method:

```
public void paintComponent(Graphics g) {
    ((Graphics2D)g).setRenderingHint(
        RenderingHints.KEY_TEXT_ANTIALIASING,
        RenderingHints.VALUE_TEXT_ANTIALIAS_ON);
    char[] chars = getText().toCharArray();

    FontMetrics fm = this.getFontMetrics(getFont());

    int h = fm.getAscent();
    int x = 0;
```

First, `paintComponent()` turns on the graphics object's anti-aliasing hint. Because the `RichJLabel` class will typically be used for large font sizes that need to be attractive, it's probably a safe bet that the developer wants smooth text.

Next, the method grabs the font and line metrics for the current text in the current font. The graphics object always draws text from the bottom of the letter, rather than from the top, as you would expect with a rectangle or line.

*\*\*pg#11\**To account for this, you need to know how far down a letter goes (its *ascent*), which is retrieved from `fm.getAscent()`.

A font's ascent is *not* the same as the height of the font. The height includes the part of letters that extend below the baseline. Most letters stop at the baseline but some, like lowercase ys and gs extend further down. The ascent only includes the part of the letters above the baseline, which is what you want.

After setting up the variables, you can start drawing each letter (this code is still in the `paintComponent()` method):

```
for(int i=0; i<chars.length; i++) {
    char ch = chars[i];
    int w = fm.charWidth(ch) + tracking;

    g.setColor(left_color);
    g.drawString(" "+chars[i],x-left_x,h-left_y);

    g.setColor(right_color);
    g.drawString(" "+chars[i],x+right_x,h+right_y);
```

```
g.setColor(getForeground());
g.drawString(" "+chars[i],x,h);

x+=w;
}

((Graphics2D)g).setRenderingHint(
    RenderingHints.KEY_TEXT_ANTIALIASING,
    RenderingHints.VALUE_TEXT_ANTIALIAS_DEFAULT);

} // end paintComponent()
```

This is a simple loop that calculates the width of each character, plus the tracking, then draws it three times: first with the left offsets, next with the right offsets, and finally in the normal position. At the end of the loop, you just increase `x` to move on to the next letter. The rendering hint line at the bottom returns the graphics object to its original anti-aliasing state.

With the class completed, it's time to try some effects. This code will draw large (140 pt) text in gray with a black drop shadow and a slight, white highlight:

```
public static void main(String[] args) {
    RichJLabel label = new RichJLabel("76", -40);
    // drop shadow w/ highlight
    label.setLeftShadow(1,1,Color.white);
    label.setRightShadow(2,3,Color.black);
    label.setForeground(Color.gray);
    label.setFont(label.getFont().deriveFont(140f));

    JFrame frame = new JFrame("RichJLabel hack");
    frame.getContentPane().add(label);
    frame.pack();
    frame.setVisible(true);
}
```

[Figure 1-8](#) shows what the code looks like running.

Figure 1-8. Drop shadow text

If you change the shadows to be only one pixel offset from their normal position and to share the same color, then you can create a subtle outline effect. Setting the tracking to `-30` pulls the letters close enough to overlap for a nice logo effect (as seen in [Figure 1-9](#)):

```
RichJLabel label = new RichJLabel("76", -30);

// subtle outline
label.setLeftShadow(1,1,Color.white);
label.setRightShadow(1,1,Color.white);
label.setForeground(Color.blue);
label.setFont(label.getFont().deriveFont(140f));
```

Figure 1-9. Outlined text

The shadow offsets let you effectively rearrange the letters to create a faded 3D effect (shown in [Figure 1-10](#)):

```
// 3d letters
label.setLeftShadow(5,5,Color.white);
label.setRightShadow(-3,-3, new Color(0xccccff));
label.setForeground(new Color(0x8888ff));
label.setFont(label.getFont().deriveFont(140f));
```

## Figure 1-10. 3D faded letters

You could expand on this hack by combining it with images and nice gradients like the Christmas Countdown counter in [Figure 1-11](#). Simple graphical effects like the ones shown in the `RichJLabel` are easy to create with Swing thanks to the power of Java2D, and they can really make your interfaces pop.

## Figure 1-11. Mild emboss effect

## Hack 3. Fill Your Borders with Pretty Pictures



Swing comes with a set of customizable borders, but sometimes you want more than they provide. This hack shows how to create a completely imagebased border that can be resized.

Swing has a prefabricated border, called the `MatteBorder`, which can accept an image in its constructor. For simple tiled backgrounds, such as a checkerboard pattern, this works fine. However, if you want to have particular images in each corner, creating a fully resizable image border, then you'll need something more powerful. Fortunately, Swing makes it very easy to create custom border classes. The image border in this hack will produce a border that looks like [Figure 1-12](#).

Figure 1-12. An image-based border

The first step to any custom border is to subclass `AbstractBorder` and implement the `paintBorder()` method. The class will take eight images in the constructor, one for each corner and each side; all the code is shown in [Example 1-6](#).

### Example 1-6. Building an image-based border

```
public class ImageBorder extends AbstractBorder {

    Image top_center, top_left, top_right;
    Image left_center, right_center;
    Image bottom_center, bottom_left, bottom_right;
    Insets insets;

    public ImageBorder(Image top_left, Image top_center, Image top_right,
        Image left_center, Image right_center,
        Image bottom_left, Image bottom_center, Image bottom_right) {

        this.top_left = top_left;
```

```

    this.top_center = top_center;
    this.top_right = top_right;
    this.left_center = left_center;
    this.right_center = right_center;
    this.bottom_left = bottom_left;
    this.bottom_center = bottom_center;
    this.bottom_right = bottom_right;
}

public void setInsets(Insets insets) {
    this.insets = insets;
}

public Insets getBorderInsets(Component c) {
    if(insets != null) {
        return insets;
    } else {
        return new Insets(top_center.getHeight(null),
            left_center.getWidth(null),
            bottom_center.getHeight(null), right_center.getWidth(null));
    }
}
}

```

The two methods after the constructor control the border insets. These are the gaps between the panel's outer edge (and its parent) and the inner edge of the panel where the panel's children are drawn. `setInsets()` lets you set any size insets, but most of the time you want the insets to be based on the actual images that make up the border. The implementation of `getBorderInsets()` returns the insets variable if it's not `null`. However, if the developer didn't set the insets, then they will be derived from the widths and heights of the images that make up each side of the border (top, bottom, left, and right).

To actually draw the border, align the corner images to the appropriate corners and then tile the side images along each border side. Doing this will require using the `TexturePaint` class, which is an implementation of the `Paint` interface. Unfortunately, `TexturePaint` takes only `BufferedImages`, not regular ones, so you've got to convert your images before use.

`BufferedImages` are a special form of image that the Java2D framework can read and write at a pixel level. The standard `Image` is controlled by the operating system and is very difficult to access at the pixel level. Java doesn't let you do a straight conversion between the two kinds of images, but you can just draw one image on top of another, which is what this method in the `ImageBorder` class does:

```

public BufferedImage createBufferedImage(Image img) {
    BufferedImage buff = new BufferedImage(img.getWidth(null),
        img.getHeight(null), BufferedImage.TYPE_INT_ARGB);
    Graphics gfx = buff.createGraphics();
    gfx.drawImage(img, 0, 0, null);
    gfx.dispose();
    return buff;
}

```

`createBufferedImage()` first creates an empty buffered image with the same size as the original image. The image type is `TYPE_INT_ARGB`, which makes the image have full 24-bit color with an alpha channel (transparency). Next, it draws the original image on top of the buffered image. The `dispose()` call releases any extra resources so that the code won't waste any memory, and then it returns the newly minted `BufferedImage`.

With buffered images in hand, the stage is set for actually filling areas of the border with images. The next `ImageBorder` method, `fillTexture()`, creates a `TexturePaint` using the appropriate image and then fills in the requested area:

```
public void fillTexture(Graphics2D g2, Image img, int x, int y, int w, int h) {
    BufferedImage buff = createBufferedImage(img);
    Rectangle anchor = new Rectangle(x,y,img.getWidth(null),img.
getHeight(null));
    TexturePaint paint = new TexturePaint(buff,anchor);
    g2.setPaint(paint);
    g2.fillRect(x,y,w,h);
}
```

The second line of this code creates an anchor rectangle. The image will be tiled to fill the entire border area, but the anchor rectangle is needed to specify where the image will be anchored. We normally think of images being anchored to (0,0), which works fine for the upper-left corner of the border but wouldn't work for the other sides. The right corners would need to be right aligned instead of left aligned, as would happen with (0,0). By setting the anchor to be the location and dimensions of the image itself, you take care of anchoring altogether. The tiling will start wherever the single image would have been drawn.

Now that you can fill an area with a properly aligned texture, you are ready for the `paintBorder()` method, shown in [Example 1-7](#).

### Example 1-7. Painting the border

```
public void paintBorder(Component c, Graphics g, int x, int y,
    int width, int height) {
    g.setColor(Color.white);
    g.fillRect(x,y,width,height);

    Graphics2D g2 = (Graphics2D)g;

    int tlw = top_left.getWidth(null);
    int tlh = top_left.getHeight(null);
    int tcw = top_center.getWidth(null);
    int tch = top_center.getHeight(null);
    int trw = top_right.getWidth(null);
```



```

int trh = top_right.getHeight(null);

int lcw = left_center.getWidth(null);
int lch = left_center.getHeight(null);
int rcw = right_center.getWidth(null);
int rch = right_center.getHeight(null);
int blw = bottom_left.getWidth(null);
int blh = bottom_left.getHeight(null);
int bcw = bottom_center.getWidth(null);
int bch = bottom_center.getHeight(null);
int brw = bottom_right.getWidth(null);
int brh = bottom_right.getHeight(null);

fillTexture(g2,top_left,x,y,tlw,tlh);
fillTexture(g2,top_center,x+tlw,y,width-tlw-trw,tch);
fillTexture(g2,top_right,x+width-trw,y,trw,trh);
fillTexture(g2,left_center,x,y+tlh,lcw,height-tlh-blh);
fillTexture(g2,right_center,x+width-rcw,y+trh,rcw,height-trh-brh);
fillTexture(g2,bottom_left,x,y+height-blh,blw,blh);
fillTexture(g2,bottom_center,x+blw,y+height-bch,width-blw-brw,bch);
fillTexture(g2,bottom_right,x+width-brw,y+height-brh,brw,brh);
}

```

The first two lines fill the entire border area with white. Then you have to cast the `Graphics` to a `Graphics2D` object because you will be doing some advanced painting later on. Next, save a reference to the width and height of each image (the top left, top center, top right, etc.). Finally, call `fillTexture()` on each section of the border to fill it in.

The test program shown in [Example 1-8](#) creates a panel that uses the `ImageBorder`. It creates a nested frame, panel, and button, and then it creates an `ImageBorder` for the panel using eight images.

## Example 1-8. Testing out an image-based border

```

public class ImageBorderHack {

    public static void main(String[] args) {
        JFrame frame = new JFrame("Hack #3: Fill Your Borders with Pretty
            Pictures");
        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
        JPanel panel = new JPanel();
        JButton button = new JButton("Image Border Test");
        panel.add(button);

        ImageBorder image_border = new ImageBorder(
            new ImageIcon("images/upper_left.png").getImage(),
            new ImageIcon("images/upper.png").getImage(),
            new ImageIcon("images/upper_right.png").getImage(),

```

```
new ImageIcon("images/left_center.png").getImage(),
new ImageIcon("images/right_center.png").getImage(),
new ImageIcon("images/bottom_left.png").getImage(),
new ImageIcon("images/bottom_center.png").getImage(),
new ImageIcon("images/bottom_right.png").getImage()
);
panel.setBorder(image_border);

frame.getContentPane().add(panel);
frame.pack();
frame.setVisible(true);
}
}
```

The sample border is made out of a single image sliced into eight pieces using Photoshop (the center image is discarded). You can see these slices in [Figure 1-13](#).

Figure 1-13. Source image in Photoshop with slices

The completed `ImageBorder` class will take the Photoshop slices and tile them to create the finished border, as seen in [Figure 1-14](#).

Figure 1-14. Completed image border

The best thing about these image-based borders is that you can completely change their look by just dropping in new images, which is easy to do with the slice tool in Photoshop. When you create your own image borders, I recommend starting with a rectangular shape layer and then using filters and effects to create drop shadows, bevels, and stroked borders.





## Hack 4. Display Dates in a Custom Calendar



You can download calendar components from third parties, but real hackers can use Swing to build a custom calendar widget on their own.

When you design an application, you'll often want to use standard widgets to display information. Swing doesn't always give you what you need, though. Consider the calendar component: Swing doesn't come with one, so most users have to download widgets to integrate into their application. However, why not go with a cool and hip teen-friendly application with an attractive, image-based component, as shown in [Figure 1-15](#)?

Figure 1-15. Custom calendar component

That would be a bit more fun, wouldn't it? This hack will show you how to build a completely custom calendar component using `java.util.Calendar` and a few images.

First, consider what you'll need. You've got to have pretty images, a component to paint them on, and then some logic to handle the different parts of the date, including what day of the week starts off the current month. You should also provide a `setDate()` method, so that MVC frameworks can play well with your calendar. Let's get started.

### 1.5.1. Create the Images

I created three images in Photoshop: one for the background, one for each day, and one for the

current day. These are shown in [Figures 1-16](#), [1-17](#), and [1-18](#).

Figure 1-16. calendar.png for the general background



Figure 1-17. day.png for the day backgrounds

Figure 1-18. highlight.png for the current day

I could have separated the day names and the title, but since they don't change, it was simpler to make them part of the image.

## 1.5.2. A Component to Paint

The easiest way to create a custom component with fancy drawing is to start off with a `JPanel` and override the `paintComponent()` method, as shown in [Example 1-9](#).

Example 1-9. A Calendar base component

```
public class CalendarHack extends JPanel {
```

```

protected Image background, highlight, day_img;
protected SimpleDateFormat month = new SimpleDateFormat("MMMM");
protected SimpleDateFormat year = new SimpleDateFormat("yyyy");
protected SimpleDateFormat day = new SimpleDateFormat("d");
protected Date date = new Date();

public void setDate(Date date) {
    this.date = date;
}

public CalendarHack() {
    background = new ImageIcon("calendar.png").getImage();
    highlight = new ImageIcon("highlight.png").getImage();
    day_img = new ImageIcon("day.png").getImage();
    this.setPreferredSize(new Dimension(300,280));
}

public void paintComponent(Graphics g) {

    ((Graphics2D)g).setRenderingHint(RenderingHints.KEY_ANTIALIASING,
        RenderingHints.VALUE_ANTIALIAS_ON);
    g.drawImage(background,0,0,null);
    g.setColor(Color.black);
    g.setFont(new Font("SansSerif",Font.PLAIN,18));
    g.drawString(month.format(date),34,36);
    g.setColor(Color.white);
    g.drawString(year.format(date),235,36);

}
}

```

This loads the images in the constructor and sets up date formatters for the month, year, and day. Override the `paintComponent()` method to turn on anti-aliasing, draw the background, and then draw the month and year for the current date.

You'll notice that there is a default date in case the developer doesn't set one (always a good practice).

### 1.5.3. Draw the Days of the Month

The `java.util.Calendar` object handles all date calculations, so let's start there. You'll need two calendars: one to represent the current date (`today`) and one that you update as you loop through the grid of dates (`cal`). Here's what that looks like in code:

```

Calendar today = Calendar.getInstance();
today.setTime(date);
Calendar cal = Calendar.getInstance();
cal.setTime(date);

cal.set(Calendar.DATE,1);
cal.add(Calendar.DATE,-cal.get(Calendar.DAY_OF_WEEK)+1);
for(int week = 0; week < 6; week++) {
    for(int d = 0; d < 7; d++) {
        Image img = day_img;
        Color col = Color.black;
        // only draw if it's actually in this month
        if(cal.get(Calendar.MONTH) == today.get(Calendar.MONTH)) {
            if(cal.equals(today)) {
                img = highlight;
                col = Color.white;
            }
            g.drawImage(img,d*30+46,week*29+81,null);
            g.drawString(day.format(cal.getTime()),
                d*30+46+4,week*29+81+20);
        }
        cal.add(Calendar.DATE,+1);
    }
}

```

You'll notice that both calendars are initialized to date, but then the code resets `cal`'s date to the first of the month and subtracts the current day of the week. This has the effect of setting `cal` to the last Sunday before (or equal to) the real current date. You have to perform this calculation because you need to start drawing in the upper-lefthand corner of the calendar grid, which will almost always include a few days from the previous month. Once all of that is done, the code loops through each week and draws each day.

Now, here's the tricky part: `cal` goes back seven days, which is almost certainly going to run back into the previous month. Because the calendar is month-based, those days in the previous month shouldn't be drawn. That's why there is a check to see if `cal`'s month is equal to today's month. If they are equal, then you can draw the day safely; if not, skip drawing and just increment the date.

The last thing to check is if the current day in `cal` is equal to the real current date. If it is, you want to use a different color and background image (`highlight`). Finally, the image and day numbers are drawn, with the position determined by the current day of the week and week number. You can adjust the multipliers and offsets (`30, 46, 29, 81`) to suit your taste. The `drawString()` method has a few extra pixels of padding to make the day number appear more centered in the day image.

And now you have a completely custom calendar, suitable for placement within the zaniest of interfaces.



## Hack 5. Add a Watermark to a Text Component



This hack will show how to create a custom image background for the `JTextField`, a complex Swing component that does not already support backgrounds or icons by default.

One of Swing's most underused features is the ability to partially override drawing code. Most programs enhance widgets by using renderers or completely overriding the paint code. By only *partially* overriding the drawing, however, you can create some very interesting effects that blend both new and existing drawing commands.

Some components, like `JList` and `JTable`, use renderers to customize their look. To put a background in a `JTextField`, however, requires more. The plan is to subclass `JTextField`, prepare the resources for drawing a background (loading the image, etc.), and then draw a new background while preserving the normal `JTextField` drawing code for the text and cursor.

The actual drawing will be done with a `TexturePaint`. Java2D allows you to fill any area with instances of the `Paint` interface. Typically you use a color, which is an implementation of `Paint`, but it is possible to use something else, such as a texture or gradient. This class will use a `TexturePaint` to tile an image across the component's background.

The first step is to create a `JTextField` subclass (shown in [Example 1-10](#)).

### Example 1-10. Preparing a field for watermarking

```
public class WatermarkTextField extends JTextField {
    BufferedImage img;
    TexturePaint texture;


    public WatermarkTextField(File file) throws IOException {
        super();
        img = ImageIO.read(file);
        Rectangle rect = new Rectangle(0,0,
            img.getWidth(null),img.getHeight(null));
        texture = new TexturePaint(img, rect);
        setOpaque(false);
    }
}
```

[Example 1-10](#) creates a class called `WatermarkTextField`. It is a subclass of `JTextField` with a custom



constructor that accepts a `File` object containing an image. It also defines two member variables: `img` and `texture`. After the obligatory call to `super()`, the constructor reads the file into the `BufferedImage` variable, `img`. If the file isn't a valid image or can't be read for some other reason the method will throw an exception (hence the `throws IOException` clause on the constructor definition).

After the image is loaded successfully, the constructor creates a `TexturePaint`. `TexturePaints` must be created with a source image and a rectangle. The rectangle defines the portion of the source to be tiled. In this case, you want the entire image to be used, so the rectangle is the same size as the image.



If you wanted to use just a portion of the image, you could make the rectangle smaller. This would also give you the ability to store all of your textures in a single large image, which could save loading time and memory.

The last thing the `WatermarkTextField` constructor does before returning is call `setOpaque(false)`. As you have seen earlier in this chapter (and will see again), the `setOpaque()` method is one of the core tools for hacking Swing. In this case, it is used to turn off the default background of the `TextField`, allowing you to substitute your own.

With the subclass created, you can add a method to do the actual drawing:

```
public void paintComponent(Graphics g) {
    Graphics2D g2 = (Graphics2D)g;
    g2.setPaint(texture);
    g.fillRect(0,0,getWidth(),getHeight());
    super.paintComponent(g);
}
```

`WatermarkTextField` overrides the parent class's `paintComponent()` method with its own version. The actual drawing is pretty simple: cast to a `Graphics2D` object (which understands how to work with `Paint` classes), then fill in the background with the texture paint and call `super()`.

Earlier, I said that you will override the parent class *partially* rather than completely. This is because the code still calls the parent class's `paintComponent()` method, but it does it after painting the new background. Because the `opaque` property is set to `false`, the parent class will not draw its own background, allowing your custom one to show through. The component will draw the text, selections, and cursors as normal on top of the custom background.

With the class ready, it's time to pull together an example [Example 1-11](#).

## Example 1-11. Trying out the watermarked text field

```
public static void main(String[] args) throws Exception {
    JFrame frame = new JFrame("Watermark JTextField Hack");
```

```
JTextField textfield = new WatermarkTextField(new File("red.png"));
textfield.setText("A Text Field");

frame.getContentPane().add(textfield);
frame.pack();
frame.show();
}
```

The `main()` method creates a `JFrame` with one child: the custom text field. It creates a new `WatermarkTextField` with an image file in the constructor, then it packs and shows the frame. The text field is every bit a normal `JTextField` except for the constructor, so you can use a variable of type `JTextField` with no problem.

The image, `red.png`, looks like [Figure 1-19](#).

Figure 1-19. `red.png`, the background image

Once tiled across the background of the component, it looks like

Figure 1-20. The running program

## Going Further

Overriding a component's background with custom drawing code is a simple technique that can be used in some surprising ways. The next hack will reuse the watermark code to create a `JTextPane` with light clouds in the background and a small image badge in the upper-righthand corner. With custom backgrounds you could also add animation, status reports, or even rotating space images (see "Put a NASA Photo into the Background of a Text Area" [\[Hack #7\]](#)).

## Hack 6. Watermark Your Scroll Panes



This hack creates a text area with a tiled background image that is fixed, even when the text area scrolls, and also a fixed foreground image that appears above the text, much like the station badges now affixed to the lower-righthand corner of most TV broadcasts.

The Swing framework was designed to let developers override portions of every component, both the visual appearance (the view) and the behavior (the model and controller). This design gives developers great flexibility. One of my favorites is the `JScrollPane`. Its nested composite design allows developers to create some stunning effects.

Once again, the idea is to override the drawing code of a standard component to create the visual effects [\[Hack #5\]](#). The difference here is that you must deal with a composite object, the `JScrollPane`. A `JScrollPane` is not a single Swing component; it's actually a wrapper around two scrollbars and the component that does the real scrolling is a `JViewport`. This viewport is the actual target component; you will subclass it to draw both above and below the `View` component (as seen in [Example 1-12](#)). The `View` is the Swing widget being scrolled; in this case, it is a `JTextArea`.

### Example 1-12. Modifying the viewport for watermarking

```
public class ScrollPaneWatermark extends JViewport {
    BufferedImage fgimage, bgimage;
    TexturePaint texture;
    public void setBackgroundTexture(URL url) throws IOException {
        bgimage = ImageIO.read(url);
        Rectangle rect = new Rectangle(0,0,
            bgimage.getWidth(null),bgimage.getHeight(null));
        texture = new TexturePaint(bgimage, rect);
    }

    public void setForegroundBadge(URL url) throws IOException {
        fgimage = ImageIO.read(url);
    }
}
```

The `ScrollPaneWatermark` class inherits from `JViewport`, adding two methods: `setBackgroundTexture()` and `setForegroundBadge()`. Each takes a `URL` instead of a `File` to allow for images loaded from places other than the local disk, such as a web server or JAR file.

`setBackgroundTexture()` does the same thing that the `WatermarkTextField` did in the previous hack.

It loads the image, creates a same-size rectangle, then initializes a `TexturePaint` for later use. `setForegroundBadge()` is even simpler, only loading the image and storing it in the `fgimage` variable.

With the class set up, it's time to draw. The code below calls `super.paintComponent()` first, and then draws the texture on top of the component. This is because the existing background might need to show through in case the texture has translucent sections. This would be especially important if the standard view background isn't just a solid color. Under Mac OS X, for example, the background is often a striped, light blue pattern. Here's the code to handle texturing:

```
public void paintComponent(Graphics g) {
    // do the superclass behavior first
    super.paintComponent(g);

    // paint the texture
    if(texture != null) {
        Graphics2D g2 = (Graphics2D)g;
        g2.setPaint(texture);
        g.fillRect(0,0,getWidth(),getHeight());
    }
}
```

`ScrollPaneWatermark` draws the foreground image badge by overriding the `paintChildren()` method, calling the superclass, and then drawing the image. This ensures that the badge is always on top of the children or view:

```
public void paintChildren(Graphics g) {
    super.paintChildren(g);
    if(fgimage != null) {
        g.drawImage(fgimage,
            getWidth()-fgimage.getWidth(), 0,
            null);
    }
}
```

The view (a text area in this example) will usually draw its own background. Because, by definition, the view is as big as the viewport (if not bigger), its background will cover up the viewport's nice texture completely. To stop that, you need to call `setOpaque()` on the view:

```
public void setView(JComponent view) {
    view.setOpaque(false);
    super.setView(view);
}
```

The `setView()` method overrides the existing version (from `JViewport`) to call `setOpaque(false)` on the view before calling the `super()` method. By putting this call here, instead of calling `setOpaque()` from the normal setup routines, it frees the developer using the `ScrollPaneWatermark` class from having to call `setOpaque()` manually, making the class more reusable.

With all of the pieces in place, you can now create a text area inside the custom scroll pane. The `main()` method in [Example 1-13](#) tests it out.

### Example 1-13. Testing the scroll pane watermark

```
public static void main(String[] args) throws Exception {
    JFrame frame = new JFrame("Scroll Pane Watermark Hack");
    JTextArea ta = new JTextArea();
    ta.setText(fileToString(new File("alice.txt")));
    ta.setLineWrap(true);
    ta.setWrapStyleWord(true);
    ScrollPaneWatermark watermark = new ScrollPaneWatermark();
    watermark.setBackgroundTexture(new File("clouds.jpg").toURL());
    watermark.setForegroundBadge(new File("flyingsaucer.png").toURL());
    watermark.setView(ta);

    JScrollPane scroll = new JScrollPane();
    scroll.setViewportView(watermark);
    frame.getContentPane().add(scroll);
    frame.pack();
    frame.setSize(600,600);
    frame.show();
}
```

The `main()` method in [Example 1-13](#) creates a frame containing a scroll pane that contains a text area. `fileToString()` is a utility function that loads a text file into the text area.


For brevity, the code for `fileToString()` is not printed here, but you can see it in the full source on the book's web site:

<http://www.oreilly.com/catalog/swinghks>.

After setting up a standard `JTextArea`, the code creates a new `ScrollPaneWatermark` viewport and loads up the images (*clouds.jpg* is a tileable image of pale, fluffy clouds, and *flyingsaucer.jpg* is a small image of a flying saucer with a translucent drop shadow that will blend nicely over the text). Finally, the `main()` method sets the text area as the viewport's view, creates a new scroll pane, and then sets the watermark as the scroll pane's viewport.

[Figure 1-21](#) shows what it looks like when it's all put together.

Figure 1-21. Finished ScrollPane hack



← PREV



## Hack 7. Put a NASA Photo into the Background of a Text Area



This hack will repurpose an existing web page, one of NASA's photo sites, by pulling their "Astronomy Picture of the Day" into the background of a text area.

You've already learned how to draw a watermark image in the background of a text area [[Hack #6](#)] using a `ScrollPaneWatermark`. This hack will pull a photo down from the Web and reuse that class to put the photo in the background. The photo itself comes from NASA's "Astronomy Picture of the Day" page: <http://antwrp.gsfc.nasa.gov/apod/>. The URL to the image changes each day, but the page itself does not. To pull the image down you will load the page, find the image URL, then load the image itself and put it into the `ScrollPaneWatermark`. Depending on the day, it may look something like [Figure 1-22](#).

Figure 1-22. Text area with a background image

The code in [Example 1-14](#) defines a class called `BackgroundLoader`, which implements `Runnable` so it can be placed on its own thread. The constructor takes as an argument the `ScrollPaneWatermark`, which the loader will put the image into. The `run()` method contains a loop that will run every two hours, loading the page, finding the `SRC` URL, then loading the image into the watermark.

Example 1-14. A thread to load a background image

```
public class BackgroundLoader implements Runnable {
    private ScrollPaneWatermark watermark;
    public BackgroundLoader(ScrollPaneWatermark watermark) {
        this.watermark = watermark;
    }
}
```

```

public void run() {
    while(true) {
        try {
            String base_url = "http://antwrp.gsfc.nasa.gov/apod/";
            URL url = new URL(base_url);
            Reader input = new InputStreamReader(url.openStream());
            char buf[] = new char[1024];
            StringBuffer page_buffer = new StringBuffer();
            while(true) {

                int n = input.read(buf);
                if(n < 0) { break; }
                page_buffer.append(buf,0,n);
            }
            // Locate the Image URL (see next section)
        } catch (Exception ex) {
            System.out.println("exception: " + ex);
            ex.printStackTrace();
        }
    }
}
}
}
}

```

First, you open the web page and load it into a `page_buffer` by looping through an `InputStreamReader`, copying the page data into a string buffer.

The `Reader` will take care of encoding issues so you don't need to worry about reading HTTP headers or converting to Unicode.

Page in hand, now you need to find the URL for the image itself. If you load the page into a web browser and view the page source, you will see that there is only a single `IMG` tag in the entire page. This makes the image very easy to find:

```

Pattern pattern = Pattern.compile("<IMG SRC=\"(.*)\"");
Matcher matcher = pattern.matcher(page_buffer);
matcher.find();
String img_url = base_url + matcher.group(1);

watermark.setBackgroundTexture(new URL(img_url));
watermark.repaint();

Thread.currentThread().sleep(1000*60*60*2);

```



First, you must create a `Pattern` object with a *regex* (regular expression) that matches the URL. You will notice in the previous code that there are parentheses around the `.*`. This is called *agrouping*. The matcher will store anything that matches the parentheses in a series of groups that you can query later. This lets you define exactly which part of the pattern you want to pull out. After creating a `Matcher` and calling `find()`, you can pull out the image URL with the line `matcher.group(1)`, prepending it with the base URL for the page.

With the final image URL ready, just set the background texture for the watermark, refresh the screen, and then sleep for two hours. The calculation in the code `(1000*60*60*2)` evaluates to the number of milliseconds in a two-hour block of time. The page only changes once a day, but this way the change will be picked up sooner if the program is running overnight.

With all of the parts assembled, you can now create a main method, shown in [Example 1-15](#), that builds a simple text editor with the `ScrollPaneWatermark` to show the space image in the background.

### Example 1-15. Testing the space image background

```
public static void main(String[] args) throws IOException {
    JFrame frame = new JFrame("Blocking Window");
    JTextArea jta = new JTextArea(10,40);
    jta.setForeground(Color.white);
    ScrollPaneWatermark viewport = new ScrollPaneWatermark();
    viewport.setView(jta);
    viewport.setOpaque(false);

    JScrollPane scroll = new JScrollPane();
    scroll.setViewport(viewport);

    Container comp = frame.getContentPane();
    comp.add("Center", scroll);

    frame.pack();
    frame.show();
    new Thread(new BackgroundLoader(viewport)).start(); }
}
```

The last line of the `main()` method starts a new thread to manage the background image.

Because the code is completely encapsulated in the `BackgroundLoader` class, you could add space images to a component that uses a scroll pane, not just a `JTextArea`.

## Hack 8. Animate Transitions Between Tabs



This hack shows how to create animated transitions that play whenever the user switches tabs on a `JTabbedPane`.

One of Swing's great strengths is that you can hack into virtually anything. In particular, I love making changes to a component's painting code. The ability to do this is one of the reasons I prefer Swing over SWT. Swing gives me the freedom to create completely new UI concepts, such as transitions.

With the standard paint methods, Swing provides most of what you will need to build the transitions. You will have to put together three additional things, however. First, you need to find out when the user actually clicked on a tab to start a transition. Next, you need a thread to control the animation. Finally, since some animations might fade between the old and new tabs, you need a way to provide images of both tabs at the same time. With those three things, you can build any animation you desire.

### 1.9.1. Building a Basic Tabbed Pane

To keep things tidy, I have implemented this hack as a subclass of `JTabbedPane`, except for the actual animation drawing, which will be delegated to a further subclass. By putting all of the heavy lifting into the parent class, you will be able to create new animations easily.


[Example 1-16](#) is the basic skeleton of the parent class.

Example 1-16. A skeleton for the transition manager

```
public class TransitionTabbedPane extends JTabbedPane
    implements ChangeListener, Runnable {
    protected int animation_length = 20;
public TransitionTabbedPane() {
    super();
    this.addChangeListener(this);
}
public int getAnimationLength() {
    return this.animation_length;
}
```

```
public void setAnimationLength(int length) {
    this.animation_length = length;
}
```

`TransitionTabbedPane` extends the standard `JTabbedPane` and also implements `ChangeListener` and `Runnable`. `ChangeListener` allows you to learn when the user has switched between tabs. Since the event is propagated *before* the new tab is painted, inserting the animation is very easy. `Runnable` is used for the animation thread itself.



You could have split the thread into a separate class, but I think that keeping all of the code together makes the system more encapsulated and easier to maintain.

`TransitionTabbedPane` adds one new property, the animation length. This defines the number of steps used for the transition, and it can be set by the subclass or external code.

## 1.9.2. Scheduling the Animation

Since the pane was added as a `ChangeListener` to itself, the `stateChanged()` method will be called whenever the user switches tabs. This is the best place to start the animation thread. Once started, the thread will capture the previous tab into a buffer, loop through the animation, and control the repaint speed:

```
// threading code
public void stateChanged(ChangeEvent evt) {
    new Thread(this).start();
}

protected int step;
protected BufferedImage buf = null;
protected int previous_tab = -1;

public void run() {
    step = 0;

    // save the previous tab
    if(previous_tab != -1) {
        Component comp = this.getComponentAt(previous_tab);
        buf = new BufferedImage(comp.getWidth(),

            comp.getHeight(),
            BufferedImage.TYPE_4BYTE_ABGR);
        comp.paint(buf.getGraphics());
    }
}
```

Notice that the `run()` method grabs the previous tab component only when the `previous_tab` index isn't `-1`. The component will always have a valid value, except for the first time the pane is shown on screen, but that's OK because the user won't have really switched from anything anyway. If there is a previous tab, then the code grabs the component and paints it into a buffer image.



It's important to note that this is not thread-safe because the code is being executed on a custom thread, not the Swing thread. However, since the tab is about to be hidden anyway and, in fact, the next real `paint()` call will only draw the new tab you shouldn't have any problems. Any changes introduced by this extra `paint()` call won't show up on screen.

With the previous component safely saved away, you can now loop through the animation:

```
for(int i=0; i<animation_length; i++) {
    step = i;
    repaint();
    try {

        Thread.currentThread().sleep(100);
    } catch (Exception ex) {
        p("ex: " + ex);
    }
}

step = -1;
previous_tab = this.getSelectedIndex();
repaint();
```

This code shows a basic animation loop from 1 to  $N$ , with a 100-millisecond duration for each frame.

A more sophisticated version of the code could have dynamic frame rates to adjust for system speed.

Once the transition finishes, the animation step is set back to `-1`, the previous tab is stored, and the screen is repainted one last time, without the transition effects.

### 1.9.3. Drawing the Animation

The `TRansitionTabbedPane` is now set up with the proper resources and repaints, but it still isn't

drawing the animation. Because the animation is going to partially or completely obscure the tabs underneath, the best place to draw is right after the children are painted:

```
public void paintChildren(Graphics g) {
    super.paintChildren(g);

    if(step != -1) {
        Rectangle size = this.getComponentAt(0).getBounds();
        Graphics2D g2 = (Graphics2D)g;
        paintTransition(g2, step, size, buf);
    }
}

public void paintTransition(Graphics2D g2, int step,
    Rectangle size, Image prev) {
}
```

This code puts all of the custom drawing into the `paintTransition()` method, currently empty. It will only be called if `step` isn't `-1`, meaning during a transition animation. The `paintTransition()` method provides the drawing canvas, the current animation step, the size and position of the content area (excluding the tabs themselves), and the image buffer that stores the previous tab's content. By putting all of this in a single method, subclasses can build their own animations very easily. [Example 1-17](#) is a simple transition with a white rectangle that grows out of the center, filling the screen, then shrinking again to reveal the new tab content.

## Example 1-17. Setting up an animated transition

```
public class InOutPane extends TransitionTabbedPane {
    public void paintTransition(Graphics2D g2, int state,
        Rectangle size, Image prev) {

        int length = getAnimationLength();
        int half = length/2;
        double scale = size.getHeight()/length;
        int offset = 0;
        // calculate the fade out part
        if(state >= 0 && state < half) {
            // draw the saved version of the old tab component
            if(prev != null) {
                g2.drawImage(prev, (int)size.getX(), (int)size.getY(), null);
            }
            offset = (int)((10-state)*scale);
        }
        // calculate the fade in part
        if(state >= half && state < length) {
            g2.setColor(Color.white);
            offset = (int)((state-10)*scale);
        }
    }
}
```

```

}

// do the drawing
g2.setColor(Color.white);
Rectangle area = new Rectangle((int)(size.getX()+offset),

    (int)(size.getY()+offset),
    (int)(size.getWidth()-offset*2),
    (int)(size.getHeight()-offset*2));

g2.fill(area);
}
}

```

`InOutPane` implements only the `paintTransition()` method, leaving all of the harder tasks to the parent class. First, it determines how long the animation will be, and then it calculates an offset to grow and shrink the white rectangle. If the drawing process is currently in the first half of the animation (`step < half`), then it draws the previous tab below the rectangle, creating the illusion that old tab content is still really on screen with the rectangle growing above it. For the second half of the animation, it just draws the rectangle, letting the real tab (the new one) shine through as the rectangle shrinks.

## 1.9.4. Putting It All Together

Because `transitionTabbedPane` is just a `JTabbedPane` subclass, it can be used wherever the original would be. [Example 1-18](#) creates a frame with two tabs, each containing a button. The running program looks like [Figure 1-23](#). As you switch between the tabs, you will see an animation like that shown in [Figure 1-24](#).

### Example 1-18. Testing out tabbed animation transitions

```

public class TabFadeTest {
    public static void main(String[] args) {
        JFrame frame = new JFrame("Fade Tabs");
        JTabbedPane tab = new InOutPane();
        tab.addTab("t1",new JButton("Test Button 1"));
        tab.addTab("t2",new JButton("Test Button 2"));

        frame.getContentPane().add(tab);
        frame.pack();
        frame.show();

    }
}

```

Figure 1-23. Two tabs, before transition effect begins



Figure 1-24. Tab transition at mid-point

## 1.9.5. Another Example

Because `TRansitionTabbedPane` makes it so easy to build new animations, I thought I'd add another one. This is the old venetian blinds effect, where vertical bars cover the old screen and uncover the new one; [Example 1-19](#) puts it together.

Example 1-19. Creating a venetian blinds effect

```
public class VenetianPane extends TransitionTabbedPane {
    public void paintTransition(Graphics2D g2, int step,
        Rectangle size, Image prev) {
        int length = getAnimationLength();
        int half = length/2;
```

```

// create a blind
Rectangle blind = new Rectangle();

// calculate the fade out part
if(step >= 0 && step < half) {
    // draw the saved version of the old tab component
    if(prev != null) {

        g2.drawImage(prev,(int)size.getX(),(int)size.getY(),null);
    }
    // calculate the growing blind
    blind = new Rectangle(
        (int)size.getX(),
        (int)size.getY(),
        step,
        (int)size.getHeight());

}
// calculate the fade in part
if(step >= half && step < length) {
    // calculate the shrinking blind
    blind = new Rectangle(

        (int)size.getX(),
        (int)size.getY(),
        length-step,
        (int)size.getHeight());

    blind.translate(step-half,0);
}

// draw the blinds
for(int i=0; i<size.getWidth()/half; i++) {
    g2.setColor(Color.white);
    g2.fill(blind);
    blind.translate(half,0);


}
}
}

```

Just like `InOutPane`, `VenetianPane` selectively draws the old tab and then calculates the placement of animated rectangles. In this case, there is a blind rectangle that spans the entire screen from top to bottom, but has the width of the current step. As a result of the step growing, this rectangle gets bigger with each frame. For the second half of the animation, it shrinks and moves to the right, making it appear to fade into nothing. Once the blind is calculated, `VenetianPane` draws the blind multiple times to cover the entire tab content area, creating the effect seen in [Figure 1-25](#).



Figure 1-25. Tab transition with a venetian blinds effect



This hack is quite extensible. With the power of Java2D you could add translucency, blurs, OS X-like genie effects, or anything else you can dream up. As a future enhancement, you could include more animation settings to control the frame rate and transition time. If you do create more, please post them on the Web for others to share.

[← PREV](#)

## Hack 9. Blur Disabled Components



This hack explores creating how to perform a blur transformation on a Swing component.

Every Swing component draws to the screen via the `paintComponent()` method. This is true even for components that offload the actual drawing to Look and Feel UI objects. Because all drawing goes through the `paintComponent()` method at some point, this point is where you can do some interesting things by manipulating the graphics object during the paint process.

Swing components draw to the `Graphics` object passed in through the `paintComponent()` method. This means that if you replace the `Graphics` object with a custom version, you can capture a component's drawing into a bitmap instead of going straight to the screen.

Blurring is a pixel-level operation, meaning the actual blurring is done pixel-by-pixel in a bitmap. By drawing the component to a bitmap, blurring that bitmap, and then drawing the bitmap *in the place* of the component, you can effectively have a blurred component without disturbing the rest of the Swing painting routines. The particular implementation in this hack uses a blurred effect to replace the normal graying of a component when it is disabled.


The first step is to capture the button into a bitmap, as shown in [Example 1-20](#).

### Example 1-20. Creating a blurrable button

```
public class BlurJButton extends JButton {
    public BlurJButton(String text) {
        super(text);
    }

    public void paintComponent(Graphics g) {
        if(isEnabled()) {
            super.paintComponent(g);
            return;
        }
        BufferedImage buf = new BufferedImage(getWidth(),getHeight(),
            BufferedImage.TYPE_INT_RGB);
        super.paintComponent(buf.getGraphics());
        // Blur the buffered image (see next section)
    }
}
```

The `BlurJButton` class extends a normal `JButton` and overrides the `paintComponent()` method. If the button is enabled (neither disabled nor grayed out), then it calls the superclass's normal version of `paintComponent()` and returns. If the button is disabled, however, then `BlurJButton` creates a new `BufferedImage` with the same dimensions as the component.




A `BufferedImage` is simply an image backed by a bunch of bytes in memory. It is a generic kind of image that gives you a lot of flexibility. I set the type of the image to `TYPE_INT_RGB`, rather than `TYPE_INT_ARGB`, because the latter adds an alpha channel. An alpha channel lets you create transparency effects, but since the blur doesn't need transparency, that feature would cost you unneeded memory.

Finally, the `BlurJButton` calls the `paintComponent()` on its superclass, the standard `JButton`, passing in the graphics obtained from the buffer. This is the key to the hack. By passing in `buf.getGraphics()` instead of the `g` variable, the button will be drawn entirely to the image buffer, thus enabling the blurring:

```
float[] my_kernel = {
    0.10f, 0.10f, 0.10f,
    0.10f, 0.20f, 0.10f,
    0.10f, 0.10f, 0.10f };
ConvolveOp op = new ConvolveOp(new Kernel(3,3, my_kernel));
Image img = op.filter(buf,null);
g.drawImage(img,0,0,null);
```

Blurring is a complex operation where each pixel is averaged with the pixels next to it to create a new pixel. The actual math is not tricky, but it's very tedious, and you need to take special care around the edges of the buffer. Fortunately, Java2D provides a class that handles all of the messy details. All you have to provide is a series of float values, called a *kernel*.

The kernel is a bunch of numbers between 0 and 1 that will be multiplied against the value of each pixel and its neighboring pixels. In the previous case, there is a 3 x 3 matrix of values where the target pixel (the one being blurred) is in the center. Multiplying 1 times the pixel value will produce the same pixel value, and therefore the same color. 0 times the pixel value will produce 0, or black. Something in between will produce a darker version of the pixel. Once the kernel is multiplied by the pixels, the values are added together. The kernel in this example has values of 0.10 for every slot except for the center one, which is 0.20. If you add those up, you will find that it comes to exactly 1. This means that the final pixel color will have the same brightness as it did originally (averaged over the entire image), but its color will be a mixture of all of the pixels around it. If the sum of the pixels came out to be less than 1, then the resulting image would be darker than the original. If the sum was greater than 1, then the image would be lighter. This system gives you a lot of flexibility. In fact many paint programs implement a great number of their filters simply by using different convolution kernels.



Try changing the values in the kernel to get effects other than blurring.

Once the kernel is created, it is passed into a new `ConvolveOp`, which does all of the actual calculations. `op.filter(buff,null)` tells the operation to begin. The `null` value in the second argument tells the operation to create a new buffer of the same size as the input buffer, `buf`. Once the blur operation is complete, the final bitmap is drawn to the real screen with the line `g.drawImage(img,0,0,null)`.

With the class in place, you can test it out in code with something like this `main()` method:

```
public static void main(String[] args) {
    JFrame frame = new JFrame("Blurred Button Hack");
    final JButton button = new BlurJButton("A Blurred Button");
    JButton control = new JButton("Switch");
    control.addActionListener(new ActionListener() {

        public void actionPerformed(ActionEvent evt) {
            button.setEnabled(!button.isEnabled());
        }
    });

    frame.getContentPane().add(button);
    frame.getContentPane().add("South",control);
    frame.pack();
    frame.show();
}
```

This is a standard `JFrame` containing a `BlurJButton` as well as a normal button for control. The control button has an `ActionListener` that toggles the blurred button's enabled state. The initial state with the button unblurred is shown in [Figure 1-26](#). When you blur the button, it looks like [Figure 1-27](#).

Figure 1-26. Enabled button with no blur effect

Figure 1-27. Disabled button with blur effect

This technique of rendering to an intermediate buffer can be very powerful. You could extend this hack by doing other pixel-level operations, such as watercolor effects, edge detection, contrast adjustments, or even animated waves and rotations. Anything you can do to a bitmap you can apply to a Swing component.



## Hack 10. Building a Drop-Down Menu Button



This hack shows how to build a color chooser as a proper drop-down component. It will behave like `JComboBox` but without the extension headaches of Sun's version of the class.

Most custom Swing components are created with simple subclasses of the standard base classes in `javax.swing`. This works fine most of the time, but every now and then you need to build something where there is no easy standard component to start with. Even worse, sometimes the obvious choice for your starting point is a component so convoluted that you can't figure out where to start. Still, you'd rather not reimplement the wheel. No, I'm not talking about `JTree` or `JTable` I'm referring to the `JComboBox`. It seems like such a simple component, but the implementation is fiendishly complex.

Most large applications use components that feel like the `JComboBox`, but do something entirely different, like select a color or show a history list. A quick search through the `JComboBox` API doesn't turn up any obvious extension points. You could customize it with some cell renderers, but if you need a component that doesn't show a list of data, you are pretty much out of luck. The source to `JComboBox` is not very helpful either. The work is spread out over several UI classes in the various Look and Feel (L&F) packages. If you did customize one of those, your component would look out of place when used in a different L&F. The only real option is to write your own combo box, which is pretty easy except for the actual drop-down part. You need to show a component on top of the others, poking out of the frame occasionally, but without any decorations of its own. It should be just a borderless floating box. Digging through Swing's source code reveals the secret ingredient: a `JWindow`.

`JWindow` is a subclass of `Window` but not of `Frame`. This means it has no decorations on the side, and it is hidden from the Dock and Taskbar. This is exactly what you want from a pop up. Care must be taken when creating it, however, as you must ensure the window appears only on top of the existing components, and that it disappears when something else gains focus or the window moves. Fortunately, you can do all of this with one composite component and a few event listeners.

`DropDownComponent` will be a composite of the visible component, a downarrow trigger button, and the hidden component that will appear in the pop up. By thinking of your custom component as a composite of existing components, you can make it very flexible. Additionally, subclasses must be able to add different components to make something new out of the same pieces.

[Example 1-21](#) is the start of a `DropDownComponent` class. It extends `JComponent` directly and implements both the action and ancestor listener interfaces. It assembles the visible and drop-down components passed into its constructor with an arrow trigger and the listeners.

Example 1-21. Skeleton for a drop-down combo box

```

public class DropDownComponent extends JComponent
    implements ActionListener, AncestorListener {
    protected JComponent drop_down_comp;
    protected JComponent visible_comp;
    protected JButton arrow;
    protected JWindow popup;

    public DropDownComponent(JComponent vcomp, JComponent ddcomp) {
        drop_down_comp = ddcomp;
        visible_comp = vcomp;

        arrow = new JButton(new MetalComboBoxIcon());
        Insets insets = arrow.getMargin();
        arrow.setMargin( new Insets( insets.top, 1, insets.bottom, 1 ) );
        arrow.addActionListener(this);
        addAncestorListener(this);

        setupLayout();
    }
}

```

The arrow is just a `JButton` with a `MetalComboBoxIcon`. Reusing this arrow lets the code pick up any Metal Look and Feel customizations. The last line of the constructor calls another method in the class `setupLayout()`, to position the arrow next to the visible component while letting the component still grow:

```

protected void setupLayout() {
    GridBagLayout gbl = new GridBagLayout();
    GridBagConstraints c = new GridBagConstraints();
    setLayout(gbl);

    c.weightx = 1.0; c.weighty = 1.0;
    c.gridx = 0; c.gridy = 0;
    c.fill = c.BOTH;
    gbl.setConstraints(visible_comp, c);
    add(visible_comp);

    c.weightx = 0;
    c.gridx++;
    gbl.setConstraints(arrow, c);
    add(arrow);
}

```

So far, this is all standard Swing code. The tricky part is dealing with the `JWindow` pop up. The pop up must be positioned right below the visible component and be on top of the screen. You also need to look for lost focus events to know when to hide the pop up again. To handle the pop up, use the

`actionPerformed()` method:

```
public void actionPerformed(ActionEvent evt) {
    // build pop-up window
    popup = new JWindow(getFrame(null));
    popup.getContentPane().add(drop_down_comp);
    popup.addWindowFocusListener(new WindowAdapter() {

        public void windowLostFocus(WindowEvent evt) {
            popup.setVisible(false);
        }
    });
    popup.pack();

    // show the pop-up window
    Point pt = visible_comp.getLocationOnScreen();
    pt.translate(0, visible_comp.getHeight());
    popup.setLocation(pt);
    popup.toFront();
    popup.setVisible(true);
    popup.requestFocusInWindow();
}
```

The `actionPerformed()` method will be called whenever the arrow button triggers it. It creates a new `JWindow`, adds the drop-down child component, positions the window, and then shows it on top of any other components. The `JWindow` has an anonymous listener that will close the window if it loses focus. Notice that the `JWindow` constructor takes the result of `getFrame()`. `getFrame()` finds the parent frame of the composite drop-down component. The `JWindow` accepts this frame as its owner, meaning it will be positioned relative to the parent frame and be moved along with it. More importantly, it can receive focus events. Windows without owners can't get focus events because they are effectively out of the focus system. These events are important as they let you know when to hide the window again. Without the frame returned from `getFrame()`, the pop up would stay visible and stationary, even if the parent frame gets focus or moves. Here's the code for `getFrame()`:

```
protected Frame getFrame(Component comp) {
    if(comp == null) {

        comp = this;
    }
    if(comp.getParent() instanceof Frame) {
        return (Frame)comp.getParent();
    }
    return getFrame(comp.getParent());
}
```



With the code so far, you can show the pop-up window. To close it, you must listen for ancestor events to find out when something above the dropdown in the component tree has changed. They all just call `hidePopup()` to safely turn it off:

```
public void ancestorAdded(AncestorEvent event){
    hidePopup();
}

public void ancestorRemoved(AncestorEvent event){
    hidePopup();
}

public void ancestorMoved(AncestorEvent event){
    if (event.getSource() != popup) {
        hidePopup();
    }
}

public void hidePopup() {
    if(popup != null && popup.isVisible()) {
        popup.setVisible(false);
    }
}
```

### 1.11.1. Adding a Color Selection Panel

With the `DropDownComponent` finished, you can finally build something with it. For this hack, I've chosen a color selector. This is a small widget that lets the user pick one of 12 standard colors without having to open up a full color chooser. Most word processors and spreadsheets have a component like this, so there's no reason for Swing not to have one, too.

`ColorSelectionPanel`, shown in [Example 1-22](#), is just a `JPanel` with a 4 x 3 grid of buttons. Each button represents one of the most common 10 colors, plus black and white. When a color button is clicked, it will call `selectColor()` to fire off a color selection event.

Example 1-22. A color selection panel to be used in the drop-down component

```
public class ColorSelectionPanel extends JPanel {
    public ColorSelectionPanel() {
        GridBagLayout gbl = new GridBagLayout();
        GridBagConstraints c = new GridBagConstraints();
        setLayout(gbl);
    }
}
```

```
// reusable listener for each button
ActionListener color_listener = new ActionListener() {
    public void actionPerformed(ActionEvent evt) {
        selectColor(((JButton)evt.getSource()).getBackground());
    }
};

// set up the standard 12 colors
Color[] colors = new Color[12];
colors[0] = Color.white;
colors[1] = Color.black;
colors[2] = Color.blue;
colors[3] = Color.cyan;
colors[4] = Color.gray;
colors[5] = Color.green;
colors[6] = Color.lightGray;
colors[7] = Color.magenta;
colors[8] = Color.orange;
colors[9] = Color.pink;
colors[10] = Color.red;
colors[11] = Color.yellow;

// lay out the grid
c.gridheight = 1;
c.gridwidth = 1;
c.fill = c.NONE;
c.weightx = 1.0;
c.weighty = 1.0;
for(int i=0; i<3; i++) {
    for(int j=0; j<4; j++) {
        c.gridx=j;
        c.gridy=i;
        JButton button = new JButton(colors[j+i*4]);
        gbl.setConstraints(button,c);
        add(button);
        button.addActionListener(color_listener);
    }
}

// fire off a selectedColor property event
protected Color selectedColor = Color.black;
public void selectColor(Color newColor) {

    Color oldColor = selectedColor;
    selectedColor = newColor;
    firePropertyChange("selectedColor",oldColor, newColor);
}
}
```

`ColorSelectionPanel` uses a custom `JButton` called `ColorButton` (shown in [Example 1-23](#)). It has no text and a small size so that you can fit 12 of them inside the drop-down window. The button's background comes from the color it represents, and the button draws its own border, so there is no need to draw a grid.

### Example 1-23. Custom JButton for color selection

```
public class ColorButton extends JButton {
    public ColorButton(Color col) {
        super();
        this.setText("");
        Dimension dim = new Dimension(15,15);
        this.setSize(dim);
        this.setPreferredSize(dim);
        this.setMinimumSize(dim);
        this.setBorderPainted(true);
        this.setBackground(col);
    }
}
```

To put the color selector together, you just need to pack the `ColorSelectionPanel` and a status button into a `DropDownComponent`. You also need to add a property change listener to detect when the user has selected a new color and then hide the pop up. This is all handled by [Example 1-24](#).

### Example 1-24. Assembling a working color selection widget


```
public class DropDownTest extends JPanel {
    public static void main(String[] args) {
        final JButton status = new JButton("Color");
        final JPanel panel = new ColorSelectionPanel();
        final DropDownComponent dropdown = new DropDownComponent(status, panel);
        panel.addPropertyChangeListener("selectedColor",
            new PropertyChangeListener() {
                public void propertyChange(PropertyChangeEvent evt) {
                    dropdown.hidePopup();
                    status.setBackground((Color)evt.getNewValue());
                }
            });

        JFrame frame = new JFrame("Drop Down Test");
        frame.setDefaultCloseOperation(frame.EXIT_ON_CLOSE);
        frame.getContentPane().setLayout(new BorderLayout());
    }
}
```

```
frame.getContentPane().add("North",dropdown);
frame.getContentPane().add("Center",new JLabel("Drop Down Test"));
frame.pack();
frame.setSize(300,300);
frame.show();
}
}
```

After building the `DropDownComponent` and putting it in a standard `JFrame`, your color selector will look like [Figure 1-28](#).

Figure 1-28. A drop-down color chooser in a test JFrame



One nice thing about assembling the drop-down from standard components is that it will still look good when used with a different Look and Feel. Everything the user sees on the screen is some subclass of the standard `JButton`, but it is just presented in a non-traditional manner. If you switch to another theme where standard buttons are shaped differently, the custom component adapts automatically.

## Hack 11. Create Menus with Drop Shadows



This hack explores a simple way to create drop shadows on menus throughout an entire application with minimal code changes.

Many modern operating systems provide menus with interesting effects to make them jump off the screen. One of the most common is the drop shadow. Some programs even provide shadows themselves when the host operating system does not. For years, a lack of low-level graphics support has denied Swing programs access to these kinds of cool effects. But not any more! Most of the effects can be duplicated with Swing's robust theming ability.

Most custom effects require either subclassing a component or messing with graphics overlays. I tried a variety of techniques to create this hack, but I kept coming across the same problem over and over. If I wanted to draw a shadow, I had to change the sizing of each menu item, plus its background, plus the pop-up frame itself. That is a lot of components to manage. It would be a lot simpler if I could tell the components to make themselves a little bit bigger and give me the extra slice of screen real estate to draw in. The solution was right under my nose: the border. Every Swing component can use a custom border, without subclassing, and the border will automatically resize the component to fit. If the border is lopsided, then it will create a kind of shadow effect. Perfect!

Every standard Swing component is actually drawn by a UI helper class, and pop-up menus are no exception. I took the `BasicPopupMenuUI` in the `javax.swing.plaf.basic` package and created a subclass called `CustomPopupMenuUI` (shown in [Example 1-25](#)). It only does two things special: adds a custom border to the pop up's parent panel and sets the panel to be transparent.

### Example 1-25. Extending the pop-up menu's UI

```
public class CustomPopupMenuUI extends BasicPopupMenuUI {
    public static ComponentUI createUI(JComponent c) {
        return new CustomPopupMenuUI();
    }
    public Popup getPopup(JPopupMenu popup, int x, int y) {
        Popup pp = super.getPopup(popup, x, y);
        JPanel panel = (JPanel)popup.getParent();
        panel.setBorder(new ShadowBorder(3,3));
        panel.setOpaque(false);
        return pp;
    }
}
```

The `getPopup()` method generates the actual menu object in the superclass. This version grabs the pop up's parent `JPanel` and adds the custom `ShadowBorder` with offsets of 3 pixels, both horizontally and vertically. It also calls `setOpaque(false)`. This tells the component that it does not have to completely fill its boundaries and that the parent component may show through. For most components, this turns off its background, which is the desired effect here.

With the custom pop-up class done, it's time to create the border. `ShadowBorder`, shown in [Example 1-26](#), is a subclass of `AbstractBorder`, which handles all of the messy details of border management and lets the developer get down to the actual drawing code pretty quickly.

### Example 1-26. Adding a shadowed border

```
class ShadowBorder extends AbstractBorder {
    int xoff, yoff;
    Insets insets;
    public ShadowBorder(int x, int y) {
        this.xoff = x;
        this.yoff = y;
        insets = new Insets(0,0,xoff,yoff);
    }
    public Insets getBorderInsets( Component c ) {
        return insets;
    }

    public void paintBorder(Component comp, Graphics g,
        int x, int y, int width, int height) {
        g.setColor(Color.black);
        g.translate(x,y);
        // draw right side
        g.fillRect(width-xoff, yoff, xoff, height-yoff);
        // draw bottom side
        g.fillRect(xoff, height-yoff, width-xoff, yoff);
        g.translate(-x,-y);
    }
}
```

The `ShadowBorder` constructor takes x- and y-offsets and creates an `Insets` object. These insets have to be returned by the `getBorderInsets()` method in order for other components to size themselves appropriately. Because the insets class uses a 0 for the first two arguments, the extra space will be on the right and bottom only, not the top and left. This will create an offset shadow in the lower-right direction, similar to most native operating system drop shadows.

The actual painting code is very simple: set the color to black, translate the graphics origin to be relative to the x and y passed in, draw the shadow, and translate back. The shadow is composed of two filled-in rectangles, one on the bottom of the component and one on its right side. Note that the

drawing begins offset slightly. The right side starts at `yoff` instead of `0`, and the bottom side starts at `xoff`. These adjustments will create a tiny square of empty space in the lower left and upper right. Those squares will allow the background to show through. Because the background panel was already turned off in the `CustomPopupMenuUI`'s `getPopup()` method, this will let the other components underneath the menu shine through. The drop shadow effect is complete.

The code in [Example 1-27](#) installs the `CustomPopupMenuUI` into the `UIManager`. This will ensure that all menus throughout the program use the custom menu. Finally, the test program creates a sample set of menus and some dummy components in the main frame. The finished program looks like [Figure 1-29](#).

### Example 1-27. Putting the custom combo box into action

```
public class MenuTest {
    public static void main(String[] args) throws Exception {
        UIManager.put("PopupMenuUI", "CustomPopupMenuUI");
        JFrame frame = new JFrame();
        JMenuBar mb = new JMenuBar();
        frame.setJMenuBar(mb);

        JMenu menu = new JMenu("File");
        mb.add(menu);
        menu.add(new JMenuItem("Open"));
        menu.add(new JMenuItem("Save"));
        menu.add(new JMenuItem("Close"));
        menu.add(new JMenuItem("Exit"));
        menu = new JMenu("Edit");
        mb.add(menu);
        menu.add(new JMenuItem("Cut"));
        menu.add(new JMenuItem("Copy"));
        menu.add(new JMenuItem("Paste"));
        menu.add(new JMenuItem("Paste Special.."));
        frame.getContentPane().setLayout(new BorderLayout());
        frame.getContentPane().add("North", new JButton("Button"));
        frame.getContentPane().add("Center", new JLabel("a label"));
        frame.getContentPane().add("South", new JCheckBox("checkbox"));
        frame.pack();
        frame.setSize(200, 150);
        frame.show();
    }
}
```

Figure 1-29. Menu with a drop shadow





## Hack 12. Add Translucence to Menus



In this hack I will show you how to add true translucency to your menus with only a slight modification to your program.

Computer interfaces are pretty sophisticated these days. Years ago, we considered ourselves lucky to simply have menu bars at all; now, we need menus with sophisticated effects like animation, shadows, and translucency.

You've already seen how to achieve visual effects by overriding the `paint()` method of a parent component and then rendering the children into a buffer [[Hack #9](#)]. It would be nice to do the same thing here, but there's just one small problem. Overriding the `paint()` method of the `JMenu` wouldn't do any good because the `JMenu` doesn't draw what we think of as a menu list of menu items that pop up when you click on the menu's title. The `JMenu` actually only draws the title at the top of a menu. The rest of the menu is drawn by a `JPopupMenu` created as a member of the `JMenu`. Unfortunately this member is marked `private`, which means you can't substitute your own `JPopupMenu` subclass for the standard version.

Fortunately there is a way out. Like all Swing components, the menu components delegate their actual drawing to a separate set of Look and Feel classes in the `javax.swing.plaf` package. If you override the right `plaf` classes for the menu items and pop-up menu, then you should be able to create the desired translucent effect. It just takes a little subclassing.

### 1.13.1. Make the Custom Menu Item

All `MenuItem`s are implemented by some form of the `javax.swing.plaf.MenuItemUI` class. When creating custom UI classes, it is always best to start by subclassing something in the `javax.swing.plaf.basic` package (in this case, `BasicMenuItemUI`) because it handles most of the heavy lifting for you, as shown in [Example 1-28](#).

#### Example 1-28. Extending the basic UI

```
public class CustomMenuItemUI extends BasicMenuItemUI {
    public static ComponentUI createUI(JComponent c) {
        return new CustomMenuItemUI();
    }

    public void paint(Graphics g, JComponent comp) {
        // paint to the buffered image
    }
}
```

```

BufferedImage bufimg = new BufferedImage(

    comp.getWidth(),
    comp.getHeight(),
    BufferedImage.TYPE_INT_ARGB);

Graphics2D g2 = bufimg.createGraphics();
// restore the foreground color in case the superclass needs it
g2.setColor(g.getColor());
super.paint(g2,comp);
// do an alpha composite
Graphics2D gx = (Graphics2D) g;
gx.setComposite(AlphaComposite.getInstance(
    AlphaComposite.SRC_OVER,0.8f));
gx.drawImage(bufimg,0,0,null);
}

}

```

No constructor is required because all UI classes have a no-arg constructor automatically. All UI classes also need a static `createUI()` method to create a new instance of the class, as you can see in the example. In the `paint()` method, instead of drawing on the graphics object passed in, the code creates a buffered image with the same dimensions as the component, and then calls `super.paint()`. This will draw the component onto the buffered image instead of the screen. Once the painting is done, it can apply a transform and then draw the image buffer onto the real `Graphics`. In this case, the transform is an alpha composite of `0.8`. This means that instead of drawing the buffer as is, it will draw the buffer partially transparent (80% solid, in this case). This will draw the `bufferedimage` into the real graphics with a translucent effect. You can vary the strength of the translucency by modifying the second parameter to the `AlphaComposite.getInstance()` method (`1` results in a solid, `0` is totally transparent).

### 1.13.2. Add a Custom JMenu

If you stopped with just the custom menu items, the menus would seem a bit translucent, but the rest of the window wouldn't shine through. This is because the menu items are inside of another component; in fact, they're inside of three! The `JMenu` puts all of the menu items inside of a `JPopupMenu`, which is placed inside of a `JPanel`, and then the whole deal is put in a layered pane at the top of the frame. The layered pane is already transparent, so you don't need to worry about it, but the `JPanel` and `JPopupMenu` are going to be a problem. [Example 1-29](#) handles the custom UI for these.

#### Example 1-29. Handling translucence for JPanels and JPopupMenu

```

public class CustomPopupMenuUI extends BasicPopupMenuUI {
    public static ComponentUI createUI(JComponent c) {
        return new CustomPopupMenuUI();
    }
}

```

```

    }

    public void installUI(JComponent c) {
        super.installUI(c);
        popupMenu.setOpaque(false);
    }

    public Popup getPopup(JPopupMenu popup, int x, int y) {
        Popup pp = super.getPopup(popup, x, y);
        JPanel panel = (JPanel)popup.getParent();
        panel.setOpaque(false);
        return pp;
    }
}

```

The custom pop-up menu UI used here is similar to the `CustomMenuItemUI` (from [Example 1-28](#)). It has a static `createUI` menu and no constructor. The pop-up menu is already stored as a protected member of the `BasicPopupMenuUI` parent class, so I can access it easily. The `installUI()` method is called right after the `JPopupMenu` is created, so this is the best place to put a call to `setOpaque(false)`. For most L&Fs, this will make the component transparent.

That takes care of the pop-up menu, but what about the parent `JPanel`? The `JPanel` is created and initialized deep within the `javax.swing.PopupFactory` class, so it's pretty well out of reach. This is one place where having access to the JRE source code is invaluable. Without that, this entire hack would have been impossible to figure out. Fortunately, we have access to the finished `JPopupMenu` from within the `getPopup` method. I overrode that to call the superclass and then grab the newly minted parent of the pop-up menu and cast it to a `JPanel`. Now, I can finally set it to be transparent, too.

### 1.13.3. Test It Out

With your two custom UI classes in place, test them out with [Example 1-30](#), which shows a frame containing two sets of menus and a few components. Before creating any components, the program installed the custom UI classes with two calls to `UIManager.put()`.

Any time you want to override part of a L&F, you can use `UIManager.put()`.

#### Example 1-30. Testing out the translucent menus

```

public class MenuTest {
    public static void main(String[] args) throws Exception {
        UIManager.put("PopupMenuUI", "CustomPopupMenuUI");
        UIManager.put("MenuItemUI", "CustomMenuItemUI");
    }
}

```

```
JFrame frame = new JFrame();
JMenuBar mb = new JMenuBar();
frame.setJMenuBar(mb);
JMenu menu = new JMenu("File");
mb.add(menu);
menu.add(new JMenuItem("Open"));
menu.add(new JMenuItem("Save"));
menu.add(new JMenuItem("Close"));
menu.add(new JMenuItem("Exit"));
menu = new JMenu("Edit");
mb.add(menu);

menu.add(new JMenuItem("Cut"));
menu.add(new JMenuItem("Copy"));
menu.add(new JMenuItem("Paste"));
menu.add(new JMenuItem("Paste Special.."));
frame.getContentPane().setLayout(new BorderLayout());
frame.getContentPane().add("North",new JButton("Button"));
frame.getContentPane().add("Center",new JLabel("a label"));
frame.getContentPane().add("South",new JCheckBox("checkbox"));
frame.pack();
frame.setSize(200,150);
frame.show();

}
}
```

With all of the code in place, you can compile it and get something that looks like [Figure 1-30](#).

Figure 1-30. Translucent menu

One bug you will notice is that after you open the menu and start moving the cursor between menu items, the background won't shine through anymore. This is because Swing, in an effort to speed up the UI, only repaints the parts it knows have changed. It repaints the menu item, but not the frame contents below (the button and label, in this case) because it thinks they are obscured by the menu item. Of course, the menu item is translucent, so the components should shine through, but Swing doesn't know that. To fix the problem, you'll need to develop a full repaint manager[\[Hack #53\]](#) that will force Swing to always repaint the entire component tree, instead of just the menu items. It's a bit slower, but worth it if you really want this effect:

```
UIManager.put("MenuItemUI", "CustomMenuItemUI");  
RepaintManager.setCurrentManager(new FullRepaintManager());
```

One more bug is that the menu must fit within the frame. There are two kinds of menus in Swing: heavyweight and lightweight. Lightweight menus are normal Swing components. Heavyweight menus, on the other hand, are drawn in their own top-level window. This means that there are two windows being drawn: one for the real frame and one for the menu. If you use heavyweight menus, the effect will stop completely because the windows themselves can't be transparent. Normally, Swing will use lightweight menus, but if the menu has to be drawn outside of the frame which can happen if you have a small window or a really large menu then it will switch to heavyweight menus automatically and nothing can switch it back until the application restarts. This means you should always make sure your menus fit inside of your windows.

### 1.13.4. Future Ideas

This hack shows just one example of how you can completely change a component's behavior by customizing its Look and Feel class. Java2D gives you the power to create a wide variety of graphical hacks. As an extension of this technique, you could try blurring the components underneath the menu or create a properly smoothed drop shadow.

[← PREV](#)

# Chapter 2. Lists and Combos

[Section 2.1. Hacks 1320: Introduction](#)

[Hack 13. Filter JLists](#)

[Hack 14. Add a Filter History](#)

[Hack 15. Make JLists Checkable](#)

[Hack 16. Make Different List Items Look Different](#)

[Hack 17. Reorder a JList with Drag-and-Drop](#)

[Hack 18. Animate Your JList Selections](#)

[Hack 19. Turn Methods into List Renderers](#)

[Hack 20. Create a Collections-Aware JComboBox](#)

[← PREV](#)

## 2.1. Hacks 1320: Introduction

Lists are underrated and underappreciated, and developers who don't appreciate JLists often use JTables when they don't need to. But lists seem to be making a comeback in desktop applications, and with good reason. A lot of the data we deal with are single-dimension collections: search results, recent URLs, downloaded files, etc. and by making the onscreen version of them more appealing and more usable, a list is the right way to present this data to the user.

[← PREV](#)

## Hack 13. Filter JLists



Make your 1,000-item list a lot more manageable.

One of the nicest things you can do with a large list is to make it manageable with a *filter box*. This is a text area that, as you type into it, removes list elements so that only those that contain the typed text are visible.

The hack to do this basically involves having a list model with two representations of its contents: everything that is in the list, and a subset with just the items to be displayed (i.e., those from the first list that match the filter). The model's get methods are then rewired to use only the second list.

The implementation in this hack, `FilteredJList`, is a single class with two inner subclasses: `FilterModel` and `FilterField`. The list owns the field, so a caller can create the `JList` fairly typically and then just ask for the field and add it wherever it makes sense in the layout.

Start by declaring `FilteredJList` as a subclass of `JList`, and provide a constructor and some convenience methods, as seen in [Example 2-1](#).

### Example 2-1. FilterList constructor and convenience methods

```
public class FilteredJList extends JList {

    private FilterField filterField;
    private int DEFAULT_FIELD_WIDTH = 20;

    public FilteredJList() {
        super();
        setModel (new FilterModel());
        filterField = new FilterField (DEFAULT_FIELD_WIDTH);
    }

    public void setModel (ListModel m) {
        if (!(m instanceof FilterModel))
            throw new IllegalArgumentException();
        super.setModel (m);
    }

    public void addItem (Object o) {
        (FilterModel)getModel().addElement (o);
    }
}
```



```

public JTextField getFilterField() {
    return filterField;
}

```

Notice that along with holding onto the `FilterField`, the `JList` also creates its own `FilterModel` in the constructor, and overrides `setModel()` to ensure that you can't push in an incompatible model. It also contains an `addItem()` method, which really just delegates to the `FilterModel`.

`FilterModel`, shown in [Example 2-2](#), is where the magic happens.


## Example 2-2. Inner class to provide a filtered model

```

class FilterModel extends AbstractListModel {
    ArrayList items;
    ArrayList filterItems;
    public FilterModel() {
        super();
        items = new ArrayList();
        filterItems = new ArrayList();
    }
    public Object getElementAt (int index) {
        if (index < filterItems.size())
            return filterItems.get (index);
        else
            return null;
    }
    public int getSize() {
        return filterItems.size();
    }
    public void addElement (Object o) {
        items.add (o);
        refilter();
    }
    private void refilter() {
        filterItems.clear();
        String term = getFilterField().getText();
        for (int i=0; i<items.size(); i++)
            if (items.get(i).toString().indexOf(term, 0) != -1)
                filterItems.add (items.get(i));
        fireContentsChanged (this, 0, getSize());
    }
}
// FilterField inner class listed below
}

```

This model has two `ArrayLists` for its contents: `items` contains all the items that have been added to the model; `filterItems` contains only the items that match the filter. The `getSize()` and `getElementAt()` methods, required by `ListModel`, draw not from the real items list, but from the `filterItems` list. The `filterItems` list is reconstituted via calls to the `refilter()` method, which fires off a `ListDataEvent` to inform the `JList` that the contents have changed and require a repaint.



The `refilter()` method works on the `String` representation of the list contents if your objects are more sophisticated, you might need to adapt the matching logic; e.g., searching the content of email messages represented as objects.

There's also an `addItem()` method, patterned after the equivalent method in `DefaultListModel` that, unlike `AbstractListModel`, assumes mutability (i.e., the ability to add and remove list contents). A more complete implementation of this model would probably need to provide equivalents for all of `DefaultListModel`'s `add` and `remove` methods. Notice that `addItem()` calls `refilter()` on each add, so that an added item is immediately added to the visible list, assuming that it matches the search term.

The `FilterField`, shown in [Example 2-3](#), is fairly trivial, and it is responsible for forcing a `refilter` when its contents change.

### Example 2-3. Text field that refilters the model on each keystroke

```
// inner class provides filter-by-keystroke field
class FilterField extends JTextField implements DocumentListener {
    public FilterField (int width) {
        super(width);
    }
    getDocument().addDocumentListener (this);
    public void changedUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
    public void insertUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
    public void removeUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
}
```

The `FilterField`'s `DocumentListener` calls for a `refilter` on each of the possible `DocumentEvents`. For efficiency, it might be faster for the model to provide a `refilter` method that starts with the filtered list and narrows it down further. This could be called by `insertUpdate()` because adding characters to the filter term can only make it more restrictive, meaning there is no point considering any items tha

aren't already matches.

To test the `FilterJList`, [Example 2-4](#) shows a simple `main()` method that populates the list with some names and puts the list and its filter field in a `JFrame`.

### Example 2-4. Simple test GUI for `FilteredJList`

```
public static void main (String[] args) {
    String[] listItems = {
        "Chris", "Joshua", "Daniel", "Michael",
        "Don", "Kimi", "Kelly", "Keagan"
    };
    JFrame frame = new JFrame ("FilteredJList");
    frame.getContentPane().setLayout (new BorderLayout());
    // populate list
    FilteredJList list = new FilteredJList();
    for (int i=0; i<listItems.length; i++)
        list.addItem (listItems[i]);
    // add to gui
    JScrollPane pane =
        new JScrollPane (list,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
    frame.getContentPane().add (pane, BorderLayout.CENTER);
    frame.getContentPane().add (list.getFilterField(),
        BorderLayout.NORTH);


    frame.pack();
    frame.setVisible(true);
}
```

When run, all the list items are displayed initially, as in [Figure 2-1](#).

Figure 2-1. Unfiltered contents of a list

But when you type an uppercase *K* (the `indexOf` search in `refilter()` is casesensitive), the list immediately shrinks to three items, shown in [Figure 2-2](#).

Figure 2-2. Filtering on a keystroke



The only matches for *K* are "Kimi," "Kelly," and "Keagan." Now type an *e*, and "Kimi" will be filtered out, as in [Figure 2-3](#).

Figure 2-3. Refiltering on successive keystrokes

## Hack 14. Add a Filter History



Remember previous searches and research with one click .

Chances are good that if you've searched for something once, it's important enough that you might well browser, a search widget at the upper right has a little magnifying glass that remembers your last 10 se pop up appears with the previous searches. Select one and it populates the field and does the search im

Here's an implementation of the same idea, grafted onto the previous hack. In other words, this remem every keystroke why bother remembering the searches "J" and "Jo" when you're really just interested in filter when the user presses return.

In the previous hack, you just needed to have a text field and a `JList` . Now a `JButton` needs to be attac bundled together in the inner class `FilterField` . This class is responsible for:

- Telling the model to refilter on each keystroke in the `JTextField` , as before.
- Remembering the `JTextField` 's contents as a saved search anytime the Return or Enter key is pre:
- Catching clicks on the `JButton` and popping up a menu with previous searches.
- Populating the `JTextField` with a previous search when one is selected from the list. It doesn't nee because changing the text area will fire a `DocumentEvent` that is already accounted for by the `JTextF`

Example 2-5 shows the new `FilterField` class.

### Example 2-5. List filtering component with text field and history button

```
class FilterField extends JComponent
    implements DocumentListener, ActionListener {
    LinkedList prevSearches;
    JTextField textField;
    JButton prevSearchButton;
    JPopupMenu prevSearchMenu;
    public FilterField (int width) {
        super();
        setLayout(new BorderLayout());
        textField = new JTextField (width);
        textField.getDocument().addDocumentListener (this);
        textField.addActionListener (this);
    }
    prevSearchButton =
        new JButton (new ImageIcon ("mag-glass.png"));
```

```

        prevSearchButton.setBorder(null);
        prevSearchButton.addMouseListener (new MouseAdapter() {
            public void mousePressed (MouseEvent me) {
            }
        });
        add (prevSearchButton, BorderLayout.WEST);
        add (textField, BorderLayout.CENTER);
        prevSearches = new LinkedList ();
    }
    public void popMenu (int x, int y) {
        prevSearchMenu = new JPopupMenu();
        Iterator it = prevSearches.iterator();
        while (it.hasNext())
            prevSearchMenu.add (
                new PrevSearchAction(it.next().toString()));
        prevSearchMenu.show (prevSearchButton, x, y);
    }
    public void actionPerformed (ActionEvent e) {
        // called on return/enter, adds term to prevSearches
        if (e.getSource() == textField) {
            prevSearches.addFirst (textField.getText());
            if (prevSearches.size() > 10)
                prevSearches.removeLast();
        }
    }
    public void changedUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
    public void insertUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
    public void removeUpdate (DocumentEvent e) {
        ((FilterModel)getModel()).refilter();
    }
}

```

Notice how this version of the class uses a `MouseListener` on the `JButton` instead of an `ActionListener`. It provides the location of the mouse click as a `Point` in the `JButton`'s coordinate space, which is useful for point of the mouse click. There is an `ActionListener` implementation, but it's for the `JTextField` so that the filter text is saved to the `JPopupMenu` (and, if there are more than 10 items, the oldest saved search i

The items in the `JPopupMenu` are instances of `PrevSearchAction`, which subclasses Swing's `Action`. This is a `String` representation to be shown in the pop-up menu, yet get an `actionPerformed()` when their menu chance to reset the filter text. Here's what the `PrevSearchAction` inner class looks like:

```

class PrevSearchAction extends AbstractAction {
    String term;
    public PrevSearchAction (String s) {

```

```
        term = s;  
        putValue (Action.NAME, term);  
    }  
    public String toString() { return term; }  
    public void actionPerformed (ActionEvent e) {  
        getFilterField().textField.setText (term);  
    }  
}
```

When a previous search is recalled, it looks like Figure 2-4.

Figure 2-4. Pop-up menu with previous searches

And when the mouse clicks on one of the menu items, the field is populated and the list is filtered. Figure 2-5.

Figure 2-5. List filtered by pop-up selection

The general idea of this pop up can be modified to work in similar ways for different kinds of searches, such as searching for a specific term in a list of items. For example, a search is to be applied to a list of items if the list items are complex. An example of this is a mail program in which the search is limited to finding the specified term in only the selected field, such as To, From, etc., meaning that the search is limited to finding the specified term in only the selected field.

## Hack 15. Make JLists Checkable



Avoid losing 50 selections to an unshifted click.

One horrible UI problem is dealing with vast collections of things that need to be presented to the user and made selectable. If, like me, you've ever had 1,000 emails in your inbox, you know what I mean. Worse, what if you pick a bunch of items to delete, but your finger slips off the key used for multi-selection (Alt on Windows, Command on the Mac, etc.) and you lose all of your previous selections? Overriding the native selection behavior can make this situation somewhat more palatable.

Because a list like this behaves differently than a normal list, it should look different, too, so I've opted for a checkbox metaphor. Each item is shown with a checkbox, and as you click more items, they get checked, and if you select an already-checked item, it gets unchecked.

This turns out to be a little harder than expected. I once did it without `JList`, creating my own scrolling layout of `JPanels` and faking the list behavior. It turned up a funny Swing bug because I was using `GridBagLayout` for the fake list, and it started totally bombing out after about 500 items were added to the list. This was because `GridBagLayout` has a bug where it can't have more than 512 rows. Considering the bug (number 4254022 on the Java Bug Parade) was filed in 1999 and is still open, I'm figuring it won't get fixed by the time you read this.

The basis of the checkable list is a `JList`. The tricky part here is that there isn't a way (that I've found) to steal the mouse clicks from the `JList` and consume them before the normal calls to the `ListSelectionModel` are made. Instead, the strategy is to set up a `ListSelectionListener` and just fix everything after `JList` has done its thing.

To implement the checkbox functionality, subclass `JList` and give it a custom `ListSelectionListener` and a `ListCellRenderer`. A complete listing is shown in [Example 2-6](#).

### Example 2-6. A checkbox-metaphor JList

```
public class CheckBoxJList extends JList
    implements ListSelectionListener {

    static Color listForeground, listBackground;
```



```

static {
    UIDefaults uid = UIManager.getLookAndFeel().getDefaults();
    listForeground =uid.getColor ("List.foreground");
    listBackground =uid.getColor ("List.background");
}

HashSet selectionCache = new HashSet();
int toggleIndex = -1;
boolean toggleWasSelected;

public CheckBoxJList() {
    super();
    setCellRenderer (new CheckBoxListCellRenderer());
    addListSelectionListener (this);
}

// valueChanged() listing below

public static void main (String[] args) {
    JList list = new CheckBoxJList ();
    DefaultListModel defModel = new DefaultListModel();
    list.setModel (defModel);
    String[] listItems = {
        "Chris", "Joshua", "Daniel", "Michael",
        "Don", "Kimi", "Kelly", "Keagan"
    };
    Iterator it = Arrays.asList(listItems).iterator();
    while (it.hasNext())
        defModel.addElement (it.next());
    // show list
    JScrollPane scroller =
        new JScrollPane (list,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
    JFrame frame = new JFrame ("Checkbox JList");
    frame.getContentPane().add (scroller);
    frame.pack();
    frame.setVisible(true);
}
}

```

There are two important sections to consider. The first is the `valueChanged()` method that implements `ListSelectionListener`. The following list describes what happens in that method.

1. Only react if `ListSelectionEvent.isValueAdjusting()` returns `false`. If it's `true`, then the event is part of a series perhaps the user is shift dragging over several items to multiselect them and you don't want to do anything until the series of events has completed.

2. Remove the `ListSelectionListener` so that changes to the list made by your code don't fire off events, which would lead to a recursive, stackblowing fiasco.
3. Cache all the selections that resulted from `JList`'s handling of the event. These will be added or removed from the final selections later.
4. Reselect all the items that were selected before the `valueChanged()` call.
5. Go through the new selections and add them to the selection if they weren't selected before. Or the other hand, if they were selected previously, deselect them.
6. Cache all these selections for the next call to `valueChanged()`.
7. Add the `ListSelectionListener` again.

The listing for `valueChanged` is shown in [Example 2-7](#).

### Example 2-7. A `ListSelectionListener` for the checkable `JList`

```
public void valueChanged (ListSelectionEvent lse) {
    if (!lse.getValueIsAdjusting()) {
        removeListSelectionListener (this);

        // determine if this selection has added or removed items
        HashSet newSelections = new HashSet();
        int size = getModel().getSize();
        for (int i=0; i<size; i++) {
            if (getSelectionModel().isSelectedIndex(i)) {
                newSelections.add (new Integer(i));
            }
        }

        // turn on everything that was selected previously
        Iterator it = selectionCache.iterator();
        while (it.hasNext()) {
            int index = ((Integer) it.next()).intValue();
            getSelectionModel().addSelectionInterval(index, index);
        }

        // add or remove the delta
        it = newSelections.iterator();
        while (it.hasNext()) {
            Integer nextInt = (Integer) it.next();
            int index = nextInt.intValue();
            if (selectionCache.contains (nextInt))
                getSelectionModel().removeSelectionInterval (index, index);
        }
    }
}
```

```

        // save selections for next time
        selectionCache.clear();
        for (int i=0; i<size; i++) {
            if (getSelectionModel().isSelectedIndex(i)) {
                selectionCache.add (new Integer(i));
            }
        }

        addListSelectionListener (this);
    }
}

```

The other important part of this class is a `ListCellRenderer` that shows the list items with checkboxes, and which is used as a visual cue that the list has checkbox-like behavior. Aside from adding a checkbox to the renderer component and setting its state appropriately, you should hack the coloring of the cell to avoid highlighting (because you are already using checkboxes). The key here is to grab the platform's colors for unselected list cell foregrounds and backgrounds, which you can get via the `UIDefaults` class and the property names `List.foreground` and `List.background`. This cell renderer always resets the list cells to these unselected colors, leaving just the checkboxes as an indication of what's selected and does it in the correct colors. The renderer is implemented as an inner class and is listed in [Example 2-8](#).

### Example 2-8. ListCellRenderer for checkbox-based JList

```

class CheckBoxListCellRenderer extends JComponent
    implements ListCellRenderer {
    DefaultListCellRenderer defaultComp;
    JCheckBox checkbox;
    public CheckBoxListCellRenderer() {
        setLayout (new BorderLayout());
        defaultComp = new DefaultListCellRenderer();
        checkbox = new JCheckBox();
        add (checkbox, BorderLayout.WEST);
        add (defaultComp, BorderLayout.CENTER);
    }

    public Component getListCellRendererComponent(JList list,
                                                    Object value,
                                                    int index,
                                                    boolean isSelected,
                                                    boolean cellHasFocus){
        defaultComp.getListCellRendererComponent (list, value, index,
                                                    isSelected, cellHasFocus);

        checkbox.setSelected (isSelected);
        Component[] comps = getComponents();
        for (int i=0; i<comps.length; i++) {

```

```
        comps[i].setForeground (listForeground);  
        comps[i].setBackground (listBackground);  
    }  
    return this;  
}  
}
```

When you click on items in the list, their selection state is shown with checkboxes, as seen in [Figure 2-6](#).

### Figure 2-6. Using the checkbox-metaphor JList

Notice how the checkboxes are all you need to see what's selected. In an early version of this hack, I went out of my way to maintain the usual selection colors and it looked lousy, probably because there were two competing metaphors to show the selection: the highlight and the checkbox. Since this hack totally changes how the JList works, it's appropriate to radically change its appearance, too

## Hack 16. Make Different List Items Look Different



An in-progress download shouldn't look like a completed one .

What made me love lists again were the OmniWeb browser and (later) Safari particularly, their download way of negative example, take the download manager for Internet Explorer 5 for Mac...please. This GUI filenames, URLs, sizes, etc., with columns not even intelligently resized for their widths. OmniWeb, on the other hand, showed a running download with a progress bar, and a finished download with the file location and file size step further with context-appropriate buttons: an X to cancel an in-progress download, a magnifying glass for an already-downloaded file, etc. But it's the same idea: *different things shouldn't look the same*.

To do this in Swing, you need a hack that goes against everything in all the other Swing books: you need to subclass `JComponent` when you write a `ListCellRenderer` . Instead, delegate the `getListCellRendererComponent()` to one of several components, choosing whichever best represents the item to be rendered.

In fact, the whole tradition of subclassing `JComponent` for `ListCellRenderers` is a pretty hateful practice but is not really used as `Component` s anyway! They're certainly not added to the `JList`. Instead, a list cell is rendered and those pixels are blitted to the `JList` . So, provided that what you return in `getListCellRendererComponent()` you want the cell to look like, it really doesn't matter how you get there.

By way of demonstration, this hack shows the items in a given directory with different layouts, depending on their type. All of the cells use an icon on the left, with a name in bold at the top of a two-line layout. However, for a folder, the bottom line contains a count of the children in that folder. If the item is a text file it ends with various extensions associated with text files (e.g., `.txt`, `.html`, `.java`) then there's a different layout that uses the second line to show file size and word count. And if the item is determined to be an image file, then a room for a little two-row image icon on the right is used.

So, there are four different prototypes, and `getListCellRendererComponent()` needs to choose one, set highlight colors, and return it. Example 2-9 is quite long, in part because of the icky `GridBagLayout` work to make the four prototypes look interesting. This is one time when I really wish I had a visual Swing GUI!

### Example 2-9. A JList with multiple cell-rendering layouts

```
public class PolymorphicJList extends JList {

    static Color listForeground, listBackground,
        listSelectionForeground, listSelectionBackground;
    static {
        UIDefaults uid = UIManager.getLookAndFeel().getDefaults();
        listForeground = uid.getColor ("List.foreground");
        listBackground = uid.getColor ("List.background");
        listSelectionForeground = uid.getColor ("List.selectionForeground");
    }
}
```

```

        listSelectionBackground = uid.getColor ("List.selectionBackground");
    }
    ImageIcon fileIcon, textFileIcon, directoryIcon,
        imageFileIcon, pngFileIcon, gifFileIcon,
        jpegFileIcon;
    JComponent fileCellPrototype, textCellPrototype,
        imageCellPrototype, directoryCellPrototype;
    JLabel fileNameLabel, textNameLabel,
        directoryNameLabel, imageNameLabel,
        fileSizeLabel,
        textSizeLabel, textWordCountLabel,
        directoryCountLabel,
        imageSizeLabel, imageIconLabel;

    public PolymorphicJList (File dir) {
        super();
        buildPrototypeCells();
        setCellRenderer (new PolyRenderer());
        setModel (new DefaultListModel());
        if (! dir.isDirectory())
            dir = new File (dir.getParent());
        buildModelFromDir (dir);
    }

    public static void main (String[] args) {
        File dir = new File (".");
        if (args.length > 0)
            dir = new File (args[0]);
        JList list = new PolymorphicJList (dir);
        JScrollPane pain =
            new JScrollPane (list,
                ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
                ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
        JFrame frame = new JFrame ("PolymorphicJList");
        frame.getContentPane().add (pain);
        frame.pack();
        frame.setVisible(true);
    }

    protected void buildModelFromDir (File dir) {
        File[] files = dir.listFiles();
        DefaultListModel mod = (DefaultListModel) getModel();
        for (int i=0; i<files.length; i++) {
            if (isTextFile (files[i]))
                mod.addElement (new TextFileItem (files[i]));
            else if (isImageFile (files [i]))
                mod.addElement (new ImageFileItem (files[i]));
            else if (files[i].isDirectory())
                mod.addElement (new DirectoryItem (files[i]));
        }
    }
    else
        mod.addElement (new FileItem (files[i]));

```

```

    }
}

protected boolean isImageFile(File f) {
    if (f.isDirectory())
        return false;
    String name = f.getName();
    return name.endsWith (".gif") || name.endsWith (".GIF") ||
        name.endsWith (".jpg") || name.endsWith (".JPG") ||
        name.endsWith (".jpeg") || name.endsWith (".JPEG") ||
        name.endsWith (".bmp") || name.endsWith (".BMP") ||
        name.endsWith (".png") || name.endsWith (".PNG");
}

protected boolean isTextFile(File f) {
    if (f.isDirectory())
        return false;
    String name = f.getName();
    return name.endsWith (".txt") || name.endsWith (".html") ||
        name.endsWith (".xml") || name.endsWith (".xhtml") ||
        name.endsWith (".java") || name.endsWith (".c") ||
        name.endsWith (".cpp") || name.endsWith (".c++") ||
        name.endsWith (".m") || name.endsWith (".h");
}

protected void buildIcons() {
    String SEP = System.getProperty ("file.separator");
    fileIcon = new ImageIcon ("images" + SEP + "generic.gif");
    textFileIcon = new ImageIcon ("images" + SEP + "text.gif");
    directoryIcon = new ImageIcon ("images" + SEP + "folder.gif");
    imageFileIcon = new ImageIcon ("images" + SEP + "image.gif");
    pngFileIcon = new ImageIcon ("images" + SEP + "png.gif");
    gifFileIcon = new ImageIcon ("images" + SEP + "gif.gif");
    jpegFileIcon = new ImageIcon ("images" + SEP + "jpeg.gif");
}

protected void buildPrototypeCells() {
    buildIcons();
    fileCellPrototype = new JPanel();
    fileCellPrototype.setLayout (new GridBagLayout());
    addWithGridBag (new JLabel(fileIcon), fileCellPrototype,
        0, 0, 1, 2,
        GridBagConstraints.WEST,
        GridBagConstraints.BOTH, 0, 0);
    fileNameLabel = new JLabel();
    Font defaultLabelFont = fileNameLabel.getFont();
    Font nameFont =
        defaultLabelFont.deriveFont (Font.BOLD,
            defaultLabelFont.getSize()+2);
}

```

```

fileNameLabel.setFont (nameFont);
addWithGridBag (fileNameLabel, fileCellPrototype,
                1, 0, 1, 1,
                GridBagConstraints.NORTH,
                GridBagConstraints.HORIZONTAL, 1, 0);      fileSizeLabel =
addWithGridBag (fileSizeLabel, fileCellPrototype,
                1, 1, 1, 1,
                GridBagConstraints.SOUTH,
                GridBagConstraints.HORIZONTAL, 1, 0);
opacify (fileCellPrototype);
// text file
textCellPrototype = new JPanel();
textCellPrototype.setLayout (new GridBagLayout());
addWithGridBag (new JLabel(textFileIcon), textCellPrototype,
                0, 0, 1, 2,
                GridBagConstraints.WEST,
                GridBagConstraints.BOTH, 0, 0);
textNameLabel = new JLabel();
textNameLabel.setFont (nameFont);
addWithGridBag (textNameLabel, textCellPrototype,
                1, 0, 2, 1,
                GridBagConstraints.NORTH,
                GridBagConstraints.HORIZONTAL, 1, 0);
textSizeLabel = new JLabel();
textWordCountLabel = new JLabel();
addWithGridBag (textSizeLabel, textCellPrototype,
                1, 1, 1, 1,
                GridBagConstraints.NORTH,
                GridBagConstraints.HORIZONTAL, 0, 0);
addWithGridBag (textWordCountLabel, textCellPrototype,
                2, 1, 1, 1,
                GridBagConstraints.SOUTH,
                GridBagConstraints.HORIZONTAL, 1, 0);

opacify (textCellPrototype);
// directory
directoryCellPrototype = new JPanel();
directoryCellPrototype.setLayout (new GridBagLayout());
addWithGridBag (new JLabel(directoryIcon), directoryCellPrototype,
                0, 0, 1, 2,
                GridBagConstraints.WEST,
                GridBagConstraints.BOTH, 0, 0);
directoryNameLabel = new JLabel();
directoryNameLabel.setFont (nameFont);
addWithGridBag (directoryNameLabel, directoryCellPrototype,
                1, 0, 1, 1,
                GridBagConstraints.NORTH,
                GridBagConstraints.HORIZONTAL, 1, 0);
directoryCountLabel = new JLabel();
addWithGridBag (directoryCountLabel, directoryCellPrototype,
                1, 1, 1, 1,
                GridBagConstraints.SOUTH,

```



```

        GridBagConstraints.HORIZONTAL, 1, 0);
    opacify (directoryCellPrototype);
// image
    imageCellPrototype = new JPanel();
    imageCellPrototype.setLayout (new GridBagLayout());
    addWithGridBag (new JLabel(imageFileIcon), imageCellPrototype,
        0, 0, 1, 2,
        GridBagConstraints.WEST,
        GridBagConstraints.BOTH, 0, 0);
    imageNameLabel = new JLabel();
    imageNameLabel.setFont (nameFont);
    addWithGridBag (imageNameLabel, imageCellPrototype,
        1, 0, 1, 1,
        GridBagConstraints.NORTH,
        GridBagConstraints.HORIZONTAL, 1, 0);
    imageSizeLabel = new JLabel();
    addWithGridBag (imageSizeLabel, imageCellPrototype,
        1, 1, 1, 1,
        GridBagConstraints.SOUTH,
        GridBagConstraints.HORIZONTAL, 1, 0);
    imageIconLabel = new JLabel();
    addWithGridBag (imageIconLabel, imageCellPrototype,
        2, 0, 1, 2,
        GridBagConstraints.EAST,
        GridBagConstraints.VERTICAL, 0, 0);
    opacify (imageCellPrototype);
}

private void addWithGridBag (Component comp, Container cont,
    int x, int y,
    int width, int height,
    int anchor, int fill,
    int weightx, int weighty) {
    GridBagConstraints gbc = new GridBagConstraints();
    gbc.gridx = x;
    gbc.gridy = y;
    gbc.gridwidth = width;
    gbc.gridheight = height;
    gbc.anchor = anchor;
    gbc.fill = fill;
    gbc.weightx = weightx;
    gbc.weighty = weighty;
    cont.add (comp, gbc);
}

private void opacify (Container prototype) {
    Component[] comps = prototype.getComponents();
    for (int i=0; i<comps.length; i++) {
        if (comps[i] instanceof JComponent)
            ((JComponent)comps[i]).setOpaque(true);
    }
}

```

```

    }
    // FileItem, ImageFileItem, TextFileItem, and
    // DirectoryItem classes listed below

    // PolyRenderer class listed below
}

```

Whew! That's a mighty big hack. The main `PolymorphicListCellRenderer` class builds the prototype cells and an `addWithGridBag()` method to make the layout take only a hundred lines instead of a thousand. It also calls `setBackground()` on every child of the prototype containers, which ensures that setting the background color will work on every cell. It then builds the list model from the directory passed to the list constructor, iterating over the items and creating appropriate `FileItems`, `ImageItems`, etc., for each one. It also holds onto some file-type icons (a directory icon, a text file icon) that the renderer will need.

In Example 2-10, `FileItem`, `ImageFileItem`, `DirectoryItem`, and `TextFileItem` are inner classes that all inherit from `FileItem`. The constructor for each one initializes the values that will be shown by the renderer: the word count or the little icon image. The renderer can do `instanceof` on the value it's asked to render, in order to determine which prototype to use for which kind of item.

### Example 2-10. Objects to represent contents of list model

```

class FileItem extends Object {
    File file;
    public FileItem (File f) {
        file = f;
    }
}

class ImageFileItem extends FileItem {
    ImageIcon icon;
    public ImageFileItem (File f) {
        super(f);
        initIcon();
    }
    void initIcon() {
        icon = new ImageIcon (file.getPath());
        // scale to 32 pix in largest dimension
        Image img = icon.getImage();
        float factor = 1.0f;
        if (img.getWidth(null) > img.getHeight(null))
            factor = Math.min (32f / img.getWidth(null), 1.0f);
        else
            factor = Math.min (32f / img.getHeight(null), 1.0f);
        Image scaledImage =
            img.getScaledInstance ((int) (img.getWidth(null) * factor),
                (int) (img.getHeight(null) * factor),
                Image.SCALE_FAST);
        icon.setImage(scaledImage);
    }
}

```

```

    }
}

class DirectoryItem extends FileItem {
    int childCount;
    public DirectoryItem (File f) {
        super(f);
        initChildCount();
    }
    public int getChildCount() { return childCount; }
    void initChildCount () {
        if (! file.isDirectory())
            childCount = -1;
        else
            childCount = file.listFiles().length;
        System.out.println (file.getPath() + ": " + childCount + " items");
    }
}

class TextFileItem extends FileItem {
    int wordCount = -1;
    public TextFileItem (File f) {
        super(f);
        initWordCount();
    }
    public int getWordCount() { return wordCount; }
    protected void initWordCount() {
        try {
            StreamTokenizer izer =
                new StreamTokenizer (new BufferedReader
                    (new FileReader(file)));
            while (izer.nextToken() != StreamTokenizer.TT_EOF)
                wordCount++;
        } catch (Exception e) {
            e.printStackTrace();
            wordCount = -1;
        }
        System.out.println (file.getPath() + ": " + wordCount + " words");
    }
}

```

The `PolyRenderer` inner class is, of course, responsible for the cell rendering. When it's passed a list item determines the class of the item and picks an appropriate prototype to modify. It sets the text or image of that prototype, and it sets foreground and background colors on all the children depending on the selected `PolyRenderer` is listed in Example 2-11.

**Example 2-11.** Inner class to render list items based on different prototypes

```

class PolyRenderer extends Object
  implements ListCellRenderer {


  public Component getListCellRendererComponent(JList list,
                                                Object value,
                                                int index,
                                                boolean isSelected,
                                                boolean cellHasFocus) {

    if (value instanceof DirectoryItem) {
      DirectoryItem item = (DirectoryItem) value;
      directoryNameLabel.setText (item.file.getName());
      directoryCountLabel.setText (item.getChildCount() + " items");
      setColorsForSelectionState (directoryCellPrototype, isSelected);
      return directoryCellPrototype;
    } else if (value instanceof TextFileItem) {
      TextFileItem item = (TextFileItem) value;
      // populate values
      textNameLabel.setText (item.file.getName());
      textSizeLabel.setText (item.file.length() + " bytes ");
      textWordCountLabel.setText (item.getWordCount() + " words");
      setColorsForSelectionState (textCellPrototype, isSelected);
      return textCellPrototype;
    } else if (value instanceof ImageFileItem) {
      ImageFileItem item = (ImageFileItem) value;
      // pouplate values
      imageNameLabel.setText (item.file.getName());
      imageSizeLabel.setText (item.file.length() + " bytes");
      imageIconLabel.setIcon (item.icon);
      setColorsForSelectionState (imageCellPrototype, isSelected);
      return imageCellPrototype;
    } else {
      FileItem item = (FileItem) value;
      // pouplate values
      fileNameLabel.setText (item.file.getName());
      fileSizeLabel.setText (item.file.length() + " bytes");
      setColorsForSelectionState (fileCellPrototype, isSelected);
      return fileCellPrototype;
    }
  }

  private void setColorsForSelectionState (Container prototype,
                                           boolean isSelected) {

    Component[] comps = prototype.getComponents();
    for (int i=0; i<comps.length; i++) {
      if (isSelected) {
        comps[i].setForeground (listSelectionForeground);
        comps[i].setBackground (listSelectionBackground);
      } else {
        comps[i].setForeground (listForeground);
        comps[i].setBackground (listBackground);
      }
    }
  }
}

```



If you supply an argument, the `main ()` method will assume it to be the path to a directory and will show contents in the list. If you don't supply an argument, the current directory is assumed. Figure 2-7 displays like when I show my home directory in the `PolymorphicJList`.

Figure 2-7. Showing my home directory as a JList with multiple cell la

As you can see, there's an obvious difference between the layout and contents for the folders, text files, Because I didn't have any pictures in my home folder at the time, I reran the demo and pointed into one folders, which created the list shown in Figure 2-8.

As you can see, image files get a little icon of their contents, while folders just show their item count. Th because they *are* different.

Figure 2-8. Showing a directory of images with special cell layou

← PREV

## Hack 17. Reorder a JList with Drag-and-Drop



Let users put things where they want .

You may be so used to immutable lists that the idea of reordering a list with drag-and-drop seems unnatural. I thought it would be useful to establish a priority (e.g., try Ethernet, then wireless, then modem) on devices in Mac OS X to tell users they could drag-and-drop the list items to rearrange them. Now that I'm used to it,

To implement this functionality in a `JList` , you basically just have to implement the full set of AWT drag-and-drop interfaces for the drag and the target of the drop. The other thing you need to do is to use some cell rendering trick.

The `ReorderableJList` , shown in Example 2-12 , is a `JList` that uses a `DefaultListModel` , which is mutable. It responds to drag-and-drops. The bulk of it is concerned with implementing the drag-and-drop interfaces `DragGestureListener` . It has an inner class implementing `Transferable` to hold the item being dragged, a `Transferable` instance variable and `null`ed the `transferable` in the drag-and-drop calls, but it d

### Example 2-12. A JList that can be reordered with drag-and-drop

```
public class ReorderableJList extends JList
    implements DragSourceListener, DropTargetListener, DragGestureListener {

    static DataFlavor localObjectFlavor;
    static {
        try {
            localObjectFlavor =
                new DataFlavor (DataFlavor.javaJVMLocalObjectMimeType);
        } catch (ClassNotFoundException cnfe) { cnfe.printStackTrace(); }
    }
    static DataFlavor[] supportedFlavors = { localObjectFlavor };
    DragSource dragSource;
    DropTarget dropTarget;
    Object dropTargetCell;
    int draggedIndex = -1;

    public ReorderableJList () {
        super();
        setCellRenderer (new ReorderableListCellRenderer());
        setModel (new DefaultListModel());
        dragSource = new DragSource();
        DragGestureRecognizer dgr =
            dragSource.createDefaultDragGestureRecognizer (this,
                DnDConstants.ACTION_MOVE,
```

```

                                                                 this);
        dropTarget = new DropTarget (this, this);
    }

    // DragGestureListener
    public void dragGestureRecognized (DragGestureEvent dge) {
        System.out.println ("dragGestureRecognized");
        // find object at this x,y
        Point clickPoint = dge.getDragOrigin();
        int index = locationToIndex(clickPoint);
        if (index == -1)
            return;
        Object target = getModel().getElementAt(index);
        Transferable trans = new RJLTransferable (target);
        draggedIndex = index;
        dragSource.startDrag (dge, Cursor.getDefaultCursor(),
                               trans, this);
    }
    // DragSourceListener events
    public void dragDropEnd (DragSourceDropEvent dsde) {
        System.out.println ("dragDropEnd()");
        dropTargetCell = null;
        draggedIndex = -1;
        repaint();
    }
    public void dragEnter (DragSourceDragEvent dsde) {}
    public void dragExit (DragSourceEvent dse) {}
    public void dragOver (DragSourceDragEvent dsde) {}
    public void dropActionChanged (DragSourceDragEvent dsde) {}
    // DropTargetListener events
    public void dragEnter (DropTargetDragEvent dtde) {
        System.out.println ("dragEnter");
        if (dtde.getSource() != dropTarget)
            dtde.rejectDrag();
        else {
            dtde.acceptDrag(DnDConstants.ACTION_COPY_OR_MOVE);
            System.out.println ("accepted dragEnter");
        }
    }
    public void dragExit (DropTargetEvent dte) {}
    // dragOver() listed below
    // drop() listed below
    public void dropActionChanged (DropTargetDragEvent dtde) {}

    // main() method to test - listed below

    // RJLTransferable listing below

    // ReorderableListCellRendering listing below
}

```



The constructor creates the list model and sets the cell renderer (an inner class that will be described so whatever input is judged by the host platform to be a drag (usually clicking and holding down the mouse `DragSource` and a `DropTarget` .

When a drag begins, `dragGestureRecognized ( )` gets called. Your responsibility at this point is to start the `DragSource` object via `startDrag ( )`. In this case, you can use the `DragGestureEvent` to get a `Point`, from which you can get the `Object` from the model, but the `DragSource` wants it to be wrapped by a `transferable` . Normally you would use the `DropTarget` on a `DataFlavor` , and it can express the transferred data. Of course, much of that is irrelevant for a list, considering the list already had it before the drag began. For this demo, we use `RJLTransferable` , which only knows how to represent plain old Java objects (usually called `POJO` s). `RJLTransferable`

### Example 2-13. Simple Transferable object for a reorderable JList

```
class RJLTransferable implements Transferable {
    Object object;
    public RJLTransferable (Object o) {
        object = o;
    }
    public Object getTransferData(DataFlavor df)
        throws UnsupportedFlavorException, IOException {
        if (isDataFlavorSupported (df))
            return object;
        else
            throw new UnsupportedFlavorException(df);
    }
    public boolean isDataFlavorSupported (DataFlavor df) {
        return (df.equals (localObjectFlavor));
    }
    public DataFlavor[] getTransferDataFlavors () {
        return supportedFlavors; }
}
```

With the drag underway, most of the `DragSourceListener` methods are irrelevant. What you're interested in is `dragOver ( )` listed in Example 2-14 which indicates a drag-in-progress over your component. In this case, you need to figure out which list item the drag is hovering over by getting a `Point` from `DropTargetDragEvent` via `locationToIndex ( )`, and then getting that item from the model. Save that target cell to the instance variable `targetCell` so that the cell renderer has a chance to animate the drop.

### Example 2-14. Handling drag-over events in a reorderable JList

```
public void dragOver (DropTargetDragEvent dtde) {
    // figure out which cell it's over, no drag to self
    if (dtde.getSource() != dropTarget)
        dtde.rejectDrag();
    Point dragPoint = dtde.getLocation();
```

```

int index = locationToIndex (dragPoint);
if (index == -1)
    dropTargetCell = null;
else
    dropTargetCell = getModel().getElementAt(index);
repaint();
}

```

The `ReorderableListCellRenderer`, shown in Example 2-15, checks this instance variable to see if the `boolean` called `isTargetCell`. You can use this in an overridden `paintComponent()` method to paint a line which will happen every time the mouse moves over the `JList` during a drag, the cell that you're dragging drop will put the dragged item before this one.

### Example 2-15. Custom cell renderer to animate potential drops on a reorder

```

class ReorderableListCellRenderer
    extends DefaultListCellRenderer {
    boolean isTargetCell;
    boolean isLastItem;
    public ReorderableListCellRenderer() {
        super();
    }
    public Component getListCellRendererComponent (JList list,
                                                    Object value,
                                                    int index,
                                                    boolean isSelected,

    isTargetCell = (value == dropTargetCell);
    isLastItem = (index == list.getModel().getSize()-1);
    boolean showSelected = isSelected &
        (dropTargetCell == null);
    return super.getListCellRendererComponent (list, value,
                                                index, showSelected,
                                                hasFocus);
    }
    public void paintComponent (Graphics g) {
        super.paintComponent(g);
        if (isTargetCell) {
            g.setColor(Color.black);
            g.drawLine (0, 0, getSize().width, 0);
        }
    }
}

```

The other major thing to handle is the drop itself. In some ways, this is like the drag-over case: you need `JList`, and you need to figure out which list item the drop has occurred over. Given this, you can pull the `DropTargetDropEvent`, delete it from its previous location in the list, and insert it in its new location

its dropped destination, then the correct drop index will be one less than you'd expect. After all, by deleting and moving up one index. All of this is handled by the `drop ()` method, shown in Example 2-16 .

### Example 2-16. Handling the drop on the reorderable JList

```
public void drop (DropTargetDropEvent dtde) {
    System.out.println ("drop()!");
    if (dtde.getSource() != dropTarget) {
        System.out.println ("rejecting for bad source (" +
            dtde.getSource().getClass().getName() + ")");
        dtde.rejectDrop();
        return;
    }
    Point dropPoint = dtde.getLocation();
    int index = locationToIndex (dropPoint);
    System.out.println ("drop index is " + index);
    boolean dropped = false;
    try {
        if ((index == -1) || (index == draggedIndex)) {
            System.out.println ("dropped onto self");
            dtde.rejectDrop();
            return;
        }
        dtde.acceptDrop (DnDConstants.ACTION_MOVE);
        System.out.println ("accepted");
        Object dragged =
            dtde.getTransferable().getTransferData(localObjectFlavor);
        // move items - note that indices for insert will
        // change if [removed] source was before target
        System.out.println ("drop " + draggedIndex + " to " + index);
        boolean sourceBeforeTarget = (draggedIndex < index);
        System.out.println ("source is" +
            (sourceBeforeTarget ? "" : " not") +
            " before target");
        System.out.println ("insert at " +
            (sourceBeforeTarget ? index-1 : index));
        DefaultListModel mod = (DefaultListModel) getModel();
        mod.remove (draggedIndex);
        mod.add ((sourceBeforeTarget ? index-1 : index), dragged);
        dropped = true;
    } catch (Exception e) {
        e.printStackTrace();
    }
    dtde.dropComplete (dropped);
}
```

Finally, you need to call `dropComplete ()` to tell the `DropTargetDropEvent` whether the drag-and-drop suc

The `main ()` method shown in Example 2-17 provides the same list of people shown in the other hacks. If you then drag the mouse toward the bottom of the list. As you drag, potential drops will be indicated by the

### Example 2-17. Testing the reorderable JList

```
public static void main (String[] args) {
    JList list = new ReorderableJList ();
    DefaultListModel defModel = new DefaultListModel();
    list.setModel (defModel);
    String[] listItems = {
        "Chris", "Joshua", "Daniel", "Michael",
        "Don", "Kimi", "Kelly", "Keagan"
    };
    Iterator it = Arrays.asList(listItems).iterator();
    while (it.hasNext())
        defModel.addElement (it.next());
    // show list
    JScrollPane scroller =
        new JScrollPane (list,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
    JFrame frame = new JFrame ("Checkbox JList");
    frame.getContentPane().add (scroller);
    frame.pack();
    frame.setVisible(true);
}
```

Figure 2-9. Dragging to reorder a J

Once dropped between the last two items, the item moves to its new location, as seen in Figure 2-10.

One limitation of this approach is that I haven't found a simple way to provide for drag-and-drop (e.g., to allow an item to be dropped before the item you drop it on).

Figure 2-10. Item dropped into new positic



## Hack 18. Animate Your JList Selections



Fading in and catching the eye .

Not every GUI involves windows and mouse pointers, and the visual language of a GUI can be very different depending on what is provided by the environment. Typically, GUIs for things like console video games and settop boxes don't use a mouse metaphor, so there's no onscreen pointer that the user is tracking. As a result, these systems often give the user more profound feedback when they move around a list: highlights slide from one item to another, selected items fade in while deselected items fade out, and so there's something the eye can track. You can do the same thing in Swing, with more cell-rendering hackery. You might not need it now, but it'll be handy if you ever design a kiosk with Swing.

One way to show a changed selection is to show a brief animation of the cell selection. Instead of just being highlighted instantly, you fade the selected cell from its unselected background and foreground colors to its selected colors over the course of a short time (really short, like a half-second, so it isn't annoying).

To do this, you'll need to create an animator thread that kicks off every time the selection changes. This short-lived thread repeatedly updates a highlight color and calls `repaint()`. The cell renderer can then use the updated highlight color as it redraws the cells in the list. Example 2-18 shows this technique.

### Example 2-18. Animating the JList cell selection

```
import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;
import java.util.*;
public class AnimatedJList extends JList
    implements ListSelectionListener {

    static java.util.Random rand = new java.util.Random();

    static Color listForeground, listBackground,
        listSelectionForeground, listSelectionBackground;
    static float[] foregroundComps, backgroundComps,
        foregroundSelectionComps, backgroundSelectionComps;

    static {
        UIDefaults uid = UIManager.getLookAndFeel().getDefaults();
        listForeground = uid.getColor ("List.foreground");
        listBackground = uid.getColor ("List.background");
    }
}
```

```

        listSelectionForeground = uid.getColor ("List.selectionForeground");
        listSelectionBackground = uid.getColor ("List.selectionBackground");
        foregroundComps =
            listForeground.getRGBColorComponents(null);
        foregroundSelectionComps =
            listSelectionForeground.getRGBColorComponents(null);
backgroundComps =
            listBackground.getRGBColorComponents(null);
backgroundSelectionComps =
            listSelectionBackground.getRGBColorComponents(null);
    }
    public Color colorizedSelectionForeground,
        colorizedSelectionBackground;

    public static final int ANIMATION_DURATION = 1000;
    public static final int ANIMATION_REFRESH = 50;

    public AnimatedJList() {
        super();
        addListSelectionListener (this);
        setCellRenderer (new AnimatedCellRenderer());
    }

    public void valueChanged (ListSelectionEvent lse) {
        if (! lse.getValueIsAdjusting()) {
            HashSet selections = new HashSet();
            for (int i=0; i < getModel().getSize(); i++) {
                if (getSelectionModel().isSelectedIndex(i))
                    selections.add (new Integer(i));
            }
            CellAnimator animator = new CellAnimator (selections.toArray());
            animator.start();
        }
    }
    public static void main (String[] args) {
        JList list = new AnimatedJList ();
        DefaultListModel defModel = new DefaultListModel();
        list.setModel (defModel);
        String[] listItems = {
            "Chris", "Joshua", "Daniel", "Michael",
            "Don", "Kimi", "Kelly", "Keagan"
        };
        Iterator it = Arrays.asList(listItems).iterator();
        while (it.hasNext())
            defModel.addElement (it.next());
        // show list
        JScrollPane scroller =
            new JScrollPane (list,
                ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
                ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
        JFrame frame = new JFrame ("Checkbox JList");
        frame.getContentPane().add (scroller);
    }

```

```

    frame.pack();
    frame.setVisible(true);
}

class CellAnimator extends Thread {
    Object[] selections;
    long startTime;
    long stopTime;
    public CellAnimator (Object[] s) {
        selections = s;
    }
    public void run() {
        startTime = System.currentTimeMillis();
        stopTime = startTime + ANIMATION_DURATION;
        while (System.currentTimeMillis() < stopTime) {
            colorizeSelections();
            repaint();
            try { Thread.sleep (ANIMATION_REFRESH); }
            catch (InterruptedException ie) {}
        }
        // one more, at 100% selected color
        colorizeSelections();
        repaint();
    }

    // colorizeSelections() listing below

    // AnimatedCellRenderer listing below
}

```

Like several previous hacks, this hack starts with some static code to get the platform colors for selected and unselected foreground and background colors. But this time, it also saves them off into arrays of their red, green, and blue components.

The component sets up a `ListSelectionListener`, which fires off a `CellAnimator` every time it gets the last of a series of `ListSelectionEvents`. The `CellAnimator` is a thread that runs for a short time only (defined by the class variable `ANIMATION_DURATION`), repeatedly calling `colorizeSelections()` and then sleeping briefly.

`colorizeSelections()`, shown in Example 2-19, calculates a float to express how much of the animation duration has elapsed. It then applies this as a proportion to the distance between the start and end values for each of the red, green, and blue components. For example, if the unselected background color is white (255, 255, 255), and the selected color is pure blue (0, 0, 255), then halfway through the animation the color should be (127, 127, 255), where 127 is halfway between the start and end values for the red and green components, and blue doesn't change.

### Example 2-19. Determining animation color for selected cells

```

public void colorizeSelections() {

```



```

// calculate % completion relative to start/stop times
float elapsed = (float) (System.currentTimeMillis() - startTime);
float completeness = Math.min ((elapsed/ANIMATION_DURATION), 1.0f);
// calculate scaled color
float colorizedForeComps[] = new float[3];
float colorizedBackComps[] = new float[3];
for (int i=0; i<3; i++) {
    colorizedForeComps[i] =
        foregroundComps[i] +
        (completeness *
         (foregroundSelectionComps[i] - foregroundComps[i]));
    colorizedBackComps[i] =
        backgroundComps[i] +
        (completeness *
         (backgroundSelectionComps[i] - backgroundComps[i]));
}
colorizedSelectionForeground =
    new Color (colorizedForeComps[0],
              colorizedForeComps[1],
              colorizedForeComps[2]);

colorizedSelectionBackground =
    new Color (colorizedBackComps[0],
              colorizedBackComps[1],
              colorizedBackComps[2]);
}

```

The cell renderer in Example 2-20 is very simple: it just looks to see if the cell it's rendering is selected; so, it sets its foreground and background to the colorized values. It also sets the cell to be opaque, meaning that the renderer wants the responsibility of drawing all the pixels, which is necessary to make the background color fill the cell. In a more complex cell layout, you might need to apply the foreground and background colors to all the cell's children and make them opaque, too.

### Example 2-20. Rendering the animated list cells

```

class AnimatedCellRenderer extends DefaultListCellRenderer {
    public Component getListCellRendererComponent(JList list,
                                                Object value,
                                                int index,
                                                boolean isSelected,
                                                boolean hasFocus) {

        Component returnMe =
            super.getListCellRendererComponent (list, value, index,
                                                isSelected, hasFocus);

        if (isSelected) {
            returnMe.setForeground (colorizedSelectionForeground);
            returnMe.setBackground (colorizedSelectionBackground);
            /* this might be necessary if you have more

```

```

        elaborate cells
    if (returnMe instanceof Container) {
        Component[] children =
            ((Container)returnMe).getComponents ();
        System.out.println (children.length + " children");
        for (int i=0;
            (children != null ) && (i<children.length); i++) {
            children[i].setForeground (colorizedSelectionForeground);
            children[i].setBackground (colorizedSelectionBackground);
        }
    }
    /*
    if (returnMe instanceof JComponent)
        ((JComponent) returnMe).setOpaque(true);
    }
    return returnMe;
}
}

```

When you run the code, clicking on a cell makes it briefly fade into the selection color, as seen in Figure 2-11 .

One potential improvement: if your list allows multiple selections, then all the selected cells will animate, and it would make more sense to animate just the one that the user has clicked on. You could do this by figuring out (by caching previous selections [Hack #15] ) which item is the new selection, and setting a flag so that the cell renderer applies only the colorized foreground and background colors to that cell.

Figure 2-11. Fading in a cell selection

## Hack 19. Turn Methods into List Renderers



By using a little bit of reflection, you can make a generic `ListCellRenderer` that can render data using any method at runtime.

`JLists`, like `JTable` and `JTree`, use a decorator pattern to customize how they look. This system of cell renderers works well, but it can require you to build a unique renderer class for each type of object you want to put into your lists. Often, all you really want to do is call a particular method on the objects in your list, but writing a complete class to just call one method is a lot of work for such a small task. This hack shows you how to use reflection to create a generic cell renderer that can be reused on any object without subclassing.

### 2.8.1. Building a Generic Renderer

The default `JList` cell renderer will just call `toString()` on the objects in the list and draw the resulting string to the screen. This is fine for simple uses where you really are just looking at a list of strings or objects with appropriate `toString()` methods. More complicated applications and they all become more complicated eventually require more complicated objects, and those objects might not have a convenient or useful `toString()` method. Eventually, you have to write a custom renderer for the particular object you wish to store. But there is another way: reflection.

Reflection lets you programmatically discover and access methods and fields in a java class at runtime. For this hack, you will use reflection to call an arbitrary method. This will allow the programmer using your generic renderer to specify a method using a string. This method will be used to render the component. Because you will be using reflection, you don't need to know the kind of objects in the list. As long as a method with the requested name exists, you can call it and get a value out. This will work even if some of the objects in the `JList` have different types. But let's not get ahead of ourselves. First, you need a basic cell renderer, as seen in [Example 2-21](#).

#### Example 2-21. A basic cell renderer

```
public class GenericListCellRenderer extends DefaultListCellRenderer {
    protected String method;
    public GenericListCellRenderer(String method) {
        super();
        this.method = method;
    }

    public Component getListCellRendererComponent(JList list, Object value,
```

```

    int index, boolean isSelected, boolean cellHasFocus) {

    JLabel label = (JLabel)super.getListCellRendererComponent(
        list,value,index, isSelected, cellHasFocus);
    label.setText("my text");
    return label;
}

```

[Example 2-21](#) declares a subclass of the `DefaultListCellRenderer` the standard implementation of a `ListCellRenderer`. The `GenericListCellRenderer` class takes a method string in its constructor. This string is the name of the method to call on the list value objects.

All `ListCellRenderers` have a `getListCellRendererComponent()` method, which returns a component to do the actual drawing. Most implementations (`DefaultListCellRenderer` included) use `JLabels` as the drawing components because they are relatively lightweight and can have both text and icons. The previous code gets the `JLabel` component from the superclass and sets the text to *my text*. Once added to a `JList`, this code will be called for each item in the list, meaning they will all be drawn as *my text*. This works, but it isn't very useful. Now it's time to add some reflection:

```

try {
    Method meth = value.getClass().getMethod(method,null);
    if(meth != null) {
        Object retval = meth.invoke(value,null);
        label.setText(""+retval);
    }
} catch (Exception ex) {
    System.out.println("got an exception: " + ex);
    ex.printStackTrace();
    label.setText(""+value);
}
return label;

```

The previous code replaces the `label.setText()` method in the original renderer. It retrieves the specified method from the current list value and stores it in a `Method` object. This object represents the abstract method itself. If you did `new String("text").getClass().getMethod("toString",null)`, then you would get an object that represents the `toString()` method on any string. Once you have this method, you can call it on the actual object at hand. `meth.invoke()` will invoke the method on the real list item, returning a value into `retval`. Both `getMethod()` and `invoke()` take an additional argument, which is null in the previous code. This argument is actually an array representing the arguments to the method being called. For this hack to work, you must assume that the method has no arguments, so `null` is used.

Once you have the return value of the method in hand, you can call `setText()`. I set it to `""+retval` because that will automatically handle `nulls` and call `toString()` on the value itself. The reflection code can throw an exception, so it's all wrapped up on a `TRY-catch` block. If the reflection fails, then it will set the text using `toString()` on the list item as a backup, which is what the standard renderer would do.

## 2.8.2. Putting It All Together

To use this new renderer, you need to create a `JList` and set its `CellRenderer` property. The following code creates a frame with one `JList` in it, creates a custom renderer for the `toString()` method, then packs and shows the frame on screen. The list contains an array of strings, representing common subatomic particles:

```
public static void main(String[] args) {
    String[] data = { "Proton", "Neutron", "Electron" };
    JList list = new JList(data);

    GenericListCellRenderer renderer =
        new GenericListCellRenderer("toString");
    list.setCellRenderer(renderer);

    JFrame frame = new JFrame("Cell Renderer Hack");
    frame.getContentPane().add(list);
    frame.pack();
    frame.setVisible(true);
}
```

The generic renderer can call any method on the list item objects as long as the method has no arguments and doesn't return void. It will even work with primitives. You could call `hashCode()`, which returns an int, like this:

```
GenericListCellRenderer renderer =
    new GenericListCellRenderer("hashCode");
```

Using `toString()` on the strings will be the same as the default renderer, simply drawing *Proton*, *Neutron*, and *Electron* in the list (see [Figure 2-12](#)).

Figure 2-12. Renderer using the `toString()` method

The resulting change would look like [Figure 2-13](#).

## Figure 2-13. Renderer using the hashCode( ) method

Using reflection for cell renderers is a very powerful concept because you can reuse potentially complicated code with very little additional effort. Using it to display strings is just a trivial example. Imagine you had a bunch of objects representing entries from an RSS feed. Instead of creating a custom renderer or wrapping the entries in objects with a custom `toString( )` method, you could use the `GenericListCellRenderer` with `getTitle( )` to automatically call the `getTitle( )` method on the entry objects no new subclasses or extra code. Just a single string and the renderer takes care of the rest. That is the power of reflection.

## Hack 20. Create a Collections-Aware JComboBox



You've moved on from Vector; your combo boxes should, too.

`JComboBox` is one of Swing's oldest components. Unfortunately, it accepts arrays of objects and Vectors only. Now that Collections objects like List have been part of the JDK for years, it would be nice to use them directly in a combo box without shuffling objects in and out of arrays. Fortunately, the `JComboBox` uses an MVC (Model-View-Controller) architecture, so you can solve this problem with a simple implementation of a `ComboBoxModel`.

To start, you need to figure out what the custom model should do. For our purposes, it needs to accept a List in the constructor and preserve any ordering supplied. Another nifty feature would be automatic updates. If you add or delete values to the List, the combo box should update itself automatically. [Example 2-22](#) is a good start.

### Example 2-22. A basic combo box to accept lists

```
public class ListComboBoxModel implements ComboBoxModel {
    protected List data;

    public ListComboBoxModel(List list) {
        this.listeners = new ArrayList();
        this.data = list;
        if(list.size() > 0) {
            selected = list.get(0);
        }
    }

    protected Object selected;
    public void setSelectedItem(Object item) {
        this.selected = item;
    }
    public Object getSelectedItem() {
        return this.selected;
    }

    public Object getElementAt(int index) {
        return data.get(index);
    }
    public int getSize() {
```

```

    return data.size();
}

protected List listeners;
public void addListDataListener(ListDataListener l) {
    listeners.add(l);
}
public void removeListDataListener(ListDataListener l) {
    this.listeners.remove(l);
}
}

```

This implementation is pretty much what you'd expect. Each method in `ComboBoxModel` is implemented (along with its parent interface, `ListDataModel`). The constructor saves a reference to the `List` and selects the first element if there is one. The `selectedItem` accessor works as expected, using the `selected` variable. `getElementAt()` and `getSize()` both pass the work on to the underlying `List`, and the `ListDataListener` methods work with a second `List` for managing the listeners. The important thing to notice here is that the code saves the reference to the `List` that was passed in, rather than creating a copy. This means that the model will always be in sync with the underlying list implementation. If you call `list.add("new item")`, it will show up in the combo box automatically.

To test this, use the simple class in [Example 2-23](#).

## Example 2-23. Testing the List-based JComboBox

```

public class CBTest {
    public static void main(String[] args) {
        JFrame frame = new JFrame("Hack #4: Create a Collections-Aware
            JComboBox");
        Container root = frame.getContentPane();
        root.setLayout(new BorderLayout(root, BorderLayout.X_AXIS));

        // List combo box
        final List list = new ArrayList();
        list.add("Blinky");
        list.add("Pinky");
        list.add("Inky");

        final ListComboBoxModel mod2 = new ListComboBoxModel(list);
        JComboBox cb2 = new JComboBox();
        cb2.setModel(mod2);
        root.add(cb2);

        final JButton bt2 = new JButton("Add Item");
        bt2.addActionListener(new ActionListener() {
            public void actionPerformed(ActionEvent evt) {
                list.add("Clyde");
            }
        });
    }
}

```



```

    }
  });
  root.add(bt2);
  // show the frame
  frame.pack();
  frame.setVisible(true);
}
}

```

The program creates a `JComboBox` that uses the new `ListComboBoxModel`. First, it creates a list, populates it with data, passes it to the `ListComboBoxModel` constructor, and then sends that to the new `JComboBox()`. There is also a button that adds a new item to the list when clicked.

When you compile and run this program, it...doesn't work! The addition to the `List` doesn't show up in the combo box. A look over the API might remind you of the `ListDataListener` class. When `setModel()` is called, the `JComboBox` registers itself as a listener so that it can update itself when the model changes. This means the `ListComboBoxModel` needs to fire off an event when the underlying `List` changes.

The problem here is that Java doesn't provide a standard event mechanism for collections. No problem we can write our own. Because `ActionEvents` are the most common ones in Swing, just reuse those with a command string of "update". Here's the new event handling code added to the bottom of `ListComboBoxModel`:

```

public class ListComboBoxModel implements ComboBoxModel, ActionListener {
  //..... the rest of the code

  // event code
  public void actionPerformed(ActionEvent evt) {
    if(evt.getActionCommand().equals("update")) {
      this.fireUpdate();
    }
  }

  public void fireUpdate() {
    ListDataEvent le = new ListDataEvent(this,
      ListDataEvent.CONTENTS_CHANGED,
      0,
      data.size());
    for(int i=0; i<listeners.size(); i++) {
      ListDataListener l = (ListDataListener)listeners.get(i);
      l.contentsChanged(le);
    }
  }
}

```

The `actionPerformed()` method implements `ActionListener`. It just looks for events with the "update"

command and calls `fireUpdate()`. That sends a `ListDataEvent` to all of the model's listeners, which includes the `JComboBox` itself.

Here is the modified `JButton` from the sample program:

```
bt2.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent evt) {
        list.add("Clyde");
        mod2.actionPerformed(new ActionEvent(bt2,0,"update"));
    }
});
```

Running the program again, everything works as expected, as seen in [Figure 2-14](#). When you press the button, *Clyde* is added to the list and the combo box updates itself.

## Figure 2-14. The collections-aware combo box

Because the `List` is backing the new model, you have to consider it to be live. This means you have to address any changes that need to be done on the event-dispatch thread in order to avoid threading issues (like race conditions). In this program, the code modifies the `List` from another action listener, which means the code is already on the event thread; however, if this was not the case, you would have to use another mechanism, such as `SwingUtilities.invokeLater()`.

Now that you have a combo box that's aware of `Lists`, it makes sense to add another that understands `Maps`. Many times when you create a UI, you will want the user to select from a set of values. These values are very meaningful to your program, but because they often come from a database, they are short strings like `"Calc_Rng"`, which won't mean anything to your users. They expect to see something like *Calculate Range*. What we need is a simple structure to map between the user-friendly descriptions and the real values. Sounds like a job for `Map` (Dora fans unite)!

Because `Map` is a collection, the implementation will be similar to what you've already seen; in fact, you can build it with a subclass of `ListComboBoxModel`. There are a few issues to tackle first, though. A `Map` defines a set of mappings between keys and values; it does not define the order of the keys themselves. This will make `getElementAt(index)` hard to implement because there is no notion of order in `Maps`. Further, the combo box only knows about the keys it uses for display, and not the underlying values, so you will need another way of pulling the real values out of the model. With

these issues in mind, take a look at [Example 2-24](#).

## Example 2-24. Map-based combo box model

```
public class MapComboBoxModel extends ListComboBoxModel {

    protected Map map_data;
    protected List index;

    public MapComboBoxModel(Map map) {
        this.map_data = map;

        index = new ArrayList();
        buildIndex();
        if(index.size() > 0) {
            selected = index.get(0);
        }
    }

    protected void buildIndex() {
        index = new ArrayList(map_data.keySet());
    }

    public Object getElementAt(int i) {
        return index.get(i);
    }

    public int getSize() {
        return map_data.size();
    }

    public void actionPerformed(ActionEvent evt) {
        if(evt.getActionCommand().equals("update")) {
            buildIndex();
            fireUpdate();
        }
    }

    public Object getValue(Object selectedItem) {
        return map_data.get(selectedItem);
    }
    public Object getValue(int selectedItem) {
        return getValue(index.get(selectedItem));
    }
}
```

The `MapComboBoxModel` accepts a collection in its constructor this time a `Map` saving it for later reference. To maintain the order of the keys, the class uses a `List` called `index`. The constructor calls `buildIndex()` to populate the `List` with the `Map`'s set of keys, and then sets the selected item just like in the `List` version. `getElementAt()` uses the index to get the display values and `getSize()` uses the size of the `Map` itself.

`actionPerformed()` is different from the `List` version and calls `buildIndex()` before `fireUpdate()`. This ensures that the index is always in sync with the underlying map and that the `JComboBox` reflects that. There is no implementation of `fireUpdate()` or managing the listeners because the parent class, `ListComboBoxModel`, takes care of those.

The final additions are the two `getValue()` methods, which allow you to retrieve the actual values out of the `Map`, based on an index or key. One uses the actual selected item and the other uses the index returned by `JComboBox`. `getSelectedIndex()`.

Here's a slight modification to the test program to try this out:

```
// Map Combo Box
final Map map = new HashMap();
map.put("Red", "#ff0000");
map.put("Green", "#00ff00");
map.put("Blue", "#0000ff");

final MapComboBoxModel mod3 = new MapComboBoxModel(map);
final JComboBox cb3 = new JComboBox();
cb3.setModel(mod3);
root.add(cb3);
final JButton bt3 = new JButton("Test Selection");
bt3.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent evt) {
        System.out.println("Human color: " + cb3.getSelectedItem());
        System.out.println("Computer color: " +
            mod3.getValue(cb3.getSelectedIndex()));
    }
});
root.add(bt3);
```

This `HashMap` maps human-readable color names into the hex values that my program wants. The associated button will test the currently selected color, printing both the description the user sees and the underlying hex value.

Again, you would have to send an `ActionEvent` to the model to keep it in sync if you added new elements.

The one downside to this approach is that you have no control over the order of the items displayed to the user. It depends on how the `Map` decides to store them. To impose order on them, you could

sort the index in the `buildIndex` method (e.g., alphabetically), but I think I'll leave that as a future enhancement.



# Chapter 3. Tables and Trees

[Section 3.1. Hacks 2127: Introduction](#)

[Hack 21. Size Your Columns to Suit Your JTable's Contents](#)

[Hack 22. Add Column Selection to JTables](#)

[Hack 23. Let Your JTables Do the Sorting](#)

[Hack 24. Create a JDBC Table Model](#)

[Hack 25. Export Table Data to an Excel Spreadsheet](#)

[Hack 26. Search Through JTables Easily](#)

[Hack 27. Animate JTree Drops](#)

[← PREV](#)

## 3.1. Hacks 2127: Introduction

A table component was one of the most obvious missing features in AWT, and among the most welcome additions when Swing came out. However, the `JTable` may be used too much it's easy to throw an `Object[][]` at the constructor and get a full-blown GUI table, and some developers don't question the wisdom of this sort of coding.

But despite the generosity of the Swing `JTable` API, there are a few things still missing. Wouldn't it be nice if the table model keep itself sorted, or if the column widths had a non-ugly default that takes their contents into account? Well, you didn't buy this book to argue API theory the point here is to hack things into shape. So, let's get started.

[← PREV](#)

## Hack 21. Size Your Columns to Suit Your JTable's Contents



A one-digit column does not need 100 pixels of dead space. You know this; your JTables should, too.

Does [Figure 3-1](#) look like your typical JTable?

Figure 3-1. JTable with default column sizing

If it does, then we have a usability problem to discuss. By default, the columns of a `JTable` are all the same size. For this data, that's obviously a *terrible* decision: there's far too much space reserved for the numbers in the count column, and not nearly enough in the URL column. So, how are you going to fix this?

If you said "turn on the horizontal scrollbar," please close this book, grasp it with both hands, and firmly smack yourself in the head with it. *No*, you are *not* turning on the horizontal scrollbar! Use the pixels available to you before you resort to the user-annoying desperation of horizontal scrolling. In this case, the count column has lots of pixels to spare; you just need to reallocate this extra space to the URL column.

### 3.2.1. Resetting Column Widths

What makes programmatic column resizing difficult for many Swing programmers is that they can't even find the right methods to use. If all you ever work with is `JTable` (and maybe a few custom cell renderers), you'll notice that the JavaDoc for those classes says nothing about column widths. The problem may be that the `JTable` is so generous with helpful methods that you'd never even notice




that it's made up of `TableColumn` objects. Take a look at that `TableColumn`'s JavaDoc, and you'll find getters and setters for minimum, maximum, and preferred widths for columns.

As with components that defer to layout managers, the right property to reset is the preferred width let the column tell the `JTable` how wide it would like to be, but let the `JTable` make the final decision based on the information available to it (after all, there could be other columns contending for space, there might not be enough space for all the columns' preferred size, etc.).

Given that the key to this hack will be calling `setPreferredWidth()` on the `TableColumns`, the obvious question is: what value should you use for the preferred width? Here's a strategy: assuming you already have the table data, use the width of the widest item in the column. And how do you get that? By using the table's cell renderers to actually figure out how big each cell should be.

`ColumnResizer`, shown in [Example 3-1](#), has a single static method, `adjustColumnPreferredWidths()`, which takes a `JTable` as its only argument.



Yes, the name is a mouthful, but it's helpful to express exactly what the method does.

### Example 3-1. Adjusting column sizes to suit their contents

```
public class ColumnResizer {
    public static void adjustColumnPreferredWidths(JTable table) {
        // strategy - get max width for cells in column and
        // make that the preferred width
        TableColumnModel columnModel = table.getColumnModel();
        for (int col=0; col<table.getColumnCount(); col++) {

            int maxwidth = 0;
            for (int row=0; row<table.getRowCount(); row++) {
                TableCellRenderer rend =
                    table.getCellRenderer(row, col);
                Object value = table.getValueAt (row, col);
                Component comp =
                    rend.getTableCellRendererComponent (table,
                        value,
                        false,
                        false,
                        row,
                        col);
                maxwidth = Math.max (comp.getPreferredSize().width, maxwidth);
            } // for row
            TableColumn column = columnModel.getColumn (col);
            column.setPreferredWidth (maxwidth);
        } // for col
    }
}
```

For each column in the table, the method goes through all the rows and renders each cell. It keeps a running tally of the widest component in the column, and after considering all the rows, it sends this maximum width to `setPreferredWidth()`.

[Example 3-2](#) demonstrates a unit test class to exercise `ColumnResizer`. `TestColumnResizer` simply puts the `JTable` into a `JFrame`, `pack()`s it, and shows it. After a five-second delay, it calls `adjustColumnPreferredWidths()` to reset the preferred column widths, and it `revalidate()`s the table to get a repaint.

### Example 3-2. Testing automatic column sizing

```
public class TestColumnResizer {
    final static Object[][] TABLE_DATA = {
        {new Integer(1), "ONJava", "http://www.onjava.com/"},
        {new Integer(2), "Joshy's Site", "http://www.joshy.org/"},
        {new Integer(3), "Anime Weekend Atlanta", "http://www.awa-con.com/"},
        {new Integer(4), "QTJ book",
        "http://www.oreilly.com/catalog/quicktimejvaadn/"}
    };

    final static String[] COLUMN_NAMES = {
        "Count", "Name", "URL"
    };

    public static void main (String[] args) {
        // 142 mac l&f has a header bug - force metal for today
        try {

            UIManager.setLookAndFeel (
                UIManager.getCrossPlatformLookAndFeelClassName());
        } catch (Exception e) { e.printStackTrace();}
        DefaultTableModel mod =
        new DefaultTableModel (TABLE_DATA, COLUMN_NAMES);
        JTable table = new JTable (mod);
        JScrollPane pane =

        new JScrollPane (table,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
        JFrame frame = new JFrame ("JTable Column Widths");
        frame.getContentPane().add (pane);
        frame.pack();
        frame.setVisible (true);

        try {
            Thread.sleep (5000);
        } catch (Exception e) { e.printStackTrace(); }
    }
}
```

```
// now get smart about col widths
final JTable fTable = table;
SwingUtilities.invokeLater(new Runnable() {

    public void run() {
        ColumnResizer.adjustColumnPreferredWidths (fTable);
        fTable.revalidate();
    }
});
}
```

Notice that the column width adjustment and `revalidate()` have to be done with a Swing worker thread because the table shouldn't be updated from anything other than the AWT event-dispatch thread.

When run, this initially produces the ugly table seen back in [Figure 3-1](#); after five seconds, it resets automatically to the much more pleasing column widths of [Figure 3-2](#).

If you resize the `JFrame`, the columns will gain and lose space proportionally, so the URL column will always have much more space than the count column, making it more likely the table will be well-suited to further contents you might add.

Figure 3-2. JTable columns resized to suit their contents

### 3.2.2. Accounting for Header Cells

There's a problem with the new weighting of the column widths: since the one-digit contents of the count column are so narrow, the count column header has been crushed to the point where Swing needs to show it with ellipses. Not so good.

The problem, of course, is that the width of the header was never considered in the preferred width calculation. You can do that yourself by changing the logic to prefer the wider of the widest content cell and the header cell. This means you need to get the header cell renderer (either from the `TableColumn` or the `JTableHeader`), then render a cell and get its width.

To do this, replace these two lines:

```
TableColumn column = columnModel.getColumn (col);
column.setPreferredWidth (maxwidth);
```

with these:

```
TableColumn column = columnModel.getColumn (col);
TableCellRenderer headerRenderer = column.getHeaderRenderer();
if (headerRenderer == null)

    headerRenderer = table.getTableHeader().getDefaultRenderer();
Object headerValue = column.getHeaderValue();
Component headerComp =
    headerRenderer.getTableCellRendererComponent (table,
        headerValue,
        false,
        false,
        0,
        col);
maxwidth = Math.max (maxwidth,
    headerComp.getPreferredSize().width);
column.setPreferredWidth (maxwidth);
```

When you run this version of `ColumnResizer`, the table should look like [Figure 3-3](#).

### Figure 3-3. Accounting for header width in JTable column resizing

Having done this, it's still possible to crush either table cells or headers if you resize (programmatically or by dragging the frame's corner) to a point where there's just not enough room for all the content. If you really wanted to keep header cells intact, you could alter the previous code to set the `TableColumn`'s minimum width to the preferred width of the header cell, assuming the header isn't much wider than the content. Ultimately, it's really a question of what data you're putting in the table

and what looks right to you.

### 3.2.3. Hacking the Hack

"But," you might be saying, "what if I don't have my table data in advance?" If you have some idea of what the data is probably going to be like, you could create your table, add this "prototype" data as a row, size the columns, and then remove the prototype...all before ever making the table visible. That would give your users reasonable default sizing, and then they could resize columns by dragging header borders as desired. Of course, you could always hook up a `TableModelListener` and resize the columns every time data is inserted, deleted, or updated, but having the column widths jump around magically can be *very* annoying.



## Hack 22. Add Column Selection to JTables



So, why can't I select a column by clicking on its header?

Here's something that seems strange about `JTables`: you can click on the column headers, but only for the purpose of reordering columns not for selecting the contents of that column. I don't know about you, but considering that I almost never reorder columns, it seems like the default behavior is backward. And if your users have had their expectations set by working with Excel or other spreadsheets, they'll surely expect the ability to select an entire column.

The to-do list for adding column selectability to a `JTable` consists of two items:

- Change which kinds of multiselection are allowed.
- Wire up a `MouseListener`.

[Example 3-3](#) shows a very simple implementation.

Example 3-3. A `JTable` that allows column selection by clicking on column headers

```
public class ColumnSelectableJTable extends JTable {
    public ColumnSelectableJTable (Object[][] items, Object[] headers) {
        super (items, headers);
        setColumnSelectionAllowed (true);
        setRowSelectionAllowed (false);
        // set up action listener on table header
        final JTableHeader header = getTableHeader();
        header.addMouseListener (new MouseAdapter() {
            public void mouseReleased (MouseEvent e) {
                if (! e.isShiftDown())
                    clearSelection();
                int pick = header.columnAtPoint(e.getPoint());
                addColumnSelectionInterval (pick, pick);
            }
        });
    }
}
```

The constructor is deliberately simple, taking only a two-dimensional array of contents and a one-dimensional array of headers. Of course, `JTable` has many more constructor signatures than this, but this is the one that will be easiest to expose to a test class (do I have to mention that building out the other constructors is left to the reader as an exercise?).

The next step is changing the defaults for multi-cell selection. The default is to allow row selection exactly what you *don't* want. So, enable column selection and disable row selection. Next, you want to catch clicks on the headers so you can select columns in response to them. Unfortunately, the `JTableHeader` component doesn't have an `addActionListener()` method, so the best you can do is add a `MouseListener` instead. Of its various methods, you only need to override `mouseReleased()`, which signals the end of a click-and-release.

To implement the column selection, check the event to see if the Shift key is down. If it is, then the user wants to do a multiple selection, meaning that he intends to add the clicked column to any that are already selected. If not, then you can clear out any existing selection. Next, you need to figure out just which column was clicked. You can do this by asking the event for the Point at which the click occurred. This will be in the coordinate space of the `JTableHeader`, making it suited for calling `JTableHeader.columnAtPoint()`. That returns an index, which you can select by calling `JTable.addColumnSelectionInterval()`, specifying a one-column range that begins and ends at the selected column.

To run this code, I've put together a class that sends some trivial table data to a `ColumnSelectableJTable` and shows the whole thing in a `JFrame`. This test is shown in [Example 3-4](#)

### Example 3-4. Testing the column-selectable JTable

```
public class TestColumnSelectableJTable extends Object {
    private static final Object[][] items= {
        {"Monday", "Cheeseburgers", "French Fries", "Peaches"},
        {"Tuesday", "Catfish", "Rice", "Starfruit"},
        {"Wednesday", "Tortellini", "Garlic Bread", "Pears"},
        {"Thursday", "Chicken", "Potatoes", "Strawberries"},
        {"Friday", "Pizza", null, "Fruit Cocktail"}
    };

    private static final Object[] headers = {
        "Day", "Main course", "Side dish", "Fruit"
    };

    public static void main (String[] args) {
        JFrame f = new JFrame ("Selectable columns");
        ColumnSelectableJTable table =


        new ColumnSelectableJTable(items, headers);
        JScrollPane scroller =

        new JScrollPane (table,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
```

```
ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS);  
f.getContentPane().add (scroller);  
f.pack();  
f.setVisible(true);  
  
}  
}
```

When run, this table's columns are selectable either by clicking on a cell in the column or on a header of any of the columns, as seen in [Figure 3-4](#).

Figure 3-4. Selecting jTable columns by clicking on headers



Day	Main course	Side dish	Fruit
Monday	Cheeseburgers	French Fries	Peaches
Tuesday	Catfish	Rice	Starfruit
Wednesday	Tortellini	Garlic Bread	Pears
Thursday	Chicken	Potatoes	Strawberries
Friday	Pizza		Fruit Cocktail



## Hack 23. Let Your JTables Do the Sorting



Why doesn't Swing already offer this? Oh well, here's how to do it yourself.

It's hard to imagine you'll do much serious work with `JTables` without needing to sort the contents by one of the columns, or support changing between columns to use as the sort criteria. In fact, given how generous the Swing API usually is, it's kind of surprising that it doesn't already offer it. Oh well, it's not that hard to do for yourself.

There are a couple of approaches you could take to solve this problem. You could create a subclass of `TableModel`, one that keeps an internal `Comparator` to do the sorting and resorts every time an `add()` or `remove()` type method is called. The drawback to this approach is choosing which of the model classes to subclass. If you go too high up the hierarchy by implementing `TableModel` or subclassing `DefaultTableModel`, you would miss some typical Swing functionality that developers expect, like the ability to add and remove rows provided by `DefaultMutableTableModel`. On the other hand, if you subclass `DefaultMutableTableModel`, other developers will be unhappy because subclassing your class requires them to pick up public `add()` and `delete()` type methods that expose their data in ways they don't want.

So, consider an alternative: two table models, one that the `JTable` sees and another that the developer sees. Specifically, the developer will pass her `TableModel` to the constructor of the sorting model, which will wire up for events on the model. Then, the developer will set the sorting model as the `JTable`'s model. Changes in the base model will force the sorting model to resort its contents and then fire off events to `JTable` to drive updates to the onscreen representation.

There are more details in the actual implementation of course, particularly when it comes to doing the sorting. [Example 3-5](#) shows the code for the `SortableTableModel`.

### Example 3-5. Self-sorting TableModel

```
public class SortableTableModel implements TableModel,
    TableModelListener {
    EventListenerList listenerList = new EventListenerList();
    TableModel delegatedModel;
    int[] sortedIndices;
    int sortColumn;
    Comparator comparator;
    Comparator[] comparators;

    public SortableTableModel (TableModel tm) {
        delegatedModel = tm;
    }
}
```

```
delegatedModel.addTableModelListener (this);
comparators = new Comparator [tm.getColumnCount()];
sortedIndicies = new int [0];
setSortColumn (0);

}
// listener stuff
public void addTableModelListener (TableModelListener l) {
    listenerList.add (TableModelListener.class, l);
}

public void removeTableModelListener (TableModelListener l) {
    listenerList.remove (TableModelListener.class, l);
}

public void fireTableModelEvent (TableModelEvent e) {
    Object[] listeners = listenerList.getListenerList();
    for (int i = listeners.length-2; i>=0; i-=2) {

if (listeners[i] == TableModelListener.class) {
    ((TableModelListener) listeners[i+1]).tableChanged(e);
}
}
}

// contents stuff
public Class getColumnClass(int columnIndex)
    if (delegatedModel.getRowCount() > 0)
return delegatedModel.getValueAt(0, columnIndex).getClass();
    else
return Object.class;
}

// getColumnCount(), getColumnName(), getRowCount(),
// getValueAt(), isCellEditable(), setValueAt() listings below

// internal helpers
public void setComparatorForColumn (Comparator c, int i) {

// range check
if (i > comparators.length) {
    Comparator[] newComparators = new Comparator[i+1];
    System.arraycopy (comparators, 0,
        newComparators, 0,
        comparators.length);
    comparators = newComparators;
}
// add the comparator
comparators[i] = c;

}
public void setSortColumn (int i) {
```

```
sortColumn = i;

// reset current comparator, possibly to null, which
// will make us use "natural ordering" for those values
comparator = null;
if ((comparators != null) &&
    (comparators.length > 0))
    // is there one in the list of comparators?
    comparator = comparators[sortColumn];

// now do the sort
resort();
}

public int getSortColumn () {
    return sortColumn;
}

// resort() method listed below
// SortingDelegate inner class listed below
// SortingDelegateComparator inner class listed below

public void tableChanged (TableModelEvent e) {
    switch (e.getType()) {
        case TableModelEvent.DELETE: {
            resort();
            fireAllChanged();
            break;
        }

        case TableModelEvent.INSERT: {
            resort();
            fireAllChanged();
            break;
        }
        case TableModelEvent.UPDATE: {
            resort();
            fireAllChanged();
            break;
        }
    }
}

protected void fireAllChanged() {
    TableModelEvent e = new TableModelEvent (this);
    fireTableModelEvent (e);
}
}
```

The instance variables in this class include a list of event listeners to support the `TableModelListener` methods specified by the `TableModel` interface, the model passed in by the caller, a map of sorted indices, the index of the column to sort by, the current `Comparator` to sort with, and an array of `Comparators` arranged by the column each one sorts (the value may be `null` if the column is a primitive or another type that doesn't need a custom `Comparator`).

The `sortedIndices` array is crucial to maintaining the relationship between the two tables. The values in this array indicate a mapped row in the `delegatedModel`. Thus, if a caller asks for a value in row 2, this model will get the value of `sortedIndices[2]` and get that row from the `delegatedModel`. All the methods of `TableModel` that work with `rows.getValueAt()`, `isCellEditable()`, and `setValueAt()` use this look up, so the real key to keeping the model working is to keep this map accurate, which in turn means to redo the sort:

- Whenever the contents of the underlying model change
- Whenever a caller changes the sorting criteria of this model

The constructor is largely trivial, setting the `delegatedModel` instance, adding a `TableModelListener` to it so the sorting model can resort on updates to the `delegatedModel`'s contents, and initializing the structures for the comparators and the row mapping. Supporting the listeners is also essentially boilerplate; here, I've used the `EventListenerList` and backward-counting event firing [[Hack #94](#)], as is done commonly throughout Swing.

The implementation of `getColumnClass()` is important; it ensures that `TableCellRenderers` will get used when appropriate. Swing's implementation of `AbstractTableModel` literally just returns `Object.class` in all cases, which causes everything to render as `JLabels` of the `Object's toString()`. Yuck. This version actually looks at the `delegatedModel` and, if it has any data, returns the class of the object in the first row of the designated column.

Next in the source, you'll find a series of methods that involve the contents of the model:

- `getColumnCount()`
- `getColumnName()`
- `getRowCount()`
- `getValueAt()`
- `isCellEditable()`
- `setValueAt()`

All of these methods delegate to the wrapped model, with the caveat that any that work with rows look up the mapped row from the `sortedIndices` array, as seen in [Example 3-6](#).

**Example 3-6.** Table model methods that delegate calls to the wrapped model

```
public int getColumnCount() {
```

```

    return delegatedModel.getColumnCount();
}
public String getColumnName (int index) {
    return delegatedModel.getColumnName (index);
}
public int getRowCount() {
    return delegatedModel.getRowCount();
}
private int getDelegatedRow (int row) {
    return sortedIndicies [row];
}
public Object getValueAt (int rowIndex, int columnIndex) {
    return delegatedModel.getValueAt (getDelegatedRow(rowIndex),
        columnIndex);
}
public boolean isCellEditable (int rowIndex, int columnIndex) {
    return delegatedModel.isCellEditable (rowIndex, columnIndex);
}
public void setValueAt (Object aValue, int rowIndex, int columnIndex) {
    delegatedModel.setValueAt (aValue, rowIndex, columnIndex);
}
}

```

But how do the contents get sorted? Any class that implements `Comparable` can be sorted by `Collections.sort()` or one of the `Arrays.sort()` methods, and thus doesn't require any special handling. However, you probably want to handle sorting any arbitrary class, which requires working with custom `Comparators` what the `comparators` array is for. In `setComparatorForColumn()`, you range-check the size of the array, and then cache the passed `Comparator` into the array index that corresponds to the column. For example, `setComparatorForColumn (myComparator, 2)` should set `comparators[2]` to `myComparator`.

This caches the comparators, but only one is used for sorting at any given time. In `setSortColumn()`, you cache the index of the sort column, but then you need to pull up the corresponding `Comparator`. Set the `comparator` the one that will be used to perform the sort to `null`, and then check the `comparators` list to see if there is a `Comparator` at the given index. If so, it will become the new `comparator`.

Now, you're ready to handle the sorting. When you need to sort, either because the sort index has changed or because the underlying model has changed, you call the `resort()` method, shown in [Example 3-7](#).

### Example 3-7. Resorting based on the current comparator

```

protected void resort() {
    // does sortedIndicies need to grow or shrink?
    if (sortedIndicies.length != delegatedModel.getRowCount()) {
        sortedIndicies = new int [delegatedModel.getRowCount()];
    }
    // build up a list of SortingDelegates
}

```

```

ArrayList sortMe = new ArrayList();
for (int i=0; i<delegatedModel.getRowCount(); i++) {

    SortingDelegate sd =
new SortingDelegate (delegatedModel.getValueAt(i, getSortColumn()), i);
    sortMe.add (sd);
}
// now sort him with the SortingDelegateComparator
SortingDelegateComparator sdc =

    new SortingDelegateComparator (comparator);
Collections.sort (sortMe, sdc);

// fill sortedIndicies array
// index -> value represents mapping from original
// row to sorted row
for (int i=0; i<sortMe.size(); i++) {

    sortedIndicies[i] =
((SortingDelegate) sortMe.get(i)).row;
}

// fire change event
fireAllChanged();
}

```

This starts by resetting the size of the `sortedIndicies` array, which will be wrong if the number of rows in the `delegatedModel` has changed. Next, build up an array list of `SortingDelegates`, an inner class containing a value from the `delegatedModel` (in the column to be sorted) and a mapped row number. This class is shown in [Example 3-8](#).

**Example 3-8.** Inner class to map sortable objects to their position in the current sort

```

public class SortingDelegate extends Object {
    public Object value; public int row;
    public SortingDelegate (Object v, int r) {
        value = v;
        row = r;
    }
}

```

This can be sorted by the `SortingDelegateComparator`, another inner class that maps the `compare()` call that is the heart of Java Collections-based sorting (shown in [Example 3-9](#)). It takes a `Comparator` (namely the sorting column's `Comparator`, if any) and on each `compare()`, it looks to see if that

`Comparator` is `null`; if not, it uses `Comparator.compare()` to do the sorting comparison. In this case, objects should be `Comparable`, which means the sorter can use `Comparable.compareTo()` to apply "natural ordering" (intuitive numeric ordering for all number types, ASCII ordering for strings, etc.). It throws an exception if there's neither a `Comparator` to use nor `Comparable` values.

### Example 3-9. Comparator for delegated sorting

```
class SortingDelegateComparator extends Object implements Comparator {
    Comparator comp;
    public SortingDelegateComparator (Comparator c) {
        comp = c;
    }
    public int compare (Object o1, Object o2) {

        Object v1 = ((SortingDelegate)o1).value;
        Object v2 = ((SortingDelegate)o2).value;
        if (comp != null)

            return comp.compare (v1, v2);
        else if (v1 instanceof Comparable)
            return ((Comparable)v1).compareTo (v2);
        else
            throw new IllegalArgumentException ("Can't compare objects "+
                "for sorting");
    }
}
```

With the list of `SortingDelegates` now sorted, you can walk the list and pull out the row field of each object, putting it in the `sortedIndices` array. The array is again ready to map all the method calls that refer to rows. You need to fire an event to tell the sorting model's listeners presumably just the `JTable` that contents have updated. Since the resort could affect none, some, or all of the rows, fire off an event saying the whole table has updated.

The final thing to deal with is the events you get from the wrapped model. These can be deletes, inserts, or updates in all cases, this implementation calls for a total resort and fires off the "everything changed" event.

A test class for this model needs to exercise the sorting and updating caused both by changing the sort criteria and by changing the underlying model. Also, to test the custom `Comparator` stuff, it needs to have at least one column whose contents aren't `Comparable` and thus need a `Comparator`.

`TestSortableTableModel` provides these with a simple three-column table with canned content and buttons to resort by each of those columns. A fourth button adds another row of data. The third column is a `java.awt.Color`, which gets its own simple `Comparator`. The code for the test class is shown in [Example 3-10](#).

### Example 3-10. Testing the self-sorting TableModel

```
public class TestSortableTableModel extends JPanel
    implements ActionListener {
    DefaultTableModel myModel;
    SortableTableModel mySortableModel;
    JButton sort1, sort2, sort3, bonus;

    static Object[] headers = {
        "Letter", "Number", "Color"
    };
    static Object[][] data = {

        {"A", new Integer(2), Color.gray.darker().darker()},
        {"B", new Integer (3), Color.gray},
        {"C", new Integer (1), Color.gray.darker()},

    };
    static Object[] bonusData = {
        "D", "0", Color.red
    };

    public TestSortableTableModel (DefaultTableModel m) {
        super (new BorderLayout());
        myModel = m; mySortableModel = new SortableTableModel (myModel);
        mySortableModel.setComparatorForColumn (new MyColorComparator(), 2);
        JTable table = new JTable (mySortableModel);
        table.setDefaultRenderer (java.awt.Color.class, new ColorRenderer());
        JScrollPane scroller =
new JScrollPane (table,
        ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
        ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS);
        table.setPreferredScrollableViewportSize (new Dimension (400, 200));
        setLayout(new BorderLayout());
        add (scroller, BorderLayout.CENTER);

        // add sort buttons
        JPanel buttonPanel = new JPanel();
        sort1 = new JButton ("Sort 1");
        buttonPanel.add(sort1);
        sort1.addActionListener(this);
        sort2 = new JButton ("Sort 2");
        buttonPanel.add(sort2);
        sort2.addActionListener(this);
        sort3 = new JButton ("Sort 3");
        buttonPanel.add(sort3);
        sort3.addActionListener(this);
        bonus = new JButton ("More data");
        buttonPanel.add(bonus);
        bonus.addActionListener(this);
        add (buttonPanel, BorderLayout.SOUTH);
    }
}
```



```

}
public void actionPerformed (ActionEvent e) {
    if (e.getSource() == sort1) {
mySortableModel.setSortColumn (0);
    } else if (e.getSource() == sort2) {
mySortableModel.setSortColumn (1);
    } else if (e.getSource() == sort3) {
mySortableModel.setSortColumn (2);
    } else if (e.getSource() == bonus) {
myModel.addRow (bonusData);
    }
}
}
public static void main (String[] args) {
    DefaultTableModel aModel =

new DefaultTableModel(data, headers) ;
    JFrame frame = new JFrame ("Sortable Table");
    frame.getContentPane().add (new TestSortableTableModel(aModel),
        BorderLayout.CENTER);
    frame.pack();
    frame.setVisible(true);

}
}

```

The test class declares its models: a `SortableTableModel` to pass to the `JTable` and a `DefaultMutableTableModel` for the developer to play with. It then declares the default table headers and data as `Object` arrays. The constructor takes a `TableModel` (as called by `main()`, it will be a `DefaultMutableTableModel` built from the canned data), from that builds a `SortableTableModel`, and then creates a `JTable`. It also sets a custom `Comparator` for the color column on the sortable model, and a custom renderer for the colors on the table. It then adds and wires up some buttons for sorting and adding extra rows, and puts it all in a `JFrame`.

The color `Comparator` is an idea that doesn't entirely make sense how can you say that green is greater than or less than blue? What this comparator does is look only at brightness, by converting from the RGB color space to HSB and grabbing the brightness value. To make this work for the test, the canned data simply uses shades of gray. Given this scheme, the sort will arrange colors in order from darkest to lightest (least bright to most bright). The comparator and a simple "fill the cell" renderer for colors are shown in [Example 3-11](#).

**Example 3-11.** The `Comparator` and `TableCellRenderer` handle color values in sorting a table test

```

class MyColorComparator implements Comparator {
    float[] hsb = new float[3];
    public int compare (Object o1, Object o2) {
        if (!(o1 instanceof Color)) ||

```

```
(! (o2 instanceof Color)))
return 0;

else {
Color c1 = (Color) o1;
Color c2 = (Color) o2;
Color.RGBtoHSB ( c1.getRed(),
                c1.getGreen(),
                c1.getBlue(),
                hsb);
float bright1 = hsb[2];
Color.RGBtoHSB ( c2.getRed(),
                c2.getGreen(),
                c2.getBlue(),
                hsb);

float bright2 = hsb[2];
if (bright1 == bright2)
    return 0;
else
    return ((bright1-bright2) < 0) ? -1 : 1;
}
}
public boolean equals (Object obj) {

return super.equals (obj);
}
}
class ColorRenderer extends DefaultTableCellRenderer {
    public Component getTableCellRendererComponent (JTable table,
        Object value,
        boolean isSelected,
        boolean hasFocus,
        int row,
        int col) {

        Component returnMe =
super.getTableCellRendererComponent (table, value,
        isSelected,
        hasFocus, row, col);
        if (value instanceof Color) {
Color color = (Color) value;
returnMe.setBackground (color);
if (returnMe instanceof JLabel) {


JLabel jl = (JLabel) returnMe;
jl.setOpaque(true);
jl.setText ("");

}
}
}
```

```
return returnMe;  
}  
}
```

When run, the table will be sorted by column0, which contains `Strings`, as seen in [Figure 3-5](#).

Figure 3-5. JTable sorted automatically by its first column




If you click the Sort 2 button (yes, the numbering is human-readable, and thus it's one greater than actual column indices), the table will immediately sort by the `Integers` in the middle column, as seen in [Figure 3-6](#).

The color column is next. Click Sort 3 to see the table sort by the colors, as seen in [Figure 3-7](#).


Figure 3-6. Sorting JTable by its second column

Figure 3-7. Sorting JTable by its third column



Finally, add in another row with the "More data" button. Because its color is solid red (maximum brightness), it will appear last when sorting by color. This is seen in [Figure 3-8](#).

Figure 3-8. Adding data to a self-sorting table model



## Hack 24. Create a JDBC Table Model



Bring your database tables into Swing with a minimum of hassle.

If you've worked with databases, you've probably also worked with the tools they provide for quick table maintenance and queries: command-line tools that are well suited to brief hack-and-slash work but hard to work with once you start dealing with any serious amount of data. It's hard enough to write the SQL command to return 10 or 20 columns in a query; it's even worse when the results word-wrap over the course of a dozen lines, and you can't tell where one result ends and another begins.

Wouldn't it be nice to be able to throw the contents of any database table into a Swing `JTable`? Give it a few JDBC strings, toss it in a `JFrame`, and *poof!* Instant GUI.

### 3.5.1. Building Connectivity

If you've worked with both JDBC and Swing, you'll grasp the concept in one sentence: use table metadata to build a Swing `TableModel` from the database table. If you haven't, here's the background you'll need: JDBC provides an abstract means of accessing databases. Java code to work with one database should work with another, the only difference is in the way that JDBC achieves a `Connection` to the database, which is usually a matter of providing `Strings` for:

- A driver class, which provides implementations of the various `java.sql` interfaces.
- A URL with which to connect to the database. This implies the use of sockets, though that's not necessarily the case. Some small embeddable databases can live in the same JVM as your application.
- An optional username.
- An optional password.

Once you have the `Connection`, you can begin to send commands (creation, deletion, and altering of tables) or queries to the database by creating `Statements` from the `Connection`. You can also use the `Connection` to get metadata about the database, like what kinds of features it supports, how long certain strings can be, etc. More importantly for this hack, it allows you to discover what tables are in the database, what columns they have, and what types of data are in those columns.

So, given just a `Connection` and the name of a table in the database, you can build a Java representation of its contents with two queries. The first query gets column metadata for the table and builds up arrays of the column names and their types. These can be mapped reasonably well to Java classes, at least for whatever types you intend to support. The second query gets all the data

from the table. For each row, it gets each column's value. This is put into a two-dimensional array, which represents the entire contents of the table.

With these two queries done, you have everything you need to support the abstract methods of `AbstractTableModel`:

- `getRowCount()` is the length of the `contents` array that you create.
- `getColumnCount()` is 0 if you have no contents, or the length of the first item in the contents array (which is itself an array because contents is a two-dimensional array).
- `getValueAt()` is the value at `contents[row][col]`.

`AbstractTableModel` has utterly trivial implementations of `getColumnClass()` and `getColumnName()`, so the first always returns `Object.class`, the second returns "A", "B", "C", etc.; holding onto column metadata from the first query allows you to provide more useful implementations of these methods, too.

[Example 3-12](#) shows how the `JDBCTableModel` is implemented.

### Example 3-12. Populating a Swing TableModel from a database connection

```
import javax.swing.*;
import javax.swing.table.*;
import java.sql.*;
import java.util.*;
/** an immutable table model built from getting
 * metadata about a table in a jdbc database
 */
public class JDBCTableModel extends AbstractTableModel {
    Object[][] contents;
    String[] columnNames;
    Class[] columnClasses;

    public JDBCTableModel (Connection conn,
        String tableName)
        throws SQLException {
        super();
        getTableContents (conn, tableName);
    }
    protected void getTableContents (Connection conn,
        String tableName)
        throws SQLException {

        // get metadata: what columns exist and what
        // types (classes) are they?
        DatabaseMetaData meta = conn.getMetaData();
```

```

System.out.println ("got meta = " + meta);
ResultSet results =
    meta.getColumns (null, null, tableName, null) ;
System.out.println ("got column results");
ArrayList colNamesList = new ArrayList();
ArrayList colClassesList = new ArrayList();
while (results.next()) {
    colNamesList.add (results.getString ("COLUMN_NAME"));
    System.out.println ("name: " +
        results.getString ("COLUMN_NAME"));
    int dbType = results.getInt ("DATA_TYPE");
    switch (dbType) {
    case Types.INTEGER:
colClassesList.add (Integer.class); break;
    case Types.FLOAT:
colClassesList.add (Float.class); break;
    case Types.DOUBLE:
    case Types.REAL:
colClassesList.add (Double.class); break;
    case Types.DATE:
    case Types.TIME:
    case Types.TIMESTAMP:
colClassesList.add (java.sql.Date.class); break;
    default:
colClassesList.add (String.class); break;
    };
    System.out.println ("type: " +
        results.getInt ("DATA_TYPE"));
    }
    columnNames = new String [colNamesList.size()];
    colNamesList.toArray (columnNames);
    columnClasses = new Class [colClassesList.size()];
    colClassesList.toArray (columnClasses);

    // get all data from table and put into
    // contents array

    Statement statement =
conn.createStatement ();
    results = statement.executeQuery ("SELECT * FROM " +
        tableName);
    ArrayList rowList = new ArrayList();
    while (results.next()) {
ArrayList cellList = new ArrayList();
for (int i = 0; i<columnClasses.length; i++) {
    Object cellValue = null;

    if (columnClasses[i] == String.class)
cellValue = results.getString (columnNames[i]);
    else if (columnClasses[i] == Integer.class)
cellValue = new Integer (

```

```

        results.getInt (columnNames[i]));
    else if (columnClasses[i] == Float.class)
cellValue = new Float (
    results.getInt (columnNames[i]));
    else if (columnClasses[i] == Double.class)
cellValue = new Double (
    results.getDouble (columnNames[i]));
    else if (columnClasses[i] == java.sql.Date.class)
cellValue = results.getDate (columnNames[i]);
    else
System.out.println ("Can't assign " +
    columnNames[i]);
    cellList.add (cellValue);
} // for
Object[] cells = cellList.toArray();
rowList.add (cells);

} // while
// finally create contents two-dim array
contents = new Object[rowList.size()] [];
for (int i=0; i<contents.length; i++)

    contents[i] = (Object []) rowList.get (i);
System.out.println ("Created model with " +
    contents.length + " rows");

// close stuff
results.close();
statement.close();

}
// AbstractTableModel methods
public int getRowCount() {
    return contents.length;
}

public int getColumnCount() {
    if (contents.length == 0)
        return 0;
    else
        return contents[0].length;
}

public Object getValueAt (int row, int column) {
    return contents [row][column];
}

// overrides methods for which AbstractTableModel
// has trivial implementations

public Class getColumnClass (int col) {
    return columnClasses [col];
}

```



```

    }

    public String getColumnName (int col) {
        return columnNames [col];
    }
}

```

The constructor dumps off its real work to `getTableContents()`, which is responsible for the two queries just described. It gets a `DatabaseMetaData` object from the `Connection`, from which you can then get the column data with a `getColumns()` call. The arguments to this method are the catalog, schema pattern, table name pattern, and column name pattern; this implementation ignores catalog and schema, although you might need to have callers specify them if you have a complex database. `getColumns()` returns a `ResultSet`, which you iterate over just like you would with the results of a regular JDBC query.

Getting the column name is easy: just call `getString("COLUMN_NAME")`. The type is a little more interesting, as the `getInt("DATA_TYPE")` call will return an `int`, which represents one of the constants of the `java.sql.Types` class. In this example, I've simply mapped `Strings` and the basic number types to appropriate Java classes. `TIMESTAMP` is SQL's concept of a point in time (a `DATE` and a `TIME`), so it gets to be a Java Date. Knowing these types will make it easier to call the right `getXXX()` method when retrieving the actual table data.

The second query is a simple `SELECT * FROM tableName`. With no `WHERE` restriction on the query, this will create a `ResultSet` with every row in the table. I shouldn't have to mention that if `tableName` is a table with millions of records, your resulting `TableModel` is not going to fit into memory. You knew that, right?

Again, you need to iterate over a `ResultSet`. Each time that `results.next()` returns true, meaning there's another result, you pull out every column you know about from the earlier metadata query. This means calling a `getXXX()` method and passing in the column name, where you know which `getXXX()` to use from your earlier investigation of the type of each column. You can go ahead and put numeric data into its proper wrapper class (`Integer`, `Double`, etc.) because that works well with the class-based rendering system of `JTables`. A caller might decide to use a `TableCellRenderer` that applies a `Format` class to all `Doubles` in the table to display them only to a certain number of decimal points, or to render Dates with relative terms like "Today" and "25 hours ago." Strongly typing the data in your model will help with that.

With the queries done, you just convert the `ArrayLists` to real arrays (which offer quick lookups for the get methods). The implementations of the `AbstractTableModel` methods mentioned previously, as well as the improved implementations of `getColumnClass()` and `getColumnName()`, are trivial uses of the `columnNames`, `columnClasses`, and `contents` arrays built up by this method.

### 3.5.2. Testing Things Out

Before you say "I can't run this hack, I don't have a database," relax! The open source world has you covered. And no, it's not some big thing like JBoss.HSQLDB, more commonly known by its old name, Hypersonic, is a JDBC relational database engine written in Java. It is really small and can be run as a standalone server or within your JVM. If you are database-less, grab HSQLDB from

<http://hsqldb.sourceforge.net/>.

Whatever your database, you'll need a driver classname, URL, username, and password to make a connection to the database. If you have your own database, I trust you already know this. If you just downloaded HSQLDB one paragraph ago, then you'll be using the following information:

- Driver: org.hsqldb.jdbcDriver
- URL: jdbc:hsqldb:file:testdb
- User: sa
- Password: (none)

This assumes you'll be running Hypersonic as part of your application, meaning you'll need to extend your classpath to pick up the *hsqldb.jar* file. Also note that this will create some *testdb* files in your current directory that you can clean up when done. You can also provide a full path to some other directory; see HSQLDB's docs for more info.

The test runner expects to pick up the connection strings as properties named `jdbctable.driver`, `jdbctable.url`, `jdbctable.user`, and `jdbctable.pass`. To make things easier, there are two ways to pass these in: either as system properties (usually specified with `-D` arguments to the `java` command), or in a file called `jdbctable.properties`. The book code has a sample of the latter with HSQLDB values as defaults.

To test the `JDBCTableModel`, the `TestJDBCTable` creates an entirely new table in the database. The model gets the `Connection` and the name of this table and loads the data from the database. Then the test class simply creates a new `JTable` from the model and puts it in a `JFrame`. [Example 3-13](#) shows the source for this demo.

### Example 3-13. Testing the JDBC-based table

```
import javax.swing.*;
import javax.swing.table.*;
import java.sql.*;
import java.util.*;
import java.io.*;
public class TestJDBCTable {
    public static void main (String[] args) {
        try {

/*
    driver, url, user, and pass can be passed in as
    system properties "jdbctable.driver",
    "jdbctable.url", "jdbctable.user", and
    "jdbctable.pass", or specified in a file
    called "jdbctable.properties" in current
    directory
*/
        */
    }
}
```

```

Properties testProps = new Properties();
String ddriver = System.getProperty ("jdbc.table.driver");
String durl = System.getProperty ("jdbc.table.url");
String duser = System.getProperty ("jdbc.table.user");
String dpass = System.getProperty ("jdbc.table.pass");

if (ddriver != null)
    testProps.setProperty ("jdbc.table.driver", ddriver);
if (durl != null)
    testProps.setProperty ("jdbc.table.url", durl);
if (duser != null)
    testProps.setProperty ("jdbc.table.user", duser);
if (dpass != null)
    testProps.setProperty ("jdbc.table.pass", dpass);
try {
    testProps.load (new FileInputStream (
        new File ("jdbc.table.properties")));
} catch (Exception e) {} // ignore FNF, etc.
System.out.println ("Test Properties:");
testProps.list (System.out);
// now get a connection
// note care to replace nulls with empty strings
Class.forName(testProps.getProperty
    ("jdbc.table.driver")).newInstance();
String url = testProps.getProperty ("jdbc.table.url");
url = ((url == null) ? "" : url);
String user = testProps.getProperty ("jdbc.table.user");
user = ((user == null) ? "" : user);
String pass = testProps.getProperty ("jdbc.table.pass");
pass = ((pass == null) ? "" : pass);

Connection conn =
    DriverManager.getConnection (url, user, pass);
// create db table to use
String tableName = createSampleTable(conn);

// get a model for this db table and add to a JTable
TableModel mod =
    new JDBCTableModel (conn, tableName);
JTable jtable = new JTable (mod);
JScrollPane scroller =
    new JScrollPane (jtable,
        ScrollPaneConstants.VERTICAL_SCROLLBAR_AS_NEEDED,
        ScrollPaneConstants.HORIZONTAL_SCROLLBAR_AS_NEEDED);
JFrame frame = new JFrame ("JDBCTableModel demo");
frame.getContentPane().add (scroller);
frame.pack();
frame.setVisible (true);

conn.close();

} catch (Exception e) {

```

```

e.printStackTrace();
}
}

public static String createSampleTable (Connection conn)
    throws SQLException {

    Statement statement = conn.createStatement();
    // drop table if it exists
    try {

statement.execute ("DROP TABLE EMPLOYEES");
    } catch (SQLException sqle) {
sqle.printStackTrace(); // if table !exists
    }

    statement.execute ("CREATE TABLE EMPLOYEES " +
        "(Name CHAR(20), Title CHAR(30), Salary INT)");
    statement.execute ("INSERT INTO EMPLOYEES VALUES " +
        "('Jill', 'CEO', 200000 )");
    statement.execute ("INSERT INTO EMPLOYEES VALUES " +
        "('Bob', 'VP', 195000 )");
    statement.execute ("INSERT INTO EMPLOYEES VALUES " +
        "('Omar', 'VP', 190000 )");
    statement.execute ("INSERT INTO EMPLOYEES VALUES " +
        "('Amy', 'Software Engineer', 50000 )");
    statement.execute ("INSERT INTO EMPLOYEES VALUES " +
        "('Greg', 'Software Engineer', 45000 )");


        statement.close();
    return "EMPLOYEES";
    }
}

```

The `createSampleTable()` method is something you could rewrite to insert your own types and values easily. In fact, because it returns the name of the table you've created, you could create many different tables in your database and test out how the model handles them. Or, use a loop to create lots of rows and see how long it takes to load them.

At any rate, when run, the `TestJDBCTable` produces a `JFrame` with the database table's contents, as seen in [Figure 3-9](#).

Figure 3-9. JTable populated from a database



NAME	TITLE	SALARY
Jill	CEO	200000
Bob	VP	195000
Omar	VP	190000
Amy	Software Engineer	50000
Greg	Software Engineer	45000

← PREV

## Hack 25. Export Table Data to an Excel Spreadsheet



I don't want an entire spreadsheet API, I just want to get a table of values into Excel.

Most corporate intranet applications require interfacing with standard office software, which usually means Microsoft Word and Excel. Interfacing with Microsoft products can be tricky business. Whole suites of products have been created just to address this issue. One of the most commonly requested features is generating a report from the data in a `JTable`. You could use a library like Poi (<http://jakarta.apache.org/poi/>) to read and write Excel files natively, but most of the time that's overkill—you probably don't need to support Excel formulas or complicated formatting. All most users really want to do is dump tabular data into a file that will open in Excel with a double-click. And with little bit of cleverness, you can do just that.

### 3.6.1. Dealing with Formatting

Excel uses a complicated database-oriented format for its native `.xls` files. This format defines the formulas, colors, charts and every other advanced feature Excel has supported over the years. Writing to the native `.xls` format is complicated but, fortunately, Excel supports other formats. The one I'm going to target is known as a *tab-delimited* text file, so called because tabs separate each field. This format is just plain text, so it will be super easy to write from Java, and open up in Excel with just a double-click.

Tab-delimited files separate each field with a tab character and each row with a standard Unix line break, `\n`. Since Swing defines a convenient `getValueAt()` method in the `TableModel` interface, it's very easy to just loop through the table cells and write it out to a file, as seen in [Example 3-14](#).

#### Example 3-14. Exporting tab-delimited data from a `TableModel`

```
public class ExcelExporter {
    public ExcelExporter() { }
    public void exportTable(JTable table, File file) throws IOException {
        TableModel model = table.getModel();
        FileWriter out = new FileWriter(file);
        for(int i=0; i < model.getColumnCount(); i++) {
            out.write(model洗getColumnName(i) + "\t");
        }
        out.write("\n");

        for(int i=0; i < model.getRowCount(); i++) {
```

```

for(int j=0; j < model.getColumnCount(); j++) {
    out.write(model.getValueAt(i,j).toString()+"\t");
}
out.write("\n");
}

out.close();
System.out.println("write out to: " + file);
}

```

This code defines an `ExcelExporter` class with a single method `exportTable()`, taking a `JTable` and a file. All `JTables` contain an implementation of the `TableModel` interface that holds the actual data. The code first retrieves the table model and opens a new `FileWriter` to the file. I used a `FileWriter` instead of a `FileInputStream` because `Writers` automatically handle text encoding issues. This means you don't have to worry about the language the program is running on. Using a `Writer` ensures that the code will work with any encoding from simple ASCII to triple-byte Korean Unicode.

The `TableModel` also defines the names of the columns, which are typically printed at the top of each column in the final spreadsheet. The code loops through the column names and prints them to the writer, following each column name with a `\t`, which represents the tab character, and finally an `\n` (the Unix newline character, which will work fine on both Mac OS X and Windows) at the end of the line. After that, it loops through each data row in turn, again separating fields with tabs and rows with the newline. After writing the fields, it closes the file and prints a status message. And with that the core of the table export is done.

The main method in [Example 3-15](#) creates a `JTable` with sample data and a button to generate an Excel file. First, it creates sample data as string arrays, and then it builds a new `DefaultTableModel` (the standard `TableModel` implementation that comes with Swing), nesting it inside of a `JTable` and then a `JScrollPane`.

### Example 3-15. Testing JTable data export

```

public static void main(String[] args) {
    String[][] data = {
        { "Housewares", "$1275.00" },
        { "Pets", "$125.00" },
        { "Electronics", "$2533.00" },
        { "Menswear", "$497.00" }
    };

    String[] headers = { "Department", "Daily Revenue" };

    JFrame frame = new JFrame("JTable to Excel Hack");
    DefaultTableModel model = new DefaultTableModel(data,headers);
    final JTable table = new JTable(model);
    JScrollPane scroll = new JScrollPane(table);

    JButton export = new JButton("Export");
}

```

```
export.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent evt) {

        try {
            ExcelExporter exp = new ExcelExporter();
            exp.exportTable(table, new File("results.xls"));
        } catch (IOException ex) {
            System.out.println(ex.getMessage());
            ex.printStackTrace();
        }
    }
});

frame.getContentPane().add("Center", scroll);
frame.getContentPane().add("South", export);
frame.pack();
frame.setVisible(true);
}
```

The export button has a simple action listener that calls `exportTable()` on a new `ExcelExporter`. The trick to getting Excel to open the file with a doubleclick on the desktop is to name the file with an `.xls` extension. It won't be a real Excel file, but the operating system will think that it is and pass it to Excel anyway. Then Excel will look at the file, realize it's actually a tab-delimited text file, and load it with the right import filter.

[Figure 3-10](#) shows what the program looks like.

Figure 3-10. An Excel-exporting JTable



## Hack 26. Search Through JTables Easily



Use this nifty `TableModel` decorator to search your `JTables` with minimal fuss.

Tables have a tendency to get very big; thousands of rows are not uncommon. But this causes some severe navigational issues for your users, like extremely small scrollbar handles, which make it difficult for them to find the information they need. One way to get around these navigational issues is to allow your users to search the table data rather than displaying it all. This hack shows you how to simply search your tables using the Apache open source Lucene search engine.

### 3.7.1. JTable Search Strategy

Rather than a custom `TableModel` with integrated Lucene functionality, you can build a `TableModel` decorator instead. This will allow you to search preexisting `TableModels` without modifying them directly.

This works by keeping a set of links to an internal table model based on search criteria. For example, say you have 10 rows in your original table model, and you have a search that limits the results to 5 of those rows. Your inner `TableModel` will remain unchanged, but your `TableModel` decorator will have links to only five of the inner `TableModel` rows making it look like it only has five rows of data.

### 3.7.2. Decorating the TableModel

Start by creating a class called `TableSearcher` that implements `TableModel`.

Next, create a simple decorator (or wrapper) that implements all of the `TableModel` methods and forwards the calls to the inner model. Depending on your IDE, you may be able to automate the process (IntelliJ IDEA does it for me). You'll have to modify a few of the methods, but most are going to remain unchanged. You don't have to touch the `getColumnName()` and `getColumnClass()` methods, for example. Just forward them to the inner `TableModel`:

```
public String getColumnName(int column) {
    return tableModel.getColumnName(column);
}

public Class getColumnClass(int column) {
    return tableModel.getColumnClass(column);
}
```

The `getColumnCount()` method is slightly different in that you have to check if the `TableModel` is null. This is because the table calls `getColumnCount()` first and calls other column methods only if there are valid columns. Here is the code with the null check:

```
public int getColumnCount() {
    return (tableModel == null) ? 0 : tableModel.getColumnCount();
}
```

### 3.7.3. Creating Logical Links to the Inner Table Model

Now, you need to introduce the idea of links between the inner table model and this table model. Create a `Collection` called `rowToModelIndex`. In it, you'll store `Integers` corresponding to the inner table model row number, at the index that corresponds to this table model's row. So, if the fifth row in the inner model is the first row in this model, you would store an `Integer` value of 5 as the first in the `rowToModelIndex`.

This method clears the searching state by making a one-to-one mapping of the inner table model to this table model:

```
private void clearSearchingState(){
    searchString = null;
    rowToModelIndex.clear();
    for (int t=0; t<tableModel.getRowCount(); t++){
        rowToModelIndex.add(new Integer(t));
    }
}
```

Now, you need to change the row reference methods to indirect through the row to model index before hitting the inner table model:

```
public int getRowCount() {
    return (tableModel == null) ? 0 : rowToModelIndex.size();
}
public boolean isCellEditable(int row, int column) {
    return tableModel.isCellEditable(getModelRow(row), column);
}
public Object getValueAt(int row, int column) {
    return tableModel.getValueAt(getModelRow(row), column);
}
```

```
public void setValueAt(Object aValue, int row, int column) {
    tableModel.setValueAt(aValue, getModelRow(row), column);
}
```

### 3.7.4. Indexing

Lucene is a document indexing and searching tool, available from <http://lucene.apache.org/>. To incorporate it into a Java application, you simply need to put its JAR file, typically named something like *lucene-version.jar*, into your classpath. For this hack, you'll need the following `import` statements:

```
import org.apache.lucene.store.*;
import org.apache.lucene.document.*;
import org.apache.lucene.analysis.*;
import org.apache.lucene.index.*;
import org.apache.lucene.search.*;
import org.apache.lucene.queryParser.*;
```

Most developers use Lucene with documents, but you can fake it to index a table model instead. First, you need to create a Lucene index, where all of the internal Lucene links are stored. You should use a `RAMDirectory` rather than a file-based directory in order to keep everything portable. You'll also need an `Analyzer` that helps communicate between data and the index, as well as an `IndexWriter` that actually writes to the index:

```
directory = new RAMDirectory();
analyzer = new WhitespaceAnalyzer();
IndexWriter writer = new IndexWriter(directory, analyzer, true);
```

For the purposes of indexing, think of every row as a document and every column as a word or a set of words (called a `Field` in Lucene-speak) for that document. Now, loop through the table model's rows, creating a new `Document` for each row and add `Fields` per column:

```
for (int row=0; row < tableModel.getRowCount(); row++){
    Document document = new Document();
    //add fields
    writer.addDocument(document);
}
```

First, add a field with the row index in the inner table model. You'll use this to link back to that row

later in the row-to-model index. Each field needs a name and a value, so create a constant called `ROW_NUMBER` that you'll refer to later when retrieving the links:

```
Document document = new Document();
document.add(new Field(ROW_NUMBER, "" + row, true, true, true));
//more indexing to come
writer.addDocument(document);
```

Then, iterate through all of the columns and add a `Field` for each column name/value pair:

```
for (int column=0; column < tableModel.getColumnCount(); column++){
String columnName = tableModel.getColumnName(column);
String columnValue = String.valueOf(

    tableModel.getValueAt(row, column)
).toLowerCase();
document.add(new Field(columnName, columnValue, true, true, true));
}
```

## 3.7.5. Searching

There are two parts to the searching. First, you have to hit the Lucene index with a search string. This will give you a list of rows in the inner table model that match the search. Then you need to reset the row-to-model index, pointing to those rows.

### 3.7.5.1 Getting results from the index.

To actually get the search results, you need an `IndexSearcher` that speaks to the index and returns your search results:

```
IndexSearcher is = new IndexSearcher(directory);
```

You want to make sure all of the fields get searched, so iterate through the table model and put all of the column names in an array that you'll pass into the Lucene search call:

```
String[] fields = new String[tableModel.getColumnCount()];
for (int t=0; t<tableModel.getColumnCount(); t++){
    fields[t]=tableModel.getColumnName(t);
}
```

Next, create a `Query` object to pass to the `IndexSearcher`; there is a helper method on `MultiFieldQueryParser` to do just that. Pass it the fields you want to search, your search `String`, and the analyzer:

```
Query query = MultiFieldQueryParser.parse(searchString, fields, analyzer);
```

Then run the search. `Hits` is the object type returned by the search call. You'll process the hits in the next section when you map the results back to the inner table model:

```
Hits hits = is.search(query);
```

### 3.7.5.2 Recreating the inner table model links.

Start by clearing the row-to-model index to get rid of the previous results:

```
rowToModelIndex.clear();
```

The `Hits` object contains a number of `Documents`, just like the ones you put into the index. Remember, you put a field in each `Document` with the name `ROW_NUMBER`. So, now you can iterate through the `Documents` and get the row number from the field value:

```
for (int t=0; t<hits.length(); t++){
    Document document = hits.doc(t);
    Field field = document.getField(ROW_NUMBER);
    Integer rowNumber = new Integer(field.stringValue());
}
```

The last step is to add an `Integer` to the row-to-model index with the row number retrieved from the document. Then, tie up all the loose ends by firing a table model update.

### 3.7.6. Try It Out

Because you're creating this table model as a decorator, it's extremely easy to use. The normal code to set up a `JTable` and a custom table model `MyTableModel` looks like this:

```

JTable table = new JTable();
MyTableModel myTableModel = new MyTableModel();
table.setTableModel(myTableModel);

```

All you need to do is wrap the `MyTableModel` with a `TableSearcher` and set the table model for the `JTable` as the `TableSearcher`:

```

JTable table = new JTable();
MyTableModel myTableModel = new MyTableModel();
TableSearcher tableSearcher = new TableSearcher(myTableModel);
table.setTableModel(tableSearcher);

```

Then, you just need to call the search method at the appropriate time. Usually, you'll have a search field to enter the search and a search button to start the search, so just attach an action listener to them both to fire off a search:

```

final JTextField searchField = new JTextField();
JButton searchButton = new JButton("Go");

ActionListener searchListener = new ActionListener() {
public void actionPerformed(ActionEvent e) {
    searchTableModel.search(searchField.getText().trim().toLowerCase());
    searchField.requestFocus();
}
};

searchButton.addActionListener(searchListener);
searchField.addActionListener(searchListener);

```

### 3.7.7. Finishing Touches

You've got the bare bones down, but there are a few things you'll want to add to make everything a little more functional. Here are a couple of ideas.

#### 3.7.7.1 Listen to inner table updates.

If the inner table model changes, you need to know about it. Otherwise, your search results will not jive with the inner table model. The simple solution is to add a `TableModelListener` to the inner table to rebuild the index, and then rerun the search against the new index.

Here's the code:

```
private class TableModelHandler implements TableModelListener {
public void tableChanged(TableModelEvent e) {
// If we're not searching, just pass the event along.
if (!isSearching()) {
clearSearchingState();
reindex();
fireTableChanged(e);
return;
}
// Something has happened to the data that may
// have invalidated the search.
reindex();
search(searchString);
fireTableDataChanged();
}
}
```

You should consider extending this hack if you have serious performance considerations. You could narrow down the area of the table that changed to fire more accurate events to the table.

### 3.7.7.2 Clear search results for blank search.

When users search with an empty string, they typically expect that to clear the search. The easiest way to do this is to check for an empty string in the search method. If they search with an empty string, clear the search and rerun the method that indexes all of the inner table model without a search:

```
public void search(String searchString){
if (searchString == null || searchString.equals("")){
clearSearchingState();
fireTableDataChanged();
return;
}
//rest of search method
}
```

If you wanted to hack further, you could make this and other small functions like it each separate decorators. Then you could combine them at will, depending on the needs of your application.

### 3.7.8. Wrapping Up

This table model decorator is now part of the main Lucene distribution. It's part of a new *lucene-contrib* project for Swing. In addition to this table model decorator, there is also a list decorator. I imagine the search logic is going to beef up, so definitely check out the Lucene site for more information. You can get read-only web access to the Lucene repository at <http://svn.apache.org/repos/asf/lucene/java/trunk/contrib/swing/>. Also note that because these models are officially part of *lucene-contrib*, they are going to be distributed with all new Lucene builds. So, they are going to come free with Lucene in the future.

*Jonathan Simon*





## Hack 27. Animate JTree Drops



Who said working with tree paths was hard? Now you can reorganize tree hierarchies with drag-and-drop.

`JTrees` are great for representing hierarchy, but they're not so hot as control widgets. You might want to drag items inside a tree, or accept a drop from some other part of your application, and it turns out not to be well suited to that. The problem is that the `JTree` isn't really a container, so from the Swing programmer's point of view, you see the tree's visual representation, but not the nodes within it.

The goal of this hack is to take a `Jtree`, like the one shown in [Figure 3-11](#), and allow you to reorganize it through drag-and-drop. The bulk of the work will be in animating and handling the drop. The payoff is that making a single tree reorderable will also get you most of the way to making it a good drag-and-drop participant with the rest of your application, since supporting drag-and-drop within the `JTree` requires you to make the tree a drag source and a drop target.

### 3.8.1. The Code

If any of the forgoing sounds familiar, it should. Bringing drag-and-drop to the `Jtree` is very similar to supporting it for the `JList`. In fact, the `JTree` and the `JList` have a lot in common both use cell renderers, both are typically put in `JScrollPane`s, etc.

Figure 3-11. JTree with drag-and-drop reordering

In fact, the code for this hack started as a straight port of the reorderable JList hack [[Hack #17](#)], with obvious changes for the different helper classes (`treeCellRenderer` instead of `ListCellRenderer`) and different handling of the model, since tree models are hierarchical.

To recap what needs to be done:

- The tree needs to implement the `DragGestureListener` (to start a drag), the `DropTargetListener` (to handle the drop), and the `DragSourceListener` (only to get the end-of-drop callback).
- The drag-and-drop implementations need to use the coordinates provided by drag-and-drop events to map to nodes of the tree as either the node to drag or as potential drop targets.
- The renderer needs to use information about whether a to-be-rendered cell is the drop target and to offer suitable visual feedback.
- The drop handling needs to remove the dragged node from its old location and insert it at its new location.

[Example 3-16](#) shows the main class (minus two inner classes that will be introduced shortly).

### Example 3-16. JTree with drag-and-drop support

```
public class DnDJTree extends JTree
    implements DragSourceListener, DropTargetListener, DragGestureListener {
    static DataFlavor localObjectFlavor;
    static {
        try {

localObjectFlavor =
    new DataFlavor (DataFlavor.javaJVMLocalObjectMimeType);
        } catch (ClassNotFoundException cnfe) { cnfe.printStackTrace(); }
    }
    static DataFlavor[] supportedFlavors = { localObjectFlavor };
    DragSource dragSource;
    DropTarget dropTarget;
    TreeNode dropTargetNode = null;
    TreeNode draggedNode = null;
    public DnDJTree () {
        super();
        setCellRenderer (new DnDTreeCellRenderer());
        setModel (new DefaultTreeModel(new DefaultMutableTreeNode("default")));
        dragSource = new DragSource();
        DragGestureRecognizer dgr =
dragSource.createDefaultDragGestureRecognizer (this,
        DnDConstants.ACTION_MOVE,
```

```

        this);
    dropTarget = new DropTarget (this, this);
}

// DragGestureListener
public void dragGestureRecognized (DragGestureEvent dge) {
    System.out.println ("dragGestureRecognized");
    // find object at this x,y
    Point clickPoint = dge.getDragOrigin();
    TreePath path = getPathForLocation (clickPoint.x, clickPoint.y);
    if (path == null) {

System.out.println ("not on a node");
return;
    }
    draggedNode = (TreeNode) path.getLastPathComponent();
    Transferable trans = new RJTTransferable (draggedNode);
    dragSource.startDrag (dge, Cursor.getDefaultCursor(),

    trans, this);
}
// DragSourceListener events
public void dragDropEnd (DragSourceDropEvent dsde) {

System.out.println ("dragDropEnd()");
dropTargetNode = null;
draggedNode = null;
repaint();

}
public void dragEnter (DragSourceDragEvent dsde) {}
public void dragExit (DragSourceEvent dse) {}
public void dragOver (DragSourceDragEvent dsde) {}
public void dropActionChanged (DragSourceDragEvent dsde) {}
// DropTargetListener events
public void dragEnter (DropTargetDragEvent dtde) {

    System.out.println ("dragEnter");

    dtde.acceptDrag(DnDConstants.ACTION_COPY_OR_MOVE);

    System.out.println ("accepted dragEnter");
}
public void dragExit (DropTargetEvent dte) {}
public void dragOver (DropTargetDragEvent dtde) {

    // figure out which cell it's over, no drag to self
    Point dragPoint = dtde.getLocation();
    TreePath path = getPathForLocation (dragPoint.x, dragPoint.y);
    if (path == null)

dropTargetNode = null;

```

```

else
    dropTargetNode = (TreeNode) path.getLastPathComponent();

    repaint();
}
public void drop (DropTargetDropEvent dtde) {
    System.out.println ("drop()!");
    Point dropPoint = dtde.getLocation();
    // int index = locationToIndex (dropPoint);
    TreePath path = getPathForLocation (dropPoint.x, dropPoint.y);
    System.out.println ("drop path is " + path);
    boolean dropped = false;
    try {
dtde.acceptDrop (DnDConstants.ACTION_MOVE);
System.out.println ("accepted");
Object droppedObject =

        dtde.getTransferable().getTransferData(localObjectFlavor);
MutableTreeNode droppedNode = null;
if (droppedObject instanceof MutableTreeNode) {
// remove from old location
droppedNode = (MutableTreeNode) droppedObject;
((DefaultTreeModel)getModel()).
    removeNodeFromParent(droppedNode); }
else {
droppedNode = new DefaultMutableTreeNode (droppedObject);
}
// insert into spec'd path. if dropped into a parent
// make it last child of that parent
DefaultMutableTreeNode dropNode =
    (DefaultMutableTreeNode) path.getLastPathComponent();
        if (dropNode.isLeaf()) {
DefaultMutableTreeNode parent =
    (DefaultMutableTreeNode) dropNode.getParent();
    int index = parent.getIndex (dropNode);
((DefaultTreeModel)getModel()).insertNodeInto (droppedNode,
    parent, index); }
else {
((DefaultTreeModel)getModel()).insertNodeInto
    (droppedNode, dropNode,
        dropNode.getChildCount());
}
dropped = true;
} catch (Exception e) {

        e.printStackTrace();
}
dtde.dropComplete (dropped);
}
public void dropActionChanged (DropTargetDragEvent dtde) {}
// main() method (unit test) goes here
// inner classes go here }

```

In several places in this code `dragGestureRecognized()`, `dragOver()`, and `drop()` you can see the use of `JTree`'s `getPathForLocation()`, which uses an  $x,y$  pair from the event to get a `treePath`. The last node of this path is the item under the cursor, or `null` if the cursor is over some non-node part of the `JTree`. In `dragGestureRecognized()`, this is used to start the drag. In `dragOver()` and `drop()`, it's used to determine which node will potentially be the drop target. The difference between these two is that `dragOver()` remembers the drop target node for use in repainting, while `drop()` actually handles the drop. Specifically, `drop()` gets the `Transferable` from the `DropTargetDropEvent` and, if it is a `MutableTreeNode`, moves it within the `treeModel`. If it isn't a node, it's assumed that this is from some other part of your GUI, and wraps it with a new `MutableTreeNode`. That block of code isn't used in this demo, but it might be useful when you extend this code.

One other thing to note about `drop()` is that it has different handling based on whether the drop is occurring on a leaf or a branch. On a leaf, the dropped item is inserted before the target. On a branch, i.e., a parent to other nodes the dropped item is inserted as the last child of the branch.

The `RJLTransferable` class shown here is used as a fairly straightforward `transferable` wrapper around local Java objects:

```
class RJLTransferable implements Transferable {
    Object object;
    public RJLTransferable (Object o) {
        object = o;
    }
    public Object getTransferData(DataFlavor df)
        throws UnsupportedFlavorException, IOException {
        if (isDataFlavorSupported (df))
            return object;
        else
            throw new UnsupportedFlavorException(df);
    }
    public boolean isDataFlavorSupported (DataFlavor df) {
        return (df.equals (localObjectFlavor));
    }
    public DataFlavor[] getTransferDataFlavors () {
        return supportedFlavors;
    }
}
```

The other helper inner class is where a lot of the "good stuff" happens. `DnDJTreeCellRenderer`, listed in the following code, has to be aware of what node is the potential drop target (this is an instance variable set by `dragOver()` in the main class) and if the node to be rendered is the drop target, it draws it differently:

```
class DnDJTreeCellRenderer
    extends DefaultTreeCellRenderer {
    boolean isTargetNode;
```

```

boolean isTargetNodeLeaf;
boolean isLastItem;
int BOTTOM_PAD = 30;
public DnDTreeCellRenderer() {
    super();
}
public Component getTreeCellRendererComponent (JTree tree,
        Object value,
        boolean isSelected,
        boolean isExpanded,
        boolean isLeaf,
        int row,
        boolean hasFocus) {
    isTargetNode = (value == dropTargetNode);
    isTargetNodeLeaf = (isTargetNode &&

        ((TreeNode)value).isLeaf());
    // isLastItem = (index == list.getModel().getSize()-1);
    boolean showSelected = isSelected &
        (dropTargetNode == null);
    return super.getTreeCellRendererComponent (tree, value,
        isSelected, isExpanded, isLeaf, row, hasFocus);
}
public void paintComponent (Graphics g) {
    super.paintComponent(g);
    if (isTargetNode) {
        g.setColor(Color.black);
        if (isTargetNodeLeaf) {
            g.drawLine (0, 0, getSize().width, 0);
        } else {
            g.drawRect (0, 0, getSize().width-1, getSize().height-1);
        }
    }
}
}
}

```

The special rendering is a two-step process. First, `getTreeCellRendererComponent( )` figures out if the cell to be rendered is the drop target, and if so, it sets a local `boolean`. It sets another `boolean` to indicate that the drop target cell is a leaf. Having set these `booleans`, it returns the superclass's implementation. In short order, the renderer's `paint( )` method is called. In the `paint( )`, you can use the `booleans` to apply special rendering. In this version, a drop target that is a leaf gets a line drawn in its top inset, suggesting that the dropped item will be inserted before this node. If rendering a drop target that is a branch, i.e., it's not a leaf then the special rendering puts a box around the component.

### 3.8.2. Running the Code

The main method, shown in [Example 3-17](#), builds a reorderable tree and puts it in a `JFrame`.

## Example 3-17. Testing the drag-and-drop JTree

```
public static void main (String[] args) {

JTree tree = new DnDJTree(); DefaultMutableTreeNode root = new
DefaultMutableTreeNode("People
DefaultMutableTreeNode set1 = new DefaultMutableTreeNode("Set 1");
DefaultMutableTreeNode set2 = new DefaultMutableTreeNode("Set 2");
DefaultMutableTreeNode set3 = new DefaultMutableTreeNode("Set 3");
set1.add (new DefaultMutableTreeNode ("Chris"));
set1.add (new DefaultMutableTreeNode ("Kelly"));
set1.add (new DefaultMutableTreeNode ("Keagan"));
set2.add (new DefaultMutableTreeNode ("Joshua"));
set2.add (new DefaultMutableTreeNode ("Kimi"));
set3.add (new DefaultMutableTreeNode ("Michael"));
set3.add (new DefaultMutableTreeNode ("Don"));
set3.add (new DefaultMutableTreeNode ("Daniel"));
root.add (set1);
root.add (set2);
set2.add (set3);
DefaultTreeModel mod = new DefaultTreeModel (root);
tree.setModel (mod);
// expand all
for (int i=0; i<tree.getRowCount(); i++)
tree.expandRow (i);
// show tree
JScrollPane scroller =
new JScrollPane (tree,
ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
JFrame frame = new JFrame ("DnD JTree");
frame.getContentPane().add (scroller);
frame.pack();
frame.setVisible(true);
}
```

[Figure 3-12](#) shows the animation of a drag. In this case, the "Chris" node is about to be dropped on top of the "Michael" node.

Figure 3-12. Dragging a node within a JTree

Because the drop is occurring over a leaf, the custom rendering shows a line on top of the "Michael" node, meaning that "Chris" will be inserted before "Michael". The result of the drop is shown in [Figure 3-13](#).

Figure 3-13. Dropping a node within a JTree

In case that wasn't such a good idea, [Figure 3-14](#) shows the "Chris" node being dragged back to where it was. In this case, the drag is over the "Set 1" branch, which causes it to be drawn with a box around it, suggesting that the drop will be "into" the branch.

Figure 3-14. Dragging a node to a branch



The drop makes the dragged node the last child of the "Set 1" branch, as shown in [Figure 3-15](#).

Figure 3-15. Dropping a node onto a branch

This code is primarily focused on making a single `Jtree` reorderable. If you want to make drag-and-drop work between widgets in your GUI, the biggest change you'll need to make is to have the `drop()` method not remove the dragged node from the tree's model, since you can't assume that the dragged item is even a node in this tree. A little bit of checking the event source makes it easy enough to find what scenario you're dealing with.

[← PREV](#)

# Chapter 4. File Choosers

[← PREV](#)

[← PREV](#)

## 4.1. Hacks 2832: Introduction

Ah, the poor `JFileChooser`. It's probably not anybody's favorite class in Swing, and it's quite likely the anti-favorite of many developers. Prior to Java 1.4, the Metal version had an "icon view" button that actually didn't do anything not that it was worth writing home about once it was implemented. Little glitches like this make `JFileChooser` the whipping boy of many Swing developers. Apple's Java guidelines for Mac OS X actually advocate giving up on the `JFileChooser` altogether and going back to the AWT `FileDialog`!

This chapter is here to...well, if not to praise the `JFileChooser`, then certainly not to bury it either. This is Swing after all, and that means there are all sorts of places that you can hack in and embellish functionality to give the user more power, or to make a component smarter about the contents it displays.

[← PREV](#)

## Hack 28. Add a Right-Click Context Menu to the JFileChooser



Improve the native platform fidelity of the `JFileChooser` by adding a contextual menu that lets the user create new folders and delete files.

The standard `JFileChooser` that comes with Swing is quite limited. It doesn't follow shortcuts or any other linked files. It doesn't have image previews or even a right-click menu. These are all features that users expect to see. Worse, these are the kinds of details that continue to reinforce the belief that Swing apps are inferior to native ones.

This hack will tackle the first limitation, the lack of a context menu. Some platform file choosers (Windows Explorer in particular) provide users with a context menu, also known as a right-click menu. This provides fast access to commonly used functions like Delete and New Folder. Java 5.0 finally added a context menu to the file chooser, but if you want to target the millions of users out there with older versions of Java, then you need your own implementation. This hack creates a right-click menu on the `JFileChooser` to give the user those missing features.

The goal of this task is to create a contextual menu. This means it's a menu that pops up when you hit the right mouse button (or Control-click on one-button mice). It also is *contextual*, or context sensitive. This means the menu changes or does something different depending on what you currently have selected. In this case, there will be two actions: Delete will delete the currently selected file or directory, if one is selected; New Folder will create a new folder (called, not surprisingly, *New Folder*) in the current directory. Both of these actions depend on the current state of the file selection, so they are considered context sensitive.

### 4.2.1. The Problem

For the most part, Swing is quite extensible, but often only in ways that the Swing team thought of beforehand. The `JFileChooser` has ways to change the rendering of file icons, filtering the file list, adding components, and changing the text. It does not have any way to add pop-up menus, though. In short, we'll have to hack it, and there's no better way to start than by reusing another hack.

[Chapter 8](#) has a hack for adding pop-up menu support to any frame; see "Create a Global Right-Click" [[Hack #57](#)]. By reusing its `RightClickGlassPane`, you can start off with a pop-up menu in place. That just leaves making a connection between the pop up and the file chooser component. Sounds easy, right? Well, if it were easy, it wouldn't be in this book! First, create a `JFileChooser` subclass and attach the right-click glass pane:

```
public class ContextMenuFileChooser extends JFileChooser {
```

```

protected Component right_click_pane;

public ContextMenuFileChooser() {
    super();
    JPopupMenu popup = new JPopupMenu();
    popup.add(new DeleteAction(this));
    popup.add(new NewFolderAction(this));
    right_click_pane = new RightClickGlassPane(this, popup);
}
}

```

This code defines a new subclass of `JFileChooserContextMenuFileChooser`. The constructor builds a custom subclass of the `RightClickGlassPane` and a new `JPopupMenu` pre-filled with two custom actions: one for deleting files and one for creating new folders.

With the `RightClickGlassPane` initialized, you need to install it in the actual window that contains the `JFileChooser`. While you can create your own window, the most common usage of `JFileChooser` is to show it with the `showDialog()` method; this method creates a new window and installs the chooser in it automatically. However, this means that you have no access to the real window until it's already on screen. Fortunately, the Swing team thought of this (let's give them some credit) and provided the `createDialog()` function. This protected method can be overridden to modify the dialog *before* it shows up on screen. A new implementation of `createDialog()` to add to `ContextMenuFileChooser` is shown here:

```

protected JDialog createDialog(Component parent) {
    JDialog dialog = super.createDialog(parent);
    // create the right-click glass pane.
    dialog.setGlassPane(right_click_pane);
    right_click_pane.setVisible(true);
    return dialog;
}

```

With this code in place, you can right-click anywhere on the file chooser to see the context menu. It's pretty useless, however, since the menu items don't actually do anything. You still have to create the Delete and New Folder actions. The `JFileChooser` API makes this pretty easy, though:

```

class DeleteAction extends AbstractAction {
    protected JFileChooser chooser;
    public DeleteAction(JFileChooser chooser) {
        super("Delete");
        this.chooser = chooser;
    }
    public void actionPerformed(ActionEvent evt) {
        File file = chooser.getSelectedFile();
        if(file != null) {
            file.delete();
        }
    }
}

```

```

        chooser.rescanCurrentDirectory();
    }
}
}

```

The new `DeleteAction` above is a standard `AbstractAction` subclass, with a small change: it requires a `JFileChooser` in its constructor. The action needs the chooser to tell it which file has been selected. In the `actionPerformed()` implementation, you can see that the action gets the selected file, deletes it, and then tells the chooser to refresh itself. That's it! Pretty simple.

The `NewFolderAction` is similar and just as simple:

```

class NewFolderAction extends AbstractAction {
protected JFileChooser chooser;
public NewFolderAction(JFileChooser chooser) {
super("New Folder");
this.chooser = chooser;
}
public void actionPerformed(ActionEvent evt) {
File cwd = chooser.getCurrentDirectory();
if(cwd != null) {
File new_dir = new File(cwd,"New Folder");
new_dir.mkdir();
chooser.rescanCurrentDirectory();
}
}
}

```

With these two actions in place, the custom file chooser will do exactly what we want it to do: pop up a right-click menu and perform the two actions when selected.

There's one glaring problem with this solution, though. The menu pops up no matter where the user clicks in the dialog. This means the menu can appear even when it's not over the file selection area. The only way to fix this glitch is to trigger the pop-up menu only when it's over the correct component. To do this, create an anonymous inline subclass of `RightClickGlassPane` that overrides the `redispatchMouseEvent()` method. In this new method, check to see if a right mouse click is over the correct components before showing the menu:

```

right_click_pane = new RightClickGlassPane(this,popup) {
protected void redispatchMouseEvent(MouseEvent e, boolean repaint) {
Component component = getRealComponent(e.getPoint());
if(component == null) { return; }
String chooser_class =
"javax.swing.plaf.metal.MetalFileChooserUI$5";
if(component.getClass().getName().equals(chooser_class)) {
super.redispatchMouseEvent(e,repaint);
}
}
}


```

```

    } else {
        doDispatch(e);
    }
}
};

```

There's one caveat here. In order to detect the file selection component, you have to know which class actually draws the file selection on screen. The `JFileChooser` doesn't expose this component, and digging through the source code only reveals that it's an anonymous inner class. With a runtime debugger, I found out that the name of the class we want is `javax.swing.plaf.metal.MetalFileChooserUI$5` at least when you are using the Metal L&F. By testing for that classname, you can detect the file selection widget; however, this will only work under the Metal L&F. For other L&Fs (or versions of Metal other than JDK 1.4), you'll need to look for a different classname. A better implementation of this hack would test for class strings from all of the most common Look and Feels on the major Java platforms.



I'll leave that task to you as an exercise. Have a ball!

With all the code in place, you can create a `main()` method that tests out the new `ContextMenuFileChooser`:


```

public static void main(String[] args) {
    final JFileChooser jfc = new ContextMenuFileChooser();
    jfc.showOpenDialog(null);
    System.exit(0);
}

```

[Figure 4-1](#) shows what the finished `JFileChooser` looks like.

Figure 4-1. Context-sensitive menu



This hack won't work with JDK 1.5 because that `JFileChooser` already provides its own context menu.



## Hack 29. Display Shortcuts in the JFileChooser



This hack will customize the `JFileChooser` to recognize shortcut (linked) folders and overlay them with a link graphic, mimicking the native Windows File Explorer.

Another of `JFileChooser`'s glaring bugs is the lack of any support for linked directories. This is hardly surprising, as Java itself has no understanding of linked directories. Most operating systems support linked files, however, and often indicate to the user that a file is linked for example, by drawing an arrow overlaid on top of the folder or directory icon. Compare the typical `JFileChooser` in [Figure 4-2](#) to the standard Windows file chooser in [Figure 4-3](#). There's more than a small difference! No wonder it's hard to get folks to move to Swing.

Figure 4-2. Normal JFileChooser

Like every Swing component, the look of the `JFileChooser` is controlled by the installed Look and Feel (L&F). However, the `JFileChooser` also uses a custom class similar to a table cell renderer for drawing the actual files and folders. That class, `FileView`, is the best place to start hacking the `JFileChooser`'s display.

The `FileView` contains five methods that determine the names, icons, and other attributes that are actually displayed in a `JFileChooser`. By overriding these methods, you can change the look or text of any file. To draw shortcuts as linked folders, you just need to override the `getIcon()` and `isTraversable()` methods. `getIcon()` returns the icon to use when drawing the file.

Figure 4-3. Standard Windows file chooser



`isTraversable()` tells the file chooser if a given file is a directory type of object, meaning the user can click and open it to list new files. These two methods will transform a *shortcut.lnk* file into a shortcut directory with the right icon.

For the sake of brevity, this is a Windows-specific hack. You should be able to modify this hack easily to work with sym-links on Unix and Linux, as well as Mac OS X. Consider it homework!

To get started, create the `ShortcutFileView` class. This extends `FileView`, overriding the `isTraversable()` method to return true if the `isDirLink()` method indicates that the file is indeed a link (determined by looking for the *.lnk* extension). If the file is not a link, `isDirLink()` will return `null`.

Notice that `isTraversable()` returns a `Boolean` instead of a `boolean`. This allows a `null` to be returned in addition to the `true/false` values that `boolean` would allow.

Any method of `FileView` subclasses that return `null` will cause the file chooser to defer to its default file view, instead of using the custom view:

```
class ShortcutFileView extends FileView {

    public boolean isDirLink(File f) {
        if(f.getName().toLowerCase().endsWith(".lnk")) {
            return true;
        }
    }
}
```

```

    }
    return false;
}
public Boolean isTraversable(File f) {
    if(isDirLink(f)) {
        return new Boolean(true);
    }
    return null;
}
}
}

```

Below is a sample program to test the `ShortcutFileView`. It creates a new file chooser, sets the file view to a new `ShortcutFileView`, and then opens the dialog. It is important to set the view before the `showOpenDialog()` because file choosers cannot be changed after they have been shown on screen:

```

public class DisplayShortcutTest {
    public static void main(String[] args) throws Exception {
        JFileChooser chooser = new JFileChooser();
        chooser.setFileView(new ShortcutFileView());
        chooser.showOpenDialog(null);
    }
}

```

This program changes the look of shortcuts to look like folders and be clickable, but they still don't have the link icon. This will require a bit more work. The second method to override in the file view is the `getIcon()` method. The plan is to get a standard folder icon then draw it onto a new icon with the overlaid link graphic. This part will create a new `JFileChooser` and get a reference to its normal file view. The following `FileChooserUI` code forces the file chooser to initialize its Look and Feel subsystem, ensuring that the `FileView` will be valid:

```

public Icon getIcon(File f) {
    if(isDirLink(f)) {

        JFileChooser chooser = new JFileChooser();
        FileChooserUI fcui = (FileChooserUI) UIManager.getUI(chooser);
        fcui.installUI(chooser);
        FileView def = fcui.getFileView(chooser);
    }
}

```

Once you have the file view, you need to pull out a folder icon. You can do this by asking for the icon of a known folder, in this case *C:\windows*:

```

// get the standard icon for a folder
File tmp = new File("C:\\windows");

```

```
Icon folder = def.getIcon(tmp);
int w = folder.getIconWidth();
int h = folder.getIconHeight();
```

Once you have the icon, you can build a new image to draw it on, and then overlay the link graphic:

```
// create a buffered image the same size as the icon
Image img = new BufferedImage(w,h,
    BufferedImage.TYPE_4BYTE_ABGR);
    Graphics g = img.getGraphics();


// draw the normal icon
folder.paintIcon(chooser,g,0,0);

// draw the shortcut image on top of the icon
Image shortcut = new ImageIcon("shortcut.png").getImage();
g.drawImage(shortcut,0,0,null);

// clean up and return
g.dispose();
return new ImageIcon(img);
    }
    return super.getIcon(f);
}
```

That's it. With the new icon created, your file chooser should look like [Figure 4-4](#).

Figure 4-4. JFileChooser showing a shortcut



← PREV

## Hack 30. Real Windows Shortcut Support



Support Windows shortcuts by actually opening and parsing files with the undocumented LNK format.

It's one thing to properly display Windows shortcuts [Hack #29] by looking for the `.lnk` extension and changing the default icon to look like a link. But there's a glaring flaw: when you click on the shortcut it doesn't actually link anywhere! This hack will make the shortcuts really work by hacking into the undocumented shortcut files themselves.

Since links are not supported natively by the filesystem, Windows fakes it by storing the shortcut metadata (path, icon, and other information) in a `.lnk` file. When you click on the shortcut, the windows file manager reads the LNK file, extracts the target file/directory path, and then opens a new window at the real location. Your Java program can do the exact same thing using a custom `FileSystemView`. The only tricky part is actually parsing the LNK files.

Microsoft has never documented the LNK file format, preferring native Windows developers to use system APIs for all manipulation. Creative hackers on the Web have reverse engineered most of the format, which fortunately includes the parts you need to extract target filepaths.

Jesse Hager has compiled a great PDF describing the format in detail. I used that document to write the code in this hack. You can read the full document at [http://www.i2s-lab.com/Papers/The\\_Windows\\_Shortcut\\_File\\_Format.pdf](http://www.i2s-lab.com/Papers/The_Windows_Shortcut_File_Format.pdf).

The LNK files are binary data broken up into a header followed by a few optional blocks of data. The format provides offsets that make parsing it easy. The following code is the beginning of a LNK parser:


```
public class LnkParser {
    public LnkParser(File f) throws Exception {
        parse(f);
    }
    public void parse(File f) throws Exception {
        // read the entire file into a byte buffer
        FileInputStream fin = new FileInputStream(f);
        ByteArrayOutputStream bout = new ByteArrayOutputStream();
        byte[] buff = new byte[256];
        while(true) {
            int n = fin.read(buff);
            if(n == -1) { break; }
        }
    }
}
```

```

    bout.write(buff,0,n);
}
fin.close();
byte[] link = bout.toByteArray();

```

The class defines one important method, `parse()`, which accepts a `File` object representing the LNK file. The first step is to load the entire file into a byte buffer.



I have seen some versions of this code use a more stream-oriented approach with loops that read byte by byte. Since LNK files are always pretty small (usually under 5k), I felt the extra memory was worth it to allow cleaner code using index offsets.

Next comes the header parsing:

```

// get the flags byte
byte flags = link[0x14];

// get the file attributes byte
final int file_atts_offset = 0x18;
byte fileatts = link[file_atts_offset];
byte is_dir_mask = (byte)0x10;
if((fileatts & is_dir_mask) > 0) {
    is_dir = true;
} else {
    is_dir = false;
}

```

The header has a lot of values in it, but we are only interested in the values at byte 0x14 (the flags) and at 0x18 (the file attributes). Each of these values is 8 bits (a byte), where each bit represents something, such as whether the LNK points to a file or a directory. Because they are always at the same place, you can just jump directly to them in the array and store the values. To access a bit you need a *mask*, which is a number that lets you hide all of the bits in a value that you *don't* want, leaving only the bit you do want. To use it, you AND (a bitwise operation specified by the `&` character) the value and the mask together. Then you can just test if the final value is greater than zero to see if that bit was set. If the 4th bit of the file attributes byte is set (i.e., is equal to 1), then the target of this shortcut is a directory. The `fileatts` and `is_dir_mask` are ANDed together. If the final value is greater than zero, then the bit must have been set and the program sets the `is_dir` variable to `true`; otherwise, it sets `is_dir` to `false`.

```

// if the shell settings are present, skip them
final int shell_offset = 0x4c;
int shell_len = 0;
if((flags & 0x1) > 0) {

```

```
// the plus 2 accounts for the length marker itself
shell_len = bytes2short(link,shell_offset) + 2;
}
```

LNK files have an optional block for shell settings, which are irrelevant for the purposes of getting the target path. If the shell settings are present (indicated by the 0th bit of the flags), then jump to the shell block, get its length from the next 2 bytes, and then skip to the end. The `if((flags & 0x1) > 0)` section ANDs the flags value and a mask to get the 0th bit and see if there is a shell block. If the shell block is not present, then you can just set the offset to 0 and continue. `bytes2short()` is a simple routine that converts two bytes into a short.

```
// get to the file block
int file_start = 0x4c + shell_len;

// get the local volume and local system values
int local_sys_off = link[file_start+0x10] + file_start;
real_file = getNullDelimitedString(link,local_sys_off);
p("real filename = " + real_file);
```

The file block starts 0x4c (76 in hexadecimal) bytes after the previous block (or the headers if there was no previous block). Once you are at the file block, you can pull out the 0x10th byte to find the offset to the local system target filename.

If the directory was on a network drive, you would have to look for a different offset, but I've assumed the file was local to keep the code simple. A more robust implementation would support both local and remote files.

Once you have the offset to the filename, pull it out as a null-delimited string and save it in the `real_file` variable.

I referenced these two utility functions earlier. `getNullDelimitedString` looks through the byte array starting at the requested offset. When it finds a null value (0), it will return a substring from the starting offset to the last valid character; that substring contains the filepath. `bytes2short` uses bit-shifting to turn two bytes into a short integer:


```
static String getNullDelimitedString(byte[] bytes, int off) {
    int len = 0;
    // count bytes until the null character (0)
    while(true) {
        if(bytes[off+len] == 0) {
            break;
        }
        len++;
    }
}
```



```

    return new String(bytes,off,len);
}
// convert two bytes into a short
// note, this is little-endian because it's for an
// Intel-only OS.
static int bytes2short(byte[] bytes, int off) {
    return bytes[off] | (bytes[off+1]<<8);
}

```



If you learned low-level programming on RISC machines like I did, you might be surprised that the second byte is being shifted instead of the first. You must remember that short-cut files are designed for Windows, which only runs on little-endian processors. After writing this hack, I remembered how much I hate bit flipping and byte manipulation. I probably switched to Java so early so that I would never have to deal with data at the byte level again!

Now, the class just needs some getters to let the outside world use the parser. These two methods expose the `is_dir` and `real_file` variables that the `parse()` method sets:

```

private boolean is_dir;
public boolean isDirectory() {
    return is_dir;
}
private String real_file;
public String getRealFilename() {
    return real_file;
}

```

LNK Parser written, it's now time to hand the shortcut information over to the file chooser. `JFileChooser`s divide the file manipulation duties into two helper classes. The `FileView` class controls the look of files [[Hack #29](#)], such as names, icons, etc. The `FileSystemView` provides the `JFileChooser` with information about the filesystem itself, including which files are directories. For controlling directories, the two methods implemented here are particularly relevant:

```

public class ShortcutFileSystemView extends FileSystemView {

    public Boolean isTraversable(File f) {
        if(isDirLink(f)) {
            return new Boolean(true);
        }
        return super.isTraversable(f);
    }
    public File[] getFiles(File dir, boolean useFileHiding) {
        if(isDirLink(dir)) {

```

```

    dir = getRealFile(dir);
}
return super.GetFiles(dir,useFileHiding);
}

```

The `JFileChooser` will call `isTraversable()` on each file to see if it is really a folder. This does not control whether it uses a folder icon, but whether the user can open up and follow the file as a directory. This implementation simply calls the `isDirLink()` method (detailed shortly) to test the current file. If it's not a shortcut then it defers to the parent class.

`getFiles()` returns the directory listing of the given file. `JFileChooser` provides this to let developers mess with the file listing. You could use this to prevent hidden files from showing or to restrict the user from areas of the filesystem they shouldn't be allowed to access. For this hack, the `getFiles()` method will look for shortcuts and replace them with the real files they point to by calling the `getRealFile()` method:

```

private boolean isDirLink(File f) {
    try {
        if(f.getName().toLowerCase().endsWith(".lnk")) {
            if(new LnkParser(f).isDirectory()) {
                return true;
            }
        }
    } catch (Exception ex) {
        System.out.println("ex: " + ex);
        ex.printStackTrace();
    }
    return false;
}

private File getRealFile(File file) {
    try {
        return new File(new LnkParser(file).getRealFilename());
    } catch (Exception ex) {
        System.out.println("ex: " + ex);
        ex.printStackTrace();
        return null;
    }
}

```

`isDirLink()` and `getRealFile()` are very simple. They just call the appropriate function on the `LnkParser` and catch exceptions. By moving all of the actual LNK handling code into the `LnkParser`, you could add support easily to other kinds of links here just by adding a few more `if` statements.

To support drawing the icons, just modify the `ShortcutFileView` from the previous hack to call the `LnkParser` as well:

```
public boolean isDirLink(File f) {
    try {
        if(f.getName().toLowerCase().endsWith(".lnk")) {
            LnkParser parser = new LnkParser(f);
            if(parser.isDirectory()) {
                return true;
            }
        }
    } catch (Exception ex) {
        System.out.println("exception: " + ex.getMessage());
        ex.printStackTrace();
    }
    return false;
}
```

And finally, here's a test class that will build a new shortcut enabled file chooser. It creates a normal file chooser, and then sets the `FileSystemView` to the new shortcut subclass. It also sets the modified version of the `ShortcutFileView`:

```
public class ShortcutTest {
    public static void main(String[] args) throws Exception {
        FileSystemView fsv = new ShortcutFileSystemView();
        JFileChooser chooser = new JFileChooser();
        chooser.setFileSystemView(fsv);
        chooser.setFileView(new ShortcutFileView());
        chooser.showOpenDialog(null);
    }
}
```

[Figure 4-5](#) shows the `JFileChooser` displaying a shortcut that will behave like a real Windows shortcut when clicked.

Figure 4-5. A `JFileChooser` with a live shortcut



← PREY

## Hack 31. Add Image Preview to File Choosers



This hack will show you how to add an image previewer to a `JFileChooser`, and it will set you on the way toward building your own customizations.

We've already talked about `JFileChooser`'s numerous limitations. Not surprisingly, many applications have their own custom choosers and extensions to support things like image previews. The standard `JFileChooser` was designed to mimic only the most common features, but it does provide a way to add your own enhancements.

The standard `JFileChooser` looks like most native file choosers. It has a directory selector, a list of files, and select and close buttons. There may also be a toolbar of sorts. If you want to build your own customized file chooser, you could do it the same way platform-specific file choosers are implemented through L&F code. This would entail subclassing `javax.swing.plaf.basic.BasicFileChooserUI`, working around the private methods, and possibly reimplementing the whole thing, none of which is easy or fun. Fortunately, the `JFileChooser` API provides a simple extension hook in the form of the `setAccessory()` method. This method lets you add any `JComponent` to an existing `JFileChooser`, thereby adding your own features without mucking around in file chooser code.

In this hack, you'll learn how to create an image previewer. This is a component that shows a thumbnail view of the currently selected file if that file is an image. It will also show the dimensions of the image. Because Java 1.4 provides robust image support with the `javax.imageio` API, this should be pretty easy. The first step is a custom `ImagePreview` component:

```
public class ImagePreview extends JPanel implements PropertyChangeListener {
    private JFileChooser jfc;
    private Image img;

    public ImagePreview(JFileChooser jfc) {
        this.jfc = jfc;
        Dimension sz = new Dimension(200,200);
        setPreferredSize(sz);
    }
}
```

The code defines the `ImagePreview` class, a subclass of `JPanel`. I've hardcoded the size of the component to 200 x 200 large enough to tell what the image is, but small enough not to impact the file chooser very much.

`ImagePreview` also implements `PropertyChangeListener` so it can detect when the user selects a file:

```

public void propertyChange(PropertyChangeEvent evt) {
    try {
        System.out.println("updating");
        File file = jfc.getSelectedFile();
        updateImage(file);
    } catch (IOException ex) {
        System.out.println(ex.getMessage());
        ex.printStackTrace();
    }
}

```

`PropertyChange` is the single method of the `PropertyChangeListener` interface. This will be called by the `JFileChooser` each time the user selects (or deselects) a file. When that happens, `ImagePreview` will call its `updateImage()` method on that file:

```

public void updateImage(File file) throws IOException {
    if(file == null) {
        return;
    }
    img = ImageIO.read(file);
    repaint();
}

```

In this method, `file` will be `null` if `jfc.getSelectedFile()` in `propertyChange()` returned `null`. This indicates the user deselected a file or pressed the Cancel button. In either case, there is no image to display. If the file is not `null`, then `updateImage()` will try to read it with `ImageIO.read()`. The `javax.imageio` interface is quite robust and complex, but the most common operations reading and writing files can be performed with the static methods in `ImageIO`. If the file is not an image file, then `read()` will return `null`, which means `updateImage()` doesn't have to handle that case. After reading the image, the method calls `repaint()` to tell Swing that the `ImagePreview` may need to be redrawn.

The `paintComponent()` method contains the guts of `ImagePreview`. First, it fills in the background with gray. Without this call, the background would be just the contents of the current buffer, which could be anything, like other components on the screen or the previous state of the `ImagePreview`:

```

public void paintComponent(Graphics g) {
    // fill the background
    g.setColor(Color.gray);
    g.fillRect(0,0,getWidth(),getHeight());
}

```

Next comes the actual image-drawing code:

```

if(img != null) {

```

```

// calculate the scaling factor
int w = img.getWidth(null);
int h = img.getHeight(null);
int side = Math.max(w,h);
double scale = 200.0/(double)side;
w = (int)(scale * (double)w);
h = (int)(scale * (double)h);
// draw the image
g.drawImage(img,0,0,w,h,null);

```

Notice the `if(img != null)` line. If `ImageIO.read()` returned `null`, then the `img` variable will be `null` as well. With this `if` statement, you don't need to check for file extensions or do image format detection. The `ImageIO` class will take care of it all. Before it paints the image, the code will calculate which side of the image is longer (length or height). By scaling the image down relative to the longer side, your code doesn't have to worry about the image being clipped; it will always be small enough to fit inside the 200 x 200 square component.

With the image in place, you just need to draw the text for the width and height near the bottom. Since the image could be in any color scheme, there is no way to guarantee that the color picked for the text would show up against the image. To handle this, I draw the text in black first, and then draw it a second time shifted up and to the left by one pixel. This creates a subtle shadow effect and ensures that the white text is always visible, even if it's on a white background:

```

// draw the image dimensions
String dim = w + " x " + h;
g.setColor(Color.black);
g.drawString(dim,31,196);
g.setColor(Color.white);
g.drawString(dim,30,195);
} else {

```

Finally, if the image is `null`, an error message is printed:

```

} else {
// print a message
g.setColor(Color.black);
g.drawString("Not an image",30,100);
}

```

With the `ImagePreview` class set up, you're ready to test things out. This code creates a standard `JFileChooser` and adds a new `ImagePreview` to it with the `setAccessory()` method. It also adds the preview as a property change listener so it can detect user file selections:


```

public static void main(String[] args) {
    JFileChooser jfc = new JFileChooser();
    ImagePreview preview = new ImagePreview(jfc);
    jfc.addPropertyChangeListener(preview);
    jfc.setAccessory(preview);
    jfc.showOpenDialog(null);
}

```

With the code all in place, the running program will look like [Figure 4-6](#).

Figure 4-6. A file chooser that previews images



As a nice enhancement, you could modify `ImagePreview` to show previews of other kinds of files (e.g., PDF or SVG). You could even preview text files by showing the first few lines of the document. Because `setAccessory()` lets you set any `JComponent`, you could create a panel that does something completely different, like connecting to a network drive, à la iDisk, or setting import preferences like encoding and line endings.






## Hack 32. Preview ZIP and JAR Files



This hack will show you how to customize the file chooser to let users navigate and load files from inside a ZIP or JAR file archive.

Most modern operating systems now have built-in support for compressed files, usually in the form of ZIP files. You can open up a ZIP file and navigate the contents from within the standard file browser or dialog box, all without actually uncompressing anything. Surprisingly, `JFileChooser` doesn't support ZIP files, even though Java has built-in ZIP support in the `java.util.zip` package. And, since JAR files are in the same format, you get two-for-one today!



Before you read any further, I want to warn you that this is one of the longest and most complicated hacks in the book. I don't want to scare you away, but the code is pretty dense. Of course, you wouldn't expect any less from a hacks book, right? What you will learn from this hack, however, will let you build custom filesystem views for any type of datasource, including FTP, WebDAV, or even SQL databases. I think the complexity is worth it. Plus, you'll learn more about how the `File` object really works and how to hack it to pieces.

### 4.6.1. Build File Proxies

The `JFileChooser` uses a `FileSystemView` to access the real filesystem. This view, unfortunately, assumes the existence of actual `java.io.File` objects. There is no way to represent a filesystem without `Files`, which wouldn't be a problem except that `File` is a real class with many methods, not a simple interface. Fortunately, `File` is not declared `final`. You can override each method with your own version to redirect the calls to another object, and that's exactly how this hack works. By creating proxies around the real ZIP file objects, you can fool the `FileSystemView` into working with items that aren't real files.

ZIP files are represented in the `java.util.zip` package by a `ZipFile` object that contains one `ZipEntry` for each compressed file it contains. To show the compressed files in the chooser, each `ZipEntry` is wrapped inside of a `ZipEntryFileProxy`, which extends the real `File` class. It contains a reference to the `ZipEntry`, the enclosing `ZipFile`, a path string, and the `File` object of the actual ZIP file, as shown in [Example 4-1](#).

Example 4-1. A ZIP file proxy

```

import java.util.zip.*;

public class ZipEntryFileProxy extends File {
    ZipFileProxy zip;
    ZipFile zipfile;
    String name, path;
    File parent;
    ZipEntry entry;
    public ZipEntryFileProxy(ZipFileProxy zip, ZipFile zipfile,
        String path, File parent) {
        super("");
        this.zip = zip;
        this.zipfile = zipfile;
        this.path = path;
        this.parent = parent;
        this.entry = zipfile.getEntry(path);
        // determine if the entry is a directory
        String tmp = path;

        if(entry.isDirectory()) {
            tmp = path.substring(0,path.length()-1);
        }
        // then calculate the name
        int brk = tmp.lastIndexOf("/");
        name = path;
        if(brk != -1) {
            name = tmp.substring(brk+1);
        }
    }
}

```

The constructor is pretty straightforward. It saves references to the passed-in object and then does some calculations on the path. If the entry is a directory, then the path will end with a slash. The code chops off this trailing slash, if present, and then looks for the name of the entry. Files inside of a ZIP are stored as a list of complete pathnames with slashes, not as a tree of objects like a real filesystem. Thus, the name of a file what you would normally think of as its filename is actually just the last part of a complete path, including the parent directories. To parse this and get the real filename, the code looks for the last slash in the filename and pulls out the trailing string.

The rest of the `ZipEntryFileProxy` class overrides a portion of the standard `File` methods. Each call returns a value based on the saved data from the ZIP file, rather than the actual `File` parent class:

```

public boolean exists() { return true; }

public int hashCode() {
    return name.hashCode() ^ 1234321;
}

public String getName() { return name; }
public String getPath() { return path; }

```

```

public boolean isDirectory() { return entry.isDirectory(); }
public boolean isAbsolute() { return true; }
public String getAbsolutePath() { return path; }
public File getAbsoluteFile() { return this; }
public File getCanonicalFile() { return this; }
public File getParentFile() { return parent; }

public boolean equals(Object obj) {
    if(obj instanceof ZipEntryFileProxy) {
        ZipEntryFileProxy zo = (ZipEntryFileProxy)obj;
        if(zo.getAbsolutePath().equals(getAbsolutePath())) {
            return true;
        }
    }
    return false;
}

public InputStream getInputStream() throws IOException {
    return zipfile.getInputStream(entry);
}

public File[] listFiles() {
    Map children = (Map)zip.hash.get(path);
    File[] files = new File[children.size()];
    Iterator it = children.keySet().iterator();
    int count = 0;
    while(it.hasNext()) {
        String name = (String)it.next();
        files[count] = new ZipEntryFileProxy(zip, zipfile, name, this);
        count++;
    }
    return files;
}

```

There are two special things to note in this code. First, the code adds one method that wasn't in the original `File` class: `getInputStream()`. There is no way to get an `InputStream` out of a normal `File`. Instead, you must create a `FileInputStream`, which of course doesn't know anything about ZIP files, so that won't work. As a workaround, `ZipEntryFileProxy` adds the method `getInputStream()` to get a proper input stream. The disadvantage of this solution is that any code that uses the file chooser will need to be aware of ZIP files; it cannot simply assume that the file chooser only returns real files. This means you would have to modify any existing code that uses the `JFileChooser` to check if the file is really a `ZipEntryFileProxy`; if it is, you need to do a cast, and then grab the input stream appropriately. Otherwise, your program will throw lots of exceptions as the `FileInputStream` tries to open a file that doesn't exist in a form it can understand.

The other thing to note is that `listFiles()` creates new `ZipEntryFileProxy` objects for each child file (if the file is a directory) by pulling the names out of a `HashTable` stored in the `ZipFileProxy` (which represents the ZIP file). The `ZipFileProxy` ([Example 4-2](#)) wraps the entire ZIP file, whereas the `ZipEntryFileProxy` maps to files stored *within* the ZIP file, though they are both custom subclasses of `java.io.File`. The `ZipFileProxy` constructor accepts a `File` object pointing to the real ZIP file on disk.

After saving a few references, the constructor calls `parse()` to set up a `HashMap` of the file entries within the ZIP.

## Example 4-2. ZipFileProxy class

```
public class ZipFileProxy extends File {
    protected Map hash;
    private ZipFile zipfile;
    private File real_file;

    public ZipFileProxy(File file) {
        super(file.getAbsolutePath());
        try {
            this.hash = new HashMap();
            this.real_file = file;
            zipfile = new ZipFile(file, ZipFile.OPEN_READ);
            hash.put("", new HashMap());
            Enumeration en = zipfile.entries();
            parse(en);
        } catch (IOException ex) {
            System.out.println(ex.getMessage());
            ex.printStackTrace();
        }
    }

    public String getPath() { return real_file.getPath(); }
    public boolean exists() { return real_file.exists(); }
    public String getName() { return real_file.getName(); }

    public File[] getFiles(String dir) {
        Map children = (Map)hash.get(dir);
        File[] files = new File[children.size()];
        Iterator it = children.keySet().iterator();
        int count = 0;
        while(it.hasNext()) {
            String name = (String)it.next();
            files[count] = new ZipEntryFileProxy(this, zipfile, name, this);
            count++;
        }
        return files;
    }

    /* create a hashtable of the entries and their paths */
    private void parse(Enumeration en) {
        while(en.hasMoreElements()) {
            ZipEntry ze = (ZipEntry)en.nextElement();
            String full_name = ze.getName();
            String name = full_name;
            if(ze.isDirectory()) {
```

```

    name = full_name.substring(0,full_name.length()-1);
    }
    int brk = name.lastIndexOf("/");
    String parent = "";
    if(brk != -1) {
    parent = name.substring(0,brk+1);
    }
    String node_name = name;
    if(brk != -1) {
    node_name = full_name.substring(brk+1);
    }

    if(ze.isDirectory()) {
    HashMap children = new HashMap();
    hash.put(full_name,children);
    }

    Map parent_children = (Map)hash.get(parent);
    parent_children.put(full_name,"");
    }
}
}

```

Just like `ZipEntryFileProxy`, `ZipFileProxy` wraps a real file object and passes most method invocations to the superclass. The special code here is `inparse()`, which loops through each entry in the ZIP file, breaks each pathname into its constituent parts, and builds up a set of nested `HashTables`. Each directory entry is represented by a `HashMap` of child filenames. A master map holds the directory entries. This nested structure is what lets the `ZipEntryFileProxy` find its place in the virtual tree of files.

## 4.6.2. Build a Custom Filesystem View

Now that you have a tree of virtual `File` objects, you can implement the real `FileSystemView`. As shown in [Example 4-3](#), `ZipFileSystemView` overrides each of its parent class's methods, redirecting them to ZIP-specific code if the file is an instance of a `ZipEntryFileProxy`.

### Example 4-3. ZipFileSystemView class

```

public class ZipFileSystemView extends FileSystemView {

    public ZipFileSystemView() throws IOException { }

    public File createNewFolder(File file) { return null; }
}

```

```
public File createFileObject(File dir, String filename) {
    if(dir instanceof ZipEntryFileProxy) {
        ZipEntryFileProxy zdir = (ZipEntryFileProxy) dir;
        return new ZipEntryFileProxy(zdir.zip, zdir.zipfile, filename, dir);
    }
    return super.createFileObject(dir,filename);
}

public File getChild(File dir, String filename) {
    if(dir instanceof ZipEntryFileProxy) {
        ZipEntryFileProxy zdir = (ZipEntryFileProxy) dir;
        return new ZipEntryFileProxy(zdir.zip,zdir.zipfile,
            dir.getPath()+filename,dir);
    }
    return super.getChild(dir,filename);
}

public String getSystemDisplayName(File f) {
    if(f instanceof ZipEntryFileProxy) {
        return f.getName();
    }
    return super.getSystemDisplayName(f);
}

}

public File getParentDirectory(File dir) {
    if(dir instanceof ZipEntryFileProxy) {
        return dir.getParentFile();
    }
    return super.getParentDirectory(dir);
}

}

public File[] getFiles(File dir, boolean useFileHiding) {
    if(dir.getName().endsWith(".zip")) {
        ZipFileProxy proxy = new ZipFileProxy(dir);
        File[] fs = proxy.getFiles("");
        return fs;
    }

    if(dir instanceof ZipEntryFileProxy) {
        return dir.listFiles();
    }

    return super.getFiles(dir,useFileHiding);
}

}

public Boolean isTraversable(File f) {
    if(f.getName().endsWith(".zip")) {
        return new Boolean(true);
    }
    if(f instanceof ZipEntryFileProxy) {
        boolean b = ((ZipEntryFileProxy)f).isDirectory();
        return new Boolean(b);
    }
}
```

```

return super.isTraversable(f);
}
}

```

Note the `isTraversable()` method, which returns true if the file ends with `.zip` or is an instance of `ZipEntryFileProxy`. Without this, the `JFileChooser` would never let the user navigate inside of ZIP files.

### 4.6.3. Put It All Together

The class in [Example 4-4](#) creates a `JFileChooser` with a `ZipFileSystemView`. The only custom code beyond the view itself is a check to see if the selected file is a `ZipEntryFileProxy`. If so, the program will cast the file to a `ZipEntryFileProxy` and call `getInputStream()`. If not, it will just create a `FileInputStream` as normal.

#### Example 4-4. A sample program

```

public class ZipTest {

    public static void main(String[] args) throws Exception {
        FileSystemView fsv = new ZipFileSystemView();
        JFileChooser chooser = new JFileChooser(".");
        chooser.setFileSystemView(fsv);
        chooser.showOpenDialog(null);
        File file = chooser.getSelectedFile();
        System.out.println("Got the file: " + file + " " + file.getClass());

        InputStream in = null;
        if(file instanceof ZipEntryFileProxy) {
            in = ((ZipEntryFileProxy)file).getInputStream();
        } else {
            in = new FileInputStream(file);
        }
    }
}

```

As you can see, this method of extending the `JFileChooser` to support an alternative filesystem is quite hackish. Sadly, it's the only way to do such a thing without writing a completely custom file chooser. This is probably why so many IDE authors have just chucked the entire `JFileChooser` and `FileSystemView` API in favor of a custom dialog. However, if you wish to remain within the standard API, you can certainly do it, as this hack proves. As a future enhancement, you might make this class more generic, handling the nasty details of file wrapping while delegating the actual alternative filesystem to a subclass. This would create an API more like `TReeModel`, from which other developers can create their own implementations easily.





# Chapter 5. Windows, Dialogs, and Frames

[Section 5.1. Hacks 3340: Introduction](#)

[Hack 33. Window Snapping](#)

[Hack 34. Make a Draggable Window](#)

[Hack 35. Add Windows Resize Icons](#)

[Hack 36. Add Status Bars to Windows](#)

[Hack 37. Save Window Settings](#)

[Hack 38. Earthquake Dialog](#)

[Hack 39. Spin Open a Detail Pane](#)

[Hack 40. Minimize to a Mini-Frame](#)

## 5.1. Hacks 3340: Introduction

For four chapters, we've hacked away at Swing widgets, from `JLabels` to `JTables`, without worrying too much about the context in which they're shown to the user. And yet, every Swing widget must ultimately be contained in some kind of window to be on the screen at all. It's not an exaggeration to say that many competent Swing programmers don't even know or care about the hierarchy of AWT Windows, Dialogs, and Frames or their Swing equivalents, `JWindow`, `JDialog`, and `JFrame`. Yet, it's these same programmers who don't know that commercial components like splash screens are all possible in Swing; they see dialogs and frames and assume everything has a titlebar. This is hardly true, though you can easily remove the decorations of a dialog, or just work with the window superclass.

Suffice it to say there's much you can do with windows and their subclasses. So much so, in fact, that it fills two chapters. This chapter will deal with hacks that deal with placing, moving, and resizing windows in ways that are fairly consistent with the design of the window classes. The next chapter will be a lot more aggressive in breaking the rules.

## Hack 33. Window Snapping



Make your windows snap to the edges of the screen by using a special event listener.

Back in the prehistoric days of desktop software, as graphics programs were being invented, they solved the problem of managing the drawing tools by creating mini-windows called *palettes* (and their later variation, toolbars). Eventually, the programs had so many palettes that the users grew frustrated trying to organize them. Lining them up on the edge of the screen was particularly nasty, so fledgling young programmers took it upon themselves to create *snappable windows*. These were windows that were magnetic (metaphorically speaking) and could align themselves to the screen's edges. This hack demonstrates how to recreate this technique with Java.

The idea is simple: you check whenever the user moves the window. If the window is off the screen, then move it back to the edge. Moving the window is pretty easy. The trickier part is knowing when the window has moved. Fortunately, AWT has an answer: the `ComponentListener` interface.

In Java, every UI component (in both AWT and Swing) fires events whenever it moves, resizes, is shown, or is hidden. Any class can receive these events by implementing the `ComponentListener` interface. For the purposes of this hack, you only need the `componentMoved` event, so start by subclassing `ComponentAdapter`, which provides default no-operation implementations of all of `ComponentListener`'s declared methods. Then just override the `componentMoved()` method, as seen in [Example 5-1](#).

### Example 5-1. A ComponentListener to snap a window into place

```
public class WindowSnapper extends ComponentAdapter {

    public WindowSnapper( ) { }

    private boolean locked = false;
    private int snap_distance = 50;

    public void componentMoved(ComponentEvent evt) {
        if(locked) return;
        Dimension size = Toolkit.getDefaultToolkit( ).getScreenSize( );
        int nx = evt.getComponent( ).getX( );
        int ny = evt.getComponent( ).getY( );
        // top
        if(ny < 0+snap_distance) {
            ny = 0;
        }
    }
}
```

```

// left
if(nx < 0+snap_distance) {
    nx = 0;
}
// right
if(nx > size.getWidth( ) - evt.getComponent( ).getWidth( ) -
    snap_distance) {
    nx = (int)size.getWidth( )-evt.getComponent( ).getWidth( );
}
// bottom
if(ny > size.getHeight( ) - evt.getComponent( ).getHeight( ) -
    snap_distance) {
    ny = (int)size.getHeight( )-evt.getComponent( ).getHeight( );
}

// make sure we don't get into a recursive loop when the
// set location generates more events
locked = true;
    evt.getComponent( ).setLocation(nx,ny);
    locked = false;
}
}

```

Every time `componentMoved( )` is called, it gets the screen size and current coordinates of the window. Because window coordinates are already relative to the screen's origin, there is no need to translate them. Next comes four `if` statements to determine whether the window is at least partially off screen. The first two handle the top and lefthand sides of the screen. If the user moves the component off screen, or even moves within `snap_distance` of the screen's edges, this method moves the window directly to 0. The second two `ifs` handle the bottom and righthand sides of the screen, which is essentially the same as the first two except they have to account for the size of the window as well. Finally, the window is moved to the correct location.

You should also take note of the `locked` variable. This is used to avoid a potential infinite loop. Essentially, the `componentMoved( )` method will be called every time the window moves. The `componentMoved( )` method will also call `setLocation( )` on the window, which will then trigger another move event. Left unchecked, these methods will be called over and over, locking the paint thread, and crashing your program with an out-of-memory error. It would be nice to look at the event and tell if the user moved the window or if the code did, but the API doesn't provide such a function. The solution: detect recursive calls by using a lock variable. If `locked` is `false`, then this is a real move event done by the user, and it's OK to do the snapping. Then, just before `setLocation( )` is called, the code sets `locked` to `True`. If `componentMoved( )` is called again, the code knows that further movement should be ignored. After `setLocation( )` returns, `locked` is set back to `false`.

To test out the `WindowSnapper`, you have to add it as a `ComponentListener` to a window:

```

public static void main(String[] args) {
    JFrame frame = new JFrame("Hack #33: Window Snapping");
    JLabel label = new JLabel(
        "Move this window's titlebar to demonstrate screen edge snapping.");
}

```

```
        frame.getContentPane( ).add(label);
        frame.pack( );

        frame.addComponentListener(new WindowSnapper( ));
        frame.setVisible(true);
    }
```

However, this hack has one major flaw. Because the component events are read-only, it is impossible to intercept the move and position the window before it has been drawn on screen. Thus the window will flash as the user moves it. Creating a custom event queue would seem to be the answer because you could then modify the events before they are sent to the components, but this won't work for move events on windows (or any subclass like `JFrame`). Windows are real structures provided by the operating system, rather than purely Java objects. The window events are created by the OS itself and passed into the JVM from the C level, meaning there is no way to capture these before they take effect. Still, in many of your applications, the flashing may be an acceptable trade-off for snapping.

[← PREV](#)

## Hack 34. Make a Draggable Window



Drag a window by clicking on its background using a special event listener .

Most windows let you move them by dragging the titlebar. Some program windows, however, don't have titlebars. In the age of eye-candy interfaces (see iTunes and WinAmp for prime examples) it is very common to have a window possibly non-rectangular without any titlebar or window controls at all. This makes for a pretty window, but how do you move it? Simply by dragging any available space on the window. Though not terribly intuitive, such programs are commonplace, and this book wouldn't be called *Swing Hacks* without providing a Java implementation of draggable windows, even when no titlebar is used.

The simplest approach to this problem is to create a listener that simply catches all drags and moves the window:

```
public class MoveMouseListener implements MouseListener, MouseMotionListener
{
    JComponent target;
    JFrame frame;
    public MoveMouseListener(JComponent target, JFrame frame) {
        this.target = target;
        this.frame = frame;
    }

    public void mouseClicked(MouseEvent e) {}
    public void mouseEntered(MouseEvent e) {}
    public void mouseExited(MouseEvent e) {}
    public void mousePressed(MouseEvent e) {}
    public void mouseReleased(MouseEvent e) {}
    public void mouseMoved(MouseEvent e) {}
    public void mouseDragged(MouseEvent e) {
        frame.setLocation(new Point(e.getX( ),e.getY( )));
    }
}
```

This class implements `MouseListener` and `MouseMotionListener` with no-ops for all methods except `mouseDragged()`, which moves the frame to the current mouse location. However, this approach has two problems. First, the mouse coordinates are going to be relative to the component, rather than the screen. Thus, a click on a 50 x 50 button in the bottom right of the screen might return (25, 25) when it should really be more like (1000, 700). The other problem is that the code moves the origin of the frame to the mouse cursor. This would look strange because the window would immediately jump so that its upper-le

corner is right under the cursor. The proper behavior is for the window to stay in the same position *relative* to the cursor as the cursor moves around.

The solution to the first problem (getting screen coordinates rather than component coordinates) is to convert mouse coordinates to absolute screen coordinates. The following method does just that (we'll use this shortly in `mouseDragged ( )`):

```
Point getScreenLocation(MouseEvent e) {
    Point cursor = e.getPoint( );
    Point target_location = this.target.getLocationOnScreen( );
    return new Point(

        (int)(target_location.getX( )+cursor.getX( )),
        (int)(target_location.getY( )+cursor.getY( )));
}
```

Solving the second issue (keeping the window static relative to the mouse) requires saving an initial offset between window and cursor, and then maintaining that offset throughout the drag. You should add a new `mousePressed ( )` implementation that saves the current screen location of the mouse cursor (`start_drag`) and the current location of the window (`start_loc`). The distance between the two points can be used to form an offset:

```
Point start_drag;
Point start_loc;
public void mousePressed(MouseEvent e) {
    this.start_drag = this.getScreenLocation(e);
    this.start_loc = this.getFrame(this.target).getLocation( );
}
```

Next, the listener should maintain the offset difference throughout the drag operation by calculating a new offset each time the mouse moves. Here is the new `mouseDragged ( )` method:

```
public void mouseDragged(MouseEvent e) {
    Point current = this.getScreenLocation(e);
    Point offset = new Point(
        (int)current.getX( )-(int)start_drag.getX( ),
        (int)current.getY( )-(int)start_drag.getY( ));
    JFrame frame = this.getFrame(target);
    Point new_location = new Point(
        (int)(this.start_loc.getX( )+offset.getX( )),
        (int)(this.start_loc.getY( )+offset.getY( )));
    frame.setLocation(new_location);
}
```

Using the utility method, it gets the current mouse position in screen coordinates, and then calculates the distance between that position and where the mouse started. Finally, it adds this offset to the starting location for the window to set the window's final location.

Every now and then, the event queue will drop a mouse event. If the code was adding the deltas (change in position) from each drag event, then eventually the user would start to see errors as a result of these dropped events. Because this code always recalculates the window position relative to the start of the drag, these errors don't have an effect. Plus, since Swing sends all mouse events to a dragged component even if the cursor moves outside the bounds of the component you don't have to worry about the user dragging off the edge of the window and shutting down the whole process.

This method of window dragging has two strengths. First, since the work is done in a listener, you can add this listener to any existing Swing component without subclassing. Any old program can become draggable! Second, only drags on the attached component affect the window you can make the background of the window draggable without affecting any of the foreground components (like the Play button on an MP3 player).

To test out the mouse listener, try adding it to the Calendar hack [Hack #4] . Change the `main ( )` function like this:

```
public static void main(String[] args) {
    JFrame frame = new JFrame( );
    CalendarHack ch = new CalendarHack( );
    ch.setDate(new Date( ));
    frame.getContentPane( ).add(ch);

frame.setUndecorated(true);
MoveMouseListener mml = new MoveMouseListener(ch, frame);
ch.addMouseListener(mml);
ch.addMouseMotionListener(mml);

    frame.pack( );
    frame.setVisible(true);
}
```

The only additions are the four bold lines in the middle of the method. The first line turns off the standard window decorations, and the second creates the `MoveMouseListener` with references to the `CalendarHack` component and its frame. The last two lines add the listener so that it receives all of the mouse events before the frame is shown on screen.

The final hack looks like Figure 5-1 , with the titlebar and window controls hidden and the entire component draggable.

Figure 5-1. A draggable calendar





← PREV

## Hack 35. Add Windows Resize Icons



The Windows resize icons aren't built into Java. Here's how to make your own .

Windows has two standard icons to let users know that they can resize a window. I can't tell you why there are two or how to decide between them, but I can tell you how to reproduce both of them in Java. Note that this hack is concerned with *painting* the icons accurately; it will be up to your code to handle events on components that use these icons and handle them appropriately.

### 5.4.1. A Tale of Two Icons


First take a look at the two icons. Figure 5-2 shows the icon used by Windows Explorer, MS Paint, and other applications; Figure 5-3 shows the icon used by Word and other Office applications.

### 5.4.2. The Icon Interface

The easiest and most flexible way to implement these icons is through the `Icon` interface. Using `Icon` allows you to change an icon's appearance easily if you need to match new system defaults. It's also a lot easier to implement transparency with an `Icon` than by making an image from the corner icon using a screen capture and editing it in a professional graphics application like Photoshop.

Figure 5-2. The Windows Explorer resize icon

Figure 5-3. The Windows MS Office resize icon



Icon is pretty simple, and it has only three methods:

```
void paintIcon(Component c, Graphics g, int x, int y);

int getIconWidth( );

int getIconHeight( );
```

The `getIconWidth( )` and `getIconHeight( )` methods should be pretty easy to implement you just need the pixel size of your custom icons. The `paintIcon( )` method is where all the interesting stuff happens.

### 5.4.3. The Explorer Icon

Figure 5-4 shows a huge blowup of what we'll call the Explorer icon.

At a glance, you can see the six squares in a triangular pattern with a subtle white 3D effect on the squares. The easiest thing to handle is the size, so start with that. This icon is 12 x 12 pixels (one square in Figure 5-4 equals one pixel).

Figure 5-4. The Windows Explorer icon zoomed in

Here are the width and height methods. Start by creating constants for height and width, and write the getters:

```

private static final int WIDTH = 12;
private static final int HEIGHT = 12;

public int getIconHeight( ) {
    return WIDTH;
}

public int getIconWidth( ) {
    return HEIGHT;
}

```

To implement `paintIcon ( )`, you'll need to recreate this icon using the graphic primitives provided by AWT. So, you need to carefully analyze how the original was created. After close inspection, you'll find that each square actually has three separate colors: the top-right color, the bottom-right color, and the left color. Here are the color constants you need:

```

private static final Color SQUARE_COLOR_LEFT = new Color(184, 180, 163);
private static final Color SQUARE_COLOR_TOP_RIGHT = new Color(184, 180, 161);
private static final Color SQUARE_COLOR_BOTTOM_RIGHT = new Color(184, 181, 161);

```

To recreate the icon, it will help to have a method to paint the gray squares. Notice that the method also caches `Graphics` ' previous color and resets the graphics color at the end of the method, which is generally a good practice:

```

private void drawSquare(Graphics g, int x, int y){
    Color oldColor = g.getColor( );
    g.setColor(SQUARE_COLOR_LEFT);
    g.drawLine(x,y, x,y+1);
    g.setColor(SQUARE_COLOR_TOP_RIGHT);
    g.drawLine(x+1,y, x+1,y);
    g.setColor(SQUARE_COLOR_BOTTOM_RIGHT);
    g.drawLine(x+1,y+1, x+1,y+1);
    g.setColor(oldColor);
}

```

The code looks strange because of all of the `drawLine ( )` calls that really should be `drawPoint ( )` calls. Because there is no `drawPoint ( )` method, you can accomplish the same thing by drawing a line to and from the same point.

You could paint each square and then add the 3D effect with more lines, but this is a good time to take

advantage of the non-transparent nature of computers. It's easier just to paint the white 3D effect as white squares and paint over the corners when you draw the gray squares.

Continuing as before, create a constant for the 3D effect color (white):

```
private static final Color THREE_D_EFFECT_COLOR = new Color(255, 255, 255);
```

The constant is used by a helper method to paint the white squares. It caches the old paint color, sets the graphics to paint white, draws the square, and resets the graphics color:

```
private void draw3dSquare(Graphics g, int x, int y){
    Color oldColor = g.getColor( );
    g.setColor(THREE_D_EFFECT_COLOR);
    g.fillRect(x,y,2,2);
    g.setColor(oldColor);
}
```

Now, think of the icon as a grid with rows and columns representing the locations for the squares. It's really a 3 x 3 grid that's partially filled in like this:

```
| | | X |
| | X | X |
| X | X | X |
```

Keep track of the rows and columns with variables to make painting easier. Also, keep track of the space between the rows and columns in pixels:

```
int firstRow = 0;
int firstColumn = 0;
int rowDiff = 4;
int columnDiff = 4;
```

The row difference works out to be four because the square is two pixels wide, plus one pixel for the white effect, plus one pixel for spacing. The same deal applies for the column difference. From there, it's easy to calculate the other rows and columns based on the starting row and column and their distances from each other:

```
int secondRow = firstRow + rowDiff;
int secondColumn = firstColumn + columnDiff;
int thirdRow = secondRow + rowDiff;
int thirdColumn = secondColumn + columnDiff;
```

Next, paint the white squares: one in the first row, two in the second, and three in the third. Notice that the white squares are offset by one pixel because the column and row variables (`firstRow`, `secondRow`, etc.) reference the gray squares. These squares provide the 3D effect.

```
//first row
draw3dSquare(g, firstColumn+1, thirdRow+1);

//second row
draw3dSquare(g, secondColumn+1, secondRow+1);
draw3dSquare(g, secondColumn+1, thirdRow+1);

//third row
draw3dSquare(g, thirdColumn+1, firstRow+1);
draw3dSquare(g, thirdColumn+1, secondRow+1);
draw3dSquare(g, thirdColumn+1, thirdRow+1);
```

Finally, paint the gray squares on top of the white squares:

```
//first row
drawSquare(g, firstColumn, thirdRow);

//second row
drawSquare(g, secondColumn, secondRow);
drawSquare(g, secondColumn, thirdRow);

//third row
drawSquare(g, thirdColumn, firstRow);
drawSquare(g, thirdColumn, secondRow);
drawSquare(g, thirdColumn, thirdRow);
```

#### 5.4.4. The Office Icon

Figure 5-5 shows the MS Office corner icon in detail.

Figure 5-5. The Windows MS Office icon zoomed in

This icon is easier it's just a couple of straight lines. Also, it's 13 x 13 pixels, which is bigger than the last icon. So, start with the trivial size methods:

```
private static final int WIDTH = 13;
private static final int HEIGHT = 13;

public int getIconHeight( ) {
    return WIDTH;
}

public int getIconWidth( ) {
    return HEIGHT;
}
```

The `paintIcon ( )` method is also pretty straightforward. Start by painting the three white lines, and follow up with the dark gray lines. Here's the code:

```
public void paintIcon(Component c, Graphics g, int x, int y) {

    g.setColor(WHITE_LINE_COLOR);
    g.drawLine(0,12, 12,0);
    g.drawLine(5,12, 12,5);
    g.drawLine(10,12, 12,10);

    g.setColor(GRAY_LINE_COLOR);
    g.drawLine(1,12, 12,1);
    g.drawLine(2,12, 12,2);
    g.drawLine(3,12, 12,3);

    g.drawLine(6,12, 12,6);
    g.drawLine(7,12, 12,7);
    g.drawLine(8,12, 12,8);

    g.drawLine(11,12, 12,11);
    g.drawLine(12,12, 12,12);
}
```

Notice you don't have to paint the light gray color because it's actually the panel background color. Any area you don't explicitly paint over picks up the background color, which is exactly what you want here.



These icons are approximations; some things will be different between applications and systems. They were taken directly, pixel by pixel, from Windows Explorer and Microsoft Office 2000 running on Windows XP Professional. Different applications are slightly different, even on the same version of Windows. Double check platforms you are deploying to and make sure the colors are correct. Meanwhile, it's still a really good working icon, even if a couple of pixels are off by a few shades.

*Jonathan Simon*





## Hack 36. Add Status Bars to Windows



Lots of applications use a bottom-of-window panel to communicate status. But Swing doesn't have a consistent way to do this. So, you need to provide it yourself.

Many applications in Microsoft Windows use a status bar area at the bottom of each window (to the left of the resize box if there is one) that can be used to communicate summary information to the user in a compact way. Typical contents of a status bar might include what a web browser is doing (e.g., "Connecting to www.oreilj.com"), or, as in Figure 5-6, a summary of the contents of a folder, showing the number of contained items, the

Figure 5-6. Windows Explorer's status bar

### 5.5.1. Standard Status Bars

This is the standard MS Windows setup for a status bar:

- An icon on the far right letting users know they can resize the application
- A label on the left for free form text
- Several labels on the right for details (e.g., 42.3 MB in Figure 5-6)

There is also a bit of custom painting involved to get the top and bottom shading right. First, you'll do the shading, and then loop back to the previous list and add all of the necessary components to the status bar.

This hack copies the Windows Explorer status bar in Windows XP. Different applications have slightly different status bars. The purpose of this hack isn't to start a religious war about which application to copy. You can just make minor changes if you want to copy a different application's status bar (such as Word or Outlook, which are different than Windows Explorer and also from other applications).

Start by creating a class called `JStatusBar` extending `JPanel` :

```
public class JStatusBar extends JPanel {
    //more to come
}
```

```
}
```

Then add a constructor and set the preferred height to be 23 pixels (the height of the Windows Explorer barcount 'em up if you don't trust me). You can ignore the preferred width of the status bar since you'll status bar to your frame with a `BorderLayout` or similar layout that will stretch this component to the width of the window:

```
public JStatusPanel( ){
    setPreferredSize(new Dimension(getWidth( ), 23));
}
```

## 5.5.2. Painting Panel Details

Figure 5-7 shows the Windows Explorer status bar zoomed in around the 42.3 MB label. There are a couple of thin lines at the top and bottom, as well as a blue line at the bottom, used to achieve a subtle gradation effect.

Figure 5-7. Explorer's status bar zoomed in

You can achieve this effect easily by overriding `paintComponent ( )` and drawing the lines yourself. Here is the overridden `paintComponent ( )` code:

```
public void paintComponent(Graphics g) {
    super.paintComponent(g);

    int y = 0;
    g.setColor(new Color(156, 154, 140));
    g.drawLine(0, y, getWidth( ), y);
    y++;
    g.setColor(new Color(196, 194, 183));
    g.drawLine(0, y, getWidth( ), y);
    y++;
    g.setColor(new Color(218, 215, 201));
    g.drawLine(0, y, getWidth( ), y);
    y++;
    g.setColor(new Color(233, 231, 217));
    g.drawLine(0, y, getWidth( ), y);
}
```

```

        y = getHeight( ) - 3;
        g.setColor(new Color(233, 232, 218));
        g.drawLine(0, y, getWidth( ), y);
        y++;
        g.setColor(new Color(233, 231, 216));
        g.drawLine(0, y, getWidth( ), y);
        y = getHeight( ) - 1;
        g.setColor(new Color(221, 221, 220));
        g.drawLine(0, y, getWidth( ), y);
    }

```

The first section draws the gray lines at the top. Midway through, `y` is reset based on the panel height, and bottom lines are drawn.

### 5.5.3. Add the Corner Icon

Next, you need to add the resize icon preferably made to resemble real Windows resize icons [Hack #36]. Use `JLabel` for the corner icon and add the icon to it. Since this hack is mimicking the Explorer status bar, use `TriangleSquareWindowsCornerIcon`. Also, remember to set the label opacity to `false`. This makes the status bar background show through the icon:

```

JLabel resizeIconLabel = new JLabel(new TriangleSquareWindowsCornerIcon( ));
resizeIconLabel.setOpaque(false);

```

Now, you need to add the label to the panel. You need the resize icon to be at the right, on the bottom of the status bar. To make this work, set the `JStatusBar` layout to a `BorderLayout`. Then create another panel called `rightPanel` and set its layout to `BorderLayout` as well. Add the `rightPanel` to the status bar, to the east; add the resize icon to `rightPanel`, to the south. Don't forget to set the `rightPanel`'s opacity to `false` as well. This will place the icon at the bottom right of the status bar:

```

JPanel rightPanel = new JPanel(new BorderLayout( ));
rightPanel.setOpaque(false);
rightPanel.add(resizeIconLabel, BorderLayout.SOUTH);
add(rightPanel, BorderLayout.EAST);

```

While you're at it, create another panel and name it `contentPanel`. Add this to the center of the status bar. In the next few sections to add the rest of the components:


```

contentPanel = new JPanel( );
contentPanel.setOpaque(false);
add(contentPanel, BorderLayout.CENTER);

```

## 5.5.4. Add the Left Component

Now that the `contentPanel` is in place, you need to configure it to hold all of the components you're going to add to the status bar. Remember that the status bar has several components on the righthand side (just to the right of the resize icon) that don't resize.



It's actually possible for these components to resize, but standard Windows behavior is to have the size stay the same and center text.

There are also a bunch of separators between each of the righthand components. And on the left, there's a main component that takes up all of the space left over after the righthand components (yes, it's rather complicated, but read this section again and you'll get it).

You could get most of this behavior with a bunch of nested panels and layouts. But it's easier to use a simple layout manager that can handle all of these, such as `FormLayout` from JGoodies. I don't want to get *too* detailed about `FormLayout`, so feel free to check out <http://www.jgoodies.com> for more info. You'll need to download JGoodies Forms from the JGoodies site and put its JAR file (`forms-1.0.5.jar` as of this writing) in your classpath. Here's the code to create a new `FormLayout` and set it on the `contentPanel`:

```
layout = new com.jgoodies.forms.layout.FormLayout(
    "2dlu, pref:grow",
    "3dlu, fill:10dlu, 2dlu");

contentPanel.setLayout(layout);
```

`FormLayout` is essentially an advanced grid, typically configured by passing in strings that describe the row and column contents in a heavily condensed syntax. So, you need to configure the grid columns and rows and place the components to the appropriate locations. It's a simplistic approach that is really powerful.

The first line `2dlu, pref:grow` creates two columns: one column is two dialog units (`dlu` in the code) wide and the other is a column that grows. This is for the left component (which needs to grow), and the second column is there simply to create a space. The dialog unit system used for this space is based on the pixel size of the dialog font, meaning it can grow and shrink as fonts and resolutions change. Overall, this is a better and more consistently sized components and windows than using absolute pixel measurements.

The second line `3dlu, fill:10dlu, 2dlu` creates the rows for the layout. In this case, it adds a three dialog unit space at the top, a two dialog unit space at the bottom, and fills the rest of the space with the component you're adding.

Now, add the left component. When you add components to a `FormLayout`-enabled panel, you need to use the `CellConstraints` object. You can use the simple `CellConstraints` that takes an `x` - and `y` -coordinate. In this case, the coordinate is (2,2) because `FormLayout` starts counting at 1 and you're skipping the first column and the space. Here is the code:

```

public void setMainLeftComponent(JComponent component){
    contentPanel.add(component, new CellConstraints(2, 2));
}

```

### 5.5.5. Add a Separator Panel

Before you can add the components to the right side, you need to make a separator panel. This is a simple component that draws a gray line and a white line in the middle of the panel. Look on the right at a 42.3 MB text in Figure 5-7 to see what the separators should look like.

Example 5-2 shows the `SeparatorPanel` code.

Example 5-2. A panel to separate sections of the status bar

```

public class SeparatorPanel extends JPanel {
    private Color leftColor;
    private Color rightColor;

    public SeparatorPanel(Color left, Color right) {
        this.leftColor = left;
        this.rightColor = right;
        setOpaque(false);
    }

    protected void paintComponent(Graphics g) {
        g.setColor(leftColor);
        g.drawLine(0,0, 0,getHeight( ));
        g.setColor(rightColor);
        g.drawLine(1,0, 1,getHeight( ));
    }
}

```

### 5.5.6. And the Rest...

Now that the right panel has been added and you've got the code for the `SeparatorPanel`, you can add the components to the status bar. You'll be adding two columns to the layout one for the `SeparatorPanel` the actual component. In order to add the components at the correct location, you'll need to cache the coordinates and increment the coordinates as you add components. So, create two fields `layoutCoordinateX` and `layoutCoordinateY` to keep track of the current coordinates:

```

public void addRightComponent(JComponent component, int dialogUnits){
    layout.appendColumn(new ColumnSpec("2dlu"));
}

```


```

        layout.appendColumn(new ColumnSpec(dialogUnits + "dlu"));

        layoutCoordinateX++;
        contentPanel.add(
            new SeparatorPanel(Color.GRAY, Color.WHITE),
            new CellConstraints(layoutCoordinateX, layoutCoordinateY)

        );
        layoutCoordinateX++;
        contentPanel.add(
            component,
            new CellConstraints(layoutCoordinateX, layoutCoordinateY)
        );
    }

```



Notice that the size is passed into this method in dialog units rather than pixels. You could easily change this to pixels if you want, but I find dialog units to be a much easier way to layout this kind of component.

### 5.5.7. Running the Hack

Example 5-3 is the code for a complete simulation frame. You just need to create the `JStatusBar` and add `main`, and right components. All of the layout and painting logic is encapsulated completely in `JStatusBar` lines in the middle of the `StatusBarSimulator` are where the status bar is created and the three components added. Also, notice that all of the labels are center aligned this mimics the standard Windows practice. You see the finished product in Figure 5-8.

Figure 5-8. The status bar from `StatusBarSimulator`

#### Example 5-3. Using the `JStatusBar` in a `JFrame`

```

public class StatusBarSimulator {

    public static void main(String[] args) {
        try {
            UIManager.setLookAndFeel(new WindowsLookAndFeel());
        } catch (Exception e){

        }
    }
}

```

```
JFrame frame = new JFrame( );
frame.setBounds(200,200, 600, 200);
frame.setTitle("Status bar simulator");

Container contentPane = frame.getContentPane( );
contentPane.setLayout(new BorderLayout( ));

JStatusBar statusBar = new JStatusBar( );

JLabel leftLabel =
    new JLabel("Your application is about to self destruct.");
statusBar.setMainLeftComponent(leftLabel);

JLabel dateLabel = new JLabel("12/31/99");
dateLabel.setHorizontalAlignment(SwingConstants.CENTER);
statusBar.addRightComponent(dateLabel, 30);

JLabel timeLabel = new JLabel("11:59 PM");
timeLabel.setHorizontalAlignment(SwingConstants.CENTER);
statusBar.addRightComponent(timeLabel, 30);

contentPane.add(statusBar, BorderLayout.SOUTH);

frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);           fran
    }
}
```

*Jonathan Simon*

## Hack 37. Save Window Settings



Make sure your windows always show up right where you left them, even after a program restarts, by saving the window position and size automatically.

Swing is a rich toolkit that can be used to create many kinds of programs, but there are certain features that virtually all applications need, like window settings and preferences. This hack shows how to automatically store and retrieve window locations and dimensions in an existing program without using custom `Frame` subclasses, or even making many changes to your existing code.

Saving the size and location of a window is actually pretty easy. You can just store them in a file and retrieve them later. The difficulty is identifying each window, and doing it in a way that's as noninvasive as possible.

### 5.6.1. The Window Saver Class

The first step is to create a class that handles all of the work. Because managing windows will be a global function of the entire program, start with a simple singleton with a factory interface, as shown in [Example 5-4](#).

#### Example 5-4. Singleton for saving window settings

```
public class WindowSaver implements AWTEventListener {

    private static WindowSaver saver;
    private Map framemap;

    private WindowSaver( ) {
        framemap = new HashMap( );
    }

    public static WindowSaver getInstance( ) {
        if(saver == null) {
            saver = new WindowSaver( );
        }
        return saver;
    }
}
```



The `WindowSaver` constructor creates a private map to store all of an application's frames. When each frame is loaded, the saver will store a reference to it in this map. Later, when the application needs to save or reload each window, it will use the map to find each frame again. The constructor is private so that only one instance (and one map) of the program ever exists in the JVM.

The `WindowSaver` also implements `AWTEventListener`. This is how it can find each frame. Swing has a global event queue that allows you to get every event throughout the JVM. You can access this queue by registering an `AWTEventListener` to the global toolkit like this:

```
Toolkit tk = Toolkit.getDefaultToolkit( );
tk.addAWTEventListener(WindowSaver.getInstance( ),
    AWTEvent.WINDOW_EVENT_MASK);
```

`AWTEventListener` defines a single method, `eventDispatched(AWTEvent)`. Through this method, you can look for each window as it is opened.

Each window produces several events for actions such as closing, opening, resizing, hiding, etc. Some events, such as activation, happen each time a window is shown on the screen. The `WINDOW_OPEN` event will be called only once per window, right when the window is first shown. This is perfect for our purposes because that particular event will happen after an application has created and initialized each window, but before the window is shown on screen, making it the ideal place to set window size and location:

```
public void eventDispatched(AWTEvent evt) {
    try {
        if(evt.getID( ) == WindowEvent.WINDOW_OPENED) {
            ComponentEvent cev = (ComponentEvent)evt;
            if(cev.getComponent( ) instanceof JFrame) {
                JFrame frame = (JFrame)cev.getComponent( );
                loadSettings(frame);
            }
        }
    } catch(Exception ex) {
        p(ex.toString( ));
    }
}
```

This code listens for `WINDOW_OPEN` events and then retrieves the reference to the `JFrame` that was created. Finally, it calls `loadSettings( )` on the frame:

```
public static void loadSettings(JFrame frame) throws IOException {
    Properties settings = new Properties( );
    settings.load(new FileInputStream("configuration.props"));
    String name = frame.getName( );
    int x = getInt(settings,name+".x",100);
```

```

        int y = getInt(settings,name+".y",100);
        int w = getInt(settings,name+".w",500);
        int h = getInt(settings,name+".h",500);
        frame.setLocation(x,y);
        frame.setSize(new Dimension(w,h));
        saver.frameMap.put(name,frame);
        frame.validate();
    }

```

`loadSettings()` demonstrates the real trickery of this hack. Every object in Java has a unique hash code, but hash codes are poor identifiers because they will be different each time the program is run. That makes them useless for saving preferences or referring to windows. Fortunately, Swing defines a little-known property for each component: `name`. You can name any component in your program with a unique string, and `name` will be the same every time the program runs. This makes it ideal for saving properties.

`loadSettings()` creates a new properties object, populates it with the contents of a `configuration.props` file, and then retrieves the name of the given frame. For each property you want to retrieve (the frame coordinates and size), just prepend the property with the name of the component. If the application developer named a frame `control-panel`, then the x-coordinate would be stored in `control-panel.x`.

After getting each property, `loadSettings()` sets the location and size of the frame, and then adds the frame to the global frame map so that it can be retrieved later. As a final step, it calls `validate()` on the frame to make sure Swing updates the frame's location and size properly. Here is `getInt()`, which is a utility method to retrieve integers from property strings and which substitutes a default value if the string is missing:

```

public static int getInt(Properties props, String name, int value) {
    String v = props.getProperty(name);
    if(v == null) {
        return value;
    }
    return Integer.parseInt(v);
}

```

So, that takes care of loading frame properties.

Once registered to the global event queue, the `WindowSaver` class will automatically adjust each frame when it is first opened, ensuring that windows are always positioned properly every time the program is run. Saving the window settings, however, is a different matter. This should really happen only when the program closes assuming the application developer wants window settings saved at all. There might be a standard location for say, dialog boxes, that should always be observed, regardless of how the user moved the windows around last time the program was run. It's probably best to allow applications to explicitly request settings be saved:

```

file.add(new AbstractAction("Quit") {
    public void actionPerformed(ActionEvent evt) {
        try {
            WindowSaver.saveSettings( );
            System.exit(0);
        } catch (Exception ex) {
            System.out.println(ex);
        }
    }
});

```

This code adds a Quit menu item that quits the application, but that also calls `saveSettings()` method, which again creates a properties object and populates it with the contents of `configuration.props`. However, instead of looking for window events, it loops through the frame map containing each of the frame references and retrieves the window settings:

```

public static void saveSettings( ) throws IOException {
    Properties settings = new Properties( );
    settings.load(new FileInputStream("configuration.props"));

    Iterator it = saver.framemap.keySet( ).iterator( );
    while(it.hasNext( )) {
        String name = (String)it.next( );
        JFrame frame = (JFrame)saver.framemap.get(name);
        settings.setProperty(name+".x", ""+frame.getX( ));
        settings.setProperty(name+".y", ""+frame.getY( ));
        settings.setProperty(name+".w", ""+frame.getWidth( ));
        settings.setProperty(name+".h", ""+frame.getHeight( ));
    }
    settings.store(new FileOutputStream("configuration.props"),null);
}

```

After looping through all of the frames, `saveSettings()` saves the properties back out to the `configuration.props` file, ready to be loaded the next time the user launches the application.

To demonstrate `WindowSaver`, you can create a `main()` method that registers the `WindowSaver`, builds a simple frame with a button and a Quit menu, and then shows the frame on screen. When the window is opened, the settings will be pulled from the properties file. When the user quits the program, the settings will be saved back to the properties file:

```

public static void main(String[] args) throws Exception {
    Toolkit tk = Toolkit.getDefaultToolkit( );
    tk.addAWTEventListener(WindowSaver.getInstance( ),
        AWTEvent.WINDOW_EVENT_MASK);

    final JFrame frame = new JFrame("Hack X");
}

```

```
frame.setName("WSTes.main");
frame.getContentPane().add(new JButton("a button"));
JMenuBar mb = new JMenuBar();
JMenu menu = new JMenu("File");
menu.add(new AbstractAction("Quit") {
    public void actionPerformed(ActionEvent evt) {
        try {
            WindowSaver.saveSettings();
            System.exit(0);
        } catch (Exception ex) {
            System.out.println(ex);
        }
    }
});
mb.add(menu);
frame.setJMenuBar(mb);
frame.pack();
frame.show();
}
```



## Hack 38. Earthquake Dialog



Make sure your users really know they got their password wrong .

One of the funny ways that Mac OS X uses animation in its UI is when the user logs in. If she enters an dialog shakes violently for a second, like a road sign thwacked with a bat, or a cartoon character who has a picture of a tunnel painted over a wall).

We like this effect a lot, so we thought we'd bring it to Swing. It's a pretty straightforward bit of animati

### 5.7.1. Exterior Animation

Here's an initial question: do you want to subclass `JDialog` and add the animation effect to that class, or another `JDialog`? I thought that subclassing would be a bad choice because `JOptionPane` generates some want to lose those. So, you'll have to have another class animate your dialogs.

I've called it `DialogEarthquakeCenter` because it'll be a class that monitors the shaking, just like seismolo

Obviously, the `DialogEarthquakeCenter` needs a reference to the dialog that it will be shaking. It also nee constants:

`SHAKE_DISTANCE`

The maximum distance in each direction the dialog should move.

`SHAKE_CYCLE`

The time in milliseconds for a complete cycle: center, right, center, left, back to center.

`SHAKE_DURATION`

Total time in milliseconds to shake the dialog.

`SHAKE_UPDATE`

How often (in milliseconds) to update the dialog's position and repaint. You might increase this if t smoothness decreases with less-frequent updates.

Beyond that, all you'll need to keep track of is where the dialog started (so you can put it back at the er

you are into the animation, and where the dialog is located. Example 5-5 shows the code to put all this in

### Example 5-5. A class to shake a JDialog back and forth

```
public class DialogEarthquakeCenter extends Object {

    public static final int SHAKE_DISTANCE = 10;
    public static final double SHAKE_CYCLE = 50;
    public static final int SHAKE_DURATION = 1000;
    public static final int SHAKE_UPDATE = 5;

    private JDialog dialog;
    private Point naturalLocation;
    private long startTime;
    private Timer shakeTimer;
    private final double HALF_PI = Math.PI / 2.0;
    private final double TWO_PI = Math.PI * 2.0;

    public DialogEarthquakeCenter (JDialog d) {
        dialog = d;
    }

    public void startShake( ) {
        naturalLocation = dialog.getLocation( );
        startTime = System.currentTimeMillis( );
        shakeTimer =
            new Timer(SHAKE_UPDATE,
                new ActionListener( ) {

                    public void actionPerformed (ActionEvent e) {
                        // calculate elapsed time
                        long elapsed = System.currentTimeMillis( )
                            - startTime;
                        // use sin to calculate an x-offset
                        double waveOffset = (elapsed % SHAKE_CYCLE) /
                            SHAKE_CYCLE;
                        double angle = waveOffset * TWO_PI;

                        // offset the x-location by an amount
                        // proportional to the sine, up to
                        // shake_distance
                        int shakenX = (int) ((Math.sin (angle) *
                            SHAKE_DISTANCE) +
                            naturalLocation.x);
                        dialog.setLocation (shakenX, naturalLocation.y);
                        dialog.repaint( );

                        // should we stop timer?
                        if (elapsed >= SHAKE_DURATION)
                    }
                }
            );
    }
}
```

```

        }
        );
        shakeTimer.start( );
    }

    public void stopShake( ) {
        shakeTimer.stop( );
        dialog.setLocation (naturalLocation);
        dialog.repaint( );
    }

    public static void main (String[] args) {
        JOptionPane pane =
            new JOptionPane ("You've totally screwed up your login\n" +
                "Go back and do it again... and do you think\n" +
                "you could remember your password this time?",
            JOptionPane.ERROR_MESSAGE, JOptionPane.OK_OPTION);
        JDialog d = pane.createDialog (null, "Shakin'!");

        DialogEarthquakeCenter dec = new
            DialogEarthquakeCenter (d);
            d.pack( );
            d.setModal (false);
            d.setVisible(true);
            dec.startShake( );

            // wait (forever) for a non-null click and then quit
            while (pane.getValue( ) == JOptionPane.UNINITIALIZED_VALUE ) {
                try { Thread.sleep(100); }
                catch (InterruptedException ie) {}
            }

            System.exit(0);
        }
    }
}

```

The class includes the constants described earlier, along with:

- A reference to the `JDialog` to be animated
- The dialog's natural location (i.e., its location before the animation begins)
- The time that the animation began (for calculating offsets)
- A `javax.swing.Timer` to run the animation
- Some trigonometry constants

The advantage of the Swing `Timer` is, of course, that it keeps the repainting on the event-dispatch thread

bit of non-Swing code executed by the timer to calculate the position, but it's not so bad that you have to

The constructor is trivial; it just remembers the dialog as an instance variable. The real fun begins in the `startShake` method. The current time and location; the time is for use in the animation, and the location is for cleaning up later. `startShake` fires every `SHAKE_UPDATE` milliseconds.

Now for some math and the methodology behind moving the dialog. Ignoring friction, air resistance, and the fantasy world of the desktop after all, we opted for *simple harmonic motion*, which is motion that can be undamped or dampened externally. Values of the sine function range from  $-1$  to  $1$ , so the dialog's horizontal offset from the center is  $\sin(t)$ , multiplied by the maximum offset (namely `SHAKE_DISTANCE`).

## Trig? Really?

Let me take a moment to explain why I'm forcing you to think about trigonometry in a Swing book. When a tuning fork or a pendulum moves back and forth, it doesn't move at a constant speed to one extreme, then a constant speed in the other direction. It slows down as it reaches the extreme, stops momentarily, and then starts moving in the other direction, moving faster until it crosses the center, at which point it starts decelerating. You need more than trigonometry to describe this motion; trig is the ticket.

So, that's what happens in the `actionPerformed` callback. The method takes the elapsed time and figure out the current position. The time of `SHAKE_CYCLE`, expressed as a `double` between 0 and 1. Multiply this by  $2\pi$ , and you've got an angle. Multiply this by `SHAKE_DISTANCE`, and you'll have an x-offset in the range  $-\text{SHAKE\_DISTANCE}$  to  $\text{SHAKE\_DISTANCE}$ . Keep the natural y-value, and you have the new location for the dialog. Call `setLocation` with this pair of coordinates.

`actionPerformed`'s only other responsibility is to check to see if the animation time has expired and, if so, call `stopShake` and `repaint`.

## 5.7.2. Shake, Rattle, and Roll

I've provided a `main` method to demonstrate the `DialogEarthquakeCenter`. To show its flexibility, I made it so that you can still use option dialogs as well as normal dialogs, although you do need to work with option dialogs a bit differently.

```
public static void main (String[] args) {
    JOptionPane pane =
        new JOptionPane ("You've totally screwed up your login\n" +
            "Go back and do it again... and do you think\n" +
            "you could remember your password this time?",
            JOptionPane.ERROR_MESSAGE,
            JOptionPane.OK_OPTION);
    JDialog d = pane.createDialog (null, "Shakin'!");
    DialogEarthquakeCenter dec = new DialogEarthquakeCenter (d);
    d.pack();
    d.setModal (false);
    d.setVisible(true);
    dec.startShake();
}
```



```

// wait (forever) for a non-null click and then quit
while (pane.getValue( ) == JOptionPane.UNINITIALIZED_VALUE ) {
    try { Thread.sleep(100); }
    catch (InterruptedException ie) {}
}
System.exit(0);
}

```

The `main ( )` method builds a `JOptionPane` dialog through what can only be called "the other way." Most c because it's convenient to get the dialog on screen immediately and provide the user's selection as a ret ever have a reference to the dialog. With `DialogEarthquakeCenter` , however, you need that reference. S values (message, message type, user options, etc.) to the `JOptionPane` constructor, and then derive a di end up with the same option dialog.

Next, you create a `DialogEarthquakeCenter` from that dialog. Then you can return to the dialog, `pack ( )` with the `JOptionPane` dialog is that it is modal, meaning it will block the AWT event-dispatch thread wher `DialogEarthquakeCenter` won't get any animation callbacks from `Timer` . To get around this, I just made 1 isn't going to be able to click it when it's moving. Another option might be for the `DialogEarthquakeCente` and to reset this state in `stopShake ( )`.

Unfortunately, there's not a great way to show the effect of this animation in book form. The best I can yourself. While you're at it, change some of the constant values to see the effect of longer or shorter sh.

## Hack 39. Spin Open a Detail Pane



You don't want to bombard the user with details, but you don't want to hide them either. Here's a way to let the user pop open a More Info widget .

You have to be careful not to weigh down your GUIs with so much information that the user can't see what really matters. On the other hand, there are times that the user may want more information than is obvious on one screen or panel. A simple way of dealing with this is to put a More Info button that pops up a new window. That leads to the annoyance of having too many windows on the screen, none associated in any way with their source.

Mac OS X has a nice idea: the spin open disclosure widget. It works like this: you have a component of some sort perhaps a simple label or a complex panel with a triangle-shaped spinner below it. When the user clicks the spinner, a whole new widget opens up below the spinner, offering more information. In fact, the new widget can have significant functionality: to set file permissions from the Finder, you open a Get Info window and spin open an Ownership and Permissions section to set your own access (if you own the file), and a second Details spinner lets you set access levels for the owner, group, and others.

### 5.8.1. The Invisible Man

This hack is fairly simple and relies on one fact: you can add a component to a layout and alternately make it visible and invisible. Its position relative to other components is preserved when it's invisible, but it takes up no onscreen space. So, a spin-open container consists of three components:

- The top component, which is always visible
- The spinner
- The bottom component, whose visibility can be set by clicking on the spinner

The layout of these three is pretty straightforward, as seen in Example 5-6, which lists the `MoreInfoPanel` class but omits an inner class (for now).

#### Example 5-6. Laying out the three panel components

```
public class MoreInfoPanel extends JPanel {

    public Component topComponent;
    protected SpinWidget spinWidget;
    public Component bottomComponent;
```

```

public static final int SPIN_WIDGET_HEIGHT = 14;

public MoreInfoPanel (Component tc, Component mic) {
    topComponent = tc;
    spinWidget = new SpinWidget( );
    bottomComponent = mic;
    doMyLayout( );
}

protected void doMyLayout( ) {
    setLayout (new BorderLayout (this, BorderLayout.Y_AXIS));
    add (topComponent);
    add (spinWidget);
    add (bottomComponent);
    resetBottomVisibility( );
}

protected void resetBottomVisibility( ) {
    if ((bottomComponent == null) ||
        (spinWidget == null))
        return;
    bottomComponent.setVisible (spinWidget.isOpen( ));
    revalidate( );
    if (isShowing( )) {
        Container ancestor = getTopLevelAncestor( );
        if ((ancestor != null) && (ancestor instanceof Window))
            ((Window) ancestor).pack( );
    }
    repaint( );
}

public void showBottom (boolean b) {
    spinWidget.setOpen (b);
}

public boolean isBottomShowing ( ) {
    return spinWidget.isOpen( );
}
// See below for SpinWidget inner class
}

```

The constructor simply assigns the top and bottom `Component` s to local variables, creates a `SpinWidget` (see Example 5-7), and calls `doMyLayout ( )`. The latter method puts the components into a vertical `BoxLayout` and calls the convenience method `resetBottomVisibility ( )`.

`resetBottomVisibility ( )` is responsible for setting the visibility of the bottom component based on whether the `SpinWidget` is currently open or closed. It then finds and re-`pack ( )`s its parent `Window`, so that if the bottom component is wider than the top, the enclosing window will resize to fit the now-visible contents. Of course, this behavior might not be appropriate in some cases: you might put a `MoreInfoPanel` in a complex GUI and not want to re-`pack ( )` the parent `Window`. Imagine an IDE in

which you browse items in a list or tree on the left, and show varying levels of detail on the right with nested `MoreInfoPanels`. The right pane might want to get sizing-related events when its child `MoreInfoPanel`s change sizes, but it wouldn't be appropriate for them to try to resize the entire `JFrame`. This might call for hacking the hack to set up an event-listener system, so that you could deliver sizing related events to a specific parent.

Now for the `SpinWidget`, shown in Example 5-7. I wrote this as a custom `JPanel` that draws the triangles with graphics primitives. This has the advantage of being self-contained, but if you'd rather just use a `JButton` with hand-drawn triangle GIFs, go for it.

### Example 5-7. Inner class spin triangle

```
public class SpinWidget extends JPanel {
    boolean open;
    Dimension mySize = new Dimension (SPIN_WIDGET_HEIGHT,
                                      SPIN_WIDGET_HEIGHT);

    final int HALF_HEIGHT = SPIN_WIDGET_HEIGHT / 2;
    int[] openXPoints =
        { 1, HALF_HEIGHT, SPIN_WIDGET_HEIGHT-1};

    int[] openYPoints =
        { HALF_HEIGHT, SPIN_WIDGET_HEIGHT-1, HALF_HEIGHT};
    int[] closedXPoints =
        { 1, 1, HALF_HEIGHT};
    int[] closedYPoints =
        { 1, SPIN_WIDGET_HEIGHT-1, HALF_HEIGHT };
    Polygon openTriangle =
        new Polygon (openXPoints, openYPoints, 3);
    Polygon closedTriangle =
        new Polygon (closedXPoints, closedYPoints, 3);

    public SpinWidget( ) {
        setOpen (false);
        addMouseListener (new MouseAdapter( ) {

            public void mouseClicked (MouseEvent e) {
                handleClick( );
            }
        });
    }

    public void handleClick( ) {
        setOpen (! isOpen( ));
    }

    public boolean isOpen( ) {
        return open;
    }

    public void setOpen (boolean o) {
```

```

        open = o;
        resetBottomVisibility( );
    }

    public Dimension getMinimumSize( ) { return mySize; }
    public Dimension getPreferredSize( ) { return mySize; }

    // don't override update( ), get the default clear
    public void paint (Graphics g) {
        if (isOpen( ))
            g.fillPolygon (openTriangle);
        else
            g.fillPolygon (closedTriangle);
    }
}

```

As you can see, the code does some work to create the points for the two triangle polygons, which are used in the `paint ( )` method. Other than that, it's a simple state machine with two boolean states: when it gets a click, it switches states. The call to `setOpen ( )` calls the enclosing class's `resetButtonVisibility ( )`, which will make the bottom component visible.

## 5.8.2. Now You See Me

To show a non-trivial use of the `MoreInfoPanel`, the `TestMoreInfoPanel` class shown in Example 5-8 creates a `JOptionPane` dialog, hijacks its content pane, and puts that into a `MoreInfoPanel` as the top component. The bottom component is a `JTextArea` with a more detailed (or obnoxious, in this case) description of the warning in the dialog. This `MoreInfoPanel` is then reset as the dialog's content pane. The initial result looks like Figure 5-9.

Figure 5-9. A Warning dialog with a closed `MoreInfoPanel`

## Example 5-8. A spin-open dialog using a `MoreInfoPanel`

```

import java.awt.*;
import javax.swing.*;

```

```

public class TestMoreInfoPanel {


    public static void main (String[] args) {
        JOptionPane pane =
            new JOptionPane ("The action you have chosen to perform\n is " +
                "not recommended.", JOptionPane.WARNING_MESSAGE);
        JDialog dialog = pane.createDialog (null, "Warning");
        Container grabbedContent = dialog.getContentPane( );
        JTextArea area =
            new JTextArea ("No, seriously dude, you are about to totally "+
                "bake your computer, if not your entire " +
                "network, if you don't bail right now. Think " +
                "I'm kidding? Would I go to such lengths to " +
                "provide such an elaborate warning message if " +
                "I were kidding? No, no, wait... you know " +
                "what? Go ahead. Click OK and blow everything " +
                "to kingdom come. See if I care.",
                5, 40);
        area.setLineWrap (true);
        area.setWrapStyleWord (true);

        JScrollPane scroller =
            new JScrollPane (area,
                ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
                ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
        MoreInfoPanel mip = new MoreInfoPanel (grabbedContent, scroller);
        dialog.setContentPane (mip);
        dialog.pack( );
        dialog.setVisible(true);
        // dialog blocks on setVisible (JOptionPane makes it modal)
        System.exit(0);
    }
}

```

When the user clicks the triangle at the bottom left, the More Info text area appears, as seen in Figure 5-10 .

Figure 5-10. The Warning dialog after opening the MoreInfoPanel



← PREV

## Hack 40. Minimize to a Mini-Frame



When you want your program to have a smaller window but still be on the screen, try building a mini-mod.

Since the advent of iTunes, it seems that all consumer-oriented applications must have meticulous interfaces that can dynamically adjust themselves. Gone are the days of simply minimizing an application. Now your program must have a small version rather than (or in addition to) hiding when minimized. The smaller version contains limited controls but can fit nicely at the bottom of the screen. This hack shows how to create a dynamic frame that can switch properly between sizes for a more modern-looking interface.

### 5.9.1. I Shall Call Him...Mini-Me

Switching a frame between two sizes is quite easy: just call `setSize()` and you're done. Doing it well is a bit more difficult, however. When you minimize the window, you also need to remove the window decorations, hide the menu bar, and remove the components that shouldn't be visible in the mini-view. This is a bit trickier, not the least of which because you can't turn off the window decorations of a frame once it has been created. But I'm getting ahead of myself. First, you need a sample application.

Let's take a simple clock program. The normal window looks like [Figure 5-11](#). The goal is to provide a mini version that looks like [Figure 5-12](#).

Figure 5-11. A normal application window





Figure 5-12. A mini application window

This program has a clock, a panel with more configuration options (represented here with just the label More configuration), a menu bar, and a pop-up menu for later use. [Example 5-9](#) creates the interface and puts the components in the right places, but it doesn't do anything with them yet.

### Example 5-9. The beginning of a clock with a mini version

```
public class MiniMizeHack implements MouseListener, ActionListener {

    public JFrame frame;
    public JPanel panel;
    public JPopupMenu popup;

    public JMenuBar menubar;
    public JLabel top;
    public JLabel bottom;

    public MiniMizeHack( ) {
        top = new JLabel(new ImageIcon("image.png"));
        bottom = new JLabel("More configuration here");

        frame = new JFrame("Mini Mize Hack");
        panel = new JPanel( );
        panel.setLayout(new BorderLayout( ));
        panel.add("Center",bottom);
        panel.add("North",top);
    }
}
```

```

        frame.getContentPane( ).add(panel);

        menubar = new JMenuBar( );
        JMenu menu = new JMenu("File");
        menu.add(new JMenuItem("Open"));
        menu.add(new JMenuItem("Quit"));
        menubar.add(menu);

        JMenu window = new JMenu("Window");
        JMenuItem mini = new JMenuItem("Minimize");
        mini.addActionListener(this);
        window.add(mini);
        menubar.add(window);
        frame.setJMenuBar(menubar);

        popup = new JPopupMenu( );
        JMenuItem restore = new JMenuItem("Restore");
        restore.addActionListener(this);
        popup.add(restore);
    }

    public void mousePressed(MouseEvent e) {
        maybeShowPopup(e);
    }

    public void mouseReleased(MouseEvent e) {
        maybeShowPopup(e);
    }

    public void mouseExited(MouseEvent e) { }
    public void mouseEntered(MouseEvent e) { }
    public void mouseClicked(MouseEvent e) { }
    private void maybeShowPopup(MouseEvent e) {
        if (e.isPopupTrigger( )) {
            popup.show(e.getComponent( ),
                e.getX( ), e.getY( ));
        }
    }
}

```

The code declares a `MiniMizeHack` class, which creates the UI and adds itself as an `ActionListener` to the Minimize and Restore menu items. The mouse listener implementation is there to control the pop up menu, but because the `MiniMizeHack` class hasn't been added as a listener to any components, the pop up won't do anything yet.

## 5.9.2. Minimize the Frame

The `actionPerformed( )` method does the actual switching. This is the meat of the hack. It tests if the bottom component is visible. If the component is visible, then this method calls `switchToMini( )` and reshapes the frame to be smaller. If the bottom component is *not* visible, then `actionPerformed( )`

calls `switchToNormal()` to reverse the changes:

```
public void actionPerformed(ActionEvent evt) {
    if(bottom.isVisible()) {
        switchToMini();
    } else {
        switchToNormal();
    }
}
```

The magic happens in the `switchToMini()` method. A big part of a mini window is that it doesn't have any borders, or at the least it uses custom ones. Swing does not let you turn off a frame's borders and window decorations after the frame has been shown on screen because it might have already allocated immutable system resources. The only way around this limitation is to seamlessly replace the old frame with a new one:

```
private Dimension normal_size;
public void switchToMini() {
    // nuke the old frame and build a new one
    Point location = frame.getLocation();
    normal_size = frame.getSize();
    frame.setVisible(false);
    frame = new JFrame();
    frame.setUndecorated(true);
    frame.getContentPane().add(panel);
}
```

The `switchToMini()` method starts by saving the current frame location and size, and then hides the frame and replaces it with a new one. Now, it can safely call `setUndecorated(true)` on the frame. The `frame.getContentPane().add(panel)` line will add the main panel to the new frame. It is not necessary to remove the panel from the old frame because Swing will take care of it automatically. There is also no need to remove the menu bar because it had never been added to the new frame.

Now, the code can hide the bottom component (the label representing the extra clock configuration) and add the mouse listener to activate the pop up on right-clicks. If you are using Java 5.0, you can add another line to make the frame always be on top. This can be annoying to some users, however, so a real program would have a preference to control that feature:

```
// hide the extra components
bottom.hide();

// add the pop up
panel.addMouseListener(this);

// stay on top
frame.setAlwaysOnTop(true);
```

```
// show the frame again
frame.pack( );
frame.setLocation(location);
frame.setVisible(true);
```

With the frame prepared, the code packs it, gives it the location of the original frame, and makes it visible again.

### 5.9.3. Restore the Frame

When the user triggers the pop-up menu and selects Normal, the `switchToNormal()` method will be called. This method reverses what the `switchToMini()` method did:

```
public void switchToNormal( ) {
    // nuke the old frame and build a new one
    Point location = frame.getLocation( );
    frame.setVisible(false);
    frame = new JFrame( );
    frame.setUndecorated(false);
    frame.getContentPane( ).add(panel);

    // show the extra components
    bottom.show( );
    frame.setJMenuBar(menubar);

    // hide the pop up
    panel.removeMouseListener(this);

    // turn off stay on top
    frame.setAlwaysOnTop(false);

    // show the frame again
    frame.pack( );
    frame.setSize(normal_size);
    frame.setLocation(location);
    frame.setVisible(true);
}
```

`switchToNormal()` will first save the location of the frame, hide the frame, and replace it with a new, fully decorated one. It then turns the menu bar and bottom component back on, removes the pop-up listener, turns off Always on Top (only for Java 5.0), and restores the frame.

To launch the application, you need to add only `amain()` method to create a mini and show it on screen:

```
public static void main(String[] args) {  
    MiniMizeHack mini = new MiniMizeHack( );  
    mini.frame.pack( );  
    mini.frame.setSize(300,300);  
    mini.frame.setVisible(true);  
}
```

Swing doesn't do everything by default, but it makes a lot of things possible. This hack showed how to create the sort of dynamic frame actions that users expect today. One enhancement you would probably want to add is the draggable background [\[Hack #34\]](#) because a window without a titlebar may be difficult to move by itself. You might also want to use small buttons instead of a pop-up menu to control the toggling since most users will be familiar with the min, max, and close buttons.

[← PREV](#)

← PREY

# Chapter 6. Transparent and Animated Windows

← PREY

[← PREV](#)

## 6.1. Hacks 4147: Introduction

In the previous chapter, our window hacks generally played by the rules we simulated the earthquake dialog [\[Hack #38\]](#) by animating calls to `setLocation()`, and switched to a mini-size window [\[Hack #40\]](#) by calling `setSize()` and removing some window decorations.

This chapter's hacks approach from outside the Window API per se, by hacking the windows with Java 2D, stuffing things into the glass pane of a `JDialog` or `JFrame`, and more. Some of them are practical, some are just pretty, but all of these hacks offer something unexpected.

[← PREV](#)

## Hack 41. Transparent Windows



Create translucent and shaped windows, while avoiding native code, with clever use of a screenshot.

One of the most commonly requested Swing features is transparent windows. Also called *shaped windows*, these are windows that have transparent portions, allowing the desktop background and other programs to shine through. Java doesn't provide any way of creating transparent windows without using the Java Native Interface (JNI) (and even then the native platform must support transparency as well), but that's not going to stop us. We can cheat using one of my favorite techniques, the screenshot.

The process of faking a transparent window is basically:

1. Take a screenshot before the window is shown.
2. Use that screenshot as the background of the window.
3. Adjust the position so that the screenshot and the real screen line up, creating the illusion of transparency.

This is the easy part. The hard part is updating the screenshot when the window moves or changes.

To start off, create a `JPanel` subclass that can capture the screen and paint it as the background, as shown in [Example 6-1](#).

### Example 6-1. A transparent background component

```
public class TransparentBackground extends JComponent {
    private JFrame frame;
    private Image background;

    public TransparentBackground(JFrame frame) {
        this.frame = frame;
        updateBackground( );
    }

    public void updateBackground( ) {
        try {
            Robot rbt = new Robot( );
```



```

Toolkit tk = Toolkit.getDefaultToolkit( );
Dimension dim = tk.getScreenSize( );
background = rbt.createScreenCapture(
    new Rectangle(0,0,(int)dim.getWidth( ),
                 (int)dim.getHeight( )));
} catch (Exception ex) {
    p(ex.toString( ));
    ex.printStackTrace( );
}
}
public void paintComponent(Graphics g) {
    Point pos = this.getLocationOnScreen( );
    Point offset = new Point(-pos.x,-pos.y);
    g.drawImage(background,offset.x,offset.y,null);
}
}

```

First, the constructor saves a reference to the parent `JFrame`; then it calls `updateBackground()`, which captures the entire screen using `java.awt.Robot.createScreenCapture()`, and saves the capture in the `background` variable. `paintComponent()` gets the panel's absolute position on screen and then fills the panel with the background image, shifted to account for the panel's location. This makes the fake background image line up with the real background, giving the appearance of transparency.

You can run this with a simple `main()` method, dropping a few components onto the panel and putting it into a frame:


```

public static void main(String[] args) {
    JFrame frame = new JFrame("Transparent Window");
    TransparentBackground bg = new TransparentBackground(frame);
    bg.setLayout(new BorderLayout( ));
    JButton button = new JButton("This is a button");
    bg.add("North",button);
    JLabel label = new JLabel("This is a label");
    bg.add("South",label);
    frame.getContentPane( ).add("Center",bg);
    frame.pack( );
    frame.setSize(150,100);
    frame.show( );
}

```

The code produces a window that looks like [Figure 6-1](#).

Figure 6-1. Transparent windows in action



The code is pretty simple, but it has two big flaws. First, if the window is moved, the background won't be refreshed automatically. `paintComponent()` only gets called when the user resizes the window. Second, if the screen ever changes, it won't match up with the background anymore.

You really don't want to update the screenshot often, though, because that involves hiding the window, taking a new screenshot, and then reshaping the window of which is disconcerting to the user. Actually detecting when the rest of the desktop changes is almost impossible, but most changes happen when the foreground window changes focus or moves. If you accept this idea (and I do), then you can watch for those events and only update the screenshot when that happens:

```
public class TransparentBackground extends JComponent
    implements ComponentListener, WindowFocusListener,
    Runnable {
    private JFrame frame;
    private Image background;
    private long lastupdate = 0;
    public boolean refreshRequested = true;
    public TransparentBackground(JFrame frame) {
        this.frame = frame;
        updateBackground( );
        frame.addComponentListener(this);
        frame.addWindowFocusListener(this);
        new Thread(this).start( );
    }
    public void componentShown(ComponentEvent evt) { repaint( ); }
    public void componentResized(ComponentEvent evt) { repaint( ); }
    public void componentMoved(ComponentEvent evt) { repaint( ); }
    public void componentHidden(ComponentEvent evt) { }

    public void windowGainedFocus(WindowEvent evt) { refresh( ); }
    public void windowLostFocus(WindowEvent evt) { refresh( ); }
```

First, make the panel, `transparentWindow`, implement `ComponentListener`, `WindowFocusListener`, and `Runnable`. The listener interfaces will let the panel catch events indicating that the window has moved, been resized, or the focus changes. Implementing `Runnable` will let the panel create a thread to handle custom `repaint()`s.

The implementation of `ComponentListener` involves the four methods beginning with `component`. They each simply call `repaint()` so that the background will be updated whenever the user moves or resizes the window. Next are the two window focus handlers, which just call `refresh()`, as shown here:

```
public void refresh( ) {
    if(frame.isVisible( )) {
        repaint( );
        refreshRequested = true;
        lastupdate = new Date( ).getTime( );
    }
}
public void run( ) {
    try {
        while(true) {
            Thread.sleep(250);
            long now = new Date( ).getTime( );
            if(refreshRequested &&
                ((now - lastupdate) > 1000)) {
                if(frame.isVisible( )) {
                    Point location = frame.getLocation( );
                    frame.hide( );
                    updateBackground( );
                    frame.show( );
                    frame.setLocation(location);
                    refresh( );
                }
                lastupdate = now;
                refreshRequested = false;
            }
        }
    } catch (Exception ex) {
        p(ex.toString( ));
        ex.printStackTrace( );
    }
}
```

`refresh()` ensures that the frame is visible and schedules a repaint. It also sets the `refreshRequested` boolean to true and saves the current time, which will become very important shortly.

The `run()` method sleeps constantly, waking up every quarter-second to see if a refresh has been requested, and whether it has been more than a second since the last refresh. If more than a second has passed and the frame is actually visible, then `run()` will save the frame location, hide it, update

the background, then put the frame back in place and call `refresh()`. This ensures that the background is never updated more than needed.

So, why all of this rigmarole about using a thread to control refreshing? One word: recursion. The event handlers could simply call `updateBackground()` and `repaint()` directly, but hiding and showing the window to generate the screenshot would cause more focus-changed events. These would then trigger another background update, causing the window to hide again, and so on, creating an infinite loop. The new focus events are generated a few milliseconds after `refresh()` is processed, so simply checking for an `isRecurring` flag wouldn't stop a loop.

Additionally, any user action that would change the screen will probably create lots of events, not just one. It's just the *last* event that should trigger `updateBackground()`, not the first. To handle all these issues, the code creates a thread that watches for repaint requests and only processes a new screenshot if it hasn't already been done in the last 1,000 milliseconds. If the user generates events continuously for five seconds (searching for that lost browser window, for example), then only when everything else has settled down for a second will the refresh actually happen. This ensures that users won't have a window disappear out from under them while they are moving things around.

Another annoyance is that the window still has its border, which sort of ruins the effect of having a transparent background. Unfortunately, removing the borders with `setUndecorated(true)` would also remove the titlebar and window controls. This probably isn't too much of a problem, though, because the types of applications that typically use shaped windows usually have draggable backgrounds [\[Hack #34\]](#).

Here's a simple test program to put this into action:

```
public static void main(String[] args) {
    JFrame frame = new JFrame("Transparent Window");
    frame.setUndecorated(true);

    TransparentBackground bg = new TransparentBackground(frame);
    bg.snapBackground();
    bg.setLayout(new BorderLayout());

    JPanel panel = new JPanel() {
        public void paintComponent(Graphics g) {
            g.setColor(Color.blue);
            Image img = new ImageIcon("mp3.png").getImage();
            g.drawImage(img, 0, 0, null);
        }
    };
    panel.setOpaque(false);

    bg.add("Center", panel);

    frame.getContentPane().add("Center", bg);
    frame.pack();
    frame.setSize(200, 200);
    frame.setLocation(500, 500);
    frame.show();
}
```

The code creates a faux MP3 player interface using a `JPanel` subclass and a PNG image with transparency. Note the call to `frame.setUndecorated(true)`, which turns off the border and titlebar. The call to `panel.setOpaque(false)` turns off the default background (usually plain gray), allowing the screenshot background to shine through the transparent parts of the image ([Figure 6-2](#)). This produces a window that looks like [Figure 6-3](#) a vision of Java programs to come?

Figure 6-2. Template for an MP3 player

Figure 6-3. Running the MP3 player

## Hack 42. Make Your Frame Dissolve



Create animated frame dissolves using two screenshots and some clever graphics code.

Dissolve is a term from old motion pictures where the director would switch scenes by fading, or *dissolving*, from one image to another. Eventually directors came up with more interesting dissolves like the vertical wipe, the venetian effect (little thin strips that look like venetian blinds), and the classic fade to black. With a little bit of screenshot hackery, you can create similar effects in Swing, allowing your program to fade away or do some other interesting animation when the user quits.

AWT doesn't support real transparent or shaped windows (though you can fake it with a screenshot pasted into a window that fills the screen [\[Hack #41\]](#)). Most dissolves involve applying some graphic effect to both the starting and ending images, which in this case means the application window itself and the rest of the user's desktop under the window. With this in mind, the basic plan is four steps:

1. Capture an image of the window.
2. Capture an image of the entire screen *without* the window.
3. Cover up the entire screen with a new window.
4. Show the dissolve animation.

To keep this simple, I have created a special class that does a simple fade-to-transparent animation. Once the class is built, you can create more complicated animations by overriding the paint method, leaving the messy details to the parent class. Here's the basic skeleton:

```
class Dissolver extends JComponent implements Runnable {
    Frame frame;
    Window fullscreen;
    int count;
    BufferedImage frame_buffer;
    BufferedImage screen_buffer;

    public Dissolver( ) { }
```

`Dissolver` is a `JComponent` that implements `Runnable` so that it can have an animation loop. It has member variables for the application frame to dissolve (`frame`), the window that covers up the screen (`fullscreen`), an animation counter (`count`), and the two buffers for storing the frame and the desktop background image (`frame_buffer` and `screen_buffer`).

## 6.3.1. Prepare the Dissolve

`Dissolver` has one method to start the dissolve process called `dissolveExit()`, which takes the `JFrame` you want to dissolve and generates everything else it needs internally:

```
public void dissolveExit(JFrame frame) {
    try {
        this.frame = frame;
        Robot robot = new Robot( );

        // cap screen w/ frame to frame buffer
        Rectangle frame_rect = frame.getBounds( );
        frame_buffer = robot.createScreenCapture(frame_rect);

        // hide frame
        frame.setVisible(false);

        // cap screen w/o frame
        Dimension screensize = Toolkit.getDefaultToolkit( )
            .getScreenSize( );
        Rectangle screen_rect = new Rectangle(0,0,
            screensize.width, screensize.height);
        screen_buffer = robot.createScreenCapture(screen_rect);

        // create big window w/o decorations
        fullscreen = new Window(new JFrame( ));
        fullscreen.setSize(screensize);
        fullscreen.add(this);
        this.setSize(screensize);
        fullscreen.setVisible(true);

        // start animation
        new Thread(this).start( );
    } catch (Exception ex) {
        System.out.println(ex);
        ex.printStackTrace( );
    }
}
```

`dissolveExit()` saves a reference to the frame and creates a new `java.awt.Robot` to handle the screen captures. Then it captures just the area of the screen containing the frame by calling `robot.createScreenCapture()`, using the rectangle returned by `frame.getBounds()`. After making this screen capture, it hides the frame and then captures the entire screen into the second buffer. Finally, it creates a new `Window` that covers the entire screen, adds the `Dissolver` as the window's only child, and starts the animation on a new thread.

There are two tricky things to look out for here. First, the code uses `aWindow` instead of a `JFrame` so that the window won't show up in a task list or the dock. This also means it won't have any window decorations that would ruin the illusion of transparency. Second, the `Window` constructor requires you to pass in another window or frame. This is because every window is attached to a parent window and will only be visible when the parent is (on certain platforms). Using the existing application frame won't work because it's just been hidden, but if you create a new, empty `JFrame`, the window will show up fine.

### 6.3.2. Run the Animation

`dissolveExit()` creates a new thread around the `run()` method (see the following code). This method will request a repaint on the component every 100 milliseconds, looping 20 times and then quitting. This will create a two-second dissolve animation, but you can certainly tweak these values to your own tastes:

```
public void run( ) {
    try {
        count = 0;
        Thread.currentThread( ).sleep(100);
        for(int i=0; i<20; i++) {
            count = i;
            fullscreen.repaint( );
            Thread.currentThread( ).sleep(100);
        }
    } catch (InterruptedException ex) { }
    System.exit(0);
}
```

### 6.3.3. Do the Drawing

Now that the component will be repainted for each frame of the animation, you can finally do some drawing. Fading to nothing is really easy with Swing. You just need to draw the background image first, and then draw the frame on top using a `Composite`. A `Composite` is a class that knows to adjust the standard mechanism in some way. An `AlphaComposite` will draw partially transparent images depending on the alpha value you pass in. An alpha value of 1 will draw the image fully opaque, while a value of 0 will be completely transparent. Values between 1 and 0 will draw the image partially transparent. Always be sure to save the old composite so you can return the `Graphics` object to its original state when you are done:

```
public void paint(Graphics g) {
    Graphics2D g2 = (Graphics2D)g;
    // draw the screen, offset in case the window isn't at 0,0
    g.drawImage(screen_buffer, -fullscreen.getX( ),
        -fullscreen.getY( ), null);
}
```



```

// draw the frame
Composite old_comp = g2.getComposite( );
Composite fade = AlphaComposite.getInstance(
    AlphaComposite.SRC_OVER,1.0f-((float)count)/20f);
g2.setComposite(fade);
g2.drawImage(frame_buffer,frame.getX( ),frame.getY( ),null);
g2.setComposite(old_comp);
}

```

The class in [Example 6-2](#) creates a frame with one button called `quit`. When you press the Quit button, the dissolve will be activated, fading the window into nothing and then calling `System.exit( )`. If you compile and run the code, it will look something like [Figure 6-4](#).

Figure 6-4. A fade dissolve



### Example 6-2. A simple test class

```

public class DissolveHack {

    public static void main(String[] args) {

        final JFrame frame = new JFrame("Dissolve Hack");
        JButton quit = new JButton("Quit");
        quit.addActionListener(new ActionListener( ) {
            public void actionPerformed(ActionEvent evt) {
                new Dissolver( ).dissolveExit(frame);
            }
        });

        frame.getContentPane( ).add(quit);
        frame.pack( );
        frame.setLocation(300,300);
        frame.setSize(400,400);
        frame.setVisible(true);
    }
}

```

```
}
}
```

### 6.3.4. Create a Genie Effect

One of my favorite bits of eye candy from Mac OS X is the minimize dissolve. When you click on the minimize button in any application, the window will shrink and slide into the dock. This is called the genie effect, and it not only looks cool, but it also gives you feedback about where a window has gone. [Example 6-3](#) is a subclass of `Dissolver` that overrides the `paint()` method to create a spinning, shrinking window that somewhat mimics the genie effect.

#### Example 6-3. Adding a genie effect to your toolbox

```
class SpinDissolver extends Dissolver {

public void paint(Graphics g) {
    Graphics2D g2 = (Graphics2D)g;
    // draw the screen, offset in case the window isn't at 0,0
    g.drawImage(screen_buffer,-fullscreen.getX( ),
        -fullscreen.getY( ),null);

    // save the current transform
    AffineTransform old_trans = g2.getTransform( );

    // move to the upper-lefthand corner of the frame
    g2.translate(frame.getX( ), frame.getY( ));

    // move the frame off toward the left
    g2.translate(-((count+1) * (frame.getX( )+frame.getWidth( ))/20),0);

    // shrink the frame
    float scale = 1f / ((float)count+1);
    g2.scale(scale,scale);

    // rotate around the center
    g2.rotate(((float)count)/3.14/1.3,
        frame.getWidth( )/2, frame.getHeight( )/2);

    // finally draw the frame
    g2.drawImage(frame_buffer,0,0,null);

    // restore the current transform
    g2.setTransform(old_trans);
}
}
```

This dissolver will shrink the window and spin it, while moving it toward the left at the same time. This make the window look like it is spinning off into oblivion, as in [Figure 6-5](#).

### Figure 6-5. A spin dissolve

This hack shows off just a few of the really cool effects you can accomplish with just a bit of Java2D code in your Swing application. Because the parent `Dissolve` class takes care of most of the tricky parts, you can easily create your own subclasses that focus on just the animation itself. You might want to try some other animations, such as the circle and linear wipes common to old movies, or a better genie effect that works when you quit your application. Java2D gives you the power to do virtually any linear transform (shear, scale, rotate, etc.), plus composites and convolutions. For even more effects, you could use Java3D or JOGL to create three-dimensional effects like spinning cubes and perspective transforms.

## Hack 43. Create Custom Tool Tips



Replace the standard rollover tool tip with an attractive custom version, including a border and rounded corners.

Every Swing component can have a *tool tip*, a little snippet of explanatory text that pops up when you let your mouse cursor linger over the component. These tool tips are often useful, but they usually look quite boring. This hack shows how to create visually interesting tool tips with a custom subclass.

In Swing, all tool tips are instances of the `JToolTip` class. To create your own version, you need only subclass `JToolTip` and override the `paintComponent()` method. In this hack, we'll create a tool tip with a rectangle that has a beveled border and a white background. The actual drawing can be taken care of with a few Java2D drawing commands. [Example 6-4](#) is the code to draw the tool tip's background and border.

### Example 6-4. A nice-looking tool tip

```
class CustomToolTip extends JToolTip {

    public void paintComponent(Graphics g) {

        // create a round rectangle
        Shape round = new RoundRectangle2D.Float(4,4,
            this.getWidth()-1-8,
            this.getHeight()-1-8,
            15,15);

        // draw the white background
        Graphics2D g2 = (Graphics2D)g;
        g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
            RenderingHints.VALUE_ANTIALIAS_ON);
        g2.setColor(Color.white);
        g2.fill(round);

        // draw the gray border
        g2.setColor(Color.gray);
        g2.setStroke(new BasicStroke(5));
        g2.draw(round);
        g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
```

```

    RenderingHints.VALUE_ANTIALIAS_DEFAULT);

// draw the text
String text = this.getComponent( ).getToolTipText( );
if(text != null) {
    FontMetrics fm = g2.getFontMetrics( );
    int h = fm.getAscent( );
g2.setColor(Color.black);
    g2.drawString(text,10,(this.getHeight( )+h)/2);
}
}

```

This code creates a round rectangle shape that is then reused to draw the background and border. Notice that anti-aliasing is turned on for drawing the shape, but it's turned back to the default (which could be on or off) before drawing the text. It would look strange to have anti-aliased text if the rest of the interface was still using standard aliased text using the default is a safer idea.

Because this tool tip needs extra space around the text to draw the border, you will need to modify the tool tip's preferred size. The `getPreferredSize( )` method here adds an extra 20 pixels in each direction:

```

public Dimension getPreferredSize( ) {
    Dimension dim = super.getPreferredSize( );
    return new Dimension((int)dim.getWidth( )+20,
        (int)dim.getHeight( )+20);
}

```

The tool tip has rounded corners, but with the code as it stands, you would still see the slivers of gray that fill out the component's real corners. In order to hide the gray and let the components below shine through, you need to make the tool tip transparent. You can do this by setting `opaque` to `false` in the tool tip's constructor. The tool tip component is not a direct child of the frame that contains the tool tip. There is another component between the tool tip and the frame that will be visible even if the tool tip is transparent. You can make this extra component transparent with an additional `setOpaque(false)` call on the tool tip's parent at the start of the `paintComponent( )` method:

```

public CustomToolTip( ) {
    super( );
    // make the tool tip not fill in its background
    this.setOpaque(false);
}
public void paintComponent(Graphics g) {

// set the parent to not be opaque
Component parent = this.getParent( );
if(parent != null) {
    if(parent instanceof JComponent) {

```

```

    JComponent jparent = (JComponent)parent;
    if(jparent.isOpaque( )) {
jparent.setOpaque(false);
    }
}
}
// ... the rest of the drawing code

```

### 6.4.1. Install the Tool Tip

To install the custom tool tip, you need to override the `createToolTip( )` method of the component you wish to modify. An example using a custom `JButton` is shown in [Example 6-5](#).

#### Example 6-5. Installing a custom tool tip

```

class CustomJButton extends JButton {
    JToolTip _tooltip;

    public CustomJButton( ) {
        _tooltip = new CustomToolTip( );
        _tooltip.setComponent(this);
    }

    public JToolTip createToolTip( ) {
        return _tooltip;
    }
}

```

Because the tool tip is specified by the custom `JButton` class, all you need to do is create some components and set their tool tip text. The code in [Example 6-6](#) creates two buttons and three labels in a frame. The buttons have custom tool tips that will display complete with the now transparent corners on top of the rest of the screen, as shown in [Figure 6-6](#).

Figure 6-6. A tool tip with a custom border



## Example 6-6. Testing out custom tool tips

```

public class ToolTipsHack {

    public static void main(String[] args) {
        JButton button;

        JFrame frame = new JFrame("Tool Tips Hack");
        BorderLayout layout = new BorderLayout(
            frame.getContentPane( ),
            BorderLayout.Y_AXIS);
        frame.getContentPane( ).setLayout(layout);

        button = new CustomJButton( );
        button.setText("Open");
        button.setToolTipText("Open an existing file");
        frame.getContentPane( ).add(button);

        button = new CustomJButton( );
        button.setText("Save");
        button.setToolTipText("Save the currently open file");
        frame.getContentPane( ).add(button);

        frame.getContentPane( ).add(new JLabel("a label"));
        frame.getContentPane( ).add(new JLabel("a label"));
        frame.getContentPane( ).add(new JLabel("a label"));

        frame.pack( );
        frame.show( );
    }
}

```

## Hack 44. Turn Dialogs into Frame-Anchored Sheets



One of Mac OS X's best ideas is binding the dialog to the window it blocks. This hack shows you how to mimic this in Swing.

One of my favorite features in Mac OS X is the *sheet*. This is a dialog box replacement that slides down from a window's titlebar. [Figure 6-7](#) shows an example of a sheet in Apple's Safari web browser.

### 6.5.1. Why Sheets Rock

Looking at it, you might think, "what's the big deal" or "how is this any different than a regular dialog?" Oh, it's far better:

*A sheet is visually anchored to the window that it blocks*

On platforms where dialogs have titlebars and close boxes, the relationship between a dialog and the window it blocks is not necessarily intuitive. On a related point...

Figure 6-7. Sheet in Mac OS X Safari browser

*A sheet doesn't have a close box*



Dialog close boxes are one of the most hateful and stupid concepts in Windows and its many Linux imitators. What does the close box mean? Cancel? The default option? What does it mean when the dialog has multiple options of equal plausibility and thus no default? Perhaps the worst thing about the close box was back in the AWT era when Java developers were too lazy to add and wire-up an OK button to their dialogs just figured users could dismiss the dialog with the close box. Mac OS 8 and 9 dialogs didn't have close boxes, so when a Java application brought up such a dialog, *the application blocked itself forever*. Duh. Sheets mean having to click one of the provided buttons, so the user's choices are unambiguous.

*A sheet is used to block one window*

This is an obvious side effect of being visually tied to a single window, but that's probably the most common case. As a side effect, this gives greater prominence to dialogs that block all windows for a single application ("Are you sure you want to Quit and lose all unsaved changes in all documents?") and dialogs that block all applications ("Are you sure you want to Shut Down?").

So, if you agree that it's an excellent GUI concept, the next question is "how do I mimic sheets in Swing?"

## 6.5.2. Use the Glass Pane

One way to imitate the Mac OS X sheet is to use the *glass pane* layer in the `LayeredPane` used by all `RootPaneContainers`, including `JApplets`, `JFrames`, `JInternalFrames`, `JWindows`, and `JDialogs`. In terms of z-order the ordering of layers on "top" of one another from the user's perspective the glass pane is "above" the content pane and the menu bar in the `LayeredPane`. It is usually empty and unfilled. One of the more typical uses for the glass pane is to add a `MouseListener` and `MouseMotionListener` to deny events to the content pane and thereby block it.

To imitate the sheet with the glass pane, the idea is to take the contents you'd usually put into a `JDialog` and place them instead into the glass pane. This will put them in the frame, above and in front of the frame's contents. To position your contents at the top center of the glass pane, you can use a `GridBagLayout` that gives the sheet a `NORTH` anchor, and then add a "glue" component in the next row that takes up as much vertical space as possible, pushing the sheet to the top of the pane.

[Example 6-7](#) shows a subclass of `JFrame` that exposes a `showJDialogAsSheet()` method, which grabs the `JDialog`'s content pane `JComponent` and inserts it into the glass pane as the sheet.

### Example 6-7. Adding a sheet in a JFrame's glass pane

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;
import java.awt.event.*;

public class SheetableJFrame extends JFrame {
```

```

JComponent sheet;
JPanel glass;

public SheetableJFrame (String name) {
    super(name);
    glass = (JPanel) getGlassPane( );
}

public JComponent showJDialogAsSheet (JDialog dialog) {
    sheet = (JComponent) dialog.getContentPane( );
    sheet.setBackground (Color.red);
    glass.setLayout (new GridBagLayout( ));
    sheet.setBorder (new LineBorder(Color.black, 1));
    glass.removeAll( );
    GridBagConstraints gbc = new GridBagConstraints( );
    gbc.anchor = GridBagConstraints.NORTH;
    glass.add (sheet, gbc);
    gbc.gridy=1;
    gbc.weighty = Integer.MAX_VALUE;
    glass.add (Box.createGlue( ), gbc);
    glass.setVisible(true);
    return sheet;
}

public void hideSheet( ) {
    glass.setVisible(false);
}
}

```

Simple enough, isn't it? To test this component, just create a `JFrame` and a `JDialog` to insert into the frame. The `SheetTest` class in [Example 6-8](#), which exercises the `SheetableJFrame`, fills the frame with interesting content by making a `JLabel` from an image file. It then creates a `JDialog` the easy way by making `JOptionPane` do it.

If you're used to calling `JOptionPane`'s various `showXXXDialog( )` methods, you might be unfamiliar with the idea of constructing and holding on to a `JOptionPane` and creating dialogs from it. This approach isn't common, but it's useful if you want to hold on to the `JDialog`, maybe for reuse (e.g., you have memory or performance concerns with repeatedly creating and disposing of dialogs) or because you don't want to block as soon as you show it. In the case of this demo, the advantage is to get a dialog to play with, without having to layout and wire up everything yourself.

## Example 6-8. Testing the SheetableJFrame

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

```

```

import java.beans.*;

public class SheetTest extends Object
    implements PropertyChangeListener {

    JOptionPane optionPane;
    SheetableJFrame frame;

    public static void main (String[] args) {
        new SheetTest( );
    }

    public SheetTest ( ) {
        frame = new SheetableJFrame ("Sheet test");
        // put an image in the frame's content pane
        ImageIcon icon = new ImageIcon ("keagy-lunch.png");
        JLabel label = new JLabel (icon);
        frame.getContentPane( ).add(label);
        // build JOptionPane dialog and hold onto it
        optionPane = new JOptionPane ("Do you want to save?",
            JOptionPane.QUESTION_MESSAGE,
            JOptionPane.YES_NO_OPTION);
        frame.pack( );
        frame.setVisible(true);
        optionPane.addPropertyChangeListener (this);
        // pause for effect, then show the sheet
        try {Thread.sleep(1000);}
        catch (InterruptedException ie) {}
        JDialog dialog =
            optionPane.createDialog (frame, "irrelevant");
        frame.showJDialogAsSheet (dialog);
    }

    public void propertyChange (PropertyChangeEvent pce) {
        if (pce.getPropertyName( ).equals (JOptionPane.VALUE_PROPERTY)) {
            System.out.println ("Selected option " +
                pce.getNewValue( ));
            frame.hideSheet( );
        }
    }
}

```

The other thing that's interesting about holding onto a `JOptionPane` is that it's not the dialog that fires events when the user clicks one of the buttons. These are fired as `PropertyChangeEvents` with the property name value, which you should refer to as `JOptionPane.VALUE_PROPERTY`. In this case, what you want to listen for is any change in the value, which indicates that something has been clicked and means it's time to hide the sheet.

When you run `SheetTest`, the image comes up in a `SheetableJFrame` and, after a one-second pause for effect, the sheet appears at top center, as seen in [Figure 6-8](#).

Figure 6-8. JDialog shown as a "sheet" in the glass pane



When you click either of the options, the event listener hides the glass pane, which makes the sheet disappear.

This is a pretty simple case of using the glass pane in fact, the test is a few lines longer than the implementation of the sheet. The only thing that's missing is the charming animation of the sheet sliding in [\[Hack #45\]](#)....

## Hack 45. Animating a Sheet Dialog



By animating the sheet's appearance and disappearance, you give the user a better clue that his attention is required. Plus, it looks cool.

Another really great thing about the sheet functionality in Mac OS X is that it doesn't just suddenly appear; it slides out from the titlebar, as if unrolling from under the bar. This animation further reinforces the relationship between the sheet and the window because the short animation catches your eye and alerts you to the fact that something about the window has changed dramatically—namely, that it is now blocked by the sheet dialog.

### 6.6.1. Animate the Sheet

You already know how to get components into the glass pane [[Hack #44](#)], so you should expect that the key to sheet animation is to perform the animation in the glass pane, on top of the other components. Of course, you might have also guessed that the tricky part of this is going to be showing successively larger parts of the dialog as the animation progresses.

To make this work, you first need to create a custom component for the animating version of the sheet, separate from the sheet itself. Then, on each pass of the animation cycle, change the size of the custom component. It will always have the same width—the width of the real sheet—but its height will be some percentage of the height of the original, based on how much of the animation time has elapsed. This approach can work for both directions of the animation: when the sheet is incoming, the height will get progressively greater; when the sheet is going out, the height will decrease.

To actually draw the animating sheet during the animation, you can use `BufferedImage.getSubimage()` to grab a portion of the real sheet, and then draw that into its own `Graphics` via `paint()` callbacks. When the animation completes, the animating sheet is removed from the glass pane and the real sheet is added.

An interesting side effect of this is that the user can't click the buttons as the sheet appears or retracts because it's just an image of the sheet, not the sheet itself. Of course, the animation is so short (one second in [Example 6-9](#), and Mac OS X's actually comes out faster than that), that it's unlikely a user could track the moving sheet with her mouse and successfully click a button anyway.

One advantage of using a custom component like this is that the kinds of things that worked for basic sheets [[Hack #44](#)] all work here as well. For example, you could use a simple `GridBagLayout` (wow, there's a phrase you don't hear often) to get the sheet centered atop the glass pane. As the sheet is

a real component, it should also handle resizing appropriately.

Setting aside the details of the custom component needed to create the animated version of the sheet, [Example 6-9](#) shows the reworked version of the sheet frame, which I've called *AniSheetableJFrame*.

### Example 6-9. JFrame for animating sheet appearance and disappearance

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;
import java.awt.event.*;
import java.awt.image.*;

public class AniSheetableJFrame extends JFrame
    implements ActionListener {

    public static final int INCOMING = 1;
    public static final int OUTGOING = -1;
    public static final float ANIMATION_DURATION = 1000f;
    public static final int ANIMATION_SLEEP = 50;

    JComponent sheet;
    JPanel glass;
    AnimatingSheet animatingSheet;
    boolean animating;
    int animationDirection;
    Timer animationTimer;
    long animationStart;
    BufferedImage offscreenImage;

    public AniSheetableJFrame (String name) {
        super(name);
        glass = (JPanel) getGlassPane( );
        glass.setLayout (new GridBagLayout( ));
        animatingSheet = new AnimatingSheet( );
        animatingSheet.setBorder (new LineBorder(Color.black, 1));
    }

    public JComponent showJDialogAsSheet (JDialog dialog) {
        sheet = (JComponent) dialog.getContentPane( );
        sheet.setBorder (new LineBorder(Color.black, 1));
        glass.removeAll( );
        animationDirection = INCOMING;
        startAnimation( );
        return sheet;
    }

    public void hideSheet( ) {
        animationDirection = OUTGOING;
        startAnimation( );
    }
}
```

```

}

private void startAnimation( ) {
    glass.repaint( );
    // clear glasspane and set up animatingSheet
    animatingSheet.setSource (sheet);
    glass.removeAll( );
    GridBagConstraints gbc = new GridBagConstraints( );
    gbc.anchor = GridBagConstraints.NORTH;
    glass.add (animatingSheet, gbc);
    gbc.gridy=1;
    gbc.weighty = Integer.MAX_VALUE;
    glass.add (Box.createGlue( ), gbc);
    glass.setVisible(true);

    // start animation timer
    animationStart = System.currentTimeMillis( );
    if (animationTimer == null)
        animationTimer = new Timer (ANIMATION_SLEEP, this);
    animating = true;
    animationTimer.start( );
}

private void stopAnimation( ) {
    animationTimer.stop( );
    animating = false;
}

// used by the Timer
public void actionPerformed (ActionEvent e) {
    if (animating) {
        // calculate height to show
        float animationPercent =
            (System.currentTimeMillis( ) - animationStart) /
            ANIMATION_DURATION;
        animationPercent = Math.min (1.0f, animationPercent);
        int animatingHeight = 0;

        if (animationDirection == INCOMING) {
            animatingHeight =
                (int) (animationPercent * sheet.getHeight( ));
        } else {
            animatingHeight =
                (int) ((1.0f - animationPercent) * sheet.getHeight( ));
        }
        // clip off that much from sheet and blit it
        // into animatingSheet
        animatingSheet.setAnimatingHeight (animatingHeight);
        animatingSheet.repaint( );

        if (animationPercent >= 1.0f) {
            stopAnimation( );
        }
    }
}

```

```

        if (animationDirection == INCOMING) {
            finishShowingSheet( );
        } else {
            glass.removeAll( );
            glass.setVisible(false);
        }
    }
}
}

private void finishShowingSheet( ) {
    glass.removeAll( );
    GridBagConstraints gbc = new GridBagConstraints( );
    gbc.anchor = GridBagConstraints.NORTH;
    glass.add (sheet, gbc);
    gbc.gridy=1;
    gbc.weighty = Integer.MAX_VALUE;
    glass.add (Box.createGlue( ), gbc);
    glass.revalidate( );
    glass.repaint( );
}
// inner class AnimatedSheet goes here
}

```

Looking at this code method by method, the constructor's only new task is to create an instance of the `AnimatingSheet` inner class that will be used by the animation.

`showJDialogAsSheet( )` again hijacks the content pane from the `JDialog` and sets it aside as the `sheet` instance variable. But instead of putting `sheet` in the glass pane immediately, it sets the `animationDirection` to `INCOMING` and calls `startAnimation( )`. The `hideSheet( )` method makes similar changes: instead of messing with the glass pane directly, it simply sets the direction to `OUTGOING` and calls `startAnimation( )`.

`startAnimation( )` begins by refreshing the glass pane with a `repaint( )`. It then informs the `AnimatingSheet` of its new source (i.e., the sheet) and adds the `AnimatingSheet` to the layout. It then sets up a `javax.swing.Timer` to get callbacks to an `actionPerformed( )` method that performs each step of the animation. The `ANIMATION_SLEEP` parameter affects how smooth the animation will look; shorter sleeps will result in a higher frame rate, but higher CPU use.

I've set this value as low as 2 ms and haven't had a problem, but I'm on a pretty fast box (a dual 1.8 GHz G5 Power Mac). You might want to play with this value to get an ideal performance-to-smoothness ratio.

`stopAnimation( )` just stops the `Timer`, as you might expect.

The `actionPerformed( )` method is used by the `Timer` callbacks. It has two tasks: calculating the height of the sheet to show, and wrapping up the animation if it has run its course. Notice that the progress calculation doesn't assume that it has been called back in accordance with the `ANIMATION_SLEEP`. It calculates the current time offset from when the animation began, and calculates



a progress from that, which in turn allows it to figure out how much of the sheet to show. This is a really good practice because if your computer can't keep up with your desired rate, the `Timer` will combine multiple callbacks into one. By just using the current time (instead of a possibly incorrect assumption about frame rate), you'll keep up with the specified rate and duration. On screen, combined callbacks will look like dropped frames, but a choppy animation is preferable to one that takes longer than it should.

If `actionPerformed()` decides that the animation has finished, it calls `stopAnimation()` and then cleans up the glass pane by either removing its contents (if the direction is `OUTGOING`) or by calling `finishShowingSheet()` (if direction is `INCOMING`). The `finishShowingSheet()` method clears the glass pane and puts the real sheet in place, just like `showJDialogAsSheet()` did in the last lab.

## 6.6.2. Self-Painting

So, the frame is responsible for adding, removing, and animating the `AnimatedSheet`, and for adding the real sheet when the incoming animation completes. What that leaves for the `AnimatedSheet` is the ability to paint itself (from a region of the original dialog) and report an accurate size for the benefit of the glass pane's `LayoutManager`.

[Example 6-10](#) shows the code for the `AnimatingSheet` inner class.

### Example 6-10. Inner class to paint sheet during animation

```
class AnimatingSheet extends JPanel {
    Dimension animatingSize = new Dimension (0, 1);
    JComponent source;
    BufferedImage offscreenImage;
    public AnimatingSheet ( ) {
        super( );
        setOpaque(true);
    }
    public void setSource (JComponent source) {
        this.source = source;
        animatingSize.width = source.getWidth( );
        makeOffscreenImage(source);
    }
    public void setAnimatingHeight (int height) {
        animatingSize.height = height;
        setSize (animatingSize);
    }
    private void makeOffscreenImage(JComponent source) {
        GraphicsConfiguration gfxConfig =
            GraphicsEnvironment.getLocalGraphicsEnvironment( )
                .getDefaultScreenDevice( )
                .getDefaultConfiguration( );
        offscreenImage =
            gfxConfig.createCompatibleImage(source.getWidth( ),
```

```

        source.getHeight( ));
    Graphics2D offscreenGraphics =
        (Graphics2D) offscreenImage.getGraphics( );
    source.paint (offscreenGraphics);
}
public Dimension getPreferredSize( ) { return animatingSize; }
public Dimension getMinimumSize( ) { return animatingSize; }
public Dimension getMaximumSize( ) { return animatingSize; }
public void paint (Graphics g) {
    // get the bottom-most n pixels of source and
    // paint them into g, where n is height

    BufferedImage fragment =
        offscreenImage.getSubimage (0,
            offscreenImage.getHeight( )
            animatingSize.height,
            source.getWidth( ),
            animatingSize.height);
    // g.drawImage (fragment, 0, 0, this);
    g.drawImage (fragment, 0, 0, this);
}
}

```

The constructor is more or less trivial, so take a look at the `setSource()` method. This method stores the source `JComponent` (the sheet that the frame created from a dialog) as an instance variable, and calculates a width for the `AnimatingSheet`. This width will be constant through the animation, so it's assigned at this step.

The `makeOffscreenImage()` that `setSource()` calls takes the source `JComponent` and draws an offscreen `BufferedImage`. It does this by calling `GraphicsConfiguration.createCompatibleImage()` with the size of the source. Using `createCompatibleImage()` is highly recommended for creating offscreen images because it will keep you from getting surprised by greater or lesser color depths on platforms other than your own. `makeOffscreenImage()` then gets the `Graphics2D` for this image and tells `source` to paint itself onto the `Graphics2D`. The offscreen image now contains an image of the source component.

`setAnimatingHeight()`, called by the frame's `Timer` just before it `repaint()`s the `AnimatingSheet`, stores away two values that will be needed by the `paint()` callback: the height in pixels to be painted and the new size of the animating sheet. This new size is returned by `getPreferredSize()`, `getMinimumSize()`, and `getMaximumSize()`, so the layout manager will know how much space to provide for it.

And now for the big payoff: `paint()` is called as a result of the frame's `Timer` callback making a `repaint()` call. It uses `BufferedImage.getSubimage()` to get the pixels for the bottom-most `animatingHeight` pixels of the offscreen image. It then draws this sub-image into the `Graphics` at 0,0. The image's size matches the newly reported preferred size of the `AnimatingSheet` component, so the sub-image fills it completely.

And that's it. The frame is responsible for managing what's in the glass pane animating sheet, real sheet, or nothing and for running the animation. The `AnimatingSheet` is just responsible for adjusting

its size when called by the animation, and for painting an appropriate representation suitable to that size, which it does by grabbing sub-images from an offscreen image of the real component.

The `SheetTest` class has only one meaningful change from the version in the last hack: the `SheetableJFrame` becomes an `AniSheetableJFrame`. Run it once to see the effect, and then play with the `ANIMATION_DURATION` and `ANIMATION_SLEEP` values to see what it looks like when you change the duration or the smoothness of the animation. For the screenshot sequence in [Figure 6-9](#), I used a duration of 10,000 ms (10 seconds) so I could get multiple shots and show the progress of the animation.

Figure 6-9. Successive screenshots of an animated glass pane sheet



## Hack 46. Slide Notes Out from the Taskbar



Pop up a note above the taskbar when your application wants attention .

On Windows, long-running applications sometimes will slide in a window above the taskbar to call attention as a finished download or an IM buddy's appearance.

If you want to do this in Java, you need to deal with a pretty significant problem: neither AWT nor Swing (whether it's auto-hiding, or anything else). As a result, you don't know where to draw the window, and it's either too high and the window floats inexplicably on the desktop, too low and it gets buried under the taskbar, or

Furthermore, how is this going to work on other operating systems? On the Mac, the proper way to get a window above the dock (there's no API exposing that functionality, can you at least use a Windows-like slide-in window above the dock, or whether the dock is even on the bottom of the screen (it might be on the right or left side, or

Fortunately, it is possible to figure out what unobstructed space is available to you on the main display. The following code shows an animation.

### 6.7.1. Figure Out Where You Are

The key to figuring out your available space is to get the local `GraphicsEnvironment` , which describes the current display. The `getAvailableDisplayableRectangles` method, introduced in Java 1.4, returns a `Rectangle` representing the largest centered `Window` that could fit on the display's usable space, like the Windows taskbar or the Mac's monolithic menu bar.

This means that on Windows, the `Rectangle` will have an upper-left corner at 0,0; on the Mac, it will be at the top of the screen. Meanwhile, the height of the `Rectangle` won't be the height of your display unless you have your taskbar or dock hidden.

So, now you have the beginnings of the slide-in above-taskbar window. By subtracting the height of the taskbar or dock, you can place the window directly above the taskbar or dock. To do the slide-in, you'll need to do an animation where a complete window is blitted into a smaller onscreen version. This is very similar to the animated sheet effect in the previous hack that you can reuse the inner class from that hack to do the progressive redrawing.

A simple implementation, `SlideInNotification` , is shown in Example 6-11 .

#### Example 6-11. Sliding in a window immediately above the taskbar or dock

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;
import java.awt.image.*;

public class SlideInNotification extends Object {
```

```
protected static final int ANIMATION_TIME = 500;
protected static final float ANIMATION_TIME_F =
    (float) ANIMATION_TIME;
protected static final int ANIMATION_DELAY = 50;

JWindow window;
JComponent contents;
AnimatingSheet animatingSheet;
Rectangle desktopBounds;
Dimension tempWindowSize;
Timer animationTimer;
int showX, startY;
long animationStart;

public SlideInNotification ( ) {
    initDesktopBounds( );
}

public SlideInNotification (JComponent contents) {
    this( );
    setContents (contents);
}

protected void initDesktopBounds( ) {
    GraphicsEnvironment env =
        GraphicsEnvironment.getLocalGraphicsEnvironment( );
    desktopBounds = env.getMaximumWindowBounds( );
    System.out.println ("max window bounds = " + desktopBounds);
}

public void setContents (JComponent contents) {
    this.contents = contents;
    JWindow tempWindow = new JWindow( );
    tempWindow.getContentPane( ).add (contents);
    tempWindow.pack( );
    tempWindowSize = tempWindow.getSize( );
    tempWindow.getContentPane( ).removeAll( );
    window = new JWindow( );
    animatingSheet = new AnimatingSheet ( );
    animatingSheet.setSource (contents);
    window.getContentPane( ).add (animatingSheet);
}

public void showAt (int x) {
    // create a window with an animating sheet
    // copy over its contents from the temp window
    // animate it
    // when done, remove animating sheet and add real contents

    showX = x;
    startY = desktopBounds.y + desktopBounds.height;
}
```

```

        ActionListener animationLogic = new ActionListener( ) {
            public void actionPerformed(ActionEvent e) {
                long elapsed =
                    System.currentTimeMillis( ) - animationStart;
                if (elapsed > ANIMATION_TIME) {
                    // put real contents in window and show
                    window.getContentPane( ).removeAll( );
                    window.getContentPane( ).add (contents);
                    window.pack( ); window.setLocation (showX,
                        startY - window.getSize( ).height);
                    window.setVisible(true);
                }
                window.repaint( );
                animationTimer.stop( ); animationTimer = null;
            } else {
                // calculate % done
                float progress =
                    (float) elapsed / ANIMATION_TIME_F;
                // get height to show int animatingHeight =
                nt) (progress * tempWindowSize.getHeight( ));

                animatingHeight = Math.max (animatingHeight, 1;
            )
            animatingSheet.setAnimatingHeight (animatingHeight);
                window.pack( );
                window.setLocation (showX,
                    startY - window.getHeight( ));
                window.setVisible(true);
                window.repaint( );
            }
        }
    };
    animationTimer =
        new Timer (ANIMATION_DELAY, animationLogic);
    animationStart = System.currentTimeMillis( );
    animationTimer.start( );
}

// AnimatingSheet inner class listed below
}

```

After setting the constants for the speed of the animation and the frame rate (i.e., how frequently to call `update`), you create a temporary window to hold the usable screen space (given the `GraphicsEnvironment` strategy just detailed) and optionally to set the constants.

The `setContents` ( ) is a little tricky because you need to figure out the size of the contents (a `JComponent` ) by breaking them into fragments. You can do this by putting them into a temporary window and packing it, which forces them to be the right size. Next, you create the real `Window` to show on screen, but instead of adding the contents, you add an `AnimatingSheet` to the window. As parts of the contents as the animation runs. When the animation is finished, the `AnimatingSheet` will be removed.

To slide in the window, a caller invokes the `showAt ( )` method, passing in an arbitrary `x`-coordinate. Not dock, so there's no way, short of going native to get your slide-in window to appear above a specific task to figure out the `y`-coordinate where the animation will begin, namely the last usable row. Given the `Rect` window, you add its `y`-coordinate to its height. The `y`-coordinate accounts for top-of-screen obstructions space from there to the taskbar or dock, if any.

`showAt ( )` contains a large, anonymous inner class `ActionListener` that performs the animation logic that

As with most animations, the first thing you do is to figure out how much time has elapsed in the animation. `AnimatingSheet`, insert the real contents, pack the `Window` and reset its location to its final visible location.

If the animation time has not fully elapsed, you calculate how far into the animation you are, as a percentage. Then, how many vertical pixels you want to show on this pass. Send this value to `AnimatingSheet`'s `setAnimatingHeight ( )` (the preferred height you just set), set the location to the starting `y`-coordinate minus the window's new

The `AnimatingSheet` inner class was already described in the previous hack, but to recap, it represents a scrollable window. When you set the source, it creates an offscreen `Image` of the component's pixels. Then, when you call `setAnimatingHeight ( )`, preferred, minimum, and maximum size to use that height (this is why it can be packed by the `Window` due to `BufferedImage.getSubimage ( )` to get a portion of the offscreen image that it can blit into the `Graphics` window.

This version, shown in Example 6-12, has two differences from the earlier version of `AnimatingSheet`:

- Because this window scrolls in the opposite direction of the drop-down sheets, the `getSubimage ( )` call uses a different number of pixels.
- On Windows, I found the offscreen buffer was black unless explicitly cleared out first. This wasn't a problem on Linux.

Example 6-12. The `AnimatingSheet` inner class is used in creating notification windows.

```
class AnimatingSheet extends JPanel {
    Dimension animatingSize = new Dimension (0, 1);
    JComponent source;
    BufferedImage offscreenImage;
    public AnimatingSheet ( ) {
        super( );
        setOpaque(true);
    }
    public void setSource (JComponent source) {
        this.source = source;
        animatingSize.width = source.getWidth( );
        makeOffscreenImage(source);
    }

    public void setAnimatingHeight (int height) {
        animatingSize.height = height;
        setSize (animatingSize);
    }
    private void makeOffscreenImage(JComponent source) {
        GraphicsEnvironment ge =
            GraphicsEnvironment.getLocalGraphicsEnvironment( );
```

```

GraphicsConfiguration gfxConfig =
    ge.getDefaultScreenDevice( ).getDefaultConfiguration( );
offscreenImage =
    gfxConfig.createCompatibleImage(source.getWidth( ),
                                    source.getHeight( ));
Graphics2D offscreenGraphics =
    (Graphics2D) offscreenImage.getGraphics( );
// windows workaround
offscreenGraphics.setColor (source.getBackground( ));
offscreenGraphics.fillRect (0, 0,
                            source.getWidth( ), source.getHeight( ));
// paint from source to offscreen buffer
source.paint (offscreenGraphics);
}
public Dimension getPreferredSize( ) { return animatingSize; }
public Dimension getMinimumSize( ) { return animatingSize; }
public Dimension getMaximumSize( ) { return animatingSize; }
public void update (Graphics g) {
    // override to eliminate flicker from
    // unnecessary clear
    paint (g);
}
public void paint (Graphics g) {
    // get the top-most n pixels of source and
    // paint them into g, where n is height
    // (different from sheet example, which used bottom-most)
    BufferedImage fragment =
        offscreenImage.getSubimage (0,
                                    0,
                                    animatingSize.height);
    g.drawImage (fragment, 0, 0, this);
}
}

```

## 6.7.2. Running the Hack

The `SlideInNotification` will take any `JComponent` as its contents. To make things a little interesting, the class grabs an icon from the `JOptionPane` class and makes a `JLabel` of that and a little nonsense text.

### Example 6-13. Testing the slide-in notification

```

import javax.swing.*;

public class TestSlideInNotification {

    public static void main (String[] args) {
        Icon errorIcon = UIManager.getIcon ("OptionPane.errorIcon");
    }
}

```



```

        JLabel label = new JLabel ("Your application asplode",
                                   errorIcon,
                                   SwingConstants.LEFT);
        SlideInNotification slider = new SlideInNotification (label);
        slider.showAt (450);
    }
}

```

When you run this application, one thing to make note of is the standard output because the `SlideInNoti` show the discovered dimensions. Here's what Windows reports with a taskbar showing:

```
max window bounds = java.awt.Rectangle[x=0,y=0,width=800,height=570]
```

and what it reports with the taskbar set to auto-hide:

```
max window bounds = java.awt.Rectangle[x=0,y=0,width=800,height=600]
```

Meanwhile, on the Mac, the bounds with a dock on the bottom of the screen look like this:

```
max window bounds = java.awt.Rectangle[x=0,y=22,width=1280,height=707]
```

and with the dock over on the right, they look like this:

```
max window bounds = java.awt.Rectangle[x=0,y=22,width=1244,height=746]
```

Notice that in each case, the first usable y-coordinate is 22, accounting for the unusable space under the dock. Also, notice that I've lost usable horizontal space because the dock is on the right. By the way, if you're doing the math, 1244 is 1280 minus 36. If you're doing the math, it's because I have a wide-screen monitor and my screen size is 1280 x 768.

Of course, don't stare too long at the console output, or you'll miss the appearance of the slide-in window. Figure 6-10 shows the slide-in window on Windows, with and without a visible taskbar.

Figure 6-10. Slide-in window on Windows with taskbar showing (

Figure 6-11 shows the slide-in window on Mac OS X. It's less appropriate on the Mac, and it will be obscure, but it's not really bad either.

Figure 6-11. Slide-in window on Mac OS X with dock on bottom of screen

### 6.7.3. Hacking the Hack

To expand this hack, the first thing you'd probably want to do is add some kind of `MouseListener` so that the slide-in window, you could react to it by removing the slide-in window, bringing your application's main components in here, so there's no reason you couldn't just generate a `JOptionPane`, make a `JDialog` for the slide-in window. That would give you real, active Swing buttons and handy `JOptionPane` return values

## Hack 47. Indefinite Progress Indicator



Despite its numerous advanced widgets, Swing offers no efficient way to show that a task of unknown length is in progress. This hack presents two solutions to address this issue.

Have you ever watched an application do something, but not tell you what that something is? Other applications let you know what's going on but don't really tell you how long they will need to complete the task. For instance, the Microsoft Windows copy dialog is famous for its silly (and lengthy) nonprogress indicators. As a user, I find this very annoying; as a programmer, I know how difficult it can be to determine the duration of a task.

### 6.8.1. The Swing Solution

To address this issue, developers created particular widgets meant to show a task of unknown length is in progress. You can see such a widget in Mozilla's installer. It displays an indefinite progress bar also called a *Cylon* which a small rectangle bounces back and forth between the two horizontal edges. I have also seen indefinite progress bars filling like regular progress bars, going backward once filled and starting all over again. The idea of an indefinite progress bar is great, but most existing implementations are just wrong. Users know what a progress bar looks like, and they also know how it is supposed to behave. It is a bad idea to present a familiar widget acting in a very surprising way. Unfortunately, the Swing designers followed this trend and added the `setIndeterminate(boolean)` method to `JProgressBar`. Check out [Example 6-14](#).

#### Example 6-14. An indefinite progress bar

```
import javax.swing.*;
public class CylonBar {
    public static void main(String[] args) {
        JFrame f = new JFrame("Progress");
        JProgressBar p = new JProgressBar( );
        p.setIndeterminate(true);
        f.getContentPane( ).add(p);
        f.pack( );
        f.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
        f.setVisible(true);
    }
}
```

This short example creates a new window containing an indefinite progress bar. When you launch the program, you can see a small rectangle bouncing back and forth within the progress bar's bounds, as in [Figure 6-12](#). The result is much better on Mac OS X because it uses the native Look and Feel automatically, as shown in [Figure 6-13](#). Despite this visual improvement, though, the result is still far from perfect.

Figure 6-12. The indefinite progress bar offered by Swing

Figure 6-13. Swing's indefinite progress bar with Mac OS X Look and Feel




There are several better ways to show that a task of unknown length is in progress.

### 6.8.2. Picture as Indicator

The first solution relies on cycling the brightness of a picture in a panel. Instead of moving a rectangle back and forth, you can increase and decrease the brightness of a picture. The result is much more appealing and lets you choose an adequate picture regarding the current running task. [Figure 6-14](#) shows the `AnimatedPanel` in action.

Figure 6-14. The first tab demonstrates the use of a picture as an indefinite progress indicator



When you click the Start button, the contents of the Animated tab are replaced by a panel containing a picture and a message. With the picture's brightness cycles, as shown in [Figure 6-15](#), you can see the most bright state on the left and the less bright state on the right.

Figure 6-15. AnimatedPanel displays a picture and cycles its brightness

To change the brightness of the picture dynamically, `AnimatedPanel` starts an animation thread responsible for computing the brightness over the time:

```
public void start( ) {
    this animator = new Thread(new HighlightCycler( ), "Highlighter");
    this animator.start( );
}

class HighlightCycler implements Runnable {
    private int way = 1;
    private final int LOWER_BOUND = 10;
    private final int UPPER_BOUND = 35;
    private int value = LOWER_BOUND;

    public void run( ) {
        while (true) {
```

```

try {
    Thread.sleep(1000 / (UPPER_BOUND - LOWER_BOUND));
} catch (InterruptedException e) {
    return;
}

value += this.way;
if (value > UPPER_BOUND) {
    value = UPPER_BOUND;
    this.way = -1;
} else if (value < LOWER_BOUND) {
    value = LOWER_BOUND;
    this.way = 1;
}

synchronized (convolvedImage) {
    setBrightness((float) value / 10);
    setGradientFactor((float) value / UPPER_BOUND);
}
}
}
}
}

```

When the `start()` method of the panel is called, a new thread is spawned to run `HighlightCycler`. The animation loop is very simple, and it increases or decreases the variable value until its `value` reaches `LOWER_BOUND` or `UPPER_BOUND`. Then, `setBrightness()` is invoked to change the brightness of the picture. Given the values of the bounds, the brightness swings between 1.0 (unchanged) and 3.5 (the picture is 3.5 times brighter). You can notice this call is synchronized with the object `convolvedImage`, which is one of the two `BufferedImages` contained in `AnimatedPanel`. This image is the result of a filter applied on `originalImage`, the picture that contains the unchanged original picture. As applying the filter can take some time, the code synchronizes on `convolvedImage` to ensure the previous filtering is done before running a new one. This code shows how to change the brightness of the picture:

```

private void setBrightness(float multiple) {
    float[] brightKernel = { multiple };
    RenderingHints hints = new RenderingHints(RenderingHints.KEY_RENDERING,
        RenderingHints.VALUE_RENDER_QUALITY);
    BufferedImageOp bright = new ConvolveOp(new Kernel(1, 1, brightKernel),
        ConvolveOp.EDGE_NO_OP, hints);
    bright.filter(originalImage, convolvedImage);
    repaint( );
}


```

The parameter `multiple` tells the method how many times brighter than the original the resulting image must be. To achieve this effect, you can simply perform a convolve operation on the original

image. The kernel contains a single value, `multiple`. When the `filter()` method is invoked, every pixel value of the original image is multiplied by the value of the kernel, making it brighter. The result is stored in `convolveImage`. It is now easy to use the `AnimatedPanel` in an application:

```
Icon icon = UIHelper.readImageIcon("network.png");
AnimatedPanel animated = new AnimatedPanel("Waiting in vain...", icon);
getContentPane().add(animated);
animated.start();
```

Besides the `start()` method, you can call `stop()` to interrupt the animation thread when the task is done. This panel can be very efficient when used with a `CardLayout`. As this layout lets you stack components, you can put a form on top of the animated panel. When the user performs an action, you can display the animated panel and start the animation. At the end of the task, you just need to stop the animation and hide the animated panel.



The example file *Demo.java* contains a complete example using `CardLayout`.


### 6.8.3. The Glass Pane as an Indicator

Using the `AnimatedPanel` proves to be efficient in form-oriented applications. Unfortunately, it does not help much when the running task must not be interrupted by any action performed by the user. In this case, you need a way to disable the entire GUI while displaying an indefinite progress indicator. This can be done with a glass pane, as shown in [Figure 6-16](#).

`InfiniteProgressPanel` is an animated glass pane you can set up on any Swing frame:

```
InfiniteProgressPanel glassPane = new InfiniteProgressPanel();
setGlassPane(glassPane);
glassPane.start();
```

Figure 6-16. `InfiniteProgressPanel` draws a white veil to disable the UI visually



When you `start()` the panel, a fade-in animation is played during the rampup phase. When `stop()` is called, a fade-out animation is played. Between the two, a circular shape is rotated at the center of the glass pane. All the while, a white translucent veil is drawn over the underlying UI to disable it visually.

The implementation of `InfiniteProgressPanel` relies on many parameters, which you can specify with the various constructors:

`text`

The optional message to be displayed below the circular shape

`barsCount`

The number of bars composing the circular shape

`shield`

The opacity of the white veil, also known as the shield

`fps`

The requested amount of frames per second during the animation



rampDelay

The time, in milliseconds, that fade-in and fade-out animations should last

## 6.8.4. Build the Circular Shape

Everything begins when the `start()` method is invoked:

```
public void start( )
{
    addMouseListener(this);
    setVisible(true);
    ticker = buildTicker( );
    animation = new Thread(new Animator(true));
    animation.start( );
}
```

Before running the animation, this method takes care of adding a mouse listener that is responsible for catching all the mouse events and preventing them from being forwarded to the underlying user interface. Thus, the user will not be able to perform any action. The second step is to set the glass pane to be visible. Finally, the `ticker`, the circular shape, is built and the animation is started. Building the shape is done with two methods:

```
private Area buildPrimitive( )
{
    Rectangle2D.Double body = new Rectangle2D.Double(6, 0, 30, 12);
    Ellipse2D.Double head = new Ellipse2D.Double(0, 0, 12, 12);
    Ellipse2D.Double tail = new Ellipse2D.Double(30, 0, 12, 12);

    Area tick = new Area(body);
    tick.add(new Area(head));
    tick.add(new Area(tail));

    return tick;
}

private Area[] buildTicker( )
{
    Area[] ticker = new Area[barsCount];
    Point2D.Double center = new Point2D.Double((double) getWidth( ) / 2,
                                                (double) getHeight( ) / 2);
    double fixedAngle = 2.0 * Math.PI / ((double) barsCount);

    for (double i = 0.0; i < (double) barsCount; i++)
    {
        Area primitive = buildPrimitive( );
```

```

AffineTransform toCenter = AffineTransform.getTranslateInstance(
    center.getX( ), center.getY( ));
AffineTransform toBorder =
    AffineTransform.getTranslateInstance(45.0, -6.0);
AffineTransform toCircle =
    AffineTransform.getRotateInstance(-i * fixedAngle,
    center.getX( ), center.getY( ));

AffineTransform toWheel = new AffineTransform( );
toWheel.concatenate(toCenter);
toWheel.concatenate(toBorder);

primitive.transform(toWheel);
primitive.transform(toCircle);

ticker[(int) i] = primitive;
}

return ticker;
}

```

The `buildTicker()` method returns an array of `Areas`, where each `Area` is one of the bars composing the resulting shape. A bar is built in `buildPrimitive()` by merging two circles and a rectangle. The role of `buildTicker()` is simply to create the requested amount of bars and to move them to their final location. To do that, the code applies several `AffineTransform` operations: `toCenter` first translates the bar to the center of the glass pane, `toBorder` then moves the bar to the perimeter of the circle you want to create, and `toCircle` finally rotates the bar around the glass pane's center.

### 6.8.5. Paint the Indicator

Once `ticker` has been built, `paintComponent()` only needs to get each bar and fill it on the graphics surface of the glass pane:

```

public void paintComponent(Graphics g)
{
    if (started)
    {
        int width = getWidth( );
        int height = getHeight( );

        Graphics2D g2 = (Graphics2D) g;
        g2.setRenderingHints(hints);

        g2.setColor(new Color(255, 255, 255, (int) (alphaLevel * shield)));
        g2.fillRect(0, 0, getWidth( ), getHeight( ));
    }
}

```

```

    for (int i = 0; i < ticker.length; i++)0
    {
        int channel = 224 - 128 / (i + 1);
        g2.setColor(new Color(channel, channel, channel, alphaLevel));
        g2.fill(ticker[i]);
    }
}
}

```

To make things clearer, this code does not contain the painting of the text. To allow the glass pane to be visible even when the animation is not started, the application first checks the value of `started`. When false, `start()` has not been called yet and nothing must be drawn. In the other case, the white veil is first painted all over the glass pane. The fourth parameter of the `Color` object used by `fillRect()` defines the opacity. Opacity depends on two parameters here: `shield` and `alphaLevel`. The latter is computed by the animation thread to fade in and fade out the glass pane. As `alphaLevel` is between 0 and 255, and you multiply it by `shield`, which is in the range 0.0 to 1.0, to obtain the opacity of the veil. Finally, the for loop computes a new color for each bar and paints it. The colors are computed so as to create a circular gradient and give an impression of movement when the circular shape is rotated.

### 6.8.6. Run the Animation Thread

The most complicated part of `InfiniteProgressPanel` is the `Animator` thread since its `run()` method handles the fade-in and -out animations, as well as the main animation. The only constructor of `Animator` requires a boolean parameter called `rampUp`. When true, the thread will play both main and fade-in animations. Otherwise, the fade-out animation is played. This is what happens when you call `InfiniteProgressPanel.stop()`. Here is the code of `Animator.run()` to handle the main animation:

```

public void run( )
{
    Point2D.Double center;
    center = new Point2D.Double((double) getWidth( ) / 2,
                               (double) getHeight( ) / 2);
    double fixedIncrement = 2.0 * Math.PI / ((double) barsCount);
    AffineTransform toCircle;
    toCircle = AffineTransform.getRotateInstance(fixedIncrement,
                                                center.getX( ),
                                                center.getY( ));

    long start = System.currentTimeMillis( );
    if (rampDelay == 0)
        alphaLevel = rampUp ? 255 : 0;

    started = true;
    boolean inRamp = rampUp;
}

```

```

while (!Thread.interrupted( ))
{
    if (!inRamp)
    {

        for (int i = 0; i < ticker.length; i++)
            ticker[i].transform(toCircle);
    }

    repaint( );

    // fade-in/out animation

    try
    {
        Thread.sleep(inRamp ? 10 : (int) (1000 / fps));
    } catch (InterruptedException ie) {
        break;
    }
    Thread.yield( );
}
}

```

The first step of this method is to create an instance of `AffineTransform` that will be used to rotate the bar by a fixed increment. By applying this transformation to the bars, each bar will move clockwise to the location of the next bar. The rotation cannot happen during the fade-in animation, when `rampUp`, and therefore `inRamp`, are true. After having rotated the ticker and repainted the glass pane, the thread goes to sleep. The length of the sleep is defined by the request amount of frames per second. The more frames you specify, the more CPU resources the animation will need. Finally, the fade-in and fadeout animations, not shown here, are performed by computing `alphaLevel` according to the elapsed time since the beginning of the animation, stored in the variable `start`. The alpha level is computed so that it goes, during the fade in, from 0 to 255 in `rampDelay` milliseconds. The same rule applies to the fade-out animation.

Displaying nice-looking, indefinite progress indicators is not very difficult in Swing, even though it requires some work. Using a circular shape is definitely the best way to show an infinite progress indicator because you can walk around it indefinitely, even if you always go in the same direction.

*Romain Guy*

[← PREV](#)

# Chapter 7. Text

[Section 7.1. Hacks 4855: Introduction](#)

[Hack 48. Make Text Components Searchable](#)

[Hack 49. Force Text Input into Specific Formats](#)

[Hack 50. Auto-Completing Text Fields](#)

[Hack 51. Write Backward Text](#)

[Hack 52. Use HTML and CSS in Text Components](#)

[Hack 53. Use Global Anti-Aliased Fonts](#)

[Hack 54. Anti-Aliased Text Without Code](#)

[Hack 55. Anti-Aliased Text with a Custom Look and Feel](#)

← PREV

## 7.1. Hacks 4855: Introduction

Text handling pervades the Swing API, from the labeling of a `JButton` to handling styled text in a `JTextArea`. When we talk about hacking Swing's text handling, we often mean two different things: hacking into the representation of the text (say, by making it searchable), or hacking into how that text is displayed. This chapter will help you see that Swing text isn't just about little `JTextFields` for entering your username.

← PREV

## Hack 48. Make Text Components Searchable



This hack will show you how to add incremental search to a text area as a simple document listener, making it very easy to integrate with your existing software.

Many years ago, text editors had either no searching capabilities or a straight word search only. You would type a word into a dialog box and the program would search for that word, moving to its first location in the document. If you were lucky, there was a command to search again, instead of starting the process over. Then one day Emacs introduced a new kind of searching. The program would search as you typed in each character, updating the cursor with each keystroke. To search again, you only had to hit the Return key. If you wanted a less specific search, you could just hit the Backspace key and remove letters. Everything updated in real time. Incremental searching was born.

Most GUI toolkits Java Swing included do not provide incremental search. Java does, however, give you the tools to build your own incremental search. The 1.4 release of Java finally added a long requested feature: regular expressions. These are complex but concise patterns that are internally compiled into searching and matching code. With a single regular expression (known more commonly as a *regex*) you could match email addresses, split a complex data field, parse SQL expressions, or recognize different date formats. This hack has much more humble needs, but Java 1.4's built-in regex support will make the search implementation very easy.

The plan for this hack is to create a searching utility object that targets a `JTextComponent` (the common subclass for all Swing text components such as `JTextArea` and `JTextField`). It will also listen for action and document change events from a search component (usually a `JTextField`) to do the actual searching. By constructing it with class agnostic listeners, you can add it easily to existing programs without changing much code.

### 7.2.1. A Basic Search Class

The code in [Example 7-1](#) defines the `IncrementalSearch` class, which implements the `DocumentListener` and `ActionListener` interfaces. Programs with search usually have a search field above the search target. The `IncrementalSearch` constructor accepts a `JTextComponent` as the target, and the document listener events will provide access to the search field itself. In addition to the usual suspects, you'll need to import the Swing event, Swing text, and regex classes.

#### Example 7-1. Starting the basic incremental search class

```
import javax.swing.event.*;
import javax.swing.text.*;
import java.util.regex.*;
```

```

public class IncrementalSearch
    implements DocumentListener, ActionListener {

    protected JTextComponent content;
    public IncrementalSearch(JTextComponent comp) {
        this.content = comp;
    }

    /* DocumentListener implementation */
    public void insertUpdate(DocumentEvent evt) {
        runNewSearch(evt.getDocument());
    }
    public void removeUpdate(DocumentEvent evt) {
        runNewSearch(evt.getDocument());
    }
    public void changedUpdate(DocumentEvent evt) {
        runNewSearch(evt.getDocument());
    }
}

```

You can see that all three document listener methods just call `runNewSearch()`, passing in the document. This forces the search to start over if the user types new text, hits the Backspace key, or replaces a selection. So far, there is nothing tricky here. The complexity lies in the `runNewSearch()` function, which handles the actual searching.

## 7.2.2. Running the Search

The `runNewSearch()` method pulls out the query string from the document. Notice that it passes 0 and the length of the document into the `getText()` method. All of the `Document` methods operate in terms of a starting and ending index. You deal with chunks of text only with these indices rather than getting and setting `Strings`, which would entail lots of byte copying. Copying isn't a big deal for this hack, but it could be a problem for large documents (think several hundred kilobytes). Here is the `runNewSearch()` method:

```

protected Matcher matcher;

private void runNewSearch(Document query_doc) {
    try {
        String query = query_doc.getText(0, query_doc.getLength());

        Pattern pattern = Pattern.compile(query);
        Document content_doc = content.getDocument();
        String body = content_doc.getText(0, content_doc.getLength());

        matcher = pattern.matcher(body);
        continueSearch();
    }
}

```



```

    } catch (Exception ex) {
        p("exception: " + ex);
        ex.printStackTrace();
    }
}

```

After getting the text, `runNewSearch()` creates a new pattern from the query (which requires no modification since it is a simple search), and then retrieves the target document and text. With the search text, target body text, and pattern in hand, it creates a `Matcher` and calls `continueSearch()`. The `Matcher` is the class that will do the actual searching with an internally compiled regex:

```

private void continueSearch() {
    if(matcher != null) {
        if(matcher.find()) {
            content.getCaret().setDot(matcher.start());
            content.getCaret().moveDot(matcher.end());
            content.getCaret().setSelectionVisible(true);
        }
    }
}

```

The `continueSearch()` method just calls `find()` on the matcher, if it exists. If `find()` returns true, meaning it found a match somewhere, it sets the selection. Selections are defined by a caret with a dot. The dot represents the selection point. By setting the dot at the start of the match and then moving it with the `moveDot()` function, it will create a selection between the start and ending points. Finally, `setSelectionVisible(true)` scrolls the target component, if needed, to make the selection visible on screen.

The action listener implementation will call `continueSearch()` whenever an action is performed. Both `JButtons` and `JTextFields` produce actionsthe former when they are clicked, and the latter when the user hits the Return key. Listening for action events is an easy way of providing a hook to repeat the search:

```

/* ActionListener implementation */
public void actionPerformed(ActionEvent evt) {
    continueSearch();
}


```

Since the matcher object remembers its place, each time `find` is called it will continue searching from the current location. This means the user can just hit Enter over and over to loop through the results in the document, highlighting each one as it goes along.

### 7.2.3. Adding Search to Swing Components

The following code creates a typical search interface. There is a large `JTextArea` below a text field. The `IncrementalSearch` is attached to the text area through its constructor. The search field is connected via the document and action listeners. Once the class is put all together, it will look like [Figure 7-1](#).

Figure 7-1. Incremental repeatable search of a `JTextArea`



```
public static void main(String[] args) {
    JTextArea text_area = new JTextArea(10,20);
    JScrollPane scroll = new JScrollPane(text_area);
    IncrementalSearch isearch = new IncrementalSearch(text_area);

    JTextField search_field = new JTextField();
    search_field.getDocument().addDocumentListener(isearch);
    search_field.addActionListener(isearch);

    JFrame frame = new JFrame("Incremental Search Hack");
    frame.getContentPane().add("North",search_field);
    frame.getContentPane().add("Center",scroll);
    frame.pack();
    frame.show();
}
```

As the user types, the search selection will update on every keystroke. Return (or Enter) will jump to the next result, and Backspace will make the search less specific.

### 7.2.4. Hacking the Hack

You could expand this hack with support for case-insensitive searching, or allow users to type in mor

complicated regular expressions instead of straight text-matching. Because the component is built as an event listener, it's very easy to drop your search routines into existing applications. Event listener are probably the best way to add new features, such as incremental searching.



## Hack 49. Force Text Input into Specific Formats



Use Java's powerful pattern matching to enforce rules on typed input

Validating input is an important GUI task, and some applications will validate your input when you tap off a field or even validate it on every keystroke. After all, it's a lot easier to deal with bogus data by not letting it into your system in the first place.

One technique for validating user input is to use a regular expression and then evaluate the input against it. For example, a field that can be uppercase letters only must always match the expression `[A-Z]*`, and one that can be any combination of uppercase, lowercase, numbers, and spaces must match `[A-Za-z0-9]*` (notice the space after 9).

Java's regex feature lets you create `TextComponents` that enforce matching against an expression. The basic idea is to watch for changes in the underlying `Document` and do your pattern match then.

### 7.3.1. Constraining a Document

Hopefully, you won't be surprised to know that you don't need to touch the view classes `TextField`, `JTextArea`, etc. to add text constraint functionality. Text entry is happening in the model in other words the `Document` so that's where you tie in your regex code. This hack, listed in [Example 7-2](#), subclasses `PlainDocument` to run the regex check on every call to `insertString()`.

Example 7-2. A document allowing input that matches only a regex

```
import javax.swing.text.*;
import java.util.regex.*;

public class RegexConstrainedDocument extends PlainDocument {

    Pattern pattern;
    Matcher matcher;

    public RegexConstrainedDocument () { super(); }
    public RegexConstrainedDocument (AbstractDocument.Content c) { super(c); }
    public RegexConstrainedDocument (AbstractDocument.Content c, String p) {
        super (c);
        setPatternByString (p);
    }
}
```

```

public RegexConstrainedDocument (String p) {
    super();
    setPatternByString (p);
}

public void setPatternByString (String p) {
    Pattern pattern = Pattern.compile (p);
    // checks the document against the new pattern
    // and removes the content if it no longer matches
    try {
        matcher = pattern.matcher (getText(0, getLength()));
        System.out.println ("matcher reset to " +          getText (0, getLength()));
        if (! matcher.matches()) {
            System.out.println ("does not match");
            remove (0, getLength());
        }
    } catch (BadLocationException ble) {
        ble.printStackTrace(); // impossible?
    }
}

public Pattern getPattern() { return pattern; }

public void insertString (int offs, String s, AttributeSet a)
    throws BadLocationException {
    // consider whether this insert will match
    String proposedInsert =
        getText (0, offs) +
        s +
        getText (offs, getLength() - offs);
    System.out.println ("proposing to change to: " +
        proposedInsert);
    if (matcher != null) {
        matcher.reset (proposedInsert);
        System.out.println ("matcher reset");
        if (! matcher.matches()) {
            System.out.println ("insert doesn't match");
            return;
        }
    }
    super.insertString (offs, s, a);
}
}

```

This class holds onto a `Pattern` and a `Matcher` to perform the regex matching. The pattern can be set in the constructor, or later with a call to `setPatternByString()`. In either case, the method compiles the pattern and creates a `Matcher` with the `Document`'s text. Changing the pattern could, of course, create a mismatch with any existing text in the `Document`, so the `Matcher` immediately calls `matches()` and if the text does not match, it deletes all the text from the `Document`.

Perhaps the more typical case is when the `Document.insertString()` method is called. This will happen on every keystroke in a `JTextComponent`. Assuming the `Matcher` is not null, meaning that the `Pattern` has been set at some point, you simply need to call `Matcher.matches()` against the `Document`'s new contents to see if they comply with the regex constraints. If not, return early, never calling the superclass's `insert()` method, and thus disallowing the input.

## 7.3.2. Adding Constrained Text Fields

Since the `Document` isn't actually visible, you need to put it in something in order to test it. The `TestRegexConstrainedDocument` class creates a `JTextField` for you to type in a regular expression to enforce, and a longer `JTextField` for text to test. You create this latter `JTextField` with the seldom-seen constructor that takes a `Document`, an initial-value `String`, and a width (specified in columns). Obviously, you use a `RegexConstrainedDocument` for the first argument. There's also a `Set JButton` that takes the `String` value of the regex field and sets that as the new pattern to match the document against, with `RegexConstrainedDocument`'s `setPatternByString()` method. The rest is mostly layout code. The test class is shown in [Example 7-3](#).

### Example 7-3. GUI to test the `RegexConstrainedDocument` in a `JTextField`

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class TestRegexConstrainedDocument extends JPanel
    implements ActionListener {

    JTextField regexField, filterField;
    JButton regexButton;
    RegexConstrainedDocument regexDoc;

    public TestRegexConstrainedDocument() {
        setLayout (new BorderLayout (this, BorderLayout.Y_AXIS));
        // top - regex stuff
        JPanel topPanel = new JPanel();
        JLabel rLabel = new JLabel ("regex:" );
        topPanel.add (rLabel);
        regexField = new JTextField (20);
        topPanel.add(regexField);
        regexButton = new JButton ("Set");
        regexButton.addActionListener (this);
        topPanel.add (regexButton);
        add (topPanel);
        // bottom - filterfield
        regexDoc =
        new RegexConstrainedDocument ();
        filterField = new JTextField (regexDoc, "", 50);
        add (filterField);
    }
}
```

```

    }

    public void actionPerformed (ActionEvent e) {
    System.out.println ("actionperformed");
    if (e.getSource() == regexButton) {
        System.out.println ("regexbutton");
        regexDoc.setPatternByString (regexField.getText());
    }
    }

    public static void main (String[] args) {
    JComponent c = new TestRegexConstrainedDocument();
    JFrame f = new JFrame ("Regex filtering");
    f.getContentPane().add (c);
    f.pack();
    f.setVisible(true);
    }
    }

```

When run, the displayed GUI looks like [Figure 7-2](#). Notice that by using the regex `[A-Z ]*`, you can enter uppercase letters and spaces, but nothing else.

When you type a comma, a question mark, or lowercase letters, they are ignored.

## Figure 7-2. Filtering JTextField input with a regular expression

You can do smart things with this tool, but also really stupid things. Let's say you want to restrict input to the characters that will be in a North American phone number of the form 123-456-7890. You can set the pattern to `[0-9\-]*`, which will allow the user to type in only numbers and the hyphen.

Now you're feeling clever, but you don't like the fact that this still allows users to type patterns that aren't phone numbers, like `1111111` or `-1-1-1-1`. So, you set the pattern to an exact description of the phone number pattern:

```
[0-9]{3}-[0-9]{3}-[0-9]{4}
```

But now your users can't enter *anything*! Why? Because although that regular expression does specify the phone number pattern, no substring of it will ever match. This expression specifies exactly 12 characters, so when you type the first one, there's only one character it doesn't match the pattern so it's rejected.

The moral of the story here is to be thoughtful. You might decide to wire up a `FocusListener` so you

impose the regex pattern only when the user moves off the field, and change the "delete everything" behavior to something a little less forceful; for example, you could pop up a dialog telling the user that her input isn't in the right format. Just don't be surprised when regular expressions give you results that are logical, but sometimes unexpected.





## Hack 50. Auto-Completing Text Fields



Typing in a whole URL is a pain. When the user starts to type, complete his text with previously entered options, and let the user select one instead of typing the whole URL.

The auto-completing text field is instantly familiar from its use in browsers, where it is probably most needed. Nobody wants to have to try to type or for that matter even remember a huge URL to some page they've visited before, particularly not something like those Amazon.com URLs with inexplicable 20-digit numbers and bunches of seemingly arbitrary characters. On the other hand, not everything needs to be saved as a bookmark.

The text field that pops up a window of recently viewed sites is a happy compromise. It jogs your memory by showing you completion options, and it saves lots of typing by letting you simply click on one of the options and having that text inserted immediately into the text field.

### 7.4.1. A Self-Completing Text Field

This hack takes a `JTextField` and has it manage a `JWindow`, which contains a `JList` of possible completion values. The real work is done by an inner class that manages the list of completions and has a `javax.util.regex.Pattern` object to match each potential completion against the field's current text. [Example 7-4](#) is what you need to get going.

#### Example 7-4. A JTextField that manages a pop-up list of completions

```
import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;
import javax.swing.text.*;
import java.util.*;
import java.util.regex.*;

public class CompletableJTextField extends JTextField
    implements ListSelectionListener {

    Completer completer;
    JList completionList;
    DefaultListModel completionListModel;
    JScrollPane listScroller;
}
```

```

JWindow listWindow;

public CompletableJTextField (int col) {
    super (col);
    completer = new Completer();
    completionListModel = new DefaultListModel();
    completionList = new JList(completionListModel);
    completionList.setSelectionMode (ListSelectionMode.SINGLE_SELECTION);
    completionList.addListSelectionListener (this);
    listScroller =
        new JScrollPane (completionList,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_AS_NEEDED,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
    listWindow = new JWindow();
    listWindow.getContentPane().add (listScroller);
}

public void addCompletion (String s) {
    completer.addCompletion (s); }

public void removeCompletion (String s) {
    completer.removeCompletion (s); }

public void clearCompletions (String s ) {
    completer.clearCompletions (); }

public void valueChanged (ListSelectionEvent e) {
    if (e.getValueIsAdjusting()) { return; }
    if (completionList.getModel().getSize() == 0) {return;}
    listWindow.setVisible (false);
    final String completionString =
        (String) completionList.getSelectedValue();
    Thread worker = new Thread() {
        public void run() {
            setText (completionString);
        }
    };
    SwingUtilities.invokeLater (worker);
}

/** inner class does the matching of the JTextField's
    document to completion strings kept in an ArrayList
    */

class Completer implements DocumentListener {
    private Pattern pattern;
    private ArrayList completions;
    public Completer() {
        completions = new ArrayList();
        getDocument().addDocumentListener (this);
    }
}

```

```
public void addCompletion (String s) {
    completions.add (s);
    buildAndShowPopup();
}

public void removeCompletion (String s) {
    completions.remove (s);
    buildAndShowPopup();
}

public void clearCompletions () {
    completions.clear();
    buildPopup();
    listWindow.setVisible(false);
}

private void buildPopup() {
    completionListModel.clear();
    System.out.println ("buildPopup for " + completions.size() +
        " completions");
    Iterator it = completions.iterator();
    pattern = Pattern.compile (getText() + ".+");
    while (it.hasNext()) {
        // check if match
        String completion = (String) it.next();
        Matcher matcher = pattern.matcher (completion);
        if (matcher.matches()) {
            // add if match
            System.out.println ("matched "+ completion);
            completionListModel.add (completionListModel.getSize(),
                completion);
        } else {
            System.out.println ("pattern " + pattern.pattern() +
                " does not match " + completion);
        }
    }
}

private void showPopup() {
    if (completionListModel.getSize() == 0) {
        listWindow.setVisible(false);
        return;
    }
    // figure out where the text field is,
    // and where its bottom left is
    java.awt.Point los = getLocationOnScreen();
    int popX = los.x;
    int popY = los.y + getHeight();
    listWindow.setLocation (popX, popY);
    listWindow.pack();
    listWindow.setVisible(true);
}
```

```

private void buildAndShowPopup() {
    if (getText().length() < 1)
        return;
    buildPopup();
    showPopup();
}

// DocumentListener implementation
public void insertUpdate (DocumentEvent e) { buildAndShowPopup(); }
public void removeUpdate (DocumentEvent e) { buildAndShowPopup(); }
public void changedUpdate (DocumentEvent e) { buildAndShowPopup(); }

}
}

```

The `CompletableJTextField` constructor is responsible for setting up the `JList` and its model; for wiring up the field as a `ListSelectionListener`; and for packing the list into a `JScrollPane`, which sits in an initially invisible `JWindow`. It also creates an instance of the inner class `Completer`, which is responsible for managing the list of completions. Note that this version of the hack supplies only one of the typical `JTextField` constructor signatures; you'd probably want to provide others to make the component more convenient for callers.

There are three methods for adding, removing, and clearing completions, but these just decorate calls to the `Completer` inner class.

Skip ahead to the `Completer` at this point because it's the guts of the implementation. This class has an `ArrayList` of all the `Strings` to be considered as completions of the field text, and a regex `Pattern` to do matching. When you want to add and delete possible completions, you need to add or delete them from the `ArrayList` and then manage the `ListModel` in the outer class and show the `JWindow`. Clearing is similar, but you clear the `ListModel` and hide the window.

`buildModel()` is a convenience class to do the list model management. It starts by clearing the list model, then creates a regex `Pattern` with the field text, concatenated with `".* "`, which means the pattern is "what's in the field, plus zero or more other characters." To match against possible completions, you get an `Iterator` of them and then go through them, each time creating a `Matcher` of the field text and looking for a match. If it matches, add it to the list model.

With the list model rebuilt, you show the updated list to the user by rechecking the field's onscreen location, putting the window directly below that, and calling `setVisible(true)`.

The inner class also provides a `DocumentListener` implementation that simply rebuilds and shows the completion list window on any kind of change to the field's underlying `Document`.

Mouse clicks on the list in this window is handled by `valueChanged()` method in the outer class. Unfortunately, this has to deal with the fact that the choice of an item fires off a chain of `ListSelectionEvents`, only one of which you're interested in. The chain of events always begins with one for which `valueIsAdjusting` is `true`. This is meant to indicate that the user is dragging through the list to make multiple selections, and it is sent even though this list is single-select. At any rate, it's not the last event, so ignore it. Another selection event is sent when the list is cleared out and has no items; this isn't worth acting on, so ignore it, too. Having screened those cases out, you

should have a nonadjusting `ListSelectionEvent` and a non-zero list size.

You can hide the window at this point and look at the selection value. Since the `Completer` just puts `Strings` in the list model, you can pull out the selected value and set that as the text of the field. And you're done.

Well, not quite. If you call `setText()` directly in `valueChanged()`, you'll be thrown an `IllegalStateException`. The problem is that you're attempting to change the value of the `Document` while it's already being changed. In other words, firing off the `DocumentEvent` is part of the document edit that began with the user's keystroke that led to the completion menu appearing; this edit needs to complete before another is attempted. As you can see in this hack, the workaround is to create a worker thread to set the field with the clicked text, and to invoke that worker on a later cycle through the event loop. This arrangement returns immediately and lets the first edit finish, then sets the field later.

## 7.4.2. Test Out Auto-Complete

To test this class, you need to put the `CompletableJTextField` in a GUI and provide a way to give it some completions. The `TestCompletableJTextField` class in [Example 7-5](#) does just that, offering a second `JTextField` where you can enter strings that will be offered as completions to text typed into the `CompletableJTextField`. When run, the test GUI originally looks like [Figure 7-3](#).

### Example 7-5. A GUI to exercise the `CompletableJTextField`

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class TestCompletableJTextField extends JPanel
    implements ActionListener {

    CompletableJTextField completableField;
    JTextField completionField;

    public TestCompletableJTextField () {
        super();
        setLayout (new BorderLayout (this, BorderLayout.Y_AXIS));
        completableField = new CompletableJTextField (75);
        add (completableField);
        JPanel bottom = new JPanel ();
        bottom.add (new JLabel ("Completion:"));
        completionField = new JTextField (40);
        completionField.addActionListener (this);
        bottom.add (completionField);
        JButton addButton = new JButton ("Add");
        addButton.addActionListener (this);
        bottom.add (addButton);
        add (bottom);
    }
}
```


```

}

public void actionPerformed (ActionEvent e) {
    completableField.addCompletion (completionField.getText());
    completionField.setText ("");
}
public static void main (String[] main) {
    JFrame f = new JFrame ("Completions...");
    f.getContentPane().add (new TestCompletableJTextField());
    f.pack();
    f.setVisible (true);
}
}
}

```

Figure 7-3. Empty CompletableJTextField



To test things out, I added the addresses of some of O'Reilly's web sites: [www.onjava.com](http://www.onjava.com), [www.onlamp.com](http://www.onlamp.com), [www.java.net](http://www.java.net), and [webservices.xml.com](http://webservices.xml.com). [Figure 7-4](#) shows that after I type *w*, all four sites match.

Figure 7-4. All completions showing after typing one character

In [Figure 7-5](#), I type a second *w*; [webservices.xml.com](http://webservices.xml.com) no longer matches, so it disappears from the list.

As I continue my typing (*www.on*), only two matches remain, as seen in [Figure 7-6](#).

At this point, I clicked [www.onjava.com](http://www.onjava.com). This text is placed into the field and the list window disappears, as seen in [Figure 7-7](#).

Figure 7-5. One completion removed after typing two characters




Figure 7-6. Another completion removed after typing six characters



Figure 7-7. Text field filled in by clicking on completion from list

One question you might ask about this implementation is "why stuff a `JList` in a `JWindow` you have to manage, when you could just use a `JPopupMenu`?" Good question, but one with a pretty straightforward answer: the `JPopupMenu` is modal, so once it appears, clicking on it is the *only* option. That's not the desired behavior here, where clicking in the menu is optional, and the more likely circumstance at any time is that the user will continue typing. So, the better approach is to let her keep typing and just keep track of the possible completions.

## Hack 51. Write Backward Text



Baffle your friends by turning their text into its mirror image.

The fact that everything in Swing goes through the Java2D rendering pipeline makes it really easy to apply all sorts of effects to Swing components. Text offers some fun possibilities. For one, you can challenge the user by turning his text into a mirror image of itself.

### 7.5.1. Messing with JLabel

The easiest text component to distort is the simple `JLabel`. The `BackwardsJLabel` class in [Example 7-6](#) subclasses `JLabel` and uses an `AffineTransform` in the `paint()` method to do the flip.

#### Example 7-6. Rendering a JLabel as a mirror image

```
import java.awt.*;
import javax.swing.*;
import java.awt.geom.*;
import javax.swing.text.Document;
public class BackwardsJLabel extends JLabel {

    public BackwardsJLabel () { super(); }
    public BackwardsJLabel (Icon image) {super (image);}
    public BackwardsJLabel (Icon image, int align) {super (image, align);}
    public BackwardsJLabel (String text) { super (text);}
    public BackwardsJLabel (String text, Icon icon, int align) {
        super (text, icon, align);
    }
    public BackwardsJLabel (String text, int align) { super (text, align);}
    public void paint (Graphics g) {
        if (g instanceof Graphics2D) {
            Graphics2D g2 = (Graphics2D) g;
            AffineTransform flipTrans = new AffineTransform();
            double widthD = (double) getWidth();
            flipTrans.setToTranslation (widthD, 0);
            flipTrans.scale (-1.0, 1);
            g2.transform (flipTrans);
            super.paint(g);
        } else {
```



```

    super.paint(g);
  }
}

```

The constructors make trivial calls to their parent classes, so the key is the overridden `paint()` method. It first checks that you have a `Graphics2D` and does the cast. Any `Graphics2D` has an `AffineTransform` that defines transforms that are to be applied as the `Graphics2D` is rendered. The `AffineTransform` of a `Component` will usually have some important transforms already defined in it, so it's best not to replace its transform, but rather to use the `Graphics2D.transform()` method to modify the existing `AffineTransform` with one of your own making.

But what kind of transform do you want to do? A mirror image consists of two separate transformations: scaling the x-coordinates by a factor of -1 (flipping them around the axis, so that the pixels furthest to the right are now furthest to the left), and translating by the width of the component (so the pixels move from negative coordinates, where they wouldn't be seen, back into positive space). This transformation is illustrated in [Figure 7-8](#).

Figure 7-8. Mirror image as scale-and-translate `AffineTransform`

## 7.5.2. Mirror, Mirror on the Wall

The following `main()` method provides a trivial setup of a frame in which you can view the `BackwardsJLabel`. The result is shown in [Figure 7-9](#).

Figure 7-9. `JLabel` rendered as mirror image

```

public static void main (String[] args) {
    BackwardsJLabel field =
        new BackwardsJLabel ("Through the looking glass");
    JFrame frame = new JFrame("Backwards Text");
    frame.getContentPane().add (field);
}

```

```
frame.pack();  
frame.setVisible(true);  
}
```

Because the transformation is simple and limited to the `paint()` method, it seems like something you could do anywhere. You can easily create a `BackwardsJTextField` that uses exactly the same `paint()` method in a trivially overridden `JTextField` honestly, it's so trivial that it's not worth listing here; just set up the trivial "call `super`" constructors, copy over this `paint()` method, and tweak the `main()` method to show the text field instead of the label. The result will look like [Figure 7-10](#).

Figure 7-10. JTextField rendered as mirror image



This looks amusing and, when you type, the new text is indeed backward. But the novelty wears off quickly; messing with the display screws up the drawing of the caret and text highlighting, along with the handling of mouse clicks to set the insert point. In playing around with `JTextArea`, we found that we hosed word wrap, too, so we were stuck on the top line.

So, it's a cute trick, but let's reserve it for labels, OK?

## Hack 52. Use HTML and CSS in Text Components



Spruce up your plain JLabels and buttons using HTML and CSS effects, such as underlines, color, and even embedded tables.

You may know that you can display HTML using a subclass of `JTextPane`, but did you also know that Swing supports simple HTML and CSS in virtually every text component? As long as you can trick it into showing it as HTML instead of the markup, you can do some pretty nifty things.

### 7.6.1. Here's the Trick


Every text component in Swing can display HTML, but the component needs to *know* that the text is HTML, rather than a string that just happens to contain a bunch of angle brackets. Since there is no `setHTMLText(true)` method on `JTextComponent`, you have to resort to being a little trickier. If the string passed to the component's constructor (or `setText()`) method starts with `<html>`, then the component will switch to HTML mode. Here is a quick example:

```
JButton bla = new JButton("<html><i>my button</i>");
```

This code will produce a button that looks like [Figure 7-11](#).

Figure 7-11. Italic text

You don't need to match the `<html>` with an `</html>` tag at the end. Swing's HTML parser is pretty tolerant of malformed HTML, so for simple things you can just type whatever is shortest. The mode can only be set once, so if you put plain text into the component first and then HTML later, it will still be in plain text mode. You should note that slower computers will exhibit a noticeable delay the first time a component is shown with HTML. This is because Swing has to load up all of the `javax.swing.text.html` classes; however, they are cached for any further instances.



To avoid this initial delay, you could load a hidden component in a separate thread during program startup.

HTML can be used as a shortcut for text effects that would be cumbersome or impossible with standard `Font` objects. For example, `Font` doesn't provide a way to draw underlined text, but with HTML you can do this:

```
JLabel l1 = new JLabel("<html><u>underlined</u></html>");
```

This produces the text seen in [Figure 7-12](#).

Figure 7-12. Underlined text

HTML also lets you get multi-lined text and mixed fonts:

```
JButton b2 = new JButton("<html><i>my</i> button</html>");
```

This produces the button seen in [Figure 7-13](#).

Figure 7-13. Mixed styles

You can even add line break tags:

```
JLabel l2 = new JLabel("<html>my multi-<br>line text</html>");
```

Using this, you get the button seen in [Figure 7-14](#).

## Figure 7-14. Multi-lined text

You can use HTML in more than just labels and buttons. `JCheckBox`, `JRadioButton`, and even `JComboBox` support it. Here is an example of each:

```
JCheckBox cb1 = new JCheckBox("<html>The <i>real</i> thing");
JRadioButton rb1 = new JRadioButton(
    "<html>Even <font color=\"#ff0000\">better</font>");
String[] vals = { "<html><i>better</i>",
    "<html><u>yet again</u>" };
JComboBox combol = new JComboBox(vals);
```

This creates the collection of HTML-styled components seen in [Figure 7-15](#).

## Figure 7-15. Some other HTML components

Swing supports most features of basic HTML: paragraphs, lists, simple tables, and colors. It also supports basic CSS, which can give you greater control over borders, padding, and other visual attributes. This next example creates a header followed by list items of large colored text surrounded by a border. Since there is so much markup, I put it into a `StringBuffer` first:

```
StringBuffer sb = new StringBuffer();
sb.append("<html><head><style type='text/css'>");
sb.append("li { font-style: italic; font-size: 30pt; }");
sb.append("li { font-family: serif; color: #ff5555; }");
sb.append("ul { border-width: 4px; border-style: solid;
    border-color: #ff0000; } ");
    sb.append("ul { background-color: #ffeeee; }");
sb.append("</style></head>");
sb.append("<h3>H3 Header</h3>");
sb.append("<ul><li>large serifed text</li><li>as list items</li>");
```

```
sb.append("</html>");

JLabel l3 = new JLabel(sb.toString());
```

This produces the label seen in [Figure 7-16](#).

Figure 7-16. Borders and lists



There is no definitive list of every CSS layout feature the `HTMLToolkit` supports, but you can get a good overview in the JavaDoc for the `javax.swing.text.html.CSS` class.

CSS also gives you the ability to define a style and reuse it with multiple components, putting you one step closer to the kind of separation of content and style that we take for granted on the Web. In this example, both labels share the same CSS declaration. If you change the declaration, it would change both labels. This declaration could even be stored in a properties file, letting non-programmers affect the look of your application:

```
StringBuffer css = new StringBuffer();
css.append("<html><head><style type='text/css'>");
css.append("body { color: #4444ff; font-weight: normal;}");
css.append("</head><body>");

JLabel l4 = new JLabel(css+"Cartman");
JLabel l5 = new JLabel(css+"Stan");
```

This produces the labels seen in [Figure 7-17](#).

Figure 7-17. Shared CSS styles

Putting HTML in Swing components is a little-known feature that packs a big punch. You can use it to quickly create layout effects that are cumbersome or impossible to do with traditional text.



## Hack 53. Use Global Anti-Aliased Fonts



Think Swing apps always look ugly because of the chunky fonts? Finally, you can do something about it!

Java 1.2 introduced Java2D, complete with the ability to draw anti-aliased text. Unfortunately, anti-aliasing is off by default and turning it on requires a programmatic change on each UI component. This hack shows how to turn on anti-aliasing for an entire frame without customizing each component. It also introduces a special repaint manager that is the key to several other hacks in this book, such as the partial translucent menus [\[Hack #12\]](#).

### 7.7.1. The Problem

To turn on anti-aliasing, you simply need to set a rendering hint:

```
Graphics2D g2 = (Graphics2D)g;
g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
    RenderingHints.VALUE_ANTIALIAS_ON);
```

Unfortunately, the `Graphics` object is not very long-lived. There is no global place to set a hint because there's a new `Graphics` object for every `repaint()`. Any property you set would be gone by the next paint call. The usual workaround is to subclass the component you want to anti-alias and override the `paint()` method:

```
class AAButton extends JButton {
    public void paint(Graphics g) {
        Graphics2D g2 = (Graphics2D)g;
        g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
            RenderingHints.VALUE_ANTIALIAS_ON);
        super.paint(g2);
    }
}
```

This will work, but it means you have to create a custom subclass for *every component in your application*. Not a very appealing solution.



Mac OS X provides anti-aliased rendering through a system property, but this only works because Apple thoughtfully added it to their JVM. Developers on other platforms are left out. Java 5.0 provide a standard system property for anti-aliasing, but that doesn't help the millions of 1.3 and 1.4 JVMs out there. Another option would be to use some form of code injection to modify each paint method at the bytecode level, but this requires an AOP tool, custom build scripts, and other things that are probably overkill for such a simple feature. There has to be a better way and there actually is.

A long, long time ago (in a research lab far, far away) I worked on a scalable UI toolkit for Java called SubArctic. One of its key features was that a component would paint onto a canvas object called a `Drawable` what we would call a `Graphics` object in Swing. This `Drawable` would be passed from parent to child in a recursive tree traversal. `Drawables` could be hacked to do all sorts of complicated things, and since a child always drew on the `Drawable` from its parent, the parent could make a change without the child knowing about it. Thus, you could create a parent panel that rotated all graphics by 45 degrees and a standard child component (like a button or scrollbar) would work without modification. This scheme was incredibly flexible. We had hacks for drop shadows, bit-level operations (blur, sharpen, b/w), affine transformations (rotate, shear), or just about any other crazy idea you could come up with. I have long wanted to do this in Swing, but there has always been one obstacle: in Swing, a child's `paint()` method is not always called by its parent's `paintChildren()` method.

Swing provides three sub-paint methods: `paint()` calls `paintBackground()`, `paintComponent()`, and `paintChildren()`, passing a `Graphics` object to each. Ideally, if you over rode `paintChildren()` in a custom panel class to add the rendering hint, then all of the children would draw anti-aliased text. Then you could just make this custom panel be the root of your frame and the rendering hint would magically apply to all of the children in the window. This would be one change per frame, instead of one per component (a definite improvement).

That sounds all nice and good, except that it doesn't work. The assumption that a child's `paint()` method is always called by its parent's `paintChildren()` method is wrong. Swing lies! In an effort to speed up rendering, Swing tracks which components have changed and need redrawing. They are, in Swing parlance, marked as *dirty*. The system repaints all of the dirty components and leave the others untouched. If Swing detects that a child component is dirty, but that its parent is not, then it will jump directly to the child's `paint()` method, bypassing the parent's `paintChildren()` method completely. Crummy, huh?

You could work around this by marking each component with `setOpaque(false)`. Then, Swing would have no guarantee that the component covers its parent completely, and the parent would have to be repainted as well. Unfortunately, `setOpaque()` was really meant for custom components, and standard widgets like `JButton` may draw erratically if opacity changes. To make matters worse, this varies by L&F, something you don't want to account for. In addition, you would have to call `setOpaque(false)` on every component in the application. This is less intrusive than subclassing, but still a huge amount of work. Next option, please!

What you really want to do is just have the entire component hierarchy be marked dirty when any component changes. Then the whole frame will be repainted, and each child's `paint()` method will be called from its parent's `paintChildren()` method, making the anti-aliased panel idea work. The key to this strategy is a little-known class called the `RepaintManager`.

`RepaintManager` is a Swing utility class used to track the dirty components in a window and to tell Swing what to repaint. The guys at Sun Microsystems made this a public class to facilitate debugging not for the strange hack we are about to attempt, but strange hacks are the point of this book, so let's get started.

`RepaintManager` has a lot of methods, but we're only interested in one of them: `addDirtyRegion()`, which is called each time a component wants to make a portion of itself dirty. The version seen in [Example 7-7](#) will still mark it dirty, but then it will mark the entire frame dirty as well, triggering a full `repaint()`.

## Example 7-7. Tricking RepaintManager

```
import javax.swing.RepaintManager;
import javax.swing.JComponent;
import java.awt.Container;

public class FullRepaintManager extends RepaintManager {
    public void addDirtyRegion(JComponent comp, int x, int y, int w,
        int h) {
        super.addDirtyRegion(comp, x, y, w, h);
        JComponent root = getRootJComponent(comp);
        // to avoid a recursive infinite loop
        if(comp != root) {
            super.addDirtyRegion(root, 0, 0, root.getWidth(),
                root.getHeight());
        }
    }
    public JComponent getRootJComponent(JComponent comp) {
        Container parent = comp.getParent();
        if(parent instanceof JComponent) {
            return getRootJComponent((JComponent)parent);
        }
        return comp;
    }
}
```

The `addDirtyRegion()` implementation first calls the super version and then looks for the highest ancestor that is still an instance of `JComponent` (because you don't really want the frame itself marked dirty). Then, it calls `addDirtyRegion()` a second time on the root component, marking the entire window dirty. Once this is done, the repaint thread will take over and repaint the entire window, ensuring that any custom `JPanel` hacks (in this case, setting the anti-aliased rendering hint) will be handled normally. By creating a custom repaint manager like this, you now have a reusable tool to use in other hacks.

Now that we have our full screen repainting, let's use it. [Example 7-8](#) is the code to an `AntiAliasedPanel` along with a simple `main()` method for testing.

## Example 7-8. Testing out anti-aliasing on a global scale

```
public class AntiAliasedPanel extends JPanel {
```

```
public void paintChildren(Graphics g) {
    Graphics2D g2 = (Graphics2D)g;
    g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
        RenderingHints.VALUE_ANTIALIAS_ON);
    super.paintChildren(g2);
}
public static void main(String[] args) {
    RepaintManager.setCurrentManager(new FullRepaintManager());
    JPanel panel = new AntiAliasedPanel();
    JFrame frame = new JFrame("Hack 100: Anti-Aliased text");
    frame.getContentPane().add(panel);

    JLabel label = new JLabel("This is anti-aliased text");
    label.setFont(label.getFont().deriveFont(40f));
    panel.add(label);

    frame.pack();
    frame.setVisible(true);
}
}
```

`AntiAliasedPanel` is just a standard `JPanel` subclass with the `paintChildren()` method overridden to turn on anti-aliasing. The `main()` method first sets the current `RepaintManager` to the custom version. Then it creates a `JFrame` with the `AntiAliasedPanel` as its root, adding a `JLabel` with large type. [Figure 7-18](#) shows what the anti-aliased label looks like. I've also shown a standard label in [Figure 7-19](#) for comparison.

Figure 7-18. With anti-aliasing

Figure 7-19. Without anti-aliasing

The disadvantage of this scheme is that we have defeated all of Swing's speed optimizations, but I think it's worth it for the possibilities we've opened up. This hack just sets the anti-aliasing rendering

hint, but we could also use custom `JPanels` to do other things with the `Graphics` object, such as blurring, rotation, or animation. For more examples of this approach, take a look at the partially translucent menus [\[Hack #48\]](#) and custom tool tip [\[Hack #43\]](#) hacks.



## Hack 54. Anti-Aliased Text Without Code



Draw anti-aliased text without any code changes at all using two clever tricks introduced in Java 5.0.

Since Java 1.2, UI programmers can draw anti-aliased text. Unfortunately, anti-aliasing must be enabled for every Swing component by writing a few lines of code for each of them [[Hack #53](#)]. This hack describes a clever way to turn on anti-aliasing for an entire frame by adding a customized repaint manager. As every programmer seeks for effortless solutions, we will discover how to do the same without writing any lines of code.

### 7.8.1. The Java 5.0 Trick

Sun Microsystems released Java 5.0, a.k.a. Tiger, in September 2004. Among many improvements, like a new theme for the Metal L&F, this release of J2SE paves the way for application-wide text anti-aliasing support in Mustang, the upcoming release of Java. To this end, the Swing team added a special field in the hidden class `com.sun.java.swing.SwingUtilities2`. Meant for internal purposes only, this class is left undocumented by Sun's engineering teams.

If you look closely at its source code, provided in *src.zip* with Sun's JVM, you'll discover a very interesting method: `drawTextAntialiased(JComponent c)`. This method returns a `boolean` value used by Swing's painting framework to know whether the specified component must be drawn with anti-aliased text. Here is its complete source code:

```
private static boolean drawTextAntialiased(JComponent c) {
    if (!AA_TEXT_DEFINED) {
        if (c != null) {
            return ((Boolean)c.getClientProperty(
                AA_TEXT_PROPERTY_KEY)).booleanValue();
        }
        return false;
    }
    return AA_TEXT;
}
```

As you can see, there are two ways to enable anti-aliased text. In the first case, the static variable `AA_TEXT_DEFINED` is set to false, and a check is performed against the component's properties. Hence, a component in which the property `AA_TEXT_PROPERTY_KEY` is set to true will be anti-aliased. You can

set this property to a given component with the following line of code:

```
myComponent.putClientProperty(SwingUtilities2.AA_TEXT_PROPERTY_KEY,  
    new Boolean(true));
```

Add this line of code in any of your applications, compile it, and launch it with J2SE 5.0 and you'll see the magic happen. While extremely useful, this trick is not enough since we sure don't want to do that for every component instance in our UI. The source code of `drawTextAntialiased()` gives us a clue to understand how to globally enable anti-aliased text. When `AA_TEXT_DEFINED` is set to true, the value `AA_TEXT` is returned. Both are defined at the beginning of *SwingUtilities2.java*.

```
static {  
    fontCache = new LSBCacheEntry[CACHE_SIZE];  
    Object aa = java.security.AccessController.doPrivileged(  
        new GetPropertyAction("swing.aatext"));  
    AA_TEXT_DEFINED = (aa != null);  
    AA_TEXT = "true".equals(aa);  
    AA_FRC = new FontRenderContext(null, true, false);  
}
```

The variables we are interested in are computed according to the value of the object `aa`. This object is the value of a JVM property called `swing.aatext`, and it is supposed to be a `String` object. `AA_TEXT_PROPERTY_KEY` is true only when this property has been set, and `AA_TEXT` is true when the value of the property is the `String` value "true". Given this information, we just need to set the `swing.aatext` property of the JVM to enable anti-aliasing. This can be done on the command line with the help of the `D` switch, as in this example:

```
javaDswing.aatext=true WebHunter
```

[Figure 7-20](#) is what an application looks like with `swing.aatext` properly set. I have also shown a screenshot of the same application without this property for comparison (in [Figure 7-21](#)).

Figure 7-20. Anti-aliased text with J2SE 5.0 `swing.aatext` property



This trick is very useful and extremely simple to set up. Best of all, it requires no change in the source code of the application, allowing use of it even with applications you did not write. Unfortunately, this hack has two major drawbacks. First, it works only with Sun's J2SE 5.0 and is not guaranteed to be available with other vendors' implementations. Also, remember that `SwingUtilities2` is an undocumented and hidden class for which no support will ever be provided. This means that it can be changed without notice. Using it might break your applications in a future release of Java.

Figure 7-21. Anti-aliased text without J2SE 5.0 swing.aatext property

*Romain Guy*

## Hack 55. Anti-Aliased Text with a Custom Look and Feel



Another way to get smooth text is to use a custom Look and Feel to avoid the fragile Java 5.0 APIs.

When the Java 5.0 anti-aliasing trick [[Hack #54](#)] was first discovered, some discussions arose on the Web. Many people strongly disagree with using it because it can be broken at any time by Sun Microsystems. Should we be deprived of anti-aliased text because of such a silly problem? Frédéric Lavigne, author of the famous Skin L&F and webmaster of [www.javootoo.com](http://www.javootoo.com), a great repository of Look and Feels for Swing, didn't think so and found an elegant and clever way to get the same result

### 7.9.1. The Wrap Look and Feel

His idea is to use a custom Look and Feel whose sole purpose is to enable anti-aliasing hints on the `Graphics` instances used to draw the UI. He implemented his idea in the Wrap Look and Feel, which can be downloaded at [wraplf.l2fprod.com](http://wraplf.l2fprod.com). Another Look and Feel, SmoothMetal, enables anti-aliasing in your application. Yet, you are stuck with Metal Look and Feel when using it. Wrap Look and Feel acts as a decorator for the current Look and Feel. Thus, you can choose any Look and Feel you want and wrap it with Wrap Look and Feel to enable anti-aliasing. Doing so requires a single line of code:

```
import com.l2fprod.common.swing.plaf.wrap Wrapper;  
Wrapper.wrap();
```

No matter which Swing Look and Feel you set, the `wrap()` method will handle it properly. One line of code is good, but not good enough. We'd be better off with no line of code at all. Frédéric feels the same way and provides the excellent `Wrapit` class you can use to install the Wrap Look and Feel at runtime:

```
java -classpath wraplf.jar;. Wrapit WebHunter
```

The `Wrapit` class contains a `main()` entry point that will install the Wrap Look and Feel and then call the `main()` entry point of the class passed as the first argument on the command line. This Look and Feel is a powerful tool you can use to enhance the appearance of any Java application, whether you have the source code or not.



*Romain Guy*



[← PREV](#)

# Chapter 8. Rendering

[Section 8.1. Hacks 5664: Introduction](#)

[Hack 56. Create a Magnifying Glass Component](#)

[Hack 57. Create a Global Right-Click](#)

[Hack 58. Block a Window Without a Modal Dialog](#)

[Hack 59. Create a Color Eyedropper](#)

[Hack 60. Changing Fonts Throughout Your Application](#)

[Hack 61. Load New Fonts at Runtime](#)

[Hack 62. Build a Colorful Vector-Based Button](#)

[Hack 63. Add a Third Dimension to Swing](#)

[Hack 64. Turn the Spotlight on Swing](#)

[← PREV](#)

## 8.1. Hacks 5664: Introduction

Sometimes it's not what you put into your GUI, but how you draw it. The hacks in this chapter are based in some way on using (or abusing) how AWT and Swing render the graphic contents of a GUI. In several cases, we use Java2D to bring graphic transformations and color-handling to Swing components. In others, we use AWT's font handling to change components; not just `JTextComponents`, but any components that need to draw text to render themselves. And in still other cases, we mess with the process by which Swing renders its contents.

[← PREV](#)

## Hack 56. Create a Magnifying Glass Component



Zoom in on those pixels with a little creative abuse of the AWT's debugging-oriented `Robot` class.

Some graphics programs use a component that shows a magnified view of what the cursor is currently hovering over. This can be very helpful for doing pixel-accurate editing of a picture.

It should be simple enough to do in Swing get pixels from one component and put them in another but there are some missing pieces. Specifically, how do you get the pixels out of the source component as an `Image` so you can `drawImage()` them into the magnified component? You could do this if you owned the source component and set it up with a double-buffer because creating the offscreen buffer would require creating an `Image`, which is exactly what you needed anyway. But for an arbitrary `JComponent`, you can't assume that level of access to the source's pixels.

But there's another option back in AWT: the `Robot` class, introduced in J2SE 1.3. It has a `createScreenCapture()` method that can grab the screen, or just part of it, and return it as a Java2D `BufferedImage`. This is what we need to get things going.

### 8.2.1. Build the Magnifying Glass

The `DetachedMagnifyingGlass` will need to keep track of the `Component` it's viewing, the current mouse location in that component, a zoom factor, and its own size. It will also need an instance of the AWT `Robot` for taking screen grabs. The other thing it needs to do is to have a `MouseMotionListener`, so that it will get updates on the cursor's position and, when it changes, do a new grab and `repaint()`.

The `DetachedMagnifyingGlass` code is shown in [Example 8-1](#).

Example 8-1. `JComponent` to provide a magnified view of another `JComponent`

```
public class DetachedMagnifyingGlass extends JComponent
    implements MouseMotionListener {

    double zoom;
    JComponent comp;
    Point point;
    Dimension mySize;
```

```
Robot robot;

public DetachedMagnifyingGlass (JComponent comp,
    Dimension size,
    double zoom) {

    this.comp = comp;
    // flag to say don't draw until we get a MouseEvent
    point = new Point (-1, -1);
    comp.addMouseListener(this);
    this.mySize = size;
    this.zoom = zoom;
    // if we can't get a robot, then we just never
    // paint anything
    try {

        robot = new Robot();
    } catch (AWTException awte) {
        System.err.println ("Can't get a Robot");
        awte.printStackTrace();
    }
}

public void paint (Graphics g) {
    if ((robot == null) || (point.x == -1))
    {
        g.setColor (Color.blue);
        g.fillRect (0, 0, mySize.width, mySize.height);
        return;
    }
    Rectangle grabRect = computeGrabRect();
    BufferedImage grabImg = robot.createScreenCapture (grabRect);
    Image scaleImg =
        grabImg.getScaledInstance (mySize.width, mySize.height,
            Image.SCALE_FAST);

    g.drawImage (scaleImg, 0, 0, null);
}

private Rectangle computeGrabRect() {
    // width, height are size of this comp / zoom
    int grabWidth = (int) ((double) mySize.width / zoom);
    int grabHeight = (int) ((double) mySize.height / zoom);
    // upper-left corner is current point
    return new Rectangle (point.x, point.y, grabWidth, grabHeight);
}

public Dimension getPreferredSize() { return mySize; }
public Dimension getMinimumSize() { return mySize; }
public Dimension getMaximumSize() { return mySize; }

// MotionEventListener implementations
```

```

public void mouseMoved (MouseEvent e) {
    Point offsetPoint = comp.getLocationOnScreen();
    e.translatePoint (offsetPoint.x, offsetPoint.y);
    point = e.getPoint();
    repaint();
}
public void mouseDragged (MouseEvent e) {
    mouseMoved (e);
}
}

```

Looking at the code, the constructor takes the source component, a size for the magnified component, and a zoom level. It assigns these to its instance variables, and sets up a `MouseListener` to get updates regarding the cursor position, which is initialized to a "don't pain me" dummy value of (-1, -1). It also builds the `AWTRobot`. Since this can fail on some OSes or under certain security situations, the `robot == null` case will have to be handled gracefully in the painting routine.

The `paint()` method begins by checking for the two conditions that indicate the magnified component can't be painted: if there's no `Robot` or if the cursor has never entered the source component. In either of these cases, the magnified component simply fills itself with blue and returns.

On the other hand, if valid data is available, the magnifier needs to figure out what portion of the source component to grab. For simplicity, you can compute a rectangle whose upper left is the current cursor location. The width and height of the rectangle are computed by multiplying the zoom factor by the magnifying component's height and width. So, for a zoom of `1.0`, the grab is exactly the size of the magnifier. For a zoom of `0.5`, it grabs half the width and half the height, and for `2.0`, it grabs twice the width and height.

With a grab rectangle calculated, call `Robot.createScreenCapture()` to grab those pixels and return them as a `BufferedImage`. Unless your zoom factor is `1.0`, this image will be larger or smaller than the `DetachedMagnifyingGlass` component, so you need to use `getScaledInstance()` to scale it to your component size. In terms of a scaling behavior, the code uses the `SCALE_FAST` constant because the moving mouse will be calling for many repaints, and thus many grabs and scales, every second. Finally, with your properly sized image in memory, you paint to the `Graphics` to get the grabbed data into your component.

One TODO item I haven't shown here, but that might provide a performance boost, would be to `flush()` the various temporary images after you've called `drawImage()`.

To ensure the AWT `LayoutManagers` respect the size that's set for the component, have `getPreferredSize()`, `getMinimumSize()`, and `getMaximumSize()` all return the size that was originally sent to the constructor, since the size of the magnifier component is critical in computing what to grab from the source component.

The last bit of code in this class is a `MouseListener`, which is used to track the mouse's location.

You need to do this so you'll always have an up-to-date point when the `paint()` method is called. You'll only get events when the cursor is over the source component, and it's easy enough to cache the point in the `MouseEvent`, but there's a catch: that point is relevant to the coordinate system of the source component, not the screen, so unless the component is at the upper-left corner of the screen, you will be grabbing the wrong pixels in `paint()`. The fix is to translate the point from the source component's coordinate system to the screen's coordinate system. Do this by getting the component's onscreen location with `getLocationOnScreen()`, and then translate the Point with `MouseEvent.translate()`.

## 8.2.2. Testing the Magnifier Out

To take `DetachedMagnifyingGlass` out for a spin, [Example 8-2](#) shows a `TestDetachedMagnifyingGlass` class, which opens an image in a `JFrame` and sets a `DetachedMagnifyingGlass` next to it.

### Example 8-2. Testing the MagnifyingGlassComponent

```
public class TestDetachedMagnifyingGlass extends Object {

    public TestDetachedMagnifyingGlass(File f) {
        // image frame
        ImageIcon i = new ImageIcon (f.getPath());
        JLabel l = new JLabel (i);

        JFrame imgFrame = new JFrame ("Image");
        imgFrame.getContentPane().add(l);
        imgFrame.pack();
        imgFrame.setVisible(true);
        // magnifying glass frame
        JFrame magFrame = new JFrame ("Mag");
        DetachedMagnifyingGlass mag =
            new DetachedMagnifyingGlass (l, new Dimension (150, 150), 2.0);
        magFrame.getContentPane().add (mag);
        magFrame.pack(); magFrame.setLocation (new Point (
            imgFrame.getLocation().x + imgFrame.getWidth(),
            imgFrame.getLocation().y));
        magFrame.setVisible(true);
    }

    public static void main (String[] args) {
        JFileChooser chooser = new JFileChooser();
        chooser.showOpenDialog(null);
        File f = chooser.getSelectedFile();
        new TestDetachedMagnifyingGlass (f);
    }
}
```

This class simply brings up a `JFileChooser` to pick an image file, which it loads into an `ImageIcon` and then into a `JLabel`. It then creates a `DetachedMagnifyingGlass` from the `JLabel`, with a size of 150 x 150 and a magnification factor of 2.0, and moves it to the immediate right of the source component.

[Figure 8-1](#) shows what the test looks like when run.

Figure 8-1. Use of the `DetachedMagnifyingGlass`



### 8.2.3. Hacking the Hack

The only problem with the Robot approach is that it doesn't limit itself to capturing from the source component; it'll take any onscreen pixels from any application. That means that when you approach the edges of the source component, you can pick up pixels from the desktop or other apps, as seen in [Figure 8-2](#).

Figure 8-2. Capturing pixels outside of the target component





Is this a problem? Some users will mind it, some won't. To get rid of it, you'll need to smarten up `computeGrabRect()` to bounds-check its right and bottom edges (the top left is the cursor position, so it can never overshoot the top or left of the component) by adding the untranslated point to the proposed grab width and seeing if that is greater than the width of the source component, and then doing the same for the height. This will take some refactoring, since `computeGrabRect()` doesn't have access to the untranslated point. Also, if you're not necessarily going to be painting the entire magnified component every time, you'll have to erase it at the top of `paint()`, so you don't have "crud" from the previous repaint left over after this repaint.

## Hack 57. Create a Global Right-Click



Give your application a right-click context menu without having to add a listener to every component.

Oftentimes, an application needs to have a pop-up menu that is accessible from more than one component. Sometimes the entire window should be right-clickable. Unfortunately, doing this the normal way in Swing would require adding a mouse listener to every component in the window, which isn't a very appealing solution, especially if your UI code is spread across many classes. It would be much nicer if there were a single place to add the context menu. This hack shows how to use a single glass pane to provide a right-clickable menu to the entire application.

A glass pane is an invisible `JComponent` that covers an entire `JFrame`. The glass pane can be used to catch events or draw on top of the rest of the application. For this hack, we will use a glass pane to capture right-click events and trigger a pop up, alleviating the need to register a mouse listener with every component in the frame. The basic idea is for the glass pane to intercept all mouse events and forward them on to the application, except for the right-click. Right-clicks will trigger the pop-up menu instead. This way there is only one listener per frame, instead of potentially hundreds.

To start off, you need a component that has a reference to the content pane of the frame and a pre-built pop-up menu. This is the beginning of just such a class:

```
public class RightClickGlassPane extends JComponent
    implements MouseListener, MouseMotionListener {

    private JPopupMenu popup;
    private Container contentPane;

    public RightClickGlassPane(Container contentPane, JPopupMenu menu) {
        addMouseListener(this);
        addMouseMotionListener(this);
        this.contentPane = contentPane;
        popup = menu;
    }

    public void paint(Graphics g) {
    }

    // catch all mouse events and redispach them
    public void mouseMoved(MouseEvent e) {
        redispachMouseEvent(e, false);
    }
}
```

```

public void mouseDragged(MouseEvent e) {
    redispatchMouseEvent(e, false);
}
public void mouseClicked(MouseEvent e) {
    redispatchMouseEvent(e, false);
}
public void mouseEntered(MouseEvent e) {
    redispatchMouseEvent(e, false);
}
public void mouseExited(MouseEvent e) {
    redispatchMouseEvent(e, false);
}
public void mousePressed(MouseEvent e) {
    redispatchMouseEvent(e, false);
}
public void mouseReleased(MouseEvent e) {
    redispatchMouseEvent(e, false);
}

```

In the `RightClickGlassPane` constructor, the code saves a reference to the content pane and pop-up menu that were passed into it. Then it registers itself as both a `MouseListener` and `MouseMotionListener` so that it can capture all mouse events and send them to the `redispatchMouseEvent()` method. The `RightClickGlassPane` also overrides the `paint()` method to do nothing, ensuring that the glass pane is invisible.

The `redispatchMouseEvent()` method is the key to the right-click glass pane. It must first check for a right-click (actually the pop-up trigger, which will also handle Control-click on the Mac), and then either show the pop up at the mouse location or forward the event to the correct component. Event forwarding is the hard part.

Each mouse event contains the current mouse coordinates, along with the state of the mouse buttons and any modifier keys (such as Control or Shift). Mouse coordinates are always relative to the component being clicked. This means that a 10,10 position relative to a `JButton` in the middle of the screen wouldn't be the same location as 10,10 relative to another `JButton` lower down on the screen. In order to account for coordinate differences, `redispatchMouseEvent()` needs to convert between coordinate systems using the `SwingUtilities.convertPoint()` method:

```

private void redispatchMouseEvent(MouseEvent e, boolean repaint) {

    // if it's a pop up
    if(e.isPopupTrigger()) {
        // show the pop up and return
        popup.show(e.getComponent(), e.getX(), e.getY());
    } else {
        // since it's not a pop up we need to redispatch it.
        // get the mouse click point relative to the content pane
        Point containerPoint = SwingUtilities.convertPoint(this,
            e.getPoint(), contentPane);
    }
}

```

```

// find the component that is under this point
Component component = SwingUtilities.getDeepestComponentAt(
    contentPane, containerPoint.x, containerPoint.y);

// return if nothing was found
if (component == null) {
    return;
}

// convert point relative to the target component
Point componentPoint = SwingUtilities.convertPoint(
    this, e.getPoint(), component);

// redispach the event
component.dispatchEvent(new
    MouseEvent(component, e.getID(),
        e.getWhen(), e.getModifiers(),
        componentPoint.x, componentPoint.y,
        e.getClickCount(), e.isPopupTrigger()));
}
}

```

In the else statement, the current mouse position is converted to be relative to the `contentPane`, which is at the root of the window. Next, the method determines which component was clicked using the `SwingUtilities.getDeepestComponentAt()` method, and then it converts the point to be relative to the target component. Finally, it uses a special method on `Component` called `dispatchEvent()`, which will rebroadcast a new mouse event to the target component as if it were the original event. The target component will never know the difference; it just won't ever receive right-clicks. The following `main()` method creates a sample screen with a few widgets and the custom `RightClickGlassPane`:

```

public static void main(String[] args) {
    // create a frame with some components in it
    JFrame frame = new JFrame("Right Click Test");
    JButton button = new JButton("this is a button");
    JTextField tf = new JTextField("this is a textfield");
    JPanel panel = new JPanel();
    panel.add(button);
    panel.add(tf);
    frame.getContentPane().add(panel);

    JPopupMenu popup = new JPopupMenu();
    popup.add(new JMenuItem("Dogs"));
    popup.add(new JMenuItem("Cats"));
    popup.add(new JMenuItem("Mass Hysteria"));

    // create the right-click glass pane.
    Component rc = new RightClickGlassPane(frame.getContentPane(), popup);
    // set as glasspane and make it visible
}

```

```
frame.setGlassPane(rc);  
rc.setVisible(true);  
  
// pack and show the frame  
frame.pack();  
frame.setSize(400,200);  
frame.show();  
  
}
```

While most of this is boilerplate, be sure to notice the call to `rc.setVisible()`. This is where the glass pane is turned on. If the glass pane is not visible, then your code won't ever receive events and work its magic.

This hack only demonstrates intercepting a mouse click, but it could be used for any other type of event capturing, such as remapping one key to another, recording mouse events, blocking mouse events [\[Hack #58\]](#), or creating completely synthetic events to fool the program.



## Hack 58. Block a Window Without a Modal Dialog



Block the input in a single window during long operations without stopping your entire application.

Since the dawn of GUIs, most toolkits have had the concept of a modal dialog box. This is a small window that restricts input to itself, blocking access to the rest of the program (or entire operating system in some cases). Modal windows often produce the desired effect, but sometimes you need a window that can block itself without blocking access to the whole application. The most common use for such a window is a long running process, like rendering frames of a movie or waiting for the network to respond. In this case, you would like to let the user still interact with the rest of the application but block the one window that represents the work in progress. Swing doesn't provide a modal window like this, but since when has that stopped us?

### 8.4.1. Blocking Basics

To block a window, you could disable the components within it, but then you would need to recursively find each component and disable it manually. This is a big headache, and would make for a very ugly window (all those grayed-out components). All you really want to do is capture all input to the window and block that. Swing provides a great way to do this: the glass pane. The glass pane sits on top of all other components in a window, making it the perfect place to implement blocking behavior.

Since you want your glass pane to be transparent, it's best to start with a plain `JComponent` that doesn't draw anything. [Example 8-3](#) defines a `WindowBlocker` class that extends `JComponent` and implements the `MouseListener` (a compound interface that combines the `MouseListener` and `MouseMotionListener`).

#### Example 8-3. Listening for mouse events

```
public class WindowBlocker extends JComponent
    implements MouseInputListener {

    public WindowBlocker() {
        addMouseListener(this);
        addMouseMotionListener(this);
    }
}
```

```

public void mouseMoved(MouseEvent e) {
}
public void mouseDragged(MouseEvent e) {
}
public void mouseClicked(MouseEvent e) {
}
public void mouseEntered(MouseEvent e) {
}
public void mouseExited(MouseEvent e) {
}
public void mousePressed(MouseEvent e) {

    Toolkit.getDefaultToolkit().beep();
}
public void mouseReleased(MouseEvent e) {
}

```

So far, the code is pretty simple. The `WindowBlocker` catches all mouse events and does nothing, sending the events to that great bit bucket in the sky. When the user presses the mouse, the computer will beep, indicating that the window is busy. The component still won't actually receive events because it is invisible by default. When you are ready to start blocking events, you should make the component visible. That's where the `block()` method comes in:

```

private Cursor old_cursor;
public void block() {
    old_cursor = getCursor();
    setCursor(Cursor.getPredefinedCursor(Cursor.WAIT_CURSOR));
    setVisible(true);
}

public void unBlock() {
    setCursor(old_cursor);
    setVisible(false);
}

```

Before setting the component to visible, you should save the current mouse image and then change it to a busy cursor. The cursor will only be in effect over the component you call `setCursor()` on, so only the blocked window will get the busy signal. All other windows will still use their normal cursors. When `unblock()` is called, you can restore the cursor and hide the `WindowBlocker` component again.

## 8.4.2. Build a Test Process

To test the window blocker, you will need some sort of long-running process. The class in [Example 8-4](#), `LongProcess`, will start a 10-second countdown when its `actionPerformed()` method is called. It will also print the current time left in a status label. Note that the call to `setText()` on the status label is

inside of a `SwingUtilities.invokeLater()` method. This makes sure that `setText()` is called from the Swing event thread, avoiding any threading issues or deadlock.

### Example 8-4. Filling up clock cycles

```
class LongProcess implements ActionListener, Runnable {
    JLabel status;
    WindowBlocker blocker;
    public LongProcess(JLabel status, WindowBlocker blocker) {
        this.blocker = blocker;
        this.status = status;
    }

    public void actionPerformed(ActionEvent evt) {
        blocker.block();
        new Thread(this).start();
    }

    public void setText(final String text) {
        SwingUtilities.invokeLater(new Runnable() {
            public void run() {
                status.setText(text);
            }
        });
    }

    public void run() {
        for(int i=10; i>0; i--) {
            // set the label
            final String text = "("+i+") seconds left";
            setText(text);

            // sleep for 1 second
            try {
                Thread.currentThread().sleep(1000);
            } catch (Exception ex) {
            }
        }
        // set the final status string
        setText("Process Complete");
        blocker.unBlock();
    }
}
```

### 8.4.3. Putting It All Together



With your window blocking and long-process classes ready, you can put them together in a simple program. The `main()` method in [Example 8-5](#) creates a text area, a button, and a status label. Then it makes a `WindowBlocker` and installs it with `frame.setGlassPane()`. The `LongProcess` is added as an action listener to the Start button, so when the user presses Start Processing, the process will launch and call `WindowBlocker.block()`. Once the process ends, it will call `WindowBlocker.unBlock()`, releasing the window.

### Example 8-5. Testing the blocking window

```
public static void main(String[] args) {
    JFrame frame = new JFrame("Blocking Window");
    JTextArea jta = new JTextArea(10,40);
    JScrollPane scroll = new JScrollPane(jta);
    JButton start = new JButton("Start Processing");
    JLabel status = new JLabel("status");

    WindowBlocker blocker = new WindowBlocker();
    frame.setGlassPane(blocker);
    start.addActionListener(new LongProcess(status,blocker));

    Container comp = frame.getContentPane();
    comp.add("North", start);
    comp.add("Center", scroll);
    comp.add("South", status);

    frame.pack();
    frame.show();
}
```

## Hack 59. Create a Color Eyedropper



Enhance your color pickers with an eyedropper tool that grabs a color from anywhere on the screen.

Most paint tools give you an eyedropper, but I've never seen a Java program do it. Getting a screen pixel requires native access, which is usually blocked off from Java programs. Java 1.3 introduced a new method to the `Robot` class, `getPixelColor()`, which can retrieve the color anywhere on the screen. The problem is that you don't get mouse events once the cursor leaves your `JFrame`. This is fine if you only want to select colors from your own application, but a color chooser needs to select from anywhere on the screen. Java 5.0 introduces new APIs for getting complete mouse events, but that doesn't help us today.

The answer to this tricky problem, of course, is to cheat! This hack makes a screenshot and then paints it into a `JFrame` called `ColorChooserDemo`, which fills the entire screen. The screenshot is indistinguishable from the real desktop except that nothing in the background updates. However, since the screenshot is only needed while the user selects a color, this should be OK. `ColorChooserDemo` also has a `JLabel` in the center of the screen, which displays the currently selected color. Once the user has finished selecting a color by releasing the mouse, the entire frame will disappear and the component that launched the chooser usually a `JButton` will get the color through `setBackground()`. While it's running, `ColorChooserDemo` looks like [Figure 8-3](#).

Figure 8-3. Running the `ColorChooserDemo`

The first step is to set up the required components. The `ColorChooserDemo` is a subclass of `JFrame` with member variables to hold the screenshot (`background_image`), the panel to draw the image (`image_panel`), the `JLabel` to display the current color under the cursor (`label`), and a few support variables. The beginnings of this class are shown in [Example 8-6](#).

### Example 8-6. Skeleton of the `ColorChooserDemo` class

```
public class ColorChooserDemo extends JFrame
    implements MouseListener, MouseMotionListener {

    JPanel image_panel;
    Dimension screen_size;
    JComponent comp = null;
    Image background_image = null;
    Robot robot;
    JLabel label;

    public ColorChooserDemo(JComponent comp) {
        // get the screen dimensions
        screen_size = Toolkit.getDefaultToolkit().getScreenSize();

        // set up the frame (this)
        this.addMouseListener(this);
        this.addMouseMotionListener(this);
        this.comp = comp;
        this.setUndecorated(true);
        this.setSize(screen_size.width, screen_size.height);

        // set up the panel that holds the screenshot
        image_panel = new JPanel() {
            public void paintComponent(Graphics g) {
                super.paintComponent(g);
                g.drawImage(background_image, 0, 0, null);
            }
        };
        image_panel.setPreferredSize(screen_size);
        this.getContentPane().add(image_panel);

        // set up the display label
        label = new JLabel("Selected Color");
        label.setOpaque(true);
        label.setSize(100, 100);
        image_panel.setLayout(null);
        image_panel.add(label);
        label.setLocation((int)screen_size.getWidth()/2 - 50,
            (int)screen_size.getHeight()/2 - 50);
    }
}
```

In its constructor, the `ColorChooserDemo` accepts a `JComponent` to store the selected color in. Next, the code gets the current screen size from the AWT Toolkit, and then follows the usual litany of listeners and setters. Note the call to `setUndecorated(true)`, which turns off the window controls. This adds to the illusion that the user is clicking on the real system desktop and not a screenshot.

The `image_panel` is a standard `JPanel` with the `paintComponent()` method overridden to draw the screenshot image over its background. It is also set to fill the screen with `setPreferredSize(screen_size)`, and then is added to the frame.

Before returning, the `ColorChooserDemo` constructor creates a 100 x 100 pixel `JLabel` to display the current selected color. By default, the label would let its parent component (the screenshot) show through instead of filling its background with the selected color, so the code calls `setOpaque(true)` to make sure the background is visible. Finally, the label is moved to the middle of the screen, calculated by dividing the screen dimensions in half and subtracting half of the label size. Of course a `LayoutManager` would mess with the explicit coordinates set here, so `image_panel`'s layout is set to `null`. This gets rid of the default layout manager, `BorderLayout`, and allows the absolute positioning to work.

Now that the chooser frame and its components are set up, the frame needs to make the actual screenshot. `ColorChooserDemo` overrides the `show()` method to make the screenshot before the frame pops up on screen. The `show()` method uses the `robot.createScreenCapture()` to capture and save the screen to the `background_image` variable before passing control to the superclass, as shown in the following code:

```
public void show() {
    try {
        // make the screenshot before showing the frame
        Rectangle rect = new Rectangle(0,0,
            (int)screen_size.getWidth(),
            (int)screen_size.getHeight());
        this.robot = new Robot();
        background_image = robot.createScreenCapture(rect);
        super.show();
    } catch (AWTException ex) {
        System.out.println("exception creating screenshot:");
        ex.printStackTrace();
    }
}
```

Once the `ColorChooserDemo` frame is visible, the user can begin selecting colors by clicking and dragging anywhere on the (now fake) screen. The `mousePressed()`, `mouseDragged()`, and `mouseReleased()` methods of the mouse/mouse-motion listener implementation update the selected color on each mouse event. `setSelectColor()` does the actual update by setting the background color on both the label (which the user can see) and the component that was passed into the constructor (currently hidden behind the frame):

```
// update the selected color on mouse press, dragged, and release
public void mousePressed(MouseEvent evt) {
```

```

    setSelectedColor(robot.getPixelColor(evt.getX(), evt.getY()));
}
public void mouseDragged(MouseEvent evt) {
    setSelectedColor(robot.getPixelColor(evt.getX(), evt.getY()));
}
// for released we want to hide the frame as well
public void mouseReleased(MouseEvent evt) {
    setSelectedColor(robot.getPixelColor(evt.getX(), evt.getY()));
    this.setVisible(false);
}
// update both the display label and the component that was passed in
public void setSelectedColor(Color color) {
    comp.setBackground(color);
    label.setBackground(color);
}

// no-ops for the rest of the mouse-event listener
public void mouseClicked(MouseEvent evt) { }
public void mouseEntered(MouseEvent evt) { }
public void mouseExited(MouseEvent evt) { }
public void mouseMoved(MouseEvent evt) { }

```

When the user releases the mouse, the `mouseReleased()` method will do one last color update and then hide the frame. This way, when the user is done selecting a color, the final color will be visible a the background of the launching component, as seen in [Figure 8-4](#).

### Figure 8-4. After a color is chosen

Launching the demo just requires a component to call `show()` on the `ColorChooserDemo`:

```

public static void main(String[] args) {
    JFrame frame = new JFrame("Color Chooser Hack");
    final JButton button = new JButton("Click to choose a color");
    button.addActionListener(new ActionListener() {
        public void actionPerformed(ActionEvent evt) {
            JFrame frame = new ColorChooserDemo(button);
            frame.show();
        }
    });

    frame.getContentPane().add(button);
    frame.pack();
}

```

```
frame.setVisible(true);  
}
```

And that's it! Now you can add full-screen color choosing to any component without requiring native access at all. As an improvement, you could make the preview actually show a magnified view of where the cursor is instead of just the selected color.



## Hack 60. Changing Fonts Throughout Your Application



Get a quick font face-lift, without having to write a whole Look and Feel.

With no standards documents to obey and more flexible user expectations, web designers get much more freedom with their fonts than Swing developers expect. They get to set font styles with CSS, while we're expected to just leave well enough alone. Sure, you can change fonts on a component-by-component basis with `setFont()`, but it's not like you can just say "from now on, I want all `JLabels` to use the Cheese Deluxe Demi-Bold font." Well, OK, you could create a subclass of `JLabel` to set that font in its constructor, but your change wouldn't be picked up by any of `JLabel`'s subclasses, like the default renderers for list, table, and tree cells. Fortunately, there is a much easier way than fighting with single inheritance.

Swing components get many of their defaults (e.g., fonts, icons, borders), from a `Hashtable` owned by the `UIManager` class. Actually, it is a subclass of `Hashtable`, called `UIDefaults`, which offers strongly typed methods like `getFont()`, `getBorder()`, `getColor()`, etc., each of which takes a key object.

Now, since this is just a `Hashtable`, you can put stuff in just as easily as you can get it out. All you have to do is know what the key is. As it turns out, for fonts, the keys are `Strings` that end with a `.font` suffix. So, for demonstration purposes, you can iterate through the keys of the `UIDefaults`, and every time you find one that ends in `.font`, put the `Font` of your choice back into the `UIDefaults`.

### 8.6.1. Changing the Default Fonts

The goal of the `ChangeAllFonts` example is to change the default font of all Swing components, by changing all the appropriate keys it can find in `UIDefaults`. It starts by getting a font name from the command line and creating a 12-point plain `Font` instance.

Next, it gets the `UIDefaults` object as a `Hashtable` and gets an `Enumeration` of its keys. It walks the enumeration and, for every key ending in `.font`, it uses `put()` to replace the previous font with the user-selected font.

Finally, it creates a simple GUI with several typical `JComponents` and shows them in a `JFrame`. This short example is shown in [Example 8-7](#).

#### Example 8-7. Changing default fonts via UI Defaults

```
public class ChangeAllFonts {
```

```
final static String[] LIST_ITEMS =
{ "JList", "with", "new Font" };

public static void main (String[] args) {
    try {
        // get user's font
        if (args.length < 1) {
            System.out.println (
                "Usage: ChangeAllFonts font-name");
            return;
        }
        String fontName = args[0];
        Font font = new Font (fontName, Font.PLAIN, 12);

        // put this font in the defaults table for every
        // ui font resource key
        Hashtable defaults = UIManager.getDefaults();
        Enumeration keys = defaults.keys();
        while (keys.hasMoreElements()) {

            Object key = keys.nextElement();
            if ((key instanceof String) &&
                (((String) key).endsWith(".font"))) {
                System.out.println (key);
                defaults.put (key, font);
            }
        }

        // now bring up a GUI to show this off
        JPanel panel = new JPanel();
        panel.setLayout (new BorderLayout (panel, BorderLayout.Y_AXIS));
        panel.add (new JLabel ("JLabel with font " + fontName));
        panel.add (new JTextField ("JTextField with font " +

            fontName));
        panel.add (new JButton ("JButton with font " +
            fontName));
        JList list = new JList (LIST_ITEMS);
        JScrollPane pane =
            new JScrollPane (list,
                ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
                ScrollPaneConstants.HORIZONTAL_SCROLLBAR_NEVER);
        panel.add (pane);

        JFrame frame = new JFrame ("Changing default fonts");
        frame.setDefaultCloseOperation (WindowConstants.EXIT_ON_CLOSE);
        frame.getContentPane().add(panel);
        frame.pack();
        frame.setVisible(true);
    } catch (Exception e) {
        e.printStackTrace();
    }
}
```



```
}
}
```

## 8.6.2. Fonts 'R' Us

To run the code, you specify the name of your desired font on the command line as the only argument to the class. If the font you want to use has one or more spaces in its name, you'll need to enclose the font name in quotes, as in the example:

```
cadamson% java ChangeAllFonts "Comic Sans MS"
```


This produces a GUI whose components all use the 12-point plain Comic Sans MS font, as seen in [Figure 8-5](#).

Figure 8-5. Changing default fonts for Swing widgets

You should also note the standard output when running this example, since the code prints out every `.font` key it finds. The output is too long to list here, but the first few items look like this:

Table 8-1.

<code>CheckBox.font</code>	<code>ToolBar.font</code>
<code>tree.font</code>	<code>ColorChooser.font</code>
<code>Viewport.font</code>	<code>ToggleButton.font</code>
<code>ProgressBar.font</code>	<code>Panel.font</code>
<code>RadioButtonMenuItem.font</code>	<code>TextArea.font</code>
<code>FormattedTextField.font</code>	



These are all `JComponents`, but they're notably lacking the "J" that starts the name of typical Swing components (`tree.font` for `Jtree`, `TextArea.font` for `JTextArea`, etc.).

Now that you know the keys for the `UIDefaults` table, instead of blindly changing all of them to the same font, you can customize a look by applying different fonts or different sizes and styles of one or two base fonts to different widgets.

← PREV

## Hack 61. Load New Fonts at Runtime



Who cares what fonts your users have? Bundle the fonts you want your application to use and load those fonts dynamically!

Using fonts with any predictability used to be a nightmare in Java. For a while, you could only depend on having access to one serif, one sans-serif, and one monospaced font, and the constants you'd use to get those fonts changed between Java 1.0 and 1.1. Fortunately, you're now free to use any font installed on the user's machine and load it by name.

Of course, not everyone has the same fonts. Even different installations of the same operating system will have different fonts available. I still use some TrueType fonts I've been toting from machine to machine for 15 years, and it's a safe bet that very few other people will have those same fonts.

This would seem to limit your Swing application to using only the fonts you know are installed with an operating system—maybe Arial and Times New Roman on Windows, Lucida Grande and Palatino on Mac OS X, etc. But it's not so. You can load font files at runtime and make them available to your Java application, even if the font isn't installed on the user's machine.

### 8.7.1. The Wonders of `createFont()`

Using dynamically loaded fonts comes down to a single, critical, often overlooked AWT method in the `Font` class: `createFont()`. This method, introduced in Java 1.3, takes two parameters: a font format (as an `int`), which to date has no legal value other than `Font.TRUETYPE_FONT`, and an `InputStream`.

This stream is typically a `FileInputStream` from a `.tff` TrueType file, or some equivalent. By equivalent, I meant that you could presumably put the font on the network and get a stream from a `URL` or put the font file inside a `jar`, find it along the classpath with `ClassLoader.getResourceAsStream()`, and load from that.

Mac OS X's font suitcase is a holdover from the Classic Mac OS aren't supported. Your fonts need to be in `.tff` files.

`FontLoadingDemo`, shown in [Example 8-8](#), offers a straightforward application of this font-loading technique. It takes the path to a `.tff` file as its command-line argument, creates an `InputStream`, and creates a `Font`. It then derives a plain, 32-point instance of the font, and uses that to put a sample `JLabel` in a `JFrame`.

## Example 8-8. Loading fonts at runtime

```
public class FontLoadingDemo {

    public static void main (String[] args) {
        try {
            // get font from path in args[0]
            if (args.length < 1) {
                System.out.println (
                    "usage: FontLoadingDemo path-to-ttf");
                return;
            }
            File f = new File (args[0]);
            FileInputStream in = new FileInputStream (f);
            Font dynamicFont =
                Font.createFont (Font.TRUETYPE_FONT, in);
            Font dynamicFont32Pt =
                dynamicFont.deriveFont (32f);

            // draw something with it
            JLabel testLabel =
                new JLabel ("Dynamically loaded font \"" +
                    dynamicFont.getName() + "\"");
            testLabel.setFont (dynamicFont32Pt);
            JFrame frame = new JFrame ("Font Loading Demo");
            frame.getContentPane().add (testLabel);
            frame.pack(); frame.setVisible(true);
        } catch (Exception e) {
            e.printStackTrace();
        }
    }
}
```


### 8.7.2. Testing Font Loading

All you need to run this demo is a `.ttf` file of a TrueType font, preferably one not already installed on your system so you'll know that the demo works. There are many free and shareware fonts on the Web; I found the Marriage Script font at <http://www.free-fonts.com/>. Once you have a `.ttf` file, run the demo like this:

```
cadamson% java FontLoadingDemo marriage_script.ttf
```

Running the demo pops up a window like the one seen in [Figure 8-6](#).

Figure 8-6. Marriage font loaded on the fly



With this technique, and a consistent scheme for bundling your application resources (i.e., stuffing all your fonts in a JAR file, perhaps with other resources like images, sounds, and localizations), you have the freedom to use whatever fonts you like in your GUI, without worrying about what end users do or don't have installed.

[← PREV](#)

## Hack 62. Build a Colorful Vector-Based Button



Build a resolution-independent OS X-style button using scalable graphics code.

The button in this hack is *resolution independent*, meaning that it can resize and rescale automatically as the user's windows and display change, stretching and tiling the graphics to fill the new space. The button doesn't depend on being any particular size to look good. As higher-quality and higher resolution monitors become more common, users will start to expect attractive interfaces that scale and reflow with their increasingly expansive displays. This hack shows how to create an attractive `JButton` that will scale with both size and resolution, opening the door for a completely vector drawn Swing Look and Feel.

### 8.8.1. Use Scaling to Your Advantage

Since this button must scale with the size of the screen, you can use a variable called `scale`. Every piece of drawing code for this button is done relative to `scale`'s value. If the scale value changes, the entire button will change accordingly. The scale value itself is based on the current font size of the component. If the component's font is resized (due to a DPI change, for example), then the scale value will change accordingly, resizing the entire button. With a scale value in place, this hack is simply a matter of recreating the Aqua button look with Java2D calls. The goal is a button that looks like [Figure 8-7](#).

Figure 8-7. A green vector JButton

Not a simple task, but it's not impossible either. All the work is done in [Example 8-9](#).

#### Example 8-9. Creating liquid buttons

```
public class VectorButton extends JButton implements MouseListener {
    public VectorButton() {
```

```

    this.addMouseListener(this);
}
public Dimension getPreferredSize() {
    String text = getText();
    FontMetrics fm = this.getFontMetrics(getFont());
    float scale = (50f/30f)*this.getFont().getSize2D();
    int w = fm.stringWidth(text);
    w += (int)(scale*1.4f);
    int h = fm.getHeight();
    h += (int)(scale*.3f);
    return new Dimension(w,h);
}
public void paintComponent(Graphics g) {
    Graphics2D g2 = (Graphics2D)g;
    g2.setRenderingHint(RenderingHints.KEY_ANTIALIASING,
        RenderingHints.VALUE_ANTIALIAS_ON);
    g2.setColor(this.getBackground());
    g2.fillRect(0,0,this.getWidth(),this.getHeight());

    float scale = (50f/30f)*this.getFont().getSize2D();

    drawLiquidButton(this.getForeground(),
        this.getWidth(), this.getHeight(),
        getText(), scale,
        g2);
}

```

The previous code is the essence of `VectorButton`. It is just a subclass of `JButton`, overriding `getPreferredSize()` and `paintComponent()` and adding a mouse listener implementation.

A custom version of `getPreferredSize()` is required because, by default, a `JButton` will size itself based on the current Look and Feel. For this hack, we want the button sized based on the scale value. You can see that scale is calculated by multiplying the current font size against a scaling factor. I chose the factor 50/30 by testing different values and simply seeing what looked right. The actual factor doesn't matter as long as you're consistent, which is why scale is calculated the same way for both `getPreferredSize()` and `paintComponent()`. The `paintComponent()` method just turns on anti-aliasing, fills the background, calculates scale, and then calls `drawLiquidButton()` where the real work is done.

`drawLiquidButton()` is a wrapper for a series of custom drawing functions that create each part of the liquid button. In order to emulate the Aqua look, you'll need to use a series of rounded rectangles and gradient fills.

To make the code more understandable, I broke it up into functions for the shadow, body, text, highlight, and border.

As you go through the code, you will notice that scale is multiplied by a small adjustment value like

0.1f or 0.04f. These numbers were chosen largely through trial and error, just by trying different values to see what looked good. Finding those values took a long time but really added to the quality of the finished button. If you decide to build your own vector widget, it will really pay to spend the time tweaking your drawing, too. Here's the method implementation:

```
protected void drawLiquidButton(Color base,
    int width, int height,
    String text, float scale,
    Graphics2D g2) {

    // calculate inset
    int inset = (int)(scale*0.04f);
    int w = width - inset*2 - 1;
    int h = height - (int)(scale*0.1f) - 1;

    g2.translate(inset,0);
    drawDropShadow(w,h,scale,g2);

    if(pressed) {
        g2.translate(0, 0.04f*scale);
    }

    drawButtonBody(w,h,scale,base,g2);
    drawText(w,h,scale,text,g2);
    drawHighlight(w,h,scale,base,g2);
    drawBorder(w,h,scale,g2);

    if(pressed) {
        g2.translate(0, 0.04f*scale);
    }
    g2.translate(-inset,0);
}
```

The `inset` value used represents the space between the start of the button and the upper left of the real `JButton` boundaries. Without an inset, the drawn button would be too close to the component borders, and the shadow would get cut off. The test for `if(pressed)` translates everything but the shadow just a tiny bit down. This will create the pressed-in effect common to buttons in most Look and Feels.

Next comes the different drawing functions. The shadow is created by overlapping two rounded rectangles with different shades of gray and alpha. Using an alpha value allows the shadows to blend well:

```
protected void drawDropShadow(int w, int h,
    float scale, Graphics2D g2) {
    g2.setColor(new Color(0,0,0,50));
    fillRoundRect(g2,
        (-.04f)*scale,
```



```

    (.02f)*scale,
    w+.08f*scale, h+0.08f*scale,
    scale*1.04f, scale*1.04f);
g2.setColor(new Color(0,0,0,100));
fillRoundRect(g2,0,0,0.06f*scale,w,h,scale,scale);
}

```

The body of the button is a gradient that goes from top to bottom. Since the developer could change the color of the button, the gradient is calculated from darker and lighter versions of the base color. The body has two parts. The outer round rectangle forms the bulk of the button, while the inner round rectangle is smaller and lighter, creating a subtle glowing effect:

```

protected void drawButtonBody(int w, int h, float scale,
    Color base, Graphics2D g2) {

    Color grad_top = base.brighter();
    Color grad_bot = base.darker();
    GradientPaint bg = new GradientPaint(
    new Point(0,0), grad_top,
    new Point(0,h), grad_bot);
    g2.setPaint(bg);

    this.fillRoundRect(g2,
    (0)*scale,
    (0)*scale,
    w,h,1*scale,1*scale);

    // draw the inner color
    Color inner = base.brighter();
    inner = alphaColor(inner,75);
    g2.setColor(inner);
    this.fillRoundRect(g2,

    scale*(.4f),
    scale*(.4f),
    w-scale*.8f, h-scale*.5f,
    scale*.6f,scale*.4f);
}

// generate the alpha version of the specified color
protected static Color alphaColor(Color color, int alpha) {
    return new Color(color.getRed(), color.getGreen(),
    color.getBlue(), alpha);
}

```

Finally, you get to handle the actual drawing of the text. The text position is calculated by centering the width and height of the text based on the current font metrics. The text is actually drawn twice:

first with a translucent gray offset by a few pixels, and then again in black. This creates a very slight drop shadow on the text itself, making it appear raised above the button surface:

```
protected void drawText(int w, int h, float scale,
    String text, Graphics2D g2) {

    // calculate the width and height
    int fw = g2.getFontMetrics().stringWidth(text);
    int fh = g2.getFontMetrics().getAscent()
        + g2.getFontMetrics().getDescent();
    int textx = (w-fw)/2;
    int texty = h/2 + fh/2;

    // draw the text
    g2.setColor(new Color(0,0,0,70));
    g2.drawString(text, (int)((float)textx+scale*(0.04f)),
        (int)((float)texty + scale*(0.04f)));
    g2.setColor(Color.black);
    g2.drawString(text, textx, texty);

}
```

The highlight is another set of round rectangles, this time going from mostly opaque to completely transparent. Since they are drawn after the text, the highlight will appear to float above the button, giving it a glossy sheen. Finally, a black border is drawn around the entire button in `drawBorder()`.

```
protected void drawHighlight(int w, int h, float scale,
    Color base, Graphics2D g2) {

    // create the highlight
    GradientPaint highlight = new GradientPaint(
        new Point2D.Float(scale*0.2f, scale*0.2f),
        new Color(255,255,255,175),
        new Point2D.Float(scale*0.2f, scale*0.55f),
        new Color(255,255,255,0)
    );
    g2.setPaint(highlight);
    this.fillRoundRect(g2, scale*0.2f, scale*0.1f,
        w-scale*0.4f, scale*0.4f, scale*0.8f, scale*0.4f);
    this.drawRoundRect(g2, scale*0.2f, scale*0.1f,
        w-scale*0.4f, scale*0.4f, scale*0.8f, scale*0.4f);
}

protected void drawBorder(int w, int h,
    float scale, Graphics2D g2) {

    // draw the border
```

```

g2.setColor(new Color(0,0,0,150));
this.drawRoundRect(g2,
    scale*(0f),
    scale*(0f),
    w,h,scale,scale);
}

```

You may have noticed in the code some calls to `fillRoundRect()` instead of `Graphics2D.fillRoundRect()`. All of this code deals with `floats`, and the `Graphics2D` version of the round rectangle methods only take `ints`. Rather than fill the code with a million `(int)` casts, it's just easier to perform a few casts in the `fillRoundRect()` and `drawRoundRect()` utility methods:

```

// float version of fill round rect
protected static void fillRoundRect(Graphics2D g2,
    float x, float y,
    float w, float h,
    float ax, float ay) {

    g2.fillRoundRect(
        (int)x, (int)y,
        (int)w, (int)h,
        (int)ax, (int)ay

    );
}

// float version of draw round rect
protected static void drawRoundRect(Graphics2D g2,
    float x, float y,
    float w, float h,
    float ax, float ay) {

    g2.drawRoundRect(
        (int)x, (int)y,
        (int)w, (int)h,
        (int)ax, (int)ay

    );
}

```

Finally, you may have noticed the `pressed` boolean in `drawLiquidButton()`. `JButton` provides a way of knowing when the button has been selected, but there is no way to know when it is pressed or released during the clicking process. Most applications have no need for this information, but because this hack involves rendering changes, you'll need to know the `pressed` state in order to draw the button properly. Since `JButton` doesn't tell you the current state, you have to detect it with a mouse listener that looks for press and release events:

```
/* mouse listener implementation */
protected boolean pressed = false;
public void mouseExited(MouseEvent evt) { }
public void mouseEntered(MouseEvent evt) { }
public void mouseClicked(MouseEvent evt) { }
public void mouseReleased(MouseEvent evt) {
    pressed = false;
}
public void mousePressed(MouseEvent evt) {
    pressed = true;
}
```

## 8.8.2. Hacking the Hack

The `VectorButton` takes an awful lot of drawing code. This isn't so much because it scales, but simply because recreating the work of Apple's talented graphic designers with Swing code is difficult. One possible improvement would be to use SVG files instead of direct Java2D code. This would let you develop the actual look of the button in a graphics program instead of the slow code/compile/run cycle we are all used to as programmers. It would also let you pass the work on to a real graphic designer while you focus on speed and functionality.

`VectorButton` shows the potential of vector-based interfaces, but it's just the tip of the iceberg. Imagine if you had an entire Look and Feel based on vectors, where all the buttons scaled according to the font size. Then you could change the font size to scale the entire application while it's running! You could even do proper DPI calculations based on the physical size and shape of the user's screen to make your application look identical on any device, scaling from PDAs all the way up to high resolution HDTVs.

## Hack 63. Add a Third Dimension to Swing




User interfaces have stuck to 2D drawing for many years. Today, Swing and Java3D give you a chance to go one step further and add 3D widgets to your UI.

Have you ever wondered how to add nice 3D components into your Swing applications? Java3D is a free API provided by Sun Microsystems for Linux and Windows, and by Apple for Mac OS X, that lets you create 3D scenes. Although well documented, Java3D seems impossible to use with Swing at least at first glance.

### 8.9.1. The Problems with Java3D

Imagine you decided to create a new, astonishing application called AmazonPick that would let the user search for books on the Amazon.com store. Your eye-candy user interface would even display the currently selected book as a 3D object; whenever the user selects another book, the 3D object would flip to show the new cover on its opposite side. [Figure 8-8](#) shows how the application should look.

Figure 8-8. AmazonPick shows books as full 3D objects



Unfortunately, you won't be able to obtain these results without a little imagination. For instance, take a close look at [Figure 8-8](#) and notice the gradient background of the window. Displaying such a background is very easy with Swing and the opaque properties of Swing components, as seen in the rather simple class in [Example 8-10](#).

### Example 8-10. A demo program for 3D components

```
public BooksDemo()
{
    super("AmazonPick");

    JButton cover1 = UIHelper.createButton("", "cover1_small_button", true);
    JButton cover2 = UIHelper.createButton("", "cover2_small_button", true);
    JButton cover3 = UIHelper.createButton("", "cover3_small_button", true);

    JPanel buttons = new JPanel();
    buttons.add(cover1);
    buttons.add(cover2);
    buttons.add(cover3);
    buttons.setOpaque(false);

    setContentPane(new GradientPanel());
    getContentPane().setLayout(new BorderLayout());
    getContentPane().add(buttons, BorderLayout.SOUTH);
}
```

```

pack();
setResizable(false);
setDefaultCloseOperation(EXIT_ON_CLOSE);

UIHelper.centerOnScreen(this);
}

```

This code creates three buttons, each containing a picture of a book loaded by the utility class `UIHelper`, and then puts them in a `JPanel`. This panel is itself added to the content pane of the window, at the south side. With the help of the `setContentPane()` method, the default content pane is replaced by a new panelan instance of `GradientPanel` that is capable of drawing a nice gradient. To make sure the gradient remains visible in the buttons panel, you need to make the panel transparent. This can be achieved easily by calling `setOpaque(false)`, which will prevent the component in our case, the panel from drawing its background, letting underlying components shine through.

Now, we have to take a slight diversion into AWT and Swing vagaries. With J2SE, you can use two different graphical toolkits to create an application: AWT and Swing. The main difference between those two is that AWT widgets are heavyweight whereas Swing widgets are lightweight. These names come from the very nature of these components. Whatever platform you are running your application on, AWT widgets are drawn using the underlying OS native toolkit. Swing, on the contrary, is completely decoupled from the OS and all the painting is done by Java itself. As a result, AWT widgets are the least common denominator between the various operating systems supported by Java. This also means that advanced features like transparency are pure fantasy with AWT: Swing lets you create transparent components very easily, but AWT does not.

The bad news is that Java3D offers an AWT component only, `Canvas3D`, to display a 3D scene. So you'll have to mix some Swing and AWT code. Here is how you can add such a component in the Swing UI:


```

Canvas3D c3d = new Canvas3D(SimpleUniverse.getPreferredConfiguration());
c3d.setSize(CANVAS3D_WIDTH, CANVAS3D_HEIGHT);
getContentPane().add(centerPanel, BorderLayout.CENTER);
createScene();

```

`createScene()` is responsible for building the 3D scene the `Canvas3D` will display. Running this code will produce a rather ugly result, as shown in [Figure 8-9](#).

Figure 8-9. A Canvas3D cannot be made transparent



As you can see, you end up with a black background in the `Canvas3D`. Because the only way to get rid of a component's background is to call `setOpaque(false)` which is defined by `JComponent` and thus isn't available to AWT components you are stuck with this ugly background. Indeed, as a lightweight component, the canvas cannot be made transparent. Things get even worse when you try to add a menu bar to the application because of the order in which components are painted: lightweight first, heavyweight next. [Figure 8-10](#) shows an example of what happens when a pop-up menu is drawn by Swing. Because it is a lightweight component, it is drawn before `Canvas3D`, when it should be drawn after the canvas.

Figure 8-10. Lightweight components are drawn behind heavyweight components

Thankfully, this new problem (it's all AWT's fault!) was so annoying that the Swing team decided to add a workaround for it. You can simply force all pop-up menus of your applications to be created as heavyweight components instead of lightweight components. A single line of code is enough to fix the



problem:

```
JPopupMenu.setDefaultLightWeightPopupEnabled(false);
```

If you invoke this method before you create the first `JMenu` or `JPopupMenu`, you ensure your menus will be drawn on top of heavyweight components. So, this takes care of one issue, but you still need to deal with the black background problem.

## 8.9.2. Faking Transparency

Because you cannot change the opacity of the `Canvas3D`, you are left with only two possible solutions. The first is to get rid of Swing, go back to AWT, and offer a crappy interface to the users. Because this doesn't seem like too great an option, we'll just have to fake transparency.

A Java3D scene is represented as a graph in which every node is an object or a group of objects. A close look at the package `com.sun.j3d.utils.geometry` reveals the existence of the `Background` class, which you can use to change the background of the 3D scene. For instance, you can create an Alpine scene just by adding a background with a photo of the Alps as its texture. Therefore, to fake transparency, you just have to use the window's content panel as texture for a new `Background` object that you then add to the scene graph. This is how AmazonPick creates the Java3D scene and adds a special background:

```
public void createScene()
{
    BranchGroup objRoot = new BranchGroup();
    objRoot.addChild(createBackground());
    // creates the whole scene
}
```

In Java3D, the scene is an instance of `BranchGroup`. By adding the `Background` created by the method `createBackground()` as a child of the scene node, you can set the background of the scene. The background itself is created like this:

```
protected Background createBackground()
{
    BufferedImage image;
    image = new BufferedImage(c3d.getParent().getWidth(),
                             c3d.getParent().getHeight(),
                             BufferedImage.TYPE_INT_RGB);
    getContentPane().paint(image.getGraphics());

    BufferedImage subImage;
    subImage = new BufferedImage(CANVAS3D_WIDTH,
```

```

        CANVAS3D_HEIGHT,
        BufferedImage.TYPE_INT_RGB);
Graphics2D subGraphics = (Graphics2D) subImage.getGraphics();
subGraphics.drawImage(image, null, -c3d.getX(), -c3d.getY());

ImageComponent2D backImage;
backImage = new ImageComponent2D(ImageComponent2D.FORMAT_RGB,
    subImage)
Background bg = new Background(backImage);
BoundingSphere bounds = new BoundingSphere();
bounds.setRadius(100.0);
bg.setApplicationBounds(bounds);

return bg;
}

```

The texture is created in two steps. The first is to create a `BufferedImage` called `image` on which you paint the content panel of the window. Notice that the picture has the same dimensions as the content panel. Calling the `paint()` method of the component you want to see through the Java3D scene is less efficient than taking a screen capture with the help of `java.awt.Robot`; however, it is a lot easier because it works even when the `Canvas3D` has already been added to the window. This allows, for instance, changing the texture when the window is resized and the gradient changes due to the new dimensions.

Once the content panel has been fully drawn in `image`, you must clip it to retrieve the exact part covered by the `Canvas3D`. This is done with another `BufferedImage` called `subImage`. This new picture has the same dimensions as the 3D scene. The second step is to draw `image` on `subImage` (without forgetting to change the origin of the drawing when you call `drawImage()`). When the two last parameters of this method are both 0, the image is drawn on the target surface with its top-left corner at the target's top-left corner. With the coordinates `c3d.getX()` and `c3d.getY()`, the pixel of `image` drawn at the top-left corner of `subImage` is the pixel where the `Canvas3D` is located on screen. This ensures the code paints the exact part of the content panel that lies behind the 3D scene.

Then, a `Background` object is created with `subImage` as a texture. To achieve this, you need to create an `ImageComponent2D` from the `BufferedImage` and don't forget to make the pixel formats compatible! Since `subImage` has its pixels stored as RGB integers, you must do the same for `ImageComponent2D`. A bounding sphere is finally attached to the background. Java3D uses this sphere to know where the background object needs to be rendered and where it should not be rendered. In this case, the background will appear within a sphere of a radius of 100 units. This value is large enough to prevent any rendering problem. [Figure 8-11](#) shows the final result, with a "transparent" 3D scene and no bugginess with pop-up menus.

*Romain Guy*

[← PREV](#)

## Hack 64. Turn the Spotlight on Swing



Users often get lost when using applications, as if they were in total darkness. Why don't you turn on a spotlight to show them the way?

Most applications involve a fair amount of data manipulation. The user creates, edits, deletes, and moves around data items. When the amount of data becomes important, it is vital for the user to be able to search for items easily. Yet, search result displays are often irritatingly complicated, and the results are a pain to browse through. This hack describes how to draw a user's attention to only the parts of the UI you want him to look at.

Figure 8-11. All the problems provoked by mixing Java3D and Swing have been solved

## 8.10.1. The Metaphor

If you have ever been to a comic show, to the theatre, or to the circus, you've probably noticed how spotlights are used to move your focus to a particular location on the stage. A search operation can be compared to a theatre stage, where actors have been replaced by search results. You just need to get the user to focus on the right location.

Take a look at an example application, shown in [Figure 8-12](#), which displays a predefined set of books and lets you search for one or more of them by entering a search query in the text field at the bottom of the window.

Since the application is just a demo, you can only enter one of the following queries: *books*, *sci-fi*, *adams*, and *pratchett*. Each query, when validated by the Enter key, will find the related books and spotlight them, as shown in [Figure 8-13](#).

Figure 8-12. The bookshelf application must let the user search for books




Figure 8-13. Searching for "sci-fi" highlights Science Fiction books



You can even go one step further: the more light you shed, the less darkness there is. For instance, when several books are found, it is likely that the search query was not very precise. This means the user will be more interested in lots of items. When the query yields only a few results, it is likely that the user wants to see only a few specific items.

As you create several spotlights one per result the interface is less darkened than with only one spotlight. If you take a close look at [Figure 8-13](#), you'll be able to perceive the other books. Nevertheless, a single search result will prevent the user from seeing the other books, as shown in [Figure 8-14](#).

Figure 8-14. With only one spotlight, it is almost impossible to see the other books



## 8.10.2. Add the Spotlight

The implementation of spotlights for Swing is divided into two classes, `SpotlightPanel` and `Spotlight`. The first class is a glass pane that needs to be set up on a frame, and the second defines the location and the shape of a spotlight. Here is an example of how to use spotlights:

```
SpotlightPanel glassPane = new SpotlightPanel();
setGlassPane(glassPane);
Spotlight s1 = glassPane.addSpotlight(0, 0, 25, 50);
Spotlight s2 = glassPane.addSpotlight(100, 100, 30);
```

Here, you create two spotlights: `s1` and `s2`. The first is an ellipse 25-pixels wide, 50-pixels high, and located at the top-left corner of the frame; the second is a circle with a radius of 30 pixels and located 100 pixels away from the top and the left of the frame's border. Each spotlight is implemented as an ellipse with the class `Ellipse2D.Double`, as shown in [Example 8-11](#).

### Example 8-11. Representing a spotlight with an Ellipse2D

```
public class Spotlight
{
    protected Ellipse2D.Double spot;
    protected Rectangle2D.Double bounds;

    public Spotlight(int x, int y, int w, int h)
    {
```

```

    this.spot = new Ellipse2D.Double(x, y, w, h);
}

public Ellipse2D getSpot()
{
    return spot;
}

public double getArea()
{
    return Math.PI * spot.getWidth() * spot.getHeight() / 4.0;
}
}

```

As you can see in the code, the `Spotlight` class is fairly simple and contains only two public methods. The first one, `getSpot()`, returns the `Ellipse2D` instance used to draw the spotlight. It can also be used to dynamically change the location and the size of the spotlight. Once you've installed a few spotlights, you will be able to get `Ellipse2D` to animate them. By moving them around, shrinking them, or growing them, you can create stunning effects. The second method of this class, `getArea()`, is used by `SpotlightPanel` to define the amount of darkness according to the total area occupied by the spotlights on the window. Thus, if you have enough spotlights to cover 80% of the window with light, `SpotlightPanel` will use a darkness of 20%. In short, `getArea()` computes the geometrical area of the spotlight's ellipse.

The `SpotlightPanel` panel class (shown in [Example 8-12](#)) only needs a few methods as well. You must be able to create spotlights, to remove a particular spotlight, to remove all spotlights, and to paint spotlights on the screen. You also need two constructors. If you look at the previous figures, you should see that the spotlights' borders are blurred to get a nicer rendering.

Unfortunately, the blurring method used in the painting algorithm is very slow and prevents smooth animation of the spotlights. To account for this, you need a special constructor to instruct the panel to draw blurred borders, along with a constructor that leaves blurring at its default (on in this class, although you may want to leave it *off* normally). When you need still spotlights, activate the blur to get a nicer result. On the contrary, when you want to animate the spotlights, deactivate the blur to get full-speed animations.

### Example 8-12. Constructors of the `SpotlightPanel` class

```

public class SpotlightPanel extends JComponent implements MouseListener
{
    protected boolean blur;
    protected List spotlights;
    protected ConvolveOp blurOp;
    protected RenderingHints hints;

    public SpotlightPanel()
    {
        this(true);
    }
}

```

```

}
public SpotlightPanel(boolean blur)
{
    this.blur = blur;
    spotlights = new ArrayList();
    blurOp = new ConvolveOp(getBlurKernel(3), ConvolveOp.EDGE_NO_OP, null);
    hints = new RenderingHints(RenderingHints.KEY_RENDERING,
        RenderingHints.VALUE_RENDER_QUALITY);
    hints.put(RenderingHints.KEY_ANTIALIASING,
        RenderingHints.VALUE_ANTIALIAS_ON);
    hints.put(RenderingHints.KEY_FRACTIONALMETRICS,
        RenderingHints.VALUE_FRACTIONALMETRICS_ON);
}

// other methods omitted
}

```

The default constructor enables the blur. You can use the second constructor and pass it `false` to deactivate this option. The rendering of the blur effect is done with the help of a `ConvolveOp`. You learned about the inner workings of a blur operation when you blurred disabled components [\[Hack #9\]](#). The constructor also creates an instance of `ArrayList` in which all the spotlights are stored:

```

public Spotlight addSpotlight(int x, int y, int w, int h)
{
    if (spotlights.size() == 0)
    {
        setVisible(true);
        addMouseListener(this);
    }

    Spotlight spot = new Spotlight(x, y, w, h);
    spotlights.add(spot);
    return spot;
}

```

When a new spotlight is added, the panel is made visible immediately, and a new mouse listener is registered on the glass pane. This mouse listener simply waits for a `mouseClicked()` event to clear the spotlights and hide the glass pane. This feature is necessary to let the user decide when she wants to get back to the application and hide the search results. The other methods related to spotlight management are `removeSpotlight(Spotlight s)` and `clearSpotlights()`. Both remove the mouse listener and hide the glass pane when all the spotlights have been removed.

The most important work is done in the `paintSpotlights()` method, called by the `paintComponent()` method:



```

protected void paintSpotlights(Graphics g)
{
    if (spotlights.size() > 0)
    {
        int width = getWidth();
        int height = getHeight();

        double screenArea = width * height;
        double spotsArea = 0.0;

        Rectangle2D screen = new Rectangle2D.Double(0, 0, width, height);
        Area mask = new Area(screen);

        for (int i = 0; i < spotlights.size(); i++)
        {
            Spotlight spot = (Spotlight) spotlights.get(i);
            spotsArea += spot.getArea();
            mask.subtract(new Area(spot.getSpot()));
        }

        Graphics2D g2 = (Graphics2D) g;
        Color shieldColor = new Color(0.0f, 0.0f, 0.0f, 1.0f - (float)
(spotsArea / screenArea));

        if (blur)
        {
            BufferedImage buffer = new BufferedImage(width, height,
                BufferedImage.TYPE_INT_ARGB);
            Graphics2D g2buffer = (Graphics2D) buffer.createGraphics();

            g2buffer.setRenderingHints(hints);
            g2buffer.setColor(shieldColor);
            g2buffer.fill(mask);

            g2.drawImage(buffer, blurOp, 0, 0);
        } else {
            g2.setRenderingHints(hints);
            g2.setColor(shieldColor);
            g2.fill(mask);
        }
    }
}

```

The very first step is to compute the area of the glass pane and the total area occupied by the spotlights. When the spotlights list is browsed to compute the area, a particular shape is created. An `Area` is a Java2D shape that encloses another shape, and on which you can then perform geometrical boolean operations like subtracting or merging shapes. In this example, spotlights can be seen as ellipsoidal holes in a black rectangle. Therefore, you first create an `Area`, called `mask`, with a `Rectangle2D` the size of the glass pane and subtract each spotlight to this shape. Using an `Area` has

many advantages, the more interesting being the possibility to overlap the spotlights, as shown in [Figure 8-15](#).

Figure 8-15. By subtracting ellipses to a rectangle, you can easily overlap the spotlights



The next step is to draw the shape containing the spotlights. Before doing that, though, you need to compute the opacity of `mask`. When you create a new `Color` instance, you can define the opacity as a number between `0.0` (fully transparent), and `1.0` (fully opaque). To compute the required opacity, the program first divides the area of the spotlights by the total area. Thereby, if spotlights occupy 20% of the total area, you obtain the value `0.2`. Subtract this from `1.0` to compute the final opacity. In this example, the opacity would be `0.8`, or 80%.

The final step of the rendering depends on whether blurring is activated. When blurring is off, the `mask` is simply filled with `shieldColor`. Note that the rendering hints defined in the constructor are used at this moment to draw anti-aliased shapes. If blurring is activated, an extra step is required. Instead of drawing the spotlights directly onto the glass pane's graphics surface, an offscreen buffer is created, with the same size as the panel itself. After having drawn `mask` on this offscreen buffer, the resulting picture is drawn onto the panel's graphics surface. All the magic happens when you call the `drawImage()` method with a `ConvolveOp` as the second parameter. The method applies our blur filter on the picture while drawing it.

*Romain Guy*

← PREV

# Chapter 9. Drag-and-Drop

← PREV

[← PREV](#)

## 9.1. Hacks 6569: Introduction

Several years ago, the Swing team introduced a pair of APIs for data transfer: `java.awt.datatransfer` and `java.awt.dnd` (Drag and Drop). The former abstracts the concept of data exchange to and from your application (participating with either Java or native applications) and provides clipboard-based copy-and-paste functionality. The latter particularizes these abstractions to the specifics of drag-and-drop behavior. While many developers use these APIs for working with unstyled clipboard text only, you can do much more. Both Drag and Drop events and the clipboard support images, `URLs`, `Files`, and even custom Java objects.

[← PREV](#)

## Hack 65. Drag-and-Drop with Files



Drag files from your application directly to the desktop, complete with translucent icons.

This hack shows you how to go much further than mere clipboard access by digging into the lower levels of the Drag and Drop APIs and building a program that can save files directly to the desktop via dragging, complete with proper file icons and drag feedback.

When you use an editor to write a large document, you often save it to a particular location on your filesystem in a *Projects* folder perhaps. This is because you will keep the file around for a long time, so you want to store it for later use. Small documents, however, are often created for transient reasons. I often write a few paragraphs and then immediately post it to a weblog or attach it to an email. Some applications (particularly those on Mac OS X) let you save something quickly by dragging a small marker into another application or the desktop. The marker represents the file and lets you quickly move the entire file into another context (a blog editor, for example) without thinking about where to save the file (and trying to remember where you stashed it 10 minutes later).

Since drag-to-save behavior is not a standard part of the Java platform, you will have to build it from scratch using the Drag and Drop APIs. First, you will need a class that can trigger the drop action. The plan is to detect the gesture, create a temp file to be saved, and then start the real drag with the appropriate cursor and user feedback. Here's a starting point:

```
class FileDragGestureListener extends DragSourceAdapter
    implements DragGestureListener {
    JTextArea text;
    Cursor cursor;
    public FileDragGestureListener(JTextArea text) {
        this.text = text;
    }
}
```

The `FileDragGestureListener` implements `DragGestureListener` and extends the `DragSourceAdapter`. Swing sends all drag events to a `DragSource` listener.

Extending the `DragSourceAdapter`, instead of implementing `DragSource` directly, lets your class avoid implementing all of the required methods.

`DragSourceAdapter` gives you empty, no-op implementations of all the methods in `DragSource`.

`FileDragGestureListener` accepts a component to grab the text from. Any provider of text would

work, but I chose a `JTextArea` because it's the most likely to be used in a text editor.

All operating systems define a *drag gesture*, which usually means something like "click and drag for more than 10 pixels," though it varies from platform to platform. Swing will detect the drag gesture and send an event to a `DragGestureListener`, which is why `FileDragGestureListener` also implements that interface. `DragGestureListener` defines one method: `dragGestureRecognized()`. This is where the real work of this hack is done:

```
public void dragGestureRecognized(DragGestureEvent evt) {
    try {

        // generate the temp file
        File proxy_temp = File.createTempFile("tempdir", ".dir", null);
        File temp = new File(proxy_temp.getParent(), "myfile.txt");
        FileOutputStream out = new FileOutputStream(temp);
        out.write(text.getText().getBytes());
        out.close();
    }
}
```

The implementation of `dragGestureRecognized()` starts by creating a temp file to store the text. Actually, first it creates a fake temp file, `proxy_temp`, using the `File.createTempFile()` method. Then it creates the real temp file in the same directory and writes the text data to the file. You could skip the `proxy_temp` part, but then if the user drags to the desktop, he will end up with a filename like *myfile158392.txt* instead of *myfile.txt*. Using the proxy file lets you create a file with a useful name, while still keeping the file in the default temp directory.

Now that the file is done, it's time to create an icon:

```
// get the right icon
FileSystemView fsv = FileSystemView.getFileSystemView();
Icon icn = fsv.getSystemIcon(temp);

Toolkit tk = Toolkit.getDefaultToolkit();
Dimension dim = tk.getBestCursorSize(
    icn.getIconWidth(), icn.getIconHeight());
BufferedImage buff = new BufferedImage(dim.width, dim.height,
    BufferedImage.TYPE_INT_ARGB);
icn.paintIcon(text, buff.getGraphics(), 0, 0);
```

In most operating systems, each type of file has a different icon, such as a little piece of paper for a text file or musical notes for MP3 files. You could bundle such icons with your program, but then they wouldn't look right on all operating systems. `FileSystemView` provides a platform-independent way to get the appropriate icon for any file type with the `getSystemIcon()` method.

Once you have the icon, you just need the underlying image. You could cast the icon to an `ImageIcon` because most platforms use those but the odd platform here or there might not. It's much safer to draw the icon into a new buffered image. Drawing into a new image also lets you convert the icon to

the right cursor size without resizing it. Without this step, the operating system might resize the image on its own, resulting in a messy drag icon that looks horrible. Note the `BufferedImage` is created with `TYPE_INT_ARGB`. This preserves any transparency that may be in the native system icons (e.g., on Mac OS X).

With the file and image in place, it's time to start the drag:

```
// set up drag image
if(DragSource.isDragImageSupported( )) {

    evt.startDrag(DragSource.DefaultCopyDrop, buff,
        new Point(0,0),
        new TextFileTransferable(temp),
        this);

} else {
    cursor = tk.createCustomCursor(buff,new Point(0,0),"billybob");
    evt.startDrag(cursor, null, new Point(0,0),

        new TextFileTransferable(temp),
        this);
}

// end the try/catch block and handle exceptions
```

Some operating systems support the idea of a *drag image*. This is a small image underneath the cursor representing what is being dragged. For OS X, this is usually a translucent version of the file icon. Windows doesn't support drag images, so you can just make the cursor itself be the file icon. That's not quite as nice, but it gives the user the same effect. In the previous code, `DragSource.isDragImageSupported()` lets you know which way to go. If drag images are supported, then it starts a new drag with `evt.startDrag()`, passing in the default copy cursor, the drag image, the cursor hotspot on the drag image, a `transferable` for the temp file (more on this later), and a `DragSource.FileDragGestureListener` just passes in `this` because it also extends the `DragSourceAdapter`. If drag images are not supported, then the code creates a custom cursor using the icon and starts the drag using the new cursor.

Once the drag is started, Swing will provide you with callbacks each time the user moves the cursor and enters or exits an area where the file could be dropped. To provide feedback about whether a file can be dropped over the current location, you should override the `dragEnter()` and `dragExit()` methods in `DragSourceAdapter` to switch the cursor and reflect the current drop target:

```
public void dragEnter(DragSourceDragEvent evt) {
    DragSourceContext ctx = evt.getDragSourceContext( );
    ctx.setCursor(cursor);
}

public void dragExit(DragSourceEvent evt) {
    DragSourceContext ctx = evt.getDragSourceContext( );
```

```
ctx.setCursor(DragSource.DefaultCopyNoDrop);  
}
```

Earlier, I mentioned the `TextFileTransferable` class. The Drag and Drop APIs, along with the clipboard, define something known as a `transferable`. This is a wrapper around some data that describes the flavor of the data and provides access to the data itself. You can think of a flavor as a MIME type. Thus, a transferable for images would support the `DataFlavor.imageFlavor` flavor, and a text transferable would support the `stringFlavor`. You can create your own flavors, too, but it's always better to use the standard ones if you can.

The `TextFileTransferable` (in [Example 9-1](#)) holds a single text file and can transfer it using the `javaFileListFlavor`, which represents a `java.util.List` containing `File` objects.

### Example 9-1. Building a temporary file holder

```
class TextFileTransferable implements Transferable {  
    File temp;  
  
    public TextFileTransferable(File temp) throws IOException {  
        this.temp = temp;  
    }  
  
    public Object getTransferData(DataFlavor flavor) {  
        List list = new ArrayList( );  
        list.add(temp);  
        return list;  
    }  
  
    public DataFlavor[] getTransferDataFlavors( ) {  
        DataFlavor[] df = new DataFlavor[1];  
        df[0] = DataFlavor.javaFileListFlavor;  
        return df;  
    }  
  
    public boolean isDataFlavorSupported(DataFlavor flavor) {  
        if(flavor == DataFlavor.javaFileListFlavor) {  
            return true;  
        }  
        return false;  
    }  
}
```



`TextFileTransferable` implements `transferable` and only recognizes the `javaFileListFlavor`. `getTransferData()` returns the single file wrapped in an `ArrayList`. `getTransferDataFlavors()` returns an array with only one element: `javaFileListFlavor`. And `isDataFlavorSupported` returns true if the specified flavor is a `javaFileListFlavor`.

With all of the components in place, it's time to make a simple application to pull it all together (see [Example 9-2](#)).

## Example 9-2. Testing out drag-and-drop

```
public class FileDropper {
    public static void main(String[] args) throws IOException {
        JFrame frame = new JFrame("Hack #65: Drag-and-Drop with Files");
        frame.setDefaultCloseOperation(frame.EXIT_ON_CLOSE);

        FileSystemView fsv = FileSystemView.getFileSystemView( );
        Icon icon = fsv.getSystemIcon(File.createTempFile("myfile.", ".txt"));
        ImageIcon iicn = (ImageIcon)icon;

        frame.getContentPane( ).setLayout(new BorderLayout( ));
        JTextArea text = new JTextArea( );


        JLabel label = new JLabel("myfile.txt", icon, SwingConstants.CENTER);
        DragSource ds = DragSource.getDefaultDragSource( );
        DragGestureRecognizer dgr = ds.createDefaultDragGestureRecognizer(
            label,
            DnDConstants.ACTION_MOVE,
            new FileDragGestureListener(text));

        frame.getContentPane( ).add("North", label);
        frame.getContentPane( ).add("Center", text);

        frame.pack( );
        frame.setSize(400, 300);
        frame.setVisible(true);
    }
}
```

`FileDropper` creates a new frame with a label and a text area. The label gets a text file icon, the same as the drag operation from earlier. The crucial part of the code is the `ds.createDefaultDragGestureRecognizer()` call. This ties the system-wide drag class to your custom recognizer. Without this call, the system would know nothing about your customizations, and nothing would happen when the user tries to drag the label to another application or the desktop. With the call, though, the cursor will switch to show a small text icon and the user can successfully drag the file to any place that accepts it (see [Figure 9-1](#)). Now you can save files or transfer them without ever going to a Save File dialog or having to navigate hierarchies of folders.

Figure 9-1. Drag-and-drop a file



← PREV

## Hack 66. Handle Dropped URLs



Drag-and-drop is like a box of chocolates; you never know what you're going to get....

Bookmark menus are so 1995. Today, you should expect to be able to drag URLs to other applications and have those applications open web pages, store the address in a bookmark database, start an email in response to a `mailto:` URL, etc. Java's networking chops are well-established and aren't the problem here. The issue is actually getting the URL itself from the drop.

To accept drops of native objects, your GUI needs to designate some `Component` as the onscreen drop target. Your code then implements the `DropTarget` interface, which means your implementation will get callbacks when the user drags the mouse into your component, over it, out of it, etc. Most of `DropTarget`'s methods can be left as no-ops; for now, only the `drop()` method matters.

What's interesting about native drag-and-drop (and copy-and-paste, for that matter) is that there's not necessarily one way to represent the data being transferred. Instead, you do a sort of negotiation with the `Transferable` passed to you by the `DropTargetDropEvent`: it specifies, in order of robustness, which `DataFlavors` it can deliver, or you ask whether specific `DataFlavors` are supported.

In the demo code in [Example 9-3](#), I have a method called `dumpDataFlavors()`, which shows the `DataFlavors` offered to you by the drop. You can use `System.out.println()` on a particular flavor to get its MIME type, which describes the contents of the drop, and a representation class, which indicates how those contents will be provided to you by `transferable.getTransferData()`. For example, some browsers will give you a `java.net.URL`, whose `DataFlavor` looks like this:

```
java.awt.datatransfer.DataFlavor[mimetype=application/x-java-url;
  representationclass=java.net.URL]
```

One thing that's surprising is the number of `DataFlavors` offered by popular web browsers. [Table 9-1](#) is a short listing of some of the browsers I tested.

Table 9-1. Browsers and their supported DataFlavors

Browser	Supported DataFlavors
Firefox 1.0 / Windows XP	78
MSIE 6.0 / Windows XP	53

Browser	Supported DataFlavors
Safari 1.3 / Mac OS X	53
Firefox 1.0 / Mac OS X	30
MSIE 5.2.3 / Mac OS X	53

Fortunately, a few `DataFlavors` appear on the lists for each browser, so your drop can just handle these common cases.

The `URLDropTargetDemo` class in [Example 9-3](#) presents a large Drop Here label and a `JTextField` to show the dropped URL. I could have opened a stream from that URL and rendered its contents in Swing's `HTMLToolkit`, but the result looks so bad with real-world web pages that it wasn't worth it. Besides, your app might be doing something other than opening web pages, such as storing bookmarks or starting emails.

### Example 9-3. A drop target for URLs

```
public class URLDropTargetDemo extends JPanel
    implements DropTargetListener {

    DropTarget dropTarget;
    JLabel dropHereLabel;
    JTextField statusField;
    static DataFlavor urlFlavor;
    static {
        try {
            urlFlavor =
                new DataFlavor ("application/x-java-url; class=java.net.URL");
        } catch (ClassNotFoundException cnfe) {
            cnfe.printStackTrace( );
        }
    }

    public URLDropTargetDemo( ) {
        super(new BorderLayout( ));
        dropHereLabel = new JLabel ("Drop here",
            SwingConstants.CENTER);

        dropHereLabel.setFont (getFont( ).deriveFont (Font.BOLD, 24.of));
        add (dropHereLabel, BorderLayout.CENTER);
        // set up drop target stuff
        dropTarget = new DropTarget (dropHereLabel, this);
        statusField = new JTextField (30);
        statusField.setEditable(false);
        add (statusField, BorderLayout.SOUTH);
    }
}
```

```
public static void main (String[] args) {
    JFrame frame = new JFrame ("URL DropTarget Demo");
    URLDropTargetDemo demoPanel = new URLDropTargetDemo( );
    frame.getContentPane( ).add (demoPanel);
    frame.pack( );
    frame.setVisible(true);
}

// drop target listener events
public void dragEnter (DropTargetDragEvent dtde) {}

public void dragExit (DropTargetEvent dte) {}

public void dragOver (DropTargetDragEvent dtde) {}

public void drop (DropTargetDropEvent dtde) {
    System.out.println ("drop");
    dtde.acceptDrop (DnDConstants.ACTION_COPY_OR_MOVE);
    Transferable trans = dtde.getTransferable( );
    dumpDataFlavors (trans);
    boolean gotData = false;
    try {

        // try for application/x-java-url flavor
        if (trans.isDataFlavorSupported (urlFlavor)) {
            URL url = (URL) trans.getTransferData (urlFlavor);
            statusField.setText (url.toString( ));
            statusField.setCaretPosition (0);
            gotData = true;
        } else if (trans.isDataFlavorSupported (DataFlavor.stringFlavor)) {
            // try for string flavor
            String s =
                (String) trans.getTransferData (DataFlavor.stringFlavor);
            statusField.setText (s);
            gotData = true;
        }
    } catch (Exception e) {
        e.printStackTrace( );
    } finally {
        System.out.println ("gotData is " + gotData);
        dtde.dropComplete (gotData);
    }
}

public void dropActionChanged (DropTargetDragEvent dtde) {}

private void dumpDataFlavors (Transferable trans) {
    System.out.println ("Flavors:");
    DataFlavor[] flavors = trans.getTransferDataFlavors( );
    for (int i=0; i<flavors.length; i++) {
        System.out.println ("*** " + i + ": " + flavors[i]);
    }
}
```

```
}
}
```

A static initializer sets up a flavor for getting real `java.net.URLs` (MIME type `application/x-java-url`) from applications that provide them. The only other `DataFlavor` you'll need is a string flavor that exists as a constant in the `DataFlavor` class itself.

The constructor does all the work needed to accept drops. Really, this just consists of creating a `DropTarget`, which requires a `Component` (the "Drop here" label), and a class implementing the `DropTargetListener` interface.

In the `drop()` method, you need to `acceptDrop()` to begin the process of handling the drop. Pull out the `transferable` from the `DropTargetDropEvent`, and look to see if it supports any `DataFlavors` that your application can support. In this demo, I implemented this with simple `if/else` statements to try the `urlFlavor` and the constant `stringFlavor`. Each block knows what the drop can be cast to, so one block casts to a `URL`, while the other casts to a `String`.

When your code is finished handling the drop successfully or not you need to call `dropComplete()` on the `DropTargetDropEvent`, and pass a `boolean` to indicate whether the drop was successful. The host OS can use this information to finish animating the drop; for example, by flying the drag image back to its source if the drop failed.

### 9.3.1. Drag Away

When you run the application, the big drop target is obvious, as seen in [Figure 9-2](#). In this case, a URL is being dragged from the Shiira web browser on Mac OS X.

Figure 9-2. Dragging a URL to a Swing component

Once you drop a URL on the target, the dropped URL replaces the text in the `JTextField` (as seen in [Figure 9-3](#)).

Figure 9-3. Swing component after handling a dropped URL



## Hack 67. Handle Dropped Images



I spy, with my little `drop( )` method, something that doesn't support `DataFlavor.imageFlavor...` arrrgh!

Handling drag-and-drop from native applications [[Hack #66](#)] can be tricky because they're not particularly consistent about how they represent the data being transferred to your application. Now, let's say you want to accept dropped images not image files, but actual images inside of browser windows, digital photo viewers, word processing and page-layout applications, etc. There's a constant in `DataFlavor` for images, so surely you can count on that being a flavor offered to you by the `Transferable`, right?

No, of course not. That would be too easy.

Using the `dumpDataFlavors( )` strategy of the earlier URL hack, I checked out the `DataFlavors` offered by images dropped from some popular Windows and Mac applications. The results are pretty interesting check out [Table 9-2](#).

Table 9-2. DataFlavor offerings for images on various platforms

Application/platform	DataFlavors
Preview 2.1 / Mac OS X	1
GraphicConverter 4.6 / Mac OS X	1
Finder / Mac OS X	1
Safari 1.3 / Mac OS X	55
Firefox 1.0 / Mac OS X	57
QuickTime Player 6.5 / Mac OS X	1
AppleWorks 6.2.9 / Mac OS X	1
MarinerWrite 3.6.4 / Mac OS X	1
iPhoto 4.0.3 / Mac OS X	1
Explorer / Windows XP	1
MSIE 6.0 / Windows XP	27



Application/platform	DataFlavors
Firefox 1.0 / Windows XP	80
Paint / Windows XP	N/A
Windows Picture and Fax Viewer / Windows XP	N/A
Windows Media Player / Windows XP	N/A
QuickTime Player 6.5.1 / Windows XP	N/A
QuickTime Picture Viewer 6.5.1 / Windows XP	N/A

The first thing you should notice is the poor support for dragging and dropping images in Windows: Paint, Picture and Fax Viewer, and the Quick-Time applications are not drag sources, and dragging an image from the playlist of Windows Media Player to the Swing application in this hack actually crashes Java.

Furthermore, the supported `DataFlavors` are all over the map. A lot of these provide references to image files in the form of either a `javaFileListFlavor` (as do the Windows and Mac desktops), a list of URIs (the MIME type `text/uri-list` defined by RFC 2483 and supported by many of the browsers), or a single URL. To top it off, some of the older Mac applications send a single, hard-to-handle `DataFlavor` that will require special QuickTime-based handling [[Hack #68](#)].

Thanks to Swing's support for common image types like GIF, JPEG, and PNG, a file reference is good enough because you can easily make an `ImageIcon` from a URL or filepath to any of these types.

### 9.4.1. Grabbing the Drop

[Example 9-4](#) shows a basic application that accepts a drop and tries to obtain from the drop (in order of preference):

1. A `java.awt.Image`
2. A `java.util.List` of `java.io.Files`
3. A `String`, formatted per the `uri-list` spec
4. A `java.net.URL`

#### Example 9-4. Handling dropped images from other applications

```
public class ImageDropTargetDemo extends JPanel
    implements DropTargetListener {
    DropTarget dropTarget;
    JLabel dropHereLabel;
```

```
static DataFlavor urlFlavor, uriListFlavor, macPictStreamFlavor;
static {

    try {
        urlFlavor =
            new DataFlavor ("application/x-java-url; class=java.net.URL");
        uriListFlavor =
            new DataFlavor ("text/uri-list; class=java.lang.String");
    } catch (ClassNotFoundException cnfe) {
        cnfe.printStackTrace( );
    }
}

public ImageDropTargetDemo( ) {
    super(new BorderLayout( ));
    dropHereLabel = new JLabel (" Drop here ",

        SwingConstants.CENTER);
    dropHereLabel.setFont (getFont( ).deriveFont (Font.BOLD, 24.0f));
    add (dropHereLabel, BorderLayout.CENTER);
    // set up drop target stuff
    dropTarget = new DropTarget (dropHereLabel, this);
}

public static void main (String[] args) {
    JFrame frame = new JFrame ("Image DropTarget Demo");
    ImageDropTargetDemo demoPanel = new ImageDropTargetDemo( );
    frame.getContentPane( ).add (demoPanel);
    frame.pack( ); frame.setVisible(true);
}

// drop target listener events

public void dragEnter (DropTargetDragEvent dtde) {}

public void dragExit (DropTargetEvent dte) {}

public void dragOver (DropTargetDragEvent dtde) {}

// drop( ) method listed below

public void dropActionChanged (DropTargetDragEvent dtde) {}

public void showImageInNewFrame (ImageIcon icon) {
    JFrame frame = new JFrame( );
    frame.getContentPane( ).add (new JLabel (icon));
    frame.pack( );
    frame.setVisible(true);
}

public void showImageInNewFrame (Image image) {
    showImageInNewFrame (new ImageIcon (image));
}
}
```

```

private void dumpDataFlavors (Transferable trans) {
    System.out.println ("Flavors:");
    DataFlavor[] flavors = trans.getTransferDataFlavors( );
    for (int i=0; i<flavors.length; i++) {
        System.out.println ("*** " + i + ": " + flavors[i]);
    }
}
}
}

```

As in "Handle Dropped URLs" [[Hack #66](#)], this program uses static initializers to set up two custom `DataFlavors`: one for URLs and another for lists of URIs provided as `Strings`. Constants for images (specifically, `java.awt.Images`) and lists of files (`java.util.Lists` of `java.io.Files`) are provided for you by the `DataFlavor` class.

You register for drag-and-drop by creating a `DropTarget` with an onscreen component and an implementation of the `DropTargetListener` class. The key to the `DropTargetListener` is to meaningfully implement the `drop()` method, taking a `DropTargetDropEvent` and accepting the drop, trying to get the data from the event's `transferable`, and reporting back to the event on whether the data was handled successfully. To prove that it worked, this application shows the dropped image in a new `JFrame`.

Of course, the devil is in the details, meaning the `drop()` method, which is listed in [Example 9-5](#).

### Example 9-5. Handling the image drop

```

public void drop (DropTargetDropEvent dtde) {
    System.out.println ("drop");
    dtde.acceptDrop (DnDConstants.ACTION_COPY_OR_MOVE);
    Transferable trans = dtde.getTransferable( );
    System.out.println ("Flavors:");
    dumpDataFlavors (trans); boolean gotData = false;
    try {
        // try to get an image
        if (trans.isDataFlavorSupported (DataFlavor.imageFlavor)) {
            System.out.println ("image flavor is supported");
            Image img = (Image) trans.getTransferData (DataFlavor.imageFlavor);
            showImageInNewFrame (img);
            gotData = true;
        } else if (trans.isDataFlavorSupported (
            DataFlavor.javaFileListFlavor)) {
            System.out.println ("javaFileList is supported");
            java.util.List list = (java.util.List)
            trans.getTransferData (DataFlavor.javaFileListFlavor);
            ListIterator it = list.listIterator( );
            while (it.hasNext( )) {
                File f = (File) it.next( );
                ImageIcon icon = new ImageIcon (f.getAbsolutePath( ));
            }
        }
    } catch (Exception e) {
        System.out.println ("Exception: " + e);
    }
}

```

```

        showImageInNewFrame (icon);
    }
    gotData = true;
} else if (trans.isDataFlavorSupported (uriListFlavor)) {
    System.out.println ("uri-list flavor is supported");
    String uris = (String)
    trans.getTransferData (uriListFlavor);

    // url-lists are defined by rfc 2483 as crlf-delimited
    StringTokenizer izer = new StringTokenizer (uris, "\r\n");
    while (izer.hasMoreTokens ( )) {
        String uri = izer.nextToken( );
        System.out.println (uri);
        ImageIcon icon = new ImageIcon (uri);
        showImageInNewFrame (icon);
    }
    gotData = true;
} else if (trans.isDataFlavorSupported (urlFlavor)) {
    System.out.println ("url flavor is supported");
    URL url = (URL) trans.getTransferData (urlFlavor);
    System.out.println (url.toString( ));
    ImageIcon icon = new ImageIcon (url);
    showImageInNewFrame (icon);
    gotData = true;
}
} catch (Exception e) {
    e.printStackTrace( );
} finally {
    System.out.println ("gotData is " + gotData);
    dtde.dropComplete (gotData);
}
}
}

```

`drop()` asks the `transferable` for supported `DataFlavors` in the order you'd prefer to deal with them. First, obviously, is `DataFlavor.imageFlavor`. If this is supported, you can trivially cast the data object returned by `transferable.getTransferData()` to an `Image`.

The next easiest thing to deal with is the Java file list, denoted by the MIME type `application/x-java-file-list`, and handled by the `DataFlavor` constant `javaFileListFlavor`. Given Swing's support for various image file formats, you can cast the transfer data to a `java.util.List`, iterate over its members, cast each one to a `File`, and make an `ImageIcon` from each file's path. URLs work pretty much the same way: cast the transfer data to a `java.net.URL` and make an `ImageIcon` from it.

URI lists take just a little work on your part. RFC 2483 defines these as being some number of URIs, separated by CRLF pairs. It's trivial to take the URI list as a string and send it to a `StringTokenizer` to pick out each URI, which can then be passed to the `ImageIcon` constructor.

## 9.4.2. Shut Up and Drag

Start up the demo and drag over an image from your favorite application, as shown in [Figure 9-4](#).

Figure 9-4. Dragging an image from a native application to a Swing component

When dropped, you'll see the image appear in its own `JFrame`. In [Figure 9-5](#), I've dragged small images from several different applications, resulting in each being opened in its own frame.

Figure 9-5. Image dropped from a native application and opened in Swing



This *won't* work if you're dragging an image from one of the Mac OS X applications that only supplies one `DataFlavor`. You'll have to deal with Picts [\[Hack #68\]](#) in that situation.



## Hack 68. Handling Dropped Picts on Mac OS X



For Mac applications that provide only the legacy Pict flavor of drops, QuickTime for Java offers a Mac-specific solution.

You should already recognize the existence of hard-to-handle `DataFlavor`s [[Hack #67](#)] passed by certain Mac applications. Of the Mac apps I tested, several old apps (many using the Carbon APIs, which were developed to migrate classic Mac apps to OS X) support only one `DataFlavor`. When I drop from GraphicConverter, QuickTime Player, AppleWorks, and MarinerWrite, the only supported `DataFlavor` was reported as:

```
java.awt.datatransfer.DataFlavor[mimetype=image/x-pict;
  representationclass=java.io.InputStream]
```

For those of you who don't use Macs, Pict is part of QuickDraw, the original Mac graphics API. The term is wildly overloaded: Pict can refer to a file format, a resource hidden in an application file, a wrapper around vector drawing commands, and as a wrapper around optionally compressed pixel data. It's in this latter form that Pict is a preferred format for passing image data on the Mac clipboard because Picts are easy for Mac applications to render and convert (through the QuickDraw library, of course).

Unfortunately, Java doesn't know the first thing about Picts, so it's frustrating to see that Pict is the only supported `DataFlavor`. Worse, the data is supplied as an `InputStream`, instead of a file or a URL, meaning you have to handle it in Java, instead of handing off to non-Java code that might be able to convert the Pict to something that can handle the format more gracefully.

Fortunately, there is a Java solution to the problem, and it's called QuickTime for Java (QTJ). This API is a Java wrapper around the native QuickTime multimedia API. It's available for Mac OS X and Windows, but since a Windows application isn't going to pass you a Pict, you only need to worry about the Mac OS X case. One advantage of all this API-wrangling: QTJ is installed by default on Mac OS X, so you can count on it being there.

Everything in this hack is Mac-specific. Since Picts are only going to be an issue on Mac OS X, don't bother with this on programs that you're sure won't need to deal with Mac OS X drops.

First, you'll need to define a `DataFlavor` for Pict data in Java input streams:

```
macPictStreamFlavor =
    new DataFlavor ("image/x-pict; class=java.io.InputStream");
```

Next, take the code from the hack on handling standard dropped images [\[Hack #67\]](#) and give `drop()` a new `else if()` {...} block to deal with this flavor. This block will use a `QTJPHelper` class, so you need to make that available (I'll show you this helper class soon). Since you don't want to need to have this class at compile time that would make life harder for Windows and Linux users, who might not have the `QTJava.zip` file to compile against this code uses reflection to load the `QTJPHelper` class and invoke its `pictStreamToJavaImage()`:

```
} else if (trans.isDataFlavorSupported (macPictStreamFlavor)) {
    System.out.println ("mac pict stream flavor is supported");
    InputStream in =
        (InputStream) trans.getTransferData (macPictStreamFlavor);
    // for the benefit of the non-mac crowd, this is
    // done with reflection. directly, it would be:
    // Image img = QTJPHelper.pictStreamToJavaImage (in);

    Class qtjphClass = Class.forName ("QTJPHelper");

    Class[] methodParamTypes = { java.io.InputStream.class };
    Method method =
        qtjphClass.getDeclaredMethod ("pictStreamToJavaImage",
            methodParamTypes);
    InputStream[] methodParams = { in };
    Image img = (Image) method.invoke (null, methodParams);
    showImageInNewFrame (img);
    gotData = true;
}
```

OK, now for the fun part: converting the input stream from Pict data to a Java image. This code is drawn from techniques in the book *QuickTime for Java: A Developer's Notebook* (O'Reilly), which has a whole chapter on QuickDraw and how to call it from Java. The gist of the technique is to use a `GraphicsImporter`, which handles various types of image data, to read the Pict. From this you can get a `GraphicsImporterDrawer` that allows you to get a `QTImageProducer`, which is an AWT `ImageProducer` and, of course, can produce a normal `java.awt.Image`.

[Example 9-6](#) shows the `QTJPHelper` helper class I mentioned earlier. Unlike most examples in the book, this listing includes the `import` statements because the QTJ stuff will be new to most readers.

### Example 9-6. Using QTJ to handle Mac Pict data in a Transferable

```
import java.awt.*;
import java.io.*;
```

```
import quicktime.*;
import quicktime.qd.*;
import quicktime.std.*;
import quicktime.std.image.*;
import quicktime.std.movies.media.*;
import quicktime.app.view.*;
public class QTJPictHelper extends Object {

    static Image pictStreamToJavaImage (InputStream in)
        throws IOException {
        Image image = null;
        // create a buffer for bytes read from stream
        byte[] buffy = new byte [2048];
        // must have empty 512-byte header so GraphicsImporter
        // will think it's a file
        int off = 512;
        int totalRead = 0;
        // loop, attempting to read as many bytes as will fit
        // in the array, growing array as necessary
        int bytesRead = 0;
        while ((bytesRead = in.read (buffy, off, buffy.length-off)) > -1) {

            totalRead += bytesRead;
            off += bytesRead;
            if (off == buffy.length) {
                // reallocate new array
                byte[] buffy2 = new byte [buffy.length * 2];
                System.arraycopy (buffy, 0, buffy2, 0, buffy.length);
                buffy = buffy2;
            }
        }
        try {
            // hand it to QTJ GraphicsImporter
            QTSession.open( );
            Pict pict = new Pict (buffy);
            DataRef ref = new DataRef (pict,
                StdQTConstants.kDataRefQTFileTypeTag,
                "PICT");
            GraphicsImporter gi =
                new GraphicsImporter (StdQTConstants.kQTFileTypePicture);
            gi.setDataReference (ref);
            QDRect rect = gi.getSourceRect ( );
            Dimension dim = new Dimension (rect.getWidth( ),
                rect.getHeight( ) );
            GraphicsImporterDrawer gid =
                new GraphicsImporterDrawer (gi);
            QTImageProducer ip = new QTImageProducer (gid, dim);

            // create AWT image
            image = Toolkit.getDefaultToolkit( ).createImage (ip);

        } catch (QTException qte) {
            qte.printStackTrace( );
        }
    }
}
```



```

    } finally {
        QTSession.close( );
    }
    return image;
}
}

```

To compile this code, you need the *QTJava.zip* file (yes, QTJ is old enough to pre-date JAR files) in your classpath. On Mac OS X, you'd compile with something like this:

```

javac -classpath /System/Library/Java/Extensions/QTJava.zip
      QTJPictHelper.java

```

The implicit QTJ hack in this code is that the `GraphicsImporter` has to be fooled into believing that a block of memory is actually a Pict file as it would appear on disk, and Pict files have a 512-byte header that the importer skips over. So, the first thing this code does is to build a byte array from the input stream, starting with 512 empty bytes.

Next is the QTJ stuff. It's OK if you don't totally understand it QTJ code is pretty twisted. That's why there's a whole book on it. First, you open a `QTSession`, which initializes QuickTime and allocates resources. You have to do this before any QTJ call. It can throw a `QTException`, as can most other QTJ calls, so the whole thing is wrapped in a `try-catch` block.

Next, you create a `Pict` object from the byte array and pass that to `DataRef`, which is a sort of generic media reference. In this case, you pass in flags to tell the `DataRef` exactly what it's pointing to. The second and third arguments indicate that we're using the old-style Mac OS file type and that its value is `PICT`. You might be wondering why being a `Pict` object isn't self-descriptive enough. It's because many QTJ objects are just pointers to blocks of memory and the functions that work with them. The `DataRef` signature used here takes a `QTHandleRef` as an argument. `QTHandleRef` is subclassed by `Pict`, but it is little more than a pointer; the only level on which the `DataRef` understands the `Pict`, in fact, is as a block of memory. My point here: QTJ code is weird and often C-like.

Create a `GraphicsImporter` for the Pict format, and point it to the `DataRef`. You have now read the Pict "file" from memory. Now, you can get the size of the imported image and create a `QTImageProducer`, with help from a `GraphicsImporterDrawer` (a sort of QT-to-Java bridge for still images, also used by QTJ's Swing `JComponents`). Since this is a normal, everyday `ImageProducer`, you can create an image with `Component.createImage( )` or `Toolkit.createImage( )`.

Finally, you need to call `QTSession.close( )` to deallocate QuickTime resources. It's OK to do it many times in a program, although it's probably more efficient to `open( )` it once and `close( )` it once; e.g., in your quit handler or a shut-down hook.

### 9.5.1. Take a Breath and Run

The code works exactly as in the previous hack all you've done is support one more `DataFlavor`. In

[Figure 9-6](#), I've dropped two images from QuickTime Player onto the Java app, and both are shown in their own windows.

Actually, this is a little more interesting than it looks because the larger image isn't a still image; it's the current frame of an MPEG-4 movie that I dragged and dropped into the Java app. The single frame is transported as a Pict, and using QTJ lets you get it into the Java world. This hack only scratches the surface of QTJ's potential if you want to do Java Media on the Mac, you should check out *QuickTime for Java: A Developer's Notebook*, by Chris Adamson (yours truly), published by O'Reilly.

Figure 9-6. Handling dropped images by supporting Pict format



## Hack 69. Translucent Drag-and-Drop



The Java implementation of drag-and-drop offers poor visual feedback. This hack shows how to provide more information and a better-looking response to the user.

A good way to create user-friendly interfaces is to provide the ability to drag-and-drop almost anything from, within, and onto those interfaces. Mac OS X is a perfect example of a good drag-and-drop use. Every time I try to drag something to drop it onto something else, it just works. AWT, and therefore Swing, let applications implement drag-and-drop but lack something Mac OS X already offers: really cool visual feedback to let the user know what's going on.

### 9.6.1. A Rather Boring Cursor

J2SE has offered drag-and-drop facilities since version 1.2. All the necessary classes and interfaces can be found in the package `java.awt.dnd`. Although not very easy to use at first, this package provides powerful features you can use to greatly improve the usability of your applications. Unfortunately, the Java drag-and-drop framework offers little visual feedback. In fact, the only feedback the user can get is a simple mouse cursor. For instance, you can show that a drag-and-drop operation is in progress with the following line of code:

```
dropTarget.setCursor(DragSource.DefaultMoveDrop);
```

[Figure 9-7](#) shows what the visual feedback looks like on Windows.

Figure 9-7. Default drag-and-drop visual feedback on Windows

```
protected GhostGlassPane glassPane;
protected String action;

private List listeners;

public GhostDropAdapter(GhostGlassPane glassPane, String action) {
    this.glassPane = glassPane;
    this.action = action;
    this.listeners = new ArrayList();
}

public void addGhostDropListener(GhostDropListener listener) {
    if (listener != null)
        listeners.add(listener);
}
```

Not only does this look bad, it also conveys very little information. Mac OS X users are used to a much richer environment, and why should Windows or Linux users expect less? As an example of what can be done, SafariMac OS X's default web browser shows a translucent thumbnail of the picture you are dragging. [Figure 9-8](#) shows what this looks like in action.


Figure 9-8. Mac OS X provides great looking visual feedback for drag-and-drop

The quality of the interaction is greatly enhanced by the quantity of information provided by the visual feedback. Another example is dragging a link from the web browser to the desktop, where a translucent text box containing the link title and the URL is shown. Wouldn't it be great to be able to do the same in your application? Thankfully, Swing is perfectly suited for that kind of job.

## 9.6.2. Translucence Rocks


Implementing a stylish drag-and-drop requires being able to draw a translucent picture over any component. Every Swing frame contains several layers on which components are painted. These layers serve many purposes, among which is the drawing of pop-up menus over the regular components. The higher-level layer is called the glass pane. A glass pane is a transparent container you can use to draw over the entire UI, as seen in the hack that turned dialogs into frame-anchored "sheets" [Hack #44]. You will use it to display translucent pictures during a drag-and-drop operation, as seen in [Figure 9-9](#).

Figure 9-9. A translucent picture as visual feedback for drag-and-drop



Yet, translucent pictures do not cover all the needs of effective drag-and-drop visual feedback. When the user drops a file on your application, you can use a picture to indicate what the type of the file is. However, what picture will you use when the user wants to drag a text box into another box, and expect the contents of the first box to be copied to the second? The best solution is simply to display a translucent copy of the component itself, referred to as a *ghost* in the code. [Figure 9-10](#) shows a ghost in mid-drag.

Figure 9-10. A ghost is a translucent copy of a Swing component



This time, you will not use the package `java.awt.dnd`; you'll need your own framework for this level of sophistication. By breaking out of the pre-built box, you gain full control of drag-and-drop.

### 9.6.3. Drawing a Ghost

The very first thing you need is a glass pane able to draw a translucent picture over the UI. A glass pane is nothing more than a transparent `JPanel`. The code of `GhostGlassPane` is very simple, as shown in [Example 9-7](#).

#### Example 9-7. Creating a glass pane for ghosting

```
import java.awt.*;
import java.awt.image.*;
import javax.swing.*;
public class GhostGlassPane extends JPanel
{
    private AlphaComposite composite;
    private BufferedImage dragged = null;
    private Point location = new Point(0, 0);

    public GhostGlassPane( )
    {
        setOpaque(false);
        composite = AlphaComposite.getInstance(AlphaComposite.SRC_OVER, 0.5f);
    }

    public void setImage(BufferedImage dragged)
```

```

{
    this.dragged = dragged;
}

public void setPoint(Point location)
{
    this.location = location;
}

public void paintComponent(Graphics g)
{
    if (dragged == null)
        return;

    Graphics2D g2 = (Graphics2D) g;
    g2.setComposite(composite);
    g2.drawImage(dragged,
        (int) (location.getX( ) - (dragged.getWidth(this) / 2)),
        (int) (location.getY( ) - (dragged.getHeight(this) / 2)),
        null);
}
}

```

This glass pane has two properties: the picture to be displayed and its location. To make the picture translucent, use an `AlphaComposite` instance. Besides colors, strokes, and painters, Java2D drawings can be affected by composites that define how the newly drawn pixels are mixed with the underlying pixels. In this case, you want the new pixels i.e., the picture to be drawn at 50% of their initial opacity. You can change the second parameter of `getInstance( )` to choose the opacity. The valid value range is from a totally opaque `0.0` to a totally transparent `1.0`. An `AlphaComposite` can be used to define how the alpha channels of the source (the pixels being drawn), and the target (the existing pixels) are mixed together. You can select the mixing mode with the first parameter of `getInstance( )` and refer to the documentation of `AlphaComposite` to get a comprehensive list of possible modes. It turns out that the `AlphaComposite.SRC_OVER` composite gives the best result for our job.

The only job of the `paintComponent( )` will be to draw the dragged picture. Therefore, there is no need to call `super.paintComponent( )`, as it will perform unnecessary operations.

Do not forget to set the composite in this method, or you might draw the picture fully opaque.

The center of the picture is painted at the location specified in `setLocation( )`. This means assuming the location given is the location of the mouse cursor. Now, you've got a fully functional glass pane, and you just need to add it to a Swing frame:

```

glassPane = new GhostGlassPane( );
setGlassPane(glassPane);

```

Also, do not forget that a glass pane is not visible by default: you will have to call `setVisible(true)` when a drag-and-drop operation is initiated. The final step is the activation of drag-and-drop on components requiring it. You can use a picture as drag-and-drop feedback:

```
JLabel label = new JLabel("New Sale");
GhostDropAdapter pictureAdapter;
pictureAdapter = new GhostPictureAdapter(glassPane,
    "new_sale",
    "images/new_sale.png")
label.addMouseListener(pictureAdapter);
label.addMouseMotionListener(new GhostMotionAdapter(glassPane));
```

You can also use a ghost feedback:

```
JButton button = new JButton("Ghost Feedback");
GhostDropAdapter componentAdapter;
componentAdapter = new GhostComponentAdapter(glassPane, "button_pushed");
button.addMouseListener(componentAdapter);
button.addMouseMotionListener(new GhostMotionAdapter(glassPane));
```

Whatever choice you make, you need two adapters to perform drag-and-drop. The first one is an adapter for the `MouseListener` interface. It can be either a `GhostPictureAdapter`, to handle pictures, or a `GhostComponentAdapter`, to handle a component ghost. The role of this adapter is to handle the beginning and the end of a drag-and-drop gesture. When a drop action is performed, an event is fired to every `GhostDropListener` registered by the adapter. The code in [Example 9-8](#) shows how `GhostComponentAdapter` works. The code of `GhostPictureAdapter` is almost the same, and it's left to you to check out (all the code for this book is online; visit <http://www.oreilly.com/catalog/swinghks>).

## Example 9-8. Handling component ghosts

```
import java.awt.*;
import java.awt.event.*;
import java.awt.image.*;
import javax.swing.*;

public class GhostComponentAdapter extends GhostDropAdapter
{
    public GhostComponentAdapter(GhostGlassPane glassPane, String action) {
        super(glassPane, action);
    }
}
```



```

public void mousePressed(MouseEvent e)
{
    Component c = e.getComponent( );

    BufferedImage image = new BufferedImage(c.getWidth( ),
        c.getHeight( ),
        BufferedImage.TYPE_INT_ARGB);
    Graphics g = image.getGraphics( );
    c.paint(g);

    glassPane.setVisible(true);

    Point p = (Point) e.getPoint( ).clone( );
    SwingUtilities.convertPointToScreen(p, c);
    SwingUtilities.convertPointFromScreen(p, glassPane);

    glassPane.setPoint(p);
    glassPane.setImage(image);
    glassPane.repaint( );
}
public void mouseReleased(MouseEvent e)
{
    Component c = e.getComponent( );

    Point p = (Point) e.getPoint( ).clone( );
    SwingUtilities.convertPointToScreen(p, c);

    Point eventPoint = (Point) p.clone( );
    SwingUtilities.convertPointFromScreen(p, glassPane);

    glassPane.setPoint(p);
    glassPane.setVisible(false);
    glassPane.setImage(null);

    fireGhostDropEvent(new GhostDropEvent(action, eventPoint));
}
}

```

When a mouse-press event is fired by the drag-and-drop source, a new off-screen picture is created. This picture has the exact same dimensions as the source component itself. Then the component is asked to paint itself on the `Graphics` surface of the picture. The code obtains a ghostly copy of the component which is passed to the glass pane.

You might wonder why the `SwingUtilities` class is used. Since the code listens to the events fired by a component, the mouse location it receives is bound to the component's coordinate system. For instance, when the mouse is pressed with the cursor at the top-left corner of the component, the location is `0,0`. Unfortunately, you cannot use this location with the glass pane. As the pane covers the whole frame, you need to translate the location from the component's coordinate system to the glass pane's coordinate system. There is no way to achieve this in one step, which is why the code

first translates the location to the screen coordinates and then to the glass pane coordinates. The glass pane can then safely paint the picture at the given location.

The second adapter required for performing a full drag-and-drop operation is an adapter for the `MouseEventListener` interface. The framework needs it to change the location of the picture, or the ghost, when the mouse moves over the window. The code is pretty simple:

```
public void mouseDragged(MouseEvent e)
{
    Component c = e.getComponent( );
    Point p = (Point) e.getPoint( ).clone( );
    SwingUtilities.convertPointToScreen(p, c);
    SwingUtilities.convertPointFromScreen(p, glassPane);
    glassPane.setPoint(p);
    glassPane.repaint( );
}
```

As before, you need to convert the location of the mouse event into the right coordinate system. Once you get a valid location, the pane is repainted. The full source code of this hack is available in this book's downloadable source code. The only part of the drag-and-drop framework you have not seen is the `GhostDropListener` and its `GhostDropEvent`. Both are very easy to understand when you remember that the drop location given by the event is expressed in screen coordinates. Therefore, you must translate it into the target component's coordinates if you need to perform some checks. The complete example provides an `AbstractGhostDropManager` that implements `GhostDropListener` to provide two methods to handle drag-and-drop targets more easily.

*Romain Guy*

[← PREV](#)

# Chapter 10. Audio

[Section 10.1. Hacks 7078: Introduction](#)

[Hack 70. Play a Sound in an Applet](#)

[Hack 71. Play a Sound with JavaSound](#)

[Hack 72. Play a Sound with Java Media Framework](#)

[Hack 73. Play a Sound with QuickTime for Java](#)

[Hack 74. Add MP3 Support to JMF](#)

[Hack 75. Build an Audio Waveform Display](#)

[Hack 76. Play Non-Trivial Audio](#)

[Hack 77. Show Audio Information While Playing SoundHack](#)

[Hack 78. Provide Audio Controls During Playback](#)

## 10.1. Hacks 7078: Introduction

Sound is underrated as a useful tool for building good user interfaces. A lot of developers balk at the thought of sound support, imagining an office full of noisy machines, emitting a beeping cacophony more like a 1980s videogame arcade than a place of business. But on the other hand, don't you appreciate it when you get a nice little audible cue? For example:

- When your IM buddy logs in
- When your CD has finished burning
- When your gigantic upload has finished
- When someone is trying to hack into your network and you're not even looking at the screen

And beyond these kinds of uses, don't forget the whole realm of applications that are, by their nature, all about sound: music players, sound editors, voice chat, and VoIP, etc. Clearly, `java.awt.Toolkit.beep()` is not going to cut it.

Java has two built-in options for playing simple sounds in memory: `appletAudioClips` and JavaSound. Because of their limitations, this chapter will also look at two extensions: Java Media Framework (JMF) and QuickTime for Java (QTJ). Later in the chapter, you'll find more sophisticated JavaSound coverage, including how to visualize an in-memory sound clip, and how to play sounds too big to fit in memory.

## Hack 70. Play a Sound in an Applet



If you're forced to write to the old Applet API for sound, here's how you do it. Good luck .

Let me be very clear up front: applet-based sound sucks. If you are in a hurry to get sound into your application and can count on your users having Java 1.3 or better, go ahead and use JavaSound instead [Hack #71] . Appletbased sound is going to be most useful to those who must deliver applets (and only applets) to very old browsers and JVMs. And it's not going to be pretty.

Java 1.0 and 1.1 shipped with no support for application-based sound. None. The only sound support was in applets, presumably so they could punt the responsibilities for audio to the enclosing browser. The idea in the early JDKs is built around an `AudioClip` , a class found in the `java.awt.applet` package as David Flanagan in *Java Foundation Classes in a Nutshell*(O'Reilly), "only because there is no better place for it."

### 10.2.1. The Code

To demonstrate `AudioClips` , Example 10-1 shows a hacked up little applet.

#### Example 10-1. Playing an AudioClip in an applet

```
public class AppletSound extends Applet
    implements ActionListener {

    JButton fileButton, loadButton, playButton, loopButton, stopButton;
    JLabel urlLabel;
    JTextField urlField;
    AudioClip clip;

    public AppletSound() {
        setLayout (new GridLayout (2,1));
        // first row layout
        JPanel topPanel = new JPanel();
        urlLabel = new JLabel ("URL:");
        topPanel.add (urlLabel);
        urlField = new JTextField (25);
        urlField.addActionListener (this);
        topPanel.add (urlField);
        loadButton = new JButton ("Load");
        loadButton.addActionListener (this);
        topPanel.add (loadButton);
        fileButton = new JButton ("File");
```

```

fileButton.addActionListener (this);
topPanel.add (fileButton);
add (topPanel);
// second row layout
JPanel bottomPanel = new JPanel();
playButton = new JButton ("Play");
playButton.addActionListener (this);
bottomPanel.add (playButton);
stopButton = new JButton ("Stop");
stopButton.addActionListener (this);
bottomPanel.add (stopButton);
loopButton = new JButton ("Loop");
loopButton.addActionListener (this);
bottomPanel.add (loopButton);
add (bottomPanel);
}
public void stop() {
clip.stop();
}

public void actionPerformed (ActionEvent e) {
Object source = e.getSource();
if (source == fileButton) {
JFileChooser chooser = new JFileChooser();
int pick = chooser.showOpenDialog(this);
if (pick == JFileChooser.APPROVE_OPTION) {
try {
File file = chooser.getSelectedFile();          urlField.setText (file.toURL().toString);
} catch (MalformedURLException murle) {          murle.printStackTrace();
}
}
} else if (source == loadButton ) {
try {
System.out.println ("field: " + urlField.getText());
URL clipURL = new URL (urlField.getText());
System.out.println ("loading " + clipURL);
clip = getAudioClip (clipURL);
System.out.println ("got clip");
} catch (MalformedURLException murle) {
murle.printStackTrace();
}
} else if (source == playButton ) {
clip.play();
} else if (source == stopButton ) {
clip.stop();
} else if (source == loopButton ) {
clip.loop();
}
}
public static void main (String args[]) {
JFrame f = new JFrame ("Applet Sound");
f.getContentPane().add (new AppletSound());
}

```

```

    f.pack();
    f.setVisible(true);
}
}

```

If you've never worked with an applet, you need to be aware that they can't simply be launched from the command line with the `java` command. They need to live in some sort of applet-aware container, typically a browser, with their size and parameters specified by HTML tags. Example 10-2 shows a simple `index.html` to show the `AppletAudio` applet in a web page.

## Example 10-2. HTML to display AppletSound applet

```

<html>
<head><title>Applet Sound</title></head>
<body>
<p>Playing sound with <code>java.applet</code></p>
<APPLET
  CODE="AppletSound.class"
  WIDTH="600"
  HEIGHT="75">
</APPLET>
</body>
</html>

```

Notice how the applet doesn't have a `setVisible(true)` line anywhere. The applet is an AWT panel that controls its own layout; its constructor will be called from the browser plug-in (or equivalent) to get its pixels into the browser window.

The constructor of this applet is concerned exclusively with layout. It provides a `JTextField` for a URL, a `JButton` to load an `AudioClip` from that URL; a File `JButton` that can be used instead of typing in a `file://` URL by hand; and Play, Stop, and Loop `JButton`s to control the `AudioClip`.

`actionPerformed()` is the guts of this applet. If you click the File button, it simply shows a `JFileChooser`, converts the chosen file to a URL, and puts that in the `TextField`.

The handler for the Load button is also critical. When this button is clicked, the applet gets the text from the `JTextField`, makes a URL out of the text, and passes that URL to `getAudioClip()`. `getAudioClip()` is an `Applet` method that's a shortcut for getting an `AppletContext` object, which describes the environment that the applet runs in and calls its `getAudioClip()`.

The last three buttons—Play, Stop, and Loop—are handled trivially in `actionPerformed()` with calls to the `Applet` methods `play()`, `stop()`, and `loop()`, respectively.

I've also provided a `main()` method here. Applets don't need them, but since an applet is just a `JPanel`, it's not just put it in a `JFrame` and run it, right? What's the worst that could happen?

## 10.2.2. No Browser, No Sound

Since there's a `main ()` method, just type `java AppletAudio` on the command line and the applet will come in its own frame, as seen in Figure 10-1.

Figure 10-1. AudioClip player launched as an application



Click the File button and choose a file to have its URL placed in the field. Now, click Play.

Nothing happens. If you have an output console, you should see something like:

```
java.lang.NullPointerException
  at java.applet.Applet.getAppletContext(Applet.java:171)
  at java.applet.Applet.getAudioClip(Applet.java:279)
  at AppletSound.actionPerformed(AppletSound.java:71)
  at javax.swing.AbstractButton.fireActionPerformed(
    AbstractButton.java:1819)
...
```

I'll save you the time of typing a URL by hand and hitting Load; the same thing happens.

What's happening is that the implicit call to `getAppletContext ()` is failing because there is no applet context i.e., the environment in which the applet is executed. An applet expects to run in a browser or something similar that provides access to cached images and sounds and the ability to get documents via URLs. Obviously, the four-line `main ()` method doesn't attempt to provide such facilities.

So, to provide a suitable environment, use a browser to open the `index.html` file. It also works to use the JDK's `appletviewer` from the command line. Either way, this should open a web page that looks like Figure 2.

Figure 10-2. Applet to play AudioClips





Click File and...nothing happens. If you have an output window open, you'll see the reason:

```
[aeris:HacksBook/Media/52] cadamson% appletviewer index.html
apple.awt.EventQueueExceptionHandler Caught Throwable : java.security.
AccessControlException: access denied (java.util.PropertyPermission user.
home read)
java.security.AccessControlException: access denied (java.util.
PropertyPermission user.home read)
    at java.security.AccessControlContext.checkPermission(
        AccessControlContext.java:269)
    at java.security.AccessController.checkPermission(
        AccessController.java:401)
    at java.lang.SecurityManager.checkPermission(
        SecurityManager.java:524)
    at java.lang.SecurityManager.checkPropertyAccess(
        SecurityManager.java:1276)
    at java.lang.System.getProperty(System.java:573)
    at sun.awt.shell.ShellFolderManager.get(ShellFolderManager.java:51)
    at sun.awt.shell.ShellFolder.get(ShellFolder.java:245)
    at javax.swing.filechooser.FileSystemView.getDefaultDirectory(
        FileSystemView.java:362)
    at javax.swing.JFileChooser.setCurrentDirectory(
        JFileChooser.java:525)
    at javax.swing.JFileChooser.<init>(JFileChooser.java:321)
    at javax.swing.JFileChooser.<init>(JFileChooser.java:273)
    at AppletSound.actionPerformed(AppletSound.java:56)
```

Thanks to restrictive applet security, you can't open a `JFileChooser` in an applet without going and rewriting your permissions file or pointing to a new, more permissive set of policies. Typing a URL by hand and trying to load it fails in the same way and for the same reason. It probably makes sense to assume the worst of an applet, but it makes it hard for an applet to do anything useful, doesn't it?

Realistically, you actually need to host the applet (HTML and code) on a web server and access it via a URL. If you have access to a web server, put `index.html` and `AppletAudio.class` in their own web directory, along with some known-to-work audio files, then access it remotely with a browser. Type in a URL to one of those files by hand and try to load it. This time, it should work (finally).

But what formats are supported? Back in Java 1.0 and 1.1, `AudioClips` had to be encoded in mono at 8,000

Hz with  $\mu$ -law encoding...which was pretty awful. In Java 1.4.2, a few simple container formats are supported. AIFF and WAV both work, but Mac OS X doesn't support the `.au` format, which used to be the only option (Windows can play `.au`, by the way). Also, `AudioClip` can't play WAVs and AIFFs whose contents are compressed in any way. And neither Mac nor Windows supports MP3 as `AudioClip`s.

You can also load audio from sites other than the one hosting your applet, which seems contrary to the stringent applet security seen earlier.

So, using `java.awt.applet`'s `AudioClip` means your application has to be an applet, it can only run a handful of audio formats, and your media can't be local unless you go through the hassle of overriding the `SecurityManager` for the applet.

As you might imagine, early Java developers demanded a replacement.



## Hack 71. Play a Sound with JavaSound



Get a small clip to play from memory with a lot less hassle.

The JavaSound API was developed to answer complaints about the inadequacies of the `AudioClip` class in the applet package...not the least of which was the fact that it couldn't be used in applications. JavaSound consists of two packages `javax.sound.sampled` and `javax.sound.midi` plus two service provider interface (`spi`) sub-packages for adding support for new devices, formats, converters, etc.

JavaSound was introduced as an extension to Java 1.2 (I know, I know, "Java 2 Standard Edition, version 1.2"), and it became part of Core Java in 1.3. In other words, you're pretty safe assuming that it's present on your user's machine. That's one big point in its favor.

### 10.3.1. Putting JavaSound to Work

To show off JavaSound, the code in [Example 10-3](#) exhibits a short application that allows the user to pick a file from the local filesystem and play it. A dialog shows the selected filename; OK it when the audio completes to exit the program.

#### Example 10-3. Playing audio with JavaSound

```
public class CoreJavaSound extends Object
    implements LineListener {

    File soundFile;
    JDialog playingDialog;
    Clip clip;

    public static void main (String[] args) {
        JFileChooser chooser = new JFileChooser();
        chooser.showOpenDialog(null);
        File f = chooser.getSelectedFile();
        try {
            CoreJavaSound s = new CoreJavaSound (f);
        } catch (Exception e) {
            e.printStackTrace();
        }
    }
}
```

```

public CoreJavaSound (File f)
    throws LineUnavailableException, IOException,
        UnsupportedAudioFileException {
    soundFile = f;
    // prepare a dialog to display while playing
    JOptionPane pane = new JOptionPane ("Playing " + f.getName(),
        JOptionPane.PLAIN_MESSAGE);
    playingDialog = pane.createDialog (null, "Application Sound");
    playingDialog.pack();

    // get and play sound
    Line.Info linfo = new Line.Info (Clip.class);
    Line line = AudioSystem.getLine (linfo);
    clip = (Clip) line;
    clip.addLineListener (this);
    AudioInputStream ais = AudioSystem.getAudioInputStream(soundFile);
    clip.open (ais);
    clip.start();
}
// LineListener
public void update (LineEvent le) {
    LineEvent.Type type = le.getType();
    if (type == LineEvent.Type.OPEN) {
        System.out.println ("OPEN");
    } else if (type == LineEvent.Type.CLOSE) {
        System.out.println ("CLOSE");
        System.exit (0);
    } else if (type == LineEvent.Type.START) {
        System.out.println ("START");
        playingDialog.setVisible(true);
    } else if (type == LineEvent.Type.STOP) {
        System.out.println ("STOP");
    }
}
}
}

```

The JavaSound API for working with sampled sounds is an elaborate perhaps even baroque set of abstractions about the various parts of a sound system. The point of entry is an `AudioSystem`, whose various `static` methods let you get at the different sound resources. These include `Lines`, which are audio feeds (input or output); `Mixers`, which combine lines; `AudioInputStreams`, which represent incoming audio data; and format conversions. `Line` has a sub-interface called `DataLine`, which has a sub-interface called `Clip`, which represents a line that can be loaded into memory and played immediately, instead of streaming out from its source. If your data is small enough to fit in memory while being played, this is a particularly convenient class to work with.

If your audio is not small enough to fit in memory, check out how to play JavaSound files of any length [\[Hack #76\]](#) later in this chapter.

---

To play audio in JavaSound, you need to set up a `DataLine` and call its `start()` method. Easier said than done, though this is the baroque part.

There are a couple of ways to get a `Line`. In the most basic case, you just indicate that you want a line that can work with a given class. Because this example works with `Clips`, it asks for a `Line.Info` object suitable for use with `Clips`. Then you pass that info object to the `AudioSystem` to get a `Line`, which can be cast to a `Clip` since that's what you asked for in the first place.

Before setting up the media data, this example sets up a `LineListener`, which will provide events when the media is opened, starts playing, stops playing, and is closed.

OK, you've got a `Clip`, so here's how to get some audio data into it. You create an `AudioInputStream` from the static `getAudioInputStream()` method, then pass it to `Clip`'s `open()` method. This makes the clip operational: it prefetches any needed system resources and enters a "ready to play" state. Now, you can just play the audio with the `start()` method, inherited from `DataLine`.

The example sets up a `LineListener` on the `Clip` and looks at the type of received events for four values defined in the `LineEvent.Type` class: `OPEN`, `CLOSE`, `START`, and `STOP`. All of these are logged to standard out, and then an appropriate action is taken: `START` makes the dialog visible, `STOP` hides the dialog and closes the clip (this is called when you OK the dialog), and `CLOSE` exits the application (and is called as a side effect of `clip.close()` in the handling of `STOP`).

There are a lot more classes in the package, and you can write really confusing code with them and I haven't even mentioned MIDI. But for the stated goal of playing a small audio file with a minimum of fuss, that's how you do it with JavaSound.

## 10.3.2. Listen Up

When you run the demo program, it brings up a regular `JFileChooser`. You need to pick a sound file from one of JavaSound's supported file formats... of which there are only three: WAV, AIFF, and AU (not MP3, WMA, or Ogg). You knew there had to be a catch, right? Moreover, by default, Java-Sound only plays uncompressed sound files, so if the data in the file is in ALAW, ULAW, MACE, etc., it won't play.

If JavaSound can read it, it will start playing the chosen file immediately. The demo also shows a dialog like [Figure 10-3](#), showing the name of the chosen audio file.

Figure 10-3. Dialog showing current sound file

Clicking the OK button clears the dialog and unblocks the AWT so that when the clip finishes playing, the `STOP` event can remove the dialog from the screen and close the clip, which exits the demo.

Working with the `AudioSystem` and having to pass around description objects is a little strange, especially with JavaSound's habit of using public inner classes as descriptor objects, but thanks to the `Clip` class, it does offer a pretty reasonable way to play small audio clips from your program.

The downside to JavaSound is the small number of supported formats. Java-Sound, at least out of the box, isn't well suited to handle having random sound formats thrown at it. That's not a problem if you're supplying your own sounds for your application just stick with AIFF or WAV. But it does make JavaSound less than useful in a media browser or some other application that is going to have to deal with random formats encountered on the Net or the user's local storage. Of course, that's part of the idea of the `spi` sub-package: Sun provides the framework, and third parties make their formats available to Java by implementing `spi` interfaces.



[← PREY](#)

## Hack 72. Play a Sound with Java Media Framework



Use the Java Media Framework for better performance and support for more audio formats.

Java Media Framework (JMF) is Sun's attempt to bring a broadly focused multimedia framework to Java, supporting audio, video, and other timebased media types. The idea is to provide Java desktop applications with these features across operating systems. Like JavaSound, it's meant to be extended so that Sun or third parties could add support for new file formats or codecs (the compression/decompression encoding schemes used inside those files).

JMF offers another way to provide sound from an application. The advantages of doing so are that JMF *may* provide access to many more sound files than JavaSound will alone, and that JMF is somewhat easier to code than JavaSound, particularly for simple tasks. The disadvantages are that JMF capabilities vary wildly by platform, and that the end user will have to install JMF separately, which will be difficult or simply not allowed for some users.

### 10.4.1. Installing JMF

Download and install JMF from its home page at <http://java.sun.com/products/java-media/jmf/index.jsp> and you should be ready to go no reboot required. The installers should have put everything into the correct path and set up your environment. If you have trouble getting JMF programs to run, or if you used the all-Java version that doesn't have a special installer, you can try adding the following environment variable:

```
JMFHOME="C:\Program Files\JMF2.1.1"
```

Next, add the two JMF Java libraries to your classpath:

```
CLASSPATH=" $JMFHOME\lib\jmf.jar;$JMFHOME\lib\sound.jar;.;$CLASSPATH"  
PATH=" $JMFHOME\lib;$PATH"
```

### 10.4.2. The Code

The demo in [Example 10-4](#) is basically a port of the `CoreJavaSound` demo used in playing audio with JavaSound [\[Hack #71\]](#), except that the eventhandling has been simplified to a "quit when done" implementation. JMF's playback metaphor involves `Players`, which simply play media, and `Processors`, which may take action on the media, such as adding effects or transcoding to other formats. This allows the simple stuff to stay simple: to play a file, you wire it up to a `Player`, tell everything to get initialized ("realized" in JMF parlance), and call `start()`. Notice that while the other `imports` are omitted as usual, this listing shows the `import javax.media.*` that will bring in the JMF classes used here.

## Example 10-4. Playing audio with Java Media Framework

```
import javax.media.*;

public class JMFSound extends Object
    implements ControllerListener {

    File soundFile;
    JDialog playingDialog;

    public static void main (String[] args) {
        JFileChooser chooser = new JFileChooser();
        chooser.showOpenDialog(null);
        File f = chooser.getSelectedFile();
        try {
            JMFSound s = new JMFSound (f);
        } catch (Exception e) {
            e.printStackTrace();
        }
    }

    public JMFSound (File f)
        throws NoPlayerException, CannotRealizeException,
            MalformedURLException, IOException {
        soundFile = f;
        // prepare a dialog to display while playing
        JOptionPane pane = new JOptionPane ("Playing " + f.getName(),
            JOptionPane.PLAIN_MESSAGE);
        playingDialog = pane.createDialog (null, "JMF Sound");
        playingDialog.pack();

        // get a player
        MediaLocator mediaLocator =
            new MediaLocator(soundFile.toURL());
        Player player =
            Manager.createRealizedPlayer (mediaLocator);
        player.addControllerListener (this);
        player.prefetch();
        player.start();
        playingDialog.setVisible(true);
    }
}
```



```

}
// ControllerListener implementation
public void controllerUpdate (ControllerEvent e) {
    System.out.println (e.getClass().getName());
    if (e instanceof EndOfMediaEvent) {
        playingDialog.setVisible(false);
        System.exit (0);
    }
}
}
}

```

The major change from the `CoreJavaSound` demo is in the constructor, after the dialog is readied. You create a `MediaLocator`, a sort of generic means of referring to the source location of media, from a URL of the selected file.

The `MediaLocator` allows you to create a `Player` with a one-line call to `Manager.createRealizedPlayer(MediaLocator)`. A lot occurs in this call: the `Manager`, a sort of central point of access to JMF resources, creates a `Player`, wires it up to the `MediaLocator`, calls `prefetch()` to process some of the media data (to reduce startup delay), and calls `realize()` to allocate systemdependent media resources. The result is a ready-to-play `Player`.

To add event-awareness, add a listener with `addControllerListener()`, `Controller` being a superclass of `Player`. Finally, you can play the media with `start()`.

The `ControllerListener` interface defines a single method, `controllerUpdate()`, which receives a `ControllerEvent`. In JMF, the class of the event is used for determining behavior; there are more than a dozen you might choose to deal with. To get the "end of the media" event, you just check to see if the event is an `EndOfMediaEvent` object, which in this case is handled by hiding the dialog and quitting the application.

### 10.4.3. Take JMF for a Spin

Functionally, the application is largely identical to the `CoreJavaSound` demo: a `JFileChooser` asks you to pick a file. When you do, it starts playing and a dialog box shows you the filename. When the audio completes, the application quits.

The one thing that's really different is that you can play many more file formats than you can with just `JavaSound`. Or maybe you can't. It all depends on what operating system you're running on. The JMF install offers an all-Java version and "performance packs" for some operating systems, which use native code. The latter offer not only better performance for the media formats supported by the all-Java version, they also integrate with the native media library on the host operating system to play other media files, ones that couldn't be opened with the all-Java version alone.

This might make you deceive yourself: if you develop a JMF application on Windows and it works with your media, it won't necessarily work on another operating system, either because Sun never made a performance pack for that system (Mac OS X), or because even with the performance pack, the native libraries don't support that format. If you go the JMF route, you need to rigorously test cross-platform, or you may very well have an application that really only works on one OS.



## Hack 73. Play a Sound with QuickTime for Java



Using QuickTime, you can play even more kinds of sounds, but only on two operating systems.

QuickTime for Java offers another way to significantly improve the media capabilities of your application. Its list of supported formats is huge (see <http://www.apple.com/quicktime/products/qt/specifications.html> for the current list) and always growing as Apple continues to improve it. That's a big advantage over JMF, which was dropped into maintenance mode in 1999 and largely ignored since then.

The huge disadvantage with QuickTime for Java is that it works on Windows and Mac only. That's because QTJ, as it's typically called, is really just an object-oriented (OO) wrapper to call C functions in the native Quick-Time library. That gives you native-speed performance, but it also means the wrappers don't do anything without an underlying native implementation.

### 10.5.1. QuickTime Beating Up on JavaSound

For the purposes of this hack, let's say you only need to support Mac and Windows, or that you need to open files from the iTunes Music Store (QTJ can do it, which is apparently the only way to do it in Java), or for whatever reason QTJ looks like the right solution. [Example 10-5](#) shows a port of the JavaSound audio player to a QTJ-based implementation.

#### Example 10-5. Playing audio with QuickTime for Java

```
import quicktime.std.*;
import quicktime.std.clocks.*;
import quicktime.std.movies.*;
import quicktime.*;
import quicktime.io.*;
import quicktime.app.time.*;

public class QTJSound extends Object {

    File soundFile;
    JDialog playingDialog;
    Movie movie;

    public static void main (String[] args) {
```

```

JFileChooser chooser = new JFileChooser();
chooser.showOpenDialog(null);
File f = chooser.getSelectedFile();
try {

    QTJSound s = new QTJSound (f);
} catch (Exception e) {
    e.printStackTrace();
}
}

public QTJSound (File f)
throws QTException {
soundFile = f;
// prepare a dialog to display while playing
    JOptionPane pane = new JOptionPane ("Playing " + f.getName(),
        JOptionPane.PLAIN_MESSAGE);
playingDialog = pane.createDialog (null, "QTJ Sound");
playingDialog.pack();

// get and play sound
QTSession.open();
QTFile qtf = new QTFile (f);
OpenMovieFile omf = OpenMovieFile.asRead (qtf);
movie = Movie.fromFile (omf);
MyDemoCloser closer = new MyDemoCloser (movie);
TaskAllMovies.addMovieAndStart ();
movie.start();
playingDialog.setVisible(true);
}
class MyDemoCloser extends ExtremesCallBack {

public MyDemoCloser (Movie m) throws QTException {    super (m.getTimeBase(),
    StdQTConstants.triggerAtStop);
        callMeWhen();
    }
public void execute() {
    playingDialog.setVisible (false);
    System.out.println ("dialog closed");
    // note: this can hang on Windows - consider
    // using QTSession.exitMovies() instead
    QTSession.close();
    System.out.println ("closed QTSession");
    System.exit(0);
}
}
}
}

```

Some of this code looks very un-Java-like and there's a reason: QTJ is an object-oriented wrapper around a straight-C API. Whenever I see the C versions of things I do in QTJ, I'm grateful they got it

as OO as they did. Nevertheless, there are differences: where a Java developer would expect to deal with listeners, QTJ makes you wrangle `CallBack` objects, which have to reregister themselves every time they're called or else they're forgotten. And the number of `imports` for a small class is quite atypical. QTJ is highly granular in its class organization.

Take a look at the constructor. After doing the file-selection dialog, it calls `QTSession.open()`. This is a call that initializes QuickTime resources and must be made before any other QTJ call, or an exception will be thrown. You'll be responsible for shutting down QuickTime later, of course.

The basic thing you want to do is to use the file to create a `Movie`. Don't worry, this isn't turning into a video hack; QuickTime uses the term *movie* for any playable or displayable thing it works with: audio, video, audio and video, Flash, static images, etc. To create the `Movie`, you need an `OpenMovieFile`, which you get by making a `QTFile` from `java.io.File` and then using the static `asRead()` to get an `OpenMovieFile`.

The demo sets up a callback by creating an instance of the inner class `MyDemoCloser`, calls the cryptic `TaskAllMovies.addMovieAndStart()` (more on that later), and finally starts the audio with `Movie.start()`. If the source is a URL, or a file on really slow media, it might help to call `Movie.prePreroll()` and `Movie.preroll()` before starting, to let QuickTime pre-allocate needed system resources and read in some data.

Setting up a callback to close everything down requires use of an `ExtRemesCallBack`, which is an object that gets called when either the beginning or end of the movie is reached. Its constructor takes the movie's timebase (which is an object representing the movie's time-keeping system) and a flag to indicate what conditions the callback should be called in. The flag is an int, but it really contains bit values that can be ORed together. For example, if the media could play in both directions and you wanted to be notified when it reached the beginning of the movie too, you'd pass `StdQTConstants.triggerAtStop | StdQTConstants.triggerAtStart`.

Next, you have to use `callMeWhen()` to register the callback. This signs you up for one callback if you're called and are still interested in future events, you have to reregister with another `callMeWhen()`.

When the sound finishes, the callback calls `execute()`. This is when you shut everything down, as in the other hacks. Notice that you close down Quick-Time with `QTSession.close()`, the obvious counterpart to `QTSession.open()`. There are some issues about how well it works on Windows: it sometimes hangs for me, and you may want to use the safer `QTSession.exitMovies()`, which only closes down some of QTJ, but the rest seems to get taken care of by QTJ itself, as I've never had a problem.

And one more bit of arcane QTJ lore: the code makes a call to `TaskAllMovies.addMovieAndStart()`. This helps deal with the fact that movies have to explicitly be given CPU time, with calls to `atask()` method, in order to work. `TaskAllMovies` is a convenience Thread that can periodically make this tasking call for all your movies. If you've read Chris' book on QTJ, you would think that this isn't necessary, as having the AWT eventdispatch thread usually provides tasking calls. The problem is that the dialog box that's showing while the audio plays is modal; thus, it *blocks the event loop*, which in turn blocks the tasking you usually get for free with AWT. So, you have to set it up yourself.

QTJ is full of weird gotchas like this. What do you expect when it's largely a port from C?

## 10.5.2. Compiling QuickTime Code

Yep, this hack has special compile instructions. First, you have to be sure that your machine even has QuickTime for Java on it. It's installed by default with Mac OS X, so this is only an issue for Windows-based developers. On Windows, if you don't have QuickTime at all, get it from <http://www.apple.com/quicktime/> and do a custom install: QuickTime for Java will be one of the non-default optional pieces, and you just need to checkmark it to include it in your install. If you do have QuickTime, run the QuickTime Updater from your Start menu or your tray to do a "custom" update, which will show the same list of optional pieces as the main installer.

The install or update will put *QTJava.zip* into the *lib/ext* of any Java home folders it finds. It should also put a copy in *C:\windows\system32* and add a system-wide environment variable `QTJAVA` pointing to one of these files, with the path in quotes (which may or may not be good for you, depending on what else you do with environment variables).

Here's the fun part about compiling: you must explicitly point your compiletime classpath to one of these *QTJava.zip* files for `javac` (or `jikes`, or whatever) to find the QTJ classes. If you don't, you'll get a bunch of compiletime errors like:

```
QTJSound.java:4: package quicktime.std does not exist
import quicktime.std.*;
^
QTJSound.java:5: package quicktime.std.clocks does not exist
import quicktime.std.clocks.*;
^
QTJSound.java:6: package quicktime.std.movies does not exist
import quicktime.std.movies.*;
```

So, assuming you want to work with a copy of Java installed in *Program Files\Java\j2re1.4.2\_06* (which is my current path...yours may vary), you compile this demo with the following command:

```
C:\>javac
-classpath "c:\Program Files\Java\j2re1.4.2_06\lib\ext\QTJava.zip"
QTJSound.java
```

This should be typed as one line I've word-wrapped to accommodate the book's margins.

You can substitute any other path to a *QTJava.zip* file for the classpath if you find it more convenient, or just write an Ant build file to automate everything for you.

On Mac OS X, the location of *QTJava.zip* is never a mystery because the system installer puts it in */System/Library/Java/Extensions.QTJava.zip*. So, you compile with:

```
[aeris:HacksBook/Media/52] cadamson% javac -classpath
/System/Library/Java/Extensions/QTJava.zip
QTJSound.java
```

In either case, you'll probably be relieved to know that you don't have to specify the classpath when *running* a QTJ application.

### 10.5.3. Running the Code

Like the JMF port [\[Hack #72\]](#), *QTJSound* looks and feels more or less the same as the original *CoreJavaSound* [\[Hack #71\]](#). The big difference is in the supported sound file formats. QuickTime will open not just uncompressed WAVs and AIFFs, but compressed data in those formats, along with MP3s, AACs, 3GPP mobile audio files, iTunes Music Store files, audio tracks of various audio/video formats like QuickTime movies (*.mov*), MPEG-4, even audio CD tracks (but only on the Mac).

That's obviously the big win with QuickTime for Java: you get support for a lot more formats. The price you pay is that your code only runs on two operating systems and that it can be difficult to write. The ideal would be if the obvious points of extensibility in *JavaSound* and *JMF* had been exploited, so that more formats would be available when using those APIs. With a notable exception [\[Hack #74\]](#), that hasn't happened yet.

By the way, to learn more about QuickTime for Java, check out *QuickTime for Java: A Developer's Notebook* (O'Reilly).

## Hack 74. Add MP3 Support to JMF



MP3s are everywhere, and by installing a plug-in you can use them with Java Media Framework, too.

It used to be said that every program will continue to grow until it includes an email reader. Today we could say the same for MP3 players. They are everywhere, and any program that has plug-ins will eventually be given a music player. Playing MP3s in Java used to be quite an ordeal, involving a suite of toolkits and codecs from different sources. Fortunately, it's a lot easier to play an MP3 file these days, and this hack shows how.

JMF came out in 1998, supporting playback of a number of audio and video formats, but not MP3. Support for this popular format arrived with JMF 2.0 in 1999. Unfortunately, in 2002, Sun removed MP3 support from JMF because of licensing problems. Finally, in November of 2004, Sun released a fully licensed MP3 plug-in for public download on their web site. With this plug-in, you can play any MP3 file with only four lines of code.

### 10.6.1. Add a Plug-In to JMF

First, install Java Media Framework [[Hack #72](#)]. To add MP3 support, download the plug-in from <http://java.sun.com/products/java-media/jmf/mp3/download.html>. The download page offers an *.exe* installer for Windows and a ZIP for other platforms. In both cases, there is an *mp3plugin.jar* file that the install docs say you need to place in the *ext/lib* directory of any JRE you want to provide the plug-in to. With the JAR in your classpath, you install the plug-in with the following command:

```
java com.sun.media.codec.audio.mp3.JavaDecoder
```

On Mac OS X, the proper way to add JAR files to the classpath is to put them in */Library/Java/Extensions*, instead of using the actual *ext/lib* directory, which is hard to find and will be wiped out by system installers and updates anyways.

### 10.6.2. Simplicity Is Nice

[Example 10-6](#) is the code for pretty much the simplest MP3 playing program you can create. You will need to `import javax.media.*` in addition to the usual `java.io` classes.



## Example 10-6. A very basic MP3 player

```
import javax.media.*;

public class MP3Player {

    public static void main(String[] args) throws Exception {
        File file = new File("test.mp3");
        MediaLocator mrl = new MediaLocator(file.toURL());
        Player player = Manager.createPlayer(mrl);
        player.start();
    }
}
```

Those four lines in `main()` do it all. The `MediaLocator` takes care of loading and buffering the file as long as you can give it a URL. The player controls the actual music output. It has the basic functions you would expect, like `start()` and `stop()`. If you compile and run this program with a test MP3 file, audio should start playing immediately.

### 10.6.3. Distribute Your Program

If you need to distribute your program, it's best to include platform installers and instruct users to install them first.

Licensing restrictions from Sun may apply here!

Even better, if you have a custom install program, make it run the JMF and MP3 installers first. If you don't have an installer or don't know which platform the program will be installed on, use the cross-platform versions (also available from the URLs mentioned in this hack). They are slower but are completely written in Java so they can run on anything.

[← PREV](#)

## Hack 75. Build an Audio Waveform Display



With a little understanding of audio data formats, you can easily build a basic graphical audio display.


Representing audio visually is extremely useful. You can use waveform displays to quickly tell audio files apart, like a file thumbnail, or for non-linear editing, such as deleting parts of the file and processing.

[Figure 10-4](#) shows a waveform displayed in Audacity, a free, open source audio editing application. This hack shows you how to build a basic waveform display from raw audio data.

Figure 10-4. Audacity with an audio waveform displayed

The end result of this hack is displayed in [Figure 10-5](#). You'll start by reading in the entire audio file using an `AudioInputStream`. Then you'll convert the raw data from the stream into useful audio samples, organized by channel. With the converted channel audio data, you'll create a single waveform panel. Then you'll wrap up the complete audio display by combining several waveform panels to display multi-channel audio.

Figure 10-5. The waveform display you'll build in this hack



### 10.7.1. Some Basic Definitions

You'll need to know a few basic terms and concepts about audio before you get started.

#### *Sample*

One measurement of audio data. For Pulse Code Modulated (PCM) encoding, a sample is an instantaneous representation of the voltage of the analog audio. There are other types of encoding, like  $\mu$ -law and a-law, that are rarely used.

#### *Sampling Rate*

The number of samples in one second. Measured in Hertz (Hz) or kilo-Hertz (kHz). The most common sampling rate is 44.1 kHz (CD quality audio). Often, you'll find 22.05 kHz or 11.025 kHz on the Web, since the files are smaller and the conversion is easier.

#### *Sample Size*

The number of bits in one sample. It is typically a multiple of eight because data is stored in 8-bit bytes. The most common sample size is 16 bits, which is CD quality audio. Often you'll find 8-bit audio because the files are smaller. You'll rarely find anything less than 8-bit audio because the quality is pretty poor. Sample size is sometimes called bit depth.

#### *Channel*

A channel is an independent stream of audio. Stereo is the most common form of multi-channel audioone independent left and right channel. Higher-end audio formats include 5.1 surround sound (actually six channels) and up.

## Frame

A frame is a cross section of samples across all channels in the audio file. So, a 16-bit stereo (two channel) audio file will have 32-bit frames (16 bits per sample \* 2 channels per frame = 32 bits per frame).

### 10.7.2. Load the Raw Data

Java reads raw audio data in 8-bit bytes, but most audio has a higher sample size. So, in order to represent the audio, you'll have to combine multiple bytes to create samples in the audio format. But first, you'll need to load all of the audio into a `buffer` before you combine the bytes into samples.

Start by getting an audio stream from a file:

```
File file = new File(filename);
AudioInputStream audioInputStream = AudioSystem.getAudioInputStream(file);
```

Now that you have the `AudioInputStream`, you can read in the audio data. `AudioInputStream` has a `read()` method that takes an unpopulated `byte[]` and reads in data the length of the `byte[]`. To read in the entire audio file in one shot, create a `byte[]` the length of the entire audio file. The complete length of the file in bytes is:

```
total number of bytes = bytes per frame * total number of frames
```

You can get the number of frames for the whole file (`frameLength`) and the size of the frame (`frameSize`) from the `AudioInputStream`:

```
int frameLength = (int) audioInputStream.getFrameLength();
int frameSize = (int) audioInputStream.getFormat().getFrameSize();
```

You can create the `byte[]` with the length set to `frameLength*frameSize`:

```
byte[] bytes = new byte[frameLength * frameSize];
```

Finally, you can read in the audio, passing the `AudioInputStream` the empty `byte[]` and catching the appropriate exceptions:

```

int result = 0;
try {
    result = audioInputStream.read(bytes) ;
} catch (Exception e) {
    e.printStackTrace();
}

```

### 10.7.3. Convert to Samples and Channels

The raw audio data isn't very useful. It needs to be broken up into channels and samples. From there, it's easy to paint the samples.

The `bytes` will be converted to samples and represented as `ints`. You'll need a container to store the samples across all channels. So, create a two dimensional `int[][]` referencing the channel and samples per channel. You've already seen how to get the frame length from the `AuduiioInputStream`, and you can get the number of channels the same way. Here is the code to initialize the `int[][]`:

```

int numChannels = audioInputStream.getFormat().getChannels();
int frameLength = (int) audioInputStream.getFrameLength();
int[][] toReturn = new int[numChannels][frameLength];

```


Now, you need to iterate through the `byte[]`, convert the bytes to samples, and place the sample in the appropriate channel in the `int[][]`. The `byte[]` is organized by frames, meaning that you'll read in a sample for every channel rather than all of the samples for a specific channel in a row. So, the flow is to loop through the channels and add samples until the `byte[]` has been iterated completely:

```

int sampleIndex = 0;

for (int t = 0; t < eightBitByteArray.length;) {
    for (int channel = 0; channel < numChannels; channel++) {
        int low = (int) eightBitByteArray[t];
        t++;
        int high = (int) eightBitByteArray[t];
        t++;
        int sample = getSixteenBitSample(high, low);
        toReturn[channel][sampleIndex] = sample;
    }
    sampleIndex++;
}

```



This hack is going to deal exclusively with 16-bit samples. They are by far the most common. Plus, you can get an idea for how sample conversion works while still keeping things pretty straightforward. This code gets much trickier with multiple dynamic sample sizes.

Now for the `getSixteenBitSample()` method. You can't simply add the bytes together using regular addition because the bits are displaced in a 16-bit sample the high byte represents bits 0 through 7, and the low byte represents bits 8 through 15. It's more like concatenation, so the type of math shown here won't work:

```
1010 1101 (high byte)
+ 0011 0010 (low byte)
  1101 1111
```

What you want is more like this:

```
1010 1101      (high byte)
+   0011 0010 (low byte)
-----
1010 1101 0011 0010
```

And in order to get this to work with standard addition, you need to add two 16-bit bytes with bits shifted and placeholder 0s added where necessary. Then you get something like this:

```
1010 1101 0000 0000 (high byte)
+ 0000 0000 0011 0010 (low byte)
-----
  1010 1101 0011 0010
```

The high byte needs to be *bit shifted*. Bit shifting, the process of sliding bits around, is typically a big no-no in Java as a result, you've probably never seen the bit-shifting operator before (it's `<<` or `>>` depending on the direction followed by the number of bits to shift in either direction). However, here it is necessary to use bit shifting, so you will bit shift the high byte 8 bits to the left:

```
high << 8
```

Now, you need to prepend the leading 0s onto the low byte. You can do this using the bit `AND` operator and using a 16-bit byte consisting of all 0s. It works like this:

```

0000 0000 0000 0000 (all 0's bytes)
+   0011 0010 (low byte)
-----
0000 0000 0011 0010

```

Here is the code for the sample conversion:

```

private int getSixteenBitSample(int high, int low) {
    return (high << 8) + (low & 0x00ff);
}

```

## 10.7.4. Creating a Single Waveform Display

Now that you have the audio sample data organized by channels, it's time to get to painting. To keep everything modular, create a class called `SingleWaveformPanel` to paint one channel of audio data. In the next section, you'll write a `WaveformPanelContainer` to use multiple `SingleWaveformPanels` to handle multi-channel audio.

The waveform painting is going to be drawn by plotting points scaled to the sample data and drawing lines between them. This is simplistic, but it yields good results. [Figures 10-4](#) and [10-5](#) show the same waveform in Audacity and the simulator for this hack; they're pretty close.

I'm going to gloss over the scaling code because I really want to concentrate on the conversion from audio information to visualization. But to understand why scaling is necessary, remember that CD quality audio has 44,100 samples per second. So, without scaling, you would need 44,100 horizontal pixels for every second of your audio file. Obviously, this is impractical. So, if you dig into the source code for this hack, you can see the scaling and how the scales are determined. Meanwhile, just assume that the waveform is always scaled to fit in the panel.

Start by drawing the center line at 0:

```

g.setColor(REFERENCE_LINE_COLOR);
g.drawLine(0, lineHeight, (int)getWidth(), lineHeight);

```

Next, mark the origin to start drawing at 0,0:

```

int oldX = 0;
int oldY = (int) (getHeight() / 2);
int xIndex = 0;

```

Now, you need to figure out the incremental jump between samples to adjust for the scale factor. This works out to be:

```
number of samples / (number of samples * horizontal scale factor)
```

The following code grabs the increment and paints a line from the origin to the first sample:

```
int increment = getIncrement()
g.setColor(WAVEFORM_COLOR);

int t = 0;

for (t = 0; t < increment; t += increment) {
    g.drawLine(oldX, oldY, xIndex, oldY);
    xIndex++;
    oldX = xIndex;
}
```

Finish up by iterating through the audio and drawing lines to the scaled samples:

```
for (; t < samples.length; t += increment) {
    double scaleFactor = getYScaleFactor();
    double scaledSample = samples[t] * scaleFactor;
    int y = (int) ((getHeight() / 2) - (scaledSample));
    g.drawLine(oldX, oldY, xIndex, y);


    xIndex++;
    oldX = xIndex;
    oldY = y;
}
}
```

### 10.7.5. Create a Container

Now that you have the waveform painting under control, you need to create a container called `WaveformPanelContainer` for `SingleWaveformPanels` in order to show multi-channel audio. [Figure 10-6](#) shows the waveform in the simulator.



Figure 10-6. Multi-channel (stereo) audio in the simulator for this hack



[Example 10-7](#) is the complete code for the `WaveformPanelContainer`. `AudioInfo` is a helper class that contains references to the loaded audio samples and the current channel.

### Example 10-7. Testing out the waveform display

```
public class WaveformPanelContainer extends JPanel {
    private ArrayList singleChannelWaveformPanels = new ArrayList();
    private AudioInfo audioInfo = null;

    public WaveformPanelContainer() {
        setLayout(new GridLayout(0,1));
    }

    public void setAudioToDisplay(AudioInputStream audioInputStream){
        singleChannelWaveformPanels = new ArrayList();
        audioInfo = new AudioInfo(audioInputStream);
        for (int t=0; t<audioInfo.getNumberOfChannels(); t++){
            SingleWaveformPanel waveformPanel
                = new SingleWaveformPanel(audioInfo, t);
            singleChannelWaveformPanels.add(waveformPanel);
            add(createChannelDisplay(waveformPanel, t));
        }
    }
    private JComponent createChannelDisplay(
        SingleWaveformPanel waveformPanel,
        int index) {

        JPanel panel = new JPanel(new BorderLayout());
        panel.add(waveformPanel, BorderLayout.CENTER);

        JLabel label = new JLabel("Channel " + ++index);
        panel.add(label, BorderLayout.NORTH);
    }
}
```

```

    return panel;
}
}

```

## 10.7.6. Seeing Is Believing

Now, you're ready to run the hack. The `main()` method shown here is the simulator code. Notice the creation of the `AudioInputStream` and the creation of the container with the stream. All painting and management of `SingleWaveformPanels` is encapsulated within the separate panel classes:

```

public static void main(String[] args) {
    try {

        JFrame frame = new JFrame("Waveform Display Simulator");
        frame.setBounds(200,200, 500, 350);

        File file = new File(args[0]);
        AudioInputStream audioInputStream
            = AudioSystem.getAudioInputStream(file);

        WaveformPanelContainer container = new WaveformPanelContainer();
        container.setAudioToDisplay(audioInputStream);

        frame.getContentPane().setLayout(new BorderLayout());
        frame.getContentPane().add(container, BorderLayout.CENTER);

        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

        frame.show();
        frame.validate();
        frame.repaint();

    } catch (Exception e){
        e.printStackTrace();
    }
}

```

Then, just make sure to pass the audio filename in at the command line. Use something like this:

```
java WaveformDisplaySimulator chord.wav
```



This hack shows you how to do all of the sample conversion and painting you need to display a waveform very simplistically. However, you should address a few key issues before using this in an audio application; for example, this only deals with 16-bit audio. You probably would want to build something a little more generic to deal with other sample sizes. You may also want to deal with compression, so you can display waveforms for MP3 files. That said, this hack still gives you a good idea of how to dig into raw audio data and get your audio visualization on.

*Jonathan Simon*

← PREY

## Hack 76. Play Non-Trivial Audio



When loading an entire audio clip into memory is a bad idea (or just impossible), you have to take JavaSound responsibilities into your own hands.

Playing JavaSound audio with a `Clip` [[Hack #71](#)] is a pretty convenient way to play a short sound, like a sound effect for a desktop application. The only problem is that the `Clip` loads all the audio into memory, which could have a couple of bad side effects:

- It makes your application use more memory, which could cause problems.
- The audio you need might not fit into memory at all.


You might have run into this second point if you tried to load a really big audio file into `Clip`. For example, I took a 3 minute, 45 second track from a CD and converted it to 8-bit mono PCM in an AIFF file, which ended up being 9.4 MB. You can guess what happened:

```
[aeris:HacksBook/Media/52] cadamson% java CoreJavaSound
javax.sound.sampled.LineUnavailableException: Failed to allocate clip data:
Requested buffer too large.
  at com.sun.media.sound.MixerClip.implOpen(MixerClip.java:536)
  at com.sun.media.sound.MixerClip.open(MixerClip.java:161)
  at com.sun.media.sound.MixerClip.open(MixerClip.java:249)
  at CoreJavaSound.<init>(CoreJavaSound.java:39)
  at CoreJavaSound.main(CoreJavaSound.java:17)
```

Unfortunately, most of the JavaSound code you'll find on the Web deals with `Clips` only and not with getting a `Line` for larger files, or potentially endless streams for that matter. Why? Perhaps because JavaSound doesn't do it for you *you* are responsible for reading bytes and feeding them to JavaSound!

### 10.8.1. Grabbing a `DataLine`

This hack is going to play an uncompressed (i.e., PCM) AIFF or WAV file of arbitrary length by getting a `DataLine` for the data and then repeatedly reading the data from disk and writing it to the `DataLine`.



PCM stands for *Pulse Code Modulation*, which means that analog audio has been sampled at regular intervals and quantized (i.e., each sample is expressed as a numeric value). It's the lowest-level, most common denominator data that JavaSound understands, since it can be delivered directly to a sound system for playback.

The class to do this will be called `PCMFilePlayer`. Given a file, its responsibilities are to:

- Verify that the file contains PCM data (signed or unsigned).
- Get a `Line` for this format.
- Kick off a thread to read bytes from the file and write them to the `Line`, which plays them.

Reading and writing bytes doesn't sound too bad, but JavaSound imposes another requirement on you: you have to send complete frames, not just a bunch of bytes, to the `Line`. A frame is one complete sample of audio in whatever format you're dealing with. For the PCM formats supported by this hack, a frame can be one of three sizes:

- 1 byte for 8-bit mono sound
- 2 bytes for either 8-bit stereo sound or 16-bit mono sound
- 4 bytes for 16-bit stereo sound

The implication for the read-write loop is that if you read some number of bytes that leave you off an even frame boundary, then you have to save the partial frame you've read, not send it to the `Line`, and instead append it to the beginning of the next read.

Finally, when you reach the end of the file, you need to call `Line.drain()` to make sure it plays out all the data you've sent it, and then close the `Line`.

The code for the `PCMLinePlayer` is shown in [Example 10-8](#).

## Example 10-8. Playing uncompressed audio files in JavaSound

```
import javax.sound.sampled.*;

public class PCMFilePlayer implements Runnable {
    File file;
    AudioInputStream in;
    SourceDataLine line;
    int frameSize;
    byte[] buffer = new byte [32 * 1024]; // 32k is arbitrary
    Thread playThread;
    boolean playing;
    boolean notYetEOF;
}
```

```

public PCMFilePlayer (File f)
throws IOException,
    UnsupportedAudioFileException,
    LineUnavailableException {
file = f;
in = AudioSystem.getAudioInputStream (f);
AudioFormat format = in.getFormat();
AudioFormat.Encoding formatEncoding = format.getEncoding();
if (!(formatEncoding.equals (AudioFormat.Encoding.PCM_SIGNED) ||
    formatEncoding.equals (AudioFormat.Encoding.PCM_UNSIGNED)))
    throw new UnsupportedAudioFileException (
        file.getName() + " is not PCM audio");
    System.out.println ("got PCM format");
frameSize = format.getFrameSize();
DataLine.Info info =
    new DataLine.Info (SourceDataLine.class, format);
System.out.println ("got info");
line = (SourceDataLine) AudioSystem.getLine (info);
System.out.println ("got line");
line.open();
System.out.println ("opened line");
playThread = new Thread (this);
playing = false;
notYetEOF = true;
playThread.start();
}
public void run() {
int readPoint = 0;
int bytesRead = 0;

try {
while (notYetEOF) {
if (playing) {
bytesRead = in.read (buffer,
    readPoint,
    buffer.length - readPoint);
if (bytesRead == -1) {
notYetEOF = false;
break;
}
// how many frames did we get,
// and how many are left over?
int frames = bytesRead / frameSize;
int leftover = bytesRead % frameSize;
// send to line
line.write (buffer, readPoint, bytesRead-leftover);
// save the leftover bytes
System.arraycopy (buffer, bytesRead,
    buffer, 0,
    leftover);
readPoint = leftover;
}
}

```

```

        } else {
            // if not playing
            // Thread.yield();
            try { Thread.sleep (10);}
            catch (InterruptedException ie) {}
        }
    } // while notYetEOF
    System.out.println ("reached eof");
    line.drain();
    line.stop();
} catch (IOException ioe) {
    ioe.printStackTrace();
} finally {
    // line.close();
}
} // run

public void start() {
    playing = true;
    if (! playThread.isAlive())
        playThread.start();
    line.start();
}

public void stop() {
    playing = false;
    line.stop();
}

public SourceDataLine getLine() {
    return line;
}

public File getFile() {
    return file;
}
}

```

Notice in the constructor that, as with the `Clip`, the way to get an actual `Line` object is to construct a `DataLine.Info` object and then pass that to `AudioSystem`. This time, you construct a `DataLine.Info` class with both the `SourceDataLine` class you need this subclass of `Line` because it provides the `write()` method with which you supply bytes to the `Line` and an `AudioFormat` object describing the data you'll be supplying. Assuming that doesn't throw a `LineUnavailableException` (and it shouldn't, because the format is already known to be PCM, which JavaSound always supports), you'll have a line that you can open and start writing bytes to.

As mentioned previously, the key issue for the thread that reads bytes from the file and writes them to the `Line` is that it has to be aware of frame boundaries. In this code, `readPoint` indicates the index of the buffer to start reading bytes into. When you have an incomplete frame after reading from the input stream, you copy the bytes from the incomplete frame to the front of the buffer in preparation

for the next read. For example, if you have a frame size of 4, and `bytesRead % 4` equals 3, then you copy those 3 bytes to the front of the buffer and set `readPoint` to 3. The next `read()` will start at 3, and the first byte read into the buffer will complete the frame from the previous `read()`.

## 10.8.2. Big Files, Big Sound

Since this is still in the realm of JavaSound, much of what was shown in the `Clip`-based hack still works. A demo application simply has to provide `PCMFilePlayer` with a file and then start it. Since `PCMFilePlayer` exposes its `Line` through a `get` method, you can even wire up as a `LineListener` and get notified of `STOP`, `START`, `OPEN`, and `CLOSE` `LineEvents`. [Example 10-9](#) shows the simple GUI, using `PCMFilePlayer`.

### Example 10-9. Playing arbitrarily long uncompressed WAV or AIFF audio

```
import javax.sound.sampled.*;

public class StreamingLineSound extends Object
    implements LineListener {
    File soundFile;
    JDialog playingDialog;
    PCMFilePlayer player;

    public static void main (String[] args) {
        JFileChooser chooser = new JFileChooser();
        chooser.showOpenDialog(null);
        File f = chooser.getSelectedFile();
        try {
            StreamingLineSound s = new StreamingLineSound (f);
        } catch (Exception e) {
            e.printStackTrace();
        }
    }

    public StreamingLineSound (File f)
        throws LineUnavailableException, IOException,
            UnsupportedAudioFileException {
        soundFile = f;
        // prepare a dialog to display while playing
        JOptionPane pane = new JOptionPane ("Playing " + f.getName(),
            JOptionPane.PLAIN_MESSAGE);
        playingDialog = pane.createDialog (null, "Streaming Sound");
        playingDialog.pack();

        player = new PCMFilePlayer (soundFile);
        player.getLine().addLineListener (this);
        player.start();
    }
}
```



```
// LineListener
public void update (LineEvent le) {
    LineEvent.Type type = le.getType();
    if (type == LineEvent.Type.OPEN) {
        System.out.println ("OPEN");
    } else if (type == LineEvent.Type.CLOSE) {
        System.out.println ("CLOSE");
        System.exit (0);
    } else if (type == LineEvent.Type.START) {
        System.out.println ("START");
        playingDialog.setVisible(true);
    } else if (type == LineEvent.Type.STOP) {
        System.out.println ("STOP");
        playingDialog.setVisible(false);
        player.line.close();
    }
}
}
```

When run, this class shows a dialog box (seen in [Figure 10-7](#)), identical to the one produced in "Play a Sound with JavaSound" [\[Hack #71\]](#). The only difference is that this one can stay up potentially indefinitely, since the player can keep reading and writing bytes forever.

Figure 10-7. Playing a large AIFF file in JavaSound

## Hack 77. Show Audio Information While Playing SoundHack



Providing visual feedback for JavaSound audio, or at least trying to... .

You might want to play a clip without any corresponding visuals; for example, if you were using it to signal a running process such as uploading a file. On the other hand, if the sound is the focus of the application, you might need to show the user some information about the audio he's playing.

### 10.9.1. The Code

You already know how to play audio from a file or stream [Hack #76] ; building on that, you can create a `DataLine` object that shows some of the basic traits of the audio, by pulling fields out of the `AudioFormat` object, which can be created once it has been created. These fields include the audio format, bits/sample, frame size and rate, and endianness (which indicates how two-byte values are to be interpreted: *big-endian* means the first byte is more significant, *little-endian* means the second is).

More impressively, `DataLine` provides a `getLevel ()` method that returns the current level of the audio between 0.0 (silence) to 1.0 (maximum volume). You can use this to create a graphical level meter by getting the level and coloring in that percentage of a component. For example, if the level is 0.5, you'd fill in half of the component.

Drawing this level meter is pretty straightforward: create a `JPanel` whose `paint ()` method clears the graphics, and fills a rectangle starting at (0,0) with a height equal to the component's height and a width equal to the component's width. Then you need to set up an animation loop; `javax.swing.Timer` is convenient because it handles thread-safety issues while doing the painting to repeatedly call `repaint ()` on the meter.

Combine this together and you have the `DataLineInfoGUI`, seen in Example 10-10. Note that to play the audio, you use the `PCMFilePlayer` class from the previous hack, so you can use an arbitrarily long AIFF or WAV, as long as it contains uncompressed PCM data.

### Example 10-10. Displaying audio format information

```
import javax.sound.sampled.*;

public class DataLineInfoGUI extends JPanel {

    PCMFilePlayer player;
    JButton startButton;

    public DataLineInfoGUI (File f) {
        super();
        try {
            player = new PCMFilePlayer (f);
        }
    }
}
```

```

    } catch (Exception ioe) {
        add (new JLabel ("Error: " +
            ioe.getMessage()));
        return;
    }
    DataLine line = player.getLine();
    // layout
    // line 1: name
    setLayout (new BorderLayout (this, BorderLayout.Y_AXIS));
    add (new JLabel ("File: " +
        player.getFile().getName()));

    // line 2: levels
    add (new DataLineLevelMeter (line));
    // line 3: format info as textarea
    AudioFormat format = line.getFormat();
    JTextArea ta = new JTextArea();
    ta.setBorder (new TitledBorder ("Format"));
    ta.append ("Encoding: " +
        format.getEncoding().toString() + "\n");
        ta.append ("Bits/sample: " +
            format.getSampleSizeInBits() + "\n");
    ta.append ("Endianness: " +
        (format.isBigEndian() ? " big " : "little") + "\n");
        ta.append (
            format.getFrameSize() + "\n");
    ta.append ("Frame rate: " +
        format.getFrameRate() + "\n");
        add (ta);

    // now start playing
    player.start();
}
public static void main (String[] args) {
    JFileChooser chooser = new JFileChooser();
    chooser.showOpenDialog(null);
    File file = chooser.getSelectedFile();
    DataLineInfoGUI demo =
        new DataLineInfoGUI (file);

    JFrame f = new JFrame ("JavaSound info");
    f.getContentPane().add (demo);
    f.pack();
    f.setVisible(true);
}
class DataLineLevelMeter extends JPanel {
    DataLine line;
    float level = 0.0f;
    public DataLineLevelMeter (DataLine l) {
        line = l;
        Timer timer =
            new Timer (50,
                new ActionListener () {
                    public void actionPerformed (ActionEvent e) {

```

```

        level = line.getLevel();
        repaint();
    }
    });

        timer.start();
    }
    public void paint (Graphics g) {
        Dimension d = getSize();
        g.setColor (Color.green);
        int meterWidth = (int) (level * (float) d.width);
        g.fillRect (0, 0, meterWidth, d.height);

    }
}
}
}

```

This is a pretty straightforward implementation of the strategy sketched out previously: the class is a `JPanel` to which you can add an arbitrary number of rows. The first is the name of the file, the second is the level meter, and the third is a `JTextArea` to which you can append various fields pulled from the `AudioFormat`.

The level meter's constructor takes care of setting up its own repaint callbacks, so there's no babysitting of the caller. All that's left for the constructor is to start the player to begin feeding bytes to the `Line`.

## 10.9.2. Testing It Out

Launch the `DataLineGUI` application and you'll get a file-selection dialog. Choose a suitable AIFF or WAV, GUI shown in Figure 10-8.

Figure 10-8. Audio player display with format information

This is all well and good for a simple GUI, but there's one problem: *where the heck is our level meter?*! I have the filename and the text area, but it's totally not there!

Initially, I suspected my repaint code was hosed, but it all seemed correct. So, right after figuring out that I had added a sanity-check debug line:

```
System.out.println ("level = " + level);
```

And when I ran it, I got a result that I really didn't want to see:

```
[aeris:HacksBook/Media/x11] cadamson% java DataLineInfoGUI
got PCM format
got info
got line
opened line
level = 0.0
level = 0.0
level = 0.0
level = 0.0
level = 0.0
```

And that was on a really loud song, so it wasn't just a slow fade in. I looked around to see if there was s have to do for `getLevel ()` to work, but there wasn't.

Then I Googled, and found this post to the `javasound-interest` mailing list from February 2003:

Table 10-1.

<b>Date :</b>	Mon, 17 Feb 2003 22:31:21 -0800
<b>Reply-To :</b>	Discussion list for JavaSound API
	<JAVASOUND-INTEREST@JAVA.SUN.COM>
<b>Sender :</b>	Discussion list for JavaSound API
	<JAVASOUND-INTEREST@JAVA.SUN.COM>
<b>From :</b>	Florian Bomers <Florian.Bomers@SUN.COM>
<b>Organization :</b>	Sun Microsystems Inc.
<b>Subject :</b>	Re: DataLine.getLevel( )?
<b>Comments :</b> To:	knute@frazmtn.com
<b>Content-Type :</b>	text/plain; charset=us-ascii

Unfortunately, it is not implemented. (actually, in my private opinion, it is a questionable me usually soundcard drivers do not provide such a primitive, so the Java Sound implementation has "level" on its own. But there are many different algorithms to do so, suited depending for what needed for, and it would possibly eat unnecessarily processor resources. So I guess it's best i the calculation of the "level" on his own on the buffers received by the TDL or written to the


Easy and fast algorithms are maximum, moving average, block average, power) .

sorry...  
Florian

Knute Johnson wrote:

```
>
> Anybody know if DataLine.getLevel() is implemented? All I get is 0.0
> on SourceDataLines and -1.0 on TargetDataLines.
>
> Thanks,
>
> Knute Johnson
```

In fact, a little further research shows that the fact that `DataLine.getLevel()` always returns `UNKNOWN_LEVEL` 4297101 in the Java Bug Parade on December 6, 1999. Five years later, it's still not fixed, though it looks like at least an attempt to fix it for Tiger (J2SE 5.0) a fix that was abandoned in August 2003.



By the way, wouldn't it have saved a lot of people a lot of time if they disclosed in the past that this method is a noop? But I digress

So, the level meter is not going to work not because of the graphics, but because there's no way to get a level meter there?

### 10.9.3. Hacking the Hack

Florian's message to `javasound-interest` says it is best if "everybody does the calculation of the 'level' on the buffers received by the TDL [`TargetDataLine`, usually used by capture devices] or written to the [`SourceDataLine`], respectively."

Setting aside the argument of duplication of effort, note that the buffers he speaks of are available in the `PCMFilePlayer` reads from the file and writes to the `Line` (specifically, a `SourceDataLine`, as Florian's in theory at least, this can be done. But it's not going to be pretty.

First, create a new `DataLineInfoGUI2` class that is identical to the one from earlier in this hack, except that `PCMFilePlayer`, it uses a `PCMFilePlayerLeveler`, a class that will be defined next.

This new class is pretty much the same as the old `PCMFilePlayer`, except that on each time through the `run` method reads the buffer and writes it to the line, it will call a method to scan through the buffer and determine the level of samples. So, after reading the bytes from the input stream but before writing them to the line, add:

```
// calculate level
calculateLevel (buffer, readPoint, leftover);
```

As Florian argues in his message, the idea of a level is up for interpretation, but there is a general sense represent the loudness or quietness of the audio at a certain time. Making the problem worse is the fact values will always be going up and down because the samples represent how much a speaker should be and it's the sample's periodic change that creates sound waves we hear. Put another way, even the loudest some 0 samples at the bottom of their waves.

As a crude attempt at approximating a level, this hack's implementation gets the maximum amplitude (if the source is stereo) in the entire buffer. To make this a little more fine-tuned, this version of the player size suitable to provide 1/20 of a second of audio, rather than the flat 32 KB used earlier. To do that, add the `Line` in the constructor:

```
// figure out a small buffer size
int bytesPerSec = format.getSampleSizeInBits() *
    (int) format.getSampleRate();
    System.out.println ("bytesPerSec = " + bytesPerSec);
int bufferSize = bytesPerSec / 20;
buffer = new byte[bufferSize];
```

This needs to sync with the line as well if the line's buffer is nearly full, it won't accept this entire buffer causing blocking. So, you can tune the while loop to do a read-and-write only if the `Line` will accept a bufferful of adding the following block after the `if` (playing) statement:

```
// only write if the line will take at
// least a buffer-ful of data
if (line.available() < buffer.length) {
    Thread.yield();
    continue;
}
```

Now, the only problem is implementing `calculateLevel ()` i.e., doing the actual iteration through the buffer to find the maximum value. This, frankly, is a huge pain in the butt, because to determine each sample value, you have to address issues you hadn't cared about before:

- Channels (i.e., mono versus stereo)
- Sample size
- Endianness
- Signing

This is handled in the `calculateLevel ()` method of `PCMFilePlayerLeveler`, listed in Example 10-11.

## Example 10-11. Method to calculate a crude "level" of sample bytes in a buf

```

private void calculateLevel (byte[] buffer,
    int readPoint,
    int leftOver) {
    int max = 0;
    boolean use16Bit = (format.getSampleSizeInBits() == 16);
    boolean signed = (format.getEncoding() ==
        AudioFormat.Encoding.PCM_SIGNED);
    boolean bigEndian = (format.isBigEndian());
    if (use16Bit) {
        for (int i=readPoint; i<buffer.length-leftOver; i+=2) {
            int value = 0;
            // deal with endianness
            int hiByte = (bigEndian ? buffer[i] : buffer[i+1]);
            int loByte = (bigEndian ? buffer[i+1] : buffer [i]);
            if (signed) {
                short shortVal = (short) hiByte;
                shortVal = (short) ((shortVal << 8) | (byte) loByte);
                value = shortVal;
            } else {
                value = (hiByte << 8) | loByte;
            }
            max = Math.max (max, value);
        } // for
    } else {
        // 8 bit - no endianness issues, just sign
        for (int i=readPoint; i<buffer.length-leftOver; i++) {
            int value = 0;
            if (signed) {
                value = buffer [i];
            } else {
                short shortVal = 0;
                shortVal = (short) (shortVal | buffer [i]);
                value = shortVal;
            }
            max = Math.max (max, value);
        } // for
    } // 8 bit
    // express max as float of 0.0 to 1.0 of max value
    // of 8 or 16 bits (signed or unsigned)
    if (signed) {
        if (use16Bit) { level = (float) max / MAX_16_BITS_SIGNED; }
        else { level = (float) max / MAX_8_BITS_SIGNED; }
    } else {
        if (use16Bit) { level = (float) max / MAX_16_BITS_UNSIGNED; }
        else { level = (float) max / MAX_8_BITS_UNSIGNED; }
    }
} // calculateLevel

```



This crude implementation just reads all the samples in order, meaning the stereo casesamples alternate rightis ignored. Thus, the maximum value wins, regardless of what channel it's on.

Figuring out the value is still a bit-munging pain because of the three outstanding issues that must be d audio, the samples should be read two at a time. You arrange the "high" (most significant) and "low" (le based on the endianness of the format, and then cast to a Java `int` or `short` based on whether you need bit (in a 32-bit `int`, the 16 bits won't be signed; in Java's 16-bit `short`, the sign will be maintained). Eig you the endianness hassle, though you still have to be aware of signage, and cast to `abyte` or `short` base need to preserve a sign.

All of this, just to figure out the value of a sample. As you might expect, the only thing left to do on each the sample's value to the maximum for this buffer, and to reset the maximum if this value is higher. At the maximum value against the maximum possible value for that combination of bits and signage to get between 0.0 and 1.0.

### 10.9.4. Running the Hacked Hack

When you run this hack, you finally get a player with a level meter, as seen in Figure 10-9.

Figure 10-9. Audio player display with format information and level

While this looks OK in a book, it really isn't very satisfactory when you're watching the audio as it plays. relate to the music that closely; that is, it seems to follow softer music OK, but it really falls apart on ro

Part of the reason is that this "maximum" algorithm is quite crude; an approach such as averaging the s might be more realistic.

But the real problem is that the access JavaSound gives you is doomed to be hopelessly behind what's k about the `available ()` method, which reports how much you can write to the `SourceDataLine`'s buffer w What's happening is that you're refilling one end of its buffer, while it drains out the other end to the sp accurately, to the native sound system (which may have its own buffers, and thus more latency). This a illustrated in Figure 10-10.

Figure 10-10. Flow of samples through buffers in JavaSound



So, you can calculate the level for the samples in the buffer, but it will be some time until those samples have a mismatch of what's being measured and what's actually being played. What you need is access to the buffer, so you could run the level check on the bytes that are just about to be played. Until and unless the suggested workaround isn't really going to work.

Of course, Sun could just go and actually implement `getLevel()`...wouldn't that be nice?

← PREV

## Hack 78. Provide Audio Controls During Playback



Let your users take control of JavaSound playback.

To complete this set of JavaSound-related hacks, why not give the user the opportunity to control the sound as it plays? JavaSound provides a very dynamic means of getting at *controls* like *gain* and *pan* (more commonly thought of as volume and balance) through a discovery mechanism that you can use to support any kind of control that might exist, even a control you know nothing about.

On the other hand, JavaSound presents a control not as a GUI widget, but just as an object that can affect the behavior of a `Line`. This hack will help you provide the GUI side.

The `Control` class simply defines a `getType()` and `toString()` method. What's more interesting is its subclasses, each of which defines a different kind of control:

### `BooleanControl`

Controls a value that can be either true or false

### `EnumControl`

Controls a value that can be one of *n* known values

### `FloatControl`

Controls a value that is expressed as a floating-point number

### `CompoundControl`

Controls multiple properties, and itself contains multiple controls

You can get the `Controls` supported by your `Line` simply by calling `Line.getControls()`, which returns an array of `Controls`. You can also ask for a specific control by using a constant of the `Control.Type` subclass, such as `BooleanControl.Type.MUTE` or `FloatControl.Type.MASTER_GAIN`. Pass this constant to `Line.isControlSupported()` to see if the control is available for the given line, and then get the control object with `Line.getControl()`.

If you look at the subclasses of `Control`, you'll see that each provides getter and setter methods appropriate to its data type. `BooleanControl`, for example, has a `getValue()` that returns a `boolean`

and a `setValue()` that takes a `boolean`. `FloatControl` has similar methods that work with `floats`. Each also provides a number of what might be called "verbiage methods" that provide text for building a GUI. For example, `FloatControl` offers label names for its minimum, maximum, and middle values, and another that describes the units represented by the control (like "dB" for a gain-related control, or "frames per second" for one that is timing-related).

Anyways, you've probably figured out that you can build a GUI by using Swing to provide a view to these `Controls`. In fact, it's fairly straightforward to take a factory approach to handing out `JComponents` based on `Controls`, as shown in [Table 10-1](#).

Table 10-2. Controls and their Swing representation

Control type	Swing representation
<code>BooleanControl</code>	<code>JCheckBox</code>
<code>EnumControl</code>	<code>JComboBox</code>
<code>FloatControl</code>	<code>JSlider</code>

The `CompoundControl` can't be handled as easily because you can't know how far you'll have to recursively dig into its hierarchy of controls, nor how to represent them in relation to one another. For what it's worth, JavaSound does not define any `CompoundControl.Type` constants, and it's not clear that any `CompoundControls` exist in J2SE; the Javadoc only speaks in theory of supporting something like a graphic equalizer, which would need to be a `CompoundControl`.

### 10.10.1. Theory to Practice

To handle the different types of controls that can be encountered, one nice approach would be to build a factory: you hand it a `Control`, and it gives you back a `JComponent` that you can add to your GUI. [Example 10-12](#) shows a simple implementation of this.

#### Example 10-12. Factory to generate Swing widgets for JavaSound controls

```
import javax.sound.sampled.*;

public class ControlComponentFactory {

    private ControlComponentFactory() {super();}

    public static JComponent getComponentFor (Control control) {
        System.out.println (control.getType().getClass());
        if (control instanceof BooleanControl)
            return new BooleanControlComponent ((BooleanControl) control);
    }
}
```

```

else if (control instanceof FloatControl)
    return new FloatControlComponent ((FloatControl) control);
return new JLabel ("unsupported");
}
}

```

You might notice that I haven't written a GUI class for `EnumControl`. That's because in my testing, the array of Controls returned by `getControl()` has never contained an `EnumControl`, so I don't have a good way to test it. After looking at the implementation of the `boolean` and `float` cases, I'll discuss how an `EnumControlComponent` would work.

The easier case is the `BooleanControl`, used for controls like Mute, which turns off the sound (but remembers the previous volume, so when unmuted, the sound is as loud as it was before) [Example 10-13](#) shows the implementation of the `BooleanControlComponent`.

### Example 10-13. Swing widget for a JavaSound BooleanControl

```

import javax.sound.sampled.*;

public class BooleanControlComponent extends JPanel
    implements ActionListener {
    BooleanControl control;
    JCheckBox box;
    public BooleanControlComponent (BooleanControl c) {
        control = c;
        box = new JCheckBox ();
        box.setSelected (control.getValue());
        add (box);
        box.addActionListener (this);
    }
    public void actionPerformed (ActionEvent ae) {
        control.setValue (box.isSelected());
    }
}

```

As you can see, this is practically trivial. The GUI contains a single `JCheckBox`, whose value you set to the value of the control so that it is in a proper state when first shown. Then, when the user clicks it, you just call the `BooleanControl`'s `setValue()` method.

Supporting a `FloatControl` is a lot harder. As you might expect, the way to represent a range of floating-point values is with a `JSlider`; the user can slide left to reduce the value and right to increase it. To ensure the GUI's usefulness, you can put `JLabels` on the left and right of the slider to show what the minimum and maximum values mean. For example, on a Pan control, which adjusts placement of stereo sound, the minimum value of -1.0 is Left and the maximum value of 1.0 is Right

What makes it hard is handling a mapping of arbitrary floating-point values to a `JSlider`'s int-based

range. Complicating things is the fact that `FloatControls` can and do use very different ranges for their values, often spanning negative and positive values, and operating in both small and vast ranges of possible values. For example, if you decide to have your `JSlider` values range from 0 to 1000, it may have to accommodate ranges as disparate as:

- -1.0 to 1.0
- 0.0 to 48000.0
- -80.0 to 13.9794

In fact, those are the ranges of default controls for pan, sampling rate, and master gain, respectively.

And to make things more fun, you have to be able to translate both ways: from control value to slider value (when first creating the widget so its initial onscreen representation is accurate), and from slider value to control value (when the user moves the slider).

But, in the end, it's just math. You can create a `setSliderFromControl()` method to calculate what percent of the control's maximum value is represented by the current value, apply that percent to the range of the `JSlider`'s possible values, and set the `JSlider` to that. A `setControlFromSlider()` would use the exact same approach, except that it figures out the percentage-of-maximum of the `JSlider`, and applies that to the control's range. The resulting `FloatControlComponent` class is shown in [Example 10-14](#).

## Example 10-14. Swing widget for a JavaSound FloatControl

```
import javax.sound.sampled.*;

public class FloatControlComponent extends JPanel
    implements ChangeListener {

    FloatControl control;
    JSlider slider;
    float min, max, range;
    final static int SLIDER_MIN = 0;
    final static int SLIDER_MAX = 1000;
    final static float SLIDER_RANGE = SLIDER_MAX - SLIDER_MIN;

    public FloatControlComponent (FloatControl c) {
        control = c;
        min = c.getMinimum();
        max = c.getMaximum();
        range = max - min;
        add (new JLabel (control.getMinLabel()));
        slider = new JSlider (SLIDER_MIN, SLIDER_MAX);
        slider.addChangeListener (this);
        setSliderFromControl();
        add (slider);
        add (new JLabel (control.getMaxLabel()));
    }
}
```

```

}
private void setSliderFromControl() {
    // figure out value as percent of range
    float offsetValue = control.getValue() - min;
    float percent = 0.0f;
    if (range != 0.0)
        percent = offsetValue / range;
        // apply that to SLIDER_RANGE
    int sliderValue = (int) (percent * SLIDER_RANGE);
    slider.setValue (sliderValue);
}
private void setControlFromSlider() {
    // figure out slider percentage
    float sliderPercentage =
        (float) slider.getValue() / SLIDER_RANGE;
    // figure out value for that percentage of range
    float rangeOffset = sliderPercentage * range;
    float newValue = rangeOffset + min;
    control.setValue (newValue);
}
// ChangeListener implementation
public void stateChanged (ChangeEvent e) {
    setControlFromSlider();
}
}

```

Having provided these two implementations, it should be clear how you would create an `EnumControlComponent`. The `EnumControl.getValues()` method returns a `String` array that you would use as the model of an uneditable `JComboBox`. You'd use `getValue()` to set one of these as the initial value, and then on user events, you could pull out the `JComboBox`'s selection and set the `EnumControl` with `setValue()`.

## 10.10.2. Check It Out!

The `DataLineControlGUI` shown in [Example 10-15](#) is a simple `JPanel` that contains a `JLabel` with the name of the file to be played on the first line of a `GridBagLayout`, and then control-name `JLabels` and factory-generated control widgets on each successive line. The sound is played by the `PCMFilePlayer`, which was introduced as part of playing uncompressed AIFFs and WAVs of arbitrary lengths [[Hack #76](#)].

### Example 10-15. Creating an audio player with GUI controls

```

import javax.sound.sampled.*;

public class DataLineControlGUI extends JPanel {

```

```
PCMFilePlayer player;
JButton startButton;

public DataLineControlGUI (File f) {
    super();
    try {
        player = new PCMFilePlayer (f);
    } catch (Exception ioe) {
        add (new JLabel ("Error: " +
            ioe.getMessage()));
        return;
    }
    DataLine line = player.getLine();
    // layout
    // line 0: name
    setLayout (new GridBagLayout());
    GridBagConstraints gbc = new GridBagConstraints();
    gbc.gridy = 0; gbc.fill = GridBagConstraints.HORIZONTAL;
    gbc.gridwidth = 2; gbc.anchor = GridBagConstraints.SOUTH;
    add (new JLabel ("File: " +
        player.getFile().getName()), gbc);
    // subsequent lines: controls
    gbc.gridwidth = 1;
    Control[] controls = line.getControls();
    for (int i=0; i<controls.length; i++) {
        gbc.gridx = 0;
        gbc.gridy++;
        gbc.anchor = GridBagConstraints.EAST;
        add (new JLabel(controls[i].getType().toString()), gbc);
        JComponent controlComp =
            ControlComponentFactory.getComponentFor (controls[i]);
        gbc.gridx = 1;
        gbc.anchor = GridBagConstraints.WEST;
        add (controlComp, gbc);
    }
    // now start playing
    player.start();
}


public static void main (String[] args) {
    JFileChooser chooser = new JFileChooser();
    chooser.showOpenDialog(null);
    File file = chooser.getSelectedFile();
    DataLineControlGUI demo =
        new DataLineControlGUI (file);

    JFrame f = new JFrame ("JavaSound control");
    f.getContentPane().add (demo);
    f.pack();
    f.setVisible(true);
}
}
```



When run with a suitable audio file, the resulting GUI looks like [Figure 10-11](#). Note that it's possible you might have other control widgets (or an unsupported label for `EnumControls` and `CompoundControls`) if JavaSound gives you different controls than it did when I wrote and ran this on Java 1.4.2.

Figure 10-11. JavaSound audio player with GUI controls



# Chapter 11. Native Integration and Packaging

[Section 11.1. Hacks 7987: Introduction](#)

[Hack 79. Launch External Programs on Windows](#)

[Hack 80. Open Files, Directories, and URLs on Mac OS X](#)

[Hack 81. Make Mac Applications Behave Normally](#)

[Hack 82. Control iTunes on Mac OS X](#)

[Hack 83. Control iTunes Under Windows](#)

[Hack 84. Construct Single-Launch Applications](#)

[Hack 85. Stuff Stuff in JARs](#)

[Hack 86. Make Quick Look and Feel Changes](#)

[Hack 87. Create an Inverse Black-and-White Theme](#)

## 11.1. Hacks 7987: Introduction

You can try really hard to develop a desktop application that looks good, feels right, and meets the user's needs, but if a Windows or Mac user has to drop down to a command line and type `java -jar MyCoolApp.jar` to run it, it's not going to win you any points in the user experience department. There are points of integration with the native platform that you'll often want and need to access from a Swing application, or specific functionality you'll want to provide on a platform-by-platform basis, and that's what this chapter is about.



Actually, this chapter was almost rendered irrelevant by the JDesktop Integration Components (JDIC) project on Java.net (<https://jdic.dev.java.net/>), which is addressing the most serious needs for desktop Java applications: creating platformappropriate double-clickables, providing access to the native web browser component, associating Java applications with certain kinds of documents, etc. JDIC may solve some of the biggest issues facing Java on the desktop...which leaves us all the more room for creative hackery.

## Hack 79. Launch External Programs on Windows



With one simple command you can tell Windows to open files, directories, and URLs on your behalf.

Swing programmers have always had difficulty dealing with native operating systems because of Java's cross-platform nature. Even simple things like opening a web browser require building native hooks with JNI or building on top of custom libraries. This hack will show you how to open files, URLs and start an email app without using any native libraries or custom C coding.

### 11.2.1. The Power of `Runtime.exec()`

Native integration in Java has always depended on the Java Native Interface, or JNI. Whether you code to JNI directly or use a third-party library, you are still dealing with native C code through a Java layer. This has always been problematic because in order to write a JNI library, you need to know a lot about the internals of the underlying operating system. Most Java developers went to Java to *get away* from that sort of thing, so it's often not worth it for something simple like opening a URL. There is another way of talking to the native OS, though. You can use `Runtime.exec()`.

Since 1.0, Java has had the `Runtime.exec()` static function to start another program directly and pass command-line parameters. It's easy to forget about command-line utilities, but for simple things they can be far, far easier than trying to deal with JNI. The disadvantages of calling a native program over a Java API are of course speed, since you are starting a new process, and the fact that the program is not cross-platform. This may be an acceptable tradeoff, however, since you could disable the feature that needs the `exec()` call or provide a different command for other platforms.

### 11.2.2. Open a Text File

Windows 2000 introduced a small program called `start`. Originally a separate install, the `start` program is now just a command built into the `cmd.exe` that comes with Windows XP. It is a simple command but it can do some powerful things, such as opening a file with the default viewer, showing a directory in the file explorer, or even launching a web browser.

For example, the sample program in [Example 11-1](#) will open a text file with the default viewer (usually Windows Notepad).

Example 11-1. Launching a text file with `start`

```
import java.io.IOException;
public class ExecTest {
    public static void main(String[] args) throws IOException {
        String cmd = "cmd.exe /c start ";
        String file = "c:\\version.txt";
        Runtime.getRuntime().exec(cmd + file);
    }
}
```

That's it! `cmd.exe` is the command processor built into Windows (a holdover from the DOS days). Whenever you open a DOS box, you are running `cmd.exe`. You can manually replicate the previous code by typing `start c:/ version.txt` into a command-line window.

### 11.2.3. Open a URL

You can open a web browser the same way as a text file because Windows associates all URLs, specifically ones that begin with `http`, with a default web browser. If you call `start` on a URL then the browser will open, as seen in [Example 11-2](#).

#### Example 11-2. Opening a URL in the default web browser on Windows

```
import java.io.IOException;
public class ExecTest {
    public static void main(String[] args) throws IOException {
        String cmd = "cmd.exe /c start ";
        String file = "http://www.google.com";
        Runtime.getRuntime().exec(cmd + file);
    }
}
```

You can also use the browser support to open up a new email message. Since `mailto:` is a URL protocol, usually mapped to the user's default email program, if you open up `mailto:` URL, Windows will open a new message ready to send (see [Example 11-3](#)).

#### Example 11-3. Using start to open an email application

```
import java.io.IOException;
public class ExecTest {
    public static void main(String[] args) throws IOException {
```

```

String cmd = "cmd.exe /c start ";
String file = "mailto:author@mybook.com";
Runtime.getRuntime().exec(cmd + file);
}
}

```

The previous code will open up a new email message addressed to *author@mybook.com*. The return address will be filled in automatically with the user's own address. You can remove the address (*author@mybook.com*) to open a new blank email.

By default, `cmd.exe` will open a requested file using the standard viewer for that file's type. For example, `cmd.exe /c start music.mp3` will open the song file using the default program, possibly the Windows Media Player or iTunes. If you would rather open the file with a particular program that you specify, then you can simply add the program name before the file.

As another example, `cmd.exe /c start version.txt` opens a text file in Windows Notepad (assuming that's the default text file viewer). `cmd.exe /c start winword.exe version.txt` would open the file in MS Word. This requires having Word installed, of course, so I would only recommend hardcoding the program name if you are sure it's really there.

## 11.2.4. Open a Directory

The `start` command can also open a directory as well as a file, meaning it will open a file manager window showing the contents of that directory. Program installers often do this after the install is complete to show where the program was placed. The code in [Example 11-4](#) will open a new Explorer window showing the contents of the `C:` drive.

### Example 11-4. Opening a directory on Windows

```

import java.io.IOException;
public class ExecTest {
    public static void main(String[] args) throws IOException {
        String cmd = "cmd.exe /c start ";
        String file = "c:\\\\";
        Runtime.getRuntime().exec(cmd + file);
    }
}

```

## Hack 80. Open Files, Directories, and URLs on Mac OS X



Open files, directories, and URLs in external programs right from your Swing app.

We can't let Windows have all of the fun. Mac OS X has a similar and even easier to use program called `open`, which lets you `open` any file, directory, or web page directly from the command line. This hack shows you how to embed `open` in your own program.

### 11.3.1. Using Open

Back in the late 80s, NeXT, Inc. created the first true integration between a graphical user interface and a Unix-like operating system when they released NeXTSTEP. Part of this OS was a command-line program called `open`, which could open a file, directory, and (once the Web was invented) a URL. Apple purchased NeXT in the late 90s and NeXTSTEP became the core of Mac OS X. Along with this purchase came the `open` command, still as useful as ever. `open` has a simple syntax: `open filename`. By calling it from within your program, you can `open` any file with its default application. `open` will start launching the viewer automatically and return control to your program immediately. As in Microsoft Windows, you can call the program using `Runtime.exec()`:

```
public static void main(String[] args) throws Exception {
    Runtime rt = Runtime.getRuntime();
    rt.exec("open notes.txt");
}
```

This program will open a file in the current directory (*notes.txt*), in the default viewer for text files, usually `TextEdit`. You can also specify an absolute path for the file:

```
rt.exec("open /Users/josh/Desktop/notes.txt");
```

If you pass a directory instead of a file, then OS X will open that directory in a new Finder window. This can be useful for showing the location of a recently downloaded file or demonstrating where to install new software:

```
// open the current working directory
rt.exec("open .");
```

```
// open the applications directory
rt.exec("open /Applications");
```

Finally, you can open any web page using the user's default web browser (probably Safari) by calling `open` with a URL:

```
// open Yahoo! in the user's web browser
rt.exec("open http://www.yahoo.com/");
```

## 11.3.2. Handle Spaces

Some filepaths may contain spaces. When you run `open` from the command line you can escape these spaces using quotes like this:

```
open 'Current Notes.txt'
```

Unfortunately, quotes won't work when you call `open` from a program because the quotes are actually interpreted by the user's command-line shell, not `open` itself. When you call `open` directly from a program, you are bypassing the shell and lose quote interpolation. The solution is to break the command line into an array of arguments manually. That way `open` knows what is a space and what is the gap between arguments:

```
Runtime rt = Runtime.getRuntime();
String[] cmd = {"open", "Current Notes.txt"};
rt.exec(cmd);
```

Now, you might wonder why `open` needs to distinguish between argument gaps and real spaces when it takes only one argument to begin with. `open` actually does have some other arguments. For example, `-t` will force the file to be opened in TextEdit, and `-f` will make `open` read from standard input rather than a file.

The most useful extra argument is probably `-a`, which lets you force the file to be opened in a particular program rather than just using the default. For example, if you wanted to open a text file in Microsoft Word instead of the default text editor, you could do something like this:

```
public static void main(String[] args) throws Exception {
    Runtime rt = Runtime.getRuntime();
    String[] cmd = {
```



```
"open",  
"-a",  
"Microsoft Word",  
"mynotes.txt"  
};  
rt.exec(cmd);  
}
```



Notice you have to use an array instead of a single string because Microsoft Word has a space in it. If you don't do that, the program will fail with a bus error.

`open` is a simple but very powerful program because it gives you easy access to launching programs and files without knowing the user's settings. The default applications will be used for each file type, including URLs. You don't have to hardcode this information into your program, thus creating a better experience for your user.

To learn more about the `open` command, you can type `man open` into a terminal window.

## Hack 81. Make Mac Applications Behave Normally



Setting a few system properties will make your application seem more like other Mac apps.

Of the desktop platforms your application is likely to run on, the Mac is the least like the others. Maybe it's because the various Linux desktops hemmed closely to Windows' ways of thinking, or maybe the GNOME guys had never used a Mac and didn't "think different." But the result is that certain assumptions you might reasonably make on Windows or Linuxlike assuming that windows have menu bars and that any corner or edge of a window can be dragged to resize the window aren't correct on the Mac.

To smooth over the cross-platform differences somewhat, Apple does certain things differently in its Java implementation. For one thing, it will automatically put a Swing application into its native Look and Feel, Aqua, rather than defaulting into cross-platform Metal or Ocean as would happen on other platforms. In other words, you don't have to do anything special to pick up the Mac Look and Feel, although redundantly asking for and setting the native Look and Feel classname doesn't hurt either.

Moreover, Apple provides some key/value pairs that you can set in the Java system properties to get even more Mac-like behavior. Because these properties all start with `apple` or `com.apple`, you can set them and not worry that they'll affect the behavior of your application on any other platform.

### 11.4.1. Using the Apple System Properties


Apple has been changing the names and behaviors of these system properties for a while, and some of them are deprecated or no-op'ed, so I'll just show four of the most useful ones here. To see the whole list, check out the Runtime System Properties of Apple's Java 1.4.1 release notes on <http://developer.apple.com/releasenotes/Java/index.html>.

You can set the properties several ways. The obvious way is to use the `-D` command-line argument:

```
java -Dapple.awt.showGrowBox=true MyClass
```

However, this becomes tedious to type after you decide to use multiple properties. Another option is to simply call `System.setProperty()` in your code, though you'll need to do so as soon as possible so the desired property gets picked up by the JVM before it's needed. A third option exists as well: if you're bundling the Java application as a double-clickable Mac application, your tool of choice will give you an opportunity to set these values. For example, the JarBundler that Apple provides with its

developer tools has a properties pane in which you can enter name/value pairs; these are saved with the application bundle and provided to the JVM as if they'd been set on the command line.



The downloadable book code contains demo applications for all the tricks shown in this chapter, but since the point in this hack is the one-line `System.setProperty()` call and not 20 lines of code that demonstrate the effect, the demo code is not shown here, just screenshots of the results.



## 11.4.2. Using the Mac's Menu Bar

One of the most striking differences between the Mac and Windows/Linux GUIs is that the Mac has a single menu bar at the top of the screen, rather than menu bars in each application window. This will break a lot of assumptions if you're coming over from the Windows world (for one thing, an application can still be running without any windows open, since the user can usually spawn a new window from the File menu), but for now, just focus on the fact that menus inside of windows are going to feel very alien to a Mac user. [Figure 11-1](#) shows what a typical Swing window looks like on a Mac with the menu bar in the window.

Figure 11-1. Swing application with menu bar in a Mac window

Change that by setting the system property `apple.laf.useScreenMenuBar` to `true`. This takes all Swing menu bars out of their `JFrames` and puts them up in the Mac menu bar. [Figure 11-2](#) shows the effect of setting this property on a Swing window.

Figure 11-2. Swing application with menus in a Mac menu bar



AWT windows will always use the Mac menu bar.

One thing worth mentioning is that if your application uses different menus in its various windows, this will still seem strange to Mac users, as the menu bar will change based on which of your application's windows has focus. But to be truly Mac-like, you'd have to have the same menu bar all the time, which on Windows/Linux might mean having completely inappropriate menus in some windows. Then again, with good design and probably some `ResourceBundles` you should be able to provide an appropriate menu bar experience to all your users.

### 11.4.3. Presenting an Appropriate Application Name

On Mac OS X, the first two items (reading left to right) on the menu bar are the Apple menu, which controls the whole system (Software Update, Restart, Log Out, etc.), and the Application menu. The Application menu is meant to contain items relevant to the entire application: an about box, preferences, the ability to hide itself or other applications, and Quit. But the menu isn't named Application; instead, it shows the current application's name. That's great for something short and memorable like Mail or Firefox. But for a Java application, it picks up the name of the application's `main()` class. And when you package your code (like you're supposed to, with the inverted Internet address style), you get a monstrosity like [Figure 11-3](#).

Figure 11-3. A long Java classname as a Mac application name

Fortunately, you can rein in the insanity with the `com.apple.mrj.application.apple.menu.about.name` property. Just set this to the name you want to show in the application menu

For example, setting it to MyDemo produces the much more reasonable application menu seen in [Figure 11-4](#).

Figure 11-4. A custom application name for a Java application

#### 11.4.4. Showing the Mac Grow Box

Traditionally, Mac applications have reserved the bottom-right corner as the only space that you can drag to resize a window. It is shown as a diagonally dimpled grow box, often reserving the space above it for a scrollbar. There's also sometimes either a scrollbar or a status bar to the box's left. At any rate, this approach to resizing is very different from having a few pixels for a border on the right, left, and bottom edges all of which are draggable as users expect from Microsoft Windows.

By default, the grow box is not shown in Mac Java windows. You can make the grow box appear by setting the property `apple.awt.showGrowBox` to `TRUE`. This does, however, have a significant downside as seen in [Figure 11-5](#).

Figure 11-5. Mac grow box intruding on Swing display space

The grow box intrudes into the Java display space. In this case, it clobbers the right-most part of a `JTextField`.

The proper way to handle this is to reserve some space for the grow box. The simple thing to do in fact, it's what Apple's Java 1.3.1 did by default is to reserve 15 pixels of vertical space for the grow box. You could probably just have a subclass of `JFrame` for your Mac users that puts the usual frame contents in the `CENTER` of a `BorderLayout`, and creates a spacer with `Box.createVerticalStrut(15)` to reserve space for the grow box in the `SOUTH`. [Figure 11-6](#) shows the corrected window after this approach is applied.

Figure 11-6. Mac grow box with space reserved for it at the bottom of JFrame

## 11.4.5. Jump on the Brushed Metal Bandwagon

Apparently, Mac applications are no longer cool unless they use the brushed metal L&F of Apple's various iApps, such as iTunes, iChat, etc. Fortunately, it's easy to pick up that appearance for your Java application. Just set the property `apple.awt.brushMetalLook` to `true`. This produces windows like the one seen in [Figure 11-7](#).

Figure 11-7. Swing window with brushed metal appearance

Apple's documentation of this feature says that this should be applied to your primary application window only, not supporting dialogs or preference windows, but it's hard to see how that rule can be enforced when this property causes all your windows to pick up the brushed metal look automatically.

## Hack 82. Control iTunes on Mac OS X



With a few bits of AppleScript, you can monitor and control Macintosh iTunes from your own application.

You can make some really great applications using plain Java, but the software world isn't what it used to be. The buzzword for new applications is integration. Modern programs are defined not only by what they do, but what they can talk to. The poster child for integration these days is iTunes, so what better way to show off the power of Java than by taking control of iTunes directly from your own Java app!

The task of dealing with native applications is, by nature, platform specific. For example, though Apple ships identical *looking* copies of iTunes for both Windows and Mac, the integration APIs couldn't be more different.

### 11.5.1. Apple Events

Most well-written Mac OS X applications support an API called Apple Events. Apple Events let a programmer send commands and requests to a running application from another program, through a process often called scripting. The application must be written to support Apple Events and every scriptable feature must be defined explicitly when the program is written. Since it was Apple that wrote iTunes, they did a very good job of exposing virtually every feature through Apple Events. All you need to do is tap into these events.

Apple Events is an API, and you need a programming language to support it. There are a variety of languages to choose from, but the easiest one to start with is AppleScript, as the syntax is simple and OS X ships with a command-line interpreter. There are also direct Java bindings available, but for the kinds of simple things you are likely to want to do with iTunes, `exec()`ing the interpreter will be much easier. All you have to do is call `osascript` with the AppleScript commands you want to run, and OS X will do the rest.

AppleScript is a simple language with a somewhat natural language feel to it. If you want to tell iTunes to toggle the Play/Pause button, you can call this script from the command line:

```
osascript -e 'tell app "iTunes" to playpause'
```

Now *that's* the kind of simple integration I like! Because you can directly execute command-line programs from inside your code, the Java equivalent would look like this:

```
String[] args = { "osascript", "-e",
"tell app \"iTunes\" to playpause" };
Process proc = rt.exec(args);
```

That's it. You can make iTunes do virtually anything you want with simple commands like this. One caveat to remember is that iTunes must be running as the same user for this to work. This usually isn't a program for desktop applications, but if you made a web application with this technique, you might need a workaround like a `chown` script or a daemon that runs next to iTunes. [Example 11-5](#) is the code for a simple program with one button that will toggle the iTunes Play/Pause button.

### Example 11-5. Controlling iTunes on the Mac

```
public class MacITunes implements ActionListener {
    public static void main(String[] args) {
        JFrame frame = new JFrame("Mac iTunes Hack");
        JButton button = new JButton("Play/Pause");
        button.addActionListener(new MacITunes());
        frame.getContentPane().add(button);
        frame.pack();
        frame.setVisible(true);
    }
    public void actionPerformed(ActionEvent evt) {
        try {
            Runtime rt = Runtime.getRuntime();
            String[] args = { "osascript",
                "-e","tell app \"iTunes\" to playpause"};
            Process proc = rt.exec(args);
        } catch (IOException ex) {
            System.out.println("exception : " + ex.getMessage());
            ex.printStackTrace();
        }
    }
}
```

This code creates a `JFrame` with one button. The button's action listener creates a new `java.lang.Runtime` object, sets up the command-line arguments, and finally calls `osascript` to control iTunes. When you click on the button in the Swing application, iTunes will start playing. If you press the button a second time, iTunes will pause. Virtually any feature in iTunes can be scripted this way.

Sometimes you don't want to tell iTunes to do something, but instead want to get information *from* it. `osascript` can handle this, too. When you call a function that returns a value, `osascript` will write the value to standard out, which you can pick up from the process's input stream. For example, if you wanted to get the name of the currently playing track, you could change the action listener code



to look like this:

```
public void actionPerformed(ActionEvent evt) {
    try {
        Runtime rt = Runtime.getRuntime();
        String[] args = { "osascript", "-e",

            "tell app \"iTunes\" to artist of current track as string"};
        Process proc = rt.exec(args);
        InputStream in = proc.getInputStream();
        String str = new DataInputStream(in).readLine();
        System.out.println("got: " + str);

    } catch (IOException ex) {

        System.out.println("exception : " + ex.getMessage());
        ex.printStackTrace();
    }
}
```

The line:

```
tell app "iTunes" to artist of current track as string
```

will call the artist method on the current track. It will return the artist as a string and print it to standard out. You can get the standard output by reading from `proc.getInputStream()`. The code then prints the string as a single line, so you can easily read it with the `readLine()` method on a `DataInputStream`. Once you have the string back, you can print it, put it in a `JLabel`, or do whatever else is appropriate for your program.

Apple has more information available on the iTunesAppleScript API at <http://www.apple.com/applescript/itunes/>. With this API, you can do almost anything. For example, you can get the name of a playing song:

```
tell app "iTunes" to name of current track as string
```

You can also get the album name:

```
tell app "iTunes" to album of current track as string
```

Muting the volume is also a piece of cake:

```
tell application "iTunes" to set mute to true
```

In the same vein, you can obtain the current volume:

```
tell application "iTunes" to sound volume as integer
```

Take a look at the API and see what other interesting things you can do. Many of the other programs that come with Mac OS X can be controlled with Apple Events as well, so there is a lot to play with. You can query the network status, open files and programs, or even tie Mail and iPhoto together to

capture, edit, and send photo albums. The possibilities are huge and are all accessible right from your own Swing application.



## Hack 83. Control iTunes Under Windows



Use a simple open source library to monitor and control Windows iTunes from your Swing application.

Windows doesn't have a standard scripting API like Apple Events, but it does have another object model that iTunes supports. Using an open source library, this hack will show you how to script iTunes just as easily on Windows as you can on the Mac.

### 11.6.1. Working with COM

The Component Object Model (COM) is a standard way for Windows components to expose functionality that other programs can call at runtime. `com4j` (<https://com4j.dev.java.net/>) is an open source library that creates connections from Java programs to COM objects. `com4j` has two parts: a command-line program to create the Java interfaces that your program will call, and a native library that binds your program to the COM object at runtime.

`com4j` uses class annotations to do its magic, so you can only use it with Java 5.0 or greater.

To get started, download the `com4j` package at <https://com4j.dev.java.net/servlets/ProjectDocumentList>. With the `com4j` stubber and the iTunes executable in your current directory, you can generate the interfaces like this:

```
java -jar tlbimp.jar -o jtunes -p test.jtunes iTunes.exe
```

This command will load the iTunes executable and look for COM definitions. Once they are located, `tlbimp` will generate a bunch of Java interfaces in the `test.jtunes` package and put the `.java` files into the `jtunes` directory. If you look at the generated Java interfaces, you will see a whole slew of methods and objects for playing, querying tracks, and dealing with virtually every other feature of iTunes. `com4j` will also pull out any embedded documentation and insert the documentation as JavaDoc comments in the generated interfaces.

This process is pretty quick, so you may find it useful to call it from Ant as part of your compile process.

Once you have the interface stubs, you can create a program to control iTunes quite easily. You can use the same program that you did when controlling iTunes on the Mac [\[Hack #82\]](#). Just replace the action listener with the class in [Example 11-6](#).

## Example 11-6. A listener to control iTunes on Windows

```
import test.jtunes.*;
public class WinItunes {
    public void actionPerformed(ActionEvent evt) {
        try {

            IiTunes itunes;
            itunes = ClassFactory.createiTunesApp();
            itunes.playPause();
        } catch (Exception ex) {
            System.out.println("exception : " + ex.getMessage());
            ex.printStackTrace();
        }
    }
}
```

Compile this class along with the interfaces in the `test.jtunes` package. You will also need the `com4j.jar` in your `CLASSPATH` and `com4j.dll` files in your `PATH`. When you run the program, the `com4j` library will connect to iTunes launching it if necessary and execute the `playPause()` method.

`com4j` only allows you to call methods from the same thread that you used to create the COM proxy. Typically, you want to update your Swing components with iTunes information, which you can do safely from the Swing event thread only. This means that you should create the COM proxy from the event thread as well (using the `ClassFactory` method). Unfortunately, this may cause your application to block for a few seconds while iTunes loads (if it's not already running). To avoid this delay, you probably want to do all of your iTunes communication through a custom queue, or use the new concurrency utilities available in Java 5.0. The `com4j` developers are working on a solution to this problem, so it may be solved by the time you read this.

### 11.6.2. Get Track Information

As with Apple Events on the Mac [\[Hack #82\]](#), the COM interface gives you a way to query the currently playing track. You can call `iTunes.currentTrack()` to get an `IITTrack` object. This object has methods to query just about anything you could possibly want to know about a track, including the artist, album, playing time, encoding method, and even the import date. Each method on the `IITTrack` object returns information as Strings or Java primitives, so it's pretty easy to access anything you want and then stuff it into your Swing interface. The following code shows how to get

the track number, count, name, album, and artist:

```
IITTrack track;  
track = itunes.currentTrack();  
int track_number = track.trackNumber();  
int track_count = track.trackCount();  
  
String track_name = track.name();  
String album_name = track.album();  
String artist_name = track.artist();
```

com4j is a great open source project that unleashes the power of Java code integrated with native applications. The iTunes COM interface provides hooks for virtually everything that iTunes can do. These two things mean you could write a program to sort songs, create new playlists, or even export track listings to your own application that prints CD labels. You can find [fscm/sdk/itunescomsdk.html](http://fscm/sdk/itunescomsdk.html), so see what other cool things you can come up with.

 **PREV**

## Hack 84. Construct Single-Launch Applications



Only allow one instance of a program, notifying the existing instance when the user tries to launch a new one.

Most graphical desktop applications are designed for multitasking. You start your program to work on something, then switch to another program and come back later. Oftentimes you'll leave a large program, like a word processor, running in the background to be used again when you need to open another document, say an email attachment you received. When you click on the attachment, your operating system won't start a new instance of the word processor; instead, it will send a message to the currently running instance to `open` the new file saving lots of system resources.

Java programs aren't designed with single-launch behavior in mind. They still use the old Unix style of single use, command-line launching. You start the program to do something and it finishes quickly. If you use the program again it will start a new instance, do the work, and finish. There is never any instance reuse, but modern desktop programs demand it. Because Java doesn't support single-launch applications, this hack shows you how to build it into your programs with a simple use of sockets.

### 11.7.1. Local Sockets

Building a single-launch application requires two parts. When the program starts, it needs to detect if another copy is already running. If there is, then the program can quit instead of continuing to launch. The new program also needs to tell the first copy about any command-line arguments the filename to `open`, for example. You could create a temp file in a known location and look to see if it already exists. This would take care of multiple program instances, but not passing arguments around. Plus, you would need to worry about race conditions and cleaning up the temp file when the last program exits. Thankfully, there's a much better solution: local sockets.

A socket is a network connection defined by a hostname and a port. A *local socket* is a network connection only on the local machine. When you open a socket to listen for connections you are *binding* to that port. Only one program can bind to any given port at one time, so the port itself can serve as your lock. If your program cannot connect to the port, then another program must already be using it. It doesn't matter what the port number is, as long as your program always uses the same one. Here is the beginning of the code to put this into action:

```
public class SingleLauncherApplication implements Runnable {
    public static final int PORT = 38629;
    public JLabel label;
    public ServerSocket server;
```

```

public void launch(String[] args) {
    try {
        server = new ServerSocket(PORT);
        new Thread(this).start();
        firstMain(args);

    } catch (IOException ioex) {
        System.out.println("already running!");
        relaunch(args);
    }
}

```

`SingleLauncherApplication` is a class with one core method: `launch()`. `launch()` takes the same arguments as the standard `main()` method, which is important since you are essentially creating fake versions of `main`. When `launch` is called, it will first try to bind to the port by creating a server socket. Notice the `PORT` constant set to the number `38629`. It is important that the port isn't reserved for use by any system services. Some operating systems also restrict user programs to only use ports over 1,000, so I picked this number at random from the 20,000 to 60,000 range. This makes it very unlikely that the port will already be in use by any other program.

If `launch()` can create a `ServerSocket`, then it will start a new thread, engage `run()`, and then call `firstMain()`:

```

public void firstMain(String[] args) {
    JFrame frame = new JFrame("Single Launch Application");
    frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
    String word = "";
    if(args.length >= 1) {

        word = args[0];
    }
    label = new JLabel("The word of the day is: " + word);
    frame.getContentPane().add(label);
    frame.pack();
    frame.show();
}

```

`firstMain()` contains the normal startup code that would have gone in `main()` previously. Here, it creates a new `JFrame` with a single label in it, containing the text "The word of the day is:" followed by the first commandline argument.

Next comes the `run()` method, which is launched in the new thread by `launch()`. Its entire purpose in life is to sit on that port and wait for connections. If another instance connects, then it reads in the arguments and calls `otherMain()` to relaunch the application:

```

public void run() {
    System.out.println("waiting for a connection");
    while(true) {
        try {
            // wait for a socket connection
            Socket sock = server.accept();

            // read the contents into a string buffer
            InputStreamReader in = new InputStreamReader(
                sock.getInputStream());
            StringBuffer sb = new StringBuffer();
            char[] buf = new char[256];
            while(true) {
                int n = in.read(buf);
                if(n < 0) { break; }
                sb.append(buf,0,n);
            }
            // split the string buffer into strings
            String[] results = sb.toString().split("\\n");
            // call other main
            otherMain(results);

        } catch (IOException ex) {
            System.out.println("ex: " + ex);
            ex.printStackTrace();
        }
    }
}
}
}

```

`server.accept()` will block until another program connects. When one does, the code will open an input stream for the socket and begin to read out characters and save it in a string buffer. If `in.read(buf)` returns `-1` (`n<0`), then it knows the other end disconnected and that's all there is. Command-line arguments are just strings, but they may have spaces in them, so the code above will split the string buffer by new lines ("`\\n`") into an array of strings. Finally, it calls `otherMain()` with the string array:

```

public void otherMain(final String[] args) {
    if(args.length >= 1) {
        SwingUtilities.invokeLater(new Runnable() {

            public void run() {
                label.setText("The word of the day is: " + args[0]);
            }
        });
    }
}
}

```



`otherMain()` doesn't repeat the startup steps of `firstMain()`. Instead it just changes the text of the label to match the new command-line arguments. Because Swing isn't thread-safe, you can't set the label text in the launching thread. Instead, you need to call it from the Swing event thread. The easiest way to do this is with the utility method: `SwingUtilities.invokeLater()`. You can pass it an anonymous `Runnable()` that does the actual `setText()` call. Note that the input variable `args` has to be made `final` for this to work.

If this is the second instance of the program, then the new `ServerSocket()` will fail, and `relaunch()` is called to send the command-line arguments to the first instance:

```
public void relaunch(String[] args) {
    try {
        // open a socket to the original instance
        Socket sock = new Socket("localhost",PORT);

        // write the args to the output stream
        OutputStreamWriter out = new OutputStreamWriter(
            sock.getOutputStream());
        for(int i=0; i<args.length; i++) {
            out.write(args[i)+"\n");
            p("wrote: " + args[i]);
        }
        // cleanup
        out.flush();
        out.close();

    } catch (Exception ex) {
        System.out.println("ex: " + ex);
        ex.printStackTrace();
    }
}
```

`relaunch()` opens a socket to the port on `localhost`. Since `new ServerSocket()` failed, it knows that the first instance of the program is already waiting on the other side of that port. Once it connects, it writes the command-line arguments to the socket's output stream, separating each argument with a newline (`\n`). Finally, it flushes the output stream to make sure everything was written, and then closes it. After that, the `relaunch()` and `launch()` methods will return, quitting the second instance of the program. The arguments have now been sent to the first instance.


To actually start this whole class, you simply call the `launch` method like this:

```
public static void main(String[] args) {
    new SingleLauncherApplication().launch(args);
}
```

The first time the program is launched it will create the window with the label. For example, running the following command would result in [Figure 11-8](#).

```
java -cp . SingleLauncherApplication 'anonymous'
```

Figure 11-8. Initial launch



Now, start the program again, with the first running:

```
java -cp . SingleLauncherApplication 'perspicacity'
```

Instead of creating a new window, the program will contact the original (and still running) instance and change the text to .

Figure 11-9. After relaunching

## Hack 85. Stuff Stuff in JARs



Hide images, sounds, and more inside JAR files.

Does your application need a special installer? Do you have to put images, sounds, icons, and properties all in their own folders or other special locations relative to your application? Does your application launch with a `.sh` script on Unix or a `.bat` on Windows?

You do? Really? I was just speaking rhetorically. I kind of figured everyone was using JARs by now.

### 11.8.1. An Obvious Secret

JAR file—the acronym is short for Java ARchive—must be the best-known, least-used feature in Java. Many developers throw a JAR in their classpath to pick up some standard extension API or third-party library, but how many actually distribute their software that way?

And JARs aren't just about code. It's really easy to put the files your program needs into a JAR. This has the added advantage of hiding your images, sounds, default settings, and so forth from end users.

But to load these items, you need to make a change in how you load stuff in your code. Instead of specifying a known path or URL, you ask a `ClassLoader` to find these resources along the classpath. By doing this, you can get your resources from flat files while you're developing, and then easily switch to getting them from inside a JAR when the code is deployed in the field.

The key is the `ClassLoader`'s `getResource()` and `getResources()` methods, which take a path relative to the loaded class and return a `URL` and an array of `URLs` respectively. A `getResourceAsStream()` method converts the `URL` to an `InputStream` as a convenience.

To clarify the relative path: say you have a directory that includes your compiled classes in a path like `com/mycompany/mypackage/...`, an `images` directory, and a `sounds` directory. A relative path would be one of the form `images/something.png`, `sounds/something.aiff`, etc. By using a resource on the classpath, there is no difference (to the user) between files in a JAR and files in sub-directories of a filesystem. Either way, you get a `URL` that you can use by passing it to methods that take `URL` arguments, by opening an `InputStream` from it, etc.

### 11.8.2. Showing Off

[Example 11-7](#) shows an example of this technique. It uses the `getResource()` method to load an image and put it in an `ImageIcon`, which in turn is used to create a  `JButton`. It also loads in a sound,

which is played via JavaSound when you click the button.

## Example 11-7. Loading image and sound as resources along the classpath

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.sound.sampled.*;
import java.net.*;

public class JarResourceLoading extends JFrame
    implements ActionListener {
    JButton button;
    ImageIcon buttonIcon;
    Clip buhClip;

    public final static String SOUND_PATH = "sounds/buhbuhbuh.aiff";
    public final static String IMAGE_PATH = "images/keagan-buh.jpeg";

    public JarResourceLoading () {
        super ("Resources from .jar");
        // get image and make button
        URL imageURL = getClass().getClassLoader().getResource (IMAGE_PATH);
        System.out.println ("found image at " + imageURL);
        buttonIcon = new ImageIcon (imageURL);
        button = new JButton ("Click to Buh!", buttonIcon);
        button.setHorizontalTextPosition (SwingConstants.CENTER);
        button.setVerticalTextPosition (SwingConstants.BOTTOM);
        button.addActionListener (this);
        getContentPane().add (button);
        // load sound into Clip
        try {
            URL soundURL = getClass().getClassLoader().getResource (SOUND_PATH);
            System.out.println ("found sound at " + soundURL);
            Line.Info linfo = new Line.Info (Clip.class);
            Line line = AudioSystem.getLine (linfo);
            buhClip = (Clip) line;
            AudioInputStream ais = AudioSystem.getAudioInputStream(soundURL);
            buhClip.open(ais);

        } catch (Exception e) {
            e.printStackTrace();
        }
    }

    public void actionPerformed (ActionEvent e) {
        System.out.println ("click!");
        if (buhClip != null) {

```

```

    buhClip.setFramePosition (0);
    buhClip.start();
}
else
    JOptionPane.showMessageDialog (this,
        "Couldn't load sound",
        Error",
        JOptionPane.ERROR_MESSAGE);
}
public static final void main (String[] args) {
    JFrame frame = new JarResourceLoading();

    frame.pack();
    frame.setVisible(true);
}
}

```

Notice how the paths to the sound and the image are relative:

```
public final static String SOUND_PATH = "sounds/buhbuhbuh.aiff";
```

These paths specify the path from a given starting point. As `getResource()` checks each entry in its classpath whether they're directories or JAR files (ZIP files are also allowed) the class loader looks for a directory called *sounds* and, if that's found, for an entry inside it called *buhbuhbuh.aiff*. It's also worth noting that you use the Unix-style forward slashes, regardless of what operating system this is run on.

When you compile and run this code from the source directory, the result looks like [Figure 11-10](#).

Figure 11-10. Application using image and sound loaded with `getResource()`



Along with showing this simple GUI, it also prints to standard out the URLs returned by `getResource()`. Running from the source directory, the output looks like this:

```
[tonberry:] cadamson% java JarResourceLoading
found image at file:/Users/cadamson/Documents/O'Reilly/books/swing%20hacks/
  HacksBook/PackagingInstalling/97/images/keagan-buh.jpeg
found sound at file:/Users/cadamson/Documents/O'Reilly/books/swing%20hacks/
  HacksBook/PackagingInstalling/97/sounds/buhbuhbuh.aiff
```

### 11.8.3. Packing Up

So far, this only proves that resource loading is a nice alternative to fully specified paths. The next step is to put the application and its resources in a JAR. You can do this with a single command:

```
jar cf buh.jar JarResourceLoading.class images sounds
```

Now, you run the application from the JAR by pointing the classpath into it. Here's what the output from that looks like:

```
[tonberry:] cadamson% java -classpath buh.jar JarResourceLoading
found image at jar:file:/Users/cadamson/Documents/O'Reilly/books/
  swing%20hacks/HacksBook/PackagingInstalling/97/buh.jar!/images/
  keagan-buh.jpeg
found sound at jar:file:/Users/cadamson/Documents/O'Reilly/books/
  swing%20hacks/HacksBook/PackagingInstalling/97/buh.jar!/sounds/
  buhbuhbuh.aiff
```

Note the different URLs: the image and sound are now found inside *buh.jar*. The format of the `jar:` URL is also interesting, in that it combines a regular `file:`-type URL for the JAR file with a path inside that JAR, using a `!` character to separate the two parts.

## 11.8.4. Double-Clicking JARs

There are a few more useful things you can do with JAR files. The first is that you can eliminate the need to specify a main class on the command line by specifying it in the JAR file instead. This has the advantage of making the JAR a double-clickable application on graphical operating systems. To do this, create a Manifest file with a line like the following in it:

```
Main-Class: JarResourceLoading
```

You put this into the JAR with the `jar` command's `m` option. Because this option requires an argument (as does `c`, which creates the JAR file), you specify the JAR file to be created and the Manifest file to be inserted in the order that you use the `m` and `c` options. So, you can create the JAR like this:

```
jar cfm buh.jar manifest.txt JarResourceLoading.class images sounds
```

or like this:

```
jar mcf manifest.txt buh.jar JarResourceLoading.class images sounds
```

You could also create the JAR with one command and add the Manifest with another. In any case, you can run the application inside the JAR by double-clicking its icon, or with the command:

```
java -jar buh.jar
```

Granted, this is all pretty burdensome if you have to do it over and over. Presumably, you'll want to automate creating and populating your JAR, and the most popular way to do that is with Apache Ant (<http://ant.apache.org/>). Ant lets you split up and customize the compiling and JAR-building tasks, and its XML syntax is far easier to read than command-line options. [Example 11-8](#) shows a simple Ant *build.xml* file that builds this example and packs it into a JAR, along with a Manifest file that specifies the main class.

Example 11-8. Ant file to compile an application and build a JAR file

```
<project name="jar-resource-loading" default="all" basedir=". ">
  <target name="compile">
    <javac srcdir="." destdir="." />
  </target>

  <target name="package">
    <jar destfile="buh.jar"
      basedir="."
      includes="*.class, images/*, sounds/*"
      manifest="manifest.txt" />
  </target>
  <target name="all" depends="compile, package" />
</project>
```

Because the default target (`all`) runs the `compile` and `package` targets as needed, to compile the application and stuff it and its resources into a JAR, use the command:

```
ant
```

## 11.8.5. And the Kitchen Sink

Because you can get a `URL` and thus an `InputStream` via `URL.openStream()` from any resource found in a JAR, you can put pretty much any kind of file into the JAR and read it back at runtime. This example used images and sounds for simplicity, since `ImageIcon`'s constructor and `AudioSystem.getAudioInputStream()` both take `URL` objects directly, but if you're willing to deal with reading the stream yourself, there's no reason you couldn't put other kinds of files in the JAR. You could put a properties file with default settings in the JAR, open a stream, and then read it into a `Properties` object via the `load()` method. You could put an executable in the JAR and extract it to the local filesystem. You could even put a ZIP file in the JAR, add code to open the ZIP and decompress it to disk, and thus have a self-extracting archive.



## Hack 86. Make Quick Look and Feel Changes



Customize Metal with custom fonts, colors, and even system-bound properties using just a few API calls.

Swing is a very customizable UI toolkit. The most advanced way of changing the look of your application is with a custom Look and Feel (L&F), but they can be tricky to build. Swing's L&F API is very complicated, often requiring thousands of lines of code for a complete custom theme. Fortunately, if you want to change just a few colors or fonts, the L&F API provides a much easier way. This hack shows how to create simple visual changes using UI properties.

### 11.9.1. Look and Feel Properties

Every Look and Feel that extends the `javax.swing.plaf.basic.*` classes can accept special properties that define the behavior of each Swing component. For example, there is property to control the background color of every `JButton`. If you change this property at the start of your program, then every `JButton` you create will have that background color.

The UI properties are stored in a static class called the `UIManager`. To set a property, just put in the name of the property and a value object like a `Color`. To set the background color of a button to green, you would do something like this:

```
UIManager.put("Button.background", Color.green);
```

It is important to set these properties before any components are created or they won't pick up the new settings.

Below is the code for a simple program that shows a few components in a frame. It has a button, label, and text field along the top and a text area in a scroll pane in the middle. There is also a simple file menu at the top. Before creating any components, it sets the foreground and background colors for the button, label, text field, and panel to light and dark green:

```
public static void main(String[] args) throws Exception {
    Color bg = Color.green.brighter();
```

```

Color fg = Color.green.darker();
UIManager.put("Button.background",bg);
UIManager.put("Button.foreground",fg);

UIManager.put("Label.background",bg);
UIManager.put("Label.foreground",fg);
UIManager.put("TextField.background",bg);
UIManager.put("TextField.foreground",fg);
UIManager.put("Panel.background",bg);
UIManager.put("Panel.foreground",fg);

JTextArea jta = new JTextArea();
jta.setText("text\ntext\ntext\ntext\ntext\ntext"+
"\ntext\ntext\ntext\ntext\ntext");
JScrollPane scroll = new JScrollPane(jta);
JButton button = new JButton("A Button");
JLabel label = new JLabel("A Label");
JTextField text = new JTextField("A TextField");

JMenuBar mb = new JMenuBar();
JMenu file = new JMenu("File");
file.add(new JMenuItem("Open"));
file.add(new JMenuItem("Close"));
mb.add(file);
JFrame frame = new JFrame("Custom LaF Defaults");
JPanel top = new JPanel();
top.setLayout(new BorderLayout(top,BoxLayout.X_AXIS));
top.add(button);
top.add(label);
top.add(text);

JPanel panel = new JPanel();
panel.setLayout(new BorderLayout());
panel.add("North",top);
panel.add("Center",scroll);

frame.getContentPane().add(panel);
frame.setJMenuBar(mb);

frame.pack();
frame.setSize(300,200);
frame.setVisible(true);
}

```

When compiled, this will look like [Figure 11-11](#).

Swing provides over 300 properties that define the colors and fonts of each standard component. This lets you customize almost anything in your program. You can even set a color to be transparent which may look interesting if you have a pattern background.

Figure 11-11. A sample program with green components



## 11.9.2. Text Components

Text components have font settings in addition to their colors. This lets you set a component to use a different font style or size. You can even load a custom font from a file:

```
Font font = Font.createFont(Font.TRUETYPE_FONT,  
    new FileInputStream("dungeon.ttf"));  
font = font.deriveFont(Font.BOLD,16f);  
UIManager.put("Label.font",font);
```

This would look like [Figure 11-12](#).


Figure 11-12. A custom font

Most components also have margins that are defined by an `Insets` object. A text field with large insets:

```
UIManager.put("TextField.margin", new Insets(25,25,25,25));
```

would look like [Figure 11-13](#).

Figure 11-13. A JTextField with large insets



Some components even have borders. Menu items have borders but they are turned off by default. You need to set an extra boolean to make a new border show up, as in [Figure 11-14](#).

```
Border border = BorderFactory.createEtchedBorder(
    EtchedBorder.LOWERED);
UIManager.put("MenuItem.border", border);
UIManager.put("MenuItem.borderPainted", new Boolean(true));
```

Figure 11-14. Menu items with etched borders

### 11.9.3. Use System Colors

The `UIManager` lets you change any color in your application to whatever you want. Now, what if you wanted to create a theme that matched the native operating system closer? You could hardcode some color values for each OS, but most windowing systems also let their users customize their colors. Hardcoded values wouldn't take those dynamic colors into account. Fortunately, AWT provides a way out: the `SystemColor` class.

`SystemColor` is a special subclass of `Color` that provides access to most of the standard color settings of any operating system. It also has the special ability to update itself whenever the underlying system color changes. This means if the user switches her native colors from a control panel, your application will automatically update itself to reflect the new settings.

Instead of methods, `SystemColor` has a bunch of constants that define each type of color from `activeCaptionText` to `windowBorder`. The documentation is minor, so you will need to play around with different settings to get the effect you are looking for:

```
Color sysbg = SystemColor.control;  
Color sysfg = SystemColor.controlText;  
UIManager.put("Button.background", sysbg);  
UIManager.put("Button.foreground", sysfg);
```


This code sets the background and foreground of every button to use the `control` and `controlText` fields of `SystemColor`. With my computer set to use the Desert theme, it looks like [Figure 11-15](#).

Figure 11-15. Window with the Desert theme

If I change my window theme to high-contrast black, it looks like [Figure 11-16](#).

`UIManager` properties give developers a simple way to customize the colors, fonts, and borders of almost any Swing component. As an enhancement, you could allow users to customize the colors themselves and store the values in a properties file.

Figure 11-16. Window with the high-contrast black theme



← PREV

## Hack 87. Create an Inverse Black-and-White Theme



Create a custom black-and-white theme for monochrome LCD displays using a few simple `UIManager` calls.

The `UIManager` lets you set simple resources for color, fonts, and padding, but you may have noticed that if you want to theme all of the components, you need to set properties on each one. Since Swing has over 300 Look and Feel properties, this could become a problem. Fortunately, there is another way to make global changes without creating an entire custom L&F. Metal, the standard cross-platform L&F that comes with Swing, can use themes. This hack demonstrates how to create a Metal theme that forces the components to use only black and white.

Swing lets you switch between different Look and Feels. You can use a native Look and Feel (such as the one that comes with Mac OS X) or a thirdparty Look and Feel if you have them installed. Swing also comes with a standard L&F called Metal. Metal is built into the JRE and is always available, making it the ideal L&F to customize.

Like all L&Fs, Metal has many, many classes that you can subclass to make changes. However, it also comes with an interface called `MetalTheme`. If you implement `MetalTheme`, then you can customize most of Metal without digging into the details. Most of the colors in Metal can be set, in fact, with just six values. Metal makes it even easier by providing a default implementation called, unsurprisingly, `DefaultMetalTheme` that you can use as a starting point.

### 11.10.1. A Black-and-White Theme

A Metal theme is defined by a series of colors and fonts. The most important ones are the three primary and three secondary colors. These define the standard set of colors used for every widget on screen. Certain components have additional colors, like the text selection, but almost everything is based on these six. [Example 11-9](#) is a theme that uses only white and black. It is useful for embedded devices that can't afford the hardware or memory requirements of a color display.

#### Example 11-9. A black-and-white Metal theme

```
import javax.swing.plaf.metal.*; import javax.swing.plaf.ColorUIResource;
public class InverseTheme extends DefaultMetalTheme {
    protected ColorUIResource getPrimary1() {
        return new ColorUIResource(255,255,255);
    }
}
```

```
protected ColorUIResource getPrimary2() {
    return new ColorUIResource(0,0,0);
}
protected ColorUIResource getPrimary3() {
    return new ColorUIResource(255,255,255);
}

// component borders
protected ColorUIResource getSecondary1() {
    return new ColorUIResource(0,0,0);
}
// selected components (button down state)
protected ColorUIResource getSecondary2() {
    return new ColorUIResource(0,0,0);
}
// component backgrounds
protected ColorUIResource getSecondary3( ) {
    return new ColorUIResource(255,255,255);
}
```


Two of the primary colors are all white, and the third is black. The three secondary colors are just the reverse: two black and one white. This introduces extra contrast. Each color controls a different part of the component. The `MetalTheme` documentation is very sparse, so the only way to know what a particular color will do is to try it. Without the theme, the screen will look like [Figure 11-17](#).

With the `InverseTheme` installed, the window will look like [Figure 11-18](#).

Figure 11-17. Window with no changes

Figure 11-18. Window with an inverse theme





Setting the six colors gets us most of the way, but there are still some problems. In particular, the label is hidden and the text field looks wrong when you select it. To correct these, you'll need to set three more colors:

```
//for label text
public ColorUIResource getSystemTextColor() {
    return new ColorUIResource(0,0,0);
}
// background of selected text
public ColorUIResource getTextHighlightColor() {
    return new ColorUIResource(0,0,0);
}
// foreground of selected text
public ColorUIResource getHighlightedTextColor() {
    return new ColorUIResource(255,255,255);
}
```

The `SystemTextColor` is used for labels and titled borders, so you have to set this to black as well. The highlighted text, as well as the background of the highlight, are controlled by the `HighlightedTextColor` and `TextHighlightColor`, respectively (confusing, I know).

The only remaining problem is the menus. They have their own set of properties, which you can also set:


```
public ColorUIResource getMenuBackground() {
    return new ColorUIResource(255,255,255);
}
public ColorUIResource getMenuForeground() {
    return new ColorUIResource(0,0,0);
}
public ColorUIResource getMenuSelectedBackground() {
    return new ColorUIResource(0,0,0);
}
public ColorUIResource getMenuSelectedForeground() {
    return new ColorUIResource(255,255,255);
}
```

With all of the colors set, you are ready to load up the theme. All you have to do is call `MetalLookAndFeel.setCurrentTheme()` before you create any Swing components.

```
public static void main(String[] args) {  
    MetalLookAndFeel.setCurrentTheme(new InverseTheme());  
    //.. set up Swing components now  
}
```

If you set it as the first line of the `main()` method in the demonstration program from the previous hack, you will see your themed window as in [Figure 11-19](#).

Figure 11-19. A better inverse theme



# Chapter 12. Miscellany

[Section 12.1. Hacks 88100: Introduction](#)

[Hack 88. Display a Busy Cursor](#)

[Hack 89. Fun with Keyboard Lights](#)

[Hack 90. Create Demonstrations with the Robot Class](#)

[Hack 91. Check Your Mail with Swing](#)

[Hack 92. Don't Block the GUI](#)

[Hack 93. Code Models That Don't Block](#)

[Hack 94. Fire Events and Stay Bug Free](#)

[Hack 95. Debug Your GUI](#)

[Hack 96. Debug Components with a Custom Glass Pane](#)

[Hack 97. Mirror an Application](#)

[Hack 98. Add Velocity for Dynamic HTML](#)

[Hack 99. Get Large File Icons](#)

[Hack 100. Make Frames Resize Dynamically](#)

[← PREV](#)

## 12.1. Hacks 88100: Introduction

Not everything about Swing fits into nice little groupings of functionality. Some of the cool stuff you can do involves cursors, event-dispatching, networking, and even the lights on the keyboard. So, here we present some hacks that were just unique (or weird) enough to defy easy categorization.

[← PREV](#)

## Hack 88. Display a Busy Cursor



Use the `setCursor()` method and an animation thread to show a frame's busy status.

One of Swing's lesser-known features is the ability to change the mouse cursor on a per-component basis. Because the cursor change happens very quickly, you could combine this ability with some simple threading to create an animated cursor. This hack will show you how to create an animated cursor useful for showing a busy status.

Any Swing component even a frame can have a custom cursor. The application as a whole will retain the normal mouse cursor, but when the user moves over the appropriately configured component, the cursor will change to whatever is set for that component. This behavior lends itself nicely to restricting user access during long running processes because the rest of the application can look and feel responsive while the portion that represents the process is visually unusable by the custom cursor.

### 12.2.1. Pre-Generating Images

The best way to manage a short animation is by pre-generating your images in an array. This lets you loop through the array rather than creating a bunch of nasty conditionals. If you later expand the animation, you can just add more images to the array, leaving the rest of the code untouched.

First, you need to build an `AnimatedCursor` class and generate the images in the constructor. In this case, the images are instances of the `java.awt.Cursor` object. I used standard, predefined cursors to keep the code easy, but you could also use cursors derived from custom images. A `JFrame` is passed into the constructor and stored for later use, as you can see in [Example 12-1](#).

#### Example 12-1. A simple animated cursor

```
public class AnimatedCursor implements Runnable, ActionListener {
    private boolean animate;
    private Cursor[] cursors;
    private JFrame frame;
    public AnimatedCursor(JFrame frame) {
        animate = false;
        cursors = new Cursor[8];
        this.frame = frame;
        cursors[0] = Cursor.getPredefinedCursor(Cursor.N_RESIZE_CURSOR);
        cursors[1] = Cursor.getPredefinedCursor(Cursor.NE_RESIZE_CURSOR);
```

```

    cursors[2] = Cursor.getPredefinedCursor(Cursor.E_RESIZE_CURSOR);
    cursors[3] = Cursor.getPredefinedCursor(Cursor.SE_RESIZE_CURSOR);
    cursors[4] = Cursor.getPredefinedCursor(Cursor.S_RESIZE_CURSOR);
    cursors[5] = Cursor.getPredefinedCursor(Cursor.SW_RESIZE_CURSOR);
    cursors[6] = Cursor.getPredefinedCursor(Cursor.W_RESIZE_CURSOR);
    cursors[7] = Cursor.getPredefinedCursor(Cursor.NW_RESIZE_CURSOR);

}
}

```

`AnimatedCursor` implements `Runnable` because it will be threaded, and it accepts action events to turn on and off the animation. You can reuse the standard directional cursors, one for each compass direction, stored in a `Cursor` array, which is eight items long.

## 12.2.2. Running the Animation

Next, you need to build the actual animation thread:

```

public void run() {
    int count = 0;
    while(animate) {

        try {
            Thread.currentThread().sleep(200);
        } catch (Exception ex) { }

        frame.setCursor(cursors[count % cursors.length]);
        count++;
    }
    frame.setCursor(Cursor.getPredefinedCursor(Cursor.DEFAULT_CURSOR));
}

```

Like most `run()` methods, the previous code does something repeatedly in a loop with `sleep()` on each pass. In this case, you call `setCursor()` on the frame and increment the count variable. Notice the code line:

```

cursors[count % cursors.length]

```

which will loop over each cursor in the array, wrapping when it reaches the end. The mod operator (%) is indispensable for these types of calculations. The loop also sleeps on every pass. I chose 200 ms because that lets the cursor make a complete revolution every second and a half, which seemed about right; you can adjust it to your taste:

```
public void actionPerformed(ActionEvent evt) {
    JButton button = (JButton)evt.getSource();
    if(animate) {
        button.setText("Start Animation");
        animate = false;

    } else {
        animate = true;
        button.setText("Stop Animation");
        new Thread(this).start();

    }
}
```

The `actionPerformed()` method starts and stops the animation thread. It also updates the text on the `JButton` as further user feedback.

### 12.2.3. Put It All Together

```
public static void main(String[] args) {
    JFrame frame = new JFrame("Animated Cursor Hack");

    JButton button = new JButton("Start Animation");
    button.addActionListener(new AnimatedCursor(frame));

    frame.getContentPane().add(button);
    frame.pack();
    frame.show();

}
```

The `main()` method in the preceding code creates a frame with a control button. The `AnimatedCursor` applies directly to the frame so that the cursor will animate whenever it's over the window. A screen capture cannot really capture the effect, but when you put it together, it will look something like [Figure 12-1](#).

Figure 12-1. An animated cursor

## 12.2.4. And More...

The most obvious enhancement is to use real images for the cursor, as the many cursor packs available on the Web can attest (type "freecursors" into Google and see what you get). Animated cursors could also be used to indicate other elements of program state, such as network traffic or the current tool in use. With a few images and the help of the `setCursor()` function, you can do almost anything.





## Hack 89. Fun with Keyboard Lights



Flash the Caps Lock, Num Lock, and Scroll Lock keys for extra user feedback.

The AWT and Swing APIs are huge and full of robust components and frameworks for building big applications. They also have some dark corners where the lesser-known functions live. While cruising through the JavaDoc for `java.awt.Toolkit`, I ran across a function I had never noticed before, despite it being in the API for over four years. This hack explores building a keyboardbusy indicator using the `Toolkit.setLockingKeyState()` function.

The root class of AWT, `Toolkit`, has a very interesting little function: `setLockingKeyState()`. You pass it the `KeyEvent` for the key you want to lock down and turn it on or off with the `boolean`. For most keyboards, this means the Caps Lock, Num Lock, and Scroll Lock keys (some keyboards may also have a Kana lock for Kanji support). Now that you have this nifty little function, what should you do with it?

My first thought was a busy cursor. If you've got three lights in a row, why not blink them off and on in sequence? The code in [Example 12-2](#) will flip each light on and off in order, creating a moving bar effect (depending on the order of your keyboard LEDs).

### Example 12-2. Lights, camera, action

```
class SpinnerThread extends Thread {
    private boolean go;
    public void quit() {
        go = false;
    }
    public void run() {
        go = true;
        // get a toolkit
        Toolkit tk = Toolkit.getDefaultToolkit();
        // save the old key states
        boolean old_num, old_caps, old_scroll;
        old_num = tk.getLockingKeyState(KeyEvent.VK_NUM_LOCK);
        old_caps = tk.getLockingKeyState(KeyEvent.VK_CAPS_LOCK);
        old_scroll = tk.getLockingKeyState(KeyEvent.VK_SCROLL_LOCK);

        // set all keys to off
        tk.setLockingKeyState(KeyEvent.VK_NUM_LOCK, false);
        tk.setLockingKeyState(KeyEvent.VK_CAPS_LOCK, false);
    }
}
```

```
tk.setLockingKeyState(KeyEvent.VK_SCROLL_LOCK, false);
```

`SpinnerThread` is a `Runnable` implementation, meaning you can launch it with `new Thread(new SpinnerThread()).start()`. The `run()` method starts an infinite loop, ending only when the `quit()` method is called. The first thing to notice is that the code saves the existing state of the buttons so that it can restore them later. If you had Caps Lock on you'd probably still want it on once the busy cursor leaves. Next, it sets all of the key states to false. This puts them into a known position so that the animation looks right:

```
int key = -1;
boolean state = false;
// loop through 100 times
int counter = 0;
while(go) {

    // select each key every 3rd time
    if(counter%3 == 0) { key = KeyEvent.VK_NUM_LOCK; }
    if(counter%3 == 1) { key = KeyEvent.VK_CAPS_LOCK; }
    if(counter%3 == 2) { key = KeyEvent.VK_SCROLL_LOCK; }
    // flip the state
    state = tk.getLockingKeyState(key);
    tk.setLockingKeyState(key, !state);
    // sleep for 500 msec
    try { Thread.currentThread().sleep(500); }
    catch (InterruptedException ex) {}

    // increment counter
    counter++;
}

// restore the key settings
tk.setLockingKeyState(KeyEvent.VK_NUM_LOCK, old_num);
tk.setLockingKeyState(KeyEvent.VK_CAPS_LOCK, old_caps);
tk.setLockingKeyState(KeyEvent.VK_SCROLL_LOCK, old_scroll);
```

Next comes the loop, which flips one key each time through the loop, cycling between the three keys. This is what produces the actual animation. Once the loop is finished, the keyboard states are restored.

Revisiting this hack (I first wrote it for a blog on <http://www.java.net>), I have been looking for other interesting ideas. One popped out at me as being truly annoying, so I chose to include it here. The class in [Example 12-3](#) flashes the Scroll Lock key on every keystroke. Thus, your computer will keep in time with your typing. Is this the future of human-computer evolution, or just plain annoying?

The key, so to speak, of this hack is once again the `Toolkit` object. It contains a very interesting method, `addAWTEventListener()`, that lets you add a listener for every event dispatched throughout the JVM. This is equivalent to putting a listener on each component in your entire program. This

method is mainly intended for debuggers and testing tools, but I've used it to listen for application-wide keystroke events.

### Example 12-3. Scroll Lock keeping up with typing

```
public class KeyboardFlasher implements AWTEventListener {
    public static void main(String[] args) {
        Toolkit tk = Toolkit.getDefaultToolkit();
        KeyboardFlasher flasher = new KeyboardFlasher();
        tk.addAWTEventListener(flasher, AWTEvent.KEY_EVENT_MASK);


        JFrame frame = new JFrame("Hack #89: Fun with Keyboard Lights");
        JTextField tf = new JTextField("this is some text");
        frame.getContentPane().add(tf);
        frame.pack();
        frame.setVisible(true);
    }
}
```

`KeyboardFlasher` implements the `AWTEventListener` interface and the `main` method adds a new flasher to the toolkit as a listener. `tk.addAWTEventListener`'s second argument, `AWTEvent.KEY_EVENT_MASK`, indicates that the listener should receive key events only. If I wanted the program to also look for mouse clicks, then I would do a bitwise OR (`|`) of `KEY_EVENT_MASK` with `MOUSE_EVENT_MASK`. Finally, the `main()` method creates a text field in a frame to test out generating keyboard events:

```
public void eventDispatched(AWTEvent evt) {
    if(evt instanceof KeyEvent) {
        KeyEvent kevt = (KeyEvent)evt;
        if(kevt.getID() == KeyEvent.KEY_PRESSED) {
            System.out.println("key event: " + evt);
            if(kevt.getKeyCode() != KeyEvent.VK_SCROLL_LOCK) {
                flipScrollLock();
            }
        }
    }
}

public void flipScrollLock() {
    Toolkit tk = Toolkit.getDefaultToolkit();
    boolean state = tk.getLockingKeyState(KeyEvent.VK_SCROLL_LOCK);
    tk.setLockingKeyState(KeyEvent.VK_SCROLL_LOCK, !state);
}
```

As an implementation of `AWTEventListener`, `KeyboardFlasher` has one required method only, `eventdispatched()`. This receives all events generated in the system. This implementation first checks that the event is indeed a keyboard event, and then checks if it is a `KEY_PRESSED` event. This will distinguish between the key going down and the key going up. Then, the method checks to make sure that the key pressed isn't the Scroll Lock key.



If I didn't add this check, the code would go into an infinite loop, as each flip of the Scroll Lock key would generate a new event and trigger a new flip.

Finally comes `flipScrollLock()`, which does exactly what it suggests: flips the state of the Scroll Lock key each time it is called. In other words, it takes two strokes to complete a cycle. For a faster effect, you could make the light turn on with the downward stroke and then off again with the upward stroke. You would just need to call `flipScrollLock()` twice, once for each event.

`setLockingKeyState()` is one of those nut-ball little functions that seems to have no purpose, but it sure lets us have some fun. What other uses can you think up? A new email alert? A three-bar sound meter? A Wi-Fi strength indicator?

## Hack 90. Create Demonstrations with the Robot Class



Use the Robot class to control the mouse cursor and create interactive software features.

One of the coolest things about Swing is that you can often use a class for something completely different than what it was originally intended. The `java.awt.Robot` class, for example, can move the mouse cursor programmatically. This feature was originally intended for use by automated testing tools (hence the name Robot), but I've found it very useful to demonstrate software features by moving the mouse cursor through the same actions as the user. Instead of just describing something in a help file, you can actually show the user what to do and this hack explains how.

### 12.4.1. I, Robot

To create a mouse animation, you need three things:

1. The ability to move the cursor
2. The start and end points of the animation
3. A way to smoothly interpolate the cursor position

The `java.awt.Robot` class has a variety of methods for capturing program state and controlling the user interface, including `Robot.mouseMove()`, which allows you to move the mouse cursor programmatically.

The following code is the implementation of a method `moveMouse()`, which takes three arguments: a starting component, an ending component, and a duration for the animation (in milliseconds). Because most demonstrations involve showing the user a particular component, the easiest points to use are the centers of start and end components. The mouse will smoothly move from the center of the starting component to the center of the ending one. We normally think of components as being positioned relative to their parents, but since the Robot class uses absolute mouse positions, you'll need to convert the components to their screen locations:

```
public void moveMouse(JComponent start, JComponent end,
    final int duration) throws Exception {
    final Robot robot = new Robot();
    // get middle of start
    final Point start_coords = start.getLocationOnScreen();
    start_coords.translate(start.getWidth()/2,
```

```

    start.getHeight()/2);

// get middle of end
final Point end_coords = end.getLocationOnScreen();
end_coords.translate(end.getWidth()/2,

    end.getHeight()/2);
// create interpolation point and offsets
int steps = duration/50;
//Point current = new Point(start_coords);
int distx = (end_coords.x - start_coords.x);
int disty = (end_coords.y - start_coords.y);

// move the mouse over 10 steps
for(int i=1; i<=steps; i++) {
    int x = start_coords.x + i*distx/steps;
    int y = start_coords.y + i*disty/steps;
    robot.mouseMove(x,y);
    try { Thread.currentThread().sleep(50);
    } catch (Exception ex) {}

}
}

```

This code creates a new `Robot` and calculates the center positions of the start and end components using screen coordinates. `steps` is the number of frames required to fill the specified duration. Since each frame will be 1/20 of a second long, the number of frames is the total duration divided by 50 ms. `distx` and `disty` are the distances between the two components in the horizontal and vertical directions. With these values in hand, it is a simple matter to interpolate a new position for each frame and then move the mouse cursor there.

To test the system, you'll need some sort of a demonstration program. The code in [Example 12-4](#) creates a fake file browser with a list of directories, a list of files, and a toolbar with three buttons: Info, New Dir, and Delete. You can see this in [Figure 12-2](#).

Figure 12-2. Sample program to demonstrate mouse automation

## Example 10-4. A simple demonstration for the power of Robot

```
public class AutoMouseHack implements ActionListener {
    public JButton info, new_dir, delete;
    public void createDemo() {
        JFrame frame = new JFrame("File Flipper");

        String[] dirs = {".", "..", "build", "docs", "lib", "src", "www"};
        String[] files = {"build.xml", "readme.txt"};
        JList dir_list = new JList(dirs);
        JList files_list = new JList(files);

        JSplitPane split = new JSplitPane(
            JSplitPane.HORIZONTAL_SPLIT,
            dir_list, files_list);

        info = new JButton("Info");
        new_dir = new JButton("New Dir");
        delete = new JButton("Delete");


        JPanel toolbar = new JPanel();
        toolbar.setLayout(new FlowLayout());
        toolbar.add(info);
        toolbar.add(new_dir);
        toolbar.add(delete);

        frame.getContentPane().setLayout(new BorderLayout());
        frame.getContentPane().add("North", toolbar);
        frame.getContentPane().add("Center", split);

        frame.pack();
        frame.show();
    }
}
```

The demonstration program also contains a Help screen (shown in [Figure 12-3](#)).

Figure 12-3. Help text



This is an HTML pane with the help text in it, plus Close and Show Me buttons. Clicking Show Me will take control of the mouse cursor and show the animation. Note that the `JEditorPane` switches to HTML mode automatically if you put in a content type of `text/html` and start the body text with `<html>`:

```

JButton showme;
public void createHelp() throws IOException {
    JFrame frame = new JFrame("Help");
    JButton close = new JButton("Close");
    showme = new JButton("Show Me");
    showme.addActionListener(this);

    JEditorPane html = new JEditorPane("text/html",
        "<html><body>" +
        "<p>Use the toolbar buttons to interact with the current window</p>."+
        "<p><b>Info</b> display properties of the current file.</p>" +
        "<p><b>New Dir</b> create a new directory</p>"+
        "<p><b>Delete</b> delete the currently selected file</p>" + "
        <p>click <i><b>Show Me</b></i> below to see how it works</p>"
    );
    frame.getContentPane().setLayout(new BorderLayout( ));
    frame.getContentPane().add("North",close);
    frame.getContentPane().add("Center",html);
    frame.getContentPane().add("South",showme);

    frame.pack();
    frame.setLocation(400,50);
    frame.setVisible(true);

}
public static void main(String[] args) throws Exception {
    AutoMouseHack hack = new AutoMouseHack();
    hack.createDemo();
    hack.createHelp();

}

```



With a demonstration program and some help text, now you can create the actual animation. The `moveMouse()` function moves the mouse cursor from one location to another over a certain amount of time. If you make the cursor start and end on the same component, then it will act as a time delay, making the cursor appear to pause over that component:

```
public void actionPerformed(ActionEvent evt) {
    try {
        moveMouse(showme, info, 2000);
        moveMouse(info, info, 1000);
        moveMouse(info, new_dir, 1000);
        moveMouse(new_dir, new_dir, 1000);
        moveMouse(new_dir, delete, 1000);

        moveMouse(delete, delete, 1000);
        moveMouse(delete, showme, 500);
    } catch (Exception ex) {
        System.out.println(""+ex);
    }
}
```

The event handler moves the cursor from the `showme` button, which is where the cursor will already be anyway, to the `info` toolbar button over a period of two seconds. After that, the cursor will hop from button to button taking one second to move with a one second pause over each button. Finally, the cursor rushes back to the `showme` button in a half-second. It is important to return the cursor to its starting position so that the user won't have to hunt for it after the animation is complete. It's best to always return things to the state you found them.

## Hack 91. Check Your Mail with Swing



Add email checking to your application with just a few method calls.

As email becomes a bigger part of our daily lives, I have seen it creep into more and more places. My email program alerts me when there is new mail. I can check my email via the phone. I log in to my web mail from an Internet cafe. Email is everywhere, so why shouldn't it be in your Swing application? This hack shows how to embed in your application an email checker that shows the current number of unread messages and can launch the user's email application.

Dealing with email servers can be a complicated and tricky business. To help address these issues, Sun created the JavaMail API, which is a set of classes defining a vendor-neutral interface for accessing email servers.

Sun's sample implementation provides IMAP support, which is what I will demonstrate here. If you have another kind of email server, such as Exchange, you could install your own service provider and use it the same way.

The code in this hack needs to do two things. First, it must open a connection to the email server periodically and check for new mail. Second, it must launch the user's email program on a double-click. I have encapsulated the email checking and launching code into separate classes, making it very easy to add to an existing program.

The `EmailChecker` class, shown in [Example 12-5](#), is a simple `Runnable` implementation that receives a `JLabel` to its constructor. The run loop will sleep for a certain amount of time (one minute in this case) then call `checkEmail()`. Every time there is new mail, it will set the text of the label to something like "You have *N* new messages."

### Example 12-5. Checking for new messages

```
import java.util.Properties;
import javax.swing.JLabel;
import javax.swing.SwingUtilities;
import javax.mail.*;

public class EmailChecker implements Runnable {
    private JLabel label;
    public EmailChecker(JLabel label) {
        this.label = label;
    }
}
```

```

}

public void run() {
    while(true) {

        try {
            checkEmail();
            Thread.currentThread().sleep(1000*60); // sleep 1 min
        } catch (Exception ex) {
            System.out.println("exception: " + ex);
            ex.printStackTrace();

        }
    }
}
}

```

Next comes the `checkEmail()` implementation:

```

public synchronized void checkEmail() throws Exception {
    String username = "joshyc@code.joshy.org";
    String password = "satans";
    String hostname = "code.joshy.org";
    int port = 143;

    Properties props = System.getProperties();
    Session sess = Session.getDefaultInstance(props);
    sess.setDebug(true);
}

```

To actually check the email, you need to first collect the relevant parameters: the username, password, hostname of the email server, and the port (usually 143 for IMAP servers). In addition to this information, you also need a copy of the system properties to allocate an email `Session`.

In a more advanced version of this hack, you could override some of the system properties to change the installed email provider or modify other settings.

Once you have the session, you can open an IMAP email store and connect to it:

```

Store store = sess.getStore("imap");
store.connect(hostname, port, username, password);

Folder inbox = store.getFolder("INBOX");
final int new_count = inbox.getUnreadMessageCount();

```

```

SwingUtilities.invokeLater(new Runnable() {
    public void run() {
        label.setText("You have " + new_count + " unread messages.");
        System.out.println("unread messages = " + new_count);
    }
});
} // end checkEmail()

```

This code connects to the email store and then opens the *INBOX* folder. Some email servers may use a different name for the inbox folder, but *INBOX* should suffice for most IMAP servers. Finally, you can get the unread message count. Once you have obtained the new message count, you can set the text of the label. It's important to do this on the Swing thread, however, which is why the code uses `SwingUtilities.invokeLater()` to perform the operation.

The second task for this hack is to actually launch the user's email program. Detecting the default email program is difficult and error prone. If you don't want to use a native library like JDIC, then your only option is to ask the user where his program is and launch it with `Runtime.exec()`. [Example 12-6](#) takes care of this, which turns out to be mercifully simple.

### Example 12-6. Asking the user for an email program

```

import java.awt.event.MouseAdapter;
import java.awt.event.MouseEvent;
public class EmailLauncher extends MouseAdapter {
    public void mousePressed(MouseEvent evt) {
        if(evt.getClickCount() >= 2) {
            launchEmailReader();
            evt.consume();
        }
    }

    public void launchEmailReader() {
        try {
            Runtime rt = Runtime.getRuntime();
            rt.exec("C:\\Program Files\\Mozilla Thunderbird\\thunderbird.exe");
        } catch (Exception ex) {
            System.out.println(ex.getMessage());
            ex.printStackTrace();
        }
    }
}

```

I implemented `EmailLauncher` as a mouse listener that looks for a double-click, which makes it very easy to add to any component with a simple `addMouseListener()` call. I have hardcoded the path to

my email program, but a more advanced version of this hack would use a preferences screen to ask the user.

[Example 12-7](#) is a simple program that creates a frame with one `JLabel` to show the mail status. It attaches an `EmailLauncher` to the status label as a mouse listener and then launches the `EmailChecker` in its own thread just before making the frame visible.

## Example 12-7. Testing out the email utilities

```
public class EmailTest {
    public static void main(String[] args) {
        JFrame frame = new JFrame("Hack #91: Check Your Mail with Swing");
        JLabel status = new JLabel("You have XXX unread messages.");
        frame.getContentPane().add(status);
        frame.pack();
        status.addMouseListener(new EmailLauncher());
        EmailChecker email = new EmailChecker(status);
        new Thread(email).start();

        frame.setVisible(true);
    }
}
```

Once you compile the program and run it, you should see something like [Figure 12-4](#).

This is a pretty simple hack, but it should give you inspiration to try other embedded features, such as checking RSS feeds or playing MP3s.

Figure 12-4. Email checker running

```

Hack #68: Embed... Table Window Help Captions ORASTy
Paste As Code (Alt+V)
0 - A A + + |≡ - |≡ |≡
~/projects/HacksBook/Misc/68
$
jmarinacci@JMARINACCI_t40 ~/projects/HacksBook/Misc/68
jmarinacci@JMARINACCI_t40 ~/projects/HacksBook/Misc/68
$
jmarinacci@JMARINACCI_t40 ~/projects/HacksBook/Misc/68
$ java -cp "mail.jar;." EmailTest

DEBUG: getProvider() returning javax.mail.Provider[STORE,imap,com.sun.mail.imap.IMAPStore,Sun Microsystems, Inc]
* OK [CAPABILITY IMAP4REV1 LOGIN-REFERRALS STARTTLS AUTH=LOGIN] dedicated.joshy.net IMAP4rev1 2003.338rh at Mon, 1 Nov 2004 16:58:38 -0500 (EST)
A0 CAPABILITY
* CAPABILITY IMAP4REV1 IDLE NAMESPACE MAILBOX-REFERRALS BINARY UNSELECT SCAN SORT THREAD=REFERENCES THREAD=ORDEREDSUBJECT MULTIAPPEND LOGIN-REFERRALS STARTTLS AUTH=LOGIN
A0 OK CAPABILITY completed
A1 AUTHENTICATE LOGIN
+ VXN1ciB0YW11AA==
+ am9zaH1AY29kZS5qb3NoeS5vcmc=
+ UGFzc3dvcmQA
c2F0YW5z
A1 OK [CAPABILITY IMAP4REV1 IDLE NAMESPACE MAILBOX-REFERRALS BINARY UNSELECT SCAN SORT THREAD=REFERENCES THREAD=ORDEREDSUBJECT MULTIAPPEND] User joshy@code.joshy.org authenticated
A2 LIST "" INBOX
* LIST (\NoInferiors) NIL INBOX
A2 OK LIST completed
A3 STATUS INBOX (MESSAGES RECENT UNSEEN UIDNEXT UIDVALIDITY)
* STATUS INBOX (MESSAGES 22 RECENT 0 UNSEEN 0 UIDNEXT 19961 UIDVALIDITY 1086879684)
A3 OK STATUS completed
unread messages = 0

```

For a more graphical effect, you could use the email icons from the windows system fonts. WebDings and WingDings contain the email icons shown in [Figures 12-5](#) and [12-6](#).

Figure 12-5. "Have Mail" icon

Figure 12-6. "No Mail" icon

However, Windows does strange codepage mapping, so these fonts aren't simple translations of letters to symbols. Instead, you will have to use the true Unicode values for the glyphs you want:

```
SwingUtilities.invokeLater(new Runnable() {
    public void run() {
        //label.setText("You have " + new_count + " unread messages.");
        if(new_count > 0) {
            label.setFont(new Font("WebDings",
                Font.PLAIN,40)); //label.getFont().getSize());
            label.setText(""+(char)0xf099);
        } else {
            label.setFont(new Font("WingDings",
                Font.PLAIN,40)); //label.getFont().getSize());
            label.setText(""+(char)0x2709);
        }
        System.out.println("unread messages = " + new_count);
    }
});
```

This code will set the label to character `0xf099` in the WebDings font (the envelope with a lightning bolt) if there is at least one unread email. If there are no unread emails, it will use character `0x2709` in the WingDings font (a plain envelope).

Java doesn't support all of the glyphs in certain custom fonts, so be sure to test your applications before going into production whenever you use non-ASCII fonts.

## Hack 92. Don't Block the GUI



Thread your heavy lifting so the event-dispatch thread stays responsive.

Practically every AWT and Swing book you'll ever see keeps things simple by responding to button clicks, menu selections, and other actions by doing something in the event listener. That's probably good for helping you learn the various GUI widgets, but it sets you up for a really bad habit: putting increasingly long-lasting calls in your event callbacks.

This is bad because the thread that calls `actionPerformed()`, `valueChanged()`, and other event-based methods is the same thread that services GUI events throughout AWT and Swing. The AWT Event Dispatch Thread is responsible for polling for events, dispatching them to listeners, and for repainting everything. If you block it on some long-lasting calls such as database or network access, intense calculation, etc. then mouse clicks and key-presses won't be processed, menus won't be available, portions of your GUI may not get repainted if they become obscured by other windows, etc. Oh, and the user will hate you. Just so you know.

The trick, then, is to keep heavy lifting out of the event-dispatch thread. There's a very straightforward way to do this in Java: move complicated processing to its own thread, and let event dispatching continue immediately after starting this new thread. Then you just have to deal with cleanup when the launched thread finishes up.

`AWTBlockDemo`, shown in [Example 12-8](#), offers a test bed for exhibiting and fixing the problem. It offers a `JTextField` along with two `JButtons`: Load (blocking) and Load (non-blocking). A menu also offers the blocking and non-blocking load as `JMenuItems`, along with a Quit menu item.

The text field takes a URL. When you click one of the load buttons or menu items, it loads the file at that address into the text area. The text area is pre-populated with the address for `java.awt.Component` in Sun's JavaDoc, a nice 300 KB file that will take a little while to load, even with a fast network connection.

If your network is *really* fast, you can put some `Thread.sleep()` calls in the code to simulate a slower network.

The code for the demo is shown in [Example 12-8](#).

Example 12-8. Demonstration of both blocking and not blocking the AWT event-dispatch thread during lengthy actions



```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import java.io.*;
import java.net.*;

public class AWTBlockDemo extends JFrame {
    JButton blockButton, dontBlockButton;
    JMenuItem blockMenuItem, dontBlockMenuItem, quitMenuItem;
    JTextField urlField;
    JTextArea contentArea;
    final static String DEFAULT_URL =

        "http://java.sun.com/j2se/1.4.2/docs/api/java/awt/Component.html";
    Thread loaderThread;
    public AWTBlockDemo () {
        super ("AWT Thread Blocking");
        initMainLayout();
        initMenus();
        initActions();
    }

    private void initMainLayout() {
        urlField = new JTextField (DEFAULT_URL, 60);
        JPanel topPanel = new JPanel ();
        topPanel.setLayout (new BorderLayout (topPanel, BorderLayout.Y_AXIS));
        topPanel.add (urlField);
        JPanel buttonPanel = new JPanel();
        blockButton = new JButton ("Load (blocking)");
        dontBlockButton = new JButton ("Load (non-blocking)");
        buttonPanel.add (blockButton);
        buttonPanel.add (dontBlockButton);
        topPanel.add (buttonPanel);
        contentArea = new JTextArea (25, 60);
        JScrollPane scroller =

            new JScrollPane (contentArea,
                ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
                ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS);
        getContentPane().setLayout(new BorderLayout());
        getContentPane().add (topPanel, BorderLayout.NORTH);
        getContentPane().add (scroller, BorderLayout.CENTER);
    }

    private void initMenus() {
        JMenuBar bar = new JMenuBar();
        JMenu fileMenu = new JMenu ("File");
        blockMenuItem = new JMenuItem ("Load (blocking)");
        dontBlockMenuItem = new JMenuItem ("Load (non-blocking)");
        fileMenu.add (blockMenuItem);
        fileMenu.add (dontBlockMenuItem);
        fileMenu.addSeparator();
    }
}
```

```
quitMenuItem = new JMenuItem ("Quit");
fileMenu.add (quitMenuItem);
bar.add (fileMenu);
setJMenuBar (bar);

}

private void initActions() {
quitMenuItem.addActionListener (new QuitAction());
BlockingLoadAction blocker = new BlockingLoadAction();
blockButton.addActionListener (blocker);
blockMenuItem.addActionListener (blocker);
NonBlockingLoadAction nonBlocker = new NonBlockingLoadAction();
dontBlockButton.addActionListener (nonBlocker);
dontBlockMenuItem.addActionListener (nonBlocker);

}

public static void main (String[] args) {
AWTBlockDemo awtbd = new AWTBlockDemo();
awtbd.pack();
awtbd.setVisible (true);

}

public void loadURL(boolean useWorker) {
try {
URL url = new URL (urlField.getText());
BufferedReader in =

    new BufferedReader (
    new InputStreamReader (url.openStream()));
StringBuffer sbuf = new StringBuffer();
char[] buffy = new char [16 * 1024];
int bytesRead = 0;
while ((bytesRead = in.read (buffy, 0, buffy.length)) > -1) {
    sbuf.append (buffy, 0, bytesRead);
    // if your net connection is too fast to see blocking
    // add the following here:
    // Thread.sleep (50);

}
if (! useWorker) {
contentArea.setText (sbuf.toString());
contentArea.setCaretPosition(0);

} else {
final StringBuffer finalSBuf = sbuf;
Thread worker = new Thread() {

public void run () {
contentArea.setText (finalSBuf.toString());
contentArea.setCaretPosition(0);
}

}
```

```

        };
        SwingUtilities.invokeLater (worker);
    }
} catch (Exception e) {
    CharArrayWriter writer = new CharArrayWriter();
    e.printStackTrace (new PrintWriter (writer));
    contentArea.setText(writer.toString());
    contentArea.setCaretPosition(0);
}
}

class QuitAction extends AbstractAction {
    public void actionPerformed (ActionEvent e) {
        System.exit(0);
    }
}

class BlockingLoadAction extends AbstractAction {
    public void actionPerformed (ActionEvent e) {
        // note that threaded version doesn't offer a means of
        // being interrupted so it refuses second launch instead
        if (loaderThread != null)
            return;
        loadURL(false);
    }
}

class NonBlockingLoadAction extends AbstractAction implements Runnable {
    // note that this doesn't offer a means of being interrupted
    // so it refuses second launch instead
    public void actionPerformed (ActionEvent e) {
        if (loaderThread != null)
            return;
        loaderThread = new Thread ((Runnable) this);
        loaderThread.start();


    }
    public void run() {
        loadURL(true);
        loaderThread = null;
    }
}
}
}

```

## 12.6.1. To Block or Not to Block

The demo application is shown in [Figure 12-7](#).

Figure 12-7. Blocking and not blocking AWT event dispatch by loading a URL into a JTextArea



After launching the application, try loading the same address with the blocking and non-blocking Load buttons. In the blocking version, you should see that you can't open the `JMenu` or reposition the caret in the `JTextField`. If you've already filled the `JTextArea`, you'll find that the scrollbar is unresponsive while you're blocking. Drag a window over the demo and then bring the demo to the foreground on some operating systems, the area previously obscured by the window won't repaint.

Of course, none of this happens when you use the non-blocking version.

Take a look back at [Example 12-8](#). There are separate `Actions` for the blocking and non-blocking buttons and menu items; but in the end, both of them call `loadURL()`. The difference is how they call it: the `BlockingLoadAction` calls `loadURL()` directly in `actionPerformed()`, while the `NonBlockingLoadAction` creates a `Thread` and runs it. As an aside, both of these methods check to see if there's already a thread running from the `NonBlockingLoadAction`, as you wouldn't want two of these threads running at once, since the first one would populate the text area only to have it clobbered when the second finished.

But back to the point: because the non-blocking load is only responsible for creating and starting a thread, it returns almost immediately. When you use this loading option, you should find that the GUI remains extremely responsive: menus are viewable, the text field is responsive, you can drag the scrollbar, etc.

The only thing that's a little tricky in the threaded case is what to do when the thread finishes. Swing is not thread-safe, so you're not supposed to make Swing calls from any thread other than the event-dispatch thread. If you do, you'll eventually create crazy bugs that look like `NullPointerExceptions`

or `ArrayIndexOutOfBoundsException`, but which are really coming from two threads trying to work with one widget at the same time, thus setting and resetting its variables in hard-to-debug race conditions.

Now, you might be thinking, "wasn't getting code off of the event-dispatch thread the whole point of this exercise?" Only to a certain extent the strategy is to put as little on event dispatch as possible, but you still need to put any Swing calls on it. So, you put the network loading in its own thread, but put the update to the `JTextArea` back on event dispatch. In other words: "render unto event dispatch what is Swing's...".

You can do your Swing work with a worker thread, which is actually just any `Runnable`, typically one whose `run()` method does some Swing work. By calling `SwingUtilities.invokeLater()` or `invokeAndWait()` the difference is in whether you want the `Runnable` executed immediately or in a few milliseconds, and whether you're willing to handle an `InterruptedException` you can put the code in the worker back on the event-dispatch thread. This scheme is effectively a callback method, but instead of being concerned about being called from some event, you're interested in ensuring you're called by a given thread, namely the event-dispatch thread.

In the `doRun()` implementation, you'll notice that there's a flag for whether or not to use a worker. The blocking version doesn't, and doesn't need to, since it's already being called from the event-dispatch thread. The non-blocking version does, but it uses a worker only to reset the contents of the text area after downloading the contents of the URL:

```
final StringBuffer finalSBuf = sbuf;
Thread worker = new Thread() {

    public void run () {
        contentArea.setText (finalSBuf.toString());
        contentArea.setCaretPosition(0);
    }
};
SwingUtilities.invokeLater (worker);
```

Notice how a `final` variable is used for the `StringBuffer`. The anonymous inner thread can see class and instance variables but not local variables like `sbuf`. It can, however, see a `final` local variable, so that's what you pass in.

## Hack 93. Code Models That Don't Block



Models should know that they're doing work on another thread.

You already know how to keep Swing responsive by moving expensive operations off the event-dispatch thread [[Hack #92](#)]. However, one downside to that approach is that it uses a separate inner class to coordinate the interaction between the work being done on the other thread and the Swing components. If you reused the same widgets in several places, you wouldn't want to have to write the "start a thread and populate when done" code over and over again. So don't. Why couldn't the model be responsible for this sort of behavior?

Well, the model can you just have to do a little thinking. Models in Swing are generally in two states: `null` (no data) or populated with data. What if you had a third state, one that indicated that the model was still loading its data?

### 12.7.1. Models Aren't Always Dumb

Adapt [Example 12-8](#) to create *AWTBlockModels.java*. To illustrate the loading, this hack has a `JProgressBar` that you need to declare before the constructor, and which you add at the bottom of `initMainLayout()`:

```
progressBar = new JProgressBar (0, 100);
getContentPane().add (progressBar, BorderLayout.SOUTH);
```

The strategy in this hack is to make the `JTextArea`'s model responsible for its own threaded loading, so get rid of the `loadURL()` method. That code will move to the models, which subclass `javax.swing.text.PlainDocument`. First, change the actions to use these documents:

```
class BlockingLoadAction extends AbstractAction {
    public void actionPerformed (ActionEvent e) {
        BlockingURLDocument bud =
            new BlockingURLDocument (urlField.getText());
        progressBar.setEnabled (true);
        progressBar.setValue (0);
        contentArea.setDocument (bud);
        progressBar.setValue (100);
    }
}
```

```

}

class NonBlockingLoadAction extends AbstractAction {
    public void actionPerformed (ActionEvent e) {
        NonBlockingURLDocument nbud =
            new NonBlockingURLDocument (urlField.getText());
        contentArea.setDocument (nbud);
        // makeProgressBarUpdaterFor (nbud);
    }
}

```

The actions are pretty much the same, except for the fact that the blocking version sets the `JProgressBar` before and after setting the `JTextArea`'s document. Why doesn't the non-blocking action touch the progress bar? We'll get back to that.

[Example 12-9](#) is the blocking document, so named because it loads all the data from the URL in its constructor, which will cause the `Action`'s constructor to block until everything is loaded.

### Example 12-9. A document that will block while loading a URL

```

class BlockingURLDocument extends PlainDocument {
    public BlockingURLDocument (String urlString) {
        super();
        try {
            URL url = new URL (urlField.getText());
            BufferedReader in =
                new BufferedReader (
                    new InputStreamReader (url.openStream()));

            StringBuffer sbuf = new StringBuffer();
            char[] buffy = new char [16 * 1024];
            int bytesRead = 0;
            while ((bytesRead = in.read (buffy, 0, buffy.length)) > -1) {
                sbuf.append (buffy, 0, bytesRead);
                // if your net connection is too fast to see blocking
                // add the following here
                // Thread.sleep (1000);
            }
            remove (0, getLength());
            insertString (0, sbuf.toString(), null);

        } catch (Exception e) {
            CharArrayWriter writer = new CharArrayWriter();
            e.printStackTrace (new PrintWriter (writer));
            try {
                remove (0, getLength());
                insertString (0, writer.toString(), null);
            } catch (Exception e2) {e2.printStackTrace();}
        }
    }
}

```

```

    }
  }
}

```

The implementation here is pretty simple: read bytes and stuff them into a `StringBuffer` until the stream is exhausted, then stuff them into the `Document` with `insertString()`. This makes for clean code because the `Document` loads its own data. The downside is that the caller, which is on the event-dispatch thread, blocks until all the data is read and inserted into the `Document`. And, of course, a blocked event-dispatch thread means nothing in your GUI gets repainted, mouse events aren't processed...basically, nobody's happy.

A more enlightened approach requires a `Document` to load its own data and yet not block the caller. In other words, it will need to return almost immediately, thread whatever work doesn't need to be on event dispatch, and use a worker thread to do the Swing work in a thread-safe manner. [Example 12-10](#) is what a non-blocking document looks like.

### Example 12-10. Document that will not block on URL loading

```

class NonBlockingURLDocument extends PlainDocument
  implements Runnable {
  protected int length = -1;
  protected int totalBytesRead = 0;
  protected String urlString;
  protected Thread readThread;
  public NonBlockingURLDocument (String urlString) {
    super();
    this.urlString = urlString;

    // start thread here
    readThread = new Thread (this);
    readThread.start();
  }
  public void run() {

  try {
    remove (0, getLength());
    URL url = new URL (urlField.getText());
    URLConnection conn = url.openConnection();
    length = conn.getContentLength();
    System.out.println ("length is " + length);
    BufferedReader in =

    new BufferedReader (
    new InputStreamReader (conn.getInputStream()));
    char[] buffy = new char [16 * 1024];
    totalBytesRead = 0;
    int bytesRead = -1;

```



```

while ((bytesRead = in.read (buffy, 0, buffy.length)) > -1) {
    final String str = new String (buffy, 0, bytesRead);
    final int finalTBR = totalBytesRead;
    Runnable worker = new Runnable () {

        public void run() {
            try {
                insertString (finalTBR, str, null);
            } catch (BadLocationException ble) {
                ble.printStackTrace();
            }
        };
        SwingUtilities.invokeLater (worker);
        totalBytesRead += bytesRead;
        System.out.println ("read " + totalBytesRead +
            " of " + length +
            ", progress == " + getProgress());
        // if your net connection is too fast to see updating,
        // make buffy smaller above (maybe 512 bytes) and
        // add the following here:
        // Thread.sleep (500);
    }
    } catch (Exception e) {
        CharArrayWriter writer = new CharArrayWriter();
        e.printStackTrace (new PrintWriter (writer));
        try {
            remove (0, getLength());
            insertString (0, writer.toString(), null);
        } catch (Exception e2) {e2.printStackTrace();}
        } finally {
            readThread = null;
        }
    }

    public boolean isAlive() {
        return (readThread != null) && (readThread.isAlive());
    }
    public float getProgress() {
        return (float) totalBytesRead/length;
    }
}

```

In this case, all the loading is done in a `run()` method, so the constructor simply creates a `Thread` called `readThread` to wrap the `run()`, starts the thread, and then returns, freeing up the event-dispatch thread almost immediately.

So, now it's up to `readThread` to read the stream and load its contents into the `Document`. As in the blocking version ([Example 12-9](#)), it reads bytes into a buffer, but instead of building a big `StringBuffer` with which to do a mass-insert, it uses `Document`'s `insertString()` method to put each bufferful into the document. Since `insertString()` will cause the model to fire off events, this will

provide for a constant updating of the view; that's why this version calls `insertString()` each time through the loop instead of once at the bottom, as the blocking version did. However, `insertString()` is a Swing method, meaning it's thread-unsafe, so you can't call it directly from the `readThread`. Instead, you set up a worker and use `SwingUtilities.invokeLater()` to put the `insertString()` call, and only that call, back onto the event-dispatch thread.

## 12.7.2. Running the Code

If you have a fast Internet connection, it is possible that you'll load the data so fast that you don't mind the blocking or you can't see the incremental updating of the non-blocking version. To make this more dramatic, increase the time that each model `sleep()`s, and reduce the size of the buffer used to read bytes from the `InputStream`. To show the incremental, non-blocking update in [Figure 12-8](#), I set the `sleep()` time to 500 milliseconds and the buffer size to a mere 80 bytes.

Now you have a URL-loading document and a model for `JTextComponents` that will handle its own threaded loading and can thus be dropped into any `JTextComponent` without needing to add any other code to manage its threaded operation.

Figure 12-8. Progressive self-update of a JTextArea's document

## 12.7.3. Exposing the Threading

But what if a caller *wants* to manage threading? You might want to at least expose the fact that a thread is still updating and have the rest of your code be aware of that state.

Notice that the `NonBlockingURLDocument` exposes a pair of extra methods `isAlive()` and `getProgress()` that aren't required by `Document` or anything else in `javax.swing.text`. These are extra methods I tossed into the demo to support the progress bar mentioned earlier in this hack.

The strategy here is to have an outside caller periodically check in on the `NonBlockingURLDocument`, get its progress, and update a progress bar. Notice I said periodically: this is a job for `javax.swing.Timer`! Using the Swing timer, you get regular callbacks, and your code is guaranteed to be on the event-dispatch thread.

So, uncomment the `makeProgressBarUpdaterFor()` call shown earlier, and add this implementation of that method, along with a helper method:

```
private void makeProgressBarUpdaterFor (NonBlockingURLDocument nbud) {
    final NonBlockingURLDocument updatingDoc = nbud;
    updateProgressBar (0);
    ActionListener callback = new ActionListener() {
        public void actionPerformed (ActionEvent ev) {
            progressBar.setEnabled (true);
            int progress = (int) (updatingDoc.getProgress() * 100);
            updateProgressBar (progress);
            if (! updatingDoc.isAlive())
                progressBarUpdater.stop();
        }
    };
    progressBarUpdater = new javax.swing.Timer (2000, callback);
    progressBarUpdater.start();
}

private void updateProgressBar (int progress) {
    // System.out.println ("update progress bar: " + progress);
    if (progress > 0) {
        progressBar.setValue (progress);
    }
    else
        progressBar.setEnabled (false);
}
```

The `makeProgressBarUpdaterFor()` method creates a `Timer` that calls back to the given `ActionListener` every two seconds. The `ActionListener` gets the progress from the `NonBlockingURLDocument` and calls `updateProgressBar()`, which updates the progress bar if the value is positive, and disables the bar if it's negative. Also, if the document is no longer loading, the callback stops the `Timer`.

You might be thinking "why would I have to check for negative progress?" As it turns out, it's an unfortunate implementation detail: a lot of web servers send `-1`, meaning unknown, as the HTTP `content-length` header. If you look around, you'll find sites that do send a valid content length. [Figure 12-9](#) shows an incremental load of <http://www.oreilly.com/>.

This approach used URLs and `Documents`, but the approach is widely applicable to other kinds of model/list models, tables models, etc. and would be well suited to other kinds of slow-to-load data. It should be straightforward to see how you could take this approach to create, say, a `TableModel` that's passed a `java.sql.Connection` and populates its rows progressively with database queries, without blocking the AWT and without making the user wait to see the first few rows of data.

Figure 12-9. Incremental self-loading with a progress bar



## Hack 94. Fire Events and Stay Bug Free



Most developers think that writing an event-firing method is trivial. Most developers are wrong.

As you develop your own Swing components, it's likely that you'll eventually need to have them fire off events; this comes up as soon as you have a model that needs to update a view. If you've strongly typed everything by writing new classes for the model, view, event, and listener, then you'll have to write your own fire method.

Most developers assume this to be trivial. For example, to manage a list of `FooListeners`, they'll typically maintain a `Vector` or `ArrayList` and fire off the event with a block like this:

```
Iterator it = listeners.iterator();
while (it.hasNext())

    ((FooListener).it.next()).handleEvent (fooEvent);
```

And there you have it. It's simple. It's clean. It's elegant. It's *wrong*.

### 12.8.1. The Problem

To illustrate the problem and its various solutions, consider the listener class in [Example 12-11](#).

#### Example 12-11. A simple event listener

```
import java.util.*;
public class TestEventListener extends Object
    implements EventListener {
    String id;
    public TestEventListener (String id) {
        this.id = id;
    }
    public void handleEvent (EventObject o) {

        System.out.println (id + " called");
        if (id.equals ("C")) {
```

```

        ((TestEventSource) o.getSource()).removeListener (this);
    }
}
}

```

This listener hangs on to a `String` and prints that string to standard out when `handleEvent()` is called. Also, if the string is a specific value `C` in this case it removes itself from the event source. If you can see why that's going to be a big deal, congratulations. If not, read on.

Next, define an abstract class to exercise various means of firing the event. This is shown in [Example 12-12](#).

### Example 12-12. Abstract class for testing event-firing techniques

```

public abstract class TestEventSource {
    public abstract void addListener (TestEventListener l);
    public abstract void removeListener (TestEventListener l);
    public abstract void fireEvent (java.util.EventObject o);
    public void test() {
        addListener (new TestEventListener ("A"));
        addListener (new TestEventListener ("B"));
        addListener (new TestEventListener ("C"));
        addListener (new TestEventListener ("D"));
        addListener (new TestEventListener ("E"));
        fireEvent(new java.util.EventObject(this));
    }
}

```

This abstract class requires subclasses to include `addListener()`, `removeListener()`, and `fireEvent()` methods. It also implements a test method that creates five listeners, identified as the letters `A` through `E`, and fires an event to each one.

Now, to show why the obvious way of firing the event is wrong, consider the `PathologicalIteratingEventSource` in [Example 12-13](#). This does exactly what the introduction to this hack advocated: it has an `ArrayList` to hold the listeners, and it uses an `Iterator` to fire off the event to the listeners.

### Example 12-13. Iterating over listeners to fire events

```

import java.util.*;
public class PathologicalIteratingEventSource
    extends TestEventSource {

```

```

ArrayList listeners = new ArrayList();
public void addListener (TestEventListener l) {
    listeners.add (l);
}

public void removeListener (TestEventListener l) {
    listeners.remove (l);
}

public void fireEvent (EventObject o) {
    Iterator it = listeners.iterator();
    while (it.hasNext()) {

        TestEventListener l = (TestEventListener) it.next();
        l.handleEvent (o);
    }
}

public static void main (String[] args) {
    PathologicalIteratingEventSource pies =
        new PathologicalIteratingEventSource();
    pies.test();
}
}

```

So, what happens when you run it? Here's the output:

```

[tonberry] cadamson% java PathologicalIteratingEventSource
A called
B called
C called *****
Exception in thread "main" java.util.ConcurrentModificationException
    at java.util.AbstractList$Itr.checkForComodification(
        AbstractList.java:448)
    at java.util.AbstractList$Itr.next(AbstractList.java:419)
    at PathologicalIteratingEventSource.fireEvent(
        PathologicalIteratingEventSource.java:19)
    at TestEventSource.test(TestEventSource.java:11)
    at PathologicalIteratingEventSource.main(
        PathologicalIteratingEventSource.java:27)

```

So, what happened? The problem is obviously with the `c` listener, the one that removes itself after being called. In fact, this removal is what causes the disaster: the `ConcurrentModificationException` indicates that you're trying to change the `Collection` that underlies the `Iterator`, while iterating over it.

## 12.8.2. And It Gets Worse

At least Java 1.2 has a fail-fast exception for this. Back in Java 1.1, without Collections, you might have used a `for` loop instead of an `Iterator` to count over the listeners. [Example 12-14](#) shows what that might look like.

### Example 12-14. Using a for-loop to fire events

```
import java.util.*;
public class PathologicalForLoopEventSource
    extends TestEventSource {
    ArrayList listeners = new ArrayList();
    public void addListener (TestEventListener l) {
        listeners.add (l);
    }

    public void removeListener (TestEventListener l) {
        listeners.remove (l);
    }

    public void fireEvent (EventObject o) {
        for (int i=0; i<listeners.size(); i++) {
            TestEventListener l = (TestEventListener) listeners.get(i);
            l.handleEvent (o);
        }
    }

    public static void main (String[] args) {
        PathologicalForLoopEventSource pfles =
            new PathologicalForLoopEventSource();
        pfles.test();
    }
}
```


Good news: this doesn't throw an exception. Bad news: this doesn't throw an exception, as seen in the console output:

```
[tonberry] cadamson% java PathologicalForLoopEventSource
A called
B called
C called
E called
```

The obvious question here is: why didn't D get called? Well, think about it: you iterate over the



listeners by index, from 0 to 4. On index 2, the code calls `C`'s `handleEvent()`, which removes itself from the `ArrayList`. As a result, `D`, which was at index 3, is now at index 2. But having serviced index 2 (which was `C`), the `for` loop moves on to index 3, which is now listener `E`. Thus, `D` never gets called.



That was a lot of fun the first time I got to debug it.

### 12.8.3. Hacking a Solution

Consider an alternative approach. Counting up gets you in trouble because a listener that removes itself shifts the indices of all subsequent listeners. But if you counted *down* from the last listener to the first then a listener could remove itself safely.

In these examples, this would mean counting from index 4 down to 0. On index 2, listener `C` removes itself, but that doesn't change the indices of the listeners that haven't been called yet, which are at indices 0 and 1.

All you have to do is change the `fireEvent()` method in the `BackwardsForLoopEventSource` class:

```
public void fireEvent (EventObject o) {
    for (int i=listeners.size()-1; i>=0; i--) {
        TestEventListener l = (TestEventListener) listeners.get(i);
        l.handleEvent (o);
    }
}
```

Run this modified code and you get the output shown here:

```
[tonberry] cadamson% java BackwardsForLoopEventSource
E called
D called
C called
B called
A called
```

Woo hoo! It works! All five listeners get called.

Does the event order matter? Do you need to require that listeners are called in the order they were added? If so, you might do something else, like going back to the `Iterator` approach and making a clone that you iterate over. But that's not really necessary.

Surprisingly, the "count backward" approach is how Swing's classes handle this problem. If you look in the source of Swing objects that have `fireXXX()` methods, you'll see they generally use

`javax.swing.event.EventListenerList`. This class maintains a list in which each pair of elements defines a listener: each even-numbered entry is the `Class` of a listener, and each odd-numbered entry is the listener itself. This means you have to go through the list two entries at a time, checking the class and then firing the event to the listener. It's kind of weird, but the JavaDoc says this provides more thread-safety and serialization support...yeah, great, I'm sure I'll appreciate that the next time I buy some JavaBeans off the shelf at Fry's.

Anyways, take a look at the JavaDoc and you'll see that Sun provides a prototype event-firing method to use with the `EventListenerList`, and like the previous example, it uses a backward `for` loop. [Example 12-15](#) shows a simple implementation as a `TestEventSource`.

## Example 12-15. Using an `EventListenerList` to fire events

```
import java.util.*;
import javax.swing.event.*;
public class EventListenerListEventSource
    extends TestEventSource {
    EventListenerList listenerList = new EventListenerList();
    public void addListener (TestEventListener l) {
        listenerList.add (TestEventListener.class, l);
    }

    public void removeListener (TestEventListener l) {
        listenerList.remove (TestEventListener.class, l);
    }

    public void fireEvent (EventObject o) {
        Object[] listeners = listenerList.getListenerList();
        for (int i = listeners.length-2; i>=0; i-=2) {
            if (listeners[i] == TestEventListener.class) {
                ((TestEventListener) listeners[i+1]).handleEvent(o);
            }
        }
    }

    public static void main (String[] args) {
        EventListenerListEventSource bfles =
            new EventListenerListEventSource();
        bfles.test();
    }
}
```

Notice the odd `for` loop you start at the second-to-last element and decrement by two each time. On each pass, you take the first object of the pair; if it's the right class to fire the event to, you get the second object of the pair and call its event-handling method. Presumably, you could use this to mix up different kinds of listeners in the same list, calling different methods for different classes.

When run, this test produces the following output. Since the eventfiring counts down through the

listeners, it's functionally the same as the simpler backward `for` loop shown earlier:

```
[tonberry] cadamson% java EventListenerListEventSource  
E called  
D called  
C called  
B called  
A called
```





## Hack 95. Debug Your GUI



Standard out and err aren't just for log files anymore.

Debugging GUIs often means keeping one or two console windows open, so you can see the debugging messages you print to standard out (via `System.out.println()` and the like), as well as stack traces printed to standard err when exceptions are caught. In the field, you might want to log these to a file with something like `java.util.logging`, but at design time, or when investigating a bug, you want to see exactly when the exceptions happen, and running `tail -f mylog.txt` in multiple terminal windows may not be practical, especially if you're trying to get a customer on the phone to do it.

An alternative is for your own application to have debugging windows that collect everything printed to standard out and err, something that you or a user can bring up with a keypress or menu item.

### 12.9.1. Hijacking Output Streams

Fortunately, taking control of the standard output and error streams is pretty easy. The trick is to repoint it into your own `JTextArea`s, as shown in [Example 12-16](#).

#### Example 12-16. Redirecting System.out and System.err to Swing windows

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import java.io.*;

JTextArea outArea, errArea;
public StdErrOutWindows () {
    // out
    outArea = new JTextArea (20, 50);
    JScrollPane pain =

        new JScrollPane (outArea,
            ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
            ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS);
    JFrame outFrame = new JFrame ("out");
    outFrame.getContentPane().add (pain);
    outFrame.pack();
```

```
outFrame.setVisible(true);
// err
errArea = new JTextArea (20, 50);
pain =

new JScrollPane (errArea,
    ScrollPaneConstants.VERTICAL_SCROLLBAR_ALWAYS,
    ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS);
JFrame errFrame = new JFrame ("err");
errFrame.getContentPane().add (pain);
errFrame.pack();
errFrame.setLocation (errFrame.getLocation().x + 20,
    errFrame.getLocation().y + 20);
errFrame.setVisible (true);
// set up streams
System.setOut (new PrintStream (new JTextAreaOutputStream (outArea)));
System.setErr (new PrintStream (new JTextAreaOutputStream (errArea)));
}
public static void main (String[] args) {
    new StdErrOutWindows();
    // test
    System.out.println ("test to out");
    System.out.println ("another test to out");
    try {

        throw new Exception ("Test exception");
    } catch (Exception e) {
        e.printStackTrace();
    }
}

public class JTextAreaOutputStream extends OutputStream {
    JTextArea ta;
    public JTextAreaOutputStream (JTextArea t) {


        super();
        ta = t;
    }

    public void write (int i) {
        char[] chars = new char[1];
        chars[0] = (char) i;
        String s = new String (chars);
        ta.append(s);
    }
    public void write (char[] buf, int off, int len) {
        String s = new String (buf, off, len);
        ta.append(s);
    }
}
}
```

The best place to start with this example is actually at the bottom, in the inner class.

`JTextAreaOutputStream` is exactly what it sounds like: an `OutputStream` that takes the data sent to `write()` and appends it to a `JTextArea`. You only need to override two methods, the `write()` that takes a single character (as a Unicode `int`) and the `write()` that takes a character array, as these are called by subclasses, including `PrintStream`'s various `print()` methods. To get the text to the `JTextArea`, all you have to do is convert it to a `String` and call `JTextArea.append()` to put it at the end of the log window.

The constructor of this demo class creates `JTextAreas` and puts them in visible `JFrames` your application may want to hide the `JFrames` until they're needed. Next, it creates `JTextAreaOutputStreams` to write to the `JTextAreas`, and it replaces the default `System.out` and `System.err` streams with them.




If you wanted to log output to the default out and err as well as your `JTextArea`, the `JTextAreaOutputStream` could hold onto a reference to the default `PrintStream` and write to that, as well as appending to the `JTextArea`.

The `main()` method exercises the streams by printing lines to `System.out`, then throwing an exception, catching it, and printing the stack trace (which goes to `System.err`). [Figure 12-10](#) shows what it looks like when run.

In this example, I turned on horizontal scrollbars for the `JTextAreas` with `ScrollPaneConstants.HORIZONTAL_SCROLLBAR_ALWAYS`. I did this to maintain the formatting of stack traces, so you can read what called what, line-by-line. In my opinion, horizontal scrollbars are often overused, especially with `JTables`, in a hateful practice of making the user do extra scrolling work to just see the contents of a row, which usually represent a single thing (the to/from/subject of one email message, the details of a downloaded file, etc.). In cases like these, I'll try to see if `AJList` with a multi-line cell renderer [\[Hack #16\]](#) can keep all the data together in a visually pleasing form. So, when is horizontal scrolling OK? I think it's appropriate when the data you're displaying is not row-oriented, and instead you're scrolling up, down, and across a single cohesive thing, like a large image or, in this case, a stack trace.

Figure 12-10. Capturing standard out and err to Swing windows



← PREV

## Hack 96. Debug Components with a Custom Glass Pane



Show component boundaries at runtime using a glass pane.

Sometimes when I'm building a really complicated Swing layout, I start to lose track of what I'm looking at. Which component is this? Does that panel extend all the way to the end of the frame? A way to visualize the layout would be a useful addition to the usual development tools. This hack explores using a custom glass pane to highlight each component and its classname.

A glass pane is a normally transparent Swing component that is drawn on top of all of the other components in a frame, as you saw when you put dialog-like "sheets" into the glass pane [[Hack #44](#)]. It is this ability that forms the center of the hack. The custom glass pane will traverse the entire tree of components in the frame, filling a translucent rectangle over each component. Deeper components will get painted multiple times resulting in a darker color. The glass pane will also watch the mouse cursor to determine which component the user is pointing at. That component's classname will then be drawn in the glass pane as well.

### 12.10.1. Screens and Glass

The first step is to create a sample screen for the glass pane to draw on top of, as seen in [Example 12-17](#).

Example 12-17. A screen for the glass pane

```
public class ComponentGlassPane extends JComponent {
    public static void main(String[] args) {
        JFrame frame = new JFrame("Component Boundary Glasspane");
        Container root = frame.getContentPane();
        root.setLayout(new BorderLayout(root, BorderLayout.Y_AXIS));
        final JButton activate =
            new JButton("Show component boundaries");
        root.add(activate);
        root.add(new JLabel("Juice Settings"));
        JPanel panel = new JPanel();
        panel.setLayout(new BorderLayout(panel, BorderLayout.X_AXIS));
        panel.add(new JLabel("Flavor"));
        panel.add(new JTextField(" "));
        root.add(panel);
    }
}
```



```

frame.pack();
frame.show();

final ComponentGlassPane glass =
    new ComponentGlassPane(frame);
frame.setGlassPane(glass);

activate.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent evt) {
        glass.setVisible(true);
    }
});
}

```

This `main()` method creates a frame with a few components and one nested panel (called `panel`). The `ComponentGlassPane` is declared as a subclass of `JComponent` so it can be passed to the `setGlassPane()` method on the frame. The glass pane is not visible initially, which produces the same behavior as if it wasn't even there. The activate button is used to make the glass pane visible.

The next step is to create the `ComponentGlassPane` constructor:

```

private JFrame frame;
private Point cursor;
public ComponentGlassPane(JFrame frame) {
    this.frame = frame;
    cursor = new Point();
    this.addMouseMotionListener(new MouseMotionAdapter() {
        public void mouseMoved(MouseEvent evt) {
            cursor = new Point(evt.getPoint());
            ComponentGlassPane.this.repaint();
        }
    });
    this.addMouseListener(new MouseAdapter() {
        public void mouseClicked(MouseEvent evt) {
            ComponentGlassPane.this.setVisible(false);
        }
    });
}

```

This method saves the parent frame that was passed in, and it creates a new point to store the cursor coordinates. Then it adds two mouse listeners to itself. The first listener copies the current mouse coordinates into the cursor object every time the mouse moves. It also requests a repaint, since the user may have moved from one component to another, which would change the currently visible label.

The second mouse listener simply waits for mouse clicks. If the user clicks the mouse, then this listener turns off the visualization effect by hiding the glass pane, and the screen goes back to normal.

So far this has all been pretty straightforward: create a custom `JComponent` and set it as the glass pane on a `JFrame`. Now comes the tricky part: painting the translucent rectangles and labels. First, you need to override the `paint()` method to retrieve the root component of the frame and pass it to the `rPaint()` method:

```
public void paint(Graphics g) {
    Container root = frame.getContentPane();
    rPaint(root,g);
}
```

`rPaint()` stands for recursive paint. It needs to recurse over the entire component tree, painting a rectangle at each step and possibly drawing the label. Because this is so complicated, I'll take it in stages. Here is the initial portion of the method:

```
private void rPaint(Component comp, Graphics g) {
    int x = comp.getX();
    int y = comp.getY();
    g.translate(x,y);
    cursor.translate(-x,-y);


    int w = comp.getWidth();
    int h = comp.getHeight();
    // draw background
    g.setColor(new Color(1.0f, 0.5f, 0.5f, 0.3f));
    g.fillRect(0,0,w,h);
    g.setColor(Color.red);
    g.drawRect(0,0,w,h);
}
```

First, the `rPaint()` method gets the x- and y-coordinates of the component and translates the `Graphics` object and the cursor. The graphics must be translated so that all drawing will happen relative to the origin of the current component. If this weren't called, then all of the rectangles would be shoved into the upper-lefthand corner of the frame. The cursor is also translated, but in the opposite direction. This is because each component's origin must be subtracted from the cursor position to make it relative to the component.

This translation of coordinates is the key to any recursive tree traversal. With this technique, you can start at the top of the tree and do any sort of operation you want to each component, safe in the knowledge that any drawing operations will line up properly.

After coordinate conversion, `rPaint()` grabs the width and height of the current component and then sets the drawing color. Note that this drawing color is composed of four numbers. The first three represent the values of each color component (red, green, and blue) from 0 to 1, where 1 represents

100% of that component and 0 represents 0%. The values `1.0f`, `0.5f`, and `0.5f` produce a medium pink.



The `f` after each number tells the compiler that this is a floating point number. You could write `(float)1.0` to get the same effect.

The last number represents the alpha channel, or transparency, going from `1` for opaque to `0` for completely transparent:

```
// if the mouse is over this component
if(comp.contains(cursor)) {
    // draw the text
    String cls_name = comp.getClass().getName();
    Graphics2D g2 = (Graphics2D)g;
    Font fnt = g.getFont();
    FontMetrics fm = g.getFontMetrics();
    int text_width = fm.stringWidth(cls_name);
    int text_height = fm.getHeight();
    int text_ascent = fm.getAscent();

    // draw text background
    g.setColor(new Color(1f,1f,1f,0.7f));
    g.fillRect(0,0,text_width,text_height);
    g.setColor(Color.white);
    g.drawRect(0,0,text_width,text_height);
    // draw text
    g.setColor(Color.black);
    g.drawString(cls_name, 0, 0+text_ascent);
}
```

Now that the pink rectangle is filled in, the glass pane needs to draw the name of the current component but only if the mouse is over that component. That is what the `comp.contains(cursor)` line does. If `contains()` is true, then `rPaint()` calculates the dimensions of the classname as a string, draws a translucent white background (with 70% opacity), draws a solid white border rectangle, and then finally draws the actual text in solid black:

```
if(comp instanceof Container) {
    Container cont = (Container)comp;
    for(int i=0; i<cont.getComponentCount(); i++) {
        Component child = cont.getComponent(i);
        rPaint(child,g);
    }
}
```

Next comes the recursion. Without this step, `rPaint()` would just work on the root component and stop. Here it checks if the current component is a `java.awt.Container` (which would always be true for any Swing component since `javax.swing.JComponent` subclasses `Container`). If the component has children, it calls `rPaint()` recursively on each child, thus traversing the entire tree of components:

```
cursor.translate(x,y);
g.translate(-x,-y);
} // end rPaint() method
```

This last step simply reverses the graphics translation from the beginning of `rPaint()`. Had the coordinates been passed in as `ints`, which are passed-by-value, it would not be necessary to undo the translations. Any changes to a passed-by-value variable are lost when the enclosing method ends. However, since `cursor` and `g` are both referenced by name, the changes have to be reversed manually.

If you compile and run this code, you will get a screen that looks like [Figure 12-11](#). When you press the activate button, you will see [Figure 12-12](#). As you move the mouse around, the classname label will update.

Figure 12-11. The normal window

Figure 12-12. The window with the glass pane showing

This hack performs a simple visualization: it creates translucent rectangles with solid labels. The same technique could be used to create a much more dynamic interface displaying more detailed information, such as button state, component IDs, color settings, or any other artifact of Swing components.

One thing to notice here is that there are two or more labels visible at any given time. This is because of the nesting of components if the cursor is over a text field and that text field is inside of a panel, then technically the cursor is over both components, producing two labels. You could enhance the `ComponentGlassPane` to only draw one label by creative use of the `SwingUtilities.getDeepestComponentAt()` method.



## Hack 97. Mirror an Application



With creative use of the AWT event log, you can bind two instances of an application together over a socket, creating a mirroring effect.

One of the coolest and severely underrated features of Java is serialization. Because Java code runs entirely in a virtual machine, it's possible to send objects over the network to another program and have the objects still functional when they get there. One day while perusing the AWT documentation, I came across the `AWTEventListener`. I wondered what interesting thing you could do by capturing all of the events in a program. I could write them to disk, of course, but it would be even cooler to send them over the network to another copy of the program. That way the two programs could reuse each other's events and become mirrors! With a global event queue and a bit of serialization, this turns out to be quite easy.

To replicate events over the network, you need to do three things:

1. Capture all AWT events. This can be done with an `AWTEventListener`.
2. Send the event objects over the network.
3. Pick the objects up on the other end of the network and repost them in the second program.

It sounds pretty simple, but there are always a few dragons hiding in the mist.

### 12.11.1. Set Up a Window

Every test program begins with a frame and a few components. This program is no different, with `ApplicationMirrorTest` (shown in [Example 12-18](#)) creating a frame, button, and text field in its constructor.

#### Example 12-18. Simple test program for mirroring

```
public class ApplicationMirrorTest {
    public ApplicationMirrorTest() {
        JFrame frame = new JFrame();
        frame.getContentPane().setLayout(new FlowLayout());

        final JButton button = new JButton("action generator");
```

```

frame.getContentPane().add(button);

JTextField tf = new JTextField("text field");
frame.getContentPane().add(tf);
frame.pack();
frame.show();
}

```

## 12.11.2. Become a Server or Client

There is only one program, but it must run in two modes: one for sending AWT events and one for receiving. If the program starts and it's the first instance running, then it should wait to receive events. If it's the second instance running, then it should send events instead. But how does the program know if it is the first or second instance? The only real way is to look for a shared resource. If the resource is already taken, then this must be the second instance. As with creating single-launch applications on Windows [\[Hack #84\]](#), a network socket is the best choice for a shared resource because you need it anyway to send the events:

```

public void start() {
    try {
        // send events
        final Socket sock = new Socket("localhost",6754);
        openSender(sock);

    } catch (Exception ex) {
        try {
            openReceiver();
        } catch (Exception ex2) {
            System.out.println("exception: " + ex);
        }
    }
}

```

The `start()` method here tries to open a socket on a known port number (6754 in this case). If the socket can be opened, then that means there is a program on the other end waiting for a connection in which case the code can call `openSender()` to start sending events. If the socket cannot be opened, then there is no other program and this is the first running instance. In that case, you can call `openReceiver()` and start waiting for another program to connect.

## 12.11.3. Send Mouse Events

To send events, you first need an output stream to send them. The `java.io` package helpfully provides the `ObjectOutputStream`. It will take any Java object, serialize it, and write it to the stream

the class represents. Next, you need to capture all relevant events and prepare them to go out. The AWT `Toolkit` object lets you add listeners for any set of AWT events you wish. You just need to OR together masks for the event types you want:

```
public void openSender(Socket sock) throws Exception {
    final ObjectOutputStream out = new
        ObjectOutputStream(sock.getOutputStream());

    Toolkit.getDefaultToolkit().addAWTEventListener(
        new AWTEventListener() {
            public void eventDispatched(AWTEvent evt) {
                try {

                    if(evt instanceof MouseEvent) {
                        MouseEvent me = (MouseEvent)evt;
                        out.writeObject(evt);
                    }
                } catch (Exception ex) { }
            }
        },

        AWTEvent.ACTION_EVENT_MASK |
        AWTEvent.MOUSE_EVENT_MASK
    );
}
```

First, `openSender()` creates a new `ObjectOutputStream` around the socket's output stream. Next, it creates a new `AWTEventListener` that takes each event and tests if it is a mouse event; if so, this method writes it to the output stream. Notice that the second argument of `addAWTEventListener()` is two event masks ORed together (using the `|` operator).

## 12.11.4. Receive Mouse Events

Receiving events is the reverse of sending them. You must open a server socket for the (sending) instance to connect to, and then pull the events off of the network one by one and repost them to the system event queue:

```
public void openReceiver() throws Exception {
    // receive events
    ServerSocket server = new ServerSocket(6754);
    Socket sock = server.accept();

    EventQueue eq = Toolkit.getDefaultToolkit().getSystemEventQueue();
    ObjectInputStream in = new ObjectInputStream(sock.getInputStream());
    while(true) {
        AWTEvent evt = (AWTEvent) in.readObject();
    }
}
```



```

if(evt instanceof MouseEvent) {

    MouseEvent me = (MouseEvent)evt;
    MouseEvent me2 = new MouseEvent(
        me.getComponent(),
        me.getID(),
        me.getWhen(),
        me.getModifiers(),
        me.getX(),
        me.getY(),
        me.getClickCount(),
        me.isPopupTrigger(),
        me.getButton()
    );
    eq.postEvent(me2);
}
}
}

```

Notice that the events are not posted directly to the event queue. Since the objects really belong to the other instance, they won't work in this instance properly all of the internal object references will be wrong. However, you can make an *exact copy* of the event just by creating a new one with the arguments from the old one. Then the new event will work fine in this second instance.

Put all of this together, with the following `main()` method, and then fire up two copies of your program. The first one will wait for a connection. When the second one starts, it will send every mouse event over the network to the first copy, which will then reuse it. If you click on the button in the second window, you will see the button depress in the first.

```

public static void main(String[] args) throws Exception {
    ApplicationMirrorTest mirror = new ApplicationMirrorTest();
    mirror.start();
}

```

## 12.11.5. Component Problems

Wait...did this work? No, it didn't. The events still don't work after being sent over the network. A little debugging will show that every part of the reconstituted event works properly except for the `getComponent()` method, which returns `null`. Why?

The reference to the component doesn't get sent over the wire because that would require sending the component itself. That component, of course, is part of your entire Swing tree, which would also have to be sent over. Pretty soon you'd be sending a few megabytes through the network for every event. To avoid this, the developers of Java made the component reference *transient*, which means the object will be skipped during serialization. That makes the component fast, but it presents a

problem: how do you know which component the event goes with?

When you think about it, you wouldn't really want the actual component in the other program anyway. You already have a component on the receiving instance that's showing on screen. You just need to associate the event with the correct component from the sending instance, and match that with the correct component in the receiving instance. Fortunately, every Swing component can have a name attached to it. If both programs use the same names (which they will since they are just different instances of the same code), then you can build a `HashMap` to keep track of them all.

[Example 12-19](#) takes care of these details.

## Example 12-19. Associating events with components via the component name

```
public class ComponentMap extends HashMap implements AWTEventListener {
    public ComponentMap() {
        Toolkit tk = Toolkit.getDefaultToolkit();
        tk.addAWTEventListener(this,
            AWTEvent.COMPONENT_EVENT_MASK);
    }

    public void eventDispatched(AWTEvent evt) {
        try {
            // p("evt = " + evt);
            ComponentEvent ce = (ComponentEvent)evt;
            // p("storing component: " + ce.getComponent().getName());
            this.put(
                ce.getComponent().getName(),
                ce.getComponent()
            );

        } catch (Exception ex) {
            // p("ex: " + ex);
        }
    }
}
```

`ComponentMap` is a subclass of `HashMap`, and it adds one key feature. It listens for component events system-wide and stores the components in its `HashTable` with the component name as the key. Now, instances can look up components using `ComponentMap`. Of course, this means you need to name all of your components. By default, subclasses of `JComponent` will have a `null` value for `getName()`, so you need to set these names explicitly:

```
Map component_map;
public ApplicationMirrorTest() {
    component_map = new ComponentMap();
}
```

```

JFrame frame = new JFrame();
frame.getContentPane().setLayout(new FlowLayout());

final JButton button = new JButton("action generator");
button.setName("button");
frame.getContentPane().add(button);

JTextField tf = new JTextField("text field");
tf.setName("textfield");
frame.getContentPane().add(tf);

frame.pack();
frame.show();
}

```

The new version of the `ApplicationMirrorTest`, which uses all of this new code, creates a `ComponentMap` to track names, and then sets a name for each component as it's created. Once you have the lookup map, you can modify the sending loop in `openSender()` to send the component's name before it sends the event:

```

if(evt instanceof MouseEvent) {
    MouseEvent me = (MouseEvent)evt;

    out.writeObject(me.getComponent().getName());
    out.writeObject(evt);
}

```

You also need to modify the `openReceiver()` method's loop to read a name in before reading in an event. Once you have the name on the receiving side, you can look up the proper component and associate that with the received event.

With these changes in place, the program will work. Each event on the sending instance side will be captured and sent over the network. On the receiving side, each event will be recreated and reposted. The two programs will stay completely in sync; even rollover effects will happen simultaneously:

```

while(true) {
    String name = (String) in.readObject();
    AWTEvent evt = (AWTEvent) in.readObject();
    if(evt instanceof MouseEvent) {

        MouseEvent me = (MouseEvent)evt;
        MouseEvent me2 = new MouseEvent(
            //me.getComponent(),
            (Component)component_map.get(name),
            me.getID(),

```

```
me.getWhen(),
me.getModifiers(),
me.getX(),
me.getY(),
me.getClickCount(),
me.isPopupTrigger(),
me.getButton()

);
eq.postEvent(me2);
}
}
```



[← PREV](#)

## Hack 98. Add Velocity for Dynamic HTML



Use the Velocity template engine to mimic server-side web technologies in your Swing application.

Servlets, JSPs, and other server-side technologies help separate an application's model from its view and allow you to build flexible and dynamic web applications. Of course, Swing applications have their own benefits, like fast user interaction without the need for web server communication. It would be cool to have the power of those server-side technologies right in your Swing application, but without the overhead of a local web server. You can actually mimic a lot of that functionality using a combination of Apache's Velocity template engine and a Swing HTML panel.

As an example, suppose you want to display the weather for the next three days as part of your application. You need a nice graphic weather display showing your users the current weather, as in [Figure 12-13](#).

Figure 12-13. A graphical weather page

### 12.12.1. Velocity and Templates

Velocity is an open source template engine, released under the Apache Jakarta umbrella. At its simplest, Velocity allows you to add intelligent replacement from a text file. At its most extreme, Velocity allows you to call Java methods and use the entire VTL (Velocity Template Language) to create intelligent templates using loops, conditionals, and variables. In other words, you get the

power of an MVC infrastructure like JSP, but in a very lightweight local-client technology.

When using Velocity, you have two basic elements to deal with: the *VelocityContext* and the *template*. The *VelocityContext* holds objects that can be referenced from the template. The template is text with imbedded VTL that controls the Velocity output.

In this simple example, `${name}` and `${what}` indicate replaceable values:

```
${name} is a total ${what}
```

Here is a simple context:

```
VelocityContext context = new VelocityContext();
context.put("name", Jonathan);
context.put("what", Rockstar);
```

When you run Velocity with this context and this template, it will print out:

```
Jonathan is a total Rockstar
```

## 12.12.2. Create the HTML

You'll probably want to create your pages in an HTML editor like Dreamweaver. Better yet, have your graphics designers handle design, and then you can add VTL tags to the HTML they create.

For each of the three days in the display, you need temperature, humidity, pressure, and the name of the day. For each measurement, you need a variable in VTL call these `TEMP`, `HUMIDITY`, and `PRESSURE` and preface them with `DAY` and the day number (like `DAY1`). [Figure 12-14](#) is a screenshot from Dreamweaver, where I built the page with all of the VTL. The dynamic data for the day, temperature, humidity, and pressure are provided by VTL tags: the first day's name is `${DAY1}`, its temperature is `${DAY1_TEMP}`, etc.

Figure 12-14. Weather web page in Dreamweaver

### 12.12.3. Create a Data Object

Now, it's time to leave template land and get into some Java code. You need to write a data object to represent the weather for a particular day. You'll find this useful when you build up your context. To keep things simple, [Example 12-20](#) uses an immutable object.

#### Example 12-20. A simple weather data object

```
public class Weather {
    private BigDecimal temperature;
    private BigDecimal humidity;
    private BigDecimal pressure;
    private String day;

    public Weather(BigDecimal temperature, BigDecimal humidity, BigDecimal
        pressure, String day) {
        this.temperature = temperature;
        this.humidity = humidity;
        this.pressure = pressure;
        this.day = day;
    }

    public BigDecimal getTemperature() {
        return temperature;
    }

    public BigDecimal getHumidity() {
        return humidity;
    }

    public BigDecimal getPressure() {
        return pressure;
    }

    public String getDay() {
        return day;
    }
}
```

Of course, you need to display all of this visual wizardry, so create a class that contains a `JEditorPane` for displaying the HTML. You can use whichever HTML renderer you choose, but `JEditorPane` is a good choice because it's built into Swing. [Example 12-21](#) is a basic container that

contains a `JEditorPane` and configures it to render HTML.

### Example 12-21. Panel to contain the HTML display pane

```
public class WeatherPanel { private JEditorPane htmlPane;
public WeatherPanel() {
    htmlPane = createHtmlPanel();
}

private JEditorPane createHtmlPanel() {
    JEditorPane editorPane = new JEditorPane();
    HTMLEditorKit editorKit = new HTMLEditorKit();
    editorKit.install(editorPane);
    editorPane.setEditorKit(editorKit);
    editorPane.setEditable(false);
    return editorPane;
}

public Component getComponent() {
    return new JScrollPane(htmlPane);
}
}
```

Next, you need to add a method to reconfigure the `htmlPane` with a collection of `Weather` objects:

```
public void displayWeather(String html, Collection weather){
    String result = html;
    try {

        VelocityContext context = createContext(weather);
        result = processString(context, html);
    } catch (Exception e){

        e.printStackTrace();
    }
    htmlPane.setText(result);
}
```

You need to read in the HTML file you created, and that's where `displayWeatherByFile()` comes in. You supply it the filename, and it reads the HTML in that file:



```

public void displayWeatherByFile(String fileName, Collection weather){
    displayWeather(readFile(fileName), weather);
}
private String readFile(String fileName) {
    StringBuffer htmlBuffer = new StringBuffer();

    try {
        InputStream inputStream = WeatherPanel.class.
getResourceAsStream(fileName);
        BufferedReader reader =
            new BufferedReader(new InputStreamReader(inputStream));

        while (true){
            String line = reader.readLine();
            if (line != null){

                htmlBuffer.append(line);
            } else {
                break;
            }
        }
    } catch (IOException iox){

        iox.printStackTrace();
    }
    return htmlBuffer.toString();
}

```

## 12.12.4. Create a Velocity Context

Now, you need to make a `VelocityContext` to supply dynamic values to your template. Create a method called `createContext` and loop through the weather collection, which contains three `Weather` objects:

```

private VelocityContext createContext(Collection weatherCollection) {
    VelocityContext context = new VelocityContext();
    int index = 1;
    for (Iterator iterator = weatherCollection.iterator();
        iterator.hasNext();) {
        Weather weather = (Weather) iterator.next();
        //add info to context
        index++;
    }

    return context;
}

```

Next, create a variable for each day, since all of the VTL is keyed on a measurement, as well as the day (`DAY1`, `DAY2`, or `DAY3`):

```
String day = "DAY" + index;
```

Now, add the day itself, as well as entries for temperature, humidity, and pressure:

```
context.put(day, weather.getDay());
context.put(day + "_TEMP", weather.getTemperature());
context.put(day + "_HUMIDITY", weather.getHumidity());
context.put(day + "_PRESSURE", weather.getPressure());
```

## 12.12.5. Fill the Template with Values

This is the easiest part. The code below is boilerplate code to initialize the Velocity engine and run a template (`htmlText`) through Velocity with a context. It then returns the completed HTML as a String:

```
private String processString(VelocityContext context, String htmlText)
    throws Exception {
    StringWriter writer = new StringWriter();
    Properties properties = new Properties();
    Velocity.init(properties);
    Velocity.evaluate(context,
        writer,
        null,
        htmlText);
    return writer.getBuffer().toString();
}
```

## 12.12.6. Sunny Outside?

Finally, take `WeatherPanel` for a spin. It's a pretty straightforward simulator, creating a display frame and a collection of `Weather` objects, and connecting the two. Notice that the `WeatherPanel` is created and configured with the `Weather` objects:

```
public WeatherPanelSimulator() {
```

```
JFrame frame = new JFrame("Weather Panel Simulator");
frame.setBounds(200,200, 500, 350);

Weather weather1 = new Weather(
    new BigDecimal("82"),
    new BigDecimal("40.0"),
    new BigDecimal(1),
    "Monday");

Weather weather2 = new Weather(
    new BigDecimal("75"),
    new BigDecimal("65.0"),
    new BigDecimal(1),
    "Tuesday");

Weather weather3 = new Weather(
    new BigDecimal("85"),
    new BigDecimal("43.0"),
    new BigDecimal(1),
    "Wednesday");

ArrayList list = new ArrayList();
list.add(weather1);
list.add(weather2);
list.add(weather3);

WeatherPanel weatherPanel = new WeatherPanel();
weatherPanel.displayWeatherByFile("html/today.html", list);

frame.getContentPane().setLayout(new BorderLayout());
frame.getContentPane().add(
    weatherPanel.getComponent(),
    BorderLayout.CENTER);

frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
frame.show();

}
```

This technique is really useful for simple dynamic variable replacement. It lets you change the interface at runtime without code changes by changing the HTML, and you can have your graphics designers implement parts of your application directly in HTML.

*Jonathan Simon*

## Hack 99. Get Large File Icons



Using an undocumented Windows-only class, you can retrieve large, full-color file icons from the operating system.

The `FileSystemView` provides access only to file icons of a default size, which usually means 16 x 16 pixels. If you look at your desktop, however, you may see icons that are much bigger and with more detail and color. There is no standard way to get the larger icons, but on Windows you can use an undocumented (and unsupported) class to get access to them. Sun's JRE for Windows includes a hidden class called `sun.awt.shell.ShellFolder` that will let you retrieve larger (32 x 32) desktop file icons.

This class is only available in Sun's JRE for Windows, so it won't work with other vendors or on other platforms.

The class in [Example 12-22](#) will take a filename and show its large icon in a window.

### Example 12-22. Grabbing a large icon

```
public class LargeIconTest {
    public static void main(String[] args) throws Exception {
        // Create a File instance of an existing file
        File file = new File(args[0]);

        // Get metadata and create an icon
        sun.awt.shell.ShellFolder sf =
            sun.awt.shell.ShellFolder.getShellFolder(file);
        Icon icon = new ImageIcon(sf.getIcon(true));
        System.out.println("type = " + sf.getFolderType());

        // show the icon
        JLabel label = new JLabel(icon);
        JFrame frame = new JFrame();
        frame.getContentPane().add(label);
        frame.pack();
        frame.show();
    }
}
```

```
}
```

`ShellFolder` is a wrapper for metadata of the selected file. With this object, you can retrieve both the icon and a text description of the file's type. A normal MP3 icon would be only 16 x 16 pixels ([Figure 12-15](#)), but if you ran the MP3 file through `LargeIconText` it would print the string `type = MPEG Layer 3 Audio` and show a much nicer 32 x 32 pixel media icon ([Figure 12-16](#)).

Figure 12-15. Normal MP3 icon

Figure 12-16. Large MP3 icon

[← PREVIOUS](#)

## Hack 100. Make Frames Resize Dynamically



Make your application feel more responsive by turning on dynamic layout.

By default, `JFrames` don't resize dynamically. This means that the frame will not redraw itself as the user is resizing it. A repaint will only occur after the user lets go of the mouse and the window is refreshed. This behavior often results in extra gray areas and an unresponsive-feeling application. However, you can fix this with just one method call!

Just call one method on the default `Toolkit`:

```
Toolkit.getDefaultToolkit().setDynamicLayout(true);
```

You can query the dynamic layout property like this:

```
if(Toolkit.getDefaultToolkit().isDynamicLayoutActive()) {  
    // do something  
}
```

or like this:

```
if(Toolkit.getDefaultToolkit().isDynamicLayoutSet()) {  
    // do something  
}
```

`isDynamicLayoutSet()` will tell you if dynamic layout was set programmatically, while `isDynamicLayoutActive()` will tell you if dynamic layout is supported. You need to use both methods because some platforms don't support dynamic layout, and others don't let you turn it off.

### 12.14.1. A Word About Speed

When you have dynamic layout turned on, the window will repaint each time the user moves the mouse. This will make the application feel responsive because there is always information on the screen being updated. If your frame contains an animated component, it will continue to play while the user resizes the window.

The disadvantage of dynamic layout is that a resize will generate a whole lot of repaint requests in a very short time. Even if the user moves the window just one pixel, it will trigger a repaint on the entire frame (unlike scrolling, which usually requires just repainting a strip at the bottom). If your painting code is slow (or you have a lot of components on screen), then the dynamic layout could actually make your program feel *slower*. Be sure you make your painting as fast as possible, perhaps skipping some of the more complicated effects during the resize. You may also want to use dynamic layout only in a program with a small streamlined window, such as a media player or utility app.





## Colophon

Our look is the result of reader comments, our own experimentation, and feedback from distribution channels. Distinctive covers complement our distinctive approach to technical topics, breathing personality and life into potentially dry subjects.

The tool on the cover of *Swing Hacks* is a reflex mallet. Doctors most commonly use reflex mallets to test a patient's "knee-jerk" reaction, which indicates the integrity of the spinal cord in the lower back region. A reflex is a simple nerve circuit, and when tapped by a reflex mallet, sensory neurons send signals to the spinal cord. Reflex tests are part of a neurological exam, and they can be helpful in testing the presence and location of spinal cord injuries or neuromuscular disease.

Marlowe Shaeffer was the production editor and proofreader for *Swing Hacks*. Derek Di Matteo was the copyeditor. Sarah Sherman and Claire Cloutier provided quality control. Ellen Troutman-Zaig wrote the index.

Ellie Volckhausen designed the cover of this book, based on a series design by Edie Freedman. The cover image is a photograph from photos.com. Karen Montgomery produced the cover layout with Adobe InDesign CS using Adobe's Helvetica Neue and ITC Garamond fonts.

David Futato designed the interior layout. This book was converted by Keith Fahlgren to FrameMaker 5.5.6 with a format conversion tool created by Erik Ray, Jason McIntosh, Neil Walls, and Mike Sierra that uses Perl and XML technologies. The text font is Linotype Birka; the heading font is Adobe Helvetica Neue Condensed; and the code font is LucasFont's TheSans Mono Condensed. The illustrations that appear in the book were produced by Robert Romano, Jessamyn Read, and Lesley Borash using Macromedia FreeHand MX and Adobe Photoshop CS. This colophon was written by Marlowe Shaeffer.



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[← PREV](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[.link file extension](#)

[.lnk file extension](#)

[.ttf file \(TrueType font\)](#)

[← PREV](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[absolute layouts](#)

[AbstractBorder class 2nd](#)

[AbstractListModel class](#)

[AbstractTableModel class](#)

[\\_getValueAt\(\)](#)

[acceptDrop\(\)](#)

[Action class](#)

[ActionListener interface 2nd 3rd](#)

[actionPerformed\(\) 2nd 3rd 4th 5th](#)

[\\_animated sheet dialog](#)

[\\_cursor animation](#)

[\\_earthquake dialog component](#)

[addAWTEventListener\(\) \(Toolkit\) 2nd](#)

[addDirtyRegion\(\) \(RepaintManager\)](#)

[adding to windows](#)

[status bars](#)

[\\_corner \(resize\) icon](#)

[\\_left component](#)

[\\_painting panel details](#)

[\\_standard MS Windows setup](#)

[addItem\(\)](#)

[addMovieAndStart\(\)](#)

[AffineTransform class](#)

[AIFF audio files](#)

[alpha levels](#)

[\\_fade-in and fade-out animations](#)

[\\_shadow for vector-based button](#)

[AlphaComposite class](#)

[AND \(&\) operator](#)

[animations](#)

[\\_busy cursor 2nd 3rd 4th](#)

[\\_earthquake dialog 2nd 3rd 4th 5th](#)

[\\_frame dissolves 2nd 3rd 4th 5th 6th](#)

[\\_glass pane as indefinite progress indicator 2nd 3rd 4th 5th](#)

[\\_JList selections 2nd 3rd 4th 5th 6th](#)

[\\_JTree drops 2nd 3rd 4th 5th 6th](#)

[\\_mouse animation 2nd 3rd 4th 5th](#)

[\\_sheet dialog 2nd 3rd 4th 5th 6th](#)

[\\_slide-in window](#)

[\\_spotlights](#)

[anti-aliased text](#)

[\\_global anti-aliased fonts 2nd 3rd 4th 5th](#)

[\\_with custom Look and Feel](#)

- [without code 2nd 3rd](#)
- [Apple Events](#)
- [Apple System Properties](#)
- [AppleScript](#)
- [applets 2nd 3rd 4th](#)
  - [restrictive applet security](#)
- applications
  - [Mac OS X](#)
- [Aqua Look and Feel](#)
- [Area](#)
- [ArrayList class](#)
- [Arrays class](#)
- [arrow for drop-down menu button](#)
- [ascent \(fonts\)](#)
- audio
  - [controls for JavaSound playback 2nd 3rd 4th 5th](#)
  - [MP3 support](#)
  - [playing a sound with JavaSound 2nd 3rd 4th 5th](#)
  - [playing non-trivial with JavaSound 2nd 3rd 4th 5th 6th](#)
    - [uncompressed PCM files of arbitrary length 2nd 3rd](#)
  - [playing sound in an applet 2nd 3rd 4th](#)
  - [playing sound with QTJ 2nd 3rd 4th 5th 6th](#)
  - [playing sounds with JMF 2nd](#)
  - [showing information while playing 2nd 3rd 4th](#)
    - [level information calculations 2nd 3rd 4th 5th](#)
- [AudioClip class 2nd 3rd 4th 5th 6th](#)
  - [playing in an applet](#)
  - [supported audio formats](#)
- [AudioFormat class](#)
- [AudioInputStream class 2nd](#)
- [AudioSystem class](#)
- [auto-completing text fields 2nd 3rd 4th 5th 6th 7th 8th](#)
- [AWT](#)
- [AWTEventListener interface 2nd 3rd](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[Background class](#)

[background property \(List\)](#)

[BackgroundLoader class \(example\)](#)

backgrounds

[\\_default](#)

[\\_drawing for custom tool tip](#)

[\\_image-themed component](#)

[\\_label](#)

[\\_text area 2nd 3rd](#)

[backward text 2nd 3rd 4th](#)

[BasicMenuItemUI class](#)

[BasicPopupMenuUI class 2nd](#)

[big-endian](#)

[binding to a port](#)

[bit shifting 2nd](#)

[blocking a window 2nd 3rd 4th](#)

[blocking Load buttons](#)

blurring

[\\_spotlight borders](#)

[BooleanControl class](#)

[BorderLayout class](#)

borders

[\\_image-based 2nd 3rd](#)

[\\_removing from transparent window](#)

[\\_shadow border](#)

[\\_text components and menu items](#)

[BoxLayout class](#)

[brightness of a picture as indefinite progress indicator 2nd 3rd](#)

[brushed metal Look and Feel](#)

[BufferedImage class 2nd](#)

[\\_3D scenes](#)

[\\_file icons](#)

[build.xml file \(Ant\)](#)

[buildIndex\(\)](#)

buttons

[\\_building colorful vector-based](#)

[\\_creating image-based](#)

[\\_custom tool tip](#)

[\\_HTML](#)

[bytes2short\(\)](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[calendar 2nd 3rd 4th](#)

[Canvas3D class](#)

[faking transparency](#)

[Caps Lock 2nd 3rd 4th](#)

cell renderers

[animated list cells](#)

[animating potential drops on reorderable list](#)

[for checkbox list](#)

[JFileChooser](#)

[JList with multiple layouts 2nd 3rd 4th 5th 6th](#)

[PolyRenderer class \(example\)](#)

[table cells](#)

[tree cell](#)

[turning methods into list renderers 2nd](#)

[ChangeListener interface](#)

[channel \(audio\)](#)

checkboxes

[making JLists checkable](#)

[circular shape for indefinite progress indicator](#)

[ClassLoader class](#)

classpaths

[loading image and sound as resources 2nd 3rd](#)

[resources on](#)

[running application from JAR file](#)

[client](#)

[Clip interface 2nd](#)

[close boxes](#)

[code models 2nd 3rd 4th 5th 6th](#)

collections

[creating List-based JComboBox 2nd](#)

[Collections class](#)

[colorizeSelections\(\)](#)

colors

[eyedropper tool 2nd 3rd](#)

[list cell foreground and background](#)

[selection panel for drop-down component 2nd 3rd](#)

[system](#)

[columnAtPoint\(\) \(JTableHeader\)](#)

columns

[adding column selection 2nd 3rd](#)

[sizing to suit content 2nd 3rd 4th 5th 6th](#)

[com4j package](#)

combo boxes

- [collections-aware JComboBox 2nd 3rd 4th 5th](#)
  - [menus with drop shadows 2nd 3rd 4th](#)
- [Comparable interface](#)
- [Comparator class](#)
  - [delegated sorting](#)
  - [sorting color values](#)
- [compare\( \)](#)
- [Component Object Model \(COM\)](#)
  - [iTunes track information](#)
- [component references](#)
- [ComponentAdapter class](#)
- [ComponentListener interface 2nd](#)
- [componentMoved\( \)](#)
- [components](#)
  - [associating events via component name](#)
  - [debugging with custom glass pane 2nd 3rd 4th 5th](#)
  - [disabled](#)
- [CompoundControl class](#)
  - [Swing representation](#)
- [computeGrabRect\( \)](#)
- [ConcurrentModificationException](#)
- [content-length header \(HTTP\)](#)
- [context menus](#)
  - [adding to JFileChooser 2nd 3rd 4th 5th](#)
  - [global right-click 2nd 3rd 4th](#)
- [continueSearch\( \)](#)
- [Control class](#)
  - [Type subclass](#)
- [ControllerListener interface](#)
- [controlling on Mac OS X](#)
  - [iTunes](#)
    - [AppleScript API](#)
- [controls 2nd 3rd 4th 5th](#)
  - [factory to generate 2nd 3rd 4th 5th](#)
- [convertPoint\( \) \(SwingUtilities\)](#)
- [ConvolveOp class](#)
- [coordinates](#)
  - [mouse 2nd](#)
  - [status bar components](#)
- [createCompatibleImage\( \) \(GraphicsConfiguration\)](#)
- [createDialog\( \)](#)
- [createFont\( \) \(Font\)](#)
- [createImage\( \)](#)
- [createScene\( \)](#)
- [createScreenCapture\( \) \(Robot\) 2nd](#)
- [createTempFile\( \) \(File\)](#)
- [createToolTip\( \)](#)
- [createUI\( \)](#)
- [CSS](#)
- [cursors 2nd 3rd 4th](#)
- [Cylon](#)





[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[data flavors](#)

[image](#)

[java.net.URLs](#)

[native drag-and-drop](#)

[data object](#)

[data types](#)

[database connections](#)

[populating Swing TableModel from](#)

[testing JDBC-based table](#)

[DatabaseMetaData objects](#)

[DataLine interface](#)

[dates 2nd](#)

[debugging](#)

[components with custom glass pane 2nd 3rd 4th](#)

[decorator \(wrapper\) 2nd 3rd 4th](#)

[GUIs](#)

[redirecting output streams to Swing windows 2nd 3rd](#)

[DefaultListCellRenderer class](#)

[DefaultListModel class](#)

[DefaultMetalTheme class](#)

[DefaultMutableTableModel class](#)

[DefaultTableModel class 2nd](#)

[DeleteAction class](#)

[deltas from drag events](#)

[desktop Java applications](#)

[launching external programs on Mac OS X 2nd](#)

[detail pane 2nd 3rd 4th 5th](#)

[dialog using \(example\)](#)

[inner class spin triangle](#)

[layout of components](#)

[dialog](#)

[dialogs](#)

[earthquake 2nd 3rd 4th](#)

[modal](#)

[sheet 2nd 3rd 4th 5th 6th 7th](#)

[turning into frame-anchored sheets 2nd 3rd 4th](#)

[directories](#)

[opening on Windows](#)

[DirectoryItem class](#)

[dirty region](#)

[disabled components 2nd 3rd](#)

[dispatchEvent\(\) \(Component\)](#)

[dispose\(\)](#)

dissolving

frames

[\\_genie effect](#)

[dissolving frames](#)

[\\_basic steps](#)

[\\_doing the drawing](#)

[\\_genie effect](#)

[\\_preparing the dissolve](#)

[\\_running the animation](#)

Document class

[\\_blocking](#)

[DocumentEvent class](#)

[DocumentListener interface 2nd](#)

documents

[\\_constraining](#)

[drag gesture](#)

[drag images](#)

drag-and-drop

[\\_draggable window 2nd 3rd 4th](#)

[\\_dropped Picts on Mac OS X 2nd 3rd](#)

[\\_files 2nd 3rd 4th](#)

[\\_handling dropped images 2nd 3rd 4th](#)

[\\_handling dropped URLs 2nd 3rd](#)

[\\_reordering JTrees](#)

[\\_reordering lists](#)

[\\_translucent 2nd](#)

[draggable 2nd 3rd](#)

[DragGestureListener class 2nd](#)

[dragGestureRecognized\( \)](#)

[DragGestureRecognizer class](#)

[dragOver\( \) 2nd](#)

[DragSource class](#)

[DragSourceAdapter class](#)

[\\_dragEnter\( \) and dragExit\( \)](#)

[DragSourceListener class](#)

drawing

[\\_animation](#)

[\\_paintComponent\( \) method](#)

[\\_tool tip background and border](#)

[drawing code](#)

[\\_watermark](#)

[\\_watermarking scroll panes](#)

[drawRoundRect\( \)](#)

[drawTextAntialiased\( \)](#)

[drop](#)

drop shadows

[\\_and embossing effects 2nd 3rd 4th 5th 6th](#)

[\\_on menus 2nd 3rd 4th](#)

[\\_text on vector-based button](#)

[drop\( \)](#)

[drop-down menu button 2nd 3rd 4th 5th 6th](#)

[\\_color selection panel 2nd 3rd 4th](#)

[dropComplete\(\)](#)

[DropTargetDragEvent class](#)

[DropTargetDropEvent class](#)

[DropTargetListener interface 2nd](#)

[dynamic HTML 2nd 3rd 4th 5th 6th](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[Ellipse2D](#)

[email](#)

[\\_checking with Swing 2nd 3rd 4th 5th](#)

[\\_opening application on Windows with start](#)

[embossing effect 2nd 3rd 4th 5th](#)

[EndOfMediaEvent object](#)

[EnumControl class 2nd](#)

[event-dispatch thread 2nd 3rd 4th 5th 6th](#)

[eventDispatched\(\)](#)

[EventListenerList class](#)

[events](#)

[\\_Apple](#)

[\\_capturing all and mirroring application 2nd 3rd 4th 5th 6th 7th](#)

[\\_keystroke](#)

[\\_list selection](#)

[\\_order of firing](#)

[\\_UI components](#)

[\\_window \(operating system\)](#)

[Excel spreadsheet 2nd 3rd 4th](#)

[exec\(\) \(Runtime\)](#)

[\\_calling open program](#)

[\\_launching email program](#)

[Explorer \(Windows\)](#)

[\\_icon 2nd 3rd 4th](#)

[\\_status bar 2nd 3rd](#)

[extension hook \(JFileChooser\)](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[fading to nothing](#)

file choosers

[adding right-click context menu](#)

[displaying shortcuts 2nd](#)

[image previewer 2nd 3rd 4th](#)

[previewing ZIP and JAR files 2nd 3rd 4th 5th 6th 7th](#)

[Windows shortcut support 2nd 3rd 4th 5th](#)

File class

[proxies](#)

FileItem class

files

[drag-and-drop 2nd 3rd](#)

[linked](#)

FileSystemView class 2nd

[custom \(ZipFileSystemView\)](#)

[file icons](#)

fileToString( )

FileView class 2nd

fillRoundRect( )

filter box

FilterField class

FilterModel class

filters

find( )

fireUpdate( ) 2nd

[firing events in proper order 2nd 3rd 4th 5th 6th 7th](#)

FloatControl class

focus events

Font class

font metrics

fonts

[changing style or size in text components](#)

[changing throughout an application 2nd 3rd 4th](#)

[email icons](#)

[HTML effects](#)

[loading new at runtime 2nd 3rd](#)

foreground property (List)

FormLayout class

frame-anchored sheets 2nd

frames

[finding parent frame of drop-down component](#)

[minimizing to mini frame 2nd 3rd 4th 5th](#)

[sheet dialog](#)

[frames \(audio\)](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[genie effect](#)

[getAudioInputStream\(\)](#)

[getColumnClass\(\) 2nd 3rd](#)

[getColumnCount\(\) 2nd](#)

[getColumnName\(\) 2nd](#)

[getComponent\(\)](#)

[getControls\(\) \(Line\)](#)

[getDeepestComponentAt\(\)](#)

[getElementAt\(\)](#)

[getFiles\(\)](#)

[getFrame\(\)](#)

[getIcon\(\) \(FileView\) 2nd](#)

[getIconHeight\(\)](#)

[getIconWidth\(\)](#)

[getInstance\(\) \(AlphaComposite\)](#)

[getLevel\(\) \(DataLine\)](#)

[bug in](#)

[getListCellRendererComponent\(\) 2nd](#)

[getLocation\(\) \(DropTargetDragEvent\)](#)

[getLocationOnScreen\(\)](#)

[getMaximumWindowBounds\(\)](#)

[getNullDelimitedString\(\)](#)

[getPathForLocation\(\) \(JTree\)](#)

[getPixelColor\(\) \(Robot\)](#)

[getPreferredSize\(\)](#)

[tool tip](#)

[getResource\(\)](#)

[getResources\(\)](#)

[getRowCount\(\)](#)

[getScaledInstance\(\)](#)

[getSize\(\)](#)

[getSubimage\(\) \(BufferedImage\) 2nd 3rd](#)

[getSystemIcon\(\)](#)

[getting large file icons](#)

[getTreeCellRendererComponent\(\)](#)

[getType\(\)](#)

[getValueAt\(\)](#)

[TableModel class](#)

[ghosting](#)

[GhostPictureAdapter class](#)

[ghosts](#)

[handling component ghosts](#)

[glass pane 2nd](#)

[\\_capturing right-click events and triggering pop up 2nd 3rd](#)  
[indicator for indefinite progress bar 2nd](#)  
[spotlights 2nd](#)  
[grab rectangle for magnifier component 2nd](#)  
[Graphics object](#)  
Graphics2D class  
[\\_round rectangle methods](#)  
[GraphicsConfiguration class](#)  
[GraphicsEnvironment class](#)  
[GraphicsImporterDrawer class 2nd](#)  
[GridBagLayout class](#)  
[grouping in regular expression pattern matching](#)  
[grow box \(Mac\)](#)  
GUI (graphical user interface)  
[\\_debugging](#)  
threading complicated processing to  
[\\_thread 2nd 3rd 4th 5th 6th](#)

[← PREV](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[Hashtable class](#)

[header cells \(table columns\)](#)

[heavyweight components](#)

[hidePopup\(\)](#)

[highlight](#)

[history](#)

[HSQLDB](#)

**HTML**

[\\_customizing labels](#)

[\\_displaying AppletSound applet](#)

[\\_dynamic](#)

[\\_enhancing text components 2nd 3rd](#)

[HTTP content-length header](#)

[Hypersonic](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[Icon interface](#)

icons

[Explorer 2nd](#)

[file](#)

[linked directory 2nd](#)

[MS Office](#)

[window resize \(Windows\) 2nd 3rd 4th 5th](#)

[windows resize icons](#)

[IITTrack object](#)

image-based

borders

[insets](#)

[image-themed components 2nd 3rd](#)

[buttons](#)

[custom calendar 2nd 3rd 4th](#)

[painting and testing the image](#)

[panel](#)

[ImageFileItem class](#)

[ImageIO interface](#)

[ImageProducer class](#)

images

[3D scene](#)

[creating image-based borders 2nd](#)

[creation of](#)

[drag image](#)

[dropped 2nd 3rd](#)

[dropped Picts on Mac OS X 2nd 3rd](#)

[loading as resource along the classpath](#)

[using for cursor](#)

[incremental searching 2nd 3rd 4th 5th](#)

[indefinite progress bar 2nd 3rd 4th 5th 6th](#)

[picture as indicator](#)

[index \(table model\)](#)

[indexing](#)

[InputStream class](#)

[InputStreamReader class](#)

[insertString\( \) \(Document\) 2nd 3rd](#)

[insertUpdate\( \)](#)

insets

[border](#)

[shadow border](#)

[text components](#)

[installUI\( \)](#)

[instanceof operator](#)

[invisible component](#)

[invokeAndWait\(\) \(SwingUtilities\)](#)

[invokeLater\(\) \(SwingUtilities\) 2nd](#)

[isDirLink\(\)](#)

[isDragImageSupported\(\)](#)

[isDynamicLayoutActive\(\)](#)

[isDynamicLayoutSet\(\)](#)

[isTraversable\(\)](#)

[JFileChooser class](#)

[isValueAdjusting\(\) \(ListSelectionEvent\)](#)

iTunes

[controlling on Mac OS X 2nd 3rd 4th](#)

[controlling on Windows 2nd 3rd](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[JAR \(Java ARchive\) files 2nd 3rd 4th](#)

[double-clicking](#)

[packaging application and resources in](#)

[Java Media Framework \(JMF\) 2nd 3rd 4th](#)

[MP3 support 2nd](#)

[playing audio with](#)

[Java Native Interface \(JNI\) 2nd](#)

[Java2D](#)

[special effects](#)

[Java3D](#)

[AWT component](#)

[BranchGroup](#)

[JavaMail API](#)

[JavaSound 2nd 3rd 4th 5th](#)

[playing audio with 2nd](#)

[showing audio information while playing 2nd 3rd 4th 5th](#)

[JButton component](#)

[JCheckBox component](#)

[HTML](#)

[JComboBox component](#)

[HTML](#)

[JComponent class](#)

[subclassing for ListCellRenderer](#)

[JDBC table model 2nd 3rd 4th 5th 6th 7th 8th](#)

[JDesktop Integration Components \(JDIC\)](#)

[JFileChooser component](#)

[opening in an applet](#)

[JGoodies](#)

[JList](#)

[animating selections 2nd 3rd 4th 5th](#)

[checkable 2nd](#)

[filtering](#)

[reordering with drag-and-drop 2nd 3rd](#)

[JMenu component](#)

[adding custom](#)

[JOptionPane component](#)

[creating dialogs](#)

[JPopupMenu class](#)

[filter text saved to](#)

[JProgressBar component 2nd](#)

[JRadioButton component](#)

[JScrollPane component](#)

[JSlider component](#)

[JTabbedPane component](#)

[JTable component](#)

[column selection](#)

[searching easily 2nd 3rd 4th](#)

[sizing columns to suit content](#)

[sorting column contents 2nd 3rd 4th 5th 6th 7th](#)

[JTableHeader component](#)

[JTextArea component](#)

[search](#)

[JTextComponent class](#)

[JTextField component](#)

[constrained text fields 2nd](#)

[rendered as mirror image](#)

[JToolTip class](#)

[JTree component 2nd 3rd 4th 5th 6th 7th 8th](#)

[JViewport component](#)

[JVM property](#)

[JWindow class](#)

[pop-up window](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[kernel](#)

[keyboard lights 2nd 3rd](#)

[← PREV](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

labels

[HTML](#)

[sprucing up 2nd 3rd](#)

[launching external programs 2nd 3rd](#)

[opening a text file](#)

[real shortcut support 2nd 3rd 4th](#)

[resize window icons 2nd](#)

[Runtime.exec\(\)](#)

[status bars](#)

[LayeredPane class](#)

[LayoutManager class](#)

layouts

[absolute](#)

[applet](#)

[BorderLayout](#)

[dynamic](#)

[FormLayout](#)

[letters in a word](#)

[level of audio being played](#)

[DataLine.getLevel\(\)](#)

[lightweight components](#)

Line interface

[isControlSupported\(\)](#)

linked directories

[displaying Windows shortcuts](#)

[real support for Windows shortcuts 2nd 3rd 4th 5th](#)

[ListCellRenderer class 2nd](#)

[as subclass of JComponent](#)

[ListComboBoxModel class](#)

[ListDataEvent class](#)

[ListDataListener class](#)

lists

[filter history 2nd 3rd](#)

[filtering](#)

[making different items look different 2nd 3rd 4th](#)

[ListSelectionEvent class](#)

[ListSelectionListener class 2nd](#)

[little-endian](#)

[LNK files 2nd 3rd 4th 5th 6th](#)

[header parsing](#)

[parser](#)

[shell settings](#)

[loading a URL into Text Area 2nd](#)

[local sockets 2nd 3rd](#)

[locationToIndex\( \) \(JList\)](#)

[locked variable](#)

[Look and Feel \(L&F\)](#)

[brushed metal](#)

[creating inverse black-and-white theme 2nd 3rd](#)

[custom](#)

[JComboBox components](#)

[making quick changes](#)

[Metal L&F](#)

[Lucene \(document indexing and search tool\)](#)

[table model and list decorators](#)





[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

Mac OS X

[slide-in window above the dock 2nd](#)

[magnifying glass component 2nd 3rd 4th 5th](#)

[mailto: URL protocol](#)

[makeOffscreenImage\(\)](#)

[Manager class](#)

[Map-based combo box 2nd](#)

[master gain](#)

[Matcher class 2nd 3rd](#)

[MediaLocator class 2nd](#)

[menu bar \(Mac\)](#)

menus

[borders for items](#)

[drop shadows on 2nd](#)

[drop-down button 2nd 3rd 4th](#)

[Mac and](#)

metadata

[shortcut](#)

[Metal Look and Feel 2nd](#)

[black-and-white theme](#)

[MetalFileChooserUI](#)

[MetalTheme interface](#)

MIME type

[getting for data flavors](#)

[Java file list](#)

[mini application window 2nd 3rd 4th 5th](#)

[clock with mini version](#)

[restoring to normal](#)

[mini-mode for frames 2nd 3rd](#)

[mirror image text 2nd 3rd](#)

[mirroring an application 2nd 3rd 4th 5th 6th 7th](#)

[mixed fonts with HTML](#)

[mod operator \(%\)](#)

[modal dialogs 2nd](#)

[Model-View-Controller \(MVC\) architecture](#)

[use by JComboBox](#)

models

[filtered list 2nd](#)

[non-blocking](#)

[MoreInfo component 2nd 3rd 4th 5th 6th](#)

[motion](#)

[mouse coordinates 2nd](#)

mouse cursor

[\\_animation using Robot class 2nd 3rd](#)

[\\_displaying busy 2nd](#)

mouse events

[\\_blocking](#)

[\\_press and release](#)

[\\_receiving](#)

[\\_sending](#)

[\\_updating selected color](#)

[mouseDragged\(\)](#)

[MouseEvent class](#)

[MouseListener interface](#)

[MouseListener class 2nd 3rd](#)

[MouseMotionListener class](#)

[mouseMove\( \) \(Robot\)](#)

[movies](#)

[MP3 player interface](#)

[MP3 support 2nd 3rd](#)

[MS Office icon](#)

[multi-lined text with HTML](#)

[mutability of lists 2nd](#)





# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[names](#)

[component](#)

[native integration constructing single-launch applications](#)

[iTunes on Mac OS X 2nd 3rd 4th](#)

[iTunes on Windows 2nd 3rd](#)

[L&F properties](#)

[Look and Feel changes 2nd 3rd 4th](#)

[inverse black-and-white theme](#)

[making Mac OS X applications behave normally 2nd 3rd](#)

[opening files 2nd](#)

[packaging in JAR files 2nd 3rd 4th](#)

[system colors](#)

[text components](#)

[NeXTSTEP operating system](#)

[non-blocking code models 2nd 3rd 4th](#)

[non-blocking Load buttons](#)

[notes](#)

[null returns](#)

[Num Lock key 2nd 3rd 4th](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[ObjectOutputStream class](#)

[Office icon](#)

[offscreen BufferedImage](#)

[open program \(Mac OS X\) 2nd 3rd](#)

[openReceiver\( \) 2nd](#)

[openSender\( \) 2nd](#)

[openStream\( \) \(URL\)](#)

operating systems

[difficulties of using Swing with](#)

[drawing AWT widgets](#)

[linked files support](#)

[NeXTSTEP](#)

[system color](#)

[window events](#)

[osascript](#)

[outline effect \(text\)](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[packaging \(JAR files\) 2nd](#)

[double-clicking JARs](#)

[Paint interface](#)

[paint\( \) 2nd 3rd](#)

[paintBackground\( \)](#)

[paintBorder\( \)](#)

[paintChildren\( \) 2nd](#)

[paintComponent\( \) 2nd 3rd](#)

[drawing in Swing components](#)

[overriding for status bar component](#)

[paintIcon\( \) 2nd](#)

[painting](#)

[paintTransition\( \)](#)

[pan](#)

[panels](#)

[handling translucence](#)

[separator panel for status bar](#)

[paths](#)

[relative paths](#)

[Pattern class](#)

[self-completing text field](#)

[Pattern objects](#)

[PCM \(Pulse Code Modulation\) files 2nd 3rd](#)

[Photoshop slices](#)

[using in image-based borders](#)

[Picts 2nd 3rd](#)

[pixels](#)

[playing sounds with](#)

[QuickTime for Java \(QTJ\)](#)

[compiling QuickTime code](#)

[running the code](#)

[pop ups](#)

[file chooser context menu 2nd 3rd 4th 5th](#)

[menu with drop shadows](#)

[menu with previous searches](#)

[translucent menu](#)

[PopupFactory class](#)

[ports](#)

[pressed state](#)

[previewer \(image\)](#)

[PrevSearchAction class](#)

[progress bars](#)

[loading URL](#)

[task of unknown length 2nd 3rd 4th 5th 6th 7th 8th 9th](#)

properties

[JDBC connection strings](#)

[propertyChange\( \)](#)

[PropertyChangeEvent class](#)

[PropertyChangeListener class](#)

proxies

[File class 2nd 3rd 4th](#)

[file proxy](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[QTImageProducer class](#)

[QuickDraw](#)

[QuickTime for Java \(QTJ\) 2nd 3rd](#)

[\\_handling Picts with](#)

[\\_playing sounds with](#)

[← PREV](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[read\(\) \(ImageIO\)](#)

[recursion](#)

[refilter\(\)](#)

[reflection 2nd 3rd 4th](#)

[refresh\(\)](#)

[regular expressions](#)

[creating Pattern object](#)

[enforcing rules on typed input](#)

[constrained document 2nd](#)

[self-completing text field](#)

[rendering](#)

[3D components for Swing applications 2nd 3rd 4th 5th 6th](#)

[blocking window without modal dialog 2nd](#)

[changing fonts throughout an application 2nd](#)

[color eyedropper 2nd 3rd 4th 5th](#)

[creating magnifying glass component](#)

[to intermediate buffer 2nd 3rd](#)

[turning spotlight on Swing 2nd 3rd 4th 5th 6th 7th](#)

[repaint manager](#)

[repaint\(\)](#)

[RepaintManager class](#)

[resetBottomVisibility\(\)](#)

[resize icons \(Windows\) 2nd 3rd](#)

[resizing frames dynamically](#)

[resizing on Mac](#)

[resolution independent](#)

[resort\(\)](#)

[revalidate\(\)](#)

[RightClickGlassPane class](#)

[Robot class 2nd 3rd 4th 5th 6th](#)

[problems with using for magnifier](#)

[RootPaneContainer classes](#)

[rounded rectangles](#)

[highlight for vector-based button](#)

[rows](#)

[run\(\) 2nd](#)

[Runnable interface 2nd](#)

[runNewSearch\(\) 2nd](#)

[Runtime System Properties](#)



[← PREVIOUS](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[Safari web browser](#)

[sample](#)

[sample size](#)

[sampling rate 2nd](#)

[saving settings 2nd 3rd 4th 5th](#)

[screen coordinates 2nd](#)

[screenshots](#)

[color chooser component 2nd](#)

[using for transparent windows 2nd 3rd](#)

[using in frame dissolves](#)

[Scroll Lock key 2nd 3rd 4th](#)

[scroll panes 2nd 3rd](#)

[searches](#)

[clearing search results for blank search](#)

[history](#)

[incremental searches 2nd 3rd 4th](#)

[JTables](#)

[table model](#)

[searching tool \(Lucene\)](#)

[security](#)

[selectable lists 2nd 3rd 4th 5th](#)

[selections](#)

[animating for JList](#)

[column selection](#)

[separator panel \(status bar\)](#)

[serialization](#)

[server](#)

[server-side web technologies 2nd](#)

[setAccessory\( \) 2nd](#)

[setAnimatingHeight\( \) 2nd](#)

[setBackground\( \)](#)

[setBorder\( \)](#)

[setCursor\( \) 2nd](#)

[setFont\( \)](#)

[setIndeterminate\( \) \(JProgressBar\)](#)

[setLocation\( \)](#)

[setLockingKeyState\( \) 2nd](#)

[setMargin\( \)](#)

[setModel\( \)](#)

[setOpaque\( \) 2nd](#)

[setPatternByString\( \)](#)

[setPreferredSize\( \)](#)

[setPreferredWidth\( \) 2nd](#)

[setSelectColor\( \)](#)  
[setSize\( \) 2nd](#)  
[setSource\( \)](#)  
[setText\( \)](#)  
[setUndecorated\( \) 2nd](#)  
[setView\( \)](#)  
shadowing  
    [text labels 2nd 3rd 4th 5th](#)  
shaped windows  
sheets 2nd  
    [animating sheet dialog 2nd 3rd 4th 5th 6th 7th](#)  
    [differences from regular dialogs](#)  
    [mimicking in Swing with glass pane 2nd 3rd 4th 5th](#)  
shell settings (LNK files)  
[ShellFolder class](#)  
[shortcut.lnk file](#)  
shortcuts  
    [displaying in JFileChooser](#)  
    [Windows system](#)  
[show\( \)](#)  
[showAt\( \)](#)  
[showDialog\( \)](#)  
showing information while playing  
    audio  
        [audio format information](#)  
simple harmonic motion  
[sine function for simple harmonic motion](#)  
[size and position of components](#)  
    [size](#)  
Skin L&F  
[slide-in windows 2nd 3rd 4th 5th 6th 7th 8th](#)  
[sliding in above taskbar 2nd 3rd 4th 5th 6th 7th 8th](#)  
[SmoothMetal Look and Feel](#)  
[snapping 2nd 3rd 4th](#)  
[sockets](#)  
[sorting JTable columns 2nd 3rd 4th 5th 6th 7th 8th 9th 10th 11th 12th](#)  
sounds  
    [playing with Java Media Framework 2nd](#)  
    [playing with JavaSound 2nd 3rd](#)  
    [playing with QTJ](#)  
[spaces in filepaths](#)  
[spacing between letters \(tracking\)](#)  
[spin-open detail pane 2nd](#)  
spinning  
[spotlight 2nd 3rd 4th 5th 6th 7th](#)  
[spreadsheet \(Excel\) 2nd](#)  
[standard output and error streams 2nd 3rd 4th](#)  
[start program \(Windows\)](#)  
[startAnimation\( \)](#)  
[stateChanged\( \)](#)  
[states](#)  
[status bar 2nd 3rd 4th 5th 6th 7th](#)

status bars

[\\_adding to windows 2nd 3rd 4th 5th 6th 7th](#)

[stopAnimation\(\)](#)

[StringBuffer class](#)

[Swing](#)

[Swing widget for 2nd 3rd](#)

[swing.aatext property](#)

SwingUtilities class

[\\_invokeLater\(\)](#)

[SwingUtilities2 class](#)

[\\_anti-aliased text variables](#)

[\\_perils of using](#)

[System Properties \(Apple\)](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[tab-delimited text file](#)

table cells

cell renderers

[figuring cell size](#)

[renderer for colors](#)

[TableCellRenderer class](#)

[TableModel interface 2nd](#)

[exporting tab-delimited data](#)

[methods working with rows](#)

[populating from database connection 2nd](#)

[TableModelListener class](#)

[listening to inner table updates](#)

tables

[exporting data to Excel spreadsheet 2nd 3rd](#)

[searching JTables easily 2nd 3rd](#)

[tabs 2nd 3rd 4th 5th](#)

[TaskAllMovies class](#)

[taskbar 2nd 3rd 4th](#)

templates

[filling with values](#)

text

[anti-aliased 2nd 3rd 4th](#)

[enhancing text components with HTML and CSS](#)

[searchable text components 2nd 3rd 4th 5th](#)

[validating user input](#)

text areas

[drawing watermark image in background 2nd 3rd](#)

[NASA photo in background 2nd](#)

text components

[adding watermark to 2nd 3rd](#)

text fields

[list filtering component with history button](#)

[refiltering model on each keystroke](#)

[text file](#)

[TextFileItem class](#)

[TextFileTransferable class](#)

texture

[3D scene background](#)

[watermark scroll pane](#)

[TexturePaint class](#)

[creating object for text watermark](#)

threads

[animation](#)

[animation thread for indefinite progress indicator](#)  
[loader for background image](#)  
[moving complicated processing out of event dispatch 2nd](#)  
Timer class  
[periodically checking on non-blocking load](#)  
[slide-window animation](#)  
tool tips 2nd 3rd 4th  
[installing](#)  
Toolkit class  
[querying dynamic layout property](#)  
toString()  
[cell renderer using](#)  
track information  
tracking  
Transferable class  
[supported image data flavors](#)  
transform( ) (Graphics2D)  
transient component references  
transitions between tabs 2nd 3rd  
animations  
[drawing the animation](#)  
[scheduling animation](#)  
translate( ) (MouseEvent)  
translucence 2nd  
translucent drag-and-drop 2nd 3rd 4th 5th 6th  
transparency  
[custom tool tip](#)  
[drawing frame dissolves](#)  
[implementing in icons](#)  
[transparent background component](#)  
[windows 2nd 3rd](#)  
transparent 2nd 3rd 4th 5th 6th  
trees  
Type class  
Types class



# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[UI classes 2nd](#)

[\\_events](#)

[UIDefaults class](#)

[\\_changing default fonts](#)

[UIManager class](#)

[\\_color changes in applications](#)

[\\_put\( \)](#)

[underlined text](#)

[updateBackground\( \)](#)

[updateImage\( \)](#)

[updateProgressBar\( \) \(ActionListener\)](#)

[URI lists](#)

[URLs](#)

[\\_AudioClip](#)

[\\_dropped](#)

[\\_getting from resources in JAR](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

[validating input 2nd 3rd 4th](#)

[valueChanged\(\) 2nd](#)

[vector-based button 2nd 3rd 4th 5th 6th](#)

[Velocity template engine 2nd 3rd 4th 5th](#)

[VelocityContext](#)

[venetian blinds effect](#)

[View component](#)

[VTL \(Velocity Template Language\)](#)

[← PREV](#)

[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

watermarking

[text component](#)

[WAV audio files](#)

waveform displays

audio

[container](#)

[waveform displays \(audio\) 2nd 3rd 4th 5th 6th 7th](#)

[basic audio term definitions](#)

[container](#)

[converting raw data to samples and channels 2nd](#)

[creating single display](#)

[running the simulator](#)

[web browsers](#)

[web pages](#)

[WebDings and WingDings fonts](#)

[widths 2nd 3rd](#)

[WindowFocusListener class](#)

windows

[blocking with sheets](#)

[blocking without modal dialog 2nd](#)

Windows operating systems

[file chooser 2nd 3rd 4th](#)

[worker threads](#)

[Wrap Look and Feel](#)



[← PREV](#)

# Index

[\[SYMBOL\]](#) [\[A\]](#) [\[B\]](#) [\[C\]](#) [\[D\]](#) [\[E\]](#) [\[F\]](#) [\[G\]](#) [\[H\]](#) [\[I\]](#) [\[J\]](#) [\[K\]](#) [\[L\]](#) [\[M\]](#) [\[N\]](#) [\[O\]](#) [\[P\]](#) [\[Q\]](#) [\[R\]](#) [\[S\]](#) [\[T\]](#) [\[U\]](#) [\[V\]](#) [\[W\]](#) [\[Z\]](#)

ZIP files

[\\_packaged in JARs](#)

[zoom level](#)

[← PREV](#)